

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 637888001
 CSJ: 6378-88-001
 HIGHWAY: SH79, ETC.
 LIMITS OF WORK: ARCHER COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY: HOT MIX MATERIAL

SUBMITTED FOR
 LETTING: 03/05/2021
 Date

APPROVED FOR
 LETTING: 03/05/2021
 Date

D. J. M. R. H., P. E.
 DIRECTOR OF MAINTENANCE

Michael D. Brown, P. E.
 DISTRICT ENGINEER

INDEX OF SHEETS

- | | |
|-------|---------------------------|
| 1 | TITLE SHEET |
| 2A-2C | GENERAL NOTES |
| 3 | ESTIMATE & QUANTITY SHEET |

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2021		 Texas Department of Transportation	
FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	MMC 6378-88-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	WICHITA	ARCHER	
CONTROL	SECTION	JOB	HWY NO.
6378	88	1	SH79, etc.
FILENAME			DATE
MMC_637888001			2/26/2021

Highway: SH79, etc.

GENERAL NOTES:

General:

Plans may be obtained from one of the plan companies listed in the “Special Notice to Contractors”, or by using one of the following web browsers: Chrome, Edge, or Mozilla Firefox to access the Texas Department of Transportation’s (TxDOT’s) Internet site at:

<https://www.txdot.gov/business/letting-bids/plans-online.html>

Contractor questions on this project are to be emailed to the following individual(s):

David Rohmer, P.E.	David.Rohmer@txdot.gov
Cody Bates, P.E.	Cody.Bates@txdot.gov

Contractor questions will only be accepted through email to the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT’s Public FTP site at:

<https://ftp.txdot.gov/pub/txdot-info/Pre-Letting Responses>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, and CCSJ/Project Name.

Contract Prosecution: Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process and/or execute all contracts at the same time.

Project Description – This project shall consist of the purchase of hot mix, materials only, to various roadways located in Archer County. The Maintenance Supervisor for Archer County is:
Cody Coltharp
940-574-2507

ITEM 4

This contract may be extended per special provision 004-004.

ITEM 8

Material requests shall be issued by work order. Each work order shall specify items, quantity, and location for material to be delivered along with the starting delivery date of the material.

Highway: SH79, etc.

Contract time charges shall begin upon issuance of “Authorization to Begin Work” letter. One hundred and twenty (120) working days have been designated for this contract. Working days shall be computed and charged in accordance with Article 8.3.1.5 “Calendar Day.”

Individual work order charge days shall run concurrently with contract time charges.

In accordance with Article 8.6 “Failure to Complete Work on Time,” liquidated damages shall be charged each day for failure to meet each work order. This will include:

1. Failure to deliver at the starting date or continually progress on the work order.
2. Failure to deliver the required number of tons per day.

The amount assessed per day for liquidated damages shall be as specified in accordance with Special Provision 000-658.

ITEM 9

Quantities shown in the plans are for bidding purposes only. TxDOT does not guarantee that all quantities shown in the plans will be requested for delivery.

ITEM 8011

There are 3 delivery locations shown in the plans. Each delivery location will have a separate bid item. These locations will not be the exact delivery point of the material but used as a reference for delivery charge. The bid price for this work shall include delivery to the bid item location, or an actual work order location shorter in mileage from the plant than the bid item location. There will not be any actual work order locations further in distance from the plant than the 3 bid item locations. The 3 bid item delivery locations are as follows:

1. The TxDOT Maintenance Yard in Archer City
 - a. 11930 SH 79, Archer City, TX 76351
2. The intersection of SH 114 & FM 210W in Megargel
3. The intersection of US 82 & FM 368 in Holiday

The pickup only item is for TxDOT picking up the material at the plant. This item will not include any delivery on the contractor’s part.

The maximum distance the hot mix plant is allowed from any of the locations shown in the plans is 125 miles.

For small quantity needs, a work order will be issued to the contractor a minimum of 24 hours in advance and the contractor shall be able to provide and deliver a minimum of 100 tons per day.

For larger quantity work locations (over 500 tons), a work order will be issued to the contractor a minimum of 2 weeks (14 calendar days) in advance of the project start date. Contractor shall be able to provide and deliver a minimum of 1,000 tons per day for these locations.

Project Number: MMC 6378-88-001
County: Archer

Sheet 2
Control: 6378-88-001

Highway: SH79, etc.

Only belly dumps will be allowed unless otherwise approved by the engineer.

A 1 hour unload time per truck will be included in the bid price. If a truck is required to stay on site longer than 1 hour due to no fault of the contractor, each additional hour will be paid at \$100 per hour per truck.

Provide mixture Type D & B using PG binder 64-22. No substitute PG Binder will be allowed on this contract.

The use of Recycled Asphalt Shingles (RAS) will not be permitted on this contract.

The maximum amount of RAP allowed will be 20% unless otherwise approved by the engineer.

Supply aggregate on the contract that meets surface aggregate classification (SAC) B.

