STATE OF TEXAS DEPARTMENT OF TRANSPORTAION

MATERIALS MAINTENANCE CONTRACT

PROJECT: MMC- 6378-11-001

CSJ: 6378-11-001 HIGHWAY: US 175, ETC.

LIMITS OF WORK: HENDERSON & ANDERSON COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY

MATERIAL: LARGE AGGREGATE (RIPRAP)

SUBIVITIED FUR	3/11/2021	
LETTING:		
	DATE	

APPROVED FOR LETTING:

3/11/2021

DATE

DocuSigned by:

Justin G. Smith, P.E.

MAINTENANCE ENGINEER

- DocuSigned by:

DIRECTOR OF MAINTENANCE

INDEX OF SHEETS

- 1 TITLE SHEET
- 2A-2D GENERAL NOTES
 - **3 ESTIMATE & QUANTITY SHEET**
 - 4 PLAN SHEET & SUMMARY

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATIONS ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

©2021	Texas Department of Transportation			
FED RD DIV NO.	PROJECT NO. SHEET NO.		SHEET NO.	
6	6378-11-001		1	
STATE	DISTRICT	COUNTY		
TEXAS	TYLER	HENDERSON, ETC.		
CONTROL	SECTION	JOB	HIGHWAY NO.	
6378	11	1	US 175, ETC.	
FILENAME		DATE		
MMC_637811001		3/3/2021		

Project Number: 6378-11-001 Sheet 2

County: Henderson, etc. Control: 6378-11-001

Highway: US 175, ETC.

GENERAL NOTES: Aggregates Materials Only

GENERAL.

Contractor questions on this project are to be emailed to the following individual(s):

Bradley Bassett <u>Bradley.Bassett@txdot.gov</u> Justin Smith <u>Justin.G.Smith@txdot.gov</u>

Contractor questions will only be accepted through email, phone, and in person to the above individuals. All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

The intent of this contract is to provide large aggregate materials at non-sites specific locations within the Athens and Palestine Maintenance Sections. The contractor will provide materials in a contractor truck to a designated location as defined in the Work Order (delivery).

A map of Henderson and Anderson Counties is included in this contract.

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any or all contracts.

Prior to beginning operations, the Department will arrange a preconstruction conference between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the contract, proposed procedures and the plans for performing the work while providing for safe passage of traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed.

Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surface used in hauling operations free of dirt or other materials.

Department-approved safety hats and safety vests will be worn by all workers and visitors when:

Workers are outside of the vehicles at all outdoor worksites. This includes those who occasionally visit worksites either on the highway surface or right-of-way.

Project Number: 6378-11-001 Sheet 2

County: Henderson, etc. Control: 6378-11-001

Highway: US 175, ETC.

Working in areas where there is a danger of head injury from impact, from falling or flying objects, or from electrical shock or burns.

Non-compliance with this requirement will be grounds for suspension of work.

All work on this contract will be scheduled and directed by the Maintenance Section Supervisor within each county. Unless bid item specifies a specific site, deliveries may be made to any or all of the following sites:

- Site 1- Athens Maintenance Yard (Henderson Co.): John Oliver 903-675-3809 2400 NE Loop 7, Athens, TX 75751
- Site 2- Palestine Maintenance Yard (Anderson Co.): Steven Thornton 903-729-5834 4089 S ST HWY 19, Palestine, TX 75801

ITEM 2: INSTRUCTIONS TO BIDDERS

This project includes plan sheets that are not part of the bid proposal. View plans on-line or download from the web at: https://www.txdot.gov/business/letting-bids/plans-online.html. Order plans from any of the plan reproduction companies shown on the web at: http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm.

ITEM 8. PROSECUTION AND PROGRESS

Working days will be computed and charged in accordance with Section 8.3.1.5., "Calendar Day."

In accordance with Article 8.6 "Failure to Complete Work on Time," Liquidated damages will be charged for failure to complete each Work Order as specified. The amount assessed per day for liquidated damages will be 5% of the estimated cost of the Work Order, but not to be less than \$250 per day and not to exceed \$1000 per day.

Time requirements for each of the Work Orders will be indicated on each individual Work Order. Contractor will be given no less than 24 hours' notice for hot mix (pick up) and 48 hours' notice for hot mix (delivery) to successfully complete each Work Order.

Notify the Maintenance Supervisor or Assistant when encountering any unforeseen delays.

ITEM 9. MEASUREMENT & PAYMENT

Project Number: 6378-11-001 Sheet 2

County: Henderson, etc. Control: 6378-11-001

Highway: US 175, ETC.

In accordance with Article 9.1., "Measurement of Quantities," furnish the tare and maximum gross weights as well as the volume capacity of all vehicles, trucks, truck-tractors, trailers, semitrailers, or combination of such vehicles used to deliver materials for this Contract. Also, furnish calculations supporting these weights and capacities. Provide all measurements required for pay a minimum of 2 days before the trucks are used.

In accordance with Article 9.2 "Plans Quantity Measurement," plans quantity measurement requirements are not applicable for this contract.

Contractor is responsible for obtaining annual overweight tolerance permit if hauling material which exceeds the legal road weight.

In addition to the complete destination address, each delivery ticket must be clearly marked with the work order number. Each shipment must be accompanied by a haul ticket.

Contractor's driver shall report to the State's representative at the time of arrival at the final delivery location and obtain a signature documenting the date and time.

Contractor must provide a conversion factor to convert hot mix from tons to cubic yards.

ITEM 500. MOBILIZATION

Mobilization does not apply to this non-site specific materials contract.

ITEM 502. BARRICADES, SIGNS AND TRAFFIC HANDLING

TxDOT will provide any traffic control needs.

Use strobe lights or rotating beacons on all motorized equipment, operating on or adjacent to the road surface.

ESTIMATE SUMMARY						
ITEM CODE		DESCRIPTION		N I	тот	AL
ITEM NO	DESC CODE			Т	EST.	FINAL
8020	6001	RIPRAP(STN CMN)(DRY)(18 IN)(VE	H)(ST 1)	CY	300	
8020	6002	RIPRAP(STN CMN)(DRY)(18 IN)(VE	H)(ST 2)	CY	150	
8020	6005	RIPRAP(DEL)(STONE PROT)(18 IN)(SITE 1)		CY	300	
8020	6006	RIPRAP(DEL)(STONE PROT)(18 IN)(SITE 2)		CY	150	
8020	6032	RIPRAP(DEL)(STONE PROT)(24 IN)(SITE 2)		CY	150	
8020	6028	RIPRAP(STN TY R)(DRY)(12 IN)(VEH)(DEL)		CY	200	
8020	6029	RIPRAP(STN TY R)(DRY)(18 IN)(VEH	1)(DEL)	CY	500	
		ESTIMATE	L QUANTITY SHI	<u> </u>		
STATE DIS	DISTRICT NO. COUNTY PROJECT NO. SHEET NO.					
10/ TYLER HENDERSON MMC 637811001			3			



Site	Maintenance Office	Address
1	Athens MO	2400 NE LP 7, Athens, TX, 75752
2	Palestine MO	4089 S SH 19, Palestine, TX, 75801

PLAN SHEET SUMMARY

©2019	Texas Department of Transportation			
FED RD DIV NO.	PROJECT NO.		SHEET NO.	
6	6378-2	11-001	1	
STATE	DISTRICT	COUNTY		
TEXAS	TYLER	HENDERSON		
CONTROL	SECTION	JOB HIGHWAY NO.		
6378	11	1	US 175	
FILENAME		DATE		
MMC_637811001		3/11/2021		