

STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION  
PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT  
PROJECT: MMC 6376-47-001  
COUNTY: FRANKLIN  
HIGHWAY: SH 11, ETC  
CALLOUT CONTRACT  
FOR THE PURCHASE OF MATERIALS ONLY, DENSE GRADE HOT MIX

Note: See Project Summary Sheets for complete listing of limits, lengths, equations and exceptions.

Index of Sheets:

- 2 General Notes
- 3 Estimate & Quantity Sheet
- 4 Plan Sheet

RECOMMENDED FOR LETTING:



---

District Maintenance Administrator

APPROVED FOR LETTING:



---

Director of Operations

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

DISTRICT	COUNTY	HIGHWAY	CONTROL
PARIS	FRANKLIN	SH 11, ETC	6376-47-001

© 2021 BY Texas Department of Transportation  
All Rights Reserved.

**County:** FRANKLIN

**Control:** 6376-47-001

**Highway:** SH 11, Etc.

**GENERAL NOTES:**

**PROJECT DESCRIPTION** – The primary intent of this contract to purchase roadway materials only.

The Contractor will provide materials that will be (picked up) at the hot mix plant that will be loaded into Department owned trucks or contracted trucks working for the Department, and/or (deliver) material to a designated location as defined in the Work Order as the Contractor's expense.

The Contractor will have at least one hot mix plant within a 50-mile radius of the Franklin County Maintenance office, and the plant within the closest proximity will be the primary source of material provided for (pick up) operations.

Contractor questions on this project are to be addressed to the following individual(s):

District Maintenance Office:

Tad Eudy – [Tad.Eudy@txdot.gov](mailto:Tad.Eudy@txdot.gov)

Tommy Henderson, P.E. – [Tommy.Henderson@txdot.gov](mailto:Tommy.Henderson@txdot.gov)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

**TXDOT PROJECT SUPERVISOR** – All work on this contract will be scheduled and directed by the following person(s). Payments will be made on a monthly basis for work completed and accepted according to specifications. All payment requests will be directed to the same:

**Hopkins County**

Shane Bolton, Asst. Maint. Section Supervisor

104 East IH 30

Mt. Vernon, Texas 75457

Phone: 903-537-4976

**County:** FRANKLIN

**Control:** 6376-47-001

**Highway:** SH 11, Etc.

**Contract Prosecution:** Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

The work performed, equipment used, and materials furnished for a complete project will be paid for directly as indicated elsewhere in the plans and specifications. Payment for complete work will be made upon accepted of the work by the department.

**ITEM 2 – INSTRUCTIONS TO BIDDERS:**

Views plans on-line or download from the web at:

<http://www.txdot.gov/business/letting-bids/plans-online.html>

Order plans from any of the plan reproduction companies shown on the web at:

<http://www.txdot.gov/business/letting-bids/repro-companies.html>

**ITEM 5 – CONTROL OF THE WORK:**

Upon completion of the work and before final acceptance and final payment is made, clear and remove from the site all surplus and discarded material and will leave the entire project in a neat and slightly condition.

**ITEM 6 – CONTROL OF MATERIALS:**

Furnish all material for this project in accordance with applicable specifications.

**ITEM 8 – PROSECUTION AND PROGRESS:**

Time will be computed according to Item 8.3.1.5 “Calendar Day”.

**ITEM 9 – MEASUREMENT & PAYMENT:**

Contractor is responsible for obtaining annual overweight tolerance permit if hauling material which exceeds the legal road weight.

**County:** FRANKLIN

**Control:** 6376-47-001

**Highway:** SH 11, Etc.

**ITEM 8011 – Dense Graded Hot-Mix Asphalt (Small Quantity) (Material Only):**

All surface mixes to be SAC A.

RAS is not allowed in surface mixes.

Specify Hot Mix Asphalt Concrete (HMAC) or Warm Mix Asphalt (WMA) at the time of design submittal. After design submittal, continue producing the chosen design unless otherwise approved.

RAP from Contractor owned sources may be used if the RAP is fractionated. The course fraction of Contractor owned RAP will not be allowed if it consists primarily of siliceous aggregates.

Perform all sampling for aggregate quality testing on stockpiles at the HMAC plant. Mixture sampling for QC/QA testing will typically be taken from the truck at the plant; however, the Engineer may direct that a sample be taken at any point or location of mixture during production, delivery or placement.

For Delivery Operations:

- Supply tarp and components necessary to tarp material during transport.
- Document wait time, in excess of one hour, when required to remain at a TxDOT designated location until unloaded. Demerge charges will be invoiced in 15 minute increments.
- Make all deliveries between the hours of 8 A.M. and 4 P.M. CST unless prior arrangements have been made with the Maintenance Supervisor.



ITEM		DESCRIPTION	QTY	UOM
8011	6001	D-GR HMA (SQ) TY D PG 64-22 (PICKUP)	2,000	TONS
8011	6002	D-GR HMA (SQ) TY D PG 64-22 (DELIVERY)	2,000	TONS

**PLAN SHEET**

© 2021 by Texas Department of Transportation  
All Rights Reserved

CONT	SECT	JOB	HIGHWAY
6376	47	1	SH 11
DIST	COUNTY		SHEET NO.
01	FRANKLIN		4