INDEX OF SHEETS

SHEET NO.

1

2-4 5

6

7-18

19

20

21

22

23

24

>

>

>

DESCRIPTION

ESTIMATE AND QUANTITY SHEET

TITLE SHEET

GENERAL NOTES

BC (1-12)-21

TCP (1-1)-18

TCP (1-2)-18

TCP (1-4)-18

WZ (RS)-16

TRB-15(1)

TRB-15(2)

QUANTITY SUMMARY

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION


PLANS OF PROPOSED HIGHWAY ROUTINE MAINTENANCE CONTRACT TYPE OF WORK:

ON CALL TREE REMOVAL

PROJECT NO. : RMC 6392-61-001

HIGHWAY: IH 30, ETC

LIMITS OF WORK : VARIOUS LOCATIONS IN HUNT AND RAINS COUNTY







THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE, AS MARKED WITH (>) HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

MAINTENANCE PROJECT NO. RMC 6392-61-001 CHECKED TEXAS PAR HUNT, ETC CONT. SECT. HIGHWAY NO. CHECKED 6392 61 001 | IH 30, ETC



SUBMITTED FOR LETTING:

James Atkins, P.C. 10/5 20 21

RECOMMENDED FOR LETTING

11-16 20 21

DISTRICT MAINTENANCE ENGINEER

APPROVED FOR LETTING

Jones 2. Harden, P.E. 11-16 20 21

DIRECTOR OF OPERATIONS

Project Number: RMC 6392-61-001

County: Hunt Control: 6392-61-001

Highway: IH 30, ETC.

GENERAL NOTES:

PROJECT DESCRIPTION – This project consists of performing tree removal on various roads in Hunt and Rains County.

Questions prior to letting may be submitted by email to the names listed below:

Greenville Area Office

James Atkins II, P.E. – James Atkins@txdot.gov

Willie Bolden II, P.E. - Willie.Bolden@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

TXDOT PROJECT SUPERVISOR - All work on this contract will be scheduled and directed by the following person. Payments will be made on a monthly basis for work completed and accepted according to specifications. All payment requests shall be directed to the same:

Hunt and Rains Counties Herman Andrus, Hunt County Maintenance Supervisor 3001 IH-30 East Greenville, TX 75402

Phone: (903) 453-3104 Fax: (903) 454-0967

Kevin Wilson, Rains County Maintenance Supervisor 1520 W US 69

Emory, TX 75440 Phone: (903) 473-2682

CONTRACT PROSECUTION - Each contract awarded by the Department stands on its own and, as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Project Number: RMC 6392-61-001

County: Hunt Control: 6392-61-001

Highway: IH 30, ETC.

ITEM 2: INSTRUCTIONS TO BIDDERS

Views plans on-line or download from the web at: http://www.txdot.gov/business/letting-bids/plans-online.html

Order plans from any of the plan reproduction companies shown on the web at: http://www.txdot.gov/business/letting-bids/repro-companies.html

ITEM 3: AWARD AND EXECUTION OF CONTRACT

This contract includes non-site specific work locations. Multiple work orders will be used to procure work of the type identified in the contract at locations not yet determined.

ITEM 5: CONTROL OF THE WORK

Begin physical work within 7 days of verbal notification and continue until all work within the respective work order is complete.

Upon completion of the work and before final acceptance and final payment is made, clear and remove from the site all surplus and discarded materials and leave the entire project in a neat and slightly condition.

The work performed, equipment used and materials furnished for a complete project will be paid for directly as indicated elsewhere in the plans and specifications. Payment for completed work will be made upon acceptance of the work by the Texas Department of Transportation. Removal and replacement of signs, delineators or mailboxes damaged by the Contractor's operations will be repaired or replaced by the Contractor at no expense to the Texas Department of Transportation.

Prior to beginning operations a conference between representatives of the state and the Contractor will be arranged by the state. In this meeting the Contractor will outline the sequence of work while providing for the safe passage of traffic at all times. Plans, specifications, unusual conditions and other pertinent items regarding the work will also be discussed.

At least one day's work will be guaranteed when the Contractor is called to work.

Supply an adequate size crew experienced in the type of work described within these specifications and capable of performing the work in a safe and timely manner. All vehicles will be equipped with flashing strobe lights and backup horns when applicable and/or as directed by the Engineer.

Project Number: RMC 6392-61-001

County: Hunt Control: 6392-61-001

Highway: IH 30, ETC.

ITEM 7 – LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

ITEM 8: PROSECUTION AND PROGRESS

Time will be computed according to Item 8.3.1.5 Calendar Day.

The number of working days for this project shall be 365 calendar days or until contract funds are expended. Work on Saturdays, Sundays, and national or state holidays will not be permitted without written permission of the Engineer.

ITEM 500: MOBILIZATION (CALL OUT)

Call out work orders may have multiple locations spanning multiple days.

ITEM 502: BARRICADES, SIGNS AND TRAFFIC HANDLING

The Contractor's personnel shall be dressed in approved safety attire while outside vehicles and/or while performing work on the highway right of way. For daytime and nighttime activity, flaggers shall wear high-visibility safety apparel that meets the Performance Class 2 or 3 requirements of the ANSI/ISEA 107–2004 publication entitled "American National Standard for High-Visibility Apparel and Headwear".

Truck mounted crash attenuator shall be furnished per applicable Traffic Control Plan.

The traffic control plan for this contract consists of the installation and maintenance of warning signs and other traffic control devises shown in the plans, specification data which may be included in the general notes, applicable provision of the Texas Manual on Uniform Traffic Control Devises (TMUTCD), traffic control plan sheets included in the plans, standard BC sheets and Item 502 of the Standard Specifications. Traffic Control will be considered subsidiary to the various bid item.

All flaggers will be required to wear an approved hard hat.

Truck mounted crash attenuator shall be furnished per applicable Traffic Control Plan.

At no time will equipment be parked on or within two feet of the edge of travel lane without proper lane closure set up and in place.

Project Number: RMC 6392-61-001

County: Hunt Control: 6392-61-001

Highway: IH 30, ETC.

ITEM 752: TREE AND BRUSH REMOVAL

The quantities shown on the bid item sheet are for estimating only. The Engineer will determine the actual number of trees to be removed.

The equipment used to remove brush shall be approved by the maintenance supervisor. The Contractor shall remove all existing limbs and small trees on the ground within the limits of brush removal.

Tree diameters will be pre-measured and marked. All payments will be made in accordance with these pre-measurements.

Remove trees as designated. After removal of designated trees, the Contractor may move out, and the remaining tree removal for this contract will be used on an as needed basis. The Engineer will send the Contractor written notification requiring him to move in and begin tree removal each time there are a minimum of 10 trees to be removed. After completion of the required tree removal the Contractor may again move out, and this procedure will continue for the duration of the contract.

All limbs, brush, and tree trunks may be chipped and scattered (not piled) along the back slopes of the right-of-ways. Chippings should be scattered in such a manner that proper drainage is maintained at cross drains, roadside ditches, channels, etc. All chips are to be removed of and disposed of or scattered in the same day in which they are chipped. The bid items for Tree Removal will not be paid until all chips are disposed of or scattered as required.

Do not deposit wood chips in developed areas or in front of houses.

Burning of brush will not be permitted within the limits of the highway right-of-way.

Trees cut by the contractor will be removed from the safety clear zone of the roadway at the end of each workday. No trees and/or logs will be left within the safety clear zone overnight.

Remove trees that are already down in the right-of-way. When right of entry can be obtained, remove trees that have fallen onto the right-of-way from private property. If right of entry cannot be obtained, cut and measure trees that have fallen from private property at the right-of way line. These trees will be paid for in the same manner as trees that are to be felled and removed.

Stump grinding to twelve inches below natural ground line and/or removal will be required for all stumps measuring four inches and larger. The bid item for tree removal will not be paid for until stump grinding has been fully completed. If, in the opinion of the Engineer, stumps on back slope cannot be ground, tress shall be cut flush with surrounding ground line.

Project Number: RMC 6392-61-001

County: Hunt Control: 6392-61-001

Highway: IH 30, ETC.

Complete all work on a roadway including stump grinding and removal of debris or chipping, before starting on another roadway, unless approved.

The Contractor shall be responsible for locating all utilities prior to beginning any tree cutting. Any damages to utilities will be repaired at the Contractor's expense.

The Contractor will be required to furnish materials and make repairs to the existing roadway and right-of-way, including rutting, at any location damaged by the Contractor's operations. This work shall be done in a manner satisfactory to the Engineer and will be considered subsidiary to various bid items. If excessive soil and vegetation disturbance is caused, the areas will be reseeded at the Contractor's expense.

ITEM 6185: TRUCK MOUNTED ATTENUATOR

Usage of truck mounted attenuator will be a case by case basis as determined by Area Engineer.

General Notes



Texas Department of Transportation

Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6392-61-001

DISTRICT Paris
HIGHWAY IH0030

COUNTY Hunt

		CONTR	OL SECTION JOB	6392-63	L-001		
			A00182	2801	1		
			COUNTY	Hun	it	TOTAL EST.	TOTAL FINAL
			HIGHWAY	IH0030		1	1111712
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	500-6033	MOBILIZATION (CALLOUT)	EA	10.000		10.000	
	752-6005	TREE REMOVAL (4" - 12" DIA)	EA	1,200.000		1,200.000	
	752-6006	TREE REMOVAL (12" - 18" DIA)	EA	260.000		260.000	
	752-6007	TREE REMOVAL (18" - 24" DIA)	EA	150.000		150.000	
	752-6008	TREE REMOVAL (24" - 30" DIA)	EA	50.000	35	50.000	
	752-6009	TREE REMOVAL (30" - 36" DIA)	EA	10.000		10.000	
	752-6010	TREE REMOVAL (36" - 42" DIA)	EA	10.000		10.000	
	752-6011	TREE REMOVAL (42" - 48" DIA)	EA	10.000		10.000	
	752-6012	TREE REMOVAL (48" - 60" DIA)	EA	5.000		5.000	
	752-6013	TREE REMOVAL (60" - 72" DIA)	EA	5.000		5.000	
	752-6014	STUMP REMOVAL	EA	5.000		5.000	
	6185-6002	TMA (STATIONARY)	DAY	30.000		30.000	



DISTRICT	COUNTY	CCSJ	SHEET
Paris	Hunt	6392-61-001	5

	SUMMARY OF TREE REMOVAL									
752-6005 TREE REMOVAL (4"-12"DIA)	752-6006 TREE REMOVAL (12"-18"DIA)	752-6007 TREE REMOVAL (18"-24"DIA)	752-6008 TREE REMOVAL (24"-30"DIA)	752-6009 TREE REMOVAL (30"-36"DIA)	752-6010 TREE REMOVAL (36"-42"DIA)	752-60 TREE REMOVAL (42"-48"DIA)	752-6012 TREE REMOVAL (48"-60"DIA)	752-6013 TREE REMOVAL (60"-72"DIA)	752-6014 STUMP REMOVAL	6185-6002 TMA (STATIONREY)
EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	DAY
1,200	260	150	50	10	10	10	5	5	5	30

©2021 Texas Department of Transportation

QUANTITY SUMMARY

FED. RD. DIV. NO.	F	SHEET NO.				
6	RMC	C 6392-61-001 6				
STATE	DIST.	COUNTY				
TEXAS	PAR	HUNT,ETC				
CONT.	SECT.	J03	HIGHWAY NO.			
6392	61	001	IH 30,ETC			

9/28/2021 4:30:08 T:\GREEN\Waintenanc

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop. sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO). "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES. CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- i2. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety appare! meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- 1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT

http://www.txdot.gov

COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)

MATERIAL PRODUCER LIST (MPL)

ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"

STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)

TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)

TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




Texas Department of Transportation


Traffic Safety Division Standar

BARRICADE AND CONSTRUCTION **GENERAL NOTES** AND REQUIREMENTS

BC(1)-21

-	-	_	
он Тэ	DOT	cs: Tx00T on	TxDOT cx: TxD0
CONT	SECT	804	HIGHWAY
6392	61	001	[H 30, ETC
0151		COUNTY	SHEET NO.
PAR		HUNT, ETC	7
	6392 0151	CONT SECT 6392 61 DIST	CONT SECT





CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the rood at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detaur signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING 15.6

C175

SIZE								
Sign Number or Series	Conventional Road	Expressway/ Freeway						
CW20 ⁴ CW21 CW22 CW23 CW25	48" × 48"	48" × 48"						
CW1, CW2, CW7, CWB, CW9, CW11, CW14	36" × 36"	48" × 48"						
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" × 48"						

SPACING

Posted Speed	Sign △ Spacing "X"
МРН	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500 ²
60	600 Z
65	700 2
70	800 s
75	900 ²
80	1000 ²
*	* 3

* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

igtriangle Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile
- 4. 36° x 36° "ROAD WORK AHEAD" (CW20-1D)signs may be used on low valume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCO", Sign Appendix or the "Standard Highway Sign Designs for Texas' manual for complete list of available sign design

SPEED STAY ALERT LIMIT R4-1 PASS TRAFFIC FINES DOUBLE * * R20-5T WORK WARNING SICKS ROAD WORK AHEAD * * R20-5aTP STATE LAW TALK OR TEXT LATER CW13-1P ROAD CH20-1D R20-3T * * G20-10T * * XX AHEAD, Type 3 Barricade or #FR CW13-1P channel izing devices Φ \Leftrightarrow => 4 ➾ SPEED R2-1 LIMIT <> WORK SPACE \Rightarrow Beginning of NO-PASSING END G20-26T X Channelizing Devices Line should CSJ Limit END When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still with sign within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices. SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS

SPEED

LIMIT

ROAD WORK

* *G20-51

X X G20-61

END ROAD WORK

G20-2 * *

ROAD

WORK

1/2 MILE

CW2O-1E

ROAL

WORK

AHEAD

CW20-10

WORK

DOUBLE

SPEED R2-1

LIMIT OO

₩R20-5T

€ ¥ R20-5oTP

STAY ALERT

TALK OR TEXT LATER

620-10

OBEY

WARNING

SIGNS

STATE LAW

➾

END G20-26T * *

\R20-31

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-51) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic
- the end of the work zone.

	LEGEND								
<u> </u>	Type 3 Barricade								
00	O Channelizing Devices								
_	Sign								
х	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.								

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE	bc-21.dan	DN: T:	100	100x1:x3	Dws	TxD01	CK: TxD
TOOxT (3)	November 2002	CONT	SECT	JOB		н1	CHWAY
	REVISIONS	6392	61	001		IH:	GHWAY BO, ETC
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	PAR		HUNT, E	TC		8

ROAD

CLOSED

Type 3 Borricode or

channel izing

devices

CWI 3-1P XX

Channelizing Devices

No warranty of any for the conversion


and by the Texas Engineering Practice Act., whotsoever, IxDOI assumes no responsibility for incorrect results or demons resulting for

Contractor will install a regulatory speed limit sign at

9/28/2021 T: \GREEN\

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in occordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Lona/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to sofely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roodway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be: 40 mph and greater 0.2 to 2 miles

0.2 to 1 mile

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the ADVANCE SPEED LIMIT (CW3-5) sign, "WORK ZONE" (G20-50P) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.


SHEET 3 OF 12



BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC(3)-21

FILEI	bc-21.dgn	OH: ÎX	TOC	CR: TxDOT DW:	1×D01	CKI TXDO	
© 1xD01	November 2002	CONT	SECT	JOB		H] GHWAY	
	REVESIONS	6392	61	001	IH	30, ETC	
9-07 7-13	8-14 5-21	DIST	COUNTY			SHEET NO.	
1-13	3-51	PAR		HUNT, ETC		9	



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall HOT be placed under skids as a means of leveling.

** Then plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two obove and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times naminal past size, centered on the splice and of at least the same gauge material.

procedures for attaching sign substrates to other types of SIDE ELEVATION Wood

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support, Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired

by splicing or

other means.

Attachment to wooden supports

will be by bolts and nuts

or screws. Use TxDOT's or


manufacturer's recommended

sign supports

STOP/SLOW PADDLES

- STOP/SLOW poddles are the primary method to control traffic. by flaggers. The STOP/SLOW poddle size should be 24° x 24° .
- 2. STOP/SLOW poddles shall be retroreflectorized when used at night. 3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW poddle faces shall only be as specifically described in Section 6£.03 Hand Signaling Devices in the TMUTCD.





SHEETING RE	QUIREMENT	S (WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE Be OR Ce SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are patentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, paints of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roodway condition. For details for covering large guide signs see the
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in occordance with the plans or as directed by the Engineer. Signs shall be used to regulate, worn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been amitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor Initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CMZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in occordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be I inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary work that occupies a location more than 3 days.
 - Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary doytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration work that occupies a location up to 1 hour.
 - Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of I foot above the povement surface but no more than 2 feet above
- the ground. Long-term/intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, recordless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6° centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-B310 for roll-up signs. The web oddress for DMS specifications is shown on BC(1). White sheeting, meeting the requirements of DMS-B300 Type A_r , shall be used for signs with a white background. Orange sheeting, meeting the requirements of DMS-B300 Type $B_{\rm FL}$ or Type $C_{\rm FL}$, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

 All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway
Administration (FHMA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roodway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be apaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opoque properties under automobile headlights at night, without damaging the sign sheeting. Burlop shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesioniess sand should be used. The sandbags will be fied shut to keep the sand from spilling and to maintain a
- Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for bollast on partable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or faid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
 Sandbags shall NOT be placed under the skid and shall not be used to level
- sign supports placed on slopes.

FLAGS ON SIGNS

Floor may be used to draw attention to warning signs. When used, the floor shall be 16 inches square or larger and shall be arange or fluorescent i red-orange in color. Flags shall not be allowed to cover any portion of the sign face.


SHEET 4 OF 12



BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) -21

bc-21, dan DN: TXDOT CR: TXDOT DW: TXDOT CR: TXDO C) TxDOT November 2002 JOB HICHBAT BEN1510MS IH 30, ETC 001 6392 61 9-07 8-14 COUNTY SHEET NO. 7-13 5-21 PAR HUNT, ETC 10



that can be used for each approved sign support.

Texas Department of Transportation

Standard

Traffic Safety Division

BARRICADE AND CONSTRUCTION
TYPICAL SIGN SUPPORT

SHEET 5 OF 12

BC(5)-21

FILE	bc-21.dgn	DNI T	TOO	CK: TxDOT DHI	Tx001	CKI TXDOT
(C) Tx00T	November 2002	CONT	SECT	J08	н	ICHRAY
7,700	REVISIONS	6392	61	001	IH	30, ETC
9-07 8-14 7-13 5-21		D151	COUNTY		SHEET NO.	
		PAR HUNT, ETC			111	

SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

Ø 7/16'

pin at angle

2* 1

SINGLE LEG BASE

-2" x 2"

upright

12 ga.

needed to match sideslope

-Welds to start on

back fill puddle.

opposite sides going in opposite directions. Minimum

weld, do not

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32"

of any

9/28/2021 4:30:13 PM T:\GREEN\Maintenance PI

WHEN NOT IN USE. REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO,"
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- 5. Always use the route or interstate designation (1H, US, SH, FM) along with the number when referring to a roadway.
- 6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "MEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Wanday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.

 10. Do not present redundant information on a two-phase message; i.e.,
- keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message. 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scrall horizontally or vertically ocross the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be obbrevioted, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCWS should default to an illegible display that will not alorm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bors is oppropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Rood	ACCS RD	Major	MAJ
Alternate	ALT	Miles	1M
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHO	Parking	PKING
CROSSING	XING	Rood	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
	DONT HIE	Saturday	SAT
Do Not		Service Road	SERV RD
East	E	Shoulder	SHLDR
Eastbound	(route) E	Slippery	SLIP
Emergency	EMER	South	\$
Emergency Vehicle		Southbound	(route) 5
Entrance, Enter	ENT	Speed	SPD
Express Lone	EXP LN	Street	\$1
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Te Lephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freewdy	FRWY, FWY	Thursday	THURS
	FWY BLKD	To Downtown	TO DWNTN
	FRI	Troffic	TRAF
Hozordous Driving Hozordous Material		Traveters	TRVLRS
		Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway	UA UAE	Vehicles (s)	VEH, VEHS
Hour (8)	HR, HRS	Worning	WARN
Information	INFO	Wednesday	WED
It Is	ITS	Weight Limit	WT LIMIT
Junction	JCT	West	1
Left	LFT	Westbound	(route) W
Left Lone	LFT LN	Wet Payement	WET PYMT
Lone Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL		1 40411
Maintenance	MAINT		

Roodway designation # 1H-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

THOSE IT CONSTITUTE FOR									
Road/Lane/Ramp Closure List Other Condition List									
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT						
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT						
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE						
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT						
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT						
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT						
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN						

CLOSED X WILE FXIT RIGHT LN CLOSED TO BE CLOSED MALL X LANES DRIVEWAY CLOSED

CLOSED

XXXXXXX BLVD

CLOSED

XXXX FT X MILES TRAFFIC LANES SIGNAL SHIFT XXXX FT

BUMP

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

· · · · · · · · · · · · · · · · · · ·	e/Effect on Trave List	l Location List	Warning List	* * Advance Notice List
MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- XX X PM-X AM
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE	NEXT TUE AUG XX
USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM- XX AM
STAY IN LANE	*	*	* See Application Guide	lines Note 6.

APPLICATION GUIDELINES

TUE - FRI

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Marning, or Advance Notice Phose Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two POMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phoses, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with doys of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- 2. Roadway designations (H, US, SH, FM and LP can be interchanged as aparapriate.
- 3. EAST, WEST, NORTH and SOUTH (or abbreviations E. W. N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary.
- 7. FT and MI. MILE and MILES interchanged as appropriate.
- 8. AT, BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

US XXX

EXIT

FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" Obove.
- 2. When symbol signs, such as the "Flogger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on 8C(7), for the

SHEET 6 OF 12




PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) -21


(FE)	DC-21, agn	Des T	r001	Cap TxDOT	Dat t	TXDOT	CK1 TXDOT
TxDOT	November 2002	CONT	SECT	JOB		н	CHUAT
REVISIONS	6392	61	001		IH:	IH 30, ETC	
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13 5-21	PAR	HUNT, ETC				12	
		-	-			_	

- Borrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address
- 2. Color of Borrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiory to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An oldernate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- 4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional)while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgetine being supplemented.
- 7. Moximum specing of Borrier Reflectors is forty (40) feet.
- Povement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations,
- 10. Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
 11. Single stope borriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is opproved for use in work zone locations, where the posted speed is 45mph, or less. See Roodway Standard Sheet LPCB.

Max, specine of barrier reflectors is 20 feet. Attach the delineators as per monufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)




DELINEATION OF END TREATMENTS


END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Worning reflector may be round or source. Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCO.
- 2. Worning Lights shall NOT be installed on borricodes.
- 3. Type A-Low Intensity Floshing Worning Lights are commonly used with drums. They are intended to warn of or mark a patentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Worning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are Intended to be used in a series for delineation to supplement ather traffic control
- devices. Their use shall be as indicated on this sheet and/or after sheets of the plans by the designation "58".

 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.

 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the worning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Worning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- 1. Type A floshing worning lights are intended to worn drivers that they are approaching or are in a patentially hazardous area.


 2. Type A random floshing worning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on tane changes, on lane closures, and on other similar conditions.
- 5. Type A. Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Worning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A worning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn worning light at the discretion of the Contractor unless otherwise nated in the plans.
- 2. The worning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- 3. The worning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the worning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channel(zing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane clasures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Floshing Arrow Boards should not be used on two-lone, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic
- control devices that should be used in conjunction with the Flashing Arrow Board. The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Atternating Diamond Coution mode as shown.
 The straight line coution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage.
- The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.

 Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is MOT ALLOWED.
 The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.

- The Floshing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
 A Floshing Arrow Board SHALL NOT BE USED to laterally shift traffic.
 A full matrix PCMS may be used to simulate a Floshing Arrow Board provided it meets visibility,
- flosh rate and dimming requirements on this sheet for the same size arrow.

 14. Minimum mounting height of traiter mounted Arrow Boards should be 7 feet from roadway.
- to bottom of panel.

REQUIREMENTS										
TYPE	MINIMA SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE							
В	30 × 60	13	3/4 mile							
С	48 × 96	15	l mile							

ATTENTION Floshing Arrow Boards shall be equipped with outomatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Monual for
- Assessing Safety Handware (MASH). Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CHIZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted
- 5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC (7) -21

	_		•				
FILE:	bc-21.dgn	DNI To	rDO1	CK: TxDOT	DWI	TxDOT	CK: TxDOI
①1xDOT	November 2002	CONT	SECT	JOB		H	CHRAY
	MÉVISIONS	6392	61	001	- 0	IH:	30, ETC
9-07 8-14 7-13 5-21	D157		COUNTY			SHEET NO.	
	PAR		HIMT F	TC		13	

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42° two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in topers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CMUTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:


- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the battom.
- The body and base shall tack together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents occidental separation due to normal handling and/or dir turbulence created by passing vehicles.
- Plostic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plostic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter hales to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retrareflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4
 inches, and a minimum of two footholds of sufficient size to allow base
 to be held down while separating the drum body from the base.
- Plostic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Brum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the clans.
- The sheeting shall be suitable for use on and shall othere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no detailnating, cracking, or loss of retroreflectivity other than that loss due to obrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above povement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a salid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to materists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to povement.





DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrion facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrion facility. Refer to WZIBTS-2) for Pedestrion Control requirements for Sidewalk Diversions. Sidewalk Detours and Crosswelk Closures.
- Diversions, Sidewalk Detours and Crosswalk Closures.

 2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian borricades similar to the one pictured above, longitudinal channelizing devices, some concrete borriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- movements.

 5. Warning lights shall not be attached to detectable pedestrian barricodes.
- Detectable pedestrian barricades should use 8° naminal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or shorp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CM1-8, Opposing Troffic Lane Divider, Driveway sign D70a, Keep Right R4 series or ather signs as approved by Engineer



12" x 24" Vertical Panel mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED
ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CM2TCO.
- 2. Chevrons and other work zone signs with an aronge background shall be manufactured with Type $B_{\rm FL}$ or Type $C_{\rm FL}$ Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with arange and white sheeting meeting the requirements of DMS-8300 Type A or Type B Diagonal stripes on Vertical Panels shall slope down toward the Intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and rut, two washers, and one locking washer for each connection.
- Mounting botts and nuts shall be fully engaged and adequately torqued. Botts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

FILE bc-21, dgn	Dies To	DOT	Cas TxDOT	Dws	TxDOT	Cu: TxDOT	
© TxDOT November 2002	ovember 2002 cont		JOB		н	I GHWA Y	
REVISIONS	6392	61	001 IH			30, ETC	
4-03 8-14 9-07 5-21 7-13	DIST	COUNTY				SHEET NO.	
	PAR	HUNT, ETC				14	



PORTABLE

of this standard is governed by the Texas Engineering Practice Act. No warranty of any by TxD01 for any purpose whatsoever. TxD01 assumes no responsibility for the conversion dard to other formats or for incorrect results or damoges resulting from its use. Do-21, again.

78/2021 4:30:16 \GREEN\Wointenand

1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.

2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as tane transitions where positive daytime and mighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.


3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective arange and reflective white and should always slope downward toward the travel lane.

4. YP's used on expressways and freeways or other high speed roodways, may have more than 270 square inches of retroreflective area facing traffic. 5. Self-righting supports are available with portable base.

See "Compliant Work Zone Traffic Control Devices List" (CW2TCD). 6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification

DMS-8300, unless noted otherwise. 7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.


VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lame Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the povement with an adhesive or rubber weight to minimize movement coused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42° cones or VPs.
- 3. Spocing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot specing
- 4. The OTLO shall be arange with a black nonreflective legend. Sheeting for the OTLD shall be retroreflective Type $B_{FL}\,\text{or}\,$ Type $C_{FL}\,\text{conforming}$ to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)






Fixed Base w/ Approved Adhesive (Driveoble Base, or Flexible Support can be used)

-). The chevron shall be a vertical rectangle with $\boldsymbol{\alpha}$ minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roodway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Specing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be arange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300. unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Troffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveoble. fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the pions. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, foded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Povement surfaces shall be prepared in a monner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final povement surfaces, including povement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- 1. ECDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums,
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on 80(7) when placed roughly parallel to the travel lanes.
- 6. LCOs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballosted systems used to channelize vehicular traffic shall be supplemented with retrareflective defineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with povement markings.

 3. Nater ballasted systems used as barriers shall be placed in accordance to application and installation requirements.
- specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging toper except in low speed (less than 45 MPH) urban areas. When used on a taper in a law speed urban area, the taper shall be delineated and the taper length should be designed to optimize rood user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flored to a point outside the clear zone.

If used to channelize pedestrians, langitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	Desiroble Toper Lengths **			Formula Taper Lengths Channelizing			ng of Lizing
		10' Offset	11 Offset	12' Offset	On a Taper	On a Tangent		
30	2	150'	1651	180'	30'	60'		
35	L - WS2	2051	225'	2451	35'	70'		
40	6	2651	295'	320'	401	80,		
45		450'	4951	5401	451	90'		
50		500'	550'	6001	501	100'		
55	L•WS	5501	6051	6601	551	110'		
60	6-115	6001	6601	720'	601	120'		
65		6501	715"	780'	65'	130'		
70		7001	770'	840'	70"	1401		
75		7501	8251	9001	751	1501		
80		8001	880'	9601	80*	1601		
WWw. all was a second								

**XToper lengths have been rounded off. L-Length of Toper (FT.) W-Width of Offset (FT.) S-Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Texas Department of Transportation

Successed Maximum

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) -21

				Comment of the Control of the			
FILE	ba-21.dgn	DNI T	tO01	CA: TXDOT	Date	TxDOT	CRI TXDOT
(C) 1 x DO1	November 2002	CONT	SECT	JOB		н	CHUAT
	MEATZIONZ	6392	61	001		IH	30, ETC
9-07	8-14	DIST		COUNTY	_		SHEET NO.
7-13 5-21	3-21	PAR		HUNT, E	TC		15

9/28/2021

TYPE 3 BARRICADES

- Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricodes and a list of all materials used in the construction of Type 3 Barricodes.
- Type 3 Borricodes shall be used at each end of construction projects closed to all traffic.
- 3. Borricodes extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring, When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricode. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roodway, should slope downward to the left. For the left side of the roodway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- Borricodes shall not be placed parallel to traffic unless an adequate clear zone is provided.
- 7. Worning lights shall NOT be installed on barricodes.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be fied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stocked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




Minimum
Width of
Reflective
Sheeting
7 inches,

TYPICAL STRIPING DETAIL FOR BARRICADE RAIL


4' min., 8' max.

Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW

4. When the shoulder width is greater than 12 feet, ateody-burn lights may be amitted if drums are used.

5. Drums must extend the length

1. Where positive redirectional

2. Plastic construction feacing

of the cutvert widening.

Plastic drum

LEGEND

or yellow warning reflector

Steady burn warning light

or yellow worning reflector

Plastic drum with steady burn light

may be used with drums for

may be amitted.

capability is provided, drums

safety as required in the plans.

3. Vertical Panels on flexible support

may be substituted for drums when the

shoulder width is less than 4 feet.

ore not required on one-way roadway

Pla

Pla

Pla

Pla


Pla

Increase number of plastic druns on the side of approaching traffic if the crown width makes it necessary. Iminimum of 2


width makes it necessory. (minimum of 2 and maximum of 4 drums)

PLAN VIEW


CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones



One-Piece cones



Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- Traffic cones and tubular markers shall be predominantly arange, and meet the height and weight requirements shown above.
- One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- Two-piece comes may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shawn above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined an BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is an-site to maintain them in their proper upright position.
- 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

FILEE	bc-21.dgn	ON: T:	r00T	CA: TxDOT	Dat 1	TxDOT	CKI TXOOT
(C) 1x001	November 2002	CONT	SECT	JOB		н	GPWAT
	REVISIONS	6392	61	001		IH.	30, ETC
9-07	B-14 5-21	DIST		COUNTY			SHEET NO.
7-13	2-21	PAR		HUNT, E	TC		16

18/2021 4: 30: 18 PM

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing powement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Payement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone povement markings shall be installed in accordance with Item 662, "Work Zone Povement Markings."

RAISED PAVEMENT MARKERS

- Roised payement markers are to be placed according to the patterns on BC(12).
- All raised povement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAYEMENT MARKERS" and Departmental Material Specification BMS-4200 or BMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone payement markings within the work limits.
- Work Zone povement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Morkings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification I tem 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement morkings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Povement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification 1tem 677 for "Eliminating Existing Povement Markings and Markers".
- The removal of pavement markings may require resurfacing or seat coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type povement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-pointing of the morkings SHALL NOT BE permitted.
- Removal of roised povement markers shall be as directed by the Engineer.
- Removal of existing payement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAYEMENT MARKINGS AND MARKERS," unless atherwise stated in the plans.
- 10. Block-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAYEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the randway.
 - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the fallowing test. Affix five (5) tabs at 24 inch intervals an an asphaltic payement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised povement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised povement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidenorks shall be bituminous material hat applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemorks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body),
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICAT	ONS
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, randway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

			_			
FILE: DC-21.dgn	DN: Ti	*DOT	cu: TxDOT	DWI	TxDO1	CK: TxDO
©TxDOT February 1998	CONT	5ECT	JOH			41CHWAT
REVISIONS	6392	61	001		IH	30, ETC
2-98 9-07 5-21 1-02 7-13	DIST	1	COUNTY			SHEET NO.
11-02 8-14	PAR		HUNT, E	TC		17

STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS 60" · 3" Type Y buttons Type II-A-A 000/ 0 0 10 Yellow Type I-C , I-A or II-A-A Type W or Y buttons 60" White or Yellow Type I-C Type W buttons 0 0 Type I-C or II-A-A-30,"+/-3" 70000 51 51 Type W or Y buttons 40' ± 1' White or Yellow Type I-C or II-A-A (when required) 1-2-Type I-C or II-C-R 5' ± 6" Raised Povement Markers 20' ± 1' Centerline only + not to be used on edge lines **SHEET 12 OF 12** Traffic Safety Division Standard Texas Department of Transportation BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS BC(12)-21

bc-21.dgn

© 1xD01 February 1998

DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO

HICHBAY IH 30, ETC


JOB


001

HUNT, ETC

6392 61

PAR





	LEGEND								
	Type 3 Barricade		Channelizing Devices						
	Heavy Work Vehicle		Truck Mounted Attenugtor (TMA)						
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)						
_	Sign	♦	Troffic Flow						
a	Flag	ПO	Flagger						

Posted Speed	Formulo	Minimum Destroble Toper Lengths ***		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Specing	Suggested Longituding) Buffer Space	Stopping Signt Distance	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	-8-	
30	ws ²	1501	1651	1801	30'	601	120'	90,	200'
35	L= WS	2051	2251	245"	35"	701	160'	120'	2501
40	00	2651	2951	3201	401	80'	240'	1551	3051
45		450'	4951	5401	45"	90'	320'	1951	3601
50		5001	5501	600.	50	100'	400'	240'	425'
55	L-WS	550'	6051	6601	55	110'	5001	295'	495'
60	- "-	600,	660'	720'	60	1201	600'	3501	570'
65	:	6501	715'	7801	65'	130'	7001	410'	645'
70		7001	770'	840'	701	140'	800,	475'	7301
75		7501	8251	9001	751	1501	9001	540'	8201

* Conventional Roads Only

** Taper lengths have been rounded off.
L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

1	TYPICAL USAGE							
	MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY			
		1	1		_			

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.

2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.

3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE

ROAD AHEAD" sign, but proper sign specing shall be maintained.

Sign spocing may be increased or an additional CW20-10 "ROAD WORK AHEAD" sign may be used if advance warning cheed of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
 A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet.

in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricodes or other channelizing devices may be substituted for the Shadow Vehicle and TMA.

6. Additional Shadow Vehicles with TMAs may be positioned off the poved surface, next to those shown in order to protect wider work spaces.

TCP (1-20)

7. R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roodways with less than 2000 ADT, work spaces should be no longer than 400 feet. 8. R1-2 "YIELD" sign with R1-20P "TO ONCOMING TRAFFIC" plaque shall be placed on a support

at a 7 foot minimum mounting height.

TCP (1-2b)

9. Flaggers should use two-way radios or other methods of communication to control traffic. 10. Length of work space should be based on the ability of flaggers to communicate.

1. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).

2. Channelizing devices on the center-line may be amitted when a pilot car is leading traffic and approved by the Engineer.

13. Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.


Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP(1-2)-18

FILE: tcp1-2-18.dgn	DNI		CKI	DWI		CRI
© 1x001 December 1985	CONT	SECT	HOL		H	CHRET
4-90 4-98	6392	61	001		IH :	30, ETC
2-94 2-12	DIST		COUNT	TV Y		SHEET NO.
1-97 2-18	PAR		HUNT.	ETC		20



	LEGEND								
· · · · · ·	Type 3 Barricade	• •	Channelizing Devices						
₽	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
Ê	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)						
_	Sign	₩	Traffic Flow						
a	Flag	TO	Flagger						

Speed	Formula	Minimum Desiroble Toper Lengths **X		Spacili Channe	Suggested Moximum Specing of Channelizing Devices		Suggested Longitudinal Buffer Space	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	"X" Distance	-8-
30	WS ²	1501	1651	1801	30'	60'	1201	90'
35	L = WS	2051	2251	2451	35'	701	160'	1201
40	80	265"	2951	3201	40′	80'	240'	1551
45		450'	4951	5401	45'	90'	320'	1951
50		5001	5501	600'	501	1001	4001	240'
55	L=WS	5501	6051	6601	55′	110'	5001	2951
60		600'	6601	7201	60'	120'	6001	350'
65		6501	7151	7801	65'	1301	7001	4101
70		7001	7701	8401	70'	140'	800'	4751
75		7501	825'	900.	75′	1501	9001	540'

* Conventional Roads Only

₩ Taper lengths have been rounded off.

L-Length of Toper (FT) W-Width of Offset (FT) S-Posted Speed (MPH)

	TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY			
	1	1					

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.

- 2. All troffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.

 3. The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
- 4. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain i place, Type 3 Barricades or other channelizing devices may be substituted
- for the Shadow Vehicle and TMA. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

6. If this TCP is used for a left tone closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

7. Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/25 where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.





Traffic Operations Division Standard

TRAFFIC CONTROL PLAN LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS

TCP(1-4)-18

Dive		CE	041		CRI
CONT	SECT	J08			(IGHAY
6392	61	001		[H	30, ETC
0151		COUNT	1		SHEET NO.
PAR HUNT, ET		ETC		21	
	6392 0151	6392 61 b151	6392 61 001 0151 00000	6392 61 001 0151 COUNTY	CONT SECT JOB





ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- 2. The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Removal of the Temporary Rumble Strips should be occomplished before removing the advance warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted povements or unpoved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate
 TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lone two-way application may utilize a flagger, an AFAD or a portable traffic signal.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment.

	LEGEND								
	Type 3 Barricade		Channelizing Devices						
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
	Trailer Mounted Flashing Arrow Panel	(M)	Portable Changeable Message Sign (PCMS)						
-	Sign	♦	Traffic Flow						
Q	Flag	гO	Flagger						

Posted Speed	Formula	Minimum Desiroble Toper Lengths **		Spacili Channe		Minimum Sign Specing	Suggested Langituding Buffer Space	
*		10° Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	*B*
30	ws2	1501	1651	180*	301	60'	120'	90,
35	L = 10	205'	225"	245"	35'	701	160'	120'
40	80	2651	295"	3201	401	80'	240'	155'
45		450'	4951	5401	45'	901	320'	195'
50		5001	550'	600'	50'	100'	400'	240'
55	L-WS	550'	6051	6601	55′	110'	500'	2951
60	- ""	600'	660'	720'	60'	120'	600'	350'
65	- 9	6501	7151	7801	651	1301	700'	410'
70	3	7001	770'	840	701	140'	8001	4751
75		7501	8251	9001	751	1501	900'	540'

- * Conventional Roads Only
- ** Taper lengths have been rounded off. L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
	1	✓		!		

Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.


1	TABLE 2					
Speed	Approximate distance between strips in an Array					
≤ 40 MPH	10'					
> 40 MPH & < 55 MPH	15'					
> 55 MPH	20'					





TEMPORARY RUMBLE STRIPS


WZ (RS) -16

FILE	wzrs16.dgn	DN: Tx	DOT	CA: TXDOT	1 W C)	TxD07	cki TxDOT	
100x1 ①	November 2012	CONT	SECT	306		HIGHWAT		
*	REVISIONS	6392	61	61 001		IH 3	IH 30, ETC	
2-14 4-16		DIST	COUNTY			SHEET NO.		
4-10		PAR	HUNT, ETC			22		









GENERAL NOTES:

TREE TRIMMING

- 1. TRIM AND REMOVE ALL TREE LIMBS ON THE PAVEMENT SIDE OF THE TRUNK 18' ABOVE THE PAVEMENT OR BRIDGE DECK ELEVATION, UNLESS OTHERWISE SHOWN ON THE PLANS.
- 2. TRIM AND REMOVE ALL TREE LIMBS BETWEEN THE TRUNK AND R.O.W. LINE 10' ABOVE NATURAL GROUND, TERRAIN OR OTHER STRUCTURE ELEVATION, UNLESS OTHERWISE SHOWN ON THE PLANS.

 TREE REMOVAL
- 3. FOR TREES MARKED FOR REMOVAL, THE DIAMETER OF TREES ARE DETERMINED BY MEASUREMENT OF THE TRUNK CIRCUMFERENCE
 - 3' ABOVE THE GROUND. TREES WITH TRUNKS OF LESS THAN 4" DIAMETER ARE CONSIDERED TO BE BRUSH. TREES WITH MULTIPLE TRUNKS AT THE POINT OF MEASUREMENT ARE MEASURED AND PAID FOR SEPARATELY.
- 4. MEASUREMENTS FOR PAYMENT OF TREE DIAMETERS ARE DIVIDED INTO THE RANGES SHOWN IN TABLE 1.


		7401.5.1						
TABLE 1								
TREE TRUNK SIZE FOR TREE REMOVAL PAYMENT								
	TRUNK D	TRUNK DIAMETER * TRUNK CIRCUMFERENCE						
		DIAMETER #		r				
		UPPER LIMIT		UPPER LIMIT				
		IS LESS THAN OR EQUAL TO		IS LESS THAN				
PAY ITEM	1000	ON EQUAL TO	THAIT	ON EUDAE TO				
752 6005	4	12	12 1/2	37 1/2				
752 6006	12	18	37_1/2	56 1/2				
<u>75</u> 2 6007	18	24	56 1/2	75 1/2				
<u>7</u> 52 6008	24	30	75 1/2	94				
752 6009	30	36	94	113				
752 6010	36	42	113	132				
752 6011	42	48	132	151				
752 6012	48	60	151	188 1/2				
752 6013	60	72	188 1/2	226				
752 6019	72	84	226	264				
	84	GREATER THAN 84	264	NOT APPLICABLE				


*SEE GENERAL NOTE *3.

Texas Depart	tment of Tra	nsp	ortatio	n	Mainte Divisio Standa	n	
TREE AN	D BRI	JS	н ғ	REN	/OV	AL	
	TRB-1	5					
FILE	Dat 1ED		CELLUS	040.16	0	ÇKI	
©Tx00T MARCH 2015	CONT	96.01	804		×104	HIGHMAY	
PEVISIONS	6392	61	00		IH 30.		

Fixed robbe 1 to 2014 Specificati

d is governed by the "Texas Engineering Practice ind is made by TxDOT for any purpose whatsoever, lity for the conversion of this standard to ect results or damages resulting from its use. DISCLAIMER
The use of this standc
Act". No warranty of any
TxDOT assumes no responsib





RM 116 . 0.40 MILES BEGINNING POINT BRUSH REMOVED TO WITHIN 1" OF GROUND <4" DIAMETER TRUNK IS DEFINED AS BRUSH UNLESS OTHERWISE DIRECTED

RM 118 • 1.50 MILES ENDING POINT

EXAMPLE: DIVIDED HIGHWAY WITH FRONTAGE ROADS

GENERAL NOTES:

TREE TRIMMING AND BRUSH REMOVAL

- 1. PAYMENT BY THE CENTERLINE MILE IS MADE TO THE NEAREST 1/100 (0.01) MILE.
- 2. LIMITS OF WORK ARE SHOWN AS DISTANCES FROM REFERENCE MARKERS (RM).
- 3. PAY ITEMS BY THE CENTERLINE MILE INCLUDE ALL TREE TRIMMING OR BRUSH REMOVAL IN THE RIGHT OF WAY ON BOTH SIDES OF THE HIGHWAY. FOR DIVIDED HIGHWAYS, THE MEDIAN IS INCLUDED. FOR HIGHWAYS WITH FRONTAGE ROADS, THE AREAS BETWEEN THE FRONTAGE ROADS AND MAIN LANES, AND THE AREAS OUTSIDE OF THE FRONTAGE ROADS ARE INCLUDED.
- 4. BRUSH REMOVAL AND TREE TRIMMING UNDER BRIDGES, IN AND ALONG CHANNELS AND EASEMENTS ARE PAID FOR BY THE ACRE FOR AREAS DESIGNATED ON THE PLANS.



₹ Texas Department of Transportation

Maintenance Division Standard Plans

TREE AND BRUSH REMOVAL

TRB-15(2)

NOT TO	SCALE						SH	IEET	2 OF 2
FILE: TR	B-15(2).DGN	DRAW(CHECKED: DWGLJB	DM: + 17	Cit-		NEG NO. 1	
0	T×DOT APRIL 20	15	STATE DISTRICT	FEDERAL REGION		ATO PRO	JECT	•	SHEET
REVISED:	5/13/2004	LJB	PAR						24
REVISED:	9/24/2004	LJB	COUNTY		CONTROL	SECTION	JO9	HIGHNAY	
REVISED:	APRIL 2015	JEO	HUNT, ETC		6392	61	001	[H 30,E10	

