STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

6386 67 001 IH 35, ETC. DIST COUNTY SHEET NO. AUS TRAVIS, ETC. 1


PLANS OF PROPOSED MATERIALS MAINTENANCE CONTRACT MATERIALS ONLY

PROJECT NUMBER MMC 638667001

TRAVIS, ETC IH 35, ETC

LIMITS: VARIOUS COUNTIES INCLUDING
BASTROP, BLANCO, BURNET, CALDWELL, GILLESPIE, HAYS, LEE, LLANO, MASON, TRAVIS AND WILLIAMSON
FOR THE DELIVERY OF FLEX BASE

CONSISTING OF FLEX BASE



EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION ON NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT.



SUBMITTED FOR LETTING:

4/12/2022



DISTRICT MAINTENANCE ENGINEER

APPROVED FOR LETTING:

4/12/2022

DocuSigned by:

Omar X. De Leon, P.E.

DIRECTOR OF OPERATIONS

Austin District Maintenance Office



Texas Department of Transportation

INDEX OF SHEETS

© 2021		CONT	SECT	JOB		HIGHWAY		
DS:	CK:	6386	67	001	ΙH	35,	ETC.	
DW:	CK:	DIST	COUNTY			SHEET NO.		
		AUS	Т	TRAVIS. ETC.			2	

Project Number: MMC 638667001 Sheet: 3
County: Travis, etc. Control: 6386-67-001

Highway: IH 35, etc.

GENERAL NOTES:

GENERAL

Contractor questions on this project are to be addressed to the following individual(s):

Pre Bid Contact List

District Maintenance Susana. Ceballos@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Written notice will be given to begin work on this project.

Work must begin within seven (7) calendar days after such notification. Time charges will begin when work begins regardless if it falls within seven (7) calendar days of the notification to begin work.

The contractor will have "One hundred twenty" (120) calendar days to complete all work under this contract.

Work under this contract consists of "Flex Base Material Delivery" at various locations in "Bastrop, Blanco, Burnet, Caldwell, Gillespie, Hays, Lee, Llano, Mason, Travis, and Williamson Counties".

Prior to beginning operations, the Department will arrange a preconstruction conference between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the contract, proposed procedures and the plans for performing the work while providing for safe passage of traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

Each contract is considered separate and individual from others. Requirements to complete work on any or all contracts may occur at the same time. If requests are issued at the same time, it is expected that the work will be completed in the time frame allowed.

Project Number: MMC 638667001 Sheet: 3
County: Travis, etc. Control: 6386-67-001

Highway: IH 35, etc.

Material orders and delivery are expected to be fulfilled no later than 21 calendar days after request for material is made. Delivery of materials will be coordinated by the responsible Maintenance Supervisor:

Bastrop	Robert Wilson	512-359-6914	Robert.Wilson@txdot.gov
Blanco	Scott D. Scott	830-868-7166	Scott.Scott@txdot.gov
Burnet	Chris Hall	512-756-2315	Christopher.Hall@txdot.gov
Caldwell	Michael Self	512-398-2412	Michael.Lynn.Self@txdot.gov
Gillespie	Logan Ketron	830-997-4362	Logan.Ketron@txdot.gov
Hays	Jesse Serna	512-353-1061	Jesse.Serna@txdot.gov
Lee	Marcus Snowden	512-253-6070	Marcus.Snowden@txdot.gov
Llano	James Low	325-247-5146	James.Low@txdot.gov
Mason	Cole Farmer	325-347-6447	Cole.Farmer@txdot.gov
Travis East & Central	Greg Stephens	512-997-2267	Gregory.Stephens@txdot.gov
Travis North	Anthony Reitan	512-331-5361	Anthony.Reitan@txdot.gov
Travis South	Ronald Switzer	512-627-9874	Ronald.Switzer@txdot.gov
Williamson East	Jackie Volek	512-365-5254	Jackie.Volek@txdot.gov
Williamson West	Chris Rizzo	512-930-4700	Chris.Rizzo@txdot.gov
Special Jobs	Jason Whitworth	512-292-2440	Jason.Whitworth@txdot.gov
Austin District Toll	Steve Schmidt	737-600-3596	Steven.Schmidt@txdot.gov
IH 35 PBC	Russ Broeckel	512-298-7924	Russ.Broeckel.@txdot.gov

ITEM 3 – AWARD AND EXECUTION OF CONTRACT

A work order will be issued to the contractor for specific items and quantities to be delivered as well as days to complete the work order and expected delivery date. The contractor will contact the responsible maintenance supervisor on the delivery date confirming delivery time.

This Contract includes non-site-specific work. Multiple work orders will be used to procure work of the type identified in the Contract at locations that have not yet been determined.

ITEM 6 - CONTROL OF MATERIALS

Use materials from pre-qualified producers. A list of material producers pre-qualified by the Construction Division (CST) of the Texas Department of Transportation (TxDOT) can be found at the following website: https://www.txdot.gov/business/resources/producer-list.html

The Contractor is responsible for furnishing all materials included in this contract. Materials provided by Contractor will be new unless otherwise shown on the plans or approved. The Contractor must receive approval from the Engineer prior to ordering materials for this contract.

The Contractor is required to have sufficient supply of material to deliver within the allotted time.

Give a minimum of 1 business day notice for materials, which require inspection at the Plant.

Furnish uncontaminated materials of uniform quality that meet the requirements of the plans and specifications. Materials may be rejected if evidence of contamination is present. Additional sampling for acceptance may be required.

General Notes Sheet A General Notes Sheet B

Project Number: MMC 638667001 Sheet: 3 A County: Travis, etc. Control: 6386-67-001

Highway: IH 35, etc.

Delivery of material will not be accepted without scale certifications and tested/approved material received 48 hours prior to scheduled delivery.

ITEM 8 – PROSECUTION AND PROGRESS

Time charges will be in accordance with Article 8.3.1.5 "Calendar Day".

In accordance with Article 8.6 "Failure to Complete Work on Time," liquidated damages shall be charged each day for failure to meet each work order. This will include:

- 1. Failure to deliver at the starting date or continually progress on the work order.
- 2. Failure to deliver the required materials per day.
- 3. Failure to complete work order within 3 weeks (21 calendar days) from the issue date on work order.

The amount assessed per day for liquidated damages shall be 1 % of the estimated cost of the work order, not to be less than \$200 per day and not to exceed \$500 per day.

ITEM 9 – MEASUREMENT AND PAYMENT

In accordance with Article 9.1," Measurement of Quantities," furnish the tare and maximum gross weights as well as the volume capacity of all vehicles, trucks, truck-tractors, trailers, semitrailers, or combination of such vehicles used to deliver materials for the contract. Also, furnish calculations supporting these weights and capacities. Provide all measurements required for pay a minimum of 2 days before the equipment is used.

In accordance with Article 9.2 "Plans Quantity Measurement," plans quantity measurement requirements are not applicable for this contract. Quantities shown in the plans are for bidding purposes only. TxDOT does not guarantee that all quantities shown in plans will be requested for delivery.

Contractor is responsible for obtaining annual overweight tolerance permit if hauling material which exceeds the legal road weight.

SS 8007 – FLEXIBLE BASE (MATERIALS ONLY)

Work order will direct delivery method and vehicle type (end dump or belly dump).

General Notes Sheet C

Sheet: 3 A

Control: 6386-67-001



Quantity Summary

CONTROLLING PROJECT ID 6386-67-001

DISTRICT Austin HIGHWAY IH0035

COUNTY Travis

		CONTROL SECTI	CONTROL SECTION JOB 6386-67-001				
PROJECT ID A00180509							TOTAL FINAL
COUNTY Travis						TOTAL EST.	
		HIGHWAY IH0035				THVAL	
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	8007-6051	FL BS (STE DEL)(TY A GR 5)(DROP OFF)(1)	CY	1,500.000		1,500.000	
	8007-6052	FL BS (STE DEL)(TY A GR 5)(DROP OFF)(2)	CY	1,500.000		1,500.000	
	8007-6053	FL BS (STE DEL)(TY A GR 5)(DROP OFF)(3)	CY	1,000.000		1,000.000	
	8007-6054	FL BS (STE DEL)(TY A GR 5)(DROP OFF)(4)	CY	500.000		500.000	



DISTRICT	COUNTY	CCSJ	SHEET
Austin	Travis	6386-67-001	4

Austin District Maintenance Office



Texas Department of Transportation

LOCATION SUMMARY

		72. 21					
© 2020		CONT	SECT	JOB	HIGHWAY		IAY
S:	٩:	6386	67	001	ΙH	35,	ETC.
w:	٩k:	DIST		COUNTY		SHEE	T NO.
	I	AUS	TI	RAVIS. ETC			5