


STATE OF TEXAS


DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6412-53-001
 CSJ: 6412 - 53 - 001
 HIGHWAY: SH 0031
 LIMITS OF WORK: NAVARRO COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
 DESCRIPTION: FLEXIBLE BASE


RECOMMENDED FOR LETTING:	6/20/2022
	Date
	
AREA ENGINEER	

RECOMMENDED FOR LETTING:	6/30/2022
	Date
DocuSigned by: 	
345B765EB03F406... DIRECTOR OF OPERATIONS	

INDEX OF SHEETS

- | | |
|-------|---------------------------|
| 1 | TITLE SHEET |
| 2 | ESTIMATE & QUANTITY SHEET |
| 3A-3D | GENERAL NOTES |
| 4 | DELIVERY SITE SHEET |

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2022		 Texas Department of Transportation	
FED.RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	MMC 6412-53-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	DALLAS	NAVARRO	
CONTROL	SECTION	JOB	HWY NO.
6412	53	001	SH0031
FILENAME			DATE
MMC 6412-53-001			6/13/2022



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6412-53-001

DISTRICT Dallas
HIGHWAY SH0031

COUNTY Navarro

CONTROL SECTION JOB		6412-53-001			
PROJECT ID	A00189793	TOTAL EST.			
COUNTY	Navarro	TOTAL FINAL			
HIGHWAY	SH0031				
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	8007-6035	FL BS (SITE DEL)(TY D GR 4)(SITE 5)	TON	2,000.000	
	8007-6036	FL BS (SITE DEL)(TY D GR 4)(SITE 6)	TON	1,500.000	
				2,000.000	
				1,500.000	



DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Navarro	6412-53-001	2

Project Number: MMC-641253001

Control: 6412-53-001

County: Navarro County

Highway: SH0031

GENERAL NOTES:

General:

The purpose of this contract is to supply “**Flexible Base**”, materials only, for the Navarro County Maintenance Sections as specified in the plans.

Provide and maintain a dedicated email address for receipt of work orders and correspondence throughout the term of this contract. Acknowledgement of emailed work order/callouts is required no more than 12 hr. from notification.

Contractor’s attention is called to the fact that all Department property will be protected during all phases of the execution of the contract and any damages incurred due to Contractor’s operation will be repaired and replaced at the Contractor’s expense.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Prior to beginning operations, the Department will arrange a preconstruction meeting between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

Coordinate work through:

Joseph Lanoue, Navarro County, Maintenance Section Supervisor
100 SW CR 1000
Corsicana, Texas 75110
903-874-5361

Bids will be received at 4777 E. Hwy 80, Mesquite, Texas 75150-6643.

Contractor questions on this project are to be emailed to the following individuals:

Juan Paredes Juan.Paredes@txdot.gov
Joseph Lanoue Joseph.Lanoue@txdot.gov
Amber Coats Amber.Coats@txdot.gov

Project Number: MMC-641253001

Control: 6412-53-001

County: Navarro County

Highway: SH0031

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Attention is directed to the possible presence of underground utilities owned by the Texas Department of Transportation (irrigation, signal, illumination and surveillance, communication, and control) on the right of way. Call TxDOT for locates at 214-320-6682, for irrigation systems call (214-320-6636), or the appropriate department of the local city or town a minimum of 48 hr. in advance of excavation.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Cost associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Item 2 – Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal.

Order plans from any Reproduction Company listed at:

http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

View or download plans at:

<http://www.dot.state.tx.us/business/plansonline/plansonline.htm>

Item 3 – Award and Execution of Contract:

This contract is non-site specific, only materials received (pickup) or delivered to the Delivery Sites within state right of way or state property specified in the plans will be paid.

Material will be made available for pickup or delivery, as indicated in the plans.

Project Number: MMC-641253001

Control: 6412-53-001

County: Navarro County

Highway: SH0031

When material is specified to be picked up by TxDOT, material shall be made available within 48 hrs. or as directed in the Work Order.

When material is specified to be delivered, successfully deliver each Work Order within 7 calendar days upon notification, or as directed in the Work Order. The delivery hours will be Monday through Friday, 8:00 AM to 5:00 PM or as directed in the Work Order.

Notify the Maintenance Section Supervisor 24 hours in advance prior to delivery.

Item 7 – Legal Relations and Responsibilities:

Appropriate Personal Protective Equipment (PPE), including Department-approved safety hats and safety shirts, will be worn by all workers and visitors when:

Workers are outside of vehicles at all outdoor worksites. This includes those who occasionally visit worksites either on the highway surface or right of way.

Working in areas where there is danger of head injury from impact, from falling or flying objects, or from electrical shock or burns.

Non-compliance with this requirement will be grounds of suspension of work.

All work on this contract will be scheduled and directed by the Maintenance Section Supervisor.

Any hazardous spills or releases of this material on TxDOT property will be promptly cleaned and remediated at Contractor's expense, including cost of spilled material.

Item 8 – Prosecution and Progress:

Contract days will be charged in accordance with Section 8.3.1.5., "Calendar Day" (120 days).

Working days will be charged in accordance with Section 8.3.1.4., "Standard Workweek".

Individual Work Order charge days shall run concurrently with Contract time charges.

Unless otherwise directed, prosecute the work continuously to completion of the Callout Work Request.

In accordance with Article 8.6, "Failure to Complete Work on Time", liquidated damages will be charged for failure to complete each Work Order in the specified number of days. The amount assessed per day for liquidated damages will be five percent (5%) of the estimated cost of the Work Order, but not to be less than \$250 per day and not to exceed \$1,000 per day.

Project Number: MMC-641253001

Control: 6412-53-001

County: Navarro County

Highway: SH0031

Item 500 – Mobilization:

Mobilization does not apply to this Maintenance Materials Contract.

Item 8007 – Flexible Base (Materials Only):

Grading Requirements

Tests to be in accordance with TXDOT Standard Test Methods

Soil Constants

Item Desc.	Linear Shrinkage	LL	Wet Ball	WBMV (incr. passing #40 sieve)
Item 247 FlexBase	6.0 max.	40 max.	40 max.	20% max.


PERCENT RETAINED ON SIEVE:

1-3/4"	7/8"	3/8"	No. 4	No. 40
0	10-35	30-50	45-65	70-85

Flexible Base will not contain more than 1% by weight of clay balls.

SITE NO.	MAINTENANCE OFFICE	STOCKPILE LOCATION*	ITEM NO.	DES. NO.	UNIT	QUANTITY
5	Navarro	100 SW CR 1000, Corsicana, Tx 75110	8007	6035	TON	2000
6	Navarro	1000Ft East of 3100 SH31 Corsicana Tx 75109	8007	6036	TON	1500

* APPROXIMATE LOCATIONS FOR DELIVERY

			
DELIVERY SITE SHEET			
DESIGN	FED RD. DIV. NO.	MAINTENANCE PROJECT NO.	HIGHWAY NO.
DP	6	MMC 6412-53-001	SH0031
GRAPHICS			
DP	STATE	DISTRICT	COUNTY
CHECK DP	TEXAS	DALLAS	AVARR
CHECK DP	CONTROL	SECTION	JOB
	6412	53	001
			4