


STATE OF TEXAS


DEPARTMENT OF TRANSPORTATION


MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6424-26-001
 CSJ: 6424 - 26 - 001
 HIGHWAY: FM 2728
 LIMITS OF WORK: KAUFMAN COUNTY
 ROCKWALL COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
 DESCRIPTION: Hot Mix

RECOMMENDED FOR LETTING:	09/21/22
	Date
	
AREA ENGINEER	


RECOMMENDED FOR LETTING:	10/25/2022
	Date
DocuSigned by:	
	
72258D0350B94E4	
MAINTENANCE ENGINEER	

RECOMMENDED FOR LETTING:	10/26/2022
	Date
DocuSigned by:	
	
345B765EB03F406...	
DIRECTOR OF OPERATIONS	

INDEX OF SHEETS

- | | |
|-------|---------------------------|
| 1 | TITLE SHEET |
| 2 | ESTIMATE & QUANTITY SHEET |
| 3A-3C | GENERAL NOTES |

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2022		 Texas Department of Transportation	
FED.RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	MMC 6424-26-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	DALLAS	KAUFMAN	
CONTROL	SECTION	JOB	HWY NO.
6424	26	001	FM 2728
FILENAME			DATE
MMC 6424-26-001			9/21/2022



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6424-26-001

DISTRICT Dallas
HIGHWAY FM2728

COUNTY Kaufman

CONTROL SECTION JOB		6424-26-001		TOTAL EST.	TOTAL FINAL
PROJECT ID	A00191446				
COUNTY	Kaufman				
HIGHWAY	FM2728				
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	8006-6001	SP MIXTURES SP-C PG64-22 (PICKUP)	TON	200.000	200.000
	8006-6005	SP MIXTURES SP-D PG64-22 (PICKUP)	TON	200.000	200.000
	8011-6001	D-GR HMA(SQ) TY D PG 64-22 (PICKUP)	TON	600.000	600.000
	8011-6016	D-GR HMA(SQ)TY C PG 64-22 (PICKUP)	TON	2,000.000	2,000.000



Report Generated By: txdotconnect_internal_ext

Report Created On: Oct 25, 2022 2:25:19 PM

DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Kaufman	6424-26-001	2

Project Number: MMC-642426001

Control: 6424-26-001

County: Kaufman County

Highway: FM2728

GENERAL NOTES:

General:

The purpose of this contract is to supply Hot Mix, materials only for the Kaufman/Rockwall County Maintenance Section.

An item for pickup is included in this contract. Materials shall be available for pickup within 35 miles of the TxDOT office located at 3260 FM 2728 Kaufman Texas 75142 or 901 E. IH 30 Rockwall Texas 75087. Load material into TxDOT equipment at time of pickup.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through:

Bobby Neely, Kaufman/Rockwall County Maintenance Section Supervisor
3260 FM 2728
Kaufman, Texas 75142
972-962-3848

Bids will be received at 4777 E. Hwy 80, Mesquite, Texas 75150-6643

Contractor questions on this project are to be emailed to the following individuals:

Lane Selman Lane.Selman@txdot.gov
Bobby Neely Bobby.Neely@txdot.gov
LeAnn Kemp LeAnn.Kemp@txdot.gov

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Section 10.2 - Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

Project Number: MMC-642426001

Control: 6424-26-001

County: Kaufman County

Highway: FM2728

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Section 10.4 – Scope of Work:

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended once not to exceed 730 calendar days for the entire contract term if mutually agreed.

Section 10.8 - Prosecution and Progress:

There are 365 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Item 500 – Mobilization:

Mobilization does not apply to this Maintenance Materials Contract.

Item 8006 – Superpave Mixtures (Materials Only):

Design and produce the mixture with a gradation that passes below the reference zone as shown in Table 9 for SS3077.

Use aggregate that meets the Surface Aggregated Classification (SAC) B requirement or better.

Materials to be picked up within a 35 mile driving radius of the Kaufman or Rockwall County Maintenance office address as presented under "General".

Item 8011 – Dense-Graded Hot-Mix Asphalt (Materials Only):

Use aggregate that meets the Surface Aggregated Classification (SAC) B requirement or better.

Project Number: MMC-642426001

Control: 6424-26-001

County: Kaufman County

Highway: FM2728

Materials to be picked up within a 35 mile driving radius of the Kaufman or Rockwall County Maintenance office address as presented under "General".