

| Project Number: MMC 6439-96-001 | Control: 6439-96-001 | Project Number: MMC 6439-96-001 | Control: 6439-96-001 |
|---------------------------------|----------------------|---------------------------------|----------------------|
| County: Shelby                  | Highway: FM 3343     | County: Shelby                  | Highway: FM 3343     |
| GENERAL NOTES:                  |                      |                                 |                      |

**PROJECT DESCRIPTION:** This project consists of delivering Flexible Base (material only) to specified site for use on state-maintained roadway within the Shelby County Maintenance Section.

Jeremy King Jeremy.King@txdot.gov Jenna Lenderman Jenna.Lenderman@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

#### https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

**TXDOT PROJECT SUPERVISORS:** All work on this contract will be scheduled and directed by the Maintenance Section Supervisor listed below. Payment will be made monthly for work completed and accepted according to specifications. All payment requests should be directed to the following Maintenance Section Supervisor listed below.

| <u>COUNTY</u> | SUPERVISOR   | ADDRESS                                  | CONTACT #      |
|---------------|--------------|--|----------------|
| Shelby        | Clint Norton | 638 State Hwy 7 East<br>Center, TX 75935 | (936) 598-4113 |

**CONTRACT PROSECUTION:** Each contract awarded by the Department stands on its own and, as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Prior to beginning operations, the Department will arrange a preconstruction conference between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the contract, proposed procedures and the plans for performing the work while providing for safe passage of traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed.

# **ITEM 2: INSTRUCTIONS TO BIDDERS**

View plans on-line or download from the web at: http://www.txdot.gov/business/contractors consultants/plans online.htm

Order plans from any of the plan reproduction companies shown on the web at: http://www.txdot.gov/business/letting-bids/repro-companies.html Bid items on this contract are listed to establish a unit price for each item. Certain items listed in the proposal may not be used if it is determined by the Engineer that the work will not be required. Actual work performed as directed will be paid utilizing these prices with no further compensation made regardless of the final quantities.

### **ITEM 4: SCOPE OF WORK**

The contract may be extended twice if in the judgment of the Engineer, the contractor has satisfactorily fulfilled the terms and conditions of the contract. The extension must be agreed upon in writing by both parties to the contract and may be extended for an additional period of time not to exceed the original contract time period. The extended contract may be for additional quantities up to the original bid quantities plus any quantities added by an approved change order. The extensions shall meet the terms and conditions of the original contract or any mutually agreed modifications to the said terms and conditions by one or more cumulative change orders. The Engineer will set a deadline for completing the agreements. This deadline will be based in the time needed to re-let and award a new contract if no extension is agreed upon.

### **ITEM 8: PROSECUTION AND PROGRESS**

Contract Time - The number of calendar days for this project shall be 120 days or until contract funds are expended.

Time charges will be in accordance with Article 8.3.1.5 "Calendar Day".

For "pick-up" operations, have materials ready within a 48 hours' notice, and for "delivery" operations, have the materials ready within 7 calendar days, unless otherwise approved by the Engineer. Notify the Shelby County Maintenance Supervisor when encountering any unforeseen delays.

Demurrage rates and terms will be discussed during the preconstruction meeting.

# **ITEM 500: MOBILIZATION**

Mobilization does not apply to this materials contract.

| Project Number: MMC 6439-96-001 | Control: 6439-96-001 | Project Number: MMC 6439-96-001 | Control: 6439-96-001 |
|---------------------------------|----------------------|---------------------------------|----------------------|
| County: Shelby                  | Highway: FM 3343     | County: Shelby                  | Highway: FM 3343     |

ITEM 8007: Flexible Base (MATERIALS ONLY)

Delivery cost for each delivery will be calculated and included in the per ton cost.

For Type E material, furnish crushed limestone produced and graded from oversize quarried aggregate that originates from a single, naturally occurring source. Do not use caliche, iron ore, gravel, or multiple sources.

Flexible Base will not contain more than 1% by weight of clay balls.

Flexible Base will be provided with a minimum PI of 2. Flexible Base will be provided with a minimum bar linear shrinkage of 2%.

This contract is for small quantities only. A work order will be issued to the contractor a minimum of a 48 hours' notice and the contractor shall be able to provide agreed upon amounts as needed.

Contact the Shelby County Maintenance Supervisor at least 1 hour prior to delivery.

The Contractor's driver shall report to the Shelby County Maintenance Supervisor or their representative at the time of arrival at the final delivery location and obtain a signature documenting the date and time of delivery and departure.

The site location for delivery is as follows:

 Site 1 - FM 3343 (RM 314-317) 6,000 Tons Needed

For Delivery Operations

• Roadway delivery times will be scheduled by the Shelby County Maintenance Supervisor.

R

# **Estimate & Quantity Sheet**

CONTROLLING PROJECT ID 6439-96-001

DISTRICT Lufkin HIGHWAY FM3343 COUNTY Shelby

Texas Department of Transportation

|                      | or mansport                     | allon                                 |         |            |                |           |  |
|----------------------|---------------------------------|---------------------------------------|---------|------------|----------------|-----------|--|
|                      | CONTROL SECTION JOB 6439-96-001 |                                       |         |            |                |           |  |
| PROJECT ID A00195511 |                                 |                                       |         |            |                |           |  |
| COUNTY               |                                 | She                                   | lby     | TOTAL EST. | TOTAL<br>FINAL |           |  |
|                      |                                 |                                       | HIGHWAY | FM3343     |                |           |  |
| ALT                  | BID CODE                        | DESCRIPTION                           | UNIT    | EST.       | FINAL          |           |  |
|                      | 8007-6063                       | FL BS (SITE DEL) (TY E GR 2) (SITE 1) | TON     | 6,000.000  |                | 6,000.000 |  |



| DISTRICT | COUNTY | CCSJ        | SHEET |
|----------|--------|-------------|-------|
| Lufkin   | Shelby | 6439-96-001 | 3     |

| SUMMARY OF MATERIAL ITEMS              |            |                                       |  |  |
|--|------------|---------------------------------------|--|--|
|  | ITEM NO.   |                                       |  |  |
| COUNTY                                 | HIGHWAYNO. | FL BS (SITE DEL) (TY E GR 2) (SITE 1) |  |  |
| COUNT                                  | HIGHWATNO. | TON                                   |  |  |
| SHELBY SITE 1:<br>FM 3343 (RM 314-317) |            | 6,000                                 |  |  |
| PROJECT TOTALS                         |            | 6,000                                 |  |  |

| QUANTITY<br>SUMMARY                |    |               |  |           |  |  |
|------------------------------------|----|---------------|--|-----------|--|--|
| Texas Department of Transportation |    |               |  |           |  |  |
| CONT SECT JOB HIGHWAY              |    |               |  |           |  |  |
| 6439                               | 96 | 6 001 FM 3343 |  |           |  |  |
| DIST                               |    | COUNTY        |  | SHEET NO. |  |  |

SHELBY

4

LFK