

Project Number: RMC 6442-56-001	Control: 6442-56-001
County: San Jacinto	Highway: US 59, ETC.
CENEDAL NOTES.	

GENERAL NOTES:

Project Description: This project consists of performing tree trimming and brush removal as well as tree removal on various roads in the San Jacinto County. This project also consists of removing trees as directed.

TXDOT PROJECT SUPERVISORS: All work on this contract will be scheduled and directed by the Maintenance Section Supervisor(s) listed below. Payment will be made on a monthly basis for work completed and accepted according to specifications. All payment requests should be directed to the Maintenance Section Supervisor(s) listed below.

COUNTY	SUPERVISOR	ADDRESS	CONTACT #
San Jacinto	Chester Dixon	8066 SH 150 West Shepherd, Texas 77371	(936) 628-3328

CONTRACT PROSECUTION: Each contract awarded by the Department stands on its own and, as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Existing regulatory, warning and guide signs within project limits are to always remain visible to the traveling public. If a sign must be repositioned during construction operations, move and install the sign to an approved location. Use care when working near existing signs and repair or replace signs damaged by work operations. All work involved repositioning existing signs will be subsidiary to various bid items.

There is a potential for work to be done in environmentally sensitive areas within these maintenance sections. All work shall be performed as directed by the appropriate Maintenance Section Supervisor to avoid impacts to these areas.

Furnish materials and make repairs to the existing roadway and right-of-way at any location damaged by construction operations. This work shall be done in an approved manner and will be subsidiary to various bid items.

Minimize vehicles and equipment in construction areas to lessen the impact on existing vegetation. The intent of the plans is to prepare only that portion of TxDOT right-of-way necessary for construction.

Always provide suitable access to adjacent businesses, private property, and side roads.

Remove dirt, silt, rocks, debris and other foreign matter that accumulates in structures due to the Contractor's operations as directed. Keep stream channels open at all times. This work will not be paid for directly but will be subsidiary to pertinent items.

All workers on TxDOT right-of-way shall wear reflective clothing meeting ANSI Class II requirements during the day and ANSI Class III requirements during the night. Only workers actively engaged in the operation of a chainsaw, clipper, or similar device shall be exempt from

Project Number: RMC 6442-56-001

County: San Jacinto

Control: 6442-56-001

Highway: US 59, ETC.

wearing safety vests. Non-compliance with any of these requirements shall be grounds for suspension of work.

Contractor questions on this project are to be addressed to the following individual(s):

Jeremy King Jeremy.King@TxDOT.gov

Tamara Gibson Tamara.Gibson@TxDOT.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 2: Instructions to Bidders

View plans on-line or download from the web at:

http://www.txdot.gov/business/contractors_consultants/plans_online.htm

Order plans from any of the plan reproduction companies shown on the web at:

http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

Item 7: Legal Relations and Responsibilities

The proposed work of this project is the removal and trimming of trees and brush at various roadways within the San Jacinto County Maintenance Section that are hazardous, dying, or protruding into State right-of-way. This activity maintains the original line and grade, hydraulic capacity, and original purpose of the site. Therefore, this project meets the definition of a routine maintenance activity as defined in the TPDES General Permit No. TXR150000 issued March 5, 2023, and TCEQ's TPDES CGP does not apply.

Dispose of all vegetative matter and any other materials removed from State Right of Way in accordance with applicable environmental laws, rules, regulations, and requirements.

Project Number: RMC 6442-56-001	Control: 6442-56-001	Рі
County: San Jacinto	Highway: US 59, ETC.	C

In order to maintain compliance with Chapter 64 of the Texas Parks and Wildlife Code and Migratory Bird Treaty Act (MBTA), construction activities that may affect nests (i.e. tree removal, tree liming, bridge work) shall be conducted outside of the nesting season (March 15 to September 15). In the event birds or active nests (eggs and/or nestlings present) are encountered, contact the engineer prior to conducting work

Portions of roadways within the San Jacinto County Maintenance Section occurs within compartments of the Sam Houston National Forest (SHNF). Below are the following roadways and actions required:

1. <u>FM 945</u>: From 2.14 miles North of SH 150 to 3.77 miles North of SH 150; From 2.68 miles South of SH 150 to 3.25 South of SH 150; From FM 2025 to 0.50 miles West of FM 2025 and from 1 mile West of FM 2025 to 6.10 West of FM 2025

2. <u>FM 1725</u>: From 0.40 miles SE of FM 3081 to 3.30 miles SE of FM 3081; From Tony Tap Rd to 0.45 miles SE of Tony Tap Rd; From 1 mile SE of Tony Tap Rd to 1.45 miles SE of Tony Tap Rd; From 2 miles SE of Tony Tap Rd to 2.22 miles SE of Tony Tap Rd; From 0.30 miles SE of Fostoria Tram Rd to 0.85 miles SE of Fostoria Tram Rd and from 1.40 miles NW of Liberty County Line to 2.28 miles NW of Liberty County Line.

3. <u>FM 2025</u>: From 0.25 miles South of SH 150 to 4.55 miles South of SH 150; From 0.64 miles North of FM 2666 to 0.40 miles South of FM 2666 and from 1.25 miles South of FM 2666 to 1.57 miles North of Liberty County Line

4. <u>SH 150</u>: From 0.10 miles NW of FM 222 to 0.23 miles SE of FM 222 and from 2 miles SE of FM 222 to 2.45 miles SE of FM 222

5. <u>FM 3081</u>: From 0.80 miles SW of FM 1725 to 1.80 miles SW of FM 1725 and From Sandy Creek Rd to 0.25 miles South of Sandy Creek Rd.

6. \underline{FM} 2666: From FM 2025 to 2.50 miles East of FM 2025 and from 1.27 miles SW of SH 150 to 2.50 miles SW of SH 150

7. FM 2693: From 1.08 miles NW of SH 150 to 3.30 miles NW of SH 150

8. FM 3018: From 1 mile SW of FM 946 to 1.50 miles SW of FM 946

NO trees along these roadways are to be cut or otherwise damaged without prior approval from US Forest Service (SHNF) and Area Engineer.

Project Number: RMC 6442-56-001

above roadways.

Control: 6442-56-001 **Highway:** US 59, ETC.

County: San Jacinto Highway: US : Area Engineer shall notify US Forest Service (SHNF) prior to commencing work on the

Red-cockaded Woodpeckers (federally endangered species) habitat is present adjacent to the ROW along the following roadways:

- On FM 945 from FS 274 to 4.1 miles North of FS 274

- On FM 945 from FFS 256 to 0.55 miles South of FS 256

- On FM 2025 from Lower Vann rd. to 1.0-mile South of Lower Vann Rd

- On FM 2666 from FM 2025 to 1.2 miles East of FM 2025

- On FM 2693 from 2.6 miles East of the Walker County line to 4.0 miles east of the Walker County line

A. Contact LFK District ENV if work is to occur on the above roadway limits.B. NO trees along these highways are to be cut or otherwise damaged without prior approval from LFK District ENV.

Do not fell trees within US Forest Service boundary without prior approval. Timber cut within US Forest Service boundary remains the property of the US Forest Service and may require measured lengths to be cut or for trees to be felled entirely onto US Forest Service land. Such requirements will not be paid for directly but be subsidiary to bid items.

Contractor to repair or replace in kind, at their own expense, any historic materials damaged (buildings, historical markers, etc.) while executing the work. Contractor is responsible for locating replacement source for historical materials damaged in the course of the work. TxDOT-Environmental Affairs Division is to be informed of proposed repairs to facilitate consultation with Texas Historical Commission prior to the execution of repairs.

Item 8: Prosecution and Progress

Contract Time – The number of working days for this project shall be 365 days or until contract funds are expended.

For this project, working days will be computed and charged in accordance with Item 8, Section 3.1.5, "Calendar Day".

Contractor shall be on site within 48 hours for emergency work, and within five business days for regular callout work orders, unless otherwise agreed upon with the Engineer.

Notify the Engineer or his Representative at least 24 hours prior to beginning work.

Project Number: RMC 6442-56-001	Control: 6442-56-001	Project Number: RMC 6442-56-001	Control: 6442-56-
County: San Jacinto	Highway: US 59, ETC.	County: San Jacinto	Highway: US 59, E
Item 9: Measurement and Payment This Contract includes callout work. In accordance with Measurement", plans quantity measurement requirement		Restrict construction work to single lane widths with closures shall conform to the traffic control plan for povernight closures will be permitted.	
shown are for estimates only and payment will be based		Provide temporary Rumble Strips as shown on Work	Cone standards when lane closures are

NONCOMPLIANCE PENALTY - A penalty will be assessed for each instance the contractor is in noncompliance. A noncompliance instance is defined by the following:

- The contractor fails to begin work at the specified time and/or location(s).
- The contractor does not have all the personnel and/or pieces of equipment necessary to fulfill the requirement of the item(s) called out at the specified time and/or location(s).
- The contractor does not complete the work continuously, unless approved by the Engineer.

The Noncompliance Penalty will be deducted from any money due or to become due for any completed item(s) or work. The Noncompliance Penalty will be assessed as follows: \$250 per instance, per location, and per day until the contractor returns to a state of compliance.

Item 502: Barricades, Signs and Traffic Handling

Traffic Control Plan (TCP):

Ensure the Contractor's Responsible Person (CRP) or their alternate for Barricades, Signs and Traffic Handling is available at all times and able to receive instructions from the Engineer or authorized Department representative. The CRP shall be a person that is usually at the project site during normal working hours.

Furnish and maintain all warning signs, flaggers, channelizing devices, etc. required for traffic control on this contract in accordance with Item 502.1 & 502.2. This work will not be paid for directly but will be considered subsidiary to the various bid items.

For protection of the traveling public, direct traffic through the work area using signs, flaggers and other devices. Required signs are shown in the plans on the Barricade And Construction Standards and Traffic Control Plan Sheets. The latest edition of the "Texas Manual On Uniform Traffic Control Devices" shall also be used as a guide for handling traffic on this project.

Texas Transportation Code 547.105 authorizes the use of warning lights to promote safety and provides an effective means of gaining the travelling public's attention as they drive in areas where construction crews are present. In order to influence the public to move over when high risk construction activities are taking place, minimize the utilization of blue warning lights. These lights must be used only while performing work on or near the travel lanes or shoulder where the travelling public encounters construction crews that are not protected by a standard work zone set up such as a lane closure, shoulder closure, or one-way traffic control. Refrain from leaving the warning lights engaged while travelling from one work location to another or while parked on the right of way away from the pavement or a work zone.

ETC.

necessary.

Provide a flashing arrow panel and a truck-mounted attenuator to supplement required signs and devices for each lane closure.

Provide adequate flaggers to protect the traveling public. All flaggers shall wear approved hardhats and reflective safety vests while flagging. Safety vests shall be clean and worn fully fastened.

Install "Be Prepared to Stop" (CW20-7B) and "Flagger Ahead" (CW22-7D) signs when flaggers are present. Position the signs where good visibility and traffic control can be maintained.

Provide one high-intensity yellow, rotating dome-light on all equipment such as distributors, spreader boxes, lay-down machines, rollers, backhoes, road graders, loaders, etc. Mount lights high enough to be visible from all directions and operating when the equipment is within 30 ft. of the travel way. On all other equipment such as trucks, trailers, automobiles, etc., use emergency flashers while within the work zone.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement

Item 752: Tree and Brush Removal

All work, except emergency work, is to be completed between September 15th and March 15th to insure compliance with the Migratory Bird Treaty Act (MBTA). Emergency work is any work required to eliminate a potential hazard(s) to the traveling public or from causing property damage.

The Contractor shall become knowledgeable of the location of utilities within the right-of-way and shall use care when working near them.

The Contractor shall be responsible for contacting all utility companies and locating all underground utilities prior to stump grinding and/or other excavating. The Contractor shall use care when working near these utilities so as not to damage them.

For "Tree Trimming / Brush Removal" and "Tree Trimming / Brush removal (Channels)", move in and complete the work continuously unless otherwise approved by the Engineer.

Project Number: RMC 6442-56-001	Control: 6442-56-001	Project Number: RM
County: San Jacinto	Highway: US 59, ETC.	County: San Jacinto

Complete at least 1centerline mile of tree trimming, brush and tree removal per day.

Trim branches, limbs, and brush to a distance of 30 feet from the edge of pavement and a height of 18 feet above the pavement unless otherwise directed. Trimming shall be performed so as to leave a neat and uniform appearance. Quantities shown are for both sides of the roadway.

The equipment used to trim limbs and remove brush shall be approved by the maintenance supervisor. A boom axe will not be allowed when trimming limbs. The Contractor shall remove all existing limbs and small trees on the ground within the limits of brush removal.

For trimming/ brush removal (channels) clear 50 feet either side of culvert center line and from right-of-way line to right-of-way line. If Waters of the US location, no work shall be performed within the channel and debris, or discharge/fill material shall not enter the channel. Equipment used at Waters of the US locations shall not enter the channel under any circumstance.

Trees to be removed shall be marked by the State with a red, white or orange "X", painted on the trunk. No other trees shall be removed without prior approval from the Engineer

Remove trees as designated. After the removal of the designated trees, the Contractor may move out, and the remaining tree removal for this contract will be used on an as needed basis. The Engineer will send the Contractor written notification requiring him to move in and begin tree removal each time there are a minimum of 10 trees to be removed and mobilization will be paid for on a callout basis. After completion of the required tree removal the Contractor may again move out, and this procedure will continue for the duration of the contract.

Pick up and remove all trees and limbs felled from right-of-way on the same day, unless otherwise approved.

Remove trees that are already down in the right-of-way. Cut and measure trees that have fallen from private property at the right-of-way line. These trees will be paid for in the same manner as trees that are to be felled and removed.

If the trees and limbs are chipped/mulch, the chips must be spread evenly near the ROW line (typically the wood line on the back slope of the ditch). Do not place chips in the ditch line. In areas with driveways or cross culvert, consult the Engineer prior to chipping for an approved location.

Grind all limbs and protruding roots. Grind all stumps to a depth of 12 inches below the ground level. Backfill any resulting holes to the level of the surrounding ground. If, in the opinion of the Engineer, stumps on back slope cannot be ground, trees shall be cut flush with surrounding ground line.

The Contractor will be required to furnish materials and make repairs to the existing roadway and right-of-way, including rutting, at any location damaged by the Contractor's operations. This work shall be done in a manner satisfactory to the Engineer and will be considered subsidiary to various bid items.

Project Number: RMC 6442-56-001

Control: 6442-56-001

Highway: US 59, ETC.

Remove a tree in increments when cutting the trees at ground level may endanger overhead utility lines or damage private property.

Removal of brush, limbs, debris, and trees less than 4 inches in diameter are considered brush and will be subsidiary to Item 752.

Trees that have fallen onto the right-of-way from private property will be cut and measured at the right-of-way line.

Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

Truck Mounted Attenuators (TMA's) shall meet the requirements of this item and the Department's Compliant Work Zone Traffic Control Device List.

Truck Mounted Attenuators (TMA's) as shown on the TCP's shall be used. Whether shown on the TCP's or added by the Department, TMA's shall be paid for under Item 6185, "Truck Mounted Attenuator" for the type of operation being performed.

Estimate & Quantity Sheet



DISTRICT Lufkin HIGHWAY US0059

COUNTY San Jacinto

		CONTROL SECTIO	N ЈОВ	6442-5	6-001		
		PROJECT ID		A0019	A00196546		
		cc	DUNTY	San Ja	cinto	TOTAL EST.	TOTAL FINAL
		HIG	USO	US0059		1110/12	
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	500-6033	MOBILIZATION (CALLOUT)	EA	5.000		5.000	
	752-6003	TREE TRIMMING / BRUSH REMOVAL	MI	5.000		5.000	
	752-6004	TREE TRIMMING / BRUSH REMOVAL(CHANNELS)	AC	5.000		5.000	
	752-6005	TREE REMOVAL (4" - 12" DIA)	EA	120.000		120.000	
	752-6006	TREE REMOVAL (12" - 18" DIA)	EA	600.000		600.000	
	752-6007	TREE REMOVAL (18" - 24" DIA)	EA	500.000		500.000	
	752-6008	TREE REMOVAL (24" - 30" DIA)	EA	300.000		300.000	
	752-6009	TREE REMOVAL (30" - 36" DIA)	EA	80.000		80.000	
	752-6010	TREE REMOVAL (36" - 42" DIA)	EA	5.000		5.000	
	752-6011	TREE REMOVAL (42" - 48" DIA)	EA	5.000		5.000	
	752-6012	TREE REMOVAL (48" - 60" DIA)	EA	5.000		5.000	
	752-6013	TREE REMOVAL (60" - 72" DIA)	EA	5.000		5.000	
	6185-6002	TMA (STATIONARY)	DAY	20.000		20.000	

CONTROLLING PROJECT ID 6442-56-001



Report Generated By: txdotconnect_internal_ext

Report Created On: Apr 10, 2023 9:13:51 AM

DISTRICT	COUNTY	CCSJ	SHEET
Lufkin	San Jacinto	6442-56-001	3

VARIOUS

5

5

120

ъĝ

DGN\QSUM.

\Desi

Ę

2 ŏ g

				SUMMARY	OF TREE	REMOVAL	ITEMS				
ITEM NO.	0752 6003	0752 6004	0752 6005	0752 6006	0752 6007	0752 6008	0752 6009	0752 6010	0752 6011	0752 6012	0752 6013
LOCATION	TREE TRIMMING/ BRUSH REMOVAL	TREE TRIMMING/ BRUSH REMOVAL (CHANNELS)	TREE REMOVAL (4"-12" DIA)	TREE REMOVAL (12"-18" DIA)	TREE REMOVAL (18"-24" DIA)	TREE REMOVAL (24"-30" DIA)	TREE REMOVAL (30"-36" DIA)	TREE REMOVAL (36"-42" DIA)	TREE REMOVAL (42"-48" DIA)	TREE REMOVAL (48"-60" DIA)	TREE REMOVAL (60"-72" DIA)
	MI	AC	EA	EA	EA	EA	EA	EA	EA	EA	EA

300

80

SUMMARY OF TRAFF	IC CONTROL ITEMS
ITEM NO.	6185 6002
LOCATION	TMA (STATIONARY)
	DAY
VARIOUS	20

500

* USE TMA WHEN REQUIRED TO DO SO

600

AS OUTLINED BY TCP STANDARDS.

QUANTITY SUMMARIES

2023

NOTE: ALL QUANTITIES ARE AN ESTIMATE AND SHALL BE VERIFIED IN THE FIELD PRIOR TO BEGINNING OF WORK. NO GUARANTEES ARE MADE AS TO THE AMOUNT OF WORK WHICH WILL BE PERFORMED AT EACH LOCATION.

5

5

5

5



ee Ľ 0 ċ 8 up 001 -95 s/6442 -s\FY23 CO CO Mainter Routine 4/11/2023 7:11:48 AM T:\LFKDOM\Maint Contracts\O_RMC of this stordard is governed by the "tease foilener in fronts letter. Af", how workny of any NDM fronts the suppose eventence to the answer to responsibility for the anoversion 2050 001 San dormtis free trimenta Rautis Removal NDEsignbub/RS (XRNAR) Abs. 21. dan -2550 001 San dormtis Free trimenta

DISCLAIMER: The use (kind is mode of this stone Plons(6442-

6:40:53 AM

DATE: 4/

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessory warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected or on ear the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.


COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES


- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEE	T 1	OF	12		
Texas Department	of Trai	nsp	ortation	1	Traffic Safety Division Standard
BARRICADE A GENER AND RE	201	N Ri	IOTES Ement		TION
BC	(1)) -	·21		
FILE: bc-21.dgn	DN: Tx	DOT	CK: TXDOT DW:	TxDC	OT CK: TXDOT
CTxDOT November 2002	CONT	SECT	JOB		HIGHWAY
4-03 7-13	6442	56	001	US	59, ETC.
9-07 8-14	DIST		COUNTY		SHEET NO.
5-10 5-21	LFK	S	AN JACINT	0	5









ANDA

All a s s et ind SCL

> AN 6:40:55

> 4/11/2023

DATE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- warranty of any r the conversion its use. ARDS/bc-21.dgn 1. The Engineer/Inspector shall approve all messages used on portable
 - changeable message signs (PCMS). Messages on PCMS should contain no more than 8 words (about four to 2. eight characters per word), not including simple words such as "TO," "FOR, " "AT, " etc.
 - 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., RE: the of this stordord is governed by the "Texas Engineering Practice Act", made by 1300 free ony burnoses entransever. This 2000 assumes and esponsibility stordord to other formats for for incorrect results are danges resulting XMSIT 6442-56-001 Son Jocinno free Trimming & Brush RemovalNesignNDGNSIT
 - "EXIT CLOSED." Do not use the term "RAMP." 5. Alwoys use the route or interstate designation (IH, US, SH, FM)
 - along with the number when referring to a roadway. When in use, the bottom of a stationary PCMS message panel should be 6. a minimum 7 feet above the roadway, where possible. 7. The message term "WEEKEND" should be used only if the work is to
 - start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work
 - is to begin on Friday evening and/or continue into Monday morning. 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
 - Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.

 - Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line. Do not use the word "Danger" in message.
 Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT"

 - on a PCMS. Drivers do not understand the message. 13. Do not display messages that scroll horizontally or vertically across
 - the face of the sign. 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PDMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
 - PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at hight and 800 feet in doylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 600 feet.
 - 16. Each line of text should be centered on the message board rather than left or right justified. 17. If disabled, the PCMS should default to an illegible display that will

 - not alarm motorists and will anly be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Nor thbound	(route) N
Construction	CONST AHD	Parkina	PKING
Ahead	LUNST AHD	Road	RD
CROSSING	XING	Right Lane	RTLN
Detour Route	DETOUR RTE	Saturday	SAT
Do Not	DONT	Service Road	SERV RD
East	E	Shoulder	SHLDR
Eastbound	(route) E	Slippery	SLIP
Emergency	EMER	South	S
Emergency Vehicle	EMER VEH	Southbound	(route) S
Entrance, Enter	ENT	Speed	SPD
Express Lane	EXP LN	Street	ST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Troffic	TRAF
Hazardous Driving		Trovelers	TRYLRS
Hozardous Material	HAZMAT	Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway		Vehicles (s)	VEH. VEHS
Hour (s)	HR, HRS	Warning	WARN
Information	INFO	Wednesday	WED
lt is	ITS	Weight Limit	WTLINIT
Junction	JCT	West	W
Left	LFT	Westbound	(route) W
Left Lane	LFT LN	Wet Pavement	WET PVMT
Lane Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL		
Maintenance	MAINT		

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 2: Possible Component Lists

Road/Lane/Ramp	o Closure List	Other Condition List			
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT		
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT		
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE		
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT		
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT		
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT		
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN		
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES		
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT *		
XXXXXXXX BLVD CLOSED	¥ LANES SHIFT in PI	hase 1 must be used with	n STAY IN LANE in Phose	e 2.	

Phase 1: Condition Lists

	/Effect on Trave _ist	Location List	Warning List
MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION
EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY
REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE
USE OTHER ROUTES	WATCH FOR WORKERS		
STAY IN LANE	×	¥ ¥ See	Application Gu

* * Advance Notice List TUE-FRI XX AM-X PM APR XX-ΧХ X PM-X AM BEGINS MONDAY BEGINS MAY XX MAY X-X XX PM -ΧΧ ΔΜ NEXT FRI-SUN XX AM то XX PM NEXT TUE AUG XX TONIGHT XX PM-

XX AM

tion Guidelines Note 6.

APPLICATION GUIDELINES


- 1. Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice
- Phase Lists". 4. A Location Phase is necessary only if a distance or location
- is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases,
- and should be understandable by themselves. 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
 Roadway designations IH, US, SH, FM and LP can be interchanged as
- oppropriate.
- BAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.

- Highway names and numbers replaced as appropriate.
 ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
 AT, BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a location phase is used.

	STreet	51	no more than one week prior to the work.		
	Sunday Telephone	SUN PHONE		SHEET 6 OF 12	
FOG AHD FRWY, FWY locked FWY BLKD	Temporary Thursday To Downtown Traffic	TEMP THURS TO DWNTN TRAF	PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4)	Texas Department of Transportation	Traffic Safety Division Standard
Driving HAZ DRIVING Moterial HAZMAT pancy HOV HWY	Travelers Tuesday Time Minutes Upper Level Vehicles (s)	TRAF TRVLRS TUES TIME MIN UPR LEVEL VEH, VEHS	PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.	BARRICADE AND CONSTR PORTABLE CHANGEA	
on INFO ITS	Warning Wednesday Weight Limit	WARN WED WT LIMIT	FULL MATRIX PCWS SIGNS	MESSAGE SIGN (PC	MS)
	West Westbound Wet Pavement Will Not	W (route) W WET PVMT WONT	 When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE WESSAGE SIGNS" above. When symbol signs, such as the "Flagger Symbol" (CMEO-1) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above. When symbol signs are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow. 	BC (6) - 21 rittle bc-21.dgn pm. TxD0T csr TxD0T [csr TxD0T] © TxD0T November 2002 conr scr T	HIGHWAY US 59, ETC. SHEET NO.
				100	



GENERAL NOTES

ŝ

ers

worrc †he †s us

ŠḉE

roctice Act". h responsibility t s resulting from

exas Engineering TxDOT assumes n results or dama

for for

is govern purpose mats or f

5 g g

of this standar s by TxDOT for a ndard to other f ?-56-001 San Jc

an sis

e tu

Å

20

÷

50

11/2023

4

Ë

- 1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only
- if personnel are present on the project at all times to maintain the cones in proper position and location. 3. For short term stationary work zones on freeways, drums are the preferred
- channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or
- single piece plastic drums as channelization devices or sign supports. 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in idth
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs. 10. Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- 1. The stripes used on drums shall be constructed of sheeting meeting the $\sim \circ \cdots \circ v^{po}$ used on u ums smail be constructed of sheeting meeting the color and retroreflectivity requirements of Deportmental Materials Specification DMS-8300, "Sign Face Materials," Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no detaminating, araking, or lass of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbaas separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches. 2. Bases with built-in ballast shall weigh between 40 lbs, and 50 lbs.
- Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck the sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list. 4. The ballast shall not be heavy objects, water, or any material that
- would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.


4" mox Each drum shall have 1 a minimum of 2 orange and 2 white stripes using Type A or Type B retroreflective 2" max sheeting with the top stripe being (typ.) orange. Toper to allow for stacking a See Ballast minimum of 5 drums Note 3

9/16" dia. (typ)

for mounting

worning Lights

signs and



DETECTABLE PEDESTRIAN BARRICADES

18" min

Handle -

Top should not

of water or

4" min

8" mox

(†yp)-


debris

Ē

12 22

allow collection

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BIS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures. 2. Where pedestrians with visual disabilities normally use the
- closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a type 3 Barricade.
 Detectable pedestrian barricades similar to the one pictured
- above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5. Worning lights shall not be attached to detectable pedestrian horricodes.
- Detectoble pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no 6. splinters, burrs, or sharp edges.





COUNTY

SAN JACINTO

I F K

9-07 5-21





WORK ZONE PAVEMENT MARKINGS

- GENERAL 1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- 2. Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (IMUICD).
- 3. Additional supplemental pavement marking details may be found in the plans or specifications.
- 4. Povement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- 5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ (STPM).
- 6. When standard payement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Povement Markings."

RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns on BC(12).
- 2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- 1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- 2. Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- 1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- 2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roodway geometrics.
- 4 Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic. 2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route. 3. Pavement markings shall be removed to the fullest extent possible. so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers". 4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677. 5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used. 6. Blast cleaning may be used but will not be required unless specifically shown in the plans. 7. Over-painting of the markings SHALL NOT BE permitted. 8. Removal of raised pavement markers shall be as directed by the 9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS, " unless otherwise stated in the plans. 10.Black-out marking tape may be used to cover conflicting existing

REMOVAL OF PAVEMENT MARKINGS

markings for periods less than two weeks when approved by the Engineer.



DMS-4200

DMS-430

DMS-6100

DMS-6130

DMS-8240

DMS-824

DMS-8242

Traffic Safety Division Standard

HICHWAY

SHEET NO

DIST

I F K

-02 7-13 I-02 8-14

COUNTY


SAN JACINTO


warranty of any the conversion its use. ARDSNbc-21. ron


N be


..£¥


esponsibili resulting




















DocuSign Envelope ID: F4EF8361-71BE-4D4D-A84F-83B21B53CAA1									
ŭ 1,	STORMWATER POLLUTION	PREVENTION-CLEAN WATE	R ACT SECTION 402	<u>п</u>	CULTURAL RESOURCES	v۲,	. HAZARDOUS MATERIALS OR CONTA	MINATION ISSUES	
ty of any priversion iree Removal EP	TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with 1 tem 506. List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities. 1. N/A Image: No Action Required Required Action				Refer to TxD0T Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately. No Action Required Required Action 1. Contractor to repair or replace in kind, at their own expense, any historic materials damaged (buildings, historical markers, etc.) in the course of executing the work. Contractor is responsible for locating replacementa source for historical materials damaged in the course of the work. TxD0T-Environmental Affairs Division is to be informed of proposed repoirs to facilitate consultation		hazardous materials by conducting sa making workers aware of potential ha provided with personal protective eq Obtain and keep on-site Material Saf	Act (the Act) for personnel who will be working with ofety meetings prior to beginning construction and zards in the workplace. Ensure that all workers are ulpment appropriate for any hazardous materials used. ety Data Sheets (MSDS) for all hazardous products	
No warrant y for the a							used on the project, which may include, but are not limited to the following or Paints, acids, solvents, asphalt products, chemical additives, fuels and concr compaunds or additives. Provide protected storage, off bare ground and covered products which may be hazardous. Maintain product labelling as required by the Maintain an adequate supply of on-site spill response materials, as indicated		
sibilit (\$4442_f	Action No.				with Texas Historical Commission prior to the execution of repairs. IV. VEGETATION RESOURCES		In the event of a spill, take actions to mitigate the spill as indicated in the M in accordance with safe work practices, and contact the District Spill Coordinate immediately. The Contractor shall be responsible for the proper containment and c		
stas Engineering Practio 14.001 assumes no reactio TBAUSNE REINORMES REA	1. The proposed work of this project is the removal and trimming of trees and brus at various roadways within the San Jacinto County Maintenance Section that are hazardous, dying, or protruding into State right-of-way. This activity maintains the original line and grade, hydraulic capacity, and original purpose of the site. The this project meets the definition of a routine maintenance activity as defined in TPDES General Permit No. TXRI50000 issued March 5, 2023 and TCEQ'S TPDES CGP does not apply.		Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, refore,164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for			of all product spills. Contact the Engineer if any of the following are detected: * Dead or distressed vegetation (not identified as normal) * Trash piles, drums, conister, barrels, etc. * Undesirable smells or odors * Evidence of leaching or seepage of substances Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)? ↓ Yes ∑ No			
19 19 19 19				1. FM 945		If "No", then no further action is required. If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection. Are the results of the asbestos inspection positive (is asbestos present)?			
11 11 11 11	ACT SECTIONS 401 AND 404			2. FM 1725 3. FM 2025 4. SH 150 5. FM 3081					
Prefort	USACE Permit required for water bodies, rivers, cree	filling, dredging, excavati ks, streams, wetlands or we			FM 2666 FM 2666		Yes No		
d is gov entropeder	be contractor must adhere to all of the terms and conditions associated with a a the following permit(s):		7. FM 2033 8. FM 3018 A. NO trees along these roadways are to be cut or otherwise damaged without			the notification, develop abatement/	ain a DSHS licensed asbestos consultant to assist with ement/mitigation procedures, and perform management notification form to DSHS must be postmarked at least build demolition		
andard For any Mer J66	No Permit Required				prior approval from US Forest Service (SHNF) and Area Engineer. B. Area Engineer shall notify US Forest Service (SHNF) prior to commencing work		If "No", then TxDOT is still required to notify DSHS 15 working days prior to any		
001 01 01 01	Image: State Stat		on the above roadways.		scheduled demolition. In either case, the Contractor is responsible for providing the date(s) for abatement				
e of th de by Tj 1700-0540				V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.		activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.			
A IMER is mus So 644	Other Nationwide Permit Required: NWP#			No Action Required X Required Action			ele hazardous materials or contamination discovered manination Issues Specific to this Project:		
0150, ד גיחם tracts\FY23 \$לו	Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS. 1. N/A The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts. Best Management Practices:			 In order to maintain compliance with Chapter 64 of the Texas Parks and Wildl Code and Migratory Bird Treaty Act (MBTA), construction activities that may aff nests (i.e. tree removal, tree limbing, bridge work) shall be conducted outside nesting season (Morch 15 to September 15). In the event birds or active nests (eggs and/or nestlings present) are encountered, contact the engineer prior to conducting work Red-cockaded Woodpeckers (federally endangered species) habitat is present adjacent to the ROW along the following roadways: On FM 945 from FS 274 to 4.1 miles North of FS 274 On FM 945 from FS 2756 to 0.55 miles South of FS 256 On FM 2025 from Lower Vann rd to 1.0 mile South of Lower Vann Rd M 2663 from FM 2025 to 1.2 miles East of FM 2025 On FM 2693 from 2.6 miles East of the Molker County line to 4.0 miles east of the Wolker County line 		ct Action No. of the 1. N/A			
Con						II. OTHER ENVIRONMENTAL ISSUES Additional Conditions for work withi (See Section V roadway and General N	rk within the Sam Houston National Forest.		
utine Maintena						Action No.	Required Action		
Ro									
RMC	Erosion	Sedimentation	Post-Construction TSS		Contact LFK District ENV if work is to occur on the above roadway limits. NO trees along these highways are to be cut or otherwise damaged				
5/0_F	Temporary Vegetation	Silt Fence	Vegetative Filter Strips		vithout prior approval from LFK District ENV.			Texas Department of Transportation	
200 T	Blankets/Matting	🗌 Rock Berm 🗍 Triangular Filter Dike	Retention/Irrigation Systems Extended Detention Basin						
8 A) ontr	Sodding	Sand Bag Berm	Constructed Wetlands					ENVIRONMENTAL PERMITS,	
+ C	Interceptor Swale	Straw Bale Dike	Wet Basin		LIST OF ABBREVIATIONS			ISSUES AND COMMITMENTS	
6:2 fain	Diversion Dike	Brush Berms	Erosion Control Compost	BMP: CGP:	Best Management Practice SPCC: Spill Preventian Control and Countermeasure Construction General Permit SWP3: Starm Water Pollution Preventian Plan			1330L3 AND COMMITMENTS	
W/W	Erosion Control Compost	Erosion Control Compost	Mulch Filter Berm and Socks	DSHS:	Texas Department of State Health Services PCN: Pre-Construction Notification			EPIC	
1202 14D0			Compost Filter Berm and Socks	MOA:	Federal Highway Administration PSL: Project Specific Location Wenarandum of Agreement TCEQ: Texas Commission on Environmental Quality				
5/15/	Compost Filter Berm and Sacks Compost Filter Berm and Sacks Vegetation Lined Ditches		MOU: MS4:	Memorandum of Understanding TPDES: Texas Pollutant Discharge Elimination System Municipal Separate Stormwater Sewer System TPND: Texas Parks and Wildlife Department			FILE: epic.dgn DN:TXDDT CK:RG DW:VP CK:AR (C)TXDDT: February 2015 CONT SECT JOB HIGHMAN		
		Stone Outlet Sediment Trops		MBTA: NOT:	Migratory Bird Treaty Act TxDOT: Texas Department of Transportation Notice of Termination T&E: Threatened and Endangered Species			12-12-2011 (DS) REVISIONS 6442 56 001 US 59, ETC.	
ATE:		Sediment Basins	Grassy Swales	NWP:	Nationwide Permit USACE: U.S. Army Corps of Engineers Notice of Intent USFWS: U.S. Fish and Wildlife Service			05-07-14 ADDED NOTE SECTION IV. 01-23-2015 SECTION I (CHANGED ITEM 1122 1 TEM HOSE ADDED GALES SAN JACTINTO 24	