

# STATE OF TEXAS

## DEPARTMENT OF TRANSPORTATION

### MAINTENANCE MATERIALS CONTRACT

PROJECT NO. MMC 6448-19-001  
 CSJ: 6448 - 19 - 001  
 HIGHWAY: SH0031  
 LIMITS OF WORK: NAVARRO COUNTY ROADWAY MATERIALS

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY  
 DESCRIPTION: FLEXIBLE BASE

RECOMMENDED FOR LETTING:	6/26/2023
	Date
DocuSigned by: <i>Juan A. Paredes, P.E.</i>	
<small>4A97FEA3D5654BC</small>	
AREA ENGINEER	

RECOMMENDED FOR LETTING:	6/26/2023
	Date
DocuSigned by: <i>David Morren, P.E.</i>	
<small>72256D0956094E4</small>	
MAINTENANCE ENGINEER	

RECOMMENDED FOR LETTING:	6/27/2023
	Date
DocuSigned by: <i>JEFFREY BUSH</i>	
<small>345B765EB03E406</small>	
DIRECTOR OF OPERATIONS	

#### INDEX OF SHEETS

- |       |                           |
|-------|---------------------------|
| 1     | TITLE SHEET               |
| 2     | ESTIMATE & QUANTITY SHEET |
| 3A-3C | GENERAL NOTES             |

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

<b>© 2023</b>	<b>Texas Department of Transportation</b>		
<small>FED.RD. DIV. NO.</small>	<small>PROJECT NO.</small>	<small>SHEET NO.</small>	
6	MMC 6448-19-001	1	
<small>STATE</small>	<small>DISTRICT</small>	<small>COUNTY</small>	
TEXAS	DALLAS	NAVARRO	
<small>CONTROL</small>	<small>SECTION</small>	<small>JOB</small>	<small>HWY NO.</small>
6448	19	001	SH0031
<small>FILENAME</small>			<small>DATE</small>
MMC 6448-19-001			6/7/2023



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6448-19-001

DISTRICT Dallas  
HIGHWAY SH0031

COUNTY Navarro

CONTROL SECTION JOB		6448-19-001		TOTAL EST.	TOTAL FINAL
PROJECT ID	A00200303	Navarro			
COUNTY	Navarro	SH0031			
HIGHWAY	SH0031	EST.	FINAL		
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	8007-6035	FL BS (SITE DEL)(TY D GR 4)(SITE 5)	TON	4,200.000	4,200.000
	8007-6036	FL BS (SITE DEL)(TY D GR 4)(SITE 6)	TON	1,500.000	1,500.000



Report Generated By: txdotconnect\_internal\_ext

Report Created On: Jun 9, 2023 1:54:32 PM

DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Navarro	6448-19-001	2

**Project Number:** MMC 6448-19-001

**Control:** 644819001

**County:** Navarro County

**Highway:** SH0031

**GENERAL NOTES:**

**General:**

The purpose of this contract is to supply “Flexible Base”, materials only, at the following locations:

Site 5	100 SW CR 1000 Corsicana, Texas 75110
Site 6	1000 FT East of 3100 SH31 Corsicana, Texas 75109

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through:

Joseph Lanoue, Maintenance Section Supervisor  
100 SW CR 1000  
Corsicana, Texas 75110  
903-874-5361

Bids will be received at 4777 E. Hwy 80, Mesquite, Texas 75150-6643

Contractor questions on this project are to be addressed to the following individuals:

Juan A Paredes, P.E., Area Engineer [Juan.Paredes@txdot.gov](mailto:Juan.Paredes@txdot.gov)  
Joseph Lanoue, Section Supervisor [Joseph.Lanoue@txdot.gov](mailto:Joseph.Lanoue@txdot.gov)

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

**Project Number:** MMC 6448-19-001

**Control:** 644819001

**County:** Navarro County

**Highway:** SH0031

**Section 10.2 - Instructions to Bidders:**

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

**Section 10.4 – Scope of Work:**

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended once not to exceed 730 calendar days for the entire contract term if mutually agreed.

**Section 10.8 - Prosecution and Progress:**

There are 365 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Types of accepted haul vehicles include 6 – yard, 12 -yard and 25- yard end dumps.

Each work order will specify a delivery site or pick up by the bid item in the contract and quantity to be supplied. The minimum amount of material to be ordered on an individual work order for Flex Base is 100 Tons. There are 7 working days allowed to complete each work order.

**Item 500 – Mobilization:**

Mobilization does not apply to this Maintenance Materials Contract.

**Project Number:** MMC 6448-19-001

**Control:** 644819001

**County:** Navarro County

**Highway:** SH0031

**Item 8007 – Flexible Base (Materials Only):**

Grading Requirements

Tests to be in accordance with TXDOT Standard Test Methods

Soil Constants

Item Desc.	Linear Shrinkage	LL	Wet Ball	WBMV (incr. passing #40 sieve)
Item 247 FlexBase	6.0 max.	40 max.	40 max.	20% max.

PERCENT RETAINED ON SIEVE:

1-3/4"	7/8"	3/8"	No. 4	No. 40
0	10-35	30-50	45-65	70-85

Flexible Base will not contain more than 1% by weight of clay balls.