

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.
6	BR 2020(924)	1
STATE	STATE DIST.	COUNTY
TEXAS	23	BROWN
CONT. SECT.	JOB	HIGHWAY NO.
0923 06	083	CR 267

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS

STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO. BR 2020(924)

CR 267 (Elkins Road)  
Brown County

FOR THE CONSTRUCTION OF BRIDGE REPLACEMENT  
CONSISTING OF REPLACING BRIDGE AND APPROACHES

LIMITS: ON CR 267 at Lewis Creek

DESIGN SPEED = 40 MPH  
ADT (2017) = 231  
ADT (2033) = 300  
RURAL MINOR COLLECTOR

LENGTH OF PROJECT



ROADWAY	=	261.50 FT	=	0.050 MI
BRIDGE	=	43.50 FT	=	0.008 MI
TOTAL	=	305.00 FT	=	0.058 MI

FINAL PLANS  
PROJECT LETTING DATE:  
CONTRACTOR:  
DATE CONTRACTOR BEGAN WORK:  
DATE WORK WAS COMPLETED AND ACCEPTED:  
FINAL CONTRACT COST:



*George E. Tillett*  
4/17/2021

BEG PROJECT  
STA 11+05.00  
0923-06-083  
END PROJECT  
STA 14+10.00  
0923-06-083



THE CONSTRUCTION WORK WAS PERFORMED IN  
ACCORDANCE WITH THE PLANS AND CONTRACT.

AREA ENGINEER, P.E.

DATE

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF  
TRANSPORTATION, NOVEMBER 2014 AND SPECIFICATION ITEMS  
LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS  
PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID  
CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY, 2012).

EQUATIONS: NONE  
EXCEPTIONS: NONE  
NO RAILROAD CROSSINGS - NONE ELIMINATED

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH  
BC (1) - 14 THRU BC (12) - 14 AND THE "TEXAS  
MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

CONFORMANCE:  
*Paul D. Willy*  
COUNTY JUDGE



4/28/2021

SUBMITTED FOR LETTING:

DocuSigned by:

*Dan A. Hoffmann, P.E.*

2E74E333C7B14AA  
DISTRICT DESIGN ENGINEER

4/28/2021

RECOMMENDED FOR LETTING:

DocuSigned by:

*PH Stitt, P.E.*

77D14777834646F  
DISTRICT DIRECTOR OF TRANSPORTATION  
PLANNING AND DEVELOPMENT

4/28/2021


RECOMMENDED FOR LETTING:

DocuSigned by:


*Elias Rmeili, P.E.*

BB9FD402431A4A3  
DISTRICT ENGINEER





EXISTING CR 267 APPROACH ROADWAY



PROPOSED CR 267 APPROACH ROADWAY

FROM STA 11+55.00 TO STA 12+35.00  
 FROM STA 12+78.50 TO STA 13+60.00

PROPOSED BRIDGE CLASS CULVERT STA 12+35.00 TO STA 12+78.50


TRANSITION FROM EXISTING WIDTH TO PROPOSED WIDTH  
 STA 11+05.00 TO 11+55.00  
 STA 13+60.00 TO 14+10.00

TRANSITION FROM EXISTING CROSS SLOPE AT STA 11+05.00 TO 2% CROSS SLOPE AT STA 12+15.00  
 TRANSITION FROM 2% CROSS SLOPE AT STA 13+00.00 TO EXISTING CROSS SLOPE AT STA 14+10.00

ITEM	CODE	DESCRIPTION	UNIT	QUANTITY
247	6055	FL BS (CMP IN PLC) (TYD) (GR-3) (FINAL POS)	CY	136

FL BS (CMP IN PLC) (TYD) (GR-3) (FINAL POS) EST. @ 54.5 CY/STA (TOTAL 88 CY)  
 ADDITIONAL FLEX BASE EST. @ 48 CY TOTAL FOR TRANS

NO.	REVISION	BY	DATE



TYPICAL SECTIONS  
 CR 267 AT LEWIS CREEK

SHEET 1 OF 1

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET NO.	
TEXAS	BWD	BROWN	3	

p:\tts-pw-bentley.com\tts-pw-01\Documents\0223-002\Cadd\Plan Sheets\Roadway\CR267\_RDW\_TYP\_01.dgn  
 7/24/2020 2:46  
 SCRIPT: CR267\_Index.pen  
 JoeLimmerman

**GENERAL NOTES**

TEST TO BE IN ACCORDANCE WITH  
TEXAS DEPARTMENT OF TRANSPORTATION  
STANDARD TEST METHODS.

Item	Description	Soil Constants		
		Max LL.	Max. PI	Min. PI
132	Embankment (Final)(Ord Cont)(Ty C)	40	30	3
247	FI Bs (Cmp In Plc) (Ty D Gr 3)(Fnal Pos)			3

Job control samples for gradation and P.I. testing will be taken from the windrow after blade mixing.

Asphalt Surface Areas-SY

Item	Description	Course	Roadway
310	Asph (RC-250)	Prime	815
316	Aggr (TY-B GR-5)	Prime	815
316	Asph (AC-20-5TR)	1 <sup>st</sup>	815
316	Aggr (TY-PB GR-3)(SAC-B)	1 <sup>st</sup>	815

Basis of Estimate

Item	Description	Course	Rate	SY	Quantity
310	Asph (RC-250)	Prime	0.25 Gal/SY	815	204 Gal
316	Aggr (TY-B GR-5)(SAC-B)	Prime	130 SY/CY	815	7 CY
316	Asph (AC-20-5TR)	1 <sup>st</sup>	0.42 Gal/SY	815	343 Gal
316	Aggr (TY-PB GR-3)(SAC-B)	1 <sup>st</sup>	90 SY/CY	815	9 CY

Trees that are to be trimmed and brush that is to be trimmed or removed that are not over the roadway or bridge(s), will be trimmed or removed in accordance with the Roadside Vegetation Management Manual to a height of fourteen feet. Remove limbs at the trunk with less than twenty-one feet of clearance above the pavement or bridge(s).

See the "Environmental" section of the plans for additional information.

**TEXAS ONE CALL**

Fiber optic cable systems, gas lines, underground power lines, water lines, sewer lines, and other various utilities may be buried within the project limits. Protection of these utility systems is of extreme importance since any break could disrupt service to users resulting in business interruption and loss of revenue and profits. The Contractor shall telephone Texas One Call at 1-800-344-8377 (a 24-hour number), to determine if utilities are buried anywhere on the project in accordance with all UNDERGROUND FACILITY

DAMAGE PREVENTION AND SAFETY laws. This action, however, will in no way be interpreted as relief of responsibilities under the terms of the Contract as set out in the plans and specifications. Coordinate the repair of all damages caused by daily operations and have facilities restored to service in a timely manner as directed at no additional cost to TxDOT.

**GENERAL**

Contractor questions on this project are to be addressed to the following individual(s):

<u>Name</u>	<u>Email Address</u>
Bart Fris P.E.	<a href="mailto:bart.fris@txdot.gov">bart.fris@txdot.gov</a>
Canaan Cavitt, P.E.	<a href="mailto:Canaan.Cavitt@txdot.gov">Canaan.Cavitt@txdot.gov</a>

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

The term "Article" or "Section" referred to hereon is defined in the forward of the Standard Specifications for Construction and Maintenance of Highways, Streets, And Bridges adopted by the Texas Department of Transportation November 2014.

The total disturbed area is shown on the SW3P sheet(s).

The Contractor will establish drainage in ditches before seeding or as directed by the Engineer.

Watering for dust control will be required as Directed by the Engineer and will be considered subsidiary to the various bid items.

**ITEM 5 CONTROL OF WORK**

The responsibility for the construction surveying on this contract will be in accordance with Section 5.9.1. "Method A".

The contractor will be required to place and maintain Blue Tops with wooden hubs for new flexible base.



Prior to contract letting, bidders may obtain a free computer diskette or a computerized transfer of files (from the Engineer's office) that contains the earthwork information. If copies of the actual cross-sections in addition to, or instead of, the diskette are requested, they will be available at the Engineers office for borrowing by copying companies for the purpose of making copies for the bidder at the bidder's expense.

#### ITEM 6 CONTROL OF MATERIALS

In accordance with **Section 6.10.2**, the Contractor will dispose of all painted steel at a steel recycling or smelting facility and a receipt will be required. In lieu of this, the Contractor has the option to either show proof that the paint is lead free or show proof that the lead paint has been abated by an abatement certified company. The Department will not be obligated for the cost of paint testing and/or abatement materials, processes, personnel, incidentals, etc.

#### ACM Removal:

No asbestos have been found in tested materials. If suspect materials are encountered during bridge removal, contact Andrew Chisholm (325-643-0442) with the Department of Transportation for report and additional details

#### ITEM 7 LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

#### ITEM 8 PROSECUTION AND PROGRESS

Working days will be computed and charged in accordance with Section 8.3.1.4. "Standard Workweek".

Work will not be performed without time being charged unless otherwise exempted by the Section as defined above.

Work on Sunday(s) will not be allowed.

#### PROJECT SCHEDULES

Critical Path Method (CPM) scheduling will be required to be submitted and maintained monthly by the Contractor unless otherwise directed by the Engineer. (8.5.2.)

For monthly submittals, the Contractor will provide the schedule in an Adobe Acrobat compatible format (PDF file). If the Engineer requests the schedule in an electronic format, the Contractor will submit a schedule that is fully compatible with Primavera P6 Professional Release 15.

#### ITEM 100 PREPARING RIGHT OF WAY

Perform "Preparing Right of Way" operations in the usual manner within the limits of the excavation and fill areas. Remove only such trees and brush as designated by the Engineer. Exercise care to avoid

disturbing the native grasses unnecessarily during construction, removal of the existing bridge, and during the installation of the temporary fence.

Within the construction limits, blade and windrow the top 8 inches of vegetative material to just outside the construction limits. Once ditch slopes and drainage have been established and approved, blade the windrow evenly over the disturbed area within the construction limits. This work is to be done as the job progresses and in conjunction with seeding. Work on the project may be suspended, if in the opinion of the Engineer, the Contractor does not make a good faith effort to stabilize loose material as the project progresses. Time will not be suspended. This work is subsidiary to Item 100.

The removal of existing and temporary fence will not be paid for directly but will be considered subsidiary to Item 100 "Preparing Right Of Way".

#### ITEM 164 SEEDING FOR EROSION CONTROL

The Contractor should anticipate two (2) separate mobilizations for seeding at each project location. Blade and windrow outside construction limits, grass, weeds, and topsoil to grass roots depth.

#### ITEM 166 FERTILIZER

Fertilize all areas of project to be seeded.  
Furnish and apply fertilizer with analysis of 20-10-10 at a rate of 300 bulk pounds per acre.

#### ITEM 168 VEGETATIVE WATERING

Water all areas of project to be seeded.

Vegetative watering is estimated at 1 inch per week for 4 weeks.

Vegetative watering may be adjusted as directed by the Engineer to ensure saturation for vegetative establishment.

#### ITEM 169 SOIL RETENTION BLANKETS

An approved Bonded Fiber Matrix Soil Retention Blanket will be used at the TTI tested rate shown below:

Cocoflex ET-FGM	3500 lbs/acre
Earthguard Fiber Matrix	3000 lbs/acre
EcoFlex HP	3500 lbs/acre
Flexterra HP-FGM	3500 lbs/acre
Flexterra FGM	3500lbs/acre
Fleterra ultra	3500 lbs/acre
Hy-C3	3500 lbs/acre
HY-C4	4000 lbs/acre
Hyrda-CX2	4000 lbs/acre

Hydra CM	3500 lbs/acre
Hydroblanket BFM	3500 lbs/acre
Hydrostraw BFM	3500 lbs/acre
ProMatrix EFM	3500 lbs/acre
Soil Guard	3700 lbs/acre sand, 3500 lbs/acre clay
Terra Matrix	3000 Lbs/acre
SprayMatrix FRM	3500 lbs/acre
Wood-Lok HPM	3500 lbs/acre
Proganics Dual	5500 lbs/acre
ProGuard	3000 lbs/acre
Conwed Fiber 2000	2500 lbs/acre

**ITEM 247 FLEXIBLE BASE**

A grader (a road grader, a blade, a maintainer, or a motor grader) will be used to process base unless otherwise approved by the Engineer.

Do not add field sand to modify the finish material to meet requirements.

Place new flexible base in lifts of approximately equal depth not to exceed 6 inches unless otherwise directed.

**ITEM 316 SURFACE TREATMENTS**

All precoated aggregate will use PG 64-22 asphalt.

Furnish aggregate with a minimum B surface aggregate classification.

The asphalt rates shown hereon are for average conditions. The rate may be varied as determined by the Engineer to obtain proper embedment of aggregate.

Warm season asphalts are not to be placed between September 1<sup>st</sup> and April 30<sup>th</sup> unless otherwise directed/approved.

Protect all existing bridges, and other exposed concrete surfaces within the limits of this project(s), as much as practicable, from asphalt materials by any means approved by the Engineer at the contractor's expense.

Use a medium pneumatic roller meeting the requirements of Item 210 as directed by the Engineer. This work will be subsidiary to the various bid items.

**ITEM 420 CONCRETE SUBSTRUCTURES**

All Class C Concrete has been measured for plan quantity payment.

**ITEM 421 HYDRAULIC CEMENT CONCRETE**

Furnish dome lids with 4" x 8" cylinder test molds.

Strength testing equipment is not required for Contract controlling test.

**ITEM 427 SURFACE FINISHES FOR CONCRETE**

Surface Area II will receive a rub finish.

**ITEM 432 RIPRAP**

Locations and quantities may be varied as directed by the Engineer to accommodate field conditions.

Limit excavation to within 1' of riprap. If excavation exceeds these limits without the Engineer's approval, riprap will be extended to the limits of the disturbance. No additional compensation will be allowed for this work.

**ITEM 496 REMOVING STRUCTURES**

Handle materials when removing structures in accordance with Item 6.

Exercise care to avoid disturbing the native grasses unnecessarily during removal of the existing bridge.

Notify TxDOT at least 60 days prior to any bridge removal. The Texas Department of State Health Services (DSHS) requires TxDOT to notify the DSHS of the bridge removal even if no asbestos is present. The notification form to retain/notify the DSHS licensed asbestos consultant must be postmarked at least 10 working days prior to the scheduled abatement and/or demolition. If the work does not happen on the notified date, then another 10 Working-Day, Prior-To-Work Notification will be required.

Provide a detailed plan for the removal of the existing structure to include the schedule of removal and list of all equipment to be used.

The structure or structures to be removed may have surface coatings, which may contain hazardous materials. Provide for the safety and health of employees and abide by all OSHA Standards and Regulations as well as those set by Texas Department of State Health Services (DSHS).

**ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING**

The Contractor will be required to keep all TCP devices clean. If notified by the Engineer to clean the TCP devices, the Contractor will have until the end of that daylight period to comply. Failure to comply will result in a suspension of all work until the TCP devices are clean. Time will not be suspended.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed

---

upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

All equipment operated by the Contractor on or within thirty feet (30') of the roadway will have a functioning flashing beacon mounted on it. Motor graders will have two standard orange warning flags mounted on them in addition to the flashing beacon.

The Contractor will be responsible for maintaining the edge of the roadway throughout the project in a traversable condition and/or as directed by the Engineer. Salvaged milling may be used as directed by the Engineer. This work will not be paid for directly and will be considered subsidiary to Item 502 "Barricades, Signs, and Traffic Handling".

All devices shown on the TCP Standards are required and considered subsidiary to Item 502 unless specifically outlined elsewhere in the plans.

All signs will be constructed in accordance with the details shown in the current Standard Highway Sign Designs for Texas manual.

#### **ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS**

BMP's will not be installed until authorized by the Engineer.  
The Engineer will determine actual time and placement locations of BMP's and temporary measures once construction has begun.

Stockpile sites may be cleared of cover vegetation, but the vegetation root system will not be destroyed.

#### **ITEM 552 WIRE FENCE**

Wire fence quantities shown on the plans are approximate and may be adjusted in the field as approved by the Engineer.

Notify the Engineer three weeks prior to beginning any fence work.



CONTROLLING PROJECT ID 0923-06-083

DISTRICT Brownwood  
HIGHWAY CR 267

COUNTY Brown

# QUANTITY SHEET

CONTROL SECTION JOB				0923-06-083		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00064129			
COUNTY				Brown			
HIGHWAY				CR 267			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6002	PREPARING ROW	STA	3.100		3.100	
	100-6017	PREP ROW (TREE)(GREATER THAN 8 IN DIA)	EA	9.000		9.000	
	110-6001	EXCAVATION (ROADWAY)	CY	91.000		91.000	
	132-6005	EMBANKMENT (FINAL)(ORD COMP)(TY C)	CY	67.000		67.000	
	164-6001	BROADCAST SEED (PERM) (RURAL) (SANDY)	SY	1,805.000		1,805.000	
	164-6009	BROADCAST SEED (TEMP) (WARM)	SY	903.000		903.000	
	164-6011	BROADCAST SEED (TEMP) (COOL)	SY	903.000		903.000	
	168-6001	VEGETATIVE WATERING	MG	42.000		42.000	
	169-6007	SOIL RETENTION BLANKETS (CL 2) (TY G)	SY	1,000.000		1,000.000	
	247-6055	FL BS (CMP IN PLC)(TY D GR 3)(FNAL POS)	CY	136.000		136.000	
	310-6012	PRIME COAT (RC-250)	GAL	204.000		204.000	
	316-6017	ASPH (AC-20-5TR)	GAL	343.000		343.000	
	316-6177	AGGR(TY-B GR-5 SAC-B)	CY	7.000		7.000	
	316-6222	AGGR(TY-PB GR-3 SAC-B)	CY	9.000		9.000	
	400-6005	CEM STABIL BKFL	CY	171.000		171.000	
	402-6001	TRENCH EXCAVATION PROTECTION	LF	52.000		52.000	
	420-6051	CL C CONC (CULV)	CY	56.000		56.000	
	422-6001	REINF CONC SLAB	SF	1,131.000		1,131.000	
	432-6031	RIPRAP (STONE PROTECTION)(12 IN)	CY	87.000		87.000	
	450-6019	RAIL (TY T631LS)	LF	157.000		157.000	
	466-6184	WINGWALL (PW - 1) (HW=9 FT)	EA	2.000		2.000	
	496-6009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000		1.000	
	496-6043	REMOV STR (SMALL FENCE)	LF	345.000		345.000	
	500-6001	MOBILIZATION	LS	100.00%		100.00%	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	6.000		6.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	80.000		80.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	80.000		80.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	1,060.000		1,060.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	1,060.000		1,060.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	110.000		110.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	110.000		110.000	
	508-6001	CONSTRUCTING DETOURS	SY	485.000		485.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	50.000		50.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000	
	552-6003	WIRE FENCE (TY C)	LF	640.000		640.000	
	552-6008	WIRE FENCE (WATER GAP)	LF	45.000		45.000	
	658-6060	REMOVE DELIN & OBJECT MARKER ASSMS	EA	4.000		4.000	



DISTRICT	COUNTY	CCSJ	SHEET
Brownwood	Brown	0923-06-083	5



CONTROLLING PROJECT ID 0923-06-083

DISTRICT Brownwood  
HIGHWAY CR 267

COUNTY Brown

# QUANTITY SHEET

CONTROL SECTION JOB				0923-06-083		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00064129			
COUNTY				Brown			
HIGHWAY				CR 267			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	6.000		6.000	
	662-6050	WK ZN PAV MRK REMOV (REFL) TY II-A-A	EA	164.000		164.000	
	662-6063	WK ZN PAV MRK REMOV (W)4"(SLD)	LF	485.000		485.000	
	662-6075	WK ZN PAV MRK REMOV (W)24"(SLD)	LF	22.000		22.000	
	662-6095	WK ZN PAV MRK REMOV (Y)4"(SLD)	LF	6,000.000		6,000.000	
	681-6001	TEMP TRAF SIGNALS	EA	2.000		2.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	



ROADWAY SUMMARY

110-6001	132-6005	164-6001	164-6009	164-6011	168-6001	SUBSIDIARY	169-6003	247-6055	502-6001	506-6002	506-6011	506-6038	506-6039
EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY C)	BROADCAST SEED (PERM) (RURAL) (SANDY)	BROADCAST SEED (TEMP) (WARM)	BROADCAST SEED (TEMP) (COOL)	VEGETATIVE WATERING	FERTILIZER	SOIL RETENTION BLANKETS (CL 1) (TY C)	FL BS (CMP IN PLC) (TY D GR 3) (FNAL POS)	BARRICADES, SIGNS AND TRAFFIC HANDLING	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
CY	CY	SY	SY	SY	MG	TON	SY	CY	MO	LF	LF	LF	LF
91	67	1805	903	903	42	0.07	1000	136	6	80	80	1060	1060

ROADWAY SUMMARY

506-6041	506-6043	508-6001	662-6050	662-6063	662-6075	662-6095	681-6001
BIODEG EROSN CONT LOGS (INSTL) (12")	BIODEG EROSN CONT LOGS (REMOVE)	CONSTRUCTING DETOURS	WK ZN PAV MRK REMOV (REFL) TY II-A-A	WK ZN PAV MRK REMOV (W) 4" (SLD)	WK ZN PAV MRK REMOV (W) 24" (SLD)	WK ZN PAV MRK REMOV (Y) 4" (SLD)	TEMP TRAF SIGNALS
LF	LF	SY	EA	LF	LF	LF	EA
110	110	485	164	485	22	6000	2

FENCE SUMMARY

LOCATION STA. - STA.	496-6043	552-6003	552-6008
	REMOV STR (SMALL FENCE)	WIRE FENCE (TY C)	WIRE FENCE (WATER GAP)
10+75.00 - 13+80.00	LF 345	LF 640	LF 45
TOTAL	345	640	45

ITEM 552-6003 WILL BE USED FOR PERMANENT & TEMP FENCING: BRACES ESTIMATED @ 16 EA. THE FENCE LOCATION MUST BE APPROVED BY THE ENGINEER BEFORE BUILDING PERMANENT FENCING TO BE LOCATED AS CLOSE TO EXISTING FENCE AS POSSIBLE UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

DELINEATOR & OBJECT MARKERS SUMMARY

658-6062
INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)
EA
6

REMOVAL SUMMARY

LOCATION STA. - STA.	496-6009	658-6060
	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	REMOVE DELIN & OBJECT MARKER ASSMS
10+75.00 - 13+80.00	EA 1	EA 4
TOTAL	1	4

MBGF & RAIL SUMMARY

LOCATION STA. - STA.	540-6002	544-6001
	MTL W-BEAM GD FEN (STEEL POST)	GUARDRAIL END TREATMENT (INSTALL)
10+75.00 - 13+80.00	LF 50	EA 4
TOTAL	50	4

SEE STRUCTURE SUMMARY FOR BRIDGE RAIL PAYMENT

PREPARING ROW SUMMARY

LOCATION STA. - STA.	100-6002	100-6017
	PREPARING ROW	PREP ROW (TREE) (GREATER THAN 8 IN DIA)
10+75.00 - 13+80.00	STA 3.1	EA 9
TOTAL	3.1	9

TREES UNDER 8" DIAMETER WILL BE PAID UNDER PREPARING ROW BY STATION

NO.	REVISION	BY	DATE
-----	----------	----	------





QUANTITY SUMMARIES  
CR 267 AT LEWIS CREEK

SHEET 1 OF 1

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET NO.	
TEXAS	BWD	BROWN	6	

pm:/tts-pw-bentley.com:tts-pw-01/Documents/0223-002 WA 3 - CR Brown Comanche Co/Cadd/Plan Sheets/General/CR267\_Summaries-01.dgn  
 JamesBrooks  
 SCRIPT: CR267\_Index.pen  
 2/25/2021 12:31

CONTROL POINTS (SURFACE COORDINATES)							
POINT	NORTH	EAST	ELEVATION	STATION	OFFSET	LT/RT	DESCRIPTION
CP7	10,571,358.853	2,734,708.632	1,359.34'	N/A	N/A	N/A	3 1/2" ALUMINUM DISK SET IN CONCRETE
CP8	10,571,717.466	2,734,316.726	1,354.44'	13+20.08	24.87'	LT	3 1/2" ALUMINUM DISK SET IN CONCRETE
CP9	10,572,171.001	2,733,750.639	1,356.63'	N/A	N/A	N/A	3 1/2" ALUMINUM DISK SET IN CONCRETE



I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON FEBRUARY 08, 2020 UTILIZING THE TxDOT VIRTUAL REFERENCE SYSTEM RTK NETWORK AND IS CORRECTLY SHOWN HEREON.



*Eric A. Kreiner*  
Eric A. Kreiner  
RPLS No. 5320  
Date 07/08/20

- NOTES:
1. THE SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E WHICH IS SIGNED, SEALED AND DATED BY A TEXAS PROFESSIONAL ENGINEER.
  2. ALL COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (2011 ADJ: EPOCH 2010.00)
  3. THE VERTICAL DATUM FOR THIS PROJECT IS THE NAVD 1988 (CORS 2011), U.S. SURVEY FEET.
  4. ALL COORDINATE VALUES ARE BASED UPON AN AVERAGE OF FOUR 180 EPOCH OBSERVATIONS UTILIZING THE TxDOT VRS NETWORK.
  5. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET. DISPLAYED IN SURFACE VALUES USING THE SURFACE ADJUSTMENT FACTOR 1.0001 (0.9999000099)

NO.	REVISION	BY	DATE

**SAM** Surveying and Mapping, LLC. (SAM)  
1341 W. Mockingbird Lane, Suite 400W  
Dallas, TX 75247 - (214) 631-7888  
FIRM REGISTRATION NO. F-1937  
TBPLS REGISTRATION NO. 10064301



**Texas Transportation Solutions, Inc.**  
Since 1988

©2020 **Texas Department of Transportation**

SURVEY CONTROL  
INDEX SHEET  
CR 267 @ LEWIS CREEK

1 OF 1

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	7	



I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON FEBRUARY 8, 2020 UTILIZING THE TXDOT VIRTUAL REFERENCE SYSTEM RTK NETWORK AND IS CORRECTLY SHOWN HEREON.



*Eric A. Kreiner* 07/08/20  
Eric A. Kreiner Date  
RPLS No. 5320

NO.	REVISION	BY	DATE

CONTROL POINT NO. 7:  
APPROXIMATE LOCATION:

3 1/2" ALUMINUM DISK SET IN CONCRETE STAMPED "CP7", +/-1.3 MILE SOUTHEAST OF THE INTERSECTION OF COUNTY ROAD 267 AND FARM TO MARKET ROAD 2126, 83' NORTH OF A TELEPHONE PEDESTAL, 7' SOUTHWEST OF A BARBED WIRE FENCE AND 17' NORTHEAST OF THE NORTH EDGE OF PAVEMENT OF COUNTY ROAD 267.

US SURVEY FEET  
NAVD 88 ELEVATION= 1,359.34'  
DATE SET: FEBRUARY 8, 2020  
MONUMENT: 3 1/2" ALUMINUM DISK SET IN CONCRETE STAMPED "CP7"  
COMANCHE COUNTY SCALE FACTOR: 1.0001  
SURFACE ENGLISH CO-ORDS  
NORTHING: 10,571,358.853  
EASTING: 2,734,708.632  
STATE PLANE ENGLISH CO-ORDS  
NORTHING: 10,570,301.823  
EASTING: 2,734,435.188  
ELEVATIONS ARE NAVD 88 BASED UPON TXDOT VRS RTK NETWORK

CONTROL POINT NO. 8:  
APPROXIMATE LOCATION:

3 1/2" ALUMINUM DISK SET IN CONCRETE STAMPED "CP8", +/- 1.2 MILE SOUTHEAST OF THE INTERSECTION OF COUNTY ROAD 267 AND FARM TO MARKET ROAD 2126, 347' NORTHWEST OF A "CAUTION BURIED HIGH PRESSURE GAS LINE" SIGN, 3' NORTHEAST OF A BARBED WIRE FENCE, AND 24' SOUTHWEST OF THE SOUTH EDGE OF PAVEMENT OF COUNTY ROAD 267.

US SURVEY FEET  
NAVD 88 ELEVATION= 1,354.44'  
DATE SET: FEBRUARY 8, 2020  
MONUMENT: 3 1/2" ALUMINUM DISK SET IN CONCRETE STAMPED "CP8"  
COMANCHE COUNTY SCALE FACTOR: 1.0001  
SURFACE ENGLISH CO-ORDS  
NORTHING: 10,571,717.466  
EASTING: 2,734,316.726  
STATE PLANE ENGLISH CO-ORDS  
NORTHING: 10,570,660.400  
EASTING: 2,734,043.321  
ELEVATIONS ARE NAVD 88 BASED UPON TXDOT VRS RTK NETWORK

**SAM** Surveying and Mapping, LLC (SAM)  
1341 W. Mockingbird Lane, Suite 400W  
Dallas, Tx 75247 - (214) 631-7888  
FIRM REGISTRATION NO. F-1937  
TBPLS REGISTRATION NO. 10064301




PRIMARY HORIZONTAL AND VERTICAL CONTROL  
CR 267 @ LEWIS CREEK

1 OF 2

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	8	

CR267 @ Lewis Creek\_HAV.dgn \$USERS\$ \$TIMES\$ \$SCRIPTS\$ \$SCRIPTS\$ 2020-07-08



I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON FEBRUARY 8, 2020 UTILIZING THE TxDOT VIRTUAL REFERENCE SYSTEM RTK NETWORK AND IS CORRECTLY SHOWN HEREON.



*E.A. Kreiner* 07/08/20  
Eric A. Kreiner Date  
RPLS No. 5320

NO.	REVISION	BY	DATE

CONTROL POINT NO. 9:  
APPROXIMATE LOCATION:

3 1/2" ALUMINUM DISK SET IN CONCRETE STAMPED "CP9", +/- 1.0 MILE SOUTHEAST OF THE INTERSECTION OF COUNTY ROAD 267 AND FARM TO MARKET ROAD 2126, 206' SOUTHEAST OF A POWER POLE, 6' SOUTHWEST OF A BARBED WIRE FENCE AND 21' NORTHEAST OF THE NORTH EDGE OF PAVEMENT OF COUNTY ROAD 267.



US SURVEY FEET  
NAVD 88 ELEVATION= 1,356.63'  
DATE SET: FEBRUARY 8, 2020  
MONUMENT: 3 1/2" ALUMINUM DISK SET IN CONCRETE STAMPED "CP9"  
EASTLAND COUNTY SCALE FACTOR: 1.0001  
SURFACE ENGLISH CO-ORDS  
NORTHING: 10,572,171.001  
EASTING: 2,733,750.639  
STATE PLANE ENGLISH CO-ORDS  
NORTHING: 10,571,113.889  
EASTING: 2,733,477.291  
ELEVATIONS ARE NAVD 88 BASED UPON TxDOT VRS RTK NETWORK

**SAM** Surveying and Mapping, LLC (SAM)  
1341 W. Mockingbird Lane, Suite 400W  
Dallas, Tx 75247 - (214) 631-7888  
FIRM REGISTRATION NO. F-1937  
TBPLS REGISTRATION NO. 10064301



PRIMARY HORIZONTAL  
AND VERTICAL CONTROL  
CR 267 @ LEWIS CREEK


FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	9	



**LEGEND**


- CURRENT PHASE CONSTRUCTION
- PREVIOUS PHASE CONSTRUCTION
- TEMPORARY SIGN
- TRAFFIC FLOW
- TY III BARRICADE

SIGNS SHOWN FOR EASTBOUND TRAFFIC,  
WESTBOUND SIGNS IDENTICAL.




**PHASE 1**

SIGNS SHOWN FOR EASTBOUND TRAFFIC,  
WESTBOUND SIGNS IDENTICAL.



**PHASE 2**

NO.	REVISION	BY	DATE



**TRAFFIC CONTROL PLAN  
CR 267 AT LEWIS CREEK**

SHEET 1 OF 2

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY		SHEET No.
TEXAS	BWD	BROWN		10

**GENERAL NOTES:**

SIGNS SHALL BE PLACED IN ACCORDANCE WITH THE BARRICADE AND CONSTRUCTION STANDARDS OR AS DIRECTED BY THE ENGINEER.

OTHER SIGNS AS DETAILED IN THE BARRICADE AND CONSTRUCTION STANDARDS AND IN THE MUTCD MAY BE USED AS REQUIRED BY THE ENGINEER IN ORDER TO PROVIDE FOR THE SAFE PASSAGE OF TRAFFIC THROUGH THE PROJECT. PAYMENT FOR ALL SUCH SIGNS, BARRICADES OR TRAFFIC CONTROL DEVICES SHALL BE CONSIDERED SUBSIDIARY TO ITEM 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."

PROVIDE ACCESS TO AND FROM DRIVEWAYS AND ALL ADJACENT PROPERTY AT ALL TIMES.

**TRAFFIC CONTROL SEQUENCE:**

THE CONTRATOR SHALL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK TO THE AREA ENGINEER PRIOR TO THE BEGINNING OF CONSTRUCTION, WHICH GENERALLY CONFORMS TO THE FOLLOWING SEQUENCE:

**PHASE 1**

1. INSTALL PROJECT LIMIT SIGNING AND BARRICADES AND SW3P PRIOR TO BEGINNING ANY OTHER WORK.
2. WITH TRAFFIC IN EXISTING CONFIGURATION, CONSTRUCT TEMPORARY BYPASS. REFER TO TEMPORARY BYPASS PLAN AND PROFILE FOR DETAILS.


**PHASE 2**

1. INSTALL PHASE 2 TCP DEVICES, TEMPORARY SIGNALS AND SHIFT TRAFFIC TO ONE-LANE-TWO-WAY TEMPORARY BYPASS.
2. COMPLETE THE CONSTRUCTION OF THE BRIDGE AND PORTIONS OF APPROACHES ACCORDING TO THE PLANS AND SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER.



pm:/fcs-pw-bentley.com:/tts-pw-01/Documents/0223-002-VA-3 - CR Brown Comanche Co/Cadd/Plan Sheets/TCP/CR267\_TCP\_01.dgn  
 3/23/2021 2:59 JamesBrooks SCRIPT: CR267\_Index.pen



SIGNS SHOWN FOR EASTBOUND TRAFFIC,  
WESTBOUND SIGNS IDENTICAL.



**PHASE 3**



**LEGEND**


- CURRENT PHASE CONSTRUCTION
- PREVIOUS PHASE CONSTRUCTION
- TEMPORARY SIGN
- TRAFFIC FLOW
- TY III BARRICADE

NO.	REVISION	BY	DATE

TRAFFIC CONTROL SEQUENCE (CONTINUED):

PHASE 3

1. INSTALL PHASE 3 TCP DEVICES AND SHIFT TEMPORARY SIGNALS AND ONE-LANE-TWO-WAY TRAFFIC TO COMPLETED BRIDGE.
2. CONSTRUCT REMAINING PORTIONS OF APPROACHES ACCORDING TO THE PLANS AND SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER.
3. REMOVE ONE-LANE-TWO-WAY TRAFFIC CONTROL AND SHIFT TRAFFIC TO FINAL CONFIGURATION AS SOON AS DETERMINED PRACTICAL BY THE ENGINEER.
4. COMPLETE ALL OTHER WORK AS DIRECTED BY THE ENGINEER.



TRAFFIC CONTROL PLAN  
CR 267 AT LEWIS CREEK

SHEET 2 OF 2

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY		SHEET No.
TEXAS	BWD	BROWN		10A

p:\tts-pw-bentley.com\tts-pw-01\Documents\0223.002 WA 3 - CR Brown Comanche Co\Cadd\Plan Sheets\TCP\CR267\_TCP\_02.dgn  
 3/23/2021 3:00  
 SCRIPT: CR267\_Index.pen  
 JamesBrooks

# TEMPORARY BYPASS - HORIZONTAL ALIGNMENT DATA

BEGINNING CHAIN CR267\_BYPASS DESCRIPTION

POINT BPCR26701 X 2,734,001.0978 Y 10,571,980.5556 STA 100+00.00

COURSE FROM BPCR26701 TO PC CURVE 1 S 45° 56' 40.5463" E DIST 47.1058

\*-----\*

CURVE DATA

CURVE 1  
P. I. STATION 101+20.70 X 2,734,087.8425 Y 10,571,896.6249  
DELTA = 12° 00' 13.6076" (RT)  
DEGREE = 8° 11' 06.4009"  
TANGENT = 73.5963  
LENGTH = 146.6538  
RADIUS = 700.0000  
EXTERNAL = 3.8582  
LONG CHORD = 146.3858  
MID. ORD. = 3.8371  
P. C. STATION 100+47.11 X 2,734,034.9512 Y 10,571,947.8004  
P. T. STATION 101+93.76 X 2,734,128.9340 Y 10,571,835.5683  
C. C. X 2,733,548.2037 Y 10,571,444.7329  
BACK = S 45° 56' 40.5463" E  
AHEAD = S 33° 56' 26.9387" E  
CHORD BEAR = S 39° 56' 33.7425" E

\*-----\*

CURVE DATA

CURVE 2  
P. I. STATION 103+53.82 X 2,734,218.2996 Y 10,571,702.7827  
DELTA = 25° 45' 31.9416" (LT)  
DEGREE = 8° 11' 06.4008"  
TANGENT = 160.0570  
LENGTH = 314.7040  
RADIUS = 700.0000  
EXTERNAL = 18.0656  
LONG CHORD = 312.0604  
MID. ORD. = 17.6111  
P. C. STATION 101+93.76 X 2,734,128.9340 Y 10,571,835.5683  
P. T. STATION 105+08.46 X 2,734,356.4917 Y 10,571,622.0287  
C. C. X 2,734,709.6643 Y 10,572,226.4037  
BACK = S 33° 56' 26.9387" E  
AHEAD = S 59° 41' 58.8804" E  
CHORD BEAR = S 46° 49' 12.9095" E

\*-----\*

CURVE DATA

CURVE 3  
P. I. STATION 105+88.51 X 2,734,425.6027 Y 10,571,581.6430  
DELTA = 13° 02' 49.2512" (RT)  
DEGREE = 8° 11' 06.4012"  
TANGENT = 80.0459  
LENGTH = 159.3993  
RADIUS = 700.0000  
EXTERNAL = 4.5618  
LONG CHORD = 159.0552  
MID. ORD. = 4.5323  
P. C. STATION 105+08.46 X 2,734,356.4917 Y 10,571,622.0287  
P. T. STATION 106+67.86 X 2,734,483.8126 Y 10,571,526.6980  
C. C. X 2,734,003.3191 Y 10,571,017.6538  
BACK = S 59° 41' 58.8804" E  
AHEAD = S 46° 39' 09.6292" E  
CHORD BEAR = S 53° 10' 34.2548" E

COURSE FROM PT CURVE 3 TO BPCR26702 S 46° 39' 09.6282" E DIST 42.1296

POINT BPCR26702 X 2,734,514.4495 Y 10,571,497.7794 STA 107+09.99

ENDING CHAIN CR267\_BYPASS DESCRIPTION

p:\tts-pw-bentley.com\tts-pw-01\Documents\0223.002 WA 3 - CR Brown Comanche Co\Cadd\Plan Sheets\TCP\CR267\_TCP\_HAD\_01.dgn  
 SCRIPT: CR267\_Index.pen  
 2/25/2021 12:31

NO.	REVISION	BY	DATE



## TEMPORARY BYPASS HORIZONTAL ALIGNMENT DATA CR 267 AT LEWIS CREEK




SHEET 1 OF 1

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET NO.	
TEXAS	BWD	BROWN	11	

CURVE 1		CURVE 2		CURVE 3	
PI STA	= 101+20.70	PI STA	= 103+53.82	PI STA	= 105+88.51
DELTA	= 12° 00' 13.6076" (RT)	DELTA	= 25° 45' 31.9416" (LT)	DELTA	= 13° 02' 49.2512" (RT)
DEGREE	= 8° 11' 06.4009"	DEGREE	= 8° 11' 06.4008"	DEGREE	= 8° 11' 06.4012"
TANGENT	= 73.5963	TANGENT	= 160.0570	TANGENT	= 80.0459
LENGTH	= 146.6538	LENGTH	= 314.7040	LENGTH	= 159.3993
RADIUS	= 700.0000	RADIUS	= 700.0000	RADIUS	= 700.0000
PC STA	= 100+47.11	PC STA	= 101+93.76	PC STA	= 105+08.46
PT STA	= 101+93.76	PT STA	= 105+08.46	PT STA	= 106+67.86

ITEM	DESCRIPTION	UNIT	QUANTITY
	RC PIPE (ARCH) (CL III) (DES 7)	LF	78
	NON-ERODIBLE MATERIAL (4" TO 6" ROCK)	CY	130
508-6001	CONSTRUCTING DETOURS	SY	485

TEMP BYPASS PAVE STRUCTURE, EARTHWORK AND PIPE SHOWN FOR CONTRACTOR'S INFORMATION ONLY. BYPASS PAID UNDER ITEM 508, CONSTRUCTING DETOURS.




TYPICAL SECTION (NTS)

- ① TEMP DITCH AS DIRECTED BY THE ENGINEER. MAINTAIN POSITIVE FLOW TO CREEK.
- ② 1 CRSE PRIME AND TYPE B GR 3.

EXISTING GAS LINE LOCATION SHOULD BE CONSIDERED APPROXIMATE. IT IS CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH UTILITY OWNER BEFORE CONSTRUCTION BEGINS.

EST	UNIT	DESCRIPTION
133	CY	EMBANK (FINAL) (ORD COMP) (TY C)
19	CY	EXCAV (RDWY)



NO.	REVISION	BY	DATE

**JAMES BROOKS**  
101002  
LICENSED PROFESSIONAL ENGINEER  
3/23/2021

**TEXAS TRANSPORTATION SOLUTIONS, INC.**  
PRO 07-10207

©2020 **Texas Department of Transportation**

**TEMPORARY BYPASS PLAN AND PROFILE  
CR 267 AT LEWIS CREEK**

FED. RD. DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	11A	

SHEET 1 OF 1

pm://tts-pw-bentley.com:tts-pw-01/Documents/0223-002-VA-3 - CR Brown Comanche Co/Cadd/Plan Sheets/TCP/CR267\_TCP\_PP\_01.dgn  
 3/23/2021 3:54 JamesBrooks

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/02233\_002/Cadd/Standard.s/BC-14.dgn

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- As shown on BC(2), the OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER (see Sign Detail G20-10T) and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. However, the TRAFFIC FINES DOUBLE sign will not be required on projects consisting solely of mobile operation work, such as striping or milling edgeline rumble strips. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits.
- Except for devices required by Note 10, traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY APPAREL NOTES:**

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.



Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found on-line at the web address given below or by contacting:

Texas Department of Transportation  
 Traffic Operations Division - TE  
 Phone (512) 416-3118


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT <a href="http://www.txdot.gov">http://www.txdot.gov</a>	
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)	
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)	
MATERIAL PRODUCER LIST (MPL)	
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"	
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)	
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)	
TRAFFIC ENGINEERING STANDARD SHEETS	

SHEET 1 OF 12

<b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b>			
<b>BC (1) - 14</b>			
FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT	SECT	JOB
REVISIONS	0923	06	083
4-03 5-10 8-14	DIST	COUNTY	SHEET NO.
9-07 7-13	BWD	BROWN	12

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent/ey.com/tts-pw-01/Documents/0223\_002/Coad/Standard/CP/BC(2)-14.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL LOCATION OF CROSSROAD SIGNS**



⊗ May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "X" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**




**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- ⊗ The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- \*\* Required CSJ Limit signing. See Note 10 on BC(1). TRAFFIC FINES DOUBLE signs will not be required on projects consisting solely of mobile operations work.
- ⊗ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- ⊗ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
⊗	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-14**


FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
9-07	8-14	DIST	COUNTY	SHEET NO.
7-13		BWD	BROWN	13



# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:47  
FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/BC(3)-14.dgn

SHEET 3 OF 12




## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 14

FILE:	bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0923	06	083	CR 267
9-07	8-14	DIST	COUNTY	SHEET NO.	
7-13		BWD	BROWN	14	


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.


\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports



Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
  - Wooden sign posts shall be painted white.
  - Barricades shall NOT be used as sign supports.
  - All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
  - The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
  - The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD). The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
  - The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
  - Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
  - The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.
- DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**
- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
    - Long-term stationary - work that occupies a location more than 3 days.
    - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
    - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
    - Short, duration - work that occupies a location up to 1 hour.
    - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24" as detailed below.
- When used at night, the STOP/SLOW paddle shall be retroreflectORIZED.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC sheets or the CWZTCD. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES


BC (4) - 14

FILE:	bc-14.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
	REVISIONS	0923	06	083	CR 267				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13		BWD	BROWN		15				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/TCP/BC-14.dgn




**SKID MOUNTED WOOD SIGN SUPPORTS**  
 LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS □



**GROUND MOUNTED SIGN SUPPORTS**  
 Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.




**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**



**WOOD POST SYSTEM FOR GROUND MOUNTED SIGN SUPPORTS**

Nominal Post Size	Number of Posts	Maximum Sq. feet of Sign Face	Minimum Soil Embedment	Drilled Hole(s) Required
4 x 4	1	12	36"	NO
4 x 4	2	21	36"	NO
4 x 6	1	21	36"	YES
4 x 6	2	36	36"	YES



**WEDGE ANCHORS**  
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**  
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- See BC(4) for definition of "Work Duration."
- ✕ Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- △ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC (5) - 14**

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	BWD	BROWN	16	

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

## Phase 1: Condition Lists

Road/Lane/Ramp Closure List		Other Condition List	
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT *
XXXXXXXXX BLVD CLOSED			

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

Action to Take/Effect on Travel List		Location List	Warning List	** Advance Notice List
MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM-X PM
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX-XX X PM-X AM
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXXXX TO XXXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM-XX AM
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE	NEXT TUE AUG XX
USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM-XX AM
STAY IN LANE *				

\*\* See Application Guidelines Note 6.

### APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

### WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

### FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12

		<b>Traffic Operations Division Standard</b>	
<h2>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h2>			
<h3>BC (6) - 14</h3>			
FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT	SECT	JOB
REVISIONS	0923	06	083
9-07	8-14	DIST	COUNTY
7-13		BWD	BROWN
			SHEET NO. 17


DATE: 7/24/2020 2:47

FILE: pw://tts-pw\_bentley.com/tts-pw-01/Document/0223\_002/Cadd/Standard/BCP/BC-14.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/TCP/BC-14.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet crashworthy standards as defined in the National Cooperative Highway Research Report 350. Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential Chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**

Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the National Cooperative Highway Research Report No. 350 (NCHRP 350) or the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

**Texas Department of Transportation**  
*Traffic Operations Division Standard*

**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) - 14**

FILE:	bc-14.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0923	06	083	CR 267				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13		BWD	BROWN		18				



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/TCP/BC-14.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DIRECTION INDICATOR BARRICADE**

- The Direction Indicator Barricade may be used in tapers, transitions, and other areas where specific directional guidance to drivers is necessary.
- If used, the Direction Indicator Barricade should be used in series to direct the driver through the transition and into the intended travel lane.
- The Direction Indicator Barricade shall consist of One-Direction Large Arrow (CW1-6) sign in the size shown with a black arrow on a background of Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange retroreflective sheeting above a rail with Type A retroreflective sheeting in alternating 4" white and orange stripes sloping downward at an angle of 45 degrees in the direction road users are to pass. Sheetting types shall be as per DMS 8300.
- Double arrows on the Direction Indicator Barricade will not be allowed.
- Approved manufacturers are shown on the CWZTCD List. Ballast shall be as approved by the manufacturers instructions.



**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a device that is detectable by a person with a visual disability traveling with the aid of a long cane shall be placed across the full width of the closed sidewalk.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades may use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 14**

FILE:	bc-14.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0923	06	083	CR 267				
4-03	7-13	DIST	COUNTY	SHEET NO.					
9-07	8-14	BWD	BROWN	19					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223\_002/Caad/Standards/TCP/BC-14.dgn



**FIXED**  
(Rigid or self-righting)

**DRIVEABLE**




(Rigid or self-righting)

**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual Appendix B "Treatment of Pavement Drop-offs in Work Zones" for additional guidelines on the use of VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10) placed near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate NCHRP 350 crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed X	Formula	Minimum Desirable Taper Lengths X X			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\*\*Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 14**

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	BWD	BROWN	20	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223\_002/Coad/Standards/TCP/BC-14.dgn


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**


1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

THIS DEVICE SHALL NOT BE USED ON PROJECTS LET AFTER MARCH 2014.



1. This device is intended only for use in place of a vertical panel to channelize traffic by indicating the edge of the travel lane. It is not intended to be used in transitions or tapers.
2. This device shall not be used to separate lanes of traffic (opposing or otherwise) or warn of objects.
3. This device is based on a 42 inch, two-piece cone with an alternate striping pattern: four 4 inch retroreflective bands, with an approximate 2 inch gap between bands. The color of the band should correspond to the color of the edgeline (yellow for left edgeline, white for right edgeline) for which the device is substituted or for which it supplements. The reflectorized bands shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless otherwise noted.
4. The base must weigh a minimum of 30 lbs.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers used at night shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.

**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 14**

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	BWD	BROWN	21	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


**BC(11) - 14**

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS				
2-98 9-07	0923	06	083	CR 267
1-02 7-13	DIST	COUNTY		SHEET NO.
11-02 8-14	BWD	BROWN		22


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/TCP/BC-14.dgn


## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A



RAISED PAVEMENT MARKERS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B



RAISED PAVEMENT MARKERS - PATTERN B


Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



CENTER LINE OR LANE LINE




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/TCP/BC-14.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."




## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 14


FILE:	bc-14.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TXDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0923	06	083	CR 267				
1-97	9-07	DIST	COUNTY	SHEET NO.					
2-98	7-13	BWD	BROWN	23					
11-02	8-14								

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:47  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002/Coad/Standards/TCP/TCP (2-7).dgn



TCP (2-7a)  
 ROADWAY DIVERSION



TCP (2-7b)  
 BRIDGE WIDENING


LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- TCP (2-7a)**
- Raised pavement markers shall be placed 40 feet c-c on centerline throughout project.
  - Roadway diversion design requirements should be based on posted speed limit or prevailing speed.
  - New pavement surface should be extended across existing roadway edge to a point where existing pavement markings left in place during project do not conflict with construction area pavement marking.
- TCP (2-7b)**
- The CW5-2 "Narrow Bridge" sign may be omitted if lane and shoulder widths are maintained.





TRAFFIC CONTROL PLAN  
 DIVERSIONS AND  
 NARROW BRIDGES

TCP (2-7) - 18

FILE: tcp2-7-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	BWD	BROWN	24	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into any other form or for any errors or omissions that may appear hereon.

DATE: 10/20/2020 6:29  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002.WA.3 - CR Brown of on the ne arge of safety signs



**LEGEND**

	Type 3 Barricade		Channelizing Devices
	Sign		Traffic Flow
	Flag		Flagger
	Raised Pavement Markers Ty II-AA		Temporary or Portable Traffic Signal

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**TYPICAL USAGE**

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
  - When this TCP is used at a location which does not involve a bridge, a 48" x 48" CW20-4D "ONE LANE ROAD AHEAD" signs should be used in lieu of the CW5-3 "ONE LANE BRIDGE" signs. The CW13-1P Advisory Speed Plaque is required with either warning sign.
  - Raised pavement markers shall be placed 40 feet c-c on centerline between DO NOT PASS signs and stop or yield lines.
  - For intermediate term situations, when it is not feasible to remove and restore pavement markings, the channelization must be made dominant by using a very close spacing. This is especially important in locations of conflicting information, such as where traffic is directed over a double yellow centerline. In such locations a maximum channelizing device spacing of 20 feet is recommended. The 20 foot channelizing device spacing recommendation is intended for the area of conflicting information and not the entire work zone.
- TCP (2-8a)**
- Traffic control by CW3-2 "YIELD AHEAD" symbol signs for one lane two-way traffic control operations should be limited to work spaces less than 400 feet long and roadways with less than 2000 ADT. Otherwise, portable traffic signals should be used.
  - If power is available, a flashing beacon should be attached to the CW3-2 "YIELD AHEAD" symbol sign for emphasis.
  - The R1-2 "YIELD" and R1-2aP "TO ONCOMING TRAFFIC" signs and other regulatory signs shall be installed at 7 foot minimum mounting height.
- TCP (2-8b)**
- A list of approved Portable Traffic Signals can be found in the "Compliant Work Zone Traffic Control Devices" list.
  - Portable traffic signals should be located to provide adequate stopping sight distance for approaching motorist (See table above).

**Texas Department of Transportation**  
*Traffic Operations Division Standard*

**TRAFFIC CONTROL PLAN  
 LONG TERM ONE-LANE  
 TWO-WAY CONTROL**

**TCP (2-8) - 18**

FILE: tcp2-8-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	BWD	BROWN	24A	
4-98 2-18				

168



# CR 267 - HORIZONTAL ALIGNMENT DATA

BEGINNING CHAIN CR267 DESCRIPTION

POINT CR26701 X 2,734,066.0282 Y 10,571,918.0248 STA 10+00.00


COURSE FROM CR26701 TO CR26702 S 46° 53' 50.7237" E DIST 515.0247

POINT CR26702 X 2,734,442.0640 Y 10,571,566.1050 STA 15+15.02

ENDING CHAIN CR267 DESCRIPTION

p:\tts-pw-bentley.com\tts-pw-01\Documents\0223.002 WA 3 - CR Brown Comanche Co\Cadd\Plan Sheets\Roadway\CR267\_RDW\_HAD\_01.dgn  
 SCRIPT: CR267\_Index.pen  
 JamesBrooks  
 12:31  
 2/25/2021




NO.	REVISION	BY	DATE



HORIZONTAL  
 ALIGNMENT DATA  
 CR 267 AT LEWIS CREEK

SHEET 1 OF 1

FED. RD. DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY		SHEET No.
TEXAS	BWD	BROWN		25



**LEGEND**


- DIRECTION OF TRAFFIC
- DIRECTION OF FLOW
- MBGF
- WIRE FENCE (TY C) (PERMANENT)
- WIRE FENCE (WATER GAP) (PERMANENT)

EXISTING GAS LINE LOCATION SHOULD BE CONSIDERED APPROXIMATE. IT IS CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH UTILITY OWNER BEFORE CONSTRUCTION BEGINS.

NOTE: TYPE C FENCE TO BE LOCATED AS CLOSE TO EXISTING FENCE AS POSSIBLE UNLESS DIRECTED BY THE ENGINEER.

EST	UNIT	DESCRIPTION
67	CY	EMBANK (FINAL) (ORD COMP) (TY C)
91	CY	EXCAV (RDW)

pm://tts-pw-bentley.com:tts-pw-01/Documents/0223-002 WA 3 - CR Brown Comanche Co/Cadd/Plan Sheets/Roadway/CR267\_RDW\_PP\_01.dgn  
 3/23/2021 3:56 JamesBrooks SCRIPT: CR267\_Index.pen



NO.	REVISION	BY	DATE

3/23/2021




TEXAS TRANSPORTATION SOLUTIONS, INC.  
PRO 01-1027

©2020 Texas Department of Transportation

**PLAN AND PROFILE  
CR 267 AT LEWIS CREEK**

FED. RD. DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	26	

SHEET 1 OF 1



- (A) 3' x 3' TOEWALL
- (B) STONE PROTECTION RIPRAP (12") THICKNESS = 18"

NO.	REVISION	BY	DATE



3/23/2021




## RIPRAP LAYOUT CR 267 AT LEWIS CREEK

SHEET 1 OF 1






FED. RD. DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	27	


p:\tts-pw-bentley.com\tts-pw-01\Documents\0223-002 WA 3 - CR Brown Comanche Co\Cadd\Plan Sheets\Roadway\CR267\_RDW\_GL\_01.dgn  
 3/23/2021 11:24  
 JamesBrooks SCRIPT: CR267\_Index.pen







DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any units of measurement to SI units or for incorrect formats or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:48  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/Revised/Revised/0923/06/083/CR 267

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS					DELINEATORS				D & OM DESCRIPTIVE CODES		
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXX)XXX(XX)		
						1-Size 2 reflector unit	1-Size 1 reflector unit	2-Size 2 reflector units	2-Size 1 reflector units	NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post FLX = Flexible Post BRF = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount	
SHEETING	Yellow, White or Red Type B or C reflective sheeting				SHEETING		Yellow, White or Red Type B or C Reflective Sheeting				
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	FLX	WC	FLX	DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back INSTL OM ASSM (OM-XX) (XXX)XXX(XX)	
MOUNT TYPE					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF	TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post FLX = Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional	

OBJECT MARKERS								
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4
		3-Size 2 reflector units	1-Size 3 reflector unit	3-Size 1 reflector units or 1-Size 4 reflector unit				
SHEETING	Yellow-Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting			Red -Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting
POST TYPE	TWT	WC	WC	FLX	TWT			TWT
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker backplates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.
DEVICE	GF1	GF2	CTB	W1-8				W1-6	
									
SHEETING	Yellow, White, Red			NOTE					
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. The Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTIONAL LARGE ARROW (W1-6).					


**Texas Department of Transportation**  
 Traffic Operations Division Standard












### DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

#### D & OM(1)-15

FILE: dcm1-15.dgn	DN: TXDOT	CK: TXDOT	DN: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10	BWD	BROWN	28	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings, specifications, or other documents into digital formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:48  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/0223.002/Cadd/Standards/0223.002.dgn

POST TYPE AND SUPPORT FOUNDATION DETAILS					TYPE OF BARRIER MOUNTS			
WING CHANNEL (WC)	FLEXIBLE POSTS (FLX)			WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT		
GND	GND	SRF	WAS	WAP	GF 1	GF 2		
								
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC	CONCRETE BARRIER / BRIDGE RAIL		
<b>NOTES</b> 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.	<b>NOTES</b> 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions.			<b>NOTE</b> 1. Install per manufacturer's recommendations.		CTB 		
<b>TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS</b>		<b>CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN</b>		<b>DELINEATORS AND TYPE 2 OBJECT MARKERS</b>			<b>GENERAL NOTES</b>	
 <p><b>NOTE</b>            Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)</p>		 <p><b>NOTE</b>            Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTIONAL LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.</p>		 <p>See general notes 1, 2 and 3.</p>			1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.	
					<b>Traffic Operations Division Standard</b>		<b>DELINEATOR &amp; OBJECT MARKER INSTALLATION</b>  <b>D &amp; OM(2) - 15</b>	
FILE: dcm2-15.dgn © TxDOT August 2004 REVISIONS 10-09 3-15 4-10		DNE: TxDOT CONT SECT 0923 06 DIST COUNTY BWD BROWN		CK: TxDOT JOB 083 COUNTY BROWN		CK: TxDOT HIGHWAY CR 267 SHEET NO. 29		
						20B		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any kind of units or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:48  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002/Cadd/Standard.s/0204059-15B.dgn

## USE OF WARNING DEVICES AT CURVES WITH ADVISORY SPEED LIMITS

Amount by which Advisory Speed Is less than Posted Speed	Warning Devices Needed
5 MPH & 10 MPH	RPMs
15 MPH & 20 MPH	RPMs, and Delineators or RPMs and ONE DIRECTION LARGE ARROW (W1-6) or (W1-9T) sign
25 MPH & Greater	RPMs and Chevrons

### SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES




Curves less than 1 degree do not normally require delineators.

**NOTE**

ONE DIRECTIONAL LARGE ARROW (W1-6) or (W1-9T) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

### SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

## DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve <sup>1</sup>	Single delineators on right side	See delineator spacing table
FRWY/EXP. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 4 on D&OM(4))	100 feet on ramp tangents. Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves).
Acceleration/Deceleration Lane	Double delineators (see Detail 4 on D&OM(4))	100 feet (See Detail 4 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence or CTB	Bi-Directional Delineators when undivided with one lane each direction  Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end. Undivided 2-lane highways - Object marker on approach and departure end.	Requires Type 3 Object Marker or reflective sheeting provided by manufacturer per D & OM(VIA).
Bridges with no Approach Rail	Type 3 Object Marker at end of rail and 3 single delineators approaching rail.	See Detail 2 on D & OM(4)
Reduced Width Approaches to Bridge Rail	Type 2 Object Markers and 3 single delineators approaching bridge.	See Detail 1 on D & OM(4)
Culverts without MBGF	Type 2 Object Markers	See Detail 3 on D & OM(4)
Crossovers	Double yellow delineators or RPM's	See Detail 5 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

**NOTES**

1. Delineators not required in urban areas with continuous illumination.
2. Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
3. Barrier reflectors may be used to replace required delineators.
4. Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
⦿	Bi-directional Delineator
⦿	Delineator
+	Sign

Traffic Operations Division Standard

## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS


### D & OM(3) - 15B

FILE: dom3-15b.dgn	DN: TXDOT	CK: TXDOT	DN: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS		0923	06	083
3-15	DIST	COUNTY	SHEET NO.	
8-15	BWD	BROWN	30	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any kind of information into digital format or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:48  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223.002/Cadd/Standards/020414-15\_02.dwg

**TWO-WAY, TWO LANE ROADWAY WITH REDUCED WIDTH APPROACH**




**DETAIL 1**

**TWO-WAY, TWO LANE ROADWAY BRIDGE WITH NO APPROACH RAIL**




**DETAIL 2**

**FOR CULVERTS WITHOUT MBGF**




**DETAIL 3**

**FREEWAY DELINEATION FOR RAMP AND ACCELERATION/DECELERATION LANES**




**DETAIL 4**

**CROSSOVERS**




**DETAIL 5**

**TYPICAL APPLICATION OF DEAD END BARRICADE**



**DETAIL 6**

**TYPICAL DEAD END BARRICADE INSTALLATION**



**NOTES**

1. Barricade striping shall be red and white reflective sheeting for all permanent road closures.
2. Barricade striping is red and white sloping toward the center of the roadway.
3. Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

**DETAIL 7**

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(4) - 15**


FILE: dcm4-15.dgn	DN: TXDOT	CK: TXDOT	DN: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
3-15	0923	06	083	CR 267
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	31	



**TWO-WAY, TWO LANE ROADWAY  
WITH REDUCED WIDTH APPROACH RAIL**




**TWO-WAY, TWO LANE ROADWAY  
WITH METAL BEAM GUARD FENCE (MBGF)**



**NOTE:**  
If terminal ends include an object marker, there is no need to install an OM-2 in front of terminal.

**TWO-WAY, TWO LANE ROADWAY  
BRIDGE WITH NO APPROACH RAIL**



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information to a different format or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:49  
FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/Revised/05-15-09/05-15-09.dwg

<b>LEGEND</b>				<b>Traffic Operations Division Standard</b>			
	Bidirectional Delineator	<b>DELINEATOR &amp; OBJECT MARKER PLACEMENT DETAILS</b> <b>D &amp; OM(5) - 15</b>					
	Delineator						
	OM-3						
	OM-2						
	Terminal End						
	TRAFFIC FLOW	FILE: dom5-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
		© TxDOT August 2015		CON: 0923	SECT: 06	JOB: 083	HIGHWAY: CR 267
		REVISIONS		DIST: BWD	COUNTY: BROWN	SHEET NO. 32	




CONTINUOUS CONCRETE BARRIER

MULTI-LANE UNDIVIDED,  
TWO-WAY ROADWAY WITH  
METAL BEAM FENCE (MBGF)

DIVIDED ROADWAY WITH  
METAL BEAM GUARD FENCE

DISCLAIMER:  
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:49  
FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223.002/Cadd/Standards/Revised/06-15-2019/0923-06-083-267



**LEGEND**

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	TRAFFIC FLOW

**Texas Department of Transportation**

*Traffic Operations Division Standard*






**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(6) - 15**




FILE: dom6-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CON: 0923	SECT: 06	JOB: 083	HIGHWAY: CR 267
REVISIONS	DIST: BWD	COUNTY: BROWN	SHEET NO. 33	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from any source into a digital format or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:49  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/ROADWAY/Attenuators/Attenuator/Attenuator.dwg



OBJECT MARKERS SMALLER THAN 3 FT<sup>2</sup>



**NOTES**


1. Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
2. Mounting should be flush with top of attenuator. Minimum size 96" x 24".

**NOTES**


1. Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
2. Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
3. Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
4. Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
5. Object Marker at nose of attenuator is subsidiary to the attenuator.
6. See D & OM (1-4) for required barrier reflectors.

		<b>Traffic Operations Division Standard</b>	
<b>DELINEATOR &amp; OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</b> <b>D &amp; OM(VIA) -15</b>			
FILE: domv15.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
© TxDOT December 1989	CONT	SECT	JOB
REVISIONS		0923	06
4-92 8-04		083	CR 267
8-95 3-15			
4-98			
	DIST	COUNTY	SHEET NO.
	BWD	BROWN	34
20G			


DATE: 7/24/2020  
 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223\_002/Cadd/Standards/Roadway/GF (31) -19.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




**TYPICAL POST PLACEMENT**



**WOOD BLOCK TO ROUND WOOD POST**




**WOOD BLOCK TO RECTANGULAR WOOD POST**



**ROUTED WOOD BLOCK TO I-BEAM STEEL POST**


**GENERAL NOTES**

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.




**ELEVATION MID-SPAN RAIL SPLICE**

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




**ELEVATION 25'-0" (NOM.) W-BEAM SECTION**

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




**BUTTON HEAD BOLT**



**MID-SPAN RAIL SPLICE DETAIL**

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

\* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



**LOW FILL CULVERT POST**


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

		<b>Design Division Standard</b>	
<b>METAL BEAM GUARD FENCE</b> <b>TL-3 MASH COMPLIANT</b> <b>GF(31)-19</b>			
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS		0923	06
DIST	COUNTY	083	CR 267
BWD	BROWN	SHEET NO. 35	

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: 7/24/2020 2:49  
FILE: pw://tts-pw\_bent/ey.com/tts-pw-01/Documents/0223\_002/Cadd/Standard/Roadway/GF (31) TR TL2-19.dgn






- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (ASTM A325 OR A449)
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 7/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563)

NOTE: HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE: CHAMFER REQUIRED ON CONCRETE RAILS THAT EXTEND BEYOND THE FACE OF GUARDRAIL TRANSITION.



- ### GENERAL NOTES
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. REFER TO GF(31) STANDARD SHEET.
  2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS.
  3. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
  4. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM BOLT LENGTH TO MEET REQUIRED LENGTH.
  5. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  6. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
  7. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
  8. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT, MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
  9. REFER TO GF(31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
  10. FOR ROUND WOOD POSTS SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE TRANSITION.




- (2) 5/8" BUTTON HEAD POST BOLTS & NUTS: (FBB04)
- (1) 5/8" FLAT WASHER: (FWC14a) UNDER EACH NUT


- (1) 5/8" BUTTON HEAD POST BOLT & NUT: (FBB04)
- (1) 5/8" FLAT WASHER: (FWC14a) UNDER EACH NUT

PLATE WASHER INSTRUCTIONS

**BRIDGE APPROACH - UPSTREAM:** THE SHORT RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.  
**BRIDGE EXIT - DOWNSTREAM:** THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.




SECTION A-A





SECTION B-B

NOTE: \* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.




LOW-SPEED TRANSITION

<b>Texas Department of Transportation</b>				<b>Design Division Standard</b>
<b>METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-2 MASH COMPLIANT GF(31) TR TL2-19</b>				
FILE: gf31tr+1219.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CGL/AG
© TxDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	36	

DISCLAIMER:  
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020  
FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223\_002/Coad/Standard/Roadway/SGT(10S)31-16.dgn



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; SoftStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MGBF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - IT IS ACCEPTABLE TO INSTALL THE SoftStop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
  - DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoaching ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

**NOTE: A** THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3'-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

**NOTE: B** PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)  
PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

**NOTE: C** W-BEAM SPLICE LOCATED BETWEEN LINE POST (4) AND LINE POST (5)  
GUARDRAIL PANEL 25'-0" PN:61G  
ANCHOR RAIL 25'-0" PN:15215G  
LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25'-0")
15205A	1	POST #0 - ANCHOR POST (6'-5 3/8")
15203G	1	POST #1 - (SYTP) (4'-9 1/2")
15000G	1	POST #2 - (SYTP) (6'-0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6'-0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B




TRINITY HIGHWAY  
SOFTSTOP END TERMINAL  
MASH - TL-3  
SGT (10S) 31-16

FILE: sgt10s3116	DN: TxDOT	CK: KM	DW: VP	CK: MB/VP
©TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
DIST	COUNTY	SHEET NO.		
BWD	BROWN	37		

NOTE:  
THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



DATE: 7/24/2020  
 FILE: pw://tts-pw\_bentf ley.com/tts-pw-01/Document/0223\_002/Cadd/Standard/Roadway/SGT(12S)31-18.dgn




- NOTES:
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
  - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
  - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" X 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/16" WASHER	W0516
c	2	5/16" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" X 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/16" O.D. X 3/16" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" X 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. \* \*  
 \* ITEM (P) 8" WOOD-BLOCKOUT  
 \* \* ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.


**Design Division Standard**

**SINGLE GUARDRAIL TERMINAL**  
**MSKT-MASH-TL-3**  
**SGT (12S) 31-18**

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT SECT	JOB	HIGHWAY	
REVISIONS	0923 06	083	CR 267	
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	38	




DATE: 7/24/2020  
 FILE: pw://tts-pw\_bent ley. com: t1s-pw-01/ Documents/0223.002/Cadd/Standards/Roadway/WF (1)-10. dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



SECTION GALVANIZED BARBED WIRE FENCE WITH WOOD POSTS  
Bracing Detail Used at Ends and Gates

TYPE "A" FENCE  
(See General Note 6)



SECTION GALVANIZED WOVEN WIRE FENCE WITH WOOD POSTS  
Bracing Detail Used at Ends and Gates


TYPE "B" FENCE  
(See General Note 6)

TABLE OF EQUIVALENT SIZES FOR OPTIONAL SHAPE


Minimum Diameter of Round Post (Inches)	Minimum Equivalent Dimension for Each Side of Square Post (Inches)
4	3 1/2
5	4 1/2
6	5 1/4

GENERAL NOTES


- Any high point which interferes with the placing of wire mesh shall be excavated to provide 2" clearance.
  - Latches for Type 1 and Type 2 gates shall be good commercial quality and design latches of the spring, fork or chain type. All latches shall be suitable for the gate and shall be approved by the Engineer.
  - Hinges for Type 2 gates shall be commercial design approved by the Engineer suitable for post and gate.
  - Concrete shall be of the design and consistency approved by the Engineer and shall contain not less than 4 sacks of cement per cubic yard. Concrete footings are to be crowned at the top to shed water.
  - If rock is encountered at a depth less than the embedded depth required, a 15" or larger diameter hole shall be drilled for the post and the post shall be set in concrete. If rock is encountered at a depth of 1'-6" or more below the ground surface, the hole shall be drilled to the required depth. If rock is encountered at a depth less than 1'-6" below the ground surface, the holes shall be drilled a minimum of 2'-0" into the rock or to the depth whichever is the lesser depth.
  - Barbed wire shall be in accordance with ASTM A 121 (Class 1) Design designation 12-2-4-1 4R or 12-2-5-1 4R, or as approved by the Engineer.
- Woven Wire Fence (Type B) shall be in accordance with ASTM A 116 (Class 1) No. 12-1/2 Grade 60 (See Table 1 ASTM A 116) to the height and design shown on the plans, or as approved by the Engineer.
- The location of gates and corner posts will be as indicated elsewhere on these plans.
  - Square wood posts may be used in lieu of round posts provided minimum equivalent size requirements, as shown are met. All wood posts shall be in accordance with Item 552, "Wire Fence."




DETAIL TYPE 1 GATE




DETAIL TYPE 2 GATE




DETAIL TYPE 3 GATE




CORNER OR PULL POST ASSEMBLY



DETAIL OF FENCE TREATMENT AT STRUCTURES




DETAIL OF STAY (Barbed wire fence)




Loop to be made from two strands twisted no. 9 1/2 ga. galv. smooth wire, and to be securely fastened to gate post with two galv. staples.


DETAIL FASTENER TYPE 3 GATE




DETAIL OF GATE HINGE BOLT ASSEMBLY



DETAIL OF FENCE SAG (Single Line Connection)



DETAIL SHOWING INSTALLATION OF HINGES OF TYPE 1 & 2 GATE



DETAIL OF EYE BOLT

Design Division Standard


## BARBED WIRE AND WOVEN WIRE FENCE (WOOD POSTS)

### WF (1) - 10


FILE: wf110.dgn	DN: TxDOT	CK: AM	DW: VP	CK:
© TxDOT 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	39	

DISCLAIMER:  
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020  
FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/Roadway/WF (2)-10.dgn




**SECTION GALVANIZED BARBED WIRE FENCE WITH METAL POSTS**  
BRACING DETAIL USED AT ENDS AND GATES  
**TYPE "C" FENCE**  
(See General Note 8)




**SECTION GALVANIZED WOVEN WIRE FENCE WITH METAL POSTS**  
BRACING DETAIL USED AT ENDS AND GATES  
**TYPE "D" FENCE**  
(See General Note 8)

Note:  
For Steel pipe and T-Post requirements.  
(See General Notes 6 & 7)


Metal gate shall consist of 5 panels not less than 4'-4" high and shall be aluminum or galvanized metal and of good quality. Gate and hardware shall meet the approval of the engineer.




**DETAIL TYPE 1 GATE**




**DETAIL TYPE 2 GATE**




**DETAIL TYPE 3 GATE**




**CORNER OR PULL POST ASSEMBLY**




**DETAIL OF FENCE TREATMENT AT STRUCTURES**



**DETAIL OF STAY**  
(Barbed Wire Fence)



**DETAIL OF FENCE SAG**



**DETAIL OF EYE BOLT**

**GENERAL NOTES**

- Any high point which interferes with the placing of wire mesh shall be excavated to provide a 2 inch clearance.
  - Latches for Type 1 and Type 2 gates shall be good commercial quality and design latch of the spring, fork or chain type. All latches shall be suitable to the gate and shall be approved by the Engineer.
  - Hinges for Type 2 gates shall be a commercial design approved by the Engineer suitable for post and gate.
  - Concrete shall be of the design and consistency approved by the Engineer and shall contain not less than 4 sacks of cement per cubic yard. Concrete footings are to be crowned at the top to shed water.
  - Steel anchor plates shall be of a design and thickness sufficient to prevent turning of the post in firm soil.
  - Steel pipe end posts, corner and pull posts shall be a minimum of 2" Std. pipe (2.375" O.D., 0.154" wall thickness) with a 1/4" Std. pipe brace (1.660" O.D., 0.140" wall thickness), with a 2"x2"x1/4" angle, or other as approved by the Engineer. Fasteners for securing barbed wire or woven wire fence to metal posts shall be a minimum of 11 gauge galvanized steel wire. Tubular posts shall be fitted with water malleable iron caps.
  - If Steel pipe is used for posts and braces, use standard pipe in accordance with ASTM A 53, Class B or A 501. For T-Posts use steel that meets ASTM A 702. Metal line posts shall be not less than 6'-6" in length and shall weigh not less than (1.33 lbs./lin.ft.). These items shall be in accordance with Item 552, "Wire Fence."
  - Barbed Wire shall be in accordance with ASTM A 121, Class 1 Design designation 12-2-4-1 4R or 12-2-5-1 4R, or as approved by the Engineer.
- Woven Wire Fence (Type D) shall be in accordance with ASTM A 116, Class 1 No. 12-1/2 Grade 60 (See Table 1 ASTM A 116) to the height and design shown on the plans, or as approved by the Engineer.
- The location of gates and corner posts will be as indicated elsewhere in these plans.



				<b>Design Division Standard</b>	
<b>BARBED WIRE AND WOVEN WIRE FENCE (STEEL POSTS)</b> <b>WF (2) - 10</b>					
FILE:	wf210.dgn	DN:	TxDOT	CK:	AM
© TxDOT	1996	CONT:	0923	SECT:	06
REVISIONS		JOB:	083	HIGHWAY:	CR 267
		DIST:	BROWN	COUNTY:	BROWN
				SHEET NO.:	40

AREA = 4.42 SQ. MI.  
 MEAN ANNUAL PRECIPITATION = 29 IN  
 SLOPE = 0.009 FT/FT  
 OMEGA (\*) = -0.106

OmegaEM Regression Coefficients									
Return Interval	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr	200-yr	250-yr	500-yr
AEP (Percent)	50%	20%	10%	4%	2%	1%	0.50%	0.40%	0.20%
Probability	P = 0.5	P = 0.2	P = 0.1	P = 0.04	P = 0.02	P = 0.01	P = 0.005	P = 0.004	P = 0.002
c =	1.398	1.308	1.203	1.14	1.105	1.071	1.034	1.021	0.988
d =	0.27	0.372	0.403	0.446	0.476	0.507	0.531	0.541	0.569
e =	0.776	0.885	0.918	0.945	0.961	0.969	0.975	0.977	0.976
a =	50.98	16.62	13.62	11.79	11.17	10.82	10.61	10.56	10.4
b =	-50.3	-15.32	-11.97	-9.819	-8.997	-8.448	-8.058	-7.943	-7.605
Lambda =	-0.0058	-0.0215	-0.0289	-0.0374	-0.0424	-0.0467	-0.0504	-0.0516	-0.0554

Estimated Peak Discharges, cfs									
Return Interval	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr	200-yr	250-yr	500-yr
Q <sub>r</sub> =	329	684	967	1414	1805	2280	2812	3013	3680



p:\tts-pw-bentley.com\tts-pw-01\Documents\0223-002\Cadd\Plan Sheets\Drainage\CR267\_DRN\_DA.dgn  
 7/25/2020 12:41

NO.	REVISION	BY	DATE

*E. Gaston*  
 7/25/2020  
 FIRM REGISTRATION NO. F-230

©2020 Texas Department of Transportation

### DRAINAGE AREA MAP


#### CR 267

#### AT LEWIS CREEK

SHEET 1 OF 1

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY		SHEET No.
TEXAS	BWD	BROWN		41





CROSS SECTION LAYOUT  
N. T. S.

HEC-RAS RIVER: LEWIS CREEK REACH: LEWIS CREEK													
Reach	River Sta	Profile	Plan	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Lewis Creek	1140	2-yr	EXIST	329	1347.24	1351.39		1351.63	0.003049	3.98	83.78	37.57	0.41
Lewis Creek	1140	2-yr	PROP V5	329	1347.24	1351.39		1351.63	0.003049	3.98	83.78	37.57	0.41
Lewis Creek	1140	100-yr	EXIST	2280	1347.24	1354.93		1355.13	0.002037	4.66	826.64	389.50	0.37
Lewis Creek	1140	100-yr	PROP V5	2280	1347.24	1354.89		1355.10	0.002135	4.75	810.80	385.56	0.38
Lewis Creek	1039	2-yr	EXIST	329	1346.63	1349.66	1349.66	1350.74	0.020855	8.33	39.50	18.24	1.00
Lewis Creek	1039	2-yr	PROP V5	329	1346.63	1349.66	1349.66	1350.74	0.020855	8.33	39.50	18.24	1.00
Lewis Creek	1039	100-yr	EXIST	2280	1346.63	1354.77	1353.22	1354.93	0.001677	3.99	876.73	510.87	0.33
Lewis Creek	1039	100-yr	PROP V5	2280	1346.63	1354.71	1353.25	1354.89	0.001819	4.12	846.36	504.01	0.35
Lewis Creek	1000			Culvert									
Lewis Creek	968	2-yr	EXIST	329	1345.81	1349.35	1348.05	1349.58	0.003185	3.82	86.22	33.48	0.42
Lewis Creek	968	2-yr	PROP V5	329	1345.81	1349.35	1348.05	1349.58	0.003185	3.82	86.22	33.48	0.42
Lewis Creek	968	100-yr	EXIST	2280	1345.81	1353.05	1352.21	1354.33	0.007968	9.13	262.87	326.55	0.73
Lewis Creek	968	100-yr	PROP V5	2280	1345.81	1353.05	1352.22	1354.33	0.008014	9.16	260.31	326.21	0.74
Lewis Creek	859	2-yr	EXIST	329	1345.69	1348.46		1348.93	0.009875	5.53	59.50	30.92	0.70
Lewis Creek	859	2-yr	PROP V5	329	1345.69	1348.46		1348.93	0.009875	5.53	59.50	30.92	0.70
Lewis Creek	859	100-yr	EXIST	2280	1345.69	1353.05		1353.41	0.002577	6.03	691.95	372.73	0.43
Lewis Creek	859	100-yr	PROP V5	2280	1345.69	1353.05		1353.41	0.002577	6.03	691.95	372.73	0.43
Lewis Creek	758	2-yr	EXIST	329	1342.89	1348.01	1346.17	1348.33	0.003505	4.53	72.60	20.33	0.42
Lewis Creek	758	2-yr	PROP V5	329	1342.89	1348.01	1346.17	1348.33	0.003505	4.53	72.60	20.33	0.42
Lewis Creek	758	100-yr	EXIST	2280	1342.89	1352.55	1352.09	1353.09	0.003502	7.58	612.66	367.47	0.48
Lewis Creek	758	100-yr	PROP V5	2280	1342.89	1352.55	1352.09	1353.09	0.003502	7.58	612.66	367.47	0.48

RIVER: LEWIS CREEK PROFILE: 2-YR CULV GROUP: CULVERT #1  
 REACH: LEWIS CREEK RS: 1000 PLAN: PROP. V5

PLAN: PROP.V5 LEWIS CREEK LEWIS CREEK RS: 1000 CULV GROUP: CULVERT #1			
Q CULV GROUP (CFS)	329	CULV FULL LEN (FT)	
# BARRELS	5	CULV VEL US (FT/S)	2.86
Q BARREL (CFS)	65.8	CULV VEL DS (FT/S)	2.83
E.G. US. (FT)	1349.65	CULV INV EL UP (FT)	1346.58
W.S. US. (FT)	1349.66	CULV INV EL DN (FT)	1346.55
E.G. DS (FT)	1349.58	CULV FRCTN LS (FT)	0.01
W.S. DS (FT)	1349.35	CULV EXIT LOSS (FT)	0
DELTA EG (FT)	0.07	CULV ENTR LOSS (FT)	0.06
DELTA WS (FT)	0.31	Q WEIR (CFS)	
E.G. IC (FT)	1348.57	WEIR STA LFT (FT)	
E.G. OC (FT)	1349.65	WEIR STA RGT (FT)	
CULVERT CONTROL	OUTLET	WEIR SUBMERG	
CULV WS INLET (FT)	1349.46	WEIR MAX DEPTH (FT)	
CULV WS OUTLET (FT)	1349.45	WEIR AVG DEPTH (FT)	
CULV NML DEPTH (FT)	1.81	WEIR FLOW AREA (SQ FT)	
CULV CRT DEPTH (FT)	1.28	MIN EL WEIR FLOW (FT)	1354.38

RIVER: LEWIS CREEK PROFILE: 100-YRCULV GROUP: CULVERT #1  
 REACH: LEWIS CREEK RS: 1000 PLAN: PROP. V5

PLAN: PROP.V5 LEWIS CREEK LEWIS CREEK RS: 1000 CULV GROUP: CULVERT #1			
Q CULV GROUP (CFS)	2198.6	CULV FULL LEN (FT)	
# BARRELS	5	CULV VEL US (FT/S)	8.12
Q BARREL (CFS)	439.72	CULV VEL DS (FT/S)	8.14
E.G. US. (FT)	1354.88	CULV INV EL UP (FT)	1346.58
W.S. US. (FT)	1354.71	CULV INV EL DN (FT)	1346.55
E.G. DS (FT)	1354.33	CULV FRCTN LS (FT)	0.04
W.S. DS (FT)	1353.05	CULV EXIT LOSS (FT)	0
DELTA EG (FT)	0.55	CULV ENTR LOSS (FT)	0.51
DELTA WS (FT)	1.66	Q WEIR (CFS)	81.4
E.G. IC (FT)	1354.09	WEIR STA LFT (FT)	685.15
E.G. OC (FT)	1354.88	WEIR STA RGT (FT)	870.92
CULVERT CONTROL	OUTLET	WEIR SUBMERG	0
CULV WS INLET (FT)	1353.35	WEIR MAX DEPTH (FT)	0.51
CULV WS OUTLET (FT)	1353.3	WEIR AVG DEPTH (FT)	0.29
CULV NML DEPTH (FT)	7.43	WEIR FLOW AREA (SQ FT)	53.34
CULV CRT DEPTH (FT)	4.55	MIN EL WEIR FLOW (FT)	1354.38

NOTES:

1. WATER SURFACE ELEVATION COMPUTED USING HEC-RAS VERSION 5.0.7.
2. THE TAILWATER WAS DETERMINED USING NORMAL DEPTH COMPUTATION WITH A SLOPE OF 0.0035 FT/FT.
3. THIS CROSSING IS LOCATED IN A FEMA ZONE "A" AS SHOWN ON MAP PANEL 48049C0400E EFFECTIVE AUGUST 28, 2018.
4. FLOODPLAIN ADMINISTRATOR COORDINATION ON JULY 10, 2020.
5. PROPOSED BCC 2 YEAR DISCHARGE: 329 CFS  
 INSIDE TOP OF CULVERT = 1354.58  
 FREEBOARD = 4.92 FT  
 PERCENT OF FLOW OVERTOPPING ROAD = 0.0%
6. PROPOSED BCC 100 YEAR DISCHARGE: 2280 CFS  
 INSIDE TOP OF CULVERT = 1354.58  
 FREEBOARD = 0.00 FT  
 PERCENT OF FLOW OVERTOPPING ROAD = 3.4%

p:\tts-pw-bentley.com\tts-pw-01\Documents\0223-002\Cadd\Plan Sheets\Drainage\CR267\_DRN\_HDS01.dgn  
 7/25/2020 12:19

NO.	REVISION	BY	DATE

*E. Gaston* 7/25/2020


FIRM REGISTRATION NO. F-230

©2020


### HYDRAULIC DATA CR 267 AT LEWIS CREEK

SHEET 1 OF 2


FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	42	



HEC-RAS PROFILE OUTPUT



HEC-RAS RATING CURVE



HEC-RAS CROSS SECTION OUTPUT

NOTES:

1. WATER SURFACE ELEVATION COMPUTED USING HEC-RAS VERSION 5.0.7.
2. THE TAILWATER WAS DETERMINED USING NORMAL DEPTH COMPUTATION WITH A SLOPE OF 0.0035 FT/FT.
3. THIS CROSSING IS LOCATED IN A FEMA ZONE "A" AS SHOWN ON MAP PANEL 48049C0400E EFFECTIVE AUGUST 28, 2018.
4. FLOODPLAIN ADMINISTRATOR COORDINATION ON JULY 10, 2020.
5. PROPOSED BCC 2 YEAR DISCHARGE: 329 CFS  
 INSIDE TOP OF CULVERT = 1354.58  
 FREEBOARD = 4.92 FT  
 PERCENT OF FLOW OVERTOPPING ROAD = 0.0%
6. PROPOSED BCC 100 YEAR DISCHARGE: 2280 CFS  
 INSIDE TOP OF CULVERT = 1354.58  
 FREEBOARD = 0.00 FT  
 PERCENT OF FLOW OVERTOPPING ROAD = 3.4%

NO.	REVISION	BY	DATE

*E. Gaston*  
7/25/2020  
FIRM REGISTRATION NO. F-230

**HYDRAULIC DATA  
 CR 267  
 AT LEWIS CREEK**



SHEET 2 OF 2

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	43	

pm:/tts-pw-bentley.com:tts-pw-01/Documents/0223-002-VA-3 - CR Brown Comanche Co/Cadd/Plan Sheets/Roadway/CR267\_CULV\_LAYOUT\_01.dgn  
 4/17/2021 1:38 JamesBrooks

ITEM	DESCRIPTION	UNIT	QUANTITY
400 6005	CEM STABIL BKFL	CY	171
402 6001	TRENCH EXCAVATION PROTECTION	LF	52
420 6007	CL C CONC (CULV)	CY	56
422 6001	REINF CONC SLAB	SF	1131
432 6001	RIPRAP (STONE PROTECTION) (12 IN)	CY	87
450 6019	RAIL (TY T631LS)	LF	157
466 6184	WINGWALL (PW - 1) (HW=9 FT)	EA	2


NO PRECAST ALLOWED



**PLAN**


EXISTING GAS LINE LOCATION SHOULD BE CONSIDERED APPROXIMATE. IT IS CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH UTILITY OWNER BEFORE CONSTRUCTION BEGINS.

EXISTING BRIDGE: 5 - 8' x 8' MBC WITH FLARED WINGS



**TYPICAL SECTION**

DESIGN SPEED: 40 MPH  
 AADT (2017): 231  
 AADT (2033): 300  
 FUNCTION CLASS: RURAL MINOR COLLECTOR  
 EXISTING NBI: 23-025-0-AA02-67-006  
 PROPOSED NBI: 23-025-0-AA02-67-008



**ELEVATION**

NO.	REVISION	BY	DATE

**JAMES BROOKS**  
 101002  
 LICENSED PROFESSIONAL ENGINEER  
 4/17/2021

**TEXAS TRANSPORTATION SOLUTIONS, INC.**  
 Form #TSS-1007

©2020 **Texas Department of Transportation**

**CULVERT LAYOUT**  
**CR 267 AT LEWIS CREEK**

FED. RD DIV. No.	CONTROL No.	SECTION No.	JOB No.	HIGHWAY No.
6	0923	06	083	CR 267
STATE	DISTRICT	COUNTY	SHEET No.	
TEXAS	BWD	BROWN	44	

SHEET 1 OF 1

DISCLAIMER:  
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information to any other format or for any errors or omissions resulting from its use.

DATE: 4/17/2021 1:40  
FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223.002.WA.3 - CR Brown

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert  No. Spans ~ Span X Height	Max Fill Height  (Ft)	Applicable Box Culvert Standard  (4)	Applicable Wingwall or End Treatment Standard	Skew Angle  (0°, 15°, 30° or 45°)	Side Slope or Channel Slope Ratio  (SL:1)	T Culvert Top Slab Thickness  (In)	U Culvert Wall Thickness  (In)	C Estimated Curb Height  (Ft)	Hw (1) Height of Wingwall  (Ft)	A Curb to End of Wingwall  (Ft)	B Offset of End of Wingwall  (Ft)	Lw Length of Longest Wingwall  (Ft)	Ltw Culvert Toewall Length  (Ft)	Atw Anchor Toewall Length  (Ft)	Riprap Apron  (CY)	Class "C" Conc (Curb)  (CY)	Class "C" Conc (Wingwall)  (CY)	Total Wingwall Area  (SF)
CR 267 AT LEWIS CREEK (Both)	5 ~ 8' X 8'	0'	MC-8-13	PW-1	0	2:1	8"	7"	0.0	8.667	N/A	N/A	17.333	43.500	N/A	0.0	0.0	49.0	600

NOTES:

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets;  
30° maximum for safety end treatment

SL:1 = Horizontal : 1 Vertical

- Side slope at culvert for flared or straight wingwalls.
- Channel slope for parallel wingwalls.
- Slope must be 3:1 or flatter for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)

B = Offset of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)


Atw = Length of anchor toewall (applicable to safety end treatment only)

Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt.  
Area for four wingwalls (two structure ends) if Both.

(1) Round the wall heights shown to the nearest foot for bidding purposes.

(2) Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class S concrete is required for the top slab of the culvert, also provide Class S concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.

(3) Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.




				<b>Bridge Division Standard</b>	
<b>BOX CULVERT SUPPLEMENT WINGS AND END TREATMENTS</b>					
<b>BCS</b>					
FILE: bcsstdel-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT	
©TxDOT February 2020	CONT: 0923	SECT: 06	JOB: 083	HIGHWAY: CR 267	
REVISIONS		DIST: BWD	COUNTY: BROWN	SHEET NO: 45	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:51  
 FILE: pw://tts-pw\_bent1 ey.com: t1s-pw-01/Document s/0223\_002/Cadd/Standar ds/ST-101-101-01.dwg



**TYPICAL SECTION**




**BOTTOM SLAB**      **TOP SLAB**  
**PART PLANS**



**SECTION THRU CURB**

TABLE OF BAR DIMENSIONS		
H	"X"	"Y"
3'-0"	3'-6 1/2"	5'-1"
4'-0"	4'-6 1/2"	5'-1"
5'-0"	5'-6 1/2"	5'-1"
6'-0"	6'-6 1/2"	5'-1"
7'-0"	7'-6 1/2"	5'-1"
8'-0"	8'-6 1/2"	5'-1"



- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR  
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.  
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

**CONSTRUCTION NOTES:**  
 Do not use permanent forms.  
 Chamfer the bottom edge of the top slab 3" at the entrance.  
 Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed, and Bars Y and Z may be reversed.

**MATERIAL NOTES:**  
 Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.  
 Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:  
 • culverts with overlay,  
 • culverts with 1-to-2 course surface treatment, or  
 • culverts with the top slab as the final riding surface.  
 Provide bar laps, where required, as follows:  
 • Uncoated or galvanized ~ #4 = 1'-8" Min  
 • Uncoated or galvanized ~ #5 = 2'-1" Min  
 • Uncoated or galvanized ~ #6 = 2'-6" Min

**GENERAL NOTES:**  
 Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.  
 See the Multiple Box Culverts Cast-In-Place Miscellaneous Detail (MC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.


Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING		SHEET 1 OF 2	
			<b>Bridge Division Standard</b>
<b>MULTIPLE BOX CULVERTS CAST-IN-PLACE</b> <b>8'-0" SPAN</b> <b>0' TO 13' FILL</b>			
<b>MC-8-13</b>			
FILE: mc813ste-20.dgn	DN: TBE	CK: BMP	DW: TxDOT
©TxDOT February 2020	CONT	SECT	JOB
REVISIONS	0923	06	083
DIST	COUNTY		SHEET NO.
BWD	BROWN		46




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:51  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223\_002/Cadd/Standard/sf-tts-pw-01/0223\_002/0223\_002.dwg




PLAN OF SKEWED ENDS ~ FROM 0° TO 15°


PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ OVER 30° TO 45°




PLAN OF SKEWED ENDS ~ OVER 15° TO 30°

- ① For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.  
 For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, Class C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension,  $N_{ba}$ , of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.  
 Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.
- ② When the spacing between Bars B or Bars E becomes less than half of the normal spacing, cut bars to avoid conflict.
- ③ The length of Bars B and Bars E will vary in the skewed end sections.
- ④  $[0.5 \times \text{overall width}] \times [\text{tangent of the skew angle}]$



PLAN OF SKEWED ENDS ~ OVER 30° TO 45°



LENGTHENING DETAIL

- ⑤ Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- ⑥ When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- ⑦ At the Contractor's option, for skews of 15° or less, place Bars B, C, D, and E parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B and Bars E shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets to accommodate the skew.
- ⑧ Extend Bars E as shown on the MC standard sheet for direct traffic culverts.

**CONSTRUCTION NOTES:**

Do not use permanent forms.  
 When required, lap Bars H 1'-8" for uncoated or galvanized bars.  
 Provide a minimum of 1 1/2" clear cover.

**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel, if required elsewhere in the plans.  
 Provide Class C concrete ( $f'c = 3,600$  psi) with these exceptions:  
 provide Class 5 concrete ( $f'c = 4,000$  psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.

**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications.  
 Refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for details of straight sections of culvert.  
 For skewed sections and angle sections, refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.  
 For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets by the cosine of the skew angle.

Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING



MULTIPLE BOX CULVERTS  
 CAST-IN-PLACE  
 MISCELLANEOUS DETAILS

MC-MD

FILE: mc-mdste-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
0923	06		083	CR 267
DIST		COUNTY		SHEET NO.
BWD		BROWN		48

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:51  
 FILE: pw://tts-pw\_bent1/ey.com/tts-pw-01/Documents/0223\_002/Coad/Standard.s/0223-002-ey.dwg

**TABLE OF DIMENSIONS AND REINFORCING STEEL**  
(Wings for one structure end)




Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings) ④		Estimated Quantities per ft of Toewall (1-toewall)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

**TABLE OF WINGWALL REINFORCING**  
(2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

**TABLE OF TOEWALL REINFORCING**

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



**WING DIMENSION FORMULAS:**

(All values are in feet.)


$$\begin{aligned}
 Hw &= H + T + C \\
 Lw &= (Hw)(SL) \div \cosine(\theta) \text{ for Type PW-1} \\
 &= (Hw - 1')(SL) \div \cosine(\theta) \text{ for Type PW-2 and } Hw \ge 4' \\
 &= (Hw - 0.5')(SL) \div \cosine(\theta) \text{ for Type PW-2 and } Hw < 4'
 \end{aligned}$$

For cast-in-place culverts:  
 $Ltw = [(N)(S) + (N + 1)(U)] \div \cosine(\theta)$

For precast culverts:  
 $Ltw = [(N)(2U + S) + (N - 1)(0.5')] \div \cosine(\theta)$   
 Total Wingwall Area (two wings ~ SF)  
 $= (2)(Hw)(Lw)$  for Type PW-1  
 $= (2)(Hw)(Lw) - 6 \text{ SF}$  for Type PW-2 and  $Hw \ge 4'$   
 $= (2)(Hw)(Lw) - 1.5 \text{ SF}$  for Type PW-2 and  $Hw < 4'$

$Hw$  = Height of wingwall  
 $Lw$  = Length of wingwall  
 $Ltw$  = Culvert toewall length  
 $N$  = Number of culvert spans  
 $SL:1$  = Channel slope ratio, (horizontal: 1 vertical, usual value is 2:1)  
 $\theta$  = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.



- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"  
For 30° skew ~ 2"  
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.

**DESIGNER NOTES:**

Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall. Type PW-2 can only be used for applications without a railing mounted to the wingwall.






**MATERIAL NOTES:**

Provide Class C concrete (f'c=3,600 psi).  
 Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.


**GENERAL NOTES:**

Designed in accordance with AASHTO LRFD Bridge Design Specifications.  
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.  
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information.  
 Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.



**DETAILS FOR NON-SKEWED BOX CULVERTS**




**DETAILS FOR SKEWED BOX CULVERTS**  
(Showing 30° skew.)

		<b>Bridge Division Standard</b>	
<b>CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2</b>			
<b>PW</b>			
FILE: pwstde01-20.dgn	DN: GAF	CK: CAT	DW: TxDOT
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY
REVISIONS	0923 06	083	CR 267
	DIST	COUNTY	SHEET NO.
	BWD	BROWN	49


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:51  
FILE: pw://tts-pw\_bent1 ey.com: t1s--pw-01\_Documents/0223\_002/Coad/Standard.s/ST-101-11-2013.dwg




### SECTION - TYPE 1

Used for curbs 1 1/2" and Less  
(Showing "C" = 1 1/2")




### SECTION - TYPE 2

Used for curbs over 1 1/2" to 3"  
(Showing "C" = 3")




### SECTION - TYPE 3

Used for curbs over 3" to 1'-0"  
(Showing "C" = 1'-0")




### SECTION - TYPE 4

Used for curbs over 1'-0" to 5'-0"  
(Showing "C" = 2'-0")



### TYPICAL SECTION THRU PARALLEL WINGWALL

Use with all curb heights shown




### OPTIONAL ADHESIVE ANCHORAGE

Optional adhesive anchor may replace cast-in-place anchor bolts for Type 1 thru Type 4 and on Typical Section Thru Parallel Wingwalls. Reinforcement for optional adhesive anchorage matches details shown for Type 1 thru Type 4 and on Typical Section Thru Parallel Wingwalls.


- 1 "T" is equal to the culvert top slab thickness. For precast boxes with slabs less than 8" thick, see SCP-MD standard for additional details.
- 2 Adjust normal culvert slab bars as necessary to clear obstructions.
- 3 Omit normal culvert curb Bars K and H.
- 4 Place Bars L as shown. Tilt hook as necessary to maintain cover.
- 5 4 formed holes for anchor bolts at each rail post. See rail standard for information not shown.
- 6 Place normal culvert curb Bars H (#4) as shown. Adjust as necessary to clear obstructions.
- 7 Omit normal culvert curb Bars K. Place Bars S as shown. Tilt Bars S as necessary to maintain cover.
- 8 Place normal culvert curb Bars K spaced at 12" Max as shown. Tilt Bars K as necessary to maintain cover. Refer to box culvert details sheets for Bars K details.
- 9 Additional Bars H (#4) as required to maintain 12" Max spa.
- 10 At TYPE 4 mountings, replace normal culvert curb Bars K with one Bar U and two Bars V as shown spaced at 12" Max. Adjust length of Bars V as necessary to maintain clear cover.
- 11 Adjust parallel wing Bars G to positions shown.
- 12 Optional Bars L are to be used only for precast box culverts with 3'-0" closure pour.
- 13 If "T" plus "C" is greater than 8", provide reinforcement per TYPE 1 mounting and anchor bolts per TYPE 2 mounting.
- 14 Quantities shown are for Contractor's information only. Quantities are per linear foot of curb length. The values for each section type in table can be interpolated for intermediate values of curb height, "C". Quantity includes Bars K (when applicable).
- 15 See "Cast-In-Place & Formed Hole Anchor Bolt Options".

1/4" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ASTM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod.




### CAST-IN-PLACE & FORMED HOLE ANCHOR BOLT OPTIONS


Applies to T631LS and T631 traffic rails.




BARS V (#5) Spaced at 12" Max




BARS S (#4) Spaced at 12" Max



BARS L (#5) Spaced at 12" Max



OPTIONAL BARS L (#5) Spaced at 12" Max



BARS U (#4) Spaced at 12" Max

TABLE OF ESTIMATED CURB QUANTITIES

Curb Height "C"	Section Type	Conc (CY/LF)	Reinf Steel (Lb/LF)
1 1/2"	1	0.005	4.7
3"	2	0.009	8.4
6"	3	0.019	8.9
1'-0"	3	0.037	8.9
1'-6"	4	0.056	14.3
2'-0"	4	0.074	15.4
2'-6"	4	0.093	17.7
3'-0"	4	0.111	18.8
3'-6"	4	0.130	21.2
4'-0"	4	0.148	22.2
4'-6"	4	0.167	24.6
5'-0"	4	0.185	25.6

CONSTRUCTION NOTES: For vehicle safety, finished grade must be flush with top of curb. Adjust reinforcing as necessary to provide 1 1/4" cover. At the Contractor's option, anchor bolts may be an adhesive anchor system. Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.

MATERIAL NOTES: Provide concrete for curb of the same Class and strength as the box culvert top slab. Galvanize all steel components of steel rail system. Provide Grade 60 reinforcing steel. Galvanize all reinforcing steel if required elsewhere. Anchor bolts for base plate must be 5/8" Dia ASTM F3125 Gr A325 or A449 bolts (or ASTM A193 Gr B7 or F1554 Gr 105 threaded rods with one tack welded heavy hex nut each) with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed fully threaded rod into slab and/or abutment wingwall using a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4 3/4". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 8 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing".

GENERAL NOTES: Designed in accordance with AASHTO LRFD Bridge Design Specifications. See T631LS or T631 rail standard for approved speed restrictions, notes and details not shown. The curb is considered as part of the box culvert for payment. These details are for use with curbs that are 5'-0" tall and less only. Curb heights that are less than or greater than those shown will require special design.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.

The use of the T631LS rail is restricted to speeds of 45 mph or less.




## BOX CULVERT MOUNTING DETAILS FOR TYPE T631LS & T631 RAILS (CURBS 5' TALL AND LESS ONLY) T631-CM

FILE:	DN:	CK:	OW:	CK:
r1std040-20.dgn	TxDOT	TxDOT	JTR	AES
0923	06	083	CR	267
BWD	BROWN			50


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

DATE: 7/24/2020 2:51  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223.002/Cadd/Standards/STANDARD 63 PLST.dgn




**ROADWAY ELEVATION OF RAIL**  
 Showing without overlay.

- ① 9" Min, 5'-9" Max
- ② Maintain 6'-3" Rail Post spacing wherever possible for use with nominal 25'-0" or 12'-6" W-Beam sections. Symmetry of post spacing on both sides and along the structure is not necessary.
- ③ Increase 2" for structures with overlay.
- ④ Tighten the first hex nut by hand until the top and bottom edges of the W-Beam engage the Backer Plate (Backer Plate should be snug against the post). Then tighten hex nut one revolution with wrench and secure with the second hex nut.
- ⑤ PL 1/8 x 1 3/4 x 1 3/4 with 3/8 Dia Hole centered in PL (ASTM A36). Square Guardrail Washer (FWR01).
- ⑥ The post nearest to a slab joint or end of structure may be shifted up to 9" in order to satisfy the minimum offset dimension. Drill a new 3/4" Dia hole in the centerline of W-beam for shifted post. Paint hole with two coats of zinc-rich paint conforming to the Item "Galvanizing". All other posts must remain on the typical spacing.
- ⑦ 3/8" Dia formed holes for 3/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ATSM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod. See "Cast-In-Place & Formed Hole Anchor Bolt Options".
- ⑧ 3/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ATSM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod. See "Cast-In-Place & Formed Hole Anchor Bolt Options".



**RAIL DETAILS ON BRIDGE SLAB**  
 Showing without overlay.



**RAIL SECTION ON ABUTMENT WINGWALL**  
 Showing without overlay.


The use of this railing is restricted to speeds of 45 mph or less.

SHEET 1 OF 2


		<b>Bridge Division Standard</b>		
				<h2>TRAFFIC RAIL</h2> <h3>TYPE T631LS</h3>
FILE: r1std037-19.dgn	DN: TxDOT	CK: AES	DW: JTR	CK: AES
©TxDOT September 2019	CONT: 0923	SECT: 06	JOB: 083	HIGHWAY: CR 267
REVISIONS	DIST: BWD	COUNTY: BROWN	SHEET NO. 51	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:51  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223\_002/Cadd/Standard.srf-tts-pw\_bent1ey.dgn




**W-BEAM ELEVATION**




**W-BEAM SPLICE ELEVATION**



**POST ELEVATION**




**SECTION A-A**




**WASHER PLATE DETAIL**

5/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ATSM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod.



**CAST-IN-PLACE & FORMED HOLE ANCHOR BOLT OPTIONS** ⑨⑩

- ⑨ See "Rail Details On Bridge Slab" and/or "Rail Section On Abutment Wingwall".
- ⑩ See "Material Notes" for anchor bolt information.
- ⑪ Backer PL 1/8" x 8 x 1'-3" (ASTM A1011 CS or SS Gr 33, or A1008 CS or SS Gr 33 (11 Gage acceptable)).
- ⑫ Used for structures with overlay.
- ⑬ Used for structures without overlay.



**ELEVATION**

**BACKER PLATE**

**MBGF AND END TREATMENT NOTES:**

This traffic railing must be anchored by metal beam guard fence (MBGF) and/or guard fence end treatments. Determine MBGF length of need in accordance with the Roadway Design Manual, unless otherwise specified. The minimum MBGF length of need required for anchoring the railing is: SGT; or DAT plus 12.5' of MBGF, as applicable. Provide CRT posts as shown in "Roadway Elevation of Rail."

**CONSTRUCTION NOTES:**

Face of rail post must be plumb unless otherwise approved by the Engineer. Post must be perpendicular to adjacent roadway grade. Use epoxy mortar under post base plates if gaps larger than 1/16" exist.  
 Fully anchored guardrail must be attached to each end of rail. A metal beam guard fence transition is not used with this rail. At the Contractor's option anchor bolts may be an adhesive anchor system. See "Material Notes".  
 Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.  
 It is recommended to show a Rail Layout with rail posts and W-beam splices. Fabricator must submit erection drawings to the Engineer for approval.  
 Round or chamfer exposed edges of rail post and backer plate to approximately 1/16" by grinding.  
 Shop drawings are not required for this rail.

**MATERIAL NOTES:**

Galvanize all steel components.  
 Anchor bolts for base plate must be 5/8" Dia ASTM F3125 Gr A325 or A449 bolts (or ASTM A193 Gr B7 or F1554 Gr 105 threaded rods with one tack welded heavy hex nut each) with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements.  
 Optional adhesive anchorage system must be 5/8" Dia ASTM A193 Gr B7 or F1554 Gr 105 fully threaded rods with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed fully threaded rod into slab and/or abutment wingwall using a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4 3/4". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 8 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing."  
 W-beam must meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified in the plans. The Contractor may furnish rail elements of 25'-0", or 12'-6" (Nominal) lengths. W-Beam must have slotted holes at 3'-1 1/2".  
 Some part numbers from the "Task Force 13" Guide to Standardized Highway Barrier Hardware have been furnished for quick reference.

**GENERAL NOTES:**

This railing has been successfully evaluated by full-scale crash test to meet MASH TL-2 criteria. This railing can be used for speeds of 45 mph and less.  
 This rail is designed to deflect approximately 2' to 2'-6" as it contains and redirects the errant vehicle. This rail may not be installed on top of or behind curbs that project above finished grade, on bridges with expansion joints providing more than 5" movement, on retaining walls, or on grade separations and interchanges.  
 Repairs to impact-damaged post and base plate unit are not permitted. Replace all impact-damaged posts with a new post and base plate unit.  
 Average weight of railing with no overlay: 13 plf total.


SHEET 2 OF 2

		<b>Bridge Division Standard</b>	
<h1>TRAFFIC RAIL</h1>			
<h2>TYPE T631LS</h2>			
FILE: r1std037-19.dgn	DN: TxDOT	CK: AES	DW: JTR
REV: 0923	SECT: 06	JOB: 083	CR: 267
DIST: BWD	COUNTY: BROWN	SHEET NO. 52	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:52  
 FILE: pw://tts-pw\_bent1ey.com/tts-pw-01/Documents/0223.002/Cadd/Standard.srr




**PLAN**



**ELEVATION**




**SECTION A-A AT CAP**




**SECTION B-B**

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



**CAP OPTION A**



**CAP OPTION B**

**DETAIL C**

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.


**GENERAL NOTES:**  
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.  
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2


		<b>Bridge Division Standard</b>	
<h1>STONE RIPRAP</h1>			
<h2>SRR</h2>			
FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH
©TxDOT April 2019	CONT	SECT	JOB
REVISIONS	0923	06	083
	DIST	COUNTY	SHEET NO.
	BWD	BROWN	53

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from any format to any format or for incorrect results or damages resulting from its use.


DATE: 7/24/2020 2:52  
 FILE: \\tts-pw\_bent1\ey.com\tts-pw-01\Documents\0223\_002\Cadd\Standards\SPR\SPR.dwg




**FIGURE 1 ~ TYPE R STONE RIPRAP**  
dry or grouted




**FIGURE 2 ~ TYPE F STONE RIPRAP**  
dry or mortared



**FIGURE 3 ~ TYPE F STONE RIPRAP**  
grouted




**FIGURE 4 ~ COMMON STONE RIPRAP**  
dry or grouted



**FIGURE 5 ~ PROTECTION STONE RIPRAP**

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "Y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.  
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



**PROTECTION STONE RIPRAP TOE OPTIONS**


**STONE RIPRAP**

**SRR**

FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	54	


DISCLAIMER:  
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for errors or omissions in the drawings or for damages resulting from its use.

DATE: 4/17/2021 1:33  
FILE: \\tts-pw-bent1\ey.com\tts-pw-01\Documents\0223.002.WA.3 - CR Brown\0223.002.WA.3.dwg



**OPTION 1 ~ PLAN WITH WINGWALLS**

Cast-in-place retaining walls similar.




**OPTION 1 ~ PLAN WITH MSE RETAINING WALLS**


- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
  - a) If flowable backfill is to be placed over MSE backfill then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
  - b) Place flowable fill in lifts not exceeding 2 feet in height, place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).

**GENERAL NOTES:**

See the Bridge Layout for selected Option. Option 2 is intended for new construction requiring high plasticity embankment fill with a plasticity index (PI) greater than 30 or pavement built in poor native soil. Poor soils are defined as high plasticity clays or expansive clays. Option 1 is intended for construction only requiring PI controlled embankment fill or excavation in competent soils/rocks in order to construct the abutment.  
Provide Cement Stabilized Backfill (CSB) meeting the requirements of Item 400, "Excavation and Backfill for Structures", to the limits shown at bridge abutments.  
If required elsewhere in the plans, provide Flowable Backfill meeting the requirements of Item 401, "Flowable Backfill", to the limits shown at bridge abutments.  
Details are drawn showing left forward skew. See Bridge Layout for actual skew direction.  
These details do not apply when Concrete Block retaining walls are used in lieu of wingwalls.



**WITHOUT APPROACH SLAB**



**SECTION A-A**


**WITH APPROACH SLAB**  
(Showing BAS-C, BAS-A similar.)

SHEET 1 OF 2

		<b>Bridge Division Standard</b>	
<b>CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT</b>			
<b>CSAB</b>			
FILE: csabste1-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT April 2019	CONT	SECT	JOB
0923	06	083	CR 267
02-20: Added Option 2.	DIST	COUNTY	SHEET NO.
BWD	BROWN		54A


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions resulting from its use.

DATE: 4/17/2021 1:34  
 FILE: pw://tts-pw\_bent1ev.com/tts-pw-01/Documents/0223.002.WA.3 - CR Brown of Abutment Backfill.dwg




**OPTION 2 ~ PLAN WITH WINGWALLS**

Cast-in-place retaining walls similar.




**OPTION 2 ~ PLAN WITH MSE RETAINING WALLS**

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
  - a). If flowable backfill is to be placed over MSE backfill then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
  - b). Place flowable fill in lifts not exceeding 2 feet in height, place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).




**WITHOUT APPROACH SLAB**



**SECTION B-B**

**WITH APPROACH SLAB**  
 (Showing BAS-C, BAS-A similar.)

SHEET 2 OF 2



**CEMENT STABILIZED  
 ABUTMENT BACKFILL  
 BRIDGE ABUTMENT**

**CSAB**

FILE: csabste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
02-20: Added Option 2.	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	54B	

UPDATED 6/22/2017  
 Prepared by \*\*\*\*\*  
 DATE: 7/24/2020 2:52  
 FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223.002/Cadd/Plan Sheets/ESCP/TXDOT\_EPIC\_CR267.dgn

During the planning phase of project development the following environmental permits, issues, and commitments have been developed during coordination with resource agencies, local governmental entities, and the general public. Any change orders and/or deviations from the final design must be reported to the Engineer prior to the commencement of construction activities, as additional environmental clearances may be required.

**I. Clean Water Act, Sec. 402 Texas Pollutant Discharge Elimination System**

(Addresses CGP and MS4 Storm Water requirements for the project.)  
 (In the event that the Contractor implements a PSL on or within one mile of the project, a Site Notice and/or a NOI will apply.)

No Action Required  Required Action

Action No. 1 Commitment No. 1  
 The project disturbs less than one acre of surface area. The contractor is responsible for the PSL as defined in the Standard Specifications for Construction and Maintenance of Highways, Street, and Bridges (2014 Edition, Section 7.7.6, Page 42). The total disturbed acreage is the combined acreage to be disturbed on the project and the contractor's PSL.

The EPIC must be updated if the disturbed area increases to one or more acres during the course of construction (refer to following sections). It may become necessary to post a site notice and/or NOI for the project and/or PSL. MS4 operators that receives discharge from the project: -N/A-

**II. Clean Water Act, Section 401 and 404 Compliance**

(Addresses Nationwide Permits, Individual Permits, and Wetlands.)  
 (Filling, dredging, or excavating in any water bodies, rivers, creeks, streams, wetlands, or wet area is prohibited unless specified in the USACE permit and approved by the Engineer.)  
 (When temporary fills implemented, only stated TxDOT standards will be used unless written authorization for an alternative is obtained from the Engineer. No equipment is allowed in any stream channel below the Ordinary High Water Mark except on temporary stream crossings or drill pads.)

No Action Required  404 Permit and 401 Certification Required

Permit	Required Action	Waters of the US	App. Plan Sheet(s)
NWP #14	Adher to permit and associated conditions	Lewis Creek	SW3P Layout

Best Management Practices for applicable 401 General Conditions:

General Condition 12 - Categories I and II BMPs required

Category I (Erosion Control)

- Temporary Vegetation
- Mulch
- Interceptor Swale
- Erosion Control Compost
- Compost Filter Berms and Socks
- Blankets, Matting
- Sod
- Diversion Dike
- Mulch Filter Berms and Socks
- Compost Blankets

Category II (Sedimentation Control)

- Sand Bag Berm
- Silt Fence
- Triangular Filter Dike
- Stone Outlet Sediment Traps
- Erosion Control Compost
- Compost Filter Berms and Socks
- Rock Berm
- Hay Bale Dike
- Brush Berms
- Sediment Basins
- Mulch Filter Berms and Socks

General Condition 25 - Category III BMPs required

Category III (Post-Construction TSS Control)

- Retention/Irrigation
- Extended Detention Basin
- Vegetative Filter Strips
- Grassy Swales
- Erosion Control Compost
- Compost Filter Berms and Socks
- Constructed Wetlands
- Wet Basins
- Vegetation-Lined Ditches
- Sand Filter Systems
- Mulch filter Berms and Socks
- Sedimentation Chambers

**III. Cultural Resources**

(Addresses any special circumstances associated with cultural resources, such as archeological or historic sites.)  
 (Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.)

No Action Required  Required Action

Action No.	Station (Rt/Lt)	Commitment
1.	---	---

**IV. Vegetation Resources**

(Addresses any special circumstances associated with vegetation, such as large trees to be avoided, or mitigation that will occur as part of the project.)

No Action Required  Required Action

Action No.	Station (Rt/Lt)	Commitment
1.	All	Avoid non-mow locations for stockpiles and equipment parking/storage.
2.	Project Limits	Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

**V. Federal Listed, Proposed, Threatened, Endangered Species, Critical Habitat, State Listed Species, Candidate Species, and Migratory Bird Treaty Act (MBTA)**

(Addresses any special habitat that may need to be avoided, lists any threatened or endangered species where habitat was observed and might be impacted within the project area, and lists any precautions such as nesting seasons for migratory birds.)

No Action Required  Required Action

Species Potentially within Project Area & Description	Habitat Description
---	---------------------

The Contractor is to be aware that if bats or active bird nests are identified during construction; they are to stop work and contact The Brownwood District Environmental Coordinator, Andrew Chisholm, 325) 643-0442. When choosing locations for storing equipment or placing other Project Specific Locations (PSLs), burrows should be avoided as these may contain species of concern. Any species entering the work area shall be left alone and allowed to leave the construction area unharmed.

The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. Migration patterns would not be affected by the proposed project. The contractor will remove all old migratory bird nests from any structure where work would be done from September 1 through the end of February. In addition, the contractor will be prepared to prevent migratory birds from building nests between March 1 and August 31, per the Environmental Permits, Issues, and Commitments (EPIC) plans. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young shall be avoided.

**VI. Hazardous Material or Contamination Issues**

(Addresses any previously identified high risk sites associated with hazardous materials that may be encountered during construction.)

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contractor will follow all applicable storage and management requirements for liquid oil products, liquid petroleum products, and other chemical liquids as per 40 CFR 112 (a.k.a. SPCC) and/or TCEQ Construction General Permit for storm water management.

Contact the Engineer if any of the following are detected:  
 Dead or distressed vegetation (not identified as normal)  
 Trash piles, drums, canisters, barrels, etc.  
 Undesirable smells/odors  
 Underground storage tanks  
 Evidence of leaching or seepage of substances  
 Any other evidence indicating possible hazardous materials or contamination discovered on-site

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structure not including box culverts)?

Yes  No

If "No", then no further action is required.  
 If "Yes", then TxDOT is responsible for completing an asbestos assessment/inspection. Are the results of the asbestos inspection positive (is asbestos present)?

Yes  No

If "Yes", then TxDOT must retain a Texas Department of State Health Services (DSHS) licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 10 working days prior to scheduled abatement and/or demolition.

If "No", then TxDOT is still required to notify DSHS 10 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Bridges on this project may contain Lead-Containing Paint (LCP) or other items that contain lead. The location of (LCP) is identified in the General Notes. Item 6.10.1.2 in the 2014 TxDOT Standard Specifications shall be utilized for this project.

**VII. Other Environmental Issues**

(Addresses any other environmental issues that may not have been covered in other sections.)

No Action Required  Required Action

Action No.	Station (Rt/Lt)	Commitment
1.	---	---

**LIST OF ABBREVIATIONS**

- BMP: Best Management Practice
- CGP: Construction General Permit
- DSHS: Texas Department of State Health Services
- FEMA: Federal Emergency Management Agency
- FHWA: Federal Highway Administration
- MOA: Memorandum of Agreement
- MOU: Memorandum of Understanding
- MS4: Municipal Separate Stormwater Sewer System
- MBTA: Migratory Bird Treaty Act
- NOI: Notice of Intent
- NOT: Notice of Termination
- NWP: Nationwide Permit
- SPCC: Spill Prevention Control and Countermeasure
- SW3P: Storm Water Pollution Prevention Plan
- PCN: Pre-Construction Notification
- PSL: Project Specific Location
- TCEQ: Texas Commission on Environmental Quality
- TPDES: Texas Pollutant Discharge Elimination System
- TPWD: Texas Parks and Wildlife Department
- TxDOT: Texas Department of Transportation
- T&E: Threatened and Endangered Species
- USACE: U.S. Army Corp of Engineers
- USFWS: U.S. Fish and Wildlife Service

**ENVIRONMENTAL PERMITS, ISSUES, AND COMMITMENTS (EPIC) LESS THAN 1 ACRE**

BROWNWOOD DISTRICT			
CONT	SECT	JOB	HIGHWAY
0923	06	083	CR 267
DIST	COUNTY		SHEET NO.
BWD	BROWN		55

**SITE DESCRIPTION**

**PROJECT LIMITS:**

CSJ 0923-06-083 CR 267 at Lewis Creek  
 Latitude = 31.661185  
 Longitude = -98.927501

**LOCATION MAPS:**

Refer to title sheet for project location map.

**PROJECT DESCRIPTION:**

CSJ 0923-06-083  
 For the construction of: Replacement of bridge consisting of: Replace bridge and approaches

**MAJOR SOIL DISTURBING ACTIVITIES:**

The major soil disturbing activities for this project will consist of preparation of R.O.W., placement and removal of temporary bypass, removing existing structure, excavation work, embankment work for the construction of the bridge and roadway, and placement and removal of erosion controls.

TOTAL PROJECT AREA: 0.34 AC

TOTAL AREA TO BE DISTURBED: 0.28 AC

**EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:**

CSJ 0923-06-083  
 Surrounding land is used as pasture range and 90% of the R.O.W. vegetative cover is predominantly comprised of various native grasses and wild flowers.

**NAME OF RECEIVING WATERS:**

CSJ 0923-06-083  
 Runoff from project flows into Stream Segment 1431 of the Colorado River Basin.

**EROSION AND SEDIMENT CONTROLS**

**OTHER EROSION AND SEDIMENT CONTROLS:**

**MAINTENANCE:** All erosion controls will be maintained in good working order. If a repair is necessary, it will be made at the earliest possible date, but no later than seven (7) calendar days after the ground has dried sufficiently to prevent further damage from equipment. The areas around creeks and drainage ways shall have priority over other areas on the project site.

**INSPECTION:** An inspection will be performed by a TxDOT inspector at least once every seven (7) calendar days. An inspection and maintenance report will be made per each inspection. Stormwater controls will be modified as directed by the Engineer based on these reports.

**WASTE MATERIALS:** Any waste materials generated during construction will be disposed of in accordance with existing federal, state, and local laws.

**HAZARDOUS WASTE (INCLUDING SPILL REPORTING):** At a minimum, any products in the following categories are considered to be hazardous: Fuels, Lubricating products, Asphalt products, or Concrete curing compounds and any additives. In the event of a spill which may be hazardous, clean-up will be done in accordance with federal, state, and local regulations.

**SANITARY WASTE:** Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor.

**OFF SITE VEHICLE TRACKING AND DUST CONTROL:**  
 DUST CONTROL (OFF SITE) AS NEEDED - PER ENGINEER  
 HAUL ROADS DAMPENED FOR DUST CONTROL  
 LOADED HAUL TRUCKS TO BE COVERED WITH TARPULIN  
 EXCESS DIRT ON ROAD REMOVED DAILY  
 STABILIZED CONSTRUCTION ENTRANCE

**REMARKS:** Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, water body or stream bed. Construction staging area and vehicle maintenance area shall be constructed by the contractor in a manner to minimize the runoff pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, false work, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.

For off R.O.W. facilities the contractor shall comply with TCEQ requirements.

The contractor is responsible for ensuring that all subcontractors are aware of and comply with all components of the SW3P per Item 506.

Furnish one SW3P permit posting sign and sign support as detailed on the SW3P Sheet. Install this sign in a location selected by the Engineer. The sign and support should be removed upon completion of the project and is the property of the Contractor. The purchase of the sign and support, installation, relocation(s) if determined necessary by the Engineer and removal at project end shall be subsidiary to Item 506.

Sedimentation Basins - Since the area disturbed is less than 10 acres per drainage area; a sedimentation basin is not required.

**Best Management Practices:**

- |   |  |  |
|---|--|--|
| <b>Erosion</b>  | <b>Sedimentation</b>                                   | <b>Post-Construction TSS</b>                           |
| <input checked="" type="checkbox"/> Temporary Vegetation          | <input checked="" type="checkbox"/> Silt Fence         | <input type="checkbox"/> Vegetative Filter Strips      |
| <input type="checkbox"/> Blankets/Matting                         | <input checked="" type="checkbox"/> Rock Berm          | <input type="checkbox"/> Retention/Irrigation Systems  |
| <input type="checkbox"/> Mulch                                    | <input type="checkbox"/> Triangular Filter Dike        | <input type="checkbox"/> Extended Detention Basin      |
| <input type="checkbox"/> Sodding                                  | <input type="checkbox"/> Sand Bag Berm                 | <input type="checkbox"/> Constructed Wetlands          |
| <input type="checkbox"/> Interceptor Swale                        | <input type="checkbox"/> Straw Bale Dike               | <input type="checkbox"/> Wet Basin                     |
| <input type="checkbox"/> Diversion Dike                           | <input type="checkbox"/> Brush Berms                   | <input type="checkbox"/> Erosion Control Compost       |
| <input type="checkbox"/> Erosion Control Compost                  | <input type="checkbox"/> Erosion Control Compost       | <input type="checkbox"/> Mulch Filter Berm and Socks   |
| <input type="checkbox"/> Mulch Filter Berm and Socks              | <input type="checkbox"/> Mulch Filter Berm and Socks   | <input type="checkbox"/> Compost Filter Berm and Socks |
| <input checked="" type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Vegetation Lined Ditches      |
|   | <input type="checkbox"/> Stone Outlet Sediment Traps   | <input type="checkbox"/> Sand Filter Systems           |
|   | <input type="checkbox"/> Sediment Basins               |  |



**NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:**

- The order of activities will be as follows:
1. Preserve existing vegetative cover as much as possible.
  2. Install temporary sediment control fencing and other items as shown on plans prior to any soil disturbing activities. Install temporary bypass.
  3. Perform bridge work, roadway work, and perform any necessary excavation, embankment and grading, temporary seeding, and signage. Remove temporary bypass.
  4. Place permanent seeding as shown in the plans and as directed by the Engineer.

**STORM WATER MANAGEMENT:**

Storm water will be carried by side road ditches which will empty into the various natural runoff channels.

**STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING**






**CR 267 BROWNWOOD DIST. STORM WATER POLLUTION PREVENTION PLAN**

CONT	SECT	JOB	HIGHWAY
0923	06	083	CR 267
DIST	COUNTY	SHEET NO.	
BWD	BROWN	56	

DATE: 4/17/2021 1:41 FILE: pw://tts-pw\_bent ley.com/tts-pw-01/Documents/0223.002\_WA\_3 - CR Brown Comanche Co/Cadd/Plan Sheets/ESCP/092306083/01.dwg



P:\tts-pw-bentley.com\tts-pw-01\Documents\0223-002 WA 3 - CR Brown Comanche Co\Cadd\Plan Sheets\ESCP\CR267\_SW3P\_LAYOUT-01.dgn  
 SCRIPT: CR267\_Index.pen  
 JamesBrooks  
 3/23/2021 4:12




**LEGEND**

- SEDIMENT CONTROL FENCE
- ROCK FILTER DAM (TYPE 2)
- TEMP EROSION CONTROL LOG
- DIRECTION OF FLOW

**NOTE:**  
 SOIL RETENTION BLANKETS SHALL BE PLACED ALONG V-DITCHES. SEE CROSS SECTIONS FOR DITCH LOCATIONS.

NO.	REVISION	BY	DATE



**SW3P LAYOUT  
 CR 267 AT  
 LEWIS CREEK**


SHEET 1 OF 1

ITEM	DESCRIPTION	UNIT	QUANTITY
164-6001	BROADCAST SEED (PERM) (RURAL) (SANDY)	SY	1805
164-6009	BROADCAST SEED (TEMP) (WARM)	SY	903
164-6011	BROADCAST SEED (TEMP) (COOL)	SY	903
168-6001	VEGETATIVE WATERING	MG	42
SUBSIDIARY	FERTILIZER	TON	0.07
169-6003	SOIL RETENTION BLANKETS (CL 1) (TY C)	SY	1000
506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	80
506-6011	ROCK FILTER DAMS (REMOVE)	LF	80
506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	1060
506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	1060
506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	110
506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	110

EXISTING GAS LINE LOCATION SHOULD BE CONSIDERED APPROXIMATE. IT IS CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH UTILITY OWNER BEFORE CONSTRUCTION BEGINS.



DATE: 7/25/2020 4:01  
 FILE: pw://tts-pw\_bentley.com/tts-pw-01/Documents/0223.002/Cadd/Plan Sheets/ESCP/TXDOT\_Temp Crossing Detail.dgn



Note: Temporary crossing will not be paid for directly but will be considered subsidiary to pertinent items.


CR 267  
 TEMP CROSSING  
 DETAIL  
 0923-06-083




CONT	SECT	JOB	HIGHWAY
0923	06	083	CR 267
DIST	COUNTY		SHEET NO.
BWD	BROWN		58

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

7/20/2020  
 708422020  
 pw\_bentley.com: t+s-pw-01/Documents/0223\_002/Cadd/Standards/ESCP/EC(1)-16.dgn



TEMPORARY SEDIMENT CONTROL FENCE



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

**SEDIMENT CONTROL FENCE USAGE GUIDELINES**

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT<sup>2</sup>. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


**LEGEND**

Sediment Control Fence



**GENERAL NOTES**

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING




**TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16**

FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	59	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020  
 FILE: pw://tts-pw.bentley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/ESCP/EC(2)-16.dgn




**FILTER DAM AT TOE OF SLOPE**

— (RFD1) —




**FILTER DAM AT SEDIMENT TRAP**

— (RFD1) — OR — (RFD2) —




**FILTER DAM AT CHANNEL SECTIONS**


— (RFD1) — OR — (RFD2) — OR — (RFD3) —




**PLAN VIEW**




**"V" SHAPE PLAN VIEW**




**PROFILE**



**SECTION C-C**




**SECTION B-B**



**TYPE 4 (SACK GABIONS)**

— (RFD4) —



**SECTION A-A**

**ROCK FILTER DAM USAGE GUIDELINES**

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT<sup>2</sup> of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

**GENERAL NOTES**

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


**PLAN SHEET LEGEND**

- Type 1 Rock Filter Dam — (RFD1) —
- Type 2 Rock Filter Dam — (RFD2) —
- Type 3 Rock Filter Dam — (RFD3) —
- Type 4 Rock Filter Dam — (RFD4) —


		<b>Design Division Standard</b>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>ROCK FILTER DAMS</b> <b>EC (2) - 16</b>			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0923 06	083	CR 267
	DIST	COUNTY	SHEET NO.
	BWD	BROWN	60

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020  
 FILE: pw://tts-pw.bentley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/ESCP/EC(9)-16.dgn



PLAN VIEW




SECTION A-A


EROSION CONTROL LOG DAM

CL-D

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
  - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
  - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
  - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
  - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
  - CL-DI EROSION CONTROL LOG AT DROP INLET
  - CL-CI EROSION CONTROL LOG AT CURB INLET
  - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



REBAR STAKE DETAIL




PLAN VIEW



SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

**SEDIMENT BASIN & TRAP USAGE GUIDELINES**

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

**Log Traps:** The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

**GENERAL NOTES:**


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<b>Design Division Standard</b>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DN: TxDOT	CK: KM	DN: LS/PT
© TxDOT: JULY 2016	CONT: 0923	SECT: 06	JOB: 083
REVISIONS			CR 267
	DIST: BWD	COUNTY: BROWN	SHEET NO. 61


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020  
 FILE: pw://tts-pw.bentley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/ESCP/EC(9)-16.dgn



EROSION CONTROL LOGS ON SLOPES  
 STAKE AND TRENCHING ANCHORING


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

\* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:  
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;  
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART





EROSION CONTROL LOGS ON SLOPES  
 STAKE AND LASHING ANCHORING

CL-SSL




STAKE AND TRENCHING ANCHORING DETAIL

CL-SST



STAKE AND LASHING ANCHORING DETAIL


CL-SSL



SHEET 2 OF 3

LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

TRENCH DEPTH TABLE



STAKE NOTCH DETAIL


Texas Department of Transportation  
 Design Division Standard

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES  
 EROSION CONTROL LOG  
 EC(9) - 16

FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	06	083	CR 267
	DIST	COUNTY	SHEET NO.	
	BWD	BROWN	62	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/24/2020  
 FILE: pw://tts-pw.bentley.com/tts-pw-01/Documents/0223.002/Cadd/Standards/ESCP/EC(9)-16.dgn




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:  
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

				<b>Design Division Standard</b>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>					
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
	0923	06	083	CR 267	
	DIST	COUNTY	SHEET NO.		
	BWD	BROWN	63		