

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

PROJECT NO. C 2855-1-23

RM 2871

TARRANT COUNTY

LIMITS:
FROM IH 20 WB TO ALEDO RD.

TOTAL PROJECT LENGTH = 4,830.00 FT = 0.915. MI.

FOR THE CONSTRUCTION OVERLAY WORK CONSISTING OF
PLANING, HOT MIX ASPHALT AND PAVEMENT MARKINGS


FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	C 2855-1-23		1
STATE	STATE DIST. NO.	COUNTY	
TEXAS	2	TARRANT	
CONT.	SECT.	JOB	HIGHWAY NO.
2855	01	023	RM 2871

AVERAGE DAILY TRAFFIC
RM 2871 (2019) = 13,030

POSTED SPEED: 60 MPH
DESIGN SPEED: 60 MPH

LETTING DATE: _____
CONTRACTOR: _____

WORK BEGAN: _____
WORK COMPLETED: _____
WORK ACCEPTED: _____
CHANGE ORDERS: _____



BEGIN PROJECT C 2855-1-23
STA. 218+35.00
RM: 272+0.83

END PROJECT C 2855-1-23
STA. 266+65.00
RM: 273+0.177



DocuSigned by:
Jeremy Arreguin
C8E51DD82649440
ENGINEER NAME, PE

1/25/2021
DATE

EQUATIONS : NONE
EXCEPTIONS: NONE
RAILROAD : UNION PACIFIC
DOT #: 839-210L
RR MP: 3, MP 257.13

SUBMITTED FOR LETTING: 1/7/2021
DATE
DocuSigned by:
Paula...
7879B0B92E50... DIRECTOR, TP&D

SUBMITTED FOR LETTING: 1/5/2021
DATE
DocuSigned by:
David...
2E562E37025E4A8... AREA ENGINEER

APPROVED FOR LETTING: 1/7/2021
DATE
DocuSigned by:
Carl Johnson
2FE36139F06... DISTRICT ENGINEER

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,
NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS,
SHALL GOVERN ON THIS PROJECT: SPECIAL LABOR PROVISIONS FOR STATE PROJECTS (000 --- 008)

GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3-7 TYPICAL SECTION
- 8, 8A-8E GENERAL NOTES
- 9 ESTIMATE & QUANTITY
- 10 QUANTITY SUMMARY

TRAFFIC CONTROL

- 11 SEQUENCE OF WORK
- 12-15 TCP NEAR ALEDO RD.
- 16 PORTABLE CHANGEABLE MESSAGE SIGN LAYOUT

TRAFFIC CONTROL AND WORK ZONE STANDARDS

- * 17-28 BC (1)-14 THRU BC (12)-14
- * 29-32 TCP (2-1)-18 THRU TCP (2-3)-18, TCP (2-8)-18
- * 33-35 TCP (3-1)-13, TCP (3-3)-14, TCP (3-4)-13
- * 36 TCP (7-1)-13
- * 37 WZ (STPM)-13
- * 38 WZ (BRK)-13
- * 39 WZ (RS)-16
- * 40 WZ (UL)-13
- * 41 WZ (RCD)-13

ROADWAY DETAILS

- 42-45 ROADWAY LAYOUT
- 46 LONGITUDINAL PAVEMENT JOINT DETAIL
- 47 PAVEMENT TRANSITION DETAILS
- 48 HMAC DRIVEWAY DETAIL
- 49 WEDGE MILL AT CONCRETE DRIVEWAYS

ROADWAY STANDARDS

- * 50 TE (HMAC)-11

PAVEMENT MARKING DETAILS

- 51-54 STRIPING LAYOUT

PAVEMENT MARKING STANDARDS


- * 55-57 PM (1)-20 THRU PM (3)-20

ENVIRONMENTAL ISSUES

- * 58-62 EC (1)-16, EC (3)-16, EC (9)-16
- 63 EPIC
- 64-65 SW3P

RAILROAD DETAILS

- 66 RAILROAD SCOPE OF WORK
- 67-68 RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS



* DENOTES STANDARD SHEETS
THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE
HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

DocuSigned by:
Jeremy Arreguin, P. E. 1/25/2021
C8E51DD82649440... DATE

1/25/2021 4:52:33 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\INDEX OF SHEETS.dgn

INDEX OF SHEETS





SHEET 1 OF 1



CONT	SECT	JOB	HIGHWAY
2855	01	023	RM 2871
DIST	COUNTY	SHEET NO.	
FTW	TARRANT	2	

CK: _____
 DW: _____
 CS: _____
 DN: _____

DATE: 1/25/2021
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TYPICAL SECTION.dgn




GENERAL NOTES

STATIONS REPRESENT APPROXIMATE LIMITS OF FEATURES SHOWN. ACTUAL LIMITS MAY VARY SLIGHTLY

PROTECT EXISTING STRUCTURES, LIGHTING UTILITIES, SIGNS, DRAINAGE FEATURES WITHIN THE ROW. DAMAGES TO THESE FEATURES AS A RESULT OF THE CONTRACTORS OPERATIONS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.

** REFER TO PAVEMENT TRANSITION DETAILS NEAR BUTT JOINTS




DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 1 OF 5

TYPICAL SECTION			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	3	

CKE:
DNF:
CCK:
DNE:

DATE: 1/25/2021
FILE: I:\STICAO Files\STICAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TYPICAL SECTION.dgn





GENERAL NOTES

STATIONS REPRESENT APPROXIMATE LIMITS OF FEATURES SHOWN. ACTUAL LIMITS MAY VARY SLIGHTLY

PROTECT EXISTING STRUCTURES, LIGHTING UTILITIES, SIGNS, DRAINAGE FEATURES WITHIN THE ROW. DAMAGES TO THESE FEATURES AS A RESULT OF THE CONTRACTORS OPERATIONS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.


*TACK COAT RATE ADJUSTED BY MANUFACTURER RECOMMENDATIONS TO BE SET AT THE TIME OF APPLICATION



DocuSigned by:
Jeremy Arreguin
C8E51DD82649440...

1/25/2021

SCALE: NONE
SHEET 2 OF 5



PROPOSED SURFACE MIX HMAC OVERLAY
3" SP-C SAC-A PG70-28


HOT APPLIED TRACKLESS TACK 0.10 GAL/SY
(PAID UNDER ITEM 3077)

PROPOSED SUBGRADE WIDENING SECTION
8" D-GR HMA TY-B PG 64-22 - TWO 4" LIFTS

HOT APPLIED TRACKLESS TACK 0.20 GAL/SY*
(SUBSIDIARY TO ITEM 340)

EXISTING SUBGRADE
SUBGRADE WIDENING (DENS CONT)

TRAFFIC DIRECTION



PROPOSED SURFACE MIX HMAC OVERLAY
3" SP-C SAC-A PG70-28

HOT APPLIED TRACKLESS TACK 0.10 GAL/SY
(PAID UNDER ITEM 3077)

BASE COURSE HMAC MIX
4" D-GR HMA TY-B PG 64-22

HOT APPLIED TRACKLESS TACK 0.10 GAL/SY*
(SUBSIDIARY TO ITEM 340)






REMAINING PAVEMENT

TRAFFIC DIRECTION

TYPICAL SECTION			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	4	

CKE:
 DW:
 CKE:
 DW:

DATE: 1/25/2021
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TYPICAL SECTION.dgn



TRAFFIC DIRECTION


GENERAL NOTES

STATIONS REPRESENT APPROXIMATE LIMITS OF FEATURES SHOWN. ACTUAL LIMITS MAY VARY SLIGHTLY

PROTECT EXISTING STRUCTURES, LIGHTING UTILITIES, SIGNS, DRAINAGE FEATURES WITHIN THE ROW. DAMAGES TO THESE FEATURES AS A RESULT OF THE CONTRACTORS OPERATIONS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.

*TACK COAT RATE ADJUSTED BY MANUFACTURER RECOMMENDATIONS TO BE SET AT THE TIME OF APPLICATION

©2021 by Texas Department of Transportation; all rights reserved



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...

1/25/2021

SCALE: NONE
 SHEET 3 OF 5





TYPICAL SECTION

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	5	

Ck: _____
 Dwf: _____
 Cks: _____
 Dns: _____

DATE: 1/25/2021
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\05-Roadway\TYPICAL SECTION.dgn



LEGEND



- PROPOSED SURFACE MIX HMA OVERLAY
3" SP-C SAC-A PG70-28
- HOT APPLIED TRACKLESS TACK 0.10 GAL/SY
(PAID UNDER ITEM 3077)
- BASE COURSE HMA MIX
4" D-GR HMA TY-B PG 64-22
- HOT APPLIED TRACKLESS TACK 0.10 GAL/SY*
(SUBSIDIARY TO ITEM 340)
- REMAINING PAVEMENT

TRAFFIC DIRECTION →


GENERAL NOTES

STATIONS REPRESENT APPROXIMATE LIMITS OF FEATURES SHOWN. ACTUAL LIMITS MAY VARY SLIGHTLY

PROTECT EXISTING STRUCTURES, LIGHTING UTILITIES, SIGNS, DRAINAGE FEATURES WITHIN THE ROW. DAMAGES TO THESE FEATURES AS A RESULT OF THE CONTRACTORS OPERATIONS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.

*TACK COAT RATE ADJUSTED BY MANUFACTURER RECOMMENDATIONS TO BE SET AT THE TIME OF APPLICATION

©2021 by Texas Department of Transportation; all rights reserved



DocuSigned by:
Jeremy Arreguin
C8E51DD82649440...

1/25/2021


SCALE: NONE
SHEET 4 OF 5



TYPICAL SECTION

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	6	

DATE: 1/25/2021
 FILE: I:\STICAO Files\STICAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TYPICAL SECTION.dgn





GENERAL NOTES

STATIONS REPRESENT APPROXIMATE LIMITS OF FEATURES SHOWN. ACTUAL LIMITS MAY VARY SLIGHTLY

PROTECT EXISTING STRUCTURES, LIGHTING UTILITIES, SIGNS, DRAINAGE FEATURES WITHIN THE ROW. DAMAGES TO THESE FEATURES AS A RESULT OF THE CONTRACTORS OPERATIONS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.



*TACK COAT RATE ADJUSTED BY MANUFACTURER RECOMMENDATIONS TO BE SET AT THE TIME OF APPLICATION



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...

1/25/2021

SCALE: NONE
 SHEET 5 OF 5



TYPICAL SECTION			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	7	

Project Number: C 2855-1-23

County: TARRANT

Highway: RM 2871

Control: 2855-01-023

Specification Data

Basis of Estimate

Item	Description	Rate	Unit
340	Hot Mix (TY B)	115 lb./sq. yd.-in.)	ton
**	Tack Coat - Hot Applied Trackless Tack	0.10-0.20 gal./sq. yd.	gal.
3077	SP Mix (SP-C) (SAC-A)	115 lb./sq. yd.-in.)	ton
3077	Tack Coat - Hot Applied Trackless Tack	0.10 gal./sq. yd.	gal
**	Non-Pay, for Contractor's Information Only.		

Special Notes

Electronic files containing answered pre-letting questions and other project related design information will be placed in the following FTP site periodically.

Check this site for new information. Notices of new postings will not be sent out by the Engineer.

The data located in these files is for non-construction purposes only and can be found at

TxDOT's public FTP site at <https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>.

Access is read-only.

All files in the FTP site are subject to the License Agreement shown on the FTP site.

To obtain a copy of the project plans free of charge, submit a request from the following site: <http://www.txdot.gov/business/letting-bids/plans-online.html>

Contractor questions on this project are to be addressed to the following individual(s):

- Area Engineer's Email: David.Neeley@txdot.gov
- Assistant Area Engineer's Email: Russell.Poer@txdot.gov
- Design Manager's Email: Ahmed.Gaily@txdot.gov
- Design Manager's Email Jeremy.Arreguin@txdot.gov
- Design Manager's Email Heather.Collie@txdot.gov

Project Number: C 2855-1-23

County: TARRANT

Highway: RM 2871

Control: 2855-01-023

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: <https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Single lane closures, except as otherwise shown in the plans, will be restricted to off-peak hours as defined in the following table:

Peak Hours		Off-Peak Hours	
6 to 9 AM Monday through Friday	3 to 7 PM Monday through Friday	9 AM to 3 PM and 7 PM to 6 AM Monday through Friday	All day Saturday and Sunday

Work that requires closure of multiple travel lanes in the same direction, except as otherwise shown in the plans, are restricted to night hours between 9 PM and 6 AM.

Existing storm sewers and utilities are shown from the best available information. Verify the location of all underground facilities prior to starting work.

For dimensions of right-of-way not shown on the plans, see right-of-way map on file at the TxDOT District Office.

Modifications to Lane Closure / Work Restrictions:

Submit a request in writing for approval by the Engineer a minimum of 10 days in advance of implementing a change to lane closure restrictions.

When deemed necessary, the Engineer will lengthen, shorten, or otherwise modify lane closure restrictions as traffic conditions warrant.

When deemed necessary, the Engineer will modify the list of major events when new events develop, existing events are rescheduled, or when warranted.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Special Events/ Special Situations will be handled on a case-by-case basis. No work restricting lane closures is allowed from 3 PM a day before to 9 AM the day after the Special Event or Special Situation.

Prevention of Migratory Bird Nesting

It is anticipated that migratory birds, a protected group of species, may try to nest on bridges, culverts, vegetation, or gravel substrate, at any time of the year. The preferred nesting season for migratory birds is from February 15 through October 1. When practicable, schedule construction operations outside of the preferred nesting season. Otherwise, avoid nests containing migratory birds and perform no work in the nesting areas until the young birds have fledged.

Mail box manipulation made necessary because of construction will be in accordance with Item 560 "Mailbox Assemblies," except that this work will not be paid for directly but will subsidiary to the pertinent bid items.

Provide all-weather surface for temporary ingress and egress to adjacent property, as directed. Materials, labor, equipment and incidentals necessary to provide temporary ingress and egress will not be paid for directly, but will be subsidiary to the various bid items.

Where necessary, the governing slopes indicated herein may be varied from the limits shown, to the extent approved.

On superelevated curves the shoulders will have the same cross-slope as the pavement, unless otherwise indicated.

On superelevated curves where the grade line is in a sag or on a flat grade, overlay the shoulders to the extent necessary to prevent trapping of water on the high side.

All driveway openings will be determined by the Engineer and will conform with Texas Department of Transportation "Regulations for Access Driveways to State Highways" adopted September 1953, and revised June 2004.

Remove the grass from the crown of shoulders or pavement edges by blading or other approved methods. Payment for this work will not be made directly, but will be subsidiary to the various items of the contract.

Provide temporary drain openings at all low points or other drainage structures, as required, at the Contractor's expense.

Remove any obstructions to existing drainage due to the contractor's operations, as required, at the Contractor's expense.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Item 4 – Scope of Work

Reimbursement for project overhead will not be considered until project completion has extended beyond the original Contract Time.

Item 7. Legal Relations and Responsibilities

This contract requires work to be done on railroad property. Cooperate with the railroads and comply with all of their requirements including obtaining any required training before performing work on railroad property.

Submit to the Engineer an original railroad liability insurance policy.

Do not initiate activities in a project specific location (PSL) associated with a U.S. Army Corps of Engineers (USACE) permit area that has not been previously evaluated by the USACE as part of the permit review of this project. Such activities include, but are not limited to haul roads, equipment staging areas, borrow and disposal sites. "Associated" as defined here means materials are delivered to or from the PSL. The permit area includes all waters of the U.S. or associated wetlands affected by activities associated with this project. Special restrictions may be required for such work. The contractor will be responsible for all consultations with the USACE regarding activities, including project specific locations (PSLs) that have not been previously evaluated by the USACE. Provide the Department with a copy of all consultations or approvals from the USACE prior to initiating activities.

The Contractor may proceed with activities in PSLs that do not affect a USACE permit area if a self-determination has been made that the PSL is non-jurisdictional or proper USACE clearances have been obtained in jurisdictional areas or have been previously evaluated by the USACE as part of the permit review of this project. The contractor is solely responsible for documenting any determinations that their activities do not affect a USACE permit area. Maintain copies of these determinations for review by the Department or any regulatory agency.

Document and coordinate with the USACE, if required, prior to any excavation hauled from or embankment hauled into a USACE permit area by either (1) or (2) below.

- (1) **Restricted Use of Materials for Previously Evaluated Permit Areas.** Document both the project specific location (PSL) and its authorization. Maintain copies for review by the Department or any regulatory agency. When an area within the project limits has been evaluated by the USACE as part of the permit process for this project:
 - a. Suitable excavation of required material in the areas shown on the plans and cross sections as specified in Item 110 is used for permanent or temporary fill (Item 132, Embankment) within a USACE permit area;
 - b. Suitable embankment (Item 132) from within the USACE permit area is used as fill within a USACE evaluated area; and,

Project Number: C 2855-1-23

County: TARRANT

Highway: RM 2871

Control: 2855-01-023

- c. Unsuitable excavation or excess excavation ["Waste"] (Item 110) that is disposed of at a location approved by the Engineer within a USACE evaluated area.

(2) Contractor Materials from Areas Other than Previously Evaluated Areas.

Provide the Department with a copy of all USACE coordination or approvals prior to initiating any activities for an area within the project limits that has not been evaluated by the USACE or for any off right of way locations used for the following, but not limited to haul roads, equipment staging areas, borrow and disposal sites:

- a. Item 132, Embankment, used for temporary or permanent fill within a USACE permit area; and,
- b. Unsuitable excavation or excess excavation ["Waste"] (Item 110, Excavation) that is disposed of outside a USACE evaluated area.

The total area disturbed for this project is 12 acres. The disturbed area in this project, all project locations in the Contract, and the Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the right of way. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the right of way to the Engineer and to the local government that operates a separate storm sewer system.

The following Holiday/Event lane closure restriction requirements apply to this project: No work that restricts or interferes with traffic shall be allowed between 3 PM on the day preceding a Holiday or Event and 9 AM on the day after the Holiday or Event.

Holiday Lane Closure Restrictions	
New Year's Eve and New Year's Day (December 31 through January 1)	3 PM December 30 through 9 AM January 2
Easter Holiday Weekend (Friday through Sunday)	3PM Thursday through 9 AM Monday
Memorial Day Weekend (Friday through Monday)	3 PM Thursday through 9 AM Tuesday
Independence Day (July 3 through July 5)	3 PM July 2 through 9 AM July 6
Labor Day Weekend (Friday through Monday)	3 PM Thursday through 9 AM Tuesday
Thanksgiving Holiday (Wednesday through Sunday)	3 PM Tuesday through 9 AM Monday

Project Number: C 2855-1-23

County: TARRANT

Highway: RM 2871

Control: 2855-01-023

Christmas Holiday (December 23 through December 26)	3 PM December 22 through 9 AM December 27
--	---

Plan work schedules around the appropriate dates above to ensure productive work is performed without lane closures.

Event Lane Closure Restrictions			
3 PM the day before Event to 9 AM the day after the Event			
NASCAR Races at Texas Motor Speedway (generally 3 events):	NASCAR Nationwide and Sprint Cup Series (Held in late March/early April)	NASCAR Nationwide and Sprint Cup Series (Held in Late October/early November)	Indy Series Racing and NASCAR Truck Series (Held in June)
Within one mile radius of major retail traffic generators i.e. malls (Thanksgiving Day through January 2)			
Fort Worth Stock Show and Rodeo			
Arlington Entertainment District			
Grapevine Festivals			
May Fest			
Weatherford Peach Festival			

Item 8. Prosecution and Progress

Working days will be computed and charged in accordance with Standard Workweek.

Item 100. Preparing Right of Way

Measurement for this item will be along the centerline of the project with the limits of measurements as shown on the plans.

Removal of minor vegetation, such as high grass, weeds or debris in works areas within the designated right of way in order complete necessary bid items will be considered subsidiary to this item and not paid separately.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Items 110, 112, and 132. Excavation, Subgrade Widening, and Embankment

Sulfate-laden subgrade material that is to be treated with either lime or cement, including material up to one foot outside the proposed treatment limits, is susceptible to sulfate heave. It has been determined that an excessive concentration of sulfate in the soils (>3,000 PPM by dry weight of the soil) exists for given areas of excavation and/or proposed treated subgrade within the project limits. The areas of moderate to high concentrations are as follows:

Moderate sulfate levels are those defined from 3,001 PPM to 7,000 PPM. Treat these soils with lime at the full 150 lb./cu. yd. rate or cement at the full 125 lb./cu. yd. rate. Do not split the rates to ensure complete reaction and mitigation of sulfate heaves. Allow the mixture to mellow for 7 days to provide for complete reaction.

High sulfate levels are not allowed within the treatment and surrounding areas as defined above.

Test soils for soluble sulfates in accordance with Test Method Tex-145 and Tex-146-E.

Treat moderate sulfate or excavate high sulfate areas identified above and other subgrade areas that may be identified during construction as having moderate to high sulfate concentrations to a depth of one foot below and laterally to one foot outside the proposed treatment limits. Treatment of the moderate level material will be paid for under Item 260, "Lime Treatment (Road Mixed)" or Item 275, "Cement Treatment (Road Mixed)." Removal of the high level material will be measured and paid for in accordance with Item 110, "Excavation" and replacement with suitable material will be measured and paid for in accordance with Item 132, "Embankment."

Any excavated sulfate-laden material will be acceptable for use in fill areas. Do not place within previously specified section boundaries of subgrade to be treated with either lime or cement.

Off-Site Borrow Sources. In addition to meeting pertinent specification requirements, test off-site borrow sources for sulfate content. Test soils for soluble sulfates in accordance with Test Method Tex-145 and Tex-146-E and provide documentation that supports compliance with previously stated requirements. The Engineer will perform additional testing for sulfates of this material upon delivery to the project. Only material that is placed within one foot vertically or laterally of subgrade treatment will require testing for sulfates. Remove and replace failing material (sulfate concentrations >7,000 PPM by dry weight).

Item 301. Asphalt Antistripping Agent

Furnish a liquid antistripping agent unless otherwise directed.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Item 340. Dense-Graded Hot-Mix Asphalt (Small Quantity) (Base Course Mix)

RAP aggregate must meet the requirements of Table 1.

Provide aggregate with a Surface Aggregate Classification (SAC) value of B

Provide a PG 64-22 asphalt for the base course.

Grade Substitution per Table 5 is not allowed.

Furnish a trackless tack. The Engineer will set the rate at time of application.

Warm Mix Asphalt (WMA) is not permitted in any mix type on this project.

RAP and RAS are not permitted in any surface and levelup mixes on this project.

Substitute binders are not allowed on this project.

Use only the Superpave Gyrotory Compactor (SGC) to design the mixture.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Include the approved mix design number on each delivery ticket.

Use a Material Transfer Device (MTD) unless otherwise directed.

Shoulders, crossovers, and other areas listed on the Plan sheets or as directed are not subject to in-place air void determination for this project.

Temporary detours are subject to in-place air void determination for this project.

Item 502. Barricades, Signs, and Traffic Handling

The contractor force account 'safety contingency' that has been established for this project is intended to be utilized for work zone enhancements to improve the effectiveness of the traffic control plan that could typically not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's responsible person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Permanent signs may be installed when construction in an area is complete and they will not conflict with the traffic control plan for the remainder of the job.

Existing signs are to remain as long as they do not interfere with construction and they do not conflict with the traffic control plan.

Any sign not detailed in the plans but called for in the layout will be as shown in the current "Standard Highway Sign Designs for Texas".

When traffic is obstructed, arrange warning devices in accordance with the latest edition of the "Texas Manual on Uniform Traffic Control Devices".

Cover or remove any work zone signs when work or condition referenced is not occurring.

Do not place barricades, signs, or any other traffic control devices where they interfere with sight distance at driveways or side streets. Provide access to all driveways during all phases of construction unless otherwise noted in the plans or as directed.

Item 506. Temporary Erosion, Sedimentation, and Environmental Controls

Remove accumulated sediment or replace SW3P controls when the capacity has been reduced by 50% or when the depth of sediment at the control structure exceeds one foot.

Items 530 And 531. Intersections, Driveways and Turnouts, and Sidewalks

The furnishing and installation of the sand cushion in proposed sidewalks, sidewalk ramps, and driveways will not be paid for directly but will be subsidiary to this bid item.

Item 585. Ride Quality for Pavement Surfaces

Use Surface Test Type B to evaluate ride quality of travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

Item 666. Reflectorized Pavement Markings with Retroreflective Requirements

Collection of retroreflectivity readings using a mobile retroreflectometer is the preferred method. If retroreflectivity readings are collected using a portable or handheld unit, then measurement is defined as a collective average of at least 20 readings taken along a 200-foot test section. A minimum of three measurements will be required per mile of roadway. Measurements collected on a centerline stripe will be averaged separately for stripe in each direction of travel. A TxDOT inspector must witness the calibration and collection of all retro-reflectivity data.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Item 3077. Superpave Mixtures (SURFACE MIX)

RAP aggregate must meet the requirements of Table 1.

Provide aggregate with a Surface Aggregate Classification (SAC) value of A for the travel lanes and shoulders.

No blending, of the material retained on the No. 4 sieve, to meet SAC A will be allowed for surface mixes.

Natural (field) sands are not allowed.

Provide a PG 70-28 asphalt for the surface course and levelup course, if applicable.

Furnish a trackless tack. The Engineer will set the rate at time of application.

Warm Mix Asphalt (WMA) is not permitted in any mix type on this project.

RAP and RAS are not permitted in any surface and levelup mixes on this project.

Grade substitution per Table 5 is not allowed.

Provide a mix design with the gradation curve below the restricted zone.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Include the approved mix design number on each delivery ticket.

Use a Material Transfer Device (MTD) unless otherwise directed.

Stop production after Lot 1. Review all test data and confirm any changes with the Engineer. Do not start production and placement on subsequent Lots until approved by the Engineer.

Shoulders, crossovers, and other areas listed on the Plan sheets or as directed are not subject to in-place air void determination for this project.

Temporary detours are subject to in-place air void determination for this project.

Project Number: C 2855-1-23

County: TARRANT

Control: 2855-01-023

Highway: RM 2871

Item 6001. Portable Changeable Message Signs

Provide all portable changeable message signs and arrow panels with a photoelectric device to allow for automatic dimming of operations to approximately 50% of their normal brightness when ambient light drops to approximately five footcandles, and then increase back again for daytime operations.

2 electronic portable changeable message sign unit(s) will be required. Individual or collective use of signs will be required by the Engineer when deemed necessary to supplement the traffic control plan.

Each sign must have programmed in its permanent memory the following 15 messages:

1. Exit Closed Ahead
2. Use Other Routes
3. Right Lane
4. Left Lane
5. Closed Ahead
6. Two Lane
7. Detour Ahead
8. Thru Traffic
9. Prepare To Stop
10. Merging Traffic
11. Expect 15 Minute Delay
12. Max Speed ** MPH
13. Merge Right
14. Merge Left
15. No Exit Next ** Miles

Item 6185. Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

Two total shadow vehicles with TMA will be required for this type of work. Determine if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.



CONTROLLING PROJECT ID 2855-01-023

DISTRICT Fort Worth
HIGHWAY RM 2871

COUNTY Tarrant

QUANTITY SHEET

CONTROL SECTION JOB				2855-01-023		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061341			
COUNTY				Tarrant			
HIGHWAY				RM 2871			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6002	PREPARING ROW	STA	49.000		49.000	
	112-6002	SUBGRADE WIDENING (DENS CONT)	STA	4.000		4.000	
	134-6002	BACKFILL (TY B)	STA	49.000		49.000	
	340-6011	D-GR HMA(SQ) TY-B PG64-22	TON	1,977.000		1,977.000	
	354-6003	PLAN & TEXT ASPH CONC PAV(0" TO 3")	SY	11,636.000		11,636.000	
	354-6010	PLAN & TEXT ASPH CONC PAV(0" TO 6")	SY	7,949.000		7,949.000	
	500-6001	MOBILIZATION	LS	100.00%		100.00%	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	3.000		3.000	
	506-6020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	120.000		120.000	
	506-6024	CONSTRUCTION EXITS (REMOVE)	SY	120.000		120.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	200.000		200.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	200.000		200.000	
	506-6042	BIODEG EROSN CONT LOGS (IN STL) (18")	LF	200.000		200.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	200.000		200.000	
	530-6005	DRIVEWAYS (ACP)	SY	551.000		551.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	50.000		50.000	
	662-6110	WK ZN PAV MRK SHT TERM (TAB)TY Y	EA	300.000		300.000	
	666-6030	REFL PAV MRK TY I (W)8"(DOT)(100MIL)	LF	45.000		45.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	450.000		450.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF	24.000		24.000	
	666-6054	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA	4.000		4.000	
	666-6078	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA	4.000		4.000	
	666-6093	REFL PAV MRK TY I (W)(RR XING)(100MIL)	EA	1.000		1.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	9,440.000		9,440.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	11,744.000		11,744.000	
	672-6007	REFL PAV MRKR TY I-C	EA	32.000		32.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	244.000		244.000	
	3077-6027	SP MIXESSP-CSAC-A PG70-28	TON	3,434.000		3,434.000	
	3077-6075	TACK COAT	GAL	1,991.000		1,991.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	190.000		190.000	
	6185-6002	TMA (STATIONARY)	DAY	26.000		26.000	
18		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	

C&G
 D&E
 C&G
 D&E

SUMMARY OF ROADWAY ITEMS								
ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.
0100 6002	0112 6002	0134 6002	0340 6011	0354 6003	0354 6010	0530 6005	3077 6027	3077 6075
PREPARING ROW	SUBGRADE WIDENING (DENS CONT)	BACKFILL (TY B)	D-GR HMA (SQ) TY-B PG64-22	PLAN & TEXT ASPH CONC PAV (0" TO 3")	PLAN & TEXT ASPH CONC PAV (0" TO 6")	DRIVEWAYS (ACP)	SP MIXES SP-C SAC-A PG70-28	TACK COAT
STA	STA	STA	TON	SY	SY	SY		
49.0	4.0	49.0	1,977.0	11,636.0	7,949.0	551.0	3,434.0	1,991.0

SUMMARY OF STRIPING ITEMS											
ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.
0662 6109	0662 6110	0666 6030	0666 6036	0666 6048	0666 6054	0666 6078	0666 6093	0666 6303	0666 6315	0672 6007	0672 6009
WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (WORD) (100MIL)	REFL PAV MRK TY I (W) (RR XING) (100MIL)	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A
EA	EA	LF	LF	LF	EA	EA	EA	LF	LF	EA	EA
50	300	45	450	24	4.0	4.0	1.0	9,440.0	11,744.0	32.0	244.0

SUMMARY OF EROSION CONTROL ITEMS					
ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.
0506 6020	0506 6024	0506 6038	0506 6039	0506 6042	0506 6043
CONSTRUCT ION EXITS (INSTALL) (TY 1)	CONSTRUCT ION EXITS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)	BIODEG EROSN CONT LOGS (INSTL) (18")	BIODEG EROSN CONT LOGS (REMOVE)
SY	SY	LF	LF	LF	LF
120.0	120.0	200.0	200.0	200.0	200.0

SUMMARY OF TRAFFIC CONTROL ITEMS		
ITEM NO.	ITEM NO.	ITEM NO.
0502 6001	6001 6001	6185 6002
BARRICADES, SIGNS AND TRAFFIC HANDLING	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)
MO	DAY	DAY
3.0	190.0	26.0

SCALE: NONE

SHEET 1 OF 1



QUANTITY SUMMARY


CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	10	

TRAFFIC CONTROL NOTES

FOLLOW STANDARD TCP SHEETS OR PROVIDED TCP FOR LANE CLOSURES DURING ALLOWED WORKING HOURS
 PLACE WK ZN PAVEMENT MARKINGS IN ACCORDANCE WITH WZ(STPM)-13
 SIGN AND TREAT EDGE CONDITIONS IN ACCORDANCE WITH WZ(UL)-13 TXDOT STANDARDS
 PLACE REMOVABLE WK ZN PAVEMENT MARKINGS/TABS IN ACCORDANCE WITH BC(11)-14 & BC(12)-14 ON FINAL SURFACES

RAILROAD FLAGGING NOTES:

A RAILROAD FLAGGER WILL BE USED ANYTIME VEHICULAR TRAFFIC WILL CONTRAFLOW IN THE OPPOSITE DIRECTION/LANE THAT IS NOT PROTECTED BY RAILROAD WARNING DEVICES.



PLACE IN ACCORDANCE WITH STNDARD SHEETS
 WZ (UL)-13, BC's, AND/OR AS DIRECTED.


UNLESS OTHERWISE SHOWN ALL CW SIGNS SHALL BE 48" X 48".

SEQUENCE OF WORK

1. PLACE NECESSARY SIGNS AND TRAFFIC CONTROL
3. PLACE NECESSARY EROSION CONTROL DEVICES
4. PLANE EXISTING HMAC
5. ALL PAVEMENT SECTIONS MILLED, SHALL HAVE HMAC PLACED ON THE SAME WORKING DAY/SHIFT
 - α. CONTRACTOR SHALL NOT MILL MORE THAN WHAT CAN BE OVERLAYED IN ONE WORKING DAY/SHIFT
6. PLACE TACK COAT
7. PLACE HMAC
8. PLACE WZ TABS OR PERMANENT STRIPING DAILY
 - α. REMOVE WZ TABS AND PLACE PERMANENT STRIPING AT INTERVALS NOT EXCEEDING DURATION OF WZ TABS
9. BACKFILL PAVEMENT EDGE
10. REMOVE TRAFFIC CONTROL DEVICES, CONSTRUCTION DEBRIS AND EROSION CONTROL DEVICES

CONSTRUCTION NOTES:

- *CONTRACTOR SHALL WORK TO OPTIMIZE TRAFFIC FLOW AND MINIMIZE TRAFFIC DELAYS DURING WORKING HOURS
- *CONTRACTOR SHALL MAINTAIN CERTIFIED FLAGGERS AT ALL ROADWAYS/INTERSECTIONS DURING WORKING HOURS
- *CONTRACTOR SHALL KEEP ALL LANES OF TRAFFIC OPEN FOR THE FOLLOWING:
 - ALL LANES OF TRAFFIC SHALL BE OPEN DURING PEAK HOURS (6AM-9AM), (3PM-7PM) AND (7PM-9PM) MONDAY-FRIDAY
 - ALL LANES OF TRAFFIC SHALL BE OPEN ON WEEKENDS
 - ALL LANES OF TRAFFIC SHALL BE OPEN NIGHTS THAT ARE NOT APPROVED BY THE AREA OFFICE IN ADVANCE
- *WEEKEND WORK IS NOT ALLOWED
- *SINGLE LANE CLOSURES SHALL ONLY BE ALLOWED WITH APPROVED TRAFFIC CONTROL PLANS DURING OFF-PEAK HOURS 9AM TO 3PM (MONDAY-FRIDAY) UNLESS NIGHT WORK IS APPROVED
- *CONTRACTOR REQUESTING NIGHT WORK SHALL BE APPROVED BY THE AREA OFFICE IN ADVANCE
 - NIGHT SHALL BE BETWEEN 9PM TO 6AM, UNLESS OTHERWISE APPROVED
- *CONTRACTOR SHALL SET UP AND REMOVE ALL TRAFFIC CONTROL DEVICES EACH WORKING DAY/SHIFT
- *CONTRACTOR SHALL CREATED TAPERED FEATHERED BUTT JOINTS TO ALLOW A TRANSITIONED RAMPED GRADE CHANGE AT END OF WORKING SHIFTS AND PRIOR TO OPENING UP TRAFFIC AFTER EACH WORKING DAY/SHIFT
- *INSTALLATION OF DRIVEWAYS SHALL RUN CONCURRENT WITH REGULAR CONSTRUCTION



DocuSigned by:
Jeremy Arreguin
 CBES1DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 1 OF 1




SEQUENCE OF WORK

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	11

1/25/2021 3:57:02 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\SEQUENCE OF WORK.dgn

DWG:
 CHK:
 DWF:
 CWS:

LEGEND			
I	TYPE 3 BARRICADE	•••	CHANNELIZING DEVICES
	HEAVY WORK VEHICLE W/TMA		TRAFFIC FLOW
	SIGN		FLAGGER
	FLAG		PORTABLE MESSAGE SIGN
	WORKSPACE		RUMBLE STRIP ARRAY



GENERAL NOTES

THE CONTRACTOR SHALL SECURE THE NECESSARY TRAFFIC CONTROL DEVICES AND ENGINEERING APPROVAL OF THE PROPOSED PLAN OF OPERATION AND SEQUENCE OF WORK AND TRAFFIC CONTROL PLAN FOR THE PROJECT OPERATION PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES.

WORK SHIFTS SHALL BE FROM 9AM TO 3PM. AT THE END OF EACH WORK SHIFT, THE CONTRACTOR SHALL REMOVE ALL TRAFFIC DEVICES AND THE ROADWAY SHALL BE OPENED UP TO TRAFFIC.

NIGHT WORK IS ALLOWED AT THE APPROVAL OF THE AREA OFFICE.

AT ALL TIMES, DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A SAFE AND COMFORTABLE ROUTE FOR THE TRAVELING PUBLIC.

FLAGGERS SHALL USE TWO-WAY RADIOS OR OTHER METHODS TO COMMUNICATE NECESSARY OPERATIONS. FLAGGERS SHALL ASSIST WITH TRAFFIC CONTROL AT INTERSECTIONS AND AREAS WHERE SIGHT DISTANCE IS LIMITED.

ALL FLAGGERS SHALL BE CERTIFIED AND TRAINED TO PERFORM ALL NECESSARY TRAFFIC CONTROL OPERATIONS. FLAGGERS SHALL WEAR PROPER PERSONAL PROTECTIVE EQUIPMENT. FLAGGERS SHALL BE EQUIPPED WITH NECESSARY STOP/SLOW PADDLES, COMMUNICATION DEVICES AND ANY OTHER TOOLS, REQUIRED TO PERFORM SAFE AND EFFECTIVE TRAFFIC CONTROL IN THE WORK AREAS.

FLAGGER LOCATIONS MAY BE ADJUSTED TO REDUCE TRAFFIC FLOW AND CYCLE TIME THROUGH THE WORK ZONE AS APPROVED BY THE AREA OFFICE

REFER TO STANDARD TCP SHEETS FOR OTHER APPROVED TRAFFIC CONTROL PLANS

ANY OTHER SIGNS AS DETAILED IN THE BARRICADES AND CONSTRUCTION STANDARDS, AND IN THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES MAY BE USED AS REQUIRED BY THE ENGINEER IN ORDER TO PROVIDE SAFE PASSAGE THROUGH THE PROJECT.

TCP AND SEQUENCE OF WORK



BEFORE BEGINNING WORK, THE CONTRACTOR IS REQUIRED TO SUBMIT A PLAN OF OPERATION FOR THE ENGINEER'S APPROVAL DESCRIBING THE SEQUENCE OF WORK, TRAFFIC CONTROL, CONTRACTOR STOCKPILE LOCATIONS, HAUL ROUTES, TRANSISTIONS AND TIES, ETC. REFER TO TCP'S FOR TRAFFIC CONTROL.

TCP NOTE

THE ENGINEER OR THE CONTRACTOR MAY REQUEST ADDITIONAL SIGNING NOT SHOWN AND THIS WILL BE CONSIDERED SUBSIDIARY TO THE PERTINENT BID ITEMS UNDER ITEM 502. MESSAGE BOARDS AND TRUCK-MOUNTED ATTENUATOR (TMA) WILL BE PAID SEPARATELY.

BARRICADES AND WARNING SIGNS

- SEE BC STANDARDS FOR PROJECT LIMIT DEVICES AND WARNING SIGN SPACING (X)
- SIGN CW20-1D SIGN SHALL BE PLACED AT ALL INTERSECTIONS AND SIDE ROADS
- SEE BC STANDARDS FOR DRUMS, PANELS AND CONES
- SIGN CW-21-2 SHALL USED AS DIRECTED BY THE ENGINEER'S REPRESENTATIVE



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021


SCALE: NONE
 SHEET 1 OF 4

TCP LAYOUT NEAR ALEDO RD. PHASE 1			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	12

1/25/2021 3:57:38 PM
 T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aleo Rd\05-Roadway\TCP NEAR ALEDO ROAD.dgn

1/25/2021 3:57:43 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TCP NEAR ALEDO ROAD.dgn

LEGEND			
I	TYPE 3 BARRICADE	•••	CHANNELIZING DEVICES
	HEAVY WORK VEHICLE W/TMA		TRAFFIC FLOW
	SIGN		FLAGGER
	FLAG		PORTABLE MESSAGE SIGN
	WORKSPACE		RUMBLE STRIP ARRAY



GENERAL NOTES

THE CONTRACTOR SHALL SECURE THE NECESSARY TRAFFIC CONTROL DEVICES AND ENGINEERING APPROVAL OF THE PROPOSED PLAN OF OPERATION AND SEQUENCE OF WORK AND TRAFFIC CONTROL PLAN FOR THE PROJECT OPERATION PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES.

WORK SHIFTS SHALL BE FROM 9AM TO 3PM. AT THE END OF EACH WORK SHIFT, THE CONTRACTOR SHALL REMOVE ALL TRAFFIC DEVICES AND THE ROADWAY SHALL BE OPENED UP TO TRAFFIC.

NIGHT WORK IS ALLOWED AT THE APPROVAL OF THE AREA OFFICE.

AT ALL TIMES, DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A SAFE AND COMFORTABLE ROUTE FOR THE TRAVELING PUBLIC.

FLAGGERS SHALL USE TWO-WAY RADIOS OR OTHER METHODS TO COMMUNICATE NECESSARY OPERATIONS. FLAGGERS SHALL ASSIST WITH TRAFFIC CONTROL AT INTERSECTIONS AND AREAS WHERE SIGHT DISTANCE IS LIMITED.

ALL FLAGGERS SHALL BE CERTIFIED AND TRAINED TO PERFORM ALL NECESSARY TRAFFIC CONTROL OPERATIONS. FLAGGERS SHALL WEAR PROPER PERSONAL PROTECTIVE EQUIPMENT. FLAGGERS SHALL BE EQUIPPED WITH NECESSARY STOP/SLOW PADDLES, COMMUNICATION DEVICES AND ANY OTHER TOOLS, REQUIRED TO PERFORM SAFE AND EFFECTIVE TRAFFIC CONTROL IN THE WORK AREAS.

FLAGGER LOCATIONS MAY BE ADJUSTED TO REDUCE TRAFFIC FLOW AND CYCLE TIME THROUGH THE WORK ZONE AS APPROVED BY THE AREA OFFICE

REFER TO STANDARD TCP SHEETS FOR OTHER APPROVED TRAFFIC CONTROL PLANS

ANY OTHER SIGNS AS DETAILED IN THE BARRICADES AND CONSTRUCTION STANDARDS, AND IN THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES MAY BE USED AS REQUIRED BY THE ENGINEER IN ORDER TO PROVIDE SAFE PASSAGE THROUGH THE PROJECT.

TCP AND SEQUENCE OF WORK



BEFORE BEGINNING WORK, THE CONTRACTOR IS REQUIRED TO SUBMIT A PLAN OF OPERATION FOR THE ENGINEER'S APPROVAL DESCRIBING THE SEQUENCE OF WORK, TRAFFIC CONTROL, CONTRACTOR STOCKPILE LOCATIONS, HAUL ROUTES, TRANSITIONS AND TIES, ETC. REFER TO TCP'S FOR TRAFFIC CONTROL.

TCP NOTE

THE ENGINEER OR THE CONTRACTOR MAY REQUEST ADDITIONAL SIGNING NOT SHOWN AND THIS WILL BE CONSIDERED SUBSIDIARY TO THE PERTINENT BID ITEMS UNDER ITEM 502. MESSAGE BOARDS AND TRUCK-MOUNTED ATTENUATOR (TMA) WILL BE PAID SEPARATELY.

BARRICADES AND WARNING SIGNS

- SEE BC STANDARDS FOR PROJECT LIMIT DEVICES AND WARNING SIGN SPACING (X)
- SIGN CW20-1D SIGN SHALL BE PLACED AT ALL INTERSECTIONS AND SIDE ROADS
- SEE BC STANDARDS FOR DRUMS, PANELS AND CONES
- SIGN CW-21-2 SHALL USED AS DIRECTED BY THE ENGINEER'S REPRESENTATIVE



DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021


SCALE: NONE
 SHEET 2 OF 4

TCP LAYOUT NEAR ALEDO RD. PHASE 1			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	13	

DWG:
 CHK:
 DWF:
 CWS:

1/25/2021 3:57:49 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TCP NEAR ALEDO ROAD.dgn

LEGEND			
I	TYPE 3 BARRICADE	•••	CHANNELIZING DEVICES
	HEAVY WORK VEHICLE W/TMA		TRAFFIC FLOW
	SIGN		FLAGGER
	FLAG		PORTABLE MESSAGE SIGN
	WORKSPACE		RUMBLE STRIP ARRAY



GENERAL NOTES

THE CONTRACTOR SHALL SECURE THE NECESSARY TRAFFIC CONTROL DEVICES AND ENGINEERING APPROVAL OF THE PROPOSED PLAN OF OPERATION AND SEQUENCE OF WORK AND TRAFFIC CONTROL PLAN FOR THE PROJECT OPERATION PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES.

WORK SHIFTS SHALL BE FROM 9AM TO 3PM. AT THE END OF EACH WORK SHIFT, THE CONTRACTOR SHALL REMOVE ALL TRAFFIC DEVICES AND THE ROADWAY SHALL BE OPENED UP TO TRAFFIC.

NIGHT WORK IS ALLOWED AT THE APPROVAL OF THE AREA OFFICE.

AT ALL TIMES, DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A SAFE AND COMFORTABLE ROUTE FOR THE TRAVELING PUBLIC.

FLAGGERS SHALL USE TWO-WAY RADIOS OR OTHER METHODS TO COMMUNICATE NECESSARY OPERATIONS. FLAGGERS SHALL ASSIST WITH TRAFFIC CONTROL AT INTERSECTIONS AND AREAS WHERE SIGHT DISTANCE IS LIMITED.

ALL FLAGGERS SHALL BE CERTIFIED AND TRAINED TO PERFORM ALL NECESSARY TRAFFIC CONTROL OPERATIONS. FLAGGERS SHALL WEAR PROPER PERSONAL PROTECTIVE EQUIPMENT. FLAGGERS SHALL BE EQUIPPED WITH NECESSARY STOP/SLOW PADDLES, COMMUNICATION DEVICES AND ANY OTHER TOOLS, REQUIRED TO PERFORM SAFE AND EFFECTIVE TRAFFIC CONTROL IN THE WORK AREAS.

FLAGGER LOCATIONS MAY BE ADJUSTED TO REDUCE TRAFFIC FLOW AND CYCLE TIME THROUGH THE WORK ZONE AS APPROVED BY THE AREA OFFICE

REFER TO STANDARD TCP SHEETS FOR OTHER APPROVED TRAFFIC CONTROL PLANS

ANY OTHER SIGNS AS DETAILED IN THE BARRICADES AND CONSTRUCTION STANDARDS, AND IN THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES MAY BE USED AS REQUIRED BY THE ENGINEER IN ORDER TO PROVIDE SAFE PASSAGE THROUGH THE PROJECT.

TCP AND SEQUENCE OF WORK



BEFORE BEGINNING WORK, THE CONTRACTOR IS REQUIRED TO SUBMIT A PLAN OF OPERATION FOR THE ENGINEER'S APPROVAL DESCRIBING THE SEQUENCE OF WORK, TRAFFIC CONTROL, CONTRACTOR STOCKPILE LOCATIONS, HAUL ROUTES, TRANSITIONS AND TIES, ETC. REFER TO TCP'S FOR TRAFFIC CONTROL.

TCP NOTE

THE ENGINEER OR THE CONTRACTOR MAY REQUEST ADDITIONAL SIGNING NOT SHOWN AND THIS WILL BE CONSIDERED SUBSIDIARY TO THE PERTINENT BID ITEMS UNDER ITEM 502. MESSAGE BOARDS AND TRUCK-MOUNTED ATTENUATOR (TMA) WILL BE PAID SEPARATELY.

BARRICADES AND WARNING SIGNS

- SEE BC STANDARDS FOR PROJECT LIMIT DEVICES AND WARNING SIGN SPACING (X)
- SIGN CW20-1D SIGN SHALL BE PLACED AT ALL INTERSECTIONS AND SIDE ROADS
- SEE BC STANDARDS FOR DRUMS, PANELS AND CONES
- SIGN CW-21-2 SHALL USED AS DIRECTED BY THE ENGINEER'S REPRESENTATIVE



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 3 OF 4




**TCP LAYOUT
 NEAR ALEDO RD.
 PHASE 2**

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	14	

C:\S:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TCP NEAR ALEDO ROAD.dgn
 DWG
 C:\S
 DWS

LEGEND			
I	TYPE 3 BARRICADE	•••	CHANNELIZING DEVICES
	HEAVY WORK VEHICLE W/TMA		TRAFFIC FLOW
	SIGN		FLAGGER
	FLAG		PORTABLE MESSAGE SIGN
	WORKSPACE		RUMBLE STRIP ARRAY



GENERAL NOTES

THE CONTRACTOR SHALL SECURE THE NECESSARY TRAFFIC CONTROL DEVICES AND ENGINEERING APPROVAL OF THE PROPOSED PLAN OF OPERATION AND SEQUENCE OF WORK AND TRAFFIC CONTROL PLAN FOR THE PROJECT OPERATION PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES.

WORK SHIFTS SHALL BE FROM 9AM TO 3PM. AT THE END OF EACH WORK SHIFT, THE CONTRACTOR SHALL REMOVE ALL TRAFFIC DEVICES AND THE ROADWAY SHALL BE OPENED UP TO TRAFFIC.

NIGHT WORK IS ALLOWED AT THE APPROVAL OF THE AREA OFFICE.

AT ALL TIMES, DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A SAFE AND COMFORTABLE ROUTE FOR THE TRAVELING PUBLIC.

FLAGGERS SHALL USE TWO-WAY RADIOS OR OTHER METHODS TO COMMUNICATE NECESSARY OPERATIONS. FLAGGERS SHALL ASSIST WITH TRAFFIC CONTROL AT INTERSECTIONS AND AREAS WHERE SIGHT DISTANCE IS LIMITED.

ALL FLAGGERS SHALL BE CERTIFIED AND TRAINED TO PERFORM ALL NECESSARY TRAFFIC CONTROL OPERATIONS. FLAGGERS SHALL WEAR PROPER PERSONAL PROTECTIVE EQUIPMENT. FLAGGERS SHALL BE EQUIPPED WITH NECESSARY STOP/SLOW PADDLES, COMMUNICATION DEVICES AND ANY OTHER TOOLS, REQUIRED TO PERFORM SAFE AND EFFECTIVE TRAFFIC CONTROL IN THE WORK AREAS.

FLAGGER LOCATIONS MAY BE ADJUSTED TO REDUCE TRAFFIC FLOW AND CYCLE TIME THROUGH THE WORK ZONE AS APPROVED BY THE AREA OFFICE

REFER TO STANDARD TCP SHEETS FOR OTHER APPROVED TRAFFIC CONTROL PLANS

ANY OTHER SIGNS AS DETAILED IN THE BARRICADES AND CONSTRUCTION STANDARDS, AND IN THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES MAY BE USED AS REQUIRED BY THE ENGINEER IN ORDER TO PROVIDE SAFE PASSAGE THROUGH THE PROJECT.

TCP AND SEQUENCE OF WORK



BEFORE BEGINNING WORK, THE CONTRACTOR IS REQUIRED TO SUBMIT A PLAN OF OPERATION FOR THE ENGINEER'S APPROVAL DESCRIBING THE SEQUENCE OF WORK, TRAFFIC CONTROL, CONTRACTOR STOCKPILE LOCATIONS, HAUL ROUTES, TRANSITIONS AND TIES, ETC. REFER TO TCP'S FOR TRAFFIC CONTROL.

TCP NOTE

THE ENGINEER OR THE CONTRACTOR MAY REQUEST ADDITIONAL SIGNING NOT SHOWN AND THIS WILL BE CONSIDERED SUBSIDIARY TO THE PERTINENT BID ITEMS UNDER ITEM 502. MESSAGE BOARDS AND TRUCK-MOUNTED ATTENUATOR (TMA) WILL BE PAID SEPARATELY.

BARRICADES AND WARNING SIGNS

- SEE BC STANDARDS FOR PROJECT LIMIT DEVICES AND WARNING SIGN SPACING (X)
- SIGN CW20-1D SIGN SHALL BE PLACED AT ALL INTERSECTIONS AND SIDE ROADS
- SEE BC STANDARDS FOR DRUMS, PANELS AND CONES
- SIGN CW-21-2 SHALL USED AS DIRECTED BY THE ENGINEER'S REPRESENTATIVE




DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 4 OF 4


TCP LAYOUT NEAR ALEDO RD. PHASE 2			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	15	

1/25/2021 3:57:54 PM
 T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\TCP NEAR ALEDO ROAD.dgn



1/25/2021 3:58:07 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\PORTABLE MESSAGE SIGN LAYOUT.dgn

LEGEND
 PORTABLE CHANGEABLE MESSAGE SIGN



DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

GENERAL NOTES
 MESSAGE BOARD LOCATION SHOWN ARE SUGGESTED LOCATIONS AND MAY BE PLACED AS DIRECTED.
 REFER TO BC STANDARD SHEETS FOR RECOMMENDED PHRASES AND FORMATS

©2021 by Texas Department of Transportation; all rights reserved

SCALE: NONE

PORTABLE CHANGEABLE MESSAGE SIGN LAYOUT

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	16

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any person who issues it. TxDOT assumes no responsibility for the conversion of this standard to metric units or for any damages resulting from its use.


DATE: 1/25/2021 3:58:22 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_R006-Standard\BC(1)-14.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- As shown on BC(2), the OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER (see Sign Detail G20-10T) and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. However, the TRAFFIC FINES DOUBLE sign will not be required on projects consisting solely of mobile operation work, such as striping or milling edgeline rumble strips. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits.
- Except for devices required by Note 10, traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY APPAREL NOTES:

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.



SIGN DETAIL (G20-10T)

Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found on-line at the web address given below or by contacting:

Texas Department of Transportation
 Traffic Operations Division - TE
 Phone (512) 416-3118


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov	
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)	
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)	
MATERIAL PRODUCER LIST (MPL)	
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"	
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)	
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)	
TRAFFIC ENGINEERING STANDARD SHEETS	

SHEET 1 OF 12

		<i>Traffic Operations Division Standard</i>
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS		
BC(1)-14		
FILE: bc-14.dgn	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT: 2855	SECT: 01
REVISIONS	JOB: 023	HIGHWAY: RM 2871
4-03 5-10 8-14	DIST: FTW	COUNTY: TARRANT
9-07 7-13		SHEET NO.: 17


DATE: 1/25/2021 3:58:28 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to A1600 ROW\06-Standard\BC(2)-14.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ⚠ May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Spacing "X" Feet (Approx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- ⊗ The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- ** Required CSJ Limit signing. See Note 10 on BC(1). TRAFFIC FINES DOUBLE signs will not be required on projects consisting solely of mobile operations work.
- ⊗ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- ⊗ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
⊗	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855 01		023	RM 2871
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13	FTW	TARRANT		18

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the travelled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or damages resulting from its use.


DATE: 1/25/2021 3:58:36 PM
FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_A1806_000005100005\BC(3)-14.dgn

SHEET 3 OF 12

		Traffic Operations Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 14</h3>			
FILE:	bc-14.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT	SECT
REVISIONS	2855 01	JOB	023
9-07 8-14		HIGHWAY	RM 2871
7-13		DIST	COUNTY
		FTW	TARRANT
		SHEET NO.	19


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.
 ** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24" as detailed below.
- When used at night, the STOP/SLOW paddle shall be retroreflectORIZED.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC sheets or the CWZTCD. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
 - Wooden sign posts shall be painted white.
 - Barricades shall NOT be used as sign supports.
 - All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
 - The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
 - The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD). The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
 - The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
 - Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
 - The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.
- DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**
- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.




BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 14


FILE: bc-14.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	FTW	TARRANT		20

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for any errors or omissions. For more information, contact TxDOT at 1-800-392-6709 or visit the website at www.txdot.gov.
 DATE: 1/25/2021 3:58:47 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo RD\06-Standards\BC(5)-14 THRU BC(12)-14.dgn




SKID MOUNTED WOOD SIGN SUPPORTS

LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS □




GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.




SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS



Nominal Post Size	Number of Posts	Maximum Sq. feet of Sign Face	Minimum Soil Embedment	Drilled Hole(s) Required
4 x 4	1	12	36"	NO
4 x 4	2	21	36"	NO
4 x 6	1	21	36"	YES
4 x 6	2	36	36"	YES

WOOD POST SYSTEM FOR GROUND MOUNTED SIGN SUPPORTS



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- See BC(4) for definition of "Work Duration."
- * Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- △ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	FTW	TARRANT	21	

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats for incorrect results or damages resulting from its use.

DATE: 1/25/2021 3:58:53 PM
FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo RD\06-Standards\BC(1)-14_THRU_BC(12)-14.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number



Traffic Operations Division Standard

BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855 01	023	RM 2871	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	FTW	TARRANT	22	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021 3:58:58 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\BC(7)-14_THRU_BC(12)-14.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)



LOW PROFILE CONCRETE BARRIER (LPCB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet crashworthy standards as defined in the National Cooperative Highway Research Report 350. Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential Chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION

Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the National Cooperative Highway Research Report No. 350 (NCHRP 350) or the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 14

FILE: bc-14.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	FTW	TARRANT	23	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021 3:59:03 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\BC(1)-14_THRU_BC(12)-14.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS


- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




Each drum shall have a minimum of 2 orange and 2 white stripes using Type A retro-reflective sheeting with the top stripe being orange.

Taper to allow for stacking a minimum of 5 drums
Base (36" dia. max)



DIRECTION INDICATOR BARRICADE


- The Direction Indicator Barricade may be used in tapers, transitions, and other areas where specific directional guidance to drivers is necessary.
- If used, the Direction Indicator Barricade should be used in series to direct the driver through the transition and into the intended travel lane.
- The Direction Indicator Barricade shall consist of One-Direction Large Arrow (CWI-6) sign in the size shown with a black arrow on a background of Type B_{FL} or Type C_{FL} Orange retroreflective sheeting above a rail with Type A retroreflective sheeting in alternating 4" white and orange stripes sloping downward at an angle of 45 degrees in the direction road users are to pass. Sheeting types shall be as per DMS 8300.
- Double arrows on the Direction Indicator Barricade will not be allowed.
- Approved manufacturers are shown on the CWZTCD List. Ballast shall be as approved by the manufacturer's instructions.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a device that is detectable by a person with a visual disability traveling with the aid of a long cane shall be placed across the full width of the closed sidewalk.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades may use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.

This detail is not intended for fabrication. See note 3 and the CWZTCD list for providers of approved Detectable Pedestrian Barricades



18" x 24" Sign (Maximum Sign Dimension)
Chevron CWI-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS


- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES			
BC (8) - 14			
FILE: bc-14.dgn	DWG: TxDOT	CR: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT	SECT	JOB
REVISIONS	2855	01	023
4-03 7-13	DIST	COUNTY	HIGHWAY
9-07 8-14	FTW	TARRANT	RM 2871
			SHEET NO. 24


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021 3:59:09 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\BC(1)-14_THRU_BC(12)-14.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual Appendix B "Treatment of Pavement Drop-offs in Work Zones" for additional guidelines on the use of VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10) placed near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate NCHRP 350 crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed * S	Formula L = WS ² / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40	L = WS	265'	295'	320'	40'	80'
45		450'	495'	540'	45'	90'
50	L = WS	500'	550'	600'	50'	100'
55		600'	660'	720'	60'	120'
60	L = WS	650'	715'	780'	65'	130'
65		700'	770'	840'	70'	140'
70	L = WS	750'	825'	900'	75'	150'
75		800'	880'	960'	80'	160'
80	L = WS	800'	880'	960'	80'	160'
80		800'	880'	960'	80'	160'

**Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	FTW	TARRANT	25	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021 3:59:14 PM
FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\BC(10)-14.dgn


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.



PLAN VIEW


1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW

These drums are not required on one-way roadway




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.


LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers used at night shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.

THIS DEVICE SHALL NOT BE USED ON PROJECTS LET AFTER MARCH 2014.



EDGE LINE CHANNELIZER

1. This device is intended only for use in place of a vertical panel to channelize traffic by indicating the edge of the travel lane. It is not intended to be used in transitions or tapers.
2. This device shall not be used to separate lanes of traffic (opposing or otherwise) or warn of objects.
3. This device is based on a 42 inch, two-piece cone with an alternate striping pattern: four 4 inch retroreflective bands, with an approximate 2 inch gap between bands. The color of the band should correspond to the color of the edgeline (yellow for left edgeline, white for right edgeline) for which the device is substituted or for which it supplements. The reflectorized bands shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless otherwise noted.
4. The base must weigh a minimum of 30 lbs.

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855 01	023	RM 2871	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	FTW	TARRANT	26	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
2-98 9-07	DIST	COUNTY	SHEET NO.	
1-02 7-13	FTW	TARRANT	27	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021 3:59:19 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\BC(11)-14_THRU_BC(12)-14.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-14




Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
1-97 9-07	DIST	COUNTY	SHEET NO.	
2-98 7-13	FTW	TARRANT	28	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 1/25/2021 3:59:27 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\BC(12)-14_THRU_BC(12)-14.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT is not responsible for any errors or omissions in this standard or for any damages resulting from its use.

DATE: 1/25/2021 3:59:36 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_AT&B\Traffic Control Plans\2855-01-023_RM_2871_TCP(2-1).dgn



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
 - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18


FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	FTW	TARRANT	29	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT reserves the right to modify or correct this standard without notice.

DATE: 1/25/2021 3:59:48 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_A1B6\Traffic\2855-01-023_RM_2871-TCP.dwg



TCP (2-2a)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH YIELD SIGNS
 (Less than 2000 ADT - See Note 9)



TCP (2-2b)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Traffic Operations Division Standard

TEXAS DEPARTMENT OF TRANSPORTATION



TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP (2-2) - 18

FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	FTW	TARRANT	30	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT is not responsible for any errors or omissions that may appear in this document.

DATE: 1/25/2021 4:00:00 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_AT&B\Traffic\Traffic\2855-01-023_RM_2871_From_IH20_to_AT&B\Traffic\Traffic\TCP(2-3)-18.dgn



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = WS ² /60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² /60	150'	165'	180'	30'	70'	120'	90'
35		205'	225'	245'	35'	80'	160'	120'
40		265'	295'	320'	40'	90'	240'	155'
45	L = WS	450'	495'	540'	45'	100'	320'	195'
50		500'	550'	600'	50'	110'	400'	240'
55		550'	605'	660'	55'	120'	500'	295'
60	L = WS	600'	660'	720'	60'	130'	600'	350'
65		650'	715'	780'	65'	140'	700'	410'
70		700'	770'	840'	70'	150'	800'	475'
75	L = WS	750'	825'	900'	75'	160'	900'	540'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓
				TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Texas Department of Transportation
 Traffic Operations Division Standard



TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS

TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	FTW	TARRANT	31	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. The user assumes all liability for any errors or omissions in this standard.

DATE: 1/25/2021 4:00:11 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_A1B1B2\Drawings\Traffic\Traffic\TCP (2-8a).dgn



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Sign		Traffic Flow
	Flag		Flagger
	Raised Pavement Markers Ty II-AA		Temporary or Portable Traffic Signal

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60	L = WS	600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75	L = WS	750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - When this TCP is used at a location which does not involve a bridge, a 48" x 48" CW20-4D "ONE LANE ROAD AHEAD" signs should be used in lieu of the CW5-3 "ONE LANE BRIDGE" signs. The CW13-1P Advisory Speed Plaque is required with either warning sign.
 - Raised pavement markers shall be placed 40 feet c-c on centerline between DO NOT PASS signs and stop or yield lines.
 - For intermediate term situations, when it is not feasible to remove and restore pavement markings, the channelization must be made dominant by using a very close spacing. This is especially important in locations of conflicting information, such as where traffic is directed over a double yellow centerline. In such locations a maximum channelizing device spacing of 20 feet is recommended. The 20 foot channelizing device spacing recommendation is intended for the area of conflicting information and not the entire work zone.
- TCP (2-8a)**
- Traffic control by CW3-2 "YIELD AHEAD" symbol signs for one lane two-way traffic control operations should be limited to work spaces less than 400 feet long and roadways with less than 2000 ADT. Otherwise, portable traffic signals should be used.
 - If power is available, a flashing beacon should be attached to the CW3-2 "YIELD AHEAD" symbol sign for emphasis.
 - The R1-2 "YIELD" and R1-2aP "TO ONCOMING TRAFFIC" signs and other regulatory signs shall be installed at 7 foot minimum mounting height.
- TCP (2-8b)**
- A list of approved Portable Traffic Signals can be found in the "Compliant Work Zone Traffic Control Devices" list.
 - Portable traffic signals should be located to provide adequate stopping sight distance for approaching motorist (See table above).

Traffic Operations Division Standard



TRAFFIC CONTROL PLAN LONG TERM ONE-LANE TWO-WAY CONTROL

TCP (2-8) - 18

FILE: tcp2-8-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	FTW	TARRANT	32	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from its original source to this standard.





DATE: 1/25/2021 4:00:23 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_A1B6_110001.dwg



LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

- GENERAL NOTES**
- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
 - The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
 - The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
 - Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
 - Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
 - Each vehicle shall have two-way radio communication capability.
 - When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
 - Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
 - "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
 - On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



Texas Department of Transportation


Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS
 UNDIVIDED HIGHWAYS


TCP (3-1) - 13

FILE:	tcp3-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	December 1985	CONT:	2855	SECT:	01	JOB:	023	RM:	2871
REVISIONS		DIST:	COUNTY:		SHEET NO.:				
2-94	4-98	FTW	TARRANT				33		
8-95	7-13								
1-97									


DATE: 1/25/2021 4:00:34 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_ATB\2855-01-023_RM_2871.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format.




TCP (3-3a)
TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3b)
TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3c)
DIVIDED MULTILANE HIGHWAY




TCP (3-3d)
UNDIVIDED MULTILANE HIGHWAY




TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display
 Flashing Arrow Board



TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board
 in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.




Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/
REMOVAL
TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	FTW	TARRANT	34	
1-97 7-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided. This standard is based on the current edition of the Manual on Uniform Traffic Control Devices (MUTCD) and the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

DATE: 1/25/2021 4:00:48 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_A1B\Drawings\Traffic\Traffic Plans\Traffic Control Plans\Traffic Control Plan\Traffic Control Plan.dwg



LEGEND		
*	Trail Vehicle	ARROW BOARD DISPLAY
**	Shadow Vehicle	
** *	Work Vehicle	RIGHT Directional
	Heavy Work Vehicle	LEFT Directional
	Truck Mounted Attenuator (TMA)	Double Arrow
	Traffic Flow	Channelizing Devices


Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. This traffic control plan is for use on conventional roads posted at 45 mph or less and is intended for mobile operations that move continuously or intermittently (stopping up to approximately 15 minutes) such as short-line striping and in-lane rumble strips. When activities are anticipated to take longer amounts of time or traffic conditions warrant, a short duration or short-term stationary traffic control plan should be used.
2. A Truck Mounted Attenuator shall be used on Shadow Vehicle. Striping on the back panel of all truck mounted attenuators shall be 8" red and white reflective sheeting placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental material specification DMS-8300, Type A.
3. All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.
4. The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the drivers side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
5. Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C as per BC Standards. The arrow board operation shall be controlled from inside the truck.



Texas Department of Transportation
 Traffic Operations Division Standard



**TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS FOR
 ISOLATED WORK AREAS
 UNDIVIDED HIGHWAYS**

TCP(3-4)-13

FILE: tcp3-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT July, 2013	CONT: 2855	SECT: 01	JOB: 023	HIGHWAY: RM 2871
REVISIONS	DIST: FTW	COUNTY: TARRANT	SHEET NO.: 35	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT is not responsible for any errors or omissions in this document. TxDOT is not responsible for any damages resulting from its use.

DATE: 1/25/2021 4:01:00 PM
 FILE: I:\STCAO Files\STCAO Des\gn\Projects\2855-01-023_RM_2871_From_IH20_to_A1B6_000001.dwg



"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- Tabs shall not be used to simulate edge lines.
- Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
- Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
- Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.

Traffic Operations Division Standard


TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS
TCP (7-1) - 13

FILE: tcp7-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT March 1991	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855 01	023	RM	2871
4-92 4-98	DIST	COUNTY	SHEET NO.	
1-97 7-13	FTW	TARRANT	36	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided. For more information, contact the TxDOT Office of Construction Services, 13000 North Loop West, Houston, Texas 77040.

DATE: 1/25/2021 4:01:11 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_toATB\Bldg\2855-01-023_RM_2871.dgn

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm




WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	2855 01	SECT:	023	JOB:	RM 2871	HIGHWAY	
REVISIONS		DIST:		COUNTY:	TARRANT	SHEET NO.		37	
1-97		FTW							
3-03									
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of any information or for any errors or omissions or for any damages resulting from its use.

DATE: 1/25/2021 4:01:22 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_AT&B_080915.dwg



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

BACKGROUND COLOR	SIGN DESIGNATION	SIGN	SIGN DIMENSIONS	REFLECTIVE SHEETING	SQ FT	GALVANIZED STRUCTURAL STEEL		DRILLED SHAFT
						Size	(LF)	
							① ②	24" DIA. (LF)
Orange	G20-7T		96" X 48"	Type B _{FL} or C _{FL}	32	▲	▲ ▲	▲
Orange	G20-7T		192" X 96"	Type B _{FL} or C _{FL}	128	W8x18	16 17	12

▲ See Note 6 Below

LEGEND

	Sign
	Large Sign
	Traffic Flow

DEPARTMENTAL MATERIAL SPECIFICATIONS

PLYWOOD SIGN BLANKS	DMS-7100
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL}
BLACK	LEGEND & BORDERS	NON-REFLECTIVE ACRYLIC FILM

GENERAL NOTES

- See BC and SMD sheets for additional sign support details.
- Sign locations shall be approved by the Engineer.
- For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
- Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
- Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
- The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
- The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:
 Item 636 - Aluminum Signs
 Item 647 - Large Roadside Sign Supports and Assemblies.
 Item 416 - Drilled Shaft Foundations
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.


				Traffic Operations Division Standard	
WORK ZONE "GIVE US A BRAKE" SIGNS					
WZ (BRK) - 13					
FILE: wzbrk-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
©TxDOT August 1995	CONT	SECT	JOB	HIGHWAY	
REVISIONS	2855 01		023	RM 2871	
6-96 5-98 7-13	DIST	COUNTY	SHEET NO.		
8-96 3-03	FTW	TARRANT	38		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided. TxDOT is not responsible for any errors or omissions in this standard or for any damages resulting from its use.


DATE: 1/25/2021 4:01:34 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_ATB\WZ (RS)-16.dgn

Warning sign and rumble strip sequence in opposite direction is same as below

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



WZ (RS-1a)
75 mph or Less
RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



WZ (RS-1b)
75 mph or Less
RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Removal of the Temporary Rumble Strips should be accomplished before removing the advance warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an AFAD or a portable traffic signal.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment.

Speed	Approximate distance between strips in an Array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
> 55 MPH	20'

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40	L = WS	265'	295'	320'	40'	80'	240'	155'
45		450'	495'	540'	45'	90'	320'	195'
50	L = WS	500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60	L = WS	600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	L = WS	700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

Texas Department of Transportation
 Traffic Operations Division Standard





TEMPORARY RUMBLE STRIPS

WZ (RS) - 16

FILE: wzrs16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
2-14	DIST	COUNTY	SHEET NO.	
4-16	FTW	TARRANT	39	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units, or for any errors, omissions, or damages resulting from its use.

DATE: 1/25/2021 4:01:45 PM
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM 2871 From IH20 to FAT\B...
 T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM 2871 From IH20 to FAT\B...



DEPARTMENTAL MATERIAL SPECIFICATIONS			
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240		
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241		
SIGN FACE MATERIALS	DMS-8300		
COLOR	USAGE	SHEETING MATERIAL	
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING	
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING	

- GENERAL NOTES**
- If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
 - UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
 - NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
 - Signs shall be spaced at the distances recommended as per BC standards.
 - Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
 - Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
 - Short term markings shall not be used to simulate edge lines.
 - All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1		
Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"

Texas Department of Transportation Traffic Operations Division Standard


SIGNING FOR UNEVEN LANES

WZ(UL) - 13


FILE: wzu1-13.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	APRIL 1992	CONT. 2855 01	SECT. 023	JOB. RM 2871
8-95 2-98 7-13		DIST. COUNTY		SHEET NO.
1-97 3-03		FTW TARRANT		40

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of any information or for any damages resulting from its use.

DATE: 1/25/2021 4:01:56 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_A1B6_0809-5-1-08.dwg



ROAD CLOSURE BEYOND THE INTERSECTION
 Signing for a Numbered Route with an Off-Site Detour



ROAD CLOSURE AT THE INTERSECTION
 Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "x" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

GENERAL NOTES


1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.



WORK ZONE ROAD CLOSURE DETAILS


WZ (RCD) - 13

FILE: wzrcd-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
1-97 4-98 7-13	DIST	COUNTY	SHEET NO.	
2-98 3-03	FTW	TARRANT	41	



SURFACE - MILL 2" AND 3" HMAC OVERLAY - 3" SPC

1/25/2021 4:02:49 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\HMAC LAYOUT.dgn



DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 1 OF 4




ROADWAY LAYOUT

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	42




1/25/2021 4:02:57 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\HMAC LAYOUT.dgn



DRIVEWAY #2
 DRIVEWAYS (ACP)
 STA 231+35 (150 SY)
 SEE HMAC DRIVEWAY DETAILS



SURFACE - MILL 2" AND 3" HMAC OVERLAY - 3" SPC




DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 2 OF 4




ROADWAY LAYOUT

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	43



GENERAL NOTES

* FOR CONTRACTORS INFORMATION



WEDGE MILL AT CONCRETE DRIVEWAY - AND 3" HMAC OVERLAY - 3" SPC




SURFACE - MILL 2" AND 3" HMAC OVERLAY - 3" SPC



SURFACE AND REHAB - MILL 6" AND 7" HMAC OVERLAY - 3" SPC OVER 4" D-GR B MIX



WIDEN SHDR - SUBGRADE WIDENING 11" DEEP AND 11" HMAC OVERLAY - 3" SPC OVER 2 LIFTS OF 4" D-GR B MIX



DocuSigned by:
Jeremy Arreguin
C8E51DD82649440...
1/25/2021

SCALE: NONE
SHEET 3 OF 4




ROADWAY LAYOUT


CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	44

1/25/2021 4:03:05 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\HMAC LAYOUT.dgn

1/25/2021 4:03:16 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\HMAC LAYOUT.dgn



- SURFACE - MILL 2" AND 3" HMAC OVERLAY - 3" SPC
- SURFACE AND REHAB - MILL 6" AND 7" HMAC OVERLAY - 3" SPC OVER 4" D-GR B MIX
- WIDEN SHDR - SUBGRADE WIDENING 11" DEEP AND 11" HMAC OVERLAY - 3" SPC OVER 2 LIFTS OF 4" D-GR B MIX



DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

©2021 by Texas Department of Transportation; all rights reserved


SCALE: NONE
 SHEET 4 OF 4

ROADWAY LAYOUT

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	45

1/25/2021 4:03:30 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\LONGITUDINAL PAVEMENT JOINT DETAIL.dgn


DW: CJK: DMF: CJK:



**EXTRUDED TAPERED LONGITUDINAL
HOT MIX JOINT DETAIL**

NOTE.

1. COMPACT TAPER WITH A SMALL STATIC STEEL-WHEEL ROLLER OR PNEUMATIC ROLLER.
2. APPLY A UNIFORM AMOUNT OF TACK COAT TO ALL VERTICAL SURFACES PRIOR TO PAVING ADJACENT AREA.
3. APPLY TACK COAT TO WEDGE (TAPERED PORTION) WHEN CONSTRUCTED PAVEMENT HAS BEEN OPEN TO TRAFFIC FOR A SIGNIFICANT AMOUNT OF TIME.



DocuSigned by:
Jeremy Arreguin
C8E51DD82649440...
1/25/2021


SCALE: NONE
SHEET 1 OF 1



**LONGITUDINAL
PAVEMENT JOINT
DETAILS**





CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	46

C:\p\11111111\11111111.dwg
 Date: 1/25/2021 4:03:45 PM
 T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Alledo Rd\05-Roadway\PAVEMENT TRANSITION DETAILS.dgn



NOTES

- 2" PLANING AND (3" TO 2") TRANSITION PLANING SHALL BE PAID UNDER ITEM 0354-6003 PLAN & TEXT ASPH CONC PAV (0" TO 3")



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021


SCALE: NONE
 SHEET 1 OF 1



PAVEMENT TRANSITION DETAILS

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	47	

1/25/2021 4:04:05 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\HMAC DRIVEWAY DETAIL.dgn







G1 = FIRST GRADE (ROADWAY) (%)
 G2 = SECOND GRADE (DRIVEWAY) (%)
 A = CHANGE IN GRADE BETWEEN G1 AND G2 (%)
 MAXIMUM A = 10% PRIVATE DRIVEWAYS, 8% OTHER DRIVEWAYS

GENERAL NOTES

IN LIEU OF MILLING, CONTRACTOR MAY CHOOSE MEANS TO GRADE DRIVEWAY TO ROADWAY TRANSITION (3" TO 2") AS APPROVED BY THE ENGINEER'S REPRESENTATIVE.

HOWEVER, ANY MILLING, GRADING, REMOVAL OF OR HAULING OFF OF MATERIAL, ETC. TO CONSTRUCT DRIVEWAY AND TRANSITION UNTO ROADWAY SHALL BE CONSIDERED SUBSIDIARY TO ITEM 530

CONTRACTOR SHALL PROVIDE A SMOOTH TRANSITION FROM DRIVEWAY ONTO ROADWAY



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...

1/25/2021




SCALE: NONE
 SHEET 1 OF 1




HMAC DRIVEWAY DETAILS

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	48	

1/25/2021 4:04:25 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\WEDGE MILL AT CONCRETE DRIVEWAYS.dgn



GENERAL NOTES
THE INTENT OF THIS DETAIL IS TO PROVIDE A FLUSH DRIVEWAY TRANSITION ONTO THE PAVEMENT SURFACE




DocuSigned by:
Jeremy Arreguin
C8E51DD82649440...
1/25/2021

SCALE: NONE
SHEET 1 OF 1

<h3>WEDGE MILL AT CONCRETE DRIVEWAYS</h3>			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	49


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\06-Standards\TE (HMAC)-11.dgn



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS


CONDITION - 1
 THIN HMAC SURFACES OR HMAC OVERLAY
 WITH THICKNESS OF 2.5" OR LESS



** EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 2
 OVERLAY OF EXISTING PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 3
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 4
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 5" OR GREATER


GENERAL NOTES

- UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
- FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
- PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
- THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
- THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

(NOT TO SCALE)

				Design Division Standard	
TAPERED EDGE DETAILS HMAC PAVEMENT					
TE (HMAC) - 11					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS		2855 01	023	RM 2871	
DIST	COUNTY	SHEET NO.			
FTW	TARRANT	50			

1/25/2021 4:33:22 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\STRIPING LAYOUT.dgn




LEGEND			
SYMBOL	DESCRIPTION	ITEM NO	SHORT
A	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	0666 6303	4" W SLD
B	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	0666 6315	4" Y SLD
C	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	0666 6030	8" W DOT
D	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	0666 6036	8" W SLD
E	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	0666 6048	24" W SLD
F	REFL PAV MRK TY I (W) (ARROW) (100MIL)	0666 6054	ARROW
G	REFL PAV MRK TY I (W) (WORD) (100MIL)	0666 6078	WORD
H	REFL PAV MRK TY I (W) (RR XING) (100MIL)	0666 6093	RR XING

GENERAL NOTES

ALL STRIPING SHALL CONFORM TO CURRENT PM STANDARD SHEETS AND CURRENT TMUTCD

STRIPING NOTES


- DOUBLE YELLOW
- SEE PM STANDARD SHEETS FOR RAISED PAVEMENT MARKER DETAILS AND SPACING



PROPOSED STRIPING SECTION E-E
 STA 219+35 TO STA 246+15
 STA 261+05 TO STA 265+50

* SHOULDER WIDTH MAY VARY SLIGHTLY

** DOUBLE YELLOW CENTERLINE. SEE PM STANDARD SHEETS FOR RPM



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021


SCALE: NONE
 SHEET 1 OF 4



STRIPING LAYOUT

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	51	


1/25/2021 4:33:29 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\STRIPING LAYOUT.dgn



LEGEND			
SYMBOL	DESCRIPTION	ITEM NO	SHORT
A	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	0666 6303	4" W SLD
B	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	0666 6315	4" Y SLD
C	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	0666 6030	8" W DOT
D	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	0666 6036	8" W SLD
E	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	0666 6048	24" W SLD
F	REFL PAV MRK TY I (W) (ARROW) (100MIL)	0666 6054	ARROW
G	REFL PAV MRK TY I (W) (WORD) (100MIL)	0666 6078	WORD
H	REFL PAV MRK TY I (W) (RR XING) (100MIL)	0666 6093	RR XING

GENERAL NOTES
 ALL STRIPING SHALL CONFORM TO CURRENT PM STANDARD SHEETS AND CURRENT TMUTCD

- STRIPING NOTES**
- DOUBLE YELLOW
 - SEE PM STANDARD SHEETS FOR RAISED PAVEMENT MARKER DETAILS AND SPACING




DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 2 OF 4

<h2>STRIPING LAYOUT</h2>			
CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT		COUNTY	SHEET NO.
FTW		TARRANT	52

1/25/2021 4:33:36 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\STRIPING LAYOUT.dgn




LEGEND			
SYMBOL	DESCRIPTION	ITEM NO	SHORT
A	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	0666 6303	4" W SLD
B	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	0666 6315	4" Y SLD
C	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	0666 6030	8" W DOT
D	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	0666 6036	8" W SLD
E	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	0666 6048	24" W SLD
F	REFL PAV MRK TY I (W) (ARROW) (100MIL)	0666 6054	ARROW
G	REFL PAV MRK TY I (W) (WORD) (100MIL)	0666 6078	WORD
H	REFL PAV MRK TY I (W) (RR XING) (100MIL)	0666 6093	RR XING

GENERAL NOTES

ALL STRIPING SHALL CONFORM TO CURRENT PM STANDARD SHEETS AND CURRENT TMUTCD


STRIPING NOTES

- DOUBLE YELLOW
- SEE PM STANDARD SHEETS FOR RAISED PAVEMENT MARKER DETAILS AND SPACING



FLUSH MEDIAN STRIPING DETAIL

SEE FLUSH MEDIAN STRIPING DETAIL



DocuSigned by:
Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021


SCALE: NONE
 SHEET 3 OF 4



STRIPING LAYOUT

CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	53	


1/25/2021 4:33:42 PM T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\05-Roadway\STRIPING LAYOUT.dgn



LEGEND			
SYMBOL	DESCRIPTION	ITEM NO	SHORT
A	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	0666 6303	4" W SLD
B	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	0666 6315	4" Y SLD
C	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	0666 6030	8" W DOT
D	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	0666 6036	8" W SLD
E	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	0666 6048	24" W SLD
F	REFL PAV MRK TY I (W) (ARROW) (100MIL)	0666 6054	ARROW
G	REFL PAV MRK TY I (W) (WORD) (100MIL)	0666 6078	WORD
H	REFL PAV MRK TY I (W) (RR XING) (100MIL)	0666 6093	RR XING

GENERAL NOTES
 ALL STRIPING SHALL CONFORM TO CURRENT PM STANDARD SHEETS AND CURRENT TMUTCD

STRIPING NOTES
 1. DOUBLE YELLOW
 2. SEE PM STANDARD SHEETS FOR RAISED PAVEMENT MARKER DETAILS AND SPACING



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

SCALE: NONE
 SHEET 4 OF 4




STRIPING LAYOUT


CONTROL	SECTION	JOB	HIGHWAY
2855	01	023	RM 2871
DISTRICT	COUNTY	SHEET NO.	
FTW	TARRANT	54	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.


DATE: 1/25/2021 4:05:51 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to ATB\2855-01-023.dgn




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown in the plans or as directed by the Engineer.

GENERAL NOTES

- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1) - 20


FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	2855	01	023	RM 2871
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	FTW	TARRANT		55

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from a previous edition of this standard. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from a previous edition of this standard.




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)




Type II (Top View)




RAISED PAVEMENT MARKERS

GENERAL NOTES

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



**REFLECTORIZED PROFILE
PATTERN DETAIL
USING REFLECTIVE PROFILE PAVEMENT MARKINGS**



NOTE
Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.


Texas Department of Transportation
 Traffic Safety Division Standard

POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	2855	01	023	RM 2871
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	FTW	TARRANT		56

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any project. TxDOT is not responsible for any errors or omissions in this standard or for any damages resulting from its use.

DATE: 1/25/2021 4:06:15 PM
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871 From IH20 to FAT\Bldg\2855-01-023_RM_2871.dgn



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

LANE REDUCTION

NOTES


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE




TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS



DETAIL A


DETAIL B

Texas Department of Transportation
 Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 20


FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
5-00 2-10	DIST	COUNTY	SHEET NO.	
8-00 2-12	FTW	TARRANT		57
3-03 6-20				

10/25/2021
 T:\E\CAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20 to Aledo Rd\06-Standards_EC(1)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES


1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	2855	01	023	RM 2871	
	DIST	COUNTY	SHEET NO.		
	FTW	TARRANT	58		

DATE: 1/25/2021
 FILE: I:\STCAO Files\STCAO Design\Projects\2855-01-023_RM_2871_From_IH20_to_Aledo_Rd\06-Standards\EC(3)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



PLAN VIEW




ELEVATION VIEW


**CONSTRUCTION EXIT (TYPE 1)
ROCK CONSTRUCTION (LONG TERM)**

GENERAL NOTES (TYPE 1)

- The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
- The coarse aggregate should be open graded with a size of 4" to 8".
- The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other materials approved by the Engineer.
- The construction exit shall be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




ELEVATION VIEW


**CONSTRUCTION EXIT (TYPE 2)
TIMBER CONSTRUCTION (LONG TERM)**

GENERAL NOTES (TYPE 2)

- The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50'.
- The treated timber planks shall be attached to the railroad ties with 1/2" x 6" min. lag bolts. Other fasteners may be used as approved by the Engineer.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The approach transitions shall be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- The construction exit should be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




**SECTION A-A
CONSTRUCTION EXIT (TYPE 3)
SHORT TERM**

GENERAL NOTES (TYPE 3)


- The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
- The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES CONSTRUCTION EXITS EC(3)-16			
FILE: ec316	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	2855	01	023
DIST	COUNTY		SHEET NO.
DSR	TARRANT		59

DATE: 1/25/2021
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\06-Standards\EC(9)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



PLAN VIEW




SECTION A-A
EROSION CONTROL LOG DAM


CL-D

LEGEND

- CL-D EROSION CONTROL LOG DAM
- CL-BOC EROSION CONTROL LOG AT BACK OF CURB
- CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
- CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
- CL-DI EROSION CONTROL LOG AT DROP INLET
- CL-CI EROSION CONTROL LOG AT CURB INLET
- CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET




PLAN VIEW




SECTION B-B
EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



REBAR STAKE DETAIL




PLAN VIEW



SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

- GENERAL NOTES:**
1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
 3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
 4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
 5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
 6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
 7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
 8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
 9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3


TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES
EROSION CONTROL LOG
EC (9) - 16

FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
	DIST	COUNTY	SHEET NO.	
	FTW	TARRANT	60	

Design Division Standard


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/25/2021
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\06-Standards\EC(9)-16.dgn



**EROSION CONTROL LOGS ON SLOPES
STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




**EROSION CONTROL LOGS ON SLOPES
STAKE AND LASHING ANCHORING**

CL-SSL



STAKE AND TRENCHING ANCHORING DETAIL


CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL

LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"



STAKE NOTCH DETAIL




SHEET 2 OF 3

Design Division Standard

**TEMPORARY EROSION,
 SEDIMENT AND WATER
 POLLUTION CONTROL MEASURES
 EROSION CONTROL LOG
 EC(9) - 16**


FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	2855	01	023	RM 2871
	DIST	COUNTY	SHEET NO.	
	FTW	TARRANT	61	

DATE: 1/25/2021
 FILE: T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\06-Standards\EC(9)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET



CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	2855 01	023	RM 2871
	DIST	COUNTY	SHEET NO.
	FTW	TARRANT	62

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.
2.
 No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
 Individual 404 Permit Required
 Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.
2.
3.
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input checked="" type="checkbox"/> Erosion Control Logs	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

During construction, efforts would be taken to avoid and minimize disturbance of vegetation and soils. Areas within the existing ROW, but outside the limits of construction, would not be disturbed. Every effort would be made to preserve trees where they would neither compromise safety nor substantially interfere with the proposed projects.

No landscaping would be a part of the proposed project activities. Re-vegetation of disturbed areas would be in compliance with the Executive Memorandum on Beneficial Landscaping (26Apr94) and the Executive Order on Invasive Species (EO 13112). Regionally native and non-invasive plants would be used to the extent practicable in landscaping and re-vegetation.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required Required Action

No disturbing, destroying, or removing active nests of Bald Eagles, including ground nesting birds, during the nesting season. Avoid the removal of unoccupied, inactive nests as practicable. Prevent the establishment of active nests during the nesting season on TxDOT owned and operated facilities and structures proposed for replacement or repair. No collecting, capturing, relocating or transporting birds, eggs, young or active nests without permit. The Eagle Protection Act prohibits the taking or possession of and commerce in eagles, parts, feathers, nests, or eggs with limited exceptions. The definition of take includes pursue, shoot, shoot at, poison, wound, kill, capture, trap, collect, molest or disturb. Eagles may not be taken for any purpose unless a permit is issued prior to the taking.

Between October 1 and February 15, the contractor would remove all old migratory bird nests from any structure that would be affected by the proposed project, and complete any bridge work/demolition and/or vegetation clearing. In addition, the contractor would be prepared to prevent migratory birds from building nests by utilizing nest prevention methods, such as bird-deterrent netting and bird-repelling sprays and/or gels, between February 15 and October 1. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young would be avoided.

The contractor and/or TxDOT personnel would be advised of the potential for Whooping Cranes to occur within the project limits. Construction personnel would be advised to avoid adverse impacts to this species and to report any sightings to TxDOT District Environmental staff. Drainage modifications would be limited to the extent practical to accommodate the additional paved surface needed to bring the roadway up to current TxDOT safety standards. The construction personnel would report all sightings to TxDOT Fort Worth District Environmental staff. Reports should include the time, date and location and any available photos.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

1.
2.
3.


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action No.

1.
2.
3.

 Texas Department of Transportation		Design Division Standard	
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC			
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (DS) REVISIONS	2855	01	023
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	FTW	TARRANT	63

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

http://www.dot.state.tx.us/ftw/specinfo/standard.htm
 1/25/2021 4:07:46 PM
 T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\06-Standards\SW3P.dgn

A. GENERAL SITE DATA

1. PROJECT LIMITS: IH 30 WB EXIT CONNECTOR ("F") TO IH 820 NB

LATTITUDE: 32.7381162 LONGITUDE: -97.4820508

2. PROJECT SITE MAPS:

- * Project Location Map: Title Sheet (Sheet 1)
- * Drainage Patterns: Drainage Area Maps N/A
- * Approx. Slopes Anticipated After Major Gradings and Areas of Soil Disturbance: Typical Sections 3:1 (VARIES)
- * Major Controls and Locations of Stabilization Practices: SW3P Site Map Sheets
- * Project Specific Locations: To be specified by Project Field Office and located in the Project SW3P File
- * Surface Waters and Discharge Locations: Drainage and Culvert Layout Sheets N/A

3. PROJECT DESCRIPTION:

FOR THE CONSTRUCTION OF OVERLAY WORK CONSISTING OF PLANING, HOT MIX ASPHALT AND PAVEMENT MARKINGS

4. MAJOR SOIL DISTURBING ACTIVITIES:

REMOVE APPROXIMATELY 12" OF TOP SOIL AND VEGETATION TO PREPARE FOR SUBGRADE WIDENING OVER APPROXIMATELY 4 STATIONS

5. EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

(Provide description of soil condition, vegetative cover and percentage)

6. TOTAL PROJECT AREA: 12 ACRES Acres

7. TOTAL AREA TO BE DISTURBED: 0.092 Acres (0.77% OF TOTAL PROJECT AREA)

8. WEIGHTED RUNOFF COEFFICIENT

BEFORE CONSTRUCTION: N/A
AFTER CONSTRUCTION: N/A

9. NAME OF RECEIVING WATERS:

N/A

10. ENDANGERED SPECIES, DESIGNATED CRITICAL HABITAT AND HISTORIC PROPERTY:

SEE EPIC SHEET FOR IDENTIFIED WILDLIFE

The documentation satisfying TPDES Construction General Permit eligibility pertaining to the existence or of any protective action taken with regards to endangered species or designated critical habitat or historical property in this project area is contained in the project's Environmental document (EA or EIS) and can be viewed under the State Open Records Act at the address shown below:

TEXAS DEPARTMENT OF TRANSPORTATION
 FORT WORTH DISTRICT HEADQUARTERS
 DISTRICT DESIGN SECTION
 2501 SW LOOP
 FORT WORTH, TX 76133
 PHONE: 817-370-6500

B. EROSION AND SEDIMENT CONTROLS

1. SOIL STABILIZATION PRACTICES:

(Select T = Temporary or P = Permanent, as applicable)

- | | |
|--|--|
| <input type="checkbox"/> TEMPORARY SEEDING | <input type="checkbox"/> PRESERVATION OF NATURAL RESOURCES |
| <input type="checkbox"/> MULCHING (Hay or Straw) | <input type="checkbox"/> FLEXIBLE CHANNEL LINER |
| <input type="checkbox"/> BUFFER ZONES | <input type="checkbox"/> RIGID CHANNEL LINER |
| <input type="checkbox"/> PLANTING | <input type="checkbox"/> SOIL RETENTION BLANKET |
| <input type="checkbox"/> SEEDING | <input type="checkbox"/> COMPOST MANUFACTURED TOPSOIL |
| <input type="checkbox"/> SODDING | <input type="checkbox"/> OTHER: (Specify Practice) |

2. STRUCTURAL PRACTICES:

(Select T = Temporary or P = Permanent, as applicable)

- | | |
|---|---|
| <input checked="" type="checkbox"/> SILT FENCES | <input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER DIKES |
| <input type="checkbox"/> HAY BALES | <input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER SWALES |
| <input type="checkbox"/> ROCK FILTER DAMS | <input type="checkbox"/> DIVERSION DIKE AND SWALE COMBINATIONS |
| <input type="checkbox"/> PIPE SLOPE DRAINS | <input checked="" type="checkbox"/> ROCK BEDDING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> PAVED FLUMES | <input type="checkbox"/> TIMBER MATTING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> CHANNEL LINERS | <input type="checkbox"/> STONE OUTLET STRUCTURES |
| <input type="checkbox"/> SEDIMENT TRAPS | <input type="checkbox"/> VELOCITY CONTROL DEVICES |
| <input type="checkbox"/> SEDIMENT BASINS | <input type="checkbox"/> CURBS AND GUTTERS |
| <input type="checkbox"/> STORM SEWERS | <input type="checkbox"/> STORM INLET SEDIMENT TRAP |
| <input type="checkbox"/> OTHER: SANDBAGS | |
| <input checked="" type="checkbox"/> OTHER: BIODEG EROSN CONT LOGS | |

3. STORM WATER MANAGEMENT:


Storm water drainage will be provided by existing drainage features

4. STORM WATER MANAGEMENT ACTIVITIES: (Sequence of Construction)

CONTRACTOR SHALL PROTECT ALL EXISTING DRAINAGE ENTRANCES OR ENTRIES TO ANY RECEIVING WATERS WITHIN THE PROJECT LIMITS FROM SEDIMENT ENTRY AS A RESULT OF CONSTRUCTION OPERATIONS REGARDLESS WHETHER SHOWN ON THE PLANS OR NOT. ADDITIONAL SEDIMENTATION OR EROSION CONTROL MEASURES SHALL BE AS DIRECTED BY THE ENGINEER.

5. NON-STORM WATER DISCHARGES:

Non-storm water discharges should be filtered, or held in retention basins, before being allowed to mix with storm water. These discharges consist of non-polluted ground water, spring water, foundation and/or footing drain water, and water used for dust control, pavement washing and vehicle washwater containing no detergents.



DocuSigned by:

Jeremy Arreguin

CBE51DD82649440...

1/25/2021

		Fort Worth District Standard	
<h3>STORM WATER POLLUTION PREVENTION PLAN (SW3P)</h3>			
SHEET 1 OF 2 SHEETS			
ORIGINAL DRAWING: 09/2002	sw3p-ftw.dgn	FED. RD. DIV. NO. 6	PROJECT NO.
DATE	REVISIONS	6	SHEET NO. 64
09/2008	NPDES TO TPDES	STATE	COUNTY
01/2012	CLARIFY NOTE C.2.	TEXAS	FTW TARRANT
08/2013	ADDED SIGN	CONT.	SECT.
05/2019	2-SHEET FORMAT	2855	01 023
		JOB	HIGHWAY NO.
			RM 2871

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE TEXAS ENGINEERING PRACTICE ACT. NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

http://www.dot.state.tx.us/ftw/specinfo/standard.htm
 1/25/2021 4:07:51 PM
 T:\STCAO Files\STCAO Design\Projects\2855-01-023 RM 2871 From IH20 to Aledo Rd\06-Standards\SW3P.dgn

C. OTHER REQUIREMENTS & PRACTICES

1. MAINTENANCE:

All erosion and sediment controls shall be maintained in good working order. If a repair is necessary, it shall be performed at the earliest date possible but no later than 7 calendar days after the surrounding exposed ground has dried sufficiently to prevent further damage from heavy equipment. Disturbed areas on which construction activities have ceased, temporarily or permanently, shall be stabilized within 14 calendar days unless they are scheduled to and do resume within 21 calendar days. The areas adjacent to creeks and drainageways shall have priority followed by devices protecting storm sewer inlets.

2. INSPECTION:

An inspection shall be performed by a TxDOT Inspector every 14 calendar days as well as within 24 hours after any rainfall of one-half inch or more is recorded on a non-freezing rain gauge to be located at the project site, or every 7 calendar days. An Inspection and Maintenance Report shall be filed for each inspection. Based on the inspection results, the controls shall be revised in accordance with the inspection report.

3. WASTE MATERIALS:

Except as noted below, all waste materials shall be collected in a metal dumpster having a secure cover. The dumpster shall meet all state and local solid waste management regulations. All trash and debris from construction shall be deposited in the dumpster. The dumpster shall be emptied, as necessary or as required by local regulation, and hauled to a local approved land fill site. The burying of construction waste on the project site shall not be permitted.

Concrete washout areas shall be required and shall consist of a pit, lined with an impervious material, of sufficient size to contain, until evaporation, all water used and washout material produced during concrete washout operations. The concrete washout locations shall be as directed by the engineer.

Lime slaking tanks shall be surrounded by an earthen berm, capable of containing any overflow.

4. HAZARDOUS WASTE (INCLUDING SPILL REPORTING):

As a minimum, any products in the following categories are considered to be hazardous: paints, acids, solvents, asphalt products, chemical additives for soil stabilization, and concrete curing compounds or additives. In the event of a spill which may be hazardous, the spill coordinator shall be contacted immediately.

5. SANITARY WASTE:

All sanitary waste shall be collected from the portable units, as necessary or as required by local regulation, by a licensed sanitary waste management contractor.

6. OFFSITE VEHICLE TRACKING:

The Contractor shall be required, on a regular basis or as may be directed by the Engineer, to dampen haul roads for dust control, stabilize construction entrances and to remove excess dirt from the roadway.


7. MANAGEMENT PRACTICES:

1. Disposal areas, stockpiles and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, waterbody or streambed.
2. Construction staging areas and vehicle maintenance areas shall be constructed by the Contractor in a manner to minimize the runoff of pollutants.
3. All temporary fills placed in waterways shall be built of erosion resistant material. (NWP 14)
4. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.


8. OTHER:

1. Listing of construction materials stored on site to be provided by Project Field Office.
2. The Project SW3P File located at the project field office shall contain the N.O.I., CGP Coverage Notice, TCEQ TPDES Form, Signature Authorization, Certification/Qualification Statements, Inspection Reports, Required Maps, and a copy of the TPDES General Permit No. TXRI50000.

STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING



No Permanent Installation Allowed.
 Sign to be Removed After Project Completion.



DocuSigned by:
 Jeremy Arreguin
 C8E51DD82649440...
 1/25/2021

		Fort Worth District Standard	
<h2>STORM WATER POLLUTION PREVENTION PLAN (SW3P)</h2>			
		SHEET 2 OF 2 SHEETS	
ORIGINAL DRAWING: 09/2002 sw3p-ftw.dgn	FED. RD. DIV. NO.: 6	PROJECT NO.: 2855 01 023 RM 2871	
DATE: 09/2008 01/2012 08/2013 05/2019	REVISIONS: NPDES TO TPDES CLARIFY NOTE C.2. ADDED SIGN 2-SHEET FORMAT	STATE DIST. NO.: TEXAS FTW	COUNTY: TARRANT
	CONT.: 2855	SECT.: 01	JOB: 023
		HIGHWAY NO.: RM 2871	SHEET NO.: 65

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

DOT #: 839 210 L
 Crossing Type: ****AT GRADE CROSSING**
 RR Company Owning Track at Crossing: UP
 Operating RR Company at Track: UP
 RR MP: 257.130
 RR Subdivision: BAIRD
 City: BENBROOK
 County: TARRANT
 CSJ at this Crossing: 2855-01-023
 Highway/Roadway name crossing the railroad: RM 2871
 # of regularly scheduled trains per day at this crossing: 20
 # of switching movements per day at this crossing: 0
 % of estimated contract cost of work within railroad ROW: 1.0%

Scope of Work at this Crossing to Be Performed by State Contractor:
Traffic control on roadway approaches to RM 2871,
from IH20 WB to Aledo Road.

Scope of Work at this Crossing to Be Performed by Railroad Company:
None

** Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian, or Closed/Abandoned

II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)

None

III. FLAGGING & INSPECTION

of Days of Railroad Flagging Expected: 33
 On this project, night or weekend flagging is:
 Expected
 Not Expected
 Flagging services will be provided by:
 Railroad Company: TxDOT will pay flagging invoices
 Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT
 Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30 day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:
 UPRR - UP.info@railpros.com
 Call Center 877-315-0513, Select #1 for flagging
 BNSF - BNSF.info@railpros.com
 Call Center 877-315-0513, Select #1 for flagging
 KCS - KCS.info@railpros.com
 Call Center 877-315-0513, Select #1 for flagging
 - Bottom Line On-Track Safety Services
 bottomline076@aol.com, 903-767-7630
 OTHERS RAILPROS
877-315-0513

Contractor must incorporate Construction Inspection into anticipated construction schedule.

Not Required
 Required: Contact Information for Construction Inspection:

IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

On this project, construction work to be performed by a railroad company is:
 Required
 Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

V. RAILROAD INSURANCE REQUIREMENTS

Railroad reference number shall be provided by TxDOT CST or DO.
 The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.
 Insurance policies must be issued for and on behalf of the Railroad. Where more than one Railroad Company is operating on the same right of way or where several Railroad Companies are involved and operate on their own separate rights of way, provide separate insurance policies in the name of each Railroad Company.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$2,000,000 / \$4,000,000
Business Automobile	\$2,000,000 combined single limit
Railroad Protective Liability	
<input type="checkbox"/> Not Required	
<input checked="" type="checkbox"/> Non - Bridge Projects	\$2,000,000 / \$6,000,000
<input type="checkbox"/> Bridge Projects	\$5,000,000 / \$10,000,000
<input type="checkbox"/> Other	

VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT

On this project, an ROE agreement is:
 Not Required
 Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)
 Required: Contractor to obtain (see Item 5, Article 8.4)
 With the following railroad companies: _____

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

<http://www.txdot.gov/inside-txdot/division/rail/samples.html>

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed ROE agreement between the Contractor and the Railroad if required on project.

VII. RAILROAD COORDINATION MEETING

On this project, a Railroad Coordination Meeting is:
 Not Required
 Required


See Item 5, Article 8.1 for more details.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are required to maintain the same insurance coverage as required of the Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
 Call Union Pacific Railroad Emergency Line
 at 888-877-7267
 Location: DOT# 839-210 L
 RR Milepost 257.130, Baird Subdivision

 Texas Department of Transportation				Rail Division	
RAILROAD SCOPE OF WORK PROJECT SPECIFIC DETAILS					
FILE:	RR Scope of Work.dgn	DN: TxDOT	CK:	DW:	CK:
© TxDOT	June 2014	CONT SECT	JOB	HIGHWAY	
REVISIONS		2855 01	023	RM 2871	
3/2020		DIST	COUNTY	SHEET NO.	
		2	TARRANT	66	

DATE:
FILE:

PART 1 - GENERAL

1.01 DESCRIPTION

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

1.02 REQUEST FOR INFORMATION / CLARIFICATION

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

1.03 PLANS / SPECIFICATIONS

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

PART 2 - UTILITIES AND FIBER OPTIC

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

PART 3 - CONSTRUCTION

3.01 GENERAL

- A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.
- B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.
- C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.
- D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.
- E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.
- F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.
- G. All permanent clearances shall be verified before project closing.

3.02 RAILROAD OPERATIONS

- A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.
- B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.
- C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:
 - 1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.
 - 2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES

- A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.
- B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.
- C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.
- D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
 - 1. Exactly what the work entails.
 - 2. The days and hours that work will be performed.
 - 3. The exact location of work, and proximity to the tracks.
 - 4. The type of window requested and the amount of time requested.
 - 5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.
- E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

3.04 INSURANCE

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

3.05 RAILROAD SAFETY ORIENTATION

- A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."
- B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

3.06 COOPERATION

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.



3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES

Abide by the following minimum temporary clearances during the course of construction:
 A. 15' - 0" (BNSF) (UPRR) and 14' - 0" (KCS) horizontal from centerline of track
 B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

3.08 APPROVAL OF REDUCED CLEARANCES

- A. Maintain minimum track clearances during construction as specified in Section 3.07.
- B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.
- C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

 Texas Department of Transportation		 Rail Division	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS			
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT October 2018	CONT	SECT	JOB
REVISIONS March 2020	2855 01	023	RM 2871
	DIST	COUNTY	SHEET NO.
	2	TARRANT	67

3.09 MAINTENANCE OF RAILROAD FACILITIES

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractor's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
 1. Pre-construction meetings.
 2. Pile driving/drilling of caissons or drilled shafts.
 3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
 4. Erection of precast concrete or steel bridge superstructure.
 5. Placement of waterproofing (prior to placing ballast on bridge deck).
 6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

3.11 RAILROAD REPRESENTATIVES

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

3.12 COMMUNICATIONS AND SIGNAL LINES

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

3.13 TRAFFIC CONTROL

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193
7:00 AM to 9:00 PM CST Monday-Friday except holidays,
staffed 24 hrs/day for emergencies
48 hrs notice required

BNSF 1-800-533-2891
24 hour number
5 working days notice required

KCS 1-800-344-8377
Texas One Call, a 24 hour number
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.


- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

3.15 RAILROAD FLAGGING

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

3.16 CLEANING OF RIGHT-OF-WAY

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

 Texas Department of Transportation				Rail Division	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE#	DN# TxDOT	CK# TxDOT	DW# TxDOT	CK# TxDOT	
©TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS	285501	023	RM	2871	
March 2020	DIST	COUNTY	SHEET NO.		
	2	TARRANT	68		