

FINAL PLANS

NAME OF CONTRACTOR: _____
 DATE OF LETTING: _____
 DATE WORK BEGAN: _____
 DATE WORK COMPLETED: _____
 DATE WORK ACCEPTED: _____
 SUMMARY OF CHANGE ORDERS:

STATE OF TEXAS
 DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
 STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT

F 2021 (790), ETC.
 CSJ: 1012-02-042, ETC.

FM 545
COLLIN COUNTY

DESIGN CY	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	F 2021 (790), ETC.		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	1
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DESIGN SPEED = 40 MPH
 FUNCTIONAL CLASSIFICATION = RURAL MAJOR COLLECTOR

ADT = 2,821 (2020)
 3,831 (2040)

LIMITS: CSJ: 1012-02-036 2.689 MI.
 FROM 0.073 MI WEST OF OLD VALDASTA RD
 TO 0.040 MI EAST OF FM 1377

LIMITS: CSJ: 1012-02-037 3.680 MI.
 FROM 0.012 MI W OF FM 2933
 TO 0.103 MI EAST OF CR 1095

LIMITS: CSJ: 1012-02-038 0.736 MI.
 FROM 0.026 MI EAST OF L'HOTE LANE
 TO BS 78D


LIMITS: CSJ: 1012-02-042 9.196 MI.
 FROM FM 2933
 TO BS 78D

NOTE:
 SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,
 NOVEMBER 1, 2014, AND THE CONTRACT PROVISIONS LISTED AND DATED AS
 FOLLOWS SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS
 FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY 1,
 2012)

TOTAL LENGTH OF PROJECT =

ROADWAY	= 47,442.58 FT.	= 8.985 MI.
BRIDGE	= 1,111.92 FT.	= 0.211 MI.
TOTAL	= 48,554.50 FT.	= 9.196 MI.

FOR THE CONSTRUCTION OF: RER - REHABILITATION OF EXISTING ROAD (1012-02-042)
 SFT - SAFETY IMPROVEMENT PROJECTS (1012-02-036, 037, 038)
 CONSISTING OF: REWORK BASE AND OVERLAY (1012-02-042); PROVIDE ADDITIONAL PAVED SURFACE WIDTH,
 MILLED EDGELINE RUMBLE STRIPS, MILLED CENTERLINE RUMBLE STRIPS (1012-02-036, 037, 038)



TEXAS DEPARTMENT OF TRANSPORTATION


SUBMITTED FOR LETTING 4/26/2021
 _____, P.E.
 DESIGN ENGINEER

RECOMMENDED FOR LETTING 4/26/2021
 _____, P.E.
 DIRECTOR OF TRANSPORTATION PLANNING & DEVELOPMENT

RECOMMENDED FOR LETTING 4/26/2021
 _____, P.E.
 DESIGN ENGINEER

APPROVED FOR LETTING 4/27/2021
 _____, P.E.
 DISTRICT ENGINEER

WORK WAS COMPLETED ACCORDING TO THE PLANS AND CONTRACT.
 _____, P.E.
 Signature of Registrant & Date



EQUATIONS: NONE
 EXCEPTIONS: NONE
 RAILROAD CROSSINGS: NONE

INDEX OF SHEETS

SHEET	DESCRIPTION
<u>I. GENERAL</u>	
1	TITLE SHEET
2	INDEX OF SHEET
3	PROJECT LAYOUT AND ADVANCE WARNING SIGNS
4, 4A-4D	TYPICAL SECTIONS
5, 5A	CORE DATA
6, 6A-6E	GENERAL NOTES
7, 7A-7C	QUANTITY SHEET
8	ROADWAY SUMMARY
9	ROADWAY & SW3P SUMMARY
10	DRAINAGE SUMMARY
11	SIGN AND PAVEMENT MARKING SUMMARY
12, 12A-12B	DRIVEWAY SUMMARY

SHEET	DESCRIPTION
<u>II. TRAFFIC CONTROL PLAN</u>	
13	TCP SEQUENCE OF WORK & GENERAL NOTES
13A	CULVERT REPLACEMENT TYPICALS
13B	CULVERT EXTENSION TYPICAL SECTIONS
13C	TCP TYPICAL SECTIONS
14-25	*BC(1)-14 THRU BC(12)-14
26	*TCP(2-1)-18
27	*TCP(2-2)-18
28	*TCP(3-1)-13
29	*TCP(3-3)-14
30	*TCP(7-1)-13
31	*WZ(STPM)-13
32	*WZ(TD)-17
33	*WZ(UL)-13
34	*WZ(RS)-16

SHEET	DESCRIPTION
<u>III. ROADWAY DETAILS</u>	
35-38	SURVEY CONTROL LAYOUT
39-45	HORIZONTAL ALIGNMENT DATA
46	HORIZONTAL ALIGNMENT DATA & SUPERELEVATION TABLE
47	VERTICAL ALIGNMENT DATA
48-68	ROADWAY PLANS
69, 69A	MISCELLANEOUS ROADWAY DETAILS
70	*RS(3)-13
70A	*RS(4)-13
71	*LJD(1-1)-07 (DAL)
72	*TE(HMAC)-11
73-76	*MB-15(1)
77-79	*MB-14(2) THRU MB-14(2B)
80	*MBGF(SR)-19
81	*GF(31)MS-19
82	*GF(31)-19
83	*GF(31)LS-19
84	*SGT(10S)31-16
85	*SGT(11S)31-18
86	*SGT(12S)31-18

SHEET	DESCRIPTION
<u>IV. RETAINING WALL DETAILS</u>	
NONE	

SHEET	DESCRIPTION
<u>V. DRAINAGE DETAILS</u>	
87-90	DRAINAGE AREA MAP
91-92	HYDROLOGIC AND HYDRAULIC CALCULATIONS
93-103	CULVERT LAYOUTS
104	*BCS
105	*SCP-6
106	*SCP-7
107-108	*SCC-7
109	*SCP-10
110-112	*SCC-10
113-114	*MC-6-16
115	*SCC-MD
116	*SCP-MD
117	*MC-MD
118	*PW
119	*ECD
120	*CH-PW-0
121-122	*SETP-CD
123	*SETP-PD
124	*PSET-SC
125	*PSET-RC
126	*PSET-RC
127	*PSET-SP
128, 128A	*SRR
129	*CRR


SHEET	DESCRIPTION
<u>VI. UTILITIES</u>	
NONE	

SHEET	DESCRIPTION
<u>VII. BRIDGES</u>	
NONE	

SHEET	DESCRIPTION
<u>VIII. TRAFFIC ITEMS</u>	
130-139	SUMMARY OF SMALL SIGNS
140-160	SIGNING & PAVEMENT MARKING LAYOUTS
161, 161A-161C	GUIDE SIGN DETAILS
162, 162A, 162B	*TSR(3)-13 THRU TSR(5)-13
163	*SMD(GEN)-08
164	*SMD(SLIP-1)-08 (DAL)
165	*SMD(SLIP-2)-08
166	*SMD(SLIP-3)-08
167	*PM(1)-20
168	*PM(2)-20
169	*PM(3)-20
170	*D & OM(1)-20
171	*D & OM(2)-20
172	*D & OM(3)-20
173	*D & OM(4)-20
174	*D & OM(5)-20
175	*2-LANE HIGHWAY CURVE SIGNING & MARKINGS (DAL)

SHEET	DESCRIPTION
<u>IX. ENVIRONMENTAL ISSUES</u>	
176	STORMWATER POLLUTION PREVENTION PLAN (SW3P)
177, 177A	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC) (DAL)
178-196	SW3P SITE MAPS
197-199	*EC(1)-16 THRU EC(3)-16
200-202	*EC(9)-16
203	*VEGETATION ESTABLISHMENT SHEET (DAL)
204	*SW3P SIGN SHEET (DAL)
205	*AREF-21

SHEET	DESCRIPTION
<u>X. MISCELLANEOUS ITEMS</u>	
NONE	





* THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE WITH (*) HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Congli Ye, P.E. 4/28/2021




FM 545 INDEX OF SHEETS


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	2
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	




INTERSECTION A




INTERSECTION C, F, G, I, J, O, Q, R, T



INTERSECTION K, V, W, X



INTERSECTION Y




INTERSECTION B, D, E, H, L-N, P, S, U

NOTES:

1. THE CONTRACTOR SHALL PLACE & MAINTAIN ALL PROJECT LIMIT TRAFFIC CONTROL DEVICES AS SHOWN ON THE CURRENT BC (2)-14 STANDARD IN CURRENT TEXAS MUTCD GUIDELINES, AND AS DIRECTED BY THE ENGINEER.
2. "X" - SPACING OF OTHER ADVANCE WARNING SIGNS SHALL BE ACCORDING TO THE CURRENT BC(2)-14 STANDARD, TEXAS MUTCD GUIDELINES, AND AS DIRECTED BY THE ENGINEER.

1	END ROAD WORK G20-2	5	WORK ZONE G20-5aP
2	BEGIN ROAD WORK 9 NAME ADDRESS CITY STATE CONTRACTOR	6	TRAFFIC FINES DOUBLE R20-5T
3	ROAD WORK AHEAD CW20-1D	7	WHEN WORKERS ARE PRESENT R20-5aTP
4	OBEDY WARNING SIGNS STATE LAW R20-3T	8	END WORK ZONE G20-2bT
10	BEGIN WORK ZONE G20-9TP	9	ROAD WORK NEXT X MILES G20-1bTR
	TRAFFIC FINES DOUBLE R20-5T	11	ROAD WORK NEXT X MILES G20-1bTL
	WHEN WORKERS ARE PRESENT R20-5aTP	12	ROAD WORK NEXT X MILES G20-1aT
			SPEED LIMIT XX R2-1
			STAY ALERT TALK OR TEXT LATER G20-10T






Congli Ye, P.E. 4/28/2021



FM 545 PROJECT LAYOUT AND ADVANCE WARNING SIGNS

SCALE: NTS

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	3
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	



Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
 © 2021


**FM 545
 TYPICAL SECTIONS**

SCALE: NTS SHEET 1 OF 5

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	4
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	


- NOTE:**
1. SUPERELEVATION & PAVEMENT TRANSITION ARE SHOWN IN PLANS.
 2. PGL WILL BE 2.5" HIGHER THAN EXISTING.
 3. MIN. CLEAR ZONE WIDTH IS 10'.
 4. MINIMIZE VEGETATION AND SOIL DISTURBANCE TO EXTENT PRACTICABLE. RE-VEGETATE DISTURBED SOILS.

DATE: \$DATE\$ FILE NAME: \$FILES\$




EXISTING TYPICAL SECTION

STA. 21+22 TO STA. 24+48



DETAIL A




PROPOSED TYPICAL SECTION

STA. 21+22 TO STA. 24+48

NOTE:

1. SUPERELEVATION & PAVEMENT TRANSITION ARE SHOWN IN PLANS.
2. PGL WILL BE 2.5" HIGHER THAN EXISTING.
3. MIN. CLEAR ZONE WIDTH IS 10'.
4. MINIMIZE VEGETATION AND SOIL DISTURBANCE TO EXTENT PRACTICABLE. RE-VEGETATE DISTURBED SOILS.



Congli Ye, P.E. 4/28/2021




FM 545 TYPICAL SECTIONS

SCALE: NTS


SHEET 2 OF 5

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	4A
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	


DATE: \$DATE\$ FILE NAME: \$FILES\$



EXISTING TYPICAL SECTION
STA. 36+27 TO STA. 46+05




DETAIL A



PROPOSED TYPICAL SECTION
STA. 36+27 TO STA. 46+05

- NOTE:**
1. SUPERELEVATION & PAVEMENT TRANSITION ARE SHOWN IN PLANS.
 2. PGL WILL BE 2.5" HIGHER THAN EXISTING.
 3. MIN. CLEAR ZONE WIDTH IS 10'.
 4. MINIMIZE VEGETATION AND SOIL DISTURBANCE TO EXTENT PRACTICABLE. RE-VEGETATE DISTURBED SOILS.




Congli Ye, P.E. 4/28/2021



**FM 545
TYPICAL SECTIONS**


SCALE: NTS		SHEET 3 OF 5	
DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN
CHECK MS	CONTROL 1012	SECTION 02	JOB 042, ETC.
			HIGHWAY NO. FM 545
			SHEET NO. 4B

DATE: \$DATE\$ FILE NAME: \$FILES\$



EXISTING TYPICAL SECTION

STA. 194+30 TO STA. 280+00




PROPOSED TYPICAL SECTION

* STA. 194+30 TO STA. 280+00

NOTE:

- * 1. TOM OVERLAY, PROFILE RUMBLE STRIPS, AND BRIDGE REPAIR WORK ONLY.



Congli Ye, P.E. 4/28/2021




**FM 545
TYPICAL SECTIONS**

SCALE: NTS SHEET 4 OF 5


DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	4C
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE: \$DATE\$ FILE NAME: \$FILES\$



EXISTING TYPICAL SECTION

STA. 422+00 TO STA. 446+70




PROPOSED TYPICAL SECTION

* STA. 422+00 TO STA. 446+70

NOTE:

- * 1. PROFILE RUMBLE STRIPS AND BRIDGE REPAIR WORK ONLY.



Congli Ye, P.E. 4/28/2021



**FM 545
TYPICAL SECTIONS**

SCALE: NTS

SHEET 5 OF 5


DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	4D
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE: \$DATE\$ FILE NAME: \$FILES\$

FM 545 from FM 2933 to BS 78D, Collin County							
CSJ 1012-02-042							
Boring No.	Coordinates		Nominal Location	Offset	Total	Pavement	Layer
	Latitude	Longitude			Thickness (Inches)	Profile (Inches)	Layer Description
B-8	33.28322	-96.54592	1.0 mi. E. of SH 121	WB Lane	10.5	0-10.5	Type "C" HMAC
						10.5-15	Light gray limestone base
						15-27	Dark brown fat clay
B-9	33.28308	-96.54196	1.2 mi. E. of SH 121	EB Lane	7.0	0-7	Type "C" HMAC
						7-18	Light gray recycled concrete base
						18-25	Dark brown fat clay
B-10	33.28280	-96.53768	1.5 mi. E. of SH 121	WB Lane	7.0	0-7	Type "C" HMAC
						7-29	Tan and light gray limestone base
						29-38	Dark gray fat clay
B-11	33.28285	-96.53354	1.7 mi. E. of SH 121	EB Lane	9.5	0-9.5	Type "C" HMAC
						9.5-17.5	Light gray limestone base
						17.5-24	Dark brown fat clay
B-12	33.28373	-63.24351	2.0 mi. E. of SH 121	SB Lane	9.0	0-9	Type "C" HMAC
						9-17	Tan recycled concrete base
						17-30	Dark brown fat clay
B-13	33.28658	-96.52722	2.2 mi. E. of SH 121	NB Lane	10.0	0-10	Type "C" HMAC
						10-17	Light gray limestone base
						17-30	Dark brown sandy lean clay
B-14	33.28973	-96.52717	2.4 mi. E. of SH 121	SB Lane	10.0	0-10	Type "C" HMAC
						10-18	Light gray and tan limestone base
						18-28	Dark brown fat clay
B-15	33.29081	-96.52328	2.7 mi. E. of SH 121	EB Lane	10.0	0-10	Type "C" HMAC
						10-20	Light gray limestone base
						20-27	Dark gray fat clay
B-16	33.29072	-96.51901	3.0 mi. E. of SH 121	WB Lane	11.0	0-11	Type "C" HMAC
						11-15	Light gray limestone base
						15-25	Dark gray fat clay with sand

B-17	33.29065	-96.51475	3.2 mi. E. of SH 121	EB Lane	5.5	0-5.5	Type "C" HMAC
						5.5-15.5	Light gray limestone base
						15.5-23	Brown fat clay with sand
B-18	33.29059	-96.51049	3.4 mi. E. of SH 121	WB Lane	11.0	0-11	Type "C" HMAC
						11-17.5	Tan limestone base
						17.5-29	Brown sandy lean clay with limestone fragments
B-19	33.29098	-96.50631	3.7 mi. E. of SH 121	EB Lane	7.0	0-7	Type "C" HMAC
						7-15.5	Light gray limestone base
						15.5-29	Tan lean clay with limestone fragments
						29-34	Tan sandy lean clay
B-20	33.29299	-96.50228	3.9 mi. E. of SH 121	SB Lane	10.0	0-10	Type "C" HMAC
						10-12	Light gray limestone base
						12-25	Dark brown fat clay
B-21	33.29539	-96.50098	4.2 mi. E. of SH 121	EB Lane	7.0	0-7	Type "C" HMAC
						7-17	Tan limestone base
						17-42	Tan clayey gravel (limestone) with sand
B-22	33.29491	-96.49649	4.4 mi. E. of SH 121	WB Lane	11.0	0-11	Type "C" HMAC
						11-22	Grayish brown clay with limestone fragments
						22-34	Grayish brown sandy lean clay with limestone fragments
B-23	33.29509	-96.49236	4.7 mi. E. of SH 121	EB Lane	3.5	0-3.5	Type "C" HMAC
						3.5-7.5	Light brown cement treated base (CTB)
						7.5-26	Dark gray and tan clay with limestone fragments
						26-35	Grayish brown fat clay with limestone fragments
B-24	33.29501	-96.48854	4.9 mi. E. of SH 121 (5.25 mi. W. of BS 78D)	WB Lane	4.0	0-4	Type "C" HMAC
						4-19	Light brown cement treated base (CTB)
						19-29	Tan and light brown lean clay with sand
B-25	33.29473	-96.48417	5.0 mi. W. of BS 78D	EB Lane	4.5	0-4.5	Type "C" HMAC
						4.5-13	Light brown cement treated base (CTB)

DATE: \$DATES\$ FILE NAME: \$FILES\$



Congli Ye, P.E. 4/28/2021



FM 545 CORE DATA


SCALE: NTS SHEET 1 OF 2

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	5
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

B-26	33.29442	-96.47959	4.7 mi. W. of BS 78D	WB Lane	4.0	0-4	Type "C" HMAC
						4-20	Light gray cement treated base (CTB)
						20-25	Grayish brown fat clay with limestone fragments
B-27	33.29443	-96.47536	4.5 mi. W. of BS 78D	EB Lane	2.5	0-2.5	Type "C" HMAC
						2.5-17	Light gray cement treated base (CTB)
						17-23	Dark brown lime treated subgrade (LTS)
						23-31	Dark brown fat clay
B-28	33.29704	-96.47255	4.2 mi. W. of BS 78D	WB Lane	3.0	0-3	Type "C" HMAC
						3-16	Gray cement treated base (CTB)
						16-23	Grayish-brown lime treated subgrade (LTS)
						23-31	Tan and brown fat clay with sand
B-29	33.29925	-96.46939	4.0 mi. W. of BS 78D	EB Lane	3.0	0-3	Type "C" HMAC
						3-16	Brown cement treated base (CTB)
						16-30	Tan lean clay with limestone fragments
B-30	33.29927	-96.46513	3.8 mi. W. of BS 78D	WB Lane	11.0	0-11	Type "C" HMAC
						11-20	Tan limestone base
						20-26	Dark brown fat clay
B-31	33.29913	-96.46086	3.5 mi. W. of BS 78D	EB Lane	15.0	0-15	Type "C" HMAC
						15-19	Light gray limestone base
						19-30	Dark brown fat clay with limestone fragments
B-32	33.29906	-96.45699	3.3 mi. W. of BS 78D	WB Lane	11.0	0-11	Type "C" HMAC
						11-20	Tan limestone base
						20-28	Grayish brown fat clay with limestone fragments
B-33	33.29890	-96.45233	3.0 mi. W. of BS 78D	EB Lane	20.0	0-20	Type "C" HMAC
						20-23	Grayish brown clay with limestone fragments
						23-31	Dark gray fat clay
B-34	33.29883	-96.44806	2.8 mi. W. of BS 78D	WB Lane	17.0	0-17	Type "C" HMAC
						17-29	Tan limestone base
						29-37	Dark brown fat clay with limestone fragments
B-35	33.29869	-96.44379	2.5 mi. W. of BS 78D	EB Lane	20.0	0-20	Type "C" HMAC
						20-27	Grayish brown clay with limestone fragments
						27-35	Dark brown clay with limestone fragments

B-36	33.29862	-96.43952	2.3 mi. W. of BS 78D	WB Lane	13.0	0-13	Type "C" HMAC
						13-25	Tan limestone base
						25-32	Dark gray fat clay
B-37	33.29848	-96.43526	2.0 mi. W. of BS 78D	EB Lane	9.0	0-9	Type "C" HMAC
						9-21	Tan limestone base
						21-29	Dark gray fat clay
B-38	33.29891	-96.43122	1.8 mi. W. of BS 78D	WB Lane	9.25	0-9.25	Type "C" HMAC
						9.25-17	Tan and gray limestone base
						17-25	Dark brown fat clay with limestone fragments
B-39	33.29943	-96.42720	1.5 mi. W. of BS 78D	EB Lane	9.5	0-9.5	Type "C" HMAC
						9.5-17	Light brown limestone base
						17-27	Dark gray fat clay
B-40	33.29940	-96.42317	1.3 mi. W. of BS 78D	WB Lane	0.25	0-0.25	Light weight surface treatment
						0.25-9	Light gray cement treated base (CTB)
						9-20	Light gray limestone base
						20-29	Dark brown fat clay
B-41	33.29900	-96.41867	1.0 mi. W. of BS 78D	EB Lane	8.0	0-8	Type "C" HMAC
						8-16	Grayish brown clay with limestone fragments
						16-25	Light gray and tan fat clay
B-42	33.29890	-96.41444	0.8 mi. W. of BS 78D	WB Lane	8.0	0-8	Type "C" HMAC
						8-20	Tan and brown fat clay with sand
B-43	33.29880	-96.41018	0.5 mi. W. of BS 78D	EB Lane	12.0	0-12	Type "C" HMAC
						12-18	Light brown limestone base
						18-25	Dark gray fat clay
B-44	33.29876	-96.40519	0.3 mi. W. of BS 78D	WB Lane	10.0	0-10	Type "C" HMAC
						10-18	Tan limestone base
						18-28	Dark gray fat clay
B-45	33.29866	-96.40156	200' W. of BS 78D	EB Lane	7.0	0-7	Type "C" HMAC
						7-17	Light brown limestone base
						17-27	Dark gray fat clay

DATE: 8/24/21 FILE NAME: 8FILES



Congli Ye, P.E. 4/28/2021



FM 545 CORE DATA

SCALE: NTS SHEET 2 OF 2

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	5A
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

County: Collin

Highway: FM 545

SPECIFICATION DATA

Table 1: Soil Constants Requirements				
Item	Description	Plasticity Index		Note
		Max	Min	
132	EMBANKMENT (FINAL) (DC)(TY C)	40	8	1

Note 1: Material excavated from the project must meet the PI requirements when used in the top 10 feet of embankment that supports the pavement structure or other locations shown in the plans. Do not use shale and obtain approval to incorporate shaley clay produced by the construction project.

Table 2: Basis of Estimate for Permanent Construction					
Item	Description	Thickness	Rate		Quantity
164	Drill Seed (Perm) R (C/S)	N/A	See Specifications		207,984 SY
166 *	Fertilizer (12-6-6)	N/A	500	Lbs./Ac	10.74 Ton
168	Vegetative Watering (Warm)**	N/A	12	MG/Ac/Day	30,941.5 MG
314	Emuls Asph	N/A	0.20	Gal/SY	24,066 Gal
3077	SP-C MIXES	See Plans	110	Lbs./SY/In	12,877 Ton
3077	Tack Coat (Undiluted Application Rate)	New HMA	0.06	Gal/SY	7,026 Gal
*For contractor's information only					
**Use Summer rate for calculation, adjust for actual field conditions/temperatures as necessary. See Vegetation Establishment Plan Sheet for estimated daily rates.					
Note: (1) Base material weight based on 1.50 Ton/CY (dry- compacted) (2) Asphalt weight based on 110 Lbs./SY/In (3) Item 314 Residual Asphalt 0.20 Gal/SY					

County: Collin

Highway: FM 545

Table 3: Basis of Estimate for Temporary Erosion Control Items				
Item	Description	Rate		Quantity
164	Drill Seeding (Temp) (Warm or Cool)	See Specifications		207,984 SY
166*	Fertilizer (12-6-6)	500	Lb/Ac	10.74 Ton
168	Vegetative Watering (Warm)**	12	MG/Ac/Day	30,941.5 MG
*For Contractor's Information Only.				
**Use Summer rate for calculation, adjust for Actual Field Conditions/Temperatures as Necessary. See Vegetation Establishment Sheet for estimated daily rates.				

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 47.16 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

This project required permits with environmental resources agencies as summarized in the plan set Environmental Permits, Issues and Commitments (EPIC) Sheet. There is a high probability that an environmentally sensitive area could be encountered on the contractor designated Project-Specific Locations (PSL) for this project (haul roads, equipment staging areas, borrow pits, disposal sites, field offices, storage areas, parking areas, etc.). Item 7.6 "Project-Specific Locations", provides a listing of regulatory agencies that may need to be contacted regarding this project.

Install traffic marking signs prior to HMA application and remove within three days after placement of traffic markings.

Leave all right of way areas undisturbed until actual construction is to be performed in said areas.

County: Collin

Highway: FM 545

Contractor questions on this project are to be emailed to the following individual(s):

Name: Jennifer Vorster Email: Jennifer.Vorster@txdot.gov

Name: Gerald Waltman Email: Gerald.Waltman@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

[https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/](https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/)

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Paper copies of cross-sections may be produced by using the provided .pdf file located on the above FTP Website at the bidders' expense and at copying companies. This data is for non-construction purposes only and it is the responsibility of the prospective bidder to validate the enclosed data with appropriate plans, specifications and estimate for the project(s).

Item 5:

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (214-320-6682) for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (214-320-6205) for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

For the project to be deemed complete, permanently stabilize all unpaved disturbed areas of the project with a vegetative cover at a minimum of 70% density for the control of erosion.

Place construction stakes/station markings at intervals of no more than 100 feet or as directed by the Engineer. Place stakes and markings so as not to interfere with normal construction operations.

Item 7:

Repair or replace any structures and utilities that might have been damaged by negligence or a failure to have utility locates performed.

Perform all electrical work in accordance with the National Electrical Code and Texas Department of Transportation Specifications.

Holiday restrictions – the engineer may decide that no lane closures or construction operations shall be allowed during the restricted periods listed in the following holiday schedule. TxDOT has the right to lengthen, shorten, or otherwise modify these restricted periods as actual, or expected, traffic conditions may warrant. Working days will not be charged for these restricted

County: Collin

Highway: FM 545

periods. No additional compensation will be allowed for these closures (i.e., overhead, delays, stand-by, barricades or any other associated cost impacts).

- New Year's Eve and Day (noon on December 31 thru 10:00 pm January 1)
- Easter Holiday weekend (noon on Friday thru 10:00 pm Sunday)
- Memorial Day weekend (noon on Friday thru 10:00pm Monday)
- Independence Day (noon on July 3 thru 10:00 pm on July 5)
- Labor Day weekend (noon on Friday thru 10:00 pm Monday)
- Thanksgiving Holiday (noon on Wednesday thru 10:00 pm Sunday)
- Christmas Holiday (noon on December 23 thru 10:00 pm December 26)

Consult with appropriate electric company representatives according to their respective area to coordinate electrical services installations.

No significant traffic generator events identified.

Item 8:

This Project will be a Five-Day Workweek in accordance with Article 8.3.1.1.

The road-user cost liquidated damages are \$1,389 per day.

Item 100:

Remove the existing roadway small signs, delineators and object markers as shown on the plans, or as directed, during construction within the right of way. Small sign, delineator and object marker removals are subsidiary to this Item.

The removal or trimming of trees is subsidiary to this item.

The limits of preparing right of way will be measured from Sta. 5+30.00 to Sta. 485+54.50 along the centerline of construction.

Item 104:

In those areas where the pavement is not to be overlaid, provide a smooth surface after the curb removal. Planning or grinding is considered an acceptable method at these locations. Measurement and payment is in accordance with this item.

Sawing of concrete is not paid for directly, but is considered subsidiary to this item.

Items 105, 251, 305, and 354:

Saw existing asphalt along neat lines where portions are to be left in place temporarily or permanently. Sawing is not paid for directly, but is subsidiary to this item.

Item 110:

Excavated shale is not an acceptable material for embankment.

Items 110 and 132:

Scarify and loosen the excavated areas, unpaved surface areas, except rock, to a depth of at least 8 inches and compact in accordance with the specifications.

County: Collin

Highway: FM 545

Excavation and embankment for driveways, sleeper slabs, alleys and intersections will not be paid for directly, but will be considered subsidiary to these items.

Item 132:

Excavated material from the project site has not been determined to be suitable for embankment. The bidder assumes all risk for the use of excavated materials for embankment and is expected to meet all material requirements for embankment regardless of the source.

Perform Tex-106-E (Plasticity Index) by an approved laboratory on excavated soils from sources outside right of way when used in roadway embankment. Provide the test results at no expense to the department. The engineer will sample and test soils produced by the construction project for specification requirements or material sources specified in the plans.

Earth embankment Type C, is mainly composed of material other than shale. Furnish material that is free from vegetation or other objectionable material and that conforms to the requirements of Table 1 (Sheet B). If necessary, treat material with lime slurry in accordance with Item 260, "Lime Treatment (Road-Mixed)" in order to meet these requirements. Use Tex-121-E, figure 1, page 4 to calculate the amount of lime required. When lime treated subgrade is specified, 3000 PPM is the maximum allowed sulfate content in the top 3 feet when material comes from borrow source. Follow recommendations of 260.4.4 for mixing and mellowing. The engineer will test material placed or excavated to a depth of one foot below and laterally to one foot outside the proposed treatment limit. Lime treatment of this material will not be paid for directly, but will be considered subsidiary to this item.

Do not use shaley clays in embankment unless approved in writing.

Item 134:

Start backfilling pavement edges as soon as possible after the surface course is started.

Backfill and compact the pavement edges to produce a smooth surface adjacent to the pavement with no vertical edges.

Use Type "A" or "B" material to backfill pavement edges as shown in plans. Type "A" or "B" material shall consist of suitable material that when compacted will support the pavement edge. Rap is considered suitable Type "A" or "B" material.

Blade the existing vegetation into a neat wind-row prior to overlay. After placing Ty A or Ty B backfill and placing seeding, the material from the wind-row shall be replaced on the completed slopes. Emulsion shall be placed at a 50/50 solution of water to emulsion over disturbed area. Emulsion rate=0.15 Gal/SY residual. This work, materials and equipment shall be subsidiary to Item 134.

Item 247:

Construct uniform layer thickness of 12 inches, or less with the required density and moisture content. Minimum PI is equal to three (3) for all grades.

County: Collin

Highway: FM 545

Item 301:

Provide liquid antistripping agents unless otherwise directed. Add the minimum dosage determined by the manufacturer or higher dosage determined by design requirement and try subsequent trials at 0.25% increments.

Item 314

Apply MS-2 or SS-1 as a prime, dilute the asphalt with base finish water, distribute in successive applications, and work into the top 1/4" of flex base. Residual asphalt 0.20 Gal/SY.

Item 316:

	AC20-5TR, AC20-XP AC15-P	CRS-2P	RC-250
JANUARY			REQUIRES INTERMEDIATE COURSE TO BE PLACED
FEBRUARY			
MARCH		REFER TO STANDARD SPECIFICATIONS ITEM 316 FOR TEMPERATURE REQUIREMENTS	
APRIL			
MAY	REFER TO STANDARD SPECIFICATIONS ITEM 316 FOR TEMPERATURE REQUIREMENTS		
JUNE			
JULY			
AUGUST			
SEPTEMBER		REFER TO STANDARD SPECIFICATIONS ITEM 316 FOR TEMPERATURE REQUIREMENTS	
OCTOBER			
NOVEMBER			REQUIRES INTERMEDIATE COURSE TO BE PLACED
DECEMBER			

Do not begin rework or flexible base operations if a first course and intermediate surface treatment cannot be placed prior to October 31.

Field conditions and traffic may require the application of an additional (intermediate) surface treatment layer to preserve and sustain a particular project segment or phase. Typically, this will be prior to the project final AC asphalt surface treatment and will be meant to ensure that the pavement integrity is protected until hot season.

County: Collin

Highway: FM 545

Utilize an asphalt distributor capable of providing a transversely varied asphalt rate. The Engineer will select the pavements where the transversely varied asphalt rate is required. When a transversely varied rate is required, the asphalt rate outside of the wheel paths will be between 22 and 32% higher than the asphalt rate applied in the wheel paths. Provide calibration documents to the Engineer that include a description of the spray bar(s) and nozzles that will be used and the percentage difference in asphalt rate achieved by each tested spray bar and nozzle arrangement. The nozzles proposed for use shall be clearly stamped or marked from the factory identifying the manufacturer.

First Course				
ITEM	APPLICATION			
	Emul. Asphalt Treatment	1 st Course		
*Asphalt Type	MS-2 or SS-1	CRS-2P	AC20-5TR, AC20-XP, AC15-P	RC-250 #
*Asph. Rate (Gal/SY)	0.20	0.50	0.42	0.28
Aggregate Type		B or L	B or L	B or L
Aggregate Grade		3	3	5
Aggr. Rate (CY/SY)		1:105	1:105	1:125
Min. Cure Time	24 hrs	14 days (Emulsion)		

* The information above is intended to provide general guidance and as a basis of estimate. Based on the season and weather conditions at the time, the engineer will determine the asphalt type and rates to be used at the time of application.

In addition to the temperature requirements of this Item, AC Asphalts used in Surface Treatments and Sealcoats must be placed between May 15 and August 31. Emulsions may be substituted for AC Asphalts outside this timeframe only with the approval of the Engineer.

Item 320:

Use a self-propelled wheel mounted MTV capable of receiving mix from the haul trucks, separate from the paver. It shall have a minimum storage capacity of approximately 25 tons. It shall be equipped with a pivoting discharge conveyor and shall completely and thoroughly remix the material prior to placement. The effectiveness of the MTV's remixing ability is subject to the approval of the Engineer. In addition, the paver shall have a surge storage insert with a minimum capacity of 20 tons.

The use of windrow pick-up equipment is allowed except on the first course of roadway material placed over the subgrade.

Item 347:

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class A.

Provide PG binder 70-22 in Type C mixture.

County: Collin

Highway: FM 545

Item 354:

Separate the asphalt pavement from the base material. Stockpile the asphalt pavement at Collin County Area Office, 2205 State Hwy 5, McKinney, TX 75069. Place the asphalt pavement material in a stockpile that meets the dimensions and requirements designated by the engineer.

Stockpile materials in uniform piles up to 15 feet in height unless otherwise instructed. Furnish adequate equipment at the stockpile to keep and leave the materials in a neat and orderly manner.

Remove the loose material from the roadway before opening to traffic.

Patch pavement cut to excessive depth by equipment failure with an approved epoxy material. Re-plane patched area to an acceptable approved ride quality. Payment for these corrections is subsidiary to this item.

Item 400:

Structural Excavation is not paid for directly but is considered subsidiary to pertinent Items.

When placing concrete storm drain pipe on slopes of greater than 10 percent, provide cement stabilized backfill to a depth shown on the plans.

Item 464:

The concrete collars and the connections of pipes to existing or proposed concrete boxes or pipe will not be paid for directly but will be considered subsidiary to the various bid items.

At locations where storm drains dead-end, plug with a concrete plug of a thickness equal to 1 ½ inches per foot of diameter of pipe with a minimum thickness of 3 inches. The cost of the plugs shall be included in the unit price bid per foot of the various storm drain pipes.

Item 500:

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

Item 502:

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times. Where turning radii are limited during phased construction at intersections, provide all weather surfaces such as RAP or base in turning movements to accommodate and to protect the traffic from edge drop-offs. Materials, labor, maintenance and removal for these temporary accesses and radii will not be paid for directly but will be considered subsidiary to the various bid items.

County: Collin

Highway: FM 545

Provide written proposed lane closure information by 1:00 pm on the business day prior to the proposed closures. Do not close lanes when this requirement is not met.

When excavation is required next to a pavement lane carrying traffic and the widening is not completed by the end of the work day, backfill against the edge of the pavement with at least a 3:1 slope using an acceptable material to support vehicular traffic. Carefully remove and dispose of this material when work resumes. Backfilling pavement edges, and the materials required for the work will be subsidiary to this item.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

Do not commence work on the road before sunrise. Do not operate or park any equipment/machinery closer than 30 feet from the traveled roadway after sunset unless authorized by the engineer.

When moving unlicensed equipment on or across any pavement or public highways, protect the pavement from all damage using an acceptable method.

Traffic Control Plans with Lane Closures causing backups of 20 minutes or greater in duration will be modified by the Engineer.

Limit lane closures along FM 545 to the hours between 9:00 am and 3:30 pm. Work in other areas of the project is not restricted to this time frame.

Item 506:

Take all practicable precautions to prevent debris from being discharged into the Waters of Texas or a designated wetland. Install Best Management Practices before demolition begins and maintain them during the demolition. Remove any debris or construction material that escapes containment devices and are discharged into the restricted areas, before the next rain event or within 24 hours of the discharge.

If temporary construction stream crossings are allowed under a Nationwide Permit, submit in writing for approval the type and location of each temporary stream crossing. Use temporary bridges, timber mats, or other structurally sound and non-eroding material for temporary stream crossings. A temporary culvert crossing will consist of storm sewer pipes and 4- to 8-inch nominal size rock. Temporary stream crossings must not cause more than minimal changes to the hydraulic flow characteristics of the stream, increase flooding, or cause more than minimal degradation of water quality. Remove the temporary stream crossings in their entirety and return the affected areas to their pre-existing elevation. All work and materials use for temporary construction stream crossings will not be paid for directly but are subsidiary to pertinent Items.

Provide SW3P Signs. Obtain from the Engineer a copy of the project's completed TPDES Storm Water Program Construction Site Notice and Contractor Site Notice. Laminate the sheets and bond with adhesive to 36" X 36" plywood sign blanks. Ensure the sheets remain dry. Apply Type C Blue reflective sheeting as the background and add the text "SW3P" in 5" white lettering, centered at the top. Attach the signs to approved temporary mounts and locate at each of the

County: Collin

Highway: FM 545

project limits just inside the right of way line at a readable height or as directed by the Engineer. If the sign cannot be placed outside the clear zone, it must adhere to the TMUTCD. SW3P signs, maintenance, and reposting (for replacement or as needed to ensure readability) will be subsidiary to Item 502.

Concrete Washouts are required per the CGP. The Concrete Washout Area(s) structural controls must consist of temporary berms, temporary shallow pits, and/or temporary storage tanks to prevent contaminated runoff and must be lined as to prevent contamination of underlying soil. Ensure pits properly maintained including removal of concrete as not to allow over flow. The location(s) of washout area will be approved by the Engineer. When washout pits are no longer needed, they will be removed and area will be restored to original condition. This work, materials and labor will not be measured or paid for directly but will be subsidiary to Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls."

Item 540:

Furnish one type of post throughout the project except as specifically noted in the plans.

Item 560:

Provide new mailbox with assembly. Cost will be subsidiary to this item.

Item 585:

Use Surface Test Type A on all intersections and driveways.

Use Surface Test Type B pay adjustment schedule 3 on the travel lanes.

Items 644:

Prior to taking elevations to determine lengths for fabrication of sign posts and/or sign support towers, obtain verification of all proposed locations.

All sign mounts shall have a clamp base system for all small roadside sign assemblies.

Affix a sign identification decal to the back of all signs in accordance with item 643.

Item 3077:

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class B_.

Provide PG binder 64-22 in Type SP-C mixture.

Item 6185:

The total number of truck mounted attenuators (TMA) required when utilizing the traffic control standards are shown in the tables below.

TCP 2 Series	Scenario	Required TMA
(2-1)-18/ (2-2)-18	All	1

County: Collin

Highway: FM 545

TCP 3 Series	Scenario			Required TMA
(3-1)-13	All			2
(3-3)-14	A	B	D	2

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA needed for the project for those times per plan requirements. Additional TMAs used that are not specified in the plans in which the contractor expects compensation will require prior approval from the Engineer.



CONTROLLING PROJECT ID 1012-02-042

DISTRICT Dallas
HIGHWAY FM 545

COUNTY Collin

QUANTITY SHEET

CONTROL SECTION JOB				1012-02-036		1012-02-037		1012-02-038		1012-02-042		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061189		A00061190		A00061191		A00066968			
COUNTY				Collin		Collin		Collin		Collin			
HIGHWAY				FM 545		FM 545		FM 545		FM 545			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	100-6002	PREPARING ROW	STA							485.500		485.500	
	104-6010	REMOVING CONC (RIPRAP)	CY							0.040		0.040	
	104-6017	REMOVING CONC (DRIVEWAYS)	SY	85.000				408.000				493.000	
	110-6001	EXCAVATION (ROADWAY)	CY							22,938.000		22,938.000	
	132-6006	EMBANKMENT (FINAL)(DENS CONT)(TY C)	CY							16,411.000		16,411.000	
	134-6004	BACKFILL (TY A OR B)	STA							485.500		485.500	
	150-6001	BLADING	STA							485.500		485.500	
	164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY							207,984.000		207,984.000	
	164-6051	DRILL SEED (TEMP)(WARM OR COOL)	SY							207,984.000		207,984.000	
	168-6001	VEGETATIVE WATERING	MG							61,883.000		61,883.000	
	247-6133	FL BS (RDWY DEL) (TY D GR 1-2)	TON							6,000.000		6,000.000	
	247-6304	FL BS (CMP IN PLACE) (TY D GR 1-2)(10")	SY							122,365.000		122,365.000	
	251-6060	REWORK BS MTL (TY C)(12"-18")(ORD COMP)	SY							99,831.000		99,831.000	
	275-6001	CEMENT	TON							826.000		826.000	
	275-6011	CEMENT TREAT(EXIST MATL)(8")	SY							124,415.000		124,415.000	
	314-6021	EMULS ASPH (PRIME)(MS-2 OR SS-1)	GAL							24,066.000		24,066.000	
	316-6024	ASPH (CRS-2P)	GAL							20,052.000		20,052.000	
	316-6029	ASPH (RC-250)	GAL							11,232.000		11,232.000	
	316-6177	AGGR(TY-B GR-5 SAC-B)	CY							326.000		326.000	
	316-6419	ASPH (AC-15P, AC-20-5TR OR AC-20XP)	GAL							16,846.000		16,846.000	
	316-6440	AGGR (TY-B GR-3 OR TY-L GR-3)(SAC-B)	CY							762.000		762.000	
	347-6002	TOM-C (AGGREGATE) SAC-A	TON							1,513.000		1,513.000	
	347-6003	TOM (ASPHALT) PG 70-22	TON							97.000		97.000	
	354-6057	PLANE ASPH CONC PAV (4")	SY							99,831.000		99,831.000	
	400-6005	CEM STABIL BKFL	CY			101.000		25.000				126.000	
	400-6008	CUT & RESTORE ASPH PAVING	SY			110.000		48.000				158.000	
	401-6001	FLOWABLE BACKFILL	CY			6.000						6.000	
	402-6001	TRENCH EXCAVATION PROTECTION	LF			99.000						99.000	
	403-6001	TEMPORARY SPL SHORING	SF	1,046.000		7,270.000						8,316.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY							61.040		61.040	
	432-6030	RIPRAP (STONE COMMON)(GROUT)(12 IN)	CY	32.000		286.000						318.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY							53.000		53.000	
	438-6009	CLEANING EXISTING JOINTS	LF							132.000		132.000	
	462-6057	CONC BOX CULV (6 FT X 6 FT)(EXTEND)	LF	60.000								60.000	
	462-6059	CONC BOX CULV (7 FT X 4 FT)(EXTEND)	LF			28.000						28.000	
	462-6078	CONC BOX CULV (10 FT X 10 FT)(EXTEND)	LF			12.000						12.000	
	464-6003	RC PIPE (CL III)(18 IN)	LF	314.000		504.000		752.000				1,570.000	



CONTROLLING PROJECT ID 1012-02-042

DISTRICT Dallas
HIGHWAY FM 545

COUNTY Collin

QUANTITY SHEET

CONTROL SECTION JOB				1012-02-036		1012-02-037		1012-02-038		1012-02-042		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061189		A00061190		A00061191		A00066968			
COUNTY				Collin		Collin		Collin		Collin			
HIGHWAY				FM 545		FM 545		FM 545		FM 545			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	464-6005	RC PIPE (CL III)(24 IN)	LF	312.000		335.000		304.000				951.000	
	464-6007	RC PIPE (CL III)(30 IN)	LF	328.000		130.000		73.000				531.000	
	464-6008	RC PIPE (CL III)(36 IN)	LF	56.000		54.000		26.000				136.000	
	466-6097	HEADWALL (CH - PW - 0) (DIA= 24 IN)	EA			3.000						3.000	
	466-6099	HEADWALL (CH - PW - 0) (DIA= 30 IN)	EA			2.000						2.000	
	466-6101	HEADWALL (CH - PW - 0) (DIA= 36 IN)	EA			2.000						2.000	
	466-6103	HEADWALL (CH - PW - 0) (DIA= 48 IN)	EA			2.000						2.000	
	466-6171	WINGWALL (PW - 1) (HW=10 FT)	EA			1.000						1.000	
	466-6172	WINGWALL (PW - 1) (HW=11 FT)	EA			1.000						1.000	
	466-6173	WINGWALL (PW - 1) (HW=12 FT)	EA			2.000						2.000	
	466-6174	WINGWALL (PW - 1) (HW=13 FT)	EA			1.000						1.000	
	466-6175	WINGWALL (PW - 1) (HW=14 FT)	EA			1.000						1.000	
	466-6181	WINGWALL (PW - 1) (HW=6 FT)	EA			2.000						2.000	
	466-6183	WINGWALL (PW - 1) (HW=8 FT)	EA	2.000								2.000	
	467-6356	SET (TY II) (18 IN) (RCP) (3: 1) (C)	EA					2.000				2.000	
	467-6363	SET (TY II) (18 IN) (RCP) (6: 1) (P)	EA	24.000		32.000		40.000				96.000	
	467-6388	SET (TY II) (24 IN) (RCP) (3: 1) (C)	EA			1.000						1.000	
	467-6395	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA	20.000		6.000		18.000				44.000	
	467-6423	SET (TY II) (30 IN) (RCP) (6: 1) (P)	EA	26.000		2.000		8.000				36.000	
	467-6454	SET (TY II) (36 IN) (RCP) (6: 1) (P)	EA	4.000								4.000	
	480-6001	CLEAN EXIST CULVERTS	EA			2.000						2.000	
	496-6004	REMOV STR (SET)	EA	36.000		20.000		27.000				83.000	
	496-6005	REMOV STR (WINGWALL)	EA	2.000		8.000						10.000	
	496-6007	REMOV STR (PIPE)	LF	900.000		801.500		1,050.000				2,751.500	
	500-6001	MOBILIZATION	LS	20.00%		35.00%		2.00%		43.00%		100.00%	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	3.000		8.000		1.000		10.000		22.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF							540.000		540.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF							540.000		540.000	
	506-6020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY							164.000		164.000	
	506-6024	CONSTRUCTION EXITS (REMOVE)	SY							164.000		164.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF							16,210.000		16,210.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF							16,210.000		16,210.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF							1,530.000		1,530.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF							1,530.000		1,530.000	
	530-6004	DRIVEWAYS (CONC)	SY	86.000				399.000				485.000	
	530-6005	DRIVEWAYS (ACP)	SY	2,730.000		3,315.000		1,479.000				7,524.000	
	533-6001	RUMBLE STRIPS (SHOULDER)	LF							65,741.000		65,741.000	

DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Collin	1012-02-042	7A



CONTROLLING PROJECT ID 1012-02-042

DISTRICT Dallas
HIGHWAY FM 545

COUNTY Collin

QUANTITY SHEET

CONTROL SECTION JOB				1012-02-036		1012-02-037		1012-02-038		1012-02-042		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061189		A00061190		A00061191		A00066968			
COUNTY				Collin		Collin		Collin		Collin			
HIGHWAY				FM 545		FM 545		FM 545		FM 545			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	533-6002	RUMBLE STRIPS (CENTERLINE)	LF							32,661.000		32,661.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	350.000		1,400.000						1,750.000	
	540-6014	SHORT RADIUS	LF			48.000						48.000	
	540-6015	DRIVEWAY TERMINAL ANCHOR SECTION	EA			2.000						2.000	
	540-6017	MTL BM GD FEN (LONG SPAN SYSTEM)	LF			100.000						100.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	625.000		350.000						975.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		6.000						10.000	
	560-6011	MAILBOX INSTALL-S (TWW-POST) TY 4	EA							39.000		39.000	
	560-6012	MAILBOX INSTALL-D (TWW-POST) TY 4	EA							6.000		6.000	
	560-6013	MAILBOX INSTALL-M (TWW-POST) TY 4	EA							1.000		1.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA							132.000		132.000	
	644-6002	IN SM RD SN SUP&AM TY10BWG(1)SA(P-BM)	EA							12.000		12.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA							21.000		21.000	
	644-6005	IN SM RD SN SUP&AM TY10BWG(1)SA(T-2EXT)	EA							1.000		1.000	
	644-6007	IN SM RD SN SUP&AM TY10BWG(1)SA(U)	EA							1.000		1.000	
	644-6033	IN SM RD SN SUP&AM TYS80(1)SA(U)	EA							7.000		7.000	
	644-6036	IN SM RD SN SUP&AM TYS80(1)SA(U-BM)	EA							6.000		6.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA							35.000		35.000	
	658-6099	INSTL OM ASSM (OM-2Z)(WFLX)GND	EA							20.000		20.000	
	662-6032	WK ZN PAV MRK NON-REMOV (Y)4"(BRK)	LF							3,133.000		3,133.000	
	662-6034	WK ZN PAV MRK NON-REMOV (Y)4"(SLD)	LF							54,409.000		54,409.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA							3,799.000		3,799.000	
	666-6018	REFL PAV MRK TY I (W)6"(DOT)(100MIL)	LF							148.000		148.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF							480.000		480.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF							289.000		289.000	
	666-6054	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA							4.000		4.000	
	666-6078	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA							4.000		4.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF							85,847.000		85,847.000	
	666-6309	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL)	LF							6,789.000		6,789.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF							3,518.000		3,518.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF							70,049.000		70,049.000	
	666-6342	REF PROF PAV MRK TY I(W)4"(SLD)(100MIL)	LF							17,686.000		17,686.000	
	666-6343	REF PROF PAV MRK TY I(W)6"(SLD)(100MIL)	LF							2,539.000		2,539.000	
	666-6344	REF PROF PAV MRK TY I(Y)4"(BRK)(100MIL)	LF							388.000		388.000	
	666-6345	REF PROF PAV MRK TY I(Y)4"(SLD)(100MIL)	LF							18,645.000		18,645.000	
	672-6007	REFL PAV MRKR TY I-C	EA							28.000		28.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA							988.000		988.000	



QUANTITY SHEET

CONTROLLING PROJECT ID 1012-02-042

DISTRICT Dallas
HIGHWAY FM 545

COUNTY Collin


CONTROL SECTION JOB				1012-02-036		1012-02-037		1012-02-038		1012-02-042		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061189		A00061190		A00061191		A00066968			
COUNTY				Collin		Collin		Collin		Collin			
HIGHWAY				FM 545		FM 545		FM 545		FM 545			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	700-6002	POTHOLE REPAIR (STANDARD)	CY							0.500		0.500	
	3077-6013	SP MIXESSP-CSAC-B PG64-22	TON	4,881.000						7,996.000		12,877.000	
	3077-6075	TACK COAT	GAL	2,663.000						4,363.000		7,026.000	
	5116-6001	AMPHIBIAN/REPTILE EXCLUSION FENCE INST	LF							3,570.000		3,570.000	
	5116-6002	AMPHIBIAN/REPTILE EXCLUSION FENCE REM	LF							3,570.000		3,570.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA							2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY							600.000		600.000	
	6185-6003	TMA (MOBILE OPERATION)	HR							480.000		480.000	
	7000-6001	REML & DISPL DRIFTWOOD & DEBRIS	CY							10.000		10.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS							1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS							1.000		1.000	

SUMMARY OF ROADWAY ITEMS FOR CSJ: 1012-02-042

PLAN	STATION	100 6002	110 6001	132 6006	134 * 6004	150 6001	247 6133	247 6304	251 6060	275 6001	275 6011	314 6021	316 6024	316 6029	316 6177	316 6419	316 6440	347 6002	347 6003
SHEET NO.		PREPARING ROW	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (DENS CONT) (TY C)	BACKFILL (TY A OR B)	BLADING	FL BS (RDWY DEL) (TY D GR1-2)	FL BS (CMP IN PLC) (TY D GR1-2) (10")	REWORK BS MTL (TY C) (12"-18") (ORD COMP)	CEMENT	CEMENT TREAT (EXIST MATL)(8")	EMULS ASPH (PRIME) (MS-2 OR SS-1)	ASPH (CRS-2P)	ASPH (RC-250)	AGGR (TY-B GR-5 SAC-B)	ASPH (AC-15P, OR AC-20XP)	AGGR (TY-B GR-3 OR TY-L GR-3) (SAC-B)	TOM-C (AGGREGATE) SAC-A	TOM (ASPHALT) PG 70-22
		STA	CY	CY	STA	STA	TON	SY	SY	TON	SY	GAL	GAL	GAL	CY	GAL	CY	TON	TON
SHEET 1	STA. 5+30 to STA. 23+00	23	1139	558	23	23		5980	4938	41	6078	1176	980	549	16	823	37		
SHEET 2	STA. 23+00 to STA. 47+00	24	1836	1000	24	24		8822	7388	60	8955	1738	1448	811	23	1216	55		
SHEET 3	STA. 47+00 to STA. 71+00	24	1249	1936	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 4	STA. 71+00 to STA. 95+00	24	1470	799	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 5	STA. 95+00 to STA. 119+00	24	1358	990	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 6	STA. 119+00 to STA. 143+00	24	1526	978	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 7	STA. 143+00 to STA. 167+00	24	1175	1608	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 8	STA. 167+00 to STA. 191+00	24	1296	1238	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 9	STA. 191+00 to STA. 215+00	24	228	101	24	24		1082	880	7	1100	213	177	99	3	149	7	379	24
SHEET 10	STA. 215+00 to STA. 239+00	24			24	24												399	25
SHEET 11	STA. 239+00 to STA. 263+00	24			24	24												435	28
SHEET 12	STA. 263+00 to STA. 287+00	24	406	264	24	24		2294	1867	16	2333	451	376	211	6	316	14	300	19
SHEET 13	STA. 287+00 to STA. 311+00	24	1569	851	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 14	STA. 311+00 to STA. 335+00	24	1802	1274	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 15	STA. 335+00 to STA. 359+00	24	1362	1064	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 16	STA. 359+00 to STA. 383+00	24	1161	1721	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 17	STA. 383+00 to STA. 407+00	24	1438	871	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 18	STA. 407+00 to STA. 431+00	24	1143	306	24	24		4917	4000	33	5000	967	806	451	13	677	31		
SHEET 19	STA. 431+00 to STA. 455+00	24	603	286	24	24		2721	2213	18	2767	535	446	250	7	374	17		
SHEET 20	STA. 455+00 to STA. 479+00	24	1721	540	24	24		7867	6400	53	8000	1547	1289	722	21	1083	49		
SHEET 21	STA. 479+00 to STA. 485+54.50	6.5	456	26	6.5	6.5		2145	1745	15	2182	422	351	197	6	295	13		
TOTAL		485.5	22938	16411	485.5	485.5	6000	122365	99831	826	124415	24066	20052	11232	326	16846	762	1513	97

SUMMARY OF ROADWAY ITEMS FOR CSJ: 1012-02-042 (CONT.)

PLAN	STATION	354 6057	432 6001	432 6045	533 6001	533 6002	560 6011	560 6012	560 6013	3077 6013	3077 6075	6001 6002	6185 6002	6185 6003
SHEET NO.		PLAN ASPH CONC PAV (4")	RIPRAP (CONC) (4")	RIPRAP (MOW STRIP) (4")	RUMBLE STRIPS (SHOULDERS)	RUMBLE STRIPS (CENTERLINE)	MAILBOX INSTALL-S (TWW-POST) TY 4 EA	MAILBOX INSTALL-D (TWW-POST) TY 4 EA	MAILBOX INSTALL-M (TWW-POST) TY 4 EA	SUPERPAVE MIXTURES SP-C SAC-B PG64-22 TON	TACK COAT GAL	PORTABLE CHANGEABLE MESSAGE SIGN EA	TMA (STATIONARY) DAY	TMA (MOBILE OPERATION) HOUR
SHEET 1	STA. 5+30 to STA. 23+00				3370	1675	6	1		643	351			
SHEET 2	STA. 23+00 to STA. 47+00			18	4455	2205	2	2		968	528			
SHEET 3	STA. 47+00 to STA. 71+00				4370	2120				838	457			
SHEET 4	STA. 71+00 to STA. 95+00				4605	2280				821	448			
SHEET 5	STA. 95+00 to STA. 119+00				4800	2400				821	448			
SHEET 6	STA. 119+00 to STA. 143+00				4800	2400				821	448			
SHEET 7	STA. 143+00 to STA. 167+00				4640	2315	1			821	448			
SHEET 8	STA. 167+00 to STA. 191+00			22	4440	2190				821	448			
SHEET 9	STA. 191+00 to STA. 215+00				660	330				113	62			
SHEET 10	STA. 215+00 to STA. 239+00													
SHEET 11	STA. 239+00 to STA. 263+00													
SHEET 12	STA. 263+00 to STA. 287+00				1253	628	2							
SHEET 13	STA. 287+00 to STA. 311+00				4800	2400	2							
SHEET 14	STA. 311+00 to STA. 335+00				4590	2265	4	1						
SHEET 15	STA. 335+00 to STA. 359+00				4800	2400	2							
SHEET 16	STA. 359+00 to STA. 383+00		61	13	4650	2325	1							
SHEET 17	STA. 383+00 to STA. 407+00				4800	2400	6	1						
SHEET 18	STA. 407+00 to STA. 431+00				2800	1375	1							
SHEET 19	STA. 431+00 to STA. 455+00				1508	753				284	155			
SHEET 20	STA. 455+00 to STA. 479+00				400	200	9	1	1	821	448			
SHEET 21	STA. 479+00 to STA. 485+54.50						3			224	122			
TOTAL			61	53	65741	32661	39	6	1	7996	4363	2	600	480



**FM 545
ROADWAY SUMMARY**

SHEET 1 OF 2

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 8
CHECK MS	CONTROL 1012	SECTION 02	JOB 042, ETC.	

* TOPSOIL ONLY

DATE: \$DATE\$ FILE NAME: \$FILE\$

SUMMARY OF ROADWAY ITEMS FOR CSJ: 1012-02-037

PLAN SHEET NO.	STATION	540	540	540	540	542	544
		6001	6014	6015	6017	6001	6001
		MTL W-BEAM GD FEN (TIM POST)	SHORT RADIUS	DRIVEWAY TERMINAL ANCHOR SECTION	MTL Q-Bem GD FEN (LONG SPAN) SYSTEM	REMOVE MTL BEAM GD FEN	GUARDRAIL END TREATMENT (INSTALL)
		LF	LF	EA	LF	LF	EA
SHEET 1	STA. 5+30 to STA. 23+00						
SHEET 2	STA. 23+00 to STA. 47+00	625	48	2	100	350	2
SHEET 3	STA. 47+00 to STA. 71+00						
SHEET 4	STA. 71+00 to STA. 95+00						
SHEET 5	STA. 95+00 to STA. 119+00						
SHEET 6	STA. 119+00 to STA. 143+00						
SHEET 7	STA. 143+00 to STA. 167+00						
SHEET 8	STA. 167+00 to STA. 191+00	775					4
SHEET 9	STA. 191+00 to STA. 215+00						
TOTAL		1400	48	2	100	350	6

SUMMARY OF ROADWAY ITEMS FOR CSJ: 1012-02-036

PLAN SHEET NO.	STATION	540	542	544	3077	3077
		6001	6001	6001	6013	6075
		MTL W-BEAM GD FEN (TIM POST)	REMOVE MTL BEAM GD FEN	GUARDRAIL END TREATMENT (INSTALL)	SUPERPAVE MIXTURES SP-C SAC-B PG64-22	TACK COAT
		LF	LF	EA	TON	GAL
SHEET 12	STA. 263+00 to STA. 287+00				240	131
SHEET 13	STA. 287+00 to STA. 311+00				821	460
SHEET 14	STA. 311+00 to STA. 335+00		625		844	448
SHEET 15	STA. 335+00 to STA. 359+00				821	448
SHEET 16	STA. 359+00 to STA. 383+00	350		4	821	448
SHEET 17	STA. 383+00 to STA. 407+00				821	448
SHEET 18	STA. 407+00 to STA. 431+00				513	280
TOTAL		350	625	4	4881	2663

SUMMARY OF EROSION CONTROL ITEMS FOR CSJ 1012-02-042

SW3P SITE MAPS SHEET NO.	LOCATION	164	164	168	506	506	506	506	506	506	506	5116	5116	
		6035	6051	6001	6002	6011	6020	6024	6038	6039	6041	6043	6001	6002
		DRILL SEEDING (PERM) (RURAL) (CLAY)	DRILL SEED (TEMP) (WARM OR COOL)	VEGETATIVE WATERING	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (REMOVE)	CONSTRUCTION EXITS (INSTALL) (TY 1)	CONSTRUCTION EXITS (REMOVE)	TEMP SEDMT CONST FENCE (INSTAL)	TEMP SEDMT CONST FENCE (REMOVE)	BIODEG EROSN CONT LOGS (INSTAL) (12")	BIODEG EROSN CONT LOGS (REMOVE)	AMPHIBIAN/ REPTILE EXCLUSION FENCE INST	AMPHIBIAN/ REPTILE EXCLUSION FENCE REM
		SY	SY	MG	LF	LF	SY	SY	LF	LF	LF	LF	LF	
SHEET 1	STA. 5+30 TO STA. 23+00	10227	10227	3043			78	78	1040	1040	80	80		
SHEET 2	STA. 23+00 TO STA. 47+00	13339	13339	3969	80	80			830	830	100	100	800	
SHEET 3	STA. 47+00 TO STA. 71+00	13867	13867	4126	80	80			640	640	80	80	400	
SHEET 4	STA. 71+00 TO STA. 95+00	13867	13867	4126					1800	1800	100	100		
SHEET 5	STA. 95+00 TO STA. 119+00	13867	13867	4126	40	40			550	550	80	80		
SHEET 6	STA. 119+00 TO STA. 143+00	13867	13867	4126	80	80			1300	1300	100	100		
SHEET 7	STA. 143+00 TO STA. 167+00	13867	13867	4126					2300	2300	100	100		
SHEET 8	STA. 167+00 TO STA. 191+00	13867	13867	4126	80	80			1180	1180	100	100	800	
SHEET 9	STA. 191+00 TO STA. 215+00	1907	1907	567					350	350	20	20		
SHEET 10	STA. 263+00 TO STA. 287+00	4044	4044	1203	20	20			870	870	20	20	200	
SHEET 11	STA. 287+00 TO STA. 311+00	13867	13867	4126					1850	1850	100	100		
SHEET 12	STA. 311+00 TO STA. 335+00	13867	13867	4126	40	40			450	450	100	100	400	
SHEET 13	STA. 335+00 TO STA. 359+00	13867	13867	4126					550	550	80	80		
SHEET 14	STA. 359+00 TO STA. 383+00	13867	13867	4126	40	40			290	290	80	80	400	
SHEET 15	STA. 383+00 TO STA. 407+00	13867	13867	4126					350	350	100	100		
SHEET 16	STA. 407+00 TO STA. 431+00	8667	8667	2579	40	40			490	490	40	40	400	
SHEET 17	STA. 431+00 TO STA. 455+00	4796	4796	1427					250	250	60	60		
SHEET 18	STA. 455+00 TO STA. 479+00	10867	10867	3233					150	150	80	80		
SHEET 19	STA. 479+00 TO STA. 485+54.50	1600	1600	476	40	40	78	78	200	200	40	40		
	ADDITIONAL QUANTITY FOR REPLACEMENT IN CASE OF DAMAGE, WEATHERING, ETC.						8	8	770	770	70	70	170	
	TOTALS	207984	207984	61883	540	540	164	164	16210	16210	1530	1530	3570	

SUMMARY OF BRIDGE REPAIR ITEMS FOR CSJ: 1012-02-042

PLAN SHEET NO.	LOCATION	BRIDGE	104	432	438	700	752 *	7000
			6010	6001	6009	6002	6003	6001
			REMOVING CONC (RIPRAP)	RIPRAP (CONC) 4"	CLEANING EXIST JOINTS	POTHOLE REPAIR (STANDARD)	TREE TRIMMING/ BRUSH REMOVAL	REML & DISPL DRIFTWOOD & DEBRIS
			CY	CY	LF	CY	MI	CY
SHEET 8	STA. 167+00 TO STA. 191+00	SISTER GROVE BRANCH						5
SHEET 10	STA. 215+00 TO STA. 239+00	SISTER GROVE CREEK	0.04	0.04	44	0.5	0.01	
SHEET 18	STA. 407+00 TO STA. 431+00	PILOT GROVE CREEK RELIEF			44			
SHEET 19	STA. 431+00 TO STA. 455+00	PILOT GROVE CREEK			44			5
	PROJECT TOTALS		0.04	0.04	132	0.5		10

* FOR CONTRACTOR'S INFORMATION ONLY
SUBSIDIARY TO ITEM 100



**FM 545
ROADWAY & SW3P SUMMARY**

SHEET 2 OF 2

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	9
CHECK	CONTROL	SECTION	JOB	
MS	JRV	1012	02	
CHECK			042, ETC.	

DATE: 8/24/21 FILE NAME: 8FILES

SUMMARY OF DRAINAGE ITEMS FOR CSJ: 1042-02-036, CSJ: 1012-02-037, AND CSJ: 1012-02-038

LOCATION	400 6005	400 6008	401 6001	402 6001	403 6001	432 6030	462 6057	462 6059	462 6078	464 6003	464 6005	464 6007	464 6008	466 6097	466 6099	466 6101
	CEMENT STABIL BKFL	CUT & RESTORING ASPH PAV	FLOWABLE BACKFILL	TRENCH EXCAVATION PROTECTION	TEMPORARY SPL SHORING	RIPRAP (STONE COMMON) (GROUT) (12")	CONC BOX CULV (6'X6') (EXTEND)	CONC BOX CULV (7'X4') (EXTEND)	CONC BOX CULV (10'X10') (EXTEND)	RC PIPE (CL III) (18 IN)	RC PIPE (CL III) (24 IN)	RC PIPE (CL III) (30 IN)	RC PIPE (CL III) (36 IN)	HEADWALL (CH-PW-0) (DIA=24 IN)	HEADWALL (CH-PW-0) (DIA=30 IN)	HEADWALL (CH-PW-0) (DIA=36 IN)
	CY	SY	CY	LF	SF	CY	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA
CSJ: 1012-02-037																
CULVERT NO.1 STA. 29+18.58					2990	77			12							
CULVERT NO.2 STA. 35+75.34					768	22		28								
CULVERT NO.3 STA. 50+35.07	34	44	4	32		9					165			2		
CULVERT NO.4 STA. 62+32.95						7					12			1		
CULVERT NO.5 STA. 110+15.38	37	34	2	35		16						108			2	
CULVERT NO.6 STA. 123+33.19	30	32		32		14							54			2
CULVERT NO.7 STA. 138+15.10						31										
CULVERT NO.8 STA. 175+09.94					1748	49										
CULVERT NO.9 STA. 182+19.15					1764	61										
SUBTOTAL	101	110	6	99	7270	286		28	12		177	108	54	3	2	2
CSJ: 1012-02-036																
CULVERT NO.10 STA. 314+05.72					1046	32	60									
SUBTOTAL					1046	32	60									
CSJ: 1012-02-038																
CULVERT NO.11 STA. 485+44.52	25	48								55						
SUBTOTAL	25	48								55						
PROJECT TOTALS	126	158	6	99	8316	318	60	28	12	55	177	108	54	3	2	2

SUMMARY OF DRAINAGE ITEMS FOR CSJ: 1042-02-036, CSJ: 1012-02-037, AND CSJ: 1012-02-038 (CONT.)

LOCATION	466 6103	466 6171	466 6172	466 6173	466 6174	466 6175	466 6181	466 6183	467 6356	467 6388	480 6001	496 6005	496 6007
	HEADWALL (CH-PW-0) (DIA=48 IN)	WINGWALL (PW-1) (HW=10 FT)	WINGWALL (PW-1) (HW=11 FT)	WINGWALL (PW-1) (HW=12 FT)	WINGWALL (PW-1) (HW=13 FT)	WINGWALL (PW-1) (HW=14 FT)	WINGWALL (PW-1) (HW=6 FT)	WINGWALL (PW-1) (HW=8 FT)	SET (TY II) (18 IN) (RCP) (3:1) (C)	SET (TY II) (24 IN) (RCP) (3:1) (C)	CLEAN EXIST CULVERTS	REMOVE STR (WINGWALL)	REMOVE STR (PIPE)
	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF
CSJ: 1012-02-037													
CULVERT NO.1 STA. 29+18.58					1	1						2	
CULVERT NO.2 STA. 35+75.34							2					2	
CULVERT NO.3 STA. 50+35.07													40
CULVERT NO.4 STA. 62+32.95									1	1			5
CULVERT NO.5 STA. 110+15.38													49
CULVERT NO.6 STA. 123+33.19													38
CULVERT NO.7 STA. 138+15.10	2										1		
CULVERT NO.8 STA. 175+09.94		1	1									2	
CULVERT NO.9 STA. 182+19.15				2								2	
SUBTOTAL	2	1	1	2	1	1	2			1	2	8	132
CSJ: 1012-02-036													
CULVERT NO.10 STA. 314+05.72								2				2	
SUBTOTAL								2				2	
CSJ: 1012-02-038													
CULVERT NO.11 STA. 485+44.52									2				46
SUBTOTAL									2				46
PROJECT TOTALS	2	1	1	2	1	1	2	2	2	1	2	10	178

DATE: \$DATES FILE NAME: \$FILES



**FM 545
DRAINAGE SUMMARY**

SHEET 1 OF 1

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	10
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

SUMMARY OF DRIVEWAY ITEMS FOR CSJ 1012-02-037

DRIVEWAY NO.	PLAN SHEET NO.	EXISTING MATERIAL/TYPE	WIDTH	RADII	464-6003 RC PIPE (III) (18 IN)	464-6005 RC PIPE (III) (24 IN)	464-6007 RC PIPE (III) (30 IN)	467-6363 SET (TY II) (18 IN) (RCP) (6:1) (P)	467-6395 SET (TY II) (24 IN) (RCP) (6:1) (P)	467-6423 SET (TY II) (30 IN) (RCP) (6:1) (P)	496-6004 REMOV STR (SET)	496-6007 REMOV STR (PIPE)	530-6005 DRIVEWAYS (ACP)
			FT	FT	LF	LF	LF	EA	EA	EA	EA	LF	SY
1	1	GRAVEL DRIVEWAY	11	15	26			2				25	41
2	1	GRAVEL DRIVEWAY	MATCH	15	20			2			2	19	43
3	1	GRAVEL DRIVEWAY	11	15	24			2			2	23	41
4	1	GRAVEL DRIVEWAY	11	15	32			2			2	30.5	40
5	1	GRAVEL DRIVEWAY	11	15	28			2			2	27	42
6	1	GRAVEL (ELAINE PLACE)	MATCH	MATCH, 20	30			2			2	30	62
7	1	GRAVEL DRIVEWAY	11	15	22			2				20	44
8	1	ASPH TO GRAVEL DRIVEWAY	11	15									48
9	1	ASPH TO GRAVEL DRIVEWAY	11	15	18			2				16	44
10 *	1	ASPH (VALLEY RUN RD)	MATCH	MATCH									
11 *	2	ASPH (MONARCH WAY)	MATCH	MATCH									
12	2	GRAVEL DRIVEWAY	MATCH	15, 20			22			2	2	21	49
13	2	GRAVEL DRIVEWAY	MATCH	15		28			2		2	26.5	49
14	2	GRASS DRIVEWAY	11	15	20			2					41
15	2	ASPH TO GRAVEL DRIVEWAY	MATCH	15									66
16	2	ASPH TO GRAVEL DRIVEWAY	MATCH	15									58
17	2	ASPH TO GRAVEL DRIVEWAY	MATCH	15	26			2				25	53
18 *	2	ASPH TO CONC DRIVEWAY	MATCH	MATCH									
19	2	ASPH DRIVEWAY	MATCH	15	36			2				34	66
20	3	ASPH (CR 415)	MATCH	MATCH									406
21 *	3	ASPH TO CONC DRIVEWAY	MATCH	MATCH									
22	4	ASPH (CR 416)	MATCH	MATCH									227
23	4	ASPH TO GRAVEL DRIVEWAY	MATCH	MATCH									75
24	5	ASPH TO GRASS DRIVEWAY	11	15	20			2				16.5	49
25	5	ASPH TO DIRT DRIVEWAY	11	MATCH									55
26	5	ASPH TO GRASS DRIVEWAY	11	15									43
27	6	ASPH TO GRASS DRIVEWAY	MATCH	15									55
28	6	GRAVEL DRIVEWAY	MATCH	20, 15		60			2		2	60	143
29	6	ASPH TO GRASS DRIVEWAY	50	20		70			2			96	153
30	7	ASPH TO GRAVEL DRIVEWAY	MATCH	MATCH	98			2				98.5	149
31	7	ASPH DRIVEWAY	MATCH	MATCH									134
32	7	ASPH TO GRAVEL DRIVEWAY	MATCH	15									62
33	7	ASPH TO GRAVEL DRIVEWAY	MATCH	15									184
34	8	ASPH (CR 472)	MATCH	MATCH									251
35	8	ASPH DRIVEWAY	MATCH	15	50			2			2	50.5	106
36	8	ASPH (CR 1095)	MATCH	MATCH									156
37	8	ASPH TO GRAVEL DRIVEWAY	MATCH	15	16			2				13	48
38	9	ASPH DRIVEWAY	MATCH	MATCH, 15	38			2			2	38	233
TOTAL					504	158	22	32	6	2	20	669.5	3315

DATE: \$DATES\$ FILE NAME: \$FILES\$

NOTE:

1. MATCH EXISTING DRIVEWAY WIDTH WITH A MINIMUM OF 11'.
2. MATCH EXISTING DRIVEWAY RADIUS WITH A MINIMUM OF 15'.
3. SEE "PLAN SHEET" AND "MISCELLANEOUS ROADWAY DETAILS" SHEET FOR THE DRIVEWAY AND DRIVEWAY PIPE LOCATIONS AND DETAILS.
4. REMOVAL OF ASPHALT DRIVEWAY IS SUBSIDIARY TO ITEM 530. NO ADDITIONAL COST FOR CUTTING PIPE AT DRIVEWAY CROSSING.
- * 5. OVERLAY ONLY FOR DRIVEWAY 10, 11, 18, AND 21.



FM 545
DRIVEWAY SUMMARY

SHEET 1 OF 3

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	12
JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

SUMMARY OF DRIVEWAY ITEMS FOR CSJ 1012-02-036

DRIVEWAY NO.	PLAN SHEET NO.	EXISTING MATERIAL/TYPE	WIDTH	RADII	104-6017 REMOVING CONC (DRIVEWAYS)	464-6003 RC PIPE (III) (18 IN)	464-6005 RC PIPE (III) (24 IN)	464-6007 RC PIPE (III) (30 IN)	464-6008 RC PIPE (III) (36 IN)	467-6363 SET (TY II) (18 IN) (RCP) (6:1) (P)	467-6395 SET (TY II) (24 IN) (RCP) (6:1) (P)	467-6423 SET (TY II) (30 IN) (RCP) (6:1) (P)	467-6454 SET (TY II) (36 IN) (RCP) (6:1) (P)	496-6004 REMOV STR (SET)	496-6007 REMOV STR (PIPE)	530-6004 DRIVEWAYS (CONC)	530-6005 DRIVEWAYS (ACP)
			FT	FT	SY	LF	LF	LF	LF	EA	EA	EA	EA	EA	LF	SY	SY
39	10	GRAVEL DRIVEWAY	11	15			32				2			2	31		98
40	10	ASPH (CR 475)	MATCH	30			36				2				25		93
41	10	ASPH (PV 5463)	11	20			44				2			2	43		67
42	11	ASPH TO GRAVEL DRIVEWAY	11	15		20				2					20		67
43	11	GRAVEL DRIVEWAY	MATCH	MATCH		30				2				2	29.5		59
44	11	ASPH TO GRASS DRIVEWAY	MATCH	15		20				2					19		46
45	11	ASPH DRIVEWAY	11	15		24				2					22		43
46	12	ASPH DRIVEWAY	11	15		24				2					22.5		42
47 *	12	ASPH (FM 2862)	MATCH	MATCH													
48	12	ASPH DRIVEWAY	11	15				44				4			40		42
49	12	ASPH DRIVEWAY	11	15				40				4		4	32.5		42
50	12	GRAVEL DRIVEWAY	MATCH	15					26				2		19		55
51	12	GRAVEL DRIVEWAY	11	15				44				4			37		43
52	12	ASPH DRIVEWAY	MATCH	15				52				4			48		46
53	12	ASPH DRIVEWAY	MATCH	15													57
54	13	ASPH TO GRAVEL DRIVEWAY	11	MATCH													43
55	13	GRAVEL DRIVEWAY	MATCH	MATCH													73
56	13	GRAVEL DRIVEWAY	MATCH	MATCH													42
57	13	CONCRETE (MCCARLEY RANCH)	MATCH	15	85	30				2				2	28.5	86	
58	13	ASPH DRIVEWAY	MATCH	MATCH		36				2							84
59	13	ASPH TO GRAVEL DRIVEWAY	11	15			44				4			4	42.5		42
60	14	GRAVEL DRIVEWAY	MATCH	15			26				2			2	24.5		47
61	14	ASPH DRIVEWAY	MATCH	15					30				2		29		50
62	14	ASPH (CR 575)	MATCH	25			62				2			2	62		99
63	15	ASPH DRIVEWAY	MATCH	15			22				2			2	18		48
64	15	ASPH TO GRASS DRIVEWAY	11	15		32				2					32		40
65	15	ASPH TO GRAVEL DRIVEWAY	11	15													51
66	15	ASPH TO GRAVEL DRIVEWAY	11	MATCH				42				2		2	42		44
67	15	ASPH TO GRAVEL DRIVEWAY	11	15		26				2				2	25		48
68	15	GRAVEL DRIVEWAY	11	MATCH				34				2		2	32.5		55
69	15	ASPH TO GRAVEL DRIVEWAY	11	15		22				2					19		48
70	15	ASPH TO GRAVEL DRIVEWAY	11	15				24				2		2	24		58
71	15	ASPH TO GRAVEL DRIVEWAY	11	15				24				2		2	23		59
72	15	ASPH TO GRAVEL DRIVEWAY	11	15			20				2			2	19		45
73	16	ASPH TO GRAVEL DRIVEWAY	11	15				24				2		2	23		55
74	16	ASPH DRIVEWAY	MATCH	MATCH, 15		24				2					24		48
75	16	ASPH DRIVEWAY	11	15		26				2					23.5		50
76	16	ASPH TO DIRT DRIVEWAY	18	MATCH													325
76A	16	ASPH TO DIRT DRIVEWAY	MATCH	15			26				2				20		
77	16	ASPH (FM 1377)	MATCH	MATCH													424
77A	16	ASPH TO GRASS DRIVEWAY	MATCH	15													50
TOTAL					85	314	312	328	56	24	20	26	4	36	900	86	2730

- NOTE:
1. MATCH EXISTING DRIVEWAY WIDTH WITH A MINIMUM OF 11'.
 2. MATCH EXISTING DRIVEWAY RADIUS WITH A MINIMUM OF 15'.
 3. SEE "PLAN SHEET" AND "MISCELLANEOUS ROADWAY DETAILS" SHEET FOR THE DRIVEWAY AND DRIVEWAY PIPE LOCATIONS AND DETAILS.
 4. REMOVAL OF ASPHALT DRIVEWAY IS SUBSIDIARY TO ITEM 530. NO ADDITIONAL COST FOR CUTTING PIPE AT DRIVEWAY CROSSING.
 - * 5. OVERLAY ONLY FOR DRIVEWAY 47.



FM 545
DRIVEWAY SUMMARY

SHEET 2 OF 3

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	12A
JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE: \$DATES\$ FILE NAME: \$FILES\$

SUMMARY OF DRIVEWAY ITEMS FOR CSJ 1012-02-038

DRIVEWAY NO.	PLAN SHEET NO.	EXISTING MATERIAL/TYPE	WIDTH	RADII	104-6017 REMOVING CONC (DRIVEWAYS)	464-6003 RC PIPE (III) (18 IN)	464-6005 RC PIPE (III) (24 IN)	464-6007 RC PIPE (III) (30 IN)	464-6008 RC PIPE (III) (36 IN)	467-6363 SET (TY II) (18 IN) (RCP) (6:1) (P) EA	467-6395 SET (TY II) (24 IN) (RCP) (6:1) (P) EA	467-6423 SET (TY II) (30 IN) (RCP) (6:1) (P) EA	496-6004 REMOV STR (SET) EA	496-6007 REMOV STR (PIPE) LF	530-6004 DRIVEWAYS (CONC) SY	530-6005 DRIVEWAYS (ACP) SY
78	17	CONCRETE (PECAN ST.)	MATCH	25	121		84				4		4	76	103	
79	17	ASPH DRIVEWAY	MATCH	15				26				2		25		52
80	18	ASPH TO DIRT DRIVEWAY	11	15			36				4		4	32		45
81	18	ASPH TO GRAVEL DRIVEWAY	11	15					26			2	1	25		45
82	18	ASPH (PRUETT ST.)	MATCH	25, 20			72				4		4	64		81
83 **	18	CONCRETE DRIVEWAY	MATCH	MATCH	29										29	
84 **	18	CONCRETE DRIVEWAY	MATCH	MATCH	27										28	
85	18	ASPH TO GRAVEL DRIVEWAY	MATCH	MATCH			32				2		2	30		74
86 **	18	CONCRETE DRIVEWAY	MATCH	MATCH	32										32	
87 **	18	CONCRETE DRIVEWAY	MATCH	MATCH	28										28	
88 **	18	CONCRETE DRIVEWAY	MATCH	MATCH	27										27	
89	18	CONCRETE DRIVEWAY	MATCH	20	118		50				2		2	44	118	
90	18	ASPH DRIVEWAY	MATCH	15				21				2	2	20.5		54
91	18	ASPH (N BAKER ST.)	MATCH	MATCH				26				2	2	25.5		61
92	18	ASPH DRIVEWAY	MATCH	15, MATCH		22				2			2	20		38
93	18	ASPH DRIVEWAY	MATCH	15, MATCH		42				2				41.5		57
94	18	ASPH (HARMON CIR.)	MATCH	15			30				2			29.5		46
95	18	ASPH DRIVEWAY	MATCH	15		26				2			2	25.5		40
96	18	ASPH (JUSTIN LANE)	MATCH	MATCH		40				2			2	39.5		45
97	18	ASPH TO GRAVEL DRIVEWAY	MATCH	15		26				2				25		34
98	18	ASPH TO GRAVEL DRIVEWAY	MATCH	15		34				2				30.5		34
99	18	ASPH DRIVEWAY	MATCH	15		25				2				23.5		32
100	18	ASPH DRIVEWAY	MATCH	15		53				2				50		32
101	18	CONCRETE DRIVEWAY	MATCH	15	27										34	
102	18	ASPH (N CHURCH ST.)	MATCH	MATCH		50				2				49		55
103	18	ASPH (S CHURCH ST.)	MATCH	MATCH		34				2				29		30
104	18	ASPH DRIVEWAY	MATCH	15		40				2				37		48
104A	18	ASPH DRIVEWAY	MATCH	15												
105	18	ASPH DRIVEWAY	MATCH	MATCH, 15		31				2				30		22
106	18	ASPH DRIVEWAY	11	15		26				2				24.5		19
107	19	ASPH DRIVEWAY	MATCH	15		50				2				20		30
108	19	ASPH DRIVEWAY	MATCH	15										18		30
109	19	ASPH TO CONC DRIVEWAY	MATCH	15		34				2				26		23
110	19	ASPH DRIVEWAY	MATCH	15		26				2				25		30
111	19	ASPH (N MORROW ST.)	MATCH	15		30				2				28		40
112	19	ASPH (S MORROW ST.)	MATCH	15		38				2				32		41
113	19	ASPH DRIVEWAY	MATCH	MATCH												41
114	19	ASPH DRIVEWAY	MATCH	15, MATCH												99
115	19	ASPH (N MAIN ST.)	MATCH	MATCH												52
116	19	ASPH (S MAIN ST.)	MATCH	MATCH												49
117	19	ASPH TO CONCRETE DRIVEWAY	MATCH	MATCH												35
118	19	ASPH DRIVEWAY	MATCH	15		36				2				28.5		36
119	19	ASPH DRIVEWAY	11	15		34				2				30		30
120	19	ASPH (BS 78D)	MATCH	30												
TOTAL					408	697	304	73	26	40	18	8	27	1004	399	1479

- NOTE:
- MATCH EXISTING DRIVEWAY WIDTH WITH A MINIMUM OF 11'.
 - MATCH EXISTING DRIVEWAY RADIUS WITH A MINIMUM OF 15'.
 - SEE "PLAN SHEET" AND "MISCELLANEOUS ROADWAY DETAILS" SHEET FOR THE DRIVEWAY AND DRIVEWAY PIPE LOCATIONS AND DETAILS.
 - REMOVAL OF ASPHALT DRIVEWAY IS SUBSIDIARY TO ITEM 530. NO ADDITIONAL COST FOR CUTTING PIPE AT DRIVEWAY CROSSING.
 - ** FOR DRIVEWAY 83, 84, 86, 87, 88, SAWCUT TO FIRST CONCRETE JOINT, DRIVEWAY PIPE AND SET TO REMAIN.



FM 545
DRIVEWAY SUMMARY

SHEET 3 OF 3

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	12B
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE: \$DATES\$ FILE NAME: \$FILES\$


GENERAL SEQUENCE OF WORK:

- 1.) ERECT PROJECT LIMIT AND ADVANCE WARNING SIGNS AS SHOWN IN THE THE PLANS, BC, TCP, AND WZ STANDARDS AND AS DIRECTED BY THE ENGINEER.
- 2.) PLACE AND MAINTAIN SW3P DEVICES AS SHOWN IN THE PLANS AND AS DIRECTED BY THE ENGINEER. TEMPORARY SW3P EROSION CONTROL MEASURES SHALL ONLY BE PLACED IN AREAS WHERE SOIL DISTURBANCE IS EXPECTED TO OCCUR WITHIN TWO WEEKS.
- 3.) USING DAILY LANE CLOSURES, EXTEND, CUT/RESTORE CULVERT REPLACEMENTS. BLADE EDGES.
- 4.) BLADE THE TOPSOIL OFF THE SLOPE, SALVAGE/WINDROW OUT OF THE WAY OF WORK.
- 5.) NOTCH DOWN BESIDE EXISTING PAVEMENT AND CONSTRUCT SUBGRADE WIDENING.
- 6.) REWORK 14" OF THE EXISTING PAVEMENT AND BASE. SHAPE REWORK MATERIALS TO 30' WIDTH INCLUDING 5' SUBGRADE WIDENIG. CEMENT TREAT 8" REWORK MATERIAL AT 2%. REWORK EACH SEGMENT FULL WIDTH EACH DAY TO WHERE NO GRADE DIFFERENCE IS PRESENT AT COMPLETION OF DAILY OPERATIONS ACROSS THE SECTION WIDTH. TRANSITION TRAFFIC DAILY BETWEEN EXISTING AND PROPOSED GRADES @ 25:1.
- 7.) PLACE 10" OF NEW FLEXIBLE BASE MATERIAL OVER CEMENT TREATED SUBGRADE ACROSS THE ENTIRE WIDTH OF THE SECTION. SEQUENCE OPERATIONS TO CONSTRUCT FULL WIDTH BASE SECTION WHERE NO GRADE DIFFERENCE IS PRESENT AT CENTERLINE AT COMPLETION OF DAILY OPERATIONS. TRANSITION TRAFFIC DAILY AS SHOWN IN STEP 6.
- 8.) PRIME THE NEW FLEX BASE, PLACE ONE COURSE SURFACE TREATMENT (OCST), INSTALL NONREMOVABLE WORK ZONE MARKINGS.
- 9.) CONSTRUCT 2" SUPERPAVE SP-C OVERLAY ON OCST FOR THE ENTIRE WIDTH OF THE SECTION FOR THE ENTIRE PROJECT LIMITS.
- 10.) CONSTRUCT DRIVEWAYS AND DRIVEWAY DRAINAGE STRUCTURES THE SAME CONSTRUCTION PHASE OR OPERATION AS ADJACENT ROADWAY PAVEMENT.
- 11.) BACKFILL/EMBANK EDGES AND GRADE TO DRAIN IN ACCORDANCE WITH CROSS-SECTIONS AND THE EXISTING TOPOGRAPHY; PULL TOPSOIL BACK UP THE SLOPE.
- 12.) ERECT PERMANENT SIGNS AND PLACE PERMANENT PAVEMENT MARKINGS.
- 13.) ESTABLISH PERMANENT VEGETATIVE COVER.
- 14.) REMOVE SW3P DEVICES UPON FINAL ESTABLISHMENT OF VEGETATIVE COVER. TEMPORARY SW3P EROSION CONTROL MEASURES SHALL BE REMOVED IN EACH AREA WITHIN TWO WEEKS OF VEGETATION ESTABLISHMENT OR AS APPROVED BY THE ENGINEER.
- 15.) PERFORM FINAL SITE CLEAN UP AS DIRECTED BY THE ENGINEER AND REMOVE PROJECT LIMIT/ADVANCE WARNING SIGNS.

TCP GENERAL NOTES:

- 1.) INTERMITTENT ONE-WAY TRAFFIC CONTROL (LANE CLOSURES) WILL BE IN ACCORDANCE WITH THE TCP STANDARDS AND AS DIRECTED BY THE ENGINEER.
- 2.) OVERNIGHT LANE CLOSURES WILL NOT BE PERMITTED.
- 3.) THE CONTRACTOR WILL PROVIDE AND MAINTAIN SKILLED FLAGGERS EQUIPPED WITH TWO-WAY RADIOS TO HANDLE TRAFFIC THROUGH THE WORK AREAS.
- 4.) COMPLY WITH TCP(7-1)-13 WHICH INCLUDES PROVISIONS FOR CERTAIN SIGNS TO BE INSTALLED AND TO REMAIN UNTIL PERMANENT PAVEMENT MARKINGS ARE IN PLACE. THESE SIGNS ARE IN ADDITION TO SIGNS THAT MAY BE REQUIRED BY THE VARIOUS TCP AND BC STANDARDS.

DATE: \$DATE\$ FILE NAME: \$FILES\$




Congli Ye, P.E. 4/28/2021



**FM 545
TRAFFIC CONTROL PLAN
SEQUENCE OF WORK
& GENERAL NOTES**

SCALE: NTS


DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	13
	CONTROL	SECTION	JOB	
	1012	02	0, 42 ETC.	




CULVERT REPLACEMENT
PHASE 1

NOTES:

1. TWO WAY TRAFFIC SHALL BE ESTABLISHED AT THE END OF EACH WORK DAY.
2. SEE CULVERT LAYOUTS FOR ADDITIONAL DETAIL.
3. WHERE FEASIBLE, TEMPORARY BARRIERS WILL NEED TO BE PLACED WITH THE PREFERRED 2' OFFSET FROM TRAFFIC LANE EDGE TO PROVIDE SHY DISTANCE AND BETTER OPERATIONS.



CULVERT REPLACEMENT
PHASE 2




Congli Ye, P.E. 4/28/2021



**FM 545
CULVERT REPLACEMENT
TYPICAL SECTIONS**


SCALE: NTS SHEET 1 OF 1

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 13A
CHECK GW	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	




 VERTICAL PANEL

- NOTES:
1. TWO WAY TRAFFIC SHALL BE ESTABLISHED AT THE END OF EACH WORK DAY.
 2. SEE CULVERT LAYOUTS FOR ADDITIONAL DETAIL.
 3. WHERE FEASIBLE, TEMPORARY BARRIERS WILL NEED TO BE PLACED WITH THE PREFERRED 2' OFFSET FROM TRAFFIC LANE EDGE TO PROVIDE SHY DISTANCE AND BETTER OPERATIONS.



DATE: \$DATES FILE NAME: \$FILES




Congli Ye, P.E. 4/28/2021




FM 545 CULVERT EXTENSION TYPICAL SECTIONS


SCALE: NTS			SHEET 1 OF 1	
DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS SP	6	SEE TITLE SHEET		FM 545
CY MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	13B
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	




STEP 1
CONSTRUCTION OPERATION PRESENT
 STA. 5+30 TO STA. 36+27
 * STA. 36+27 TO STA. 46+05
 STA. 46+05 TO STA. 194+30
 STA. 280+00 TO STA. 422+00
 STA. 446+70 TO STA. 485+54.50



STEP 2
CONSTRUCTION OPERATION PRESENT
 STA. 5+30 TO STA. 36+27
 * STA. 36+27 TO STA. 46+05
 STA. 46+05 TO STA. 194+30
 STA. 280+00 TO STA. 422+00
 STA. 446+70 TO STA. 485+54.50



STEP 3
CONSTRUCTION OPERATION PRESENT
 STA. 5+30 TO STA. 36+27
 * STA. 36+27 TO STA. 46+05
 STA. 46+05 TO STA. 194+30
 STA. 280+00 TO STA. 422+00
 STA. 446+70 TO STA. 485+54.50



STEP 4
CONSTRUCTION OPERATION PRESENT
 STA. 5+30 TO STA. 36+27
 * STA. 36+27 TO STA. 46+05
 STA. 46+05 TO STA. 194+30
 STA. 280+00 TO STA. 422+00
 STA. 446+70 TO STA. 485+54.50

STEP 5 - CEMENT TREAT 8" X 30' WITH 1 LANE 2-WAY TRAFFIC
 * 8" X (30'-40') FROM STA. 36+27 TO STA. 46+05

STEP 6 - 10" FLEXBASE X 29' WITH PRIME COAT WITH 1 LANE 2-WAY TRAFFIC
 * 10" X (29'-39') FROM STA. 36+27 TO STA. 46+05

STEP 7 - EMBANK SLOPES/BACKFILL PVMT EDGES


STEP 8 - 2" SP-C SAC-B OVERLAY X 28' WITH 1 LANE 2-WAY TRAFFIC
 * 2" X (28'-38') FROM STA. 36+27 TO STA. 46+05



VERTICAL PANEL

NOTES:

1. TWO WAY TRAFFIC SHALL BE ESTABLISHED AT THE END OF EACH WORK DAY.
2. SEE CULVERT LAYOUTS FOR ADDITIONAL DETAIL.
3. WHERE FEASIBLE, TEMPORARY BARRIERS WILL NEED TO BE PLACED WITH THE PREFERRED 2' OFFSET FROM TRAFFIC LANE EDGE TO PROVIDE SHY DISTANCE AND BETTER OPERATIONS.



Congli Ye, P.E. 4/28/2021



FM 545
TCP TYPICAL SECTIONS

SCALE: NTS SHEET 1 OF 1

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	13C
CHECK	CONTROL	SECTION	JOB	
CHECK	JRV	1012	02 042, ETC.	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- As shown on BC(2), the OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER (see Sign Detail G20-10T) and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. However, the TRAFFIC FINES DOUBLE sign will not be required on projects consisting solely of mobile operation work, such as striping or milling edgeline rumble strips. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits.
- Except for devices required by Note 10, traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY APPAREL NOTES:

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.

DATE:
 FILE:



Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found on-line at the web address given below or by contacting:

Texas Department of Transportation
 Traffic Operations Division - TE
 Phone (512) 416-3118


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov	
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)	
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)	
MATERIAL PRODUCER LIST (MPL)	
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"	
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)	
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)	
TRAFFIC ENGINEERING STANDARD SHEETS	

SHEET 1 OF 12

		<i>Traffic Operations Division Standard</i>
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS		
BC (1) - 14		
FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT: 1012	SECT: 02
REVISIONS	DATE	BY
4-03	5-10	8-14
9-07	7-13	
DIST: DAL	COUNTY: COLLIN	SHEET NO.: 14

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL LOCATION OF CROSSROAD SIGNS



* May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- * The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- ** Required CSJ Limit signing. See Note 10 on BC(1). TRAFFIC FINES DOUBLE signs will not be required on projects consisting solely of mobile operations work.
- * Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- * Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
—	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation
 Traffic Operations Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-14


FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	04Z, ETC.	FM 545
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	DAL	COLLIN	15	

DATE: FILE:

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3) - 14

FILE:	bc-14.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:		SECT:		JOB:		HIGHWAY:	
REVISIONS		1012	02	042, ETC.		FM	545		
9-07	8-14	DIST:		COUNTY:		SHEET NO.:			
7-13		DAL		COLLIN			16		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24" as detailed below.
2. When used at night, the STOP/SLOW paddle shall be retroreflectORIZED.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC sheets or the CWZTCD. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
 2. Wooden sign posts shall be painted white.
 3. Barricades shall NOT be used as sign supports.
 4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
 5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
 6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD). The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
 7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
 8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
 9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.
- DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**
1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.




BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 14

FILE:	bc-14.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1012	02	04Z, ETC.	FM 545				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13		DAL	COLLIN		17				


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS

LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS □




GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.




SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS



WOOD POST SYSTEM FOR GROUND MOUNTED SIGN SUPPORTS

Nominal Post Size	Number of Posts	Maximum Sq. feet of Sign Face	Minimum Soil Embedment	Drilled Hole(s) Required
4 x 4	1	12	36"	NO
4 x 4	2	21	36"	NO
4 x 6	1	21	36"	YES
4 x 6	2	36	36"	YES



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- See BC(4) for definition of "Work Duration."
- * Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- △ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	04Z, ETC.	FM 545
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	DAL	COLLIN	18	

DATE: FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

Other Condition List

ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number



Traffic Operations Division Standard


BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 14

FILE: bc-14.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	DAL	COLLIN	19	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet crashworthy standards as defined in the National Cooperative Highway Research Report 350. Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, and on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential Chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the National Cooperative Highway Research Report No. 350 (NCHRP 350) or the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 14

FILE: bc-14.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	04Z, ETC.	FM 545
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	DAL	COLLIN	20	

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.





DIRECTION INDICATOR BARRICADE

- The Direction Indicator Barricade may be used in tapers, transitions, and other areas where specific directional guidance to drivers is necessary.
- If used, the Direction Indicator Barricade should be used in series to direct the driver through the transition and into the intended travel lane.
- The Direction Indicator Barricade shall consist of One-Direction Large Arrow (CWI-6) sign in the size shown with a black arrow on a background of Type B_{FL} or Type C_{FL} Orange retroreflective sheeting above a rail with Type A retroreflective sheeting in alternating 4" white and orange stripes sloping downward at an angle of 45 degrees in the direction road users are to pass. Sheetting types shall be as per DMS 8300.
- Double arrows on the Direction Indicator Barricade will not be allowed.
- Approved manufacturers are shown on the CWZTCD List. Ballast shall be as approved by the manufacturers instructions.

DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a device that is detectable by a person with a visual disability traveling with the aid of a long cane shall be placed across the full width of the closed sidewalk.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades may use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.

This detail is not intended for fabrication. See note 3 and the CWZTCD list for providers of approved Detectable Pedestrian Barricades



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 14

FILE:	bc-14.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1012	02	042, ETC.	FM 545				
4-03	7-13	DIST	COUNTY		SHEET NO.				
9-07	8-14	DAL	COLLIN		21				


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)

DRIVEABLE




(Rigid or self-righting)

PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual Appendix B "Treatment of Pavement Drop-offs in Work Zones" for additional guidelines on the use of VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10) placed near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate NCHRP 350 crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed * S	Formula L = WS ² / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40	L = WS	265'	295'	320'	40'	80'
45		450'	495'	540'	45'	90'
50	L = WS	500'	550'	600'	50'	100'
55		600'	660'	720'	60'	120'
60	L = WS	650'	715'	780'	65'	130'
65		700'	770'	840'	70'	140'
70	L = WS	750'	825'	900'	75'	150'
75		800'	880'	960'	80'	160'
80	L = WS	800'	880'	960'	80'	160'
80		800'	880'	960'	80'	160'

**Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	DAL	COLLIN	22	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.



PLAN VIEW


1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW


These drums are not required on one-way roadway



PLAN VIEW

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector


CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS



28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers used at night shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.

THIS DEVICE SHALL NOT BE USED ON PROJECTS LET AFTER MARCH 2014.



EDGE LINE CHANNELIZER

1. This device is intended only for use in place of a vertical panel to channelize traffic by indicating the edge of the travel lane. It is not intended to be used in transitions or tapers.
2. This device shall not be used to separate lanes of traffic (opposing or otherwise) or warn of objects.
3. This device is based on a 42 inch, two-piece cone with an alternate striping pattern: four 4 inch retroreflective bands, with an approximate 2 inch gap between bands. The color of the band should correspond to the color of the edgeline (yellow for left edgeline, white for right edgeline) for which the device is substituted or for which it supplements. The reflectorized bands shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless otherwise noted.
4. The base must weigh a minimum of 30 lbs.

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 14

FILE: bc-14.dgn	DW: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13	DAL	COLLIN	23	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11) - 14

FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
2-98 9-07	DIST	COUNTY	SHEET NO.	
1-02 7-13	DAL	COLLIN	24	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:


PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A



REFLECTORIZED PAVEMENT MARKINGS - PATTERN B




RAISED PAVEMENT MARKERS - PATTERN A



RAISED PAVEMENT MARKERS - PATTERN B


Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-14


FILE: bc-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
1-97 9-07	DIST	COUNTY	SHEET NO.	
2-98 7-13	DAL	COLLIN	25	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




TCP (2-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.




TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK


TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	DAL	COLLIN	26	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-2a)
2-LANE ROADWAY WITHOUT PAVED SHOULDERS
ONE LANE TWO-WAY
CONTROL WITH YIELD SIGNS
(Less than 2000 ADT - See Note 9)



TCP (2-2b)
2-LANE ROADWAY WITHOUT PAVED SHOULDERS
ONE LANE TWO-WAY
CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
 ONE-LANE TWO-WAY
 TRAFFIC CONTROL**

TCP (2-2) - 18


FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	1012	02	042, ETC.	FM 545
8-95 3-03	DIST:	COUNTY:	SHEET NO.:	
1-97 2-12	DAL	COLLIN	27	
4-98 2-18				

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY




TRAIL/SHADOW VEHICLE A
with RIGHT Directional display Flashing Arrow Board

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)


TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES


1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.




TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



TRAIL/SHADOW VEHICLE B
with Flashing Arrow Board in CAUTION display



STRIPING FOR TMA









**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
UNDIVIDED HIGHWAYS**

TCP (3-1) - 13

FILE:	tcp3-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	December 1985	CONT:		SECT:		JOB:		HIGHWAY:	
REVISIONS		1012	02	042, ETC.		FM 545			
2-94	4-98								
8-95	7-13								
1-97									
DIST:	COUNTY:					SHEET NO.			
DAL	COLLIN					28			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
12. For divided highways with three or four lanes in each direction, use TCP(3-2).
13. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
14. The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
15. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation


Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	04Z, ETC.	FM 545
2-94 4-98	DIST	COUNTY		SHEET NO.
8-95 7-13	DAL	COLLIN		29
1-97 7-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



NOTE
 Signing shown for one direction of travel only.

NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS



TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS
 For seal coat, micro-surface or similar operations

"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- Tabs shall not be used to simulate edge lines.
- Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
- Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
- Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.



TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS


TCP (7-1) - 13

FILE: tcp7-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT March 1991	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	04Z, ETC.	FM 545
4-92 4-98	DIST	COUNTY	SHEET NO.	
1-97 7-13	DAL	COLLIN	30	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS

SOLID LINES




BROKEN LINES

(FOR CENTER LINE OR LANE LINE)




WIDE DOTTED LINES

(FOR LANE DROP LINES)



WIDE GORE MARKINGS



NOTES:


- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)


- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

DATE: FILE:


WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS




CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS




LANE LINES FOR DIVIDED HIGHWAY



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



TWO-WAY LEFT TURN LANE



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm


WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	1012	SECT:	02	JOB:	042, ETC.	REVISIONS:	FM 545
1-97	3-03	DIST:	DAL	COUNTY:	COLLIN	SHEET NO.:	31		
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



NOTES:

1. Length of Safety Glare screen will be specified elsewhere in the plans.
2. The cumulative nominal length of the modular safety glare screen units shall equal the length of the individual sections of temporary concrete traffic barrier on which they are installed so the joint between barrier sections will not be spanned by any one safety glare screen unit.
3. Screen Panel/blades will be designed such that reflective sheeting conforming with Departmental Material Specification DMS-8300, Sign Face Materials, Type B or C Yellow, minimum size of 2 inches by 12 inches can be attached to the edge of the panel/blade. The sheeting shall be attached to one glare screen panel/blade per section of concrete barrier not to exceed a spacing of 30 feet. Barrier reflectors are not necessary when panel/blades are installed with reflective sheeting as described.
4. Payment for these devices will be under statewide Special Specification "Modular Glare Screens for Headlight Barrier."
5. This detail is only intended to show types of locations where Glare Screens would be appropriate. Required signing and other devices shall be as shown elsewhere in the plans.


BARRIER DELINEATION WITH MODULAR GLARE SCREENS

LEGEND	
	Type 3 Barricade
	Channelizing Devices
	Trailer Mounted Flashing Arrow Board
	Sign
	Safety glare screen

DEPARTMENTAL MATERIAL SPECIFICATIONS	
SIGN FACE MATERIALS	DMS-8300
DELINEATORS AND OBJECT MARKERS	DMS-8600
MODULAR GLARE SCREENS FOR HEADLIGHT BARRIER	DMS-8610

Only pre-qualified products shall be used. A copy of the Compliant Work Zone Traffic Control Devices List (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:

<http://www.txdot.gov/business/resources/producer-list.html>



NOTES:





1. When two-lane, two way traffic control must be maintained on one roadway of a normally divided highway, opposing traffic shall be separated with either temporary traffic barriers, channelizing devices, or a temporary raised island throughout the length of the two way operation. The above Typical Application is intended to show the appropriate application of channelizing devices when they are used for this purpose. This is not a traffic control plan. If this detail is to be used for other types of roads or applications, those locations should be stated elsewhere in the plans.
2. Space devices according to the Tangent Spacing shown on the Device Spacing table on BC(9) but not exceeding 100'.
3. Every fifth device should be an OTLD except when spaced closer to accommodate an intersection. An OTLD should be the first device on each side of intersecting streets or roads.
4. Locations where surface mount bases with adhesives or self-righting devices will be required in order to maintain them in their proper position should be noted elsewhere in the plans.
5. Channelizing devices are to be vertical panels, 42" cones or tubular markers that are at least 36" tall. Tubular markers used to separate traffic should have a rubber base weighing at least 30 pounds. Tubular markers that are 42" tall or more shall have four bands of reflective material as detailed for 42" cones on BC(10). Tubular markers less than 42" but at least 36" tall shall have three bands of 3" wide white reflective material spaced 2" apart. Reflective material shall meet DMS-8300, Type A.

VERTICAL PANELS & OPPOSING TRAFFIC LANE DIVIDERS (OTLD) SEPARATING TWO-WAY TRAFFIC ON NORMALLY DIVIDED HIGHWAYS

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN TYPICAL DETAILS			
WZ(TD) - 17			
FILE:	wz1d-17.dgn	DN:	TxDOT
© TxDOT	February 1998	CONT:	1012 02
REVISIONS		SECT:	042, ETC.
4-98	2-17	JOB:	FM 545
3-03		DIST:	DAL
7-13		COUNTY:	COLLIN
		SHEET NO.:	32

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"





SIGNING FOR UNEVEN LANES

WZ (UL) - 13

FILE: WZUL-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
8-95 2-98 7-13	DIST	COUNTY	SHEET NO.	
1-97 3-03	DAL	COLLIN	33	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Warning sign and rumble strip sequence in opposite direction is same as below



GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Removal of the Temporary Rumble Strips should be accomplished before removing the advance warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an AFAD or a portable traffic signal.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment.

Speed	Approximate distance between strips in an Array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
> 55 MPH	20'

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	700'	770'	840'	70'	140'	800'	475'	
75	750'	825'	900'	75'	150'	900'	540'	

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.



Texas Department of Transportation
 Traffic Operations Division Standard

TEMPORARY RUMBLE STRIPS

WZ (RS) - 16

FILE: wzrs16.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: TxDOT
 © TxDOT November 2012 CONT SECT JOB HIGHWAY
 REVISIONS 1012 02 042, ETC. FM 545
 2-14 DIST COUNTY SHEET NO.
 4-16 DAL COLLIN 34

DATE:
FILE:



CONTROL POINT No. E0430165

APPROXIMATE LOCATION:
 WITHIN EAST R.O.W. OF FM 2933, AT THE END OF A PRIVATE GRAVEL DRIVE. +/- 0.30 MILES SOUTH OF THE INTERSECTION OF FM 2933 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 2" ALUMINUM CAP SET ON A CONCRETE HEADWALL MARKED "TEXAS DALLAS GPS E0430165".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,154,623.059
 EASTING: 2,565,718.254
 NAVD 88 ELEVATION= 643.90'

CONTROL POINT No. E0430175

APPROXIMATE LOCATION:
 WITHIN R.O.W. OF FM 2933, AT THE END OF A PRIVATE GRAVEL DRIVE. +/- 195' SOUTH OF THE INTERSECTION OF FM 2933 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 2" ALUMINUM CAP SET ON A CONCRETE HEADWALL MARKED "TEXAS DALLAS GPS E0430175".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,156,242.131
 EASTING: 2,565,771.445
 NAVD 88 ELEVATION= 653.01'

I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON 09/14/2015.

CHRISTOPHER R. FREEMAN - R.P.L.S. NO. 5701

LTRA
 LINA T. RAMEY & ASSOCIATES, INC.
 3320 Belt Line Rd.
 Farmers Branch, Texas 75234 - 214-979-1144
 FIRM REGISTRATION NO. F-782
 TBPLS REGISTRATION NO. 10140700

Texas Department of Transportation
 © 2015


FM 545 SURVEY CONTROL

SCALE: "N. T. S."


DESIGN DD	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS DD	STATE TEXAS	DISTRICT 18	COUNTY COLLIN
CHECK	CONTROL	SECTION 02	JOB 030
CHECK CF	1012	02	030

SHEET NO. 35

CP No. E0430185



CP No. E0430195



CONTROL POINT No. E0430185

APPROXIMATE LOCATION:

WITHIN R.O.W. OF COUNTY ROAD 474, +/- 1763' NORTH OF THE INTERSECTION OF COUNTY ROAD 474 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 3 1/2" ALUMINUM CAP SET IN CONCRETE MARKED "TEXAS DALLAS GPS E0430185".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,162,557.025
 EASTING: 2,584,775.792
 NAVD 88 ELEVATION= 577.60'

CONTROL POINT No. E0430195

APPROXIMATE LOCATION:

WITHIN WEST R.O.W. OF FM 2933, AT THE END OF A PRIVATE GRAVEL DRIVE, +/- .20 MILES NORTH OF THE INTERSECTION OF COUNTY ROAD 474 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 3 1/2" ALUMINUM CAP SET IN CONCRETE MARKED "TEXAS DALLAS GPS E0430195".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,161,730.414
 EASTING: 2,584,349.982
 NAVD 88 ELEVATION= 563.98'

I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON 09/14/2015.



Christopher R. Freeman
 CHRISTOPHER R. FREEMAN - R.P.L.S. NO. 5701





LINA T. RAMEY & ASSOCIATES, INC.
 3320 Belt Line Rd.
 Farmers Branch, Texas 75234 - 214-979-1144
 FIRM REGISTRATION NO. F-782
 TBPLS REGISTRATION NO. 10140700



FM 545 SURVEY CONTROL

SCALE: "N. T. S."

DESIGN DD	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS DD	STATE	DISTRICT	COUNTY
CHECK	TEXAS	18	COLLIN
CHECK CF	CONTROL	SECTION	JOB
	1012	02	030



CONTROL POINT No. E0430205

APPROXIMATE LOCATION:
 WITHIN WEST R.O.W. OF COUNTY ROAD 575, WITHIN NORTH R.O.W. OF A PRIVATE GRAVEL DRIVE. +/- .20 MILES NORTH OF THE INTERSECTION OF COUNTY ROAD 474 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 3 1/4" ALUMINUM CAP SET IN CONCRETE MARKED "TEXAS DALLAS GPS E0430205".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,163,795.623
 EASTING: 2,599,402.140
 NAVD 88 ELEVATION= 626.85'

CONTROL POINT No. E0430215

APPROXIMATE LOCATION:
 WITHIN WEST R.O.W. OF COUNTY ROAD 575, +/- 65' NORTH OF THE INTERSECTION OF COUNTY ROAD 575 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 3 1/4" ALUMINUM CAP SET IN CONCRETE MARKED "TEXAS DALLAS GPS E0430215".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,162,708.708
 EASTING: 2,599,435.586
 NAVD 88 ELEVATION= 622.88'

I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON 09/14/2015.

Christopher R. Freeman
 CHRISTOPHER R. FREEMAN - R.P.L.S. NO. 5701

LTRA LINA T. RAMEY & ASSOCIATES, INC.
 3320 Belt Line Rd.
 Farmers Branch, Texas 75234 - 214-979-1144
 FIRM REGISTRATION NO. F-782
 TBPLS REGISTRATION NO. 10140700



Texas Department of Transportation
 © 2015

FM 545 SURVEY CONTROL

SCALE: "N. T. S."

DESIGN DD	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS DD	STATE TEXAS	DISTRICT 18	COUNTY COLLIN
CHECK DD	CONTROL	SECTION 02	JOB 030
CHECK CF	1012	02	030

SHEET NO. 37



CONTROL POINT No. E0430225

APPROXIMATE LOCATION:

WITHIN EAST R.O.W. OF BUSINESS S.H. 78, AND SOUTH R.O.W. OF BRATCHER STREET, +/- 386' NORTH OF THE INTERSECTION OF BUSINESS S.H. 78 AND FM 545.

DATE SET: 09/14/2015
 MONUMENT: A 3 1/4" ALUMINUM CAP SET IN CONCRETE MARKED "TEXAS DALLAS GPS E0430225".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,163,306.380
 EASTING: 2,610,168.956
 NAVD 88 ELEVATION= 607.20'

CONTROL POINT No. E0430235

APPROXIMATE LOCATION:

WITHIN EAST R.O.W. OF BUSINESS S.H. 78, AT THE ENTRANCE TO UNITED STATES POST OFFICE, +/- 638' NORTH OF THE INTERSECTION OF BUSINESS S.H. 78 AND FM 545.


DATE SET: 09/14/2015
 MONUMENT: A 3 1/4" ALUMINUM CAP SET IN CONCRETE MARKED "TEXAS DALLAS GPS E0430235".
 HORIZONTAL COORDINATES ARE SURFACE COORDINATES, US SURVEY FEET, TEXAS COORDINATE SYSTEM NAD 83, (EPOCH 2002) NORTH CENTRAL ZONE 4202 GEOID 2012A AS DERIVED FROM THE TxDOT VRS NETWORK

ELEVATIONS ARE NAVD 88 AS DERIVED FROM THE TxDOT VRS NETWORK

COLLIN COUNTY SURFACE ADJUSTMENT FACTOR: 1.00015271

NORTHING: 7,162,279.976
 EASTING: 2,610,252.058
 NAVD 88 ELEVATION= 610.28'

I HEREBY CERTIFY THAT THE HORIZONTAL AND VERTICAL DATA SHOWN HEREON WAS DETERMINED BY A FIELD SURVEY ON 09/14/2015.



Christopher R. Freeman
 CHRISTOPHER R. FREEMAN - R.P.L.S. NO. 5701



LINA T. RAMEY & ASSOCIATES, INC.
 3320 Belt Line Rd.
 Farmers Branch, Texas 75234 - 214-979-1144
 FIRM REGISTRATION NO. F-782
 TBPLS REGISTRATION NO. 10140700



FM 545 SURVEY CONTROL

SCALE: "N. T. S."

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
DD	6	SEE TITLE SHEET		FM 545
DD	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	18	COLLIN	
CHECK	CONTROL	SECTION	JOB	38
CF	1012	02	030	

Copyright: (c) 2013 Bentley Systems, Incorporated. All rights reserved.
 Project: FM545
 Subject:
 Job No. 99 Operator: CY
 Date: Thursday June 25, 2020 2:51 pm

SYSTEM FIX 6 ASEC 0 BEAR PRI 0 RED XY STA 4 FILE: 'FM545CHAIN'

* 1 Describe Chain PROP_FM545

Chain PROP_FM545 contains:

1 2 3 4 CUR PROP_FM545_9 CUR PROP_FM545_12 5 CUR PROP_FM545_17 CUR PROP_FM545_20 CUR PROP_FM545_23 6 CUR PROP_FM545_28 CUR PROP_FM545_31 7 CUR PROP_FM545_36 CUR PROP_FM545_39 CUR PROP_FM545_42 CUR PROP_FM545_45 CUR PROP_FM545_48 8 CUR PROP_FM545_53 CUR PROP_FM545_56 CUR PROP_FM545_59 9 CUR PROP_FM545_64 CUR PROP_FM545_67 10 11 12 13 CUR PROP_FM545_78 CUR PROP_FM545_81 14 CUR PROP_FM545_86 CUR PROP_FM545_89 15 16 17 18 19 20 21 22 CUR PROP_FM545_108 CUR PROP_FM545_111 23 24 25 CUR PROP_FM545_120 CUR PROP_FM545_123 CUR PROP_FM545_126 26 27 28 29 30 31

Beginning chain PROP_FM545 description

Feature: Road_Centerline

Point 1 X 2,565,811.011665 Y 7,156,432.195914 Sta 0+00.0000

Course from 1 to 2 S 89° 05' 17" E Dist 1,140.046858

Point 2 X 2,566,950.914121 Y 7,156,414.051225 Sta 11+40.0469

Course from 2 to 3 S 89° 18' 30" E Dist 318.870811

Point 3 X 2,567,269.761698 Y 7,156,410.202031 Sta 14+58.9177

Course from 3 to 4 S 89° 05' 10" E Dist 689.177751

Point 4 X 2,567,958.851776 Y 7,156,399.209393 Sta 21+48.0954

Course from 4 to PC PROP_FM545_9 S 88° 43' 35" E Dist 797.984756

Curve Data

Curve PROP_FM545_9

P.I. Station 31+52.3794 X 2,568,962.887640 Y 7,156,376.885889
 Delta = 2° 03' 20" (LT)
 Degree = 0° 29' 54"
 Tangent = 206.299245
 Length = 412.554240

Radius = 11,500.000000
 External = 1.850259
 Long Chord = 412.532118
 Mid. Ord. = 1.849961
 P.C. Station 29+46.0802 X 2,568,756.639367 Y 7,156,381.471566
 P.T. Station 33+58.6344 X 2,569,169.167684 Y 7,156,379.700584
 C.C. X 2,569,012.264569 Y 7,167,878.630161
 Back = S 88° 43' 35" E
 Ahead = N 89° 13' 06" E
 Chord Bear = S 89° 45' 15" E

Course from PT PROP_FM545_9 to PC PROP_FM545_12 N 89° 13' 06" E Dist 124.641022

Curve Data

Curve PROP_FM545_12

P.I. Station 35+64.7902 X 2,569,375.304295 Y 7,156,382.513322
 Delta = 1° 41' 54" (RT)
 Degree = 1° 02' 30"
 Tangent = 81.514778
 Length = 163.017620
 Radius = 5,500.000000
 External = 0.604027
 Long Chord = 163.011653
 Mid. Ord. = 0.603960
 P.C. Station 34+83.2754 X 2,569,293.797104 Y 7,156,381.401155
 P.T. Station 36+46.2931 X 2,569,456.808645 Y 7,156,381.209516
 C.C. X 2,569,368.837724 Y 7,150,881.913096
 Back = N 89° 13' 06" E
 Ahead = S 89° 05' 01" E
 Chord Bear = S 89° 55' 58" E

Course from PT PROP_FM545_12 to 5 S 89° 05' 01" E Dist 354.399176

Point 5 X 2,569,811.162485 Y 7,156,375.541003 Sta 40+00.6922

Course from 5 to PC PROP_FM545_17 S 88° 53' 40" E Dist 630.931872


Curve Data

Curve PROP_FM545_17

P.I. Station 48+21.8018 X 2,570,632.119193 Y 7,156,359.696975
 Delta = 45° 49' 10" (LT)
 Degree = 12° 43' 57"
 Tangent = 190.177712
 Length = 359.865551
 Radius = 450.000000
 External = 38.536142

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISTING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



Congli Ye, P.E. 4/28/2021



**FM 545
HORIZONTAL ALIGNMENT DATA**

SHEET 1 OF 8

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	39
CHECK	CONTROL	SECTION	JOB	
JRV	1012	02	042, ETC.	

Long Chord = 350.352669
 Mid. Ord. = 35.496379
 P.C. Station 46+31.6241 X 2,570,441.976888 Y 7,156,363.366620
 P.T. Station 49+91.4897 X 2,570,767.265038 Y 7,156,493.499676
 C.C. X 2,570,450.660032 Y 7,156,813.282838
 Back = S 88° 53' 40" E
 Ahead = N 45° 17' 10" E
 Chord Bear = N 68° 11' 45" E

Course from PT PROP_FM545_17 to PC PROP_FM545_20 N 45° 17' 10" E Dist 1,018.296936

Curve Data

 Curve PROP_FM545_20
 P.I. Station 62+74.7758 X 2,571,679.205714 Y 7,157,396.377054
 Delta = 44° 59' 01" (LT)
 Degree = 8° 57' 09"
 Tangent = 264.989220
 Length = 502.471368
 Radius = 640.000000
 External = 52.689892
 Long Chord = 489.665297
 Mid. Ord. = 48.682002
 P.C. Station 60+09.7866 X 2,571,490.896624 Y 7,157,209.939469
 P.T. Station 65+12.2580 X 2,571,680.605026 Y 7,157,661.362579
 C.C. X 2,571,040.613949 Y 7,157,664.742188
 Back = N 45° 17' 10" E
 Ahead = N 0° 18' 09" E
 Chord Bear = N 22° 47' 40" E

Course from PT PROP_FM545_20 to PC PROP_FM545_23 N 0° 18' 09" E Dist 1,348.554945

Curve Data

 Curve PROP_FM545_23
 P.I. Station 81+98.7084 X 2,571,689.510561 Y 7,159,347.789525
 Delta = 90° 29' 35" (RT)
 Degree = 17° 06' 12"
 Tangent = 337.895514
 Length = 529.099807
 Radius = 335.000000
 External = 140.813386
 Long Chord = 475.795766
 Mid. Ord. = 99.140726
 P.C. Station 78+60.8129 X 2,571,687.726257 Y 7,159,009.898722
 P.T. Station 83+89.9127 X 2,572,027.373496 Y 7,159,343.097407
 C.C. X 2,572,022.721586 Y 7,159,008.129708
 Back = N 0° 18' 09" E

Ahead = S 89° 12' 16" E
 Chord Bear = N 45° 32' 57" E

Course from PT PROP_FM545_23 to 6 S 89° 12' 16" E Dist 779.993594

Point 6 X 2,572,807.291883 Y 7,159,332.266184 Sta 91+69.9063

Course from 6 to PC PROP_FM545_28 S 88° 59' 34" E Dist 1,182.011475

Curve Data

 Curve PROP_FM545_28
 P.I. Station 104+51.9173 X 2,574,089.104804 Y 7,159,309.732767
 Delta = 2° 51' 51" (LT)
 Degree = 1° 25' 57"
 Tangent = 99.999492
 Length = 199.957333
 Radius = 4,000.000000
 External = 1.249792
 Long Chord = 199.936514
 Mid. Ord. = 1.249402
 P.C. Station 103+51.9178 X 2,573,989.120760 Y 7,159,311.490420
 P.T. Station 105+51.8751 X 2,574,189.051774 Y 7,159,312.973365
 C.C. X 2,574,059.427232 Y 7,163,310.872498
 Back = S 88° 59' 34" E
 Ahead = N 88° 08' 35" E
 Chord Bear = N 89° 34' 30" E


Course from PT PROP_FM545_28 to PC PROP_FM545_31 N 88° 08' 35" E Dist 280.432720

Curve Data

 Curve PROP_FM545_31
 P.I. Station 110+23.4855 X 2,574,660.414462 Y 7,159,328.256435
 Delta = 2° 11' 26" (RT)
 Degree = 0° 34' 23"
 Tangent = 191.177666
 Length = 382.308761
 Radius = 10,000.000000
 External = 1.827278
 Long Chord = 382.285479
 Mid. Ord. = 1.826944
 P.C. Station 108+32.3078 X 2,574,469.337206 Y 7,159,322.061105
 P.T. Station 112+14.6166 X 2,574,851.588892 Y 7,159,327.143966
 C.C. X 2,574,793.398562 Y 7,149,327.313273
 Back = N 88° 08' 35" E
 Ahead = S 89° 40' 00" E
 Chord Bear = N 89° 14' 17" E

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



Congli Ye, P.E. 4/28/2021



**FM 545
 HORIZONTAL ALIGNMENT DATA**

SHEET 2 OF 8

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	40
JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

Course from PT PROP_FM545_31 to 7 S 89° 40' 00" E Dist 1,606.567268

Point 7 X 2,576,458.128960 Y 7,159,317.795297 Sta 128+21.1839

Course from 7 to PC PROP_FM545_36 S 89° 13' 31" E Dist 964.917055

Curve Data

Curve PROP_FM545_36
P.I. Station 139+42.1097 X 2,577,578.952383 Y 7,159,302.641734
Delta = 22° 54' 26" (LT)
Degree = 7° 26' 28"
Tangent = 156.008801
Length = 307.850296
Radius = 770.000000
External = 15.645433
Long Chord = 305.804048
Mid. Ord. = 15.333868
P.C. Station 137+86.1009 X 2,577,422.957838 Y 7,159,304.750784
P.T. Station 140+93.9512 X 2,577,723.465606 Y 7,159,361.418211
C.C. X 2,577,433.367308 Y 7,160,074.680419
Back = S 89° 13' 31" E
Ahead = N 67° 52' 03" E
Chord Bear = N 79° 19' 16" E

Course from PT PROP_FM545_36 to PC PROP_FM545_39 N 67° 52' 03" E Dist 791.971764

Curve Data

Curve PROP_FM545_39
P.I. Station 150+41.3722 X 2,578,601.075458 Y 7,159,718.360050
Delta = 22° 49' 38" (LT)
Degree = 7° 26' 28"
Tangent = 155.449224
Length = 306.775121
Radius = 770.000000
External = 15.534507
Long Chord = 304.750209
Mid. Ord. = 15.227301
P.C. Station 148+85.9230 X 2,578,457.080579 Y 7,159,659.794394
P.T. Station 151+92.6981 X 2,578,711.071854 Y 7,159,828.202001
C.C. X 2,578,166.982281 Y 7,160,373.056602
Back = N 67° 52' 03" E
Ahead = N 45° 02' 25" E
Chord Bear = N 56° 27' 14" E

Course from PT PROP_FM545_39 to PC PROP_FM545_42 N 45° 02' 25" E Dist 413.577867

Curve Data

Curve PROP_FM545_42
P.I. Station 157+62.6881 X 2,579,114.398702 Y 7,160,230.962540
Delta = 42° 42' 50" (LT)
Degree = 14° 19' 26"
Tangent = 156.412131
Length = 298.200052
Radius = 400.000000
External = 29.493603
Long Chord = 291.342418
Mid. Ord. = 27.468258
P.C. Station 156+06.2760 X 2,579,003.720950 Y 7,160,120.440190
P.T. Station 159+04.4760 X 2,579,120.747380 Y 7,160,387.245773
C.C. X 2,578,721.077016 Y 7,160,403.481541
Back = N 45° 02' 25" E
Ahead = N 2° 19' 34" E
Chord Bear = N 23° 41' 00" E

Course from PT PROP_FM545_42 to PC PROP_FM545_45 N 2° 19' 34" E Dist 328.741134


Curve Data

Curve PROP_FM545_45
P.I. Station 164+49.8876 X 2,579,142.885319 Y 7,160,932.207859
Delta = 66° 34' 33" (RT)
Degree = 17° 21' 44"
Tangent = 216.670420
Length = 383.450038
Radius = 330.000000
External = 64.773443
Long Chord = 362.239355
Mid. Ord. = 54.145578
P.C. Station 162+33.2172 X 2,579,134.090792 Y 7,160,715.715995
P.T. Station 166+16.6672 X 2,579,345.031759 Y 7,161,010.200730
C.C. X 2,579,463.818842 Y 7,160,702.321486
Back = N 2° 19' 34" E
Ahead = N 68° 54' 08" E
Chord Bear = N 35° 36' 51" E

Course from PT PROP_FM545_45 to PC PROP_FM545_48 N 68° 54' 08" E Dist 328.520383

Curve Data

Curve PROP_FM545_48
P.I. Station 170+76.7540 X 2,579,774.277781 Y 7,161,175.813983
Delta = 24° 44' 09" (RT)



Congli Ye, P.E. 4/28/2021

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



**FM 545
HORIZONTAL ALIGNMENT DATA**

SHEET 3 OF 8

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	41
JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE: \$DATE\$ FILE NAME: \$FILES\$

Degree = 9° 32' 57"
 Tangent = 131.566454
 Length = 259.033179
 Radius = 600.000000
 External = 14.255429
 Long Chord = 257.026210
 Mid. Ord. = 13.924594
 P.C. Station 169+45.1876 X 2,579,651.530568 Y 7,161,128.455209
 P.T. Station 172+04.2208 X 2,579,905.579104 Y 7,161,167.465649
 C.C. X 2,579,867.507084 Y 7,160,568.674766
 Back = N 68° 54' 08" E
 Ahead = S 86° 21' 43" E
 Chord Bear = N 81° 16' 12" E

Course from PT PROP_FM545_48 to 8 S 86° 21' 43" E Dist 607.342482

Point 8 X 2,580,511.697672 Y 7,161,128.927724 Sta 178+11.5632

Course from 8 to PC PROP_FM545_53 S 86° 13' 34" E Dist 156.991420

Curve Data

Curve PROP_FM545_53
 P.I. Station 180+88.2233 X 2,580,787.757861 Y 7,161,110.718090
 Delta = 28° 34' 11" (RT)
 Degree = 12° 11' 26"
 Tangent = 119.668694
 Length = 234.357738
 Radius = 470.000000
 External = 14.995460
 Long Chord = 231.937372
 Mid. Ord. = 14.531819
 P.C. Station 179+68.5547 X 2,580,668.348663 Y 7,161,118.594625
 P.T. Station 182+02.9124 X 2,580,888.860660 Y 7,161,046.696060
 C.C. X 2,580,637.413493 Y 7,160,649.613799
 Back = S 86° 13' 34" E
 Ahead = S 57° 39' 23" E
 Chord Bear = S 71° 56' 29" E

Course from PT PROP_FM545_53 to PC PROP_FM545_56 S 57° 39' 23" E Dist 120.905438

Curve Data

Curve PROP_FM545_56
 P.I. Station 185+70.7247 X 2,581,199.609056 Y 7,160,849.918687
 Delta = 64° 56' 31" (LT)
 Degree = 14° 46' 01"
 Tangent = 246.906878

Length = 439.778723
 Radius = 388.000000
 External = 71.898909
 Long Chord = 416.612725
 Mid. Ord. = 60.658497
 P.C. Station 183+23.8178 X 2,580,991.008330 Y 7,160,982.012379
 P.T. Station 187+63.5966 X 2,581,407.620023 Y 7,160,982.939152
 C.C. X 2,581,198.585991 Y 7,161,309.816459
 Back = S 57° 39' 23" E
 Ahead = N 57° 24' 06" E
 Chord Bear = N 89° 52' 21" E

Course from PT PROP_FM545_56 to PC PROP_FM545_59 N 57° 24' 06" E Dist 57.235037

Curve Data

Curve PROP_FM545_59
 P.I. Station 189+56.0344 X 2,581,569.742596 Y 7,161,086.614551
 Delta = 33° 26' 45" (RT)
 Degree = 12° 43' 57"
 Tangent = 135.202789
 Length = 262.683158
 Radius = 450.000000
 External = 19.872104
 Long Chord = 258.969428
 Mid. Ord. = 19.031661
 P.C. Station 188+20.8316 X 2,581,455.838670 Y 7,161,013.774386
 P.T. Station 190+83.5147 X 2,581,704.930596 Y 7,161,084.614887
 C.C. X 2,581,698.275047 Y 7,160,634.664108
 Back = N 57° 24' 06" E
 Ahead = S 89° 09' 09" E
 Chord Bear = N 74° 07' 28" E

Course from PT PROP_FM545_59 to 9 S 89° 09' 09" E Dist 113.918970

Point 9 X 2,581,818.837106 Y 7,161,082.930013 Sta 191+97.4337


Course from 9 to PC PROP_FM545_64 S 87° 46' 18" E Dist 248.145922

Curve Data

Curve PROP_FM545_64
 P.I. Station 196+44.8772 X 2,582,265.942272 Y 7,161,065.532469
 Delta = 2° 55' 38" (LT)
 Degree = 0° 44' 04"
 Tangent = 199.297598
 Length = 398.508489
 Radius = 7,800.000000

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



Congli Ye, P.E. 4/28/2021



**FM 545
 HORIZONTAL ALIGNMENT DATA**

SHEET 4 OF 8

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	42
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

External = 2.545708
 Long Chord = 398.465148
 Mid. Ord. = 2.544878
 P.C. Station 194+45.5796 X 2,582,066.795381 Y 7,161,073.281578
 P.T. Station 198+44.0881 X 2,582,465.225041 Y 7,161,067.963626
 C.C. X 2,582,370.075761 Y 7,168,867.383259
 Back = S 87° 46' 18" E
 Ahead = N 89° 18' 04" E
 Chord Bear = S 89° 14' 07" E

Course from PT PROP_FM545_64 to PC PROP_FM545_67 N 89° 18' 04" E Dist 174.379455

Curve Data

Curve PROP_FM545_67
 P.I. Station 201+96.1705 X 2,582,817.281227 Y 7,161,072.258547
 Delta = 2° 47' 20" (RT)
 Degree = 0° 47' 06"
 Tangent = 177.702929
 Length = 355.335681
 Radius = 7,300.000000
 External = 2.162579
 Long Chord = 355.300602
 Mid. Ord. = 2.161939
 P.C. Station 200+18.4676 X 2,582,639.591521 Y 7,161,070.090816
 P.T. Station 203+73.8033 X 2,582,994.865945 Y 7,161,065.777880
 C.C. X 2,582,728.641488 Y 7,153,770.633979
 Back = N 89° 18' 04" E
 Ahead = S 87° 54' 36" E
 Chord Bear = S 89° 18' 16" E

Course from PT PROP_FM545_67 to 10 S 87° 54' 36" E Dist 382.761572

Point 10 X 2,583,377.372897 Y 7,161,051.818909 Sta 207+56.5648

Course from 10 to 11 S 87° 25' 08" E Dist 544.370633

Point 11 X 2,583,921.191307 Y 7,161,027.305176 Sta 213+00.9355

Course from 11 to 12 S 86° 42' 39" E Dist 296.465580

Point 12 X 2,584,217.168487 Y 7,161,010.294914 Sta 215+97.4011

Course from 12 to 13 S 87° 12' 47" E Dist 157.464852

Point 13 X 2,584,374.447089 Y 7,161,002.638493 Sta 217+54.8659

Course from 13 to PC PROP_FM545_78 S 88° 11' 46" E Dist 79.108789

Curve Data

Curve PROP_FM545_78
 P.I. Station 220+07.7942 X 2,584,627.250082 Y 7,160,994.676824
 Delta = 1° 43' 55" (RT)
 Degree = 0° 29' 54"
 Tangent = 173.819543
 Length = 347.612616
 Radius = 11,500.000000
 External = 1.313544
 Long Chord = 347.599382
 Mid. Ord. = 1.313394
 P.C. Station 218+33.9747 X 2,584,453.516676 Y 7,161,000.148310
 P.T. Station 221+81.5873 X 2,584,800.738762 Y 7,160,983.957167
 C.C. X 2,584,091.520092 Y 7,149,505.847179
 Back = S 88° 11' 46" E
 Ahead = S 86° 27' 51" E
 Chord Bear = S 87° 19' 49" E

Course from PT PROP_FM545_78 to PC PROP_FM545_81 S 86° 27' 51" E Dist 845.624398

Curve Data

Curve PROP_FM545_81
 P.I. Station 231+62.4830 X 2,585,779.767313 Y 7,160,923.464165
 Delta = 1° 33' 00" (RT)
 Degree = 0° 34' 23"
 Tangent = 135.271267
 Length = 270.526034
 Radius = 10,000.000000
 External = 0.914874
 Long Chord = 270.517785
 Mid. Ord. = 0.914790
 P.C. Station 230+27.2117 X 2,585,644.753532 Y 7,160,931.806505
 P.T. Station 232+97.7377 X 2,585,914.506038 Y 7,160,911.472849
 C.C. X 2,585,028.041645 Y 7,150,950.841298
 Back = S 86° 27' 51" E
 Ahead = S 84° 54' 51" E
 Chord Bear = S 85° 41' 21" E


Course from PT PROP_FM545_81 to 14 S 84° 54' 51" E Dist 636.922373

Point 14 X 2,586,548.920946 Y 7,160,855.011948 Sta 239+34.6601

Course from 14 to PC PROP_FM545_86 S 86° 06' 02" E Dist 362.278342

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



Congli Ye, P.E. 4/28/2021



**FM 545
 HORIZONTAL ALIGNMENT DATA**

SHEET 5 OF 8

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	43
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

Curve Data

Curve PROP_FM545_86
P.I. Station 250+17.7770 X 2,587,629.530397 Y 7,160,781.354991
Delta = 61° 34' 03" (LT)
Degree = 4° 44' 07"
Tangent = 720.838518
Length = 1,300.210490
Radius = 1,210.000000
External = 198.441752
Long Chord = 1,238.552615
Mid. Ord. = 170.482393
P.C. Station 242+96.9385 X 2,586,910.360615 Y 7,160,830.375345
P.T. Station 255+97.1489 X 2,588,015.052084 Y 7,161,390.437250
C.C. X 2,586,992.646213 Y 7,162,037.574202
Back = S 86° 06' 02" E
Ahead = N 32° 19' 55" E
Chord Bear = N 63° 06' 56" E

Course from PT PROP_FM545_86 to PC PROP_FM545_89 N 32° 19' 55" E Dist 937.851856

Curve Data

Curve PROP_FM545_89
P.I. Station 272+08.5453 X 2,588,876.865395 Y 7,162,752.008377
Delta = 58° 12' 17" (RT)
Degree = 4° 44' 07"
Tangent = 673.544469
Length = 1,229.198235
Radius = 1,210.000000
External = 174.832897
Long Chord = 1,177.021154
Mid. Ord. = 152.760528
P.C. Station 265+35.0008 X 2,588,516.637697 Y 7,162,182.887865
P.T. Station 277+64.1990 X 2,589,550.380300 Y 7,162,745.697804
C.C. X 2,589,539.043568 Y 7,161,535.750914
Back = N 32° 19' 55" E
Ahead = S 89° 27' 47" E
Chord Bear = N 61° 26' 04" E

Course from PT PROP_FM545_89 to 15 S 89° 27' 47" E Dist 1,423.553489

Point 15 X 2,590,973.871307 Y 7,162,732.360247 Sta 291+87.7525

Course from 15 to 16 S 89° 20' 38" E Dist 1,765.015681

Point 16 X 2,592,738.771248 Y 7,162,712.147579 Sta 309+52.7682

Course from 16 to 17 S 89° 10' 03" E Dist 918.246200

Point 17 X 2,593,656.920511 Y 7,162,698.805311 Sta 318+71.0144

Course from 17 to 18 S 89° 20' 34" E Dist 1,254.739393

Point 18 X 2,594,911.577344 Y 7,162,684.411710 Sta 331+25.7538

Course from 18 to 19 S 89° 44' 40" E Dist 570.889183

Point 19 X 2,595,482.460849 Y 7,162,681.865451 Sta 336+96.6430

Course from 19 to 20 S 89° 19' 44" E Dist 1,145.738791

Point 20 X 2,596,628.121062 Y 7,162,668.447022 Sta 348+42.3818

Course from 20 to 21 S 89° 29' 47" E Dist 1,384.166476

Point 21 X 2,598,012.234040 Y 7,162,656.277498 Sta 362+26.5483

Course from 21 to 22 S 89° 25' 16" E Dist 2,049.104969

Point 22 X 2,600,061.234444 Y 7,162,635.576785 Sta 382+75.6532

Course from 22 to PC PROP_FM545_108 S 89° 09' 12" E Dist 565.732493


Curve Data

Curve PROP_FM545_108
P.I. Station 390+22.6514 X 2,600,808.151049 Y 7,162,624.538601
Delta = 56° 07' 38" (LT)
Degree = 16° 51' 06"
Tangent = 181.265670
Length = 333.065616
Radius = 340.000000
External = 45.301497
Long Chord = 319.907026
Mid. Ord. = 39.975212
P.C. Station 388+41.3857 X 2,600,626.905170 Y 7,162,627.217113
P.T. Station 391+74.4513 X 2,600,911.392485 Y 7,162,773.530041
C.C. X 2,600,631.929255 Y 7,162,967.179991
Back = S 89° 09' 12" E
Ahead = N 34° 43' 10" E
Chord Bear = N 62° 46' 59" E

Course from PT PROP_FM545_108 to PC PROP_FM545_111 N 34° 43' 10" E Dist 125.982362

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



Congli Ye, P.E. 4/28/2021



**FM 545
HORIZONTAL ALIGNMENT DATA**

SHEET 6 OF 8

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	44
JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

Curve Data

Curve PROP_FM545_111
P.I. Station 394+88.0283 X 2,601,089.992959 Y 7,163,031.274829
Delta = 55° 02' 52" (RT)
Degree = 15° 54' 56"
Tangent = 187.594590
Length = 345.874818
Radius = 360.000000
External = 45.945477
Long Chord = 332.724745
Mid. Ord. = 40.745304
P.C. Station 393+00.4337 X 2,600,983.146832 Y 7,162,877.081329
P.T. Station 396+46.3085 X 2,601,277.586001 Y 7,163,032.037231
C.C. X 2,601,279.049075 Y 7,162,672.040204
Back = N 34° 43' 10" E
Ahead = N 89° 46' 02" E
Chord Bear = N 62° 14' 36" E

Course from PT PROP_FM545_111 to 23 N 89° 46' 02" E Dist 140.873671

Point 23 X 2,601,418.458509 Y 7,163,032.609756 Sta 397+87.1822

Course from 23 to 24 S 89° 45' 49" E Dist 430.773887

Point 24 X 2,601,849.228729 Y 7,163,030.832499 Sta 402+17.9561

Course from 24 to 25 N 89° 52' 59" E Dist 886.603802

Point 25 X 2,602,735.830685 Y 7,163,032.642147 Sta 411+04.5599

Course from 25 to PC PROP_FM545_120 N 89° 59' 22" E Dist 1,266.592173

Curve Data

Curve PROP_FM545_120
P.I. Station 424+78.7906 X 2,604,110.061348 Y 7,163,032.892910
Delta = 6° 09' 41" (RT)
Degree = 2° 51' 53"
Tangent = 107.638514
Length = 215.069537
Radius = 2,000.000000
External = 2.894418
Long Chord = 214.965927
Mid. Ord. = 2.890235
P.C. Station 423+71.1520 X 2,604,002.422836 Y 7,163,032.873268
P.T. Station 425+86.2216 X 2,604,217.080216 Y 7,163,021.359850
C.C. X 2,604,002.787786 Y 7,161,032.873302

Back = N 89° 59' 22" E
Ahead = S 83° 50' 57" E
Chord Bear = S 86° 55' 47" E

Course from PT PROP_FM545_120 to PC PROP_FM545_123 S 83° 50' 57" E Dist 1,277.211474

Curve Data

Curve PROP_FM545_123
P.I. Station 440+03.6151 X 2,605,626.314151 Y 7,162,869.491504
Delta = 11° 26' 09" (LT)
Degree = 4° 05' 33"
Tangent = 140.182006
Length = 279.432630
Radius = 1,400.000000
External = 7.000709
Long Chord = 278.969026
Mid. Ord. = 6.965876
P.C. Station 438+63.4331 X 2,605,486.939135 Y 7,162,884.511475
P.T. Station 441+42.8657 X 2,605,765.900199 Y 7,162,882.403905
C.C. X 2,605,636.943835 Y 7,164,276.452059
Back = S 83° 50' 57" E
Ahead = N 84° 42' 54" E
Chord Bear = S 89° 34' 02" E

Course from PT PROP_FM545_123 to PC PROP_FM545_126 N 84° 42' 54" E Dist 162.808038

Curve Data


Curve PROP_FM545_126
P.I. Station 443+97.0205 X 2,606,018.974527 Y 7,162,905.814535
Delta = 5° 13' 49" (RT)
Degree = 2° 51' 53"
Tangent = 91.346784
Length = 182.566690
Radius = 2,000.000000
External = 2.084972
Long Chord = 182.503310
Mid. Ord. = 2.082801
P.C. Station 443+05.6737 X 2,605,928.016088 Y 7,162,897.400428
P.T. Station 444+88.2404 X 2,606,110.321269 Y 7,162,905.902145
C.C. X 2,606,112.239464 Y 7,160,905.903065
Back = N 84° 42' 54" E
Ahead = N 89° 56' 42" E
Chord Bear = N 87° 19' 48" E

Course from PT PROP_FM545_126 to 26 N 89° 56' 42" E Dist 1,884.145456

Point 26 X 2,607,994.465858 Y 7,162,907.709225 Sta 463+72.3859

NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.



Congli Ye, P.E. 4/28/2021



**FM 545
HORIZONTAL ALIGNMENT DATA**

SHEET 7 OF 8

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	45
JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

Course from 26 to 27 S 89° 52' 34" E Dist 263.741814

Point 27 X 2,608,258.207055 Y 7,162,907.138426 Sta 466+36.1277

Course from 27 to 28 N 89° 51' 02" E Dist 568.710980

Point 28 X 2,608,826.916104 Y 7,162,908.620532 Sta 472+04.8387

Course from 28 to 29 N 89° 42' 15" E Dist 433.660538

Point 29 X 2,609,260.570865 Y 7,162,910.858892 Sta 476+38.4992

Course from 29 to 30 N 89° 54' 31" E Dist 700.809191

Point 30 X 2,609,961.379162 Y 7,162,911.978126 Sta 483+39.3084


Course from 30 to 31 N 89° 02' 18" E Dist 244.178998

Point 31 X 2,610,205.523759 Y 7,162,916.076786 Sta 485+83.4874

=====
Ending chain PROP_FM545 description

SUPERELEVATION TABLE

PC	PI	PT	BEGIN SUPER TRANSITION	END SUPER TRANSITION	END FULL SUPER	END SUPER TRANSITION	SUPERELEVATION RATE
				BEGIN FULL SUPER	BEGIN SUPER TRANSITION		e
STA.	STA.	STA.	STA.	STA.	STA.	STA.	%
46+31.62	48+21.80	49+91.49	45+10.24	46+61.96	49+61.15	51+12.87	6
60+09.79	62+74.78	65+12.26	58+92.96	60+39.00	64+83.05	66+29.09	5.7
78+60.81	81+98.71	83+89.91	77+39.43	78+91.15	83+59.57	85+11.29	6
137+86.10	139+42.11	140+93.95	136+73.64	138+14.17	140+65.88	142+06.23	5.4
148+85.92	150+41.37	151+92.70	147+73.64	149+13.99	151+64.63	153+04.98	5.4
156+06.28	157+62.69	159+04.48	154+84.90	156+36.62	158+74.14	160+25.86	6
162+33.22	164+49.89	166+16.67	161+11.84	162+63.56	165+86.33	167+38.05	6
169+45.19	170+76.75	172+04.22	168+26.85	169+74.78	174+74.63	173+22.65	5.8
179+68.55	180+88.22	182+02.91	178+47.17	179+98.89	181+72.57	183+24.29	6
183+23.82	185+70.72	187+63.60	182+02.44	183+54.16	187+33.26	188+84.98	6
188+20.83	189+56.03	190+83.51	186+99.45	188+51.17	190+53.17	192+04.89	6
388+41.39	390+22.65	391+74.45	387+20.01	388+71.73	391+44.11	392+95.83	6
393+00.43	394+88.03	396+46.31	391+79.05	393+30.77	396+15.97	397+67.69	6



Congli Ye, P.E. 4/28/2021



**FM 545
HORIZONTAL ALIGNMENT DATA
& SUPERELEVATION TABLE**

SHEET 8 OF 8

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	46
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	


NOTES:

1. THE HORIZONTAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.

VERTICAL CURVE INFORMATION								
VPI	ELEVATION	G1	G2	A	L	K	CREST/SAG	DESIGN SPEED
	(FT)	(%)	(%)		(FT)			(MPH)
14+21.75	677.72	1.8164	-2.4778	-4.2942	440	-102	CREST	50
29+59.85	639.61	-2.4778	1.8227	4.3005	200	47	SAG	30
32+73.73	645.33	1.8227	-1.4964	-3.3191	220	-66	CREST	45
35+41.82	641.32	-1.4964	3.8474	5.3438	200	37	SAG	30
42+04.55	666.82	3.8474	-1.3245	-5.1719	580	-112	CREST	50
49+40.46	657.07	-1.3245	1.4284	2.7529	480	174	SAG	65
60+16.88	672.45	1.4284	0.4082	-1.0202	270	-265	CREST	70
63+73.44	673.90	0.4082	1.8908	1.4826	360	243	SAG	80
75+83.29	702.45	1.8908	0.6337	-1.2571	150	-119	CREST	55
87+50.57	707.95	0.6337	-1.0541	-1.6878	150	-89	CREST	50
91+48.82	703.75	-1.0541	-2.5150	-1.4609	120	-82	CREST	45
97+87.13	687.70	-2.5150	-1.5627	0.9523	680	714	SAG	80
105+36.93	675.98	-1.5627	-2.6824	-1.1197	440	-393	CREST	80
110+66.62	661.77	-2.6824	1.4249	4.1073	610	149	SAG	60
115+29.07	668.36	1.4249	-1.6222	-3.0471	230	-75	CREST	45
125+72.81	651.43	-1.6222	3.2846	4.9068	600	122	SAG	55
131+88.21	671.64	3.2846	-5.3093	-8.5939	380	-44	CREST	40
137+58.90	641.34	-5.3093	1.9079	7.2172	530	73	CREST	45
144+22.38	654.00	1.9079	0.9740	-0.9339	140	-150	SAG	60
158+58.18	667.99	0.9740	-5.4190	-6.3930	1460	-228	CREST	65
174+05.95	584.11	-5.4190	0.2824	5.7014	230	40	SAG	35
183+99.80	586.92	0.2824	6.1092	5.8268	480	82	SAG	45
189+33.11	619.50	6.1092	0.5709	-5.5383	160	-29	CREST	35
281+72.73	599.25	-0.3710	3.0153	3.3863	430	127	SAG	55
291+20.45	627.82	3.0153	1.1666	-1.8487	890	-481	CREST	80
303+16.60	641.78	1.1666	-2.1800	-3.3466	700	-209	CREST	65
314+89.74	616.20	-2.1800	1.5512	3.7312	775	208	SAG	75
335+82.29	648.66	1.5512	-1.0143	-2.5655	780	-304	CREST	70
355+71.12	628.49	-1.0143	-0.0994	0.9149	1550	1694	SAG	80
387+92.65	625.29	-0.0994	-1.6792	-1.5798	170	-108	CREST	50
396+28.82	611.25	-1.6792	-0.9341	0.7451	800	1074	SAG	80
405+05.86	603.05	-0.9341	-2.4288	-1.4947	380	-254	CREST	70
409+70.90	591.76	-2.4288	2.0103	4.4391	530	119	SAG	65
416+36.63	605.14	2.0103	-5.6226	-7.6329	610	-80	CREST	45
446+78.80	545.04	-0.7488	1.3439	2.0927	520	248	SAG	80
457+97.38	560.08	1.3439	0.3762	-0.9677	350	-362	CREST	75
468+78.12	564.14	0.3762	4.3122	3.9360	750	191	SAG	70
479+38.01	609.85	4.3122	1.8371	-2.4751	330	-133	CREST	55
483+53.04	617.47	1.8371	-3.4512	-5.2883	235	-44	CREST	40

NOTES:

1. THE VERTICAL ALIGNMENT DATA SHOWN ON THIS PAGE IS FOR DESIGN PURPOSES ONLY. DO NOT USE THIS INFORMATION FOR CONSTRUCTION. PERFORM THE WIDENING OFF THE EXISTING ROADWAY ACCORDING TO THE TYPICAL SECTIONS.
2. TO VERIFY THE GEOMETRIC DATA SEE AS-BUILT CSJ 1012-02-001.







Congli Ye, P.E. 4/28/2021




FM 545
VERTICAL ALIGNMENT DATA

SHEET 1 OF 1

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	47
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. OVERLAY ONLY FOR DRIVEWAY 10.







Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021


**FM 545
PLAN SHEET**
BEGIN PROJECT TO STA. 23+00

SHEET 1 OF 21

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	48
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. OVERLAY ONLY FOR DRIVEWAY 11 AND 18.



Congli Ye, P.E. 4/28/2021





Texas Department of Transportation
© 2021

**FM 545
PLAN SHEET**


STA. 23+00 TO STA. 47+00

SHEET 2 OF 21

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO. 49
CHECK MS	TEXAS	DALLAS	COLLIN	
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. OVERLAY ONLY FOR DRIVEWAY 21.








Congli Ye, P.E. 4/28/2021



**FM 545
PLAN SHEET**
STA. 47+00 TO STA. 71+00

SHEET 3 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	50
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



Congli Ye, P.E. 4/28/2021

- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.







**FM 545
PLAN SHEET**


STA. 71+00 TO STA. 95+00

SHEET 4 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	51
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.



Congli Ye, P.E. 4/28/2021







**FM 545
PLAN SHEET**

STA. 95+00 TO STA. 119+00

SHEET 5 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	52
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
JRV				



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.

CONGLI YE
 82802
 LICENSED PROFESSIONAL ENGINEER





Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
 © 2021

**FM 545
 PLAN SHEET**
 STA. 119+00 TO STA. 143+00

SHEET 6 OF 21

DESIGN	CY	FED. RD. DIV. NO.	6	FEDERAL AID PROJECT NO.	SEE TITLE SHEET	HIGHWAY NO.	FM 545
GRAPHICS	CY	STATE	TEXAS	DISTRICT	DALLAS	COUNTY	COLLIN
CHECK	MS	CONTROL		SECTION		JOB	53
CHECK	JRV		1012		02		042, ETC.








- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.

 **Texas Department of Transportation**
© 2021

**FM 545
PLAN SHEET**
STA. 143+00 TO STA. 167+00

SHEET 7 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	54
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.



Congli Ye, P.E. 4/28/2021






- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. SEE "ROADWAY & SW3P SUMMARY" SHEET FOR BRIDGE REPAIR ITEMS.
 6. FIELD VERIFY THE LOCATIONS AND LIMITS OF THE BRIDGE REPAIR.



**FM 545
PLAN SHEET**
STA. 167+00 TO STA. 191+00

SHEET 8 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	55
CHECK	CONTROL	SECTION	JOB	
MS				
CHECK	JRV	1012	02	042, ETC.



Congliye, P.E. 4/28/2021



**FM 545
PLAN SHEET**







STA. 191+00 TO STA. 215+00

SHEET 9 OF 21

NOTES:

1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
5. TOM OVERLAY AND PROFILE RUMBLE STRIPS WORK ONLY FROM STA. 194+30 TO STA. 215+00.

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	56
CHECK	CONTROL	SECTION	JOB	
MS	JRV	1012	02	042, ETC.



Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021




**FM 545
PLAN SHEET**

STA. 215+00 TO STA. 239+00


SHEET 10 OF 21

- NOTES:
 1. TOM OVERLAY, PROFILE RUMBLE STRIPS, AND BRIDGE REPAIR WORK ONLY IN THIS SHEET.
 2. SEE "ROADWAY & SW3P SUMMARY" SHEET FOR BRIDGE REPAIR ITEMS.
 3. FIELD VERIFY THE LOCATIONS AND LIMITS OF THE BRIDGE REPAIR.

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	57
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.



NOTES:
1. TOM OVERLAY AND PROFILE RUMBLE STRIPS WORK ONLY IN THIS SHEET.







Congli Ye, P.E. 4/28/2021



**FM 545
PLAN SHEET**
STA. 239+00 TO STA. 263+00
SHEET 11 OF 21


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	58
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.



BEGIN CSJ: 1012-02-036
 END TOM OVERLAY
 BEGIN SHOULDER WIDENING
 BEGIN PAVEMENT TRANSITION
 END PROFILE RUMBLE STRIPS
 BEGIN MILLED RUMBLE STRIPS
 C/L FM 545
 STA. 280+00

END PAVEMENT TRANSITION
 C/L FM 545
 STA. 281+00

- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. TOM OVERLAY AND PROFILE RUMBLE STRIPS WORK ONLY FROM STA. 263+00 TO STA. 280+00.



Congli Ye, P.E. 4/28/2021








**FM 545
 PLAN SHEET**

STA. 263+00 TO STA. 287+00

SHEET 12 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	59
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.

Texas Department of Transportation
© 2021





**FM 545
PLAN SHEET**
STA. 287+00 TO STA. 311+00

SHEET 13 OF 21


DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	60
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

MATCH LINE STA. 311+00

MATCH LINE STA. 323+00



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. OVERLAY ONLY FOR DRIVEWAY 47.



Congli Ye, P.E. 4/28/2021




**FM 545
PLAN SHEET**

STA. 311+00 TO STA. 335+00


SHEET 14 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	61
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.


MATCH LINE STA. 335+00





MATCH LINE STA. 347+00



MATCH LINE STA. 347+00



MATCH LINE STA. 359+00



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.

Congli Ye, P.E. 4/28/2021



**FM 545
PLAN SHEET**



STA. 335+00 TO STA. 359+00

SHEET 15 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	62
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRJ	1012	02	042, ETC.	



MATCH LINE STA. 359+00

MATCH LINE STA. 371+00




MATCH LINE STA. 371+00

MATCH LINE STA. 383+00



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.



Congli Ye, P.E. 4/28/2021






**FM 545
PLAN SHEET**


STA. 359+00 TO STA. 383+00

SHEET 16 OF 21

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 63
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.








Congli Ye, P.E. 4/28/2021


Texas Department of Transportation
© 2021

**FM 545
PLAN SHEET**
STA. 383+00 TO STA. 407+00
SHEET 17 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	64
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
 5. PROFILE RUMBLE STRIPS AND BRIDGE REPAIR WORK ONLY FROM STA. 422+00 TO STA. 431+00.
 6. SEE "ROADWAY & SW3P SUMMARY" SHEET FOR BRIDGE REPAIR ITEMS.
 7. FIELD VERIFY LOCATIONS AND LIMITS OF THE BRIDGE REPAIR.



Congli Ye, P.E. 4/28/2021







**FM 545
PLAN SHEET**

STA. 407+00 TO STA. 431+00


SHEET 18 OF 21

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	65
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	



NOTES:

1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.
5. PROFILE RUMBLE STRIPS AND BRIDGE REPAIR WORK ONLY FROM STA. 431+00 TO STA. 446+70.
6. SEE "ROADWAY & SW3P SUMMARY" SHEET FOR BRIDGE REPAIR ITEMS.
7. FIELD VERIFY LOCATIONS AND LIMITS OF THE BRIDGE REPAIR.



Congli Ye, P.E. 4/28/2021







**FM 545
PLAN SHEET**

STA. 431+00 TO STA. 455+00


SHEET 19 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	66
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.



NOTES:

1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.



Congli Ye, P.E. 4/28/2021





**FM 545
PLAN SHEET**

STA. 455+00 TO STA. 479+00

SHEET 20 OF 21

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	67
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	




END PROJECT CSJ 1012-02-042, ETC.
 END CSJ: 1012-02-038
 END CSJ: 1012-02-042
 END WIDENING
 END PAVEMENT TRANSITION
 MATCH EXISTING PAVEMENT
 C/L FM 545
 STA. 485+54.50

- NOTES:
1. SEE "TYPICAL SECTIONS" SHEET FOR ADDITIONAL INFORMATION.
 2. SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ADDITIONAL INFORMATION.
 3. SEE "VERTICAL ALIGNMENT DATA & SUPERELEVATION TABLE" SHEET FOR SUPERELEVATION INFORMATION.
 4. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEET AND "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL DRIVEWAY INFORMATION.


Congli Ye, P.E. 4/28/2021

 © 2021				
FM 545 PLAN SHEET STA. 479+00 TO END PROJECT SHEET 21 OF 21				
DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK	JRV			68

**ASPHALT DRIVEWAY
OVERLAY DETAILS
W/PIPE REPLACEMENT**




PLAN VIEW




SECTION A-A

**ASPHALT DRIVEWAY
OVERLAY DETAILS
WITHOUT PIPE REPLACEMENT**




PLAN VIEW




SECTION B-B

CONCRETE DRIVEWAYS




PLAN VIEW




SECTION C-C

NOTES:

- 1) DRIVEWAY LOCATIONS MAY BE SHIFTED AT TIME OF CONSTRUCTION AS DIRECTED BY THE ENGINEER TO MATCH EXISTING CONDITIONS.
- 2) MATCH EXISTING DRIVEWAY WIDTH WITH A MINIMUM OF 11'.
- 3) MATCH EXISTING DRIVEWAY RADIUS WITH A MINIMUM OF 15'.
- 4) SEE "DRIVEWAY SUMMARY" SHEET FOR ADDITIONAL INFORMATION.



TYPICAL PAVEMENT TRANSITION




Congli Ye, P.E. 4/28/2021




**FM 545
MISCELLANEOUS
ROADWAY DETAILS**


SCALE: NTS			SHEET 1 OF 2
DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY
CHECK MS	TEXAS	DALLAS	COLLIN
CHECK JRV	CONTROL	SECTION	JOB
	1012	02	042, ETC.
			69



**CUT & RESTORE DETAIL
SIDE VIEW**



**CUT & RESTORE DETAIL
PLAN VIEW**




**CONCRETE COLLAR FOR
PIPE CONNECTION DETAIL**

THIS DETAIL IS TO ALSO BE USED
ON ALL CONNECTIONS BETWEEN
NEW AND EXISTING PIPES.

NOTES:

1. SEE THE TxDOT BARRICADE AND CONSTRUCTION AND TRAFFIC CONTROL PLAN STANDARDS FOR ADDITIONAL INFORMATION.
2. SEE CULVERT LAYOUTS FOR ADDITIONAL INFORMATION.
3. CULVERTS SHALL BE CONSTRUCTED FROM DOWNSTREAM TO UPSTREAM.
4. MAINTAIN POSITIVE DRAINAGE DURING CULVERT CONSTRUCTION.
5. MATCH EXISTING CROSS SLOPES AND ELEVATIONS.
6. PROVIDE DAYTIME ONE-WAY TRAFFIC CONTROL AS NECESSARY FOR PHASED CONSTRUCTION. RE-OPEN FM 545 TO TWO-WAY TRAFFIC AT THE CONCLUSION OF EACH DAY'S WORK.

DATE: 8/20/21 FILE NAME: 8F1LE\$



Congli Ye, P.E. 4/28/2021




**FM 545
MISCELLANEOUS
ROADWAY DETAILS**

SCALE: NTS			SHEET 2 OF 2
DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	
GRAPHICS CY	STATE	DISTRICT DALLAS	HIGHWAY NO. FM 545
CHECK MS	TEXAS	COUNTY COLLIN	SHEET NO. 69A
CHECK JRV	CONTROL	SECTION 042, ETC.	





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




TWO LANE TWO-WAY ROADWAYS

CENTERLINE RUMBLE STRIPS




PROFILE VIEW




PLAN VIEW
OPTION 1

MILLED CENTERLINE RUMBLE STRIPS




PLAN VIEW
OPTION 2

RAISED CENTERLINE RUMBLE STRIPS



PLAN VIEW
OPTION 3

RAISED CENTERLINE RUMBLE STRIPS AND PREFORMED THERMOPLASTIC STRIPS



PLAN VIEW
OPTION 4

PROFILE CENTERLINE MARKINGS AND PREFORMED THERMOPLASTIC STRIPS

GENERAL NOTES

1. This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
2. Centerline and edgeline rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks.
6. Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, and dimensions pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inch depth of milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips.

WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
11. The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.

WHEN INSTALLING EDGELINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

12. See standard sheet RS(4).




CENTERLINE RUMBLE STRIPS ON TWO LANE TWO-WAY HIGHWAYS

RS(3) - 13


FILE: r's(3) - 13.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	70	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




PLAN VIEW




PROFILE VIEW
OPTION 1

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW




PROFILE VIEW
OPTION 2

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW

* This distance may vary based on width of shoulder




PROFILE VIEW
OPTION 3

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW




PROFILE VIEW
OPTION 4

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)



PLAN VIEW
OPTION 5

RAISED EDGELINE RUMBLE STRIPS



PLAN VIEW
OPTION 6

PROFILE EDGELINE MARKINGS

SHOULDER WIDTH TABLE		
EQUAL TO OR LESS THAN 2 FEET	GREATER THAN 2 FEET LESS THAN 4 FEET	EQUAL TO OR GREATER THAN 4 FEET
Option 1, 5 OR 6	Option 1, 2, 3 5 OR 6	Option 2, 4, 5 OR 6

GENERAL NOTES

- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
- See the table below for determining what options may be used for edgeline rumble strips.

WHEN INSTALLING MILLED DEPRESSION EDGELINE RUMBLE STRIPS:





- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
- Pavement markings can be applied over milled shoulder rumble strips to create an edgeline rumble stripe.
- Breaks in edgeline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inches depth of milled rumble strip may be considered in these areas.

- On roadways with high bicycle activity, consideration should be given before the installation of edgeline rumble strips. Things to consider include size of rumble strips, rumble strip material and location of rumble strips on the shoulder. If the designer determines that gaps are needed in the rumble strips due to bicycle use of the road, then follow the requirement shown in FHWA Technical Advisory T5040.39, or latest version. A detail of the spacing shall be included in the plans.

WHEN INSTALLING RAISED OR PROFILE EDGELINE RUMBLE STRIPS:

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edgeline when used as a rumble strip. The color of the button should match the color of the adjacent edgeline marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Breaks in edgeline rumble strips using raised traffic buttons shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks when installed on conventional highways.
- The minimum distance between the edgeline and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edgelines may substitute for buttons.

		Traffic Operations Division Standard	
EDGELINE RUMBLE STRIPS ON UNDIVIDED OR TWO LANE HIGHWAYS RS(4)-13			
FILE:	rs(4)-13.dgn	DN:	TxDOT
©TxDOT	October 2013	CK:	TxDOT
REVISIONS:		DW:	TxDOT
		CK:	TxDOT
		CON:	
		SECT:	
		JOB:	
		HIGHWAY:	
		1012	02
		042, ETC.	FM 545
		DIST:	COUNTY
		DAL	COLLIN
		SHEET NO.	70A




@ IF BACKFILLED SLOPE IS LESS THAN 3:1, COVER WEDGE WITH APPROVED BACKFILL.

* SEE TYPICAL SECTION FOR DEPTH AND TYPE OF HMA.
 # NOTCH DEPTH SHALL NOT BE LESS THAN NOMINAL AGGREGATE SIZE.

NOTES:

1. THE ABOVE DETAILS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LANE WIDTH AND BE LAID MONOLITHICALLY WITH ADJOINING MAT. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED STRIKE-OFF DEVICE THAT WILL PROVIDE A UNIFORM SLOPE AND WILL NOT RESTRICT THE MAIN SCREED. CLEAN WEDGE PRIOR TO PLACEMENT OF TACK COAT. TACK COAT SHALL BE APPLIED UNIFORMLY TO THE IN-PLACE TAPER WITH A DISTRIBUTOR BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED. COMPACTION OF THE INITIAL TAPER SECTION WILL BE REQUIRED AS NEAR TO FINAL DENSITY AS POSSIBLE. ROLL ADJACENT MAT FROM HOT SIDE TO COLD.
2. THE TYPE OF DEVICE TO PRODUCE ABOVE REFERENCED DETAILS SHALL PROVIDE INITIAL COMPACTION EQUIVALENT TO LAYDOWN MACHINE, WITH FINAL DENSITY ADHERING TO NOTE 1, AND BE APPROVED BY THE ENGINEER.
3. HOT MIX MATERIAL AND PLACEMENT SHALL BE PAID FOR UNDER THE PERTINENT ITEM. ANY ADDITIONAL SURFACE PREPARATION, TACK COAT, TACK COAT PLACEMENT, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS TO PRODUCE TAPERED EDGE AND JOINTS AS DESCRIBED ABOVE SHALL BE CONSIDERED SUBSIDIARY TO THE HOT MIX ITEM.
4. THE TAPERED JOINT DETAIL IS NOT INTENDED FOR USE ON 2 WAY 2 LANE ROADBED CENTERLINE WITH LESS THAN 22' OVERALL WIDTH.
5. FULL PAVING OF ALL LANES AND SHOULDRS BY THE END OF EACH DAY PRODUCTION WILL NOT REQUIRE A TAPERED JOINT.


HOT MIX EDGE AND LONGITUDINAL JOINT DETAILS
DALLAS DISTRICT STANDARD
LJD(1-1)-07


FED. RD. DIV. NO.	PROJECT NUMBER	SHEET NUMBER
18	SEE TITLE SHEET	71
STATE	DISTRICT	COUNTY
TEXAS	DALLAS	COLLIN
CONTROL	SECTION	HIGHWAY NUMBER
1012	02	042, ETC. FM 545

REVISED ON 9/10/08

FILENAME: SFILES\$


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS


CONDITION - 1
THIN HMAC SURFACES OR HMAC OVERLAY
WITH THICKNESS OF 2.5" OR LESS



** EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 2
OVERLAY OF EXISTING PAVEMENT
HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 3
NEW OR RECONSTRUCTED PAVEMENT
HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 4
NEW OR RECONSTRUCTED PAVEMENT
HMAC THICKNESS 5" OR GREATER


GENERAL NOTES

1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

(NOT TO SCALE)

					Design Division Standard
TAPERED EDGE DETAILS HMAC PAVEMENT					
TE (HMAC) - 11					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS		1012	02	042, ETC.	FM 545
DIST	COUNTY		SHEET NO.		
DAL	COLLIN		72		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SINGLE AND DOUBLE MAILBOX MOUNT
FOR SUPPORT/FOUNDATION
DETAILS SEE SHEET 3 OF 4

* Type 2 object marker in accordance with Traffic Engineering standard Delineators & Object Markers - Installation D&OM (1) or tube type post wrapped with 12" Conformable Reflective Sheeting in accordance with DMS 8300 for tubular post needed to produce a smooth wrap around tube, DHT 161812 or 3 each of 3" x 4" Conformable Reflective Sheeting tabs (DHT 165382) or 1 each of 3" x 12" Reflective Sheeting.

Note: Mailbox installations in sidewalk areas shall be in accordance with the latest TxDOT Pedestrian Facilities Curb ramps standard *PED-XX for pedestrian facilities.

*PED-XX: XX is the standard year for example PED-12, PED-13, etc.



PLACEMENT OF EMERGENCY LOCATION NUMBER

Location Number shall be placed on: 1. A yellow, type A plate with class 1 flat surface reflective sheeting in accordance with DMS 8600. The color of numbers shall be black, or 2. A green or blue plate with white numbers attached to post beside the object marker. Other contrasting color configuration, as approved, may be used. (Use Same type plate as used for the type 2 Object Marker. Recommended sign size is 6" by 15")

SIZE	TYPICAL MAILBOX SIZE			LIGHT WEIGHT MATERIAL	
	LENGTH	WIDTH	HEIGHT	SHEET METAL	**PLASTIC
	INCHES			POUNDS	
SMALL	19 1/2	6	7	5	5
MEDIUM	22 1/2	8	11 1/2	7	7
LARGE	23 1/2*	11 1/2*	13 1/2*	10	10

* Maximum allowed dimensions for mailbox
** Excluding Molded Plastic on 4 X 4 Post


VIEW	LOCKABLE ARCHITECTURAL MAILBOX SIZE (INCHES)				
	TOP	BOTTOM	FRONT SIDE	BACK SIDE	WEIGHT
SIDE	18	15	18.3	15	(POUNDS)
BACK	11 1/2	11 1/2		15	22.4

SEE TOP RIGHT CORNER OF SHEET 2 OF 4


Mailboxes shall be made of light weight sheet metal or light weight plastic. Lockable architectural mailboxes shall meet the requirements of the above table.

Heavy steel, cast iron or decorative mailboxes shall not be used on the state highway system.

MAILBOX SIZES




MULTIPLE MAILBOX PLACEMENT



Clear Distance between single or double mounted posts. (Normally when 3 or more mailboxes are in one location, a multiple support is used).

SINGLE & DOUBLE MAILBOX PLACEMENT



DOUBLE AND MULTIPLE MAILBOX MOUNT


FOR SUPPORT/FOUNDATION
DETAILS SEE SHEET 3 OF 4
FOR DHT NUMBERS
SEE SHEET 4 OF 4

NEWSPAPER RECEPTACLE

A light weight receptacle for newspaper delivery can be attached to mailbox posts as shown on this page if the receptacle:

- Does not touch the mailbox.
- Does not present a hazard to traffic or delivery of the mail.
- Does not extend beyond the front of the mailbox.
- Does not display advertising, except the publication title.
- Newspaper receptacles on separate supports are prohibited.

LOCKABLE ARCHITECTURAL MAILBOX



MULTIPLE MAILBOX MOUNT


INDEX OF MAILBOX DETAIL SHEETS

- 1 of 4 MAILBOX MOUNTING AND SPACING
- 2 of 4 MAILBOX BRACKET CONNECTING DETAILS
- 3 of 4 MAILBOX SUPPORT / FOUNDATION
- 4 of 4 TABLE OF DHT NUMBERS


MAILBOX MOUNTING AND SPACING
MB-15(1)

FILE:MB14(1).DGN	DW: JEO	CK: JEO	DW:	CK:
© TxDOT APRIL 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS:	1012	02	042, ETC.	FM 545
Added additional newspaper receptacle for double mailbox support	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN		73


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SINGLE MAILBOX



DOUBLE MAILBOX




MULTIPLE MAILBOX




WELDED SINGLE MAILBOX BRACKET


WELDED DOUBLE MAILBOX BRACKET WITH ADAPTER PLATE



LOCKABLE ARCHITECTURAL MAILBOX CONNECTION DETAILS



SMALL MAILBOX



MEDIUM AND LARGE MAILBOXES


GENERAL NOTES

1. Connecting hardware detailed on this sheet is for the hardware that the Department stocks at the Regional Warehouses. This hardware is available to the contractor only when so stated elsewhere in the plans or specification.
2. Hardware for mounting mailboxes to the support/foundation furnished by industry should be used when shown on the Maintenance Divisions "Approved Products List." Only mailbox hardware that have been crash tested in accordance with NCHRP Report 350, will be on the approved list.
3. Hardware furnished by industry shall be erected in accordance with the manufacturer's recommendation.
4. Bracket and bracket extension shall be constructed of 14 gauge galvanized steel sheet metal.
5. The angles, brackets and adapter plates shall be constructed of 12 gauge galvanized steel sheet metal.
6. Items with evidence of damage to the galvanized coating or wet storage stains (white rust) will not be accepted.


SHEET 2 OF 4






MAILBOX BRACKET CONNECTING DETAILS MB-15(1)



For use with galvanized thinwall steel posts DHT # 143426 or powder-coated thinwall steel post DHT # 162911.




For use with RCR post DHT # 161442 or galvanized thinwall steel post DHT # 143426 or powder-coated thinwall steel post. DHT # 162911.




HARDWARE AT TxDOT REGIONAL WAREHOUSES




Brackets and adapter plate shown in this section should be available to the Contractor when stated elsewhere in plans or specifications.



DHT 148939
Mailbox Bracket










DHT 148938
Used for extending 6" wide bracket to attach larger mailboxes.
Bracket Extension



See Table of Applicable DHT Numbers on sheet 4 of 4 for DHT description and unit of measure.

FILE:MB14(1).DGN	DW: JEO	CK:	DW: JEO	CK:
© TxDOT APRIL 2015	CONT	SECT	JOB	HIGHWAY
ADDED DHT 163730	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	74	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GENERAL NOTES

- Erect post plumb or vertical.
- When galvanized part is required galvanize in accordance with Item 445.
- type 1, 2, 3, 4 or 7 supports or foundation can be used for single or double mailbox installations. The RCR post should be used only for a single installation with a small mailbox. The Type 5 support/foundation is used for the single molded plastic mailbox. The Type 4 support/foundation is used for the 2.375" O.D. RR post, thin wall steel post, and white multiple mailbox post.
- The Type 1 or type 7 support/foundation can be used for a multiple mailbox mount.
- The Type 4 support should be used with thin wall steel pipe for the medium, large and double mailbox installations.
- Use a concrete footing as shown or when directed. Concrete footing will be required when soils do not hold the support/foundations in a stable condition.

MB-(X) ASSM TY (XXX) (X) (XX) (OPTIONAL)

Type of Mailbox
S = Single
D = Double
M = Multiple
SP = Single Plastic

Type of Post
WC = Winged Channel Post
RR = Recycled Rubber
TWW = Thin Walled White Tubing
TWG = Thin Walled Galvanized Tubing
TIM = Timber

Type of Foundation
Ty 1 = V-Loc
Ty 2 = Wedge Anchor Steel System
Ty 3 = Winged Channel post
Ty 4 = Wedge Anchor Plastic System
Ty 5 = 4 X 4 Post
Ty 7 = Wedge Anchor

Type of Bracket
AB = Angle Bracket.
TB = 2.375" Tube Bracket

*HDTIP: High density thermoplastic polyesters

DOUBLE AND LARGE MAILBOXES MUST BE ON STEEL POST.

FILE:MB14(1).DGN
DN: JEO
CK:
DW: JEO
CK:

© TxDOT APRIL 2015
REVISIONS

CONT	SECT	JOB	HIGHWAY
1012	02	042, ETC.	FM 545
DIST	COUNTY	SHEET NO.	
DAL	COLLIN	75	

SHEET 3 OF 4

Maintenance Division Standard


MAILBOX SUPPORT AND FOUNDATION
MB-15(1)

LOCKABLE ARCHITECTURAL MAILBOX

SINGLE-MOUNT INSTALLATION PARTS

#	PART NAME	PART/DHT #	QTY
1	SOCKET, TYPE 4 FOUNDATION	160891	1
2	WEDGE FOR TYPE 4 FOUNDATION	160892	1
3	THIN-WALL WHITE STEEL TUBE 2.375 OD	162911	1
4	BRACKET FOR ATTACHING MAILBOX	161443	1
5	ARCHITECTURAL MAILBOX	SEE NOTE	1
6	NUT, 5/16" HEX	NUT, 5/16" HEX	1
7	BOLT, 5/16 X 3 HEX	GRADE 5	1
8	PLATE WASHER FOR ARCHITECTURAL MAILBOX	SEE SEE SHEET 2	2
9	WASHER, 3/8 FLAT		8
10	WASHER, 3/8 LOCK		4
11	NUT, 3/8 HEX		4
12	BOLT, 3/8 X 1-1/4 HEX	GRADE 5	4
13	CONCRETE, CLASS B (2000 PSI)		1

LOCKABLE ARCHITECTURAL MAILBOX DETAILS



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TABLE OF APPLICABLE DHT NUMBERS

DHT NUMBER	DESCRIPTION
FOUNDATIONS	
46625	WEDGE FOR V-WING SOCKET FOR TYPE 1 FOUNDATION
149340	V-WING SOCKET FOR TYPE 1 FOUNDATION
143433	WEDGE FOR TYPE 2 FOUNDATION
143434	ANCHOR FOR TYPE 2 FOUNDATION
166103	ANCHOR FOR TYPE 7 FOUNDATION
160891	SOCKET FOR TYPE 4 FOUNDATION
160892	WEDGE FOR TYPE 4 FOUNDATION
166104	WEDGE FOR TYPE 7 FOUNDATION
POSTS	
4289	WINGED CHANNEL MAILBOX POST
149339	MULTIPLE MAILBOX POST (GALVANIZED TUBING)
164116	MULTIPLE MAILBOX POST (WHITE COATED)
166114	MULTIPLE MAILBOX POST (WHITE COATED OCTAGONAL)
166153	MULTIPLE MAILBOX POST (GALVANIZED OCTAGONAL)
161442	RECYCLED RUBBER POST. FOR SMALL MAILBOX ONLY
143426	THIN-WALL GALVANIZED STEEL TUBE 2.375" OUTER DIAMETER
162911	THINWALL WHITE STEEL TUBE 2.375" OUTER DIAMETER
	SINGLE OR DOUBLE THIN-WALL MAILBOX POST GALVANIZED
166152	2" OCTAGONAL
	SINGLE OR DOUBLE THIN-WALL MAILBOX POST WHITECOATED
166112	2" OCTAGONAL
REFLECTIVE SHEETING	
161812	REFLECTIVE SHEETING FOR EMERGENCY LOCATION NUMBER PANEL
CONNECTING HARDWARE	
2917	ANGLE BRACKET USED FOR TEMPORARY MAILBOX SUPPORT
166105	BRACKET FOR SINGLE MOUNTING OF MAILBOXES (MOUNTING KIT)
3789	PLATE FOR DOUBLE MOUNTING OF MAILBOXES
166108	BRACKET FOR DOUBLE MOUNTING OF MAILBOXES (MOUNTING KIT)
166111	BRACKET FOR MULTIPLE MOUNTING OF MAILBOXES (MOUNTING KIT)
148939	BRACKET FOR ATTACHING SMALL OR MEDIUM SIZE MAIL BOX
148938	EXTENDER TO BRACKET FOR ATTACHING LARGE MAILBOX
159489	ANGLE BRACKET PART A
159490	ANGLE BRACKET PART B
	BRACKET FOR DOUBLE MOUNTING OF MAILBOXES ON THINWALL
162323	STEEL POST, GALVANIZED OR POWDERCOATED.
	BRACKET FOR ATTACHING MAILBOX TO RECYCLED RUBBER POST
161443	AND TO MULTIPLE WHITE MAILBOX POST
158358	CASTING (NEWSPAPER RECEPTACLE BRACKET)
163731	U-BOLT (NEWSPAPER RECEPTACLE BRACKET)
160698	BOLT; HEX HEAD, GALV; 3/8"DIA X 3/4"L HD, W/2-FLAT WASHERS
163750	BOLT; HEX HEAD, GALV; 3/8" X 1-1/2, 16 NC, W/WASHERS
160701	BOLT; HEX HEAD, GALV; 3/8"DIA X 2-1/2"L, HD, W/2-FLAT WASHERS
163730	BOLT; HEX HEAD, GALV; 3/8" X 3-1/2", NC, W/NUT, 2 FLAT WASHERS
160699	BOLT; HEX HEAD, GALV; 3/8"DIA X 3-3/4"L HD, W/2-FLAT WASHERS
160700	BOLT; HEX HEAD, GALV; 3/8"DIA X 4"L HD, W/2-FLAT WASHERS


SHEET 4 OF 4




**DHT NUMBERS TABLE
MB-15(1)**

FILE:MB14(1).DGN	DN:	CK:	DW:	CK:
© TxDOT APRIL 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	76	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




CASE 1. OFF TRAVEL WAY DELIVERY



CASE 2. BACK SIDE DELIVERY




CASE 3. DELIVERY NEAR RIGHT OF WAY LINE




PLAN CASE 1

GENERAL NOTES:

1. CASE 1 IS THE MOST COMMON METHOD.
2. TURN OUT BEHIND MAILBOX FOR CASE 2 WILL NORMALLY BE ALLOWED FOR NATURAL TERRAIN THAT WILL SERVE AS AN ALL WEATHER SURFACE.
3. ALL WEATHER DRIVEWAYS FOR CASE 3 MAILBOXES LOCATED AT THE RIGHT OF WAY LINE SHOULD NORMALLY BE PLACED IN CONJUNCTION WITH COUNTY ROADS OR OTHER CONNECTING COMMUNITY ROADS OR STREETS. IF THE NUMBER OF MAILBOXES EXCEEDS FOUR, A COMMUNITY MAIL BOX SHOULD BE ENCOURAGED AT THESE LOCATIONS.



DETAIL A



TYPICAL SECTION CASE 1

↑ MAIL DELIVERY VEHICLE TRAVEL DIRECTION


SHEET 1 OF 3

		Maintenance Division Standard	
<i>Guideline</i> MAILBOX SIDE ROAD PLACEMENT AND TURNOUTS MB-14(2)			
FILE: MB14(2).DGN	DN: JEO	CK:	DW: JEO
© TxDOT MAY 2014	CONT	SECT	JOB
REVISIONS	1012	02	042, ETC.
DECEMBER 2012-NEW TxDOT TITLE BLOCK	DIST	COUNTY	SHEET NO.
	DAL	COLLIN	77


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:




MAILBOX SIDEWALK INSTALLATION RELATIVE TO ANY OTHER OBSTRUCTION SUCH AS A SIGN (MINIMUM BORDER DISTANCE)




PLAN VIEW



ELEVATION



MAILBOX SIDEWALK INSTALLATION (DESIRABLE BORDER DISTANCE)



PLAN VIEW

SHEET 2 OF 3




SINGLE MAILBOX PLACEMENT BEHIND CURBS WITH OR WITHOUT SIDEWALKS
MB-14(2A)


FILE: MB-14(2A)	DN:	CK:	DW:	CK:
© TxDOT MAY 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	78	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:




MAILBOX SIDEWALK INSTALLATION RELATIVE TO ANY OTHER OBSTRUCTION SUCH AS A SIGN (MINIMUM BORDER DISTANCE)




PLAN VIEW



MAILBOX SIDEWALK INSTALLATION (DESIRABLE BORDER DISTANCE)



PLAN VIEW



*OBJECT MARKER TYPE 2
SEE MB13(01) FOR MORE MULTIPLE MAILBOX SUPPORT TYPES
DIRECTION OF VEHICULAR TRAFFIC IN ADJACENT LANE

SHEET 3 OF 3




MULTIPLE MAILBOX PLACEMENT BEHIND CURBS WITH OR WITHOUT SIDEWALKS

MB-14(2B)


FILE: MB-14(2A)	DN:	CK:	DW:	CK:
© TxDOT MAY 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
DIST	COUNTY		SHEET NO.	
DAL	COLLIN		79	

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE:
FILE:




WOOD BLOCK TO RECTANGULAR WOOD (CRT) POST
Showing the required 3 1/2" Dia. holes.




(CRT) POST DETAIL CONTROLLED RELEASE TERMINAL POST


Two or more wood CRT post(s) are required at any radius installation located at intersecting roadways or driveways.



WOOD BLOCK TO ROUND WOOD (CRT) POST
Showing the required 2 1/2" Dia. holes.



RAIL SPLICE DETAIL



PLAN VIEW SHOWING TYPICAL RADIUS


The required radius is shown elsewhere on the plans.

GENERAL NOTES

- The type of (CRT) post (round wood post, or rectangular wood post) will be shown elsewhere in the plans. The exact position of MBGF shall be shown elsewhere in the plans or as directed by the Engineer.
- Steel posts are not permitted at CRT post positions.
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans. The Contractor may furnish rail elements of 12 1/2 or 25 foot nominal lengths.
- Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the nut (ASTM A563) and Type A (1 3/4" O.D.) washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 5/8" x 1 1/4" (or 2" long at triple rail splices) with a 3/8" double recessed nut (ASTM A563).
- Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item.
- Crown shall be widened to accommodate the Metal Beam Guard Fence.
- The lateral approach to the guard fence, shall have a slope rate of not more than 1V:10H.
- Unless otherwise shown in the plans, guard fence placed in the vicinity of curbs shall be positioned so that the face of curb is located directly below or behind the face of the block. Rail placed over curbs shall be installed so that the post bolt is located approximately 21 inches above the gutter pan or roadway surface.
- If solid rock is encountered within 0 to 18" of the finished grade, drill a 22" dia. hole, 24" into the rock, or drill two 12" dia. front to back overlapping holes, 24" into the rock. If solid rock is encountered below 18", drill a 12" dia. hole, 12" into the rock or to the standard embedment depth, whichever is less. Any excess post length, after meeting these depths, may be field cut to ensure proper guardrail mounting height. Backfill with a cohesionless material.
- Guardrail posts shall not be set in concrete, of any depth.
- Special rail fabrication will be required at installations having a curvature of less than 150 ft. radius. The required radius shall be shown on the plans.
- The terminal anchor section (TAS) post shall be set in Class A concrete (unless otherwise shown in the plans) in accordance with Item 421, "Hydraulic Cement Concrete." Concrete shall be subsidiary to the bid item requiring construction of the terminal anchor section (TAS). Terminal anchor post to be galvanized in accordance with Item 445, "Galvanizing."
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.

"DRIVEWAY" TERMINAL ANCHOR SECTION

Only for use within driveway locations, where a standard (TAS) Terminal Anchor Section can not be installed.



ELEVATION LAYOUT

GENERAL NOTES

- The "Driveway" Terminal Anchor Section is ONLY to be used within driveway locations, where the ROW is limited and a standard 25 ft. (TAS) Terminal Anchor Section, is too long.
- Terminal anchor post shall be set in Class A concrete.
- All steel shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."






PLATE WASHER FOR METAL BEAM
(Galvanized after fabrication)



ANCHOR POST



RAIL ADAPTER
Rail - 10 gauge
(Galvanized after fabrication)


ONLY FOR USE IN MAINTENANCE REPAIRS OR HIGHLY CONSTRAINED SITE CONDITIONS.



METAL BEAM GUARD FENCE (SHORT RADIUS) MBGF (SR) - 19


FILE: mbgfsr19.dgn	DN: TxDOT	CK: KM	DW: BD	CK: VP
© TxDOT NOVEMBER 2019 REVISIONS	CONT	SECT	JOB	HIGHWAY
	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	80	

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)



SECTION A-A


Typical



MOW STRIP DETAIL


Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
 2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
 3. The leave-out behind the post shall be a minimum of 7".
 4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
 5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
 6. Thickness of the mow strip will be 4".
 7. The limits of payment for reinforced concrete will include leave-outs for the posts.
 8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)

Curb shown on top of mow strip




CURB OPTION (3)

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF(31)MS-19			
FILE: gf31ms19.dgn	DN:TxDOT	CK:KM	DW:VP
©TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	1012	02	042, ETC.
	DIST	COUNTY	SHEET NO.
	DAL	COLLIN	81

DATE:
FILE:


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:




TYPICAL POST PLACEMENT


NOTE: (SEE GENERAL NOTE 14 FOR RAIL HEIGHT MEASUREMENT)



WOOD BLOCK TO ROUND WOOD POST




WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST


GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
- 13.



ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.

SPLICE BOLT LENGTH VARIES

FBB01 = 1 1/4"

FBB02 = 2"


POST & BLOCK LENGTH

FBB03 = 10"

FBB04 = 18"

BUTTON HEAD BOLT


NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.


NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

		Design Division Standard	
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19			
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	1012	02	042, ETC
	DIST	COUNTY	FM 545
	DAL	COLLIN	SHEET NO. 82

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE:
 FILE:

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.



**RECTANGULAR CRT POST
(6" X 8" X 6' LONG)**

(6) CRT REQUIRED
SEE ELEVATION DETAIL FOR LOCATIONS




**LATERAL OFFSET BETWEEN THE
GUARDRAIL AND THE CULVERT HEADWALL**

GENERAL NOTES

1. THE TYPE OF LINE POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF THE TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENT SHALL MEET ALL REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 12'-6" OR 25'-0" NOMINAL LENGTHS.
3. RAIL POST HOLES ARE OFFSET 3'-1 1/2" FROM STANDARD GUARDRAIL TO ACCOMMODATE THE MIDSPAN SPLICING.
4. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC160) AND NO MORE THAN 1" BEYOND IT.
5. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
6. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
7. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
8. REFER TO GF(31) STANDARD SHEET FOR ADDITIONAL DETAILS.
9. FLAME CUTTING OF HOLES IN GUARDRAIL SHALL NOT BE PERMITTED. IF YOU ENCOUNTER MIS-ALIGNED BOLT HOLES IN GUARDRAIL CONTACT THE DESIGN DIVISION FOR ADDITIONAL INFORMATION & OPTIONS.

NOTE: SEE GF(31) STANDARD FOR STANDARD LINE POSTS.




DIRECTION OF TRAFFIC



**ELEVATION DETAIL
LONG SPAN GUARDRAIL**

		Design Division Standard	
METAL BEAM GUARD FENCE LONG SPAN TL-3 MASH COMPLIANT			
GF(31)LS-19			
FILE: gf31ls19.dgn	DN: TxDOT	CK: KM	DW: VP
©TXDOT: NOVEMBER 2019	CON: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	DIST: DAL		COUNTY: COLLIN
	SHEET NO.:		83

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; Soft+Stop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MBOG STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IT IS ACCEPTABLE TO INSTALL THE Soft+Stop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
 - DO NOT ATTACH THE Soft+Stop SYSTEM DIRECTLY TO A RIGID BARRIER.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE Soft+Stop SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTE: A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE: B PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

NOTE: C W-BEAM SPLICE LOCATED BETWEEN LINE POST(4) AND LINE POST(5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	Soft+Stop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	Soft+Stop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	Soft+Stop DOWNSTREAM W-BEAM RAIL (12GA) (25'-0")
15205A	1	POST #0 - ANCHOR POST (6'-5 3/8")
15203G	1	POST #1 - (SYTP) (4'-9 1/2")
15000G	1	POST #2 - (SYTP) (6'-0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6'-0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B

Texas Department of Transportation
Design Division Standard

TRINITY HIGHWAY SOFTSTOP END TERMINAL MASH - TL-3 SGT (10S) 31-16








FILE: sgt10s3116	DN: TxDOT	CK: KM	DW: VP	CK: MB/VP
©TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	84	

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE Soft+Stop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

APPROACH GRADING AT GUARDRAIL END TREATMENTS

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
- FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
- SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
- COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
- IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
- MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
- IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
- THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
- A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	3/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	3/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS

Texas Department of Transportation Design Division Standard

MAX-TENSION END TERMINAL


MASH - TL-3

SGT (11S) 31-18

FILE: sg11s3118.dgn DN: TxDOT CK: KM DW: TxDOT CK: CL
 © TxDOT: FEBRUARY 2018 CONT SECT JOB HIGHWAY
 REVISIONS 1012 02 042, ETC. FM 545
 DIST COUNTY SHEET NO.
 DAL COLLIN 85



DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MOW STRIP STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
o	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
i	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.


Design Division Standard

SINGLE GUARDRAIL TERMINAL



MSKT-MASH-TL-3

SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	86	



MATCH LINE A-A




MATCH LINE A-A

BEGIN PROJECT
CSJ: 1012-02-042, ETC.
C/L FM 545
STA. 0+00

- DRAINAGE AREA (ACRE)
- DRAINAGE AREA NUMBER
- STRUCTURE LOCATION
- DIRECTION OF FLOW
- DRAINAGE AREA BOUNDARY

NOTE:
1. CONTOUR DATA IS BASED ON THE 2019 USGS MAP.





Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

FM 545 DRAINAGE AREA MAP

SHEET 1 OF 4

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	87
CHECK MS	CONTROL	SECTION	JOB	
CHECK	JRV	1012	02 042, ETC.	



- ⊗⊗ DRAINAGE AREA (ACRE)
- ⊗ DRAINAGE AREA NUMBER
- STRUCTURE LOCATION
- ← DIRECTION OF FLOW
- - - DRAINAGE AREA BOUNDARY

MATCH LINE STA. 128+00

MATCH LINE STA. 258+00

CO RD 420

CO RD 473

CO RD 472

CO RD 474

Brinlee Cem

Brinlee Br

STONEY POINT DR

CO RD 472

Chambliss

SISTER GROVE CREEK

Meat Producers Reservoir

CULVERT NO. 7

CULVERT NO. 8

CULVERT NO. 9

TRIBUTARY TO BRINLEE BRANCH

END CSJ 1012-02-037 STA. 194+30

STATE OF TEXAS

CONGLI YE
82802
LICENSED PROFESSIONAL ENGINEER

Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

FM 545 DRAINAGE AREA MAP





SHEET 2 OF 4



DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	88
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

NOTE:

1. CONTOUR DATA IS BASED ON THE 2019 USGS MAP.
2. NO DRAINAGE AREA SHOWN FOR CULVERT NO. 7, 8, AND 9 DUE TO NO HYDRAULIC ANALYSIS NEEDED TO BE DONE FOR THESE CULVERTS.



-  DRAINAGE AREA (ACRE)
DRAINAGE AREA NUMBER
-  STRUCTURE LOCATION
-  DIRECTION OF FLOW
-  DRAINAGE AREA BOUNDARY



Congli Ye, P.E. 4/28/2021

 Texas Department of Transportation
© 2021



FM 545 DRAINAGE AREA MAP

SHEET 3 OF 4

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	89
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

NOTE:
1. CONTOUR DATA IS BASED ON THE 2019 USGS MAP.

TRIBUTARY TO SISTER GROVE CREEK
 BEGIN CSJ 1012-02-036
 STA. 280+00
 TRIBUTARY TO SISTER GROVE CREEK
 HARRINGTON BRANCH
 CULVERT NO. 10
 MATCH LINE STA. 258+00
 MATCH LINE STA. 388+00



END PROJECT
 CSJ: 1012-02-042, ETC.
 C/L FM 545
 STA. 485+54.50

MATCH LINE STA. 388+00

TRIBUTARY TO
 PILOT GROVE CREEK

END CSJ 1012-02-036
 STA. 422+00

BEGIN CSJ 1012-02-038
 STA. 446+70

FM 545

SCOTT

CULVERT NO. 11

PILOT GROVE CREEK
 TRIBUTARY TO
 PILOT GROVE CREEK


WETLAND ASSOCIATED WITH
 PILOT GROVE CREEK

S BUS HI

NOTE:

1. CONTOUR DATA IS BASED ON THE 2019 USGS MAP.

- DRAINAGE AREA (ACRE)
DRAINAGE AREA NUMBER
- STRUCTURE LOCATION
- DIRECTION OF FLOW
- DRAINAGE AREA BOUNDARY



Cong Li Ye, P.E. 4/28/2021

Texas Department of Transportation
 © 2021

FM 545 DRAINAGE AREA MAP

SHEET 4 OF 4

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 90
CHECK MS	CONTROL 1012	SECTION 02	JOB 042, ETC.	
CHECK JRV				

RATIONAL METHOD RUNOFF CALCULATIONS


DESCRIPTION	DA	Cr	Ci	Cv	Cs	C	A	Tc	10-YEAR		100-YEAR	
	I.D.						(acres)	(min)	I ₁₀ (in/hr)	Q ₁₀ (cfs)	I ₁₀₀ (in/hr)	Q ₁₀₀ (cfs)
CULVERT NO. 2	DA 2	0.14	0.1	0.11	0.10	0.45	86	17.0	5.44	211	8.19	317
CULVERT NO. 3	DA 3	0.13	0.1	0.11	0.10	0.44	23	23.0	4.63	47	6.97	71
CULVERT NO. 4	DA 4	0.12	0.1	0.11	0.10	0.43	9	23.0	4.63	18	6.97	27
CULVERT NO. 5	DA 5	0.12	0.1	0.1	0.09	0.41	27	13.0	6.20	69	9.32	103
CULVERT NO. 6	DA 6	0.12	0.1	0.11	0.10	0.43	9	11.0	6.68	26	10.03	39
CULVERT NO. 11	DA 10	0.12	0.1	0.11	0.10	0.43	2	10.0	6.95	6	10.44	9

NRCS RUNOFF CALCULATIONS

CULVERT NO.	1	10
DRAINAGE AREA (SQ.MI.)	1.61	0.65
CURVE NUMBER	83	83
TIMER OF CONCENTRATION (MIN.)	146	96
LAG TIME (MIN.)	102	67
ACCUMULATED RAINFALL DEPTH (IN) (10-YR)	5.2	4.4
ACCUMULATED RAINFALL DEPTH (IN) (100-YR)	8.2	6.9
Q(10-YR) (CFS)	962	460
Q(100-YR) (CFS)	1688	817

NOTE:

1. DRAINAGE ANALYSIS PERFORMED IN CONFORMANCE WITH THE TXDOT HYDRAULIC DESIGN MANUAL (SEPTEMBER 2019) PROCEDURES .
2. RATIONAL METHOD USED TO ANALYZE DRAINAGE BASIN LESS THAN 200 ACRES.
3. HEC-HMS VERSION 4.4 USED TO ANALYZE DRAINAGE BASIN MORE THAN 200 ACRES (FOR CULVERTS NO. 1, AND NO. 10)
4. A USGS FREQUENCY STORM WITH A DURATION OF 12 HOURS WAS USED FOR ANALYSIS OF CULVERTS NO. 1 AND SIX HOURS WAS USED FOR ANALYSIS OF CULVERTS NO. 10.



Congli Ye, P.E. 4/28/2021



**FM 545
HYDROLOGIC AND HYDRAULIC
CALCULATIONS**

SHEET 1 OF 2


DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.			HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET			FM 545
CHECK MS	STATE	DISTRICT	COUNTY		SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN		91
	CONTROL	SECTION	JOB		
	1012	02	042, ETC.		

CULVERT HYDRAULICS CALCULATIONS

CULVERT	STATION	DESCRIPTION	DRAINAGE AREA NO.	ALLOWABLE HEADWATER	10 YEAR (DESIGN)						100 YEAR (CHECK)						
					RUNOFF (CFS)	HW ELEV (FT)	TW ELEV (FT)	TW DEPTH (FT)	OUTLET VELOCITY (FPS)	TW VELOCITY (FPS)	RUNOFF (CFS)	HW ELEV (FT)	TW ELEV (FT)	TW DEPTH (FT)	OUTLET VELOCITY (FPS)	TW VELOCITY (FPS)	
No. 1	29+18.58	EXISTING	1-10'X10'X54' BC (45 SKEW)	1		962	637.02	633.09	7.64	12.59	5.49	1688	641.58	634.89	9.44	15.05	6.32
		PROPOSED	1-10'X10'X66' BC (45 SKEW)	1	641.00	962	637.05	633.06	7.64	12.59	5.49	1688	641.58	634.86	9.44	15.04	6.32
No. 2	35+75.34	EXISTING	1-7'X4'X26' BC	2		211	641.06	639.64	4.33	7.54	3.76	317	643.35	640.35	5.04	10.64	4.16
		PROPOSED	1-7'X4'X54' BC	2	642.79	211	641.27	639.43	4.33	7.54	3.76	317	643.37	640.14	5.04	10.42	4.16
No. 3	50+35.07	EXISTING	1-36"X40' CMP	3		47	656.47	653.62	2.46	13.24	2.58	71	658.68	654.04	2.88	14.70	2.86
		PROPOSED	3-24"X55' RCP	3	658.96	47	655.80	653.96	2.46	4.99	2.58	71	657.04	654.38	2.88	7.53	2.86
No. 4	62+32.95	EXISTING	1-24"X40' RCP	4		18	670.70	669.16	1.72	8.92	2.03	27	672.31	669.44	2.00	10.06	2.25
		PROPOSED	1-24"X47' RCP	4	672.50	18	670.72	669.07	1.72	9.05	2.03	27	672.33	669.35	2.00	10.14	2.25
No. 5	110+15.38	EXISTING	1-36"X49' CMP	5		69	665.54	660.57	2.85	15.42	2.84	103	665.68	661.03	3.31	15.50	3.14
		PROPOSED	2-30"X54' RCP	5	665.45	69	663.39	661.05	2.85	7.03	2.84	103	665.56	661.51	3.31	10.20	3.14
No. 6	123+33.19	EXISTING	1-36"x38' CMP	6		26	653.35	652.02	1.97	9.97	2.23	39	654.12	652.35	2.30	10.92	2.46
		PROPOSED	1-36"x54' RCP	6	655.50	26	652.73	651.45	1.97	9.27	2.23	39	653.20	651.78	2.30	10.22	2.46
No. 10	314+05.72	EXISTING	3-6'X6'X34" MBC	10		460	617.58	617.10	5.80	4.41	4.56	817	619.90	618.49	7.19	7.56	5.27
		PROPOSED	3-6'X6'X54" MBC	10	619.77	460	617.54	617.04	5.80	4.41	4.56	817	619.88	618.43	7.19	7.56	5.27
No. 11	485+44.52	EXISTING	1-18"x46' CMP	11		6	609.82	609.03	1.14	6.24	1.54	9	610.39	609.22	1.33	6.89	1.71
		PROPOSED	1-18"x55' RCP	11	610.08	6	608.79	608.22	1.14	4.17	1.54	9	609.38	608.41	1.33	5.45	1.71

NOTE:

1. HY-8 V7.5 USED TO ANALYZE CULVERTS.
2. NO HYDRAULIC ANALYSIS FOR CULVERTS NO. 7, 8, AND 9 DUE TO NO CULVERT EXTENSION OR THE EXTENSIONS ARE LESS THAN 10% OF THE EXISTING CULVERT'S LENGTH.
3. ALL ELEVATIONS ARE BASED ON THE NAVD88 VERTICAL DATUM.
4. THE DOWNSTREAM WATER SURFACE ELEVATION WAS BASED ON NORMAL DEPTH AT A CHANNEL SLOPE OF 0.003 FT/FT.



Congli Ye, P.E. 4/28/2021






FM 545 HYDROLOGIC AND HYDRAULIC CALCULATIONS

SHEET 2 OF 2



DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	92
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

HYDRAULIC DATA

DRAINAGE AREA = 1030 ACRE	
Q ₁₀ = 962 CFS	Q ₁₀₀ = 1688 CFS
HW ₁₀ = 637.05'	HW ₁₀₀ = 641.58'
TW ₁₀ = 633.06'	TW ₁₀₀ = 634.86'
V ₁₀ = 12.59 FT/S	V ₁₀₀ = 15.04 FT/S



SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
403-6001	TEMPORARY SPL SHORING	SF	2990
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	77
462-6078	CONC BOX CULV (10'X10') (EXTEND)	LF	12
466-6174	WINGWALL (PW-1) (HW=13 FT)	EA	1
466-6175	WINGWALL (PW-1) (HW=14 FT)	EA	1
496-6005	REMOVE STR (WINGWALL)	EA	2





Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 1 LAYOUT
AT STA. 29+18.58


SHEET 1 OF 11

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 93
CHECK MS	CONTROL 1012	SECTION 02	JOB 042, ETC.	
CHECK JRV				




SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
403-6001	TEMPORARY SPL SHORING	SF	768
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	22
462-6059	CONC BOX CULV (7'x4') (EXTEND)	LF	28
466-6181	WINGWALL (PW-1) (HW=6 FT)	EA	2
496-6005	REMOVE STR (WINGWALL)	EA	2

HYDRAULIC DATA			
DRAINAGE AREA = 86 ACRE			
Q ₁₀ = 211 CFS	Q ₁₀₀ = 317 CFS		
HW ₁₀ = 641.27'	HW ₁₀₀ = 643.37'		
TW ₁₀ = 639.43'	TW ₁₀₀ = 640.14'		
V ₁₀ = 7.54 FT/S	V ₁₀₀ = 10.42 FT/S		



CULVERT NO. 2
 EXISTING: 1-7'x4'x26' BC & WW (US & DS)
 PROPOSED: EXTEND 14' WITH PW (US & DS)
 REMOVE EXISTING WW (US & DS)





Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 2 LAYOUT
AT STA. 35+75.34



SHEET 2 OF 11

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
CY	6	SEE TITLE SHEET	FM 545
GRAPHICS	STATE	DISTRICT	COUNTY
CY	TEXAS	DALLAS	COLLIN
CHECK	CONTROL	SECTION	JOB
MS			
CHECK	JRV	1012	02
			042, ETC.
			94



SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
400-6005	CEMENT STABIL BKFL	CY	34
400-6006	CUT & RESTORING PAV	SY	44
401-6001	FLOWABLE BACKFILL	CY	4
402-6001	TRENCH EXCAVATION PROTECTION	LF	32
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	9
464-6005	RC PIPE (CL III) (24 IN)	LF	165
466-6097	HEADWALL (CH-PW-0) (DIA=24 IN)	EA	2
496-6007	REMOVE STR (PIPE)	LF	40

HYDRAULIC DATA	
DRAINAGE AREA = 23 ACRE	
Q ₁₀ = 47 CFS	Q ₁₀₀ = 71 CFS
HW ₁₀ = 655.80'	HW ₁₀₀ = 657.04'
TW ₁₀ = 653.96'	TW ₁₀₀ = 654.38'
V ₁₀ = 4.99 FT/S	V ₁₀₀ = 7.53 FT/S



Congli Ye, P.E. 4/28/2021




FM 545
CULVERT NO. 3 LAYOUT
AT STA. 50+35.07

SHEET 3 OF 11



DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 95
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	

CULVERT NO. 3
 EXISTING: 1-36"X40' CMP TO BE REMOVED
 PROPOSED: 3-24"X55' RCP WITH CH-PW-0 (US & DS)



SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	7
464-6005	RC PIPE (CL III) (24 IN)	LF	12
466-6097	HEADWALL (CH-PW-0) (DIA=24 IN)	EA	1
467-6388	SET (TY II) (24 IN) (RCP) (3:1) (C)	EA	1
480-6001	CLEAN EXIST CULVERTS	EA	1
496-6007	REMOVE STR (PIPE)	LF	5

HYDRAULIC DATA			
DRAINAGE AREA = 9 ACRE			
Q ₁₀ = 18 CFS	Q ₁₀₀ = 27 CFS		
HW ₁₀ = 670.72'	HW ₁₀₀ = 672.33'		
TW ₁₀ = 669.07'	TW ₁₀₀ = 669.35'		
V ₁₀ = 9.05 FT/S	V ₁₀₀ = 10.14 FT/S		



Conglye, P.E. 4/28/2021





FM 545
CULVERT NO. 4 LAYOUT
AT STA. 62+32.95

SHEET 4 OF 11



DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	
MS				
CHECK	JRV	1012	02	042, ETC.

CULVERT NO. 4
 EXISTING: 1'-24"X40' RCP
 PROPOSED: BREAKBACK 3' AND EXTEND 1' (TOTAL OF 4' RCP) WITH PSET-SC (US)
 BREAKBACK 2' AND EXTEND 6' (TOTAL OF 8' RCP) WITH CH-PW-0 (DS)



SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
400-6005	CEMENT STABIL BKFL	CY	37
400-6006	CUT & RESTORING PAV	SY	34
401-6001	FLOWABLE BACKFILL	CY	2
402-6001	TRENCH EXCAVATION PROTECTION	LF	35
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	16
464-6007	RC PIPE (CL III) (30 IN)	LF	108
466-6099	HEADWALL (CH-PW-0) (DIA=30 IN)	EA	2
496-6007	REMOVE STR (PIPE)	LF	49

HYDRAULIC DATA			
DRAINAGE AREA = 27 ACRE			
Q ₁₀ = 69 CFS	Q ₁₀₀ = 103 CFS		
HW ₁₀ = 663.39'	HW ₁₀₀ = 665.56'		
TW ₁₀ = 661.05'	TW ₁₀₀ = 661.51'		
V ₁₀ = 7.03 FT/S	V ₁₀₀ = 10.20 FT/S		



Congli Ye, P.E. 4/28/2021





FM 545 CULVERT NO. 5 LAYOUT AT STA. 110+15.38

SHEET 5 OF 11



DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	
MS				
CHECK	JRV	1012	02	042, ETC.
				97

CULVERT NO. 5
 EXISTING: 1-36"X49' CMP TO BE REMOVED
 PROPOSED: 2-30"X54' RCP WITH CH-PW-0 (US & DS)



SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
400-6005	CEMENT STABIL BKFL	CY	30
400-6006	CUT & RESTORING PAV	SY	32
402-6001	TRENCH EXCAVATION PROTECTION	LF	32
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	14
464-6008	RC PIPE (CL III) (36 IN)	LF	54
466-6101	HEADWALL (CH-PW-0) (DIA=36 IN)	EA	2
496-6007	REMOVE STR (PIPE)	LF	38

HYDRAULIC DATA	
DRAINAGE AREA = 9 ACRE	
Q ₁₀ = 26 CFS	Q ₁₀₀ = 39 CFS
HW ₁₀ = 652.73'	HW ₁₀₀ = 653.50'
TW ₁₀ = 651.45'	TW ₁₀₀ = 651.78'
V ₁₀ = 9.27 FT/S	V ₁₀₀ = 10.22 FT/S



Congli Ye, P.E. 4/28/2021





FM 545
CULVERT NO. 6 LAYOUT
AT STA. 123+33.19

SHEET 6 OF 11


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
CY	6	SEE TITLE SHEET	FM 545
GRAPHICS	STATE	DISTRICT	COUNTY
CY	TEXAS	DALLAS	COLLIN
CHECK	CONTROL	SECTION	JOB
MS			
CHECK	JRV	1012	02
		042, ETC.	

CULVERT NO. 6
 EXISTING: 1-36"X38" CMP TO BE REMOVED
 PROPOSED: 1-36"X54" RCP WITH CH-PW-0 (US & DS)




SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	31
466-6103	HEADWALL (CH-PW-0) (DIA=48 IN)	EA	2
480-6001	CLEAN EXIST CULVERTS	EA	1

NOTE:
NO HYDRAULIC ANALYSIS NEEDED DUE TO NO CULVERT EXTENSION.



CULVERT NO. 7
EXISTING: 1-48"X53' RCP
PROPOSED: INSTALL CH-PW-0 (US & DS)






Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 7 LAYOUT
AT STA. 138+15.10


SHEET 7 OF 11

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
CY	6	SEE TITLE SHEET	FM 545
GRAPHICS	STATE	DISTRICT	COUNTY
CY	TEXAS	DALLAS	COLLIN
CHECK	CONTROL	SECTION	JOB
MS			
CHECK	JRV	1012	02
			042, ETC.
			99




SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
403-6001	TEMPORARY SPL SHORING	SF	1748
432-6030	RIPRAP (STONE COMMON) (GROUT) (12")	CY	49
466-6171	WINGWALL (PW-1) (HW=10 FT)	EA	1
466-6172	WINGWALL (PW-1) (HW=11 FT)	EA	1
496-6005	REMOVE STR (WINGWALL)	EA	2

NOTE:
NO HYDRAULIC ANALYSIS NEEDED DUE TO NO CULVERT EXTENSION.
NBI #: 18-043-0-1012-02-004



CULVERT NO. 8
 EXISTING: 4-6' X 6' X 51' BC & WW (US & DS)
 PROPOSED: INSTALL PW (US & DS)
 REMOVE EXISTING WW (US & DS)





Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 8 LAYOUT
AT STA. 175+09.94


SHEET 8 OF 11

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN
CHECK MS	CONTROL	SECTION	JOB
CHECK JRV	1012	02	042, ETC.




SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
403-6001	TEMPORARY SPL SHORING	SF	1764
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	61
466-6173	WINGWALL (PW-1) (HW=12 FT)	EA	2
496-6005	REMOVE STR (WINGWALL)	EA	2

NOTE: NO HYDRAULIC ANALYSIS NEEDED DUE TO NO CULVERT EXTENSION.



CULVERT NO. 9
 EXISTING: 1-5'X6'X47' BC & WW (US & DS)
 PROPOSED: INSTALL PW (US & DS)
 REMOVE EXISTING WW (US & DS)





Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 9 LAYOUT
AT STA. 182+19.15

SHEET 9 OF 11


DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN
CHECK MS	CONTROL	SECTION	JOB
CHECK JRV	1012	02	042, ETC.




SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
403-6001	TEMPORARY SPL SHORING	SF	1046
432-6030	RIIPRAP (STONE COMMON) (GROUT) (12")	CY	32
462-6057	CONC BOX CULV (6'X6') (EXTEND)	LF	60
466-6183	WINGWALL (PW-1) (HW=8 FT)	EA	2
496-6005	REMOVE STR (WINGWALL)	EA	2

HYDRAULIC DATA

DRAINAGE AREA = 416 ACRE	
Q ₁₀ = 460 CFS	Q ₁₀₀ = 817 CFS
HW ₁₀ = 617.54'	HW ₁₀₀ = 619.88'
TW ₁₀ = 617.04'	TW ₁₀₀ = 618.43'
V ₁₀ = 4.41 FT/S	V ₁₀₀ = 7.56 FT/S



CULVERT NO. 10
 EXISTING: 3-6' X6' X34' BC & WW (US & DS)
 PROPOSED: EXTEND 10' WITH PW (US & DS)
 REMOVE EXISTING WW (US & DS)





Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 10 LAYOUT
AT STA. 314+05.72



SHEET 10 OF 11

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
CY	6	SEE TITLE SHEET	FM 545
GRAPHICS	STATE	DISTRICT	COUNTY
CY	TEXAS	DALLAS	COLLIN
CHECK	CONTROL	SECTION	JOB
MS	1012	02	042, ETC.
CHECK			
JRV			



SUMMARY OF CULVERT QUANTITIES			
BID CODE	DESCRIPTION	UNIT	QUANTITY
400-6005	CEMENT STABIL BKFL	CY	25
400-6006	CUT & RESTORING PAV	SY	48
464-6003	RC PIPE (CL III) (18 IN)	LF	55
467-6356	SET (TY II) (18 IN) (RCP) (3:1) (C)	EA	2
496-6007	REMOVE STR (PIPE)	LF	46

HYDRAULIC DATA	
DRAINAGE AREA = 2 ACRE	
Q ₁₀ = 6 CFS	Q ₁₀₀ = 9 CFS
HW ₁₀ = 608.79'	HW ₁₀₀ = 609.38'
TW ₁₀ = 608.22'	TW ₁₀₀ = 608.41'
V ₁₀ = 4.17 FT/S	V ₁₀₀ = 5.45 FT/S



Congli Ye, P.E. 4/28/2021



FM 545
CULVERT NO. 11 LAYOUT
AT STA. 485+44.52

SHEET 11 OF 11

CULVERT NO. 11
 EXISTING: 1-18"X46" CMP TO BE REMOVED
 PROPOSED: 1-18"X55" RCP WITH PSET-SC (US & DS)

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	103
MS	JRV	1012	02	
CHECK			042, ETC.	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert No. Spans ~ Span X Height	Max Fill Height (Ft)	Applicable Box Culvert Standard (4)	Applicable Wingwall or End Treatment Standard	Skew Angle (0°, 15°, 30° or 45°)	Side Slope or Channel Slope Ratio (SL:1)	T Culvert Top Slab Thickness (In)	U Culvert Wall Thickness (In)	C Estimated Curb Height (Ft)	Hw (1) Height of Wingwall (Ft)	A Curb to End of Wingwall (Ft)	B Offset of End of Wingwall (Ft)	Lw Length of Longest Wingwall (Ft)	Ltw Culvert Toewall Length (Ft)	Atw Anchor Toewall Length (Ft)	Riprap Apron (CY)	Class "C" Conc (Curb) (CY) (2)	Class "C" Conc (Wingwall) (CY) (3)	Total Wingwall Area (SF)
Culvert No.1 at Sta. 29+18.58 (L+)	1 ~ 10' x 10'	5'	SCC-10	PW-1	45°	2:1	8"	7"	3.000'	13.667'	N/A'	N/A'	38.655'	15.792'	N/A	0.0	1.8	82.5	1057
Culvert No.1 at Sta. 29+18.58 (R+)	1 ~ 10' x 10'	5'	SCC-10	PW-1	45°	2:1	8"	7"	2.000'	12.667'	N/A'	N/A'	35.827'	15.792'	N/A	0.0	1.2	67.6	908
Culvert No.2 at Sta. 35+75.34 (Both)	1 ~ 7' x 4'	5'	SCC-7	PW-1	0°	2:1	8"	7"	1.000'	5.667'	N/A'	N/A'	11.333'	8.167'	N/A	0.0	0.6	17.8	256
Culvert No.8 at Sta. 175+09.94 (L+)	4 ~ 6' x 6'	8'	MC-6-16	PW-1	0°	2:1	9"	7"	3.000'	9.75'	N/A'	N/A'	19.500'	26.917'	N/A	0.0	3.0	27.2	380
Culvert No.8 at Sta. 175+09.94 (R+)	4 ~ 6' x 6'	8'	MC-6-16	PW-1	0°	2:1	9"	7"	3.500'	10.25'	N/A'	N/A'	20.500'	26.917'	N/A	0.0	3.5	28.4	420
Culvert No.9 at Sta. 182+19.15 (Both)	1 ~ 5' x 6'	8'	Non-Stdnd	PW-1	0°	2:1	8"	7"	4.500'	11.167'	N/A'	N/A'	22.333'	6.167'	N/A	0.0	2.0	66.0	998
Culvert No.10 at Sta. 314+05.72 (Both)	3 ~ 6' x 6'	5'	MC-6-16	PW-1	0°	2:1	9"	7"	1.000'	7.75'	N/A'	N/A'	15.500'	20.333'	N/A	0.0	1.6	33.6	480

NOTES:

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets;
30° maximum for safety end treatment

SL:1 = Horizontal : 1 Vertical

- Side slope at culvert for flared or straight wingwalls.
- Channel slope for parallel wingwalls.
- Slope must be 3:1 or flatter for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)

B = Offset of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)

Atw = Length of anchor toewall (applicable to safety end treatment only)

Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt.
Area for four wingwalls (two structure ends) if Both.

① Round the wall heights shown to the nearest foot for bidding purposes.

② Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class 5 concrete is required for the top slab of the culvert, also provide Class 5 concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.

③ Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.

④ Regardless of the type of culvert shown on this sheet, the Contractor has the option of furnishing cast-in-place or precast culverts unless otherwise shown elsewhere on the plans. If the Contractor elects to provide culverts of a different type than those shown on this sheet, it is the Contractor's responsibility to make the necessary adjustments to the dimensions and quantities shown.

SPECIAL NOTE:

This sheet is a supplement to the box culvert standards. It is to be filled out by the culvert specifier and provides dimensions for the construction of the box culvert wingwalls and safety end treatments.

An Excel 2010 spreadsheet to assist in completing this table can be downloaded from the Bridge Standards (English) web page on the TxDOT web site. The completed sheet must be signed, sealed, and dated by a licensed Professional Engineer.




Bridge Division Standard

**BOX CULVERT SUPPLEMENT
WINGS AND END TREATMENTS**

BCS

FILE: bcsstd1-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	104	



Congli Ye, P.E. 4/28/2022

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:

BOX DATA


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) ^②						① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	
6	2	8	7	7	< 2	-	0.23	0.27	0.19	0.17	0.19	0.17	7.2
6	2	7	7	7	2 < 3	43	0.25	0.21	0.17	0.17	-	-	6.8
6	2	7	7	7	3 - 5	43	0.20	0.17	0.17	0.17	-	-	6.8
6	2	7	7	7	10	39	0.20	0.17	0.17	0.17	-	-	6.8
6	2	7	7	7	15	39	0.26	0.20	0.20	0.17	-	-	6.8
6	2	7	7	7	20	39	0.34	0.26	0.26	0.17	-	-	6.8
6	2	7	7	7	25	39	0.43	0.32	0.32	0.17	-	-	6.8
6	2	7	7	7	30	39	0.52	0.38	0.39	0.17	-	-	6.8
6	3	8	7	7	< 2	-	0.20	0.31	0.22	0.17	0.19	0.19	7.9
6	3	7	7	7	2 < 3	43	0.21	0.24	0.19	0.17	-	-	7.5
6	3	7	7	7	3 - 5	39	0.17	0.18	0.17	0.17	-	-	7.5
6	3	7	7	7	10	39	0.17	0.18	0.19	0.17	-	-	7.5
6	3	7	7	7	15	38	0.22	0.24	0.24	0.17	-	-	7.5
6	3	7	7	7	20	38	0.28	0.31	0.31	0.17	-	-	7.5
6	3	7	7	7	25	38	0.35	0.38	0.39	0.17	-	-	7.5
6	3	7	7	7	30	38	0.42	0.46	0.46	0.17	-	-	7.5
6	4	8	7	7	< 2	-	0.19	0.34	0.25	0.17	0.19	0.19	8.6
6	4	7	7	7	2 < 3	43	0.19	0.27	0.21	0.17	-	-	8.2
6	4	7	7	7	3 - 5	39	0.17	0.21	0.19	0.17	-	-	8.2
6	4	7	7	7	10	39	0.17	0.20	0.21	0.17	-	-	8.2
6	4	7	7	7	15	38	0.18	0.27	0.27	0.17	-	-	8.2
6	4	7	7	7	20	38	0.24	0.34	0.35	0.17	-	-	8.2
6	4	7	7	7	25	38	0.29	0.43	0.42	0.17	-	-	8.2
6	4	7	7	7	30	38	0.35	0.51	0.52	0.17	-	-	8.2
6	5	8	7	7	< 2	-	0.19	0.37	0.28	0.17	0.19	0.19	9.3
6	5	7	7	7	2 < 3	43	0.17	0.30	0.24	0.17	-	-	8.9
6	5	7	7	7	3 - 5	43	0.17	0.23	0.21	0.17	-	-	8.9
6	5	7	7	7	10	39	0.17	0.22	0.23	0.17	-	-	8.9
6	5	7	7	7	15	38	0.17	0.28	0.29	0.17	-	-	8.9
6	5	7	7	7	20	38	0.20	0.37	0.38	0.17	-	-	8.9
6	5	7	7	7	25	38	0.25	0.45	0.46	0.17	-	-	8.9
6	5	7	7	7	30	38	0.30	0.54	0.55	0.17	-	-	8.9
6	6	8	7	7	< 2	-	0.19	0.38	0.30	0.17	0.19	0.19	10
6	6	7	7	7	2 < 3	52	0.17	0.32	0.26	0.17	-	-	9.6
6	6	7	7	7	3 - 5	52	0.17	0.24	0.22	0.17	-	-	9.6
6	6	7	7	7	10	43	0.17	0.23	0.24	0.17	-	-	9.6
6	6	7	7	7	15	39	0.17	0.29	0.31	0.17	-	-	9.6
6	6	7	7	7	20	39	0.18	0.38	0.39	0.17	-	-	9.6
6	6	7	7	7	25	38	0.23	0.46	0.48	0.17	-	-	9.6
6	6	7	7	7	30	38	0.27	0.55	0.57	0.17	-	-	9.6

① For box length = 8'-0"

② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.




FILL HEIGHT 2 FT AND GREATER



FILL HEIGHT LESS THAN 2 FT

④ Length is equal to spacing of longitudinal reinforcing plus 2". (10" Min) (Typ)



SECTION A-A

(Showing top and bottom slab joint reinforcement.)

MATERIAL NOTES:

Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.
Provide Class H concrete (f'c = 5,000 psi).

GENERAL NOTES:

Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.
See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.
In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

HL93 LOADING


		Bridge Division Standard	
<h2>SINGLE BOX CULVERTS PRECAST 6'-0" SPAN</h2>			
<h3>SCP-6</h3>			
FILE: scp06sts-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	DIST: DAL	COUNTY: COLLIN	HIGHWAY: FM 545
			SHEET NO: 105

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

BOX DATA


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) ^②							① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8	
7	3	8	8	8	< 2	-	0.23	0.31	0.22	0.19	0.19	0.19	0.19	9.6
7	3	8	8	8	2 < 3	47	0.27	0.25	0.24	0.19	-	-	-	9.6
7	3	8	8	8	3 - 5	43	0.19	0.19	0.19	0.19	-	-	-	9.6
7	3	8	8	8	10	43	0.21	0.20	0.21	0.19	-	-	-	9.6
7	3	8	8	8	15	43	0.28	0.26	0.27	0.19	-	-	-	9.6
7	3	8	8	8	20	43	0.36	0.34	0.35	0.19	-	-	-	9.6
7	3	8	8	8	25	43	0.45	0.42	0.43	0.19	-	-	-	9.6
7	3	8	8	8	30	43	0.54	0.50	0.51	0.19	-	-	-	9.6
7	4	8	8	8	< 2	-	0.21	0.34	0.25	0.19	0.19	0.19	0.19	10.4
7	4	8	8	8	2 < 3	43	0.23	0.28	0.28	0.19	-	-	-	10.4
7	4	8	8	8	3 - 5	43	0.19	0.22	0.19	0.19	-	-	-	10.4
7	4	8	8	8	10	43	0.19	0.23	0.23	0.19	-	-	-	10.4
7	4	8	8	8	15	41	0.24	0.30	0.30	0.19	-	-	-	10.4
7	4	8	8	8	20	41	0.31	0.38	0.39	0.19	-	-	-	10.4
7	4	8	8	8	25	41	0.38	0.47	0.48	0.19	-	-	-	10.4
7	4	8	8	8	30	41	0.46	0.57	0.57	0.19	-	-	-	10.4
7	5	8	8	8	< 2	-	0.19	0.36	0.27	0.19	0.19	0.19	0.19	11.2
7	5	8	8	8	2 < 3	47	0.21	0.31	0.31	0.19	-	-	-	11.2
7	5	8	8	8	3 - 5	43	0.19	0.24	0.21	0.19	-	-	-	11.2
7	5	8	8	8	10	43	0.19	0.25	0.26	0.19	-	-	-	11.2
7	5	8	8	8	15	41	0.21	0.32	0.33	0.19	-	-	-	11.2
7	5	8	8	8	20	41	0.27	0.41	0.42	0.19	-	-	-	11.2
7	5	8	8	8	25	41	0.33	0.51	0.52	0.19	-	-	-	11.2
7	5	8	8	8	30	41	0.40	0.61	0.62	0.19	-	-	-	11.2
7	6	8	8	8	< 2	-	0.19	0.38	0.30	0.19	0.19	0.19	0.19	12.0
7	6	8	8	8	2 < 3	59	0.19	0.33	0.34	0.19	-	-	-	12.0
7	6	8	8	8	3 - 5	47	0.19	0.25	0.23	0.19	-	-	-	12.0
7	6	8	8	8	10	43	0.19	0.26	0.27	0.19	-	-	-	12.0
7	6	8	8	8	15	41	0.19	0.34	0.35	0.19	-	-	-	12.0
7	6	8	8	8	20	41	0.24	0.43	0.45	0.19	-	-	-	12.0
7	6	8	8	8	25	41	0.29	0.53	0.55	0.19	-	-	-	12.0
7	6	8	8	8	30	41	0.35	0.64	0.65	0.19	-	-	-	12.0
7	7	8	8	8	< 2	-	0.19	0.40	0.33	0.19	0.19	0.19	0.19	12.8
7	7	8	8	8	2 < 3	59	0.19	0.36	0.37	0.19	-	-	-	12.8
7	7	8	8	8	3 - 5	59	0.19	0.27	0.25	0.19	-	-	-	12.8
7	7	8	8	8	10	47	0.19	0.27	0.29	0.19	-	-	-	12.8
7	7	8	8	8	15	43	0.19	0.35	0.37	0.19	-	-	-	12.8
7	7	8	8	8	20	43	0.22	0.44	0.46	0.19	-	-	-	12.8
7	7	8	8	8	25	43	0.27	0.54	0.57	0.19	-	-	-	12.8
7	7	8	8	8	30	41	0.32	0.65	0.67	0.19	-	-	-	12.8



FILL HEIGHT 2 FT AND GREATER



FILL HEIGHT LESS THAN 2 FT



MATERIAL NOTES:
 Provide 0.03 sq. in./ft. minimum longitudinal reinforcing at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.
 Provide Class H concrete ($f'c = 5,000$ psi).

GENERAL NOTES:
 Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.
 See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.
 In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

① For box length = 8'-0"
 ② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.

HL93 LOADING

Texas Department of Transportation

Bridge Division Standard


SINGLE BOX CULVERTS PRECAST 7'-0" SPAN

SCP-7


FILE: scp07sts-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	106	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




TYPICAL SECTION




PLAN OF REINF STEEL




SECTION THRU CURB



BARS C



BARS D



BARS K (#4)
(Spa = 1'-0" Max)
(Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

MATERIAL NOTES:

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete ($f'_c = 3,600$ psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete ($f'_c = 4,000$ psi) for top slabs of:
 - culverts with overlay,
 - culverts with 1-to-2 course surface treatment, or
 - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
 - Uncoated or galvanized ~ #4 = 1'-8" Min
 - Uncoated or galvanized ~ #5 = 2'-1" Min
 - Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.



**SINGLE BOX CULVERTS
 CAST-IN-PLACE
 0' TO 30' FILL**

SCC-7


FILE: scc07ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	107	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

SECTION DIMENSIONS				FILL HEIGHT ⑤	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																										QUANTITIES												
					Bars B					Bars C					Bars D					Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total					
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
7'-0"	3'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	7'-11"	1,338	3'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	3'-0"	216	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.533	124.8	0.6	71	21.9	5,062
7'-0"	3'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	8'-0"	1,352	3'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	3'-0"	216	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.583	125.5	0.6	71	23.9	5,090
7'-0"	3'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	8'-2"	1,380	3'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	3'-0"	164	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.663	126.3	0.6	78	27.1	5,128
7'-0"	3'-0"	11"	8"	30'	108	#6	9"	8'-1"	1,311	162	#5	6"	8'-3"	1,394	3'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	3'-0"	164	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.714	127.0	0.6	78	29.2	5,156
7'-0"	4'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	8'-11"	1,507	4'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	4'-0"	289	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.576	130.8	0.6	71	23.6	5,304
7'-0"	4'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	9'-0"	1,521	4'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	4'-0"	289	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.627	131.5	0.6	71	25.7	5,332
7'-0"	4'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	9'-2"	1,549	4'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	4'-0"	219	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.712	131.9	0.6	78	29.1	5,352
7'-0"	4'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	9'-3"	1,563	4'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	4'-0"	219	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.763	149.0	0.6	78	31.1	6,036
7'-0"	5'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	9'-11"	1,676	5'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	5'-0"	361	5	39'-9"	133	35	39'-9"	929	7'-11"	21	18	50	0.619	139.5	0.6	71	25.4	5,651
7'-0"	5'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	10'-0"	1,690	5'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	5'-0"	361	5	39'-9"	133	35	39'-9"	929	7'-11"	21	18	50	0.670	140.2	0.6	71	27.4	5,679
7'-0"	5'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	10'-2"	1,718	5'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	5'-0"	274	5	39'-9"	133	35	39'-9"	929	8'-1"	22	20	56	0.761	140.1	0.6	78	31.1	5,682
7'-0"	5'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	10'-3"	1,732	5'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	5'-0"	274	5	39'-9"	133	35	39'-9"	929	8'-1"	22	20	56	0.813	157.2	0.6	78	33.1	6,366
7'-0"	6'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	10'-11"	1,845	6'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	6'-0"	433	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.663	148.2	0.6	71	27.1	5,999
7'-0"	6'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	11'-0"	1,859	6'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	6'-0"	433	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.713	148.9	0.6	71	29.1	6,027
7'-0"	6'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	11'-2"	1,887	6'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	6'-0"	329	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.811	148.4	0.6	78	33.1	6,013
7'-0"	6'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	11'-3"	1,901	6'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	6'-0"	329	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.862	165.5	0.6	78	35.1	6,697
7'-0"	7'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	11'-11"	2,014	7'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.706	154.2	0.6	71	28.8	6,240
7'-0"	7'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	12'-0"	2,028	7'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.756	154.9	0.6	71	30.8	6,268
7'-0"	7'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	12'-2"	2,056	7'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.860	157.0	0.6	78	35.0	6,358
7'-0"	7'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	12'-3"	2,070	7'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.912	174.1	0.6	78	37.1	7,042

⑤ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.

 Texas Department of Transportation				Bridge Division Standard	
SINGLE BOX CULVERTS CAST-IN-PLACE 0' TO 30' FILL					
SCC-7					
FILE: scc07ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT	
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY	
REVISIONS	1012	02	042, ETC.	FM 545	
04/2021 Updated X values.	DIST	COUNTY		SHEET NO.	
	DAL	COLLIN		108	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

BOX DATA

SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) ^②						① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	
10	4	10	10	10	< 2	-	0.33	0.34	0.27	0.24	0.24	0.24	16.5
10	4	10	10	10	2 < 3	58	0.38	0.35	0.30	0.24	-	-	16.5
10	4	10	10	10	3 - 5	53	0.31	0.28	0.27	0.24	-	-	16.5
10	4	10	10	10	10	52	0.36	0.32	0.33	0.24	-	-	16.5
10	4	10	10	10	15	52	0.47	0.42	0.43	0.24	-	-	16.5
10	4	10	10	10	20	52	0.61	0.54	0.55	0.24	-	-	16.5
10	4	10	10	10	25	52	0.75	0.67	0.68	0.24	-	-	16.5
10	5	10	10	10	< 2	-	0.30	0.36	0.30	0.24	0.24	0.24	17.5
10	5	10	10	10	2 < 3	58	0.35	0.39	0.34	0.24	-	-	17.5
10	5	10	10	10	3 - 5	52	0.28	0.31	0.30	0.24	-	-	17.5
10	5	10	10	10	10	52	0.33	0.35	0.36	0.24	-	-	17.5
10	5	10	10	10	15	47	0.42	0.46	0.47	0.24	-	-	17.5
10	5	10	10	10	20	47	0.55	0.59	0.61	0.24	-	-	17.5
10	5	10	10	10	25	47	0.68	0.73	0.75	0.24	-	-	17.5
10	6	10	10	10	< 2	-	0.28	0.38	0.33	0.24	0.24	0.24	18.5
10	6	10	10	10	2 < 3	58	0.32	0.42	0.37	0.24	-	-	18.5
10	6	10	10	10	3 - 5	53	0.26	0.34	0.33	0.24	-	-	18.5
10	6	10	10	10	10	52	0.30	0.38	0.39	0.24	-	-	18.5
10	6	10	10	10	15	47	0.39	0.49	0.51	0.24	-	-	18.5
10	6	10	10	10	20	47	0.50	0.63	0.65	0.24	-	-	18.5
10	6	10	10	10	25	47	0.61	0.78	0.80	0.24	-	-	18.5
10	7	10	10	10	< 2	-	0.25	0.40	0.36	0.24	0.24	0.24	19.5
10	7	10	10	10	2 < 3	58	0.30	0.45	0.40	0.24	-	-	19.5
10	7	10	10	10	3 - 5	58	0.24	0.36	0.35	0.24	-	-	19.5
10	7	10	10	10	10	52	0.28	0.40	0.42	0.24	-	-	19.5
10	7	10	10	10	15	47	0.36	0.52	0.54	0.24	-	-	19.5
10	7	10	10	10	20	47	0.46	0.67	0.69	0.24	-	-	19.5
10	7	10	10	10	25	47	0.56	0.82	0.85	0.24	-	-	19.5
10	8	10	10	10	< 2	-	0.24	0.41	0.38	0.24	0.24	0.24	20.5
10	8	10	10	10	2 < 3	64	0.27	0.47	0.43	0.24	-	-	20.5
10	8	10	10	10	3 - 5	58	0.24	0.38	0.38	0.24	-	-	20.5
10	8	10	10	10	10	52	0.26	0.42	0.44	0.24	-	-	20.5
10	8	10	10	10	15	47	0.34	0.54	0.57	0.24	-	-	20.5
10	8	10	10	10	20	47	0.43	0.69	0.72	0.24	-	-	20.5
10	9	10	10	10	< 2	-	0.24	0.42	0.41	0.24	0.24	0.24	21.5
10	9	10	10	10	2 < 3	70	0.26	0.50	0.46	0.24	-	-	21.5
10	9	10	10	10	3 - 5	64	0.24	0.40	0.40	0.24	-	-	21.5
10	9	10	10	10	10	58	0.25	0.43	0.46	0.24	-	-	21.5
10	9	10	10	10	15	52	0.32	0.56	0.59	0.24	-	-	21.5
10	9	10	10	10	20	47	0.40	0.71	0.75	0.24	-	-	21.5
10	10	10	10	10	< 2	-	0.24	0.44	0.44	0.24	0.24	0.24	22.5
10	10	10	10	10	2 < 3	79	0.25	0.52	0.48	0.24	-	-	22.5
10	10	10	10	10	3 - 5	70	0.24	0.42	0.43	0.24	-	-	22.5
10	10	10	10	10	10	64	0.24	0.44	0.48	0.24	-	-	22.5
10	10	10	10	10	15	52	0.30	0.57	0.61	0.24	-	-	22.5
10	10	10	10	10	20	52	0.38	0.73	0.77	0.24	-	-	22.5


① For box length = 8'-0"

② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.



CORNER OPTION "A" CORNER OPTION "B"


FILL HEIGHT 2 FT AND GREATER



CORNER OPTION "A" CORNER OPTION "B"

FILL HEIGHT LESS THAN 2 FT

④ Length is equal to spacing of longitudinal reinforcing plus 2". (10" Min) (Typ)



SECTION A-A

(Showing top and bottom slab joint reinforcement.)

MATERIAL NOTES:

Provide 0.03 sq. in./ft. minimum longitudinal reinforcing at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.
Provide Class H concrete (f'c = 5,000 psi).

GENERAL NOTES:


Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.
See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.
In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

HL93 LOADING


		Bridge Division Standard	
SINGLE BOX CULVERTS PRECAST 10'-0" SPAN			
SCP-10			
FILE: scp10sts-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	DIST: DAL	COUNTY: COLLIN	HIGHWAY: FM 545
			SHEET NO: 109

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




TYPICAL SECTION



PLAN OF REINF STEEL



SECTION THRU CURB



- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:

Do not use permanent forms.
 Chamfer the bottom edge of the top slab 3" at the entrance.
 Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

MATERIAL NOTES:

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
 - culverts with overlay,
 - culverts with 1-to-2 course surface treatment, or
 - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
 - Uncoated or galvanized ~ #4 = 1'-8" Min
 - Uncoated or galvanized ~ #5 = 2'-1" Min
 - Uncoated or galvanized ~ #6 = 2'-6" Min
 - Uncoated or galvanized ~ #7 = 3'-3" Min

GENERAL NOTES:

Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
 See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 3

Bridge Division Standard

SINGLE BOX CULVERTS CAST-IN-PLACE 0' TO 30' FILL

SCC-10

FILE: scc10ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	110	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results from its use.

DATE: FILE:

SECTION DIMENSIONS				FILL HEIGHT ⁵	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																												QUANTITIES										
					Bars B					Bars C					Bars D					Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total					
S	H	T	U		No.	Size	Spa	Length	Wt	No.	Size	Spa	Length	Wt	" X "	" Y "	No.	Size	Spa	Length	Wt	" Y "	" Z "	No.	Spa	Length	Wt	No.	Length	Wt	No.	Length	Wt	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)	Conc (CY)	Reinf (Lb)	Conc (CY)	Reinf (Lb)
10' - 0"	9' - 0"	8"	7"	7'	162	#6	6"	10' - 11"	2,656	162	#6	6"	15' - 4"	3,731	9' - 6"	5' - 10"	162	#6	6"	8' - 11"	2,170	5' - 10"	3' - 1"	108	9"	9' - 0"	649	7	39' - 9"	186	53	39' - 9"	1,407	10' - 11"	29	24	67	0.940	270.0	0.8	96	38.4	10,895
10' - 0"	9' - 0"	8"	7"	10'	162	#6	6"	10' - 11"	2,656	162	#6	6"	15' - 4"	3,731	9' - 6"	5' - 10"	162	#6	6"	8' - 11"	2,170	5' - 10"	3' - 1"	108	9"	9' - 0"	649	7	39' - 9"	186	53	39' - 9"	1,407	10' - 11"	29	24	67	0.940	270.0	0.8	96	38.4	10,895
10' - 0"	9' - 0"	9"	8"	13'	162	#6	6"	11' - 1"	2,697	162	#6	6"	15' - 6"	3,772	9' - 7"	5' - 11"	162	#6	6"	9' - 1"	2,210	5' - 11"	3' - 2"	108	9"	9' - 0"	649	7	39' - 9"	186	53	39' - 9"	1,407	11' - 1"	30	26	72	1.074	273.0	0.8	102	43.8	11,023
10' - 0"	9' - 0"	10"	8"	16'	162	#6	6"	11' - 1"	2,697	162	#6	6"	15' - 7"	3,792	9' - 8"	5' - 11"	162	#6	6"	9' - 2"	2,230	5' - 11"	3' - 3"	162	6"	9' - 0"	974	7	39' - 9"	186	53	39' - 9"	1,407	11' - 1"	30	26	72	1.144	282.2	0.8	102	46.6	11,388
10' - 0"	9' - 0"	12"	9"	20'	162	#6	6"	11' - 3"	2,737	162	#6	6"	15' - 10"	3,853	9' - 10"	6' - 0"	162	#6	6"	9' - 5"	2,291	6' - 0"	3' - 5"	162	6"	9' - 0"	974	7	39' - 9"	186	53	39' - 9"	1,407	11' - 3"	30	26	72	1.352	286.2	0.8	102	54.9	11,550
10' - 0"	9' - 0"	13"	10"	23'	162	#6	6"	11' - 5"	2,778	162	#6	6"	15' - 11"	3,873	9' - 11"	6' - 0"	162	#6	6"	9' - 6"	2,312	6' - 0"	3' - 6"	162	6"	9' - 0"	974	7	39' - 9"	186	53	39' - 9"	1,407	11' - 5"	31	26	72	1.492	288.3	0.9	103	60.5	11,633
10' - 0"	9' - 0"	14"	11"	26'	162	#6	6"	11' - 7"	2,819	162	#6	6"	16' - 1"	3,913	10' - 0"	6' - 1"	162	#6	6"	9' - 8"	2,352	6' - 1"	3' - 7"	162	6"	9' - 0"	974	7	39' - 9"	186	53	39' - 9"	1,407	11' - 7"	31	26	72	1.634	291.3	0.9	103	66.2	11,754
10' - 0"	9' - 0"	15"	12"	30'	162	#7	6"	11' - 9"	3,891	162	#6	6"	16' - 3"	3,954	10' - 1"	6' - 2"	162	#6	6"	9' - 10"	2,393	6' - 2"	3' - 8"	162	6"	9' - 0"	974	7	39' - 9"	186	53	39' - 9"	1,407	11' - 9"	31	26	72	1.778	320.1	0.9	103	72.0	12,908
10' - 0"	10' - 0"	8"	7"	7'	162	#6	6"	10' - 11"	2,656	162	#6	6"	16' - 4"	3,974	10' - 6"	5' - 10"	162	#6	6"	8' - 11"	2,170	5' - 10"	3' - 1"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	10' - 11"	29	24	67	0.984	286.9	0.8	96	40.2	11,571
10' - 0"	10' - 0"	8"	7"	10'	162	#6	6"	10' - 11"	2,656	162	#6	6"	16' - 4"	3,974	10' - 6"	5' - 10"	162	#6	6"	8' - 11"	2,170	5' - 10"	3' - 1"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	10' - 11"	29	24	67	0.984	286.9	0.8	96	40.2	11,571
10' - 0"	10' - 0"	9"	8"	13'	162	#6	6"	11' - 1"	2,697	162	#6	6"	16' - 6"	4,015	10' - 7"	5' - 11"	162	#6	6"	9' - 1"	2,210	5' - 11"	3' - 2"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	11' - 1"	30	26	72	1.123	289.9	0.8	102	45.8	11,699
10' - 0"	10' - 0"	10"	8"	16'	162	#6	6"	11' - 1"	2,697	162	#6	6"	16' - 7"	4,035	10' - 8"	5' - 11"	162	#6	6"	9' - 2"	2,230	5' - 11"	3' - 3"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	11' - 1"	30	26	72	1.193	290.9	0.8	102	48.6	11,739
10' - 0"	10' - 0"	12"	9"	20'	162	#6	6"	11' - 3"	2,737	162	#6	6"	16' - 10"	4,096	10' - 10"	6' - 0"	162	#6	6"	9' - 5"	2,291	6' - 0"	3' - 5"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	11' - 3"	30	26	72	1.407	295.0	0.8	102	57.1	11,901
10' - 0"	10' - 0"	13"	10"	23'	162	#6	6"	11' - 5"	2,778	162	#6	6"	16' - 11"	4,116	10' - 11"	6' - 0"	162	#6	6"	9' - 6"	2,312	6' - 0"	3' - 6"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	11' - 5"	31	26	72	1.553	297.0	0.9	103	63.0	11,984
10' - 0"	10' - 0"	14"	11"	26'	162	#6	6"	11' - 7"	2,819	162	#6	6"	17' - 1"	4,157	11' - 0"	6' - 1"	162	#6	6"	9' - 8"	2,352	6' - 1"	3' - 7"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	11' - 7"	31	26	72	1.702	300.1	0.9	103	69.0	12,106
10' - 0"	10' - 0"	15"	12"	30'	162	#7	6"	11' - 9"	3,891	162	#6	6"	17' - 3"	4,197	11' - 1"	6' - 2"	162	#6	6"	9' - 10"	2,393	6' - 2"	3' - 8"	162	6"	10' - 0"	1,082	7	39' - 9"	186	53	39' - 9"	1,407	11' - 9"	31	26	72	1.852	328.9	0.9	103	75.0	13,259

⁵ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.





**SINGLE BOX CULVERTS
CAST-IN-PLACE
0' TO 30' FILL**

SCC-10

FILE: scc10ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	112	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




TYPICAL SECTION

PART PLANS



SECTION THRU CURB

TABLE OF BAR DIMENSIONS		
H	"X"	"Y"
2'-0"	2'-7 1/2"	4'-1"
3'-0"	3'-7 1/2"	4'-1"
4'-0"	4'-7 1/2"	4'-1"
5'-0"	5'-7 1/2"	4'-1"
6'-0"	6'-7 1/2"	4'-1"



- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR
Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86"
Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:
Do not use permanent forms.
Chamfer the bottom edge of the top slab 3" at the entrance.
Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed, and Bars Y and Z may be reversed.

MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide galvanized reinforcing steel if required elsewhere in the plans.
Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
• culverts with overlay,
• culverts with 1-to-2 course surface treatment, or
• culverts with the top slab as the final riding surface.
Provide bar laps, where required, as follows:
• Uncoated or galvanized ~ #4 = 1'-8" Min
• Uncoated or galvanized ~ #5 = 2'-1" Min
• Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
See the Multiple Box Culverts Cast-In-Place Miscellaneous Detail (MC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2

Texas Department of Transportation Bridge Division Standard


MULTIPLE BOX CULVERTS CAST-IN-PLACE
6'-0" SPAN
0' TO 16' FILL

MC-6-16


FILE: mc616ste-20.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
DIST	COUNTY		SHEET NO.	
DAL	COLLIN		113	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




PLAN OF SKEWED ENDS ~ FROM 0° TO 15°



PLAN OF SKEWED ENDS ~ OVER 30° TO 45°



PLAN OF SKEWED ENDS ~ OVER 15° TO 30°



LENGTHENING DETAIL

1 For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.
 For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.
 Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.


- 2 When the spacing between Bars B becomes less than half of the normal spacing, cut bars to avoid conflict.
- 3 The length of Bars B vary in the skewed end sections.
- 4 $[One\ half\ of\ overall\ width] \times [tangent\ of\ the\ skew\ angle]$
- 5 Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- 6 When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- 7 At the Contractor's option, for skews of 15° or less, place Bars B, C, and D parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B shown on the Single Box Culverts Cast-In-Place (SCC) standards sheets to accommodate the skew.

CONSTRUCTION NOTES:
 Do not use permanent forms.
 When required, lap Bars H 1'-8" for uncoated or galvanized bars.
 Provide a minimum of 1 1/2" clear cover.


MATERIAL NOTES:
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel, if required elsewhere in the plans.
 Provide Class C concrete (f'c = 3,600 psi) with these exceptions:
 provide Class S concrete (f'c = 4,000 psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for details of straight sections of culvert.
 For skewed sections and angle sections, refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.
 For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the culvert Single Box Culverts Cast-In-Place (SCC) standard sheets by the cosine of the skew angle.


Cover dimensions are clear dimensions, unless noted otherwise.



PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ OVER 30° TO 45°

HL93 LOADING


		Bridge Division Standard	
SINGLE BOX CULVERTS CAST-IN-PLACE MISCELLANEOUS DETAILS			
SCC-MD			
FILE: sccmdste-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT February 2020	CON: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	DIST: DAL		COUNTY: COLLIN
			SHEET NO: 115

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




MULTIPLE UNIT PLACEMENT



SECTION B-B




DETAIL "A" (13)




WINGWALL CONNECTION

(Also applies to safety end treatment.)




SECTION THRU TOP SLABS LESS THAN 8"




SECTION THRU CURB

QUANTITIES PER FOOT OF CURB (10)	
Reinforcing Steel	4.12 Lb
Concrete	0.037 CY



BARS C (#4)
(Spa = 1'-0" Max)




BARS K (#4)
(Spa = 1'-0" Max)
(Length = 4'-2")

- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail, bicycle rail, or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- Extend curb, wingwall, or safety end treatment reinforcing into concrete closure. Bend or trim, as necessary, any reinforcing that does not fit into closure area.
- Provide a 3'-0" Min cast-in-place concrete closure. Break back boxes in the field or cast boxes short. Provide bands of reinforcing in the closure that are the same size and spacing as in the precast box section. Provide #4 longitudinal reinforcement spaced at 12 inches Max within the closure. Except where shown otherwise, construct the cast-in-place closure flush with the inside and outside faces of the precast box section.
- For multiple unit placements, adjust the length of the closure for the interior walls as necessary. Provide a 3'-0" Min cast-in-place closure in the top slab, bottom slab, and exterior wall. See Section B-B detail when interior walls are cast full length.
- Extend precast box reinforcing a minimum of 1'-0" into concrete closure (Typ).
- Place bands of reinforcing matching the inside and outside face reinforcing in the gaps of the top and bottom slabs. Place a band matching the outside face reinforcing of the wall in the gaps of the walls (placed in the outside face only). Tack weld the bands to the exposed reinforcing at each point of contact.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- Cement stabilized backfill between boxes is considered part of the box culvert for payment.
- All curb concrete and reinforcing is considered part of the box culvert for payment.
- Any additional concrete and reinforcing required for the closures will be considered subsidiary to the box culvert for payment.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- For multiple unit placement with overlay, with 1 to 2 course surface treatment, or with the top slab as the final riding surface, provide wall closure as shown in Detail "A".
- This dimension may be increased with approval of the Engineer to allow the precast boxes to be tunneled or jacked in accordance with Item 476, "Jacking, Boring, or Tunneling Pipe or Box". No payment will be made for any additional material in the gap between adjacent boxes.


MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide ASTM A1064 welded wire reinforcement.
Provide Class C concrete (f_c = 3,600 psi) for the closures.
Provide cement stabilized backfill meeting the requirements of Item 400, "Excavation and Backfill for Structures."
Any additional concrete required for the closures will be considered subsidiary to the box culvert.

GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications.
Refer to the Single Box Culverts Precast (SCP) standard sheets for details and notes not shown.
Chamfer the bottom edge of the top slab closure 3 inches at culvert closure ends.


Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bars dimensions are out-to-out of bars.



ANGLE DETAIL



SECTION A-A



PLAN OF SKEWED ENDS


(Showing multi-box placement.)

HL93 LOADING


Texas Department of Transportation		Bridge Division Standard	
BOX CULVERTS PRECAST MISCELLANEOUS DETAILS			
SCP-MD			
FILE: scpmdsts-20.dgn	DN: GAF	CK: LMW	DW: BWH/TxDOT
©TxDOT February 2020	CONT	SECT	JOB
REVISIONS	1012	02	042, ETC.
	DIST	COUNTY	SHEET NO.
	DAL	COLLIN	116

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:






PLAN OF ANGLE SECTION ~ FROM 0° TO 15°




PLAN OF ANGLE SECTION ~ OVER 15° TO 30°



PLAN OF ANGLE SECTION ~ OVER 30° TO 45°



LENGTHENING DETAIL



- ① For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.
For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, Class C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, N_b , of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.
Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.
- ② When the spacing between Bars B or Bars E becomes less than half of the normal spacing, cut bars to avoid conflict.
- ③ The length of Bars B and Bars E will vary in the skewed end sections.
- ④ $[0.5 \times \text{overall width}] \times [\text{tangent of the skew angle}]$
- ⑤ Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- ⑥ When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- ⑦ At the Contractor's option, for skews of 15° or less, place Bars B, C, D, and E parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B and Bars E shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets to accommodate the skew.
- ⑧ Extend Bars E as shown on the MC standard sheet for direct traffic culverts.

- CONSTRUCTION NOTES:**
Do not use permanent forms.
When required, lap Bars H 1'-8" for uncoated or galvanized bars.
Provide a minimum of 1 1/2" clear cover.
- MATERIAL NOTES:**
Provide Grade 60 reinforcing steel.
Provide galvanized reinforcing steel, if required elsewhere in the plans.
Provide Class C concrete ($f'_c = 3,600$ psi) with these exceptions:
provide Class S concrete ($f'_c = 4,000$ psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.
- GENERAL NOTES:**
Designed according to AASHTO LRFD Bridge Design Specifications.
Refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for details of straight sections of culvert.
For skewed sections and angle sections, refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.
For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets by the cosine of the skew angle.
- Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING

Texas Department of Transportation
Bridge Division Standard

MULTIPLE BOX CULVERTS CAST-IN-PLACE MISCELLANEOUS DETAILS

MC-MD

FILE: mc-mdste-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
1012	02	042, ETC.	FM 545	
DIST	COUNTY	SHEET NO.		
DAL	COLLIN	117		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

TABLE OF DIMENSIONS AND REINFORCING STEEL
(Wings for one structure end)




Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings) ④		Estimated Quantities per ft of Toewall (1-toewall)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

TABLE OF WINGWALL REINFORCING
(2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

TABLE OF TOEWALL REINFORCING

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



WING DIMENSION FORMULAS:
(All values are in feet.)

$Hw = H + T + C$
 $Lw = (Hw)(SL) \div \cosine(\theta)$ for Type PW-1
 $Lw = (Hw - 1')(SL) \div \cosine(\theta)$ for Type PW-2 and $Hw \ge 4'$
 $Lw = (Hw - 0.5')(SL) \div \cosine(\theta)$ for Type PW-2 and $Hw < 4'$








For cast-in-place culverts:
 $Ltw = [(N)(S) + (N + 1)(U)] \div \cosine(\theta)$

For precast culverts:
 $Ltw = [(N)(2U + S) + (N - 1)(0.5')] \div \cosine(\theta)$
 Total Wingwall Area (two wings ~ SF)
 $= (2)(Hw)(Lw)$ for Type PW-1
 $= (2)(Hw)(Lw) - 6 SF$ for Type PW-2 and $Hw \ge 4'$
 $= (2)(Hw)(Lw) - 1.5 SF$ for Type PW-2 and $Hw < 4'$

Hw = Height of wingwall
 Lw = Length of wingwall
 Ltw = Culvert toewall length
 N = Number of culvert spans
 $SL:1$ = Channel slope ratio, (horizontal: 1 vertical, usual value is 2:1)
 θ = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.

- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"
For 30° skew ~ 2"
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.



DESIGNER NOTES:
 Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall.
 Type PW-2 can only be used for applications without a railing mounted to the wingwall.

MATERIAL NOTES:
 Provide Class C concrete (f'c=3,600 psi).
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel if required elsewhere in the plans.

GENERAL NOTES:
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information.
 Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.

Bridge Division Standard


CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2

PW

FILE: pwstde01-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
REVISIONS	CONV	SECT	JOB	HIGHWAY
	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	118	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




TYPICAL SECTION


Used for curbs over 1'-0" to 5'-0"




BARS V (#5)
Spaced at 12" Max



BARS L (#5)
Spaced at 12" Max



OPTIONAL BARS L (#5)
Spaced at 12" Max



BARS U (#4)
Spaced at 12" Max

- ① "T" is equal to the culvert top slab thickness. For precast boxes with slabs less than 8" thick, see SCP-MD standard for additional details.
- ② Adjust normal culvert slab bars as necessary to clear obstructions.
- ③ Place bars L as shown. Tilt hook as necessary to maintain cover.
- ④ Place normal culvert curb bars H(#4) as shown. Adjust as necessary to clear obstructions.
- ⑤ Additional bars H(#4) as required to maintain 12" Max spacing.
- ⑥ Replace normal culvert curb bars K with one bar U and two bars V as shown spaced at 12" Max. Adjust length of bars V as necessary to maintain clear cover.
- ⑦ Optional bars L are to be used only for precast box culverts with 3'-0" closure pour.
- ⑧ Quantities shown are for Contractor's information only. Quantities are per linear foot of curb length. The value in table can be interpolated for intermediate values of curb height, "C". Quantity includes bars K (when applicable).

TABLE OF ESTIMATED CURB QUANTITIES ⑧		
Curb Height "C"	Conc (CY/LF)	Reinf Steel (Lb/LF)
1'-0"	0.037	10.4
1'-6"	0.056	14.5
2'-0"	0.074	15.6
2'-6"	0.093	18.0
3'-0"	0.111	19.0
3'-6"	0.130	21.3
4'-0"	0.148	22.4
4'-6"	0.167	24.8
5'-0"	0.185	25.9

CONSTRUCTION NOTES:
Adjust reinforcing steel as necessary to provide 1 1/2" cover.
For vehicle safety, top of the curb must not project more than 3" above the finished grade.

MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide galvanized reinforcing steel if required elsewhere in the plans.
Provide Class "C" concrete (f'c = 3,600 psi) minimum for curbs.
Provide bar laps, where required, as follows:
• Uncoated or galvanized ~ #4 = 1'-8" Min

GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications.
These extended curb details have sufficient strength to allow for future retrofit of Type T631 or T631LS railing. These details are suitable for use with PR11, PR22 and PR3 type rails. These details are not suitable for the mounting of other rail types. For new construction using T631 or T631LS railing, use the T631-CM standard.
This Curb is considered as part of the Box Culvert for payment.

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bar dimensions shown are out-to-out of bar.



EXTENDED CURB DETAILS
FOR BOX CULVERTS WITH CURBS OVER 1'-0" TO 5'-0" TALL





ECD				
FILE:	DN:	CK:	DW:	CK:
ecdstd1-20.dgn	GAF	TxDOT	TxDOT	GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	119	

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

TABLE OF VARIABLE DIMENSIONS (5) AND QUANTITIES FOR ONE HEADWALL

Slope	Dia of Pipe (D)	Values for One Pipe		Values To Be Added for Each Add'l Pipe			
		W	Reinf (Lbs) (1)	Conc (CY) (2)	W	Reinf (Lbs) (1)	Conc (CY) (2)
2:1	12"	9'-0"	122	1.1	1'-9"	15	0.2
	15"	10'-3"	136	1.3	2'-2"	16	0.2
	18"	11'-6"	163	1.5	2'-8"	19	0.3
	21"	12'-9"	200	1.8	3'-1"	31	0.4
	24"	14'-0"	217	2.1	3'-7"	34	0.4
	27"	15'-3"	254	2.4	3'-11"	37	0.5
	30"	16'-6"	272	2.7	4'-4"	40	0.6
	33"	17'-9"	314	3.1	4'-8"	43	0.6
	36"	19'-0"	371	3.9	5'-1"	46	0.8
	42"	21'-6"	442	4.9	5'-10"	52	1.0
	48"	25'-0"	569	6.4	6'-7"	59	1.3
	54"	27'-6"	701	7.5	7'-6"	82	1.6
60"	30'-0"	794	8.8	8'-3"	90	1.8	
66"	32'-6"	894	10.2	8'-9"	96	2.0	
72"	35'-0"	1,055	11.7	9'-4"	103	2.3	
3:1	12"	13'-0"	175	1.6	1'-9"	14	0.2
	15"	14'-9"	193	1.9	2'-2"	17	0.2
	18"	16'-6"	228	2.2	2'-8"	19	0.3
	21"	18'-3"	299	2.6	3'-1"	31	0.4
	24"	20'-0"	323	3.0	3'-7"	33	0.4
	27"	21'-9"	371	3.5	3'-11"	37	0.5
	30"	23'-6"	415	4.0	4'-4"	40	0.5
	33"	25'-3"	469	4.6	4'-8"	43	0.6
	36"	27'-0"	556	5.7	5'-1"	46	0.8
	42"	30'-6"	675	7.1	5'-10"	52	1.0
	48"	35'-6"	837	9.2	6'-7"	59	1.3
	54"	39'-0"	1,015	11.0	7'-6"	84	1.6
60"	42'-6"	1,171	12.9	8'-3"	91	1.8	
66"	46'-0"	1,298	14.9	8'-9"	98	2.0	
72"	49'-6"	1,561	17.1	9'-4"	103	2.3	
4:1	12"	17'-0"	229	2.0	1'-9"	15	0.2
	15"	19'-3"	266	2.4	2'-2"	17	0.2
	18"	21'-6"	308	2.9	2'-8"	19	0.3
	21"	23'-9"	382	3.5	3'-1"	31	0.3
	24"	26'-0"	430	3.9	3'-7"	34	0.4
	27"	28'-3"	486	4.7	3'-11"	37	0.5
	30"	30'-6"	539	5.2	4'-4"	40	0.6
	33"	32'-9"	603	6.0	4'-8"	42	0.6
	36"	35'-0"	738	7.5	5'-1"	47	0.8
	42"	39'-6"	881	9.3	5'-10"	52	1.0
	48"	46'-0"	1,102	12.1	6'-7"	61	1.3
	54"	50'-6"	1,364	14.4	7'-6"	84	1.6
60"	55'-0"	1,547	16.9	8'-3"	91	1.8	
66"	59'-6"	1,741	19.5	8'-9"	98	2.0	
72"	64'-0"	2,077	22.4	9'-4"	102	2.3	
6:1	12"	25'-0"	336	3.0	1'-9"	14	0.2
	15"	28'-3"	384	3.6	2'-2"	17	0.2
	18"	31'-6"	452	4.2	2'-8"	19	0.3
	21"	34'-9"	581	5.1	3'-1"	31	0.4
	24"	38'-0"	644	5.8	3'-7"	34	0.4
	27"	41'-3"	737	6.9	3'-11"	37	0.5
	30"	44'-6"	807	7.7	4'-4"	39	0.6
	33"	47'-9"	912	8.9	4'-8"	44	0.6
	36"	51'-0"	1,108	11.0	5'-1"	48	0.8
	42"	57'-6"	1,318	13.7	5'-10"	54	1.0
	48"	67'-0"	1,682	17.9	6'-7"	59	1.3
	54"	73'-6"	2,072	21.3	7'-6"	83	1.6
60"	80'-0"	2,351	24.9	8'-3"	89	1.8	
66"	86'-6"	2,643	28.9	8'-9"	96	2.0	
72"	93'-0"	3,121	33.1	9'-4"	101	2.3	



- ① Total quantities include one 3'-1" lap for bars over 60' in length.
- ② Quantities shown are for concrete pipe and will increase slightly for metal pipe installations.
- ③ Indicated slope is perpendicular to centerline pipe or pipes.
- ④ For vehicle safety, construct curbs no more than 3" above finished grade. Reduce curb heights, if necessary, to meet these requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ⑤ Dimensions shown are usual and maximum.
- ⑥ Quantities shown are for one structure end only (one headwall).

TABLE OF CONSTANT DIMENSIONS

Dia of Pipe (D)	G	K (5)	H	T	E
12"	0'-9"	1'-0"	2'-8"	0'-9"	1'-9"
15"	0'-11"	1'-0"	2'-11"	0'-9"	1'-9"
18"	1'-2"	1'-0"	3'-2"	0'-9"	1'-9"
21"	1'-4"	1'-0"	3'-5"	0'-9"	2'-0"
24"	1'-7"	1'-0"	3'-8"	0'-9"	2'-0"
27"	1'-8"	1'-0"	3'-11"	0'-9"	2'-3"
30"	1'-10"	1'-0"	4'-2"	0'-9"	2'-3"
33"	1'-11"	1'-0"	4'-5"	0'-9"	2'-6"
36"	2'-1"	1'-0"	4'-8"	1'-0"	2'-6"
42"	2'-4"	1'-0"	5'-2"	1'-0"	2'-9"
48"	2'-7"	1'-3"	5'-11"	1'-0"	3'-0"
54"	3'-0"	1'-3"	6'-5"	1'-0"	3'-3"
60"	3'-3"	1'-3"	6'-11"	1'-0"	3'-6"
66"	3'-3"	1'-3"	7'-5"	1'-0"	3'-9"
72"	3'-4"	1'-3"	7'-11"	1'-0"	4'-0"

TABLE OF (6) REINFORCING STEEL

Bar	Size	Spa	No.
A1	#5	~	2
A2	#5	1'-6"	~
E	#5	~	2
F	#5	1'-0"	~

MATERIAL NOTES:
 Provide Grade 60 reinforcing steel.
 Provide Class C concrete (f'c = 3,600 psi).

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Do not mount bridge rails of any type directly to these culvert headwalls.
 This standard may not be used for wall heights, H, exceeding the values shown.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing dimensions are out-to-out of bars.

Bridge Division Standard


CONCRETE HEADWALLS WITH PARALLEL WINGS FOR NON-SKEWED PIPE CULVERTS

CH-PW-0

FILE: chpw0ste-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	120	

CROSS PIPE LENGTHS AND PIPE RUNNER LENGTHS ① ②


Nominal Culvert I.D.	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length												
			3:1 Side Slope				4:1 Side Slope				6:1 Side Slope				
			0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	
24"	1' - 7"	3' - 5"	N/A	N/A	N/A	5' - 10"	N/A	N/A	N/A	8' - 1"	N/A	N/A	N/A	12' - 9"	
27"	1' - 8"	3' - 8"	N/A	N/A	N/A	5' - 5"	6' - 11"	N/A	N/A	7' - 7"	9' - 7"	N/A	N/A	11' - 11"	14' - 11"
30"	1' - 10"	3' - 11"	N/A	N/A	N/A	6' - 4"	8' - 0"	N/A	N/A	8' - 9"	11' - 0"	N/A	N/A	13' - 8"	17' - 0"
33"	1' - 11"	4' - 2"	6' - 2"	6' - 5"	7' - 3"	9' - 1"	8' - 6"	8' - 10"	10' - 0"	12' - 5"	13' - 3"	13' - 9"	15' - 5"	19' - 2"	
36"	2' - 1"	4' - 5"	6' - 11"	7' - 3"	8' - 2"	10' - 2"	9' - 6"	9' - 11"	11' - 2"	13' - 10"	14' - 9"	15' - 3"	17' - 2"	21' - 3"	
42"	2' - 4"	4' - 11"	8' - 6"	8' - 10"	9' - 11"	12' - 4"	11' - 7"	12' - 0"	13' - 6"	16' - 8"	17' - 9"	18' - 5"	20' - 8"	25' - 7"	
48"	2' - 7"	5' - 5"	10' - 1"	10' - 5"	11' - 9"	N/A	13' - 7"	14' - 2"	15' - 10"	N/A	20' - 9"	21' - 6"	24' - 2"	N/A	
54"	3' - 0"	5' - 11"	11' - 8"	12' - 1"	N/A	N/A	15' - 8"	16' - 3"	N/A	N/A	23' - 10"	24' - 8"	N/A	N/A	
60"	3' - 3"	6' - 5"	13' - 3"	N/A	N/A	N/A	17' - 9"	N/A	N/A	N/A	26' - 10"	N/A	N/A	N/A	



NOTE: All pipe runners, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER

(Showing corrugated metal pipe (CMP) culvert. Details of reinforced concrete pipe (RCP) culvert are similar.)



SIDE ELEVATION OF CAST-IN-PLACE CONCRETE

(Showing reinforced concrete pipe (RCP) culvert. Details of corrugated metal pipe (CMP) culvert are similar. Pipe runners not shown for clarity)

TYPICAL PIPE CULVERT MITERS ③

Side Slope	0° Skew	15° Skew	30° Skew	45° Skew
3:1	3:1	3.106:1	3.464:1	4.243:1
4:1	4:1	4.141:1	4.619:1	5.657:1
6:1	6:1	6.212:1	6.928:1	8.485:1

CONDITIONS WHERE PIPE RUNNERS ARE NOT REQUIRED ②


Nominal Culvert I.D.	Single Pipe Culvert	Multiple Pipe Culverts
12" thru 21"	Skews thru 45°	Skews thru 45°
24"	Skews thru 45°	Skews thru 30°
27"	Skews thru 30°	Skews thru 15°
30"	Skews thru 15°	Skews thru 15°
33"	Skews thru 15°	Always required
36"	Normal (no skew)	Always required
42" thru 60"	Always required	Always required

STANDARD PIPE SIZES AND MAX PIPE RUNNER LENGTHS ①

Pipe Size	Pipe O.D.	Pipe I.D.	Max Pipe Runner Length
2" STD	2.375"	2.067"	N/A
3" STD	3.500"	3.068"	10' - 0"
4" STD	4.500"	4.026"	19' - 8"
5" STD	5.563"	5.047"	34' - 2"

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY) ⑤

Nominal Culvert I.D.	3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
12"	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.6	0.7	0.7	0.7	0.8
15"	0.5	0.5	0.5	0.6	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9
18"	0.5	0.5	0.6	0.6	0.6	0.7	0.7	0.8	0.8	0.8	0.9	1.0
21"	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9	0.9	0.9	1.0	1.2
24"	0.6	0.7	0.7	0.8	0.8	0.8	0.8	1.0	1.0	1.0	1.1	1.3
27"	0.7	0.7	0.8	0.9	0.8	0.9	0.9	1.1	1.1	1.1	1.2	1.4
30"	0.8	0.8	0.8	0.9	0.9	0.9	1.0	1.2	1.2	1.2	1.3	1.6
33"	0.8	0.8	0.9	1.0	1.0	1.0	1.1	1.3	1.3	1.4	1.5	1.7
36"	0.9	0.9	0.9	1.1	1.1	1.1	1.2	1.4	1.4	1.5	1.6	1.8
42"	1.0	1.0	1.1	1.3	1.2	1.3	1.3	1.6	1.6	1.7	1.8	2.1
48"	1.1	1.1	1.2	N/A	1.4	1.4	1.5	N/A	1.9	1.9	2.1	N/A
54"	1.3	1.3	N/A	N/A	1.6	1.6	N/A	N/A	2.1	2.1	N/A	N/A
60"	1.4	N/A	N/A	N/A	1.7	N/A	N/A	N/A	2.3	N/A	N/A	N/A



ISOMETRIC VIEW OF TYPICAL INSTALLATION

(Showing installation with no skew.)

① Provide pipe runner of the size shown in the tables. Provide cross pipe of the same size as the pipe runner. Provide cross pipe stub out and bottom anchor pipe of the next smaller size pipe as shown in the Standard Pipe Sizes and Max Pipe Runner Lengths table.

② This standard allows for the placement of only one pipe runner across each culvert pipe opening. In order to limit the clear opening to be traversed by an errant vehicle, the following conditions must be met:

For 60" culvert pipes, the skew must not exceed 0°.
 For 54" culvert pipes, the skew must not exceed 15°.
 For 48" culvert pipes, the skew must not exceed 30°.
 For all culvert pipe sizes 42" and less, the skew must not exceed 45°.

If the above conditions cannot be met, the designer should consider using a safety end treatment with flared wings. For further information, refer to the TxDOT Roadway Design Manual.

③ Miter = slope of mitered end of pipe culvert.

④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".

⑤ Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only.



SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE


SETP-CD

FILE: setpcdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY	
REVISIONS	1012 02	042, ETC.		FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	121	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




OPTION A1 **OPTION A2**
CROSS PIPE AND CONNECTIONS DETAILS




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

PIPE RUNNER DETAILS



OPTION B1 **OPTION B2**
BOTTOM ANCHOR PIPE DETAILS ⑩




OPTION B1 **OPTION B2**
BOTTOM ANCHOR TOEWALL DETAILS

(Culvert and riprap not shown for clarity.)


MATERIAL NOTES:
Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
Provide pipe runners, cross pipes, and anchor pipes conforming to the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.
Provide ASTM A307 bolts and nuts.
Galvanize all steel components, except concrete reinforcing, after fabrication.
Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:
Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.
Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.
Payment for riprap and toewall is included in the price bid for each safety end treatment.
Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap".




SIDE ELEVATION OF SAFETY END TREATMENT INSTALLATION


(Showing pipe runner with Cross Pipe Connection Option A1 and Anchor Pipe Option B2 on corrugated metal pipe (CMP) culvert. Reinforced concrete pipe culvert (RCP) details are similar. Riprap not shown for clarity)



PLAN OF SKEWED INSTALLATION



SECTION A-A
SHOWING CROSS PIPE AND ANCHOR TOEWALL




SHOWING TYPICAL PIPE CULVERT AND RIPRAP

- ④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- ⑥ Recommended values of side slope are 3:1, 4:1, and 6:1. All quantities, calculations, and dimensions shown herein are based on these recommended values. Slope of 3:1 or flatter is required for vehicle safety.
- ⑦ Note that actual slope of pipe runner may vary slightly from side slope of riprap and trimmed culvert pipe edge.
- ⑧ Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1/2 inch hole to ensure that the lap of the pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.

		Bridge Division Standard	
SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE			
SETP-CD			
FILE: setpcdse-20.dgn	DN: GAF	CK: CAT	DW: JRP
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY
REVISIONS	1012 02	042, ETC.	FM 545
DIST	COUNTY	SHEET NO.	
DAL	COLLIN	122	

DATE:
FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




NOTE: All cross pipes, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER

(Showing corrugated metal pipe (CMP) culvert. Details at reinforced concrete pipe (RCP) culvert are similar.)





ISOMETRIC VIEW OF TYPICAL INSTALLATION




SIDE ELEVATION OF CAST-IN-PLACE CONCRETE

(Showing reinforced concrete pipe (RCP) culvert. Details at corrugated metal pipe (CMP) culvert are similar.)




PIPE WITH ANCHOR BARS




SECTION C-C

CROSS PIPE DETAILS



DETAIL "A"


(Showing invert with corrugated metal pipe (CMP) culvert. Reinforced concrete pipe (RCP) culvert details are similar. Cross pipes not shown for clarity.)




SECTION B-B

(Cross pipes not shown for clarity.)


Limits of riprap (to be included with SET for payment) ⑤



SHOWING TYPICAL PIPE CULVERT AND RIPRAP



SHOWING CROSS PIPE WITH ANCHOR BAR



SHOWING CROSS PIPE WITH BOLTED ANCHOR

SECTION A-A

CROSS PIPE LENGTHS, REQUIRED PIPE SIZES, AND RIPRAP QUANTITIES

Nominal Culvert I.D.	Conc Riprap (CY) ⑥	Pipe Culvert Spa ~ G	Single Barrel ~ Q1	Multi-Barrel ~ Q1	Q2	Conditions for Use of Cross Pipes	Cross Pipe Sizes
12"	0.6	0' - 9"	N/A	2' - 1"	1' - 9"	3 or more pipe culverts	3" Std (3.500" O.D.)
15"	0.7	0' - 11"	N/A	2' - 5"	2' - 2"		
18"	0.8	1' - 2"	N/A	2' - 10"	2' - 8"		
21"	0.9	1' - 4"	N/A	3' - 2"	3' - 1"		
24"	0.9	1' - 7"	N/A	3' - 6"	3' - 7"	3 or more pipe culverts	3 1/2" Std (4.000" O.D.)
27"	1.0	1' - 8"	N/A	3' - 10"	3' - 11"	2 or more pipe culverts	
30"	1.1	1' - 10"	N/A	4' - 2"	4' - 4"	All pipe culverts	
33"	1.2	1' - 11"	4' - 2"	4' - 5"	4' - 8"	All pipe culverts	4" Std (4.500" O.D.)
36"	1.3	2' - 1"	4' - 5"	4' - 9"	5' - 1"	All pipe culverts	
42"	1.5	2' - 4"	4' - 11"	5' - 5"	5' - 10"	All pipe culverts	5" Std (5.563" O.D.)
48"	1.7	2' - 7"	5' - 5"	6' - 0"	6' - 7"		
54"	2.0	3' - 0"	5' - 11"	6' - 9"	7' - 6"		
60"	2.2	3' - 3"	6' - 5"	7' - 4"	8' - 3"		
66"	2.4	3' - 3"	6' - 11"	7' - 10"	8' - 9"	All pipe culverts	5" Std (5.563" O.D.)
72"	2.7	3' - 4"	7' - 5"	8' - 5"	9' - 4"		

- The proper installation of the first cross pipe is critical for vehicle safety. Place the top of the first cross pipe no more than 6" above the flowline.
- Provide cross pipes, except the first bottom pipe, of the size shown in the table. Provide a 3 1/2" standard pipe (4" O.D.) for the first bottom pipe.
- Install the third cross pipe from the bottom of the culvert using a bolted connection. Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access. At the Contractor's option, install all other cross pipes using the bolted connection details.
- Match cross slope as shown elsewhere in the plans. Cross slope of 6:1 or flatter is required for vehicle safety.
- Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for contractor's information only.

MATERIAL NOTES:

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. Provide cross pipes that meet the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 (Gr B), or API 5LX52. Provide ASTM A307 bolts and nuts. Galvanize all steel components, except concrete reinforcing, after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:

Cross pipes are designed for a traversing load of 10,000 pounds at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981. Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the cross pipes. Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap". Payment for riprap and toewall is included in the Price Bid for each Safety End Treatment.

Texas Department of Transportation
SAFETY END TREATMENT FOR 12" DIA TO 72" DIA PIPE CULVERTS TYPE II ~ PARALLEL DRAINAGE
 SETP-PD

FILE: setppdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
REVISIONS	CONT	SECT	JOB	HIGHWAY
	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	123	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness (8)	"D" (1)	Slope	Min Length of Unit	Single Pipe		Multiple Pipes	
						Skew	Pipe Runners Required	Skew	Pipe Runners Required
12"	2"	1.15"	17.00"	3:1	2' - 11"	≤ 45°	No	≤ 45°	No
				4:1	3' - 6"				
				6:1	4' - 9"				
15"	2 1/4"	1.30"	20.50"	3:1	3' - 8"	≤ 45°	No	≤ 45°	No
				4:1	4' - 7"				
				6:1	6' - 5"				
18"	2 1/2"	1.60"	24.00"	3:1	4' - 6"	≤ 45°	No	≤ 45°	No
				4:1	5' - 8"				
				6:1	8' - 0"				
24"	3"	1.95"	31.00"	3:1	6' - 2"	≤ 45°	No	= 30°	No
				4:1	7' - 10"				
				6:1	11' - 3"				
30"	3 1/2"	2.65"	38.50"	3:1	7' - 10"	= 15°	No	= 15°	No
				4:1	10' - 1"				
				6:1	14' - 8"				
36"	4"	2.75"	45.50"	3:1	9' - 5"	= 0°	No	≥ 0°	Yes
				4:1	12' - 3"				
				6:1	17' - 11"				
42"	4 1/2"	N/A	52.50"	3:1	11' - 1"	≥ 0°	Yes	≥ 0°	Yes
				4:1	14' - 5"				
				6:1	21' - 2"				


SAFETY PIPE RUNNER DIMENSIONS

Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"




PLAN

(Showing bell end connection.)




LONGITUDINAL ELEVATION

(Showing bell end connection.)




END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS

(If required)



OPTIONAL JOINT FOR RCP

(Showing joint between RCP and precast safety end treatment)




OPTION A

DETAIL A


OPTION B

(If required)




MULTIPLE PIPE INSTALLATION

OPTION WITH SQUARE BOTTOM



OPTION WITH INVERT BOTTOM

SECTION A-A



INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS

(If required)

- ① Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- ② Slope as shown elsewhere in plans. Slope of 3:1 or flatter is required for vehicle safety.
- ③ Toewall to be used only when dimension is shown elsewhere in the plans.
- ④ Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- ⑤ Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- ⑥ Measured along slope.
- ⑦ Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- ⑧ Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".

When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.

Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:

A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).

B. For precast (steel formed) sections, provide Class "C" concrete (f'c = 3,600 psi).

At the option and expense of the Contractor, the next larger size of safety end treatment may be furnished as long as the "D" dimension cast is that of the required size of pipe.

Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.

Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.


Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464 "Reinforced Concrete Pipe". Connect TP by grouting. See PBGC standard for grouted connections with TP and precast safety end treatment.


		Bridge Division Standard	
PRECAST SAFETY END TREATMENT			
TYPE II ~ CROSS DRAINAGE			
PSET-SC			
FILE: psetscss-20.dgn	DN: RLW	CK: KLR	DW: JTR
©TxDOT February 2020	CONT: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	DIST: COUNTY		HIGHWAY: FM 545
	DAL COLLIN		SHEET NO. 124

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




PLAN VIEW
(Showing spigot end connection.)



LONGITUDINAL ELEVATION
(Showing spigot end connection.)




OPTION A




OPTION B


DETAIL A




END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS
(If required)



INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS
(If required)



SECTION A-A



MULTIPLE PIPE INSTALLATION

MAX SAFETY PIPE RUNNER LENGTHS AND REQUIRED SAFETY PIPE RUNNER SIZES

Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. / ft. of pipe)	Slope	Minimum Length of Unit	Single Pipe		Multiple Pipe			
							Skew	Pipe Runners Required	Skew	Pipe Runners Required		
12"	2"	16"	16"	0.07 Circ.	3:1	2'-0"	≤ 45°	No	≤ 45°	No		
											4:1	2'-8"
											6:1	4'-0"
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	3:1	2'-10"	≤ 45°	No	≤ 45°	No		
											4:1	3'-9"
											6:1	5'-8"
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	3:1	3'-8"	≤ 45°	No	≤ 45°	No		
											4:1	4'-10"
											6:1	7'-3"
24"	3"	30"	27"	0.07 Circ.	3:1	5'-3"	≤ 45°	No	≤ 30°	No		
											4:1	7'-0"
											6:1	10'-6"
30"	3 1/2"	37"	31"	0.18 Circ.	3:1	6'-3"	≤ 15°	No	≤ 15°	No		
											4:1	8'-2"
											6:1	12'-1"
36"	4"	44"	36"	0.19 Ellip.	3:1	7'-10"	= 0°	No	≥ 0°	Yes		
											4:1	10'-4"
											6:1	15'-4"
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	3:1	9'-6"	≥ 0°	Yes	≥ 0°	Yes		
											4:1	12'-6"
											6:1	18'-7"

MATERIAL NOTES:

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.
Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (CRP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".
When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.
Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.
Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.
Methods of lifting shall be provided by the manufacturer for ease of loading, unloading, and installation.
Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.

Texas Department of Transportation Bridge Division Standard


PRECAST SAFETY END TREATMENT TYPE II ~ CROSS DRAINAGE

PSET-RC

FILE: psetrcss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT: 1012	SECT: 02	JOB: 042, ETC.	HIGHWAY: FM 545
REVISIONS	DIST: DAL	COUNTY: COLLIN	SHEET NO: 125	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




PLAN

(Showing bell end connection.)




LONGITUDINAL ELEVATION

(Showing bell end connection.)




INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS

(If required)




OPTION A




OPTION B

END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS

(If required)




MULTIPLE PIPE INSTALLATION




OPTION WITH SQUARE BOTTOM

SECTION A-A



OPTION WITH INVERT BOTTOM



OPTIONAL JOINT FOR RCP

(Showing joint between RCP and precast safety end treatment.)

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness (7)	"D" (1)	Slope	Min Length	Pipe Runners Required		Required Pipe Runner Size		
						Single Pipe	Multiple Pipe	Nominal Dia.	O.D.	I.D.
12"	2"	1.15"	17.00"	6:1	4' - 9"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
15"	2 1/4"	1.30"	20.50"	6:1	6' - 5"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
18"	2 1/2"	1.60"	24.00"	6:1	8' - 0"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
24"	3"	1.95"	31.00"	6:1	11' - 3"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
30"	3 1/2"	2.65"	38.50"	6:1	14' - 8"	No	Yes	4" STD	4.500"	4.026"
36"	4"	2.75"	45.50"	6:1	17' - 11"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	N/A	52.50"	6:1	21' - 2"	Yes	Yes	4" STD	4.500"	4.026"

- Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- Toewall to be used only when dimension is shown elsewhere in the plans.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".
 When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.
 Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
 Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:
 A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).
 B. For precast (steel formed) sections, provide Class "C" concrete (f'c = 3,600 psi).
 At the option and expense of the Contractor the next larger size of safety end treatment may be furnished; as long as the "D" dimension cast is that of the required size of pipe.
 Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.
 Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.
 Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.
 Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464, "Reinforced Concrete Pipe". Connect TP by grouting. See PBGC standard for grouted connections with TP and precast safety end treatment.

Texas Department of Transportation Bridge Division Standard


PRECAST SAFETY END TREATMENT TYPE II ~ PARALLEL DRAINAGE

PSET-SP


FILE: psetspss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
REVISIONS	CONT	SECT	JOB	HIGHWAY
	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	126	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




PLAN VIEW - 12" THRU 24"
(Showing spigot end connection.)



LONGITUDINAL ELEVATION - 12" THRU 24"
(Showing spigot end connection.)




SECTION A-A




MULTIPLE PIPE INSTALLATION


- ① Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
Provide cement stabilized bedding and backfill in accordance with the Item, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- ③ Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- ④ Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- ⑤ Safety pipe runners are required for multiple pipe culverts with more than two pipes.



INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS
(If required)



OPTION A



OPTION B

END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS
(If required)

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. per ft. of Pipe)	Max Slope	Min Length of Unit	Pipe Runner Requirements		Required Pipe Runner Sizes		
							Single Pipe	Multiple Pipe	Nominal Dia	O.D.	I.D.
12"	2"	16"	16"	0.07 Circ.	6:1	4'-0"	No	⑤	3" STD	3.500"	3.068"
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	6:1	5'-8"	No	⑤	3" STD	3.500"	3.068"
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	6:1	7'-3"	No	⑤	3" STD	3.500"	3.068"
24"	3"	30"	27"	0.07 Circ.	6:1	10'-6"	No	⑤	3" STD	3.500"	3.068"
30"	3 1/2"	37"	31"	0.18 Circ.	6:1	12'-1"	No	Yes	4" STD	4.500"	4.026"
36"	4"	44"	36"	0.19 Ellip.	6:1	15'-4"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	6:1	18'-7"	Yes	Yes	4" STD	4.500"	4.026"

MATERIAL NOTES:
Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.
Galvanize steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:
Precast safety end treatment for reinforced concrete pipe (RCP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".
When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.
Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.
Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.
Methods of lifting shall be provided by the manufacturer for ease of loading, unloading and installation.
Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.




PRECAST SAFETY END TREATMENT TYPE II ~ PARALLEL DRAINAGE

PSET-RP


FILE: psetrpss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONF	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	127	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




PLAN



ELEVATION




SECTION A-A AT CAP




SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A



CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2

					Bridge Division Standard	
<h2>STONE RIPRAP</h2>						
<h3>SRR</h3>						
FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES		
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY		
REVISIONS	1012	02	042, ETC.	FM 545		
	DIST	COUNTY	SHEET NO.			
	DAL	COLLIN	128			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




FIGURE 1 ~ TYPE R STONE RIPRAP
dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP
dry or mortared






FIGURE 3 ~ TYPE F STONE RIPRAP
grouted

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "Y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



PROTECTION STONE RIPRAP TOE OPTIONS ⑤





FIGURE 4 ~ COMMON STONE RIPRAP
dry or grouted





FIGURE 5 ~ PROTECTION STONE RIPRAP ⑤


SHEET 2 OF 2

					Bridge Division Standard	
<h2>STONE RIPRAP</h2>						
<h3>SRR</h3>						
FILE: srrside1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES		
©TxDOT April 2019	CONT SECT	JOB	HIGHWAY			
REVISIONS	1012 02	042, ETC.	FM 545			
	DIST	COUNTY	SHEET NO.			
	DAL	COLLIN	128A			

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:






INTERMEDIATE TOEWALL


PLAN




ELEVATION



SHOWING KEYWAY OPTION



SECTIONS THRU RIPRAP AT CAP



REINFORCEMENT DETAILS

- 1 When riprap is shown extended around header on layout, extend slab and toewall as shown and eliminate 4" curb.
- 2 Limits and configuration of drains and depressions are as shown elsewhere in plans or as directed by the Engineer.
- 3 Location of shoulder drain must consider limitations imposed by rail transition. Do not locate shoulder drains at expansion joints between approach slab and concrete pavement.
- 4 See details elsewhere in plans for installation of guard fence posts through concrete riprap.
- 5 Provide intermediate toewall only when designated elsewhere in the plans or included in the specifications.
- 6 Provide lower level of 2" Dia weep holes at 10' c-c backed by 1 CF packet of gravel and galvanized hardware cloth at all locations unless directed by the Engineer to eliminate.
- 7 Use wider or other drain configurations if shown elsewhere in plans or if directed by the Engineer.
- 8 Wall extension may be reduced or modified if approved by the Engineer. Increase wall extension to 1'-6" whenever the optional intermediate toewall is called for in the plans.
- 9 Top of cap to top of riprap dimension varies as directed by the Engineer. Should be 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.
- 10 #5 bars shown are required even when synthetic fiber reinforcing option is selected.
- 11 Provide sealing option for joint between the face of cap and riprap as designated by the Engineer or as shown elsewhere on plans.
- 12 Flashing (shown in Cap Option A) may be used at wingwall in addition to Exp Jt Mat'l if shown on plans or directed by the Engineer.
- 13 Provide #3 reinforcing bars at 18" Spa c-c. Provide Welded Wire Reinforcement (WWR) as 6x6-D2.9xD2.9 or D3xD3. Combinations of WWR and reinforcing bars may be used if both are permitted. Use lap splices of a minimum 6 inches, measured from the transverse wire of WWR, and the ends of reinforcing bars.
- 14 If granular material is specified, provide upper level of 2" Dia weep holes at 10' c-c backed by galvanized hardware cloth.
- 15 8" x 18 Gage Galv Sheet Metal
- 16 Provide WWR or #3 bars, with 1'-0" extension into slope.
- 17 WWR or reinforcing steel is continuous through riprap construction joints. Provide WWR or reinforcing steel that extends 1'-1" minimum into adjacent riprap on each side of construction joint even if synthetic reinforcing fiber is utilized.

GENERAL NOTES:
 Provide Class "B" concrete (f'c = 2,000 psi) unless noted elsewhere in plans.
 Provide Grade 60 reinforcing steel.
 Provide deformed welded wire reinforcement (WWR) meeting ASTM A1064, unless otherwise shown.
 Provide reinforcing bars, deformed WWR, or any suitable combination of both types for riprap reinforcing, unless specified elsewhere in the plans.
 Optionally synthetic fibers may be used if approved by the Engineer. Provide synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) in lieu of steel reinforcing in riprap concrete.
 Install construction joints or grooved joints extending the full slant slope height at intervals of approximately 20 feet unless otherwise directed by the Engineer.
 Hardware cloth, loose grade stone behind weep holes, flashing, or other sealing material are subsidiary to the bid item "Riprap".
 See Layout for limits of riprap.
 RR8 is to be used on stream crossings.
 RR9 is to be used on other embankments.

FOR CONTRACTOR'S INFORMATION ONLY:

5" of RR8	= 0.015 CY/SF
4" of RR9	= 0.012 CY/SF
#3 Reinf at 18" c-c	= 0.501 Lbs/SF
6x6-D3xD3	= 0.408 Lbs/SF

		Bridge Division Standard	
CONCRETE RIPRAP AND SHOULDER DRAINS EMBANKMENTS AT BRIDGE ENDS (TYPES RR8 & RR9)			
CRR			
FILE: crrstd1-19.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT April 2019	CON: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	1012	02	FM 545
DIST: DAL	COUNTY: COLLIN	SHEET NO. 129	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
1	1	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P		
	2	M3-2 M1-6F	EAST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	24 x 12 24 x 24	X X		10BWG	1	SA	P		
	3	S3-1T	<SYMBOL - SCHOOL BUS STOP AHEAD>	36 x 36	X		10BWG	1	SA	P		
	4	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
	5	D2-1	(DESTINATION) (DISTANCE) <1 LINE>	90 x 18	X		10BWG	1	SA	T	2EXT	
	6	M3-4 M1-6F	WEST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	24 x 12 24 x 24	X X		10BWG	1	SA	P		
	7	M2-1 M1-6F	JCT <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	21 x 15 24 x 24	X X		10BWG	1	SA	P		
2	1	W1-1L W13-1P	SYMBOL - HORIZ ALN TURN LEFT (SPEED) MPH <ADVISORY SPEED PLAQUE>	36 x 36 18 x 18	X X		10BWG	1	SA	P		
	2	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	3	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	3	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
**	2	D3-1	(STREET NAME)	30 X 9	X		10BWG	1	SA	P	BM	
**		D3-1	(STREET NAME)	36 X 6	X							
		R1-1	STOP	36 x 36	X							
	3	W1-6L W1-6R	<LARGE ARROW LEFT> <LARGE ARROW RIGHT>	48 x 24 48 x 24	X X		10BWG	1	SA	T		
	4	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	5	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	6	W1-2L W13-1P	SYMBOL - HORIZ CURVE LEFT (SPEED) MPH <ADVISORY SPEED PLAQUE>	36 x 36 18 x 18	X X		10BWG	1	SA	P		
	7	W1-1R W13-1P	SYMBOL - HORIZ ALN TURN RIGHT (SPEED) MPH <ADVISORY SPEED PLAQUE>	36 x 36 18 x 18	X X		10BWG	1	SA	P		
	8	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	9	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	10	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P		
	11	W1-6L W1-6R	<LARGE ARROW LEFT> <LARGE ARROW RIGHT>	48 x 24 48 x 24	X X		10BWG	1	SA	T		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 1 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	130	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
3	12	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	13	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	14	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	15	W1-1R W13-1P	SYMBOL - HORIZ ALN TURN RIGHT (SPEED) MPH < ADVISORY SPEED PLAQUE >	36 x 36 18 x 18	X X		10BWG	1	SA	P	
4	1	W1-2R W13-1P	SYMBOL - HORIZ CURVE RIGHT (SPEED) MPH < ADVISORY SPEED PLAQUE >	36 x 36 18 x 18	X X		10BWG	1	SA	P	
	2	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	3	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	4	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	T	
	5	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	6	R1-1	STOP	36 x 36	X		10BWG	1	SA	P	
	7	W1-6L W1-6R	< LARGE ARROW LEFT > < LARGE ARROW RIGHT >	48 x 24 48 x 24	X X		10BWG	1	SA	T	
	8	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	9	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	10	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	11	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	12	W1-1L W13-1P	SYMBOL - HORIZ ALN TURN LEFT (SPEED) MPH < ADVISORY SPEED PLAQUE >	36 x 36 18 x 18	X X		10BWG	1	SA	P	
5	1	D14-4T	ADOPT A HWY NEXT (MI) MILES (GROUP NAME)	48 x 48	X		10BWG	1	SA	T	
	2	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	3	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	4	I-2aT	(CITY NAME) CITY LIMIT	48 x 24	X		10BWG	1	SA	T	
	5	M3-2 M1-6F D10-7aT D10-7aT	EAST < AUXILIARY SIGN > < FM SHIELD > FARM ROAD (ROUTE #) < 3 DIGIT VERTICAL NUMBER > < 3 DIGIT VERTICAL NUMBER >	24 x 12 24 x 24 3 x 10 3 x 10	X X X X		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 2 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	131	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
6	1	W1-2L	SYMBOL - HORIZ CURVE LEFT	36 x 36	X		10BWG	1	SA	P		
		W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
	2	W11-10L	SYMBOL - BE ALERT FOR TRUCKS ENTERING LT	36 x 36	X		10BWG	1	SA	P		
	3	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	4	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	5	W1-6L	< LARGE ARROW LEFT >	48 x 24	X		10BWG	1	SA	T		
		W1-6R	< LARGE ARROW RIGHT >	48 x 24	X							
	6	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	7	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	8	W1-5L	SYMBOL - WINDING ROAD LEFT	36 x 36	X		10BWG	1	SA	P		
		W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
7	1	W1-2R	SYMBOL - HORIZ CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
		W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
	2	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	3	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	4	W1-6L	< LARGE ARROW LEFT >	48 x 24	X		10BWG	1	SA	T		
		W1-6R	< LARGE ARROW RIGHT >	48 x 24	X							
	5	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	6	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	7	W11-10L	SYMBOL - BE ALERT FOR TRUCKS ENTERING LT	36 x 36	X		10BWG	1	SA	P		
	8	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	9	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
10		W1-6L	< LARGE ARROW LEFT >	48 x 24	X		10BWG	1	SA	T		
		W1-6R	< LARGE ARROW RIGHT >	48 x 24	X							
	11	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							
	12	W1-8L	< CHEVRON LEFT >	24 x 30	X		10BWG	1	SA	P		
		W1-8R	< CHEVRON RIGHT >	24 x 30	X							

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 3 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	132	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
7	13	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	14	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	15	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	16	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	17	W1-6L W1-6R	< LARGE ARROW LEFT > < LARGE ARROW RIGHT >	48 x 24 48 x 24	X X		10BWG	1	SA	T	
	18	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	19	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	20	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
8	1	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	2	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	3	W1-6L W1-6R	< LARGE ARROW LEFT > < LARGE ARROW RIGHT >	48 x 24 48 x 24	X X		10BWG	1	SA	T	
	4	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	5	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	6	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	7	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	8	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
**	9	D3-1 R1-1	(STREET NAME) STOP	30 X 9 36 x 36	X X		10BWG	1	SA	P	
	10	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	11	W1-6L W1-6R	< LARGE ARROW LEFT > < LARGE ARROW RIGHT >	48 x 24 48 x 24	X X		10BWG	1	SA	T	
	12	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 4 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	133	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
	8	13	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		14	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		15	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		16	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		17	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		18	W1-6L W1-6R	< LARGE ARROW LEFT > < LARGE ARROW RIGHT >	48 X 24 48 X 24	X X		10BWG	1	SA	T	
		19	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		20	D3-3bTL D3-3bTR	STONY POINT CEMETERY (LEFT ARROW) STONY POINT CEMETERY (RIGHT ARROW)	60 X 30 60 X 30	X X		10BWG	1	SA	U	
	**	21	D3-1 R1-1	(STREET NAME) STOP	30 X 9 36 x 36	X X		10BWG	1	SA	P	
		22	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		23	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		24	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		25	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		26	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		27	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	9	1	W1-8L W1-8R	< CHEVRON LEFT > < CHEVRON RIGHT >	24 x 30 24 x 30	X X		10BWG	1	SA	P	
		2	W1-5L W13-1P	SYMBOL - WINDING ROAD LEFT (SPEED) MPH < ADVISORY SPEED PLAQUE >	36 x 36 18 X 18	X X		10BWG	1	SA	P	
	12	1	I-2cT	< DESTINATION >	66 X 18	X		10BWG	1	SA	T	
	**	2	D3-1 R1-1	(STREET NAME) STOP	30 X 9 36 x 36	X X		10BWG	1	SA	P	
		3	W1-2L W13-1P	SYMBOL - HORIZ CURVE LEFT (SPEED) MPH < ADVISORY SPEED PLAQUE >	36 x 36 18 x 18	X X		10BWG	1	SA	P	
		4	R1-1	STOP	36 x 36	X		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

Texas Department of Transportation

Traffic Operations Division Standard

SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	134	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
13	1	M2-1 M1-6F	JCT <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	21 x 15 24 x 24	X	X	10BWG	1	SA	P		
	2	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
	3	D1-2	(DESTINATION - 2 LINE)	102 X 30	X		S80	1	SA	U	BM	
	4	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P		
14	1	M3-4 M1-6F	WEST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	24 x 12 24 x 24	X	X	10BWG	1	SA	P		
	2	M3-4 M1-6F	WEST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	24 x 12 24 x 24	X	X	S80	1	SA	U		
		M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21 x 15	X							
		M3-2	EAST <AUXILIARY SIGN>	24 x 12	X							
		M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X							
		M6-3	<ARROW - VERTICAL STRGHT> <AUX. SIGN>	21 x 15	X							
	3	M3-2 M1-6F M6-1 M3-4	EAST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #) <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN> WEST <AUXILIARY SIGN>	24 x 12 24 x 24 21 x 15 24 x 12	X X X X		S80	1	SA	U		
		M1-6F M6-1	<FM SHIELD> FARM ROAD (ROUTE #) <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	24 x 24 21 x 15	X X							
	4	W1-7T	<BI-DIRECTIONAL LRG ARR w/ CHEVRONS>	96 x 36	X		S80	1	SA	U	BM	
	5	R1-1	STOP	36 x 36	X		10BWG	1	SA	P		
	6	M3-4 M1-6F M6-3 M3-4 M1-6F M6-1	WEST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #) <ARROW - VERTICAL STRGHT> <AUX. SIGN> WEST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #) <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN> STOP	24 x 12 24 x 24 21 x 15 24 x 12 24 x 24 21 x 15	X X X X X X		S80	1	SA	U		
	7	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P		
	8	M3-2 M1-6F D10-7aT D10-7aT	EAST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #) <3 DIGIT VERTICAL NUMBER> <3 DIGIT VERTICAL NUMBER>	24 x 12 24 x 24 3 x 10 3 x 10	X X X X		10BWG	1	SA	P		
	9	D1-2	(DESTINATION - 2 LINE)	102 X 30	X		S80	1	SA	U	BM	
	10	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
	11	D14-4T	ADOPT A HWY NEXT (MI) MILES (GROUP NAME)	48 x 48	X		10BWG	1	SA	T		
	12	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 6 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	135	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
14	13	M2-1 M1-6F	JCT <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	21 x 15 24 x 24	X X		10BWG	1	SA	P	
16	1	D14-4T	ADOPT A HWY NEXT (MI) MILES (GROUP NAME)	48 x 48	X		10BWG	1	SA	T	
**	2	D3-1 R1-1	(STREET NAME) STOP	30 x 9 36 x 36	X X		10BWG	1	SA	P	
	3	W1-3L #REF! W13-1P	SYMBOL - REVERSE TURN LEFT (SPEED) MPH <ADVISORY SPEED PLAQUE>	36 x 36 18 x 18	X X		10BWG	1	SA	P	
17	1	W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	2	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	3	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	4	W1-6L W1-6R	<LARGE ARROW LEFT> <LARGE ARROW RIGHT>	48 x 24 48 x 24	X X		10BWG	1	SA	T	
	5	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	6	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	7	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	8	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	9	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	10	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	11	W1-6L W1-6R	<LARGE ARROW LEFT> <LARGE ARROW RIGHT>	48 x 24 48 x 24	X X		10BWG	1	SA	T	
	12	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	13	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	14	W1-8L W1-8R	<CHEVRON LEFT> <CHEVRON RIGHT>	24 x 30 24 x 30	X X		10BWG	1	SA	P	
	15	M2-1 M1-6F	JCT <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	21 x 15 24 x 24	X X		10BWG	1	SA	P	
	16	W1-3L W13-1P	SYMBOL - REVERSE TURN LEFT (SPEED) MPH <ADVISORY SPEED PLAQUE>	36 x 36 18 x 18	X X		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 7 OF 10

Texas Department of Transportation

Traffic Operations Division Standard

SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	136	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
18	1	D2-1	(DESTINATION) (DISTANCE) < 1 LINE >	72 X 18	X		10BWG	1	SA	T	
	2	R2-1	SPEED LIMIT (SPEED)	30 X 36	X		10BWG	1	SA	P	
	3	D1-2	(DESTINATION - 2 LINE)	90 X 30	X		S80	1	SA	U	BM
	4	M3-4	WEST < AUXILIARY SIGN >	24 X 12	X		10BWG	1	SA	P	
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
	5	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 X 36	X		10BWG	1	SA	P	
	6	M3-2	EAST < AUXILIARY SIGN >	24 X 12	X		S80	1	SA	U	
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		M6-3		21 X 15	X						
		M3-3	SOUTH < AUXILIARY SIGN >	24 X 12	X						
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		M6-1	< ARROW - HORIZ. STRGHT > < AUXILIARY SIGN >	21 X 15	X						
	7	W1-7T	< BI-DIRECTIONAL LRG ARRW w/ CHEVRONS >	96 X 36	X		S80	1	SA	U	BM
	8	M3-4	WEST < AUXILIARY SIGN >	24 X 12	X		S80	1	SA	U	
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		M6-1	< ARROW - HORIZ. STRGHT > < AUXILIARY SIGN >	21 X 15	X						
		M3-2	EAST < AUXILIARY SIGN >	24 X 12	X						
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		M6-1	< ARROW - HORIZ. STRGHT > < AUXILIARY SIGN >	21 X 15	X						
	9	R1-1	STOP	36 X 36	X		10BWG	1	SA	P	
		W4-4P	CROSS TRAFFIC DOES NOT STOP (PLAQUE)	24 X 12	X						
	10	M3-2	EAST < AUXILIARY SIGN >	24 X 12	X		10BWG	1	SA	P	
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		D10-7aT	< 3 DIGIT VERTICAL NUMBER >	3 X 10	X						
		D10-7aT	< 3 DIGIT VERTICAL NUMBER >	3 X 10	X						
	11	M3-3	SOUTH < AUXILIARY SIGN >	24 X 12	X		S80	1	SA	U	
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		M6-1	< ARROW - HORIZ. STRGHT > < AUXILIARY SIGN >	21 X 15	X						
		M3-4	WEST < AUXILIARY SIGN >	24 X 12	X						
		M1-6F	< FM SHIELD > FARM ROAD (ROUTE #)	24 X 24	X						
		M6-3	< ARROW - VERTICAL STRGHT > < AUX. SIGN >	21 X 15	X						
	12	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 X 36	X		10BWG	1	SA	P	
	19	1	R2-1	SPEED LIMIT (SPEED)	30 X 36	X	10BWG	1	SA	P	
		2	R2-1	SPEED LIMIT (SPEED)	30 X 36	X	10BWG	1	SA	P	
		3	D3-1G	(STREET NAME)	30 X 8	X	10BWG	1	SA	P	BM
			D3-1G	(STREET NAME)	36 X 8	X					
			R1-1	STOP	36 X 36	X					

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 8 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	137	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
20	1	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	2	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	3	D3-1G R1-1	(STREET NAME) STOP	30 x 8 36 x 36	X X		10BWG	1	SA	P	BM
**	4	D14-4T	ADOPT A HWY NEXT (MI) MILES (GROUP NAME)	48 x 48	X		10BWG	1	SA	T	
	5	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	6	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	7	D3-1G R1-1	(STREET NAME) STOP	42 x 8 36 x 36	X X		10BWG	1	SA	P	BM
	8	D3-1G R1-1	(STREET NAME) STOP	42 x 8 36 x 36	X X		10BWG	1	SA	P	BM
	9	D3-1G R1-1	(STREET NAME) STOP	36 x 8 36 x 36	X X		10BWG	1	SA	P	BM
	10	M2-1 M4-3 M1-6TB	JCT <AUXILIARY SIGN> BUSINESS <AUXILIARY SIGN> SH Shield (SH 78)	21 x 15 24 x 12 24 x 24	X X X		10BWG	1	SA	P	
	11	S1-1	SYMBOL - PED CROSSING <PENTAGONAL>	36 x 36	X		10BWG	1	SA	P	
	12	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P	
	13	D3-1G R1-1	(STREET NAME) STOP	42 x 8 36 x 36	X X		10BWG	1	SA	P	BM
	14	D3-1G R1-1	(STREET NAME) STOP	42 x 8 36 x 36	X X		10BWG	1	SA	P	BM
	15	W3-1	SYMBOL - STOP AHEAD	30 x 30	X		10BWG	1	SA	T	
21	1	M3-4 M1-6F	WEST <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	24 x 12 24 x 24	X X		10BWG	1	SA	P	
	2	D1-2	(DESTINATION - 2 LINE)	102 x 30	X		S80	1	SA	U	BM

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post

SHEET 9 OF 10



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	138	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
21	3	D3-1G R1-1	(STREET NAME) STOP	42 X 8 30 x 8	X X		10BWG	1	SA	P	BM	TY = TYPE TY N TY S
	4	D3-1G D3-1G R1-1	(STREET NAME) (STREET NAME) STOP	30 x 8 36 x 8 36 x 36	X X X		10BWG	1	SA	P	BM	
	5	W11-8L	SYMBOL - BE ALERT FOR EMRGNCY VEHS LT	36 x 36	X		10BWG	1	SA	P		
	6	D3-1G D3-1G R1-1	(STREET NAME) (STREET NAME) STOP	30 x 8 36 x 8 36 x 36	X X X		10BWG	1	SA	P	BM	
	7	D3-1G R1-1	(STREET NAME) STOP	36 x 8 36 x 36	X X		10BWG	1	SA	P	BM	
	8	M4-5 M1-6F M6-1 M4-3 M1-6TB M6-4	TO <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #) <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN> BUSINESS <AUXILIARY SIGN> SH Shield (SH 78) <ARROW - DUAL LEFT & RIGHT> <AUX. SIGN>	24 x 12 24 x 24 21 x 15 24 x 12 24 x 24 21 x 15	X X X X X X		S80	1	SA	U		
	9	R1-1 W4-4P	STOP CROSS TRAFFIC DOES NOT STOP (PLAQUE)	36 x 36 24 x 12	X X		10BWG	1	SA	P		
	10	S1-1	SYMBOL - PED CROSSING <PENTAGONAL>	36 x 36	X		10BWG	1	SA	P		
	11	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>



- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).
- ** Salvage Signs and Reinstall on the New Post



SUMMARY OF SMALL SIGNS




SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	COLLIN	139	



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ⋈ DELINEATOR





Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

**FM 545
SIGNING & PAVEMENT
MARKING LAYOUT**
STA. 0+00 TO STA. 23+00




SHEET 1 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	140
CHECK	CONTROL	SECTION	JOB	
JRV	1012	02	042, ETC.	



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ⊞ DELINEATOR





Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 23+00 TO STA. 47+00


SHEET 2 OF 21


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	141
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ⊕ DELINEATOR






 Congli Ye, P.E. 4/28/2021


Texas Department of Transportation
 © 2021

FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT
 STA. 47+00 TO STA. 71+00




SHEET 3 OF 21

DESIGN	CY	FED. RD. DIV. NO.	6	FEDERAL AID PROJECT NO.	SEE TITLE SHEET	HIGHWAY NO.	FM 545
GRAPHICS	CY	STATE	TEXAS	DISTRICT	DALLAS	COUNTY	COLLIN
CHECK	MS	CONTROL	1012	SECTION	02	JOB	042, ETC.
CHECK	JRV						142



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - ▬ OBJECT MARKER
 - ≡ DELINEATOR




Congliye, P.E. 4/28/2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 71+00 TO STA. 95+00



SHEET 4 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	143
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.




NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - ⇌ OBJECT MARKER
 - ≡ DELINEATOR




ADOPT A HIGHWAY NEXT 2 MILES
THIS SECTION AVAILABLE FOR ADOPTION (972) 542-2461
D14-4T
①



Melissa
CITY LIMIT
POP. 4695
I-2gT
④

EAST M3-2
ROAD 545
MI-6F
D10-7gT 604 D10-7gT
⑤



Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 95+00 TO STA. 119+00

SHEET 5 OF 21

DESIGN	CY	FED. RD. DIV. NO.	6	FEDERAL AID PROJECT NO.	SEE TITLE SHEET	HIGHWAY NO.	FM 545
GRAPHICS	CY	STATE	TEXAS	DISTRICT	DALLAS	COUNTY	COLLIN
CHECK	MS	CONTROL	1012	SECTION	02	JOB	042, ETC.
CHECK	JRV						144

MATCH LINE STA. 119+00

MATCH LINE STA. 131+00






NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ≡ DELINEATOR

MATCH LINE STA. 131+00

MATCH LINE STA. 143+00



Congli Ye, P.E. 4/28/2021





**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**

STA. 119+00 TO STA. 143+00


SHEET 6 OF 21


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	MS	CONTROL	SECTION	JOB
CHECK	JRV	1012	02	042, ETC.
				145



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST.
 - OBJECT MARKER
 - ⊞ DELINEATOR





 Congli Ye, P.E. 4/28/2021

 Texas Department of Transportation
 © 2021

FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT
 STA. 143+00 TO STA. 167+00





SHEET 7 OF 21

DESIGN	CY	FED. RD. DIV. NO.	6	FEDERAL AID PROJECT NO.	SEE TITLE SHEET	HIGHWAY NO.	FM 545
GRAPHICS	CY	STATE	TEXAS	DISTRICT	DALLAS	COUNTY	COLLIN
CHECK	MS	CONTROL	1012	SECTION	02	JOB	042, ETC.
CHECK	JRV						146



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - ▬ OBJECT MARKER
 - ⊕ DELINEATOR






Conglye, P.E. 4/28/2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 167+00 TO STA. 191+00




SHEET 8 OF 21

DESIGN	CY	FED. RD. DIV. NO.	6	FEDERAL AID PROJECT NO.	SEE TITLE SHEET	HIGHWAY NO.	FM 545
GRAPHICS	CY	STATE	TEXAS	DISTRICT	DALLAS	COUNTY	COLLIN
CHECK	MS	CONTROL	1012	SECTION	02	JOB	042, ETC.
CHECK	JRV						147



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ≡ DELINEATOR






Congli Ye, P.E. 4/28/2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 191+00 TO STA. 215+00




SHEET 9 OF 21

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	148
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - DELINEATOR



Congli Ye, P.E. 4/28/2021

MATCH LINE STA. 215+00

MATCH LINE STA. 227+00

MATCH LINE STA. 227+00







MATCH LINE STA. 239+00



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 215+00 TO STA. 239+00

SHEET 10 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	149
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK	JRV			




Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 239+00 TO STA. 263+00






SHEET 11 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	150
CHECK	MS	CONTROL	SECTION	JOB
CHECK	JRV	1012	02	042, ETC.



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - DELINEATOR





Congli Ye, P.E. 4/28/2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 263+00 TO STA. 287+00






SHEET 12 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	151
MS	1012	02	042, ETC.	
JRV				



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - ⇌ OBJECT MARKER
 - ⊘ DELINEATOR





Congliye, P.E. 4/28/2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 287+00 TO STA. 311+00



SHEET 13 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	152
CHECK	MS	CONTROL	SECTION	JOB
CHECK	JRV	1012	02	042, ETC.



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ≡ DELINEATOR



Congli Ye, P.E. 4/28/2021



Texas Department of Transportation
© 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 311+00 TO STA. 335+00

SHEET 14 OF 21


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	153
CHECK	CONTROL	SECTION	JOB	
MS	JRV	1012	02	042, ETC.

MATCH LINE STA. 335+00




NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - ⊕ OBJECT MARKER
 - ⚡ DELINEATOR



MATCH LINE STA. 347+00



Texas Department of Transportation
© 2021



**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 335+00 TO STA. 359+00

SHEET 15 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	154
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	042, ETC.

MATCH LINE STA. 359+00

MATCH LINE STA. 371+00







NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
 - ⇐ OBJECT MARKER
 - ⊘ DELINEATOR

MATCH LINE STA. 371+00

MATCH LINE STA. 383+00



Congli Ye, P.E. 4/28/2021



Texas Department of Transportation
© 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**

STA. 359+00 TO STA. 383+00

SHEET 16 OF 21



DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	155
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

LEGEND:

- * SIGNS TO REMAIN
- ** SALVAGE SIGN AND REINSTALL ON THE NEW POST
- OBJECT MARKER
- ⊘ DELINEATOR




Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 383+00 TO STA. 407+00



SHEET 17 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	156
MS	1012	02	042, ETC.	
JRV				



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - ⇨ OBJECT MARKER
 - ⊘ DELINEATOR



CONGLI YE

 82802

 LICENSED PROFESSIONAL ENGINEER



Congli Ye, P.E. 4/28/2021

© 2021

FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT
 STA. 407+00 TO STA. 431+00




SHEET 18 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	157
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - OBJECT MARKER
 - ⊘ DELINEATOR



CONGLI YE
 82802
 LICENSED PROFESSIONAL ENGINEER

Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
 © 2021

FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT
 STA. 431+00 TO STA. 455+00

SHEET 19 OF 21


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	158
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	

MATCH LINE STA. 455+00


MATCH LINE STA. 467+00

MATCH LINE STA. 467+00

MATCH LINE STA. 479+00





ADOPT A HIGHWAY NEXT 2 MILES
BLUE RIDGE UNITED METHODIST CHURCH




NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - ➔ OBJECT MARKER
 - ⚡ DELINEATOR



* EXISTING SIGNS, POLE AND SCHOOL FLASHER TO REMAIN





Congliye, P.E. 4/28/2021

Texas Department of Transportation © 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT**
STA. 455+00 TO STA. 479+00


SHEET 20 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	159
MS	JRV	1012	02	042, ETC.



NOTE: ALL SIGNS WILL BE PLACED ACCORDING TO THE SIGNING STANDARDS.

- LEGEND:
- * SIGNS TO REMAIN
 - ** SALVAGE SIGNS AND REINSTALL ON THE NEW POST
 - ⇌ OBJECT MARKER
 - ⊘ DELINEATOR




Congli Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

**FM 545
SIGNING AND PAVEMENT
MARKING LAYOUT
STA. 479+00 TO END PROJECT**


SHEET 21 OF 21

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	160
CHECK	MS	CONTROL	SECTION	
CHECK	JRV	1012	02	
		042, ETC.		




D2-1 8in;
 1.5" Radius, 0.5" Border, White on, Green;
 "Blue Ridge", ClearviewHwy-3-W; "9", ClearviewHwy-3-W;

SHEET 1 SIGN 4




I-2aT 6in;
 1.5" Radius, 0.8" Border, White on, Green;
 "Melissa", ClearviewHwy-5-W-R;
 "CITY LIMIT", ClearviewHwy-3-W;
 "POP 4695", ClearviewHwy-3-W;

SHEET 5 SIGN 4



I-2cT 8in;
 1.5" Radius, 0.5" Border, White on, Green;
 "Valdasta", ClearviewHwy-5-W-R;


SHEET 10 SIGN 1



D3-3bTR;
 2.3" Radius, 0.8" Border, White on, Green;
 "Stony Point", ClearviewHwy-3-W; "Cemetery", ClearviewHwy-3-W;
 Standard Arrow Custom 20.0" X 5.4" 0°;

D3-3bTL;
 2.3" Radius, 0.8" Border, White on, Green;
 "Stony Point", ClearviewHwy-3-W; "Cemetery", ClearviewHwy-3-W;
 Standard Arrow Custom 20.0" X 5.4" 180°;

SHEET 8 SIGN 20



Mark A. Aboso, P.E. 04/15/2021
 Signature of Registrant Date




FM 545
 GUIDE SIGN DETAILS

SCALE: NTS SHEET 1 OF 4

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
HR	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
HR	TEXAS	DALLAS	COLLIN	161
CHECK BA	CONTROL	SECTION	JOB	
CHECK FRC	1012	02	042, ETC.	

DATE: 4/16/2021 FILE NAME: C:\Users\MABOSO\Desktop\PROJECTS\FM 545 SUNGUN AND HADEEL CSJ 1012-02-042, ETC\SEALED FM 545 Guide Sign Details.dgn

DATE: 4/16/2021 FILE NAME: C:\Users\WABOSO\Desktop\PROJECTS\FM 545 SUNGUN AND HADEL CSJ 1012-02-042, ETC\SEALED FM 545 Guide Sign Details.dgn




D1-2 8in UP-LT;
 1.9" Radius, 0.8" Border, White on, Green;
 Standard Arrow Custom 12.0" X 7.1" 180"; "Blue Ridge", ClearviewHwy-3-W;
 1.9" Radius, 0.8" Border, White on, Green;
 Standard Arrow Custom 12.0" X 7.1" 180"; "Westminster", ClearviewHwy-3-W;

SHEET 11 SIGN 3




D1-2 8in UP-RT;
 1.9" Radius, 0.8" Border, White on, Green;
 Standard Arrow Custom 10.0" X 7.1" 90"; "Melissa", ClearviewHwy-3-W;
 1.9" Radius, 0.8" Border, White on, Green;
 "Westminster", ClearviewHwy-3-W; Standard Arrow Custom 12.0" X 7.1" 0°;

SHEET 12 SIGN 9




D2-1 8in;
 1.5" Radius, 0.5" Border, White on, Green;
 "Melissa", ClearviewHwy-3-W; "10", ClearviewHwy-3-W;

SHEET 16 SIGN 1



D1-2 8in UP-RT;
 1.9" Radius, 0.8" Border, White on, Green;
 Standard Arrow Custom 10.0" X 7.1" 90"; "Blue Ridge", ClearviewHwy-3-W;
 1.9" Radius, 0.8" Border, White on, Green;
 "Princeton", ClearviewHwy-3-W; Standard Arrow Custom 12.0" X 7.1" 0°;

SHEET 16 SIGN 3



Mark A. Aboso, P.E. 04/15/2021
 Signature of Registrant Date




FM 545
 GUIDE SIGN DETAILS


SCALE: NTS SHEET 2 OF 4

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
HR	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
HR	TEXAS	DALLAS	COLLIN	161A
CHECK BA	CONTROL	SECTION	JOB	
CHECK FRC	1012	02	042, ETC.	

DATE: 4/16/2021 FILE NAME: C:\Users\WABOSO\Desktop\PROJECTS\FM 545 SUNGUN AND HADEEL CSJ 1012-02-042, ETC\SEALED FM 545 Guide Sign Detail.s.dgn




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"FM 545", ClearviewHwy-3-W;




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"Pecan", ClearviewHwy-3-W;
"St", ClearviewHwy-3-W;

SHEET 17 Sign 3




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"Justin", ClearviewHwy-3-W;
"Ln", ClearviewHwy-3-W;

SHEET 18 Sign 9




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"Pruett", ClearviewHwy-3-W;

SHEET 18 Sign 3




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"N", ClearviewHwy-3-W;
"Church", ClearviewHwy-3-W;
"St", ClearviewHwy-3-W;

SHEET 18 Sign 13




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"N", ClearviewHwy-3-W;
"Morrow", ClearviewHwy-3-W;
"St", ClearviewHwy-3-W;

SHEET 19 Sign 3




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"N", ClearviewHwy-3-W;
"Baker", ClearviewHwy-3-W;
"St", ClearviewHwy-3-W;

SHEET 18 Sign 7




D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"S", ClearviewHwy-3-W;
"Church", ClearviewHwy-3-W;
"St", ClearviewHwy-3-W;

SHEET 18 Sign 14



D3-1G(3) 4in;
1.0" Radius, 0.4" Border, White on, Green;
"Harmon", ClearviewHwy-3-W;
"Cir", ClearviewHwy-3-W;

SHEET 18 Sign 8




Mark A. Aboso, P.E. 04/15/2021
Signature of Registrant Date



FM 545
GUIDE SIGN DETAILS


SCALE: NTS SHEET 3 OF 4

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
HR	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
HR	TEXAS	DALLAS	COLLIN	161B
CHECK BA	CONTROL	SECTION	JOB	
CHECK FRC	1012	02	042, ETC.	




D1-2 8in LT-RT;
 1.9" Radius, 0.8" Border, White on, Green;
 Standard Arrow Custom 12.0" X 7.1" 180"; "Leonard", ClearviewHwy-3-W;
 1.9" Radius, 0.8" Border, White on, Green;
 "Farmersville", ClearviewHwy-3-W; Standard Arrow Custom 12.0" X 7.1" 0°;

SHEET 19 SIGN 2




D3-1G(3) 4in;
 1.0" Radius, 0.4" Border, White on, Green;
 "FM 545", ClearviewHwy-3-W;
 D3-1G(3) 4in;
 1.0" Radius, 0.4" Border, White on, Green;
 "S", ClearviewHwy-3-W;
 "Morrow", ClearviewHwy-3-W;
 "St", ClearviewHwy-3-W;

SHEET 19 Sign 4




D3-1G(3) 4in;
 1.0" Radius, 0.4" Border, White on, Green;
 "FM 545", ClearviewHwy-3-W;
 D3-1G(3) 4in;
 1.0" Radius, 0.4" Border, White on, Green;
 "N", ClearviewHwy-3-W;
 "Main", ClearviewHwy-3-W;
 "St", ClearviewHwy-3-W;

SHEET 19 Sign 6



D3-1G(3) 4in;
 1.0" Radius, 0.4" Border, White on, Green;
 "S", ClearviewHwy-3-W;
 "Main", ClearviewHwy-3-W;
 "St", ClearviewHwy-3-W;

SHEET 19 Sign 7



Mark A. Aboso, P.E. 04/15/2021
 Signature of Registrant Date



FM 545
 GUIDE SIGN DETAILS

SCALE: NTS SHEET 4 OF 4

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
HR	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
HR	TEXAS	DALLAS	COLLIN	161C
CHECK BA	CONTROL	SECTION	JOB	
CHECK FRC	1012	02	042, ETC.	



DATE: 4/16/2021 FILE NAME: C:\User's\WABOSO\Desktop\PROJECTS\FM 545_SJUNGUN AND HADEEL_CSJ 1012-02-042, ETC\SEALED FM 545 Guide Sign Detail.s.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>


Texas Department of Transportation		Traffic Operations Division Standard		
<h2 style="margin: 0;">TYPICAL SIGN REQUIREMENTS</h2>				
<h3 style="margin: 0;">TSR(3) - 13</h3>				
FILE: tsr3-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	DAL	COLLIN	162	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



TYPICAL SIGN REQUIREMENTS


TSR(4) - 13

FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	October 2003	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		1012	02	042, ETC.	FM 545				
12-03	7-13	DIST:	COUNTY:	SHEET NO.:					
9-08		DAL	COLLIN	162A					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	


CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT

NOTE

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.


The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5



EXIT ONLY PANEL


MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

NOTE:

- Sheeting for legend, symbols, and borders must be cut at panel joints.
- Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".



SCREW ATTACHMENT




NUT/BOLT ATTACHMENT


NOTE:

Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.



TYPICAL SIGN REQUIREMENTS

TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	DAL	COLLIN	162B	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

Post Type

FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)


Anchor Type

UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




BEHIND BARRIER




BEHIND GUARDRAIL

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.



BEHIND CONCRETE BARRIER



* Signs shall be mounted using the following condition that results in the greatest sign elevation:


- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND



RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

Texas Department of Transportation
 Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS


SMD(GEN)-08

© TxDOT July 2002	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CON: 1012	SECT: 02	JOB: 042, ETC.
		DIST: DAL	COUNTY: COLLIN	SHEET NO.: 163
			HIGHWAY: FM 545	

DATE: FILE:



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



SM RD SGN ASSM TY XXXX(X)SA(X-XXXX)


NOTE
 The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.



TOP VIEW

DETAIL A

CONCRETE ANCHOR



5/8" diameter Concrete Anchor - 8 places (embed a minimum of 5 1/2" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

SM RD SGN ASSM TY XXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE

- Foundation**
- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
 - The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
 - Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
 - Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
 - The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

ADDED DETAIL A FOR CLAMP BASE

10-2010
















SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08(DAL)

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
12-10 (DISTRICT)		1012	02	042, ETC.	FM 545
ADDED CLAMP BASE DETAIL FOR SLIP BASE INSTALLATION		DIST	COUNTY	SHEET NO.	
		DAL	COLL TN	164	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GENERAL NOTES:

SIGN SUPPORT	# OF POSTS	MAX. SIGN AREA
10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF

- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
- Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.
- Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT

SIGN DESCRIPTION	SUPPORT
	48-inch STOP sign (R1-1)
60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
48x60-inch signs	TY S80(1)XX(T)
48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
48x60-inch signs	TY S80(1)XX(T)
48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

Texas Department of Transportation
Traffic Operations Division




SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-2)-08

© TxDOT July 2002	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CON: 1012	SECT: 02	JOB: 042, ETC.
		DIST: DAL	COUNTY: COLLIN	SHEET NO.: 165



DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:






Splices shall only be allowed behind the sign substrate.



* Additional stiffener placed at approximate center of signs when sign width is greater than 10'.



See Detail E for clamp installation



Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details
See Detail E for clamp installation

GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.


REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)




**SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-3)-08**

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		1012	02	042, ETC.	FM 545
		DIST	COUNTY		SHEET NO.
		DAL	COLLIN		166


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.

YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES

- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


GENERAL NOTES

- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1) - 20


FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	1012	02	042, ETC.	FM 545
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	DAL	COLLIN		167

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS




POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	1012	02	042, ETC.	FM 545
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	DAL	COLLIN		168


GENERAL NOTES

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



REFLECTORIZED PROFILE PATTERN DETAIL

USING REFLECTIVE PROFILE PAVEMENT MARKINGS




NOTE

Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

NOTES






- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES

- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Texas Department of Transportation
Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 20

FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
5-00 2-10	DIST	COUNTY	SHEET NO.	
8-00 2-12	DAL	COLLIN	169	
3-03 6-20				

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES			
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	DEVICE	SINGLE	DOUBLE	INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX)			
										NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount	
SHEETING: Yellow, White or Red Type B or C reflective sheeting				SHEETING: Yellow, White or Red Type B or C Reflective Sheeting						DIRECTION: If Required, BI = Bi-Directional, BR = Bi-Directional with red on back	
NOTE: 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE: WC, YFLX, WFLX, GND						INSTL OM ASSM (OM-XX) (XXXX)XXX (XX)	
				MOUNT TYPE: GND, SRF						TYPE OF OBJECT MARKER: 1, 2, 3, or 4	

OBJECT MARKERS									
DEVICE	Type 1 (OM-1)		Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4	
									NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION: If Required, BI = Bi-Directional
SHEETING	Yellow-Type B _{FL} or C _{FL} Sheeting		Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			Red -Type B _{FL} or C _{FL} Sheeting
POST TYPE	TWT		WC	WC	WFLX	TWT			TWT
MOUNT TYPE	WAS, WAP		GND	GND	GND, SRF	WAS, WAP			WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.
DEVICE	GF1	GF2	CTB	W1-8				W1-6	
SHEETING: Yellow, White, Red			SIZE (W x L): 18"x 24" (Conventional), 24"x 30" (Conventional Oversize), 30"x 36" (Expressway), 36" x 48" (Freeway)				SIZE (W x L): 48" x 24" (Conventional), 60" x 30" (Expressway & Freeway)		
NOTE: 1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			MOUNTING HEIGHT: 4'-0" or 7'-0"				MOUNTING HEIGHT: 7'-0"		
NOTE: 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			NOTE: 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).						

Texas Department of Transportation
 Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

D & OM(1)-20

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	DAL	COLLIN	170	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS	
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT
GND	GND	SRF	WAS	WAP	GF 1
<p>Ground Line</p> <p>2'-0" Usual</p>	<p>Reflective material</p> <p>Post</p> <p>Stub</p>	<p>Reflective material</p> <p>Post</p> <p>Base</p>	<p>12" Dia.</p> <p>27" 30"</p>	<p>3" (Approx.)</p> <p>15"</p> <p>17" 20"</p> <p>12" Dia.</p>	<p>Centerline of MBCF rail element</p>
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.	NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.		

TYPE OF BARRIER MOUNTS	
GUARD FENCE ATTACHMENT	
GF 1	GF 2
<p>Centerline of MBCF rail element</p>	<p>Attached to post or block</p> <p>2'-6" Min.</p> <p>4" Min.</p> <p>4'-0"</p>

CONCRETE TRAFFIC BARRIER (CTB)	
<p>Place Barrier Reflector on top or on side(s) of CTB.</p>	

- GENERAL NOTES**
- Place delineators on a section of roadway at a consistent distance from the edge of pavement.
 - Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
 - When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
 - Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
 - Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
 - Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS
<p>4'-0"</p> <p>Pavement surface</p> <p>Ground Line</p>
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN
<p>7'-0"</p> <p>Pavement surface</p> <p>Ground Line</p>
NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

DELINEATORS AND TYPE 2 OBJECT MARKERS
<p>Approximately 4'-0"</p> <p>Pavement surface</p> <p>Ground Line</p> <p>2'-0" to 8'-0" or in front of object being marked</p>
NOTE See general notes 1, 2 and 3.

Texas Department of Transportation
 Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	DAL	COLLIN	171	


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation
Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20


FILE: dom3-20.dgn	DW: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS		1012 02	042, ETC.	FM 545
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	DAL	COLLIN	172	

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:

CROSSOVERS




DETAIL 1

FOR CULVERTS WITHOUT MBGF




DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES




DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4) -20

FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
3-15	DIST	COUNTY	SHEET NO.	
7-20	DAL	COLLIN	173	


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**

D & OM(5)-20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
7-20	DIST	COUNTY	SHEET NO.	
	DAL	COLLIN	174	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


STIMES

SDATES


Dallas District Standard for Two-Lane Highway Curve Signing/Markings



Typical Curve Treatment with Intersection



Typical Reverse Curve Edge Line Treatment



Curve Safety Sequence

Applicable Minimum Measures

Advisory Speed 55 mph or higher	Advisory Speed 40-50 mph	Advisory speed 35 mph or less	Curve signing, delineation and pavement markings (listed in order from minimum to maximum level of treatment as needed)
+	+	+	1 Advance warning (36" x 36") and advisory mph (18" x 18")
+	+	+	2 Chevron alignment signs if advisory speed is 15 mph or greater than posted speed
	+	+	3 Edge lines
			3a Pavement width 24' or greater 6" solid white edge line
			3b Pavement width 20' - 24' 4" solid white edge line
			3c Pavement width 20' or less no edge line
			Supplemental Measures
		#	4 Add shoulders and edge line (see #3a)
		#	5 Yellow high intensity flourescent chevron alignment signs - add reflective sheeting to sign support from bottom edge of sign
#	#	#	6 Large advance warning (48" x 48") and advisory mph (30" x 30")
#	#	#	7 Arrow sign (48" x 24")
		#	8 Large arrow sign with diagonals (96" x 36")
		#	9 Add flashers to advance warning signs
#	#	#	10 Surface treatment to improve friction
		**	** The W1-1R or L sign shall only be used when the advisory speed is 30 mph or less

+ = required
= optional

Applications 4 - 10 are additional supplemental applications which may be added as directed by the Area Engineer.

Note:
"B" - Chevron Spacing referenced from D&OM(3)-15B

Notes:

- Two methods will be used to determine the appropriate advisory speed for curves, the GPS Method (existing curves) and the Design Method (new curves).
- Notify the Traffic Engineering Section for all requests on advisory speeds for existing curves.

* Standard Double Yellow Stripes shall be dropped through a non-signalized intersection within the city limit. Outside the city limit, the Standard Double Yellow Strip shall be carried through all non-signalized intersections.

OCT-2014 UPDATED NOTES	Texas Department of Transportation ©2020			
JAN-2016 NOTE ADDED	TWO-LANE HIGHWAY CURVE SIGNING & MARKINGS DALLAS DISTRICT STANDARD			
SEPT-2016 NOTE ADDED FOR STRIPING IN CURVE				
MAR-2017 REMOVED REFERENCE TO DELINEATORS	SCALE: NTS	SHEET 1 OF 1		
MAY-2019 MODIFIED SIGN SIZE	DESIGN/CK BLS	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
	CHECK BLS	STATE	DISTRICT	COUNTY
	CHECK FRC	TEXAS	DALLAS	VARIOUS
	CHECK ARO	CONTROL	SECTION	JOB
		1012	02	042, ETC.
				175

FILES

A. GENERAL SITE DATA

1. **PROJECT LIMITS:** FM 545 from FM 2933 to BS 78D

Begin Project Coordinates : Latitude (N) : 33.2832336 Longitude (W) : -96.5466854
 Begin Project Coordinates : Latitude (N) : 33.2986841 Longitude (W) : -96.4009068

2. **PROJECT SITE MAPS:**

- * Project Location Map: The Title Sheet
- * Drainage Patterns: Drainage Area Maps (Sheets 87-90)
- * Slopes Anticipated After Major Gradings or Areas of Soil Disturbance: Typical Sections (Sheets 4-4D)
- * Location of Erosion and Sediment Controls: SW3P Site Maps (Sheets 17B-196)
- * Surface Waters and Discharge Locations: Drainage and Culvert Layouts (Sheets 91-103)
- * Project Specific Location(s) (PSL): To be determined by the project Construction Personnel. Location(s) shown on SW3P Site Map (if PSL location(s) is within one mile of project) and information located in project SW3P Binder (Reference Item *10 below).

3. **PROJECT DESCRIPTION:**

Construction of additional paved surface width, safety treated fixed objects. Consisting of grading, base, pavement structure, signage and pavement markings.

4. **MAJOR SOIL DISTURBING ACTIVITIES:**

Excavate and backfill to construct roadway shoulders and embankment; final grade ROW for drainage management.

5. **EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:**

The existing soil and vegetative cover is in good condition and is covered with approximately 95% vegetative cover. The soil type is primarily Houston black clay.

6. **TOTAL PROJECT AREA:** 67.83 Acres

7. **TOTAL AREA TO BE DISTURBED:** 47.16 Acres (70 %)

8. **WEIGHTED RUNOFF COEFFICIENT**

BEFORE CONSTRUCTION: 0.35
 AFTER CONSTRUCTION: 0.35

9. **NAME OF RECEIVING WATERS:**

Stiff Creek and its tributaries, Brinless Branch and its tributary, Sister Grove Creek and its tributaries, Harrington Branch, Lick Branch, Pilot Grove Creek and its tributaries, and multiple unnamed ponds. All project area waters flow to Sister Grove Creek (Segment 0821B) or Pilot Grove Creek (Segment 0821A), with no water quality impairments.

10. **PROJECT SW3P BINDER:**

A. For projects disturbing one to five acres, TxDOT will maintain a SW3P Binder at the project field office (if there is not a project field office, should be kept at the Area Office) which contains the following: Index Sheet, TCEQ Signature Authority, TxDOT's and Contractor's Small Construction Site Notice, SW3P Inspector Qualification Statements, EPIC Sheet, SW3P Sheet, Site Location Maps, Inspection and Maintenance Reports (Form 2118), Construction Stage Gate Checklists (CSGC), Stored Material Lists specifying associated control measures and the Appendix which contains the TPDES Construction General Permit, TxDOT and Contractor MS4 Operator Notification(s) and the Construction PSL Permits per all applicable requirements.

B. For projects disturbing 5 acres or more, TxDOT will follow the actions listed in (10.A.) above with the addition of the following: TxDOT and Contractor Notice of Intent (N.O.I.) and Fee Payment Form, TxDOT and Contractor Large Construction Site Notice (to be used instead of Small Site Notice), and TPDES Permit Coverage Notice.

C. For projects disturbing less than one acre, actions described in (10.A.) and (10.B.) above are not required. Acreage is calculated by adding Total Area To Be Disturbed Acres on project (See *7 above) and the PSL(s) acreage located within one mile of project.

B. EROSION AND SEDIMENT CONTROLS

1. **SOIL STABILIZATION PRACTICES:** (Select T = Temporary or P = Permanent, as applicable)

- | | |
|---|--|
| <input checked="" type="checkbox"/> TEMPORARY SEEDING | <input type="checkbox"/> PRESERVATION OF NATURAL RESOURCES |
| <input type="checkbox"/> MULCHING (Hay or Straw) | <input type="checkbox"/> FLEXIBLE CHANNEL LINER |
| <input type="checkbox"/> BUFFER ZONES | <input type="checkbox"/> RIGID CHANNEL LINER |
| <input type="checkbox"/> PLANTING | <input type="checkbox"/> SOIL RETENTION BLANKET |
| <input checked="" type="checkbox"/> SEEDING | <input type="checkbox"/> COMPOST MANUFACTURED TOPSOIL |
| <input type="checkbox"/> SODDING | <input checked="" type="checkbox"/> VERTICAL TRACKING |
| | <input type="checkbox"/> OTHER: (Specify Practice) |

2. **STRUCTURAL PRACTICES:** (Select T = Temporary or P = Permanent, as applicable)

- | |
|---|
| <input checked="" type="checkbox"/> SILT FENCES |
| <input checked="" type="checkbox"/> EROSION CONTROL LOGS |
| <input type="checkbox"/> EROSION CONTROL COMPOST BERMS (Low Velocity) |
| <input checked="" type="checkbox"/> ROCK FILTER DAMS |
| <input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER DIKES |
| <input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER SWALES |
| <input type="checkbox"/> DIVERSION DIKE AND SWALE COMBINATIONS |
| <input type="checkbox"/> PIPE SLOPE DRAINS |
| <input type="checkbox"/> PAVED FLUMES |
| <input checked="" type="checkbox"/> ROCK BEDDING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> TIMBER MATTING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> CHANNEL LINERS |
| <input type="checkbox"/> SEDIMENT TRAPS |
| <input type="checkbox"/> SEDIMENT BASINS |
| <input type="checkbox"/> STORM INLET SEDIMENT TRAP |
| <input type="checkbox"/> STONE OUTLET STRUCTURES |
| <input type="checkbox"/> CURBS AND GUTTERS |
| <input type="checkbox"/> STORM SEWERS |
| <input type="checkbox"/> VELOCITY CONTROL DEVICES |
| <input type="checkbox"/> OTHER: |

NOTE: TOP OF BMP'S SHOULD NOT BE HIGHER THAN ROADWAY ELEVATION AS NOT TO FLOOD ROADWAY UNLESS PRIOR APPROVAL FROM ENGINEER IS OBTAINED.

3. **STORM WATER MANAGEMENT:**

- A. Storm water drainage will be provided by ditches, inlets, and storm water systems which carry drainage within the R.O.W. to the lows within the roadway and project site which drains to natural facilities.
- B. Other permanent erosion controls include hydraulic design to limit structure outlet velocities and grading design generally consisting of 4:1 or flatter slopes with permanent vegetative cover.

4. **STORM WATER MANAGEMENT ACTIVITIES:** (Sequence of Construction)

See construction progress schedule for major soil disturbing activities, sequence & durations.

1. Install SW3P control devices (BMPs) to protect area receiving waters, and adjacent active roads and sidewalks, prior to construction activities disturbing soil in their vicinity, as shown in the SW3P Layout and/or as directed or authorized by Engineer.
2. Preserve existing vegetation, maintain a vegetative buffer along receiving waters, and phase construction activities to minimize exposure of disturbed soils - to the extent practicable.
3. Stabilize disturbed soils with Vegetative Tracking or other authorized BMPs as appropriate.
4. Revegetate unpaved surfaces in completed project areas as soon as practicable.
5. When construction activity is complete, project area is stabilized, and as directed or authorized by Engineer, remove all temporary SW3P controls.
6. Avoid storing portable sanitary units, concrete washouts or chemicals within 50 feet upgradient of a receiving water or drainage conveyance without adequate pollution controls.

Note: Storm water retention ponds were not utilized for this project due to limit ROW and equivalent protection being achieved with other devices.

5. **NON-STORM WATER DISCHARGES:**

Filter non-storm water discharges, or hold in retention basins, before being allowed to mix with storm water. These discharges consist of, but not limited to, non-polluted ground water, spring water, foundation or footing drain water, water used for dust control or pavement washing and vehicle washwater containing no detergents.

C. OTHER REQUIREMENTS & PRACTICES

1. **MAINTENANCE:**

Maintain all erosion and sediment controls in good working order. Perform any necessary cleaning/repairs/replacements at the earliest possible date prior to next rain event, but no later than 7 calendar days. Ensure the surrounding ground has dried sufficiently to prevent damage from equipment. "Too Wet" is the only reason for not adhering to timeframes described. When construction activities permanently or temporarily cease and are not expected to resume for 14 or more days on a disturbed portion of the site, stabilization measures must be initiated immediately.

2. **INSPECTION:**

A TxDOT Inspector will perform a regularly scheduled SW3P Inspection every 7 calendar days. An Inspection and Maintenance Report, signed by the TxDOT Inspector and the Contractor, will be filed for each inspection. Revise/clean/repair/replace each BMP control device in accordance with the current Field Inspection and Maintenance Report (Form 2118) and Item 1 (Maintenance) above.

3. **WASTE MATERIALS:**

On a daily basis, or as may be directed, collect all waste materials, trash and debris from the construction site and deposit into a metal dumpster having a secure cover and which meets all state and local city solid waste management requirements. Empty the dumpster as required by regulation, or as may be directed, at a local approved landfill site. Do not bury construction waste on the construction project site.

4. **HAZARDOUS WASTE & SPILL REPORTING:**

As a minimum, any products in the following categories are considered to be hazardous: Paints, Acids, Solvents, Fuels, Asphalt Products, Chemical Additives for Soil Stabilization, and Concrete Curing Compounds or Additives. When storing hazardous material on the project site, or at a Project Specific Location, take all practicable precaution to prevent and/or contain any spillage of these materials. In the event of a spill, contact the spill coordinator immediately.

5. **SANITARY WASTE:**

Use a licensed sanitary waste management contractor to collect all sanitary waste from portable units as may be required by local regulation, or as directed.

6. **CONSTRUCTION VEHICLE TRACKING:**

On a regular basis, or as may be directed, dampen haul roads for dust control and construct construction entrances/exits. Provide for a motorized broom or vacuum type sweeper to be available on a daily basis, or as may be directed, to remove sediment from paved roadways on project, abutting and traversing the project site.


7. **MANAGEMENT PRACTICES:**

- A. Construct disposal areas, stockpiles, haul roads and PSL's in a manner that will minimize and control the amount of sediment that may enter receiving waters. Do not locate disposal areas in any wetland, waterbody or streambed.
- B. Locate construction staging areas, vehicle maintenance and PSL's areas in a manner to minimize the runoff of pollutants.
- C. When working in or near a wetland, install and maintain operating soil erosion and sediment controls at all times during construction and isolate the work from the wetland.
- D. Clear all waterways as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.
- E. Procedures and/or practices should be taken to control dust.
- F. Sediment to be removed from roadways daily or when work begins after weather events if construction activities have ceased due to weather event.

FILE NAME

DATE

DESIGNER



Congli Ye, P.E. 4/28/2021



DALLAS DISTRICT ENVIRONMENTAL

STORM WATER POLLUTION PREVENTION PLAN (SW3P)

TEMPLATE REVISION DATE: 02/07/18

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	176
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

Notes To Designer:
 1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
 2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.
 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.
 Filled Out: xx/xx/xxxx
 Prepared by:

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List adjacent MS 4 Operator(s) that receive discharges from this project. They need to be notified prior to construction activities.
 (Note: Leave blank only if no adjacent MS 4 Operator(s) are affected.)

1. Collin County, East Fork/Phase II, Tracy Homfeld, Assistant Director of Engineering, 4690 Community Ave, Suite 200, McKinney, TX 75071
 2. Blue Mound/West Fork/Phase II, Kat Sanchez, City Secretary, 301 Blue Mound Road, Blue Mound, TX 76131
 3. Melissa, Elm Fork/Phase II, Jeff Cartwright, Public Works Director
- No Action Required Required Action

Action Number:

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
4. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the ordinary High Water Mark except on approved temporary stream crossings or drill pads.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# 25

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1. Culvert 1 Stiff Creek Sta. 29+18.58
2. Culvert 2 Trib. Stiff Creek Sta. 35+75.34
3. Culvert 3 Brinlee Branch Sta. 175+09.94
4. Culvert 4 Brinlee Branch Sta. 182+19.15
5. Culvert 10 Harrington Branch Sta. 314+05.72

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices for applicable 401 General Conditions:
 (Note: If CORP Permit not required, do not check boxes.)

Erosion <input checked="" type="checkbox"/> Temporary Vegetation <input type="checkbox"/> Blankets/Matting <input type="checkbox"/> Mulch <input type="checkbox"/> Sodding <input type="checkbox"/> Interceptor Swale <input type="checkbox"/> Diversion Dike <input type="checkbox"/> Erosion Control Compost <input type="checkbox"/> Mulch Filter Berm and Socks <input type="checkbox"/> Compost Filter Berm and Socks	Sedimentation <input checked="" type="checkbox"/> Silt Fence <input type="checkbox"/> Rock Berm <input type="checkbox"/> Triangular Filter Dike <input type="checkbox"/> Sand Bag Berm <input type="checkbox"/> Straw Bale Dike <input type="checkbox"/> Brush Berms <input type="checkbox"/> Erosion Control Compost <input type="checkbox"/> Erosion Control Compost <input type="checkbox"/> Mulch Filter Berm and Socks <input type="checkbox"/> Compost Filter Berm and Socks <input type="checkbox"/> Stone Outlet Sediment Traps <input type="checkbox"/> Sediment Basins	Post-Construction TSS <input type="checkbox"/> Vegetative Filter Strips <input type="checkbox"/> Retention/Irrigation Systems <input type="checkbox"/> Extended Detention Basin <input type="checkbox"/> Constructed Wetlands <input type="checkbox"/> Wet Basin <input type="checkbox"/> Erosion Control Compost <input type="checkbox"/> Mulch Filter Berm and Socks <input type="checkbox"/> Compost Filter Berm and Socks <input checked="" type="checkbox"/> Vegetation Lined Ditches <input type="checkbox"/> Sand Filter Systems <input type="checkbox"/> Grassy Swales
--	---	--

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action Number:
1.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751 & 752 in order to comply with requirements for invasive species, beneficial landscaping and tree/brush removal commitments.

- No Action Required Required Action

Action Number:

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT.

- No Action Required Required Action

Action Number:

1. Southern crawfish frog
 - 1) Minimize impacts to wetland habitats including isolated ephemeral pools;
 - 2) Water Quality BMPs;
 - 3) Amphibian BMPs
2. Water Quality BMPs: In addition to BMPs required for a TCEQ SWPPP and/or 401 water quality permits:
 - a. Minimize the use of equipment in streams and riparian areas during construction. When possible, equipment access should be from banks, bridge decks, or barges.
 - b. When temporary stream crossings are unavoidable, remove stream crossings once they are no longer needed and stabilize banks and soils around the crossing.

SECTION V. - CONTINUATION ON PAGE II

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

Special Note: The Migratory Bird Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. The contractor would remove all old migratory bird nests from any structure or trees where work would be done from October 1 to February 15. In addition, the contractor would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, efforts to avoid adverse impacts on protected birds, active nests, eggs and/or young would be observed.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corp of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):
 Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canisters, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?
 Yes No

If "No", then no further action is required.
 If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?
 Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action Number:

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action Number:

- 1.
- 2.

© 2021 Texas Department of Transportation
 Dallas District

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC) SHEET 1 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	FM 545
STATE	DISTRICT	COUNTY
TX	Dallas	Collin
CONTROL	SECTION	JOB
1012	02	042 etc.
		SHEET NO.
		177

GENERAL NOTE:
 Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.

Notes To Designer:

1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.
3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

Filed Out: xx/xx/xxxx
Prepared By:

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act".
No warranty of any kind is made by TxDOT for any purpose whatsoever.
TxDOT assumes no responsibility for the conversion of this standard to other
formats or for incorrect results or damage resulting from its use.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES,
CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES,
AND MIGRATORY BIRDS TREATY ACT. - CONTINUATION FROM PAGE I.


3. Streckers chorus frog and Woodhouses toad. Amphibian BMPs:
 - a. Contractors will be advised of potential occurrence in the project area, and to avoid harming the species if encountered.
 - b. Minimize impacts to wetland habitats, including isolated ephemeral pools; also minimize impacts to temporary and permanent open water features, including depressions, and riverine habitats.
 - c. Maintain hydrologic regime and connections between wetlands and other aquatic features.
 - d. N/A
 - e. Apply hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas where feasible. If hydromulching and/or hydroseeding are not feasible due to site conditions, using erosion control blankets or mats that contain no netting, or only contain loosely woven natural fiber netting is preferred. Plastic netting should be avoided to the extent practicable.
 - f. Project specific locations (PSLs) proposed within state-owned ROW should be located in uplands away from aquatic features.
 - g. When work is directly adjacent to the water, minimize impacts to shoreline banking sites (e.g., downed trees, sand bars, exposed bedrock) and overwinter sites (e.g., brush and debris piles, crayfish burrows) where feasible.
 - h. Avoid or minimize disturbing or removing downed trees, rotting stumps, and leaf litter, which may be refugia for terrestrial amphibians, where feasible.
 - i. N/A
4. Eastern box turtle, slender glass lizard, Texas garter snake, timber rattlesnake, and western box turtle Terrestrial Reptile BMPs:
 - a. Apply hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas where feasible. If such measures are not feasible due to site conditions, utilize erosion control blankets or mats that contain no netting or contain loosely woven, natural fiber netting. Plastic netting should be avoided to the extent practicable.
 - b. For open trenches and excavated pits, install escape ramps at an angle of less than 45 degrees (1:1) in areas left uncovered. Visually inspect excavation areas for trapped wildlife prior to backfilling.
 - c. If reptiles are found on the project site, allow the species to safely leave the project area.
 - d. Avoid or minimize disturbing or removing downed trees, rotting stumps, and leaf litter where feasible.
 - e. Contractors will be advised of potential occurrence in the project area, and to avoid harming the species if encountered.
5. Eastern spotted skunk, long-tailed weasel, swamp rabbit, and western hog-nosed skunk - Contractors will be advised of potential occurrence in the project area, and to avoid harming the species if encountered, and to avoid unnecessary impacts to dens

SECTION XXX. - CONTINUATION FROM PAGE 1



NA...

GENERAL NOTE:

Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.

 Texas Department of Transportation Dallas District			
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)			
SHEET 2 OF 2			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		FM 545
STATE	DISTRICT	COUNTY	
TX	Dallas	Collin	
CONTROL	SECTION	JOB	SHEET NO.
1012	02	042 etc.	177A

DATE DISTURBED: -----
 DATE STABILIZED: -----





APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	


	DATE INSTALLED	DATE REMOVED
BMP 1-1		
BMP 1-2		
BMP 1-3		
BMP 1-4		
BMP 1-5		
BMP 1-6		
BMP 1-7		
BMP 1-8		
BMP 1-9		
BMP 1-10		
BMP 1-11		
BMP 1-12		
BMP 1-13		

LEGEND:

- WATER FLOW DIRECTION
- EROSION CONTROL LOG
- ROCK FILTER DAM (TY 2)
- SILT FENCE
- CONSTRUCTION EXIT



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.





Congliye, P.E. 4/28/2021



**FM 545
 SW3P SITE MAPS**
 BEGIN PROJECT TO STA. 23+00

SHEET 1 OF 19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	178
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK	JRV			





BMP ID	DATE INSTALLED	DATE REMOVED
BMP 2-1		
BMP 2-2		
BMP 2-3		
BMP 2-4		
BMP 2-4A		
BMP 2-5		
BMP 2-6		
BMP 2-6A		
BMP 2-7		
BMP 2-7A		
BMP 2-8		
BMP 2-8A		
BMP 2-9		
BMP 2-10		
BMP 2-11		
BMP 2-11A		
BMP 2-12		
BMP 2-13		
BMP 2-14		
BMP 2-15		
BMP 2-16		
BMP 2-17		
BMP 2-18		

BMP ID	DATE INSTALLED	DATE REMOVED
BMP 2-18A		
BMP 2-19		
BMP 2-19A		
BMP 2-20		
BMP 2-21		
BMP 2-22		
BMP 2-23		
BMP 2-23A		
BMP 2-24		
BMP 2-24A		
BMP 2-25		
BMP 2-26		
BMP 2-27		
BMP 2-28		
BMP 2-29		
BMP 2-30		


APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021



**FM 545
SW3P SITE MAPS**
STA. 23+00 TO STA. 47+00




SHEET 2 OF 19

DATE DISTURBED: _____
DATE STABILIZED: _____

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	179
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE DISTURBED: -----



DATE STABILIZED: -----




	DATE INSTALLED	DATE REMOVED
BMP 3-1		
BMP 3-2		
BMP 3-3		
BMP 3-4		
BMP 3-5		
BMP 3-5A		
BMP 3-6		
BMP 3-6A		
BMP 3-7		
BMP 3-8		
BMP 3-9		
BMP 3-10		
BMP 3-11		
BMP 3-12		
BMP 3-13		
BMP 3-14		
BMP 3-15		
BMP 3-16		
BMP 3-17		
BMP 3-17A		
BMP 3-18		
BMP 3-18A		
BMP 3-19		
BMP 3-20		
BMP 3-21		
BMP 3-22		
BMP 3-23		
BMP 3-24		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021






**FM 545
SW3P SITE MAPS**
STA. 47+00 TO STA. 71+00

SHEET 3 OF 19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS				
CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	COLLIN	
MS	CONTROL	SECTION	JOB	180
CHECK	JRV	1012	02	042, ETC.




DATE DISTURBED: -----
 DATE STABILIZED: -----



	DATE INSTALLED	DATE REMOVED
BMP 4-1		
BMP 4-2		
BMP 4-3		
BMP 4-4		
BMP 4-5		
BMP 4-6		
BMP 4-7		
BMP 4-8		
BMP 4-9		
BMP 4-10		
BMP 4-11		
BMP 4-12		
BMP 4-13		
BMP 4-14		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



Congli Ye, P.E. 4/28/2021

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.





**FM 545
 SW3P SITE MAPS**
 STA. 71+00 TO STA. 95+00

SHEET 4 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 181
CHECK MS	CONTROL 1012	SECTION 02	JOB 042, ETC.	
CHECK JRV				

DATE DISTURBED: -----

DATE STABILIZED: -----





BMP	DATE INSTALLED	DATE REMOVED
BMP 5-1		
BMP 5-2		
BMP 5-3		
BMP 5-4		
BMP 5-5		
BMP 5-6		
BMP 5-7		
BMP 5-8		
BMP 5-9		
BMP 5-10		
BMP 5-11		
BMP 5-12		
BMP 5-13		
BMP 5-14		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT


PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

LEGEND:

- WATER FLOW DIRECTION
- EROSION CONTROL LOG
- ROCK FILTER DAM (TY 2)
- SILT FENCE
- CONSTRUCTION EXIT



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021






**FM 545
SW3P SITE MAPS**
STA. 95+00 TO STA. 119+00

SHEET 5 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	182
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

MATCH LINE STA. 119+00



MATCH LINE STA. 131+00



	DATE INSTALLED	DATE REMOVED
BMP 6-1		
BMP 6-2		
BMP 6-3		
BMP 6-4		
BMP 6-5		
BMP 6-6		
BMP 6-7		
BMP 6-8		
BMP 6-9		
BMP 6-10		
BMP 6-11		
BMP 6-12		
BMP 6-13		
BMP 6-14		
BMP 6-15		
BMP 6-16		
BMP 6-17		
BMP 6-18		
BMP 6-19		
BMP 6-20		
BMP 6-21		
BMP 6-22		
BMP 6-23		


APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	




MATCH LINE STA. 131+00

MATCH LINE STA. 143+00



DATE DISTURBED: _____
 DATE STABILIZED: _____

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021




**FM 545
 SW3P SITE MAPS**
 STA. 119+00 TO STA. 143+00

SHEET 6 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	183
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE DISTURBED: -----

DATE STABILIZED: -----




	DATE INSTALLED	DATE REMOVED
BMP 7-1		
BMP 7-2		
BMP 7-3		
BMP 7-4		
BMP 7-5		
BMP 7-6		
BMP 7-7		
BMP 7-8		
BMP 7-9		
BMP 7-10		
BMP 7-11		
BMP 7-12		
BMP 7-13		
BMP 7-14		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

LEGEND:

- WATER FLOW DIRECTION
- EROSION CONTROL LOG
- ROCK FILTER DAM (TY 2)
- SILT FENCE
- CONSTRUCTION EXIT



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.




Cong Li Ye, P.E. 4/28/2021

Texas Department of Transportation
© 2021

**FM 545
SW3P SITE MAPS**
STA. 143+00 TO STA. 167+00

SHEET 7 OF 19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	184
CHECK	MS	CONTROL	SECTION	JOB
CHECK	JRV	1012	02	042, ETC.



	DATE INSTALLED	DATE REMOVED
BMP 8-1		
BMP 8-2		
BMP 8-3		
BMP 8-4		
BMP 8-5		
BMP 8-6		
BMP 8-6A		
BMP 8-7		
BMP 8-8		
BMP 8-9		
BMP 8-9A		
BMP 8-10		
BMP 8-10A		
BMP 8-11		
BMP 8-12		
BMP 8-12A		
BMP 8-13		
BMP 8-14		
BMP 8-15		
BMP 8-16		
BMP 8-17		
BMP 8-18		
BMP 8-18A		




	DATE INSTALLED	DATE REMOVED
BMP 8-19		
BMP 8-19A		
BMP 8-20		
BMP 8-21		
BMP 8-22		
BMP 8-22A		
BMP 8-23		
BMP 8-23A		
BMP 8-24		
BMP 8-25		
BMP 8-26		
BMP 8-27		
BMP 8-28		
BMP 8-29		
BMP 8-30		
BMP 8-31		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT


PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

- LEGEND:**
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT

- NOTES:**
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021





DATE DISTURBED: _____
 DATE STABILIZED: _____

Texas Department of Transportation
 © 2021

**FM 545
 SW3P SITE MAPS**
 STA. 167+00 TO STA. 191+00

SHEET 8 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY
CHECK MS	TEXAS	DALLAS	COLLIN
CHECK JRV	CONTROL	SECTION	JOB
	1012	02	042, ETC.






- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

	DATE INSTALLED	DATE REMOVED
BMP 9-1		
BMP 9-2		
BMP 9-3		



Congli Ye, P.E. 4/28/2021

DATE DISTURBED: -----
 DATE STABILIZED: -----



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.
 - NO SOIL DISTURBANCE AND OTHER WORK WITH POTENTIAL STORMWATER POLLUTANTS PLANNED BETWEEN STA. 194+30 AND STA. 280+00.



**FM 545
 SW3P SITE MAPS**
 STA. 191+00 TO STA. 215+00

SHEET 9 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 186
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	





APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	


	DATE INSTALLED	DATE REMOVED
BMP 10-1		
BMP 10-1A		
BMP 10-2		
BMP 10-3		
BMP 10-4		
BMP 10-4A		
BMP 10-5		
BMP 10-6		
BMP 10-7		
BMP 10-8		

- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT



DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.
 - NO SOIL DISTURBANCE AND OTHER WORK WITH POTENTIAL STORMWATER POLLUTANTS PLANNED BETWEEN STA. 194+30 AND STA. 280+00.



Congli Ye, P.E. 4/28/2021




**FM 545
 SW3P SITE MAPS**
 STA. 263+00 TO STA. 287+00

SHEET 10 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	187
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE DISTURBED: -----

DATE STABILIZED: -----





	DATE INSTALLED	DATE REMOVED
BMP 11-1		
BMP 11-2		
BMP 11-3		
BMP 11-4		
BMP 11-5		
BMP 11-6		
BMP 11-7		
BMP 11-8		
BMP 11-9		
BMP 11-10		
BMP 11-11		
BMP 11-12		
BMP 11-13		
BMP 11-14		
BMP 11-15		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT


PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT



NOTES:

- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
- ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
- CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
- SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
- BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
- SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021



**FM 545
SW3P SITE MAPS**
STA. 287+00 TO STA. 311+00

SHEET 11 OF 19


DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	188
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

MATCH LINE STA. 311+00

MATCH LINE STA. 323+00

MATCH LINE STA. 323+00


MATCH LINE STA. 335+00



BMP ID	DATE INSTALLED	DATE REMOVED
BMP 12-1		
BMP 12-1A		
BMP 12-2		
BMP 12-2A		
BMP 12-3		
BMP 12-3A		
BMP 12-4		
BMP 12-5		
BMP 12-6		
BMP 12-7		
BMP 12-7A		
BMP 12-8		
BMP 12-8A		
BMP 12-9		
BMP 12-9A		
BMP 12-10		
BMP 12-11		
BMP 12-12		
BMP 12-13		
BMP 12-14		
BMP 12-15		
BMP 12-16		
BMP 12-17		
BMP 12-18		
BMP 12-19		
BMP 12-20		


APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



DATE DISTURBED: _____
 DATE STABILIZED: _____



- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.





**FM 545
 SW3P SITE MAPS**
 STA. 311+00 TO STA. 335+00

SHEET 12 OF 19


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	MS	CONTROL	SECTION	JOB
CHECK	JRV	1012	02	042, ETC.



- LEGEND:
- ← WATER FLOW DIRECTION
 - ⌋ EROSION CONTROL LOG
 - ⌋ ROCK FILTER DAM (TY 2)
 - SCF SILT FENCE
 - CONSTRUCTION EXIT




- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT



	DATE INSTALLED	DATE REMOVED
BMP 13-1		
BMP 13-2		
BMP 13-3		
BMP 13-4		
BMP 13-5		
BMP 13-6		
BMP 13-7		
BMP 13-8		
BMP 13-9		
BMP 13-10		


APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.





Cong Li Ye, P.E. 4/28/2021



**FM 545
 SW3P SITE MAPS**
 STA. 335+00 TO STA. 359+00

SHEET 13 OF 19





DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	190
MS	1012	02	042, ETC.	
JRV				



	DATE INSTALLED	DATE REMOVED
BMP 14-1		
BMP 14-2		
BMP 14-3		
BMP 14-4		
BMP 14-5		
BMP 14-6		
BMP 14-7		
BMP 14-8		
BMP 14-8A		
BMP 14-9		
BMP 14-9A		
BMP 14-10		
BMP 14-11		
BMP 14-12		
BMP 14-12A		
BMP 14-13		
BMP 14-13A		
BMP 14-14		
BMP 14-15		
BMP 14-16		
BMP 14-17		


APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021





**FM 545
SW3P SITE MAPS**
 STA. 359+00 TO STA. 383+00

SHEET 14 OF 19

DESIGN CY	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS CY	6	SEE TITLE SHEET		FM 545
CHECK MS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JRV	TEXAS	DALLAS	COLLIN	191
	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	

DATE DISTURBED: -----
 DATE STABILIZED: -----




- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT

	DATE INSTALLED	DATE REMOVED
BMP 15-1		
BMP 15-2		
BMP 15-3		
BMP 15-4		
BMP 15-5		
BMP 15-6		
BMP 15-7		
BMP 15-8		
BMP 15-9		
BMP 15-10		
BMP 15-11		
BMP 15-12		


APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



NOTES:

1. 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
2. ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
3. CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
4. SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
5. BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
6. SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.





Congli Ye, P.E. 4/28/2021



**FM 545
 SW3P SITE MAPS**
 STA. 383+00 TO STA. 407+00

SHEET 15 OF 19





DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 192
CHECK MS	CONTROL	SECTION	JOB	
CHECK JRV	1012	02	042, ETC.	



BMP	DATE INSTALLED	DATE REMOVED
BMP 16-1		
BMP 16-2		
BMP 16-2A		
BMP 16-3		
BMP 16-3A		
BMP 16-4		
BMP 16-5		
BMP 16-6		
BMP 16-7		
BMP 16-7A		
BMP 16-8		
BMP 16-8A		
BMP 16-9		
BMP 16-10		
BMP 16-11		
BMP 16-12		
BMP 16-13		
BMP 16-14		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	



DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.
 - NO SOIL DISTURBANCE AND OTHER WORK WITH POTENTIAL STORMWATER POLLUTANTS PLANNED BETWEEN STA. 422+00 AND STA. 446+70.

CONGLI YE
 82802
 LICENSED PROFESSIONAL ENGINEER



Congli Ye, P.E. 4/28/2021

© 2021

FM 545
SW3P SITE MAPS
 STA. 407+00 TO STA. 431+00

SHEET 16 OF 19

DESIGN CY	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET		HIGHWAY NO. FM 545
GRAPHICS CY	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK MS	TEXAS	DALLAS	COLLIN	193
CHECK JRV	CONTROL	SECTION	JOB	
	1012	02	042, ETC.	





	DATE INSTALLED	DATE REMOVED
BMP 17-1		
BMP 17-2		
BMP 17-3		
BMP 17-4		
BMP 17-5		
BMP 17-6		
BMP 17-7		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT


PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

- LEGEND:
- WATER FLOW DIRECTION
 - EROSION CONTROL LOG
 - ROCK FILTER DAM (TY 2)
 - SILT FENCE
 - CONSTRUCTION EXIT



DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.
 - NO SOIL DISTURBANCE AND OTHER WORK WITH POTENTIAL STORMWATER POLLUTANTS PLANNED BETWEEN STA. 422+00 AND STA. 446+70.





**FM 545
 SW3P SITE MAPS**
 STA. 431+00 TO STA. 455+00

SHEET 17 OF 19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	194
CHECK	MS	CONTROL	SECTION	JOB
CHECK	JRV	1012	02	042, ETC.



MATCH LINE STA. 455+00




BMP	DATE INSTALLED	DATE REMOVED
BMP 18-1		
BMP 18-2		
BMP 18-3		
BMP 18-4		
BMP 18-5		
BMP 18-6		
BMP 18-7		
BMP 18-8		
BMP 18-9		
BMP 18-10		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	




MATCH LINE STA. 467+00



DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.





Congli Ye, P.E. 4/28/2021



**FM 545
 SW3P SITE MAPS**
 STA. 455+00 TO STA. 479+00

SHEET 18 OF 19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	195
CHECK	CONTROL	SECTION	JOB	
MS	1012	02	042, ETC.	
CHECK				
JRV				



LEGEND:

	WATER FLOW DIRECTION
	EROSION CONTROL LOG
	ROCK FILTER DAM (TY 2)
	SILT FENCE
	CONSTRUCTION EXIT


	DATE INSTALLED	DATE REMOVED
BMP 19-1		
BMP 19-2		
BMP 19-3		
BMP 19-4		
BMP 19-5		
BMP 19-6		
BMP 19-7		
BMP 19-8		
BMP 19-9		
BMP 19-10		
BMP 19-11		
BMP 19-12		

APPROXIMATE LENGTH/SPACING OF SW3P DEVICES		
TYPE OF DEVICE	APPROX. LENGTH	SPACING
ECL	10 LF/SIDE OF ROAD	EVERY 500' OF DITCH
RFD	40 LF	AT EACH CULVERT

PERMANENT SEEDING (PER TYPICAL SECTION)	
DATE PLACED	

DATE DISTURBED: -----
 DATE STABILIZED: -----

- NOTES:
- 10 LF OF EROSION CONTROL LOG TO BE PLACED IN THE DITCH ON BOTH SIDES OF THE ROAD EVERY 500', THE BEGIN AND END OF PROJECT, AND ON EACH CORNER OF THE INTERSECTION.
 - ACTUAL LOCATION OF THE EROSION CONTROL LOG TO BE DETERMINED BY THE ENGINEER.
 - CONSTRUCTION EXIT LOCATIONS TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - BMP'S SHALL NOT BE INSTALLED IN THEIR CONTROL AREAS ANY SOONER THAN 2 WEEKS PRIOR TO SOIL DISTURBING OF THAT AREA.
 - SEE TYPICAL SECTIONS FOR THE DISTURBANCE AND SEEDING LIMITS.



Congli Ye, P.E. 4/28/2021




**FM 545
 SW3P SITE MAPS**
 STA. 479+00 TO END PROJECT

SHEET 19 OF 19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CY	6	SEE TITLE SHEET		FM 545
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CY	TEXAS	DALLAS	COLLIN	
CHECK	CONTROL	SECTION	JOB	196
MS	1012	02	042, ETC.	
CHECK	JRV			


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE
FILE



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	1012	02	042, ETC.	FM 545	
	DIST	COUNTY	SHEET NO.		
	DAL	COLLIN	197		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




FILTER DAM AT TOE OF SLOPE

(RFD1)




FILTER DAM AT SEDIMENT TRAP

(RFD1) OR (RFD2)




FILTER DAM AT CHANNEL SECTIONS


(RFD1) OR (RFD2) OR (RFD3)




PLAN VIEW




"V" SHAPE PLAN VIEW




PROFILE



SECTION C-C




SECTION B-B



TYPE 4 (SACK GABIONS)

(RFD4)



SECTION A-A

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES			
ROCK FILTER DAMS			
EC(2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	1012	02	042, ETC.
DIST	COUNTY		SHEET NO.
DAL	COLLIN		198

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 05/12/2020 03:44 PM
FILE: DOCUMENT NAME



PLAN VIEW




ELEVATION VIEW


CONSTRUCTION EXIT (TYPE 1)
ROCK CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 1)

1. The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
2. The coarse aggregate should be open graded with a size of 4" to 8".
3. The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
4. The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other materials approved by the Engineer.
5. The construction exit shall be graded to allow drainage to a sediment trapping device.
6. The guidelines shown hereon are suggestions only and may be modified by the Engineer.
7. Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




ELEVATION VIEW


CONSTRUCTION EXIT (TYPE 2)
TIMBER CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 2)

1. The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50'.
2. The treated timber planks shall be attached to the railroad ties with 1/2" x 6" min. lag bolts. Other fasteners may be used as approved by the Engineer.
3. The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
4. The approach transitions shall be no steeper than 6:1 and constructed as directed by the Engineer.
5. The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
6. The construction exit should be graded to allow drainage to a sediment trapping device.
7. The guidelines shown hereon are suggestions only and may be modified by the Engineer.
8. Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




SECTION A-A
CONSTRUCTION EXIT (TYPE 3)
SHORT TERM

GENERAL NOTES (TYPE 3)


1. The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
2. The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
3. The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
4. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES CONSTRUCTION EXITS EC(3)-16			
FILE: ec316	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	1012	02	042
DIST	COUNTY	SHEET NO.	
DAL	COLLIN	199	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PLAN VIEW




SECTION A-A

EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW




SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

- GENERAL NOTES:**
1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
 3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
 4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
 5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
 6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
 7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
 8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
 9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
 - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
 - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
 - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
 - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
 - CL-DI EROSION CONTROL LOG AT DROP INLET
 - CL-CI EROSION CONTROL LOG AT CURB INLET
 - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET

SHEET 1 OF 3

Design Division Standard

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES


EROSION CONTROL LOG

EC (9) - 16

FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
DIST	COUNTY		SHEET NO.	
DAL	COLLIN		200	


\$DATE\$ \$TIME\$ \$FILE\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




EROSION CONTROL LOGS ON SLOPES
STAKE AND TRENCHING ANCHORING

CL-SST




SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




EROSION CONTROL LOGS ON SLOPES
STAKE AND LASHING ANCHORING

CL-SSL





STAKE AND TRENCHING ANCHORING DETAIL

CL-SST



STAKE AND LASHING ANCHORING DETAIL

CL-SSL



STAKE NOTCH DETAIL

LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

SHEET 2 OF 3


Texas Department of Transportation
Design Division Standard

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES
EROSION CONTROL LOG
EC(9) - 16

FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
DIST	COUNTY	SHEET NO.		
DAL	COLLIN	201		


\$TIME\$
\$DATE\$
\$FILE\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT: 1012	SECT: 02	JOB: 042, ETC.
REVISIONS	DIST: DAL		COUNTY: COLLIN
			SHEET NO.: 202

\$DATE\$ \$TIME\$ \$FILE\$

USER ID

SURFACE PREPARATION ITEM 160* TOPSOIL SY / ITEM 161* COMPOST MANUF. TOPSOIL (BOS) (4") SY

SURFACE PREPARATION

Prepare planting area surface BEFORE placing Topsoil, Compost, Fertilizer, Seed and/or Sod. Once project area has been completed to final lines, grade and compaction, remove objectionable materials from planting area surface and cultivate existing surface to a depth of 4 inches, unless otherwise specified or directed.

Refer to Items 160 and 161 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.

TOPSOIL NOTES:

- When Topsoil is specified under Item 160, use suitable material salvaged from the project ROW in accordance with Item 160 specifications, and/or secure additional good material from approved sources.
- Topsoil shall include only the top 6 inches of its native surface, and be easily cultivated, fertile, erosion-resistant and free of objectionable materials.
- Topsoil obtained from sites outside of the ROW must come from approved sources and have a pH between 5.5 and 8.5 su.
- Place Topsoil on pre-cultivated surface, spread to a uniform loose cover at thickness specified, and shape per plans. Water and roll the finished surface with a light roller or other suitable equipment per Item 160.3; do not over-compact.

COMPOST NOTES:

- When Compost Manufactured Topsoil (4") is specified under Item 161, use compost meeting all requirements of Item 161.2 and Table 1. Provide quality control (QC) documentation and obtain Engineer approval prior to compost delivery.
- Contractor shall provide tickets/invoices that document material type, quantity and placement for all compost delivered.
- Additional topsoil may be required to be imported to achieve the compost/topsoil mix ratio. Topsoil must meet Item 160 specifications.

APPLICATION OF COMPOST MANUFACTURED TOPSOIL (4")

AFTER Surface Preparation, uniformly spread a 1-inch layer of compost on-grade with 3 inches topsoil over pre-cultivated planting area. (25% compost and 75% topsoil = 1" compost and 3" topsoil.) Then mix compost and topsoil together by cultivating the compost into the topsoil (by till or disk) to a 4-inch (4") depth. Roll the finished surface with a light corrugated drum; do not over-compact.

FERTILIZER ITEM 166* FERTILIZER AC

SOIL ANALYSIS FOR FERTILIZER APPLICATION RATE

Unless otherwise stated in the plans, Contractor shall perform at least one soil analysis on each project before fertilization, and submit results to Engineer with recommended fertilizer rates based on soil analysis. Engineer may direct sample location(s). Soil analysis may be waived if both compost and sod are used on entire project.

FERTILIZER NOTES:

- Refer to Item 166 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Apply fertilizer BEFORE seeding, or AFTER placing sod.
- Use fertilizer containing nitrogen (N), phosphoric acid (P) and potash (K) nutrients, unless otherwise specified. At least 50% of the Nitrogen component shall be a slow-release sulfur-coated urea as described in Item 166.3. Do not apply more than 60 lbs Nitrogen per acre without Engineer concurrence.
- Deliver fertilizer in bags, clearly labeled to show contents, unless otherwise specified or approved prior to delivery. When non-bagged, loose fertilizer is approved, provide documentation for each load of material delivered, to validate authenticity of the material.
- Apply fertilizer uniformly, as a dry, granular material, essentially dust-free, and do not mix with water for application as a slurry.
- When both temporary and permanent seeding are specified for the same area, apply half of the required fertilizer before the temporary seeding operation and the other half before the permanent seeding operation.

SEEDING FOR EROSION CONTROL ITEM 164* DRILL SEEDING AC

RECOMMENDED PLANTING SEASON	PERMANENT RURAL SEED MIX ITEM 164 - DRILL SEEDING (PERM) (RURAL) (CLAY)	PERMANENT URBAN SEED MIX ITEM 164 - DRILL SEEDING (PERM) (URBAN) (CLAY)	TEMPORARY DRILL SEED MIX ITEM 164 - DRILL SEEDING (TEMP) (WARM OR COOL)
WARM SEASON Mar. 15th, April, May, June, July, August, Sept. 15th	Green Sprangletop (Van Horn) - 1.0 lbs/AC Sideoats Grama (Haskell) - 1.0 lbs/AC Texas Grama (Atascosa) - 1.0 lbs/AC Hairy Grama (Chaparral) - 0.4 lbs/AC Shortspike Windmillgrass (Welder) - 0.2 lbs/AC Little Bluestem (OK Select) - 0.8 lbs/AC Purple Prairie Clover (Cuero) - 0.6 lbs/AC Engelmann Daisy (Eldorado) - 0.75 lbs/AC Illinois Bundlesflower - 1.3 lbs/AC Awnless Bushsunflower (Plateau) - 0.2 lbs/AC	Green Sprangletop (Leptochloa dubia) - 0.3 lbs/AC Sideoats Grama (El Reno) (Bouteloua curtipendula) - 3.6 lbs/AC Buffalograss (Texoka) (Buchloe dactyloides) - 1.6 lbs/AC Bermudagrass (Cynodon dactylon) - 2.4 lbs/AC	Foxtail Millet (Setaria italica) - 34 lbs/AC
COOL SEASON Sept 16th, Oct, Nov, Dec, Jan, Feb, Mar 14th			Tall Fescue (Festuca arundinaceae) - 4.5 lbs/AC Western Wheatgrass (Agropyron smithii) - 5.6 lbs/AC Red Winter Wheat (Triticum aestivum) - 34 lbs/AC Cereal Rye - 34 lbs/AC

SEEDING NOTES:

- When seeding is specified under Item 164, refer to TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown. Materials and construction shall meet specifications.
- Conduct seeding upon completion of each applicable construction stage (dependent upon planting season requirements), without compensation for additional move-ins.
- Place seed AFTER preparing planting area surface. Refer to Surface Preparation detail in this sheet, as well as Topsoil Item 160 and Compost Manufactured Topsoil Item 161 when specified. Apply fertilizer per Item 166 BEFORE seeding, per specifications and this sheet, to help drill the fertilizer into the soil.
- When temporary grasses are well-established and more than 2 inches tall, mow planting area before seeding permanent grasses; mowing for this purpose will be subsidiary. When vegetation is not already well-established, cultivate planting area to a depth as described in Item 164.3, before temporary seeding and before permanent seeding.
- Seed material must be appropriate to the location, soil type and season. Use the seed mix species and pure live seed rates designated in Tables 1-4 of the TxDOT 2014 Standard Specifications* for Item 164, unless otherwise specified.
- All seed shall meet labeling, delivery, analysis, and testing requirements described in Item 164.2.1. Deliver seed in labeled, unopened bags or containers to Engineer prior to planting.
- Uniformly plant seed over the designated planting area, along the contour of slopes, and drill seed to a depth as described in Item 164.3.4.
- Hydroseeding may be allowed, when specified or Engineer concurs.
- Implement and continue Vegetative Watering per the schedule, rate and volume specified under Item 168.

TXDOT REFERENCE MATERIALS:

- "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES" 2014
- "A GUIDANCE TO ROADSIDE VEGETATION ESTABLISHMENT" 2004
- ONLINE TRAINING COURSE: MNT415 REVEGETATION DURING CONSTRUCTION
- DALLAS DISTRICT "VEGETATION ESTABLISHMENT GUIDELINES"

SODDING FOR EROSION CONTROL ITEM 162* BLOCK SOD (BERMUDA) SY

BLOCK OR ROLL SOD	COMMON NAME	BOTANICAL NAME
	Common Bermuda Grass	Cynodon dactylon

SODDING NOTES:

- Refer to Item 162 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Place sod between the average date of the last freeze in the Spring and 6 weeks before the average date of the first freeze in the Fall, per the Texas Almanac for the project area.
- Place sod only AFTER soil surface preparation is complete as detailed in this sheet. Dry soil may require pre-watering.
- Place all sod (blocks or rolls) within 24 hours of delivery to the site, and keep moist from the time it is dug up until it is planted. Sod with dried roots will not be accepted.
- Place sod with joints alternating on each row to prevent all joints from lining up, and place blocks firmly against adjacent blocks. Roll, tamp and trim sod per Item 162.3.
- Place fertilizer promptly AFTER sodding operation is complete in each area.
- Water sod immediately following placement, and continue Vegetative Watering per Item 168.

VEGETATIVE WATERING FOR ESTABLISHING SEED AND SOD ITEM 168* VEGETATIVE WATERING MG

SEASON (Usual Months)	RATE	TIME SCHEDULE	TOTAL WATER ESTIMATE
SPRING & FALL (March, April, May, October)	7,000 gallons/acre per working day	Vegetative watering for seed shall begin on the day after rainfall described below and continue for 60 consecutive working days; vegetative watering for sod shall begin on the day the sod is placed and continue for a minimum of 15 consecutive working days.	420,000 gallons/acre (60 working days)
SUMMER (June, July, August, September)	12,000 gallons/acre per working day		720,000 gallons/acre (60 working days)
WINTER (November through February)	1,000 gallons/acre per working day	Vegetative watering for seed and/or sod shall begin on the day after placement for 15 consecutive working days	15,000 gallons/acre (15 working days)

Notes: Rate and frequency may be adjusted, with the approval of the Engineer, to meet site conditions (especially with sod). For informational purposes only: 1,000 gallons equals 1 MG

VEGETATIVE WATERING NOTES:

- Refer to Item 168 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Use clean water free of industrial waste and other substances harmful to vegetation growth, per Item 168.2.
- Use Vegetative Watering to keep the seed bed moist during germination; not to provide initial watering. After drill seeding, postpone watering operations until site receives at least 1/2-inch of natural rainfall in a single day. Delay watering operations for warm season grasses until soil temperature exceeds 70 degrees F.
- For sod, water immediately.
- All water distribution equipment shall be furnished and operated to provide water at a uniform and controllable rate. Use a metering device on all watering equipment.
- Evenly distribute water over entire area designated for seeding and/or sodding, using even spray patterns that do not disturb seed bed and/or dislodge seed from seed bed.
- Do not water between the hours of 12:00 p.m. and 6:00 p.m. when daytime temperatures exceed 95 degrees F.
- After initial establishment period, continue intermittent watering of newly established seed or sod at a rate of approximately 1-inch water/week, during summer months until end of contract.
- If 1/4-inch or more of rainfall occurs on site on any given working day, no vegetative watering will be needed on that working day. (Note: 1/4-inch rain equals 7,000 gallons of water per acre.)
- Should the Contractor fail to apply the specified amount of water within the time allowed, any seed or sod in poor condition shall be replaced, fertilized, and watered at Contractor's expense.

ROADSIDE MOWING ITEM 730* PROJECT MAINTENANCE AC

MOWING NOTES:

- During project construction, once seed is established, use mowing to promote permanent grasses by mowing any remaining temporary grasses.
- Also mow established turf and ROW grasses in designated areas of project limits as specified or directed by Engineer.
- Remove litter and debris prior to mowing.
- Do not mow on wet ground when soil rutting can occur.
- Hand-trim around obstructions and stormwater control devices as needed.
- Maintain paved surfaces free of tracked soils and clipped vegetation.

SEQUENCE OF WORK:

- CULTIVATE SURFACE SOIL.
- PREPARE / PLACE TOPSOIL, OR
- PREPARE / PLACE COMPOST MANUFACTURED TOPSOIL.
- APPLY FERTILIZER AND THEN PLACE SEEDING, OR
- PLACE SOD AND THEN APPLY FERTILIZER.
- CONDUCT VEGETATIVE WATERING.
- CONDUCT ROADSIDE MOWING, AS DIRECTED.



VEGETATION ESTABLISHMENT SHEET
(DALLAS DISTRICT)


TEMPLATE REVISION DATE: 02/21/19

DESIGN CPB	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. (See Title Sheet)		HIGHWAY NO. FM 545
GRAPHICS XXX	STATE TEXAS	DISTRICT DALLAS	COUNTY COLLIN	SHEET NO. 203
CHECK XXX	CONTROL 1012	SECTION 02	JOB 042, ETC.	

DATE

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

LEVELS DISPLAYED	
1	




Sign Dimensions

36" X 36"

- Letters - White
- Numbers - White
- Border - White
- Background - Blue

SW3P SIGN

TxDOT & Contractor
Construction Site Note
(CSN)



GENERAL NOTES:

1. The alphabets and lateral spacing between letters and numerals shall conform with the "Texas Manual on Uniform Traffic Control Devices for Streets and Highways", (TMUTCD) latest edition, and the "Compliant Work Zone Traffic Control Devices List". Lateral spacing of text shall provide a balanced appearance. All materials shall conform to Department Specifications.
2. Legend and border may be applied by reverse screening process with transparent colored ink, cut-out white reflective sheeting applied to colored background or combination thereof. Background shall be reflective sheeting Type C.
3. CSN Sheets will be laminated and attached to the sign with an adhesive. Ensure sheets remain dry. (See Figure 1).
4. SW3P Signs should be placed just inside the ROW line at the project limits at a readable height. It may be placed perpendicular or parallel to ROW line. If the sign cannot be placed outside the clear zone, it will be mounted per TMUTCD requirements.
5. Final location of the signs will be as approved by the Engineer.




Figure 1

DEPARTMENT MATERIAL SPECIFICATIONS	
PLYWOOD SIGN BLANKS	DMS-7100
FLAT SURFACE REFLECTIVE SHEETING	DMS-8300
VINYL NON-REFLECTIVE DECAL SHEETING	DMS-8320

COLOR	USAGE	REFLECTIVE SHEETING OR OTHER MATERIAL
BLUE	BACKGROUND	TYPE C (FLUORESCENT PRISMATIC)
WHITE	LEGEND & BORDERS	VINYL NON-REFLECTIVE DECAL SHEETING


Texas Department of Transportation
DALLAS DISTRICT STANDARD

SW3P SIGN SHEET

FILE#	DW: I&DOI	CK:	DW:	CK:
©TxDOT 2016	DISTRICT	FEDERAL AID PROJECT	SHEET	
	18	SEE TITLE SHEET	204	
REVISION DATE: 10-16-15	COUNTY	CONTROL	SECT	JOB
	COLLIN	1012	02	042, ETC. FM 545

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



TRENCH SIDE VIEW DETAIL


FABRIC TOE-IN IS TO RUN DOWN THE TRENCH AND ALONG THE BOTTOM OF THE TRENCH

EMBED POSTS 18" MIN. (OR ANCHOR IF IN ROCK)

4' MINIMUM STEEL POST SPACED AT 6'. (STEEL POST ONLY PERMITTED)


ATTACH THE WIRE MESH AND FABRIC ON END POSTS USING 4 EVENLY SPACED T-CLIPS OR SEWN VERTICAL POCKETS.

BACKFILL AND HAND TAMP




HINGE JOINT KNOT WOVEN MESH DETAIL

GALVANIZED HINGE JOINT KNOT WOVEN MESH (12.5 GA. SWG MIN.) REQUIRES A MINIMUM OF FIVE HORIZONTAL WIRES SPACED AT A MAXIMUM OF 12 INCHES APART AND ALL VERTICAL WIRES SPACED AT A MAXIMUM OF 12 INCHES APART.



FABRIC TOE-IN (ALONG BOTTOM OF THE TRENCH)



J-HOOK END OF FENCE DETAIL (TOP VIEW)

TRENCH IS TO STAY 6 IN DEEP AND 6 IN WIDE WITH FABRIC TOE-IN TO MATCH TRENCH DETAIL.

J-HOOK APPLIES AT DRIVEWAY BREAKS, ROADWAY BREAKS, AND AT ANY LOCATION AS DIRECTED BY THE ENGINEER.

GENERAL NOTES

1. REMOVE ALL ROOTS AND OTHER OBSTRUCTIONS FROM THE TRENCH BEFORE FABRIC PLACEMENT.
2. AMPHIBIAN AND REPTILE EXCLUSION FENCE MUST BE CHECKED DAILY, INCLUDING DAYS DURING RAINFALL SHUTDOWN PERIODS.
3. ANY DAMAGE TO FENCE, INCLUDING SMALL HOLES, MUST BE REPAIRED THE DAY IT IS OBSERVED BEFORE DARK.
4. SMALL HOLES (WITH THE ENGINEER'S DISCRETION) MAY BE REPAIRED WITH TAPE AS DIRECTED BY THE ENGINEER.
5. AS DIRECTED BY THE ENGINEER, SECTIONS OF FENCE WHERE THE DAMAGE IS DEEMED DETRIMENTAL TO THE FENCE WILL BE REPLACED RATHER THAN REPAIRED.
6. A MINIMUM OF 2' SHOULD BE OVERLAPPED WHEN JOINING FABRIC SECTIONS.
7. PAINT "AREF" OR "TEF" ON THE FABRIC IN BRIGHT COLOR EVERY 50' AND AT BREAKS.
8. REMOVE SEDIMENT, VEGETATION, OR OTHER DEBRIS TO MAINTAIN THE 24" AREF CLEARANCE.
9. FOR PAYMENT AND ADDITIONAL INFORMATION FOR AREF, SEE SPEC. 5116 (AMPHIBIAN AND REPTILE EXCLUSION FENCE).

LEGEND

- AREF — AMPHIBIAN AND REPTILE EXCLUSION FENCE
- AMPHIBIAN AND REPTILE DIRECTION OF TRAVEL

Texas Department of Transportation *Design Division Standard*

AMPHIBIAN AND REPTILE EXCLUSION FENCE

AREF-21

FILE: aref21.dgn	DN: TJ	CK: KM	DW: SS	CK: AG
© TxDOT: FEBRUARY 2021	CONT	SECT	JOB	HIGHWAY
REVISIONS	1012	02	042, ETC.	FM 545
DIST	COUNTY		SHEET NO.	
DAL	COLLIN		205	