

**INDEX OF SHEETS**

SEE SHEET NO 2

**VOLUME 2 OF 2  
CONTRACT CSJ 0495-08-136**

**STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT**

STATE AID PROJECT NO. C 495-10-94

**HARRISON COUNTY**


NET LENGTH OF PROJECT= 41,500 FT. = 7.859 MI.

LIMITS: FROM: 0.5 MI. W. OF US 80  
TO: LOUISIANA STATE LINE

FOR THE CONSTRUCTION OF AN OVERLAY OF AN EXISTING 4-LANE INTERSTATE  
CONSISTING OF CONCRETE PAVEMENT REPAIR, FLEXIBLE PAVEMENT REPAIR, PLANING, ACP SURFACE,  
MBGF, AND PAVEMENT MARKINGS

THE CONTRACTOR SHALL MAKE HIS OWN  
INVESTIGATIONS AND ARRANGEMENTS FOR  
DELIVERY OF MATERIALS.


REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH  
THE CURRENT BARRICADE AND CONSTRUCTION OR BC  
SHEETS AND THE "TEXAS MANUAL ON UNIFORM  
TRAFFIC CONTROL DEVICES".



BEGIN PROJECT  
CSJ: 0495-10-094  
STA. 2085+00.00  
REF MRK: 628+0.766  
=STA: 2085+00.00  
CPM: 495-10-158

END PROJECT  
CSJ: 0495-10-094  
STA: 2500+00.00  
REF MRK: 636+0.118  
=STA: 2500+00.00  
CPM: 495-10-158

EXCEPTIONS: NONE  
EQUATIONS: NONE  
RAILROAD CROSSINGS: NONE



FEDERAL AID PROJECT NO.			
C 495-10-94			
CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		1

DESIGN SPEED = 75 MPH  
A. D. T. (2020) = 32,745  
A. D. T. (2040) = 65,490

FINAL PLANS

LETTING DATE: \_\_\_\_\_  
DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_  
DATE WORK WAS COMPLETED & ACCEPTED: \_\_\_\_\_  
FINAL CONTRACT COST: \$ \_\_\_\_\_  
CONTRACTOR : \_\_\_\_\_  
CONTRACTOR ADDRESS: \_\_\_\_\_  
LIST OF APPROVED FIELD CHANGES: \_\_\_\_\_

THE CONSTRUCTION WORK WAS PERFORMED IN SUBSTANTIAL  
COMPLIANCE WITH THE CONTRACT.

\_\_\_\_\_  
P. E.

\_\_\_\_\_  
DATE



RECOMMENDED FOR LETTING: 9/17/2021

DocuSigned by:  
*Deanne Simmons, P.E.*  
929084EF4AF345A...  
DISTRICT DIRECTOR OF TRANSPORTATION  
PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 9/17/2021

DocuSigned by:  
*Joe A. Williams, P.E.*  
0EAA5DC25F0F45E...  
DISTRICT ENGINEER

DATE: 9/12/2021 2:06 PM  
FILE: p:\dot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094\4 - Design\Master Design Files\Plans\TITLE SHEET.dgn

COUNTY: HARRISON PROJ. NO. \_\_\_\_\_  
HWY. NO. IH 20 LETTING DATE \_\_\_\_\_  
DATE ACCEPTED \_\_\_\_\_


SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,  
NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS,  
SHALL GOVERN ON THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS  
FOR ALL STATE CONSTRUCTION PROJECTS. (SP 000---008)

<u>DESCRIPTION</u>	
<u>GENERAL</u>	
1	TITLE SHEET
2	INDEX OF SHEETS
3-8	TYPICAL SECTIONS
9, 9A-9D	GENERAL NOTES
10-14	MISCELLANEOUS SUMMARIES
<u>TRAFFIC CONTROL PLAN</u>	
# 15-26	BC (1)-21 THRU BC (12)-21
# 27	TCP (ATL-61)-14 (DIST STANDARD)
# 28	TCP(3-2)-13
# 29	TCP(3-3)-14
# 30	TCP(5-1)-18
# 31	TCP(6-1)-12
# 32	TCP(6-2)-12
# 33	TCP(6-3)-12
# 34	TCP(6-4)-12
# 35	TCP(6-5)-12
# 36	RS(1)-13
# 37	WZ(STPM)-13
# 38	WZ(UL)-13
39	TREATMENT FOR VARIOUS EDGE CONDITIONS
39A	TCP DETAILS
39B	TCP CULVERT REPLACEMENT
39C	CRASH CUSHION SUMMARY SHEET
# 39D	BARRIERGUARD-19
# 39E	HIGHWAYGUARD-21
# 39F	HV2 BARRIER-21
# 39G	ZONEGUARD-19
# 39H-39I	OMITTED
# 39J	OMITTED
# 39K-39L	SSCB(2)-10
# 39M	SSCB(5)-10
# 39N	ABSORB(M)-19
# 39O	SLED-19

<u>ROADWAY DETAILS AND STANDARDS</u>	
40-47	MBGF LAYOUT
48	MISCELLANEOUS DETAILS
48A-48B	ROADWAY DETAILS
48C	CULVERT LAYOUT
# 49	GF(31)-19
# 50	GF(31)DAT-19
# 51	GF(31)MS-19
# 52	SGT(10S)31-16
# 53	SGT(11S)31-18
# 54	SGT(12S)31-18
# 55	SGT(13S)31-18
# 56	SGT(14W)31-18
# 57	SGT(15)31-20
# 58	TE(HMAC)-11
# 58A-58C	SETP-FW-0

<u>TRAFFIC STANDARDS</u>	
# 59	D&OM(1)-20
# 60	D&OM(2)-20
# 61	D&OM(3)-20
# 62	D&OM(4)-20
# 63	D&OM(6)-20
# 64	D&OM(VIA)-20
# 65-67	FPM(1)-12 THRU FPM(3)-12
# 68	FPM(5)-19

<u>ENVIRONMENTAL ISSUES</u>	
69	SWP3
70	EPIC



*Glenn R. Yowell, P.E.*  
 10/5/2021



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A '#' ON THIS SHEET HAVE BEEN ISSUED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AND ARE APPLICABLE TO THIS PROJECT.

### INDEX OF SHEETS

©2021 Texas Department of Transportation



FHWA TEXAS DIVISION		FEDERAL AID PROJECT NO. C495-10-94		SHEET NO. 2
STATE	DISTRICT	COUNTY		
TEXAS	ATL	HARRISON		
CONTROL	SECTION	JOB	HIGHWAY NO.	
0495	10	094	1H 20	

DATE: 10/5/2021 10:37:09 AM  
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\5x000 TYPICAL SECTIONS.





EXISTING SECTION

STA. 2292+50 TO STA. 2500+00



EXISTING SECTION

STA. 2085+00 TO STA. 2292+50





TYPICAL SECTIONS

SHEET 1 OF 6


CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		3

NOT TO SCALE

DATE: 10/5/2021 10:37:49 AM  
 FILE: pw:\xtdot\projectwiseonline.com:TXDOT15\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\0000 TYPICAL SECTIONS.



BLADE MATERIAL FROM EDGE OF PAVEMENT PRIOR TO PLANING ACP. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO ITEM "BACKFILL (TY B)".





**PROPOSED SECTION**

(WESTBOUND LANES)

STA. 2292+50 TO STA. 2500+00

PLANE 4' ACP SHOULDER FROM 2" - 0" AT THE EDGE OF PAVEMENT TO CHANGE SHOULDER FROM +3% TO -2% TO MATCH MAINLANES. SEE QUANTITY SUMMARIES FOR LOCATIONS AND MISCELLANEOUS DETAILS FOR MORE INFORMATION.




BLADE MATERIAL FROM EDGE OF PAVEMENT PRIOR TO PLANING ACP. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO ITEM "BACKFILL (TY B)".

**PROPOSED SECTION**

(WESTBOUND LANES)

STA. 2085+00 TO STA. 2292+50




*Glenn R. Yowell, P.E.*

10/5/2021

**TYPICAL SECTIONS**


SHEET 2 OF 6





CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	4	

**NOT TO SCALE**



DATE: 10/5/2021 10:38:26 AM  
 FILE: \\atdot\projectwiseonline.com\TXDOT15\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\000 TYPICAL SECTIONS.



PROPOSED SECTION  
 (EASTBOUND LANES)  
 STA. 2292+50 TO STA. 2500+00



PROPOSED SECTION  
 (EASTBOUND LANES)  
 STA. 2085+00 TO STA. 2292+50



*Glenn R. Yowell, P.E.*

10/5/2021


TYPICAL SECTIONS

NOT TO SCALE

SHEET 3 OF 6


CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	5	

DATE: 10/5/2021 10:39:03 AM  
 FILE: pw:\dot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\000 TYPICAL SECTIONS.




**PROPOSED EASTBOUND IH 20 EXIT RAMP**

US 80 - STA. 0+00 TO STA. 14+25  
 FM 134 - STA. 0+00 TO STA. 12+29  
 SP 156 - STA. 0+00 TO STA. 18+73




**PROPOSED EASTBOUND IH 20 ENTRANCE RAMP**

US 80 - STA. 20+40 TO STA. 33+90  
 FM 134 - STA. 10+82 TO STA. 0+00  
 SP 156 - STA. 10+65 TO STA. 0+00




**EXISTING EASTBOUND IH 20 EXIT RAMP**

US 80 - STA. 0+00 TO STA. 14+25  
 FM 134 - STA. 0+00 TO STA. 12+29  
 SP 156 - STA. 0+00 TO STA. 18+73



**EXISTING EASTBOUND IH 20 ENTRANCE RAMP**

US 80 - STA. 20+40 TO STA. 33+90  
 FM 134 - STA. 10+82 TO STA. 0+00  
 SP 156 - STA. 10+65 TO STA. 0+00




**TYPICAL SECTIONS**

SHEET 4 OF 6

		© 2021	
CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		6


**NOT TO SCALE**

DATE: 10/5/2021 10:39:44 AM  
 FILE: pw:\dot\project\wiseonline.com:TXDOT15\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\0000 TYPICAL SECTIONS.




**PROPOSED WESTBOUND IH 20 EXIT RAMP**

US 80 - STA. 0+00 TO STA. 12+70  
 FM 134 - STA. 0+00 TO STA. 8+76  
 SP 156 - STA. 0+00 TO STA. 10+65




**PROPOSED WESTBOUND IH 20 ENTRANCE RAMP**

US 80 - STA. 0+00 TO STA. 13+35  
 FM 134 - STA. 0+00 TO STA. 11+10  
 SP 156 - STA. 0+00 TO STA. 19+55




**EXISTING WESTBOUND IH 20 EXIT RAMP**

US 80 - STA. 0+00 TO STA. 12+70  
 FM 134 - STA. 0+00 TO STA. 8+76  
 SP 156 - STA. 0+00 TO STA. 10+65



**EXISTING WESTBOUND IH 20 ENTRANCE RAMP**

US 80 - STA. 0+00 TO STA. 13+35  
 FM 134 - STA. 0+00 TO STA. 11+10  
 SP 156 - STA. 0+00 TO STA. 19+55



*Glenn R. Yowell, P.E.*  
 10/5/2021

**TYPICAL SECTIONS**


SHEET 5 OF 6

		© 2021	
		CONT	SECT
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		7

**NOT TO SCALE**

DATE: 10/5/2021 10:40:13 AM  
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\000 TYPICAL SECTIONS

REPLACE SHOULDER MATERIAL WITH CONCRETE AGGR. GR 8 AND ACP TO TOP OF CONCRETE PAVEMENT IN ACCORDANCE WITH ITEM 361. PLACE ACP IN 2 APPROX. EQUAL COURSES AND TAMP EACH COURSE. ACP MAY BE OBTAINED FROM COMMERCIAL SOURCE.





COMPLETED PAVEMENT REPAIR  
HALF SECTION

NOTE: REMOVAL AND REPLACEMENT OF THE ACP OVERLAY WILL BE CONSIDERED SUBSIDIARY TO ITEM 361.

ACP PLACED ON REPAIR AREAS SHALL BE D-GR HMA TY-D SAC-A PG76-22 IN ACCORDANCE WITH ITEM 341.

REPLACE OR RESTORE ANY EXISTING EDGE DRAIN DAMAGED BY THE CONTRACTOR'S OPERATIONS. REPLACEMENT OF EXISTING EDGE DRAIN WILL BE CONSIDERED SUBSIDIARY TO ITEM 361.

REPAIR WILL BE DONE AT VARIOUS LOCATIONS THROUGHOUT THE PROJECT AS DIRECTED BY THE ENGINEER.




TYPICAL BREAKOUT FOR REPAIR  
HALF SECTION

  
 Glenn R. Yowell, P.E.  
 10/5/2021

TYPICAL SECTIONS

SHEET 6 OF 6

© 2021



CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		8

NOT TO SCALE



**GENERAL NOTES****GENERAL:**

Contractor questions on this project are to be addressed to the following individuals:

Wendy Starkes, P. E. – Area Engineer  
 Wendy.Starkes@txdot.gov  
 Jacob Vise, P. E. – Assistant Area Engineer  
 Jacob.Vise@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

**ITEM 5:**

Place construction points, stakes, and marks at intervals of no more than 100 ft., or as directed. Place stakes and marks so as not to interfere with normal maintenance operations.

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

**ITEM 7:**

This project is considered a maintenance activity and is exempt from the Construction General Permit (CGP) coverage.

No significant traffic generator events exist.

**ITEM 8:**

Prior to any other work on the project starting, all work involving the culvert replacement shall be completed and traffic restored to original lane configuration.

Work on project 0495-10-094 (Volume 2 of 2) West Bound shall be completed through the placement of the SMA before work 0495-08-136, ETC (Volume 1 of 2) is to begin, unless otherwise directed by the Engineer.

Provide progress schedules meeting the requirements of Section 8.5.2 in 2014 Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges.

The road user cost liquidated damages are \$ 8,028 per day.

Working days will be charged in accordance with Section 8.3.1.6, "Other," as defined below:

Working days will be charged Monday through Thursday, excluding national or state holidays, if weather or other conditions permit the performance of the principal unit of work underway, as determined by the Engineer, for a continuous period of at least seven (7) hours between 7:00 a.m. and 6:00 p.m. Work on Fridays, Saturdays, Sundays, and national or state holidays will not be permitted without written permission of the Engineer.

**ITEM 9:**

When uniformed off duty police officers and squad cars are used for traffic control, provide documentation such as payroll, log sheets with signatures and badge number, or invoices from the government entity providing the officers for reimbursement in accordance with Article 9.7, "Payment for Extra Work and Force Account Method." Complete the weekly tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Reimbursement will not be made for coordination fees charged by the police department.

**ITEM 134:**

Provide material meeting requirements of Article 160.2, "Materials" for Type A Backfill.

Apply an emulsified asphalt treatment, consisting of SS-1 asphalt, at a rate of 0.3 gal. per sq. yd. to Type A and Type B Backfill.

Apply fertilizer (13-13-13) at a rate of 1 lb. per 10 sq. yd. to Type A Backfill.

Place RAP generated during the project as Type B Backfill at underpasses, the former rest area driveways, emergency crossovers, and other locations as directed.

Mow tall growing vegetation as directed, to provide optimum growing conditions for temporary or permanent seeded areas in accordance with Item 730 "Roadside Mowing" except for measurement and payment. This work will be subsidiary to pertinent bid items.

**ITEM 164:**

**PERMANENT PLANTING MIXTURE**

Species and Rates  
(lb. PLS/ac.)

(Season: February 1 to May 15)

Green Sprangletop	0.4
Bermudagrass	2.4
Sand Lovegrass	1.0
Lance-Leaf Coreopsis	1.25

(Season: September 1 to November 30)

Bermuda (Unhulled)	12
Crimson Clover	10

**TEMPORARY SEEDING FOR EROSION CONTROL**

Warm Season

(Season: May 15 to August 31)

Bermudagrass	6
Foxtail Millet	34

Cool Season

(Season: September 1 to November 30)

Tall Fescue	4.5
Oats	24
Wheat	34

Adjust the seeding mixture and rates if directed.

Inoculate crimson clover seed with a legume inoculant. Sow inoculated seed dry, with either hand operated or mechanical equipment, after the fertilizer is placed.

Do not use Bahiagrass.

Use broadcast seeding for temporary erosion control, when and as directed. This will not be paid for directly but is subsidiary to the various bid items.

Use additional temporary seeding if permanent seeding is placed outside the optimum growing season shown for this item, if directed.

**ITEM 166:**

When seeding between September 1 and January 1, place one-half of the amount of fertilizer specified for seeding with the seeds and place the remainder the following spring unless otherwise directed. When seeding is placed between January 1 and June 1, place one-half the amount of fertilizer specified for seeding with the seeds and place the remainder 30 days later unless otherwise directed.

**ITEM 301:**

Add hydrated lime to the aggregate by the following method only: mix in an approved pug mill mixer with damp aggregate containing water at least 2% above saturated surface dry conditions.

**ITEM 320:**

Provide a Material Transfer Device (MTD) with remixing capability.

**ITEM 346:**

Use field sand with a sand equivalent value of at least 35 when sampled and tested in accordance with TEX-203-F.

The Plant is the designated aggregate sampling location, unless otherwise approved by the Engineer.

Construct longitudinal joints in the surface course as shown in the plans. Construct longitudinal joints in all other courses by tapering the bituminous mat as shown in the plans or providing a 6 in. minimum offset from lift to lift. Extend the tapered portion of the mat beyond the normal lane width. Construct the tapered portion of the mat using an approved strike-off device that will provide a uniform slope and will not restrict the main screed. Apply tack coat to the in-place taper before the adjacent mat is placed. Final density requirements for the entire pavement, including the taper area will not change. Compaction of the initial taper section will be required to be as near to final density as possible. Use a small static roller (approximately 200 lbs) located immediately behind the paver for pre-compaction of the notched wedge joint.

The Engineer will determine the correction when the total thickness of the ACP at any location, is deficient by more than 1/4 in. Correct by adjusting the profile grade or removing and replacing the pavement structure to the correct grade, lines and thickness as shown on the plans. Correction

of defective work will be in accordance with Section 5.3.2, "Correction of Defective or Unauthorized Work".

Construct longitudinal joints so that the hot side overlaps the cold side by 0.5 inch minimum at the joint.

Furnish clean 5 gallon plastic buckets with lids and wire handles for sampling, transporting, and shipping aggregate and base to the District Lab.

For hotmix items, in place of typical tack material shown in Table 18 under Item 300, use a tracking resistant asphalt interlayer (TRAIL) material as a tack coat. Approved TRAIL products are found on TxDOT's Material Producer List under Asphalt Interlayer (Tracking Resistant) through <http://www.txdot.gov/business/resources/materials.html>.

There should be little to no evidence of tracking or pickup of the tack coat on the wheels of the equipment as determined by the Engineer. Use approved release agents or misters on equipment tires as necessary.

**ITEM 351:**

Use SP (TY-C) or SP (TY-D) (PG70-22) for mainlane repairs. No binder substitution will be allowed.

**ITEM 354:**

The Contractor shall retain ownership of material removed under this Item.

**ITEM 361:**

The Engineer will determine if concrete pavement repair is required. If concrete pavement repair is not required, the area will be measured and paid for in accordance with Item 351 "Flexible Pavement Structure Repair".

Use SS-1 asphalt for curing paving repairs.

Where repairs involve existing terminal anchor lugs, carefully remove the concrete pavement from the lugs and leave the terminal anchor reinforcing steel intact. Clean and straighten the terminal anchor steel as necessary and tie to the new mat of reinforcing steel of the pavement patch. At bridge ends or other locations where repair areas involve existing expansion joints and sleeper slabs, furnish and install premolded expansion board, roofing felt and any other items necessary to restore the expansion joint to its original function. Payment for this work is subsidiary to this bid item.

Provide High Early Strength (HES) concrete, unless otherwise approved by the Engineer.

Demonstrate, through simulated job conditions that the bond strength of the epoxy-grouted tiebar meets pullout strength of at least  $\frac{3}{4}$  of the yield strength of the tiebar when tested in accordance with ASTM E 488 within 3hr. after grouting.

Air-entrainment is not required for class P or HES concrete.

Do not bend tie bars.

**ITEM 421:**

The Department will furnish and maintain concrete compressive strength testing equipment.

Elevate beam tanks as directed.

The sand equivalent value will be at least 90.

Use grade 2 or 3 aggregate for concrete pavement unless otherwise directed.

When a curing tank is provided the following information must be provided. All items must be clearly legible and visible from all directions at all times.

- Post and maintain the message "Caution Lime Solution, Eye and Skin Irritant".
- Provide a copy of the SDS sheet for the lime in use.
- Provide the personal protective equipment (PPE) listed below for Department use only: Face shield, a pair of chemical gloves at least 18 inches in length and a chemical apron. Store the SDS sheet and PPE in a clean dry location adjacent to the curing tank.
- Provide an eye wash station capable of providing a 15 minute flush as required by the United States Occupational Safety and Health Administration (OSHA). The eye wash station shall be located within ten feet of the curing tank. When a tank heater is required, ensure that all electrical wiring, receptacles, and devices meet National Electrical Code and Underwriters Laboratories Inc. requirements.

**ITEM 432:**

Provide  $\frac{1}{2}$ " expansion joint material with an area equal to the area of contact between the two concrete surfaces. The joint material will be visually inspected for approval.

**ITEM 502:**

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These

enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

As approved by the Engineer, provide uniformed off duty police officers and squad cars during IH 20 lane closures, nighttime work, or other situations that indicate a need for additional traffic control to protect the traveling public or the construction workforce.

At the time construction activity obliterates the center stripe on the roadway, erect a "No Center Line" sign (CW8-12) (36"x36") and a "Do Not Pass" sign (R4-1) (24"x30") at each end of the work area. Erect additional signs every 1/2 mile within the work area and at other locations as directed. Locate the CW8-12 signs in such a manner that drivers can read the sign and immediately see the change from marked center stripe to no center stripe. Supplement the CW8-12 sign with the "Next XX Miles" sign (CW7-3aP) (30"x24") mounted below it. The CW8-12 signs are to remain until standard pavement markings are placed. The R4-1 signs are to remain until the permanent pavement markings are placed.

Length of lane closures will be as directed based on the demonstrated ability to prosecute the work within the closed section.

Multiple lane closures for pavement repair may be set up in the same lane based on the demonstrated ability to prosecute the work safely with no adverse conditions to traffic.

Plan and coordinate ACP placements and planing operations so that traffic lanes will not be left with open longitudinal joints and traffic shall be restored to original two lanes by the end of the workday.

Restrict the movement of equipment across traffic lanes to an absolute minimum.

Use strobe lights or rotating beacons on all motorized equipment, operating on or adjacent to the road surface.

Do not leave equipment within 30 feet of the travel way. Equipment and/or obstructions within 30 feet of the travel way will be removed or clearly marked by warning lights and barricades, as directed.

The Contractor's responsible person (CRP) will be responsible for ensuring that the signs and traffic control devices are in place and functioning properly.

The CRP will inspect and ensure any deficiencies are corrected each and every day throughout the duration of this contract. Notify the Engineer in writing of the name, address, and telephone number of this employee or these employees.

Begin ACP laydown operations after the planing operations as soon as it is feasible. At no time will the length of exposed planed pavement exceed 2 miles beyond the ACP laydown operation. The distance that the planing operation is ahead of the ACP laydown operation may be adjusted by the Engineer.

The Traffic Control Plan for this contract consists of the installation and maintenance of warning signs and or other traffic control devices shown in the plans, specification data which may be included in the general notes, applicable provisions of the Texas Manual on Uniform Traffic Control Devices (TMUTCD), traffic control plan sheets included in the plans, standard BC sheets and Item 502 of the standard specifications.

The traffic control plan sheets when shown in the plans are for handling traffic through the work area. The signing arrangement and spacing shown may be varied as necessary to fit field conditions; however, any proposed changes in the traffic control plan must be approved by the Engineer prior to implementation.

Notify inspector prior to any planned lane closures. Lane closures must be entered in the HCR (Highway Condition Report) 48 hours prior to beginning work.

**ITEM 506:**

Place erosion or pollution control measures deemed necessary by the Engineer. Work performed for which there is no applicable pay items in the contract will be reimbursed in accordance with Article 9.7, "Payment for Extra Work and Force Account Method".

**ITEM 533:**

Use option 2 on TxDOT standard RS(1)-13, with a 16" minimum length.

**ITEM 540:**

Furnish round timber posts unless otherwise shown.

**ITEM 544:**

Place sufficient dry batch concrete mix in holes to ensure minimum of 2 inch embedment of tubes and posts.

**ITEM 542:**

Dispose of all rail elements, fittings, and posts off the right-of-way.

**ITEM 543:**

Any existing cable barrier damaged by the Contractor's operations shall be replaced at the Contractor's expense.

**ITEM 585:**

For SMA placement use surface test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with this Item. For PFC (CSJ 0495-08-136, ETC) use surface test Type A.

**ITEM 658:**

Install only round posts meeting the requirements of DMS-4400 or as directed.

**ITEM 662:**

Non-removable pavement markings may be paint and beads.

**ITEM 6149:**

Place pavement markings within 14 days after completion of the final surface.

Mark the lateral locations of pavement markings with pilot lines. Use outside edge of pavement as the reference, measuring distance to edge of concrete pavement every 250 feet prior to placement of the SMA surface coarse. Ensure that edge lines are applied over concrete pavement. Obtain approval of the location and alignment of the pilot lines before application of permanent markings.

A mobile unit will be required to take reflectivity readings, readings will be taken on all lines in both directions. The mobile reflectivity readings will not be paid for separately but will be subsidiary to this bid item. Strict compliance with report output will be exercised in accordance to this general note. Information for each road must be together in the same file on a disk. Table of contents as shown in section 3E Video DVD will be easily identified as described and visible on the cover of the DVD in order to be able to identify the contents of the DVD without the use of the computer. An internet site will also be required that contains those reports and information. The internet site will contain a customer interactive report that generates a color coded map where the user can verify passing and failing sections of roadway. The color coded map should match the color coded graphs generated by the data in the computer. The graphs should have a color coded portion or shaded area representing failing and passing. The map should be standard Google earth maps or equal. The internet web site reports need to be in

numerical order by reference number, concurrent with direction, labeled and separated by color, and include the posting date. The format will require prior acceptance by the Engineer.

Use a mobile retroreflectometer that is prequalified at the Texas A&M Transportation Institute test facility. The prequalification is at the contractor's expense.

The required values of wet and dry readings will be strictly measured within this contract as per manufacturer's recommendations.

**ITEM 6185:**

The shadow vehicle with truck mounted attenuator (TMA) will not be optional but will be required as shown on the appropriate traffic control plan sheets.

A total of one (1) shadow vehicle with TMA will be required for work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.

A total of two (2) shadow vehicles with TMA will be required for Pavement Marking Operations.

**BASIS OF ESTIMATE**

ITEM	DESCRIPTION	RATE	UNIT	QUANTITY
*166	Fertilizer (13-13-13)	300 lb./5,000 sq. yd. of Seed	ton	2

\*FOR CONTRACTOR'S INFORMATION ONLY.


DATE: 10/6/2021 9:53:49 AM  
 FILE: pw:\dot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\SUMMARY SUMMARY.dgn

SUMMARY OF ROADWAY ITEMS													
LOCATION	②	134 6001	134 6002	① 164 6054	168 6001	346 6014	346 6058	③ 351 6002	354 6045	③ 361 6002	354 6005		
	EMULS ASPH (EROSN CONT)(SS-1)	BACKFILL (TY A)	BACKFILL (TY B)	BOND FBR MTRX SEED (PERM)(RURAL) (SAND)	VEGETATIVE WATERING	STONE-MTRX- ASPH SMA-D SAC-A PG76-22	TACK COAT	FLEXIBLE PAVEMENT STRUCTURE REPAIR(6")	PLANE ASPH CONC PAV (2")	FULL - DEPTH REPAIR CRCP (8")	PLANE ASPH CONC PAV (2 TO 4")		
	GAL	STA	STA	SY	MG	TON	GAL	SY	SY	SY	SY		
	0.3 GAL/SY	-	-	-	80MG / 5000SY	220 LB/SY	0.10 GAL/SY	-	-	-	-		
<b>WESTBOUND LANES ONLY</b>	-	-	-	-	-	-	-	100	-	108	-		
FROM STA: 2085+00 TO 2500+00	8,302	415	415	27,953	444	19,275	17,523		-		175,224	-	
<b>US 80 OVERPASS</b>	-	-	-	-	-	-	-		-		-	-	
EXIT RAMP	254	13	13	847	14	373	339		-		3,387	-	
ENTRANCE RAMP	267	14	14	890	15	392	356		-		3,560	-	
<b>FM 134 OVERPASS</b>	-	-	-	-	-	-	-		-		-	-	
EXIT RAMP	176	9	9	584	10	257	234		-		2,336	-	
ENTRANCE RAMP	222	12	12	740	12	326	296		-		2,960	-	
<b>SP 156 OVERPASS</b>	-	-	-	-	-	-	-		-		-	-	
EXIT RAMP	213	11	11	710	12	312	284		-		2,840	-	
ENTRANCE RAMP	391	20	20	1,304	21	574	522		-		5,214	-	
<b>SMA TRANS. FOR PFC OVERLAY</b>	-	-	-	-	-	-	-		-		-	-	
STA. 2087+64 TO STA. 2089+14	-	-	-	-	-	-	-		-		-	-	634
STA. 2089+14 TO STA. 2091+50	-	-	-	-	-	-	-		-		-	-	997
STA. 2091+50 TO STA. 2093+00	-	-	-	-	-	-	-		-		-	-	634
STA. 2429+79 TO STA. 2431+29	-	-	-	-	-	-	-		-		-	-	634
STA. 2431+29 TO STA. 2449+50	-	-	-	-	-	-	-	-	-	-	7,689		
STA. 2449+50 TO STA. 2451+00	-	-	-	-	-	-	-	-	-	-	634		
<b>SHEET 1 SUBTOTALS</b>	<b>9,825</b>	<b>494</b>	<b>494</b>	<b>33,028</b>	<b>528</b>	<b>21,509</b>	<b>19,554</b>	<b>100</b>	<b>195,521</b>	<b>108</b>	<b>11,222</b>		

- ① INCLUDES QUANTITIES FOR FOR MBGF APPROACH
- ② FOR CONTRACTOR INFORMATION ONLY
- ③ SEE ADDITIONAL QUANTITIES ELSEWHERE IN PLANS

**MISCELLANEOUS  
SUMMARIES**

SHEET 1 OF 5



© 2021

CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		10


DATE: 10/6/2021 9:54:40 AM  
 FILE: pw:\dot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\SUMMARY SUMMARIES.dgn

SUMMARY OF ROADWAY ITEMS												
LOCATION	②	134 6001	134 6002	① 164 6054	168 6001	346 6014	346 6058	③ 351 6002	354 6045	③ 361 6002	354 6005	
	EMULS ASPH (EROSN CONT)(SS-1)	BACKFILL (TY A)	BACKFILL (TY B)	BOND FBR MTRX SEED (PERM)(RURAL) (SAND)	VEGETATIVE WATERING	STONE-MTRX- ASPH SMA-D SAC-A PG76-22	TACK COAT	FLEXIBLE PAVEMENT STRUCTURE REPAIR(6")	PLANE ASPH CONC PAV (2")	FULL - DEPTH REPAIR CRCP (8")	PLANE ASPH CONC PAV (2" TO 4")	
	GAL	STA	STA	SY	MG	TON	GAL	SY	SY	SY	SY	
	0.3 GAL/SY	-	-	-	80MG / 5000SY	220 LB/SY	0.10 GAL/SY	-	-	-	-	
<b><u>EASTBOUND LANES ONLY</u></b>	-	-	-	-	-	-	-	100	-	108	-	
FROM STA: 2085+00 TO 2292+50	4,151	207.5	207.5	14,119	222	9,638	8,762		-		87,612	-
FROM STA: 2292+50 TO 2500+00	4,151	207.5	207.5	13,891	222	9,638	8,762		-		87,612	-
<b><u>US 80 OVERPASS</u></b>	-	-	-	-	-	-	-		-		-	-
EXIT RAMP	286	15	15	950	16	418	380		-		3,800	-
ENTRANCE RAMP	270	14	14	900	15	396	360		-		3,600	-
<b><u>FM 134 OVERPASS</u></b>	-	-	-	-	-	-	-		-		-	-
EXIT RAMP	246	13	13	820	14	361	328		-		3,278	-
ENTRANCE RAMP	218	11	11	722	12	317	289		-		2,886	-
<b><u>SP 156 OVERPASS</u></b>	-	-	-	-	-	-	-		-		-	-
EXIT RAMP	376	19	19	1,249	20	549	500		-		4,995	-
ENTRANCE RAMP	214	11	11	710	12	312	284		-		2,840	-
<b><u>SMA TRANS. FOR PFC OVERLAY</u></b>	-	-	-	-	-	-	-		-		-	-
STA. 2087+64 TO STA. 2089+14	-	-	-	-	-	-	-		-		-	-
STA. 2089+14 TO STA. 2091+50	-	-	-	-	-	-	-		-		-	-
STA. 2091+50 TO STA. 2093+00	-	-	-	-	-	-	-		-		-	-
STA. 2429+79 TO STA. 2431+29	-	-	-	-	-	-	-	-	-	-		
STA. 2431+29 TO STA. 2449+50	-	-	-	-	-	-	-	-	-	-		
STA. 2449+50 TO STA. 2451+00	-	-	-	-	-	-	-	-	-	-		
<b>SHEET 2 SUBTOTALS</b>	<b>9,912</b>	<b>498</b>	<b>498</b>	<b>33,361</b>	<b>533</b>	<b>21,629</b>	<b>19,665</b>	<b>100</b>	<b>196,623</b>	<b>108</b>	<b>0</b>	
<b>PROJECT TOTALS</b>	<b>19,737</b>	<b>992</b>	<b>992</b>	<b>66,389</b>	<b>1,061</b>	<b>43,136</b>	<b>39,219</b>	<b>200</b>	<b>392,144</b>	<b>216</b>	<b>11,222</b>	

- ① INCLUDES QUANTITIES FOR FOR MBGF APPROACH
- ② FOR CONTRACTOR INFORMATION ONLY
- ③ SEE ADDITIONAL QUANTITIES ELSEWHERE IN PLANS

**MISCELLANEOUS  
SUMMARIES**

SHEET 2 OF 5



© 2021

CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		11


DATE: 10/6/2021 9:55:29 AM  
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\SUMMARY SUMMARY.dgn

SUMMARY OF METAL BEAM GUARD FENCE ITEMS													
LOCATION	104 6010	① 104 6054	132 6017	① 432 6045	540 6001	540 6002	540 6016	542 6001	542 6002	544 6001	544 6003	658 6061	658 6064
	REMOVING CONC (RIPRAP)	REMOVING CONCRETE(MOW STRIP)	EMBANKMENT (VEHICLE)(ORD COMP)(TY A)	RIPRAP (MOW STRIP)(4 IN)	MTL W-BEAM GD FEN (TIM POST)	MTL W-BEAM GD FEN (STEEL POST)	DOWNSTREAM ANCHOR TERMINAL SECTION	REMOVE METAL BEAM GUARD FENCE	REMOVE TERMINAL ANCHOR SECTION	GUARDRAIL END TREATMENT (INSTALL)	GUARDRAIL END TREATMENT (REMOVE)	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2	INSTL DEL ASSM (D-SY)SZ 1(BRF)GF2
	CY	LF	CY	CY	LF	LF	EA	LF	EA	EA	EA	EA	EA
<b>EAST AND WEST BOUND</b>													
IH 20 DRAW EB	-	-	165	7	112.5	37.5	1	150	1	1	1	5	-
IH 20 DRAW WB	-	-	163	7	112.5	37.5	1	150	1	1	1	5	-
IH 20 EB ENT RAMP DRAW	-	300	258	12	275	-	1	225	1	1	1	-	10
IH 20 WB EXIT RAMP DRAW N	-	200	201	10	200	-	1	200	1	1	1	-	8
IH 20 WB EXIT RAMP DRAW S	-	-	220	14	225	-	1	225	1	1	1	-	10
BIG SISK CREEK	-	-	220	10	225	-	1	250	1	1	1	8	-
LITTLE SISK CREEK	-	-	173	9	162.5	37.5	1	200	1	1	1	7	-
JONESVILLE CUTOFF EB	4	-	141	7	150	-	1	112.5	1	1	1	5	-
JONESVILLE CUTOFF WB	4	-	141	7	150	-	1	112.5	1	1	1	5	-
FM 134 OVERPASS EB	4	-	141	7	150	-	1	112.5	1	1	1	5	-
FM 134 OVERPASS WB	4	-	141	7	150	-	1	112.5	1	1	1	5	-
<b>PROJECT TOTALS</b>	<b>16</b>	<b>500</b>	<b>1,964</b>	<b>97</b>	<b>1,913</b>	<b>113</b>	<b>11</b>	<b>1850</b>	<b>11</b>	<b>11</b>	<b>11</b>	<b>45</b>	<b>28</b>

① SEE ADDITIONAL QUANTITIES ELSEWHERE IN PLANS

MISCELLANEOUS  
SUMMARIES

SHEET 3 OF 5



CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		12



DATE: 10/6/2021 11:48:01 AM  
 FILE: pw:\xtdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\QUANTITY SUMMARIES.dgn

**SUMMARY OF PAVEMENT MARKING ITEMS**

LOCATION	533 6003	① 662 6004	662 6012	① 662 6034	662 6064	668 6084	672 6010	6149 6004	6149 6005	6149 6010	① 6185 6002	6185 6005
	RUMBLE STRIPS (SHOULDER) ASPHALT	WK ZN PAV MRK NON-REMOV (W)4"(SLD)	WK ZN PAV MRK NON-REMOV (W)8"(SLD)	WK ZN PAV MRK NON-REMOV (Y)4"(SLD)	WK ZN PAV MRK RMOV (W)(6" )(BRK)	PREFAB PAV MRK TY C (W) (NUMBER)	REFL PAV MRKR TY II-C-R	REFL PAV MRK AWT (W) 6" (SLD) (100MIL)	REFL PAV MRK AWT (W) 6" (BRK) (100MIL)	REFL PAV MRK AWT (Y) 6" (SLD) (100MIL)	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	LF	LF	LF	LF	LF	EA	EA	LF	LF	LF	DAY	DAY
<b>EASTBOUND LANES ONLY</b>	-	-	-	-	-	-	-	-	-	-		
FROM STA: 2085+00 TO 2292+50	-	-	-	-	4,671	-	243	19,370	5,188	20,750		
FROM STA: 2292+50 TO 2500+00	-	-	-	-	4,671	-	237	18,920	5,188	20,750		
EB OUTSIDE EDGE LINE	38,020	-	-	-	-	-	-	-	-	-		
EB INDSIDE EDGE LINE	41,500	-	-	-	-	-	-	-	-	-		
<b>US 80 OVERPASS</b>	-	-	-	-	-	-	-	-	-	-		
EXIT RAMP	-	1,370	580	710	-	3	29	-	-	-	37	29
ENTRANCE RAMP	-	1,880	580	1,075	-	-	29	-	-	-		
<b>FM 134 OVERPASS</b>	-	-	-	-	-	-	-	-	-	-		
EXIT RAMP	-	1,160	500	750	-	3	25	-	-	-		
ENTRANCE RAMP	-	1,300	500	870	-	-	25	-	-	-		
<b>SP 156 OVERPASS</b>	-	-	-	-	-	-	-	-	-	-		
EXIT RAMP	-	1,790	480	1,400	-	3	24	-	-	-		
ENTRANCE RAMP	-	1,230	400	770	-	-	20	-	-	-		
<b>SHEET 1 SUBTOTALS</b>	<b>79,520</b>	<b>8,730</b>	<b>3,040</b>	<b>5,575</b>	<b>9,342</b>	<b>9</b>	<b>632</b>	<b>38,290</b>	<b>10,376</b>	<b>41,500</b>		
<b>WESTBOUND LANES ONLY</b>	-	-	-	-	-	-	-	-	-	-		
FROM STA: 2085+00 TO 2500+00	-	-	-	-	9,342	-	480	38,290	10,376	41,500		
EB OUTSIDE EDGE LINE	38,020	-	-	-	-	-	-	-	-	-		
EB INDSIDE EDGE LINE	41,500	-	-	-	-	-	-	-	-	-		
<b>US 80 OVERPASS</b>	-	-	-	-	-	-	-	-	-	-		
EXIT RAMP	-	1,380	500	960	-	3	25	-	-	-	36	29
ENTRANCE RAMP	-	1,550	410	1,110	-	-	21	-	-	-		
<b>FM 134 OVERPASS</b>	-	-	-	-	-	-	-	-	-	-		
EXIT RAMP	-	1,000	350	660	-	3	18	-	-	-		
ENTRANCE RAMP	-	1,425	660	685	-	-	33	-	-	-		
<b>SP 156 OVERPASS</b>	-	-	-	-	-	-	-	-	-	-		
EXIT RAMP	-	1,180	480	790	-	3	24	-	-	-		
ENTRANCE RAMP	-	2,170	440	1,490	-	-	22	-	-	-		
<b>SHEET 2 SUBTOTALS</b>	<b>79,520</b>	<b>8,705</b>	<b>2,840</b>	<b>5,695</b>	<b>9,342</b>	<b>9</b>	<b>623</b>	<b>38,290</b>	<b>10,376</b>	<b>41,500</b>		
<b>PROJECT TOTALS</b>	<b>159,040</b>	<b>17,435</b>	<b>5,880</b>	<b>11,270</b>	<b>18,684</b>	<b>18</b>	<b>1,255</b>	<b>76,580</b>	<b>20,752</b>	<b>83,000</b>		

① SEE ADDITIONAL QUANTITIES ELSEWHERE IN PLANS

**MISCELLANEOUS SUMMARIES**

SHEET 4 OF 5



CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		13

© 2021

DATE: 10/6/2021 11:49:14 AM  
 FILE: \\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEET\QUANT\TY SUMMARIES.dgn

PIPE REPLACEMENT SUMMARY											
	① 104 6054	① 164 6054	354 6082	① 361 6002	① 351 6002	401 6001	402 6001	403 6001	420 6071	① 432 6045	464 6009
LOCATION	REMOVING CONCRETE (MOW STRIP)	BOND FBR MTRX SEED (PERM) (RU RAL) (SAND)	PLANE ASPH CONC PAV (10")	FULL - DEPTH REPAIR CRCP (8")	FLEXIBLE PAVEMENT STRUCTURE REPAIR (6")	FLOWABLE BACKFILL	TRENCH EXCAVATION PROTECTION	TEMPORARY SPL SHORING	CL C CONC (COLLAR)	RIPRAP (MOW STRIP) (4 IN)	RC PIPE (CL III) (42 IN)
	LF	SY	SY	SY	SY	CY	LF	SF	EA	CY	LF
PHASE 1			1,778								
PHASE 2	150	300		71	89	150	29	180	1	6	29
PHASE 3		300		36	80		29	180			27
<b>TOTAL:</b>	<b>150</b>	<b>600</b>	<b>1,778</b>	<b>107</b>	<b>169</b>	<b>150</b>	<b>58</b>	<b>360</b>	<b>1</b>	<b>6</b>	<b>56</b>


PIPE REPLACEMENT SUMMARY - CONT.												
	467 6020	496 6007	506 6038	506 6039	512 6072	512 6074	512 6076	543 6001	543 6021	545 6003	545 6005	545 6019
LOCATION	SET (TY1) (42IN) (6:1) (C)	REMOV STR (PIPE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)	PTB (FRN&INST L) (SGL SLP) (TY 1) OR (STL)	PTB (MOVE) (SGL SLP) (TY 1) OR (STL)	PTB (REMOVE) (SGL SLP) (TY 1) OR (STL)	CABLE BARRIER SYSTEM (TL-3)	REMOVE CABLE BARRIER	CRASH CUSH ATTEN (MOVE & RESET)	CRASH CUSH ATTEN (REMOVE)	CRASH CUSH ATTEN (INSTL) (S) (N) (TL 3)
	EA	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA
PHASE 1												
PHASE 2		29	200	200	960	480		150	150			2
PHASE 3	1	27					960			1	2	
<b>TOTAL:</b>	<b>1</b>	<b>56</b>	<b>200</b>	<b>200</b>	<b>960</b>	<b>480</b>	<b>960</b>	<b>150</b>	<b>150</b>	<b>1</b>	<b>2</b>	<b>2</b>

PIPE REPLACEMENT SUMMARY - CONT.										
	658 6013	658 6026	662 6005	① 662 6004	① 662 6034	677 6002	3077 6075	3077 6080	② 6001 6002	① 6185 6002
LOCATION	INSTL DEL ASSM (D-SW) SZ (BRF) CTB	INSTL DEL ASSM (D-SY) SZ (BRF) CTB	WK ZN PAV MRK NON-REMOV (W) 6" (BRK)	WK ZN PAV MRK NON-REMOV (W) 4" (SLD)	WK ZN PAV MRK NON-REMOV (Y) 4" (SLD)	ELIM EXT PAV MRK & MRKS (6")	TACK COAT	SP MIXES SP-C OR SP-D PG70-22	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATION ARY)
	EA	EA	LF	LF	LF	LF	GAL	TON	EA	DAY
PHASE 1							963	1,059		
PHASE 2		4	1,100	3,200	4,225	8,525			4	19
PHASE 3	4		480	3,800	1,900	2,380				
<b>TOTAL:</b>	<b>4</b>	<b>4</b>	<b>1,580</b>	<b>7,000</b>	<b>6,125</b>	<b>10,905</b>	<b>963</b>	<b>1,059</b>	<b>4</b>	<b>19</b>

- ① SEE ADDITONAL QUANTITIES ELSEWHERE IN PLANS
- ② PCMS TO BE USED FOR DURATION OF CONTRACT

**MISCELLANEOUS  
SUMMARIES**

SHEET 5 OF 5



CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		14

DATE: 9/17/2021 4:35:48 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 049510094 - Design Master Design Files\04 - STANDARD SHEETS\000 BC(1)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this information into any other format or for the use of this information in any other project.

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b> <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard
<b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b>		
<b>BC (1) - 21</b>		
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT: 0495	SECT: 10
	JOB: 094	HIGHWAY: IH 20
4-03 7-13	DIST: ATL	COUNTY: HARRISON
9-07 8-14		SHEET NO. 15
5-10 5-21		


DATE: 9/17/2021 4:35:50 PM  
 FILE: \\txdot\project\wisonline.com\TXDOTS\Documents\19 - ATL\Design Projects\0495-10\0495-10-094.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein.

### TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

### T-INTERSECTION



### CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

### TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

### GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

### WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

### SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



### SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



### NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



## BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ATL	HARRISON	16	

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12



## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC (3) -21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0495	10	094	IH 20				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ATL	HARRISON	17					

DATE: 9/17/2021 4:35:51 PM  
 FILE: \\txdot\project\wiseonline.com\TXDOT5\Documents\19 - ATL\Design Project\00841\_0815\19090508039081\_0815\19090508039081\_0815.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions.

DATE: 9/17/2021 4:35:52 PM  
 FILE: \\txdot.projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 BC(1)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for its use, or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12




**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**



FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		049510	094	IH 20					
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ATL	HARRISON	18					

DATE: 9/17/2021 4:35:53 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDA05\000 BC(1)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats for use in other software applications.




**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS





**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**WEDGE ANCHORS**

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

**GENERAL NOTES**

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."  
 \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.  
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC(5) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0495	10	094	IH	20				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ATL	HARRISON	19					

DATE: 9/17/2021 4:35:55 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04\_STANDARD\$000 BC(1)-21.dgn  
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats.

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

**PORTABLE CHANGEABLE MESSAGE SIGNS**

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

**RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES**

(The Engineer may approve other messages not specifically covered here.)

**Phase 1: Condition Lists**

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

Other Condition List

FRONTAGE ROAD CLOSED
SHOULDER CLOSED XXX FT
RIGHT LN CLOSED XXX FT
RIGHT X LANES OPEN
DAYTIME LANE CLOSURES
I-XX SOUTH EXIT CLOSED
EXIT XXX CLOSED X MILE
RIGHT LN TO BE CLOSED
X LANES CLOSED TUE - FRI

ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT

ROAD REPAIRS XXXX FT
LANE NARROWS XXXX FT
TWO-WAY TRAFFIC XX MILE
CONST TRAFFIC XXX FT
UNEVEN LANES XXXX FT
ROUGH ROAD XXXX FT
ROADWORK NEXT FRI-SUN
US XXX EXIT X MILES
LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

**Phase 2: Possible Component Lists**

Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE *

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

\*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

**APPLICATION GUIDELINES**

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

**WORDING ALTERNATIVES**

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

**FULL MATRIX PCMS SIGNS**


- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

<b>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</b>			
<b>BC (6) - 21</b>			
FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT	SECT	JOB
REVISIONS	0495 10	094	IH 20
9-07 8-14	DIST	COUNTY	SHEET NO.
7-13 5-21	ATL	HARRISON	20




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 9/17/2021 4:35:56 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 BC(1)-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**


- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**




**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.


REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.


WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

**WARNING LIGHTS**

- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>PL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**

- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0495	10	094	IH 20				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ATL	HARRISON	21					

DATE: 9/17/2021 4:35:57 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 BC(1)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension)  
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel  
 mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0495	10	094	IH 20				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	ATL	HARRISON	22					
7-13									


DATE: 9/17/2021 4:35:58 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 BC(1)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**PORTABLE**

**VERTICAL PANELS (VPs)**




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\*\*Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ATL	HARRISON	23	

DATE: 9/17/2021 4:36:00 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 BC(10)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the use of this standard to other formats or for incorrect results or damages resulting from its use.

**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.


Barricades shall NOT be used as a sign support.



**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**


Each roadway of a divided highway shall be barricaded in the same manner.



**PERSPECTIVE VIEW**


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




**PLAN VIEW**

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



**PERSPECTIVE VIEW**




**PLAN VIEW**

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



**Two-Piece cones**

**One-Piece cones**

**Tubular Marker**

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(10)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ATL	HARRISON	24	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


**BC(11)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	ATL	HARRISON	25	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 9/17/2021 4:36:01 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-13614 - Design\Master Design Files\04 STANDARDS\000 BC(11)-21.dgn

DATE: 9/17/2021 4:36:02 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-13614 - Design\Master Design Files\04 STANDARDS\000 BC(11)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.






RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



### SOLID LINES




### BROKEN LINES



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	ATL	HARRISON	26	
11-02 8-14				



Shoulder

Shoulder

Work Space

500' Min.

100' Approx.

Use 3 drums in front of each repair area. Use a Ty "C" Light on the drum nearest to traffic.

Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights

For nighttime closures, replace every third channelizing device in the taper with a CW1-8 (36"x48") on portable sign supports.

LEGEND							
	Type 3 Barricade		Channelizing Devices				
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)				
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)				
	Sign		Traffic Flow				
	Flag		Drum				

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		**			On a Taper	On a Tangent	
		10' Offset	11' Offset	12' Offset			
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

### GENERAL NOTES


- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans or when approved by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Duplicate construction warning signs shall be erected on the median side of freeways.
- The TCP details may require additional and/or relocation of route shields, guide signs, etc. to guide motorists along entire length of detour due to ramp and freeway closure.
- See BC Standards for additional sign details.
- When possible, changeable message signs should be located 500 feet in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- A minimum of two PCMS per direction shall be placed in advance of the lane closure. PCMS shall be placed a minimum of 0.5 mile in advance of the taper. An additional PCMS shall be placed approximately 3 miles in advance of the taper or at the end of the queue, whichever is greater.
- Channelizing devices shall be placed in accordance with BC Standards and "WORKSHEET FOR EDGE CONDITION TREATMENT TYPES."
- Neither work activity nor storage of equipment, vehicles, or materials shall occur within the buffer space.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20 signs already in place on the project.

#A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used and positioned per the Manufacturer's Roll Ahead Distance (MRAD) in advance of the area of crew exposure without adversely affecting the work performance.


Texas Department of Transportation  
 Atlanta District Standard  
**TRAFFIC CONTROL PLAN**  
**FREWAY PAVEMENT REPAIRS**  
**TCP (ATL-61)-14**

FILE:	DW:	TXDOT	CK:	TXDOT	DW:	TXDOT	CK:	TXDOT
© TXDOT	REVISIONS	CONT	SECT	JOB	HIGHWAY			
0495	10	094		IH 20				
DIST	COUNTY			SHEET NO.				
ATL	HARRISON			27				

DATE: 9/17/2021 4:36:25 PM  
 FILE: \\txdot\project\wiseon\line.com\TXDOT5\Documents\19 - ATL\Design Projects\0918136\0918136.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information to any other format or for any errors or omissions that may appear hereon.



**RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)**




**INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)**

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle	→	RIGHT Directional
☐	Heavy Work Vehicle	←	LEFT Directional
▲	Truck Mounted Attenuator (TMA)	↔	Double Arrow
↶	Traffic Flow	⚠	CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

**GENERAL NOTES**

- ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
- For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
- Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
- The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
- Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
- The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.



**STRIPING FOR TMA**

Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN  
MOBILE OPERATIONS  
DIVIDED HIGHWAYS**

**TCP(3-2)-13**


FILE: tcp3-2.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	ATL	HARRISON	28	
1-97				




DATE: 9/17/2021 4:36:36 PM  
 FILE: \\txdot\project\wiseonline.com\TXDOT5\Documents\19 - ATL\Design\Projects\090819\090819.dgn  
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this drawing to any other format.




**TCP (3-3a)**  
**TWO LANE HIGHWAY WITH PAVED SHOULDERS**  
**(WORK ON TRAVEL LANE)**




**TCP (3-3b)**  
**TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS**  
**(WORK ON TRAVEL LANE)**




**TCP (3-3c)**  
**DIVIDED MULTILANE HIGHWAY**




**TCP (3-3d)**  
**UNDIVIDED MULTILANE HIGHWAY**




**TRAIL/SHADOW VEHICLE A**  
 with RIGHT Directional display  
 Flashing Arrow Board



**TRAIL/SHADOW VEHICLE B**  
 with Flashing Arrow Board  
 in Caution Mode



**ADVANCE WARNING VEHICLE**



**STRIPING FOR TMA**

LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
Heavy Work Vehicle		LEFT Directional
Truck Mounted Attenuator (TMA)		Double Arrow
Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**



- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS**  
**RAISED PAVEMENT**  
**MARKER INSTALLATION/**  
**REMOVAL**  
**TCP (3-3) - 14**

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	ATL	HARRISON	29	
1-97 7-14				

DATE: 9/17/2021 4:36:45 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\09182021\09182021\18.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another.



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	$L = WS$	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

- GENERAL NOTES**
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
  - 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.



Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
 SHOULDER WORK FOR  
 FREEWAYS / EXPRESSWAYS**

**TCP (5-1) - 18**

FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
2-18	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	30	

DATE: 9/17/2021 4:36:54 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\0908236\0908236.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into any other format or for any errors or omissions that may appear in this document.



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

\* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.


Texas Department of Transportation  
 Traffic Operations Division Standard

## TRAFFIC CONTROL PLAN FREEWAY LANE CLOSURES


### TCP (6-1) - 12

FILE: tcp6-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
8-12	0495	10	094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	31	

DATE: 9/17/2021 4:37:05 PM  
FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Project\049510\049510.dgn  
DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion or effect of the use of this standard on any project.



**TCP (6-2a)**  
**ENTRANCE RAMP OPEN**  
**WORK WITHIN 500' OF RAMP**



**TCP (6-2b)**  
**ENTRANCE RAMP CLOSED**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\*Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- ### GENERAL NOTES
- 1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
  - 2. ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainline can be seen from both roadways.
  - 3. See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
  - 4. The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.
- \*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.


Texas Department of Transportation  
Traffic Operations Division Standard

## TRAFFIC CONTROL PLAN WORK AREA NEAR RAMP


### TCP (6-2) - 12

FILE:	tcp6-2.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	February 1994	CON:	SECT:	JOB:	HIGHWAY:				
REVISIONS	0495	10	094		IH 20				
1-97	8-98								
4-98	8-12								
		DIST:	COUNTY:	SHEET NO.:					
		ATL	HARRISON	32					


DATE: 9/17/2021 4:37:31 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\09-12-2021\19-12-2021\19-12-2021.dgn  
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of electronic files to paper or for the use of the information contained herein for any purpose other than that for which it was prepared.



TCP (6-3a)  
**ENTRANCE RAMP OPEN**



TCP (6-3b)  
**EXIT RAMP CLOSED**  
**TRAFFIC EXITS PRIOR TO CLOSED RAMP**



**LEGEND**

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**TYPICAL USAGE**

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES:**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN  
 WORK AREA BEYOND RAMP**

**TCP (6-3) - 12**


FILE:	tcp6-3.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	February 1994	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0495	10	094	IH 20				
1-97 8-98		DIST	COUNTY	SHEET NO.					
4-98 8-12		ATL	HARRISON	33					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another. For more information, contact the Texas Department of Transportation, 4905 West Loop South, P.O. Box 12188, Houston, TX 77255-1218. DATE: 9/17/2021 4:37:39 PM FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\19094949\19094949.dgn



TCP (6-4a)  
**EXIT RAMP CLOSED**  
TRAFFIC EXITS PAST CLOSED RAMP

STREET A EXIT CLOSED USE STREET B EXIT  
Or, as an option when exits are numbered  
EXIT XX CLOSED USE EXIT XY  
Place 1 mile (approx.) in advance of closed ramp.



TCP (6-4b)  
**EXIT RAMP OPEN**

LEGEND			
[Symbol]	Type 3 Barricade	[Symbol]	Channelizing Devices (CDs)
[Symbol]	Heavy Work Vehicle	[Symbol]	Truck Mounted Attenuator (TMA)
[Symbol]	Trailer Mounted Flashing Arrow Board	[Symbol]	Portable Changeable Message Sign (PCMS)
[Symbol]	Sign	[Symbol]	Traffic Flow
[Symbol]	Flag	[Symbol]	Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
  - See BC Standards for sign details.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.


Texas Department of Transportation  
Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
WORK AREA AT EXIT RAMP**


**TCP (6-4) - 12**

FILE:	tcp6-4.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	February 1994	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0495	10	094	IH	20				
1-97	8-98	DIST	COUNTY	SHEET NO.					
4-98	8-12	ATL	HARRISON	34					

DATE: 9/17/2021 4:37:48 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\0908236\0908236.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into digital form. TxDOT is not responsible for any errors or omissions in this document.



TCP (6-5a)  
**EXIT RAMP OPEN**



TCP (6-5b)  
**EXIT RAMP OPEN  
 TWO LANE CLOSURE WITHIN  
 1500' PAST EXIT RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC standards for sign details.
- If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN  
 WORK AREA BEYOND EXIT RAMP**

**TCP (6-5) - 12**

FILE: tcp6-5.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	ATL	HARRISON	35	

DATE: 9/17/2021 4:37:55 PM  
 FILE: \\txdot\project\wiseon\line.com\TXDOT5\Documents\19 - ATL\Design\Projects\090823\090823.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another.



TYPICAL RUMBLE STRIP PLACEMENT AT EXIT AND ENTRANCE RAMP

**GENERAL NOTES**


- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
- See the table below for determining what options may be used for edgeline rumble strips.

**WHEN INSTALLING MILLED DEPRESSION EDGELINE RUMBLE STRIPS:**


- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
- Pavement markings can be applied over milled shoulder rumble strips to create an edgeline rumble strip.
- Breaks in edgeline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inches depth of milled rumble strip may be considered in these areas.
- On roadways with high bicycle activity, consideration should be given before the installation of edgeline rumble strips. Things to consider include size of rumble strips, rumble strip material and location of rumble strips on the shoulder. If the designer determines that gaps are needed in the rumble strips due to bicycle use of the road, then follow the requirement shown in FHWA Technical Advisory T5040.39, or latest version. A detail of the spacing shall be included in the plans.

**WHEN INSTALLING RAISED OR PROFILE EDGELINE RUMBLE STRIPS:**

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edgeline when used as a rumble strip. The color of the button should match the color of the adjacent edgeline marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Breaks in edgeline rumble strips using raised traffic buttons shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks when installed on conventional highways.
- The minimum distance between the edgeline and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edgelines may substitute for buttons.




PLAN VIEW




PROFILE VIEW  
OPTION 1

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW




PROFILE VIEW  
OPTION 2

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)

\* This distance may vary based on width of shoulder




PLAN VIEW




PROFILE VIEW  
OPTION 3

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)

\* This distance may vary based on width of shoulder




PLAN VIEW




PROFILE VIEW  
OPTION 4

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)



PLAN VIEW  
OPTION 5

RAISED EDGELINE RUMBLE STRIPS



PLAN VIEW  
OPTION 6

PROFILE EDGELINE MARKINGS

SHOULDER WIDTH TABLE		
EQUAL TO OR LESS THAN 2 FEET	GREATER THAN 2 FEET LESS THAN 4 FEET	EQUAL TO OR GREATER THAN 4 FEET
Option 1, 5 OR 6	Option 1, 2, 3, 5 or 6	Option 2, 4, 5 OR 6




**EDGELINE RUMBLE STRIPS ON FREEWAYS AND DIVIDED HIGHWAYS RS(1)-13**

FILE: rs(1)-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2006	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
2-10	DIST	COUNTY	SHEET NO.	
10-13	ATL	HARRISON	36	



DATE: 9/17/2021 4:38:04 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\090949.ctb  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS




### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:  
[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)







## WORK ZONE SHORT TERM PAVEMENT MARKINGS

### WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	0495	SECT:	10	JOB:	094	REV:	IH 20
1-97	3-03	DIST:	ATL	COUNTY:	HARRISON	SHEET NO.		37	
7-13									

DATE: 9/17/2021 4:38:17 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\0089000000 WZ (UL) -13.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format.



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

**GENERAL NOTES**

- If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
- UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
- NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
- Signs shall be spaced at the distances recommended as per BC standards.
- Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
- Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
- Short term markings shall not be used to simulate edge lines.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1		
Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

**TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.**

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"




**SIGNING FOR UNEVEN LANES**

**WZ (UL) - 13**



FILE: WZUL-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
8-95 2-98 7-13	DIST	COUNTY	SHEET NO.	
1-97 3-03	ATL	HARRISON	38	

# DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS


Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet





Edge Condition I  
S = (3:1) (or flatter)



Edge Condition II  
S = ((2.99):1) to (1:1)



Edge Condition III  
S is steeper than (1:1)




Zone	Treatment Types Guidelines:
①	No treatment
②	CW 8-11 "Uneven Lanes" signs.
③	CW 8-9a Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.
④	CW8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge slope to that of the proferred Edge Condition I.
⑤	Check indications (Figure-1) for possitive barrier. Where positive barrier is not indicated, the treatment shown above for Zone-4 may be used after consideration of other applicable factors.

### Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

## FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ( [Cross-hatched] )



- $E = ADT \times T$   
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within the clear zone.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.

### FACTORS CONSIDERED IN THE GUIDELINES:

- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided herein. For more information, contact the Texas Department of Transportation, Design Division, 1701 North Loop West, Austin, Texas 78761-1701.

DATE: 10/4/2021 10:29:36 AM  
FILE: \\txdot\project\wiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\1909419\1909419.dgn

Engineer's Seal





Date Glenn R. Yowell, P.E.  
10/5/2021

Texas Department of Transportation  
Traffic Safety Division Standard

## TREATMENT FOR VARIOUS EDGE CONDITIONS


FILE: edgecon.dgn	DN:	CK:	DW:	CK:
© TxDOT August 2000	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
03-01 08-01 9-21	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	39	

CHK: \_\_\_\_\_  
 DWF: \_\_\_\_\_  
 CKS: \_\_\_\_\_  
 DWS: \_\_\_\_\_



**NOTES:**


1. SEE TCP CULVERT REPLACEMENT SHEET FOR MORE INFORMATION.
2. BARRIER SHALL REMAIN IN PLACE WHILE WORK IS BEING PERFORMED WITHIN THE CLEARZONE (30 LF).
3. DOWNSTREAM END OF CULVERT SHALL BE CONSTRUCTED FIRST.
4. SEE MISCELLANEOUS DETAILS SHEET, AND CULVERT LAYOUT SHEET FOR ADDITIONAL INFORMATION.



*Glenn R. Yowell, P.E.*

10/5/2021

**TCP DETAILS**




CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	39A	

NOT TO SCALE

DATE: \_\_\_\_\_  
 FILE: \_\_\_\_\_

DATE: 10/4/2021 3:33:25 PM  
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\IH20\2 in RCR\Repa\m2384+80-WB\1000




TCP - CONSTRUCTION STEP 2  
 WESTBOUND DIRECTION ONLY

NOT TO SCALE

- NOTES:
1. ALL DIMENSIONS SHOWN ARE MINIMUM.
  2. THE END ROAD WORK (G20-2) SIGN MAY BE OMITTED WHEN IT CONFLICTS WITH G20-2 SIGNS ALREADY IN PLACE ON THE PROJECT.
  3. CONFLICTING PAVEMENT MARKINGS SHALL BE REMOVED.
  4. SEE TCP DETAILS SHEET AND CULVERT LAYOUT FOR ADDITIONAL INFORMATION.


For nighttime closures, replace every third channelizing device in the taper with a CW1-8 (36"x48") on portable sign supports.



NOT TO SCALE


TCP - CONSTRUCTION STEP 1  
 WESTBOUND SHOULDER.  
 USING TCP(6-1)-12 FOR DAYTIME OPERATION  
 DURING THE PLANING AND OVERLAY FOR WB SHOULDER.  
 SEE MISC. DETAIL SHEET FOR MORE INFORMATION..

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Drum



TCP - CONSTRUCTION STEP 3  
 WESTBOUND DIRECTION ONLY


NOT TO SCALE



Glenn R. Yowell, P.E.

10/5/2021

TCP  
 CULVERT  
 REPLACEMENT



CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	39B	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

LOC NO.	TCP PHASE	PLAN SHEET NUMBER	LOCATION	STA	TEST LEVEL	DIRECTION OF TRAFFIC (UNI/BI)	FOUNDATION PAD		BACKUP SUPPORT			AVAILABLE SITE LENGTH	CRASH CUSHION													
							PROPOSED MATERIAL	PROPOSED THICKNESS	DESCRIPTION	WIDTH	HEIGHT		INSTALL	REMOVE	MOVE / RESET		L	L	R	R	S	S				
															MOVE/RESET	FROM LOC. #							N	W	N	W
1A	2	39B	WESTBOUND MAIN LANE	STA. 2384+80	TL-3	UNI	ASPH	4.5"	CTB OR STEEL	2'	32"	> 30'	X									X				
1A	3	39B	WESTBOUND MAIN LANE	STA. 2384+80	TL-3	UNI	ASPH	4.5"	CTB OR STEEL	2'	32"	> 30'		X	X	1A							X			
1B	2	39B	EASTBOUND MAIN LANE	STA. 2384+80	TL-3	UNI	ASPH	4.5"	CTB OR STEEL	2'	32"	> 30'	X										X			
1B	3	39B	EASTBOUND MAIN LANE	STA. 2384+80	TL-3	UNI	ASPH	4.5"	CTB OR STEEL	2'	32"	> 30'		X		1B							X			
												TOTALS	2	2	1											

LEGEND:  
 L=LOW MAINTENANCE  
 R=REUSABLE  
 S=SACRIFICIAL  
 N=NARROW  
 W=WIDE





FOR DEFINITIONS SEE THE "CRASH CUSHION CATEGORIZATION CHART.PDF" AT THE DESIGN DIVISION (ROADWAY STANDARDS) WEBSITE. USE QUICK LINKS TO ACCESS ATTENUATORS / CRASH CUSHIONS SECTION.  
<http://www.dot.state.tx.us/insdtdot/orgchart/cmd/cserve/standard/rdwylse.htm>

GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
 Glenn R. Yowell, P.E.  
 10/5/2021

**CRASH CUSHION SUMMARY SHEET**

FILE: CCSS.dgn	DN: TxDOT	CK:	CK:
© TxDOT	CONT	SECT	JOB
REVISIONS	0495	10	094
	DIST	COUNTY	
	ATL	HARRISON	
	FEDERAL AID PROJECT	SHEET NO.	
		39C	

DATE: 10/4/2021 9:32:28 AM  
 FILE: pw:\txdot.projects\19 - ATL\Design Projects\049510094 Lets with 0495-08-13614 - Design\Master Design Files\H20 42in RCP Repair (2384+80 WB)\STA  
 DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- ### GENERAL NOTES
- THE SYSTEM SHOWN ON THIS DRAWING IS A PROPRIETARY BARRIER TRADED AS BARRIERGUARD 800 AND BARRIERGUARD 800 MDS AND HAS BEEN DESIGNED AND MANUFACTURED BY LAURA METAAL ROAD SAFETY INC. FOR TECHNICAL ASSISTANCE AND APPLICATION SUPPORT CONTACT LEE STUART AT LAURA METAAL ROAD SAFETY INC. AT (702) 664-2009 OR [lstuart.laurametal@outlook.com](mailto:lstuart.laurametal@outlook.com)
  - THE BARRIERGUARD 800 SYSTEM HAS BEEN CRASH TESTED TO MASH AND HAS FHWA APPROVAL AS A TL-3 BARRIER. THE DEFLECTION TABLE OUTLINES BASIC SYSTEM PERFORMANCE AND COMPONENT ANCHORING REQUIREMENTS.
  - THIS DRAWING PACKAGE PROVIDES THE RELEVANT INFORMATION AND GENERAL GRAPHICS REQUIRED TO IDENTIFY THE COMPONENT PARTS OF BARRIERGUARD 800 AND THEIR INCORPORATION AS A WHOLE SYSTEM FOR DEPARTMENTAL STANDARD APPLICATIONS.
  - BARRIERGUARD 800 REQUIRES ANCHORING (PINNING) AT EACH END OF THE INSTALLED LENGTH. (INTERMEDIATE ANCHORS CAN BE USED TO REDUCE DEFLECTION).
  - INSTALLATION OF BARRIERGUARD 800 OR BARRIERGUARD 800 MDS, NORMALLY STARTS WITH A MALE TERMINAL SECTION AND IS FINISHED WITH A FEMALE TERMINAL SECTION. STANDARD SECTIONS ARE USED BETWEEN THE TERMINAL SECTIONS TO OBTAIN THE REQUIRED LENGTH OF POSITIVE BARRIER PROTECTION.
  - THE FULL HEIGHT TERMINAL (FHT) SECTIONS MAY BE CAPPED WITH A FHT COVER, HOWEVER IF EXPOSED TO ON-COMING TRAFFIC THE END SHOULD BE PROTECTED WITH A SUITABLE CRASH CUSHION. THE BARRIERGUARD 800 RANGE IS COMPATIBLE WITH MOST COMMONLY USED CRASH CUSHION END TREATMENTS. FOR DETAILS OF BARRIERGUARD 800 CRASH CUSHION CONNECTIONS THAT ARE NOT DETAILED WITHIN THESE DRAWINGS, PLEASE CONTACT LAURA METAAL ROAD SAFETY INC. FOR MORE DETAILS. THE FULL HEIGHT TERMINAL COVER IS SUITABLE FOR THE "DOWN STREAM" END OF A SYSTEM THAT DOES NOT HAVE EXPOSURE TO ON-COMING TRAFFIC.
  - WHEN INSTALLING THE MINIMUM DEFLECTION SYSTEM (MDS), THE SYSTEM CAN BE INSTALLED WITH ADDITIONAL INTERMEDIATE ANCHORS ALONG THE LENGTH OF THE BARRIER RUN AT INTERVALS SHOWN IN THE DEFLECTION TABLE. EACH BARRIER RUN CAN BE MADE UP OF ANY MIXTURE OF THE SYSTEMS BY THE INTRODUCTION OF INTERMEDIATE ANCHORS AND/OR T-TOP AS REQUIRED.
  - THERE ARE SEVERAL METHODS OF ACHIEVING RADIUS IN A LENGTH OF BARRIERGUARD 800. RADIUS CAN BE ACHIEVED USING VARIOUS METHODS AND THUS ALLOWING THE BARRIERGUARD TO FOLLOW THE DESIRED CURVATURE IN THE INSTALLATION, THESE METHODS ARE, THE MOVEMENT IN THE QUICKLINK, ADJUSTABLE 20FT. SECTIONS OR SHORT ANGLED SECTIONS WHICH ALLOW A RADIUS AS LOW AS 12FT. FOR FURTHER INFORMATION AND ADVICE CONTACT LAURA METAAL ROAD SAFETY INC.
  - A BARRIERGUARD 800 VARIABLE LENGTH BARRIER (VLB) SECTION SHOULD BE USED WHEN BARRIERGUARD 800 OR BARRIERGUARD 800 MDS IS ANCHORED ACROSS A BRIDGE EXPANSION JOINT. IF T-TOP IS TO BE USED IN CONJUNCTION WITH THE VLB, THE T-TOP SHOULD BE USED FOR MINIMUM 40FT ON EITHER SIDE OF THE VLB AND TERMINATED WITH TRANSITIONS. THE VLB SECTION PROVIDES APPROXIMATELY 7in OF EXTENSION AND 7in OF CONTRACTION. MULTIPLE VLB'S CAN BE LINKED TOGETHER TO PROVIDE MORE EXPANSION OR CONTRACTION. THE VLB'S SHOULD BE PLACED IN THE VICINITY OF THE EXPANSION JOINT. THE VLB DOES NOT NEED TO BE PLACED DIRECTLY OVER THE EXPANSION JOINT BUT MUST BE BETWEEN THE NEAREST ANCHORS ON EACH SIDE OF THE JOINT. IT IS RECOMMENDED THAT THE VLB IS PLACED WITHIN 40FT OF THE JOINT.
  - THE T-TOP CAN BE INSTALLED EITHER BEFORE OR AFTER THE BARRIERGUARD 800 HAS BEEN FULLY ASSEMBLED AND ANCHORED IN PLACE. T-TOP IS REQUIRED WHEN THE BARRIERGUARD 800 IS USED AS A MDS, ANCHORED EVERY 20FT, GATE SECTIONS AND VARIABLE LENGTH BARRIERS. THE T-TOP SHOULD EXTEND 40FT ON EITHER SIDE OF THESE CONDITIONS AND BE TERMINATED WITH TRANSITIONS.
  - THE BARRIERGUARD 800 RANGE HAS BEEN DESIGNED TO BE USED ON AND HAS BEEN TESTED ANCHORED ON ASPHALT, CONCRETE AND COMPACTED SUBBASE. CONTACT LAURA METAAL ROAD SAFETY INC. FOR FURTHER INFORMATION.
  - BARRIERGUARD 800 COMPONENTS ARE MANUFACTURED IN SI (METRIC) UNITS. ENGLISH UNITS SHOWN ARE APPROXIMATE. ALL COMPONENTS ARE FULLY GALVANIZED.
  - BARRIERGUARD 800 SYSTEMS SHALL BE ASSEMBLED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS DETAILED DRAWINGS, PROCEDURES AND SPECIFICATIONS. FOR ANY INSTALLATIONS OUTSIDE OF THE SCOPE OF THESE DRAWINGS PLEASE CONTACT LAURA METAAL ROAD SAFETY INC. FOR DETAILS.

BARRIERGUARD 800 DEFLECTION TABLE		
	STANDARD SYSTEM	MINIMUM DEFLECTION SYSTEMS (MDS)
DESCRIPTION	ONLY ANCHORED AT THE EXTREME ENDS OF THE BARRIER LENGTH	ANCHORED EVERY 20 FT.
DEFLECTION AT MASH TL-3	5'-6"	18 1/2"
T-TOP REQUIREMENTS	NONE REQUIRED	REQUIRED FOR MDS SECTIONS

	RESIN STUD ANCHORS			DRIVEN ANCHORS		Hilti HSL-3 SHALLOW MECHANICAL
	CONCRETE *	UNREINFORCED CONCRETE *	ASPHALT	ASPHALT	SUBBASE/SOIL	CONCRETE
ANCHOR DIAMETER	1 in.	1 in.	1 in.	1-3/16 in.	5-1/2 in.	**
EMBEDMENT DEPTH	6 in.	8 in.	16 in.	16 in.	32 in.	**
DRILL DIAMETER	1-1/8 in.	1-1/8 in.	1-1/8 in.	1-3/16 in.	DRIVEN	**
PULL OUT CAPACITY (MIN)	17500 lb	17500 lb	N/A	N/A	N/A	**
SHEAR CAPACITY (MIN)	25000 lb	25000 lb	N/A	N/A	N/A	**

\* ALTERNATIVE ANCHORS INCLUDING MECHANICAL ANCHORS FOR CONCRETE MAYBE USED IF THEY MEET THE STRENGTH REQUIREMENTS LISTED, DETAILS WILL BE MANUFACTURER SPECIFIC.  
 \*\* CONTACT: LAURA METAAL ROAD SAFETY INC. FOR SPECIFIC APPLICATION.



Design Division Standard

## BARRIERGUARD 800 SYSTEM

### STEEL BARRIER


### MASH TL-3

## BARRIERGUARD-19


FILE: barrierguard19.dgn	DN: TxDOT	CK: KM	DW: VP	CK:
© TxDOT: JULY 2019	CONT SECT	JOB	HIGHWAY	
REVISIONS	0495 10	094	IH 20	
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	39D	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2021  
FILE: \$FILEL\$.S




PLAN VIEW




ELEVATION VIEW  
LEFT SIDE




VIEW A-A




ISOMETRIC VIEW



ELEVATION VIEW SIDE VIEW



PLAN VIEW  
T-CONNECTOR DETAILS



DETAIL A  
SEE ANCHORING TABLES

METHOD	DESCRIPTION	APPROX. RADIUS (FT)
1	20FT BARRIER SECTION WITH STANDARD T-CONNECTIONS AT MAXIMUM ANGLE	581
2	20FT BARRIER SECTION WITH 2.5° T-CONNECTION	460
3	20FT BARRIER SECTION WITH 5° T-CONNECTION	230
4	20FT BARRIER SECTION WITH 10° T-CONNECTION	115
5	20FT BARRIER SECTION WITH 10° BARRIER SECTION AND STANDARD T-CONNECTION	135
6	10° BARRIER SECTION WITH STANDARD T-CONNECTIONS	22
7	10° BARRIER SECTION WITH 10° T-CONNECTION	12

\* SEE PRODUCT MANUAL OR CONTACT HIGHWAY CARE LTD. FOR MORE INFORMATION ON ANGLE T-CONNECTORS

	ANCHOR OPTIONS	ANCHOR LENGTH	EMBEDMENT DEPTH (MIN.)	DRILL DIAMETER
1	1" GALV. RESIN THREADED ANCHOR (WITH 1" GALV. WASHER & NUT)	1'-1"	11 3/4"	1 1/8"
2	1 3/8" GALV. DROP IN PIN (NOT DRIVEN PIN)	1'-2 3/8"	1'-1 3/4"	1 1/4"
3	1" GALV. RESIN THREADED ANCHOR (WITH 1" GALV. WASHER & NUT)	1'-6"	1'-4 1/2"	1 1/4"
4	1" GALV. CHEMICAL THREADED "LEFTY" KELKEN REMOVABLE ANCHOR (WITH 1" GALV. WASHER & NUT)	NA	1'-0"	1 1/4"

\*\* 2" MIN. ASPHALT DEPTH ABOVE AN APPROPRIATELY COMPACTED DGA SUBBASE AND 2" MIN. ASPHALT DEPTH ABOVE A MIN. OF 6" REINFORCED CONCRETE SUBBASE.

NOTE: ANCHORS ARE TO BE POSITIONED A MINIMUM OF 5 3/4" AWAY FROM THE EDGE OF AN EXCAVATION FOR RESIN ANCHORS OR 7 3/4" FOR DROP IN PINS.

	ANCHOR OPTIONS	ANCHOR LENGTH	EMBEDMENT DEPTH (MIN.)	DRILL DIAMETER
1	1" GALV. RESIN THREADED ANCHOR (WITH 1" GALV. WASHER & NUT)	9"	6"	1 1/8"
2	1" HILTI HSL-3 MECHANICAL ANCHOR	9 1/4"	***	***
3	1" GALV. CHEMICAL THREADED "LEFTY" KELKEN REMOVABLE ANCHOR (WITH 1" GALV. WASHER & NUT)	NA	6"	1 1/4"
4	1 3/8" GALV. DROP IN PIN (NOT DRIVEN PIN)	1'-2 3/8"	1'-1 3/4"	1 1/4"

\*\*\* 7 1/2" MINIMUM REINFORCED CONCRETE DEPTH. 10" MINIMUM UNREINFORCED CONCRETE DEPTH. \*\*\* CONTACT: HIGHWAY CARE LTD. FOR SPECIFIC APPLICATION.

NOTE: ANCHORS ARE TO BE POSITIONED A MINIMUM OF 11 1/8" FROM THE EDGE OF THE CONCRETE PAD.

GENERAL NOTES

- THE SYSTEM SHOWN ON THIS DRAWING IS A PROPRIETARY BARRIER TRADED AS HIGHWAYGUARD AND HIGHWAYGUARD LDS AND HAS BEEN DESIGNED AND MANUFACTURED BY HIGHWAY CARE LTD. FOR TECHNICAL ASSISTANCE AND APPLICATION SUPPORT CONTACT AT (888) 323-6374 OR [engineering@highwaycare.com](mailto:engineering@highwaycare.com)
- THE HIGHWAYGUARD HAS BEEN CRASH TESTED TO MASH AND HAS FHWA APPROVAL AS A TL-3 & TL-4 BARRIER. THE DEFLECTION TABLE OUTLINES BASIC SYSTEM PERFORMANCE AND COMPONENT ANCHORING REQUIREMENTS.
- THIS DRAWING PACKAGE PROVIDES THE RELEVANT INFORMATION AND GENERAL GRAPHICS REQUIRED TO IDENTIFY THE COMPONENT PARTS OF HIGHWAYGUARD AND THEIR INCORPORATION AS A WHOLE SYSTEM FOR DEPARTMENTAL STANDARD APPLICATIONS.
- INSTALLATION OF HIGHWAYGUARD BARRIER OR HIGHWAYGUARD LDS BARRIER, NORMALLY STARTS WITH AN END CAP THAT MUST BE PROTECTED WITH A SUITABLE CRASH CUSHION END TREATMENT IF EXPOSED TO ONCOMING TRAFFIC. THE CRASH CUSHION CONNECTIONS ARE NOT DETAILED WITHIN THESE DRAWINGS, PLEASE CONTACT HIGHWAY CARE LTD. FOR MORE DETAILS.
- THE FULL HEIGHT OF HIGHWAYGUARD BARRIER 20FT SEGMENT IS 31.5". EACH SEGMENT IS LOWERED INTO POSITION WITH THE T-CONNECTION ALREADY ATTACHED TO THE END OF THE BARRIER THAT IS BEING JOINED TO THE RUN OF BARRIER. ENSURE ORIENTATION OF T-CONNECTOR ALLOWS ALIGNMENT PINS TO BE LOWERED ONTO NEXT SECTION. THE T-CONNECTOR ALLOWS THE BARRIER FOR ADJUSTMENTS, QUICK INSTALLATION, QUICK REMOVAL AND REPLACEMENT OF DAMAGED BARRIERS. MINIMUM INSTALLATION LENGTH OF HIGHWAYGUARD BARRIER IS 200'-0".
- THERE ARE SEVERAL METHODS OF ACHIEVING RADIUS IN A LENGTH OF HIGHWAYGUARD BARRIER. RADIUS CAN BE ACHIEVED USING VARIOUS T-CONNECTORS AND THUS ALLOWING THE HIGHWAYGUARD BARRIER TO FOLLOW THE DESIRED CURVATURE IN THE INSTALLATION, THESE TYPE OF T-CONNECTORS ARE, 2.5°, 5° AND 10° ANGLES. FOR FURTHER INFORMATION AND ADVICE CONTACT HIGHWAY CARE LTD.
- USING HIGHWAYGUARD BARRIER OR HIGHWAYGUARD BARRIER LDS ON BRIDGE STRUCTURES, POSSIBLE ANCHORING SHOULD TAKE PLACE OFF BRIDGE DECKS. ANY ANCHORING ON BRIDGE DECKS NEEDS TO BE AGREED IN ADVANCE WITH THE TECHNICAL EXPERT RESPONSIBLE FOR THE BRIDGE TO ENSURE IT IS NOT DAMAGED. IF ANCHORING EITHER SIDE OF A BRIDGE DECK EXPANSION JOINT, THEN THIS MOVEMENT MUST BE MIRRORRED IN THE BARRIER. FOR FURTHER INFORMATION AND ADVICE CONTACT HIGHWAY CARE LTD.
- THE HIGHWAYGUARD BARRIER SECTIONS CAN BE EQUIPPED WITH OPTIONAL WHEELSETS THAT ALLOW THE BARRIERS TO BE MANEUVERED WITHOUT LIFTING THE MACHINERY/EQUIPMENT SUCH AS INSTALLING IN TUNNELS OR AREAS WITH OVERHEAD RESTRICTIONS. THE WHEELSETS CAN BE RAISED AND LOWERED FROM THE TOP OF THE BARRIER USING A MANUAL WRENCH AND 1" SOCKET.
- THE HIGHWAYGUARD BARRIER HAS BEEN MASH TESTED, USING 1 3/8" DIA. DROP IN PIN ANCHORS AND EMBEDDED 1'-6" INTO ASPHALT. ALTERNATIVE GROUND EMBEDMENT CONDITIONS MAY BE ACCEPTABLE BUT MIGHT REQUIRE DIFFERENT ANCHOR SOLUTIONS, PLEASE CONTACT HIGHWAY CARE LTD. FOR FURTHER INFORMATION.
- ALL COMPONENTS ARE FULLY GALVANIZED.
- HIGHWAYGUARD BARRIER SYSTEMS SHALL BE ASSEMBLED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS DETAILED DRAWINGS, PROCEDURES AND SPECIFICATIONS. FOR ANY INSTALLATIONS OUTSIDE OF THE SCOPE OF THESE DRAWINGS, PLEASE CONTACT HIGHWAY CARE LTD. FOR DETAILS.
- FOR ANCHORING LAYOUTS FOR HIGHWAYGUARD AND HIGHWAYGUARD LDS, PLEASE SEE MANUFACTURER'S PRODUCT MANUAL OR CONTACT HIGHWAY CARE LTD. FOR INFORMATION.









	STANDARD SYSTEM	MINIMUM DEFLECTION SYSTEMS (LDS)
DESCRIPTION	ONLY ANCHORED AT THE FIRST AND ENDS OF THE BARRIER LENGTH	ANCHORS ARE STAGGERED EVERY 39'-4 1/2"
DEFLECTION AT MASH TL-3	64"	2'-3"
DEFLECTION AT MASH TL-4	71"	2'-7"

NOTE: SEE PRODUCT MANUAL OR CONTACT HIGHWAY CARE LTD. FOR MORE INFORMATION ON ANCHOR REQUIREMENTS FOR THE LENGTH OF BARRIER.


				Design Division Standard
<b>HIGHWAYGUARD SYSTEM</b> <b>STEEL BARRIER</b> <b>MASH TL-3 &amp; TL-4</b> <b>HIGHWAYGUARD-21</b>				
FILE: highwayguard21.dgn	DW: TxDOT	CK: KM	DW: SS	CK: XX
© TxDOT: JULY 2021	CONT	SECT	JOB	HIGHWAY
REVISIONS	049510		094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	39E	



DATE: 10/4/2021  
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\H20 42in RCP Repair (2384+80 WB)\STA  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



ITEM NO.	PART NUMBER	DESCRIPTION
①	SRP000036	HV2 SQUARE TOP RAIL
②	SRP000037	CONNECTOR
③	SRP000038	HV2 SKIN
④	SRP000039	HV2 END
⑤	SRP000040	HV2 FEET
⑥	SRP000041	CONCRETE BALLAST
⑦	SRP000043	HV2 LIFTING BAR
⑧	SRP000048	HV2 SPACER



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SAFEROADS HV2 BARRIER, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.

**GENERAL NOTES**

- FOR TECHNICAL AND APPLICATION SUPPORT PLEASE CONTACT SAFEROADS PTY, LTD, AT (859)469-0364, WEBSITE: www.saferoads.com.au OR www.hv2barrier.com.
- HV2 BARRIER HAS BEEN ACCEPTED BY FHWA AS A MASH TL-4 LONGITUDINAL BARRIER.
- STANDARD INSTALLATIONS IS A FREE STANDING TEMPORARY LONGITUDINAL BARRIER SYSTEM. HIGH CONTAINMENT AND LOW DEFLECTION INSTALLATIONS REQUIRE NO ANCHORING. NO MODIFICATIONS ARE NECESSARY OTHER THAN FAST DEPLOYMENT AND RETRIEVAL.
- OVERALL LENGTH PER BARRIER IS 19.2FT. AND WEIGHS 4,600LBS EACH. HV2 SAFETY BARRIER CAN BE DEPLOYED ON A HORIZONTAL RADIUS AS TIGHT AS 255.9FT/78M. HV2 SAFETY BARRIER INSTALLATIONS REQUIRE A MIN. DEPLOYMENT LENGTH OF 323.5FT/98.6M (17NO. HV2 BARRIERS) PLUS THE REQUIRED END TREATMENTS, TO SAFELY CONTAIN AND REDIRECT AT MASH TL3.
- SAFEROADS HV2 SAFETY BARRIER SHOULD NOT BE INSTALLED IF THERE IS:
  - CURVATURE TIGHTER THAN 262 FT (80m) RADIUS.
  - CROSS SLOPE STEEPER THAN 5%.
  - LONGITUDINAL SLOPE STEEPER THAN 5%.
  - CREST SHARPER THAN 5%.
  - DITCH SHARPER THAN 5%.
  - CURBS OR SIMILAR OBSTACLES RESTRICTING DEFLECTION.
- SAFEROADS HV2 SAFETY BARRIER COMPONENTS ARE MANUFACTURED IN SI [METRIC] UNITS. ENGLISH UNITS SHOWN ARE APPROXIMATE. ALL COMPONENTS ARE CONSTRUCTED FROM STEEL WITH CONCRETE BALLASTING.
- WHEN TAPERING HV2 SAFETY BARRIER OUTSIDE THE CLEAR ZONE, THE LENGTH OF NEED BEGINS AND ENDS 74FT/22.5M FROM THE ENDS OF THE SYSTEM FOR A MASH TL-3 DEPLOYMENT AND 164FT/50M FROM THE ENDS OF THE SYSTEM FOR A MASH TL-4 DEPLOYMENT.

SPEED	25°	20°	15°	10°	5°
62MPH	4'-10" [1.47]	3'-11" [1.18]	2'-11" [0.88]	2'-0" [0.59]	1'-0" [0.30]
56MPH	4'-5" [1.33]	3'-7" [1.07]	2'-8" [0.80]	1'-10" [0.54]	11" [0.27]
50MPH	3'-11" [1.18]	3'-2" [0.95]	2'-4" [0.71]	1'-7" [0.48]	10" [0.24]
43MPH	3'-5" [1.03]	2'-9" [0.83]	2'-1" [0.62]	1'-5" [0.42]	9" [0.21]
37MPH	2'-11" [0.89]	2'-4" [0.71]	1'-9" [0.53]	1'-3" [0.36]	8" [0.18]
31MPH	2'-6" [0.74]	2'-0" [0.59]	1'-6" [0.44]	1'-0" [0.30]	6" [0.15]
25MPH	2'-0" [0.59]	1'-7" [0.48]	1'-3" [0.36]	10" [0.24]	5" [0.12]

SPEED	15°	10°	5°
56MPH	7'-10" [2.37]	5'-3" [1.58]	2'-8" [0.79]
50MPH	7'-0" [2.11]	4'-8" [1.41]	2'-4" [0.71]
43MPH	6'-1" [1.85]	4'-1" [1.23]	2'-1" [0.62]
37MPH	5'-3" [1.58]	3'-6" [1.06]	1'-9" [0.53]
31MPH	4'-4" [1.32]	2'-11" [0.88]	1'-6" [0.44]
25MPH	3'-6" [1.06]	2'-4" [0.71]	1'-2" [0.35]


Texas Department of Transportation  
 Design Division Standard

**SAFEROADS HV2 SAFETY STEEL BARRIER MASH TL-4 HV2 BARRIER-21**


FILE: hv2barrier21.dgn	DN: TxDOT	CK: KM	DW: SS	CK: AG
© TxDOT: JULY 2021	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	39F	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2021  
 FILE: pw:\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\IH20 42 in RCP Repair (2384+80 WB)\STA




PLAN VIEW




ELEVATION VIEW  
 ZONEGUARD STANDARD UNIT x 50'-0"




PLAN VIEW




ELEVATION VIEW  
 ZONEGUARD STANDARD UNIT x 33'-4"




PLAN VIEW




ELEVATION VIEW  
 ZONEGUARD STANDARD UNIT x 16'-8"




PLAN VIEW



ELEVATION VIEW  
 ZONEGUARD EXPANSION UNIT x 46'-5 1/2"  
 (SEE GENERAL NOTE 5)



ZONEGUARD RADIUS UNITS



ZONEGUARD TYPICAL SECTION

**GENERAL NOTES**

- FOR TECHNICAL AND APPLICATION SUPPORT PLEASE CONTACT HILL & SMITH INC. AT 614-340-6294.
- ZONEGUARD HAS BEEN ACCEPTED BY FHWA AS A MASH TL-3 LONGITUDINAL BARRIER.
- STANDARD INSTALLATIONS REQUIRE ANCHORING AT EACH END OF THE RUN. MINIMUM DEFLECTION INSTALLATIONS REQUIRE ANCHORING AT 33'-4 CENTERS. NO MODIFICATIONS ARE NECESSARY OTHER THAN INCREASED ANCHORING.
- 50-0' UNITS CAN BE USED TO ACHIEVE DOWN TO AN 800' RADIUS CURVE. 16'-8" UNITS CAN BE USED TO ACHIEVE CURVES DOWN TO 250' RADIUS. SPECIAL SHORT UNITS (SHOWN) IN 2.5 DEGREE INCREMENTS CAN BE USED TO ACHIEVE DIRECTION CHANGES OR AT A FIXED RADIUS OF 47'-0".
- HILL & SMITH OFFERS AN EXPANSION UNIT THAT CAN BE USED ACROSS A BRIDGE EXPANSION JOINT OR TO ACCOMMODATE THERMAL EXPANSION. THE UNIT IS ANCHORED IN THE MIDDLE, AND ADJUSTED ACCORDING TO THE TEMPERATURE AT THE TIME OF INSTALLATION. THE EXPANSION JOINT CAN BE USED WITH ENGINEER APPROVAL. THE EXPANSION UNIT HAS NOT BEEN ASSESSED TO MASH CRITERIA.
- ANCHOR PINS ARE 1 1/4" DIAMETER. LENGTH IS 1'-8" FOR ASPHALT AND 1'-0" FOR CONCRETE. SEE ANCHORING TABLE FOR ADDITIONAL DETAILS.

	STANDARD INSTALLATION	MINIMUM DEFLECTION INSTALLATION CONCRETE	MINIMUM DEFLECTION INSTALLATION ASPHALT
	FOUR ANCHORS AT END OF THE RUN	TWO ANCHORS (ONE EACH SIDE) EVERY 33'-4"	TWO ANCHORS (ONE EACH SIDE) EVERY 33'-4"
MASH TL-3 DEFLECTION (2270 KG TRUCK @ 25° & 100 KM/HR)	6'-10"	5"	2'-0"

**EXPECTED DEFLECTION TABLE**

DESCRIPTION	ASPHALT	CONCRETE
1 1/4" PIN ANCHOR	1'-8" LONG, MINIMUM ASPHALT COVER OF 3"	1'-0" LONG, MINIMUM CONCRETE COVER OF 6"
1 1/4" ALL THREAD ANCHOR	-	1'-0" LONG, MINIMUM EMBEDMENT OF 6"

**ANCHORING TABLE**

ALTERNATE ANCHORING METHODS CERTIFIED BY HILL & SMITH, INC. ARE AVAILABLE PER FHWA APPROVAL LETTER.

**Texas Department of Transportation**



**Design Division Standard**

## ZONEGUARD SYSTEM STEEL BARRIER MASH TL-3 ZONEGUARD-19


FILE: zoneguard19	DN: TxDOT	CK: KM	DW: VP	CK: CGL
© TxDOT: JULY 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	39G	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2021  
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\H20 42in RCP Repair (2384+80 WB)\STA



Note:  
 V1 Bars above the drainage slots may be bent to accommodate 1 1/2" clear cover as directed by the Engineer.









All precast barrier edges shall have a 3/4" chamfer or tooling radius.

**Single Slope Concrete Traffic Barrier**

Precast SSCB barrier may be connected to cast-in-place SSBC. The joint connection "Types" may be used in the cast-in-place barrier, to match the precast barrier connection.


**General Notes**

- Concrete shall be Class H with a minimum compressive strength of 3,600 psi.
- Where used, rebar reinforcement shall be Grade 60 and conform to ASTM A615.
- Precast barrier length shall be 30 ft. unless otherwise specified on the plans.
- All precast barrier edges shall have a 3/4" chamfer or a tooling radius.
- All concrete, reinforcement, joint connection systems, grout etc. as shown, are considered as part of the barrier payment.
- Conduit trough when required shall be shown elsewhere on the plans, or as directed by the Engineer.
- Regardless of the method of handling, barrier lifting points shall be approx. 7.5 feet from the ends of the barrier. Lifting devices and attachments to barrier sections shall be approved by the Engineer.
- Surface finishing and grouting (where required) shall be two parts sand one part cement with enough water to make the mixture plastic. Grouting shall be done in a manner that will assure a smooth surface. Surface finishing shall be considered subsidiary to the various bid items.
- All steel assemblies shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."




**CONNECTION PLATE DETAILS**

One (1) Plate required per assembly. Four (4) required per Joint. All steel fittings for joint Type X shall be galvanized after fabrication in accordance with Item 445.



Two (2) Threaded Rods (Or Equivalent Hex Hd. Bolts) (w/ Two (2) PL 3/8 x 3 x 3 Plate Washers & Two (2) Std Hex Nuts) required per Joint.


Weight of one precast 30 ft. (SSCB) segment = Approx. 10.5 Tons or 717 lbs per ft.



**Welded Wire Reinforcement (WWR) Option for Bars R and V1**

**(WWR) General Notes**

- Deformed Welded Wire Reinforcement (WWR) shall conform to ASTM A497.
- Welded wire cage may be cut or bent to accommodate the Type X joint connection and drainage slots, as directed by the Engineer.
- All reinforcement shall comply with Item 440, "Reinforcing Steel."
- Combinations of reinforcing steel and WWR will be permitted, as directed by the Engineer. The dimension from the end of the barrier section to the first wire shall not exceed 3".




Texas Department of Transportation Design Division Standard


**SINGLE SLOPE CONCRETE BARRIER**  
 PRECAST BARRIER (TYPE 1)  
 SSCB(2)-10

FILE: sscb210.dgn	DN: TxDOT	CR: AM	DW: BD	CK:
© TxDOT December 2010	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495 10	094	IH 20	
DIST	COUNTY	SHEET NO.		
ATL	HARRISON	39K		


DATE: 10/4/2021  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\H20 42 in RCP Repair (2384+80 WB)\STA



**END VIEW**  
 "QUICK-BOLT" POCKET LOCATIONS




**ELEVATION VIEW**  
 "QUICK-BOLT" (SSCB)  
 See Manufacturer's shop drawing for additional details




**ELEVATION VIEW SHOWING JOINT CONNECTION**  
 "QUICK-BOLT"


**Joint Connection (Type Q)**



**TOP VIEW**  
 PRECAST (SSCB) WITH J-J HOOKS  
 See Manufacturer's shop drawing for additional details



**VIEW FROM ABOVE**  
 J-J HOOK CONNECTION




**END VIEW**

**Proprietary Joint Connections (SSCB)**


Two proprietary joint connections are acceptable as alternates to the (Type X) connection shown, here on. These joint connections types are:

J-J Hooks by Easi-Set Industries, (800)547-4045  
 Quick-Bolt by Bexar Concrete, (210)497-3773


If one of these connection systems are exclusively specified in the plans, prior approval for sole source use must be obtained. Details of the connection components and barrier reinforcement for these systems, will be shown on the manufacturer's shop drawing(s) furnished to the Engineer.




**SECTION A-A**  
 Showing (Type R)  
 Rebar Grid




**ELEVATION**  
 V1 Bars (See Sheet 1)



**TOP VIEW**  
 JOINT CONNECTION  
 Typical at both ends of barrier segment



**(#4) V2 BARS**  
 6 ~ two piece bars per barrier segment




**WELDED REBAR GRID**

**Joint Connection (Type R)**


SHEET 2 OF 2

		<i>Design Division Standard</i>	
<b>SINGLE SLOPE CONCRETE BARRIER</b>			
<b>PRECAST BARRIER (TYPE 1)</b>			
<b>SSCB(2) - 10</b>			
FILE: sscb210.dgn	DN: TXDOT	CK: AM	DW: VP
© TXDOT December 2010	CONT SECT	JOB	HIGHWAY
REVISIONS	0495 10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	39L	


DATE: 10/4/2021  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\H20 42 in RCP Repair (2384+80 WB)\STA



**DETAIL 1**  
 Precast SSCB (42")  
 Showing hole locations



**DETAIL 2**  
 Placement on (ACP)  
 Asphalt Conc. Pavement  
 or Treated Base Material  
 (30" Pin required)




**DETAIL 3**  
 Bridge Deck or CRCP  
 (27" Pin required).


**GENERAL NOTES**

1. These details provide a method of laterally restraining precast concrete barrier to limit deflections under normally expected passenger vehicle impacts. These details are intended for use in work zones, primarily on bridge decks, or pavement where temporary barrier must be placed less than 2 ft. from the longitudinal edge of the deck or dropoff and parallel to the direction of travel. Other applications of these details are acceptable as directed by the Engineer.
2. Each precast concrete barrier section shall have a minimum of four or total of eight 1 3/8 in. ID holes formed or cored through the barrier. The center lines of the holes are shown in the hole location detail. If rebar is encountered, the entry point may be shifted 2" plus or minus longitudinally along the barrier. The eight holes are spaced along the length of the barrier as shown in Detail 1.
3. The drilling of the travel surface is accomplished by placing the pre-drilled barrier section on the travel surface in the desired position. Then the hole is drilled with the bit passing through the hole in the barrier. The bit is to be inserted into the hole in the barrier so that the travel surface is drilled to a point which is slightly more than the pin length.
4. Note that steel washers have been welded to the top of the steel pins to aid in the removal of the pins, when the barrier is removed.
5. See SSCB(2) standard sheet for reinforcement requirements and joint connection types.
6. The forming or coring of holes in the barrier, drilling of holes in bridge deck or pavement, fabrication and materials for the 1/4 in. pins, installation of pins, and any repair to the barrier shall be considered as subsidiary to the barrier bid items.
7. The barrier and travel surface will be repaired as directed by the Engineer in accordance with Item 429, "Concrete Structure Repair."
8. All steel pins shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."
9. Weight of barrier is approx. 700 lbs per foot.


**CORE DRILLING EXISTING BARRIER**  
 Core drilling existing concrete barrier is permitted. Holes shall be drilled with coring or masonry drilling type equipment. Percussion (star) drilling shall not be used. A special drill bit (to cut through existing reinforcing) will likely be required. Spalls in the concrete exceeding 1/2" shall be patched.




**HOLE LOCATION DETAIL**




**VIEW A-A**



**(30") PIN DETAIL**  
 See Detail 2



**(27") PIN DETAIL**  
 See Detail 3



Note:  
 The "Bolt Through" method of pinning precast barrier on a bridge deck, is primarily used in a permanent location that requires limited barrier deflection.

**PRECAST SSCB (BOLT THROUGH) PLACEMENT OVER LONGITUDINAL EXPANSION JOINT**

For bolt through locations, use the (Front) hole locations shown on Detail 1.

Note:  
 Steel washer welded to pin at 29 degree angle so that the washer is flush with barrier surface. (See View A-A)



		<b>Design Division Standard</b>	
<h1>SINGLE SLOPE CONCRETE BARRIER</h1> <h2>PRECAST BARRIER (TYPE 1) PINNED PLACEMENT</h2> <h3>SSCB(5) - 10</h3>			
FILE: sscb510.dgn	DN: TXDOT	CK: AM	DW: BD
© TXDOT December 2010	CONT SECT	JOB	HIGHWAY
REVISIONS	0495 10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	39M	

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 10/4/2021

FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\IH20 42in RCP Repair (2384+80 WB)\STA

SYSTEM SHOWN - ABSORB-M TL-3





THE ABSORB-M IS A NON-REDIRECTIVE, GATING, CRASH CUSHION DESIGNED TO MEET THE LATEST TL-3 & TL-2 MASH REQUIREMENTS.

THE SYSTEM IS DESIGNED TO ACCOMMODATE A VARIETY OF F-SHAPE AND SINGLE SLOPE CONCRETE BARRIERS. CONTACT THE MANUFACTURER FOR GUIDANCE REGARDING OTHER ALLOWABLE SHAPES.

TEST LEVEL	NUMBER OF ELEMENTS	EFFECTIVE LENGTH	MAXIMUM LENGTH
TL-2	2	14' - 7 3/4"	17' - 4"
TL-3	3	20' - 11 3/4"	23' - 8"

NOTE: CROSS SLOPES OF UP TO 8% (OR 1:12 SLOPE) CAN BE ACCOMMODATED WITH STANDARD HARDWARE SHOWN WITHIN THE INSTRUCTIONS MANUAL. FOR SLOPES WITH EXCESS OF 8% (OR 1:12) CONTACT, LINDSAY TRANSPORTATION SOLUTIONS.



NOTE: APPLY A HIGH REFLECTIVE DECAL TO THE NOSE PLATE. DELINEATION DECAL ORIENTATION IS SHOWN ON THE CONSTRUCTION PLAN SET AND SHALL BE IN ACCORDANCE WITH THE TEXAS MUTCD FOR (TRAFFIC CONTROL DEVICES). DECALS ARE AVAILABLE FOR TRAFFIC FLOW ON THE LEFT-SIDE, BOTH -SIDES AND RIGHT-SIDE.

**GENERAL NOTES**

- FOR SPECIFIC INFORMATION REGARDING THE INSTALLATION AND TECHNICAL GUIDANCE, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800. 180 RIVER ROAD, RIO VISTA, CA 94571
- THE ABSORB-M SYSTEM IS ONLY APPROVED FOR USE IN (TEMPORARY WORK ZONE) LOCATIONS.
- THE ABSORB-M IS A WATER FILLED NON-REDIRECTIVE, GATING CRASH CUSHION THAT DOES NOT NEED TO BE ATTACHED TO A FOUNDATION AND CAN BE INSTALLED ON TOP OF CONCRETE, ASPHALT, OR ANY SURFACE CAPABLE OF BEARING THE WEIGHT OF THE SYSTEM.
- MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
- THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
- THE ABSORB-M SHOULD BE LOCATED APPROXIMATELY PARALLEL WITH THE BARRIER.
- THE USE OF THE ABSORB-M IS RESTRICTED TO A BARRIER HEIGHT OF UP TO 42 INCHES.
- DO NOT ADD WATER TO FRONT ELEMENT (TL-2 OR TL-3 UNIT).

BILL OF MATERIALS (BOM) ABSORB-M TL-3 & TL-2 SYSTEMS			QTY	QTY
ITEM #	PART NUMBER	PART DESCRIPTION	TL-2 SYSTEM	TL-3 SYSTEM
1	BSI-1809036-00	TRANSITION - (GALV)	1	1
2	BSI-1808002-00	PRE-ASSEMBLED ABSORBING (ELEMENTS)	2	3
3	BSI-4004598	FILL CAPS	8	12
4	BSI-4004599	DRAIN PLUGS	2	3
5	BSI-1809053-00	TENSION STRAP - (GALV)	8	12
6	BSI-2001998	C-SCR FH 3/8-16 X 1 1/2 GR5 PLT	8	12
7	BSI-2001999	C-SCR FH 3/8-16 X 1 GR5 PLT	8	12
8	BSI-1809035-00	MIDNOSE - (GALV)	1	1
9	BSI-1808014-00	NOSE PLATE	1	1
10	BSI-1809037-00	TRANSITION STRAP (LEFT-HAND) - (GALV)	1	1
11	BSI-1809038-00	TRANSITION STRAP (RIGHT-HAND) - (GALV)	1	1
12	BSI-1808005-00	PIN ASSEMBLY	8	10
13	BSI-2002001	ANC MECH 5/8-11X5 (GALV)	6	6
14	ABSORB-M	INSTALLATION AND INSTRUCTIONS MANUAL	1	1

\* COMPONENTS PRE-ASSEMBLED WITH ELEMENT ASSEMBLY


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE ABSORB-M, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.

**SACRIFICIAL**


		Design Division Standard	
<b>LINDSAY TRANSPORTATION SOLUTIONS CRASH CUSHION (MASH TL-3 &amp; TL-2) TEMPORARY - WORK ZONE ABSORB (M) - 19</b>			
FILE: absorbm19	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2019	CONT SECT	JOB	HIGHWAY
REVISIONS	0495 10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	39N	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2021  
 FILE: pw:\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136.4 - DesignMaster Design Files\H20 42in RCP Repair (2384+80 WB)\STA




**PLAN VIEW**




**ELEVATION VIEW**

**GENERAL NOTES**

1. REFER TO THE INSTALLATION MANUAL FOR SPECIFIC SYSTEM ASSEMBLY AND MODULE ORIENTATION. FOR ADDITIONAL INFORMATION, CONTACT TRAFFIX, INC. AT (949) 361-5663.
2. THE SLED SYSTEM IS A MASH APPROVED TEST LEVEL 3 (TL-3) CRASH CUSHION APPROVED FOR USE IN TEMPORARY WORK ZONES. THE SLED SYSTEM IS A NON-REDIRECTIVE, GATING CRASH CUSHION THAT DOES NOT NEED TO BE ATTACHED TO THE GROUND AND CAN BE INSTALLED ON CONCRETE, ASPHALT, GRAVEL OR COMPACTED SOIL.
3. MAXIMUM PERMISSIBLE CROSS SLOPE IS 8° (DEGREES) (14%).
4. THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
5. THE SLED SYSTEM CAN BE ATTACHED TO:
  - CONCRETE BARRIER, TEMPORARY OR PERMANENT, 45" MAXIMUM HEIGHT
  - STEEL BARRIER
  - PLASTIC BARRIER
  - CONCRETE BRIDGE ABUTMENTS
  - W-BEAM GUARD RAIL
  - THRIE BEAM GUARD RAIL




**SECTION A-A**



**NOTE:**  
SEE INSTALLATION MANUAL FOR CUSTOMIZED DELINEATION NOSE SHEETING FOR DECAL PLACEMENT.

TEST LEVEL	NUMBER OF SECONDARY MODULES	SYSTEM LENGTH
TL-3	3	25' 3"

BILL OF MATERIAL		
PART NUMBER	DESCRIPTION	QTY: TL-3
45131	TRANSITION FRAME, GALVANIZED	1
45150	TRANSITION PANEL, GALVANIZED	2
45147-CP	TRANSITION SHORT DROP PIN W/ KEEPER PIN, GALVANIZED	2
45148-CP	TRANSITION LONG DROP PIN W/ KEEPER PIN, GALVANIZED	1
45050	ANCHOR BOLTS	9
12060	WASHER, 3/4" ID X 2" OD	9
45044-Y	SLED YELLOW WATER FILLED MODULE	3
45044-YH	SLED YELLOW "NO FILL" MODULE	1
45044-S	CIS (CONTAINMENT IMPACT SLED), GALVANIZED	1
45043-CP	T-PIN W/ KEEPER PIN	4
18009-B-I	FILL CAP W/ "DRIVE BY" FLOAT INDICATOR	3
45033-RC-B	DRAIN PLUG	3
45032-DPT	DRAIN PLUG REMOVAL TOOL	1



**SLED TRANSITION COMPONENTS FOR ATTACHMENT TO CMB**

**NOTE:**  
SEE MANUFACTURER'S INSTALLATION MANUAL FOR FURTHER DETAILS.

TRANSITION OPTIONS
SLED TRANSITION TO CONCRETE TRAFFIC BARRIER (TEMPORARY OR PERMANENT)
SLED TRANSITION TO STEEL TRAFFIC BARRIER (CONTACT MFGR FOR PROPER TRANSITION)
SLED TRANSITION TO PLASTIC TRAFFIC BARRIER (CONTACT MFGR FOR PROPER TRANSITION)
SLED TRANSITION TO W-BEAM OR THRIE BEAM GUARD RAIL (CONTACT MFGR FOR PROPER TRANSITION)
SLED TRANSITION TO CONCRETE BRIDGE ABUTMENT

**NOTE:**  
THIS STANDARD IS A BASIC REPRESENTATION OF THE SLED, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.


**SACRIFICIAL**

Design Division Standard

SLED  
 CRASH CUSHION  
 TL-3 MASH COMPLIANT  
 (TEMPORARY, WORK ZONE)  
 SLED-19

FILE: sled19.dgn	DN: TxDOT	CK: KM	DW: VP	CK:
© TxDOT: DECEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
DIST	COUNTY	SHEET NO.		
ATL	HARRISON	390		


DATE: 9/17/2021 4:25:36 PM  
 FILE: \\atl\project\wiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136.4 - Design\Master Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn



EXISTING HOLE BEHIND HEADWALL TO BE FILLED WITH EMBANKMENT (2CY)

IH 20  
 STA 2116+48.71  
 2 - 10' X 8' MBC  
 32° 29' 35.14"N 94° 09' 37.51"W

- NOTES:
1. REMOVE EXISTING 225' MBGF (TIM POST), 37.5' MBGF (STL POST), SGT AND TAS PER LOCATION SHOWN.
  2. PLACE MBGF (TIM POST) AND (STL POST), SGT AND DAT WITH QUANTITIES AS SHOWN. PLACE NEW MBGF (STL POST) IN SAME LOCATION AS EXISTING STEEL POSTS. VERIFY LENGTH OF MBGF (STL POST) NEEDED IN FIELD BEFORE ORDERING.
  3. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT (TY A) TO PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).



*Glenn R. Yowell, P.E.*  
 9/17/2021


**MBGF LAYOUT  
 SHEET 1 OF 8**

NBI: 191030049510135

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	40
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	



DATE: 9/17/2021 4:26:10 PM  
 FILE: \\atl\project\wiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136.4 - Design\Master Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn



IH 20  
 STA 2116+48.71  
 2 - 10'X10' MBC  
 32° 29' 35.14"N 94° 09' 37.51"W

STATE OF TEXAS  
 GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
*Glenn R. Yowell, P.E.*  
 9/17/2021


- NOTES:
1. REMOVE EXISTING 675' MBGF (TIM POST), SGT AND TAS PER LOCATION SHOWN. REMOVE EXISTING MOW STRIP.
  2. PLACE MBGF (TIM POST), SGT AND DAT WITH QUANTITIES AS SHOWN.
  3. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT TY A TO PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).

**MBGF LAYOUT  
 SHEET 2 OF 8**

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	41
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	


NBI: 191030049510137  
 NBI: 191030049510134

DATE: 9/17/2021 4:27:09 PM  
 FILE: \\atl\projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design Master Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn



IH 20  
 STA 2205+57.75  
 6 - 10' X 10' MBC  
 32° 29' 14.67"N 94° 07' 56.78"W

- NOTES:
1. REMOVE EXISTING 250' MBGF (TIM POST), SGT AND TAS PER LOCATION SHOWN. REMOVE EXISTING MOW STRIP.
  2. PLACE MBGF (TIM POST), SGT AND DAT WITH QUANTITIES AS SHOWN.
  3. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT TY A TO PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).




*Glenn R. Yowell, P.E.*  
 9/17/2021

**MBGF LAYOUT  
 SHEET 3 OF 8**

NBI: 191030049510111

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	42
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	

DATE: 9/17/2021 4:27:41 PM  
 FILE: \\atdof.projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn



IH 20  
 STA 2230+41.92  
 3 - 10' X 8' MBC  
 32° 29' 09.09"N 94° 07' 28.78"W

- NOTES:
1. REMOVE EXISTING 162.5' MBGF (TIM POST), 37.5' MBGF (STL POST), SGT AND TAS PER LOCATION SHOWN.
  2. PLACE MBGF (TIM POST) AND (STL POST), SGT AND DAT WITH QUANTITIES AS SHOWN. PLACE NEW MBGF (STL POST) IN SAME LOCATION AS EXISTING STEEL POSTS. VERIFY LENGTH OF MBGF (STL POST) NEEDED IN FIELD BEFORE ORDERING.
  3. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT (TY A) TO PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).




9/17/2021

NBI: 191030049510114

**MBGF LAYOUT  
 SHEET 4 OF 8**

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	43
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	

DATE: 9/17/2021 4:28:13 PM  
 FILE: \\atl\tdot\projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn




- NOTES:
1. REMOVE EXISTING 112.5' MBGF (TIM POST), SGT AND TAS PER LOCATION SHOWN. REMOVE EXISTING MOW STRIP.
  2. PLACE MBGF (TIM POST), SGT AND DAT WITH QUANTITIES AS SHOWN.
  3. SEE GF(31)MS-19 STANDARD FOR DIMENSIONS OF MOW STRIP TO BE PLACED.
  4. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT TY A TO PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).

STATE OF TEXAS  
 GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
*Glenn R. Yowell, P.E.*  
 9/17/2021

**MBGF LAYOUT  
 SHEET 5 OF 8**

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	44
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	

DATE: 9/17/2021 4:29:17 PM  
 FILE: \\atl\projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn



IH 20  
 STA 2271+50  
 BRIDE COLUMNS  
 32° 29' 01.09"N 94° 06' 40.69"W


- NOTES:
1. REMOVE EXISTING 112.5' MBGF (TIM POST), SGT AND TAS PER LOCATION SHOWN. REMOVE EXISTING MOW STRIP.
  2. PLACE MBGF (TIM POST), SGT AND DAT WITH QUANTITIES AS SHOWN.
  3. SEE GF(31)MS-19 STANDARD FOR DIMENSIONS OF MOW STRIP TO BE PLACED.
  4. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT TY A TO PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).

STATE OF TEXAS  
 GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
*Glenn R. Yowell, P.E.*  
 9/17/2021

**MBGF LAYOUT  
 SHEET 6 OF 8**

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	45
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	

DATE: 9/17/2021 4:30:03 PM  
 FILE: \\atdof.projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn




- NOTES:
1. REMOVE EXISTING 112.5' MBGF (TIM POST), SGT AND TAS PER LOCATION SHOWN. REMOVE EXISTING MOW STRIP.
  2. PLACE MBGF (TIM POST), SGT AND DAT WITH QUANTITIES AS SHOWN.
  3. SEE GF (31)MS-19 STANDARD FOR DIMENSIONS OF MOW STRIP TO BE PLACED.
  4. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT TO BE PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).

STATE OF TEXAS  
 ★  
 GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
*Glenn R. Yowell, P.E.*  
 9/17/2021

**MBGF LAYOUT  
 SHEET 7 OF 8**

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	46
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	

DATE: 9/17/2021 4:30:44 PM  
 FILE: \\txdot\projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEETS\000 MBGF LAYOUTS.dgn



IH 20  
 STA 2348+00  
 BRIDGE COLUMNS  
 32° 28' 44.57"N 94° 05' 13.67"W


- NOTES:
1. REMOVE EXISTING 112.5' MBGF (TIM POST), SGT AND TAS PER LOCATION SHOWN. REMOVE EXISTING MOW STRIP.
  2. PLACE MBGF (TIM POST), SGT AND DAT WITH QUANTITIES AS SHOWN.
  3. SEE GF(31)MS-19 STANDARD FOR DIMENSIONS OF MOW STRIP TO BE PLACED.
  4. SEE QUANTITY SUMMARIES FOR ADDITIONAL EMBANKMENT TO BE PLACED BEHIND MOW STRIP (CALCULATED AT 0.76 CY/LF).

STATE OF TEXAS  
 ★  
 GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
*Glenn R. Yowell, P.E.*  
 9/17/2021


**MBGF LAYOUT  
 SHEET 8 OF 8**

Texas Department of Transportation © 2021			
CONTROL	SECTION	JOB	SHEET NO.
0495	10	094	47
DIST	COUNTY	HIGHWAY	
ATL	HARRISON	IH20	

CKS  
 DMF  
 CKS  
 DNF




PAVEMENT REPAIR DETAIL




SHOULDER REPAIR DETAIL


(FOR BEGIN/END LIMITS OF SHOULDER REPAIR SEE TCP CULVERT REPLACEMENT SHEET.)



SECTION A-A  
FLEXIBLE PAVEMENT STRUCTURE REPAIR DETAIL




SECTION B-B  
SHOULDER STRUCTURE REPAIR DETAIL




CONCRETE COLLAR DETAIL

- NOTE:
1. SEE REPCP-14 FOR CONCRETE PAVEMENT REPAIR DETAILS.
  2. SEE TCP CULVERT REPLACEMENT SHEET, TCP DETAILS SHEET, AND CULVERT LAYOUT SHEET FOR ADDITIONAL INFORMATION.
  3. PAVEMENT REPAIR LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER DURING CONSTRUCTION.



*Glenn R. Yowell, P.E.*  
10/5/2021

**MISCELLANEOUS  
DETAILS**




CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	48	

NOT TO SCALE

DATE:  
 FILE:



DATE: 10/5/2021 9:47:10 AM  
 FILE: pw:\txdot\projectwiseonline.com\TXDOT15\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136.v4 - DesignMaster Design Files\01 PLANSHEET\000 ROADWAY DETAILS.dwg





① SEE CSJ 0495-10-098 (SEE #9),  
 VOLUME 1 OF 2 OF CCSJ 0495-08-136, ETC  
 FOR MORE INFORMATION

**SMA TRANSITION FOR PFC OVERLAY ①**

PLANE 2" TO 3.5" IN THE FOLLOWING SECTIONS  
 BEGIN TAPER: STA. 2087+64 TO STA. 2089+14 WB

PLANE 3.5" IN THE FOLLOWING SECTIONS  
 STA. 2089+14 TO STA. 2091+50 WB



**SMA TRANSITION FOR PFC OVERLAY ①**

PLANE 3.5" TO 2" IN THE FOLLOWING SECTIONS  
 END TAPER: STA. 2091+50 TO STA. 2093+00 WB

**ROADWAY DETAILS**


SHEET 1 OF 2

Texas Department of Transportation  
 © 2021

CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		48A

NOT TO SCALE

DATE: 10/5/2021 9:47:40 AM  
 FILE: pw:\dot\projectwiseonline.com:TXDOT\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\01 PLANSHEETS\000 ROADWAY DETAILS.dwg




SMA TRANSITION FOR PFC OVERLAY ①


PLANE 2" TO 3.5" IN THE FOLLOWING SECTIONS  
 BEGIN TAPER: STA. 2429+79 TO STA. 2431+29 WB

PLANE 3.5" IN THE FOLLOWING SECTIONS  
 STA. 2431+29 TO STA. 2449+50 WB

① SEE CSJ 0495-10-098 (SEE #10),  
 VOLUME 1 OF 2 OF CCSJ 0495-08-136, ETC  
 FOR MORE INFORMATION



*Glenn R. Yowell, P.E.*  
 10/5/2021



SMA TRANSITION FOR PFC OVERLAY ①

PLANE 3.5" TO 2" IN THE FOLLOWING SECTIONS  
 END TAPER: STA. 2449+50 TO STA. 2451+00 WB

ROADWAY  
 DETAILS




SHEET 2 OF 2



CONT	SECT	JOB	HIGHWAY
0495	10	094	IH 20
DIST	COUNTY		SHEET NO.
ATL	HARRISON		48B

NOT TO SCALE


DATE: 10/5/2021 10:33:52 AM  
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\IH20\2 in RCP\Repa\m\2384+80.WB\NCU



- NOTES:**
- SEE "TCP CULVERT REPLACEMENT", "TCP DETAILS", AND "MISCELLANEOUS DETAILS" SHEETS FOR ADDITIONAL INFORMATION.
  - EXISTING PIPE SLOPE AND FLOWLINE ELEVATIONS TAKEN FROM 0495-10-001 (DATED 4/7/1961), TO BE FIELD VERIFIED.
  - ADDITIONAL WORK TO BE DONE IN THIS AREA AFTER PIPE REPLACEMENT IS SHOWN ELSEWHERE IN THE PLANS.

CONCRETE PAVEMENT REPAIR AREA  
 APPROX. 107 SY  
 (SEE CONC PVMNT REPAIR DETAILS)


FLEXIBLE PAVEMENT REPAIR AREA  
 APPROX. 63 SY  
 (SEE FLEX. PVMNT. REPAIR DETAILS)



STATE OF TEXAS  
 GLENN R. YOWELL  
 92077  
 LICENSED PROFESSIONAL ENGINEER  
*Glenn R. Yowell, P.E.*  
 10/5/2021


**CULVERT LAYOUT**

STA. 2384+80  
 EXISTING: 1-62' x 42" RCP  
 PROPOSED: 1-SET (TY I) (42IN) (RCP) (6:1) (C)  
 1-42" X 56' RCP (CL III)  
 (SETP-FW-0)  
 (PIPE RUNNERS REQUIRED)




CONT	SECT
0495	10
JOB	HIGHWAY
094	IH 20
DIST	SHEET NO.
ATL	48C

DATE: 9/17/2021  
 FILE: \\txdot.projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 GF (31)-19.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




**TYPICAL POST PLACEMENT**




**ELEVATION MID-SPAN RAIL SPLICE**

NOTE: \*\* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




**ELEVATION 25' - 0" (NOM.) W-BEAM SECTION**

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




**BUTTON HEAD BOLT**

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



**MID-SPAN RAIL SPLICE DETAIL**

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.




**WOOD BLOCK TO ROUND WOOD POST**      **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.

- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
  2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
  3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
  4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
  7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
  8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
  9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
  10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
  12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
  13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
  14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

\* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



**LOW FILL CULVERT POST**


- NOTE: TWO INSTALLATION OPTIONS.
1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
  2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.

				Design Division Standard
<b>METAL BEAM GUARD FENCE</b> <b>TL-3 MASH COMPLIANT</b> <b>GF (31) - 19</b>				
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	49	

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.  
 DATE: 9/17/2021  
 FILE: \\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 GF (31)\DAT-19.dgn










**DOWNSTREAM ANCHOR TERMINAL (DAT)**

NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.

- GENERAL NOTES**
1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
  2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
  3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
  4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
  5. REFER TO GF(31) SHEET FOR TERMINAL CONNECTION DETAILS.

**MOW STRIP INSTALLATION**  
 IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.

#	(DAT) PARTS LIST	QTY
1	STEEL FOUNDATION TUBE	2
2	DAT TERMINAL POST	2
3	CHANNEL STRUT	2
4	TERMINAL RAIL ELEMENT	1
5	SHELF ANGLE BRACKET	1
6	BCT BEARING PLATE	1
7	BCT POST SLEEVE	1
8	GUARDRAIL ANCHOR BRACKET	1
9	(ROUNDED) W-BEAM END SECTION	1
10	BCT CABLE ANCHOR	1
11	RECESSED NUT, GUARDRAIL	20
12	1 1/4" BUTTON HEAD BOLT	4
13	10" BUTTON HEAD BOLT	2
14	5/8" X 2" HEX HEAD BOLT	8
15	5/8" X 8" HEX HEAD BOLT	4
16	5/8" X 10" HEX HEAD BOLT	2
17	5/8" FLAT WASHER	18




Design Division Standard

**METAL BEAM GUARD FENCE  
 (DOWNSTREAM ANCHOR TERMINAL)  
 TL-3 MASH COMPLIANT  
 GF (31) DAT-19**

FILE: gf31dat19.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	049510	094	IH	20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	50	


DATE: 9/17/2021  
 FILE: \\txdot.projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 GF (31)MS-19.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



Note: See SGT standard sheets for proper installation and length of need requirements.

**GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS**

Note: Site Condition(s)  
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.  
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




**PLAN**

GF(31) shown with Mow Strip  
 (See GF(31) standard sheet for proper installation)


**GENERAL NOTES**

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type I or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




**SECTION A-A**

Typical




**MOW STRIP DETAIL**

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




**CURB OPTION (1)**

This option will increase the post embedment throughout the system.



**CURB OPTION (2)**


Curb shown on top of mow strip



**CURB OPTION (3)**

		Design Division Standard	
<b>METAL BEAM GUARD FENCE (MOW STRIP)</b> <b>TL-3 MASH COMPLIANT</b> <b>GF (31)MS-19</b>			
FILE: gf31ms19.dgn	DN:TXDOT	CK:KM	DW:VP
©TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0495 10	094	IH 20
	DIST	COUNTY	SHEET NO.
	ATL	HARRISON	51

DATE: 9/17/2021  
 FILE: pw:\txdot.projects\atl\Design Projects\049510094 Lets with 0495-08-136.v4 - DesignMaster Design Files\04 STANDARDS\000 SGT(10S)31-16.dgn



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; Soft+Stop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MBOG STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - IT IS ACCEPTABLE TO INSTALL THE Soft+Stop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
  - DO NOT ATTACH THE Soft+Stop SYSTEM DIRECTLY TO A RIGID BARRIER.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE Soft+Stop SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

**NOTE: A** THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3'-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

**NOTE: B** PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

**NOTE: C** W-BEAM SPLICE LOCATED BETWEEN LINE POST (4) AND LINE POST (5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	Soft+Stop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	Soft+Stop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	Soft+Stop DOWNSTREAM W-BEAM RAIL (12GA) (25' - 0")
15205A	1	POST #0 - ANCHOR POST (6' - 5 3/8")
15203G	1	POST #1 - (SYTP) (4' - 9 1/2")
15000G	1	POST #2 - (SYTP) (6' - 0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6' - 0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT
HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B

Design Division Standard

## TRINITY HIGHWAY SOFTSTOP END TERMINAL MASH - TL-3 SGT (10S) 31-16


FILE: sgt10s3116	DW: TXDOT	CK: KM	DW: VP	CK: MB/VP
© TXDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	049510	094	IH	20
DIST	COUNTY	SHEET NO.		
ATL	HARRISON	52		

**NOTE:** THIS STANDARD IS A BASIC REPRESENTATION OF THE Soft+Stop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.







DATE: 9/17/2021  
 FILE: \\txdot\projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 SGT(12S)31-18.dgn  
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
  - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
i	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

**Design Division Standard**


## SINGLE GUARDRAIL TERMINAL

### MSKT-MASH-TL-3


### SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
DIST	COUNTY		SHEET NO.	
ATL	HARRISON		54	

DATE: 9/17/2021  
 FILE: \\txdot\projectwiseonline\ine.com\TXDOTS\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 SGT(13S)31-18.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, AND REFER TO THE LATEST ROADWAY MBSG STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - THE EXISTING SKT 31" STANDARD STEEL POST SYSTEM MUST BE THOROUGHLY INSPECTED, AND DETERMINED TO BE INTACT, AND FREE OF ANY DAMAGE OR DEFECTS BEFORE RETROFITTING. THIS INSPECTION INCLUDES COMPLETING THE MSKT RETROFIT INSPECTION CHECKLIST FOR THE EXISTING SKT 31" STEEL POST NCHRP 350 SYSTEM. ALL EXISTING, AND REUSABLE PARTS MUST BE FREE OF ANY DAMAGE FOR A MASH COMPLIANT RETROFIT.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - SPECIAL DRIVING CAP TO BE USED WHEN DRIVING (LOWER POSTS 1 & 2) TO PREVENT DAMAGE TO THE WELDED PLATES.



- ITEM 10 INSTALL NEW OBJECT MARKER (E3151)
- ITEM 1 INSTALL NEW MASH MSKT IMPACT HEAD SEE: CONNECTION DETAIL A
- SEE: CONNECTION DETAIL B
- REUSE EXISTING UPPER STEEL POST
- ITEM 5 NEW GROUND STRUT
- ITEM 2 INSTALL NEW TOP POST (6" X 6" X 1/8") STEEL TUBE (MTPHP1A)
- ITEMS 6, 7, 8 HARDWARE FOR GROUND STRUT
- ITEM 3 INSTALL NEW BOTTOM POST (MTPHP1B) 6'-0" (W6X15) I-BEAM
- REMOVE SHORT POST 3'-5 7/8" W6X9 I-BEAM POST
- ITEM 4 INSTALL NEW BOTTOM POST (HP2B) 6'-0" (W6X9) I-BEAM

ITEMS	QTY	MAIN SYSTEM COMPONENTS	PART NUMBERS
*	1	MSKT IMPACT HEAD	MS3000
	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
	1	GROUND STRUT	MS785
	1	5/8" X 9" HEX BOLT (GRD A449)	B580904A
	2	5/8" WASHERS	W050
	1	5/8" H.G.R NUT	N050
	1	CABLE TIE-STEEL	CT-100ST
*	1	OBJECT MARKER 18" X 18"	E3151

COMPONENTS REQUIRED TO RETROFIT: EXISTING 31" STEEL POST (NCHRP 350) SKT GUARDRAIL TERMINAL WITH THE NEW 31" (MASH COMPLIANT MSKT IMPACT HEAD).

\* IF THE EXISTING NCHRP 350 (31" STEEL POST SKT) ALREADY HAS THE MSKT IMPACT HEAD THERE IS NO NEED TO REPLACE THE IMPACT HEAD OR OBJECT MARKER AS LONG AS IT IS NOT DAMAGED.

Design Division Standard


## RETROFIT STANDARD SKT 31" STEEL POST SYSTEM TO MASH MSKT SGT (13S) 31-18

FILE: sgt13s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495 10	094	IH 20	
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	55	

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE EXISTING; SKT END TERMINAL RETROFITTED TO THE MSKT MASH COMPLIANT TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:




**GENERAL NOTES**

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432) 263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
- FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
- IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, AND REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- THE EXISTING SKT 31" STANDARD WOOD POST SYSTEM MUST BE THOROUGHLY INSPECTED, AND DETERMINED TO BE INTACT, AND FREE OF ANY DAMAGE OR DEFECTS BEFORE RETROFITTING. THIS INSPECTION INCLUDES COMPLETING THE MSKT RETROFIT INSPECTION CHECKLIST FOR THE EXISTING SKT 31" WOOD POST NCHRP 350 SYSTEM. ALL EXISTING, AND REUSABLE PARTS MUST BE FREE OF ANY DAMAGE FOR A MASH COMPLIANT RETROFIT.
- UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
- A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
- SPECIAL DRIVING CAP TO BE USED WHEN DRIVING (LOWER POSTS 1 & 2) TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEMS	QTY	MAIN SYSTEM COMPONENTS	PART NUMBERS
1	1	MSKT IMPACT HEAD	MS3000
2	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
3	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
4	1	POST 2 - ASSEMBLY TOP	UHP2A
5	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
6	1	GROUND STRUT	MS785
7	2	5/16" X 1" HEX BOLT (GRD 5)	B516014A
8	4	5/16" WASHERS	W0516
9	2	5/8" HEX NUT	N0516
10	2	5/8" X 9" HEX BOLT (GRD A449)	B580904A
11	3	5/8" WASHERS	W050
12	3	5/8" H.G.R NUT	N050
13	1	5/8" X 1 1/4" SPLICE BOLT	B580122
14	1	3/4" X 8 1/2" HEX BOLT (GRD 5)	B340854A
15	1	3/4" HEX NUT	N030
16	1	CABLE TIE-STEEL	CT-100ST
17	1	OBJECT MARKER 18" X 18"	E3151

COMPONENTS REQUIRED TO RETROFIT: EXISTING 31" WOOD POST (NCHRP 350 SKT) GUARDRAIL TERMINAL WITH THE NEW 31" (MASH COMPLIANT MSKT IMPACT HEAD).  
 \* IF THE EXISTING NCHRP 350 (31" WOOD POST SKT) ALREADY HAS THE MSKT IMPACT HEAD THERE IS NO NEED TO REPLACE THE IMPACT HEAD OR OBJECT MARKER AS LONG AS IT IS NOT DAMAGED.




Texas Department of Transportation  
 Design Division Standard

**RETROFIT STANDARD  
 SKT 31" WOOD POST SYSTEM  
 TO MASH MSKT  
 SGT (14W) 31-18**

FILE: sgt14w3118.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT SECT	JOB	HIGHWAY	
REVISIONS	0495 10	094	IH 20	
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	56	






NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE EXISTING; SKT END TERMINAL RETROFITTED TO THE MSKT MASH COMPLIANT TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DATE: 9/17/2021  
 FILE: \\txdot\project\wiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - DesignMaster Design Files\04 STANDARDS\000 SGT(15)31-20.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
  - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CBO8
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WB08
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/8"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GGR17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81
SMALL HARDWARE			
o	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPlice BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563HD HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M




NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

**SPIG INDUSTRY, LLC**  
**SINGLE GUARDRAIL TERMINAL**  
**SGET - TL-3 - MASH**  
**SGT (15) 31-20**

FILE: sg153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT: 0495	SECT: 10	JOB: 094	HIGHWAY: IH 20
REVISIONS	0495	10	094	11
DIST: ATL	COUNTY: HARRISON	SHEET NO. 57		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/17/2021  
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 TE (HMAC) - 11.dgn




\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 1**  
 THIN HMAC SURFACES OR HMAC OVERLAY  
 WITH THICKNESS OF 2.5" OR LESS




\*\* EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.  
 \*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 2**  
 OVERLAY OF EXISTING PAVEMENT  
 HMAC THICKNESS 2.5" TO 5"



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 3**  
 NEW OR RECONSTRUCTED PAVEMENT  
 HMAC THICKNESS 2.5" TO 5"



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 4**  
 NEW OR RECONSTRUCTED PAVEMENT  
 HMAC THICKNESS 5" OR GREATER

**GENERAL NOTES**

1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.


(NOT TO SCALE)

					Design Division Standard
<b>TAPERED EDGE DETAILS          HMAC PAVEMENT</b>					
<b>TE (HMAC) - 11</b>					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0495	10	094	IH 20	
	DIST	COUNTY	SHEET NO.		
	ATL	HARRISON	58		




DATE: 10/4/2021 9:50:11 AM  
 FILE: \\txdot\project\wison\line.com\TXDOT15\Documents\19 - ATL\Design Projects\0495100941\19-0915-08-13644s or Design Master Design Files\H20\_42.in.RCP.Repair (2384+80.WB) \STB\


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units.



**SECTION B-B**  
 (Showing headwall pipe runner. Except for upper bracket, wingwall pipe runners are similar.)



**PIPE RUNNER PLAN**




**ELEVATION SIDE VIEW**



**SECTION C-C ELEVATION**  
 (Showing installed bracket.) (Showing installed bracket normal to wall. Pipe not shown for clarity.)

NOTE: Match the wingwall bracket to the upper bracket size.


**WINGWALL BRACKET DETAILS**



**SIDE VIEW ELEVATION**


NOTE: Match upper and lower brackets, except for the brackets used with non-sliding pipe runners, with the required pipe diameters as shown in the table.

**UPPER AND LOWER BRACKET DETAILS**




Note: Pipe size is the same as required for headwall pipe runner. Adjust the corresponding lower bracket accordingly.  
**NON-SLIDING PIPE RUNNER DETAILS (10)**

- (8) At Contractor's option, 3/8" diameter hole may be formed or cored drilled. Percussion drilling is not permitted. Adjust placement of reinforcing steel as necessary to avoid bolt holes.
- (9) After installation of the pipe runner, use the 1/2" inspection hole to ensure that the lap of the anchor pipe with the pipe runner is adequate.
- (10) Non-sliding pipe runners are used for those installations that would require pipe runner lengths of 1'-9" or less. The non-sliding pipe runner, when required, replaces the outermost pipe runner and anchor pipe. See table on Sheet 3 of 3 to determine if the non-sliding pipe runner is required.
- (11) At Contractor's option, an adhesive anchor may be used. Provide adhesive anchors that are 3/4" Dia ASTM A307 Grade A fully threaded rods. Embed threaded rods into curb, wingwalls, and/or toewall using a Type III, Class C, D, E, or F anchor adhesive. Minimum embedment depth is 5 1/2". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 20 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use.



Note: Use pipe diameter required for headwall pipe runner and for wingwall pipe runner.

**PIPE RUNNER DETAILS**



**ANCHOR PIPE DETAILS**

SHEET 2 OF 3

		<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT WITH FLARED WINGS</b>			
<b>FOR 0 SKEW PIPE CULVERTS TYPE I ~ CROSS DRAINAGE</b>			
<b>SETP-FW-0</b>			
FILE: setpf0se-20.dgn	DN: GAF	CK: CAT	DW: TXDOT
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY
REVISIONS	0495 10	094	IH 20
DIST	COUNTY	SHEET NO.	
ATL	HARRISON	58B	

DATE: 10/4/2021 9:48:42 AM  
 FILE: \\txdot.projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\0495100941\0495100941.dwg  
 PROJECT: 0495100941  
 DESIGNER: P. Les  
 CHECKER: P. Les  
 TITLE: 42 in RCP Repair (2384\*80 WB) STA

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units.

Side Slope	Pipe Culvert Dia	L1	P1	No. of Spaces in L3	L3 Overall Dimension	P2	No. of Spaces in L4	L4 Overall Dimension	Headwall Pipe Runner Length	No. of Wing Pipes (13)	Longest Wingwall Pipe Runner Length	Shortest Wingwall Pipe Runner Length	Non-Sliding Pipe Length	Pipe Runner Size (14)	Total Length of Wingwall Pipe Runners (13)
3:1	33"	0'-9"	2'-0"	2	4'-2 3/4"	3'-7"	1	4'-2 3/4"	8'-4"	4	5'-5 1/2"	N/A	3'-1"	3" STD	17'-1"
	36"	0'-9"	2'-0"	2	4'-8"	3'-7"	1	4'-8"	9'-1 1/2"	4	5'-10 1/4"	N/A	3'-1"	3" STD	17'-10 1/2"
	42"	1'-0"	3'-0"	2	4'-9 1/2"	5'-7"	1	4'-9 1/2"	10'-8 1/4"	4	7'-9 1/2"	3'-5"	N/A	4" STD	22'-5"
	48"	1'-3"	2'-0"	3	7'-4"	3'-7"	2	9'-9 1/4"	13'-0 3/4"	6	10'-6 1/4"	6'-0 3/4"	3'-1"	4" STD	39'-4"
	54"	0'-6"	2'-0"	3	7'-5 1/2"	3'-7"	2	9'-11 1/4"	14'-7 3/4"	6	10'-8"	6'-1 1/2"	3'-1"	4" STD	39'-9"
	60"	0'-9"	2'-0"	4	8'-6 3/4"	3'-7"	3	12'-10 1/4"	16'-2 3/4"	8	13'-3 3/4"	5'-6"	3'-1"	4" STD	62'-7 1/4"
	66"	1'-0"	2'-0"	4	9'-8 1/4"	3'-7"	3	14'-6 1/4"	17'-9 3/4"	8	14'-10 1/4"	6'-0"	3'-1"	4" STD	68'-8 3/4"
4:1	33"	0'-9"	2'-0"	3	6'-0 3/4"	3'-7"	2	8'-1"	11'-4 1/2"	6	8'-8 3/4"	5'-1 1/4"	3'-0"	4" STD	33'-8"
	36"	0'-9"	2'-0"	3	6'-7 3/4"	3'-7"	2	8'-10 1/4"	12'-4 3/4"	6	9'-5"	5'-5 1/2"	3'-0"	4" STD	35'-9"
	42"	1'-0"	2'-9"	3	7'-3 1/2"	5'-1"	2	9'-8 3/4"	14'-5 1/2"	6	11'-6 1/4"	2'-10 1/4"	N/A	4" STD	43'-1 1/2"
	48"	1'-3"	2'-3"	4	9'-9 1/4"	4'-1"	3	14'-8"	17'-6 3/4"	8	15'-0 1/2"	1'-11 1/2"	N/A	4" STD	68'-0"
	54"	0'-6"	2'-6"	4	9'-11 1/4"	4'-7"	3	14'-10 3/4"	19'-7 1/2"	8	15'-8 3/4"	2'-4 3/4"	N/A	5" STD	72'-4"
	60"	0'-9"	2'-0"	5	11'-10"	3'-7"	4	18'-11 1/4"	21'-8 1/4"	10	18'-5"	5'-8 3/4"	3'-0"	5" STD	102'-7"
	66"	1'-0"	2'-9"	5	12'-6"	5'-1"	4	19'-11 3/4"	23'-9"	10	20'-8 1/4"	2'-10 1/4"	N/A	5" STD	117'-8 1/2"
6:1	33"	0'-9"	2'-0"	4	9'-8 3/4"	3'-7"	3	14'-7"	17'-7"	8	14'-3"	5'-8 1/2"	2'-11 1/2"	4" STD	65'-9 1/2"
	36"	0'-9"	2'-9"	4	9'-10"	5'-1"	3	14'-9"	19'-1 1/4"	8	15'-8 3/4"	2'-9 1/4"	N/A	5" STD	74'-0"
	42"	1'-0"	2'-3"	5	12'-3 3/4"	4'-1"	4	19'-8 1/2"	22'-1 3/4"	10	19'-2 1/4"	1'-10 3/4"	N/A	5" STD	105'-5"
	48"	1'-3"	2'-6"	6	14'-11"	4'-7"	5	24'-10 1/4"	26'-8 1/2"	12	24'-1 3/4"	2'-4"	N/A	5" STD	158'-10 1/2"
	54"	0'-6"	2'-0"	7	16'-4 3/4"	3'-7"	6	28'-1 1/4"	29'-9"	14	26'-1 1/2"	5'-6 3/4"	2'-11 1/2"	5" STD	196'-0 1/2"
	60"	0'-9"	3'-0"	7	17'-4 1/2"	5'-7"	6	29'-9 1/2"	32'-9 1/2"	14	29'-4 1/4"	3'-2 1/2"	N/A	5" STD	227'-11 1/4"

- (12) If the outermost wing pipe runner is a non-sliding pipe runner, consider the next outermost wing pipe runner the shortest.
- (13) Quantities shown include, if present, the non-sliding pipes.
- (14) The anchor pipe size is the next smaller size than the pipe runner size.


STANDARD PIPE RUNNER AND ANCHOR PIPE SIZES (14)		
Pipe Size	Pipe O.D.	Pipe I.D.
2" STD	2.375"	2.067"
3" STD	3.500"	3.068"
4" STD	4.500"	4.026"
5" STD	5.563"	5.047"

**TOTAL PIPE LENGTHS FORMULAS:**

$$\text{Total Length of All Pipe Runners} = \text{Total Length of Wingwall Pipe Runners} + \left( \frac{\text{No. of Headwall Pipe Runners}}{\text{Pipe Runner Length}} \right) (\text{Headwall Pipe Runner Length})$$

$$\text{Total Length of All Anchor Pipes} = (3.000') \left( \frac{\text{No. of Wing Pipe Runners}}{\text{Pipe Runners}} + \frac{\text{No. of Headwall Pipe Runners}}{\text{Pipe Runners}} - \frac{\text{No. of Non-Sliding Pipe Runners}}{\text{Pipe Runners}} \right)$$

**SPECIAL NOTE:**  
 Note that the tabular quantities are given for estimating purposes only. It is likely that these quantities will change due to field conditions. Therefore, verify all dimensions in the field prior to fabrication of the safety end treatment components.



**PIPE RUNNER LAYOUT**

Pipe Culvert Dia	No. of Pipe Culverts	No. of L2 Spaces	L2 Overall Dimension	No. of Headwall Pipes
33"	1	1	2'-0 1/4"	2
	2	3	6'-8 1/4"	4
	3	5	11'-4 1/4"	6
	4	7	16'-0 1/4"	8
	5	9	20'-8 1/4"	10
36"	1	1	2'-3 3/4"	2
	2	3	7'-4 3/4"	4
	3	5	12'-5 3/4"	6
	4	7	17'-6 3/4"	8
42"	1	1	2'-4 3/4"	2
	2	4	8'-2 3/4"	5
	3	6	14'-0 3/4"	7
	4	8	19'-10 3/4"	9
	5	11	25'-8 3/4"	12
	6	13	31'-6 3/4"	14
48"	1	1	2'-5 3/4"	2
	2	4	9'-0 3/4"	5
	3	7	15'-7 3/4"	8
	4	9	22'-2 3/4"	10
	5	12	28'-9 3/4"	13
	6	15	35'-4 3/4"	16
54"	1	2	4'-6 3/4"	3
	2	5	12'-0 3/4"	6
	3	8	19'-6 3/4"	9
	4	11	27'-0 3/4"	12
	5	14	34'-6 3/4"	15
	6	17	42'-0 3/4"	18
60"	1	2	4'-7 3/4"	3
	2	6	12'-10 3/4"	7
	3	9	21'-1 3/4"	10
	4	12	29'-4 3/4"	13
	5	16	37'-7 3/4"	17
	6	19	45'-10 3/4"	20
66"	1	2	4'-8 3/4"	3
	2	6	13'-5 3/4"	7
	3	9	22'-2 3/4"	10
	4	13	30'-11 3/4"	14
	5	16	39'-8 3/4"	17
	6	20	48'-5 3/4"	21
72"	1	2	4'-9 3/4"	3
	2	6	14'-1 3/4"	7
	3	10	23'-5 3/4"	11
	4	14	32'-9 3/4"	15
	5	17	42'-1 3/4"	18
	6	21	51'-5 3/4"	22

		<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT WITH FLARED WINGS</b> FOR 0° SKEW PIPE CULVERTS TYPE I ~ CROSS DRAINAGE			
<b>SETP-FW-0</b>			
FILE: setpf0se-20.dgn	DN: GAF	CK: CAT	DW: TxDOT
©TxDOT February 2020	CONT: 049510	SECT: 10	JOB: 094
REVISIONS:	COUNTY: HARRISON		HIGHWAY: IH 20
DIST: ATL	COUNTY: HARRISON		SHEET NO: 58C



DATE: 9/17/2021 4:39:53 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\082919\082919.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4
SHEETING	Yellow, White or Red Type B or C reflective sheeting			
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.			

DELINEATORS				
DEVICE	SINGLE		DOUBLE	
SHEETING	Yellow, White or Red Type B or C Reflective Sheeting			
POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX
MOUNT TYPE	GND	GND, SRF	GND	GND, SRF

D & OM DESCRIPTIVE CODES	
INSTL DEL ASSM	(D-XX)SZ X (XXXX)XXX(XX)
NUMBER OF REFLECTORS	S = Single D = Double
COLOR OF REFLECTORS	W = White Y = Yellow R = Red
REFLECTOR UNIT SIZE	1 or 2
TYPE OF POST OR DELINEATOR	WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector
TYPE OF MOUNT	GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount
DIRECTION	If Required BI = Bi-Directional BR = Bi-Directional with red on back
INSTL OM ASSM	(OM-XX) (XXXX)XXX(XX)
TYPE OF OBJECT MARKER	1, 2, 3, or 4
NUMBER OF REFLECTORS OR DIRECTION	X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only)
TYPE OF POST	WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing
TYPE OF MOUNT	GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic
DIRECTION	If Required BI = Bi-Directional

OBJECT MARKERS							
DEVICE	Type 1 (OM-1)		Type 2 (OM-2)		Type 3 (OM-3)		Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C
SHEETING	Yellow-Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting		Red -Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting
POST TYPE	TWT	WC	WC	WFLX	TWT		TWT
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP		WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)		
DEVICE		
SHEETING	Yellow, White, Red	
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.	

CHEVRONS			
DEVICE			
SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway) / 36" x 48" (Freeway)
MOUNTING HEIGHT	4'-0" or 7'-0"		
NOTE	1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).		

ONE DIRECTION LARGE ARROW	
DEVICE	
SIZE (W x L)	48" x 24" (Conventional) / 60" x 30" (Expressway & Freeway)
MOUNTING HEIGHT	7'-0"

**NOTE:**  
 Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.

**DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION**  
**D & OM(1)-20**

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	ATL	HARRISON	59	

20A

DATE: 9/17/2021 4:40:00 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\090909.dgn  
 PROJECT: 090909  
 DRAWING: 090909-01  
 TITLE: DELINEATOR & OBJECT MARKER INSTALLATION  
 AUTHOR: J. W. BROWN  
 CHECKED: J. W. BROWN  
 APPROVED: J. W. BROWN  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided.

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS	
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT
GND	GND	SRF	WAS	WAP	GF 1
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC
<b>NOTES</b> 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.	<b>NOTES</b> 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		<b>NOTE</b> 1. Install per manufacturer's recommendations.		

TYPE OF BARRIER MOUNTS	
GUARD FENCE ATTACHMENT	
GF 1	GF 2

CONCRETE TRAFFIC BARRIER (CTB)	

GENERAL NOTES
1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS
<b>NOTE</b> Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN
<b>NOTE</b> Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

DELINEATORS AND TYPE 2 OBJECT MARKERS
See general notes 1, 2 and 3.


		<b>Traffic Safety Division Standard</b>	
<b>DELINEATOR &amp; OBJECT MARKER INSTALLATION</b>			
<b>D &amp; OM(2) -20</b>			
FILE: dom2-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT August 2004	CONT	SECT	JOB
REVISIONS	0495	10	094
10-09 3-15	DIST	COUNTY	SHEET NO.
4-10 7-20	ATL	HARRISON	60

DATE: 9/17/2021 4:40:08 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\09091909\09091909.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

### MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


### SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



**NOTE**

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

### SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



**NOTE**

At least one chevron pair is installed beyond the point of tangent in tangent section.

### DELINEATOR AND CHEVRON SPACING

Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

### DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

**NOTES**

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Traffic Safety Division Standard


## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

### D & OM(3)-20

FILE: dom3-20.dgn	DW: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS		0495 10	094	IH 20
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	ATL	HARRISON	61	


DATE: 9/17/2021 4:40:16 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510\049510.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into a digital format or for any errors or omissions that may appear in this document.

**CROSSOVERS**




**DETAIL 1**

**FOR CULVERTS WITHOUT MBGF**




**DETAIL 2**

**FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES**




**DETAIL 3**

**TYPICAL APPLICATION OF DEAD END BARRICADE**



**DETAIL 4**

**TYPICAL DEAD END BARRICADE INSTALLATION**



**NOTES**

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

**DETAIL 5**

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(4) -20**


FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
3-15	DIST	COUNTY	SHEET NO.	
7-20	ATL	HARRISON	D&OM(4)	

DATE: 9/17/2021 4:40:24 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\082319\082319.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions in this standard.


### CONTINUOUS CONCRETE OR STEEL BARRIER




### MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



### DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



### EMERGENCY CROSSOVER



#### NOTES

1. Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delineators. On Continuous Barrier, equal spacing (100' max.)
2. Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delineators.
3. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

#### LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow








Texas Department of Transportation  
 Traffic Safety Division Standard

## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS


### D & OM(6)-20

FILE: dom6-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
7-20	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	63	

DATE: 9/17/2021 4:40:32 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510\049510.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to PDF format.



OBJECT MARKERS SMALLER THAN 3 FT<sup>2</sup>




**NOTES**

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

		<b>Traffic Safety Division Standard</b>	
<b>DELINEATOR &amp; OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</b>			
<b>D &amp; OM(VIA) -20</b>			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT
© TXDOT December 1989	CONT	SECT	JOB
REVISIONS		0495 10	094 IH 20
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	ATL	HARRISON	64
4-98 7-20			
20G			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/17/2021 4:40:43 PM  
 FILE: \\txdot\projectwise\one\ine.com\TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 FPM(1)-12.dgn




PAVEMENT MARKERS (REFL) TYPE II-C-R SHALL BE SPACED ON 80' CENTERS WITH THE CLEAR FACE TOWARD NORMAL TRAFFIC AND THE RED FACE TOWARD WRONG WAY TRAFFIC.

### TRAFFIC LANE LINES PAVEMENT MARKING DETAILS

EDGELINES SHOULD TYPICALLY BE 4" WIDE AND THE MATERIALS SHALL BE AS SPECIFIED IN THE PLANS. IF RAISED PROFILE PAVEMENT MARKINGS ARE USED SEE DETAILS BELOW.




### EDGELINE PAVEMENT MARKINGS




ALL RAISED MARKERS IN THE WRONG WAY ARROW SHALL BE TYPE I-R REFLECTORIZED PAVEMENT MARKERS WITH THE REFLECTORIZED SURFACE FACING THE WRONG WAY TRAFFIC. TYPE II-C-R SHALL NOT BE USED. REFLECTORIZED WRONG WAY ARROWS, NOT TO EXCEED TWO, MAY BE PLACED ON EXIT RAMP. LOCATION OF THE ARROWS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER.


### WRONG WAY ARROW DETAIL




### PARALLEL ACCELERATION LANE



### TYPICAL EXIT RAMP GORE MARKING




### TYPICAL ENTRANCE RAMP GORE MARKING




### TAPERED ACCELERATION LANE

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

### RAISED PAVEMENT MARKERS







Texas Department of Transportation  
 Traffic Operations Division

## TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS WITH RAISED PAVEMENT MARKERS

FPM(1)-12

© TxDOT May 1974		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS					
4-92	2-10	CONT	SECT	JOB	HIGHWAY
5-00	2-12	0495	10	094	IH 20
8-00		DIST	COUNTY		SHEET NO.
2-08		ATL	HARRISON		65

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 9/17/2021 4:40:54 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 FPM(2)-12.dgn



**GENERAL NOTES**

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") Dotted Lane Line (See Detail B) is used to separate a through lane from a lane drop at normal exit ramp and from an auxiliary lane between an entrance and exit ramp.
4. Normal (4") Dotted Lane Line (See Detail C) is used at parallel acceleration and deceleration lanes.

LEGEND	
←	Denotes direction of traffic.
↪	Pavement marking arrows (white)
*	Arrow markings are optional, however "ONLY" is required if arrow is used

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




**TYPICAL STANDARD  
FREEWAY PAVEMENT MARKINGS  
ENTRANCE AND EXIT RAMP**  
FPM(2)-12

REVISIONS		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
NO.	DATE	CONTRACT	SECTION	JOB	HIGHWAY
4-92	2-10	0495	10	094	IH 20
8-95	2-12				
5-00					
8-00					
		DIST	COUNTY	SHEET NO.	
		ATL	HARRISON	66	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/17/2021 4:41:01 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\049510094 Lets with 0495-08-136\4 - Design\Master Design Files\04 STANDARDS\000 FPM(3)-12.dgn




**SINGLE LANE EXIT - LANE DROP OR EXIT ONLY**




**SINGLE LANE EXIT - LANE DROP OR EXIT ONLY (LEFTHAND)**

LEGEND	
←	Denotes direction of traffic.
↶	Pavement marking arrows (white)
✱	Arrow markings are optional, however "ONLY" is required if arrow is used



**DETAIL A**



**DETAIL B**

Wide (12") Dotted Lane Line (See Note 3)

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

**GENERAL NOTES**

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") Dotted Lane Line (See Detail B) is used to separate a through lane from a lane drop at normal exit ramp and from an auxiliary lane between an entrance and exit ramp.




**TYPICAL STANDARD  
 FREEWAY PAVEMENT MARKINGS  
 LANE DROP (EXIT ONLY) EXIT RAMPS  
 FPM(3)-12**

REVISIONS		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
5-00		CONT	SECT	JOB	HIGHWAY
8-00		0495	10	094	IH 20
2-10		DIST		COUNTY	SHEET NO.
2-12		ATL		HARRISON	67


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided. This drawing is for informational purposes only. It is not to be used for any other purpose without the written consent of TxDOT. DATE: 9/17/2021 4:41:08 PM FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\090821\090821\090821\FPM(5)-19.dgn

### EXIT NUMBER PAVEMENT MARKING NOTES

1. Minimum 8 foot white markings should be used, unless otherwise noted.
2. Spacing between letters and numbers should be approximately 4 inches.
3. Pavement markings are to be located as specified elsewhere in the plans.
4. All pavement marking materials shall meet the required Departmental Material Specifications or as specified in these plans.
5. Numbers and Letters details can be found in the Standard Highway Design for Texas (SHSD) Chapter 12 at <http://www.txdot.gov>



**MARKINGS WITH EXIT NUMBER**



### NOTES


1. Raised pavement markers shall be centered between chevron or gore lines.
2. For more information, see ReflectORIZED Raised Pavement Marker Detail.

**DETAIL A**


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

LEGEND	
←	Traffic flow
□	ReflectORIZED Raised Markers (RPM) Type II-C-R



**Type II (Top View)**



**SECTION A**

### REFLECTORIZED RAISED PAVEMENT MARKER (RPM)




### EXIT GORE PAVEMENT MARKINGS

### FPM(5) - 19

FILE: fpm(5)-19.dgn	DN:	CK:	DW:	CK:
© TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0495	10	094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	68	

**MARKINGS WITHOUT EXIT NUMBER**



DATE: 9/17/2021 4:55:47 PM  
 FILE: \\txdot\projectwiseonline.com\TXDOTS\Documents\19 - ATL\Design Projects\049510\049510.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another.

**SITE DESCRIPTION**

PROJECT LIMITS: FROM: 0.5 MI. W. OF US 80  
 TO: LOUISIANA STATE LINE

PROJECT DESCRIPTION: FOR THE CONSTRUCTION OF REHABILITATION OF EXISTING ROADWAY

MAJOR SOIL DISTURBING ACTIVITIES: NONE, THIS PROJECT IS CONSIDERED A MAINTENANCE ACTIVITY

TOTAL PROJECT AREA: 0.0 ACRES

TOTAL AREA TO BE DISTURBED: 0.0 ACRES

EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER: N/A

NAME OF RECEIVING WATERS: N/A

ANTICIPATED EFFECT OF STORM WATER ON THREATENED AND ENDANGERED SPECIES AND WILDLIFE HABITAT: REFER TO EPIC SHEET

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES: N/A

STORM WATER MANAGEMENT: N/A

DETAILED SITE MAP OR LAYOUT INDICATING THE FOLLOWING: (SEE SWP3 SITE MAP OR LAYOUT) N/A

**EROSION AND SEDIMENT CONTROLS**

**SOIL STABILIZATION PRACTICES:**

- PERMANENT PLANTING, SODDING, OR SEEDING
- TEMPORARY SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- BUFFER ZONES
- PRESERVATION OF NATURAL RESOURCES
- SLOPE TEXTURING

N/A

**STRUCTURAL PRACTICES:**

- SILT FENCES
- HAY BALES
- ROCK BERMS
- PAVED FLUMES
- CHANNEL LINERS
- SEDIMENT TRAPS
- FILTER DAMS
- CURBS AND GUTTERS
- STORM SEWERS
- ROCK BEDDING AT CONSTRUCTION EXIT
- TIMBER MATTING AT CONSTRUCTION EXIT
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION DIKE AND SWALE COMBINATIONS
- STORM INLET SEDIMENT TRAP
- VELOCITY CONTROL DEVICES
- EROSION CONTROL LOGS

OTHER: \_\_\_\_\_

MAINTENANCE: N/A

INSPECTION: ITEM 506 N/A

OFFSITE VEHICLE TRACKING: N/A

CONCRETE TRUCK WASHOUT AREAS: N/A

**WASTE MATERIALS**


HAZARDOUS WASTE (INCLUDING SPILL REPORTING): AT A MINIMUM, ANY PRODUCTS IN THE FOLLOWING CATEGORIES ARE CONSIDERED TO BE HAZARDOUS: PAINTS, ACIDS FOR CLEANING MASONRY SURFACES, CLEANING SOLVENTS, ASPHALT PRODUCTS, CHEMICAL ADDITIVES FOR SOIL STABILIZATION, CONCRETE CURING COMPOUNDS AND ADDITIVES OR MOTOR OIL. MATERIALS SHALL BE STORED IN ACCORDANCE WITH APPLICABLE REGULATIONS. IN THE EVENT OF A SPILL WHICH MAY BE HAZARDOUS, IMMEDIATELY REPORT SPILL IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS.

WASTE MATERIALS: THE BURYING OF CONSTRUCTION WASTE MATERIAL ON SITE WILL NOT BE PERMITTED. DISPOSAL OF WASTE MATERIALS SHALL MEET ALL STATE AND LOCAL SOLID WASTE MANAGEMENT REGULATIONS. WASTE MATERIALS STORED ON SITE SHALL BE COLLECTED IN A METAL DUMPSTER WITH A LOCKING, SECURE COVER AND A DRAIN PLUG IN PLACE.

SANITARY WASTE: ALL SANITARY WASTE WILL BE DISPOSED OF IN ACCORDANCE WITH ALL STATE AND LOCAL REGULATIONS. SPECIFIC LOCATIONS OF PORTABLE UNITS MUST BE SHOWN ON THE SWP3 SITE MAP OR LAYOUT.

REMARKS: DISPOSAL AREAS, STOCKPILES, AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT MAY ENTER RECEIVING WATERS. DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WETLAND, WATERBODY OR STREAMBED. CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED BY THE CONTRACTOR IN A MANNER TO MINIMIZE THE RUNOFF OF POLLUTANTS. ALL WATERWAYS SHALL BE CLEARED AS SOON AS PRACTICAL OF TEMPORARY EMBANKMENT, TEMPORARY BRIDGES, MATTING FALSEWORK, PILING, DEBRIS OR OTHER OBSTRUCTIONS PLACED DURING CONSTRUCTION OPERATIONS THAT ARE NOT A PART OF THE FINISHED WORK.

NOTES: THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL SUBCONTRACTORS ARE AWARE OF AND COMPLY WITH ALL COMPONENTS OF THE SWP3.


**Texas Department of Transportation**  
 © 2021  
**TxDOT STORM WATER POLLUTION PREVENTION PLAN**  
 (LESS THAN ONE ACRE)  
**SWP3**

FILE: swp3less1acre.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
Revisions	CONT	SECT	JOB	HIGHWAY
May 2017	0495	10	094	IH 20
	DIST	COUNTY	SHEET NO.	
	ATL	HARRISON	69	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. N/A

No Action Required     Required Action  
Action No.

1. This project is considered a maintenance activity and is exempt from the requirements of TPDES TXR 150000.

Commitment No.

1. Refer to the SWP3 Plan Sheet, BMPs, and Detail. It will address sweeping, chemical storage, sanitary waste, and all other management practices.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 1.
- 2.
- 3.
- 4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

**Best Management Practices:**

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required     Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required     Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

No Action Required     Required Action

Action No.

- 1.
- 2.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes     No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes     No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required     Required Action

Action No.

- 1.


**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required     Required Action

Action No.

- 1.
- 2.
- 3.

 <b>Texas Department of Transportation</b>		<b>Design Division Standard</b>		
<h2 style="margin: 0;">ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</h2> <h1 style="margin: 0;">EPIC</h1>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0495	10	094	IH 20
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.	
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	ATL	HARRISON	70	