

FINAL PLANS

NAME OF CONTRACTOR: _____
 DATE OF LETTING: _____
 DATE WORK BEGAN: _____
 DATE WORK COMPLETED: _____
 DATE WORK ACCEPTED: _____
 SUMMARY OF CHANGE ORDERS:

STATE OF TEXAS
 DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
 STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO.
 F 2022(152)

CCSJ: 0173-05-041, ETC.

SH 34, ETC.

KAUFMAN COUNTY

DESIGN JR	FED. RD. DIV. NO.	FEDERAL PROJECT NO.		HIGHWAY NO.
GRAPHICS SB	6	F 2022(152)		SH 34, ETC
CHECK FR	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	1
CHECK FR	CONTROL	SECTION	JOB	
	0173	05	041, ETC	

CCSJ:0173-05-041 (SH 34)
 DESIGN SPEED = N/A (PM)
 FUNCTIONAL CLASSIFICATION: 4 - RURAL MINOR ARTERIAL
 CSJ:2815-01-009 (FM 2757)
 DESIGN SPEED = N/A (PM)
 FUNCTIONAL CLASSIFICATION: 5 - RURAL MAJOR COLLECTOR

ADT CCSJ:0173-05-041 (SH 34) 8,152 (2021) --- 13,455 (2041)
 ADT CSJ:2815-01-009 (FM 2757) 1,258 (2021) --- 1,529 (2041)

NOTE:
 SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014, AND THE CONTRACT PROVISIONS LISTED AND DATED AS FOLLOWS SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY 1, 2012)


CCSJ: 0173-05-041 (SH 34)
 LIMITS: FROM N OF BUS SH 34 (VIRGINIA ST)
 TO 3.0 MI S OF HUNT COUNTY LINE

CSJ: 2815-01-009 (FM 2757)
 LIMITS: FROM FM 740 TO FM 741

TOTAL LENGTH OF PROJECT = $\left\{ \begin{array}{l} \text{ROADWAY} = 18,152.44 \text{ FT.} = 3.438 \text{ MI.} \\ \text{BRIDGE} = 53.00 \text{ FT.} = 0.010 \text{ MI.} \\ \text{TOTAL} = 18,205.44 \text{ FT.} = 3.448 \text{ MI.} \end{array} \right\}$

TOTAL LENGTH OF PROJECT = $\left\{ \begin{array}{l} \text{ROADWAY} = 19,389.23 \text{ FT.} = 3.672 \text{ MI.} \\ \text{BRIDGE} = 126.00 \text{ FT.} = 0.024 \text{ MI.} \\ \text{TOTAL} = 19,515.23 \text{ FT.} = 3.696 \text{ MI.} \end{array} \right\}$

FOR THE CONSTRUCTION OF OVERLAY
 CONSISTING OF: BASE REPAIR, OVERLAY AND PAVEMENT MARKINGS




WORK WAS COMPLETED ACCORDING TO THE PLANS AND CONTRACT.

_____, P.E.
 Signature of Registrant & Date

KAUFMAN COUNTY
 SCALE 0 1 2 3 4 5 6 MILES
 DALLAS DISTRICT

EQUATIONS: NONE
 EXCEPTIONS: NONE
 RAILROAD CROSSINGS: NONE

© 2021 by Texas Department of Transportation; all rights reserved



TEXAS DEPARTMENT OF TRANSPORTATION

SUBMITTED FOR LETTING: 9/23/2021
 Submitted By: *Falon Renfro*, P.E.
 DESIGN ENGINEER
 BF3C6897A5A0461...

RECOMMENDED FOR LETTING: 9/23/2021
 Submitted By: *Lane Selman*, P.E.
 AREA ENGINEER
 29F92BAFC304498...

RECOMMENDED FOR LETTING: 9/23/2021
 Submitted By: *[Signature]*, P.E.
 DIRECTOR OF TRANSPORTATION
 PLANNING & DEVELOPMENT

APPROVED FOR LETTING: 9/23/2021
 Submitted By: *[Signature]*, P.E.
 DISTRICT ENGINEER
 E2527653E8DE475...

INDEX OF SHEETS

I. GENERAL

1 TITLE SHEET
 2 INDEX OF SHEETS
 3 SH 34 PROJECT LAYOUT
 4 FM 2757 PROJECT LAYOUT
 5 SH 34 TYPICAL SECTIONS
 6-9 FM 2757 TYPICAL SECTIONS
 10, 10A-10C GENERAL NOTES
 11, 11A ESTIMATE & QUANTITY SHEET
 12-15 QUANTITY SUMMARY

II. TRAFFIC CONTROL PLAN

16 TCP NARRATIVE
 * 17-28 BC (1)-21 THRU BC (12)-21
 * 29 TCP (1-6)-18
 * 30 TCP (2-1)-18
 * 31 TCP (2-2)-18
 * 32 TCP (2-3)-18
 * 33 TCP (3-1)-13
 * 34 TCP (3-3)-14
 * 35 TCP (7-1)-13
 * 36 WZ (STPM)-13
 * 37 WZ (UL)-13
 * 38 WZ (RS)-16

III. ROADWAY DETAILS

39-48 SH 34 PLAN AND PAVEMENT MARKINGS
 49-65 FM 2757 PLAN AND PAVEMENT MARKINGS
 66 RDWY MISC DETAIL
 67 DRIVEWAY/INTERSECTION DETAILS
 ** 68 LJD(1-1)07 (DAL)
 * 69 TE (HMAC) -11

IV. RETAINING WALL DETAILS

NONE

V. DRAINAGE DETAILS

NONE

VI. UTILITIES

NONE

VII. BRIDGE

NONE

VIII. TRAFFIC ITEMS

* 70-72 D&OM(1)-20, D&OM(2)-20, D&OM(4)-20
 * 73-75 PM (1)-20, PM (2)-20, PM(3)-20
 * 76-78 RS(2) -13, RS(3) -13, RS(4) -13
 ** 79 TWO-LANE HIGHWAY CURVE SIGNING & MARKINGS (DAL)

IX. RAILROAD


NONE

X. ENVIRONMENTAL ISSUES

80-81 STORMWATER POLLUTION PREVENTION PLAN (SW3P)
 82 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS
 * 83 EC (1)-16
 * 84-86 EC (9)-16
 ** 87 VEGETATION ESTABLISHMENT SHEET (DAL)

XI. MISCELLANEOUS ITEMS

NONE



* STATEWIDE STANDARDS
 ** DALLAS DISTRICT STANDARDS

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Falon J. Renfroce, P.E., P.E. 9/14/2021
 Signature of Registrant & Date




INDEX OF SHEETS


SCALE: NTS

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
SB	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	2
CHECK FR	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

DATE: 9/14/2021 7:36:14 AM
 FILE: pw:\txdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\A03_PROECT_LAYOUT.dgn



NOTE: PLACE ADVANCE WARNING SIGNS IN ACCORDANCE WITH BC, TCP AND WZ STANDARDS AND TMUTCD, AND AS DIRECTED BY THE ENGINEER.



Falon Renfro, P.E., P.E. 9/14/2021
 Signature of Registrant & Date



**SH 34
 PROJECT LAYOUT**



SCALE: NTS

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	3
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

DATE: 9/22/2021 7:58:12 AM
 FILE: pw:\dot\projectwise\line.com:TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757 OVERLAY\A03B_PROJECT_LAYOUT.dgn

DALLAS CO. LINE

ROCKWALL CO. LINE



Falon Renfro, P.E. 9/22/2021
 Signature of Registrant & Date




FM 2757
 PROJECT LAYOUT

SCALE: NTS

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	4
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	

NOTE: PLACE ADVANCE WARNING SIGNS IN ACCORDANCE WITH BC, TCP AND WZ STANDARDS AND TMUTCD, AND AS DIRECTED BY THE ENGINEER.

DATE: 9/29/2021 8:10:57 AM
 FILE: \\txdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\A04_TYPICAL SECTIONS_01.dgn





EXISTING TYPICAL SECTION
 STA 138+50.00 TO STA 320+55.44

APPROX. 8" ACP
 12" CEMENT TREATED BASE
 SHOULDER RUMBLE STRIPS

NOTES:


1. FLEXIBLE PAVEMENT STRUCTURE REPAIR (ITEM 351) CONSISTING OF:
 6" OF REMOVAL (MIN WIDTH 12 FT)
 6" SP-B
 AT VARIOUS LOCATIONS AS DIRECTED BY THE ENGINEER. REPAIR AREA SHALL BE FULL LANE WIDTH. DO NOT PLACE A JOINT UNDER THE WHEEL PATH.
2. 2" OVERLAY SP-C (SAC-B) PG (70-22) 46' WIDE (ITEM 3077)
3. PAVEMENT CROSS SLOPES SHALL MATCH EXISTING CROSS SLOPE UNLESS OTHERWISE NOTED



PROPOSED TYPICAL SECTION
 STA 138+50.00* TO STA 320+55.44*

BACKFILL TY A OR B
 SHOULDER RUMBLE STRIPS
 6" FLEXIBLE PAVEMENT STRUCTURE REPAIR AREA VARIES SEE DETAIL
 2" OVERLAY (SP-C SAC B PG (70-22))

*SEE RDWY MISC DETAIL SHEET FOR PAVEMENT TRANSITION DETAIL




Falon Renfro, P.E. 9/29/2021
 Signature of Registrant & Date




**SH 34
 TYPICAL
 SECTIONS**

SCALE: NTS				
DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	5
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	


DATE: 9/14/2021 7:37:19 AM
 FILE: \\txdot\projectwise\line.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757 OVERLAY\FM2757_typical_section1.dgn



EXISTING TYPICAL SECTION
 STA 5+36.00 TO STA 126+41.00
 STA 127+40.00 TO STA 189+76.00
 BRIDGE STA 126+41.00 TO STA 127+40.00



EXISTING TYPICAL SECTION
 STA 0+00.00 TO STA 5+36.00
 TRANSITIONS FROM 39' TO 28' WIDE
 STA 4+36.00 TO STA 5+36.00




Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date




**FM 2757
 TYPICAL
 SECTIONS**

SCALE: NTS			SHEET 1 OF 4	
DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	
SB	TEXAS	DAL	KAUFMAN	
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	
CHECK				6
FR				

DATE: 9/14/2021 7:37:27 AM
 FILE: pw:\tdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757 OVERLAY\FM2757_typical_section2.dgn



STA 189+76.00 TO STA 195+15.23
 TRANSITIONS FROM 28' TO 39' WIDE
 STA 189+76.00 TO STA 190+76.00



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date




FM 2757
 TYPICAL
 SECTIONS


SCALE: NTS SHEET 2 OF 4

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	7
CHECK	FR	CONTROL	SECTION	
FR	0173	05	041, ETC.	

DATE: 9/28/2021 2:57:15 PM
 FILE: \\txdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757 OVERLAY\FM2757_typical_section3.dgn



PROPOSED TYPICAL SECTION
 STA 5+36.00 TO STA 22+92.00
 STA 29+28.00 TO STA 57+03.00
 STA 58+95.00 TO STA 87+90.00
 STA 90+00.00 TO STA 124+34.00
 STA 129+22.00 TO STA 137+00.00
 STA 150+55.00 TO STA 189+76.00




**PROPOSED TYPICAL SECTION
 TURN LANE**
 STA 0+00.00 TO STA 5+36.00*
 TRANSITIONS FROM 39' TO 28' WIDE
 STA 4+36.00 TO STA 5+36.00

*SEE RDWY MISC DETAIL SHEET FOR PAVEMENT TRANSITION DETAIL

NOTES:

- 2" OVERLAY SP-C (SAC-B) PG (64-22) 28'-39' WIDE (ITEM 3077)
- PAVEMENT CROSS SLOPES SHALL MATCH EXISTING CROSS SLOPE UNLESS OTHERWISE NOTED
- EXISTING MAILBOX WILL REMAIN IN PLACE




Falon Renfro, P.E. 9/28/2021
 Signature of Registrant & Date



**FM 2757
 TYPICAL
 SECTIONS**


SCALE: NTS		SHEET 3 OF 4		
DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	8
CHECK	FR	CONTROL	SECTION	
CHECK	FR	0173	05	
			JOB	
			041, ETC.	

DATE: 9/28/2021 2:58:43 PM
 FILE: \\txdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757 OVERLAY\FM2757_typical_section4.dgn



PROPOSED TYPICAL SECTION
 STA 22+92.00 TO STA 29+28.00- GUARD RAIL RT
 STA 57+03.00 TO STA 58+95.00- GUARD RAIL RT
 STA 87+90.00 TO STA 90+00.00- GUARD RAIL RT
 STA 124+34.00 TO STA 126+41.00 - GUARD RAIL BOTH *
 STA 126+41.00 TO STA 127+40.00 - NO WORK ON BRIDGE
 STA 127+40.00 TO STA 129+22.00- GUARD RAIL BOTH *
 STA 137+00.00 TO STA 140+55.00- GUARD RAIL BOTH

*SEE RDWY MISC DETAIL SHEET FOR PAVEMENT TRANSITION DETAIL





**PROPOSED TYPICAL SECTION
 TURN LANE**

STA 189+76.00 TO STA 195+15.23 *
 TRANSITIONS FROM 28' TO 39' WIDE
 STA 189+76.00 TO STA 190+76.00

*SEE RDWY MISC DETAIL SHEET FOR PAVEMENT TRANSITION DETAIL

NOTES:

- 2" OVERLAY SP-C (SAC-B) PG (64-22) 28'-39' WIDE (ITEM 3077)
- PAVEMENT CROSS SLOPES SHALL MATCH EXISTING CROSS SLOPE UNLESS OTHERWISE NOTED
- EXISTING MBGF AND CONCRETE MOW STRIP TO REMAIN IN PLACE.
- EXISTING MAILBOX WILL REMAIN IN PLACE



Falon Renfro, P.E. 9/28/2021
 Signature of Registrant & Date



**FM 2757
 TYPICAL
 SECTIONS**

SCALE: NTS		SHEET 4 OF 4	
DESIGN SB	FED. RD. DIV. NO. 6	PROJECT NO. (SEE TITLE SHEET)	
GRAPHICS SB	STATE	DISTRICT	HIGHWAY NO. SH 34, ETC
CHECK FR	TEXAS	DAL	COUNTY KAUFMAN
CHECK FR	CONTROL	SECTION	JOB 9
	0173	05	041, ETC.

County: Kaufman

Highway: SH 34, ETC.

SPECIFICATION DATA

Table 1: Basis of Estimate for Permanent Construction					
Item	Description	Thickness	Rate		Quantity
3077	SP MIXES	See Plans	110	Lbs./SY/In	17,067 Ton
3077	Tack Coat (Undiluted Application Rate)	Oxidized HMA	0.08	Gal/SY	12,303 Gal
		Milled HMA	0.11		152 Gal
Note: (1) Asphalt weight based on 110 Lbs./SY/In					

County: Kaufman

Highway: SH 34, ETC.

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 0.0 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

This project required no consultation or permitting with environmental resources agencies. There is a high probability that an environmentally sensitive area could be encountered on the contractor designated Project-Specific Locations (PSL) for this project (haul roads, equipment staging areas, borrow pits, disposal sites, field offices, storage areas, parking areas, etc.). Item 7.6 "Project-Specific Locations", provides a listing of regulatory agencies that may need to be contacted regarding this project.

Install traffic marking signs prior to sealcoat application and remove within three days after placement of traffic markings.

Leave all right of way areas undisturbed until actual construction is to be performed in said areas.

Contractor questions on this project are to be addressed to the following individual(s):

Lane Selman, P.E. Lane.Selman@txdot.gov
 Nicholas Wadlington, P.E Nicholas.Wadlington@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:
<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

County: Kaufman

Highway: SH 34, ETC.

Paper copies of cross-sections may be produced by using the provided .pdf file located on the above FTP Website at the bidders' expense and at copying companies. This data is for non-construction purposes only and it is the responsibility of the prospective bidder to validate the enclosed data with appropriate plans, specifications and estimate for the project(s).

Item 5:

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (214-320-6682) for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (214-320-6205) for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

For the project to be deemed complete, permanently stabilize all unpaved disturbed areas of the project with a vegetative cover at a minimum of 70% density for the control of erosion.

Place construction stakes/station markings at intervals of no more than 100 feet or as directed by the Engineer. Place stakes and markings so as not to interfere with normal construction operations.

Item 7:

Repair or replace any structures and utilities that might have been damaged by negligence or a failure to have utility locates performed.

Holiday restrictions – the engineer may decide that no lane closures or construction operations shall be allowed during the restricted periods listed in the following holiday schedule. TxDOT has the right to lengthen, shorten, or otherwise modify these restricted periods as actual, or expected, traffic conditions may warrant. Working days will not be charged for these restricted periods. No additional compensation will be allowed for these closures (i.e., overhead, delays, stand-by, barricades or any other associated cost impacts).

- New Year's Eve and Day (noon on December 31 thru 10:00 pm January 1)
- Easter Holiday weekend (noon on Friday thru 10:00 pm Sunday)
- Memorial Day weekend (noon on Friday thru 10:00pm Monday)
- Independence Day (noon on July 3 thru 10:00 pm on July 5)
- Labor Day weekend (noon on Friday thru 10:00 pm Monday)
- Thanksgiving Holiday (noon on Wednesday thru 10:00 pm Sunday)
- Christmas Holiday (noon on December 23 thru 10:00 pm December 26)

No significant traffic generator events identified.

County: Kaufman

Highway: SH 34, ETC.

Item 8:

This Project will be a Standard Workweek.

Meet weekly with the engineer to notify him or her of planned work for the upcoming week.

Provide the engineer with a daily work schedule of planned work.

Item 134:

Start backfilling pavement edges as soon as possible after the surface course is started.

Backfill and compact the pavement edges to produce a smooth surface adjacent to the pavement with no vertical edges.

Use Type "A" or "B" material to backfill pavement edges as shown in plans. Type "A" or "B" material shall consist of suitable material that when compacted will support the pavement edge. Rap is considered suitable Type "A" or "B" material.

Blade the existing vegetation into a neat wind-row prior to overlay. After placing Ty A or Ty B backfill, the material from the wind-row shall be replaced on the completed slopes. Emulsion shall be placed at a 50/50 solution of water to emulsion over disturbed area. Emulsion rate=0.15 Gal/SY residual. This work, materials and equipment shall be subsidiary to Item 134.

Item 301:

Provide liquid antistripping agents unless otherwise directed. Add the minimum dosage determined by the manufacturer or higher dosage determined by design requirement and try subsequent trials at 0.25% increments.

Item 320:

Use a self-propelled wheel mounted MTV capable of receiving mix from the haul trucks, separate from the paver. It shall have a minimum storage capacity of approximately 25 tons. It shall be equipped with a pivoting discharge conveyor and shall completely and thoroughly remix the material prior to placement. The effectiveness of the MTV's remixing ability is subject to the approval of the Engineer. In addition, the paver shall have a surge storage insert with a minimum capacity of 20 tons.

The use of windrow pick-up equipment is allowed except on the first course of roadway material placed over the subgrade.

Item 354:

Remove the loose material from the roadway before opening to traffic.

Patch pavement cut to excessive depth by equipment failure with an approved epoxy material. Re-plane patched area to an acceptable approved ride quality. Payment for these corrections is subsidiary to this item.

Saw existing asphalt along neat lines where portions are to be left in place temporarily or permanently. Sawing is not paid for directly, but is subsidiary to this item. Take possession of recycled asphalt pavement from the project and recycle the material.

County: Kaufman

Highway: SH 34, ETC.

Properly dispose of unsalvageable material at your own expense.

Slope longitudinal faces greater than 1 ¼" to a minimum of 1:1 slope at the end of the work period if traffic is able to traverse the joint. Slope transverse tapers to a minimum of 36:1 at the end of the workday. Remove the taper prior to continuing the milling.

For open shoulder sections, plane the asphalt so the flow of water is not impeded at the shoulder edge or across the surface. Added planing up to three feet in width outside the lines and grades of the plans, necessary to provide proper drainage, will be subsidiary to the bid item.

Item 421:

Furnish mix designs to the Engineer in a format compatible to the latest version of the Department's Construction Management System (Site Manager). Mix Design templates will be provided by the Engineer.

Strength evaluation using maturity testing, Tex-426-A, may be used for all concrete elements except drilled shafts and mass concrete pours.

Supply the Engineer with a list of certified personnel and copies of their current ACI certificates before beginning production and when personnel changes are made. Supply hard copies of calibration reports for testing equipment when required by the Engineer.

Item 500:

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

Item 502:

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times. Where turning radii are limited during phased construction at intersections, provide all weather surfaces such as RAP or base in turning movements to accommodate and to protect the traffic from edge drop-offs. Materials, labor, maintenance and removal for these temporary accesses and radii will not be paid for directly but will be considered subsidiary to the various bid items.

Provide written proposed lane closure information by 1:00 pm on the business day prior to the proposed closures. Do not close lanes when this requirement is not met.

When excavation is required next to a pavement lane carrying traffic and the widening is not completed by the end of the work day, backfill against the edge of the pavement with at least a 3:1 slope using an acceptable material to support vehicular traffic. Carefully remove and

County: Kaufman

Highway: SH 34, ETC.

dispose of this material when work resumes. Backfilling pavement edges, and the materials required for the work will be subsidiary to this item.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

Do not commence work on the road before sunrise. Do not operate or park any equipment/machinery closer than 30 feet from the traveled roadway after sunset unless authorized by the engineer.

When moving unlicensed equipment on or across any pavement or public highways, protect the pavement from all damage using an acceptable method.

Item 506:

Take all practicable precautions to prevent debris from being discharged into the Waters of Texas or a designated wetland. Install Best Management Practices before demolition begins and maintain them during the demolition. Remove any debris or construction material that escapes containment devices and are discharged into the restricted areas, before the next rain event or within 24 hours of the discharge.

If temporary construction stream crossings are allowed under a Nationwide Permit, submit in writing for approval the type and location of each temporary stream crossing. Use temporary bridges, timber mats, or other structurally sound and non-eroding material for temporary stream crossings. A temporary culvert crossing will consist of storm sewer pipes and 4- to 8-inch nominal size rock. Temporary stream crossings must not cause more than minimal changes to the hydraulic flow characteristics of the stream, increase flooding, or cause more than minimal degradation of water quality. Remove the temporary stream crossings in their entirety and return the affected areas to their pre-existing elevation. All work and materials use for temporary construction stream crossings will not be paid for directly but are subsidiary to pertinent Items.

Concrete Washouts are required per the CGP. The Concrete Washout Area(s) structural controls must consist of temporary berms, temporary shallow pits, and/or temporary storage tanks to prevent contaminated runoff and must be lined as to prevent contamination of underlying soil. Ensure pits properly maintained including removal of concrete as not to allow over flow. The location(s) of washout area will be approved by the Engineer. When washout pits are no longer needed, they will be removed and area will be restored to original condition. This work, materials and labor will not be measured or paid for directly but will be subsidiary to Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls."

Item 585:

Use Surface Test Type A on all intersections and driveways.

Use Surface Test Type B pay adjustment schedule 3 on the travel lanes.

Item 730:

At the discretion of the Engineer, mow non-paved areas within the project prior to placement of permanent vegetation. Mow up to one (1) cycles per growing season per CSJ.

County: Kaufman

Highway: SH 34, ETC.

Item 3077:

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class B.

Provide PG binder 70-22 in Type C mixture for CCSJ 0173-05-041.

Provide PG binder 64-22 in Type C mixture for CSJ 2815-01-009.

Item 6185:

The total number of truck mounted attenuators (TMAs) or trailer attenuators (TAs) required when utilizing the traffic control standards are shown in the tables below.

TCP 1 Series	Scenario	Required TMA/TA
(1-6)-18		1

TCP 2 Series	Scenario	Required TMA/TA	
(2-1)-18 / (2-2)-18	All	1	
(2-3)-18	A B	1	2

TCP 3 Series	Scenario	Required TMA/TA
(3-1)-13	All	2
(3-3)-14	A B D	2
	C	3

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed for the project. Additional TMAs/TAs used that are not specified in the plans in which the contractor expects compensation will require prior approval from the Engineer.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0173-05-041

DISTRICT Dallas
HIGHWAY FM 2757, SH 34

COUNTY Kaufman

CONTROL SECTION JOB				0173-05-041		2815-01-009		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00019675		A00176129			
COUNTY				Kaufman		Kaufman			
HIGHWAY				SH 34		FM 2757			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	134-6004	BACKFILL (TY A OR B)	STA	182.060		192.170		374.230	
	351-6002	FLEXIBLE PAVEMENT STRUCTURE REPAIR(6")	SY	1,507.000				1,507.000	
	354-6002	PLAN & TEXT ASPH CONC PAV(0" TO 2")	SY	4,135.000		4,328.000		8,463.000	
	500-6001	MOBILIZATION	LS	0.610		0.390		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000				5.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100.000		100.000		200.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100.000		100.000		200.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	100.000		100.000		200.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	100.000		100.000		200.000	
	530-6005	DRIVEWAYS (ACP)	SY	2,821.000		2,171.000		4,992.000	
	533-6003	RUMBLE STRIPS (SHOULDER) ASPHALT	LF	35,911.000		37,898.000		73,809.000	
	533-6004	RUMBLE STRIPS (CENTERLINE) ASPHALT	LF	15,536.000		19,442.000		34,978.000	
	658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	30.000		24.000		54.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	132.000		168.000		300.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,821.000		1,952.000		3,773.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	1,317.000		840.000		2,157.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF			48.000		48.000	
	666-6054	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA	4.000		6.000		10.000	
	666-6078	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA	4.000		4.000		8.000	
	666-6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	35,911.000		19,450.000		55,361.000	
	666-6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	15,536.000		19,442.000		34,978.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	36,132.000		35,172.000		71,304.000	
	666-6309	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL)	LF			3,728.000		3,728.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF	3,042.000		3,220.000		6,262.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	23,492.000		19,089.000		42,581.000	
	672-6007	REFL PAV MRKR TY I-C	EA	66.000		43.000		109.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	728.000		330.000		1,058.000	
	677-6001	ELIM EXT PAV MRK & MRKS (4")	LF			59,303.000		59,303.000	
	677-6002	ELIM EXT PAV MRK & MRKS (6")	LF			3,736.000		3,736.000	
	730-6107	FULL - WIDTH MOWING	CYC	1.000		1.000		2.000	
	3077-6013	SP MIXESSP-CSAC-B PG64-22	TON			6,792.000		6,792.000	
	3077-6023	SP MIXESSP-CSAC-B PG70-22	TON	10,275.000				10,275.000	
	3077-6075	TACK COAT	GAL	7,515.000		4,940.000		12,455.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000				2.000	
	6185-6002	TMA (STATIONARY)	DAY	49.000		37.000		86.000	
	6185-6003	TMA (MOBILE OPERATION)	HR	80.000		16.000		96.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0173-05-041

DISTRICT Dallas
HIGHWAY FM 2757, SH 34

COUNTY Kaufman

CONTROL SECTION JOB				0173-05-041		2815-01-009		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00019675		A00176129			
COUNTY				Kaufman		Kaufman			
HIGHWAY				SH 34		FM 2757			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000	

DATE: 9/16/2021 7:42:05 AM
 FILE: \\txdot\projectwiseonline.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\10A_QUANTITY_SUMMARY.dgn

SUMMARY OF ROADWAY ITEMS										
LOCATION		LENGTH	WIDTH	AREA	134	351	354	3077	3077	3077
					6004	6002	6002	6013	6023	6075
STA.		FT	FT	SY	BACKFILL (TY A OR B)	FLEXIBLE PAVEMENT STRUCTURE REPAIR (6")	PLAN & TEXT ASPH CONC PAV (0" TO 2")	SP MIXES SP-C (SAC-B) PG64-22	SP MIXES SP-C (SAC-B) PG70-22	TACK COAT
STA.	STA.	FT	FT	SY	STA	SY	SY	TON	TON	GAL
CCSJ: 0173-05-041										
138+50.00	139+50.00	100	46	512	1.00	200	512		57	57
139+50.00	319+55.00	18005	46	92026	180.05	1107			10123	7363
319+55.00	320+55.44	100.44	46	514	1.01	200	514		57	57
ADDITIONAL AREA 1				113			113		13	13
ADDITIONAL AREA 2				175			175		20	20
ADDITIONAL AREA 3				45					5	5
CCSJ: 0173-05-041 TOTALS					182.06	1507	1314		10275	7515
CSJ: 2815-01-009										
0+0.00	1+00.00	100	39	434	1.00		434	48		35
1+00.00	4+36.00	336	39	1456	3.36			161		117
4+36.00	5+36.00	100	33.5	373	1.00			42		30
5+36.00	22+92.00	1756	28	5464	17.56			602		438
22+92.00	29+28.00	636	28	1979	6.36		212	218		159
29+28.00	57+03.00	2775	28	8634	27.75			950		691
57+03.00	58+95.00	192	28	598	1.92		64	66		48
58+95.00	87+90.00	2895	28	9007	28.95			991		721
87+90.00	90+00.00	210	28	654	2.10		70	72		53
90+00.00	124+34.00	3434	28	10684	34.34			1176		855
124+34.00	125+41.00	107	28	333	1.07		72	37		27
125+41.00	126+41.00	100	29	323	1.00		323	36		26
126+41.00	127+40.00	99	30	330			BRIDGE NO WORK			
127+40.00	128+40.00	100	31	345	1.00		345	38		28
128+40.00	129+22.00	82	28	256	0.82		72	29		21
129+22.00	137+00.00	778	28	2421	7.78			267		194
137+00.00	140+55.00	355	28	1105	3.55		66	122		89
140+55.00	189+76.00	4921	28	15310	49.21			1685		1225
189+76.00	190+76.00	100	33.5	373	1.00			42		30
190+76.00	194+15.00	339	39	1469	3.39			162		118
194+15.00	195+15.23	100	39	435	1.01		435	48		35
CSJ: 2815-01-009 TOTALS					192.17		2093	6792		4940
PROJECT TOTALS					374.23	1507	3407	6792	10275	12455

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS							
LOCATION	662	662	677	677	6001	6185	6185
	6109	6111	6001	6002	6002	6002	6003
LOCATION	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	ELIM EXT PAV MRK & MRKS (4")	ELIM EXT PAV MRK & MRKS (6")	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	TMA (MOBILE OPERATION)
LOCATION	EA	EA	EA	EA	EA	DAY	HR
CCSJ: 0173-05-041							
STA. 138+50.00 TO STA. 320+55.44	132	1821			2	49	80
CCSJ: 0173-05-041 TOTALS							
	132	1821			2	49	80
CSJ: 2815-01-009							
STA. 0+00.00 TO STA. 195+15.23	168	1952	59303	3736		37	16
CSJ: 2815-01-009 TOTALS							
	168	1952	59303	3736		37	16
PROJECT TOTALS							
	300	3773	59303	3736	2	86	96




QUANTITY SUMMARY

SCALE: NTS				SHEET 1 OF 4	
DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.	
SB	6	(SEE TITLE SHEET)		SH 34, ETC.	
GRAPHICS	STATE	DISTRICT	COUNTY		SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN		12
FR	CONTROL	SECTION	JOB		
CHECK	FR	0173	05	041, ETC.	

DATE: 9/15/2021 11:38:32 AM
 FILE: \\ttdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\10B_QUANTITY_SUMMARY.dgn

SUMMARY OF PAVEMENT MARKING ITEMS																		
CSJ: 0173-05-041		LENGTH	533 6003	533 6004	658 6100	666 6036	666 6048	666 6054	666 6078	666 6170	666 6207	666 6303	666 6309	666 6312	666 6315	672 6007	672 6009	
STA.	STA.	LF	RUMBLE STRIPS (SHOULDER) ASPHALT	RUMBLE STRIPS (CENTERLINE) ASPHALT	INSTL OM ASSM (OM-2Z) (WFLX 1 GND (B1))	REFL PAV MRK TY I (W) 8" (SLD) (1 00MIL)	REFL PAV MRK TY I (W) 24" (SLD) (1 100MIL)	REFL PAV MRK TY I (W) (ARROW) (1 00MIL)	REFL PAV MRK TY I (W) (WORD) (10 0MIL)	REFL PAV MRK TY I (W) 4" (SLD)	REFL PAV MRK TY I (Y) 4" (SLD)	RE PM W/RET REQ TY I (W) 4" (SLD) (1 00MIL)	RE PM W/RET REQ TY I (W) 6" (SLD) (1 00MIL)	RE PM W/RET REQ TY I (Y) 4" (BRK) (1 100MIL)	RE PM W/RET REQ TY I (Y) 4" (SLD) (1 100MIL)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY 11-A-A	
CCSJ: 0173-05-041																		
138+50.00	157+00.00	1850	3700	1850						3700	1850	3700			3700		46	
157+00.00	177+00.00	2000	4000	2000	4					4000	2000	4000		500	2000		50	
177+00.00	197+00.00	2000	4000	2000						4000	2000	4000		475	2100		50	
197+00.00	217+00.65	2001	3901	1901	6					3901	1901	3901		500	1250		41	
217+00.65	237+01.42	2001	4002	2001	4					4002	2001	4002		500			25	
237+01.42	257+01.42	2000	4000	1532	4					4000	1532	4000		383	3358		131	
257+01.42	277+02.52	2001	3802		10	1317		4	4	3802		3823			4514	66	226	
277+02.52	297+02.52	2000	3800	1900						3800	1900	4000		391	3035		50	
297+02.52	317+02.55	2000	4000	2000	2					4000	2000	4000		293	2830		100	
317+02.55	320+55.44	353	706	353						706	353	706			706		9	
CCSJ: 0173-05-041 TOTALS			18205	35911	15536	30	1317	4	4	35911	15536	36132		3042	23492	66	728	
CSJ: 2815-01-009																		
30+00.00	12+00.00	1170	1820	1170		420	24	3	2	1170	1170	2340			2340	22	15	
12+00.00	24+00.00	1200	2400	1200	2					1200	1200	1441	959		2400		15	
24+00.00	36+00.00	1200	2400	1200	2					1200	1200	1355	1045	103	1690		20	
36+00.00	48+00.00	1200	2400	1200						1200	1200	2400		300			30	
48+00.00	60+00.00	1200	2400	1200	2					1200	1200	2400		300			15	
60+00.00	72+00.00	1200	2400	1200						1200	1200	2400		300	200		18	
72+00.00	84+00.00	1200	2400	1200						1200	1200	2400		113	1500		30	
84+00.00	96+04.00	1204	2408	1200	4					1204	1200	1361	1047		2408		15	
96+04.00	108+08.00	1204	2408	1200	2					1204	1200	1731	677	51	1002		18	
108+08.00	120+08.00	1200	2400	1200						1200	1200	2400		300	712		24	
120+08.00	132+08.00	1200	2400	1200						1200	1200	2400		300			15	
132+08.00	144+08.00	1200	2400	1200	4					1200	1200	2400		300	100		16	
144+08.00	156+08.00	1200	2400	1200	2					1200	1200	2400		300	1200		30	
156+08.00	168+08.00	1200	2400	1200	2					1200	1200	2400		300	1200		30	
168+08.00	180+08.00	1200	2400	1200	2					1200	1200	2400		30	2283		16	
180+08.00	192+08.00	1200	2190	1200	2	148		1	1	1200	1200	2400		523	1510	7	19	
192+08.00	194+80.00	272	272	272		272	24	2	1	272	272	544			544	14	4	
CSJ: 2815-01-009 TOTALS			19450	37898	19442	24	840	48	6	4	19450	19442	35172	3728	3220	19089	43	330
PROJECTS TOTALS			37655	73809	34978	54	2157	48	10	8	55361	34978	71304	3728	6262	42581	109	1058

SUMMARY OF EROSION CONTROL ITEMS					
LOCATION	506 6038	506 6039	506 6041	506 6043	730 6107
	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)	BIODEG EROSN CONT LOGS (INSTL) (12"	BIODEG EROSN CONT LOGS (REMOVE)	FULL - WIDTH MOWING
	LF	LF	LF	LF	CYC
CCSJ: 0173-05-041					
STA. 138+50.00 TO STA. 320+55.44	100	100	100	100	1
CCSJ: 0173-05-041 TOTALS					
	100	100	100	100	1
CSJ: 2815-01-009					
STA. 0+00 TO STA. 195+15.23	100	100	100	100	1
CSJ: 2815-01-009 TOTALS					
	100	100	100	100	1
PROJECT TOTALS					
	200	200	200	200	2


Texas Department of Transportation
 © 2021


QUANTITY SUMMARY

SCALE: NTS SHEET 2 OF 4

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	13
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

DATE: 9/15/2021 11:42:13 AM
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\10C_QUANTITY_SUMMARY.dgn

SUMMARY OF DRIVEWAYS AND INTERSECTIONS 0173-05-041 (SH 34)									
	STATION	SIDE	WIDTH	LENGTH	RADIUS	DRIVEWAY TYPE	354-6002	0530-6005	
							PLAN & TEXT & ASPH CONC PAV	DRIVEWAYS ACP	
							(0" TO 2")		
			FT	FT	FT		SY	SY	
1	139+24	LT	16	15	15	ASPHALT	34	34	
2	140+90	LT	16	15	15	ASPHALT	34	34	
3	143+35	LT	16	15	15	ASPHALT	34	34	
4	148+95	RT	22	15	15	ASPHALT	48	48	
5	149+60	LT	14	15	15	ASPHALT	36	36	
6	151+70	LT	14	15	15	ASPHALT	36	36	
7	169+17	RT	20	25	25	ASPHALT	86	86	
8	169+17	LT	22	15	15	ASPHALT	48	48	
9	170+48	LT	12	15	15	ASPHALT	33	33	
10	176+78	RT	12	15	15	ASPHALT	33	33	
11	182+79	RT	20	25	25	ASPHALT	86	86	
12	184+19	LT	14	25	25	ASPHALT	69	69	
13	187+43	LT	14	25	25	ASPHALT	69	69	
14	191+92	RT	24	20	20	ASPHALT	75	75	
15	200+54	LT	18	25	25	ASPHALT	80	80	
16	214+82 CR 320	LT	18	25	25	ASPHALT	80	80	
17	219+34	RT	20	25	25	ASPHALT	86	86	
18	241+58	LT	20	25	25	ASPHALT	86	86	
19	246+44	RT	14	25	25	ASPHALT	69	69	
20	253+35	RT	14	25	25	ASPHALT	69	69	
21	266+30 CR 322	RT	24	35	35	ASPHALT	162	162	
22	266+40 CR 322	LT	23	30	15	ASPHALT	236	236	
23	266+84	LT	12	15	15	ASPHALT	152	152	
24	269+57	LT	14	20	20	ASPHALT	50	50	
25	273+85	LT	16	25	25	ASPHALT	79	79	
26	275+43	LT	14	25	25	ASPHALT	69	69	
27	278+98	LT	14	25	25	ASPHALT	69	69	
28	282+69	LT	12	25	25	ASPHALT	64	64	
29	285+35	LT	12	25	25	ASPHALT	64	64	
30	286+31	LT	12	25	25	ASPHALT	64	64	
31	291+45	LT	14	25	25	GRAVEL	69	69	
32	295+92	LT	12	25	25	ASPHALT	64	64	
33	296+52	LT	12	25	25	ASPHALT	64	64	
34	298+61	RT	14	25	25	ASPHALT	69	69	
35	298+73	LT	14	25	25	ASPHALT	69	69	
36	305+23	LT	14	25	25	ASPHALT	69	69	
37	313+63	LT	16	25	25	ASPHALT	79	79	
38	315+66	LT	14	25	25	GRAVEL	69	69	
39	318+23	LT	14	25	25	ASPHALT	69	69	
CSJ: 0173-05-041 TOTALS							2821	2821	



© 2021


QUANTITY SUMMARY

SCALE: NTS SHEET 3 OF 4

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	14
FR	CONTROL	SECTION	JOB	
CHECK	FR	0173	05 041, ETC.	

DATE: 9/15/2021 11:47:52 AM
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\Plan Set\1. Summary\SUMMARY.dgn

SUMMARY OF DRIVEWAYS AND INTERSECTIONS 2815-01-009 (FM 2757)									
	STATION	SIDE	WIDTH	LENGTH	RADIUS	DRIVEWAY TYPE	354-6002	0530-6005	
			FT	FT	FT		PLAN & TEXT & ASPH CONC PAV	DRIVEWAYS ACP	
							(0" TO 2")		
			SY	SY					
1	3+37	RT	14	20	20	ASPHALT	28	28	
2	4+99	RT	16	15	15	ASPHALT	26	26	
3	7+67	RT	15	15	15	ASPHALT	33	33	
4	9+27	RT	17	15	15	ASPHALT	33	33	
5	10+24	RT	14	15	15	ASPHALT	24	24	
6	11+37	RT	18	15	15	ASPHALT	41	41	
7	13+69	RT	14	15	15	ASPHALT	36	36	
8	13+75	LT	30	25	25	ASPHALT	83	83	
9	16+26	LT	20	25	25	ASPHALT	64	64	
10	19+70	LT	18	15	15	ASPHALT	32	32	
11	28+70	LT	50	25	25	ASPHALT	139	139	
12	11&12 BECAME ONE SINGLE DRIVEWAY								
13	30+36	RT	20	15	15	ASPHALT	27	27	
14	38+74	RT	20	15	15	ASPHALT	56	56	
15	41+60	LT	15	15	15	ASPHALT	56	56	
16	58+70	RT	25	15	15	ASPHALT	55	55	
17	59+80	LT	18	15	15	GRAVEL	41	41	
18	83+22	LT	20	15	15	ASPHALT	44	44	
19	89+19	LT	22	25	25	ASPHALT	91	91	
20	89+75	RT	40	25	25	ASPHALT	141	141	
21	95+12	RT	15	15	15	ASPHALT	36	36	
22	97+48	LT	30	15	15	CONCRETE	10		
23	100+24	RT	20	20	20	ASPHALT	64	64	
24	101+48	LT	70	15	15	CONCRETE	24		
25	108+40	RT	30	15	15	CONCRETE	10		
26	109+86	RT	12	15	15	GRAVEL	31	31	
27	110+00	LT	30	15	15	CONCRETE	10		
28	115+88	RT	18	15	15	ASPHALT	41	41	
29	119+55	RT	30	15	15	CONCRETE	10		
30	122+32	LT	15	15	15	GRAVEL	36	36	
31	125+24	RT	16	15	15	GRAVEL	36	36	
32	132+81	RT	14	15	15	ASPHALT	36	36	
33	134+60	LT	22	15	15	ASPHALT	44	44	
34	137+51	RT	20	15	15	ASPHALT	44	44	
35	141+96*	LT	16	15	15	ASPHALT	36	36	
36	142+82	RT	16	15	15	GRAVEL	36	36	
37	145+00	RT	18	15	15	ASPHALT	41	41	
38	150+71	RT	12	15	15	ASPHALT	31	31	
39	160+97	RT	18	15	15	ASPHALT	41	41	
40	163+34	RT	16	15	15	ASPHALT	36	36	
41	165+26	RT	14	15	15	ASPHALT	36	36	
42	167+27	RT	14	15	15	ASPHALT	36	36	
43	167+90	LT	24	15	15	ASPHALT	51	51	
44	168+53	RT	24	20	20	ASPHALT	72	72	
45	169+97	RT	18	15	15	ASPHALT	41	41	
46	171+54	RT	24	15	15	ASPHALT	51	51	
47	174+56	RT	22	15	15	ASPHALT	47	47	
48	176+17	RT	14	15	15	GRAVEL	36	36	
49	181+59	RT	15	15	15	GRAVEL	36	36	
50	182+43	RT	18	15	15	ASPHALT	41	41	
51	185+61	RT	18	15	15	ASPHALT	41	41	
52	185+91	LT	20	15	15	ASPHALT	44	44	
CSJ: 2815-01-009 TOTALS							2235	2171	



© 2021

QUANTITY SUMMARY

SCALE: NTS SHEET 4 OF 4

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	15
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

SUGGESTED SEQUENCE OF WORK

TCP GENERAL NOTES

SH 34

PHASE I

1. ERECT PROJECT SIGNS & ADVANCE WARNING SIGNS IN ACCORDANCE WITH ALL APPLICABLE STANDARDS OR AS DIRECTED BY ENGINEER.
2. PLACE SW3P DEVICES AS PER STANDARD AND DIRECTED BY THE ENGINEER.
3. SET CHANNELIZING DEVICES TO PERFORM FLEXIBLE PAVEMENT STRUCTURE REPAIR AS DIRECTED BY THE ENGINEER. THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH TCP (2-2).

PHASE II

1. SET TRAFFIC CONTROL FOR OVERLAYING EXISTING PAVEMENT IN ACCORDANCE WITH TCP (2-2) & TCP (7-1). SET TRAFFIC CONTROL FOR SHOULDER WORK IN ACCORDANCE WITH TCP (2-1).
2. PERFORM 0"-2" MILL AND 2" OVERLAY AS SPECIFIED IN THE TYPICAL SECTIONS. APPLY TACK COAT BEFORE PLACING SUPERPAVE. FLAGGERS SHALL BE USED FOR ONE-LANE TWO WAY TRAFFIC CONTROL. BOTH LANES SHALL BE OPENED AT THE END OF EACH WORKDAY.
3. PLACE TABS FOR TEMPORARY STRIPING IN ACCORDANCE WITH WZ(STPM). INSTALL PERMANENT PAVEMENT MARKINGS AND RUMBLE STRIPS WITHIN 14 DAYS AFTER PLACING OVERLAY IN ACCORDANCE WITH TCP 3-1 & TCP 3-3.
4. PERFORM WORK ON DRIVEWAYS AS DIRECTED IN THE PLANS PLAN SHEETS IN ACCORDANCE WITH TCP (2-1).

PHASE III

1. SET UP BARRICADES
2. PLACE BACKFILL ALONG PAVEMENT EDGES IN ACCORDANCE WITH TCP (2-1).
3. INSTALL OBJECT MARKERS AT CROSS STRUCTURES AS DIRECTED BY THE ENGINEER AND IN ACCORDANCE WITH TCP (2-1).
4. PERFORM FINAL CLEANUP AS DIRECTED BY ENGINEER.

FM 2757

PHASE I

1. ERECT PROJECT SIGNS & ADVANCE WARNING SIGNS IN ACCORDANCE WITH ALL APPLICABLE STANDARDS OR AS DIRECTED BY ENGINEER.
2. PLACE SW3P DEVICES AS PER STANDARD AND DIRECTED BY THE ENGINEER.
3. SET TRAFFIC CONTROL FOR OVERLAYING EXISTING PAVEMENT IN ACCORDANCE WITH TCP (2-2) & TCP (7-1). SET TRAFFIC CONTROL
4. REMOVE PROFILE PAVEMENT MARKINGS. PLACE TEMPORARY TABS AND REMOVE PRIOR TO MILLING AND/OR OVERLATING OPERATIONS.
5. PERFORM 0"-2" MILL AND 2" OVERLAY AS SPECIFIED IN THE TYPICAL SECTIONS. APPLY TACK COAT BEFORE PLACING SUPERPAVE. FLAGGERS SHALL BE USED FOR ONE-LANE TWO WAY TRAFFIC CONTROL. BOTH LANES SHALL BE OPENED AT THE END OF EACH WORKDAY.
6. PLACE NEW TABS FOR TEMPORARY STRIPING IN ACCORDANCE WITH WZ(STPM). INSTALL PERMANENT PAVEMENT MARKINGS AND RUMBLE STRIPS WITHIN 14 DAYS AFTER PLACING OVERLAY IN ACCORDANCE WITH TCP 3-1 & TCP 3-3.
7. PERFORM WORK ON DRIVEWAYS AS DIRECTED IN THE PLANS PLAN SHEETS IN ACCORDANCE WITH TCP (2-1).

PHASE II

1. SET UP BARRICADES
2. PLACE BACKFILL ALONG PAVEMENT EDGES IN ACCORDANCE WITH TCP (2-1).
3. INSTALL OBJECT MARKERS AT CROSS STRUCTURES AS DIRECTED BY THE ENGINEER AND IN ACCORDANCE WITH TCP (2-1).
4. PERFORM FINAL CLEANUP AS DIRECTED BY ENGINEER.

OVERNIGHT LANE CLOSURES WILL NOT BE PERMITTED.

LIMIT THE LENGTH OF DAILY WORK TO THAT AREA OF OPERATION THAT CAN BE COMPLETED IN ONE WORK DAY IN ORDER TO ALLOW FOR TWO-WAY TRAFFIC AT NIGHT. SUCH AREAS MUST NOT EXCEED ONE (1) MILE, UNLESS APPROVED BY THE ENGINEER. WITHIN THE 1 MILE SECTION, ONLY CLOSE OFF THE AREA WHERE ACTUAL WORK IS BEING PERFORMED.

INTERMITTENT ONE-WAY TRAFFIC CONTROL (LANE CLOSURES) WILL BE IN ACCORDANCE WITH TCP & WZ STANDARD AND AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR WILL PROVIDE WRITTEN NOTICE TO THE ENGINEER BEFORE 1:00 PM ON THE BUSINESS DAY PRECEDING PROPOSED LANE CLOSURES. LANE CLOSURES WILL NOT BE PERMITTED WITHOUT THIS NOTIFICATION.

PAVEMENT EDGE DROP-OFFS WILL NOT BE ALLOWED TO REMAIN OVER NIGHT. AT THE END OF EACH WORKDAY ALL PAVEMENT EDGE DROP-OFFS SHALL BE BACK FILLED BY A SUITABLE MATERIAL TO FORM A STABLE 3:1 SLOPE OR FLATTER.

COMPLY WITH TCP (7-1)-13, WHICH INCLUDES PROVISIONS FOR CERTAIN SIGNS TO BE INSTALLED AND TO REMAIN UNTIL PERMANENT PAVEMENT MARKINGS ARE IN PLACE. THESE SIGNS ARE IN ADDITION TO SIGNS THAT MAY BE REQUIRED BY THE VARIOUS TCP AND BC STANDARDS.


THE CONTRACTOR SHALL COVER OR REMOVE ANY CONFLICTING SIGNS OR PAVEMENT MARKINGS DURING CONSTRUCTION AS DIRECTED BY ENGINEER AND THIS WORK SHALL BE SUBSIDIARY TO ITEM 502.

THE CONTRACTOR WILL PROVIDE AND MAINTAIN SKILLED FLAGGERS EQUIPPED WITH TWO-WAY RADIOS TO HANDLE TRAFFIC THROUGH THE WORK AREAS FOR THE SAFETY AND CONVENIENCE OF THE TRAVELING PUBLIC AND CONTRACTOR PERSONNEL.

AUTOMATED FLAGGER ASSISTANCE DEVICES (AFADS) MAY BE USED AT THE CONTRACTOR'S EXPENCE. IF THE CONTRACTOR CHOOSES TO USE AFADS, TCP (1-6) SHALL BE FOLLOWED.

PAY ATTENTION TO OVERHEAD UTILITIES.

MAINTAIN DRIVEWAY AND SIDE STREET ACCESS AT ALL TIMES WITH AN ALL WEATHER SURFACE CONSISTING OF RAP OR BASE. THIS WORK IS SUBSIDIARY TO ITEM 502.



Falon Renfro, P.E. 9/15/2021
Signature of Registrant & Date



TCP NARRATIVE


SCALE: NTS

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	16
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

DATE: 9/15/2021 2:44:21 PM
FILE: \\txdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\B01_TCP NARRATIVE.dgn


DATE: 9/14/2021 7:38:57 AM
 FILE: \\txdot\project\wisonline.com\txdot5\Documents\18 - DAL\Design Projects\18050112\18050112.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of any information derived from this standard.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation
Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173	05	041, ETC.	SH 34, ETC.
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	KAUFMAN	18	

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein. The user of this standard shall be responsible for its use.

DATE: 9/14/2021 7:38:57 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\18 - DAL\Design Projects\1809142021\1809142021.dgn


SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT:	0173 05
REVISIONS		SECT:	041, ETC. SH 34, ETC.
9-07	8-14	DIST:	
7-13	5-21	COUNTY:	KAUFMAN
		SHEET NO.:	19

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2021 7:38:57 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1 - General\STANDARDS\bc-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflective when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTC list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTC) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTC lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTC list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.


FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12



<p>BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES</p>			
<p>BC (4) - 21</p>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CR:	TxDOT
		OW:	TxDOT
		CK:	TxDOT
REVISIONS	CONT	SECT	JOB
0173	05	041, ETC.	SH 34, ETC.
9-07	8-14	DIST	COUNTY
7-13	5-21	DAL	KAUFMAN
			SHEET NO.
			20

DATE: 9/14/2021 7:38:58 AM
 FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\01705041\4 - Design Plan Set\General\STANDARD\BC-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS





GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



WEDGE ANCHORS
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT
BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0173	05	041, ETC.	SH	34,	ETC.			
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	DAL	KAUFMAN	21					

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXXX TO XXXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT


Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CONT:	SECT:
REVISIONS	0173 05	JOB:	041, ETC. SH 34, ETC.
9-07	8-14	DIST:	COUNTY:
7-13	5-21	DAL:	KAUFMAN
		SHEET NO.:	22

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/14/2021 7:38:58 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Design Projects\017305041\4 - Design\Plan Set\1 - General\STANDARDS\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS
END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation
 Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0173	05	041, ETC.		SH 34, ETC.			
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	DAL	KAUFMAN			23			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 9/14/2021 7:38:59 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\STANDARDS\bc-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS



- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.



BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension)
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel
 mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0173	05	041, ETC. SH 34, ETC.					
4-03	8-14					SHEET NO.			
9-07	5-21								
7-13		DAL	KAUFMAN						24


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2021 7:38:59 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Design Projects\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1 - General\STANDARDS\bc-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
2. The OTLD may be used in combination with 42" cones or VPs.
3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
4. To be effective, the chevron should be visible for at least 500 feet.
5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
2. LCDs may be used instead of a line of cones or drums.
3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

1. Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

**Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173	05	041, ETC.	SH 34, ETC.
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	KAUFMAN	25	

DATE: 9/14/2021 7:39:00 AM
 FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1 - General\STANDARDS\bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TRAFFIC CONTROL FOR MATERIAL STOCKPILES


Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




PLAN VIEW

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) -21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0173	05	041, ETC. SH 34, ETC.					
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	DAL	KAUFMAN	26					

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12




BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		0173 05 041, ETC. SH 34, ETC.		
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	DAL	KAUFMAN	27	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 9/14/2021 7:39:00 AM
 FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\General\STANDARDS\bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS



BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173	05	041, ETC.	SH 34, ETC.
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	DAL	KAUFMAN	28	
11-02 8-14				

DATE: 9/14/2021 7:39:00 AM
 FILE: \\txdot.projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\STANDARDS\bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DATE: 9/14/2021 7:39:06 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\18 - DAL\Design Projects\180904101\180904101.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units or for the use of this standard in any other project or for any other purpose.



LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Automated Flagger Assistance Device (AFAD)		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- AFADs shall only be used in situations where there is one lane of approaching traffic in the direction to be controlled.
- Adequate stopping sight distance must be provided to each AFAD location for approaching traffic. (See table above).
- Each AFAD shall be operated by a qualified/certified flagger. Flaggers operating AFADs shall not leave them unattended while they are in use.
- One flagger may operate two AFADs only when the flagger has an unobstructed view of both AFADs and of the approaching traffic in both directions.
- When pilot cars are used, a flagger controlling traffic shall be located on each approach. AFADs shall not be operated by the pilot car operator.
- All AFADs shall be equipped with gate arms with an orange or fluorescent red-orange flag attached to the end of the gate arm. The flag shall be a minimum of 16" square.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the AFAD.
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- The R1-7aT "WAIT ON STOP" sign and the R1-8aT "GO ON SLOW" sign shall be installed at the AFAD location on separate supports or they may be fabricated as one 48" x 30" sign. They shall not obscure the face of the STOP/SLOW AFAD.
- The R10-6 "STOP HERE ON RED" arrow sign shall be offset so as not to obscure the lenses of the AFAD.


Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 AUTOMATED FLAGGER ASSISTANCE DEVICES (AFADs)**

TCP (1-6)-18


FILE: tcp1-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0173 05	041, ETC.	SH 34, ETC.
	DIST	COUNTY	SHEET NO.	
	DAL	KAUFMAN	29	

DATE: 9/14/2021 7:39:12 AM
 FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\180904101\180904101.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions that may appear herefrom.




TCP (2-1a)

WORK SPACE NEAR SHOULDER
 Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
 Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
 - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - Additional work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18


FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	0173	05	041, ETC.	SH 34, ETC.
2-94 4-98	DIST:	COUNTY:	SHEET NO.	
8-95 2-12	DAL	KAUFMAN	30	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project. For more information, contact the Texas Department of Transportation, 12000 North Loop West, Dallas, Texas 75244, or call 1-800-392-0011.

DATE: 9/14/2021 7:39:17 AM
 FILE: \\txdot\project\wiseon\line.com\txdot\Documents\18 - DAL\Design Projects\180901\180901.dgn



TCP (2-2a)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH YIELD SIGNS
 (Less than 2000 ADT - See Note 9)



TCP (2-2b)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)



TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL			
TCP (2-2) - 18			
FILE:	tcp2-2-18.dgn	DN:	CK:
© TxDOT	REVISIONS	CON:	SECT:
8-95	3-03	0173	05
1-97	2-12	JOB: 041, ETC. SH 34, ETC.	
4-98	2-18	DIST:	COUNTY:
		DAL	KAUFMAN
			SHEET NO. 31

DATE: 9/14/2021 7:39:23 AM
 FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\18041010001\18041010001.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from its use.



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.


Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS


TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173	05	041, ETC.	SH 34, ETC.
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	DAL	KAUFMAN	32	
4-98 2-18				


DATE: 9/14/2021 7:39:35 AM
 FILE: \\txdot\project\wiseonline.com\TXDOT5\Documents\18 - DAL\Design Projects\1809041\1809041.dwg
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format.




TCP (3-3a)
TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3b)
TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)



TCP (3-3c)
DIVIDED MULTILANE HIGHWAY




TCP (3-3d)
UNDIVIDED MULTILANE HIGHWAY




TRAIL/SHADOW VEHICLE A

with RIGHT Directional display
Flashing Arrow Board




TRAIL/SHADOW VEHICLE B

with Flashing Arrow Board
in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
12. For divided highways with three or four lanes in each direction, use TCP(3-2).
13. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
14. The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
15. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.


Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/REMOVAL
TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173 05	041, ETC.	SH 34, ETC.	
2-94 4-98				
8-95 7-13	DIST	COUNTY	SHEET NO.	
1-97 7-14	DAL	KAUFMAN	34	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein. TxDOT is not responsible for the accuracy of the information contained herein.

DATE: 9/14/2021 7:39:41 AM
 FILE: \\txdot\project\wiseonline.com\TxDOT\Documents\18 - DAL\Design Projects\1809041\1809041.dgn



NOTE
 Signing shown for one direction of travel only.

NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS



TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS
 For seal coat, micro-surface or similar operations

"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- A. Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- B. At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- D. R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- A. Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- B. At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- C. The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- A. When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- A. Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- B. Tabs shall not be used to simulate edge lines.
- C. Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- A. The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- B. Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- 1. The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- 2. The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
- 3. Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- 4. When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
- 5. Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.



TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS


TCP (7-1) - 13

FILE:	tcp7-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	March 1991	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS	0173 05	041, ETC.		SH 34, ETC.					
4-92 4-98	1-97 7-13	DIST:	COUNTY:	SHEET NO.					
		DAL	KAUFMAN	35					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units. This standard is not intended to replace any other standards or specifications.

DATE: 9/14/2021 7:39:46 AM
 FILE: \\txdot.projectwiseonline.com:TXDOTS\Documents\18 - DAL\Design Projects\180411\180411.dwg

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm







WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	0173	SECT:	05	JOB:	041, ETC.	SH:	34, ETC.
REVISIONS:		DIST:	DAL	COUNTY:	KAUFMAN	SHEET NO.:	36		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein. TxDOT is not responsible for any errors or omissions in this document. DATE: 9/14/2021 7:39:52 AM FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\0904101\0904101.dgn



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"







SIGNING FOR UNEVEN LANES

WZ (UL) - 13

FILE: wzu1-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT	APRIL 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS		0173	05	041, ETC.	SH 34, ETC.
8-95	2-98	7-13	DIST	COUNTY	SHEET NO.
1-97	3-03	DAL	KAUFMAN		37


DATE: 9/14/2021 7:40:18 AM
 FILE: \\txdot\projectwiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -1.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date






**SH 34
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=100' SHEET 1 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	39
CHECK FR	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	


DATE: 9/14/2021 7:40:24 AM
 FILE: pw:\txdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -2.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date







SH 34
 PLAN AND PAVEMENT
 MARKINGS

SCALE: 1"=100' SHEET 2 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	40
CHECK FR	CONTROL	SECTION	JOB	
	0173	05	041, ETC.	


DATE: 9/14/2021 7:40:31 AM
 FILE: pw:\txdot\projectwise\line.com\txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -3.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date





**SH 34
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=100' SHEET 3 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	41
CHECK	FR	CONTROL	SECTION	
CHECK	FR	0173	05	
			JOB	
			041, ETC.	



DATE: 9/14/2021 7:40:37 AM
 FILE: pw:\xtdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -4.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date







**SH 34
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=100' SHEET 4 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	42
CHECK	FR	CONTROL	SECTION	
FR	0173	05	041, ETC.	

DATE: 9/14/2021 7:40:45 AM
 FILE: pw:\txdot\projectwise\line.com\txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -5.dgn




LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

NOTES:

1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro P.E. 9/14/2021
 Signature of Registrant & Date







SH 34
 PLAN AND PAVEMENT
 MARKINGS

SCALE: 1"=100' SHEET 5 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	43
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	


DATE: 9/14/2021 7:40:51 AM
 FILE: pw:\txdot\projectwiseonline.com\txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -6.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date






**SH 34
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=100' SHEET 6 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	44
CHECK	FR	CONTROL	SECTION	
CHECK	FR	0173	05	
			JOB	
			041, ETC.	


DATE: 9/14/2021 7:40:58 AM
 FILE: pw:\txdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -7.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date







SH 34
 PLAN AND PAVEMENT
 MARKINGS

SCALE: 1"=100' SHEET 7 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	45
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	

DATE: 9/14/2021 7:41:04 AM
 FILE: pw:\txdot\projectwiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -8.dgn




LEGEND

(XX)	DRIVEWAY ASSIGNED NUMBER
------	--------------------------

NOTES:

1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date







SH 34
 PLAN AND PAVEMENT
 MARKINGS

SCALE: 1"=100' SHEET 8 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	46
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	


DATE: 9/14/2021 7:41:10 AM
 FILE: pw:\txdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -9.dgn



LEGEND

(XX)	DRIVEWAY ASSIGNED NUMBER
------	--------------------------

- NOTES:
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro P.E. 9/14/2021
 Signature of Registrant & Date





SH 34
 PLAN AND PAVEMENT
 MARKINGS

SCALE: 1"=100' SHEET 9 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	47
CHECK	FR	CONTROL	SECTION	
CHECK	FR	0173	05	
			JOB	
			041, ETC.	


DATE: 9/14/2021 7:41:17 AM
 FILE: pw:\txdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\SH 34 STRIPING LAYOUT -10.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date





**SH 34
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=100' SHEET 10 OF 10

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	48
CHECK FR	CONTROL	SECTION	JOB	
	0173	05	041, ETC.	


DATE: 9/14/2021 7:41:35 AM
 FILE: pw:\t\dot\projectwiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan1.dgn



LEGEND

(XX)	DRIVEWAY ASSIGNED NUMBER
------	--------------------------

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date




**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 1 OF 17


DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	49
FR	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

DATE: 9/14/2021 7:41:35 AM
 FILE: pw:\txdot\projectwiseonline.com\txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan1.dgn

MATCHLINE STA. 12+00.00
 MATCHLINE STA. 18+00.00
 MATCHLINE STA. 18+00.00
 MATCHLINE STA. 24+00.00




PI STATION = 16+67.74
 DELTA = 2° 26' 18.31" (LT)
 DEGREE OF CURVE = 0° 48' 51.48"
 TANGENT = 149.75
 LENGTH = 299.45
 RADIUS = 7,036.19
 PC STATION = 15+17.99
 PT STATION = 18+17.44



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**




SCALE: 1"=50' SHEET 2 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	50
FR	CONTROL	SECTION	JOB	
CHECK	FR	0173	05 041, ETC.	

DATE: 9/14/2021 7:41:35 AM
 FILE: pw:\t\dot\projectwiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan1.dgn

NOTE:
 DRIVEWAYS #11 & 12
 BECAME ONE SINGLE DRIVEWAY
 AFTER THIS SURVEY WAS COMPLETED


PI STATION = 25+71.86
 DELTA = 4° 45' 49.62" (RT)
 DEGREE OF CURVE = 0° 40' 44.31"
 TANGENT = 351.01
 LENGTH = 701.62
 RADIUS = 8,458.55
 PC STATION = 22+20.85
 PT STATION = 29+22.46



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 3 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	51
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	



DATE: 9/14/2021 7:41:35 AM
 FILE: pw:\txdot\projectwiseonline.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan1.dgn

MATCHLINE STA. 36+00.00

MATCHLINE STA. 42+00.00

MATCHLINE STA. 42+00.00


MATCHLINE STA. 48+00.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 4 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	52
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	



DATE: 9/22/2021 9:49:20 AM
 FILE: \\fdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan1.dgn

MATCHLINE STA. 48+00.00

MATCHLINE STA. 54+00.00

MATCHLINE STA. 54+00.00


MATCHLINE STA. 60+00.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/22/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 5 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	53
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	



DATE: 9/14/2021 7:41:36 AM
 FILE: pw:\txdot\projectwiseonline.com\txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815p\plan1.dgn

MATCHLINE STA. 60+00.00

MATCHLINE STA. 66+00.00

MATCHLINE STA. 66+00.00


MATCHLINE STA. 72+00.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**


SCALE: 1"=50' SHEET 6 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	54
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	


STA. 69+70
 END 4" YELLOW BRK
 START 4" YELLOW BRK
 4" YELLOW SOLID

DATE: 9/14/2021 7:41:41 AM
 FILE: \\txdot\projectwiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan7.dgn

MATCHLINE STA. 72+00.00
 MATCHLINE STA. 78+00.00




MATCHLINE STA. 78+00.00
 MATCHLINE STA. 84+00.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date





**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 7 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	55
CHECK FR	CONTROL	SECTION	JOB	
	0173	05	041, ETC.	


DATE: 9/14/2021 7:41:41 AM
 FILE: pw:\txdot\projectwiseonline.com\txdot5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan7.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date





**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 8 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	56
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	


DATE: 9/14/2021 7:41:42 AM
 FILE: \\pww\projectwise\line.com:TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan7.dgn




LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



PI STATION	= 105+30.79
DELTA	= 6° 34' 24.28" (RT)
DEGREE OF CURVE	= 4° 20' 00.14"
TANGENT	= 75.93
LENGTH	= 151.69
RADIUS	= 1,322.20
PC STATION	= 104+54.86
PT STATION	= 106+06.55



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date





**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 9 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	57
FR	CONTROL	SECTION	JOB	
CHECK	FR	0173	05 041, ETC.	


DATE: 9/14/2021 7:41:42 AM
 FILE: pw:\xtdot\projectwiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan7.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date






**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 10 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	58
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	


DATE: 9/14/2021 7:41:42 AM
 FILE: \\txdot\projectwise\line.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan7.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/14/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 11 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	59
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	



DATE: 9/15/2021 10:03:04 AM
 FILE: pw:\tdot\projectwiseonline.com:TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan7.dgn

MATCHLINE STA. 132+08.00

MATCHLINE STA. 138+08.00

MATCHLINE STA. 138+08.00


MATCHLINE STA. 144+08.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/15/2021
 Signature of Registrant & Date





**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 12 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	60
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	


DATE: 9/15/2021 10:20:24 AM
 FILE: pw:\t\dot\project\wiseonline.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815p\lan13.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro P.E. 9/15/2021
 Signature of Registrant & Date






**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 13 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	61
CHECK FR	CONTROL	SECTION	JOB	
CHECK FR	0173	05	041, ETC.	


DATE: 9/15/2021 10:21:23 AM
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan13.dgn



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:**
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/15/2021
 Signature of Registrant & Date



**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 14 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
SB	TEXAS	DAL	KAUFMAN	62
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	




DATE: 9/15/2021 TIME: 10:14 AM FILE: \\pxdot.projectwiseonline.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757 OVERLAY\2815plan13.dgn

MATCHLINE STA. 168+08.00

MATCHLINE STA. 174+08.00

MATCHLINE STA. 174+08.00


MATCHLINE STA. 180+08.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro P.E. 9/15/2021
Signature of Registrant & Date



**FM 2757
PLAN AND PAVEMENT
MARKINGS**

SCALE: 1"=50' SHEET 15 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	63
FR	CONTROL	SECTION	JOB	
CHECK	FR	0173	05 041, ETC.	




DATE: 9/15/2021 10:22:14 AM
 FILE: pw:\t\dot\project\wiseonline.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan13.dgn

MATCHLINE STA. 180+08.00

MATCHLINE STA. 186+08.00

MATCHLINE STA. 186+08.00


MATCHLINE STA. 192+08.00



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/15/2021
 Signature of Registrant & Date





**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 16 OF 17

DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK FR	TEXAS	DAL	KAUFMAN	64
CHECK	CONTROL	SECTION	JOB	
FR	0173	05	041, ETC.	

DATE: 9/15/2021 10:22:34 AM
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\281501009-FM2757-OVERLAY\2815plan13.dgn


MATCHLINE STA. 192+08.15



LEGEND

(XX) DRIVEWAY ASSIGNED NUMBER

- NOTES:
1. ALL EXISTING SIGNS TO REMAIN IN PLACE.
 2. EXISTING SIGNS AND MAILBOXES DAMAGED BY CONTRACTOR, SHALL BE REPLACED BY CONTRACTOR'S OWN EXPENSES.
 3. EXISTING METAL BEAM GUARD FENCE TO REMAIN IN PLACE.



Falon Renfro, P.E. 9/15/2021
 Signature of Registrant & Date




**FM 2757
 PLAN AND PAVEMENT
 MARKINGS**

SCALE: 1"=50' SHEET 17 OF 17


DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	65
FR	CONTROL	SECTION	JOB	
CHECK	FR	0173	05 041, ETC.	

DATE: 9/14/2021 8:09:21 AM
 FILE: p:\t\dot\project\wiseonline.com\TxDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1 - General\G03_RDWY_MISC_DETAIL.dgn



PAVEMENT TRANSITION DETAIL

- NOTE:
1. EXACT LOCATIONS OF PROPOSED PAVEMENT TRANSITIONS ARE SHOWN IN THE TYPICAL SECTIONS.
 2. EXISTING MAILBOXES ARE TO REMAIN.
 3. MAILBOXES DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.





Falon Renfro P.E. 9/14/2021
 Signature of Registrant & Date



ROADWAY MISC DETAILS



SCALE: NTS				SHEET 1 OF 1
DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET)		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	66
FR	CONTROL	SECTION	JOB	
CHECK	FR	0173	05 041, ETC.	

DATE: 9/15/2021 9:16:48 AM
 FILE: p:\t\tdot\project\wise\line.com:TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\G02_DRIVEWAY_INTERSECTION DETAIL.dgn





- DRIVEWAY/INTERSECTION NOTES:**
1. EXIST CONC DRIVEWAY - TO REMAIN. PLANE SHOULDER 0" TO 2" AND OVERLAY 2".
 2. EXISTING DRIVEWAY CULVERTS ARE TO REMAIN IN PLACE. ANY DRIVEWAY CULVERTS DAMAGED BY THE CONTRACTOR SHALL BE REPLACED OR REPAIRED AT THE CONTRACTOR'S EXPENCE.
 3. MAXIMUM DRIVEWAY SLOPE 12% AND MAXIMUM INTERSECTION SLOPE 10%
 4. NEW ACP SHALL BE SP-C SAC-B PG 70-22 FOR CCSJ 0173-05-041 & SP-C SAC-B PG 64-22 FOR CSJ 2815-01-009


TYPICAL DRIVEWAY/INTERSECTION ASPHALT



TYPICAL DRIVEWAY/INTERSECTION CONCRETE



TYPICAL DRIVEWAY/INTERSECTION GRAVEL





Falon Renfro, P.E. 9/15/2021
 Signature of Registrant & Date




DRIVEWAY/INTERSECTION DETAILS

SCALE: NTS


DESIGN	FED. RD. DIV. NO.	PROJECT NO.		HIGHWAY NO.
SB	6	(SEE TITLE SHEET) SH		34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DAL	KAUFMAN	67
FR	CONTROL	SECTION	JOB	
CHECK	JR	0173	05	041, ETC.



TAPERED OUTSIDE
EDGE DETAIL



TAPERED JOINT DETAIL
1.5" TO 4" LIFTS




TAPERED JOINT DETAIL
OVER 4" LIFTS

@ IF BACKFILLED SLOPE IS LESS THAN 3:1,
COVER WEDGE WITH APPROVED BACKFILL.

* SEE TYPICAL SECTION FOR DEPTH AND TYPE OF HMA.
NOTCH DEPTH SHALL NOT BE LESS THAN NOMINAL AGGREGATE SIZE.

NOTES:

1. THE ABOVE DETAILS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LANE WIDTH AND BE LAID MONOLITHICALLY WITH ADJOINING MAT. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED STRIKE-OFF DEVICE THAT WILL PROVIDE A UNIFORM SLOPE AND WILL NOT RESTRICT THE MAIN SCREED. CLEAN WEDGE PRIOR TO PLACEMENT OF TACK COAT. TACK COAT SHALL BE APPLIED UNIFORMLY TO THE IN-PLACE TAPER WITH A DISTRIBUTOR BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED. COMPACTION OF THE INITIAL TAPER SECTION WILL BE REQUIRED AS NEAR TO FINAL DENSITY AS POSSIBLE. ROLL ADJACENT MAT FROM HOT SIDE TO COLD.
2. THE TYPE OF DEVICE TO PRODUCE ABOVE REFERENCED DETAILS SHALL PROVIDE INITIAL COMPACTION EQUIVALENT TO LAYDOWN MACHINE, WITH FINAL DENSITY ADHERING TO NOTE 1, AND BE APPROVED BY THE ENGINEER.
3. HOT MIX MATERIAL AND PLACEMENT SHALL BE PAID FOR UNDER THE PERTINENT ITEM. ANY ADDITIONAL SURFACE PREPARATION, TACK COAT, TACK COAT PLACEMENT, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS TO PRODUCE TAPERED EDGE AND JOINTS AS DESCRIBED ABOVE SHALL BE CONSIDERED SUBSIDIARY TO THE HOT MIX ITEM.
4. THE TAPERED JOINT DETAIL IS NOT INTENDED FOR USE ON 2 WAY 2 LANE ROADBED CENTERLINE WITH LESS THAN 22' OVERALL WIDTH.
5. FULL PAVING OF ALL LANES AND SHOULDERS BY THE END OF EACH DAY PRODUCTION WILL NOT REQUIRE A TAPERED JOINT.



**HOT MIX EDGE AND
LONGITUDINAL JOINT DETAILS
DALLAS DISTRICT STANDARD**
LJD(1-1)-07


FED. RD. DIV. NO.	PROJECT NUMBER	SHEET NUMBER
18	(SEE TITLE SHEET)	68
STATE	DISTRICT	COUNTY
TEXAS	DAL	KAUFMAN
CONTROL	SECTION	SECTION HIGHWAY NUMBER
0173	05	041, ETC. SH 34, ETC.

REVISED ON 9/10/08

FILENAME: pw:\txdot\projectwiseonline.com\txdot\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1 - General\STANDARDS\jld1.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2021
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\STANDARDS\tehmac11 (1).dgn



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS


CONDITION - 1
 THIN HMAC SURFACES OR HMAC OVERLAY
 WITH THICKNESS OF 2.5" OR LESS



** EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 2
 OVERLAY OF EXISTING PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 3
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 4
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 5" OR GREATER

GENERAL NOTES












1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

(NOT TO SCALE)

					Design Division Standard
TAPERED EDGE DETAILS HMAC PAVEMENT					
TE (HMAC) - 11					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS		0173	05	041, ETC.	SH 34, ETC.
DIST	COUNTY	SHEET NO.			
DAL	KAUFMAN	69			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. The user of this standard is advised to consult the latest edition of the Texas Engineering Practice Act and the Texas Administrative Code for any changes or amendments.


DATE: 06/15/2021 10:01:55AM
 FILE: D:\PROJECTS\OBJECT MARKERS\18 - DAL\Design Project\18 - DAL\Documents\18 - DAL\Design Project\18 - DAL\Design Project.dwg

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS																										
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT																									
GND	GND	SRF	WAS	WAP	GF 1																									
																														
	EMBEDDED	SURFACE MOUNT	STEEL	PLASTIC	CONCRETE TRAFFIC BARRIER (CTB)																									
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.		NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.																										
TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS																										
																														
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		See general notes 1, 2 and 3.																										
GENERAL NOTES																														
1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.																														
 Traffic Safety Division Standard																														
DELINEATOR & OBJECT MARKER INSTALLATION D & OM(2)-20																														
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>FILE: dom2-20.dgn</td> <td>DN: TxDOT</td> <td>CK: TxDOT</td> <td>OW: TxDOT</td> <td>CR: TxDOT</td> </tr> <tr> <td>© TxDOT August 2004</td> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>REVISIONS</td> <td>017305</td> <td>041</td> <td>ETCSH 34</td> <td>ETC.</td> </tr> <tr> <td>10-09 3-15</td> <td>DIST</td> <td>COUNTY</td> <td colspan="2">SHEET NO.</td> </tr> <tr> <td>4-10 7-20</td> <td>DAL</td> <td>KAUFMAN</td> <td colspan="2">71</td> </tr> </table>						FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT	© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY	REVISIONS	017305	041	ETCSH 34	ETC.	10-09 3-15	DIST	COUNTY	SHEET NO.		4-10 7-20	DAL	KAUFMAN	71	
FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT																										
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY																										
REVISIONS	017305	041	ETCSH 34	ETC.																										
10-09 3-15	DIST	COUNTY	SHEET NO.																											
4-10 7-20	DAL	KAUFMAN	71																											

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units or for any other changes to this standard. The user is responsible for verifying the accuracy of this standard from its use.


DATE: 06/24/2002 10:01:50 AM
 FILE: D:\PROJECTS\OBJECT\WISCONSIN\18 - DAL\Design Project\180411.dwg

CROSSOVERS




DETAIL 1

FOR CULVERTS WITHOUT MBGF




DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES




DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator


DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4) - 20


FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173	05	041, ETC. SH 34, ETC.	
3-15	DIST	COUNTY	SHEET NO.	
7-20	DAL	KAUFMAN	72	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. This standard is subject to change without notice.


DATE: 9/14/2021 7:42:56 AM
 FILE: \\txdot\project\wiseon\line.com\TxDOT5\Documents\18 - DAL\Design Projects\1809041\1809041.dwg




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.

YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

GENERAL NOTES

- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1) - 20


FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	0173	05	041, ETC.	SH 34, ETC.
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	DAL	KAUFMAN	73	

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein. This standard is subject to change without notice.




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



RAISED PAVEMENT MARKERS


GENERAL NOTES

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.




POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	0173	05	041, ETC.	SH 34, ETC.
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	DAL	KAUFMAN	74	




**REFLECTORIZED PROFILE
PATTERN DETAIL
USING REFLECTIVE PROFILE PAVEMENT MARKINGS**



NOTE
Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any project.

DATE: 9/14/2021 7:43:08 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\18 - DAL\Design Projects\041111\041111.dwg



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

LANE REDUCTION

NOTES


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES

- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE



TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A

DETAIL B


Texas Department of Transportation
 Traffic Safety Division Standard

**TWO-WAY LEFT TURN LANES,
 RURAL LEFT TURN BAYS,
 AND LANE REDUCTION
 PAVEMENT MARKINGS
 PM(3) - 20**

FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173	05	041, ETC.	SH 34, ETC.
5-00 2-10	DIST	COUNTY	SHEET NO.	
8-00 2-12	DAL	KAUFMAN	75	
3-03 6-20				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information presented herein. This standard is subject to change without notice.

DATE: 9/14/2021 7:43:13 AM
 FILE: \\txdot.projectwiseonline.com:txdot5\Documents\18 - DAL\Design Projects\180411\0411001\180411001.dgn




MULTILANE UNDIVIDED HIGHWAY WITH SHOULDER

CENTERLINE RUMBLE STRIPS




PROFILE VIEW




PLAN VIEW
OPTION 1

MILLED CENTERLINE RUMBLE STRIPS




PROFILE VIEW




PLAN VIEW
OPTION 2

RAISED CENTERLINE RUMBLE STRIPS



PROFILE VIEW



PLAN VIEW
OPTION 3

PROFILE CENTERLINE MARKINGS

GENERAL NOTES

1. This standard sheet provides guidelines for installing centerline rumble strips on multilane undivided highways.
2. Centerline and edgeline rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks.
6. Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inch depth of milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips for normal centerline spacing. For wider medians, specify in the plans the exact placement of the rumble strips. Place the rumble strips under each centerline marking or centered in the middle of the median.

WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The color of the button should be yellow for a continuous no passing roadway. The button will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.

WHEN INSTALLING EDGE LINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

11. See standard sheet RS(4).



CENTERLINE RUMBLE STRIPS ON MULTILANE UNDIVIDED HIGHWAYS


RS(2) - 13

FILE:	r's(2)-13.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	October 2013	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0173	05	041, ETC. SH 34, ETC.					
DIST	COUNTY	SHEET NO.							
DAL	KAUFMAN	76							

DISCLAIMER:


The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein.

DATE: 9/14/2021 7:43:19 AM
FILE: \\txdot\project\wiseonline.com\TxDOT\Documents\18 - DAL\Design Projects\04109041\04109041.dwg




TWO LANE TWO-WAY ROADWAYS


CENTERLINE RUMBLE STRIPS




MILLED RUMBLE STRIPS



RAISED TRAFFIC BUTTONS




PREFORMED THERMOPLASTIC STRIPS




PROFILE MARKINGS

PROFILE VIEW




PLAN VIEW
OPTION 1

MILLED CENTERLINE RUMBLE STRIPS




PLAN VIEW
OPTION 2

RAISED CENTERLINE RUMBLE STRIPS



PLAN VIEW
OPTION 3

RAISED CENTERLINE RUMBLE STRIPS AND PREFORMED THERMOPLASTIC STRIPS



PLAN VIEW
OPTION 4

PROFILE CENTERLINE MARKINGS AND PREFORMED THERMOPLASTIC STRIPS

GENERAL NOTES

1. This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
2. Centerline and edgeline rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks.
6. Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, and dimensions pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inch depth of milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips.

WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
11. The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.

WHEN INSTALLING EDGELINE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

12. See standard sheet RS(4).




CENTERLINE RUMBLE STRIPS ON TWO LANE TWO-WAY HIGHWAYS


RS(3) - 13

FILE:	rs(3) - 13.dgn	DW:	TxDOT	CR:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	October 2013	CONT.	SECT.	JOB	HIGHWAY				
REVISIONS	0173	05	041, ETC. SH 34, ETC.						
	DIST.	COUNTY	SHEET NO.						
	DAL	KAUFMAN	77						

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units of measurements.
 DATE: 9/14/2021 7:43:24 AM
 FILE: \\txdot\project\wiseonline.com:TXDOTS\Documents\18 - DAL\Design Projects\1809041\1809041.dwg




PLAN VIEW




PROFILE VIEW
OPTION 1

**CONTINUOUS MILLED DEPRESSIONS
(Rumble Strips)**




PLAN VIEW



PROFILE VIEW
OPTION 2


**CONTINUOUS MILLED DEPRESSIONS
(Rumble Strips)**

* This distance may vary based on width of shoulder




PLAN VIEW

* This distance may vary based on width of shoulder




PROFILE VIEW
OPTION 3

**CONTINUOUS MILLED DEPRESSIONS
(Rumble Strips)**




PLAN VIEW




PROFILE VIEW
OPTION 4

**CONTINUOUS MILLED DEPRESSIONS
(Rumble Strips)**



PLAN VIEW
OPTION 5

RAISED EDGELINE RUMBLE STRIPS



PLAN VIEW
OPTION 6

PROFILE EDGELINE MARKINGS

SHOULDER WIDTH TABLE		
EQUAL TO OR LESS THAN 2 FEET	GREATER THAN 2 FEET LESS THAN 4 FEET	EQUAL TO OR GREATER THAN 4 FEET
Option 1, 5 OR 6	Option 1, 2, 3 5 OR 6	Option 2, 4, 5 OR 6

GENERAL NOTES


- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
- See the table below for determining what options may be used for edgeline rumble strips.

WHEN INSTALLING MILLED DEPRESSION EDGELINE RUMBLE STRIPS:

- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
- Pavement markings can be applied over milled shoulder rumble strips to create an edgeline rumble stripe.
- Breaks in edgeline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inches depth of milled rumble strip may be considered in these areas.
- On roadways with high bicycle activity, consideration should be given before the installation of edgeline rumble strips. Things to consider include size of rumble strips, rumble strip material and location of rumble strips on the shoulder. If the designer determines that gaps are needed in the rumble strips due to bicycle use of the road, then follow the requirement shown in FHWA Technical Advisory T5040.39, or latest version. A detail of the spacing shall be included in the plans.

WHEN INSTALLING RAISED OR PROFILE EDGELINE RUMBLE STRIPS:

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edgeline when used as a rumble strip. The color of the button should match the color of the adjacent edgeline marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Breaks in edgeline rumble strips using raised traffic buttons shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks when installed on conventional highways.
- The minimum distance between the edgeline and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edgelines may substitute for buttons.




Traffic Operations Division Standard


EDGELINE RUMBLE STRIPS ON UNDIVIDED OR TWO LANE HIGHWAYS RS(4) - 13

FILE: rs(4)-13.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	0173 05	041, ETC. SH 34, ETC.		
DIST	COUNTY	SHEET NO.		
DAL	KAUFMAN	78		


Dallas District Standard for Two-Lane Highway Curve Signing/Markings



Typical Curve Treatment with Intersection



Typical Reverse Curve Edge Line Treatment



Curve Safety Sequence

Applicable Minimum Measures

Advisory Speed 55 mph or higher	Advisory Speed 40-50 mph	Advisory speed 35 mph or less	Curve signing, delineation and pavement markings (listed in order from minimum to maximum level of treatment as needed)
+	+	+	1 Advance warning (36" x 36") and advisory mph (18" x 18")
+	+	+	2 Chevron alignment signs if advisory speed is 15 mph or greater than posted speed
	+	+	3 Edge lines
			3a Pavement width 24' or greater 6" solid white edge line
			3b Pavement width 20' - 24' 4" solid white edge line
			3c Pavement width 20' or less no edge line
			Supplemental Measures
		#	4 Add shoulders and edge line (see #3a)
		#	5 Yellow high intensity fluorescent chevron alignment signs - add reflective sheeting to sign support from bottom edge of sign
#	#	#	6 Large advance warning (48" x 48") and advisory mph (30" x 30")
#	#	#	7 Arrow sign (48" x 24")
		#	8 Large arrow sign with diagonals (96" x 36")
		#	9 Add flashers to advance warning signs
#	#	#	10 Surface treatment to improve friction
		XX	The W1-1R or L sign shall only be used when the advisory speed is 30 mph or less

+ = required
= optional

Applications 4 - 10 are additional supplemental applications which may be added as directed by the Area Engineer.

Note:
"B" - Chevron Spacing referenced from D&OM(3)-20

Notes:

- Two methods will be used to determine the appropriate advisory speed for curves, the GPS Method (existing curves) and the Design Method (new curves).
- Notify the Traffic Engineering Section for all requests on advisory speeds for existing curves.

* Standard Double Yellow Stripes shall be dropped through a non-signalized intersection within the city limit. Outside the city limit, the Standard Double Yellow Strip shall be carried through all non-signalized intersections.

OCT-2014 UPDATED NOTES	Texas Department of Transportation © 2021				
JAN-2016 NOTE ADDED					
SEPT-2016 NOTE ADDED FOR STRIPING IN CURVE	TWO-LANE HIGHWAY CURVE SIGNING & MARKINGS DALLAS DISTRICT STANDARD SCALE: NTS SHEET 1 OF 1				
MAR-2017 REMOVED REFERENCE TO DELINEATORS					
MAY-2019 MODIFIED SIGN SIZE	DESIGN/CK BLS	FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. (SEE TITLE SHEET)		HIGHWAY NO. SH 34, ETC.
	CHECK BLS	STATE	DISTRICT	COUNTY	SHEET NO.
	CHECK FRC	TEXAS	DALLAS	KAUFMAN	79
	CHECK ARO	CONTROL	SECTION	JOB	
		0173	05	041, ETC.	

A. GENERAL SITE DATA

1. PROJECT LIMITS:

SH 34: from N OF BUS SH 34 (VIRGINIA ST) to 3.0 MI S OF HUNT COUNTY LINE
 Begin Project Coordinates (SH 34): Latitude (N): 32.7681° Longitude (W): - 96.2516°
 End Project Coordinates (SH 34): Latitude (N): 32.8177° Longitude (W): - 96.1942°

2. PROJECT SITE MAPS:

- * Project Location Map: (SHEET 3)
- * Drainage Patterns: Typical Sections (SHEET 5)
- * Slopes Anticipated After Major Gradings or Areas of Soil Disturbance: Typical Sections (SHEET 5)
- * Location of Erosion and Sediment Controls: Project Location SHEET 3)
- * Surface Waters and Discharge Locations: Project Location (SHEET 3)
- * Project Specific Location(s) (PSL): To be determined by the project Construction Personnel. Location(s) shown on SW3P Site Map (if PSL location(s) is within one mile of project) and information located in project SW3P Binder (Reference Item *10 below).

3. PROJECT DESCRIPTION:

REHABILITATION OF EXISTING ROAD CONSISTING OF BASE REPAIR, OVERLAY AND PAVEMENT MARKINGS

4. MAJOR SOIL DISTURBING ACTIVITIES:

1.67 ACRES OF SOIL WILL BE DISTURBED AS PART OF ROUTINE MAINTENANCE PROJECT EXEMPT FROM STORM WATER PERMITTING UNDER TXR150000, PART 1, SECTION B

DISTURBANCE (WITHIN LINE AND GRADE OF EXISTING ROADWAY/BASE) INCLUDES TEMPORARY PEELING BACK TOPSOIL AND RETURN OF THE TOPSOIL/BACK FILL AT PAVEMENT EDGES, AND SURFACE STABILIZATION (EMULSION) FOR NATURAL REVEGETATION.

5. EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

SOIL IS WELL DRAINED. GENTLY SLOPING TO MODERATELY STEEP. CLAYEY AND LOOMY SOILS THAT HAVE MODERATE AND VERY SLOW PERMEABILITY. THE GENERAL AREA AROUND THE PROJECT HAS APPROXIMATELY 50% VEGETATION COVER OF MOSTLY GRASSES

6. TOTAL PROJECT AREA: 58.51 Acres

7. TOTAL AREA TO BE DISTURBED: 0.00 Acres (0.00 %)

8. WEIGHTED RUNOFF COEFFICIENT

BEFORE CONSTRUCTION: 0.85
 AFTER CONSTRUCTION: 0.85

9. NAME OF RECEIVING WATERS:

Kings Creek (SEGMENT ID 0818C) and its unnamed tributaries; and tributaries to Greasy Creek which flows to South Fork Sabine River (Segment 0507G. [Segments 0818C and 0507G are both impaired by Bacteria in water (Recreation use).]

10. PROJECT SW3P Binder:

A. For projects disturbing one to five acres, TxDOT will maintain a SW3P Binder at the project field office (if there is not a project field office, should be kept at the Area Office) which contains the following: Index Sheet, TCEQ Signature Authority, TxDOT's and Contractor's Small Construction Site Notice, SW3P Inspector Qualification Statements, EPIC Sheet, SW3P Sheet, Site Location Maps, Inspection and Maintenance Reports (Form 2118), Construction Stage Gate Checklists (CSGC), Stored Material Lists specifying associated control measures and the Appendix which contains the TPDES Construction General Permit, TxDOT and Contractor MS4 Operator Notification(s) and the Construction PSL Permits per all applicable requirements.

B. For projects disturbing 5 acres or more, TxDOT will follow the actions listed in (10.A.) above with the addition of the following: TxDOT and Contractor Notice Of Intent (N.O.I.) and Fee Payment Form, TxDOT and Contractor Large Construction Site Notice (to be used instead of Small Site Notice), and TPDES Permit Coverage Notice.

C. For projects disturbing less than one acre, actions described in (10.A.) and (10.B.) above are not required. Acreage is calculated by adding Total Area To Be Disturbed Acres on project (See *7 above) and the PSL(s) acreage located within one mile of project.

B. EROSION AND SEDIMENT CONTROLS

1. SOIL STABILIZATION PRACTICES: (Select T = Temporary or P = Permanent, as applicable)

- | | |
|--|--|
| <input type="checkbox"/> TEMPORARY SEEDING | <input type="checkbox"/> P PRESERVATION OF NATURAL RESOURCES |
| <input type="checkbox"/> MULCHING (Hay or Straw) | <input type="checkbox"/> FLEXIBLE CHANNEL LINER |
| <input type="checkbox"/> BUFFER ZONES | <input type="checkbox"/> RIGID CHANNEL LINER |
| <input type="checkbox"/> PLANTING | <input type="checkbox"/> SOIL RETENTION BLANKET |
| <input type="checkbox"/> SEEDING | <input type="checkbox"/> COMPOST MANUFACTURED TOPSOIL |
| <input type="checkbox"/> SODDING | <input type="checkbox"/> VERTICAL TRACKING |
| | <input type="checkbox"/> OTHER: |

2. STRUCTURAL PRACTICES: (Select T = Temporary or P = Permanent, as applicable)

- T SILT FENCES
- T EROSION CONTROL LOGS
- EROSION CONTROL COMPOST BERMS (Low Velocity)
- ROCK FILTER DAMS
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION DIKE AND SWALE COMBINATIONS
- PIPE SLOPE DRAINS
- PAVED FLUMES
- ROCK BEDDING AT CONSTRUCTION EXIT
- TIMBER MATTING AT CONSTRUCTION EXIT
- CHANNEL LINERS
- SEDIMENT TRAPS
- SEDIMENT BASINS
- STORM INLET SEDIMENT TRAP
- STONE OUTLET STRUCTURES
- CURBS AND GUTTERS
- STORM SEWERS
- VELOCITY CONTROL DEVICES
- OTHER:

NOTE: TOP OF BMP'S SHOULD NOT BE HIGHER THAN ROADWAY ELEVATION AS NOT TO FLOOD ROADWAY UNLESS PRIOR APPROVAL FROM ENGINEER IS OBTAINED.

3. STORM WATER MANAGEMENT:

A. Storm water drainage will be provided by ditches and storm water systems which carry drainage within the R.O.W. to the lows within the roadway and project site which drains to natural facilities.

4. STORM WATER MANAGEMENT ACTIVITIES: (Sequence of Construction)

1. THE MAJORITY OF THE PROJECT AREA, WITHIN THE TXDOT ROW, IS SURROUNDED BY EXISTING VEGETATION WHICH WILL REMAIN UNDISTURBED AND PROVIDE A NATURAL BUFFER TO PROTECT WATER QUALITY, CONTROL STORM WATER VELOCITY, MINIMIZE POTENTIAL EROSION AND SEDIMENTATION, ETC. TO THE EXTENT PRACTICABLE, PRESERVE EXISTING VEGETATION, MAINTAIN A VEGETATIVE BUFFER ALONG RECEIVING WATERS, AND PHASE CONSTRUCTION ACTIVITIES IN MINIMIZE EXPOSURE OF DISTURBED SOILS.

2. INSTALL SW3P CONTROL DEVICES (BMPs) TO PROTECT RECEIVING WATERS, DOWN SLOPE PERIMETERS, AND ACTIVE ROADWAYS PRIOR TO POTENTIAL POLLUTANT GENERATING CONSTRUCTION ACTIVITIES IN THEIR VICINITY, AS NEEDED AND/OR AS DIRECTED OR AUTHORIZED BY THE ENGINEER. DO NOT INSTALL BMPs MORE THAN TWO WEEKS PRIOR TO THE ACTIVITIES IN THEIR CONTROL AREA.

3. AVOID STORING PORTABLE SANITARY UNITS, CONCRETE WASHOUTS OR CHEMICALS WITHIN 50 FEET UP GRADIENT OF A RECEIVING WATER OR DRAINAGE CONVEYANCE WITHOUT ADEQUATE POLLUTION CONTROLS.

4. CONTRACTOR IS RESPONSIBLE FOR STABILIZING/RE-VEGETATING SOILS DISTURBED BY THE PROJECT AS SOON AS PRACTICABLE OR AS DIRECTED BY THE ENGINEER. FOLLOW TXDOT STANDARDS AND SPECIFICATION AND THE DALLAS DISTRICT VEGETATION ESTABLISHMENT SHEET.

5. NON-STORM WATER DISCHARGES:

Filter non-storm water discharges, or hold in retention basins, before being allowed to mix with storm water. These discharges consist of, but not limited to, non-polluted ground water, spring water, foundation or footing drain water, water used for dust control or pavement washing and vehicle washwater containing no detergents.

C. OTHER REQUIREMENTS & PRACTICES

1. MAINTENANCE:

Maintain all erosion and sediment controls in good working order. Perform any necessary cleaning/repairs/replacements at the earliest possible date prior to next rain event, but no later than 7 calendar days. Ensure the surrounding ground has dried sufficiently to prevent damage from equipment. "Too Wet" is the only reason for not adhering to timeframes described. When construction activities permanently or temporarily cease and are not expected to resume for 14 or more days on a disturbed portion of the site, stabilization measures must be initiated immediately.

2. INSPECTION:

A TxDOT Inspector will perform a regularly scheduled SW3P Inspection every 7 calendar days. An Inspection and Maintenance Report, signed by the TxDOT Inspector and the Contractor, will be filed for each inspection. Revise/clean/repair/replace each BMP control device in accordance with the current Field Inspection and Maintenance Report (Form 2118) and Item 1 (Maintenance) above.

3. WASTE MATERIALS:

On a daily basis, or as may be directed, collect all waste materials, trash and debris from the construction site and deposit into a metal dumpster having a secure cover and which meets all state and local city solid waste management requirements. Empty the dumpster as required by regulation, or as may be directed, at a local approved landfill site. Do not bury construction waste on the construction project site.

4. HAZARDOUS WASTE & SPILL REPORTING:

As a minimum, any products in the following categories are considered to be hazardous: Paints, Acids, Solvents, Fuels, Asphalt Products, Chemical Additives for Soil Stabilization, and Concrete Curing Compounds or Additives. When storing hazardous material on the project site, or at a Project Specific Location, take all practicable precaution to prevent and/or contain any spillage of these materials. In the event of a spill, contact the spill coordinator immediately.

5. SANITARY WASTE:

Use a licensed sanitary waste management contractor to collect all sanitary waste from portable units as may be required by local regulation, or as directed.

6. CONSTRUCTION VEHICLE TRACKING:

On a regular basis, or as may be directed, dampen haul roads for dust control and construct construction entrances/exits. Provide for a motorized broom or vacuum type sweeper to be available on a daily basis, or as may be directed, to remove sediment from paved roadways on project, abutting and traversing the project site.


7. MANAGEMENT PRACTICES:

- A. Construct disposal areas, stockpiles, haul roads and PSL's in a manner that will minimize and control the amount of sediment that may enter receiving waters. Do not locate disposal areas in any wetland, waterbody or streambed.
- B. Locate construction staging areas, vehicle maintenance and PSL's areas in a manner to minimize the runoff of pollutants.
- C. When working in or near a wetland, install and maintain operating soil erosion and sediment controls at all times during construction and isolate the work from the wetland.
- D. Clear all waterways as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.
- E. Procedures and/or practices should be taken to control dust.
- F. Sediment to be removed from roadways daily or when work begins after weather events if construction activities have ceased due to weather event.

FILE NAME

DATE

DESIGNER



Falon Benfroe 9/29/2021
 P.E.
 Signature of Registrant & Date



DALLAS DISTRICT ENVIRONMENTAL

STORM WATER POLLUTION PREVENTION PLAN (SW3P)

TEMPLATE REVISION DATE: 02/07/18

DESIGN	JR	FED. RD. DIV. NO.	6	FEDERAL AID PROJECT NO.	SEE TITLE SHEET	HIGHWAY NO.	SH 34, ETC.
GRAPHICS	FR	STATE	TEXAS	DISTRICT	DALLAS	COUNTY	KAUFMAN
CHECK	FR	CONTROL	SECTION	JOB			80
CHECK	JR		0173	05	041, ETC		

A. GENERAL SITE DATA

1. PROJECT LIMITS:

FM 2757: from FM 740 to FM 741
 Begin Project Coordinates (FM 2757): Latitude (N): 32.69809722° Longitude (W): - 96.50248056°
 End Project Coordinates (FM 2757): Latitude (N): 32.66009444° Longitude (W): - 96.45793889°

2. PROJECT SITE MAPS:

- * Project Location Map: (SHEET 4)
- * Drainage Patterns: Typical Sections (SHEETS 6-9)
- * Slopes Anticipated After Major Gradings or Areas of Soil Disturbance: Typical Sections (SHEETS 6-9)
- * Location of Erosion and Sediment Controls: Project Location Map (SHEETS 4)
- * Surface Waters and Discharge Locations: Project Location Map (SHEETS 4)
- * Project Specific Location(s) (PSL): To be determined by the project Construction Personnel. Location(s) shown on SW3P Site Map (if PSL location(s) is within one mile of project) and information located in project SW3P Binder (Reference Item *10 below).

3. PROJECT DESCRIPTION:

REHABILITATION OF EXISTING ROAD CONSISTING OF BASE REPAIR, OVERLAY AND PAVEMENT MARKINGS

4. MAJOR SOIL DISTURBING ACTIVITIES:

1.79 ACRES OF SOIL WILL BE DISTURBED AS PART OF ROUTINE MAINTENANCE PROJECT EXEMPT FROM STORM WATER PERMITTING UNDER TXR150000, PART 1, SECTION B

DISTURBANCE (WITHIN LINE AND GRADE OF EXISTING ROADWAY/BASE) INCLUDES TEMPORARY PEELING BACK TOPSOIL AND RETURN OF THE TOPSOIL/BACK FILL AT PAVEMENT EDGES, WITHIN FINAL SURFACE STABILIZATION (EMULSION) FOR NATURAL REVEGETATION.

5. EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

SOIL IS WELL DRAINED. GENTLY SLOPING TO MODERATELY STEEP. CLAYEY AND LOOMY SOILS THAT HAVE MODERATE AND VERY SLOW PERMABILITY. THE GENERAL AREA AROUND THE PROJECT HAS APPROXIMATELY 50% VEGETATION COVER OF MOSTLY GRASSES

6. TOTAL PROJECT AREA: 44.80 Acres

7. TOTAL AREA TO BE DISTURBED: 0.00 Acres (0.00 %)

8. WEIGHTED RUNOFF COEFFICIENT

BEFORE CONSTRUCTION: 0.85
 AFTER CONSTRUCTION: 0.85

9. NAME OF RECEIVING WATERS:

MUSTANG CREEK and its unnamed tributaries which flow to EAST FORK TRINIRY RIVER [(segment ID 0819) water quality impaired by sulfate in water and by bacteria in water (recreational use)].

10. PROJECT SW3P Binder:

A. For projects disturbing one to five acres, TxDOT will maintain a SW3P Binder at the project field office (if there is not a project field office, should be kept at the Area Office) which contains the following: Index Sheet, TCEQ Signature Authority, TxDOT's and Contractor's Small Construction Site Notice, SW3P Inspector Qualification Statements, EPIC Sheet, SW3P Sheet, Site Location Maps, Inspection and Maintenance Reports (Form 2118), Construction Stage Gate Checklists (CSGC), Stored Material Lists specifying associated control measures and the Appendix which contains the TPDES Construction General Permit, TxDOT and Contractor MS4 Operator Notification(s) and the Construction PSL Permits per all applicable requirements.

B. For projects disturbing 5 acres or more, TxDOT will follow the actions listed in (10.A.) above with the addition of the following: TxDOT and Contractor Notice Of Intent (N.O.I.) and Fee Payment Form, TxDOT and Contractor Large Construction Site Notice (to be used instead of Small Site Notice), and TPDES Permit Coverage Notice.

C. For projects disturbing less than one acre, actions described in (10.A.) and (10.B.) above are not required. Acreage is calculated by adding Total Area To Be Disturbed Acres on project (See *7 above) and the PSL(s) acreage located within one mile of project.

B. EROSION AND SEDIMENT CONTROLS

1. SOIL STABILIZATION PRACTICES: (Select T = Temporary or P = Permanent, as applicable)

- | | |
|--|--|
| <input type="checkbox"/> TEMPORARY SEEDING | <input type="checkbox"/> P PRESERVATION OF NATURAL RESOURCES |
| <input type="checkbox"/> MULCHING (Hay or Straw) | <input type="checkbox"/> FLEXIBLE CHANNEL LINER |
| <input type="checkbox"/> BUFFER ZONES | <input type="checkbox"/> RIGID CHANNEL LINER |
| <input type="checkbox"/> PLANTING | <input type="checkbox"/> SOIL RETENTION BLANKET |
| <input type="checkbox"/> SEEDING | <input type="checkbox"/> COMPOST MANUFACTURED TOPSOIL |
| <input type="checkbox"/> SODDING | <input type="checkbox"/> VERTICAL TRACKING |
| | <input type="checkbox"/> OTHER: |

2. STRUCTURAL PRACTICES: (Select T = Temporary or P = Permanent, as applicable)

- SILT FENCES
- EROSION CONTROL LOGS
- EROSION CONTROL COMPOST BERMS (Low Velocity)
- ROCK FILTER DAMS
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION DIKE AND SWALE COMBINATIONS
- PIPE SLOPE DRAINS
- PAVED FLUMES
- ROCK BEDDING AT CONSTRUCTION EXIT
- TIMBER MATTING AT CONSTRUCTION EXIT
- CHANNEL LINERS
- SEDIMENT TRAPS
- SEDIMENT BASINS
- STORM INLET SEDIMENT TRAP
- STONE OUTLET STRUCTURES
- CURBS AND GUTTERS
- STORM SEWERS
- VELOCITY CONTROL DEVICES
- OTHER:

NOTE: TOP OF BMP'S SHOULD NOT BE HIGHER THAN ROADWAY ELEVATION AS NOT TO FLOOD ROADWAY UNLESS PRIOR APPROVAL FROM ENGINEER IS OBTAINED.

3. STORM WATER MANAGEMENT:

A. Storm water drainage will be provided by ditches and storm water systems which carry drainage within the R.O.W. to the lows within the roadway and project site which drains to natural facilities.

4. STORM WATER MANAGEMENT ACTIVITIES: (Sequence of Construction)

1. THE MAJORITY OF THE PROJECT AREA, WITHIN THE TXDOT ROW, IS SURROUNDED BY EXISTING VEGETATION WHICH WILL REMAIN UNDISTURBED AND PROVIDE A NATURAL BUFFER TO PROTECT WATER QUALITY, CONTROL STORM WATER VELOCITY, MINIMIZE POTENTIAL EROSION AND SEDIMENTATION, ETC. TO THE EXTENT PRACTICABLE, PRESERVE EXISTING VEGETATION, MAINTAIN A VEGETATIVE BUFFER ALONG RECEIVING WATERS, AND PHASE CONSTRUCTION ACTIVITIES IN MINIMIZE EXPOSURE OF DISTURBED SOILS.

2. INSTALL SW3P CONTROL DEVICES (BMPs) TO PROTECT RECEIVING WATERS, DOWN SLOPE PERIMETERS, AND ACTIVE ROADWAYS PRIOR TO POTENTIAL POLLUTANT GENERATING CONSTRUCTION ACTIVITIES IN THEIR VICINITY, AS NEEDED AND/OR AS DIRECTED OR AUTHORIZED BY THE ENGINEER. DO NOT INSTALL BMPs MORE THAN TWO WEEKS PRIOR TO THE ACTIVITIES IN THEIR CONTROL AREA.

3. AVOID STORING PORTABLE SANITARY UNITS, CONCRETE WASHOUTS OR CHEMICALS WITHIN 50 FEET UP GRADIENT OF A RECEIVING WATER OR DRAINAGE CONVEYANCE WITHOUT ADEQUATE POLLUTION CONTROLS.

4. CONTRACTOR IS RESPONSIBLE FOR STABILIZING/RE-VEGETATING SOILS DISTURBED BY THE PROJECT AS SOON AS PRACTICABLE OR AS DIRECTED BY THE ENGINEER. FOLLOW TXDOT STANDARDS AND SPECIFICATION AND THE DALLAS DISTRICT VEGETATION ESTABLISHMENT SHEET.

5. NON-STORM WATER DISCHARGES:

Filter non-storm water discharges, or hold in retention basins, before being allowed to mix with storm water. These discharges consist of, but not limited to, non-polluted ground water, spring water, foundation or footing drain water, water used for dust control or pavement washing and vehicle washwater containing no detergents.

C. OTHER REQUIREMENTS & PRACTICES

1. MAINTENANCE:

Maintain all erosion and sediment controls in good working order. Perform any necessary cleaning/repairs/replacements at the earliest possible date prior to next rain event, but no later than 7 calendar days. Ensure the surrounding ground has dried sufficiently to prevent damage from equipment. "Too Wet" is the only reason for not adhering to timeframes described. When construction activities permanently or temporarily cease and are not expected to resume for 14 or more days on a disturbed portion of the site, stabilization measures must be initiated immediately.

2. INSPECTION:

A TxDOT Inspector will perform a regularly scheduled SW3P Inspection every 7 calendar days. An Inspection and Maintenance Report, signed by the TxDOT Inspector and the Contractor, will be filed for each inspection. Revise/clean/repair/replace each BMP control device in accordance with the current Field Inspection and Maintenance Report (Form 2118) and Item 1 (Maintenance) above.

3. WASTE MATERIALS:

On a daily basis, or as may be directed, collect all waste materials, trash and debris from the construction site and deposit into a metal dumpster having a secure cover and which meets all state and local city solid waste management requirements. Empty the dumpster as required by regulation, or as may be directed, at a local approved landfill site. Do not bury construction waste on the construction project site.

4. HAZARDOUS WASTE & SPILL REPORTING:

As a minimum, any products in the following categories are considered to be hazardous: Paints, Acids, Solvents, Fuels, Asphalt Products, Chemical Additives for Soil Stabilization, and Concrete Curing Compounds or Additives. When storing hazardous material on the project site, or at a Project Specific Location, take all practicable precaution to prevent and/or contain any spillage of these materials. In the event of a spill, contact the spill coordinator immediately.

5. SANITARY WASTE:

Use a licensed sanitary waste management contractor to collect all sanitary waste from portable units as may be required by local regulation, or as directed.

6. CONSTRUCTION VEHICLE TRACKING:

On a regular basis, or as may be directed, dampen haul roads for dust control and construct construction entrances/exits. Provide for a motorized broom or vacuum type sweeper to be available on a daily basis, or as may be directed, to remove sediment from paved roadways on project, abutting and traversing the project site.


7. MANAGEMENT PRACTICES:

- A. Construct disposal areas, stockpiles, haul roads and PSL's in a manner that will minimize and control the amount of sediment that may enter receiving waters. Do not locate disposal areas in any wetland, waterbody or streambed.
- B. Locate construction staging areas, vehicle maintenance and PSL's areas in a manner to minimize the runoff of pollutants.
- C. When working in or near a wetland, install and maintain operating soil erosion and sediment controls at all times during construction and isolate the work from the wetland.
- D. Clear all waterways as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.
- E. Procedures and/or practices should be taken to control dust.
- F. Sediment to be removed from roadways daily or when work begins after weather events if construction activities have ceased due to weather event.

FILE NAME

DATE

DESIGNER



Falon Renfro, 9/29/2021
 Signature of Registrant & Date



DALLAS DISTRICT ENVIRONMENTAL

STORM WATER POLLUTION PREVENTION PLAN (SW3P)

TEMPLATE REVISION DATE: 02/07/18

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
JR	6	SEE TITLE SHEET		SH 34, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
FR	TEXAS	DALLAS	KAUFMAN	81
CHECK	CONTROL	SECTION	JOB	
CHECK	JR	0173	05	041, ETC

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act".
 No warranty of any kind is made by TxDOT for any purpose whatsoever.
 TxDOT assumes no responsibility for the conversion of this standard to other
 formats or for incorrect results or damage resulting from its use.

Notes To Designer:
 1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
 2. If additional space is needed for a numbered section, fence and adjust sections up or down
 as needed for proportioning and readability but do not relocate from its relative position.
 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to
 support actions needed.
 Filled Out: XX.XX.XXXX
 Prepared By: Name/Section

I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.
 List adjacent MS 4 Operator(s) that receive discharges from this project. They need to be notified prior to construction activities.
 (Note: Leave blank only if no adjacent MS 4 Operator(s) are affected.)

- 1.
 - 2.
- No Action Required Required Action

Action Number:

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
4. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the ordinary High Water Mark except on approved temporary stream crossings or drill pads.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# 3(a)

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 1.
- 2.
- 3.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices for applicable 401 General Conditions:
 (Note: If CORP Permit not required, do not check boxes.)

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action Number:

- 1.
- 2.
- 3.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751 & 752 in order to comply with requirements for invasive species, beneficial landscaping and tree/brush removal commitments.

- No Action Required Required Action

Action Number:

- 1.
- 2.
- 3.
- 4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT.

- No Action Required Required Action

Action Number:

- 1.
- 2.
- 3.
- 4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediated area, and contact the Engineer immediately.

Special Note: The Migratory Bird Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. The contractor would remove all old migratory bird nests from any structure or trees where work would be done from October 1 to February 15. In addition, the contractor would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, efforts to avoid adverse impacts on protected birds, active nests, eggs and/or young would be observed.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corp of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):
 Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Safety Data Sheets (SDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the SDS. In the event of a spill, take actions to mitigate the spill as indicated in the SDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canisters, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action Number:

- 1.
- 2.
- 3.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action Number:

- 1.

GENERAL NOTE:


Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.



ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		SH 34, ETC
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	DALLAS	Kaufman	
CONTROL	SECTION	JOB	
0173	05	041	82

90A#2021
 p:\ins\txdot\projectwiseonline.com\txdot\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1 - General\STANDARDS\ec116.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING


				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS		0173	05	041, ETC.	SH 34, ETC.
DIST	COUNTY			SHEET NO.	
DAL	KAUFMAN			83	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2021
 FILE: p:\t\tdot\projectwiseonline.com\TxDOT\Documents\18 - DAL\Design Projects\017305041\4 - Design\Plan Set\1. General\STANDARDS\ec916.dgn




PLAN VIEW




SECTION A-A
EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B
EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW



SECTION C-C


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
 - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
 - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
 - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
 - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
 - CL-DI EROSION CONTROL LOG AT DROP INLET
 - CL-CI EROSION CONTROL LOG AT CURB INLET
 - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0173 05	041, ETC. SH 34, ETC.	
DIST	COUNTY	SHEET NO.	
DAL	KAUFMAN	84	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/22/2021
 FILE: \\txdot\projectwise\online.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\PIAN Set\1. General\STANDARDS\ec916.dgn



**EROSION CONTROL LOGS ON SLOPES
STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART





**EROSION CONTROL LOGS ON SLOPES
STAKE AND LASHING ANCHORING**

CL-SSL




STAKE AND TRENCHING ANCHORING DETAIL

CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL



LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

TRENCH DEPTH TABLE




STAKE NOTCH DETAIL

SHEET 2 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC(9) - 16			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0173 05	041, ETC. SH 34, ETC.	
DIST	COUNTY	SHEET NO.	
DAL	KAUFMAN	85	


DATE: 9/22/2021
 FILE: p:\txdot\projectwise\line.com\TXDOT5\Documents\18 - DAL\Design Projects\017305041\4 - Design\PIAN Set\1. General\STANDARDS\ec916.dgn

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0173	05	041, ETC. SH 34, ETC.
DIST	COUNTY	SHEET NO.	
DAL	KAUFMAN	86	

SURFACE PREPARATION ITEM 160* TOPSOIL SY / ITEM 161* COMPOST MANUF. TOPSOIL (BOS) (4") SY

SURFACE PREPARATION

Prepare planting area surface BEFORE placing Topsoil, Compost, Fertilizer, Seed and/or Sod. Once project area has been completed to final lines, grade and compaction, remove objectionable materials from planting area surface and cultivate existing surface to a depth of 4 inches, unless otherwise specified or directed.

Refer to Items 160 and 161 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.

TOPSOIL NOTES:

- When Topsoil is specified under Item 160, use suitable material salvaged from the project ROW in accordance with Item 160 specifications, and/or secure additional good material from approved sources.
- Topsoil shall include only the top 6 inches of its native surface, and be easily cultivated, fertile, erosion-resistant and free of objectionable materials.
- Topsoil obtained from sites outside of the ROW must come from approved sources and have a pH between 5.5 and 8.5 su.
- Place Topsoil on pre-cultivated surface, spread to a uniform loose cover at thickness specified, and shape per plans. Water and roll the finished surface with a light roller or other suitable equipment per Item 160.3; do not over-compact.

COMPOST NOTES:

- When Compost Manufactured Topsoil (4") is specified under Item 161, use compost meeting all requirements of Item 161.2 and Table 1. Provide quality control (QC) documentation and obtain Engineer approval prior to compost delivery.
- Contractor shall provide tickets/invoices that document material type, quantity and placement for all compost delivered.
- Additional topsoil may be required to be imported to achieve the compost/topsoil mix ratio. Topsoil must meet Item 160 specifications.

APPLICATION OF COMPOST MANUFACTURED TOPSOIL (4")

AFTER Surface Preparation, uniformly spread a 1-inch layer of compost on-grade with 3 inches topsoil over pre-cultivated planting area. (25% compost and 75% topsoil = 1" compost and 3" topsoil.) Then mix compost and topsoil together by cultivating the compost into the topsoil (by till or disk) to a 4-inch (4") depth. Roll the finished surface with a light corrugated drum; do not over-compact.

FERTILIZER ITEM 166* FERTILIZER AC

SOIL ANALYSIS FOR FERTILIZER APPLICATION RATE

Unless otherwise stated in the plans, Contractor shall perform at least one soil analysis on each project before fertilization, and submit results to Engineer with recommended fertilizer rates based on soil analysis. Engineer may direct sample location(s). Soil analysis may be waived if both compost and sod are used on entire project.

FERTILIZER NOTES:

- Refer to Item 166 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Apply fertilizer BEFORE seeding, or AFTER placing sod.
- Use fertilizer containing nitrogen (N), phosphoric acid (P) and potash (K) nutrients, unless otherwise specified. At least 50% of the Nitrogen component shall be a slow-release sulfur-coated urea as described in Item 166.3. Do not apply more than 60 lbs Nitrogen per acre without Engineer concurrence.
- Deliver fertilizer in bags, clearly labeled to show contents, unless otherwise specified or approved prior to delivery. When non-bagged, loose fertilizer is approved, provide documentation for each load of material delivered, to validate authenticity of the material.
- Apply fertilizer uniformly, as a dry, granular material, essentially dust-free, and do not mix with water for application as a slurry.
- When both temporary and permanent seeding are specified for the same area, apply half of the required fertilizer before the temporary seeding operation and the other half before the permanent seeding operation.

SEEDING FOR EROSION CONTROL ITEM 164* DRILL SEEDING AC

RECOMMENDED PLANTING SEASON	PERMANENT RURAL SEED MIX ITEM 164 - DRILL SEEDING (PERM) (RURAL) (CLAY)	PERMANENT URBAN SEED MIX ITEM 164 - DRILL SEEDING (PERM) (URBAN) (CLAY)	TEMPORARY DRILL SEED MIX ITEM 164 - DRILL SEEDING (TEMP) (WARM OR COOL)																														
WARM SEASON Mar. 15th, April, May, June, July, August, Sept. 15th	<table border="0"> <tr><td>Green Sprangletop (Van Horn)</td><td>- 1.0 lbs/AC</td></tr> <tr><td>Sideoats Grama (Haskell)</td><td>- 1.0 lbs/AC</td></tr> <tr><td>Texas Grama (Atascosa)</td><td>- 1.0 lbs/AC</td></tr> <tr><td>Hairy Grama (Chaparral)</td><td>- 0.4 lbs/AC</td></tr> <tr><td>Shortspike Windmillgrass (Welder)</td><td>- 0.2 lbs/AC</td></tr> <tr><td>Little Bluestem (OK Select)</td><td>- 0.8 lbs/AC</td></tr> <tr><td>Purple Prairie Clover (Cuero)</td><td>- 0.6 lbs/AC</td></tr> <tr><td>Engelmann Daisy (Eldorado)</td><td>- 0.75 lbs/AC</td></tr> <tr><td>Illinois Bundlesflower</td><td>- 1.3 lbs/AC</td></tr> <tr><td>Awnless Bushsunflower (Plateau)</td><td>- 0.2 lbs/AC</td></tr> </table>	Green Sprangletop (Van Horn)	- 1.0 lbs/AC	Sideoats Grama (Haskell)	- 1.0 lbs/AC	Texas Grama (Atascosa)	- 1.0 lbs/AC	Hairy Grama (Chaparral)	- 0.4 lbs/AC	Shortspike Windmillgrass (Welder)	- 0.2 lbs/AC	Little Bluestem (OK Select)	- 0.8 lbs/AC	Purple Prairie Clover (Cuero)	- 0.6 lbs/AC	Engelmann Daisy (Eldorado)	- 0.75 lbs/AC	Illinois Bundlesflower	- 1.3 lbs/AC	Awnless Bushsunflower (Plateau)	- 0.2 lbs/AC	<table border="0"> <tr><td>Green Sprangletop (Leptochloa dubia)</td><td>- 0.3 lbs/AC</td></tr> <tr><td>Sideoats Grama (El Reno) (Bouteloua curtipendula)</td><td>- 3.6 lbs/AC</td></tr> <tr><td>Buffalograss (Texoka) (Buchloe dactyloides)</td><td>- 1.6 lbs/AC</td></tr> <tr><td>Bermudagrass (Cynodon dactylon)</td><td>- 2.4 lbs/AC</td></tr> </table>	Green Sprangletop (Leptochloa dubia)	- 0.3 lbs/AC	Sideoats Grama (El Reno) (Bouteloua curtipendula)	- 3.6 lbs/AC	Buffalograss (Texoka) (Buchloe dactyloides)	- 1.6 lbs/AC	Bermudagrass (Cynodon dactylon)	- 2.4 lbs/AC	<table border="0"> <tr><td>Foxtail Millet (Setaria italica)</td><td>- 34 lbs/AC</td></tr> </table>	Foxtail Millet (Setaria italica)	- 34 lbs/AC
Green Sprangletop (Van Horn)	- 1.0 lbs/AC																																
Sideoats Grama (Haskell)	- 1.0 lbs/AC																																
Texas Grama (Atascosa)	- 1.0 lbs/AC																																
Hairy Grama (Chaparral)	- 0.4 lbs/AC																																
Shortspike Windmillgrass (Welder)	- 0.2 lbs/AC																																
Little Bluestem (OK Select)	- 0.8 lbs/AC																																
Purple Prairie Clover (Cuero)	- 0.6 lbs/AC																																
Engelmann Daisy (Eldorado)	- 0.75 lbs/AC																																
Illinois Bundlesflower	- 1.3 lbs/AC																																
Awnless Bushsunflower (Plateau)	- 0.2 lbs/AC																																
Green Sprangletop (Leptochloa dubia)	- 0.3 lbs/AC																																
Sideoats Grama (El Reno) (Bouteloua curtipendula)	- 3.6 lbs/AC																																
Buffalograss (Texoka) (Buchloe dactyloides)	- 1.6 lbs/AC																																
Bermudagrass (Cynodon dactylon)	- 2.4 lbs/AC																																
Foxtail Millet (Setaria italica)	- 34 lbs/AC																																
COOL SEASON Sept 16th, Oct, Nov, Dec, Jan, Feb, Mar 14th			<table border="0"> <tr><td>Tall Fescue (Festuca arundinaceae)</td><td>- 4.5 lbs/AC</td></tr> <tr><td>Western Wheatgrass (Agropyron smithii)</td><td>- 5.6 lbs/AC</td></tr> <tr><td>Red Winter Wheat (Triticum aestivum)</td><td>- 34 lbs/AC</td></tr> <tr><td>Cereal Rye</td><td>- 34 lbs/AC</td></tr> </table>	Tall Fescue (Festuca arundinaceae)	- 4.5 lbs/AC	Western Wheatgrass (Agropyron smithii)	- 5.6 lbs/AC	Red Winter Wheat (Triticum aestivum)	- 34 lbs/AC	Cereal Rye	- 34 lbs/AC																						
Tall Fescue (Festuca arundinaceae)	- 4.5 lbs/AC																																
Western Wheatgrass (Agropyron smithii)	- 5.6 lbs/AC																																
Red Winter Wheat (Triticum aestivum)	- 34 lbs/AC																																
Cereal Rye	- 34 lbs/AC																																

SEEDING NOTES:

- When seeding is specified under Item 164, refer to TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown. Materials and construction shall meet specifications.
- Conduct seeding upon completion of each applicable construction stage (dependent upon planting season requirements), without compensation for additional move-ins.
- Place seed AFTER preparing planting area surface. Refer to Surface Preparation detail in this sheet, as well as Topsoil Item 160 and Compost Manufactured Topsoil Item 161 when specified. Apply fertilizer per Item 166 BEFORE seeding, per specifications and this sheet, to help drill the fertilizer into the soil.
- When temporary grasses are well-established and more than 2 inches tall, mow planting area before seeding permanent grasses; mowing for this purpose will be subsidiary. When vegetation is not already well-established, cultivate planting area to a depth as described in Item 164.3, before temporary seeding and before permanent seeding.
- Seed material must be appropriate to the location, soil type and season. Use the seed mix species and pure live seed rates designated in Tables 1-4 of the TxDOT 2014 Standard Specifications* for Item 164, unless otherwise specified.
- All seed shall meet labeling, delivery, analysis, and testing requirements described in Item 164.2.1. Deliver seed in labeled, unopened bags or containers to Engineer prior to planting.
- Uniformly plant seed over the designated planting area, along the contour of slopes, and drill seed to a depth as described in Item 164.3.4.
- Hydroseeding may be allowed, when specified or Engineer concurs.
- Implement and continue Vegetative Watering per the schedule, rate and volume specified under Item 168.

TXDOT REFERENCE MATERIALS:

- "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES" 2014
- "A GUIDANCE TO ROADSIDE VEGETATION ESTABLISHMENT" 2004
- ONLINE TRAINING COURSE: MNT415 REVEGETATION DURING CONSTRUCTION
- DALLAS DISTRICT "VEGETATION ESTABLISHMENT GUIDELINES"

SODDING FOR EROSION CONTROL ITEM 162* BLOCK SOD (BERMUDA) SY

BLOCK OR ROLL SOD	COMMON NAME	BOTANICAL NAME
	Common Bermuda Grass	Cynodon dactylon

SODDING NOTES:

- Refer to Item 162 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Place sod between the average date of the last freeze in the Spring and 6 weeks before the average date of the first freeze in the Fall, per the Texas Almanac for the project area.
- Place sod only AFTER soil surface preparation is complete as detailed in this sheet. Dry soil may require pre-watering.
- Place all sod (blocks or rolls) within 24 hours of delivery to the site, and keep moist from the time it is dug up until it is planted. Sod with dried roots will not be accepted.
- Place sod with joints alternating on each row to prevent all joints from lining up, and place blocks firmly against adjacent blocks. Roll, tamp and trim sod per Item 162.3.
- Place fertilizer promptly AFTER sodding operation is complete in each area.
- Water sod immediately following placement, and continue Vegetative Watering per Item 168.

VEGETATIVE WATERING FOR ESTABLISHING SEED AND SOD ITEM 168* VEGETATIVE WATERING MG

SEASON (Usual Months)	RATE	TIME SCHEDULE	TOTAL WATER ESTIMATE
SPRING & FALL (March, April, May, October)	7,000 gallons/acre per working day	Vegetative watering for seed shall begin on the day after rainfall described below and continue for 60 consecutive working days; vegetative watering for sod shall begin on the day the sod is placed and continue for a minimum of 15 consecutive working days.	420,000 gallons/acre (60 working days)
SUMMER (June, July, August, September)	12,000 gallons/acre per working day		720,000 gallons/acre (60 working days)
WINTER (November through February)	1,000 gallons/acre per working day	Vegetative watering for seed and/or sod shall begin on the day after placement for 15 consecutive working days	15,000 gallons/acre (15 working days)

Notes: Rate and frequency may be adjusted, with the approval of the Engineer, to meet site conditions (especially with sod). For informational purposes only: 1,000 gallons equals 1 MG

VEGETATIVE WATERING NOTES:

- Refer to Item 168 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Use clean water free of industrial waste and other substances harmful to vegetation growth, per Item 168.2.
- Use Vegetative Watering to keep the seed bed moist during germination; not to provide initial watering. After drill seeding, postpone watering operations until site receives at least 1/2-inch of natural rainfall in a single day. Delay watering operations for warm season grasses until soil temperature exceeds 70 degrees F.
- For sod, water immediately.
- All water distribution equipment shall be furnished and operated to provide water at a uniform and controllable rate. Use a metering device on all watering equipment.
- Evenly distribute water over entire area designated for seeding and/or sodding, using even spray patterns that do not disturb seed bed and/or dislodge seed from seed bed.
- Do not water between the hours of 12:00 p.m. and 6:00 p.m. when daytime temperatures exceed 95 degrees F.
- After initial establishment period, continue intermittent watering of newly established seed or sod at a rate of approximately 1-inch water/week, during summer months until end of contract.
- If 1/4-inch or more of rainfall occurs on site on any given working day, no vegetative watering will be needed on that working day. (Note: 1/4-inch rain equals 7,000 gallons of water per acre.)
- Should the Contractor fail to apply the specified amount of water within the time allowed, any seed or sod in poor condition shall be replaced, fertilized, and watered at Contractor's expense.

ROADSIDE MOWING ITEM 730* PROJECT MAINTENANCE AC

MOWING NOTES:

- During project construction, once seed is established, use mowing to promote permanent grasses by mowing any remaining temporary grasses.
- Also mow established turf and ROW grasses in designated areas of project limits as specified or directed by Engineer.
- Remove litter and debris prior to mowing.
- Do not mow on wet ground when soil rutting can occur.
- Hand-trim around obstructions and stormwater control devices as needed.
- Maintain paved surfaces free of tracked soils and clipped vegetation.

SEQUENCE OF WORK:

- CULTIVATE SURFACE SOIL.
- PREPARE / PLACE TOPSOIL, OR
- PREPARE / PLACE COMPOST MANUFACTURED TOPSOIL.
- APPLY FERTILIZER AND THEN PLACE SEEDING, OR
- PLACE SOD AND THEN APPLY FERTILIZER.
- CONDUCT VEGETATIVE WATERING.
- CONDUCT ROADSIDE MOWING, AS DIRECTED.



VEGETATION ESTABLISHMENT SHEET
(DALLAS DISTRICT)

TEMPLATE REVISION DATE: 02/21/19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CPB	6	(See Title Sheet)		SH 34, ETC
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
XXX	TEXAS	DAL	KAUFMAN	87
CHECK	CONTROL	SECTION	JOB	
XXX	0173	05	041, ETC.	