



# INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
<b>GENERAL</b>	
1	TITLE SHEET
2	INDEX OF SHEETS
3-7	LOCATION MAP
8-16	TYPICAL SECTIONS
17, 17A-17C	GENERAL NOTES
18-18A	ESTIMATE & QUANTITY
19-21	QUANTITY SUMMARY
22	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

<b><u>TRAFFIC CONTROL PLAN</u></b>	
23	TCP SELECTION

<b>TRAFFIC CONTROL PLAN STANDARDS</b>	
24-35 #	BC (1)-21 THRU BC (12)-21
36 #	TCP (1-2)-18
37 #	TCP (1-4)-18
38 #	TCP (1-5)-18
39 #	TCP (3-1)-13
40 #	TCP (3-2)-13
41 #	TCP (3-3)-14
42 #	WZ (BTS-1)-13
43 #	WZ (RCD)-13

<b><u>TRAFFIC</u></b>	
44	RAILROAD SCOPE OF WORK
45-46	RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

<b>TRAFFIC STANDARDS</b>	
47-50 #	PM (1)-20 THRU PM (4)-20
51-52 #	RCD (1)-16 & RCD (2)-16
53 #	TS2 (PL-1)-18

<b><u>ENVIRONMENTAL ISSUES</u></b>	
54	STORM WATER POLLUTION PREVENTION PLAN



*Jose Madrid Jr., P.E.*  
12-01-2021

\* THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

## DISTRICTWIDE GENERAL INDEX OF SHEETS

SHEET 1 OF 1


Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		2





DWG:   
 CHK:   
 DWF:   
 CJK:

NOTE:  
 1. SEE TYPICAL SECTIONS FOR ADDITIONAL INFORMATION.



DATE: 12/1/2021 2:37:20 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\LOCATION\_MAP\_03.dgn

SECTION	ROADWAY	CONTROL SECTION	COUNTY	FROM	TO	DFO_BEGIN	DFO_END	RM_BEGIN	RM_END	LENGTH (MI)	PROPOSED WORK
10	US 90	0924-00-106	JEFF DAVIS	CULBERSON CL	9.2 MI S OF CULBERSON CL	19.89	29.216	130+1.94	104+1.279	9.324	100 MIL ON SEAL COAT
11	US 90	0924-00-106	JEFF DAVIS	9.2 MI S OF CULBERSON CL	7.7 MI N OF PRESIDIO CL	29.216	38.144	140+1.279	150+0.236	8.928	100 MIL ON SEAL COAT
12	US 90	0924-00-106	JEFF DAVIS	7.7 MI N OF PRESIDIO CL	PRESIDIO CL	38.144	45.774	150+0.236	158+0.020	7.611	100 MIL ON SEAL COAT
13	US 90	0924-00-106	PRESIDIO	PRESIDIO CL	14.1 MI E OF PRESIDIO CL	45.774	59.877	158+0.020	172+0.166	14.103	RETRACE
14	US 90	0924-00-106	PRESIDIO	14.1 MI E OF PRESIDIO CL	US0090 & HIGHLAND AVE	59.877	73.402	172+0.166	184+1.724	3.525	RETRACE
15	SH 118	0924-00-106	CULBERSON	0.01 MI S OF RM 2424	1.45 MI S OF IH 10	0	1.517	382+0.000	382+1.517	1.517	100 MIL ON SEAL COAT
16	SH 118	0924-00-106	JEFF DAVIS	1.45 MI S OF IH 10	0.62 MI S OF SH 166	1.517	22.824	382+1.517	404+1.233	21.307	100 MIL ON SEAL COAT
17	SH 118	0924-00-106	JEFF DAVIS	0.62 MI S OF SH 166	1.73 MI W OF SS 78	22.824	35.791	404+1.233	418+0.104	12.967	100 MIL ON SEAL COAT
18	SH 118	0924-00-106	JEFF DAVIS	1.73 MI W OF SS 78	SH 17	35.791	51.01	418+0.104	432+1.346	15.219	100 MIL ON SEAL COAT
19	SH 17	0924-00-106	JEFF DAVIS	REEVES COUNTY LINE	7.77 MI E OF SH 118	44.095	63.901	404+0.017	424+0.130	20.052	100 MIL ON SEAL COAT
20	SH 17	0924-00-106	JEFF DAVIS	7.77 MI E OF SH 118	0.48 MI S OF SH 118	63.901	73.288	424+0.131	432+1.382	9.387	100 MIL ON SEAL COAT
21	SH 17	0924-00-106	JEFF DAVIS	0.48 MI S OF SH 118	8.24 MI N OF FM 1112	73.288	85.698	432+1.382	444+1.772	12.41	100 MIL ON SEAL COAT
22	SH 17	0924-00-106	PRESIDIO	8.24 MI N OF FM 1112	0.87 MI N OF FM 1112	85.698	93.416	444+1.772	452+1.660	7.673	100 MIL ON SEAL COAT
23	SS 78	0924-00-106	JEFF DAVIS	0.508 MI N OF SS77	0.63 MI S OF 77	0.132	1.481	160+0.012	160+1.361	1.547	100 MIL ON SEAL COAT
24	SS 77	0924-00-106	JEFF DAVIS	SS78	0.44 MI N OF SS78	0.001	0.438	406+0.001	406+0.438	0.478	100 MIL ON SEAL COAT

Jose Madrid Jr., P.E.  
 12-01-2021


**DISTRICTWIDE**  
**GENERAL**  
**LOCATION MAP**

SHEET 3 OF 5  
© 2021

Texas Department of Transportation	
CONT	SECT
0924	00
JOB	
106, ETC	
HIGHWAY	
VA	
COUNTY	
EL PASO, ETC	
SHEET NO.	
5	

DW:   
 C/S:   
 DW:   
 C/S:

NOTE:  
 1. SEE TYPICAL SECTIONS FOR ADDITIONAL INFORMATION.



*Jose Madrid Jr., P.E.*  
 12-01-2021



**DISTRICTWIDE  
 GENERAL  
 LOCATION MAP**

DATE: 12/1/2021 2:37:23 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\LOCATION\_MAP\_04.dgn

ROADWAY	CONTROL SECTION	COUNTY	FROM	TO	DFO_BEGIN	DFO_END	RM_BEGIN	RM_END	LENGTH (MI)	PROPOSED WORK	
25	RM 2424	0924-00-157	CULBERSON	RM 2424 JUNCTION & IH0010	14 MI N OF RM 2424 JUNCTION & IH0010	0	13.7	368+0.00	380+1.726	13.7	100 MIL ON SEAL COAT
26	RM 1832	0924-00-157	JEFF DAVIS	SH0017 & RM1832 INTERSECTION	11.2 MI W OF RM1832	0	11.2	164+0.000	174+0.846	11.2	100 MIL ON SEAL COAT
27	RM 1837	0924-00-157	JEFF DAVIS	SH0118 & RM1837 INTERSECTION	3.376 MI E OF SH0118 & RM1837	0	3.376	172-0.002	174+1.381	3.376	100 MIL ON SEAL COAT
28	RM 2627	0924-00-157	BREWSTER	US0385 & RM2627 INTERSECTION	27.96 MI S OF RM2627	0	27.96	478-0.051	506+0.032	27.96	100 MIL ON SEAL COAT

CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		6

DATE: 12/1/2021 2:37:26 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\LOCATION\_MAP\_05.dgn



SEE DETAIL 1

SEE NOTE 1

DETAIL 1

NOTES:

1. LOCATIONS A-I ARE FOR REPLACEMENTS OF MISSING RPMS WITHIN LIMITS.
2. VERIFY ACTIVE CONSTRUCTION PROJECT LIMITS PRIOR TO COMMENCEMENT OF WORK.
3. VERIFY LOCATIONS FOR FULL REPLACEMENT, OR AS DIRECTED BY THE ENGINEER.

0924-00-106 SUMMARY OF PAVEMENT MARKING ITEMS (TABLE 1 OF 1)				
LOCATION	PROPOSED WORK	672	672	672
		6007	6009	6010
		REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	REFL PAV MRKR TY II-C-R
		EA	EA	EA
A - IH 10	RPM INSTALLATION	20,114	0	20,114
B - SL 0375	RPM INSTALLATION	4,028	0	4,028
C - US 54	RPM INSTALLATION	2,692	0	2,692
D - US 62	RPM INSTALLATION	1,191	14,602	1,191
E - US 67	RPM INSTALLATION	357	12,738	357
F - US 0090	RPM INSTALLATION	74	9,858	74
G - US 90	RPM INSTALLATION	61	5,499	61
H - SS 601	RPM INSTALLATION	676	0	676
I - FM 1437	RPM INSTALLATION	0	2,174	0
<b>PROJECT TOTALS</b>		<b>29,191</b>	<b>44,871</b>	<b>29,191</b>

#	ROADWAY	CONTROL SECTION	COUNTY	FROM	TO	DFO_BEGIN	DFO_END	RM_BEGIN	RM_END	LENGTH (MI)	PROPOSED WORK
29	US54/IH-10 Ramps	0924-00-106	EL PASO	COPIA EXIT ON IH-10	RAYNOLDS EXIT ON IH-10	0.599	23.086	23+0.15	20+0.554	2.88	REMOVE AND REPLACE
A	IH 10	0924-00-106	EL PASO	TEXAS & NEW MEXICO STATE LINE	REEVES COUNTY LINE	0	185.526	1-0.998	185+0.97	185.526	RPM INSTALLATION
B	SL 375	0924-00-106	EL PASO	DONIPHAN DR & TALBOT	SL 375 AND EL PASO ST.	11.561	48.994	11+00	60+785	37.433	RPM INSTALLATION
C	US 54	0924-00-106	EL PASO	FROM CESAR CHAVEZ BORDER HIGHWAY US 54 EXIT RAMP	TEXAS AND NEW MEXICO STATE LINE	0	19.866	21-1.177	40+00	19.866	RPM INSTALLATION
D	US 62	0924-00-106	EL PASO	SPUR 601 AND US 54 CONNECTION RAMP	SL 375 AND SPUR 601	0	7.275	112-0.257	27+0.288	7.275	RPM INSTALLATION
E	US 67	0924-00-106	EL PASO	SL 375 AND US 62	TEXAS AND NEW MEXICO STATE LINE	14.228	128.756	34+0.000	148+0.66	114.528	RPM INSTALLATION
F	US90	0924-00-106	HUDSPETH	FM 1437 AND US 62	TEXAS AND NEW MEXICO STATE LINE	0	16.373	314+00	330+1.367	16.373	RPM INSTALLATION
G	US90	0924-00-106	CULBERSON	BIO010 AND US 90	JEFF DAVIS COUNTY LINE	107.72	160.948	222-1.847	272+1.477	53.22	RPM INSTALLATION
H	SS 601	0924-00-106	BREWSTER	US 90 AND US 67	UNITED STATES AND MEXICO BORDER	0	73.402	112-0.57	184+1.725	73.402	RPM INSTALLATION
I	FM 1437	0924-00-106	BREWSTER	US 90 AND US 67	REEVES COUNTY LINE	107.72	160.948	222-1.847	272+1.477	53.228	RPM INSTALLATION




Jose Madrid Jr., P.E.  
12-01-2021


**DISTRICTWIDE**  
**GENERAL**  
**LOCATION MAP**

SHEET 5 OF 5  
© 2021


Texas Department of Transportation	
CONT 0924	SECT 00
JOB 106, ETC	HIGHWAY VA
DIST ELP	COUNTY EL PASO, ETC
SHEET NO. 7	




SH-20 PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6006	REFL PAV MRK TY I (W) 4" (DOT) (100MIL)	LF	1,440
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	1,855
666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)	LF	2,000
666	6093	REFL PAV MRK TY I (W) (RR XING) (100MIL)	EA	1
666	6095	REFL PAV MRK TY I (W) (SYMBOL) (090MIL)	EA	1
666	6105	REFL PAV MRK TY I (W) (BIKE ARW) (100MIL)	EA	9
666	6111	REFL PAV MRK TY I (W) (BIKE SYML) (100MIL)	EA	9
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	10,900
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	4,330
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	1,910
666	6302	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)	LF	10,900
666	6305	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	LF	4,330
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	1,910
672	6010	REFL PAV MRKER TY II-C-R	EA	250
672	6009	REFL PAV MRKR TY II-A-A	EA	32
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	16,505
677	6002	ELIM EXT PAV MRK & MRKS (6")	LF	4,330
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	1,855
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	1,450
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	2,000
677	6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA	1
677	6017	ELIM EXT PAV MRK & MRKS (SYMBOL)	EA	1
677	6023	ELIM EXT PAV MRK & MARKS (BIKE ARROW)	EA	9
677	6025	ELIM EXT PAV MRK & MARKS (BIKE SYMBOL)	EA	9
678	6001	PAV SURF PREP FOR MRK (4")	LF	16,505
678	6002	PAV SURF PREP FOR MRK (6")	LF	4,330
678	6004	PAV SURF PREP FOR MRK (8")	LF	1,855
678	6008	PAV SURF PREP FOR MRK (24")	LF	2,000
678	6020	PAV SURF PREP FOR MRK (RR XING)	EA	1
678	6021	PAV SURF PREP FOR MRK (SYMBOL)	EA	1
678	6026	PAV SURF PREP FOR MRK (BIKE ARROW)	EA	9
678	6028	PAV SURF PREP FOR MRK (BIKE SYMBOL)	EA	9



FM-259 PAVEMENT MARKINGS (CSJ: 0924-00-106) (RETRACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6036	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	LF	570
666	6042	REFL PAV MRK TY I (W) 12" (SLD) (100MIL)	LF	360
666	6048	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	LF	164
666	6054	REFL PAV MRK TY I (W) (ARROW) (100MIL)	EA	8
666	6078	REFL PAV MRK TY I (W) (WORD) (100MIL)	EA	3
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	10,900
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	790
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	7,895
672	6009	REFL PAV MRKR TY II-A-A	EA	198



SL-375 PAVEMENT MARKINGS (CSJ: 0924-00-106) (RETRACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6030	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	LF	310
666	6036	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	LF	2,648
666	6042	REFL PAV MRK TY I (W) 12" (SLD) (100MIL)	LF	653
666	6048	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	LF	768
666	6054	REFL PAV MRK TY I (W) (ARROW) (100MIL)	EA	29
666	6078	REFL PAV MRK TY I (W) (WORD) (100MIL)	EA	15
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	12,440
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	785
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	7,895
672	6007	REFL PAV MRKR TY I-C	EA	219
672	6009	REFL PAV MRKR TY II-A-A	EA	30



FM-1905 PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	430
666	6093	REFL PAV MRK TY I (W) (RR XING) (100MIL)	EA	1
666	6095	REFL PAV MRK TY I (W) (SYMBOL) (090MIL)	EA	1
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	10,324
666	6205	REFL PAV MRK TY II (Y) 4" (BRK)	LF	675
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	2,550
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	655
666	6314	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	LF	2,550
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	10,324
672	6009	REFL PAV MRKR TY II-A-A	EA	98
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	10,983
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	430
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	470
677	6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA	1
677	6017	ELIM EXT PAV MRK & MRKS (SYMBOL)	EA	1
678	6001	PAV SURF PREP FOR MRK (4")	LF	10,983
678	6004	PAV SURF PREP FOR MRK (8")	LF	430
678	6020	PAV SURF PREP FOR MRK (RR XING)	EA	1
678	6021	PAV SURF PREP FOR MRK (SYMBOL)	EA	1

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
(A)	ELIM EXT PAV MRK & MRKS (4")
(B)	ELIM EXT PAV MRK & MRKS (6")
(C)	PAV SURF PREP FOR MRK (4")
(D)	PAV SURF PREP FOR MRK (6")
(E)	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
(F)	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
(G)	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
(H)	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
(I)	REFL PAV MRK TY II (W) 4" (SLD)
(J)	REFL PAV MRK TY II (W) 6" (BRK)
(K)	REFL PAV MRK TY II (Y) 4" (BRK)
(L)	REFL PAV MRK TY II (Y) 4" (SLD)
(M)	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
(N)	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
(O)	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
(P)	REFL PAV MRKR TY I-C
(Q)	REFL PAV MRKR TY II-A-A
(R)	REFL PAV MRKR TY II-C-R
(S)	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
(T)	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
(U)	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
(V)	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)




*José Madrid Jr., P.E.*  
 12-02-2021

**DISTRICTWIDE  
 GENERAL  
 TYPICAL SECTIONS**

SH 20, FM 259,  
 SL 375 & FM 1905  
 SHEET 1 OF 9


Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		8

CSE  
 DWF  
 CSE  
 DWF




**5 US 85 (PAISANO DR) TYPICAL SECTION**

FROM: RM 322+1.280 TO: RM 322+1.510  
 FROM: RM 324+0.270 TO: RM 324+0.970  
 FROM: RM 324+1.100 TO: RM 324+1.620




**5 US 85 (PAISANO DR) TYPICAL SECTION**

FROM: RM 322+1.510 TO: RM 322+1.740




**5 US 85 (PAISANO DR) TYPICAL SECTION**

FROM: RM 322+1.740 TO: RM 324+0.270




**5 US 85 (PAISANO DR) TYPICAL SECTION**

FROM: RM 324+0.970 TO: RM 324+1.100




**5 US 85 (PAISANO DR) TYPICAL SECTION**

FROM: RM 324+1.620 TO: RM 324+1.850



**5 US 85 (PAISANO DR) TYPICAL SECTION**


FROM: RM 324+1.850 TO: RM 326+0.650



**5 US 85 (PAISANO DR) TYPICAL SECTION**


FROM: RM 326+0.650 TO: RM 326+1.150

US-85 PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	2,723
666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)	LF	432
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	30,090
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	51,060
666	6302	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)	LF	83,840
666	6305	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	LF	20,960
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	15,878
666	6314	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	LF	10,480
672	6010	REFL PAV MRKER TY II-C-R	EA	1,048
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	94,320
677	6002	ELIM EXT PAV MRK & MRKS (6")	LF	20,960
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	2,723
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	1,421
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	432
678	6001	PAV SURF PREP FOR MRK (4")	LF	39,230
678	6002	PAV SURF PREP FOR MRK (6")	LF	41,920
678	6004	PAV SURF PREP FOR MRK (8")	LF	2,723
678	6008	PAV SURF PREP FOR MRK (24")	LF	432




**6 IH 10 FRONTAGE RD TYPICAL SECTION**

WB FRONTAGE RD  
 FROM: KANSAS ST TO: SANTA FE ST



**6 IH 10 FRONTAGE RD TYPICAL SECTION**

WB FRONTAGE RD  
 FROM: COPIA ST TO: VIRGINIA ST



**6 IH 10 FRONTAGE RD TYPICAL SECTION**

EB FRONTAGE RD  
 FROM: PIEDRAS ST TO: COPIA ST

**6 IH 10 FRONTAGE RD TYPICAL SECTION**

IH-10-FR PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	5,070
666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)	LF	2,085
666	6053	REFL PAV MRK TY I (W) (ARROW) (090MIL)	EA	30
666	6056	REFL PAV MRK TY I (W) (DBL ARROW) (090MIL)	EA	10
666	6059	REFL PAV MRK TY I (W) (TPL ARRW) (090MIL)	EA	2
666	6077	REFL PAV MRK TY I (W) (WORD) (090MIL)	EA	15
666	6093	REFL PAV MRK TY I (W) (RR XING) (100MIL)	EA	3
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	3,240
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	4,835
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	1,990
666	6302	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)	LF	3,240
666	6305	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	LF	4,835
666	6314	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	LF	1,990
672	6010	REFL PAV MRKER TY II-C-R	EA	1,845
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	2,265
677	6002	ELIM EXT PAV MRK & MRKS (6")	LF	4,835
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	5,070
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	5,635
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	2,085
677	6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA	25
677	6009	ELIM EXT PAV MRK & MRKS (DBL ARROW)	EA	8
677	6010	ELIM EXT PAV MRK & MRKS (TPL ARROW)	EA	16
677	6012	ELIM EXT PAV MRK & MRKS (WORD)	EA	12
678	6001	PAV SURF PREP FOR MRK (4")	LF	2,265
678	6002	PAV SURF PREP FOR MRK (6")	LF	4,835
678	6004	PAV SURF PREP FOR MRK (8")	LF	5,635
678	6008	PAV SURF PREP FOR MRK (24")	LF	2,085
678	6009	PAV SURF PREP FOR MRK (ARROW)	EA	10
678	6010	PAV SURF PREP FOR MRK (DBL ARROW)	EA	8
678	6011	PAV SURF PREP FOR MRK (TPL ARROW)	EA	16
678	6016	PAV SURF PREP FOR MRK (WORD)	EA	12

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
A	ELIM EXT PAV MRK & MRKS (4")
B	ELIM EXT PAV MRK & MRKS (6")
C	PAV SURF PREP FOR MRK (4")
D	PAV SURF PREP FOR MRK (6")
E	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
F	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
G	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
H	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
I	REFL PAV MRK TY II (W) 4" (SLD)
J	REFL PAV MRK TY II (W) 6" (BRK)
K	REFL PAV MRK TY II (Y) 4" (BRK)
L	REFL PAV MRK TY II (Y) 4" (SLD)
M	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
N	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
O	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
P	REFL PAV MRKR TY I-C
Q	REFL PAV MRKR TY II-A-A
R	REFL PAV MRKR TY II-C-R
S	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
T	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
U	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
V	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)

DATE: 12/2/2021 2:32:17 PM  
 FILE: m:\0924-00-106\4-des\ign\plan set\1. general\TYPICAL\_SECTIONS\_01.dgn



Jose Madrid Jr., P.E.  
 12-02-2021

**DISTRICTWIDE**  
**GENERAL**


**TYPICAL SECTIONS**

US 85 & IH 10 FRONTAGE RD


SHEET 2 OF 9

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		9

DATE: 12/2/2021 2:32:20 PM  
 FILE: m:\0924-00-106\4-des\ign\plan set\1 - general\TYPICAL\_SECTIONS\_01.dgn




**7 FM 76 (N LOOP) TYPICAL SECTION**  
 FROM: RM 352+0.235 TO: RM 354+1.450




**7 FM 76 (N LOOP) TYPICAL SECTION**  
 FROM: RM 354+1.450 TO: RM 366+1.611


FM-76 - PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	1,390
666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)	LF	1,969
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	122,120
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	9,730
666	6205	REFL PAV MRK TY II (Y) 4" (BRK)	LF	9,730
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	58,090
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	122,120
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	7,500
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	58,090
672	6009	REFL PAV MRKR TY II-A-A	EA	900
672	6010	REFL PAV MRKER TY II-C-R	EA	525
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	189,940
677	6002	ELIM EXT PAV MRK & MRKS (6")	LF	9,830
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	1,390
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	860
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	1,969
678	6001	PAV SURF PREP FOR MRK (4")	LF	189,940
678	6002	PAV SURF PREP FOR MRK (6")	LF	9,730
678	6004	PAV SURF PREP FOR MRK (8")	LF	1,390
678	6008	PAV SURF PREP FOR MRK (24")	LF	1,969




**8 FM 258 TYPICAL SECTION**  
 FROM: RM 348+0.129 TO: RM 348+0.250




**8 FM 258 TYPICAL SECTION**  
 FROM: RM 348+0.250 TO: RM 348+0.380



**8 FM 258 TYPICAL SECTION**  
 FROM: RM 348+0.380 TO: RM 348+1.150



**8 FM 258 TYPICAL SECTION**  
 FROM: RM 348+1.150 TO: RM 350+1.710  
 FROM: RM 356+0.610 TO: RM 356+0.850  
 FROM: RM 358+0.160 TO: RM 358+0.670



**8 FM 258 TYPICAL SECTION**  
 FROM: RM 350+1.710 TO: RM 356+0.610  
 FROM: RM 356+0.850 TO: RM 358+0.160  
 FROM: RM 358+0.670 TO: RM 364+0.555

FM-258 PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	3,550
666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)	LF	1,950
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	173,460
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	17,050
666	6205	REFL PAV MRK TY II (Y) 4" (BRK)	LF	17,050
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	73,415
666	6302	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)	LF	173,460
666	6305	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	LF	11,630
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	17,035
666	6314	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	LF	73,415
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	67,825
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	135,650
672	6009	REFL PAV MRKR TY II-A-A	EA	1,188
672	6010	REFL PAV MRKR TY II-C-R	EA	1,165
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	263,910
677	6002	ELIM EXT PAV MRK & MRKS (6")	LF	17,035
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	3,550
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	2,273
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	1,950
678	6001	PAV SURF PREP FOR MRK (4")	LF	261,765
678	6002	PAV SURF PREP FOR MRK (6")	LF	17,031
678	6004	PAV SURF PREP FOR MRK (8")	LF	3,550
678	6008	PAV SURF PREP FOR MRK (24")	LF	1,950

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
A	ELIM EXT PAV MRK & MRKS (4")
B	ELIM EXT PAV MRK & MRKS (6")
C	PAV SURF PREP FOR MRK (4")
D	PAV SURF PREP FOR MRK (6")
E	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
F	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
G	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
H	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
I	REFL PAV MRK TY II (W) 4" (SLD)
J	REFL PAV MRK TY II (W) 6" (BRK)
K	REFL PAV MRK TY II (Y) 4" (BRK)
L	REFL PAV MRK TY II (Y) 4" (SLD)
M	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
N	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
O	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
P	REFL PAV MRKR TY I-C
Q	REFL PAV MRKR TY II-A-A
R	REFL PAV MRKR TY II-C-R
S	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
T	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
U	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
V	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*José Madrid Jr., P.E.*  
 12-02-2021


**DISTRICTWIDE  
 GENERAL  
 TYPICAL SECTIONS**

FM 76 & SH 258


SHEET 3 OF 9

Texas Department of Transportation		© 2021	
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		10


DATE: 12/2/2021 2:32:23 PM  
 FILE: m:\0924-00-106\4-des\typical\_sections\_01.dgn




9 SH 20 (ALAMEDA AVE) TYPICAL SECTION  
 FROM: RM 342+1.731 TO: RM 348+1.510



9 SH 20 (ALAMEDA AVE) TYPICAL SECTION  
 FROM: RM 348+1.510 TO: RM 356+0.230




9 SH 20 (ALAMEDA AVE) TYPICAL SECTION  
 FROM: RM 356+0.230 TO: RM 356+0.970




9 SH 20 (ALAMEDA AVE) TYPICAL SECTION  
 FROM: RM 356+0.970 TO: RM 370+0.010

SH-20 PAVEMENT MARKINGS (CSJ: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	LF	4,250
666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)	LF	1,249
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	493,550
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	56,565
666	6205	REFL PAV MRK TY II (Y) 4" (BRK)	LF	53,620
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	126,345
666	6305	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	LF	56,565
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	53,620
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	493,550
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	126,345
672	6007	REFL PAV MRKR TY I-C	EA	905
672	6009	REFL PAV MRKR TY II-A-A	EA	4,395
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	673,515
677	6002	ELIM EXT PAV MRK & MRKS (6")	LF	56,565
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	4,250
677	6005	ELIM EXT PAV MRK & MRKS (12")	LF	1,787
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	1,249
678	6001	PAV SURF PREP FOR MRK (4")	LF	673,515
678	6002	PAV SURF PREP FOR MRK (6")	LF	56,565
678	6004	PAV SURF PREP FOR MRK (8")	LF	4,250
678	6008	PAV SURF PREP FOR MRK (24")	LF	1,249




10 US 90 TYPICAL SECTION  
 FROM: RM 130+1.940 TO: RM 140+1.279


US-90 PAVEMENT MARKINGS (CS: 0020-03-21) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	98,500
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	9,505
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	11,241



11 US 90 TYPICAL SECTION  
 FROM: RM 140+1.279 TO: RM 148+1.920  
 FROM: RM 150+0.220 TO: RM 150+0.236



11 US 90 TYPICAL SECTION  
 FROM: RM 148+1.920 TO: RM 150+0.040  
 FROM: RM 150+0.180 TO: RM 150+0.220



11 US 90 TYPICAL SECTION  
 FROM: RM 150+0.040 TO: RM 150+0.160

US-90 PAVEMENT MARKINGS (CS: 0020-04-017) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6054	REFL PAV MRK TY I (W) (ARROW) (100MIL)	EA	3
666	6078	REFL PAV MRK TY I (W) (WORD) (100MIL)	EA	2
666	6147	REFL PAV MRK TY I (Y) 24" (SLD) (100MIL)	LF	231
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	11,445
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	4,102
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	94,280

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
A	ELIM EXT PAV MRK & MRKS (4")
B	ELIM EXT PAV MRK & MRKS (6")
C	PAV SURF PREP FOR MRK (4")
D	PAV SURF PREP FOR MRK (6")
E	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
F	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
G	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
H	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
I	REFL PAV MRK TY II (W) 4" (SLD)
J	REFL PAV MRK TY II (W) 6" (BRK)
K	REFL PAV MRK TY II (Y) 4" (BRK)
L	REFL PAV MRK TY II (Y) 4" (SLD)
M	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
N	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
O	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
P	REFL PAV MRKR TY I-C
Q	REFL PAV MRKR TY II-A-A
R	REFL PAV MRKR TY II-C-R
S	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
T	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
U	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
V	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*Jose Madrid Jr., P.E.*  
 12-02-2021


**DISTRICTWIDE  
 GENERAL  
 TYPICAL SECTIONS**

SH 20 & US 90


SHEET 4 OF 9

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		11


DATE: 12/2/2021 2:32:25 PM  
 FILE: m:\0924-00-106\4-des\ign\plan set\1. general\TYPICAL\_SECTIONS\_01.dgn



**12 US 90 TYPICAL SECTION**  
 FROM: RM 150+0.236 TO: RM 156+1.120  
 FROM: RM 156+1.510 TO: RM 158+0.020




**12 US 90 TYPICAL SECTION**  
 FROM: RM 156+1.120 TO: RM 156+1.230  
 FROM: RM 156+1.420 TO: RM 156+1.510




**12 US 90 TYPICAL SECTION**  
 FROM: RM 156+1.230 TO: RM 156+1.410


US-90 PAVEMENT MARKINGS (CS: 0020-05-016) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6036	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	LF	860
666	6042	REFL PAV MRK TY I (W) 12" (SLD) (100MIL)	LF	380
666	6054	REFL PAV MRK TY I (W) (ARROW) (100MIL)	EA	3
666	6078	REFL PAV MRK TY I (W) (WORD) (100MIL)	EA	2
666	6147	REFL PAV MRK TY I (Y) 24" (SLD) (100MIL)	LF	380
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	87,750
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	9,430
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	6,200



**14 US 90 TYPICAL SECTION**  
 FROM: RM 172+0.160 TO: RM 184+0.160  
 FROM: RM 184+0.720 TO: RM 184+1.070




**14 US 90 TYPICAL SECTION**  
 FROM: RM 184+0.160 TO: RM 184+0.720




**14 US 90 TYPICAL SECTION**  
 FROM: RM 184+1.070 TO: RM 184+1.730

US-90 PAVEMENT MARKINGS (CS: 0924-00-106) (RETRACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6054	REFL PAV MRK TY I (W) (ARROW) (100MIL)	EA	8
666	6078	REFL PAV MRK TY I (W) (WORD) (100MIL)	EA	6
666	6302	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)	LF	74,500
666	6305	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	LF	16,302
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	17,450
666	6314	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	LF	17,319



**13 US 90 TYPICAL SECTION**  
 FROM: RM 158+0.020 TO: RM 172+0.160

US-90 PAVEMENT MARKINGS (CS: 0924-00-106) (RETRACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6302	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)	LF	148,940
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	18,620
666	6314	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	LF	74,480
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	148,940



**15 SH 118 TYPICAL SECTION**  
 FROM: RM 382+0.000 TO: RM 382+1.517

SH-118 PAVEMENT MARKINGS (CS: 0512-01-013) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	780
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	12,035
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	16,020

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
(A)	ELIM EXT PAV MRK & MRKS (4")
(B)	ELIM EXT PAV MRK & MRKS (6")
(C)	PAV SURF PREP FOR MRK (4")
(D)	PAV SURF PREP FOR MRK (6")
(E)	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
(F)	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
(G)	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
(H)	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
(I)	REFL PAV MRK TY II (W) 4" (SLD)
(J)	REFL PAV MRK TY II (W) 6" (BRK)
(K)	REFL PAV MRK TY II (Y) 4" (BRK)
(L)	REFL PAV MRK TY II (Y) 4" (SLD)
(M)	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
(N)	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
(O)	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
(P)	REFL PAV MRKR TY I-C
(Q)	REFL PAV MRKR TY II-A-A
(R)	REFL PAV MRKR TY II-C-R
(S)	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
(T)	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
(U)	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
(V)	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*Jose Madrid Jr., P.E.*  
 12-02-2021


**DISTRICTWIDE  
 GENERAL  
 TYPICAL SECTIONS**

US 90 & SH 118

SHEET 5 OF 9


Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		12

DATE: 12/2/2021 2:32:28 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\TYPICAL\_SECTIONS\_01.dgn




**16 SH 118 TYPICAL SECTION**  
 FROM: RM 382+1.517 TO: RM 404+1.233

SH-118 PAVEMENT MARKINGS (CS: 0512-02-015) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	225,000
666	6344	REF PROF PAV MRK TY I(Y)4" (BRK) (100MIL)	LF	24,600
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	73,220




**17 SH 118 TYPICAL SECTION**  
 FROM: RM 404+1.233 TO: RM 418+0.104

SH-118 PAVEMENT MARKINGS (CS: 0415-02-028) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	127,500
666	6344	REF PROF PAV MRK TY I(Y)4" (BRK) (100MIL)	LF	2,400
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	53,750




**18 SH 118 TYPICAL SECTION**  
 FROM: RM 418+0.104 TO: RM 430+0.590  
 FROM: RM 430+0.760 TO: RM 432+1.346




**18 SH 118 TYPICAL SECTION**  
 FROM: RM 430+0.590 TO: RM 430+0.760

SH-118 PAVEMENT MARKINGS (CS: 0415-01-026) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6306	RE PM W/RET REQ TY I (W)6" (BRK) (100MIL)	LF	80
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	166,000
666	6344	REF PROF PAV MRK TY I(Y)4" (BRK) (100MIL)	LF	8,300
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	121,260




**19 SH 17 TYPICAL SECTION**  
 FROM: RM 404+0.017 TO: RM 406+0.590  
 FROM: RM 406+1.750 TO: RM 412+0.460  
 FROM: RM 412+1.510 TO: RM 416+0.420  
 FROM: RM 416+1.580 TO: RM 424+0.130




**19 SH 17 TYPICAL SECTION**  
 FROM: RM 406+0.590 TO: RM 406+1.750  
 FROM: RM 412+0.460 TO: RM 412+1.510  
 FROM: RM 416+0.420 TO: RM 416+1.580


SH-17 PAVEMENT MARKINGS (CS: 0104-02-030) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6306	RE PM W/RET REQ TY I (W)6" (BRK) (100MIL)	LF	8,868
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	212,470
666	6344	REF PROF PAV MRK TY I(Y)4" (BRK) (100MIL)	LF	12,500
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	138,489



**20 SH 17 TYPICAL SECTION**  
 FROM: RM 424+0.131 TO: RM 430+1.970  
 FROM: RM 432+0.007 TO: RM 432+0.730



**20 SH 17 TYPICAL SECTION**  
 FROM: RM 430+1.970 TO: RM 432+0.005



**20 SH 17 TYPICAL SECTION**  
 FROM: RM 432+0.730 TO: RM 432+1.382

SH-17 PAVEMENT MARKINGS (CS: 0104-03-039) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6048	REFL PAV MRK TY I (W)24" (SLD) (100MIL)	LF	124
666	6102	REF PAV MRK TY I(W)36" (YLD TRI) (100MIL)	EA	6
666	6147	REFL PAV MRK TY I (Y)24" (SLD) (100MIL)	LF	437
666	6306	RE PM W/RET REQ TY I (W)6" (BRK) (100MIL)	LF	335
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	99,150
666	6344	REF PROF PAV MRK TY I(Y)4" (BRK) (100MIL)	LF	7,060
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	58,737

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND

- ↑ DIRECTION OF TRAVEL
- (A) ELIM EXT PAV MRK & MRKS (4")
- (B) ELIM EXT PAV MRK & MRKS (6")
- (C) PAV SURF PREP FOR MRK (4")
- (D) PAV SURF PREP FOR MRK (6")
- (E) RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
- (F) RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
- (G) RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
- (H) RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
- (I) REFL PAV MRK TY II (W) 4" (SLD)
- (J) REFL PAV MRK TY II (W) 6" (BRK)
- (K) REFL PAV MRK TY II (Y) 4" (BRK)
- (L) REFL PAV MRK TY II (Y) 4" (SLD)
- (M) REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
- (N) REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
- (O) REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
- (P) REFL PAV MRKR TY I-C
- (Q) REFL PAV MRKR TY II-A-A
- (R) REFL PAV MRKR TY II-C-R
- (S) RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
- (T) RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
- (U) RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
- (V) RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*Jose Madrid Jr., P.E.*  
 12-02-2021


**DISTRICTWIDE  
 GENERAL  
 TYPICAL SECTIONS**

SH 118 & SH 17


SHEET 6 OF 9

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		13


CHK: \_\_\_\_\_  
 DWF: \_\_\_\_\_  
 CDS: \_\_\_\_\_  
 DWS: \_\_\_\_\_



**21 SH 17 TYPICAL SECTION**  
FROM: RM 432+0.730 TO: RM 432+1.680




**21 SH 17 TYPICAL SECTION**  
FROM: RM 432+1.680 TO: RM 434+1.690  
FROM: RM 434+1.820 TO: RM 444+1.772




**21 SH 17 TYPICAL SECTION**  
FROM: RM 434+1.690 TO: RM 434+1.750  
FROM: RM 434+1.760 TO: RM 434+1.820

SH-17 PAVEMENT MARKINGS (CS: 0104-04-014) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6036	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	LF	73
666	6042	REFL PAV MRK TY I (W) 12" (SLD) (100MIL)	LF	334
666	6048	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	LF	12
666	6102	REF PAV MRK TY I (W) 36" (YLD TRI) (100MIL)	EA	15
666	6147	REFL PAV MRK TY I (Y) 24" (SLD) (100MIL)	LF	334
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	155,000
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	15,780
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	14,068




**22 SH 17 TYPICAL SECTION**  
FROM: RM 444+1.772 TO: RM 452+1.660

SH-17 PAVEMENT MARKINGS (CS: 0104-05-026) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6342	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	LF	112,500
666	6344	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	LF	10,150
666	6345	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	LF	9,589




**23 SS 78 TYPICAL SECTION**  
FROM: RM 160-0.012 TO: RM 160+0.470




**23 SS 78 TYPICAL SECTION**  
FROM: RM 160+0.470 TO: RM 160+1.361

SS-77 PAVEMENT MARKINGS (CS: 0415-06-004) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6303	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	LF	9,530
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	1,005
666	6315	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	LF	13,860



**24 SS 77 TYPICAL SECTION**  
FROM: RM 406+0.001 TO: RM 406+0.180



**24 SS 77 TYPICAL SECTION**  
FROM: RM 406+0.180 TO: RM 406+0.438

SS-78 PAVEMENT MARKINGS (CS: 0415-05-016) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6303	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	LF	9,275
666	6311	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	LF	8,620
666	6315	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	LF	9,589

**NOTES:**

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
(A)	ELIM EXT PAV MRK & MRKS (4")
(B)	ELIM EXT PAV MRK & MRKS (6")
(C)	PAV SURF PREP FOR MRK (4")
(D)	PAV SURF PREP FOR MRK (6")
(E)	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
(F)	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
(G)	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
(H)	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
(I)	REFL PAV MRK TY II (W) 4" (SLD)
(J)	REFL PAV MRK TY II (W) 6" (BRK)
(K)	REFL PAV MRK TY II (Y) 4" (BRK)
(L)	REFL PAV MRK TY II (Y) 4" (SLD)
(M)	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
(N)	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
(O)	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
(P)	REFL PAV MRKR TY I-C
(Q)	REFL PAV MRKR TY II-A-A
(R)	REFL PAV MRKR TY II-C-R
(S)	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
(T)	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
(U)	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
(V)	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*Jose Madrid Jr., P.E.*  
12-02-2021

**DISTRICTWIDE  
GENERAL**

**TYPICAL SECTIONS**


SH 17, SS 78 & SS 77

SHEET 7 OF 9

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		14


DATE: 12/2/2021 2:32:31 PM  
 FILE: m:\0924-00-106\4-des\toplan set\1. general\TYPICAL\_SECTIONS\_01.dgn

CSJ: 0924-00-157 (SECT. 25 - 28)




**25 RM 2424 TYPICAL SECTION**  
FROM: RM 368+0.000 TO: RM 380+1.726

RM-2424 PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6047	REFL PAV MRK TY I (W)24" (SLD) (090MIL)	LF	46
666	6092	REFL PAV MRK TY I (W) (RR XING) (090MIL)	EA	2
666	6093	REFL PAV MRK TY I (W) (RR XING) (100MIL)	EA	2
666	6205	REFL PAV MRK TY II (Y) 4" (BRK)	LF	10,600
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	87,849
666	6311	RE PM W/RET REQ TY I (Y)4" (BRK) (090MIL)	LF	10,600
666	6314	RE PM W/RET REQ TY I (Y)4" (SLD) (090MIL)	LF	87,849
672	6009	REFL PAV MRKR TY II-A-A	EA	1,628
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	98,441
677	6007	ELIM EXT PAV MRK & MRKS (24")	LF	46
677	6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA	2
678	6001	PAV SURF PREP FOR MRK (4")	LF	98,441
678	6008	PAV SURF PREP FOR MRK (24")	LF	46
678	6020	PAV SURF PREP FOR MRK (RR XING)	EA	2




**27 RM 1837 TYPICAL SECTION**  
FROM: RM 368+0.000 TO: RM 380+1.726

RM-1837 - PAVEMENT MARKINGS (CSJ: 0924-00-106) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6312	RE PM W/RET REQ TY I (Y)4" (BRK) (100MIL)	LF	10,080
666	6315	RE PM W/RET REQ TY I (Y)4" (SLD) (100MIL)	LF	18,047



**26 RM 1832 TYPICAL SECTION**  
FROM: RM 368+0.000 TO: RM 380+1.726

RM-1832 - PAVEMENT MARKINGS (CSJ: 0924-00-106) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6312	RE PM W/RET REQ TY I (Y)4" (BRK) (100MIL)	LF	4,250
666	6315	RE PM W/RET REQ TY I (Y)4" (SLD) (100MIL)	LF	92,619



**28 RM 2627 TYPICAL SECTION**  
FROM: RM 368+0.000 TO: RM 380+1.726

RM 2627 - PAVEMENT MARKINGS (CSJ: 0924-00-106) (100 MIL ON SEAL COAT)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6312	RE PM W/RET REQ TY I (Y)4" (BRK) (100MIL)	LF	14,330
666	6315	RE PM W/RET REQ TY I (Y)4" (SLD) (100MIL)	LF	213,629

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND

↑	DIRECTION OF TRAVEL
A	ELIM EXT PAV MRK & MRKS (4")
B	ELIM EXT PAV MRK & MRKS (6")
C	PAV SURF PREP FOR MRK (4")
D	PAV SURF PREP FOR MRK (6")
E	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
F	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
G	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
H	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
I	REFL PAV MRK TY II (W) 4" (SLD)
J	REFL PAV MRK TY II (W) 6" (BRK)
K	REFL PAV MRK TY II (Y) 4" (BRK)
L	REFL PAV MRK TY II (Y) 4" (SLD)
M	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
N	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
O	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
P	REFL PAV MRKR TY I-C
Q	REFL PAV MRKR TY II-A-A
R	REFL PAV MRKR TY II-C-R
S	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
T	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
U	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
V	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*Jose Madrid Jr., P.E.*  
12-02-2021

**DISTRICTWIDE**

**GENERAL**


**TYPICAL SECTIONS**

RM 2424, RM 1832,  
RM 1837 & RM 2627

SHEET 8 OF 9

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		15

CHK: \_\_\_\_\_  
 DWF: \_\_\_\_\_  
 CDS: \_\_\_\_\_  
 DNE: \_\_\_\_\_




**29 RAMP TYPICAL SECTION**  
RAMPS B, C & J

RAMP B PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W)8" (SLD) (090MIL)	LF	175
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	750
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	750
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	750
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	750
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	1,500
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	175
678	6001	PAV SURF PREP FOR MRK (4")	LF	1,500
678	6004	PAV SURF PREP FOR MRK (8")	LF	175

RAMP C PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W)8" (SLD) (090MIL)	LF	250
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	1,050
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	1,050
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	1,050
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	1,050
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	2,100
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	175
678	6001	PAV SURF PREP FOR MRK (4")	LF	2,100
678	6004	PAV SURF PREP FOR MRK (8")	LF	175

RAMP J PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W)8" (SLD) (090MIL)	LF	825
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	2,950
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	2,950
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	2,950
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	2,950
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	5,900
677	6003	ELIM EXT PAV MRK & MRKS (8")	LF	825
678	6001	PAV SURF PREP FOR MRK (4")	LF	5,900
678	6004	PAV SURF PREP FOR MRK (8")	LF	825



**29 RAMP TYPICAL SECTION**  
RAMPS A, D, H & K

RAMP A PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	1,900
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	475
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	1,900
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	1,900
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	1,900
666	6346	REF PROF PAV MRK TY I(Y)6" (BRK) (100MIL)	LF	475
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	3,800
678	6001	PAV SURF PREP FOR MRK (4")	LF	3,800
678	6002	PAV SURF PREP FOR MRK (6")	LF	475

RAMP D PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	2,250
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	570
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	2,250
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	2,250
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	2,250
666	6346	REF PROF PAV MRK TY I(Y)6" (BRK) (100MIL)	LF	570
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	4,500
678	6001	PAV SURF PREP FOR MRK (4")	LF	4,500
678	6002	PAV SURF PREP FOR MRK (6")	LF	570


RAMP K PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6035	REFL PAV MRK TY I (W)8" (SLD) (090MIL)	LF	900
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	3,500
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	875
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	3,500
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	3,500
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	3,500
666	6346	REF PROF PAV MRK TY I(Y)6" (BRK) (100MIL)	LF	875
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	7,000
678	6001	PAV SURF PREP FOR MRK (4")	LF	7,000
678	6002	PAV SURF PREP FOR MRK (6")	LF	875
678	6004	PAV SURF PREP FOR MRK (8")	LF	900

RAMP H PAVEMENT MARKINGS (CS: 0924-00-106) (REMOVE AND REPLACE)				
ITEM	CODE	DESCRIPTION	UNITS	QTY
666	6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	3,000
666	6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	750
666	6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	3,000
666	6342	REF PROF PAV MRK TY I(W)4" (SLD) (100MIL)	LF	3,000
666	6345	REF PROF PAV MRK TY I(Y)4" (SLD) (100MIL)	LF	3,000
666	6346	REF PROF PAV MRK TY I(Y)6" (BRK) (100MIL)	LF	750
677	6001	ELIM EXT PAV MRK & MRKS (4")	LF	6,000
678	6001	PAV SURF PREP FOR MRK (4")	LF	6,000
678	6002	PAV SURF PREP FOR MRK (6")	LF	750

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY AND SHALL NOT BE USED FOR QUANTITY CALCULATIONS, OR AS A CONSTRUCTION DETAIL. REFER TO SPECIFIC DETAIL SHEET AND STATE STANDARDS.
2. REFERENCE MARKERS ARE FOR LOCATION PURPOSES ONLY. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS.
3. REFER TO RCD(1)-16 AND RCD(2)-16 FOR RAILROAD PAVEMENT MARKINGS.
4. REFER TO TCP SELECTION SHEET FOR APPLICABLE TRAFFIC CONTROL PLAN.

LEGEND	
↑	DIRECTION OF TRAVEL
A	ELIM EXT PAV MRK & MRKS (4")
B	ELIM EXT PAV MRK & MRKS (6")
C	PAV SURF PREP FOR MRK (4")
D	PAV SURF PREP FOR MRK (6")
E	RE PM W/RET REQ TY I (W) 4" (SLD) (090MIL)
F	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)
G	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)
H	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)
I	REFL PAV MRK TY II (W) 4" (SLD)
J	REFL PAV MRK TY II (W) 6" (BRK)
K	REFL PAV MRK TY II (Y) 4" (BRK)
L	REFL PAV MRK TY II (Y) 4" (SLD)
M	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)
N	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)
O	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)
P	REFL PAV MRKR TY I-C
Q	REFL PAV MRKR TY II-A-A
R	REFL PAV MRKR TY II-C-R
S	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
T	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
U	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
V	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)



*José Madrid Jr., P.E.*  
12-02-2021

**DISTRICTWIDE  
GENERAL  
TYPICAL SECTIONS**

RAMPS

SHEET 9 OF 9

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		16

DATE: 12/2/2021 2:32:36 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\TYPICAL\_SECTIONS\_01.dgn

CONTROL: 0924-00-106, ETC

COUNTY: EL PASO, ETC

HIGHWAY: VARIOUS

### General Requirements

Maintain the entire project area in a neat and orderly manner throughout the duration of the work. Remove all construction litter and undesirable vegetation within the right of way inside the project limits. This work will be subsidiary to the various bid items.

General Project Description – This project consists of Roadway Pavement Markings on various Highways in El Paso, Texas.

Contractor questions on this project are to be addressed to the following individual(s):

**Omar Moreno, P.E.**  
East El Paso Area Engineer  
[Omar.Moreno1@txdot.gov](mailto:Omar.Moreno1@txdot.gov)

**Aldo Madrid, P.E.**  
Director of Construction  
[Aldo.Madrid@txdot.gov](mailto:Aldo.Madrid@txdot.gov)

Contractor questions on this project are to be addressed to the following individual(s)  
Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

### Item 7 – Legal Relations and Responsibilities

Comply with all requirements of the Environmental Permits Issues and Commitments (EPIC) Sheet.

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

Occupational Safety & Health Administration (OSHA) regulations prohibit operations that bring people or equipment within 10 ft. of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all necessary adjustments to ensure the safety of workers near the energized line.

Obtain any required traffic control permits from the City of El Paso when traffic control devices encroach City ROW or traffic control setup impacts City streets. The contractor shall be responsible for submitting a traffic control plan to the City of El Paso – Streets and Maintenance Department at [tcp@elpasotexas.gov](mailto:tcp@elpasotexas.gov) for review no later than two weeks prior to beginning of construction.

No significant traffic generator events identified.

CONTROL: 0924-00-106, ETC

COUNTY: EL PASO, ETC

HIGHWAY: VARIOUS

### Law Enforcement Personnel

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site.

### Item 8 – Prosecution and Progress

Working days will be calculated in accordance with Section 8.3.1., "Standard Workweek."

Create and maintain a Bar Chart schedule.

Submit baseline schedule and obtain approval prior to beginning construction. The monthly progress payment will be held if the monthly update is not submitted.

### Item 9 – Measurement and Payment

Monthly progress payments will be made for items of work completed by the 27<sup>th</sup> day of each month. Any work completed after the 27<sup>th</sup> will be included for payment in the subsequent monthly progress payment.

Submit Material on Hand (MOH) payment requests at least **three (3)** working days before the end of the month for payment consideration on that month's estimate.

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" (Course #133119) which can be found online at the following site: [www.nhi.fhwa.dot.gov](http://www.nhi.fhwa.dot.gov)

Certificates of completion should be available to all who finish the course. These should be kept by the officers to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case by case basis.

**Item 502 – Barricades, Signs, and Traffic Handling**

Prior to beginning construction, the Engineer will approve the routing of traffic and sequence of work.

Additional signs and barricades, placed as directed, will be considered subsidiary to this Item.

In accordance with Section 7.2.6.1, designate, in writing, a Contractor Responsible Person (CRP) and a CRP alternate to take full responsibility for the set-up, maintenance, and necessary corrective measures of the traffic control plan. The CRP or CRP alternate must be present at site and implement the initial set up of every traffic control phase/stage, at each location, and/or each call out, for the entire duration of the project.

At the written request of the Engineer, immediately remove the CRP or CRP alternate from the project if, in the opinion of the Engineer, is not competent, not present at initial TCP set-ups, or does not perform in a proper, skillful, or safe manner. These individuals shall not be reinstated without written consent of the Engineer.

CRP and CRP alternate must be trained using Department approved training. Provide a copy of the certificate of completion to the Engineer for project records. Refer to **Table 1** for Department approved Training.

**Table 1  
Contractor Responsible Person and Alternate**

Provider	Course Number	Course Title	Duration	Notes
American Traffic Safety Services Association	TCS	Traffic Control Supervisor	2 days	
National Highway Institute	133112	Design and Operation of Work Zone Traffic Control	1 day	Both courses are required to meet minimum required training.
	133113	Work Zone Traffic Control for Maintenance Operations	1 day	
Texas Engineering Extension Services	133112A	Design and Operation of Work Zone Traffic Control	3 days	
University of Texas Arlington Division for Enterprise Development	WKZ421	Traffic Control Supervisor	16 hours	Contact UTA for training needs.

All contractor workers involved with the traffic control implementation and maintenance must participate and complete a Department approved training course. Provide a copy of the certificate of completion to the Engineer for project records. Refer to **Table 2** for Department approved training.

**Table 2  
Other Work Zone Personnel**

Provider	Course Number	Course Title	Duration	Notes
American Traffic Safety Services Association	TCT	Traffic Control Technician	1 day	
Texas Engineering Extension Services	HWS002	Work Zone Traffic Control	16 hours	Identical to HWS-410. Counts for 3 year CRP requirement.
National Highway Institute	133116	Maintenance of Traffic for Technicians	5 hours	Web based
National Highway Institute	134109-I	Maintenance Training Series: Basics of Work Zone Traffic Control	1 hour	Free, Web based
University of Texas at Arlington, Division for Enterprise Development	WKZ100	Work Zone Safety: Temporary Traffic Control	4 hours	Note name change. Free, Web based
TxDOT/AGC Joint Development	N/A	Safe Workers Awareness	16 minutes	Videos available through AGC of Texas offices. English & Spanish
		Highway Construction Work Zone Hazards	18 minutes	
AGC America	N/A	Highway Work Zone Safety Training	1 day	
Texas Engineering Extension Service	HWS400	Temporary Traffic Control Worker	4 hours	Contact TEEX, if interested in course
TxDOT/AGC Joint Development	N/A	Work Zone Fundamentals	10 minutes	Videos available through ACT of Texas offices. English & Spanish

Contractor may choose to train workers involved with the traffic control implementation and maintenance with a contractor developed training in lieu of Department approved training. Contractor developed training must be equivalent to the Department approved training shown in Table 2. Provide the Engineer a copy of the course curriculum for pre-approval, prior to conducting the contractor

CONTROL: 0924-00-106, ETC

COUNTY: EL PASO, ETC

HIGHWAY: VARIOUS

developed training. Provide the Engineer a copy of the log of attendees after training completion for project records.

Existing regulatory signs, route marker auxiliaries, guide signs, and warning signs that must be removed due to widening shall be relocated temporarily and erected on approved supports at locations shown in the plans, or as directed. This work will not be paid for directly but considered subsidiary to this Item.

Notify the Department officials when major traffic changes are to be made, such as detours. Coordinate with the Department on all traffic changes. Advance notification for the following week's work must be made by 5 P.M. on Wednesdays.

If Law Enforcement Personnel is required by the Engineer, coordinate with local law enforcement as directed or agreed. Complete the weekly tracking form provided by the Department and submit invoices with 5% allowance for Law Enforcement payments by Contractor that agree with the tracking form for payment at the end of each month where approved services were provided.

Always provide access to intersecting side roads and driveways, unless otherwise directed.

Any approved change to the sequence of work or TCP, must be signed and sealed by a Contractor's Licensed Professional Engineer assuming full responsibility for any additional barricade signs and devices needed.

Use striping operations to channelize traffic into the newly completed roadway, as directed. Maintain shoulders and median areas in a condition capable of serving as emergency paths, as approved. This work will be subsidiary to this Item.

Use portable changeable message signs (PCMS) to alert public of construction two weeks prior to construction.

Use flaggers when directed. Provide two-way radio communication for all flaggers.

Place and maintain sufficient additional warning signs, beacons, delineators, and barricades to warn and always guide the public of all hazards through the construction zone, and as directed.

Use flashing arrow boards on all tapers for each lane closure.

Some signs, barricades, and channelization devices may not be shown at the precise or measured position. Place the barricades, devices, or signs, with approval, in positions to meet field conditions.

Fill any holes left by barricade or sign supports and restore the area to its original condition.

Use Type A flashing warning lights or delineators to mark open excavation, footings, foundations, or other obstructions near lanes that may be open to traffic, as directed.

CONTROL: 0924-00-106, ETC

COUNTY: EL PASO, ETC

HIGHWAY: VARIOUS

For additional information pertaining to channelization, signing, spacing details, and flagging procedures required to regulate, warn, and guide traffic through project, refer to the "Barricade and Construction Standards," BC(1)-21 and to the current *Texas Manual on Uniform Traffic Control Devices(TMUTCD)*.

Remove or cover signs that do not apply to current conditions at the end of each day's work.

Repair and/or replace all signs damaged by the public or due to weather events.

#### **Safety Contingency**

The contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancement, to improve the effectiveness of the TCP that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

#### **Item 666 –Retroreflectorized Pavement Markings**

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required as pavement surface preparation.

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engineer as directed. Place final striping on these locations.

#### **Item 672 – Raised Pavement Markers**

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required for pavement surface preparation.

Furnish adhesives that conform to DMS-6100, "Epoxy and Adhesives," and DMS-6130, "Bituminous Adhesive for Pavement Markers," for this Item.

Do not place raised pavement markers when the pavement surface temperature is below 60°F.

Removal of all existing raised pavement markers will be considered subsidiary to the various bid items.

CONTROL: 0924-00-106, ETC

COUNTY: EL PASO, ETC

HIGHWAY: VARIOUS

CONTROL: 0924-00-106, ETC

COUNTY: EL PASO, ETC

HIGHWAY: VARIOUS

SHEET 17C

**Item 6185 – Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)**

All TMA Operators must participate in a TMA workshop to be conducted by the El Paso District Safety Office, on the proper use of TMAs, prior to working on Department Right of Way (ROW). A certificate of completion will be issued to TMA Operators that successfully complete the TMA workshop. The certificate of completion must always be carried by TMA Operators while working on Department right of way.

Acquire the TCP and TMA Operator’s certificates of completion prior to the authorization to begin work. No time suspension will be granted, and no traffic control work will be allowed without certificates of completion.

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

The supporting vehicle for the TMA shall have a minimum gross (i.e., ballasted) vehicular weight of 19,000 pounds.

Basis of Estimate for TMAs			
Standard	Required	Additional	TOTAL
TCP (1-2) – 18	1		1
TCP (1-4) – 18	1*		1*
TCP (1-5) – 18	1		1
TCP (3-1) – 13	2		2
TCP (3-2) – 13	3		3
TCP (3-3) – 14	3		3

\*One (1) TMA required per lane closed



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0924-00-106

DISTRICT El Paso  
HIGHWAY Various

COUNTY El Paso

CONTROL SECTION JOB				0924-00-106		0924-00-157		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00058827		A00181580			
COUNTY				El Paso		El Paso			
HIGHWAY				Various		Various			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	500-6001	MOBILIZATION	LS	1.000				1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	7.000				7.000	
	666-6006	REFL PAV MRK TY I (W)4"(DOT)(100MIL)	LF	1,440.000				1,440.000	
	666-6030	REFL PAV MRK TY I (W)8"(DOT)(100MIL)	LF	310.000				310.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	21,418.000				21,418.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	4,151.000				4,151.000	
	666-6042	REFL PAV MRK TY I (W)12"(SLD)(100MIL)	LF	1,727.000				1,727.000	
	666-6047	REFL PAV MRK TY I (W)24"(SLD)(090MIL)	LF	9,685.000		46.000		9,731.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF	1,068.000				1,068.000	
	666-6053	REFL PAV MRK TY I (W)(ARROW)(090MIL)	EA	30.000				30.000	
	666-6054	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA	51.000				51.000	
	666-6056	REFL PAV MRK TY I(W)(DBL ARROW)(090MIL)	EA	10.000				10.000	
	666-6059	REFL PAV MRK TY I(W)(TPL ARRW)(090MIL)	EA	2.000				2.000	
	666-6077	REFL PAV MRK TY I (W)(WORD)(090MIL)	EA	15.000				15.000	
	666-6078	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA	28.000				28.000	
	666-6092	REFL PAV MRK TY I (W)(RR XING)(090MIL)	EA			2.000		2.000	
	666-6093	REFL PAV MRK TY I (W)(RR XING)(100MIL)	EA	5.000		2.000		7.000	
	666-6095	REFL PAV MRK TY I (W)(SYMBOL)(090MIL)	EA	2.000				2.000	
	666-6102	REF PAV MRK TY I(W)36"(YLD TRI)(100MIL)	EA	21.000				21.000	
	666-6105	REFL PAV MRK TY I (W)(BIKE ARW)(100MIL)	EA	9.000				9.000	
	666-6111	REFL PAV MRK TY I(W)(BIKE SYML)(100MIL)	EA	9.000				9.000	
	666-6147	REFL PAV MRK TY I (Y)24"(SLD)(100MIL)	LF	1,382.000				1,382.000	
	666-6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	857,184.000				857,184.000	
	666-6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	146,240.000				146,240.000	
	666-6205	REFL PAV MRK TY II (Y) 4" (BRK)	LF	81,075.000		10,600.000		91,675.000	
	666-6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	295,578.000		87,849.000		383,427.000	
	666-6302	RE PM W/RET REQ TY I (W)4"(SLD)(090MIL)	LF	494,880.000				494,880.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	18,805.000				18,805.000	
	666-6305	RE PM W/RET REQ TY I (W)6"(BRK)(090MIL)	LF	114,622.000				114,622.000	
	666-6306	RE PM W/RET REQ TY I (W)6"(BRK)(100MIL)	LF	9,283.000				9,283.000	
	666-6311	RE PM W/RET REQ TY I (Y)4"(BRK)(090MIL)	LF	117,005.000		10,600.000		127,605.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF			28,660.000		28,660.000	
	666-6314	RE PM W/RET REQ TY I (Y)4"(SLD)(090MIL)	LF	180,234.000		87,849.000		268,083.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	23,449.000		324,295.000		347,744.000	
	666-6342	REF PROF PAV MRK TY I(W)4"(SLD)(100MIL)	LF	2,260,429.000				2,260,429.000	
	666-6344	REF PROF PAV MRK TY I(Y)4"(BRK)(100MIL)	LF	132,280.000				132,280.000	
	666-6345	REF PROF PAV MRK TY I(Y)4"(SLD)(100MIL)	LF	859,861.000				859,861.000	



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0924-00-106

DISTRICT El Paso  
HIGHWAY Various

COUNTY El Paso

CONTROL SECTION JOB				0924-00-106		0924-00-157		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00058827		A00181580			
COUNTY				El Paso		El Paso			
HIGHWAY				Various		Various			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	666-6346	REF PROF PAV MRK TY I(Y)6"(BRK)(100MIL)	LF	2,670.000				2,670.000	
	672-6007	REFL PAV MRKR TY I-C	EA	30,315.000				30,315.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	51,712.000		1,628.000		53,340.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA	34,024.000				34,024.000	
	677-6001	ELIM EXT PAV MRK & MRKS (4")	LF	1,282,238.000		98,441.000		1,380,679.000	
	677-6002	ELIM EXT PAV MRK & MRKS (6")	LF	113,555.000				113,555.000	
	677-6003	ELIM EXT PAV MRK & MRKS (8")	LF	20,443.000				20,443.000	
	677-6005	ELIM EXT PAV MRK & MRKS (12")	LF	13,896.000				13,896.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	9,685.000		46.000		9,731.000	
	677-6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA	25.000				25.000	
	677-6009	ELIM EXT PAV MRK & MRKS (DBL ARROW)	EA	8.000				8.000	
	677-6010	ELIM EXT PAV MRK & MRKS (TPL ARROW)	EA	16.000				16.000	
	677-6012	ELIM EXT PAV MRK & MRKS (WORD)	EA	12.000				12.000	
	677-6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA	2.000		135.000		137.000	
	677-6017	ELIM EXT PAV MRK & MRKS (SYMBOL)	EA	2.000				2.000	
	677-6023	ELIM EXT PAV MRK & MARKS (BIKE ARROW)	EA	9.000				9.000	
	677-6025	ELIM EXT PAV MRK & MARKS (BIKE SYMBOL)	EA	9.000				9.000	
	678-6001	PAV SURF PREP FOR MRK (4")	LF	1,225,003.000		98,441.000		1,323,444.000	
	678-6002	PAV SURF PREP FOR MRK (6")	LF	137,081.000				137,081.000	
	678-6004	PAV SURF PREP FOR MRK (8")	LF	21,908.000				21,908.000	
	678-6008	PAV SURF PREP FOR MRK (24")	LF	9,685.000		46.000		9,731.000	
	678-6009	PAV SURF PREP FOR MRK (ARROW)	EA	10.000				10.000	
	678-6010	PAV SURF PREP FOR MRK (DBL ARROW)	EA	8.000				8.000	
	678-6011	PAV SURF PREP FOR MRK (TPL ARROW)	EA	16.000				16.000	
	678-6016	PAV SURF PREP FOR MRK (WORD)	EA	12.000				12.000	
	678-6020	PAV SURF PREP FOR MRK (RR XING)	EA	2.000		2.000		4.000	
	678-6021	PAV SURF PREP FOR MRK (SYMBOL)	EA	2.000				2.000	
	678-6026	PAV SURF PREP FOR MRK (BIKE ARROW)	EA	9.000				9.000	
	678-6028	PAV SURF PREP FOR MRK (BIKE SYMBOL)	EA	9.000				9.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1.000				1.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	138.000				138.000	
08		EROSION CONTROL MAINTENANCE (NON-PART)	LS	1.000				1.000	
		RAILROAD FLAGGING: CONTRACTOR FORCE ACCOUNT WORK (NON-PARTICIPATING)	LS	1.000				1.000	
		SAFETY CONTINGENCY (NON-PART)	LS	1.000				1.000	
		LAW ENFORCEMENT	LS	1.000				1.000	

NOTES:

- 1. LOCATION IS PLACING 100 MIL OVER FY 2021 SEAL COAT PROJECT CSJ: 0924-00-106 & CSJ: 0924-00-157

DATE: 12/2/2021 2:58:45 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\QUANTITY SUMMARY.dgn

0924-00-106 SUMMARY OF PAVEMENT MARKING ITEMS (TABLE 1 OF 3)																							
LOCATION	PROPOSED WORK	500	502	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666		
		6001	6001	6006	6030	6035	6036	6042	6047	6048	6053	6054	6056	6059	6077	6078	6093	6095	6102	6105	6111	6147	666
		MOBILIZATION	BARRICADES, SIGNS AND TRAFFIC HANDLING	REFL PAV MRK TY I (W) 4" (DOT) (100MIL)	REFL PAV MRK TY I (W) 8" (DOT) (100MIL)	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	REFL PAV MRK TY I (W) 12" (SLD) (100MIL)	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	REFL PAV MRK TY I (W) (ARROW) (100MIL)	
1-0002-01	REMOVE AND REPLACE	0.04	7	1,440	0	1,855	0	2,000	0	0	0	0	0	0	0	0	0	0	0	0	0	10,900	
2-0001-05	RETRACE	0.04	0	0	0	570	360	0	164	0	8	0	0	0	0	0	0	0	0	0	0	0	
3-2552-01	RETRACE	0.04	0	0	310	0	2,648	653	0	768	0	29	0	0	0	0	0	0	0	0	0	0	
4-0001-07	REMOVE AND REPLACE	0.04	0	0	0	430	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	10,324	
5-0001-04	REMOVE AND REPLACE	0.04	0	0	0	2,723	0	0	432	0	0	0	0	0	0	0	0	0	0	0	0	30,090	
6- IH0010-FR	REMOVE AND REPLACE	0.04	0	0	0	5,070	0	0	2,085	0	30	0	10	2	15	0	3	0	0	0	0	3,240	
7-0674-01	REMOVE AND REPLACE	0.04	0	0	0	1,390	0	0	1,969	0	0	0	0	0	0	0	0	0	0	0	0	122,120	
8-0002-14	REMOVE AND REPLACE	0.04	0	0	0	3,550	0	0	1,950	0	0	0	0	0	0	0	0	0	0	0	0	173,460	
9-0002-02	REMOVE AND REPLACE	0.04	0	0	0	4,250	0	0	1,249	0	0	0	0	0	0	0	0	0	0	0	0	493,550	
10-0020-03-021	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
11-0020-04-017	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	231	
12-0020-05-016	100 MIL ON SEAL COAT	0.04	0	0	0	0	860	380	0	0	0	0	0	0	0	0	0	0	0	0	0	380	
13-0020-06	RETRACE	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
14-0020-07	RETRACE	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
15-0512-01-013	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
16-0512-02-015	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
17-0415-02-028	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
18-0415-01-026	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
19-0104-02-030	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
20-0104-03-039	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	124	0	0	0	0	0	0	0	0	0	0	0	0	437	
21-0104-04-014	100 MIL ON SEAL COAT	0.04	0	0	0	73	334	0	12	0	0	0	0	0	0	0	0	0	0	0	0	334	
22-0104-05-026	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
23-0415-05-016	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
24-0415-06-004	100 MIL ON SEAL COAT	0.04	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
29-0924-00-106	REMOVE AND REPLACE	0.04	0	0	0	2,150	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	13,500	
<b>PROJECT TOTALS</b>		<b>1</b>	<b>7</b>	<b>1,440</b>	<b>310</b>	<b>21,418</b>	<b>4,151</b>	<b>1,727</b>	<b>9,685</b>	<b>1,068</b>	<b>30</b>	<b>51</b>	<b>10</b>	<b>2</b>	<b>15</b>	<b>28</b>	<b>5</b>	<b>2</b>	<b>21</b>	<b>9</b>	<b>9</b>	<b>1,382</b>	<b>857,184</b>

0924-00-106 SUMMARY OF PAVEMENT MARKING ITEMS (TABLE 2 OF 3)																						
LOCATION	PROPOSED WORK	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	666	
		6171	6205	6207	6302	6303	6305	6306	6311	6314	6315	6342	6344	6345	6346	6007	6009	6010	6001	6002	6003	6005
		REFL PAV MRK TY II (W) 6" (BRK)	REFL PAV MRK TY II (Y) 4" (BRK)	REFL PAV MRK TY II (Y) 4" (SLD)	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	REF PROF PAV MRK TY I (W) 4" (SLD) (100MIL)	REF PROF PAV MRK TY I (Y) 4" (BRK) (100MIL)	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	REF PROF PAV MRK TY I (Y) 4" (SLD) (100MIL)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	REFL PAV MRKR TY II-C-R	ELIM EXT PAV MRK & MRKS (4")	ELIM EXT PAV MRK & MRKS (6")	ELIM EXT PAV MRK & MRKS (8")	ELIM EXT PAV MRK & MRKS (12")	ELIM EXT PAV MRK & MRKS (24")
1-0002-01	REMOVE AND REPLACE	4,330	0	1,910	10,900	0	4,330	0	0	0	0	0	0	0	1,910	0	0	16,505	4,330	1,855	1,450	2,000
2-0001-05	RETRACE	0	0	0	0	0	0	0	0	0	0	0	0	10,900	790	7,895	0	0	0	0	0	0
3-2552-01	RETRACE	0	0	0	0	0	0	0	0	0	0	0	0	12,440	785	7,895	0	219	0	0	0	0
4-0001-07	REMOVE AND REPLACE	0	675	2,550	0	0	0	655	2,550	0	10,324	0	0	0	0	0	98	10,983	0	430	470	0
5-0001-04	REMOVE AND REPLACE	51,060	0	15,878	83,840	0	20,960	0	0	10,480	0	0	0	0	0	0	0	1,048	94,320	20,960	2,723	1,421
6- IH0010-FR	REMOVE AND REPLACE	4,835	0	1,990	3,240	0	4,835	0	0	1,990	0	0	0	0	0	0	0	1,845	2,265	4,835	5,070	5,635
7-0674-01	REMOVE AND REPLACE	9,730	9,730	58,090	0	0	0	0	0	0	0	0	0	122,120	7,500	58,090	0	900	525	189,940	9,830	1,390
8-0002-14	REMOVE AND REPLACE	17,050	17,050	73,415	173,460	0	11,630	0	17,035	73,415	0	67,825	0	135,650	0	0	1,188	1,165	263,910	17,035	3,550	2,273
9-0002-02	REMOVE AND REPLACE	56,565	53,620	126,345	0	0	56,565	0	53,620	0	0	493,550	0	126,345	0	905	4,395	0	673,515	56,565	4,250	1,787
10-0020-03-021	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	98,500	9,505	11,241	0	0	0	0	0	0	0	0
11-0020-04-017	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	94,280	11,445	4,102	0	0	0	0	0	0	0	0
12-0020-05-016	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	87,750	9,430	6,200	0	0	0	0	0	0	0	0
13-0020-06	RETRACE	0	0	0	148,940	0	0	0	18,620	74,480	0	148,940	0	0	0	0	0	0	0	0	0	0
14-0020-07	RETRACE	0	0	0	74,500	0	16,302	0	17,450	17,319	0	0	0	0	0	0	0	0	0	0	0	0
15-0512-01-013	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	780	12,035	16,020	0	0	0	0	0	0	0	0
16-0512-02-015	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	225,000	24,600	73,220	0	0	0	24,600	0	0	0	0
17-0415-02-028	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	127,500	2,400	53,750	0	0	0	0	0	0	0	0
18-0415-01-026	100 MIL ON SEAL COAT	0	0	0	0	0	0	80	0	0	0	166,000	8,300	121,260	0	0	0	0	0	0	0	0
19-0104-02-030	100 MIL ON SEAL COAT	0	0	0	0	0	0	8,868	0	0	0	212,470	12,500	138,489	0	0	0	0	0	0	0	0
20-0104-03-039	100 MIL ON SEAL COAT	0	0	0	0	0	0	335	0	0	0	99,150	7,060	58,737	0	0	0	0	0	0	0	0
21-0104-04-014	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	155,000	15,780	14,068	0	0	0	0	0	0	0	0
22-0104-05-026	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	112,500	10,150	9,589	0	0	0	0	0	0	0	0
23-0415-05-016	100 MIL ON SEAL COAT	0	0	0	0	9,530	0	0	1,005	0	13,860	0	0	0	0	0	0	0	0	0	0	0
24-0415-06-004	100 MIL ON SEAL COAT	0	0																			

NOTES:

- 1. LOCATION IS PLACING 100 MIL OVER FY 2021 SEAL COAT PROJECT CSJ: 0924-00-106 & CSJ: 0924-00-157


DW: CJK  
 DW: CJK  
 DW: CJK

0924-00-106 SUMMARY OF PAVEMENT MARKING ITEMS (TABLE 3 OF 3)																							
LOCATION	PROPOSED WORK	677	677	677	677	677	677	677	677	678	678	678	678	678	678	678	678	678	678	678	6001	6185	
		6008	6009	6010	6012	6016	6017	6023	6025	6001	6002	6004	6008	6009	6010	6011	6016	6020	6021	6026	6028	6002	6005
		ELIM EXT PAV MRK & MRKS (ARROW)	ELIM EXT PAV MRK & MRKS (DBL ARROW)	ELIM EXT PAV MRK & MRKS (TPL ARROW)	ELIM EXT PAV MRK & MRKS (WORD)	ELIM EXT PAV MRK & MRKS (RR XING)	ELIM EXT PAV MRK & MRKS (SYMBOL)	ELIM EXT PAV MRK & MRKS (BIKE ARROW)	ELIM EXT PAV MRK & MRKS (BIKE SYMBOL)	PAV SURF PREP FOR MRK (4")	PAV SURF PREP FOR MRK (6")	PAV SURF PREP FOR MRK (8")	PAV SURF PREP FOR MRK (24")	PAV SURF PREP FOR MRK (ARROW)	PAV SURF PREP FOR MRK (DBL ARROW)	PAV SURF PREP FOR MRK (TPL ARROW)	PAV SURF PREP FOR MRK (WORD)	PAV SURF PREP FOR MRK (RR XING)	PAV SURF PREP FOR MRK (SYMBOL)	PAV SURF PREP FOR MRK (BIKE ARROW)	PAV SURF PREP FOR MRK (BIKE SYMBOL)	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (MOBILE OPERATION)
		EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	
1-0002-01	REMOVE AND REPLACE	0	0	0	0	1	1	9	9	16,505	4,330	1,855	2,000	0	0	0	0	1	1	9	9	1	138
2-0001-05	RETRACE	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3-2552-01	RETRACE	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
4-0001-07	REMOVE AND REPLACE	0	0	0	0	1	1	0	0	10,983	0	430	0	0	0	0	0	1	1	0	0	0	
5-0001-04	REMOVE AND REPLACE	0	0	0	0	0	0	0	0	39,230	41,920	2,723	432	0	0	0	0	0	0	0	0	0	
6-1H0010-FR	REMOVE AND REPLACE	25	8	16	12	0	0	0	0	2,265	4,835	5,635	2,085	10	8	16	12	0	0	0	0	0	
7-0674-01	REMOVE AND REPLACE	0	0	0	0	0	0	0	0	189,940	9,730	1,390	1,969	0	0	0	0	0	0	0	0	0	
8-0002-14	REMOVE AND REPLACE	0	0	0	0	0	0	0	0	261,765	17,031	3,550	1,950	0	0	0	0	0	0	0	0	0	
9-0002-02	REMOVE AND REPLACE	0	0	0	0	0	0	0	0	673,515	56,565	4,250	1,249	0	0	0	0	0	0	0	0	0	
10-0020-03-021	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
11-0020-04-017	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
12-0020-05-016	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
13-0020-06	RETRACE	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
14-0020-07	RETRACE	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
15-0512-01-013	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
16-0512-02-015	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
17-0415-02-028	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
18-0415-01-026	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
19-0104-02-030	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
20-0104-03-039	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
21-0104-04-014	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
22-0104-05-026	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
23-0415-05-016	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
24-0415-06-004	100 MIL ON SEAL COAT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
29-0924-00-106	REMOVE AND REPLACE	0	0	0	0	0	0	0	0	30,800	2,670	2,075	0	0	0	0	0	0	0	0	0	0	
<b>PROJECT TOTALS</b>		<b>25</b>	<b>8</b>	<b>16</b>	<b>12</b>	<b>2</b>	<b>2</b>	<b>9</b>	<b>9</b>	<b>1,225,003</b>	<b>137,081</b>	<b>21,908</b>	<b>9,685</b>	<b>10</b>	<b>8</b>	<b>16</b>	<b>12</b>	<b>2</b>	<b>2</b>	<b>9</b>	<b>9</b>	<b>1</b>	<b>138</b>

0924-00-106 SUMMARY OF PAVEMENT MARKING ITEMS (TABLE 1 OF 1)				
LOCATION	PROPOSED WORK	672	672	672
		6007	6009	6010
		REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	REFL PAV MRKR TY II-C-R
		EA	EA	EA
A - IH 10	RPM INSTALLATION	20,114	0	20,114
B - SL 0375	RPM INSTALLATION	4,028	0	4,028
C - US 54	RPM INSTALLATION	2,692	0	2,692
D - US 62	RPM INSTALLATION	1,191	14,602	1,191
E - US 67	RPM INSTALLATION	357	12,738	357
F - US 0090	RPM INSTALLATION	74	9,858	74
G - US 90	RPM INSTALLATION	61	5,499	61
H - SS 601	RPM INSTALLATION	676	0	676
I - FM 1437	RPM INSTALLATION	0	2,174	0
<b>PROJECT TOTALS</b>		<b>29,191</b>	<b>44,871</b>	<b>29,191</b>

**DISTRICTWIDE**  
**GENERAL**  
**QUANTITY SUMMARY**

DATE: 12/2/2021 2:58:46 PM  
 FILE: m:\0924-00-106\4-des\ign\plan set\1. general\QUANTITY SUMMARY.dgn

© 2021			
			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		20

DW:      CK:      DW:      CK:      DW:

NOTES:


- LOCATION IS PLACING 100 MIL OVER FY 2021 SEAL COAT PROJECT CSJ: 0924-00-106 & CSJ: 0924-00-157

0924-00-157 SUMMARY OF PAVEMENT MARKING ITEMS (TABLE 1 OF 1)																	
LOCATION	PROPOSED WORK	666	666	666	666	666	666	666	666	666	672	677	677	677	678	678	678
		6047	6092	6093	6205	6207	6311	6312	6314	6315	6009	6001	6007	6016	6001	6008	6020
		REFL PAV MRK TY I (W)24" (SLD ) (090MIL)	REFL PAV MRK TY I (W) (RR XING) (090M IL)	REFL PAV MRK TY I (W) (RR XING) (100M IL)	REFL PAV MRK TY II (Y) 4" (BRK)	REFL PAV MRK TY II (Y) 4" (SLD)	RE PM W/RET REQ TY I (Y)4" (BRK ) (090MIL)	RE PM W/RET REQ TY I (Y)4" (BRK ) (100MIL)	RE PM W/RET REQ TY I (Y)4" (SLD ) (090MIL)	RE PM W/RET REQ TY I (Y)4" (SLD ) (100MIL)	REFL PAV MRKR TY II-A-A	ELIM EXT PAV MRK & MRKS (4")	ELIM EXT PAV MRK & MRKS (24")	ELIM EXT PAV MRK & MRKS (RR XING)	PAV SURF PREP FOR MRK (4")	PAV SURF PREP FOR MRK (24")	PAV SURF PREP FOR MRK (RR XING)
	LF	EA	EA	LF	LF	LF	LF	LF	LF	EA	LF	LF	EA	LF	LF	EA	
CSJ: 924-00-157																	
25-0512-06	REMOVE AND REPLACE	46	2	2	10,600	87,849	10,600	0	87,849	0	1,628	98,441	46	2	98,441	46	2
26-2257-01	100 MIL ON SEAL COAT	0	0	0	0	0	0	4,250	0	92,619	0	0	0	0	0	0	0
27-2258-01	100 MIL ON SEAL COAT	0	0	0	0	0	0	10,080	0	18,047	0	0	0	0	0	0	0
28-2913-01	100 MIL ON SEAL COAT	0	0	0	0	0	0	14,330	0	213,629	0	0	0	0	0	0	0
<b>PROJECT TOTALS</b>		<b>46</b>	<b>2</b>	<b>2</b>	<b>10,600</b>	<b>87,849</b>	<b>10,600</b>	<b>28,660</b>	<b>87,849</b>	<b>324,295</b>	<b>1,628</b>	<b>98,441</b>	<b>46</b>	<b>2</b>	<b>98,441</b>	<b>46</b>	<b>2</b>

DATE: 12/2/2021 2:58:49 PM  
 FILE: m:\0924-00-106\4-design\plan set\1. general\QUANTITY SUMMARY.dgn

**DISTRICTWIDE**  
**GENERAL**  
**QUANTITY SUMMARY**

SHEET 3 OF 3

			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		21

DATE: 12/1/2021 2:38:06 PM  
 FILE: m:\0924-00-106\4-design\plan set\9. ENVIRONMENTAL\epic.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.  
2.
- No Action Required     Required Action

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required  
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)  
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)  
 Individual 404 Permit Required  
 Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.  
2.  
3.  
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

**Best Management Practices:**

<b>Erosion</b>	<b>Sedimentation</b>	<b>Post-Construction TSS</b>
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SWSP: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes     No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes     No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required     Required Action

Action No.

1.  
2.  
3.

**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required     Required Action

Action No.

1.  
2.  
3.

 <b>Texas Department of Transportation</b>		<b>Design Division Standard</b>		
<b>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC</b>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0924 00	106, ETC	VA	
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.	
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	ELP	EL PASO, ETC	22	

**TCP SELECTION TABLE**

CHK: \_\_\_\_\_  
 DWF: \_\_\_\_\_  
 CDS: \_\_\_\_\_  
 DWS: \_\_\_\_\_

#	ROADWAY	LIMITS FROM	LIMITS TO	TYPE OF WORK	SHEET	SHEET DESCRIPTION
1	SH0020	ROUNDBABOUTS AT PAISANO DR AND ALAMEDA AVE	INTERSECTION OF FM 76 AND SH 20	EDGE LINE, BROKEN, AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-2) - 13	MOBILE OPERATIONS DIVIDED HIGHWAYS
2	FM0259	DONIPHAN DR AND FM259 INTERSECTION	NEW MEXICO STATE LINE	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
				RPM INSTALLATION	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
3	SL0375	SH 20 AND TALBOT INTERSECTION	TALBOT/SL375 INTERSECTION	EDGE LINE, BROKEN, AND CENTERLINE STRIPING	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
				RPM INSTALLATION	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
4	FM1905	SH20 AND FM1905 INTERSECTION	NEW MEXICO STATE LINE	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-2) - 13	MOBILE OPERATIONS DIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
5	US0085	0.28 MI W OF US85 ANE EJECUTIVE BLVD INTERSECTION	SANTA FE ST. AND PAISANO INTERSECTION	EDGE LINE, BROKEN, AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-2) - 13	MOBILE OPERATIONS DIVIDED HIGHWAYS
6	IH0010	LEFT FRONTAGE ON IH-10 (COPIA INTERSECTION)	LEFT FRONTAGE IH-10 (YANDELL AND SANTA FE INTERSECTION)	EDGE LINE, BROKEN, AND CENTERLINE STRIPING	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
				RPM INSTALLATION	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
7	FM0076	LP 375	FABENS COUNTY LINE	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-2) - 13	MOBILE OPERATIONS DIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
8	FM0258	INTERSECTION OF FM658 AND ZARAGOZA RD	FABENS COUNTY LINE	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
9	SH0020	INTERSECTION OF SH20 AND RIO VISTA RD	EL PASO/HUDSPETH STATE LINE	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
10	US0090	CULBERSON CL	9.2 MI S OF CULBERSON CL	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
11	US0090	9.2 MI S OF CULBERSON CL	7.7 MI N OF PRESIDIO CL	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
12	US0090	7.7 MI N OF PRESIDIO CL	PRESIDIO CL	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
13	US0090	PRESIDIO CL	14.1 MI E OF PRESIDIO CL	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
14	US0090	14.1 MI E OF PRESIDIO CL	US0090 & HIGHLAND AVE	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
15	SH0118	0.01 MI S OF RM 2424	1.45 MI S OF IH 10	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
16	SH0118	1.45 MI S OF IH 10	0.62 MI S OF SH 166	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
17	SH0118	0.62 MI S OF SH 166	1.73 MI W OF SS 78	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
18	SH0118	1.73 MI W OF SS 78	SH 17	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
19	SH0017	REEVES C/L	7.77 MI E OF SH 118	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
20	SH0017	7.77 MI E OF SH 118	0.48 MI S OF SH 118	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
21	SH0017	0.48 MI S OF SH 118	8.24 MI N OF FM 1112	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
22	SH0017	8.24 MI N OF FM 1112	0.87 MI N OF FM 1112	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
23	SS0078	0.508 MI N OF SS77	0.63 MI S OF 77	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
24	SS0077	SS78	0.44 MI N OF SS78	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
25	RM2424	2424 JUNCTION & IH0010	14 MI NORTH OF 2424 JUNCTION & IH0010	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
26	RM1832	SH0017 & RM1832 INTERSECTION	11.2 MI W OF RM1832	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
27	RM1837	SH0118 & RM1837 INTERSECTION	3.376 MI E OF SH0118 & RM1837	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
28	RM2627	US0385 & RM2627 INTERSECTION	27.96 MI S OF RM2627	EDGE LINE, BROKEN AND CENTERLINE STRIPING	TCP (3-1) - 13	MOBILE OPERATIONS UNDIVIDED HIGHWAYS
				RPM INSTALLATION	TCP (3-3) - 14	MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL



*Jose Madrid Jr., P.E.*  
12-01-2021

**DISTRICTWIDE**  
**LINE DIAGRAM**  
**TCP SELECTION**

DATE: 12/1/2021 2:38:08 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCPVA\_TCP\_SELECTION.dgn

Texas Department of Transportation			
CONT	SECT	JOB	HIGHWAY
0924	00	106, ETC	VA
DIST	COUNTY		SHEET NO.
ELP	EL PASO, ETC		23

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:11 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

<b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b> <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS


SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard
<b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b>		
<b>BC (1) - 21</b>		
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT SECT	JOB HIGHWAY
REVISIONS	0924 00	106, ETC VA
4-03 7-13		
9-07 8-14		
5-10 5-21	ELP	EL PASO, ETC 24

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/1/2021 2:38:13 PM  
 FILE: m:\0924-00-106\4-des\gn\plan set\2\_TCP\standards\bc-21.dgn

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			80	1000 <sup>2</sup>
*			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - Contractor will install a regulatory speed limit sign at the end of the work zone.

**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**


**BC(2)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106	ETC	VA
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	EL PASO, ETC		25

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

### GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/1/2021 2:38:15 PM  
FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT SECT	JOB HIGHWAY
REVISIONS		0924 00	106, ETC VA
9-07	8-14	DIST	COUNTY SHEET NO.
7-13	5-21	ELP	EL PASO, ETC 26

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**



Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

**Nails shall NOT be allowed.**  
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12





**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

BC (4) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0924	00	106	ETC	VA			
9-07	8-14	DIST		COUNTY		SHEET NO.			
7-13	5-21	ELP	EL PASO, ETC				27		


DATE: 12/1/2021 2:38:17 PM  
FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





### SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



### SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

### WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

### GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- \* See BC(4) for definition of "Work Duration."
- \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



## BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	ETC	HIGHWAY			
REVISIONS		0924	00	106	ETC	VA			
9-07	8-14	DIST	COUNTY			SHEET NO.			
7-13	5-21	ELP	EL PASO, ETC			28			

DATE: 12/1/2021 2:38:19 PM  
FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

### Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:21 PM  
FILE: m:\0924-00-106\4-des\gn\plan set\2\_TCP\standards\bc-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	Hwy	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT


Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
REVISIONS	0924 00	DW:	TxDOT
9-07	8-14	OW:	TxDOT
7-13	5-21	CK:	TxDOT
CONT	SECT	JOB	HIGHWAY
		106, ETC	VA
DIST	COUNTY	SHEET NO.	
ELP	EL PASO, ETC	29	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/17/2021 2:38:23 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**  
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>PL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0924	00	106, ETC	VA				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ELP	EL PASO, ETC	30					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:26 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
 (Maximum Sign Dimension)  
 Chevron CW1-8, Opposing Traffic Lane  
 Divider, Driveway sign D70a, Keep Right  
 R4 series or other signs as approved  
 by Engineer



12" x 24"  
 Vertical Panel  
 mount with diagonals  
 sloping down towards  
 travel way

Plywood, Aluminum or Metal sign  
 substrates shall NOT be used on  
 plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0924	00	106, ETC	VA				
4-03	8-14								
9-07	5-21	DIST		COUNTY	SHEET NO.				
7-13		ELP		EL PASO, ETC	31				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:28 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\* \* \* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106	ETC	VA
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ELP	EL PASO, ETC	32	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:29 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) -21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106, ETC	VA	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ELP	EL PASO, ETC	33	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924	00	106, ETC	VA
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	ELP	EL PASO, ETC	34	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:31 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106, ETC	VA	
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	ELP	EL PASO, ETC	35	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:33 PM  
FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\bc-21.dgn




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:38 PM  
 FILE: m:\0924-00-106\4-design\plan set\2. TCP\standards\tcp1-4-18.dgn



TCP (1-4a)  
**ONE LANE CLOSED**



TCP (1-4b)  
**TWO LANES CLOSED**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	$L = WS$	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

**TCP (1-4a)**

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.


**TCP (1-4b)**

- Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.


		Traffic Operations Division Standard	
<b>TRAFFIC CONTROL PLAN</b> <b>LANE CLOSURES ON MULTILANE</b> <b>CONVENTIONAL ROADS</b>			
<b>TCP (1-4) - 18</b>			
FILE:	tcp1-4-18.dgn	DN:	CK:
© TxDOT	December 1985	CONT	SECT
2-94	4-98	0924	00
8-95	2-12	106,	ETC
1-97	2-18	ELP	EL PASO, ETC
			37

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/1/2021 2:38:40 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\tcp1-5-18.dgn



**ONE LANE CLOSURE**



**LANE CLOSURE NEAR EXIT RAMP**



**LANE CLOSURE NEAR ENTRANCE RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation  
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN  
 LANE CLOSURES FOR  
 DIVIDED HIGHWAYS**

**TCP (1-5) - 18**


FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	0924 00	106, ETC	VA	
REVISIONS	DIST	COUNTY	SHEET NO.	
	ELP	EL PASO, ETC	<b>38</b>	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/1/2021 2:38:42 PM  
 FILE: m:\0924-00-106\4-des\ign\plan set\2\_TCP\standards\tcp3-1.dgn




TCP (3-1a)  
**UNDIVIDED MULTILANE ROADWAY**




TCP (3-1b)  
**TWO-WAY ROADWAY WITH PAVED SHOULDERS**



TCP (3-1c)  
**TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS**



**TRAIL/SHADOW VEHICLE A**  
 with RIGHT Directional display Flashing Arrow Board




**TRAIL/SHADOW VEHICLE B**  
 with Flashing Arrow Board in CAUTION display

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



**STRIPING FOR TMA**

Texas Department of Transportation  
 Traffic Operations Division Standard



**TRAFFIC CONTROL PLAN  
 MOBILE OPERATIONS  
 UNDIVIDED HIGHWAYS**

**TCP (3-1) - 13**



FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106, ETC	VA	
2-94 4-98				
8-95 7-13				
1-97				
ELP	EL PASO, ETC			39

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:44 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standard\tcp3-2.dgn



**RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)**




**INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)**

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**

- ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
- For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
- Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
- The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
- Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
- The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.











**STRIPING FOR TMA**

		<b>Traffic Operations Division Standard</b>	
<b>TRAFFIC CONTROL PLAN          MOBILE OPERATIONS          DIVIDED HIGHWAYS</b>			
<b>TCP(3-2)-13</b>			
FILE: tcp3-2.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT December 1985	CONT	SECT	HIGHWAY
REVISIONS	0924 00	106, ETC	VA
2-94 4-98			
8-95 7-13			
1-97			
ELP	EL PASO, ETC		SHEET NO. 40

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:46 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\tcp3-3.dgn



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
12. For divided highways with three or four lanes in each direction, use TCP(3-2).
13. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
14. The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
15. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation




Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
 MOBILE OPERATIONS  
 RAISED PAVEMENT  
 MARKER INSTALLATION/  
 REMOVAL  
 TCP (3-3) - 14**

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106	ETC	VA
2-94 4-98				
8-95 7-13				
1-97 7-14				
DIST	COUNTY			SHEET NO.
ELP	EL PASO, ETC			41

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:49 PM  
 FILE: m:\0924-00-106\4-des\gn\plan set\2\_TCP\standards\wzbtb-13.dgn




LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.**



**GENERAL NOTES**

- The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.
- Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- High level warning devices (flag trees) may be used at corners of the vehicle.
- When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P) signs may be implemented when approved by the engineer.
- For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.
- Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.

SHEET 1 OF 1




**TRAFFIC SIGNAL WORK TYPICAL DETAILS**

**WZ(BTS-1)-13**


FILE: wzbtb-13.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106, ETC	VA	
2-98 10-99 7-13	DIST	COUNTY	SHEET NO.	
4-98 3-03	ELP	EL PASO, ETC	42	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:38:51 PM  
 FILE: m:\0924-00-106\4-design\plan set\2\_TCP\standards\wzrcd-13.dgn



**ROAD CLOSURE BEYOND THE INTERSECTION**  
 Signing for a Numbered Route with an Off-Site Detour



**ROAD CLOSURE AT THE INTERSECTION**  
 Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "x" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

\* Conventional Roads Only

**GENERAL NOTES**

1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices List (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.

Texas Department of Transportation Traffic Operations Division Standard

**WORK ZONE ROAD CLOSURE DETAILS**

**WZ (RCD) - 13**

FILE: wzrcd-13.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924 00	106, ETC	VA	
1-97 4-98 7-13	DIST	COUNTY	SHEET NO.	
2-98 3-03	ELP	EL PASO, ETC	43	

DATE: 12/1/2021 2:38:53 PM  
 FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC\RR Scope of Work.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)**

DOT #: REFER TO TABLE 1  
 Crossing Type: \*\*REFER TO TABLE 1  
 RR Company Owning Track at Crossing: REFER TO TABLE 1  
 Operating RR Company at Track: REFER TO TABLE 1  
 RR MP: REFER TO TABLE 1  
 RR Subdivision: REFER TO TABLE 1  
 City: REFER TO TABLE 1  
 County: REFER TO TABLE 1  
 CSJ at this Crossing: REFER TO TABLE 1  
 Highway/Roadway name crossing the railroad: REFER TO TABLE 1  
 # of regularly scheduled trains per day at this crossing: REFER TO TABLE 1  
 # of switching movements per day at this crossing: REFER TO TABLE 1  
 % of estimated contract cost of work within railroad ROW: REFER TO TABLE 1

Scope of Work at this Crossing to Be Performed by State Contractor:  
PAVEMENT MARKINGS  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Scope of Work at this Crossing to Be Performed by Railroad Company:  
N/A  
 \_\_\_\_\_  
 \_\_\_\_\_

\*\* Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian, or Closed/Abandoned

**II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)**

N/A

**III. FLAGGING & INSPECTION**

# of Days of Railroad Flagging Expected: 4  
 On this project, night or weekend flagging is:  
 Expected  
 Not Expected  
 Flagging services will be provided by:  
 Railroad Company: TxDOT will pay flagging invoices  
 Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30 day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

UPRR - UP.info@railpros.com  
 Call Center 877-315-0513, Select #1 for flagging  
 BNSF - BNSF.info@railpros.com  
 Call Center 877-315-0513, Select #1 for flagging  
 KCS - KCS.info@railpros.com  
 Call Center 877-315-0513, Select #1 for flagging  
 - Bottom Line On-Track Safety Services  
 bottomline076@aol.com, 903-767-7630

OTHERS \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Contractor must incorporate Construction Inspection into anticipated construction schedule.

Not Required  
 Required: Contact Information for Construction Inspection:  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD**

On this project, construction work to be performed by a railroad company is:  
 Required  
 Not Required  
 Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

**V. RAILROAD INSURANCE REQUIREMENTS**

Railroad reference number shall be provided by TxDOT CST or DO.  
 The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice. Insurance policies must be issued for and on behalf of the Railroad. Where more than one Railroad Company is operating on the same right of way or where several Railroad Companies are involved and operate on their own separate rights of way, provide separate insurance policies in the name of each Railroad Company.  
 No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$2,000,000 / \$4,000,000
Business Automobile	\$2,000,000 combined single limit
Railroad Protective Liability	
<input checked="" type="checkbox"/> Not Required	
<input type="checkbox"/> Non - Bridge Projects	\$2,000,000 / \$6,000,000
<input type="checkbox"/> Bridge Projects	\$5,000,000 / \$10,000,000
<input type="checkbox"/> Other	

#	DOT	City	County	CSJ at Crossing	Highway/Roadway Name at Crossing	Crossing Type	RR Company Owning Track at Crossing	Operating RR at Track	RR MP:	RR Subdivision
1	796213J	VAN HORN	CULBERSON	0924-00-106	FM 2424	AT GRADE	UNION PACIFIC	UNION PACIFIC	698.47	TOYAH
2	019753N	ANTHONY	EL PASO	0924-00-106	FM 1905	AT GRADE	BNSF	BNSF	1136.34	EL PASO
3	741156U	EL PASO	EL PASO	0924-00-106	1H 0010	AT GRADE	UNION PACIFIC	UNION PACIFIC	968.47	CARRIZOZO
4	741614F	EL PASO	EL PASO	0924-00-106	1H 0010	AT GRADE	UNION PACIFIC	UNION PACIFIC	968.523	CARRIZOZO

**VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT**

On this project, an ROE agreement is:  
 Not Required  
 Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)  
 Required: Contractor to obtain (see Item 5, Article 8.4)  
 With the following railroad companies: \_\_\_\_\_

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

<http://www.txdot.gov/inside-txdot/division/rail/samples.html>

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed ROE agreement between the Contractor and the Railroad if required on project.

**VII. RAILROAD COORDINATION MEETING**

On this project, a Railroad Coordination Meeting is:  
 Not Required  
 Required  
 See Item 5, Article 8.1 for more details.

**VIII. SUBCONTRACTORS**

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are required to maintain the same insurance coverage as required of the Contractor.

**IX. EMERGENCY NOTIFICATION**

**In Case of Railroad Emergency**  
 Call Union Pacific Railroad  
 Railroad Emergency Line at 800-877-7267  
 BNSF Railway (BNSF): 800-832-5452  
 Union Pacific Railroad (UPRR): 800-848-8715  
 Location: See Table 1 on all applicable entries.  
 RR Milepost: See Table 1 on all applicable entries.  
 Subdivision: Various

Rail Division

## RAILROAD SCOPE OF WORK

### PROJECT SPECIFIC DETAILS

FILE: RR Scope of Work.dgn	DN: TxDOT	CK:	DW:	CK:
© TxDOT June 2014	CONT	SECT	JOB	HIGHWAY
3/2020	REVISIONS	0924 00	106, ETC	VA
	DIST	COUNTY	SHEET NO.	
	ELP	EL PASO, ETC	<b>44</b>	

**PART 1 - GENERAL**

**1.01 DESCRIPTION**

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

**1.02 REQUEST FOR INFORMATION / CLARIFICATION**

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

**1.03 PLANS / SPECIFICATIONS**

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

**PART 2 - UTILITIES AND FIBER OPTIC**

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

**PART 3 - CONSTRUCTION**

**3.01 GENERAL**

- A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.
- B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.
- C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.
- D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.
- E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.
- F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.
- G. All permanent clearances shall be verified before project closing.

**3.02 RAILROAD OPERATIONS**

- A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.
- B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.
- C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:
  - 1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.
  - 2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

**3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES**

- A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.
- B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.
- C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.
- D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
  - 1. Exactly what the work entails.
  - 2. The days and hours that work will be performed.
  - 3. The exact location of work, and proximity to the tracks.
  - 4. The type of window requested and the amount of time requested.
  - 5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.
- E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

**3.04 INSURANCE**

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

**3.05 RAILROAD SAFETY ORIENTATION**

- A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.
 

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."
- B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

**3.06 COOPERATION**

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

**3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES**

Abide by the following minimum temporary clearances during the course of construction:  
A. 15' - 0" (BNSF) (UPRR) and 14' - 0" (KCS) horizontal from centerline of track  
B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

**3.08 APPROVAL OF REDUCED CLEARANCES**

- A. Maintain minimum track clearances during construction as specified in Section 3.07.
- B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.
- C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

DATE: 12/1/2021 2:38:55 PM  
FILE: m:\0924-00-106\4-des\gn\plan set\8. TRAFFIC.VRR Non-Bridge-Projects.dgn

				Rail Division	
<b>RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS</b>					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS March 2020	0924 00	106, ETC	VA		
	DIST	COUNTY	SHEET NO.		
ELP	EL PASO, ETC		45		

**3.09 MAINTENANCE OF RAILROAD FACILITIES**

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractor's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

**3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE**

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
  1. Pre-construction meetings.
  2. Pile driving/drilling of caissons or drilled shafts.
  3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
  4. Erection of precast concrete or steel bridge superstructure.
  5. Placement of waterproofing (prior to placing ballast on bridge deck).
  6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

**3.11 RAILROAD REPRESENTATIVES**

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

**3.12 COMMUNICATIONS AND SIGNAL LINES**

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

**3.13 TRAFFIC CONTROL**

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

**3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK**

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193  
7:00 AM to 9:00 PM CST Monday-Friday except holidays,  
staffed 24 hrs/day for emergencies  
48 hrs notice required

BNSF 1-800-533-2891  
24 hour number  
5 working days notice required

KCS 1-800-344-8377  
Texas One Call, a 24 hour number  
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

**3.15 RAILROAD FLAGGING**

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

**3.16 CLEANING OF RIGHT-OF-WAY**


When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

DATE: 12/1/2021 2:38:57 PM  
FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC.RR Non-Bridge-Projects.dgn


 Texas Department of Transportation				Rail Division	
<b>RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS</b>					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0924 00	106, ETC	VA		
March 2020	DIST	COUNTY	SHEET NO.		
	ELP	EL PASO, ETC	46		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/1/2021 2:39:00 PM  
 FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC\standards\pm1-20.dgn




**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**



**YIELD LINES**




**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

- NOTES**
- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
  - Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
  - Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

- GENERAL NOTES**
- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
  - The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**  
Based on Traveled Way and Pavement Widths  
for Undivided Highways

Texas Department of Transportation

Traffic Safety Division Standard

TYPICAL STANDARD  
PAVEMENT MARKINGS


PM(1) - 20

FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	0924	00	106, ETC	VA
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	ELP	EL PASO, ETC	47	


22B

# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/1/2021 2:39:02 PM  
 FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC\standards\pm2-20.dgn




**CENTERLINE FOR ALL TWO LANE ROADWAYS**



**CENTERLINE & LANE LINES  
FOR FOUR LANE TWO-WAY HIGHWAYS**



**CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE**




**LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)**


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**Type I (Top View)**



**Type II (Top View)**



**RAISED PAVEMENT MARKERS**


**GENERAL NOTES**

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.




## POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	0924 00	106, ETC	VA	
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	ELP	EL PASO, ETC	48	




**REFLECTORIZED PROFILE  
PATTERN DETAIL  
USING REFLECTIVE PROFILE PAVEMENT MARKINGS**



**NOTE**  
Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:39:04 PM  
 FILE: m:\0924-00-106\4-des\gn\plan set\8. TRAFFIC\standards\pm3-20.dgn



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

**LANE REDUCTION**

**NOTES**


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

**GENERAL NOTES**


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




**TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE**




**TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY**



**TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS**



**TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP**



**DETAIL A**

**DETAIL B**


Texas Department of Transportation  
 Traffic Safety Division Standard

**TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 20**

FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924	00	106, ETC	VA
5-00 2-10	DIST	COUNTY	SHEET NO.	
8-00 2-12	ELP	EL PASO, ETC	49	
3-03 6-20				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:39:06 PM  
 FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC\standards\pm4-20.dgn




**HIGH-VISIBILITY LONGITUDINAL CROSSWALK AT CONTROLLED APPROACH**

**GENERAL NOTES**

1. Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
3. For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
5. Each crosswalk shall be a minimum of 6' wide.
6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
7. Final placement of Stop Bar/Yield Triangles and Crosswalk shall be approved by the Engineer in the field.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**UNSIGNALIZED MID BLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK**



**NOTES**

1. Use yield triangles with "Yield Here to Pedestrians" signs at unsignalized mid block crosswalks.
2. Use stop bars with "Stop Here on Red" signs at mid block crosswalks controlled by traffic signals or pedestrian hybrid beacons.


		<b>Texas Department of Transportation</b>		<b>Traffic Safety Division Standard</b>	
<h2>CROSSWALK PAVEMENT MARKINGS</h2> <h3>PM(4) - 20</h3>					
FILE: pm4-20.dgn	DN:	CK:	DW:	CK:	
© TxDOT June 2020	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0924	00	106, ETC	VA	
	DIST	COUNTY	SHEET NO.		
	ELP	EL PASO, ETC	50		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/1/2021 2:39:08 PM  
 FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC\standards\rcd1-16.dgn



**2-WAY, MULTIPLE LANES EACH DIRECTION**



**2 LANES, 2-WAY**



**1-WAY STREET WITH CURB**

- NOTES**
- T: Tip of gate to edge of curb: 1' max for Quiet Zone SSM, 90% of traveled way covered by gates for all other locations
  - U: Non-traversable curb length from gate: 100' min. for a Quiet Zone SSM, 10' min for all other locations.

**NOTES**

- A1: Center of RR mast to center of rail: 12' minimum, 15' typical.
- A2: Tip of gate to center of rail: 12' minimum, 15' typical.
- B: Center of mast (cantilever, gate, or mast flasher) of nearest active traffic control device to stop line: 8' (NOTE: Stop line may be moved as needed, but should be at least 8' back from gates, if present).
- C: Center of detectable warning device to nearest rail: 6' minimum
- D: Center of gate mast to center of cantilever mast: 6' typical. NOTE: Cantilever may be located in front or behind gates.
- E: Edge of median or curb to nearest rail: 10' typical. NOTE: Design median edge to be parallel with rail.
- F: Edge of planking panel from edge of pavement or sidewalk: 3' minimum. NOTE: Field panels need not be in line with gauge panels.
- G: Length of panels along rail: 8' typical.
- H: Width of field panel: 2' typical (check with railroad company).
- I: Distance between rails: 4'-8.5\".
- J: Tip of gate to tip of gate: 2' maximum for Quiet Zone SSM or 90% of traveled way covered by gates for all other locations.
- K: Nearest edge of RR cabin from edge of pavement: 30' typical. NOTE: Cabinet not required to be parallel to edge of pavement.
- L: Nearest edge of RR cabin from nearest rail: 25' typical.
- M: Center of RR mast to edge of sidewalk: 6' minimum.
- N: Center of gate mast to leading edge of non-traversable median: 100' minimum to qualify as a Quiet Zone SSM. NOTE: 60' will suffice if there is a street intersection within the 100' and all street intersections within 60' are closed.
- O: Width of median: 8'-6\" minimum, 10' typical when using median gates. NOTE: Center of gate mast minimum 4'-3\" from face of curb.
- P: Center of RR mast to face of curb: 4'-3\" minimum. Center of RR mast to edge of pavement (with shoulder): 6' minimum. Center of RR mast to edge of pavement (no shoulder): 8'-3\" minimum. NOTE: BNSF prefers 5'-3\", 7', and 9'-3\" minimums, respectively.
- Q: Gate length: 28' or less typical, but railroad company may allow up to 32' under special circumstances.
- R: Stop line to first RR Crossing transverse line (bike lane): 50' typical.
- S: Stop line to GRADE CROSSING ADVANCE WARNING (W10-1) sign and adjacent RR Crossing pavement markings. See Table 1. See RCD(2) for other signs.

**TABLE 1**


Approach Speed (mph)	Desirable Placement (feet)
20	100
25	100
30	100
35	100
40	125
45	175
50	250
55	325
60	400
65	475
70	550
75	650

**LEGEND**

	Sign
	Object Marker
	Traffic Flow
	Cantilever
	Gate Assembly
	Mast Flasher Pair

**GENERAL NOTES**

- Medians and curbs must be non-traversable to qualify as a Quiet Zone Supplementary Safety Measure (SSM). Non-traversable curbs in Quiet Zones are 6\" tall minimum and used on roadways where speed does not exceed 40 mph.
- Raised pavement markers may be used to supplement striping. See PM(2) and PM(3) standard sheets.
- Medians preferred whenever possible to prevent vehicles from driving around gates.
- Longitudinal edge striping may be continued thru crossing as needed. Illumination may also be considered for nighttime visibility.
- See SMD standard sheets for sign mounting details.
- See the Standard Highway Sign Design for Texas (SHSD) manual for sign and pavement marking details.



**CROSSING SURFACE CROSS SECTION**


Texas Department of Transportation  
 Traffic Operations Division Standard

**RAILROAD CROSSING DETAILS  
 SIGNING, STRIPING, AND  
 DEVICE PLACEMENT  
 RCD(1)-16**

FILE: rcd1-16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT FEBRUARY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924	00	106, ETC	VA
DIST	COUNTY	SHEET NO.		
ELP	EL PASO, ETC	51		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:39:11 PM  
 FILE: m:\0924-00-106\4-des\ign\plan set\8. TRAFFIC\standards\rcd2-16.dgn



### PASSIVE CROSSING

- NOTES**
1. Stop or yield sign may also be installed to the left of the crossbuck sign, rather than below it.
  2. A 2" white retroreflective strip shall be installed on front and back of crossbuck sign post.




### PATHWAY CROSSING

- NOTES**
1. A shared use pathway is considered a separate pathway crossing when more than 25' from traveled way of adjacent roadway.
  2. Detectable warning used at stop bar.
  3. Smaller sign sizes preferred than shown to the right on this sheet.





Approach Speed (mph)	Desirable Placement (feet)
20	100
25	100
30	100
35	100
40	125
45	175
50	250
55	325
60	400
65	475
70	550
75	650

- GENERAL NOTES**
1. Railroad company to provide active traffic control devices, CROSSBUCK (R15-1), NUMBER OF TRACKS Plaque (R15-2P) (if more than 1 track), and EMERGENCY NOTIFICATION (I-13) signs.
  2. LOW GROUND CLEARANCE (W10-5) signs may be relocated further upstream of crossing to provide advance warning of alternate route.
  3. GRADE CROSSING AND INTERSECTION ADVANCE WARNING (W10-2) signs may be modified as needed to fit roadway geometry.
  4. Table 1 placement distances may vary per Sect. 2C.05 of the TMUTCD.
  5. See Table 1 to determine placement of STOP AHEAD (W3-1) and YIELD AHEAD (W3-2) signs unless shown otherwise.
  6. DO NOT STOP ON TRACKS (R8-8) signs installed when potential for vehicles stopping on tracks is significant as determined by sealing engineer. Install so sign does not block view of RR mast.
  7. See the Standard Highway Sign Design for Texas (SHSD) manual for sign and pavement marking details.



	"A" < 100'	"A" ≥ 100'
"B"	See Table 1. Place pavement markings and signs on opposite side of intersection from rail if spacing from Table 1 would put markings within intersection.	See Table 1. Place pavement markings and signs between rail and intersection if spacing from Table 1 would put markings within intersection.
"C"	See Table 1.	GRADE CROSSING AND INTERSECTION ADVANCE WARNING (W10-2, W10-3, W10-4) signs should only be installed if W10-1 sign is not between intersection and railroad crossing. If needed, see Table 1.


### GRADE CROSSING NEAR A PARALLEL STREET



### 2 ADJACENT CROSSINGS

**SIGNS**

 1 W10-1 36" DIA.	 2 W10-2L 36" X36"	 3 W10-2R 36" X36"	 IF NEEDED W10-5 36" X36"  W10-5P 30" X24"
 5 R8-8 24" X30"	 6 W3-1 30" X30"	 R1-1 36" X36"  R1-3P 18" X6"	 R15-1 48" X9"  R15-2P 27" X18"  R1-1 36" X36"
 R15-1 48" X9"  R15-2P 27" X18"  R1-2 48" X48" X48"	 R15-1 48" X9"  R15-2P 27" X18"	 W10-1 36" DIA.  NO GATES OR LIGHTS W10-13P 30" X24"	 I-13 15" X9" REPORT EMERGENCY OR PROBLEM 1-800-555-5555 CROSSING 836 597 H Sign may be placed perpend. to travel lanes.
 13 W3-2 30" X30"	 NO TRAIN HORN W10-9P 30" X24"	 LOW GROUND CLEARANCE W10-5P 30" X24"	** Includes a NO TRAIN HORN Plaque (W10-9P) if crossing is in a Quiet Zone. LOW GROUND CLEARANCE Plaque (W10-5P) if needed is mounted below W10-2/W10-3/W10-4 signs.



### T-INTERSECTION


- NOTE**
- Separate active traffic control devices, railroad crossing pavement markings, and adjacent signs required when tracks are more than 100' apart.

**RAILROAD CROSSING DETAILS SIGNING & STRIPING**  
**RCD(2) - 16**


FILE: rcd2-16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT FEBRUARY 2016 REVISIONS	CONT	SECT	JOB	HIGHWAY
	0924 00	106, ETC	VA	
DIST	COUNTY	SHEET NO.		
ELP	EL PASO, ETC	52		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/1/2021 2:39:13 PM  
 FILE: m:\0924-00-106\4-design\plan set\8. TRAFFIC\standards\ts2-1-18.dgn



**SEPARATED**



**ALTERNATING**

LEGEND	
	Sign
	Traffic Flow

TYPICAL TAPER LENGTH (L)	
Formula *	$L = WS$

\* Transition length should be rounded up to nearest 5 foot increment.

L=Length of Transition (FT)  
 W=Width of Offset (FT)  
 S=Posted Speed (MPH)

**EXAMPLE**

A 12 foot lane is added on a 70 mph roadway. The length of the transition should be:

$L = 12 \times 70 = 840 \text{ ft}$

**TABLE 1  
 ADVANCE WARNING SIGN  
 DISTANCE (D)  
 AND BUFFER DISTANCE (B)**

Posted Speed	D (FT)	B (FT)
40	670	305
45	775	360
50	885	425
55	990	495
60	1100	570
65	1200	645
70	1250	730
75	1350	820

**GENERAL NOTES**

1. For minimum and desirable design details, see the Roadway Design Manual, Chapter 4, Section 6, Super 2 Highways.
2. For Raised Pavement Markers (RPM) details, see Pavement Markings Standard sheet, PM(2). Note that RPMs are not recommended on the 4" dotted white extension lines.
3. For rumble strip options available for the designed shoulder width, see rumble strip standard sheet RS(4).



**TEXAS SUPER 2  
 PASSING LANES**

**TS2 (PL-1) - 18**

FILE: ts2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT May 2010	CONT	SECT	JOB	HIGHWAY
REVISIONS	0924	00	106, ETC	VA
2-12	DIST	COUNTY	SHEET NO.	
3-12	ELP	EL PASO, ETC	53	
3-18				

**1. SITE OR PROJECT DESCRIPTION:**

NATURE OF THE CONSTRUCTION ACTIVITY: SEE TITLE SHEET

**POTENTIAL POLLUTANTS AND SOURCES:**

Sediment laden storm water	Storm water conveyance over disturbed areas
Fuels, oils, and lubricants	Construction vehicles and storage areas
Construction debris and waste	Various construction activities
Sanitary waste	
Trash	

**SEQUENCE OF ACTIVITIES THAT WILL DISTURB SOILS:**

1. Soils will not be disturbed due to project solely consisting of pavement markings installation.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.

**AREAS:**

TOTAL AREA OF PROJECT: 868.755 MILES  
 TOTAL AREA OF SOIL DISTURBANCE: 0.000 ACRES  
 TOTAL AREA OFF-SITE: Offsite area will not be affected.  
 WEIGHTED RUNOFF COEFFICIENT (BEFORE AND AFTER CONSTRUCTION): N/A

GENERAL LOCATION MAP: SEE TITLE SHEET

**THE LOCATION AND DESCRIPTION OF CONCRETE AND ASPHALT PLANTS:**

N/A

NAME OF RECEIVING WATERS: N/A

401 WATER QUALITY CERTIFICATION: YES \_\_\_ NO X

**2. BEST MANAGEMENT PRACTICES (BMPs):**

**EROSION AND SEDIMENT CONTROLS:** Erosion and sediment controls have been designed to retain sediment on-site. Controls shall be utilized to reduce off site transport of suspended sediments and pollutants if it is necessary to pump water from the site. Control measures shall be installed per specifications or as directed. Sediment must be removed from controls per manufacturers recommendations, but no later than the time that design capacity has been reduced by 50%. If sediment escapes the site, accumulations will be removed to minimize further negative effects. Controls will be developed to limit the off site transportation of litter, construction debris, and construction materials.

**INTERIM (INT), PERMANENT (PER), AND 401 CERTIFICATION BMP'S:**

EROSION CONTROLS:			SEDIMENT CONTROLS:				
	401	INT	PER		401	INT	PER
<input type="checkbox"/> Compaction & Tracking of slopes	—	—	—	<input type="checkbox"/> Silt Fence	—	—	—
<input type="checkbox"/> Diversion Dike	—	—	—	<input type="checkbox"/> Rock Berm	—	—	—
<input type="checkbox"/> Preserve Existing Vegetation	—	—	—	<input type="checkbox"/> Buffer Zones	—	—	—
<input type="checkbox"/> Soil Stabilization	—	—	—	<input type="checkbox"/> Vegetative Filter Strips	—	—	—
<input type="checkbox"/> Permanent Vegetation	—	—	—	<input type="checkbox"/> Ditch Block	—	—	—
<input checked="" type="checkbox"/> No Erosion Controls are Required.				<input checked="" type="checkbox"/> No Sediment Controls are Required.			

**POST CONSTRUCTION TSS CONTROL (401 CERTIFICATION ONLY):**

- |  |  |
|--|--|
| <input type="checkbox"/> Vegetation Lined Drainage Ditch | <input type="checkbox"/> Grassy Swales   |
| <input type="checkbox"/> Retention/Irrigation            | <input type="checkbox"/> Vegetative Filter Strips                              |
| <input type="checkbox"/> Erosion Control Compost         | <input checked="" type="checkbox"/> No Post Construction TSS Control Required. |

The El Paso District of the Texas Department of Transportation uses Site-Manager, a computer based construction record-keeping system. Documentation describing grading activities, temporary or permanent cessation of construction, and stabilization measures is a part of this system and is incorporated by reference into this SWPPP.

**5. OTHER CONTROLS:**

**OFF-SITE VEHICLE TRACKING OF SEDIMENTS AND THE GENERATION OF DUST:** The off site vehicle tracking of sediments shall be minimized by removal of excess dirt from the road and at entrances to the work site. The generation of dust will be minimized as directed by the Project Engineer by dampening haul roads and covering haul trucks with a tarpaulin.

**CONSTRUCTION AND WASTE MATERIALS:**

The contractor will maintain a clean, orderly construction site. Construction waste including trash, rubble, scrap and vegetation shall be disposed of in lidded dumpsters or in a manner approved by the Project Engineer. Disposal methods must meet Federal, State, and Local waste management guidelines. No construction waste will be buried or burned on site. Spoils disposal, material storage, and materials resulting from the destruction of existing roads and structures shall be stored in areas designated by the Project Engineer and protected from run-off. All waterways shall be cleared of temporary embankment, temporary bridges, matting, false work, piling, debris, or other obstructions placed during construction operations, that are not part of the finished work, as soon as practicable. All excess soil generated by the construction will be collected and disposed of by the contractor. Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, water body, or stream bed.

**POLLUTANT SOURCES FROM AREAS OTHER THAN CONSTRUCTION:** Staging areas and vehicle maintenance areas shall be located and constructed in a manner to minimize the runoff of pollutants. If potential pollutant sources are identified after the start of construction, controls and measures shall be implemented as directed by the Project Engineer.

**5. OTHER CONTROLS (CONT):**

**DEDICATED ASPHALT PLANTS:** Asphalt or asphaltic material for this project will be produced off site. If the project requires a dedicated asphalt plant and the plant within 1 mile of the project limits it will be considered an off site PSL. Consideration shall be given to on site plant and storage facilities and measures implemented as directed by the Project Engineer.

**DEDICATED CONCRETE PLANTS:** Cement or Concrete material for this project will be produced off site. If the project requires a dedicated concrete plant and the plant is within 1 mile of the project limits it will be considered an off site PSL. Consideration shall be given to on site plant and storage facilities and measures implemented as directed by the Project Engineer. Concrete trucks shall be washed or washed out in locations designated by the Project Engineer. The locations shall be protected by a berm sufficient to contain all waste and wash water. Wash water shall not be allowed to enter any storm drainage system or waterway. The residual material and contaminated soil shall be collected and disposed of in accordance with Federal, State, and Local guidelines. Staging areas and vehicle maintenance areas shall be located and constructed in a manner to minimize the runoff of pollutants.

**HAZARDOUS MATERIALS AND SPILL REPORTING:** The contractor shall take appropriate measures to prevent, minimize, and control the spillage or leakage of hazardous materials and any associated wastes on site and in maintenance and staging areas. Hazardous materials shall include but are not limited to paints, acids, solvents, asphalt products, chemical additives, curing compounds, oils, fuels, and lubricants. Hazardous materials shall not be stored, accumulated, or transported in open containers subject to precipitation or spillage, but shall be stored, accumulated, or transported in closed containers of the type recommended by the manufacturer. In the event of a spill the Project Engineer should be contacted immediately. All spills shall be immediately cleaned and any contaminated soil removed and disposed of in accordance with Local, State, and Federal laws. Fuel tanks shall be protected by a secondary containment, such as a lined berm, capable of containing 1.5 times the capacity of the tank, or as approved by the Project Engineer.

**OFF SITE PSLs:** All off site project specific locations including dedicated asphalt plants, concrete plants, or utility installations, required by the contractor, are the contractor's responsibility. The contractor shall secure all permits required by local, state, or federal laws for off site PSLs. The contractor shall provide diagrams and areas of disturbance for all PSL's within 1 mile of the project.


**SANITARY FACILITIES:** All sanitary or septic wastes that are generated onsite shall be treated and disposed of in accordance with state and local regulations. Raw sewage or septage shall not be discharged or buried on site. Precaution shall be taken to prevent illicit discharges to storm water. Licensed waste management contractors shall be required to dispose of sanitary waste. Porta johns will be required for the construction site or as directed by the Project Engineer.

**VELOCITY DISSIPATION DEVICES:** Velocity dissipation devices shall be placed at discharge locations and along the length of any outfall channel as shown in the plans or as directed by the Project Engineer to provide a non-erosive flow velocity from the structure to a watercourse so that the natural physical and biological characteristics and functions are maintained and protected.

**7. MAINTENANCE:** Control measures shall be properly installed according to specifications. If inspections or other information indicates a control has been installed, used, or is performing inadequately, the contractor must replace or modify the control as soon as practicable after discovery. Control measures shall be maintained in effective operating condition. If inspections determine that BMPs are not operating effectively maintenance will be performed as necessary to continue the effectiveness of the controls. Maintenance must be accomplished as soon as practicable. Controls adjacent to creeks, culverts, bridges, and water crossings shall have priority. Controls that have been disabled, run over, removed, or otherwise rendered ineffective must be corrected immediately upon discovery.

**8. INSPECTION OF CONTROLS:** A TxDOT inspector will inspect disturbed areas of the site that have not been finally stabilized, areas used for storage of materials that are exposed to precipitation, and structural controls for evidence of, or the potential for, pollutants entering the drainage system. Sediment and erosion controls measures identified in the SWP3 will be inspected to ensure that they are operating correctly. Locations where vehicles enter or exit the site will be inspected for evidence of off-site vehicle tracking.

**9. NON-STORM WATER COMPONENTS:** The contractor shall be required to implement appropriate pollution prevention controls and measures for all eligible non-storm water components of the discharge as approved and directed by the Project Engineer.



Jose Madrid Jr., P.E.  
12-01-2021

**TxDOT STORM WATER POLLUTION PREVENTION PLAN (SWP3) (SOIL DISTURBANCE LESS THAN 1 ACRE)**



FED. RD. DIV. NO.	6			SHEET NO.	54
STATE	STATE DIST.	COUNTY			
TEXAS	ELP	EL PASO, ETC			
CONT.	SECT.	JOB	HIGHWAY NO.		
0924	00	106, ETC	VA		

REV: 07-2014