

FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.	
	STP 2022(366)HES	1	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10

INDEX OF SHEETS

SEE SHEET #2

**STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT.

PROJECT NO.: STP 2022(366)HES

CSJ: 0028-13-141

**IH 10
JEFFERSON**

LIMITS: US 90, EAST TO PINE ST

FOR THE CONSTRUCTION OF A SAFETY IMPROVEMENT PROJECT
CONSISTING OF INSTALLING WRONG WAY DRIVER TECHNOLOGIES

FINAL PLANS

LETTING DATE: _____

DATE CONTRACTOR BEGAN WORK: _____

DATE WORK WAS COMPLETED & ACCEPTED: _____

FINAL CONTRACT COST: \$ _____

CONTRACTOR : _____

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH
BC (1)-21 THRU BC (12)-21 AND THE "TEXAS MANUAL
ON UNIFORM TRAFFIC CONTROL DEVICES".



BEGIN PROJECT
CSJ 0028-13-141
WRONG WAY DRIVER DETECTION

END PROJECT
CSJ 0028-13-141
WRONG WAY DRIVER DETECTION

SEE PROJECT LOCATION MAP FOR PROJECT LOCATIONS

EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE



SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,
NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS,
SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR
ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY 2012)

© 2021
BY TEXAS DEPARTMENT OF TRANSPORTATION
ALL RIGHTS RESERVED.



SUBMITTED FOR LETTING BY: 11/30/2021

Peter Jungen
PROJECT ENGINEER

RECOMMENDED FOR LETTING: 12/5/2021

Adam Jack
DISTRICT DIRECTOR OF TRANSPORTATION
PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 12/6/2021

Maxine M. Gandy, P.E.
DISTRICT ENGINEER

578CD749500574

GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3-6 GENERAL NOTES
- 7 ESTIMATE & QUANTITY
- 8 QUANTITY SUMMARY
- 9-10 LOCATION MAP

WRONG WAY DRIVING PLAN LAYOUT SHEETS

- 11 EXIT #1 & #2 - EXIT #855B WESTBOUND - PINE STREET
- 12 EXIT #3 - EXIT #854 WESTBOUND - MLK JR PKWY
- 13 EXIT #4 - EXIT #853C WESTBOUND - 7TH STREET/EXIT #5 - EXIT #W853B WESTBOUND - FINGER ST/7TH STREET
- 14 EXIT #6 - EXIT #853B EASTBOUND - 11TH STREET
- 15 EXIT #7 - EXIT #852B WESTBOUND - GLADYS AVE
- 16 EXIT #8 - EXIT #852B WESTBOUND - HARRISON AVE
- 17 EXIT #9 - EXIT #852A WESTBOUND - LAUREL AVE
- 18 EXIT #10 - EXIT #852A WESTBOUND - LAUREL AVE
- 19 EXIT #11 - EXIT #852B EASTBOUND - RUSK/LAUREL AVE
- 20 EXIT #12 - EXIT #851 WESTBOUND - COLLEGE STREET

TRAFFIC CONTROL PLAN STANDARDS

- ## 21-32 BC (1)-21 THRU BC (12)-21
- ## 33 TCP (1-5)-18
- ## 34 TCP (2-6)-18
- ## 35 TCP (5-1)-18
- ## 36 TCP (6-1)-12
- ## 37 TCP (6-2)-12
- ## 38 TCP (6-3)-12
- ## 39 TCP (6-4)-12
- ## 40 TCP (6-5)-12
- ## 41 TCP (6-8)-14
- ## 42 WZ (RS)-16

SIGN STANDARDS

- ## 43 RFBA-13
- ## 44 SPRFBA(1)-13
- 45 TS-FD-12
- ## 46 ED(1)-14
- ## 47 ED(2)-14
- ## 48 ED(4)-14
- ## 49 SMD(GEN)-08
- ## 50 SMD(SLIP-1)08
- ## 51 SMD(SLIP-2)-08

INTELLIGENT TRANSPORTATION SYSTEMS

- ## 52 ITS(1)-15
- ## 53 ITS(3)-16
- ## 54 ITS(4)-15
- ## 55 ITS(15)-15
- ## 56 ITS(24)-15
- ## 57 ITS(25)-15
- ## 58 ITS(26)-15

WRONG WAY DETECTION EQUIPMENT

- 59 DETECTOR POLE MASTER DETAIL
- 60 "P" POST DETAIL
- 61 EXISTING "T" POST DETAIL
- 62 EXISTING "P" POST DETAIL

ENVIRONMENTAL ISSUES

- ## 63 SW3P-I
- ## 64 EC (1)-16
- 65 EPIC

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A "##" HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

DocuSigned by:
Peter Jungen 12/20/2021
 NAME:BD0FB8D3636401... DATE



**IH-10
INDEX OF SHEETS**

FILE: \$FILES\$
DATE: \$DATES\$ TIME: \$TIMES\$

© 2021 Texas Department of Transportation

FEDERAL AID PROJECT NO.		SHEET NO.	
		2	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10

County: Jefferson
Highway: IH 10

Control: 0028-13-141

General:

Contractor questions on this project are to be addressed to the following individuals:

Kenneth Wiemers, P.E.
Kenneth.Weimers@txdot.gov

Peter Jungen, P.E.
Peter.jungen@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses>.

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

The scope of this Contract is the installation of Wrong Way Detection elements at 12 locations on IH 10 in Jefferson County.

Replaced parts on this project will be returned to TxDOT to verify work completed, except as noted in the various Bid items.

The Engineer will verify and approve work to be done before work is started by the Contractor.

The Contractor is expected to maintain sufficient quantities on hand of materials necessary to perform the work.

All anticipated bid Items have been included on the estimate. If any additional Items of work are encountered, they will be paid for under Item 4 Changes in the Work.

Obtain all required toll tags for all equipment when work on SH 99 is required. This requirement will be subsidiary to the various bid Items.

Submit a material list of all major materials supplied, on company letterhead, for approval.

Designate in writing the persons authorized to pick up materials. Pick up materials at the District Signal Shop after giving a 24-hour request for materials.

County: Jefferson
Highway: IH 10

Control: 0028-13-141

Verify material quantities and dimensions before ordering materials.

Replace any major materials damaged or lost with an approved equivalent. Return all unused major materials prior to final payment.

Repair highway and appurtenances within 14 calendar days if damage is due to work being performed under this Contract. Repair work will be considered satisfactory if approved.

Maintain ingress and egress to adjacent property.

Remove equipment and material from highway right of way at the end of each work day.

Maintain adequate drainage during all construction phases.

Use 29 Code of Federal Regulation 1910.333 for electrical safety practices when performing overhead construction in the vicinity of overhead electrical lines. Consult appropriate utility company prior to beginning work.

Work, materials and services not expressly called for on the plans may need to be performed, furnished and installed at no extra compensation to ensure complete and proper construction.

Confirm utility locations 48 hours prior to any work. Notify company involved in case of conflict or damage. Repair damages to utilities prior to release from the Contract.

Department approved safety hats and safety vests will be worn by all Contractors' employees and visitors when:

1. Out-side vehicles at all outdoor work sites. This includes those who occasionally visit work sites either on the highway surface or right of way.
2. Working in areas where there is a danger of head injury from impact, or falling or flying objects, or from electrical shock or burns.

Non-compliance with this requirement will be grounds for suspension of work.

Item 6: Control of Materials

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

Control: 0028-13-141

County: Jefferson
Highway: IH 10

Control: 0028-13-141

County: Jefferson
Highway: IH 10**Item 7: Legal Relations & Responsibilities**

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the State. Maintain ingress and egress to the adjacent property at all times. Consider this work to be subsidiary to the various Bid Items of the Contract.

No significant traffic generator events have been identified in the project limits.

Item 8: Prosecution and Progress

Working days will be computed and charged in accordance with Article 8.3.1.4 Standard Workweek.

Create and maintain a bar chart schedule.

The Contractor will provide the Engineer with a valid email address and phone number for work site notification.

In instances where work is not completed within the allotted days shown on the work order, liquidated damages will be charged in accordance with SP 000-658 for each day the work is not complete. Working days will not transfer from one work order to another. Each work order is a stand-alone entity.

Manage construction of all phases to minimize disruption to traffic.

Notify the Engineer 72 hours in advance of any temporary or permanent lane, ramp or connector affected by closures, detours, or restrictions to lane widths, alterations to vertical clearances or modifications to alignment/radii. Any other modification to the roadway that may adversely affect the mobility of oversized/overweight trucks will require 5 business day advance written notice to the Engineer.

Work requiring temporary lane, ramp, or connector closures will only be allowed during non-peak hours, and only with written approval of the Engineer. Unless approved by the Engineer non-peak hours will be nighttime, or weekends. Nighttime hours will be defined as 9:00 PM until 5:00 AM, Sunday night thru Thursday night. Weekend hours will be defined as 9:00 PM on Friday night until 5:00 AM on Monday morning. No lane, ramp or connector closures will be allowed at any time during the following unless approved in writing by the Engineer: on Good Friday until midnight Easter Sunday, after 7 AM Tuesday before Thanksgiving Day through midnight Sunday after Thanksgiving, after 7 AM December 23 through January 2. One lane in each direction of each travel way is to remain open at all times. Placement of traffic control devices for night or weekend operations will not commence until after the start time and all devices will be removed from the roadway prior to the finish time. For all travel lanes, ramps, or

connector closures, provide information regarding dates, times, typical work hours, type of closure, reason for closure, and expected project duration to the Beaumont Area Office. This information shall be provided 72 hours in advance of the closure to the District Traffic Office. If approved, the District Traffic Office will forward the information to the Public Information Officer for the Beaumont District.

Work may be performed on Saturday when approved by the Engineer.

No simultaneous daytime and nighttime work will be allowed unless approved by the Engineer. Night work may be required on all projects. If required, nighttime hours will be defined as 9:00 PM until 5:00 AM, Sunday night thru Thursday night. Ensure all lanes are reopened by 5:00 A.M.

Night work will be allowed.

Law enforcement will be considered for this contract under the following conditions unless otherwise directed:

- Work involving controlled access facilities,
- Night work operations that create substantial traffic safety risks for workers and/or road users,
- Major traffic shifts involving high speed (greater than 55 MPH) and/or high-volume roadways (ADT exceeds 10,000),
- Traffic shifts at intersections where unexpected or sudden queuing is anticipated,
- Complex intersections where flaggers may not be able to maintain adequate traffic control.

Provide full-time, off-duty uniformed officer(s), with transportation jurisdiction and full police powers in the county or city in which the project is located, during construction as directed. The officer(s) must be able to show proof of certification by the Texas Commission on Law Enforcement Officers Standards.

Officer(s) will be paid by force account and must be approved. The vehicle used must be a marked law enforcement vehicle in the city or county where the project is located. Complete the daily tracking form provided by the Department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Maintain one lane open to traffic during construction, unless approved by the Engineer.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless approved by the Engineer.

County: Jefferson
Highway: IH 10

Control: 0028-13-141

Complete all work at one location before proceeding to a new location. If additional locations are approved, erect barricades only for those additional locations. Maintain barricades at each of these locations until all work at the site is completed and accepted.

The Engineer will suspend time charges after completion of all work and removal of the barricades. The Department will grant final acceptance when all performance periods are complete.

Accrue Contract time charges through the Contractor's completion of the final punch list. Time will not be suspended until all work is completed.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Item 9: Measurement and Payment

It is not anticipated that any erosion, sedimentation, or environment control devices will be needed on this project. The Contractor Force Account "SW3P" that has been established for this project is intended to be used in the event that such controls become necessary. The SW3P for this project will consist of the use of any temporary erosion control measures deemed necessary and as specified under this item. This work will be paid for in accordance with Article 4.4, "Changes in the work".

Item 100 Preparing Right of Way

When bridge demolition, tree trimming or tree/brush removal is required from February 15 to September 30, the contractor will provide a qualified biologist with a Bachelor's Degree in biology and demonstrated bird nest survey experience to conduct nesting surveys before work can begin and until vegetation work is completed to ensure compliance with the Migratory Bird Treaty Act (MBTA). See EPIC sheet for details.

Item 416: Drilled Shaft Foundations

Drilled shaft depths will be the depth shown on the plans. Any additional drilled shaft length required to raise the pole out of the ground will require the addition of reinforcing steel.

Leave minimum of one full diameter thread exposed on each anchor bolt securing a signal.

Set pole foundations so that two anchor bolts are in compression and two anchor bolts are in tension.

Use Class C concrete.

County: Jefferson
Highway: IH 10

Control: 0028-13-141

Place all Concrete for each pole foundation in one placement. Grout and rub any exposed signal pole foundation concrete.
Tack weld foundation spiral wire to the reinforced steel bars at all points.

Dispose of all excavated material, the same day of excavation, to an approved site.

Complete each foundation installation, started that day, by the end of that day's work. Ensure there will be no open foundation shafts holes at the end of each day.

Provide ground rods a minimum of 10 ft. in length.

Item 502: Barricades, Signs and Traffic Handling

Moving an existing sign to a temporary location is subsidiary to this Item. Installations with permanent supports will be paid for under the applicable Item.

"The Contractor Force Account 'Safety Contingency' that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of the enhancement."

Item 506: Erosion Control

It is not anticipated that any erosion, sedimentation, or environment control devices will be needed on this project. The Contractor Force Account "SW3P" that has been established for this project is intended to be used in the event that such controls become necessary. The SW3P for this project will consist of the use of any temporary erosion control measures deemed necessary and as specified under this item. This work will be paid for in accordance with Article 4.4, "Changes in the work".

Item 618: Conduit

PVC Conduit systems that snap or lock together without glue and that are UL listed to be used for bored PVC electrical applications, will be allowed for PVC Schedule 40 and PVC Schedule 80 upon approval.

Install necessary conduit when proposed conductors cannot be pulled through the existing conduit.

County: Jefferson
Highway: IH 10

Control: 0028-13-141

Place conduit under existing roadways and driveways as directed and in accordance with Item 476.

Cap open ends of conduit do not glue.

Ensure open trenches and excavations are filled at the end of each workday.

Use non-metallic pull rope to install conductors in PVC conduit.

Leave a minimum length of 2 ft. for each conductor cable in each ground box and in each pole.

Item 620: Electrical Conductors

Wire luminaries within a traffic signal system with 2 - #12 XHHW insulated conductors (one black and one white). Phasing tape to mark neutral conductor white will not be allowed. The entire outer jacket of the neutral conductor's insulation must be white in color. In addition, one equipment-grounding conductor must be installed in every conduit as called for by the plans and standard sheets.

Item 624: Ground Boxes

Place ground boxes 5 ft. from the edge of shoulder or curb or as directed.

Class A concrete will be considered miscellaneous.

Item 644: Signs

Sign supports shall have a minimum outside diameter of 4.5" and a minimum height of 14'.

The wedge anchor system shown on Standard Sheet SMD(TWT) is not allowed.

The set screw type for Triangular Slipbase Systems is not allowed.

Item 687: Pedestal Poles

All detector poles of the Wrong Way Driver systems shall be 20' steel poles with a minimum 4.5" outside diameter unless otherwise specified by the Engineer.

For standard sheet RFBA-13, Roadside Flashing Beacon Assembly, the flashing beacons and electrical noted do not apply to this project. The standard is included for the installation of the pole which will be used to support the Wrong Way Driver equipment. The drill shaft foundation will be used for this project.

County: Jefferson
Highway: IH 10

Control: 0028-13-141

Item 6001: Portable Changeable Message Sign

Provide up to four portable changeable message signs per intersection for seven days in advance of turning traffic signal on. Provide enough portable changeable message signs to support the turning on of two traffic signals simultaneously.

Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

In addition to the shadow vehicles with truck mounted attenuators (TMA) that are specified as being required on the traffic control plan for this project, no additional shadow vehicles with TMA will be needed. Therefore, 2 total shadow vehicles with TMA will be required for this type of work. The Contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe light are required.

Item 6409: Wrong Way Driver Thermal Imaging Camera and Associated Equipment

This Item is for "Furnish and Install" of the LED Wrong Way Driver System.

Use TAPCO Thermal Detection System or equivalent.

This Item shall include the furnishing and installation of 4G cellular modems for each location.

Partial payments consist of the following:

Materials-On-Hand: The Contractor's paid amount is based on the invoices for the material and received and stored in his/her yard.

Field Installation: When the Contractor has completed the installation of the Wrong Way Driver Thermal Imaging Camera and Associated Equipment – including LED Wrong Way Sign with basic solar power kit or other similar Items, the Department will pay up to 80% of the bid Item.

When the Wrong Way Driver Thermal Imaging Camera and Associated Equipment has passed the test portion of the Final Acceptance Test, the Department will pay the final 20% of the bid Item.

Solar Panels installation will be required for this project.

During the performance testing period, wrong way driving notifications must be received by the designated TxDOT Beaumont District and City of Beaumont 9-1-1 Dispatch personnel within the system's allotted time frame or the test will be considered as not passing.



CONTROLLING PROJECT ID 0028-13-141

DISTRICT Beaumont
HIGHWAY IH 10

COUNTY Jefferson

Estimate & Quantity Sheet

CONTROL SECTION JOB				0028-13-141		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00180223			
COUNTY				Jefferson			
HIGHWAY				IH 10			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6001	PREPARING ROW	AC	1.000		1.000	
	416-6002	DRILL SHAFT (24 IN)	LF	72.000		72.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4.000		4.000	
	618-6023	CONDT (PVC) (SCH 40) (2")	LF	180.000		180.000	
	618-6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	590.000		590.000	
	620-6011	ELEC CONDR (NO.4) BARE	LF	770.000		770.000	
	620-6012	ELEC CONDR (NO.4) INSULATED	LF	770.000		770.000	
	620-6015	ELEC CONDR (NO.2) BARE	LF	770.000		770.000	
	620-6016	ELEC CONDR (NO.2) INSULATED	LF	770.000		770.000	
	620-6019	ELEC CONDR (NO.1/0) BARE	LF	770.000		770.000	
	620-6020	ELEC CONDR (NO.1/0) INSULATED	LF	770.000		770.000	
	624-6002	GROUND BOX TY A (122311)W/APRON	EA	9.000		9.000	
	644-6009	IN SM RD SN SUP&AM TY10BWG(1)SB(P)	EA	39.000		39.000	
	644-6078	REMOVE SM RD SN SUP&AM (SIGN ONLY)	EA	3.000		3.000	
	687-6001	PED POLE ASSEMBLY	EA	12.000		12.000	
	6185-6002	TMA (STATIONARY)	DAY	60.000		60.000	
	6409-6001	LED WRONG WAY DRIVER SYSTEM (THERMAL)	EA	12.000		12.000	
18		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\ESTIMATE AND QUANTITY SHEET.dgn
DATE: 11/29/2021 1:15:40 PM



Report Generated By: txdotconnect_internal_ext

Report Created On: Nov 28, 2021 4:02:20 PM

DISTRICT	COUNTY	CCSJ	SHEET
Beaumont	Jefferson	0028-13-141	7


FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\QUANTITY SUMMARY SHEET.dgn
 DATE: 11/29/2021 1:15:46 PM

EXIT NUMBER	100	416	618	618	624	644	644	687	6409	*	*	*	*
	6001	6002	6023	6024	6002	6009	6078	6001	6001				
	PREP RIGHT-OF-WAY	DRILL SHAFT (24 IN)	CONDUIT (PVC) (SCH 40) (2")	CONDUIT (PVC) (SCH 40) (2")(BORE)	GROUND BOX TY A (122311) W/APRON	IN SM RD SN SUP&AM TY10BWG(1)SB(P)	REMOVE SM RD SN SUP&AM (SIGN ONLY)	PED POLE ASSEMBLY	INSTALL WWD THERMAL CAMERA & EQUIP	LED WRONG WAY WARNING POLE W/SOLAR	DETECTOR POLE W/SOLAR POWER KIT (D)	REMOTE SOLAR POLE W/SOLAR POWER KIT (RS)	10 FT POLE EXTENSION
	AC	LF	LF	LF	EA	EA	EA	EA		EA	EA	EA	EA
1 & 2	0.167	12		590	6	7		2	2	5	2	2	
3	0.084	6				3		1	1	3	1		
4	0.083	6				3		1	1	3	1		
5	0.083	6				3		1	1	3	1		
6	0.084	6				3		1	1	3	1		
7	0.083	6	180		3	5	2	1	1	2	1	1	2
8	0.084	6				3		1	1	3	1		
9	0.083	6				3	1	1	1	1	1		2
10	0.083	6				3		1	1	3	1		
11	0.083	6				3		1	1	3	1		
12	0.083	6				3		1	1	3	1		
TOTAL	1	72	180	590	9	39	3	12	12	32	12	3	4

* - SUBSIDIARY TO ITEM 6409 - 6001

EXIT NUMBER	620	620	620	620	620	620
	6011	6012	6015	6016	6019	6020
	ELEC CONDR (NO. 4) BARE	ELEC CONDR (NO. 4) INSULATED	ELEC CONDR (NO. 2) BARE	ELEC CONDR (NO. 2) INSULATED	ELEC CONDR (NO. 1/0) BARE	ELEC CONDR (NO. 1/0) INSULATED
	LF	LF	LF	LF	LF	LF
1 & 2	590	590	590	590	590	590
3						
4						
5						
6						
7	180	180	180	180	180	180
8						
9						
10						
11						
12						
TOTAL	770	770	770	770	770	770

IH-10
 QUANTITY SUMMARY SHEET



DocuSigned by:
Peter Jungen 11/30/2021
NAME: BD0FB8D3636401... DATE




**IH-10
LOCATION MAP**

NOT TO SCALE
© 2021 Texas Department of Transportation
SHEET 1 OF 2


FHWA TEXAS DIVISION		FEDERAL AID PROJECT NO.		SHEET NO.	
				9	
STATE	DISTRICT	COUNTY			
TEXAS	BMT	JEFFERSON			
CONTROL	SECTION	JOB	HIGHWAY NO.		
0028	13	141	IH-10		

FILE: T:\BMTTRAFC\Wrong Way Driving\CSJ 0028-13-141\DGNS\LOCATION MAP.dgn
DATE: 11/29/2021 1:15:49 PM

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\LOCATION MAP.dgn
 DATE: 11/29/2021 15:50 PM




DocuSigned by:
 Peter Jungert 11/30/2021
 NAME: 3BD0FB8D3636401 DATE:




IH-10
LOCATION MAP

NOT TO SCALE
 © 2021 Texas Department of Transportation




FEDERAL AID PROJECT NO.		SHEET NO.	
		10	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10



PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



INSTALL WARNING POLE (WP)
 - LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE

INSTALL DETECTOR POLE (D):
 - 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN

INSTALL REMOTE SOLAR (RS)
 - DUAL 130W SOLAR PANEL & ASSEMBLY
 - WIRE TO ADJACENT ITS POLE MOUNT CABINET
 - 12V 100AH BATTERIES

INSTALL CONDUIT (CB):
 - CONDUIT BORE


DocuSigned by:
 Peter Jungen 11/30/2021
 MMBD0FB8D3636401... DATE



PROPOSED ESTIMATED QUANTITIES - EXIT #1 & EXIT #2						
ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY	
416	6002		DRILL SHAFT (24 IN)	LF	12	
618	6024	CB	CONDUIT (PVC)(SCH 40)(2")(BORE)	LF	590	
624	6002		GROUND BOX	EA	6	
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	7	
687	6001		PED POLE ASSEMBLY	EA	2	
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA		
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	5	
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	2	
*		RS*	REMOTE SOLAR POLE W/SOLAR POWER KIT	EA	2	

- NOTES:
- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
 - THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
 - DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
 - ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

IH-10
 EXIT #1 & EXIT #2
 EXIT #855B WESTBOUND
 PINE ST



© 2021 Texas Department of Transportation


SHEET 1 OF 10

FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.
TEXAS	BMT	11
CONTROL	SECTION	JOB
0028	13	141
		HIGHWAY NO.
		IH-10


FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\PLAN SHEETS.dgn
 DATE: 11/29/2021 1:15:52 PM

- INSTALL DETECTOR POLE (D):**
- 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN


PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



DNE
(R5-1)



- INSTALL WARNING POLE (WP):**
- LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE

DocuSigned by:
Peter Jungen 11/30/2021
NAME: PETER C JUNGEN... DATE:




PROPOSED ESTIMATED QUANTITIES - EXIT #3					
ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3

NOTES:



- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

IH-10
EXIT #3
EXIT #854 WESTBOUND
MLK JR PKWY



© 2021 Texas Department of Transportation

STATE		DISTRICT		COUNTY	
TEXAS		BMT		JEFFERSON	
CONTROL		SECTION		JOB	
0028		13		141	
DIVISION		FEDERAL AID PROJECT NO.		SHEET NO.	
				12	
				HIGHWAY NO.	
				IH-10	



PROPOSED ESTIMATED QUANTITIES - EXIT #4					
ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1

* - SUBSIDIARY TO ITEM 6409 - 6001


PROPOSED ESTIMATED QUANTITIES - EXIT #5					
ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1

* - SUBSIDIARY TO ITEM 6409 - 6001


NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

DocuSigned by:
Peter Jungen 11/30/2021
NAME3BD0FB8D3636401... DATE




IH-10
EXIT #4
EXIT #E853C EASTBOUND
7TH ST
EXIT #5
EXIT #W853B WESTBOUND
FINGER ST/7TH ST




© 2021 Texas Department of Transportation

FEDERAL AID PROJECT NO.		SHEET NO.	
		13	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10



FILE: T:\BMTTRAF\Wrong Way Driving\GSJ 0028-13-141\DGNS\PLAN SHEETS.dgn DATE: 11/29/2021 1:16:12 PM



PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



INSTALL WARNING POLE (WP)
 - LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE

INSTALL DETECTOR POLE (D):
 - 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN

DocuSigned by:
Peter Jungen 11/30/2021
 NAME: P00FB8D3636401... DATE:




PROPOSED ESTIMATED QUANTITIES - EXIT #6					
ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1

* - SUBSIDIARY TO ITEM 6409 - 6001

NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

IH-10
EXIT #6
EXIT #853B EASTBOUND
11TH ST



© 2021 Texas Department of Transportation

FEDERAL AID PROJECT NO.		SHEET NO.	
		14	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\PLAN SHEETS.dgn DATE: 11/29/2021 1:16:21 PM

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\PLAN SHEETS.dgn
DATE: 11/29/2021 1:16:26 PM



INSTALL DETECTOR POLE (D):
 - 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN

INSTALL REMOTE SOLAR (RS):
 - DUAL 130W SOLAR PANEL & ASSEMBLY
 - WIRE TO ADJACENT ITS POLE MOUNT CABINET
 - 12V 100AH BATTERIES


INSTALL CONDUIT (C):
 - CONDUIT

INSTALL WARNING POLE (WP):
 - LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE


INSTALL WARNING POLE (WP 24/7):
 - LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - 10' PED POLE




PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



EXISTING SIGNS TO BE REMOVED



NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

PROPOSED ESTIMATED QUANTITIES - EXIT #7


ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
618	6023	C	CONDUIT (PVC) (SCH 40)(2")	LF	180
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	5
644	6078	DNE	REMOVE EXISTING DO NOT ENTER SIGNS	EA	2
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	2
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1
*		RS*	REMOTE SOLAR POLE W/SOLAR POWER KIT	EA	1
*		WP 24/7*	WRONG WAY WARNING 24/7 W/10 FT POLE EXTENSION	EA	2

* - SUBSIDIARY TO ITEM 6409 - 6001

DocuSigned by:
Peter Jungen 11/30/2021
 NAME: 3BD0FB8D3636401... DATE



IH-10
EXIT #7
EXIT #852B WESTBOUND
GLADYS AVE



© 2021 Texas Department of Transportation

STATE		DISTRICT		COUNTY	
TEXAS		BMT		JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.		
0028	13	141	IH-10		


SHEET 5 OF 10
 SHEET NO. 15

- INSTALL DETECTOR POLE (D):**
- 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN



- INSTALL WARNING POLE (WP):**
- LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE



PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



PROPOSED ESTIMATED QUANTITIES - EXIT #8

ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1

* - SUBSIDIARY TO ITEM 6409 - 6001

NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

DocuSigned by:
Peter Jungen 11/30/2021
NAME DATE




IH-10

**EXIT #8
EXIT #852B WESTBOUND
HARRISON AVE**



© 2021 Texas Department of Transportation

STATE		DISTRICT		COUNTY	
TEXAS		BMT		JEFFERSON	
CONTROL		SECTION		JOB	
0028		13		141	
HIGHWAY NO.		JOB		SECTION	
IH-10					



- INSTALL DETECTOR POLE (D):**
- 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN


- INSTALL WARNING POLE (WP):**
- LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE

PROPOSED SIGNS




WP & WP 24/7
(R5-1a-LED)

EXISTING SIGNS TO REMAIN



DNE
(R5-1)

EXISTING SIGNS TO REMOVED



WW
(R5-1a)

PROPOSED ESTIMATED QUANTITIES - EXIT #9

ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
644	6078	WW	REMOVE EXISTING WRONG WAY SIGN	EA	1
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	1
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1
*		WP 24/7*	WRONG WAY WARNING 24/7 W/10 FT POLE EXTENSION	EA	2

* - SUBSIDIARY TO ITEM 6409 - 6001


NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCITON.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

DocuSigned by:
Peter Jungen 11/30/2021
3BD0FB8D3636401... DATE



IH-10
EXIT #9
EXIT #852A WESTBOUND
LAUREL AVE




© 2021 Texas Department of Transportation


SHEET 7 OF 10

FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.
		17
STATE	DISTRICT	COUNTY
TEXAS	BMT	JEFFERSON
CONTROL	SECTION	JOB
0028	13	141
		HIGHWAY NO.
		IH-10


FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\PLAN SHEETS.dgn
DATE: 11/29/2021 1:16:42 PM



PROPOSED SIGNS




EXISTING SIGNS TO REMAIN




PROPOSED ESTIMATED QUANTITIES - EXIT #10					
ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1

* - SUBSIDIARY TO ITEM 6409 - 6001

DocuSigned by:
Peter Jungen 11/30/2021
 NAME 3BD0FB8D3636401... DATE



IH-10
EXIT #10
EXIT #852A WESTBOUND
LAUREL AVE




NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCITON.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.


FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\PLAN SHEETS.dgn
 DATE: 11/29/2021 1:16:48 PM

© 2021 Texas Department of Transportation


FEDERAL AID PROJECT NO.		SHEET NO.	
		18	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10



PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



DNE
(R5-1)

INSTALL WARNING POLE (WP)
 - LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE

INSTALL DETECTOR POLE (D):
 - 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN

ESTIMATED QUANTITIES - EXIT #11

ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1

* - SUBSIDIARY TO ITEM 6409 - 6001

DocuSigned by:
 Peter Jungen 11/30/2021
 NAME: 3BD0FB8D3838401... DATE:



IH-10
 EXIT #11
 EXIT #852B EASTBOUND
 RUSK ST/LAUREL AVE



© 2021 Texas Department of Transportation

SHEET 9 OF 10

FHWA DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.	
TEXAS	BMT	19	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\PLAN SHEETS.dgn
 DATE: 11/29/2021 1:16:56 PM


NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.





- INSTALL DETECTOR POLE (D):**
- 20' PED POLE
 - 2 EA WWD THERMAL SENSOR & CCTV EQUIP
 - 2 EA LED ILLUMINATORS
 - CELLULAR MODEM
 - ITS PLE MOUNT CABLE (CONTROLLER, RADIO TO WARNING POLES)
 - LED WWD BLINKERSIGN

PROPOSED SIGNS



EXISTING SIGNS TO REMAIN



- INSTALL WARNING POLE (WP):**
- LED WWD BLINKERSIGN WITH TOP OF POLE SOLAR POWER KIT
 - WIRELESS RADIO COMMUNICATIONS TO WWD CONTROLLER
 - 13' PED POLE

ESTIMATED QUANTITIES - EXIT #12

ITEM NO.	CODE	DESIGNATION	DESCRIPTION	UNIT	QUANTITY
416	6002		DRILL SHAFT (24 IN)	LF	6
644	6009		SMALL ROAD SIGN ASSEMBLY	EA	3
687	6001		PED POLE ASSEMBLY	EA	1
6409	6001		FURNISH AND INSTALL WWD THERMAL CAMERA AND EQUIPMENT	EA	
*		WP*	LED WRONG WAY WARNING POLE W/SOLAR POWER KIT	EA	3
*		D*	DETECTOR POLE W/SOLAR POWER KIT	EA	1


* - SUBSIDIARY TO ITEM 6409 - 6001

DocuSigned by:
Peter Jungen 11/30/2021
NAME 3BD0FB8D3636401... DATE



IH-10

**EXIT #12
 EXIT #851 WESTBOUND
 COLLEGE ST**



© 2021 Texas Department of Transportation

SHEET 10 OF 10

FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.
		20
STATE	DISTRICT	COUNTY
TEXAS	BMT	JEFFERSON
CONTROL	SECTION	JOB
0028	13	141
		HIGHWAY NO.
		IH-10

NOTES:

- EXISTING UTILITIES WITHIN THE PROJECT AREA ARE NOT SHOW IN THE THE PLANS. BEFORE DIGGING, DRILLING OR BORING IN THE PROJECT AREA, THE CONTRACTOR SHALL PERFORM A "ONE CALL" AND NOTIFY THE UTILITY COMPANIES 72 HOURS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL HAVE THE MANUFACTURER'S REPRESENTATIVE ON SITE TO ASSIST WITH THE INSTALLATION OF ALL EQUIPMENT BEFORE ANY WORK BEGINS.
- DAMAGE TO ANY EQUIPMENT IDENTIFIED TO REMAIN OR DURING RELOCATION TO BE REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE.
- ALL EXISTING SIGNS TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:11 PM
 FILE: T:\BMT\TRAF\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

BC (1) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	13	141	IH-10				
4-03	7-13								
9-07	8-14								
5-10	5-21	BMT	JEFFERSON		SHEET NO.		21		


DATE: 11/29/2021 1:17:12 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	JEFFERSON	22	

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:13 PM
FILE: T:\BMT\TRAF\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) -21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT:	13
REVISIONS		JOB:	141
9-07	8-14	HIGHWAY:	IH-10
7-13	5-21	DIST:	JEFFERSON
		COUNTY:	
		SHEET NO.:	23

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.


SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

ATTACHMENT FOR SIGN SUPPORTS




Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.



BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES



BC (4) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	13	141	IH-10				
9-07	8-14	DIST		COUNTY		SHEET NO.			
7-13	5-21	BMT		JEFFERSON		24			

DATE: 11/29/2021 1:17:14 PM
FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:15 PM
 FILE: T:\BMT\TRAFC\Wrong Way Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- * See BC(4) for definition of "Work Duration."
- ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS	0028	13	141	IH-10					
9-07	8-14	DIST:	COUNTY:	SHEET NO.					
7-13	5-21	BMT	JEFFERSON	25					

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:16 PM
FILE: T:\BMT\TRAFFIC\Wrong Way Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	Hwy	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	13	141	IH-10				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	JEFFERSON	26					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:18 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



Install a minimum of 3 Barrier Reflectors as per manufacturer's recommendations.

DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	13	141	IH-10				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	BMT	JEFFERSON		27				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:19 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES


- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



This detail is not intended for fabrication. See note 3 and the CWZTCD list for providers of approved Detectable Pedestrian Barricades



18" x 24" Sign (Maximum Sign Dimension)
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
 mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	13	141	IH-10				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	BMT	JEFFERSON	28					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:20 PM
 FILE: I:\BMT\TRAF\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	JEFFERSON	29	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:21 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TRAFFIC CONTROL FOR MATERIAL STOCKPILES


Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




PLAN VIEW

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) -21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	JEFFERSON	30	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	JEFFERSON	31	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:22 PM
FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	BMT	JEFFERSON	32	
11-02 8-14				




Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:23 PM
FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:25 PM
 FILE: T:\BMT\TRAFFIC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp1-5-18.dwg



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.


Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 LANE CLOSURES FOR
 DIVIDED HIGHWAYS**


TCP (1-5) - 18

FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	0028	13	141	IH-10
	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	33	


DATE: 11/29/2021 1:17:26 PM
 FILE: I:\BMT\TRAFFIC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp2-6-18.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-6a)
ONE LANE CLOSURE



TCP (2-6b)
LANE CLOSURE NEAR EXIT RAMP



TCP (2-6c)
LANE CLOSURE NEAR ENTRANCE RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
 - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

TCP (2-6) - 18

FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	BMT	JEFFERSON	34	
1-97 2-18				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:27 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp5-1-18.dgn



TCP (5-1a)

WORK AREA ON SHOULDER



TCP (5-1b)

WORK AREA ON SHOULDER

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	L = WS ² / 60	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

GENERAL NOTES

1. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
2. 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.




**TRAFFIC CONTROL PLAN
 SHOULDER WORK FOR
 FREEWAYS / EXPRESSWAYS**

TCP (5-1) - 18


FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
2-18	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	35	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:29 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp6-1.dgn



TCP (6-1a)
**TYPICAL FREEWAY
 ONE LANE CLOSURE**



TCP (6-1b)
**TYPICAL FREEWAY
 TWO LANE CLOSURE**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Texas Department of Transportation
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
 FREEWAY LANE CLOSURES**

TCP (6-1) - 12


FILE:	tcp6-1.dgn	DWG:	TxDOT	CHK:	TxDOT	DWG:	TxDOT	CHK:	TxDOT
© TxDOT	February 1998	CONT:		SECT:		JOB:		HIGHWAY:	
8-12	REVISIONS	0028	13	141		IH-10			
	DIST:	BMT		COUNTY:	JEFFERSON	SHEET NO.:	36		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:30 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp6-2.dgn



TCP (6-2a)
ENTRANCE RAMP OPEN
WORK WITHIN 500' OF RAMP



TCP (6-2b)
ENTRANCE RAMP CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
 - ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainlane can be seen from both roadways.
 - See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
 - The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
WORK AREA NEAR RAMP

TCP (6-2) - 12


FILE:	tcp6-2.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	February 1994	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0028	13	141	IH-10					
1-97	8-98	DIST	COUNTY	SHEET NO.					
4-98	8-12	BMT	JEFFERSON	37					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:31 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp6-3.dgn



TCP (6-3a)
ENTRANCE RAMP OPEN



TCP (6-3b)
EXIT RAMP CLOSED
TRAFFIC EXITS PRIOR TO CLOSED RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES:
 1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
 WORK AREA BEYOND RAMP**

TCP (6-3) - 12


FILE: tcp6-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	BMT	JEFFERSON	38	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:32 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp6-4.dgn



TCP (6-4a)
EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP



TCP (6-4b)
EXIT RAMP OPEN

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

**Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
 - See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP (6-4) - 12


FILE: tcp6-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	BMT	JEFFERSON	39	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:34 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp6-5.dgn



TCP (6-5a)
EXIT RAMP OPEN



TCP (6-5b)
**EXIT RAMP OPEN
 TWO LANE CLOSURE WITHIN
 1500' PAST EXIT RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" * * *			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC standards for sign details.
- If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN
 WORK AREA BEYOND EXIT RAMP**

TCP (6-5) - 12


FILE: tcp6-5.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	BMT	JEFFERSON	40	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:35 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\tcp6-8.dgn



TCP (6-8a)



TCP (6-8b)



TCP (6-8c)

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Place channelizing devices in the gore at 20' spacing.
 - See the Standard Highway Sign Design for Texas (SHSD) for sign details.
 - The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
 - When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) for traffic control details.
 - Truck mounted attenuator is required.
 - The PCMS may be omitted if replaced with a "RAMP CLOSED" AHEAD (CW20RP-3D) Sign.
 - Roadway ADT should be greater than 10,000.



WORK IN EXIT GORE FOR ADT GREATER THAN 10,000

TCP (6-8) - 14


FILE: tcp6-8.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	41	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:36 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\wzrs16.dgn

Warning sign and rumble strip sequence in opposite direction is same as below

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



WZ (RS-1a)
75 mph or Less
RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



WZ (RS-1b)
75 mph or Less
RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Removal of the Temporary Rumble Strips should be accomplished before removing the advance warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an AFAD or a portable traffic signal.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment.

Speed	Approximate distance between strips in an Array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
> 55 MPH	20'

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	700'	770'	840'	70'	140'	800'	475'	
75	750'	825'	900'	75'	150'	900'	540'	

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

Texas Department of Transportation
 Traffic Operations Division Standard

TEMPORARY RUMBLE STRIPS


WZ (RS) - 16

FILE: wzrs16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
2-14	DIST	COUNTY	SHEET NO.	
4-16	BMT	JEFFERSON	42	


DATE: 11/29/2021 1:17:38 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\rfba-13.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES:


1. Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
2. See Item 685, "Roadside Flashing Beacon Assemblies" for further requirements.
3. See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
4. Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered flashing beacon assemblies.
5. When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
6. Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on poles.
7. Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
8. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
9. Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening of connection.
10. Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL in the file "Roadway Illumination and Electrical Supplies." Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse slug. For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
11. Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
12. Make connections to ground rods according to NEC. Ground rod clamps shall be listed for their intended purpose.
13. Ensure height of conduit and ground rod is below top of anchor bolts.




FRONT



SIDE



NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS



**NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS
EXPLODED VIEW**

Texas Department of Transportation

Traffic Operations Division Standard

ROADSIDE FLASHING BEACON ASSEMBLY

RFBA-13



FILE: rfba-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT January 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
5-93 12-04	DIST	COUNTY	SHEET NO.	
10-93 3-13	BMT	JEFFERSON	43	
4-98				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:39 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\spb1-13.dgn

GENERAL NOTES:

- Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
- See Item 685, "Roadside Flashing Beacon Assemblies" for further requirements.
- See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered flashing beacon assemblies.
- When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- Use materials specifically designed for attaching cabinets, beacon heads, solar panels, etc., to poles.
- Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on poles.
- Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening on connection.
- Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL in the file "Roadway Illumination and Electrical Supplies." Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse slug. For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
- Install the batteries in a battery box. Place the batteries on a 3/16" thick plastic sheet and connect together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and 3/16" plastic sheet are subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies." When required, install batteries in the flasher cabinet. Wire batteries according to manufacturers recommendations. Provide the number of batteries as required by the manufacturer.
- See standard sheet Electrical Details (ED) for additional requirements regarding the installation of ground boxes/battery boxes, conduit, and cabinets.
- Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
- Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- Orient solar panel for optimum exposure to sunlight (face to the south). Prior to installation, check the location to ensure there is no overhead obstruction that would block the solar panel from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- Ensure height of conduit is below top of anchor bolts.



NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS



**NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS
EXPLODED VIEW**

SOLAR POWERED ROADSIDE FLASHING BEACON ASSEMBLY DETAILS
SPRFBA (1) - 13

FILE: spb1-13.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
12-04	DIST	COUNTY	SHEET NO.	
3-13	BMT	JEFFERSON	44	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the consequences of any use of this standard to other formats or for incorrect results or damages resulting from its use.

DISCLAIMER:

DATE: 11/29/2021 1:17:40 PM
 FILE: I:\BMT\TRAFC\Wrong Way Driving\CSJ 0028-13-141\STANDARDS\ts-fd.dgn

FOUNDATION DESIGN TABLE

FDN TYPE	DRILLED SHAFT DIA	REINFORCING STEEL		EMBEDDED DRILLED SHAFT LENGTH-ft (4), (5), (6)			ANCHOR BOLT DESIGN (1)			FOUNDATION DESIGN LOAD (2)		TYPICAL APPLICATION	
		VERT BARS	SPIRAL & PITCH	TEXAS CONE PENETROMETER N Blows/ft			ANCHOR BOLT DIA	Fy (ksi)	BOLT CIR DIA	ANCHOR TYPE	MOMENT K-ft		SHEAR Kips
				10	15	40							
24-A	24"	4- #5	#2 at 12"	5.7	5.3	4.5	3/4"	36	12 3/4"	1	10	1	Pedestal pole, pedestal mounted controller.
30-A	30"	8- #9	#3 at 6"	11.3	10.3	8.0	1 1/2"	55	17"	2	87	3	Mast arm assembly. (see Selection Table)
36-A	36"	10- #9	#3 at 6"	13.2	12.0	9.4	1 3/4"	55	19"	2	131	5	Mast arm assembly. (see Selection Table) 30' strain pole with or without luminaire.
36-B	36"	12- #9	#3 at 6"	15.2	13.6	10.4	2"	55	21"	2	190	7	Mast arm assembly. (see Selection Table) Strain pole taller than 30' & strain pole with mast arm
42-A	42"	14- #9	#3 at 6"	17.4	15.6	11.9	2 1/4"	55	23"	2	271	9	Mast arm assembly. (see Selection Table)

NOTES:


- Anchor bolt design develops the foundation capacity given under Foundation Design Loads.
- Foundation Design Loads are the allowable moments and shears at the base of the structure.
- Foundations may be listed separately or grouped according to similarity of location and type. Quantities are for the Contractor's information only.
- Field Penetrometer readings at a depth of approximately 3 to 5 feet may be used to adjust shaft lengths.
- If rock is encountered, the Drilled Shaft shall extend a minimum of two diameters into solid rock.
- Decimal lengths in Design Table are to allow interpolation for other penetrometer values. Round to nearest foot for entry into Summary Table.

FOUNDATION SUMMARY TABLE (3)

LOCATION IDENTIFICATION	AVG. N BLOW /ft.	FDN TYPE	NO. EA	DRILLED SHAFT LENGTH (6) (FEET)				
				24-A	30-A	36-A	36-B	42-A
EXIT #1 - D	10	24-A	1	6				
EXIT #2 - D	10	24-A	1	6				
EXIT #3 - D	10	24-A	1	6				
EXIT #4 - D	10	24-A	1	6				
EXIT #5 - D	10	24-A	1	6				
EXIT #6 - D	10	24-A	1	6				
EXIT #7 - D	10	24-A	1	6				
EXIT #8 - D	10	24-A	1	6				
EXIT #9 - D	10	24-A	1	6				
EXIT #10 - D	10	24-A	1	6				
EXIT #11 - D	10	24-A	1	6				
EXIT #12 - D	10	24-A	1	6				
TOTAL DRILLED SHAFT LENGTHS				72				

FOUNDATION SELECTION TABLE FOR STANDARD MAST ARM PLUS ILSN SUPPORT ASSEMBLIES (ft)

80 MPH DESIGN WIND SPEED	MAX SINGLE ARM LENGTH	FDN 30-A	FDN 36-A	FDN 36-B	FDN 42-A
		24' X 24'			
MAXIMUM DOUBLE ARM LENGTH COMBINATIONS	28' X 28'				
	32' X 28'				
	36' X 36'				
	40' X 36'				
100 MPH DESIGN WIND SPEED	MAX SINGLE ARM LENGTH		36'	44'	
	MAXIMUM DOUBLE ARM LENGTH COMBINATIONS	24' X 24'			
		28' X 28'			
		32' X 24'			
			32' X 32'		
			36' X 36'		
			40' X 24'	40' X 36'	
				44' X 36'	






ANCHOR BOLT & TEMPLATE SIZES

BOLT DIA IN.	(7) BOLT LENGTH	TOP THREAD	BOTTOM THREAD	BOLT CIRCLE	R2	R1
3/4"	1'-6"	3"	—	12 3/4"	7 1/8"	5 5/8"
1 1/2"	3'-4"	6"	4"	17"	10"	7"
1 3/4"	3'-10"	7"	4 1/2"	19"	11 1/4"	7 3/4"
2"	4'-3"	8"	5"	21"	12 1/2"	8 1/2"
2 1/4"	4'-9"	9"	5 1/2"	23"	13 3/4"	9 1/4"

(7) Min dimensions given, longer bolts are acceptable.

EXAMPLE:

- For 80mph design wind speed, foundation 30-A can support up to a 32' arm with another arm up to 28'
- For 100mph design wind speed, foundation 36-A can support a single 36' mast arm.



FOUNDATION DETAILS

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals and interim revisions thereto.


Reinforcing steel shall conform to Item 440, "Reinforcing Steel".

Concrete shall be Class "C".

Threads for anchor bolts and nuts shall be rolled or cut threads of 8UN series up to 2" in diameter or UNC series for all sizes. Bolts and nuts shall have Class 2A and 2B fit tolerances. Galvanized nuts shall be tapped after galvanizing.

Anchor bolts that are larger than 1" in diameter shall conform to "alloy steel" or "medium-strength mild steel" per Item 449, "Anchor Bolts". Anchor bolts that are 1" in diameter or less shall conform to ASTM A36. Galvanize a minimum of the top end thread length plus 6" for all anchor bolts unless otherwise noted. Exposed washers and exposed nuts shall be galvanized. All galvanizing shall be in accordance with Item 445, "Galvanizing".

Templates and embedded nuts need not be galvanized. Lubricate and tighten anchor bolts when erecting the structure in accordance with Item 449, "Anchor Bolts".



11/30/2021



TRAFFIC SIGNAL POLE FOUNDATION

TS-FD-12

© TxDOT August 1995		DN: MS	CK: JSY	DW: MAQ/MMF	CK: JSY/TEB
REVISONS	CONT	SECT	JOB	HIGHWAY	
	0028	13	141	IH-10	
DIST	COUNTY		SHEET NO.		
BMT	JEFFERSON		45		

DATE: 11/29/2021 1:17:42 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\ed1-14.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES FOR ALL ELECTRICAL WORK

- The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
- Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
- Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is 1/2 in. or less in diameter.
- Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
- Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
- When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

CONDUIT

A. MATERIALS

- Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
- Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
- Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.


AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" x 8" x 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" x 8" x 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" x 8" x 4"	8" x 8" x 4"	10" x 10" x 4"
#8	8" x 8" x 4"	8" x 8" x 4"	8" x 8" x 4"

- Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
- Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
- Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
- Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

- Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
- When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
- Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.


B. CONSTRUCTION METHODS

- Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
- Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
- Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
- Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
- When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
- Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
- During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
- Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
- Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
- Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
- At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
- Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
- Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
- File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.

				Traffic Operations Division Standard	
<h1>ELECTRICAL DETAILS CONDUITS & NOTES</h1>					
<h2>ED(1) - 14</h2>					
FILE:	ed1-14.dgn	DW:	CK:	DW:	CK:
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0028	13	141	IH-10
		DIST	COUNTY		SHEET NO.
		BMT	JEFFERSON		46

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



DATE: 11/29/2021 1:17:43 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\ed2-14.dgn



CONDUIT HANGING DETAIL


CONDUIT MOUNTING CHANNEL		
"SPAN"	"W" x "H"	"T"
less than 2'	1 5/8" x 1 3/8"	12 Ga.
2'-0" to 2'-6"	1 5/8" x 1 5/8"	12 Ga.
>2'-6" to 3'-0"	1 5/8" x 2 7/16"	12 Ga.

Channels with round or short slotted hole patterns are allowed, if the load carrying capacity is not reduced by more than 15%.




HANGER ASSEMBLY DETAIL

ELECTRIC CONDUIT TO BRIDGE DECK ATTACHMENT



CONDUIT MOUNTING OPTIONS

Attachment to concrete surfaces
 See ED(1)B.2



TYPICAL CONDUIT ENTRY TO BRIDGE STRUCTURE DETAIL


EXPANSION ANCHOR NOTES FOR BRIDGE DECK ATTACHMENT

1. Use torque controlled mechanical expansion anchors that are approved for use in cracked concrete by the International Code Council, Evaluation Service (ICC-ES). The chosen anchor product shall have a designated ICC-ES Evaluation Report number, and its approval status shall be maintained on the ICC-ES website under Division 031600 for Concrete Anchors.
2. Unless otherwise approved by the Engineer: do not use adhesive anchors; do not use expansion anchors that are not included in the ICC-ES approval list; and do not use expansion anchors that are only approved for use in uncracked concrete.
3. Use anchors manufactured with stainless steel expansion wedges. Anchors manufactured with carbon steel expansion wedges are not allowed. Anchor bodies can be either zinc-plated carbon steel or stainless steel. For application in marine environment, both the anchor body and expansion wedge shall be stainless steel.
4. Install anchors as shown on the plans and in accordance with the anchor manufacturer's published installation instructions. Arrange a field demonstration test to evaluate the procedures and tools. The test shall be witnessed and approved by the Engineer prior to furnishing anchors on the structure.
5. Prior to hole drilling, use rebar locator to ensure clearing of existing deck strands or reinforcement. Install anchors to ensure a minimum effective embedment depth, (h_{ef}), as shown. Increase (h_{ef}) as needed to ensure sufficient thread length for proper torquing and tightening of anchors.
6. Use anchors of minimum 1600 Lbs tensile capacity (minimum of steel, concrete breakout, and concrete pullout strengths as determined by ACI 318 Appendix D) at the required minimum embedment depth (h_{ef}). No lateral loads shall be introduced after conduit installation.

		Traffic Operations Division Standard	
<h2>ELECTRICAL DETAILS CONDUIT SUPPORTS</h2>			
<h3>ED(2) - 14</h3>			
FILE:	ed2-14.dgn	DN:	TxDOT
© TxDOT	October 2014	CK:	TxDOT
REVISIONS	0028	DW:	TxDOT
	13	CK:	TxDOT
DIST	BMT	JOB	141
COUNTY	JEFFERSON	HIGHWAY	IH-10
		SHEET NO.	47

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:44 PM
 FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\ed4-14.dgn




APRON FOR GROUND BOX

- (1) Uniformly space ends of conduits within the ground box. Position ends of conduits so that ground box walls do not interfere with the installation of grounding bushings or bell end fittings.
- (2) Maintain sufficient space between conduits to allow for proper installation of bushing.
- (3) Place aggregate under the box, not in the box. Aggregate should not encroach on the interior volume of the box.
- (4) Install a grounding bushing on the upper end of all RMC terminating in a ground box. Ground RMC elbows when any part of the elbow is less than 18 in. below the bottom of the ground box. Install a PVC bushing or bell end fitting on the upper end of all PVC conduits terminating in a ground box.

GROUND BOX DIMENSIONS	
TYPE	OUTSIDE DIMENSIONS (INCHES) (Width x Length X Depth)
A	12 X 23 X 11
B	12 X 23 X 22
C	16 X 29 X 11
D	16 X 29 X 22
E	12 X 23 X 17

GROUND BOX COVER DIMENSIONS								
TYPE	DIMENSIONS (INCHES)							
	H	I	J	K	L	M	N	P
A, B & E	23 1/4	23	13 3/4	13 1/2	9 7/8	5 1/8	1 3/8	2
C & D	30 1/2	30 1/4	17 1/2	17 1/4	13 1/4	6 3/4	1 3/8	2



GROUND BOX COVER

GROUND BOXES

A. MATERIALS

1. Provide polymer concrete ground boxes measuring 16x30x24 in. (WxLxD) or smaller in accordance with Departmental Material Specification (DMS) 11070 "Ground Boxes" and Item 624 "Ground Boxes."
2. Provide Type A, B, C, D, and E ground boxes as shown in the plans, and as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 624.
3. Ensure ground box cover is correctly labeled in accordance with DMS 11070.
4. Provide larger ground boxes in accordance with Item 624 and as shown in the plans.

B. CONSTRUCTION METHODS

1. Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure aggregate bed is in place and at least 9 inches deep, prior to setting the ground box. Install ground box on top of aggregate.
2. Cast ground box aprons in place. Reinforcing steel may be field bent. Ensure the depth of concrete for the apron extends from finished grade to the top of the aggregate bed under the box. Ground box aprons, including concrete and reinforcing steel, are subsidiary to ground boxes when called for by descriptive code.
3. Keep bolt holes in the box clear of dirt. Bolt covers down when not working in ground boxes.
4. Install all conduits and ells in a neat and workmanlike manner. Uniformly space conduits so grounding bushings and bell end fittings can easily be installed.
5. Temporarily seal all conduits in the ground box until conductors are installed.
6. Permanently seal conduits immediately after the completion of conductor installation and pull tests. Permanently seal the ends of all conduits with duct seal, expandable foam, or other method as approved. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a sealant.
7. When a ground rod is present in a ground box, bond all equipment grounding conductors together and to the ground rod with listed connectors.
8. When a type B or D ground box is stacked to meet volume requirements, it is allowable to cut an appropriately sized hole for conduit entry in the side wall at least 18 inches below grade.
9. If an existing ground box in the contract has a metal cover, bond the cover to the equipment grounding conductor with a 3 ft. long stranded bonding jumper the same size as the grounding conductor. The bonding jumper is subsidiary to various bid items. Verify existing ground boxes with metal covers are shown on the plans, with notes fully describing the work required.
10. If other ground boxes with metal covers are within the project limits but are not part of the contract, the Engineer may direct the Contractor to bond the metal covers, identifying the specific boxes in writing. This work will be paid for separately.
11. Bond metal ground box covers to the grounding conductor with a tank ground type lug.

				Traffic Operations Division Standard	
<h2>ELECTRICAL DETAILS</h2> <h3>GROUND BOXES</h3> <h4>ED(4) - 14</h4>					
FILE:	ed4-14.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2014	CONT:	0028	SECT:	13
REVISIONS:		JOB:	141	HIGHWAY:	IH-10
		DIST:	JEFFERSON	COUNTY:	
				SHEET NO.:	48

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


Post Type
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)

Anchor Type
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))



Sign Mounting Designation
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))

REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT






To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION



No more than 2 sign posts should be located within a 7 ft. circle.



TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND



RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>




SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS SMD(GEN)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0028	13	141	IH-10
		DIST	COUNTY		SHEET NO.
		BMT	JEFFERSON		49

DATE: 11/29/2021 1:17:46 PM
 FILE: I:\BMT\TRAFC\Wrong Way Driving\CSJ_0028-13-141\STANDARDS\smgen.dgn

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



SM RD SGN ASSM TY XXXXX(X)SA(X-XXXX)

NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



5/8" diameter Concrete Anchor - 8 places (embed a minimum of 5 1/2" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:47 PM
FILE: I:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\smads1.dgn

Texas Department of Transportation
Traffic Operations Division















SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0028	13	141	IH-10
		DIST	COUNTY	SHEET NO.	
		BMT	JEFFERSON	50	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:48 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\smds2.dgn



All dimensions are in english unless detailed otherwise.

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

GENERAL NOTES:

- SIGN SUPPORT # OF POSTS MAX. SIGN AREA

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
- Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.
- Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)




SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM
 SMD(SLIP-2)-08


© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0028	13	141	IH-10
		DIST	COUNTY		SHEET NO.
		BMT	JEFFERSON		51

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:50 PM
 FILE: T:\BMT\TRAFFIC\Wrong Way Driving\CSJ_0028-13-141\STANDARDS\ITS(1)-15.dgn




ITS Pole with Cabinet




Detail A




Handhole Cover Plate Detail
(Bottom Handhole)




Top Plate Plan




Base Plate Plan
4 Bolt Base Plate (ASTM A36)




Base Plate Plan
6 Bolt Base Plate (ASTM A36)



Base Plate Plan
8 Bolt Base Plate (ASTM A36)



Section A-A
Handhole Frame



Section B-B

- General Notes**
1. Designed according to Sixth Edition 2013 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications.
 2. Unless otherwise noted, all parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."
 3. Deviation from the design criteria, values, and dimensions shown herein and on ITS(4), constitutes an alternative design and will require submission of shop drawings and calculations for approval, sealed by a Texas Professional Engineer.
 4. Direct substitution of twelve sided or round poles, matching the design criteria, values, and dimensions shown herein, require submission of shop drawings for approval to confirm design criteria and values on ITS(4) is met.
 5. Locate handholes opposite of the direction of travel.
 6. Appropriate number of anchor bolts for base plate determined by height of pole. See 'L' on sheet ITS(4).
 7. Location for ITS equipment mount may vary by device. Locate mid span handhole and pipe nipple to accommodate location for ITS equipment as identified in the plans or per manufacturer recommendations. Identify location for mid span handhole and pipe nipple on shop drawings for approval.
- Reference Notes:**
- 1 See tables on Sheet ITS(4) for values of dimension variables.
 - 2 See lap joint note for 55' and 60' pole heights on ITS(4) at the bottom of each table.


**ITS POLE DETAILS
 OCTAGONAL POLE
 (EIGHT SIDED POLE)**

ITS(1)-15


FILE: its(1)-15.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	52	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/29/2021 1:17:51 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\ITS(3)-16.dgn




Top and Bottom Template (Four Bolt)
Detail A




Top and Bottom Template (Six Bolt)
Detail B




Top and Bottom Template (Eight Bolt)
Detail C



Foundation Details (Typical)
Elevation
 Not to Scale



Top and Bottom Template (Twelve Bolt)
Detail D



Anchor Bolt Detail
Detail D

- General Notes:**
1. Drilled shaft concrete shall be Class "C" (f_c = 3,600 PSI) in accordance with Item 416, "Drilled Shaft Foundations."
 2. Reinforcing bars shall be Grade 60 (F_y = 60 KSI) and conform to ASTM A-615. All reinforcing shall conform to Item 440, "Reinforcing Steel."
 3. Provide ASTM A-36 steel for templates. Top and bottom templates need not be galvanized.
 4. Anchor bolts shall be rigidly held in position during concrete placement using steel templates at the top and bottom. Top templates shall remain in place until the concrete has cured in place beyond initial set time.
 5. Lubricate and tighten anchor bolts, when erecting pole, in accordance with Item 449, "Anchor Bolts."
 6. Anchor bolts shall conform to ASTM F1554 Grade 55, or ASTM A193 B7 with ASTM A194 Grade 2H or A563 heavy hex nuts with F436 washers. Galvanize a minimum of the top end thread length plus 6 inches for all anchor bolts unless otherwise noted. Exposed washers and exposed nuts shall be galvanized. All galvanizing shall be in accordance with Item 445, "Galvanizing."
 7. All vertical reinforcement shall be carried to the bottom of the drilled shaft.
 8. Place three flat turns of the spiral bar at the top and one flat turn at the bottom of the drilled shaft.
 9. Drilled shaft shall be measured by the linear foot and paid under Item 416, "Drill Shaft Foundations."
 10. If rock is encountered, the drilled shaft to extend a minimum of two diameters into solid rock.
 11. Location for conduit entering foundation may vary. Orient conduit entering foundation to coincide with location of ground boxes and primary ground rod.
 12. Bond anchor bolts to rebar with #2/0 AWG jumper and two mechanical connectors or by bending No. 3 bar on bottom template as shown and wire tightly with ten turns of No. 10 wire or one mechanical connector. Mechanical connectors shall be UL Listed for concrete encasement.

Reference Notes:

1. See tables on Sheet ITS(4) for values of dimension variables.

Texas Department of Transportation

Traffic Operations Division Standard


ITS POLE FOUNDATION DETAILS

ITS(3) - 16

FILE: its(3)-16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
April 2016	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	53	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:54 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\its(15)-15.dgn




Pole Mounted Cabinet - Type 2 Front View

Not to Scale



Pole Mounted Cabinet - Type 2 Side View


Not to Scale



Note:
 ITS Pole May be Round, Octagonal (8 Sided), or Dodecahedron (12 Sided).
 See ITS(1), and ITS(2) for Details.


Mounting Bracket Detail

Not to Scale



Interior - Type 2 Without 19" EIA Rack - Front View

Not to Scale





Interior - Type 2 With 19" EIA Rack - Front View

Not to Scale

Typical Equipment Layout Legend	
Example Equipment	
①	CCTV Interface Panel, Radar Vehicle Sensing Device (RVSD) Equipment, DMS/LCS Controller, Environmental Sensor Station (ESS) Equipment, Bluetooth Equipment, or ITS Radio Equipment (See General Note 1)
②	Ethernet Switch, Video Encoder, Terminal Server, Fiber Optic Transceivers, or Media Conversion Equipment (See General Note 1)
③	Power Distribution Assembly, Service Entrance Breakers, Primary AC Power, Auxiliary Power Strip, Ground Bus Bar, Surge Protection Equipment

General Notes:

- Layout of hardware equipment and configuration shown is diagrammatic in nature and intended to represent a preferred Type 2 pole mounted cabinet setup. Hardware needed for each Type 2 cabinet varies and not all cabinet equipment may be shown. The contractor will be responsible for configuring cabinets with all appropriate ITS hardware and power supplies in accordance with the plans and specifications. The contractor may alter the cabinet configuration shown to maximize space and ensure easy access for maintenance.
- Mount cabinet as detailed on ITS(15) or ITS(17). Orientation of cabinet on ITS pole may vary depending on field conditions. Mount the pole mounted cabinet to the backside of the ITS pole, to allow maintenance personnel to access the cabinet while being able to view oncoming traffic.
- For ITS pole sites located on slopes greater than 4H:1V, mount the cabinet to the backside of the ITS pole as detailed on ITS(7). Mounting height to accommodate maintenance pad for easy access.
- All dimensions are approximate and represent minimum cabinet dimensions.
- Provide conduit entrances at the bottom of the cabinet.
- Paid under Special Specification "ITS Pole with Cabinet" (Configuration 1) without 19" EIA rack.
 Paid under Special Specification "ITS Pole with Cabinet" (Configuration 2) with 19" EIA rack.



Orientation of Type 2 Cabinet on ITS Pole (Typical)

Not to Scale

Texas Department of Transportation
 Traffic Operations Division Standard








ITS POLE MOUNTED CABINET TYPE 2 DETAILS

ITS(15)-15

FILE: its(15)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
DIST	COUNTY		SHEET NO.	
BMT	JEFFERSON		55	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:56 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\its(24)-15.dgn



Solar Panel Mounting Table


Dimension	Distance/Angle
S1	= D x (sin(S3)) + 4 (in.)
S2	= D x (sin(S3)) x (tan(S3)) (in.)
S3	= 90 deg. - S4 (zenith angle)
S4	Variable

S1 = Panel offset
 S2 = Optimum vertical clearance between panels (in.)
 S3 = Tilt angle (degrees), also sun elevation from horizon
 S4 = Sun zenith angle (degrees) oriented for maximum exposure per National Renewable Energy Laboratory (NREL)
 D = Depth of panel (in.)

Solar Panel Matrix Table *

Wind Zone (MPH)	Pole Height (FT)	Stiffeners	Max. No. of Solar Panels	Max. Height of Upper Solar Panel (FT)
90 or 110	20	Not Included	1	15
90 or 110	30-60	Not Included	2	20
90 or 110	30	Included	3	25
90 or 110	40-60	Included	4	30
130	20-60	Not Included	1	15
130	30-60	Included	3	25

* - ITS pole height less than 20 ft. have not been designed to support solar panels



General Notes:

- Orient photovoltaic module (Pv) for optimum exposure to sunlight (face to the south) per National Renewable Energy Laboratory (NREL) guidelines. Prior to installation, check the location to ensure there is no overhead obstruction that would block the Photovoltaic Module from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- When required for batteries to be installed in a battery ground box, place the batteries on a 3/16" thick plastic sheet and connect batteries together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and thick plastic sheet will be subsidiary to special specification "ITS Solar Power System."
- When required for batteries to be installed in an pole mounted cabinet, wire batteries according to manufacturer's recommendations. Provide the number of batteries as required by the manufacturer. Stack the batteries in the cabinet on shelves with 1" vertical separation.
- See Electrical Details (ED) standard sheets for additional requirements regarding the installation of ground boxes/battery boxes, and conduit.
- Use materials specifically designed for attaching cabinets, photovoltaic modules, etc., to poles.
- See special specification "ITS Solar Power System" for further requirements.
- When provisioned in the plans, solar controller and batteries are permitted to be installed along with ITS equipment inside ITS pole mounted cabinet for new installations. For existing conditions, solar controller and batteries are permitted if spare capacity exists. Engineer to verify existing cabinet type and spare capacity before sizing solar power system.
- Pv = Photovoltaic
- See sheets ITS(1), ITS(2), and ITS(4) "ITS Pole Details" for further information regarding the ITS pole assembly.
- Use hardware specifically designed for attaching equipment (i.e., cabinet, photovoltaic module, etc.) to pole as recommended by equipment manufacturer. Provide mounting details for approval.

Texas Department of Transportation
 Traffic Operations Division Standard

ITS SOLAR POWER SYSTEM POLE MOUNTING DETAILS

ITS(24)-15


FILE: its(24)-15.dgn DWN: TxDOT CK: TxDOT DW: TxDOT CK: TxDOT

© TxDOT June 2015 CONT: 0028 SECT: 13 JOB: 141 HIGHWAY: IH-10








REVISIONS: DIST: BMT COUNTY: JEFFERSON SHEET NO.: 56

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:58 PM
 FILE: T:\BMT\TRAFC\Wrong_Way_Driving\CSJ_0028-13-141\STANDARDS\ITS(25)-15.dgn



Detail For Photovoltaic Module, Cabinet, and Batteries Located Out of Clear Zone on Aluminum Pole
 Not to Scale



General Notes:

- Orient photovoltaic module for optimum exposure to sunlight (face to the south) per National Renewable Energy Laboratory (NREL) guidelines. Prior to installation, check the location to ensure there is no overhead obstruction that would block the Photovoltaic Module from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- When required for batteries to be installed in a battery ground box, place the batteries on a 3/16" thick plastic sheet and connect batteries together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and 3/16" thick plastic sheet will be subsidiary to special specification "ITS Solar Power System."
- When required for batteries to be installed in an pole mounted cabinet, wire batteries according to manufacturers recommendations. Provide the number of batteries as required by the manufacturer. Stack the batteries in the cabinet on shelves with 1" vertical separation.
- See Electrical Details (ED) standard sheets for additional requirements regarding the installation of ground boxes/battery boxes, and conduit.
- Use materials specifically designed for attaching cabinets, photovoltaic modules, etc., to poles.
- See special specification "ITS Solar Power System" for further requirements.
- See plans for electrical conductor circuit size from solar cabinet to ITS pole mounted cabinet. Circuit to be designed based off of ITS equipment design load and allowable 5% voltage drop over distance from the solar assembly to ITS cabinet.
- Provide pedestal pole assembly in accordance with Item 687. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 aluminum pipe, ASTM B429 or B221 (alloy 6061-T6 only). Aluminum conduit will not provide the necessary strength and will not be allowed.
- Use either a screw-in type anchor foundation or a drilled shaft foundation as identified in the plans. When plans require a drilled shaft foundation, construct in accordance with Item 416 and standard sheet TS-FD. Install the screw-in type anchor foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-in shaft foundation will be subsidiary to special specification "ITS Solar Power System."
- If more than 2 photovoltaic modules are needed, a second pedestal pole assembly may be required.
- See sheets ITS(1)-15, ITS(2), and ITS(4) "ITS Pole Details" for further information regarding the steel ITS pole assembly.
- Pv = Photovoltaic
- Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening at connection.
- Use hardware specifically designed for attaching equipment (i.e., cabinet, photovoltaic module, etc.) to pole as recommended by equipment manufacturer. Provide mounting details for approval.

Texas Department of Transportation
 Traffic Operations Division Standard


ITS SOLAR POWER SYSTEM ALUMINUM POLE MOUNTING DETAILS

ITS (25) - 15

FILE: its (25) - 15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	57	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:17:59 PM
 FILE: T:\BMT\TRAFFIC\Wrong Way Driving\CSJ_0028-13-141\STANDARDS\its(26)-15.dgn









Solar Panel Mounting Table	
Dimension	Distance/Angle
S1	= $D \times (\sin(S3)) + 4$ (in.)
S2	= $D \times (\sin(S3)) \times (\tan(S3))$ (in.)
S3	= 90 deg. - S4 (zenith angle)
S4	Variable

S1 = Panel offset
 S2 = Optimum vertical clearance between panels (in.)
 S3 = Tilt angle (degrees), also sun elevation from horizon
 S4 = Sun zenith angle (degrees) oriented for maximum exposure per National Renewable Energy Laboratory (NREL)
 D = Depth of panel (in.)

Detail For Photovoltaic Module, Cabinet, and Batteries Located Out of Clear Zone on Timber Pole
 Not to Scale

General Notes:

- Orient photovoltaic module for optimum exposure to sunlight (face to the south) per National Renewable Energy Laboratory (NREL) guidelines. Prior to installation, check the location to ensure there is no overhead obstruction that would block the Photovoltaic Module from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- When required for batteries to be installed in a battery ground box, place the batteries on a 3/16" thick plastic sheet and connect batteries together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and 3/16" thick plastic sheet will be subsidiary to Special Specification "ITS Solar Power System."
- When required for batteries to be installed in an pole mounted cabinet, wire batteries according to manufacturer's recommendations. Provide the number of batteries as required by the manufacturer. Stack the batteries in the cabinet on shelves with 1" vertical separation.
- See Electrical Details (ED) standard sheets for additional requirements regarding the installation of ground boxes/battery boxes, and conduit.
- Use materials specifically designed for attaching cabinets, photovoltaic modules, etc., to poles.
- See Special Specification "ITS Solar Power System" for further requirements.
- See plans for electrical conductor circuit size from solar cabinet to ITS pole mounted cabinet. Circuit to be designed based off of ITS equipment design load and allowable 5% voltage drop over distance from the solar assembly to ITS cabinet.
- Provide 20' or 40' in length ANSI 05-1 Class 5 timber poles treated per Item 627, "Treated Timber Poles". Install pole as shown or at the edge of the Right of Way. If more than two photovoltaic modules are needed provide the taller timber pole. Timber pole will be subsidiary to Special Specification "ITS Solar Power System."
- Use materials specifically designed for attaching cabinets, photovoltaic modules, etc., to poles.
- See sheets ITS(1), ITS(2), and ITS(4) "ITS Pole Details" for further information regarding the steel ITS pole assembly.
- Pv = Photovoltaic
- Use hardware specifically designed for attaching equipment (i.e., cabinet, photovoltaic module, etc.) to pole as recommended by equipment manufacturer. Provide mounting details for approval.



Explanation of ITS Solar Power System Descriptive Code

SPS X (X W) X W (X AH) X x X A₁ X₂ X₃ X₄ X₅ X₆ X₇

Construction Application
 INS = Install
 REM = Remove
 REL = Relocate

Total System Load Capacity (Watts)
 Total Solar Panel Capacity (Watts)
 Total Battery Capacity (Amp Hours)
 No. of Charge Controllers (EA) x Amperage Capacity of Each (Amps)
 Cabinet Installation Type
 1 = ITS Pole Mounted Cabinet (Type 1, 2, or 3)
 2 = Manufacturer Supplied on Pedestal Pole
 3 = Manufacturer Supplied on Timber Pole


Example: SPS INS (60W) 1440W (750AH) 3x50A (1)

Texas Department of Transportation
 Traffic Operations Division Standard

**ITS SOLAR POWER SYSTEM
 WOOD POLE MOUNTING
 DETAILS**

ITS(26) - 15

FILE: its(26)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	13	141	IH-10
DIST	COUNTY		SHEET NO.	
BMT	JEFFERSON		58	



NOTES:

1. FOR INSTALLATION LOCATIONS, SEE PLAN SHEETS.
2. ORIENTATION OF THE THERMAL AND CCTV CAMERAS MAY VARY BY LOCATION. SEE PLAN SHEETS FOR DETAILS. THERMAL CAMERA SHALL BE FACING I-35 OFF RAMP. QUANTITY OF THERMAL AND CCTV MAY VARY BY PROVIDER AND LOCATION.
3. REFER TO STANDARD SHEET TS-FD FOR ADDITIONAL FOUNDATION DETAILS.
4. SEE ITEM 687, "PEDESTAL POLE ASSEMBLIES" FOR FURTHER REQUIREMENTS.
5. PER MANUFACTURER'S RECOMMENDATIONS, ENGAGE ALL THREADS ON THE PEDESTAL POLE BASE AND PIPE UNLESS THE PIPE IS FULLY SEATED INTO BASE. USE A POLE AND BASE COLLAR ASSEMBLY TO ADD STRENGTH AND PREVENT LOOSENING ON CONNECTION.
6. SEE STANDARD SHEET ELECTRICAL DETAILS (ED) FOR ADDITIONAL REQUIREMENTS REGARDING THE INSTALLATION OF CONDUITS, CONDUCTORS, AND CABINETS.
7. UNLESS OTHERWISE SHOWN ON THE PLANS, POLE SHAFT SHALL BE ONE PIECE, SCHEDULE 40 ALUMINUM PIPE, ASTM B429 OR B221 (ALLOY 6061-T6 ONLY). ALUMINUM CONDUIT WILL NOT DEVELOP THE NECESSARY STRENGTH AND WILL NOT BE ALLOWED.
8. ENSURE HEIGHT OF CONDUIT IS BELOW TOP OF ANCHOR BOLTS.
9. INSTALL BATTERIES IN THE CABINET. WIRE BATTERIES ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.

DocuSigned by:
Peter Jungen 11/30/2021
 3BD0FB8D3639461...
 NAME DATE



IH-10

**DETECTOR POLE
 MASTER DETAIL**

**WWD ASSEMBLY MASTER DETAIL
 DETECTOR POLE TYPICAL
 N. T. S**

NOT TO SCALE



© 2021 Texas Department of Transportation

STATE		COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10

FILE: T:\BMTTRAFIC\Wrong Way Driving\CSJ 0028-13-141\DGNS\DETECTOR POLE MASTER DETAIL.dgn
 DATE: 11/29/2021 1:18:02 PM

NOTES:

1. DETAILS SHOW A TYPICAL LED WRONG WAY SIGN WITH A SOLAR POWER INSTALLATION.
2. FOR SIGN INSTALLATION LOCATIONS, SEE PLAN SHEETS.
3. WHEN THE SHOULDER IS 6' OR LESS IN WIDTH, THE SIGN MUST BE PLACED AT LEAST 12' FROM THE EDGE OF THE TRAVEL LANE. WHEN THE SHOULDER IS GREATER THAN 6' IN WIDTH, THE SIGN MUST BE PLACED AT LEAST 6' FROM THE EDGE OF THE SHOULDER.
4. SEE SMD STANDARD SHEETS FOR LATERAL AND VERTICAL CLEARANCES AND SIGN MOUNTING DETAILS. INSTALL SIGNS AS SHOWN ON THE PLAN SHEETS.
5. ORIENT SOLAR PANEL FOR OPTIMUM EXPOSURE TO SUNLIGHT (FACE TO THE SOUTH). PRIOR TO INSTALLATION, CHECK THE LOCATION TO ENSURE THERE IS NO OVERHEAD OBSTRUCTION THAT WOULD BLOCK THE SOLAR PANEL FROM RECEIVING FULL SUNLIGHT. UNLESS SPECIFIED ELSEWHERE, MOUNT A MINIMUM OF 14' ABOVE GRADE.



WWD "P" POST DETAIL
N. T. S

DocuSigned by:
Peter Jungen 11/30/2021
3BD0FB8D3636401
NAME DATE



IH-10
"P" POST DETAIL

NOT TO SCALE

© 2021 Texas Department of Transportation


SHEET 1 OF 1

FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.
TEXAS	BMT	60
CONTROL	SECTION	JOB
0028	13	141
		HIGHWAY NO.
		IH-10


FILE: T:\BMTTRAF\Wrong Way Driving\GSJ 0028-13-141\DGNS\POST DETAIL.dgn
DATE: 11/29/2021 1:18:03 PM

NOTES:


1. DETAILS SHOW A TYPICAL LED WRONG WAY SIGN WITH A SOLAR POWER INSTALLATION.
2. FOR SIGN INSTALLATION LOCATIONS, SEE PLAN SHEETS.
3. WHEN THE SHOULDER IS 6' OR LESS IN WIDTH, THE SIGN MUST BE PLACED AT LEAST 12' FROM THE EDGE OF THE TRAVEL LANE. WHEN THE SHOULDER IS GREATER THAN 6' IN WIDTH, THE SIGN MUST BE PLACED AT LEAST 6' FROM THE EDGE OF THE SHOULDER.
4. SEE SMD STANDARD SHEETS FOR LATERAL AND VERTICAL CLEARANCES AND SIGN MOUNTING DETAILS. INSTALL SIGNS AS SHOWN ON THE PLAN SHEETS.
5. ORIENT SOLAR PANEL FOR OPTIMUM EXPOSURE TO SUNLIGHT (FACE TO THE SOUTH). PRIOR TO INSTALLATION, CHECK THE LOCATION TO ENSURE THERE IS NO OVERHEAD OBSTRUCTION THAT WOULD BLOCK THE SOLAR PANEL FROM RECEIVING FULL SUNLIGHT. UNLESS SPECIFIED ELSEWHERE, MOUNT A MINIMUM OF 14' ABOVE GRADE.



FRONT VIEW



SIDE VIEW



REAR VIEW

DocuSigned by:
Peter Jungen 11/30/2021
 3BD0FB8D3636401
 NAME DATE



IH-10
EXISTING "T" POST DETAIL

NOT TO SCALE




FHWA TEXAS DIVISION		FEDERAL AID PROJECT NO.		SHEET NO.	
TEXAS		BMT		JEFFERSON	
CONTROL		SECTION		JOB	
0028		13		141	
				HIGHWAY NO.	
				IH-10	


WWD EXISTING "T" POST DETAIL
 N. T. S

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\EXISTING T POST DETAIL.dgn
 DATE: 11/29/2021 1:18:05 PM


- NOTES:
1. DETAILS SHOW A TYPICAL LED WRONG WAY SIGN WITH A SOLAR POWER INSTALLATION.
 2. FOR SIGN INSTALLATION LOCATIONS, SEE PLAN SHEETS.
 3. WHEN THE SHOULDER IS 6' OR LESS IN WIDTH, THE SIGN MUST BE PLACED AT LEAST 12' FROM THE EDGE OF THE TRAVEL LANE. WHEN THE SHOULDER IS GREATER THAN 6' IN WIDTH, THE SIGN MUST BE PLACED AT LEAST 6' FROM THE EDGE OF THE SHOULDER.
 4. SEE SMD STANDARD SHEETS FOR LATERAL AND VERTICAL CLEARANCES AND SIGN MOUNTING DETAILS. INSTALL SIGNS AS SHOWN ON THE PLAN SHEETS.
 5. ORIENT SOLAR PANEL FOR OPTIMUM EXPOSURE TO SUNLIGHT (FACE TO THE SOUTH). PRIOR TO INSTALLATION, CHECK THE LOCATION TO ENSURE THERE IS NO OVERHEAD OBSTRUCTION THAT WOULD BLOCK THE SOLAR PANEL FROM RECEIVING FULL SUNLIGHT. UNLESS SPECIFIED ELSEWHERE, MOUNT A MINIMUM OF 14' ABOVE GRADE.



FRONT VIEW



SIDE VIEW



REAR VIEW

DocuSigned by:
Peter Jungen
 NAME: 3DD0FB8D93636401... DATE: 11/30/2021



WWD EXISTING "P" POST DETAIL
 N. T. S

IH-10
EXISTING "P" POST DETAIL

NOT TO SCALE

© 2021 Texas Department of Transportation

STATE		COUNTY	
TEXAS	BMT	JEFFERSON	
CONTROL	SECTION	JOB	HIGHWAY NO.
0028	13	141	IH-10

FEDERAL AID PROJECT NO. SHEET NO. 62

FILE: T:\BMTTRAF\Wrong Way Driving\CSJ 0028-13-141\DGNS\EXISTING P POST DETAIL.dgn
 DATE: 11/29/2021 1:18:07 PM

SITE DESCRIPTION**Notes:**

- (1) The Site Description is accomplished using various sheets, each revealing separate details. This Index Sheet's purpose is to point the user to the appropriate location where the information required by the TPDES CGP can be found.
- (2) The project limits shown on the Title Sheet and limits of TxDOT Right Of Way shall also be the limits of coverage of the SW3P.

NATURE OF ACTIVITY: Install Wrong Way Driver TechnologyINTENDED SEQUENCE OF MAJOR SOIL DISTURBING ACTIVITIES: N/A

TOTAL AREA OF SITE: _____ AREA TO BE DISTURBED: _____

If area of disturbance can be expected to exceed 1.0 acres, Beaumont District Standard SW3P-B should be included in the plans.

PRE-CONSTRUCTION RUNOFF CO-EFFICIENT: N/APOST-CONSTRUCTION RUNOFF CO-EFFICIENT: N/AEXISTING SOIL DESCRIPTION: SILT LOAM, CLAY AND SANDY LOAMGENERAL LOCATION MAP: SEE TITLE SHEET AND LOCATION MAPRECEIVING WATERS: SEGMENT NUMBER 0601SEGMENT NAME NECHES RIVER TIDALLOCATION OF WETLAND OR SPECIAL AQUATIC SITES: N/ADRAINAGE PATTERNS: N/ATYPICAL AREAS OF SOIL DISTURBANCE: N/ATYPICAL AREAS WHICH WILL NOT BE DISTURBED: N/ALOCATION OF OFF-SITE SURFACE RECEIVING WATERS: N/ALOCATIONS WHERE STABILIZATION PRACTICES WILL OCCUR: N/ALOCATIONS OF OFF-SITE STORAGE OF MATERIALS AND EQUIPMENT, WASTE, BORROW;
OR DEDICATED MATERIAL PROCESSING PLANTS: N/A

LOCATIONS WHERE STORM WATER DISCHARGES TO SURFACE WATERS: _____

SAWPIT GULLY

LOCATION OF POLLUTION CONTROL MEASURES: N/A**CONTROLS****SOIL STABILIZATION PRACTICES****INTERIM:**

_____ TEMPORARY SEEDING * PRESERVATION OF NATURAL RESOURCES
 _____ MULCHING (Hay or Straw) _____ FLEXIBLE CHANNEL LINER
 _____ BUFFER ZONES _____ OTHER

PERMANENT:

_____ SEEDING _____ RETENTION BLANKET
 _____ BLOCK SOD _____ CHANNEL LINER
 _____ OTHER

STRUCTURAL PRACTICES (T/P) *

_____ SILT FENCE _____ PAVED FLUMES
 _____ HAY BALES _____ ROCK BEDDING AT CONSTRUCTION EXIT
 _____ ROCK BERMS _____ TIMBER MATTING AT CONSTRUCTION EXIT
 _____ PIPE SLOPE DRAINS _____ SEDIMENT TRAPS
 _____ CHANNEL LINERS _____ SEDIMENT BASINS
 _____ STORM SEWERS _____ CURB and GUTTER
 _____ STORM INLET SEDIMENT TRAP _____ VELOCITY CONTROL DEVICES
 _____ STONE OUTLET STRUCTURES _____ EROSION CONTROL LOGS
 _____ DIVERSION, INTERCEPTOR, or PERIMETER SWALES
 _____ DIVERSION, INTERCEPTOR, or PERIMETER DIKES

* T means Temporary - P means Permanent

PERMANENT POST CONSTRUCTION TSS CONTROLS

_____ RETENTION / IRRIGATION
 _____ EXTENDED DETENTION BASINS
 _____ VEGETATIVE FILTER STRIPS / VEGETATIVE SWALES
 _____ CONSTRUCTED WETLANDS
 _____ WET BASINS

OTHER CONTROLS

_____ WATERING FOR DUST CONTROLS
 _____ SEDIMENT REMOVAL FROM ROADWAY (SWEEPING)
 _____ LOADED TRUCKS WILL BE COVERED WITH TARP

The above indicated practices are proposed to control pollutants in storm water discharges. These practices are based on information contained in TxDOT Storm Water Management Guidelines. The Schedule of implementation of these practices will be based on the intended Sequence of Major Soil Disturbing Activities. Stabilization measures shall be initiated no later than 14 days after construction activity of that portion of the site has temporarily or permanently ceased.

Describe construction and waste materials expected to be stored on site and proposed controls to reduce pollutants from these materials (include storage practices spill prevention and response. ALL WASTE MATERIAL WILL BE DISPOSED OF IN ACCORDANCE WITH ALL STATE LAWS AND REGULATIONS. NO CONSTRUCTION WASTE MATERIAL WILL BE BURIED ON SITE. IN THE EVENT OF A SPILL WHICH MAY BE HADARDOUS, THE

SPILL COORDINATOR SHALL BE CONTACTED IMMEDIATELY.
 Describe pollutant sources from areas other than construction and measures implemented at those sites to minimize pollutant discharges. DISPOSAL AREA, STOCKPILES, AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT MAY ENTER RECEIVING WATER. TEMPORARY

STRUCTURAL CONTROLS MAY BE REQUIRED TO CONTROL POLLUTANTS.
 Describe measures necessary to protect listed endangered or threatened species, or critical habitat. N/A

INFORMATION**MAINTENANCE:**

All erosion and sediment control and other protective measures identified in the SW3P must be maintained in effective operating conditions. If site inspections required by this permit identify BMP's that are not operating effectively, maintenance shall be performed before the next anticipated storm event, or as necessary to maintain the continued effectiveness of storm water controls. If maintenance prior to the next anticipated storm event is unpracticable, maintenance must be scheduled and accomplished as soon as practical.

INSPECTION:

Qualified personnel shall inspect disturbed areas of the construction site that have not been finally stabilized, areas used for storage of materials that are exposed to precipitation, structural control measures, and locations where vehicles enter or exit the site.

Inspection Cycle Options:

1. At least every 14 calendar days or within 24 hrs after 0.5 inches or more of rainfall.
 2. At least every 7 calendar days.
 3. At least monthly (Engineer & DEQC approved revision to SW3P required).

a). Disturbed areas that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. Sediment and erosion control measures identified on the SW3P shall be observed to ensure that they are operating correctly. Locations where vehicles enter or exit the site shall be inspected for evidence of offsite sediment tracking. Sediments must be removed from sediment control structures no later than the time that the design capacity has been reduced by 50%.

b). Based on the result of the inspection, the SW3P shall be revised to include (show on Site Map) additional or modified BMP's designed to correct the observed deficiency. Revisions to the SW3P must be completed within seven (7) calendar days following the inspection.

c). A report summarizing the scope, date, name and qualifications of inspector, and major observations relating to the implementation of the SW3P shall be produced and retained as part of the SW3P for 3 years from date of final stabilization.

d). The following records must be maintained and either attached to or referenced in the SW3P, and made readily available upon request to the parties in Part III.D.1 of the CGP: 1). The dates when major grading activities occur; 2). The dates when construction activities temporarily or permanently cease on a portion of the site and; 3). The dates when stabilization measures are initiated.

INSPECTOR PAPERWORK CHECKLIST:

- Contact Form (1)
 Notice of Intent (1) (2)
 SW3P Certification Statement (signed by AE) (2)
 Delegation of Signature Authority (all Inspectors signing reports) (2) (3)
 TPDES General Permit (2) (3)
 Environmental Document (2)
 Inspection and Maintenance Report (2) (3)
 Notice of Termination (2)
 SW3P Plan (2) (3)
 Inspector Qualification Form (2) (3)
 Project Diary (2) (3)

- (1) The information should be displayed on the Project Bulletin Board.
 (2) The information should be a part of the permanent SW3P file maintained at the Area Office.
 (3) The information should be maintained at the Field Office.

STORM WATER POLLUTION PREVENTION PLAN is consistent with requirements specified in applicable sediment and erosion site plans or site permits, or storm water management site plans or site permits approved by State, Tribal or local officials (i.e. MS4 Permits).


Any reportable quantity of Hazardous Material release must be reported to the National Response Center at 1-800-424-8802. In addition the Beaumont District "Hazardous Material Spill Information Form" must be completed and mailed to the EPA Regional Office in Dallas, Tx.

A copy of the Construction General Permit is part of the SW3P.

DocuSigned by:

Peter Jungen 11/30/2021

3BD0FB8D3636401...




© 2021

Texas Department of Transportation
BEAUMONT DISTRICT**SW3P INDEX**
(SW3P-I)


REVISIONS	FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.
05/22/02 VW	6		63
11/08/02 VW			
03/06/03 VW			
06/11/04 VW			
09/15/15 MW			
STATE DIST. NO.		COUNTY	
TEXAS BMT		JEFFERSON	
CONT.	SECT.	JOB	HIGHWAY NO.
0028	13	141	IH-10

10/25/2021
 T:\BIBITRAFC\Wrong Way Driving\CSJ 0028-13-141\STANDARDS\ec116.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0028	13	141	IH-10	
	DIST	COUNTY		SHEET NO.	
	BMT	JEFFERSON		64	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/29/2021 1:18:11 PM
 FILE: T:\BMT\TRAFFIC\Wrong Way Driving\CSJ_0028-13-1-141\DGNS\EPIC.dgn

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. TxDOT - Beaumont District
 2. Cities of Baytown, Beaumont, Groves, Lumberton, Nederland, Orange, Port Arthur, Port Neches, and Vidor.
- No Action Required Required Action

Action No.

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
2. Comply with the SW3P and revise when necessary to control pollution or as required by the Engineer.
3. The project is estimated to involve less than one acre of soil disturbance. In the event the project disturbance acreage becomes equal to or greater than one acre, the CGP is applicable. Contact TxDOT project inspector for coordination with DEQC for necessary action.
4. Take measures to prevent construction materials and debris including, but not limited to wastewater (i.e., cooling liquid, etc.) associated with concrete removal from entering any inlets, ditches, or waterways.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions, including Regional conditions for the State of Texas, associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required: Permit # _____
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1. Maintain a neat and clean worksite next to the water and do not allow any debris to fall into the water.
2. Comply with "Work In or Near Waters/Wetlands Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	

III. CULTURAL RESOURCES

- No Action Required Required Action

Action No.

1. Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

IV. VEGETATION RESOURCES

- No Action Required Required Action

Action No.

1. No tree vegetation removal/trimming of any kind is allowed. Exceptions are allowed for mowed and maintained grass and landscaping.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required Required Action

Action No.

1. If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own.
2. If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEQC for guidance.
3. Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
4. Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and TPW Code Section 64.002. The full TxDOT MBTA guidance may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/toolkit/350-01-gui.pdf>
5. Roadside Appurtenance Maintenance Program BMPs from the Maintenance EA Best Management Practices Summary Report shall be reviewed and implemented where appropriate.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

- No Action Required Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances
- * Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
none				

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

Action No.

1. Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous materials or contamination is noted during construction.
2. Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action No.

1. Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.



ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC

APPROVED BY: Jason Lighttower DATE: 12/3/2021
 DISTRICT ENVIRONMENTAL DEPARTMENT

FILE: epic.dgn	DW: TxDOT	CK: AM	DW: VP	CK: AR
© TxDOT February 2019	CONT	SECT	JOB	HIGHWAY
	0028	13	141	IH-10
	DIST	COUNTY	SHEET NO.	
	BMT	JEFFERSON	65	