INDEX OF SHEETS

SHEET NO. DESCRIPTION

> TITLE SHEET INDEX OF SHEETS

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,

FEDERAL - AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY 2012).

NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, WILL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT: STP 2022(410) HES


CORYELL COUNTY

SH 36

CSJ 0184-01-065

LIMITS: AT FM 107

FOR THE CONSTRUCTION OF SAFETY CONSISTING OF INSTALL FLASHING BEACON



EXCEPTIONS: NONE

SCALE: I" = 2000.00'

EQUATIONS: NONE RR CROSSINGS: NONE

© 2022 by Texas Department of Transportation; all rights reserved.

FEDERAL AID PROJECT NO. STP 2022(410) HES SH 36 STATE DISTRICT SHEET NO. CHECK TEXAS WACO CORYELL CONTROL SECTION JOB CHECK 01 065 0184

YEAR	AADT
2020	12017
2040	16824

Texas Department of Transportation 12/29/2021

Jarod E. Johnson P.E.

Director of (rapeportation

12/29/2021 Approved for Le+DirouSigned by

Stanley Swiatek


SHEEI NO. DESCRIPTION

61

EPIC

```
GENERAL
            TITLE SHEET
            INDEX OF SHEETS
   2
   3, 3A-3C GENERAL NOTES
            ESTIMATE & QUANTITY
            CONSOLIDATED SUMMARIES
            SEQUENCE OF CONSTRUCTION
            IRAFFIC CONTROL STANDARDS
 7 - 18 *BC(1)-21 THROUGH BC(12)-21
   19
           * WZ (BTS-1)-13
   20
           * WZ (BTS-2) -13
   21
           * WZ (RS) -16
22 - 23 *TCP(1-1)-18 THROUGH TCP(1-2)-18
   24
          * TCP (1-4)-18
25 - 26 *TCP(2-1)-18 THROUGH TCP(2-2)-18
   27
           * TCP (2-4) -18
            IRAFFIC
   28
            EXISTING LAYOUT
   29
            PROPOSED FLASHING BEACON LAYOUT
   30
            TYPICAL SPAN WIRE
   31
            CONDUIT RUN AND SHEET SUMMARY
   32
            ELECTRICAL SERVICE DATA
            IRAFFIC SIANDARDS
   33
           *ED(1)-14
34 - 41 *ED(3)-14 THROUGH ED(10)-14
   42
           *RID(1)-20
43 - 44 *SP-80(1)-12 THROUGH SP-80(2)-12
   45
           * TS-FD-12
           * LUM-A-12
   46
   47
           * CFA-12
   48
           * TS-BP-20
            EROSION_CONTROL_STANDARDS
   49
            WACO DISTRICT STORM WATER POLLUTION PREVENTION PLAN (SW3P)
   - 59 *TA-BMP (WACO DISTRICT STANDARDS)
50
   60
           * EC(1)-16
```

* THE STANDARD SHEET SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY DIRECT SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



INDEX OF SHEETS

[®] Texas Department of Transportation

STATE DIST	CODIVIT	311221 1101
67175	COUNTY	SHEET NO.
6 0184 01	065	SH 36
HANGE ORDER FED. RD. CONT SECT	T JOB	HIGHWAY

HIGHWAY: SH 36 CSJ: 0184-01-065 HIGHWAY: SH 36 CSJ: 0184-01-065

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 0.00 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

There is a high probability that an environmentally sensitive area could be encountered on the contractor designated Project-Specific Locations (PSL) for this project (haul roads, equipment staging areas, borrow pits, disposal sites, field offices, storage areas, parking areas, etc.). Item 7.6 "Project-Specific Locations", provides a listing of regulatory agencies that may need to be contacted regarding this project.

Contractor questions on this project are to be emailed to the Waco District at the following address:

Bill Compton - Wacoprebid@txdot.gov, 254-867-2707, 100 S. Loop Dr., Waco, TX Carmen Chau - Wacoprebid@txdot.gov, 254-867-2794, 100 S. Loop Dr., Waco, TX

All contractor questions will be reviewed by the District Traffic Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

GENERAL NOTES

COUNTY: CORYELL

ITEM 4: SCOPE OF WORK

This project includes the construction of an intersection flashing beacon and safety lighting.

SHEET 3

ITEM 5: CONTROL OF THE WORK

Submit all fabrication and shop drawings per TxDOT's online shop drawing submittal system and copy the District Traffic Engineer on the email submittal, unless otherwise directed.

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (254)867-2808 for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (254)867-2726 for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

ITEM 6: CONTROL OF MATERIALS

References to manufacturer's trade name or catalog numbers are for the purpose of identification only and the contractor will be permitted to furnish like materials of other manufacturers provided they are of equal quality and comply with specifications for this project.

ITEM 7: LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

If utilizing private property for waste disposal sites, field office sites, equipment storage sites or for any other purpose involved with this project, provide to the Engineer written proof of the property owner's approval of the use of this property. This proof may be in the form of a letter or agreement signed by the property owner or other documents acceptable to the Engineer.

Personal vehicles of the contractor's employees will not be parked within the right of way at any time including any section closed to public traffic, unless the vehicle is being utilized for construction procedures. However, the contractor's employees may park on the right of way at the sites where the contractor has his office, equipment and materials storage yard.

GENERAL NOTES SHEET A GENERAL NOTES SHEET B

HIGHWAY: SH 36 CSJ: 0184-01-065

Law Enforcement Personnel.

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site. A minimum number of hours is not guaranteed. Payment is for work performed. If the Contractor has a field office, provide an office location for a supervisory officer when event requires a supervising officer. This work is subsidiary.

A maximum combined rate of \$65 per hour for the law enforcement personnel and the patrol vehicle will be allowed. Any scheduling fee is subsidiary per Standard Specification 502.4.2.

Cancel law enforcement personnel when the event is canceled. Cancellation, minimums or "show up" fees will not be paid when cancellation is made 12 hours prior to beginning of the event. Failure to cancel within 12 hours will not be cause for payment for cancellation, minimums, or "show up" time. Payment of actual "show up" time to the event site due to cancellation will be on a case-by-case basis at a maximum of 2 hours per officer.

Alterations to the cancellation and maximum rate must be approved by the Engineer or pre-determined by official policy of the officers governing authority.

ITEM 8: PROSECUTION AND PROGRESS

The 90-Day Delay Start provision is included for material acquisition.

This Project will be a Standard Workweek in accordance with Article 8.3.1.4.

For this project, provide a Bar Chart progress schedule.

ITEM 500: MOBILIZATION

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

COUNTY: CORYELL SHEET 3A

HIGHWAY: SH 36 CSJ: 0184-01-065

ITEM 502: BARRICADES, SIGNS, AND TRAFFIC HANDLING

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times.

Provide written proposed lane closure information by 1:00 pm on the business day prior to the proposed closures. Do not close lanes when this requirement is not met.

When excavation is required next to a pavement lane carrying traffic and the widening is not completed by the end of the work day, backfill against the edge of the pavement with at least a 3:1 slope using an acceptable material to support vehicular traffic. Carefully remove and dispose of this material when work resumes. Backfilling pavement edges, and the materials required for the work will be subsidiary to this item.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

As approved by the Engineer, provide uniformed off duty police officers and squad cars during lane or ramp closures or other situations that indicate a need for additional traffic control to protect the traveling public or the construction workforce. Provide documentation such as payroll, log sheets with signatures and badge number, or invoices from the government entity providing the officers for reimbursement. Complete the weekly tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Reimbursement will not be made for coordination fees charged by any party.

The Contractor Responsible Person(s) (CRP) for Work Zone Traffic Controls will inspect and ensure any deficiencies are corrected each and every day throughout the duration of this contract. Any misaligned or damaged traffic control devices will be repaired as soon as practical after deficiency is discovered.

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee(s) available to respond on the project for emergencies and for taking corrective measures within One (1) Hour.

GENERAL NOTES SHEET C GENERAL NOTES SHEET D

HIGHWAY: SH 36 CSJ: 0184-01-065

Traffic Control Plans with Lane Closures causing backups of 20 minutes or greater in duration will be modified by the Engineer.

ITEM 506: TEMPROARY EROSION, SEDIMENTATION AND ENVIRONMENTAL CONTROLS

Take all practicable precautions to prevent debris from being discharged into the Waters of Texas or a designated wetland. Install Best Management Practices before demolition begins and maintain them during the demolition. Remove any debris or construction material that escapes containment devices and are discharged into the restricted areas, before the next rain event or within 24 hours of the discharge.

Leave all right of way areas undisturbed until actual construction is to be performed in said areas.

No soil disturbing activities will begin on any section of TxDOT ROW without adequate sedimentation controls first being installed and functioning at adjacent drainage outfalls. Begin and continuously prosecute the repairs, additions and maintenance of erosion and sedimentation control devices within seven days after the Contractor receives each Form 2118, Field Inspection and Maintenance Report, from the Engineer. Failure of the Contractor to fulfill either of the above requirements places TxDOT in potential non-compliance with permit requirements and may result in withholding estimates or stopping work or both until all environmental permit requirements are fulfilled.

Concrete Washouts are required per the CGP. The Concrete Washout Area(s) structural controls must consist of temporary berms, temporary shallow pits, and/or temporary storage tanks to prevent contaminated runoff and must be lined as to prevent contamination of underlying soil. Ensure pits properly maintained including removal of concrete as not to allow overflow. The location(s) of washout area will be approved by the Engineer. When washout pits are no longer needed, they will be removed, and area will be restored to original condition. This work, materials and labor will not be measured or paid for directly but will be subsidiary to Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls."

Cleaning and sweeping of open roadways due to material spillage or loss from Contractor equipment or tires will be the responsibility of the Contractor at no cost to TxDOT. This work will not be charged as Item 738, "Cleaning and Sweeping Highways". Cleaning and sweeping of roadways will be completed as directed, including multiple times per day if necessary, to maintain acceptable roadways for the traveling public and to meet environmental regulations. Construction activities will cease when material deposited on the roadway is not properly removed or when equipment is not available as needed.

COUNTY: CORYELL SHEET 3B

HIGHWAY: SH 36 CSJ: 0184-01-065

Adequate construction exits will be planned, constructed and maintained by the Contractor per Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls".

ITEM 618: CONDUIT

The locations of conduit as shown are for diagrammatic purposes only and may be varied to meet local conditions, subject to approval.

When backfilling bore pits, ensure that the conduit does not become damaged during installation or due to any settling of the backfill material. Compact select backfill in three equal lifts to the bottom of the conduit or if sand is used, place to a point two (2) inches above the conduit. Backfill density will be equal to the existing soil. Be careful to prevent any material from entering the conduit.

Backfill all open trenches before the end of the workday and do not leave any trench open overnight.

ITEM 620: ELECTRIAL CONDUCTORS

Place the communications and/or coaxial cables in a separate conduit from the 120 or 240-volt electrical conductors.

Any damage to any wire or any cable is cause for immediate rejection of the entire cable being tested. Remove and replace the entire cable at the Contractor's expense.

For both transformer and shoe-base type illumination poles, provide double-pole breakaway fuse holder from manufacturers pre-qualified by the Traffic Operations Division.

Provide ten (10) amp time delay fuses.

ITEM 624: GROUND BOXES

Ground box locations shown on the plans are approximate locations. Actual locations are as directed.

GENERAL NOTES SHEET E GENERAL NOTES SHEET F

HIGHWAY: SH 36 CSJ: 0184-01-065

ITEM 628: ELECTRICAL SERVICES

Contact the Electric Utility Company to make all necessary arrangements to provide electrical service shown on the plans in accordance with Article 628.5 and the Electrical Details, except that TxDOT will make application to the Electric Utility Company for service (See note below).

NOTE:

Before fabricating the electrical service, contact the Waco District Traffic Signal Service Supervisor (Phone (254) 867-2807), to make application (billing arrangements) for service with the Electric Utility Company.

Furnish and install a lock on all electrical services. The lock is to be a Master-Lock number 2195.

The proposed electrical service location will be approved by TxDOT prior to installation.

ITEM 656: FOUNDATIONS FOR TRAFFIC CONTROL DEVICES

Locations shown on the plans are for diagrammatic purposes only and may be varied to meet local conditions, subject to approval. Stake these locations and have them approved before installation of foundations.

Consult with the Engineer to ensure proper location and orientation of the beacon controller before construction.

Backfill all open foundation holes before the end of the workday and do not leave any holes open overnight.

Clean up and remove from all work areas all loose material resulting from contract operations each day before suspending work for the day.

ITEM 682: VEHICLE AND PEDESTRAIN SIGNAL HEADS

Provide new signal head housings with black aluminum housings and back plates.

Cover all signal heads installed, but not in operation, in an approved manner from the time of installation until the signal is placed in operation. This will not be paid for directly, but will be subsidiary to Item 682, "Vehicle and Pedestrian Signal Heads".

Provide and install standard detachable tunnel visors on all signal heads. Provide and install all necessary mounting hardware to insure proper mounting of all signal heads. The mounting hardware and attachments will be new (no reuse of old existing attachment hardware) and the same color as the signal head housings. Use signal heads made of aluminum with 12 inch LED indications and aluminum back plates.

Ensure that each signal head has a minimum vertical clearance of 18.5 feet and a maximum vertical clearance of 19 feet between the bottom edge of the signal head and the surface of the roadway.

COUNTY: CORYELL SHEET 3C

HIGHWAY: SH 36 CSJ: 0184-01-065

ITEM 6185: TRUCK MOUNTED ATTENUATORS

The total number of truck mounted attenuators (TMA) required when utilizing the traffic control standards are shown in the tables below.

TCP 1 Series	Scenario	Required TMA
(1-1)-18 / (1-2)-18		1
(1-4)-18		1

TCP 2 Series	Scenario	Required TMA
(2-1)-18 / (2-2)-18 / (2-4)-18	All	1

Shadow vehicles equipped for truck mounted attenuators (TMA) for stationary operations will be paid for by the day and must be available for use at any time as determined by the Engineer.

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA needed for the project for those times per plan requirements. Additional TMAs used that are not specified in the plans in which the contractor expects compensation will require prior approval from the Engineer.

GENERAL NOTES SHEET G GENERAL NOTES SHEET H



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0184-01-065

DISTRICT Waco HIGHWAY SH 36 **COUNTY** Coryell

Report Created On: Dec 27, 2021 8:41:22 AM


		CONTROL SECTION	N JOB	0184-0	L-065		
		PROJI	ECT ID	A00004	1904		
		cc	DUNTY	TY Coryell		TOTAL EST.	TOTAL FINAL
		HIG	HWAY	SH 3	36		
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	416-6004	DRILL SHAFT (36 IN)	LF	24.000		24.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	2.000		2.000	
	618-6029	CONDT (PVC) (SCH 40) (3")	LF	188.000		188.000	
	620-6007	ELEC CONDR (NO.8) BARE	LF	338.000		338.000	
	620-6008	ELEC CONDR (NO.8) INSULATED	LF	1,052.000		1,052.000	
	624-6010	GROUND BOX TY D (162922)W/APRON	EA	1.000		1.000	
	625-6003	ZINC-COAT STL WIRE STRAND (3/8")	LF	300.000		300.000	
	628-6145	ELC SRV TY D 120/240 060(NS)SS(E)SP(O)	EA	1.000		1.000	
	680-6001	INSTALL HWY TRF SIG (FLASH BEACON)	EA	1.000		1.000	
	682-6003	VEH SIG SEC (12")LED(YEL)	EA	4.000		4.000	
	682-6005	VEH SIG SEC (12")LED(RED)	EA	2.000		2.000	
	682-6021	BACK PLATE (12")(1 SEC)	EA	6.000		6.000	
	684-6008	TRF SIG CBL (TY A)(12 AWG)(3 CONDR)	LF	123.000		123.000	
	686-6020	INS TRF SIG PL AM (S)STR(TY D)LUM	EA	2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY	30.000		30.000	
	18	LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Waco	Coryell	0184-01-065	4


SUMMARY OF TRAFFIC ITEMS							
	416-6004	618-6029	620-6007	620-6008	624-6010	625-6003	628-6145
				ELEC CONDR	GROUND BOX	ZINC-COAT	ELC SRV TY D
LOCATION	DRILL SHAFT	CONDT (PVC)	ELEC CONDR	(NO.8)	TY D (162922)	STL WIRE STRAND	120/240 060
	(36 IN)	(SCH 40) (3")	(NO.8) BARE	INSULATED	W/APRON	(3/8")	(NS) SS (E) SP (O)
	LF	LF	LF	LF	EA	LF	EA
SH 36 at FM 107	24	188	338	1052	1	300	1
PROJECT TOTALS	24	188	338	1052	1	300	1

SUMMARY OF TRAFF	IC ITEMS CONT.						
	680-6001	682-6003	682-6005	682-6021	684-6008	686-6020	6185-6002
	INSTALL HWY	VEH SIG SEC	VEH SIG SEC		TRF SIG CBL	INS TRF SIG	
LOCATION	TRF SIG	(12 IN) LED	(12 IN) LED	BACK PLATE	(TY A) (12 AWG)	PL AM (S) STR	TMA
	(FLASH BEACON)	(YEL)	(RED)	(12 IN) (1 SEC)	(3 CONDR)	(TY D) LUM	(STATIONARY)
	EA	EA	EA	EA	LF	EΑ	DAY
SH 36 at FM 107	1	4	2	6	123	2	30
PROJECT TOTALS	1	4	2	6	123	2	30



CONSOLIDATED SUMMARIES

HANGE ORDER	FED.RD. DIV. NO.	CONT	SECT JOB		H	HIGHWAY
	6	0184	01	065	•	SH 36
	STATE	DIST	COUNTY SHI		SHEET NO.	
	TEXAS	WAC	CORYELL		5	



VICINITY MAP

NOTES:


- I. ALL TRAFFIC CONTROL DEVICES WILL
 CONFORM WITH THE TEXAS "MANUAL ON
 UNIFORM TRAFFIC CONTROL DEVICES FOR
 STREETS AND HIGHWAYS" (TMUTCD), AND
 WILL BE MAINTAINED AS DIRECTED.
 ADDITIONAL GUIDELINES FOR TRAFFIC
 CONTROL DEVICES MAY BE FOUND IN THE TMUTCD.
- FOR CHANNELING DEVICE PLACEMENT AND SPACING FOR ALL PHASES, REFER TO THE TCP STANDARDS.
- 3. SIGNS G20-IT WITH PLAQUE OR G20-5T, G20-6, G20-2a, G20-2b, CW20-ID, R20-3, R20-5, G20-9T AND R20-5 PLAQUE WILL BE REQUIRED AT PROJECT LIMITS.
- 4. CW20-ID AND G20-20 WILL BE REQUIRED AT ALL CROSSROADS.
- 5. G20-Ia WILL BE REQUIRED AT ALL MAJOR CROSSROADS.

GENERAL

- A. INSTALL ALL SIGNS, BARRICADES AND TRAFFIC CONTROL DEVICES AS SHOWN AND IN ACCORDANCE WITH THE STANDARD BC SHEETS AND AS DIRECTED.
- B. ADDITIONAL SIGNS, BARRICADES OR TRAFFIC CONTROL DEVICES OTHER THAN THOSE SPECIFIED MAY BE REQUIRED FOR THE SAFE MOVEMENT OF TRAFFIC THROUGH THE PROJECT. PAYMENT FOR ALL SUCH SIGNS, BARRICADES OR TRAFFIC CONTROL DEVICES WILL BE CONSIDERED SUBSIDIARY TO THE ITEM "BARRICADES, SIGNS AND TRAFFIC HANDLING".
- C. WORK SITES SHOULD BE CAREFULLY MONITORED TO ENSURE THAT TRAFFIC CONTROL MEASURES ARE OPERATING EFFECTIVELY AND THAT ALL DEVICES USED ARE CLEARLY VISIBLE, CLEAN AND IN GOOD REPAIR.
- D. THE CONTRACTOR WILL PROVIDE SAFE ACCESS TO AND FROM ALL PRIVATE PROPERTY AT ALL TIMES AND IN ALL WEATHER CONDITIONS.
- E. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK PRIOR TO THE BEGINNING OF CONSTRUCTION WHICH GENERALLY CONFORMS TO THE SEQUENCE SHOWN ON THE TCP SEQUENCE OF OPERATION BELOW.
- F. COMPLETE ALL WORK ON PROJECT AS SHOWN ON THE VARIOUS PLAN SHEETS AND IN COMPLIANCE WITH THE GENERAL NOTES OF THIS CONTRACT.
- G. ANY REQUEST TO ALTER THE SEQUENCE OF OPERATION OR TRAFFIC CONTROL PLAN WILL BE SUBMITTED TO THE ENGINEER FOR WRITTEN APPROVAL.


SEQUENCE OF CONSTRUCTION

- A. THIS PROJECT CONSISTS OF ONE WORK AREA AS DEFINED BY CSJ:
 - (LIMITS: SH 36 at FM 107 INTERSECTION) (CSJ: 0184-01-065)
- B. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK TO THE DISTRICT TRAFFIC ENGINEER PRIOR TO THE BEGINNING OF CONSTRUCTION, WHICH GENERALLY CONFORMS TO THE FOLLOWING SEQUENCE:
 - I. ORDER ALL EQUIPMENT FOR ALL LOCATIONS.
 - 2.PROVIDE AND INSTALL ALL SIGNS, BARRICADES, AND TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE TRAFFIC CONTROL STANDARDS.
 - 3.INSTALL CONDUIT
 - 4. PULL WIRES
 - 5. PLACE STRAIN POLE FOUNDATIONS.
 - 6.SET STRAIN POLES AND CABINET.
 - 7. INSTALL FLASHING BEACONS.
 - 8.COMPLETE ALL OTHER WORKS AS DIRECTED.
 - 9. FINAL CLEAN UP.



PAV EDGE DROP-OFF DETAIL

- I. LESS THAN 2 INCHES: CW 8-II SIGNS ARE REQUIRED.
- GREATER THAN 2 INCHES BUT LESS THAN 24 INCHES: VERTICAL PANELS AND EITHER CW 8-9g OR CW 8-II SIGNS ARE REQUIRED.
- 3. GREATER THAN 24 INCHES: POSITIVE BARRIER REQUIRED.
- 4. THE SAFETY SLOPE WILL BE CONSTRUCTED WITH AN ALL- WEATHER MATERIAL SUCH AS RAP, WHICH IS CLEAN AND FREE OF DEBRIS AND LARGE ROCKS.



1" = 2000' HORIZ.

SECT

01

JOB

065

CORYELL

COUNTY

HIGHWAY

SH 36

SHEET NO

6

CONT

0184

DIST

WAC

CHANGE ORDER

FED. RD. DIV. NO.

6

STATE

TEXAS

of this standard is governed by the "Texas Engineering Practice Act". No warranty of any by TxDOI for any purpose whatsoever. TxDOI assumes no responsibility for the conversion and the formings of for incorrect results or damages resulting from its use.

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12



Division Standard


BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC(1)-21

			•				
LE:	bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		н	GHWAY
1-03	REVISIONS 7-13	0184	01	065		SH	36
9-07	8-14	DIST		COUNTY		SHEET NO.	
5-10 5-21 W		WAC		CORYEL	L		7

Æ₽

3:08:17 -\TRAFFIC



- \sharp May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

BEGIN T-INTERSECTION WORK ZONE ★ ★ G20-9TP ★ ★ R20-5T FINES DOUBL X R20-50TP BINEM BORKERS ARE PRESENT ROAD WORK ⟨⇒ NEXT X WILES X X G20-2bT WORK ZONE G20-1bTI INTERSECTED 1000' - 1500' - Hwy 1 Block - City 1000'-1500' - Hwy 1 Block - City ROADWAY \Rightarrow G20-1bTR ROAD WORK WORK ZONE G20-2bT * * Limit BEGIN * * G20-9TP ZONE TRAFFI G20-6T * * R20-5T FINES DOUBLE X X R20-5aTP WHEN WORKERS ROAD WORK G20-2

CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING 1,5,6

SIZE

onventional

48" x 48'

36" × 36"

48" x 48"

Sign

Number

or Series

CW20'

CW21

CW22

CW23

CW25

CW14

CW1, CW2,

CW7. CW8.

CW9, CW11

CW3, CW4,

CW5, CW6,

CW10, CW12

CW8-3,

SPACING

Expressway/ Freeway			
48" × 48" 30 120 35 160 40 240 45 320 50 400 55 500 ² 60 600 ² 65 700 ² 70 800 ² 75 900 ² 80 1000 ²			Spacing
48" × 48" 35		MPH	
48" × 48" 48" × 48" 48" × 48" 48" × 48" 48" × 48" 48" × 48" 48" × 48" 48" × 48" 48" × 48"	48" × 48"	30	120
48" x 48" 45 320 50 400 55 500 ² 60 600 ² 65 700 ² 70 800 ² 75 900 ² 80 1000 ²		35	160
48" x 48" 50 400 55 500 ² 60 600 ² 65 700 ² 70 800 ² 75 900 ² 80 1000 ²		40	240
48" x 48" 55		45	320
48" × 48" 55 500 ² 60 600 ² 65 700 ² 70 800 ² 75 900 ² 80 1000 ²	48" × 48"	50	400
48" × 48" 65 700 ² 70 800 ² 75 900 ² 80 1000 ²		55	500 ²
70 800 ² 75 900 ² 80 1000 ²		60	600 ²
75 900 ² 80 1000 ²		65	700 ²
75 900 ² 80 1000 ²	48" × 48"	70	800 ²
		75	900 ²
* * 3		80	1000 ²
		*	* 3

- * For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- \triangle Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS X X G20-9TP SPEED STAY ALERT ROAD LIMIT R4-1 DO NOT PASS appropriate: OBEY TRAFFIC **X X** R20-5T WORK WARNING * * G20-5 ROAD WORK AHEAD DOUBLE SIGNS € ★ R20-5aTP ME PRESENT CW20-1D ROAD STATE LAW TALK OR TEXT LATER CW13-1P R2-1 X > ROAD ★ ★ G20-6T WORK WORK G20-10T * * R20-3T * * AHEAD AHEAD Type 3 Barricade or WPH CW13-1P CW20-1D channelizing devices \Diamond \Diamond \Diamond \Leftrightarrow \Rightarrow \Leftrightarrow ➾ \Rightarrow Beginning of NO-PASSING SPEED END G20-2bT X X R2-1 LIMIT line should $\otimes \times \times$ coordinate ROAD WORK then extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional with sign location ROAD WORK AHEAD"(CW20-1D)signs are placed in advance of these work areas to remind drivers they are still G20-2 X X NOTES within the project limits. See the applicable TCP sheets for exact location and spacing of signs and

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS

★ ★G20-9TP STAY ALERT ZONE BEGIN ROAD WORK NEXT X MILES OBEY SPEED TRAFFI × + G20-5T ROAD LIMIT ROAD ROAD ¥ ¥R20-5T FINES SIGNS WORK CLOSED R11-2 WORK DOUBLE STATE LAW √2 MILE TALK OR TEXT LATER AHEAD X X R20-5aTP SHEN SHEEN ARE PRESENT * *G20-6T Type 3 R20-3T R2-1 G20-10 CW20-1D Barricade or CW13-1P CW20-1E channelizina devices -CSJ Limi Channelizing Devices \Rightarrow SPEED R2-1 END LIMIT END | ROAD WORK WORK ZONE G20-26T * * G20-2 * *

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer.

- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2b1 shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at the end of the work zone.

	LEGEND			
Ι	Type 3 Barricade			
000 Channelizing Devices				
4	Sign			
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.			

SHEET 2 OF 12

Texas Department of Transportation

Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

			•	_			
:	bc-21.dgn	DN: T	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		HIC	HWAY
	REVISIONS		01	065		SH	36
-07	8-14	DIST	ST COUNTY			SHEET NO.	
'-13	5-21	WAC		CORYEL	L		8

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:

40 mph and greater 0.2 to 2 miles

35 mph and less 0.2 to 1 mile

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to:
 A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only.
 Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12



Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

			_		_			
E:	bc-21.dgn		DN: Tx[TO	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 200	2	CONT	SECT	JOB		HIC	HWAY
	REVISIONS		0184	01	065		SH	36
9-07 8-14	8-14 5-21		DIST		COUNTY			SHEET NO.
7-13	3-21		WAC		CORYEL	L		9

97

- * When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.
 - * * When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.



No warranty of any for the conversion m its use.

exas Engineering Practice Act". IXDOI assumes no responsibility results or damages resulting fro

3:08:18

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.


SIDE ELEVATION Wood

Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

STOP/SLOW PADDLES

- 1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24". STOP/SLOW paddles shall be retroreflectorized when used at night.
- 3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING RE	QUIREMENT	S (WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports. the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

<u>DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)</u>

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
- Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
- Short, duration work that occupies a location up to 1 hour. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plagues mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- 3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL} , shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs. Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular
- impact. Rubber (such as tire inner tubes) shall NOT be used. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured
- with rubber bases may be used when shown on the CWZTCD list. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or
- hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face. SHEET 4 OF 12

Traffic Safety Division Standard



BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21

FILE:	bc-21.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxD0T	November 2002	CONT	SECT	JOB		HI	GHWAY
	REVISIONS 8-14	0184	01	065		SH 36	
9-07		DIST	DIST COUNTY			SHEET NO.	
7-13	5-21	WAC		CORYEL	.L		10

98

12/20/2021 3:08:19 T:\WACTRAFFIC

going in opposite directions. Minimum

back fill puddle.

weld starts here

weld, do not

¥ Maximum 12 sq. ft. of * Maximum wood 21 sq. ft. of sign face post sign face 2x6 4×4 block block 72" Length of skids may Top be increased for wood additional stability. post for sign Top 2x4 x 40" height 24" 2x4 brace for sign requirement height 3/8" bolts w/nuts requiremen or 3/8" x 3 1/2" (min.) lag screws Front 4x4 block 40" 4x4 block 36" Side Front

SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

-2" x 2"

12 ga.

upright

2"

SINGLE LEG BASE

Side View


Post / Post Post max. desirable 34" min. in Optional strong soils, 48" reinforcing 55" min. in minimum sleeve -34" min. in (1/2" larger weak soils. strong soils, than sian 55" min, in post) x 18" weak soils. Anchor Stub Anchor Stub (1/4" larger (1/4" larger than sign than sign post) post) -OPTION 2 OPTION 1 OPTION 3 (Anchor Stub) (Direct Embedment) (Anchor Stub and Reinforcing Sleeve)) PERFORATED SQUARE METAL TUBING

See the CWZTCD for embedment. WING CHANNEL

Post

GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
 - ★ See BC(4) for definition of "Work Duration."
 - Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

		_					
FILE:	bc-21.dgn	DN: T	×DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB		H]	GHWAY
	REVISIONS	0184	01	065		SF	1 36
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	WAC		CORYEL	L		11

<u>SKID MOUNTED</u>	PERFORATED	SQUARE	STEEL	<u>TUBING</u>	SIGN	<u>SUPPORTS</u>	

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32'

PORTABLE CHANGEABLE MESSAGE SIGNS

Texas Engineering Practice Act". No warranty of any ixDOI assumes no responsibility for the conversion tresults or damages resulting from its use.

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED," Do not use the term "RAMP,"
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message.
- 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking Road	PK ING RD
CROSSING	XING	Right Lane	RT LN
Detour Route	DETOUR RTE	Saturday	SAT
Do Not	DONT	Service Road	SERV RD
East	F	Shoulder	SHLDR
Eastbound	(route) E	Slippery	SLIP
Emergency	EMER	South	S
Emergency Vehicle		Southbound	(route) S
Entrance, Enter	ENT	Speed	SPD
Express Lane	EXP LN	Street	ST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY. FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving	HAZ DRIVING		TRVLRS
Hazardous Material		Travelers	TUES
High-Occupancy	HOV	Tuesday Time Minutes	TIME MIN
Vehicle	HWY		UPR LEVEL
Highway	HWT	Upper Level	
Hour (s)	HR, HRS	Vehicles (s) Warnina	VEH, VEHS
Information	INFO		WED
It Is	ITS	Wednesday	ML LIWIL
Junction	JCT	Weight Limit	M. LIWII
Left	LFT	West Westbound	(route) W
Left Lane	LFT LN		WET PVMT
Lane Closed	LN CLOSED	Wet Pavement	
Lower Level	LWR LEVEL	Will Not	WONT
Maintenance	MAINT		

designation # IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp	o Closure List	Other Cond	lition List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT
xxxxxxxx			

Phase 2: Possible Component Lists

mp Closure List	Other Cond	dition List	Action to Take/E Li		Location List	Warning List	* * Advance Notice List
FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT	MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT	DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- XX X PM-X AM
RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE	USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT	STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT	TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT	WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN	EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES	REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE	NEXT TUE AUG XX
X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT *	USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM- XX AM
* LANES SHIFT in Phas	se 1 must be used with	h STAY IN LANE in Phase 2.	STAY IN LANE *		* * See	e Application Guidelines	Note 6.

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- 2. Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- 7. FT and MI. MILE and MILES interchanged as appropriate.
- 8. AT. BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


FULL MATRIX PCMS SIGNS

BLVD

CLOSED

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE


Traffic Safety Division Standard

BC(6)-21

MESSAGE SIGN (PCMS)


	_			_			
FILE:	bc-21.dgn	DN: TxD	TO	ck: TxDOT	DW:	T×DOT	ck: TxDOT
© TxD0T	November 2002	CONT S	ECT	JOB		HIGHWAY	
REVISIONS		0184	01	065		SH	36
9-07	8-14	DIST	DIST COUNTY			SHEET NO.	
7-13	5-21	WAC		CORYEL	.L		12

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of pregualified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)


- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10. Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer
- 11. Single slope barriers shall be delineated as shown on the above detail.



IN WORK ZONES LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)




DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- 5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.


WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.

 2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions
- or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- 4. The Flashing Arrow Board should be able to display the following symbols:



- 5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage.
 The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
 Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal
- intervals of 25 percent for each sequential phase of the flashing chevron.

 9. The sequential arrow display is NOT ALLOWED.

 10. The flashing arrow display is the TxDOT standard; however, the sequential chevron
- display may be used during daylight operations.
- 11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
 12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
 13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility,
- flash rate and dimming requirements on this sheet for the same size arrow.
- 14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

	REQUIREMENTS								
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE						
В	30 × 60	13	3/4 mile						
С	48 × 96	15	1 mile						

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE
TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted in the plans.
- 5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL. REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC(7) - 21

FILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C TxD0T	November 2002	CONT	SECT	JOB		HIC	SHWAY
		0184	01	065		SH	36
9-07	8-14	DIST	OIST COUNTY			SHEET NO.	
7-13	5-21	WAC		CORVEI	1		17



1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.

- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

GENERAL NOTES

Pre-qualified plastic drums shall meet the following requirements:


- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- 3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10.Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.





DETECTABLE PEDESTRIAN BARRICADES

- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- 2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian
- 5. Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24" Vertical Panel mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- 1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- 3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- 5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each
- 6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum, A minimum of three (3) should be used at each location called for in the plans.
- 8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12



BARRICADE AND CONSTRUCTION


Traffic Safety


BC (8) - 21

CHANNEL IZING DEVICES

	• • •	•	~ .			
FILE: bc-21.dgn	DN: T>	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>T×DOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	T×DOT	ck: TxDOT
CTxDOT November 2002	CONT	SECT	JOB		HIC	SHWAY
4-03 8-14	0184	01	065		SH	36
4-03 8-14 9-07 5-21	DIST		COUNTY			SHEET NO.
7-13	WAC		CORYEL	L		14


12/20/2021 3:08:22 T:\WACTRAFF\TRAFFIC






- 1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane. 4. VP's used on expressways and freeways or other high
- speed roadways, may have more than 270 square inches of retroreflective area facing traffic. 5. Self-righting supports are available with portable base.
- See "Compliant Work Zone Traffic Control Devices List" 6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification
- DMS-8300, unless noted otherwise, 7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42"
- 3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black nonreflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the out side of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

	sted eed	Formula		esirab er Lend **		Spacin Channe Dev	
			10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
3	Ö	. ws²	150′	1651	180′	30'	60′
- 3	35	L = WS	2051	225′	245′	35′	70′
4	0	80	265′	295′	3201	40′	80′
4	5		450′	495′	540′	45′	90′
5	Ö		5001	550′	600,	50′	100′
5	5	L=WS	550′	6051	660′	55′	110′
6	Ö	L - 11 3	600'	660′	720′	60′	120′
6	55		650′	715′	7801	65 <i>°</i>	130′
7	ŏ		700′	770′	840′	701	140′
7	5		750′	825′	900'	75′	150′
8	0		8001	880′	960′	80'	160′
	VVT locathe have been recorded ass						

XX Taper lengths have been rounded off. L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Traffic Safety Division Standard

Suggested Maximum


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) -21


ILE:	bc-21.dgn	DN: T	×DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		HIC	GHWAY
REVISIONS		0184	01	065		SH	36
9-07	8-14	DIST		COUNTY		,	SHEET NO.
7-13 5-21	2-21	WAC		CORYEL	.L		15

TYPE 3 BARRICADES

- 1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- 2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- 6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- Warning lights shall NOT be installed on barricades.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The $\,$ sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION

Two-Piece cones



CONES 4" min. orange ₹2" min. 1 4" min. white 2" min. ↑ 4" min. orange [6" min. _2" min. 2" min. **1**4 min. 4" min. white 42" min. 28" min.

2" min.

2" to 6" min.

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

One-Piece cones

Tubular Marker

FOR SKID OR POST TYPE BARRICADES

Alternate Alternate Drums, vertical panels or 42" cones Approx. Approx. 50' at 50' maximum spacing 50' Min. 2 drums or 1 Type 3 or 1 Type 3 barricade STOCKPILE On one-way roads Desirable downstream drums stockpile location Channelizing devices parallel to traffic or barricade may be is outside should be used when stockpile is omitted here clear zone. within 30' from travel lane. \Diamond

TRAFFIC CONTROL FOR MATERIAL STOCKPILES

➾

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- 1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- 2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- 3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- 7. Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

			-				
ILE:	bc-21.dgn	DN: T	×DOT	ck: TxDOT	DW:	T×DOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		HIG	YAWH
		0184	01	065		SH	36
9-07	8-14	DIST		COUNTY		s	HEET NO.
7-13	5-21	WAC		CORYEL	.L		16

\WACTRAFF\TRAFFIC\Traffic Control Devic

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10. Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body).
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIO	NS
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

		- •				
E: bc-21.dgn	DN: TxDOT		CK: TXDOT DW:		TxDOT	ck: TxDOT
TxDOT February 1998	CONT	SECT	JOB		HI	GHWAY
REVISIONS -98 9-07 5-21	0184	01	065		SH	I 36
-98 9-07 5-21 -02 7-13	DIST		COUNTY		SHEET NO.	
-02 8-14	WAC CORYELL 17				17	

11-02

STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS Type Y buttons Type II-A-A 000/100// DOUBLE PAVEMENT NO-PASSING REFLECTOR 17FD PAVEMENT LINE Type I-C, I-A or II-A-A Type W or Y buttons RAISED EDGE LINE SOL I D PAVEMENT OR SINGLE LINES 60" REFLECTORIZED NO-PASSING LINE PAVEMENT White or Yellow Type I-C Type W buttons WIDE RAISED PAVEMENT LINE REFLECTOR 17FD (FOR LEFT TURN CHANNELIZING LINE OR CHANNELIZING LINE USED TO MARKINGS DISCOURAGE LANE CHANGING,) White 30"<u>+</u> 3' 30"+/-3" Type I-C or II-A-A 0 Q 0 9 0 RAISED **CENTER** PAVEMENT | 5' | 5' | MARKERS ✓Type W or LINE OR LANE REFLECTORIZED LINE MARKINGS White or Yellow Type I-C or II-A-A **BROKEN** (when required) LINES RAISED п _ ‡8 п П 1-2" _ MARKERS **AUXILIARY** Type I-C or II-C-OR LANEDROP REFLECTORIZED LINE PAVEMENT REMOVABLE MARKINGS 5′ <u>+</u> 6" WITH RAISED **PAVEMENT MARKERS** If raised pavement markers are used Raised Pavement Markers to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier 20' ± 1' removal of raised pavement markers Centerline only - not to be used on edge lines **SHEET 12 OF 12** Traffic Safety Division Standard Texas Department of Transportation BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS." BC(12)-21 DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO ©⊺xDOT February 1998 0184 01 065 SH 36 1-97 9-07 5-21 2-98 7-13 11-02 8-14 CORYELI



SIGNAL WORK AHEAD

CW20SG-1

SIGNAL WORK AHEAD

CW20SG-1

 \triangle

 \Box

14.

R4-7 24" × 30"

 $\langle \rangle$

NEAR SIDE LANE CLOSURE

SHORT DURATION OR SHORT TERM STATIONARY

 \Diamond

 \bigcirc

SIGNAL WORK AHEAD

CW20SG-1


Typical

SIGNAL WORK AHEAD

CW20SG-1 48" x 48"

1/2L

1010



24" × 30"

 \Diamond

 $\langle \rangle$

SIGNAL WORK AHEAD

CW20SG-1 48" × 48'

SIGNAL WORK AHEAD

CW20SG-1

LANE CLOSE

SIGNAL WORK AHEAD

SIGNAL WORK AHEAD

CW20SG-1

OPERATIONS IN THE INTERSECTION

WORK

CW20SG-1 48" x 48"

See Note

ſ	LEGEND										
ſ		Туре :	Barr	icade				Chan	nelizing	Devices	
I		Heavy	Work	Vehic	е				k Mounted nuator (
		Traile Flash		nted row Bo	ard		Ŋ		able Cha age Sign		
Ī	4	Sign	Sign				ን	Traf	ffic Flow		
Ī	\Diamond	Flag	Flag			П	Ō	Flag	ger .		
ed ed	Formula	Desirable S			oacii onne	d Ma ng o lizi ices		Minimum Sign Spacing "X"	Suggested Longitudin Buffer Spa		
		10' Offset	11' Offset	12' Offset	On Tap			n a igent	Distance	"В"	
)	. WS ²	150′	165′	180'	30)′		60'	120′	90′	
	ı WS	2051	225/	0.457	7.0	- /		701	• • • • •	100/	

Speed	Formula	* *		gths	Channelizing Devices		Sign Spacing "X"	Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	WS ²	150′	165′	180′	30'	60′	120′	90′
35	L = WS	2051	225′	245′	35'	70′	160′	120′
40	80	265′	2951	3201	40′	80`	240'	155′
45		450′	495′	540′	45′	90′	320′	1951
50		5001	550′	6001	50,	1001	400′	240'
55	L=WS	550′	605′	6601	55`	110′	500′	295′
60	L - 11 3	600′	660′	720′	60,	120′	600'	350′
65		650′	715′	7801	65′	130′	700′	410′
70		700′	770′	840′	70′	140′	800'	475′
75		750′	8251	9001	75'	150′	900'	540′
		·						

* Conventional Roads Only

WORK

CW20SG-1

LEFT LANE CLOSED

CW20-5TL

CW20-5TL 48" x 48

SIGNAL WORK AHEAD

CW20SG-1

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.

GENERAL NOTES

SIGNAL WORK AHEAD

CW20SG-1

 \Diamond

➪

SIGNAL WORK AHEAD

CW20SG-1

 \bigcirc

♡ || ☆

SIGNAL WORK AHEAD

CW20SG-1

1. The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.

FAR SIDE LEFT LANE CLOSURE

SHORT DURATION OR SHORT TERM STATIONARY

- 2. Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- 3. Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- 4. Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- 5. High level warning devices (flag trees) may be used at corners of the vehicle.
- 6. When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P) signs may be implemented when approved by the engineer.
- 7. For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- 8. The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.
- Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.

SHEET 1 OF 2




Traffic Operations Division Standard

TRAFFIC SIGNAL WORK TYPICAL DETAILS

WZ(BTS-1)-13

E: wzbts-13.dgn	DN: T	×DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT April 1992	CONT SECT JOB HIGH		CONT SECT JOB		SHWAY	
REVISIONS	0184	01	065		SH	36
98 10-99 7-13	DIST		COUNTY			SHEET NO.
98 3-03	WAC		CORYEL	.L		19



GENERAL NOTES FOR WORK ZONE SIGNS

Wooden sign posts shall be painted white.

directed by the Engineer.

directed by the Engineer.

DURATION OF WORK

SIGN MOUNTING HEIGHT

REMOVING OR COVERING

shown on Figure 6F-2 of the TMUTCD.

Barricades shall NOT be used as sign supports.

Nails shall NOT be used to attach signs to any support.

Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

Signs shall be installed and maintained in a straight and plumb condition. $\ensuremath{\,^{\circ}}$

All signs shall be installed in accordance with the plans or as

Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as

The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).

The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.


Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".

Work zone durations are defined in Part 6, Section 66.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

Sign height of Short-term/Short Duration warning signs shall be as



TYPICAL ADVANCE SIGNAL PROJECT SIGNING

FOR LONG TERM and INTERMEDIATE-TERM STATIONARY WORK OPERATIONS

REFLECTIVE SHEETING

All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

warning sign spacing.

under way, as directed by the Engineer.

5. See the Table on sheet 1 of 2 for Typical

4. Warning sign spacing shown is typical for both

SIGN SUPPORT WEIGHTS

- Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber, such as tire inner tubes, shall not be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fastners. Sandbags shall be placed along the length of the skids to weigh down the
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

por is pide	or is praced on stopes.						
	LEGEND						
-	≗ Sign						
	Channelizing Devices						
	Type 3 Barricade						

DEPARTMENTAL MATERIAL	SPECIFICATIONS
SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
WHITE	BACKGROUND	TYPE A SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD)

describes pre-qualified products and their sources and may be found at the following web address: http://www.txdot.gov/txdot_library/publications/construction.htm

♦∥♦ ♡ || ☆ | SIDEWALK DIVERSION SIDEWALK CLOSE SIDEWALK SIGNAL WORK CLOSED CROSS HERE CROSS HERE AHEAD R9-11aL 24" x 12" R9-9 24" x 12" 24" x 12' CW20SG-1 48" x 48 ♦∥♦ ♡|| 公| \Diamond ♦ -Work Area ♦ 4> ♡∥☆ ♡ SIDEWALK DETOUR See Note 8 36" × 36" **SIDEWALK** See Note 6 R9-11aR CLOSED R9-11L 24" x 12" CROSS HERE 24" x 12' CW11-2 SIGNA 36" × 36" WORK AHEAD See Note 6 AHEAD CW16-9P CW16-7PL 24" x 12" 24" x 12" K \bigcirc ₹ /CW20SG-1 -Work Area 48" × 48" \Diamond \Diamond ♦ ➾ ♡ SIGNA 89-10DBL IDEWALK CLOSE CROSSWALK CLOSURES AHEAD USE OTHER SIDE CW2OSG-PEDESTRIAN CONTROL

Temporary Traffic Barrier

10' Min.

♦∥♦

 \Diamond

₹>

Note 4 below

4′ Min.(See Note 7 below

- Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.
- "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation, R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic
- substrates, they may be mounted on top of a plastic drum at or near the location shown. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of

blunt ends and installation of water filled devices shall be as per BC(9)

- and manufacturer's recommendations. Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.
- Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.
- The width of existing sidewalk should be maintained if practical.
- Pavement markings for mid-block crosswalks shall be paid for under the appropriate bid items.
- When crosswalks or other pedestrian facilities are closed or relocated. temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian



Texas Department of Transportation

TRAFFIC SIGNAL WORK BARRICADES AND SIGNS

WZ(BTS-2)-13

Operation Division Standard

CW20SG-1

SIGNA

WORK

 \Diamond

₹>


wzbts-13. dgn DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO JOB TxDOT April 1992 0184 01 065 SH 36 2-98 10-99 7-13 4-98 3-03 CORYFL 20


When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.

When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs.

- Duct tape or other adhesive material shall NOT be affixed to a sign face. $\,$
- Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

Rumble Strip Array (See note 1) Rumble Strip Array based on Table 1, this array may be omitted when the ADT is lower than the thresholds shown (See note 1)-





GENERAL NOTES

- 1. Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- 2. The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide warning.
- 3. Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control
- 4. Removal of the Temporary Rumble Strips should be accomplished before removing the advance warning signs.
- 5. Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- 6. Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- 7. This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- 8. The one-lane two-way application may utilize a flagger, an AFAD or a portable traffic signal.
- 9. Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment.

RUMBLE

STRIPS

AHEAD

CW17-2T 48" X 48" (See note 2)

ROAD

WORK

AHEAD

CW20-1D 48" X 48"

	LEGEND										
	Type 3 Barricade		Channelizing Devices								
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)								
E	Trailer Mounted Flashing Arrow Panel	(M	Portable Changeable Message Sign (PCMS)								
-	Sign	Ŷ	Traffic Flow								
\bigcirc	Flag	ПO	Flagger								


Speed	Minimum Desirable Formula Taper Lengths X X Suggested Maxin Spacing of Channelizing Devices		ng of Iizing	Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space			
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	ws ²	150′	165′	180′	30′	60′	120'	90′
35	L = WS	2051	2251	2451	35′	701	160′	120′
40	80	265′	2951	3201	40′	80'	240'	155′
45		450′	495′	540'	45′	90′	320'	195′
50		500′	550′	6001	50°	100′	4001	240′
55	L=WS	550′	605′	660′	55′	110′	500′	295′
60	L - # 3	600'	660′	7201	60′	120′	600'	350′
65		6501	715′	7801	65′	130′	700′	410'
70		700′	770′	840′	70′	140′	800'	475′
75		750′	825′	900′	75′	150′	900′	540′

- * Conventional Roads Only
- ** Taper lengths have been rounded off. L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed (MPH)

TYPICAL USAGE										
MOBILE	SHORT DURATION	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY							
	✓	✓								

♦ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.


Т	ABLE 2
Speed	Approximate distance between strips in an Array
<u> < 40 MPH</u>	10'
> 40 MPH & < 55 MPH	15′
> 55 MPH	20′





TEMPORARY RUMBLE STRIPS

WZ(RS) - 16

	"-		•	. •			
FILE:	wzrs16.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C TxDOT	November 2012	CONT	SECT	JOB		н	GHWAY
	REVISIONS	0184	01	065		SH	36
2-14 4-16		DIST		COUNTY			SHEET NO.
4-10		WAC		CORYE	LL		21







Conventional Roads

	LEGEND									
	Type 3 Barricade		Channelizing Devices							
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)							
۱	Sign	∿	Traffic Flow							
\Diamond	Flag	4	Flagger							

Posted Speed	Formula	**			Spacir Channe	uggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	ws ²	150′	1651	1801	30'	60′	120′	90'
35	L = WS	2051	2251	245′	35′	70′	160′	120′
40	80	265′	295′	3201	40′	80′	240′	155′
45		450'	495′	540′	45′	90′	320′	195′
50		500'	550′	6001	50′	100′	400′	240′
55	L=WS	550′	6051	660′	55′	110′	500′	295′
60	L-#3	600'	660′	7201	60′	120'	600′	350′
65		650′	715′	7801	65′	1301	700′	410′
70		7001	770′	840′	701	140′	800′	475′
75		750′	8251	900′	75′	150′	900'	540′

- * Conventional Roads Only
- ** Taper lengths have been rounded off.
- L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY								
	√	√							

GENERAL NOTES

- 1. Flags attached to signs where shown are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- 3. Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 5. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- 6. See TCP(5-1) for shoulder work on divided highways, expressways and
- 7. CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(1-1)-18

LE:	tcp1	-1-18. dgn	DN:		CK:	DW:		CK:
IXT (DOT	December 1985	CONT	SECT	JOB		нто	CHWAY
-94	4-98 RE	EVISIONS	0184	01	065		SH	36
-95	2-12		DIST		COUNTY			SHEET NO.
-97	2-18		WAC		CORYE	LL		22

Warning Sign Sequence in Opposite Direction ROAD WORK Same as Below G20-2 48" X 24" ♡□↔ 42" X 42 " X 42 ΤO ONCOMING TRAFFIC R1-2aP 48" X 36" (See note 8) Channelizing devices separate work space from traveled way —Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. (See notes 5 & 6) ONCOMING ♡ | ☆ TCP (1-2a) ONE LANE TWO-WAY CONTROL WITH YIELD SIGNS

(Less than 2000 ADT - See note 7)

END

R1 - 2aP

CW3-2 48" X 48"

CW20-4D

CW20-1D

(Flags-

48" X 48"

ONE LANE


ROAD

AHEAD

ROAD

WORK

AHEAD



	LEGEND										
I		Type 3 Barricade		Channelizing Devices							
		Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
		Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)							
	þ	Sign	♡	Traffic Flow							
	\Diamond	Flag	ПО	Flagger							

Posted Speed	Formula	D	Minimum esirab er Lend **	le	Spacii Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"	
30	2	1501	1651	1801	30′	60′	1201	90′	200'
35	L = \frac{WS^2}{60}	2051	225'	245′	35′	70′	160′	120′	250′
40	80	2651	2951	3201	40'	80′	240′	155′	305′
45		450′	4951	540′	45′	90'	320′	195′	360′
50		5001	550′	600,	50′	100′	4001	240′	425′
55	L=WS	550′	6051	660'	55′	110′	500′	295′	495′
60	L-#3	600'	660′	720′	60′	120′	600′	350′	570′
65		650′	715′	7801	65′	130'	700′	410′	645′
70		7001	7701	840′	701	140′	800′	475′	730′
75		750'	825′	900′	75′	150′	900′	540′	820′

* Conventional Roads Only

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE										
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY						
	1	1								

GENERAL NOTES

- 1. Flags attached to signs where shown are REQUIRED.
- 2, All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- 4. Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 6. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

- 7. R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- 8. R1-2 "YIELD" sign with "R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

- 9. Flaggers should use two-way radios or other methods of communication to control traffic.
- 10. Length of work space should be based on the ability of flaggers to communicate.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above)
- 12. Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- 3. Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP(1-2)-18

FILE: tcp1-2-18.dgn	DN:		CK:	DW:	CK:
ℂTxDOT December 1985	CONT	SECT	JOB		HIGHWAY
4-90 4-98 REVISIONS	0184	0184 01 065			SH 36
2-94 2-12	DIST		COUNTY		SHEET NO.
1-97 2-18	WAC		CORYE	LL	23



	LEGEND							
~~~	Type 3 Barricade		Channelizing Devices					
	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)					
(E)	Trailer Mounted Flashing Arrow Board	(M	Portable Changeable Message Sign (PCMS)					
•	Sign	♡	Traffic Flow					
$\Diamond$	Flag	Ф	Flagger					

Posted Speed	Formula	D	Minimur esirab er Lend **	le	Spacir Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	L = WS ²	150′	1651	180'	30′	60′	120′	90′
35		2051	225′	245'	35′	70′	160′	120′
40	60	265′	2951	320′	40′	80′	240'	155′
45		450′	495′	540'	45′	90′	320′	195′
50		5001	550′	600′	50'	100′	400′	240′
55	L=WS	550′	605′	660′	55′	110'	500′	295′
60	L - W 3	600′	660′	720′	60′	120'	600′	350′
65		650′	715′	780′	65′	130′	700′	410′
70		700′	770′	840'	70′	140′	800′	475′
75		750′	8251	9001	75′	150′	900′	540′

- * Conventional Roads Only
- ₩ Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	1	1						

#### GENERAL NOTES

- 1. Flags attached to signs where shown are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer. 3. The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the
- visibility of the work zone is less than 1500 feet.

  4. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 5. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

6. If this TCP is used for a left lane closure , CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

7. Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS

TCP(1-4)-18

FILE: tcp1-4-18.dgn	DN:		CK:	DW:		CK:
© TxDOT December 1985	CONT	SECT	JOB		HIG	HWAY
2-94 4-98 REVISIONS	0184	01	065		SH	36
8-95 2-12	DIST		COUNTY		S	SHEET NO.
1-97 2-18	WAC		CORYE	LL		24



LEGEND Type 3 Barricade Channelizing Devices Truck Mounted Attenuator (TMA) Heavy Work Vehicle Portable Changeable Message Sign (PCMS) Trailer Mounted Flashing Arrow Board M Traffic Flow Sign  $\Diamond$ Ф Flag Flagger

_									
Posted Speed	Formula	Minimum Desirable Taper Lengths **			Spacii Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	
*	*		11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"	
30	2	150′	1651	1801	30′	60'	120′	90'	
35	$L = \frac{WS^2}{60}$	2051	2251	245'	35′	70′	160′	120′	
40	60	2651	2951	3201	40′	80′	240′	155′	
45		4501	4951	540′	45′	90′	320′	195′	
50	1	500′	5501	600′	50′	100′	400′	240′	
55	L=WS	550′	605′	660′	55′	110′	500′	295′	
60	- " -	600'	660′	720′	60′	120'	600′	350′	
65		650′	715′	780′	65′	130′	700′	410′	
70		7001	770′	840'	70′	140′	800′	475′	
75		750′	8251	900′	75′	150′	900′	540′	

- * Conventional Roads Only
- ** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY					
	1 1 1								

#### **GENERAL NOTES**

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer
- 3. Stockpiled material should be placed a minimum of 30 feet from
- nearest traveled way.

  4. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 5. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space. 6. See TCP(5-1) for shoulder work on divided highways, expressways and
- 7. Inactive work vehicles or other equipment should be parked near the
- right-of-way line and not parked on the paved shoulder.
- 8. CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.


Texas Department of Transportation


Traffic Operations Division Standard


TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(2-1)-18

	_	- •		-	
ILE: tcp2-1-18.dgn	DN:		CK:	DW:	CK:
TxDOT December 1985	CONT	SECT	JOB		HIGHWAY
REVISIONS 2-94 4-98	0184	01	065		SH 36
3-95 2-12	DIST		COUNTY		SHEET NO.
-97 2-18	WAC		CORYE	LL	25







ONE LANE TWO-WAY

CONTROL WITH FLAGGERS

		LEGEND								
	~~~	Type 3 Barricade		Channelizing Devices						
		Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
		Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)						
	þ	Sign	♡	Traffic Flow						
	\Diamond	Flag	9	Flagger						
_										

Posted Formul Speed		**		Spacin Channe	Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space	Stopping Sight Distance	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	"X" Distance	"B"	
30	. <u>ws</u> 2	150′	1651	180′	30′	60′	120'	90′	200'
35	L = WS 60	2051	2251	245'	35′	70′	160′	120′	250′
40	80	265′	2951	3201	40'	80′	240'	1551	305′
45		450′	4951	540′	45′	90′	320′	195′	360′
50		5001	550′	600′	50'	100′	400′	240′	425′
55	L=WS	550′	6051	660,	55′	110'	500′	295′	495′
60	_ "3	600′	660′	720′	60'	120'	600'	350'	570′
65		650′	715′	780′	65′	130′	700′	410′	645'
70		700′	770′	840′	70′	140′	8001	475′	730′
75		750′	8251	900′	75′	150′	900'	540′	820′

* Conventional Roads Only

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	1	1	1					

GENERAL NOTES

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
- Flaggers should use two-way radios or other methods of communication to control traffic.
- 5. Length of work space should be based on the ability of flaggers to communicate.
- 6. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 7. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-2a)

- 8. The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
- 9. The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.

TCP (2-2b)

- 10.Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- 11.If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles.
- 12.Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situtations.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP (2-2) -18

FILE: tcp2-2-18.dgn	DN:		CK:	DW:		CK:
© TxDOT December 1985	CONT	SECT	JOB		HIG	HWAY
REVISIONS 8-95 3-03	0184 01 065			SH 36		
1-97 2-12	DIST		COUNTY		S	HEET NO.
4-98 2-18	WAC		CORYE	_L		26





	LEGEND								
~~~	Type 3 Barricade	8 8	Channelizing Devices						
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
<b>E</b>	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)						
-	Sign	♡	Traffic Flow						
$\Diamond$	Flag	TO.	Flagger						

	V \							
Posted Speed	Desir Formula Taper L *		Minimur esirab er Len <del>X X</del>	le	Spacir Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	$L = \frac{WS^2}{60}$	150′	1651	1801	30′	60′	120'	90′
35		2051	2251	2451	35′	701	160′	120′
40		265′	2951	320′	40`	80′	240'	155′
45		450′	495′	5401	45′	90′	320'	195′
50		500′	550′	6001	50°	100'	400'	240′
55	L=WS	550′	6051	660′	55′	110′	500′	295′
60	- ""	600′	6601	720′	60`	120'	600,	350′
65		650′	715′	780′	65 <i>°</i>	130′	700′	410′
70		700′	770′	8401	70′	140′	800'	475′
75		750′	825′	900′	75′	150′	900'	540′

- * Conventional Roads Only
- ** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
		<b>✓</b>	<b>√</b>					

#### GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
   All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- 3. The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- 1. For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- . Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

#### CP (2-4a)

7. If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

#### CP (2-4b)

8. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.





Traffic Operations Division Standard


TRAFFIC CONTROL PLAN LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS

TCP(2-4)-18

FILE: tcp2-4-18.dgn	DN:		CK:	DW:	CK:	
© TxDOT December 1985	CONT	SECT	JOB		HIGHWAY	
8-95 3-03 REVISIONS	0184	01	065		SH 36	
1-97 2-12	DIST	COUNTY			SHEET NO.	
4-98 2-18	WAC		CORYE	LL	27	









THE ENTIRE SIGNAL HEAD HOUSING AND VISOR
OF EACH SIGNAL SECTION SHALL BE BLACK IN COLOR

#### TYPICAL SPAN WIRE FLASHING BEACON

(SEE PLAN LAYOUT FOR HEAD CONFIGURATION)



- NOTES:
  1. STEEL STRAIN POLES WILL BE IN ACCORDANCE
  WITH STANDARD SHEETS SP-80(1)-12 AND SP-80(2)-12
- 2. SIGNAL HEADS WILL BE MOUNTED PERPENDICULAR TO THE TRAVEL LANE AND CENTERED IN THE TRAVEL LANE.
- 3. SIGNAL HEADS WILL BE 12" ALUMINUM WITH LED INDICATIONS. THE NUMBER OF DIRECTIONS AND THE NUMBER OF HEADS SHALL BE AS SHOWN ON THE TRAFFIC SIGNAL LAYOUT SHEETS.
- 4. HARDWARE REQUIRED FOR THE INSTALLATION OF SIGNAL HEADS WILL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS BID ITEMS.



Tahmina Khan, PE

12/20/2021

© 2022 Texas Department of Transportation

SIGNATURE OF REGISTRANT

#### TYPICAL SPAN WIRE

(SH 36 AT FM 107)

CHANGE ORDER	FED.RD. DIV. NO.	CONT	SECT	JOB	F	HIGHWAY
	6	0184	01 065		•	SH 36
	STATE	DIST	COUNTY			SHEET NO.
	TEXAS	WAC	CORYELL			30


		CONDU	JIT A	ND C	ABLE RUNS	5	
		CONDUIT TRENCH			ELECTRICA CONDUCTOR		
RUN	LENGTH OF RUN (FT)	CONDT (PVC) (SCH 40) (3")	NO. 8 (BARE)	NO. 8 (INSULATED)	ZINC-COAT STL WIRE STRAND (3/8")	TRF SIG CBL (TY A) (12 AWG) (3 CONDR)	RUN
		EA	EΑ	EΑ	EA	EA	
01	140	1	1	4			01
02	48	1	1	4			02
03	42		1	2	2	1	03
04	20		1	2	2	1	04
05	12		1	2 2 2 2	2 2 2 2 2 2	1	05
06	18		1	2	2	1	06
07	31		1	2	2	1	07
08	27		1	2	2		08

#### PROPOSED FLASHING BEACON SHEET SUMMARY

		PROPOSED FLASHING BEACON SHEET SUMMART		
ITEM	CODE	DESCRIPTION	<u>UNIT</u>	QTY
416	6004	DRILL SHAFT (36 IN)	LF	24
618	6029	CONDT (PVC) (SCH 40) (3")	LF	188
620	6007	ELEC CONDR (NO. 8) BARE	LF	338
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	1052
624	6010	GROUND BOX TY D (162922) W/APRON	EA	1
625	6003	ZINC-COAT STL WIRE STRAND (3/8")	LF	300
628	6145	ELC SRV TY D 120/240 060(NS)SS(E)SP(O)	EΑ	1
680	6001	INSTALL HWY TRF SIG (FLASH BEACON)	EA	1
682	6003	VEH SIG SEC (12 IN)LED(YEL)	EA	4
682	6005	VEH SIG SEC (12 IN)LED(RED)	EΑ	2
682	6021	BACK PLATE (12 IN)(1 SEC)	EA	6
684	6008	TRF SIG CBL (TY A) (12 AWG) (3 CONDR)	LF	123
686	6020	INS TRF SIG PL AM (S)STR(TY D)LUM	EA	2

#### NOTES:


1. REFER TO CONSOLIDATED SUMMARY SHEET FOR PROJECT TOTALS.



# CONDUIT RUN AND SHEET SUMMARY

HANGE ORDER	FED.RD. DIV. NO.	CONT	SECT	JOB	H	HIGHWAY
	6	0184	4 01 065 SH 3		065	
	STATE	DIST	COUNTY			SHEET NO.
	TEXAS	WAC		CORYELL		31

				ELECTRI	CAL SERVI	CE DATA						
SERVICE POLE ID	PLAN LAYOUT SHEET TITLE	ELECTRICAL SERVICE DESCRIPTION (SEE ED(5)-14)	SERVICE CONDUIT SIZE	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK. POLE/AMPS	TWO-POLE CONTACTOR (AMPS)	PANEL BD./ LOADCENTER AMP RATING (MIN)	BRANCH CIRCUIT ID	BRANCH CKT. BRK. POLE/AMPS	BRANCH CIRCUIT AMPS	TOTAL KVA LOAD
SH 36 at FM 107	PROPOSED FLASHING BEACON LAYOUT	ELC SRV TY D 120/240 060(NS)SS(E)SP(O)	2" PVC	3/#6	N/A	2P/60A		1 OOA	FLASHING BEACONS	1P/30A	6	1.1
							2P/30A		ILLUMINATION	2P/30A	1.42	





## ELECTRICAL SERVICE DATA

	TEXAS	WAC	CORYELL			32	
	STATE	DIST		COUNTY		SHEET NO.	
	6	0184	01	065		SH 36	
CHANGE ORDER	FED. RD. DIV. NO.	CONT	SECT	JOB	-	HIGHWAY	

#### GENERAL NOTES FOR ALL ELECTRICAL WORK

- The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
- 2. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
- 3. Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is  $\frac{1}{2}$  in. or less in diameter.
- 4. Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
- 5. Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
- 5. When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies."

  No substitutions will be allowed for materials on this list.

#### CONDUIT

#### A. MATERIALS

- 1. Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
- 2. Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
- 3. Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.

AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" × 8" × 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" × 8" × 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" × 8" × 4"	8" × 8" × 4"	10" x 10" x 4"
#8	8" × 8" × 4"	8" × 8" × 4"	8" × 8" × 4"

- 4. Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
- 5. Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
- 6. Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
- 7. Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

- 8. Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
- 9. When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
- 10. Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.
- B. CONSTRUCTION METHODS
- 1. Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
- 2. Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
- 3. Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
- 4. Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
- 5. When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
- 6. Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
- 7. During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
- 8. Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
- 9. Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
- 10. Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
- 11. At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
- 12. Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
- 13. Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
- 14. File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.



# ELECTRICAL DETAILS CONDUITS & NOTES

Operation: Division Standard

ED(1)-14

	<del></del> -							
E:	ed1-14.dgn	DN:		CK:	DW:		CK:	
TxDOT	October 2014	CONT	SECT	CT JOB		HIG	HIGHWAY	
	REVISIONS	0184	01	065		SH 36		
		DIST		COUNTY			SHEET NO.	
		WAC		CORYE	LL		33	

#### A. MATERIAL INFORMATION

- 1. Provide Type XHHW insulated conductors in accordance with Departmental Material Specification (DMS)11040 "Conductors" and Item 620 "Electrical Conductors." Provide conductors as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 620. Color code insulated conductors in conformance with the NEC. Identify grounded (neutral) conductors with white insulation. Identify grounding conductors (ground wires) with green insulation or bare conductors. Identify ungrounded (hot) conductors with any color insulation except green, white, or gray. Keep color scheme consistent throughout the wiring system. Identify conductors 6 American Wire Gauge (AWG) and smaller by continuous color jacket. Identify electrical conductors 4 AWG and larger by continuous color jacket or by colored tape. When identifying conductors with colored tape, mark at least 6 in. of the conductor's insulation with half laps of tape.
- 2. Provide a solid copper 6 AWG grounding electrode conductor to bond the electrical service equipment to the concrete encased grounding electrode or the ground rod at the service location. Connect the grounding electrode conductor to the ground rod with a UL listed connector in accordance with DMS 11040. Connect the grounding electrode conductor to the concrete encased grounding electrode as shown in the plans.
- 3. Where two or more circuits are present in one conduit or enclosure, permanently identify the conductors of each branch circuit by attaching a non-metallic tag around both circuit conductors at each accessible location. Provide tags with two straps, large enough to indicate circuit number, letter, or other identification as shown in the plans. Print circuit identification on the tag with a permanent marker.
- 4. Use listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors for splicing as specified in DMS 11040. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Provide UL listed gel-filled insulating splice covers. Splicing materials, insulating materials, breakaway disconnects, splice covers, and fuse holders are subsidiary to various bid items.
- B. CONSTRUCTION METHODS
- 1. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the conduit system. After installing conductors in conduit, perform conductor pull test. If a conductor cannot be freely pulled, make any needed alterations or repairs at no additional cost to the department. Perform insulation resistance tests in accordance with Item 620. Coordinate with the Engineer to witness the tests.
- 2. Leave 2 ft. minimum, 3 ft. maximum length for each conductor up to the splice in ground boxes. Leave 3 ft. minimum, 4 ft. maximum length of conductor in ground boxes when pulled through with no splice. Leave 1 ft. minimum, 1.5 ft. maximum length of conductor at enclosures, weatherheads and pole bases.
- 3. Make splices only in junction boxes, ground boxes, pole bases, or electrical enclosures and use only listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors. Insulate splices with heavy wall heat shrink tubing or gel-filled insulating splice covers to provide a watertight splice. Overlap conductor insulation with heat shrink tubing a minimum of 2 in. past both sides of the splice. Where heat shrink tubing may not shrink sufficiently to provide a watertight seal around the individual conductors, prior to heating the tubing, increase the diameter of the conductor insulation using hot melt adhesive tape to provide a watertight seal between the individual conductors and the heat shrink tubing. Ensure the tape extends past the heat shrink tubing. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Heat shrink tubing that appears to have been burned, or overheated, is considered defective and must be replaced.
- Size and install gel-filled insulating splice covers according to manufacturer's specifications when used in place of heat shrink tubing.
- 5. Wire nuts with factory applied waterproof sealant may be used for 8 AWG or smaller conductors in above ground junction boxes, but not in pole bases or ground boxes. Install wire nuts in an upright position to prevent the accumulation of water.
- 6. Support conductors in illumination poles with a J-hook at the top of the pole.
- 7. When terminating conductors, remove the insulation and jacketing material without nicking the individual strands of the conductor. Conductors with nicked individual conductor strands or removed strands will be considered damaged.
- 8. Replace conductors and cables that are damaged beyond repair or that fail an insulation resistance test at no additional cost to the department.
- Do not repair damaged conductors with duct tape, electrical tape, or wire nuts. Use only approved splicing methods.
- 10. Do not terminate more than one conductor under a single connector, unless the connector is rated for multiple conductors. Do not exceed the pressure connector's listing for maximum number and size of conductors allowed.
- 11. Install breakaway connectors on conductors bid under Item 620 whenever those conductors pass through a breakaway support device. Follow manufacturer's instructions when terminating conductors to breakaway connectors. Properly torque threaded connections. Proper terminations are critical to the safe operation of breakaway devices. Trim waterproofing boots on breakaway connectors to fit snugly around the conductor to ensure waterproof connection. Only one conductor may enter a single opening in a boot. Provide waterproof boots with the correct number of openings. Leave unused openings factory sealed. Use prequalified breakaway connectors as shown on the MPL.

12. Provide and install a separate stranded equipment grounding conductor (EGC) in all conduits that contain circuit wiring of 50 volts or more. Unless shown elsewhere, size the EGC to be the same size as the largest current carrying conductor contained in the conduit. Ensure all EGCs are bonded together at every accessible location. For traffic signal installations, provide a minimum size 8 AWG EGC. The EGC is paid for under Item 620.

#### C. TEMPORARY WIRING


- Install temporary conductors and electrical equipment in accordance with the NEC article "Temporary Installations" and Department standard sheets.
- 2. Provide a ground fault circuit interrupter (GFCI) for power outlets for portable electrical equipment, power tools, ice machines, ice storage bins and refrigerators located outdoors at grade. GFCI may be any one of the following: molded cord and plug set, receptacle, or circuit breaker type.
- Use listed wire nuts with factory applied sealant for temporary wiring where approved.
- 4. Enclose conductor splices within a listed enclosure or ground box, or ensure the splices are more than 10 ft. above grade vertically and more than 5 ft. horizontally from any metal structure. Where installing temporary conductors in areas subject to vehicle traffic or mobile construction equipment, ensure the vertical clearance to ground is at least 18 ft. when measured at the lowest point. Ground messenger wires that support power conductors in conformance with the NEC.
- Protect and when necessary repair any existing electrical conduits uncovered during the construction process in a timely manner and in conformance with the NEC.


#### GROUND RODS & GROUNDING ELECTRODES

- A. MATERIAL INFORMATION
- 1. Provide and install a grounding electrode at electrical services. Provide ground rods according to DMS 11040 and the plans. Larger diameter or longer length rods may be called for in some specific locations, see the individual plans sheets. Concrete encased grounding electrodes may be called for in specific locations including electrical service, see individual plan sheets.


#### B. CONSTRUCTION METHODS

- 1. Furnish auxiliary ground rods for lightning protection and install in soil, concrete, or both, as called for in the plans. For ground rods installed in concrete, ensure the connection of the conductor to the ground rod is readily accessible for inspection or repairs. For ground rods installed in soil, ensure that the upper end is between 2 to 4 in. below finished grade.
- 2. Do not place ground rods in the same drilled hole as a timber pole.
- Install ground rods so the imprinted part number is at the upper end of the rod.
- 4. Remove all non-conductive coatings such as concrete splatter from the rod at the clamp location.
- Route all conductors as short and straight as possible for connection to lightning protection ground rods. When a bend is required, ensure a minimum radius bend of four inches for these conductors.
- 6. Unless otherwise called for in the plans, protect grounding electrode conductors with non-metallic conduit. When protecting grounding electrode conductors with metal conduit, provide and install a grounding type bushing and properly sized bonding jumper on each end of the metal conduit.
- 7. Written authorization is required before installing a ground rod in a horizontal trench for rocky soil or a solid rock bottom.







#### SPLICE OPTION 1 Compression Type



SPLICE OPTION 2
Split Bolt Type







#### APRON FOR GROUND BOX

- (1) Uniformly space ends of conduits within the ground box. Position ends of conduits so that ground box walls do not interfere with the installation of grounding bushings or bell end fittings.
- (2) Maintain sufficient space between conduits to allow for proper installation of bushing.
- (3) Place aggregate under the box, not in the box. Aggregate should not encroach on the interior volume of the box.
- (4) Install a grounding bushing on the upper end of all RMC terminating in a ground box. Ground RMC elbows when any part of the elbow is less than 18 in. below the bottom of the ground box. Install a PVC bushing or bell end fitting on the upper end of all PVC conduits terminating in a ground box.


GROUND BOX DIMENSIONS									
TYPE	OUTSIDE DIMENSIONS (INCHES) (Width x Length X Depth)								
Α	12 X 23 X 11								
В	12 X 23 X 22								
С	16 X 29 X 11								
D	16 X 29 X 22								
E	12 X 23 X 17								

GROUND BOX COVER DIMENSIONS										
DIMENSIONS (INCHES)										
TYPE	Н	I	J	К	L	М	N	Р		
A, B & E	23 1/4	23	13 ¾	13 ½	9 %	5 1/8	1 3/8	2		
C & D	30 ½	30 1/4	17 1/2	17 1/4	13 1/4	6 ¾	1 3/8	2		





**END** 



SIDE

GROUND BOX COVER

#### GROUND BOXES A. MATERIALS

- Provide polymer concrete ground boxes measuring 16x30x24 in. (WxLxD) or smaller in accordance with Departmental Material Specification (DMS) 11070 "Ground Boxes" and Item 624 "Ground Boxes."
- 2. Provide Type A, B, C, D, and E ground boxes as shown in the plans, and as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 624.
- 3. Ensure ground box cover is correctly labeled in accordance with DMS 11070.
- 4. Provide larger ground boxes in accordance with Item 624 and as shown in the plans.
- B. CONSTRUCTION METHODS
- Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure aggregate bed is in place and at least 9 inches deep, prior to setting the ground box. Install ground box on top of aggregate.
- Cast ground box aprons in place. Reinforcing steel may be field bent. Ensure the depth
  of concrete for the apron extends from finished grade to the top of the aggregate bed
  under the box. Ground box aprons, including concrete and reinforcing steel, are
  subsidiary to ground boxes when called for by descriptive code.
- 3. Keep bolt holes in the box clear of dirt. Bolt covers down when not working in ground boxes.
- 4. Install all conduits and ells in a neat and workmanlike manner. Uniformly space conduits so grounding bushings and bell end fittings can easily be installed.
- 5. Temporarily seal all conduits in the ground box until conductors are installed.
- 6. Permanently seal conduits immediately after the completion of conductor installation and pull tests. Permanently seal the ends of all conduits with duct seal, expandable foam, or other method as approved. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a sealant.
- 7. When a ground rod is present in a ground box, bond all equipment grounding conductors together and to the ground rod with listed connectors.
- 8. When a type B or D ground box is stacked to meet volume requirements, it is allowable to cut an appropriately sized hole for conduit entry in the side wall at least 18 inches below grade.
- 9. If an existing ground box in the contract has a metal cover, bond the cover to the equipment grounding conductor with a 3 ft. long stranded bonding jumper the same size as the grounding conductor. The bonding jumper is subsidiary to various bid items. Verify existing ground boxes with metal covers are shown on the plans, with notes fully describing the work required.
- 10. If other ground boxes with metal covers are within the project limits but are not part of the contract, the Engineer may direct the Contractor to bond the metal covers, identifying the specific boxes in writing. This work will be paid for separately.
- 11. Bond metal ground box covers to the grounding conductor with a tank ground type lug.



Traffic Operations Division Standard

#### GROUND BOXES

ED(4)-14

			•				
FILE:	ed4-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxD01
© TxD0T	October 2014	CONT	SECT	JOB		HIC	GHWAY
REVISIONS		0184	01	065		SH	36
		DIST		COUNTY			SHEET NO.
		WAC		CORYE	LL		35

#### ELECTRICAL SERVICES NOTES

- 1. Provide new materials. Ensure installation and materials comply with the applicable provisions of the National Electrical Code (NEC) and National Electrical Manufacturers Association (NEMA) standards. Ensure material is Underwriters Laboratories (UL) listed. Provide and install electrical service conduits, conductors, disconnects, contactors, circuit breaker panels, and branch circuit breakers as shown on the Electrical Service Data chart in the plans. Faulty fabrication or poor workmanship in material, equipment, or installation is justification for rejection. Where manufacturers provide warranties and guarantees as a customary trade practice, furnish these to the State.
- 2. Provide electrical services in accordance with Electrical Details standard sheets, Departmental Material Specification (DMS) 11080 "Electrical Services, "DMS 11081 "Electrical Services-Type A," DMS 11082 "Electrical Services-Type C," DMS 11083 "Electrical Services-Type D," DMS 11084 "Electrical Services-Type T," DMS 11085 "Electrical Services-Pedestal (PS)", and Item 628 "Electrical Services" of the Standard Specifications. Provide electrical service types A, C, and D, as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 628. Provide other service types as detailed on the plans.
- Provide all work, materials, services, and any incidentals needed to install a complete electrical service as specified in the plans.
- 4. Coordinate with the Engineer and the utility provider for metering and compliance with utility requirements. Primary line extensions, connection charges, meter charges, and other charges by the utility company to provide power to the location are paid for in accordance with Item 628. Get approval for the costs associated with these charges prior to engaging the utility company to do the work. Consult with the utility provider to determine costs and requirements, and coordinate the work as approved.
- 5. The enclosure manufacturer will provide Master Lock Type 2 with brass tumblers keyed #2195 for all custom electrical enclosures. Installing Contractor is to provide Master Lock #2195 Type 2 with brass tumblers for "off the shelf" enclosures. Master Lock #2195 keys and locks become property of the State. Unless otherwise approved, do not energize electrical service equipment until locks are installed.
- 6. Enclosures with external disconnects that de-energize all equipment inside the enclosure do not need a dead front trim. Protect incoming line terminations from incidental contact as required by the NEC.
- When galvanized is specified for nuts, screws, bolts or miscellaneous hardware, stainless steel may be used.
- 8. Provide wiring and electrical components rated for 75°C. Provide red, black, and white colored XHHW service entrance conductors of minimum size 6 American Wire Gauge (AWG). Identify size 6 AWG conductors by continuous color jacket. Identify electrical conductors sized 4 AWG and larger by continuous color jacket or by colored tape. Mark at least 6 inches of the conductor's insulation with half laps of colored tape, when identifying conductors. Ensure each service entrance conductor exits through a separately bushed non-metallic opening in the weatherhead. The lengths of the conductors outside the weatherhead are to be 12 inches minimum, 18 inches maximum, or as required by utility.
- 9. All electrical service conduit and conductors attached to the electrical service including the riser or the elbow below ground are subsidiary to the electrical service. For an underground utility feed, all service conduit and conductors after the elbow, including service conduit and conductors for the utility pole riser when furnished by the Contractor, will be paid for separately.
- 0. Provide rigid metal conduit (RMC) for all conduits on service, except for the  $V_2$  in. PVC conduit containing the electrical service grounding electrode conductor. Size the service entrance conduit as shown in the plans. Ensure conduit for branch circuit entry to enclosure is the same size as that shown on the layout sheets for branch circuit conduit. Extend all rigid metal conduits a minimum of 6 inches underground and then couple to the type and schedule of the conduit shown on the layout for that particular branch circuit. Install a grounding bushing on the RMC where it terminates in the service enclosure.
- 11. Use of liquidtight flexible metal conduit (LFMC) is allowed between the meter and service enclosure when they are mounted 90 to 180 degrees to each other. Size the LFMC the same size as service entrance conduit. LFMC must not exceed 3 feet in length. Strap LFMC within 1 foot of each end. LFMC less than 12 inches in length need not be strapped. Each end of LFMC must have a grounding bushing or be terminated with a grounding fitting. The LFMC must contain a grounded (neutral) conductor. Ensure any bend in LFMC never exceeds 180 degrees. A pull test is required on all installed conductors, with at least six inches of free conductor movement demonstrated to the satisfaction of the Engineer.
- Ensure all mounting hardware and installation details of services conform to utility company specifications.
- 13. For all electrical service enclosures listed under Item 628 on the MPL, the UL 508 enclosure manufacturers will prepare and submit a schematic drawing unique to each service. Before shipment to the job site, place the applicable laminated schematic drawings and the laminated plan sheet showing the electrical service data chart used to build the enclosure in the enclosure's data pocket. The installing contractor will copy and laminate the actual project plan sheets detailing all equipment and branch circuits supplied by that service. The laminated plan sheets are to be placed in the service enclosure's document pocket. Reduce 11 in. x 17 in. plan sheets to 8  $\frac{1}{2}$  in. x 11 in. before laminating. If the installation differs from the plan sheets, the installing contractor is to redline plan sheets before laminating.
- 14. When providing an "Off The Shelf" Type D or Type T service, provide laminated plan sheets detailing equipment and branch circuits supplied by that service. Reduce 11 in. x 17 in. plan sheets to 8  $\frac{1}{2}$  in. x 11 in before laminating. Deliver these drawings before completion of the work to the Engineer, instead of placing in enclosure that has no door pocket.
- 15. Do not install conduit in the back wall of a service enclosure where it would penetrate the equipment mounting panel inside the enclosure. Provide grounding bushings on all metal conduits, and terminate bonding jumpers to grounding bus. Grounding bushings are not required when the end of the metal conduit is fitted with a conduit sealing hub or threaded boss, such as a meter base hub.

#### SERVICE ASSEMBLY ENCLOSURE

- 1. Provide threaded hub for all conduit entries into the top of enclosure.
- 2. Type galvanized steel (GS) enclosures may be used for Type C panelboards and for Type D and T services that do not use an enclosure mounted photocell or lighting contactor. Provide GS enclosures in accordance with DMS 11080, 11082, 11083, and 11084.
- 3. Provide aluminum (AL) and stainless steel (SS) enclosures for Types A, C, and D in accordance with DMS 11080, 11081, 11082, 11083, and 11084. Do not paint stainless steel.
- 4.Provide pedestal service (PS) enclosures in accordance with ED(9) and DMS 11080 and 11085. Do not provide GS pedestal services. If GS is shown in the PS descriptive code, provide an AL enclosure.

#### MAIN DISCONNECT & BRANCH CIRCUIT BREAKERS


- 1. Field drill flange-mounted remote operator handle if needed, to ensure handle is lockable in both the "On" and "Off" positions.
- 2. When the utility company provides a transformer larger than 50 KVA, verify that the available fault current is less than the circuit breaker's ampere interrupting capacity (AIC) rating and provide documentation from the electric utility provider to the Engineer.


#### PHOTOELECTRIC CONTROL

1. Provide photocell as listed on the MPL. Move, adjust, or shield the photocell from stray or ambient night time light to ensure proper operation. Mount photocell facing north when practical. Mount top of pole photocells as shown on Top Mounted Photocell Detail.

	* ELECTRICAL SERVICE DATA											
Elec. Service ID	Plan Sheet Number	Electrical Service Description	Service Conduit **Size	Service Conductors No./Size	Safety Switch Amps	Main Ckt. Bkr. Pole/Amps	Two-Pole Contractor Amps	Panelbd/ Loadcenter Amp Rating	Branch Circuit ID	Branch Ckt. Bkr. Pole/Amps	Branch Circuit Amps	KVA Load
SB 183	289	ELC SRV TY A 240/480 100(SS)AL(E)SF(U)	2"	3/#2	100	2P/100	100	N/A	Lighting NB	2P/40	26	28.1
									Lighting SB	2P/40	25	
									Underpass	1P/20	15	
NB Access	30	ELC SRV TY D 120/240 060(NS)SS(E)TS(O)	1 1/4"	3/#6	N/A	2P/60		100	Sig. Controller	1P/30	23	5.3
							30		Luminaires	2P/20	9	
									CCTV	1P/20	3	
2nd & Main	58	ELC SRV TY T 120/240 000(NS)GS(N)SP(O)	1 1/4"	3/#6	N/A	N/A	N/A	70	Flashing Beacon 1	1P/20	4	1.0
									Flashing Beacon 2	1P/20	4	


- * Example only, not for construction. All new electrical services must have electrical service data chart specific to that service as shown in the plans.
- ** Verify service conduit size with utility. Size may change due to utility meter requirements. Ensure conduit size meets the National Electrical Code.





#### TOP MOUNTED PHOTOCELL


Install conduit strap maximum 3 feet from box. 5 foot maximum spacing between straps supporting conduit.




Operation

ED (5) - 14


on | DN: TXDOT | CK: TXDOT





SCHEMATIC TYPE A THREE WIRE


SCHEMATIC TYPE C THREE WIRE



SCHEMATIC TYPE D - CUSTOM 120/240 VOLTS - THREE WIRE

	WIRING LEGEND
	Power Wiring
	Control Wiring
—N—	Neutral Conductor
— G—	Equipment grounding conductor-always required

	SCHEMATIC LEGEND
1	Safety Switch (when required)
2	Meter (when required-verify with electric utility provider)
3	Service Assembly Enclosure
4	Main Disconnect Breaker (See Electrical Service Data)
5	Circuit Breaker, 15 Amp (Control Circuit)
6	Auxiliary Enclosure
7	Control Station ("H-O-A" Switch)
8	Photo Electric Control (enclosure- mounted shown)
9	Lighting Contactor
10	Power Distribution Terminal Blocks
11	Neutral Bus
12	Branch Circuit Breaker (See Electrical Service Data)
13	Separate Circuit Breaker Panelboard
14	Load Center
15	Ground Bus



#### SCHEMATIC TYPE T

#### 120/240 VOLTS - THREE WIRE

Galvanized steel-"Buy Off The Shelf" only. When required install photocell top of the pole or on luminaire only, no lighting contractor will be installed.



Traffic Operations Division Standard

ELECTRICAL DETAILS SERVICE ENCLOSURE AND NOTES


ED(6)-14


E:	ed6-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	October 2014	CONT	SECT	JOB		HIGHWAY	
	REVISIONS	0184	01	065 SH		36	
		DIST	COUNTY			SHEET NO.	
		WAC		CORYFI	11		37

3:08:40

#### SUPPORT TYPE STEEL POLE (SP) AND STEEL FRAME (SF)

- 1.Provide steel pole and steel frame supports as per TxDOT Departmental Material Specification (DMS)11080 "Electrical Services." Mount all equipment and conduit on 12 gauge galvanized steel or stainless steel channel strut, 1  $\frac{1}{2}$  in. or 1  $\frac{5}{8}$  in. wide by 1 in. up to 3  $\frac{3}{4}$  in. deep Unistrut, Kindorf, B-line or equal. Bolt or weld all channel and hardware to vertical members as approved. Do not stack channel. File smooth and paint field cut ends of all channel with zinc-rich paint before installing.
- 2. Provide poles for overhead service with an eyebolt or similar fitting for attachment of the service drop to the pole in conformance with the electric utility provider's specifications.
- 3. Provide and install galvanized  $\frac{y_4}{4}$  in. x 18 in. x 4 in. (dia. x length x hook length) anchor bolts for underground service supports. Provide and install galvanized  $\frac{3}{4}$  in. x  $\frac{5}{6}$  in. x 4 in. anchor bolts for overhead service supports. Ensure anchor bolts have 3 in of thread, with  $3 \frac{1}{4}$  in, to  $3 \frac{1}{2}$  in, of the exposed anchor bolt projecting above finished foundation. Provide and install leveling nuts for all anchor bolts.
- 4. Bond one of the anchor bolts to the rebar cage with 6 AWG bare stranded copper conductor. Use listed mechanical connectors rated for embedment in concrete. See Inset B.
- 5. Furnish and install rigid metallic ells in all steel pole and steel frame foundations for all conduits entering the service from underground.
- 6.Use class C concrete for foundations. Ensure reinforcing steel is Grade 60 with 3" of unobstructed concrete cover.
- 7. Drill and tap steel poles and frames for  $\frac{1}{2}$  in. X 13 UNC tank ground fitting. For steel pole service supports, provide and install tank ground fitting 4 in. to 6 in. below electrical service enclosure. Provide properly sized hole through the bottom of the enclosure for the service grounding electrode conductor. Ensure electrical service grounding electrode conductor is as short and straight as possible from the enclosure to the tank ground fitting. For steel frame service supports, provide and install tank ground fitting on steel frame post. Install service grounding electrode conductor in a non-metallic conduit or tubing from the enclosure to the steel frame post. Connect electrical service grounding electrode conductor to the tank ground fitting. See steel frame and steel pole details and Inset Å for more information. Size service entrance conduit and branch circuit conduit as shown in the plans. For underground conduit runs from the electrical service, extend RMC from the service enclosure to an RMC elbow, and then connect the schedule type and size of conduit shown in the plans. Provide and install grounding bushings where RMC terminates in the enclosure. Grounding bushings are not required when RMC is fitted into a sealing hub or threaded boss.
- 8. If Steel pole or frame is painted, bond each separate painted piece with a bonding jumper attached to a tapped hole.
- 9. Provide  $\frac{1}{4}$ " 20 machine screws for bonding. Do not use sheet metal screws. Remove all nonconductive material at contact points. Terminate bonding jumpers with listed devices. Install minimum size 6 AWG stranded copper bonding jumpers. Make up all threaded bonding connections wrench tight.
- 10. Avoid contact of the service drop and service entrance conductors with the metal pole to prevent abrasion of the insulated conductors.
- 11. Shop drawings are not required for service support structure unless specifically stated elsewhere or directed by the Engineer.





SERVICE SUPPORT TYPE SP(U) - UNDERGROUND SERVICE

20' measured from

may require the

grade. Circumtances

electrical service

than the 20" shown, check with utility

before installing.

of service drop

Point of

attachment

support to be taller

White insulation

or color code 6"

insulation with

white tape where

conductor exits

Red insulation

or color code 6"

length of Line 1

of neutral

conductor's

weatherhead.

or Line 2

Varies

SERVICE


ENCLOSURE

conductor's

to 6'

4" (typ.)

**RMC** 



Top of


of pole.



BOTTOM OF POLE


| 1/2 "

1 1/4



TOP VIEW


SERVICE SUPPORT TY SF (0) & SF (U)



DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO JOB ◯TxDOT October 2014 0184 01 065 SH 36 CORYEL

#### TRAFFIC SIGNAL NOTES

- 1. Do not pass luminaire conductors through the signal controller cabinet.
- 2. Include an equipment grounding conductor in all conduits throughout the electrical system. Bond all exposed metal parts to the grounding
- 3. Provide roadway luminaires, when required, in accordance with the material and construction sections of Item 610, "Roadway Illumination Assemblies, "except for performance testing of luminaires. Test installed roadway luminaires for proper operation as a part of the associated traffic signal system test.
- 4. If internally illuminated street name signs are approved for use, ground the fixture to the pole with a 12 AWG green XHHW conductor.
- Bond anchor bolts to rebar cage in two locations using #3 bars or 6 AWG stranded copper conductors. Use listed mechanical connectors rated for embedment in concrete. See TXDOT standard TS-FD for further
- 6. Drill and tap signal poles for  $\frac{1}{2}$  in. X 13 UNC tank ground fitting. Provide and install tank ground fitting 4 in. to 6 in. directly below electrical service enclosure. Provide properly sized hole through the bottom of the enclosure for the service grounding electrode conductor. Connect the electrical service grounding electrode conductor to the tank ground fitting. Ensure electrical service grounding electrode conductor is as short and straight as possible from the enclosure to the tank ground fitting. See Inset A detail for further information. Size service entrance conduit and branch circuit conduit as shown in the plans.
- 7. Mount electrical service enclosure and meter to signal pole with stainless steel bands. Ensure bands are a minimum width of  $\frac{3}{4}$  in. Secure enclosures to bands using two-bolt brackets. Install brackets near top and bottom of each enclosure. Install properly sized stainless steel washers on each bolt in the enclosure. Band or drill and tap properly sized stand-off straps to signal pole for attaching conduit.
- 8. Conduct pull tests and insulation resistance tests on all illumination and power conductors as required in Item 620 "Electrical Conductors" and ED(3). To prevent electronics damage, do not conduct insulation resistance tests on traffic signal cables after termination.
- 9. Lock all enclosures and bolt down all ground box covers before applying power to the signal installation.
- 10. Terminate conduits entering the top of enclosures with a conduit-sealing hub or threaded boss such as meter hub. Install a grounding bushing on all metal conduits not connected to conduit-sealing hub or threaded boss. Bond the grounding bushing to the ground bus with a bonding jumper. Seal all conduits entering enclosures with duct seal or expanding foam. Do not use silicone to seal conduit ends.
- 11. For all conduits, ensure the burial depth is a minimum of 18". Ensure the minimum burial depth for conduit placed under a roadway is 24".



#### SIGNAL POLE WITH SERVICE

Type T electrical service mounted on signal pole shown as an example. See electrical details, layout sheets, and electrical service data chart for

SIGNAL CONTROLLER FRONT VIEW

SIGNAL POLE



Traffic Operation: Division Standard

#### ELECTRICAL DETAILS TYPICAL TRAFFIC SIGNAL SYSTEM DETAILS

ED(8) - 14

ed8-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
CTxDOT October 2014	CONT	SECT	JOB		HIO	GHWAY	
REVISIONS	0184	01	065		SH	SH 36	
	DIST	COUNTY		SHEET NO.			
	WAC		CORYE	LL		39	


SIGNAL CONTROLLER SIDE VIEW


See TS-CF standard for conduit and grounding requirements. See layout sheets for ground box locations and any additional conduits that are required.

12/20/2021 3:08:41 PM T:\WACTRAFF\TRAFFIC\T

#### PEDESTAL SERVICE NOTES


- 1. Manufacture pedestal electrical services in accordance with Departmental Material Specifications (DMS)11080 "Electrical Services", 11085 "Electrical Services-Pedestal (PS)" and Item 628 "Electrical Services. "Provide pedestal electrical services as listed on the Material Producers list (MPL) on the Department's web site under "Roadway Illumination and Electrical Supplies," Item 628. Ensure all mounting hardware and installation details of services meet utility company specifications. Contact the local utility company for approval of pedestal details prior to installing the electrical pedestal service. Submit any changes required by the utility company prior to manufacturing the pedestal enclosure.
- 2. When a meter socket is required, provide a socket with a minimum 100 amp rating that complies with local utility requirements.
- 3. Provide Class A or C concrete for pedestal service foundations in accordance with Item 420, "Concrete Substructures," except that concrete will not be paid for directly but is considered subsidiary to Item 628.
- 4. Provide #4 reinforcing steel for foundations in accordance with Item 440, "Reinforcement for Concrete."
- 5. Install  $\frac{1}{2}$  in, X 2  $\frac{1}{16}$  in, minimum length concrete single expansion type anchors for mounting pedestal enclosure to foundation. Anchor location to match mounting holes in each corner of enclosure. Secure each of the four corners of the pedestal enclosure to the anchors in the foundation with a  $\frac{1}{2}$  in, galvanized or stainless steel machine thread bolt, a properly sized locknut and a flat washer.
- 6. Finish top of concrete foundation in a neat and workmanlike manner. If leveling washers are used, ensure no more than  $\frac{1}{16}$  in, gap at any corner. Do not exceed a maximum dip or rise in the foundation of  $\frac{1}{16}$  in, per foot. When properly installed, ensure the top of the service enclosure is level front to back and side to side within  $\frac{1}{16}$  in. Repair rocking or movement of the service enclosure at no additional cost to the department.
- 7. Do not use liquidtight flexible metal conduit (LFMC) on pedestal type services.
- 8. Ensure all elbows in the foundation are sized as per utility provider's conduit requirements for underground conduit and feeders. PVC extensions may be installed provided the ends of the rigid metal conduits are more than 2 in. below the top of the concrete foundation. Where extension conduits are metal, grounding bushings must be installed with a bonding jumper properly terminated.





SECTION A-A

ANCHOR BOLT DETAIL



TYPE C shown, TYPE A similar except that TYPE A shall have individual circuit breakers (CB) mounted on an equipment mounting panel. CB Handles shall protrude through hinged deadfront trim.

	LEGEND								
1	Meter Socket, (when required)								
2	Meter Socket Window, (when required)								
3	Equipment Mounting Panel								
4	Photo Electric Control Window, (When required)								
5	Hinged Deadfront Trim								
6	Load Side Conduit Trim								
7	Line Side Conduit Area								
8	Utility Access Door, with handle								
9	Pedestal Door								
10	Hinged Meter Access								
11	Control Station (H-O-A Switch)								
12	Main Disconnect								
13	Branch Circuit Breakers								
14	Copper Clad Ground Rod - 5/8" X 10'								



Traffic Operations Division Standard

ELECTRICAL DETAILS
ELECTRICAL SERVICE SUPPORT
PEDESTAL SERVICE TYPE PS

ED(9)-14

ILE:	ed9-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
C) TxDOT	October 2014	CONT	SECT	JOB		н	GHWAY	
	REVISIONS		01	065		SI	SH 36	
			COUNTY			SHEET NO.		
		WAC		CORYE	LL		40	


No warranty of any for the conversion

Practice Act". responsibility

e of this standard i de by TxDOI for any madardSharq-bara

#### TIMBER POLE (TP) SERVICE SUPPORT NOTES

- Ensure electrical service support is a class 5 treated timber pole as per Item 627 "Treated Timber Poles." Embed timber pole to depth required in Item 627.
- Conduit and electrical conductors attached to the electrical service pole and underground within 12 in. of service pole are not paid for directly but are subsidiary to the electrial service.
- 3. Install pole-top mounted photocell (T) on north side of pole, or in service enclosure (E) as required. See Electrical Service Data chart in plan set.
- 4. Gain pole as required to provide flat surface for each channel. Gain timber pole to  $\frac{1}{18}$  in. max. depth and 1  $\frac{1}{18}$  in. max. height. Gain pole in a neat and workmanlike manner.
- 5. Mount meter and service equipment on stainless steel or galvanized channel (Unistrut, Kindorf, or equal). Provide channel sized 1 in. to  $3\,\frac{3}{4}$  i maximum depth, and  $1\!\frac{1}{2}$  in. to  $1\!\frac{5}{6}$  in. maximum width. File smooth the cut ends of galvanized channel and paint with zinc rich paint before installing on pole. Secure each channel section to timber pole with two galvanized or SS lag bolts,  $\frac{1}{4}$  in. minimum diameter by  $1\!\frac{1}{2}$  in. minimum length. Use a galvanized or SS flat washer on each lag bolt. Do not stack channel.
- When excess length must be trimmed from poles, trim from the top end only.
- (1) Class 5 pole, height as required
- ② Service drop from utility company (attached below weatherhead)
- 3 Service conduit (RMC) and service entrance conductors - One Red, One Black, One White (See Electrical Service Data)
- (4) Safety switch (when required)
- (5) Meter (when required)
- (6) Service enclosure
- (7) 6 AWG bare grounding electrode conductor in ½ in. PVC to ground rod extend ½ in. PVC 6 in. underground.
- (8) % in. x 8 ft. Copper clad ground rod drive ground rod to a depth of 2 in. to 4 in. below grade.
- 9 RMC same size as branch circuit conduit.
- See pole-top mounted photocell detail on ED(5).
- (1) When required by the serving utility provide bare 6 AWG copper conductor. Run wire from pole top to butt wrap or copper butt plate. Protect conductor with non-conductive material to a height of 8 ft. above finished grade.
- (2) When required by utility, cut top of pole at an angle to enhance rain run off.




#### SERVICE SUPPORT TYPE TP (O)

#### GRANITE CONCRETE (GC) & OTHER CONCRETE (OC) NOTES


Ensure electrical service support structures bid as type Granite Concrete (GC) or Other Concrete (OC) meet the following requirements.

- Provide GC and OC poles that meet the requirements of DMS 11080 "Electrical Services."
- 2. Provide prestressed concrete poles suitable for direct embedment into the ground without special foundations.
- 3. Verify poles are marked as required on DMS 11080. Location of marking should be approximately 4' above final grade. Use the two-point pickup locations when handling pole in horizontal position, and one-point pickup location for use in raising the pole to a vertical position. These marks are small but conspicuous.
- 4. Embed poles 42 in. or 10% of the length plus 2 ft., whichever is greater.
- Ensure all installation details of services are in accordance with utility company specifications.
- Install a one point rack or eye bolt bracket 6 inches to 12 inches below the weatherhead as an overhead service drop anchoring point for the electric utility.
- 7. Furnish and install galvanized or stainless steel channel strut 1  $\frac{1}{2}$  in, or 1  $\frac{5}{8}$  in. wide by 1 in. up to 3  $\frac{3}{4}$  in. deep (Unistrut, Kindorf, B-line or equal). Attach channel strut with stainless steel concrete anchors (max. 1" depth), square U-bolts or back to back channel strut with long bolts, or other secure mounting as approved by the Engineer. Ensure bolts are galvanized in accordance with ASTM A153. Do not stack channel struts.
- 8. Backfill the holes thoroughly by tamping in 6 in. lifts. After tamping to grade, place additional backfill material in a 6 inch high cone around the pole to allow for settling. Use material equal in composition and density to the surrounding area. Backfilling will not be paid for directly but is subsidiary to various bid items.




#### CONCRETE SERVICE SUPPORT

Overhead(0)




#### CONCRETE SERVICE SUPPORT

Underground (U)



#### DETAIL A

See Note 7. Before installing channel that has been cut, file sharp edges and paint with zinc-rich paint. Ensure there is no paint splatter on the pole.



0184 01

WAC

065

CORYELL

SH 36

41

#### ROADWAY ILLUMINATION ASSEMBLY NOTES

- Details apply to roadway lighting installations bid or referenced under Item 610, "Roadway Illumination Assemblies."
  Provide, furnish, and install all other materials not shown on the plans which may be necessary for complete and proper
  construction. Where manufacturers provide warranties or guarantees as a customary trade practice, furnish to the State
  such warranties or guarantees.
- 2. The locations of poles and fixtures may be shifted by the Engineer to accommodate local conditions. Install or remove poles and luminaires located near overhead electrical lines using established industry and utility safety practices and in accordance with laws governing such work. Consult with the appropriate utility company prior to beginning such work.
- 3. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC),TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association, Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection.
- 4. Provide Roadway Illumination Light Fixtures as per TxDOT Departmental Material Specification (DMS) 11010, Item 610, and as shown on the Material Producers List (MPL) for Roadway Illumination and Electrical Supplies.
- 5. Fabricate steel roadway illumination poles in accordance with Roadway Illumination Poles (RIP) standards and Item 610. Poles fabricated according to RIP standards do not require shop drawing submittals.
  - a. Alternate designs to RIP standards or the use of aluminum to fabricate poles will require the submission of shop drawings electronically. For instructions on submitting shop drawings electronically see "Guide to Electronic Shop Drawing Submittal" on the TxDOT web site.
  - b. Limitations on use of the RIP standard: The RIP standard details were developed for installations in locations where the 3-second gust basic maximum wind speed is 110 mph, and where the elevation of the base of the pole is less than (i.e. not more than) 25′ above the elevation of the surrounding terrain, in accordance with the "AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals," 6th Edition (2013) of the AASHTO Design Specifications. For poles to be installed in regions where the maximum basic wind speed exceeds 110 mph or to be mounted more than 25′ above the surrounding terrain, provide poles meeting the following requirements:
    - i. Submittals. Following the electronic shop drawing submittal process (see Guide to Electronic Shop Drawing Submittal on the TxDOT web site), submit to the Engineer for approval fabrication drawings and calculations for the poles, sealed by a Texas licensed professional engineer (P.E.).
    - ii. Luminaire Structural Support Requirements. Provide Light poles, arms, and anchor bolt assemblies with a 25 year design life to safely resist dead loads, ice loads and the required basic wind speeds at the location of installation in accordance with the 6th edition (2013) of the AASHTO Design Specifications. For transformer base poles, include transformer base and connecting hardware in calculations and shop drawing submittals. Structurally test all transformer bases to resist the theoretical plastic moment capacity of the pole. Submit certification of the plastic moment load test and FHWA breakoway requirement test of the model of base being furnished with the shop drawings. Show breakoway base model number, manufacturer's name, and logo on shop drawings. Include on manufacturer's shop drawings the ASTM designations for all materials to be used.
- 6. For both transformer and shoe-base type illumination poles, provide and install double-pole breakaway fuse holders as specified by DMS-11040. Breakaway fuse holders are listed on the MPL for Roadway Illumination and Electrical Supplies under Items 610 & 620. Provide 10 amp time delay fuses for breakaway connectors in light poles, or inside the light fixture for underpass luminaires. In each pole, connect luminaires to the breakaway connector with continuous stranded 12 AWG copper conductors as listed on the MPL. Bond all equipment grounding conductors together and to the ground lug in the transformer base or hand hole.
- Tighten anchor bolts for shoe base, concrete traffic barrier base, and bridge mount roadway illumination poles, in accordance with Item 449.
- 8. Install T-Base with following procedure:
  - a. Anchor Bolt Tightening.
    - i. Coat the threads of the anchor bolts with electrically conductive lubricant.
    - ii. Place the T-base over the anchor bolts. Foundation must be level and flat. The maximum permissible gap under any one corner of the t-base is 1/8" before nuts are tightened.
    - iii.Coat the bearing surfaces of the nuts and washers with electrically conductive lubricant. Install (1) 1/2" hold down washer, (1) lock washer, and (1) nut on each anchor bolt. Turn the nuts onto the bolts so that each is hand-tight against the washer.
    - iv. Using a torque wrench, tighten each nut to 150 ft-Ib. Uniform contact is required between the foundation and the T-base in the corner regions of the T-base, and all corner gaps must be closed after applying torque. If a gap still exists after torquing to 150 ft-Ibs, continue torquing each bolt incrementally until gap is closed or maximum allowable torque of 250 ft. pound is reached, whichever comes first. If 250 ft-Ibs is not enough to close the gap the foundation must be leveled. Gaps along the straight sides of the T-bases and the foundation.
    - v. Check top of T-base for level. If not level then foundation must be leveled.
  - b. Top Bolt Procedure
    - i. Erect pole over T-base with crane. Coat bolts, nuts, washers, and lock washers with electrically conductive lubricant.


- ii. Install bolts and 1/2" connecting washers from the inside of the T-base, thread up through the pole base. Install flat washers, lock washers and nuts snug tight according to Item 447, "Structural Bolting."
- iii. Tighten each nut to 150 ft-Ib. using a torque wrench.
- c. Level and Plumb
  - Ensure pole is plumb and mast arm is perpendicular to the roadway according to plans to within 5 degrees.
- 9. Construct luminaire pole foundations in accordance with Item 416, "Drilled Shaft Foundations," and TxDOT standard sheet RID(2).
- 10. Provide and install underpass luminaires in accordance with Item 610, DMS-11010, and TxDOT standard sheet RID(3). Typical luminaire size for underpass luminaires is 150W HPS or 150W EQ LED.
- 11. Mount luminaires on arms level as shown by the luminaire level indicator.
- 12. Orient luminaires perpendicular to the roadway intended to be lit unless otherwise shown on the plans.

#### Wiring Diagram Notes:


- Use 1/2 in.-13 UNC threaded, copper or tin-plated copper, pole bonding connector, sized appropriately for conductors, bonded to T-base, or use ground lug in handhole as available.
- Use pre-qualified two-pole breakaway connectors for all luminaire pole installations. For luminaires fed by a circuit with a neutral conductor, use double pole breakaway connectors with the neutral side unfused and marked white.
- (3) Split Bolt or other connector.

#### Decorative LED Lighting Notes:

- LED Drivers in Remote Outdoor enclosures (for drivers that do not include an enclosure as part of a factory assembly):
  - a. Provide NEMA 3R outdoor enclosure or as approved.
  - b. Install enclosure at least 12" above ground or other horizontal surface. Mount vertically or on ceiling, and avoid direct sun where possible.
  - Install drivers with at least 2 inches of space from enclosure walls.
  - d. For multiple drivers in an enclosure, provide at least 4 inches side to side and 1 inch end to end from other drivers or electronic equipment
  - e. For drivers mounted on back wall of enclosure, mount enclosure on 1 5/8" strut or other standoff to dissipate heat, or mount driver to side of the enclosure or to the metal cover.
  - f. Provide remote drivers with a maximum of 100 watts
  - g. Provide drivers with documentation of 100,000 hr lifetime at Tcase of 65C or higher.



Driver Spacing In Remote Enclosure



G = Grounding Conductor

#### TYPICAL WIRING DIAGRAM

LUMINAIRES SERVED AT 480V ON 240/480 VOLT SERVICE OR LUMINAIRES SERVED AT 240V FOR 120/240 VOLT SERVICE.



LIL	, <b>,</b> ,	•	<b>Z V</b>		
LE: rid1-20.dgn	DN:		CK:	DW:	CK:
© TxDOT January 2007	CONT	SECT	JOB		HIGHWAY
REVISIONS	0184	01	065		SH 36
-17 -20	DIST		COUNTY	•	SHEET NO.
-20	WAC		CORVE	1	12


DID(11-20

Traffic Safety Division Standard

72A


STRAIN POLE DESCRIPTION	Pole Type	Found- ation Type	Maximum Permissible Span Wire Load (lbs.)
26' Pole	Α	36-A	5200
30' Pole	В	36-A	4600
30' Pole with Lum.	В	36-A	4400
30' Pole with 20' Mast Arm	С	36-B	5600
30' Pole with 24' Mast Arm	С	36-B	5500
30' Pole with 28' Mast Arm	С	36-B	5300
30' Pole with 32' Mast Arm	С	36-B	5100
30' Pole with 36' Mast Arm	С	36-B	4900
30' Pole with 20' Mast Arm & Lum.	С	36-B	5300
30' Pole with 24' Mast Arm & Lum.	С	36-B	5200
30' Pole with 28' Mast Arm & Lum.	С	36-B	5000
30' Pole with 32' Mast Arm & Lum.	С	36-B	4800
30' Pole with 36' Mast Arm & Lum.	С	36-B	4500
34' Pole	D	36-B	5600
34' Pole with Lum.	D	36-B	5400

② Numbers on Load Span Charts indicate the number of signal heads on the span. The total span wire design load is based on one 5-section head and one or more additional 3-section head(s). Design wind pressures on cables are assumed as 1.0 lb/ft. Weight of span wire cables (one per signal head) is assumed as 0.65 lb/ft which includes an allowance for conductor cables and miscellaneous hardware. The effect of the sway cable on load distribution is ignored as it is assumed to break at design wind conditions. When a pole supports 2 spans, the span wire design loads for both spans should be added vectorially to determine the design load for that pole.



#### STRAIN POLE ELEVATIONS HORIZONTAL SIGNALS

(Mast arms are not used with vertical signals)



4000 3000 Signal Heads Span (ft.)

#### ²SIGNALS WITH 12-INCH LENS

5000				,			,	, ,		
				/		.'/			//	,
( sq ) 4000	No. of Signal	Heads-	7	,	//			/		
			/	//			//			
ر د		4	3	//	,5/	2/	5	<u>/</u> 4		
Span Wire Design Load		11	6	161	4	3/	//	3	2	
ā		1//	///				//			
± 2000	11							2		
Spa		///		/		. /				
1000	000		-	3				C		021
			-	_	(ft.	)		•	-	-
	2		-4		_		<b>.</b>			

#### SIGNALS WITH 8-INCH LENS

Signal Head Type	Wt. Per Head	Wind Area �
5-Section, 12" Lens	125 lbs	9.6 sq. ft.
5-Section, 8" Lens	70 lbs	4.8 sq. ft.
3-Section, 12" Lens	75 lbs	5.64 sq. ft.
3-Section 8" Lens	45 lbc	3 0 co f+

♦ Effective projected design wind area (actual area times drag coefficient)

- Sag = 4'-6" (26' or 30' Pole) Sag = 8'-0" (30' or 34' Pole) - - Sag = 11'-6" (34' Pole)

		ROUND	POLES		POLYGONAL POLES			
Pole Type	D _B	D _T	(4)+hk	Н	D _B	Dτ	(4)+hk	H
1,700	ir.	in.	in.	ft.	in.	in.	in.	ft.
Α	12.5	8.9	.239	26	13.0	9.0	.239	26
В	13.5	9.3	.239	30	14.0	9.0	.239	30
С	15.5	11.3	.239	30	16.0	11.0	.239	30
D	15.5	10.7	. 239	34	16.0	11.0	.239	34

 $D_B$  = Pole Base O.D. D T = Pole Top O.D. H = Pole Height

#### SHIPPING PARTS LIST

Poles	(Without Traff	ic Signal Arm)					
	Strain poles with	n Luminaire	Strain poles without Luminaire				
Pole Type	Ship each pole w hardware attached handhole at base, simplex and 1 pig	, pole cap, 2 clar		Ship each pole with the following hardware attached: handhole at base, pole cap and I pipe plug.			
	Description	Designation	Quantity	Description	Designation	Quantity	
А				26' Strain Pole	SP 26 A-80		
В	30' Strain Pole	SPL 30 B-80		30' Strain Pole	SP 30 B-80		
D	34' Strain Pole	SPL 34 D-80		34' Strain Pole SP 34 D-8			

Dolos	/W:+b	Troff:	C:anal	A \
Poles	CWITH	Traffic	Stanat	Arm)

	Strain poles v	ith Luminaire		Strain poles w	ithout Luminaire	:	
Pole Type	Ship each pole w hardware attached handhole at base, simplex and 3 pig	j: pole cap, clamp		Ship each pole with the following hardware attached: handhole at base, pole cap and 3 pipe plugs.			
	Description	Designation	Quantity	Description	Designation	Quantity	
С	C 30' SPw/TS Arm SPL 30 C-80		30' SPw/TS Arm	SP 30 C-80			

#### Traffic Signal Arms (For Type C poles)

	Type I Arm (	(1 Signal)	Type II Arm	(2 Signals)	Type III Arm (	3 Signals)
Nominal Arm Length	the following attached:	tors, 1 clamp Connectors and 1 clamp Connectors and 1 clamp		the following hattached: 2 Bracket Assem Connectors and with bolts and		
ft.	Designation	Quantity	uantity Designation Quant		Designation	Quantity
20	201-80					
24	24 I -80		24 П -80			
28	28 I -80		28 П -80	28 П -80		
32			32 П -80		32 III -80	
36			36 П -80	36 П -80		

#### <u>Anchor Bolt Assemblies</u> (1 per pole)

Anchor Bolt Diameter	Anchor Bolt	Templates may be remo for shipment.	ove
	Length	Quantity	
1 3/4"	3′-10"		_
2"	4'-3"		E o
			8 / т

4 Thickness shown are minimum, thicker materials

may be used.

<u>Luminaire Arms</u>	
Nominal Arm Length	Quantity
8' Arm	

ach Anchor Bolt Assembly consists of the following: Top and Bottom templates, 4 anchor bolts, 8 nuts, 3 flat washers, and 4 nut anchor devices (Type 2) per Standard Drawing "TS-FD".


1) See Sheet "DMA-80"

SHEET 1 OF 2

Texas Department of Transportation Traffic Operations Division TRAFFIC SIGNAL SUPPORT STRUCTURES STRAIN POLE ASSEMBLIES


> (80 MPH WIND ZONE) SP-80(1)-12

© TxDOT March 1996	DN: MS		CK: JSY	DW:	BR	CK: JSY
REVISIONS	CONT	SECT	JOB		HIG	HWAY
6-96 1-12	0184	01	065		SH	36
	DIST		COUNTY		s	HEET NO.
	WAC		CORYFI	1		<b>⊿</b> ス









of circumferential base welds.

MATERIALS ASTM A595 Gr.A, A588, A1008 HSLAS Gr.50 Class 2, A1011 HSLAS Gr.50 Class 2, A572 Gr.50 or A1011 SS Gr.50 (1) Round Shafts or Polygonal Shafts® Plates (9) ASTM A36, A588, or A572 Gr.50 Connection Bolts ASTM A325 except where noted Pin Bolts ASTM A325 ASTM A53 Gr.B, A501, A1008 HSLAS-F Gr.50, A1011 HSLAS-F Gr.50 Pipe 9 ASTM A475, 7 Wire Steel Cable Utilities Grade Galvanized steel or stainless steel Misc. Hardware

- ASTM A572, A1008 HSLAS, A1011 HSLAS, A1008 HSLAS-F, A1011 HSLAS-F, or A1011 SS may have higher yield strengths but shall not have less elongation than the grade indicated.
- () ASTM A1011 SS Gr.50 shall also have a minimum elongation of 18 percent in 8 inches or 23 percent in 2 inches. Material thickness in excess of those stipulated under A1011 SS will be acceptable providing the material meets all other A1011 SS requirements and the requirements of this item.

#### **GENERAL NOTES**

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications thereto. Design Wind Speed equals 80 mph plus a 1.3 gust factor. The maximum permissible span wire design loads tabulated are calculated at a stress load of 1.4 times the basic allowable stress. A simultaneous wind on the pole, mast arm, and luminaire is also included.

See standard sheet "DMA-80" for details of clamp-on traffic signal arms, sheet "MA-C" for traffic signal arm connection details, sheet "LUM-A" for luminaire arm and connection details, and sheet "TS-FD" for anchor bolt and foundation details.


Fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of this sheet and Item 686, "Traffic Signal Pole Assemblies (Steel)".

Unless otherwise noted, all parts shall be galvanized in accordance with Item 445, "Galvanizing", after fabrication.

Deviation from the details and dimensions shown herein require submission of shop drowings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.

Foundation Type	I ROLL	Bolt Hole Diameter	Bolt Circle Diameter	Base PL Dim. L x T
36-A	1 3/4"	2"	19"	19" × 1 ¾"
36-B	2"	2 1/4"	21"	21" × 2"

SHEET 2 OF 2



(80 MPH WIND ZONE) SP-80(2)-12

© TxDOT March 1996	DN: MS	CK: JSY DW	: BR CK: JSY
REVISIONS 6-96	CONT SEC	CT JOB	H [ GHWAY
1-12	0184 0	1 065	SH 36
	DIST	COUNTY	SHEET NO.
	WAC	CORYELL	44

3:08:45

FOUNDATION DESIGN TABLE EMBEDDED DRILLED SHAFT LENGTH-ft(4),(5),(6) TEXAS CONE PENETROMETER RE INFORCING FOUNDATION
DESIGN
LOAD STEEL LOAD BOL T CIR TYPE SHAFT TYPICAL APPLICATION Fy (ksi) SPIRAL ANCHOR VERT BARS MOMENT SHEAR K-ft Kips N blows/ft DIA TYPE 10 40 15 DIA Pedestal pole, pedestal mounted 24-A 24' 5.3 3∕4 " 36 12 3/4' 10 #2 at 12 5.7 4.5 controller. 30-A 30" 8- #9 |#3 at 6 11.3 10.3 8.0 1 1/2 ' 55 17" 2 87 3 Mast arm assembly. (see Selection Table) Mast arm assembly. (see Selection Table) 30' strain pole with or without luminaire 36-A 36" 10-#9|#3 at 6 13.2 12.0 9.4 1 3/4" 55 19" 2 131 Mast arm assembly. (see Selection Table) Strain pole taller than 30' & strain pole with mast arm 2" 55 21" 36-B 36" 12-#9 #3 at 6" 15.2 13.6 10.4 2 190 55 42-A 42" |14- #9| #3 a+ 6" 17.4 15.6 11.9 2 1/4" 23" 2 271 Mast arm assembly. (see Selection Table)

	FOUNDATION SELE ARM PLUS IL	CTION TABL SN SUPPORT	E FOR STANDA ASSEMBLIES	ARD MAST (ft)	
		FDN 30-A	FDN 36-A	FDN 36-B	FDN 42-A
_	MAX SINGLE ARM LENGTH	32′	48′		
IGN D		24′ X 24′			
DES1 SPEEC		28' X 28'			
] <u> </u>	MAXIMUM DOUBLE ARM	32' X 28'	32' X 32'		
80 MPH WIND	LENGTH COMBINATIONS		36′ X 36′		
∣໘⋝			40′ X 36′		
~			44′ X 28′	44′ X 36′	
z	MAX SINGLE ARM LENGTH		36′	44'	
DESIGN SPEED			24' X 24'		
			28' X 28'		
] H	MAXIMUM DOUBLE ARM		32' X 24'	32' X 32'	
₹2	LENGTH COMBINATIONS			36′ X 36′	
OO MPH WIND				40′ ×24′	40' X 36'
-					44′ × 36′
	EXAMPLE:				

Span Wires

Clomp Arm Length

Supporting

TI SN

Sway Cable

1. For 80mph design wind speed, foundation

30-A can support up to a 32' arm with

2. For 100mph design wind speed, foundation

36-A can support a single 36' mast arm.

Type 2

**NUT ANCHOR** (TYPE 2)

Thickness =

d/4 (inch) min.

<2 Sides</p>

2 Flat Washers

per Anchor Bolt

another arm up to 28°

-Heavy Hex Nut (Typ)

¼" thk. min. Circular Steel

Top Template

Lengt read Min.

ze Thr 6" |

Type

R=d-

1 ½" Min

Circular Steel Bottom Template

HOOKED ANCHOR

(TYPE 1)

ANCHOR BOLT ASSEMBLY


8 Orient anchor bolts orthogonal with the fixed arm direction to

ensure that two bolts are in

tension under dead load.

(Omit bottom template

for FDN 24-A)



embedded shaft.

Luminaire Arm (optional)

Wire loads.

TYPICAL STRAIN POLE

**ASSEMBLY** 

Fixed Arm Length

Luminaire

Arm (optional)

8'-0"

(8)

TYPICAL MAST ARM

**ASSEMBLY** 

Anchor bolts to be

approximately oriented

tension from the Span

so that two bolts are in

Ignore the top 1' of soil.

#### NOTES:

- 1 Anchor bolt design develops the foundation capacity given under Foundation Design Loads.
- (2) Foundation Design Loads are the allowable moments and shears at the base of the structure.
- (3) Foundations may be listed separately or grouped according to similarity of location and type. Quantities are for the Contractor's information only.
- 4 Field Penetrometer readings at a depth of approximately 3 to 5 feet may be used to adjust shaft lengths.
- (5) If rock is encountered, the Drilled Shaft shall extend a minimum of two diameters into solid rock.
- (6) Decimal lengths in Design Table are to allow interpolation for other penetrometer values. Round to nearest foot for entry into Summary Table.

ANCHOR BOLT & TEMPLATE SIZES											
BOLT DIA LENGTH THREAD THREAD CIRCLE R2 R1											
3∕4 "	1′-6"	3"	_	12 ¾"	7 1/8"	5 % "					
1 1/2"	3′-4"	6"	4"	17"	10"	7"					
1 3/4"	3'-10"	7"	4 1/2 "	19"	11 1/4"	7 3/4"					
2"	4'-3"	8"	5"	21"	12 ½"	8 ½"					
2 1/4"	4'-9"	9"	5 1/2"	23"	13 3/4"	9 1/4"					

(7) Min dimensions given, longer bolts are acceptable.

TOP VIEW

project above concrete

Template

-Spiral

Bars

-Vertical

Diameter

Bolt Circle

Conduit

Steel Template with holes 1/16 " greater

Bond anchor bolts to

than bolt diameter

rebar cage, two

bar or #6 copper

Conduit (See Layout Sheets for diameter.

Orient as directed by

the Engineer. 1 or 2

Vertical Bars (See

Design Table for size

Spiral, 3 flat turns top & 1 flat turn

Table for size & pitch)

bottom. (See Design


required)

locations usina #3

jumper. Mechanical

Listed for concrete

connectors shall be UL




#### **GENERAL NOTES:**

Threads for anchor bolts and nuts shall be in diameter or UNC series for all sizes. Bolts and nuts shall have Class 2A and 2B fit tolerances.

Anchor bolts that are larger than 1" in diameter shall conform to "alloy steel" or "medium-strength mild steel" per Item 449, "Anchor Bolts". Anchor bolts that are 1" in diameter or less shall conform to ASTM A36. Galvanize a minimum of the top end thread length plus 6" for all anchor bolts unless otherwise noted. Exposed washers and exposed nuts

Templates and embedded nuts need not be galvanized. Lubricate and tighten anchor bolts when erecting the structure in accordance with Item 449, "Anchor Bolts".



TRAFFIC SIGNAL POLE FOUNDATION

Texas Department of Transportation

Traffic Operations Division

**TS-FD-12** 

DIxDOT August 1	1995	DN: MS		CK: JSY	DW:	MAO/MMF	CK: JSY/TE
REVISIONS		CONT	SECT	JOB		HIC	HWAY
		0184	01	065		SH	36
		DIST		COUNTY		,	SHEET NO.
		WAC		CORYEL	L		45

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals and interim revisions thereto.

Reinforcing Steel shall conform to Item 440, "Reinforcing Steel".

Concrete shall be Class "C".


rolled or cut threads of 8UN series up to 2" Galvanized nuts shall be tapped after galvanizing.

shall be galvanized. All galvanizing shall be in accordance with Item 445, "Galvanizing".



2/20/202 DATE

concrete is placed. FOUNDATION DETAILS	Tahmina Khan, PE 12
on bottom of drilled hole if material is firm enough to do so when  ELEVATION	(d
Vertical bars may rest Shaft Dia	



of any converits use

is governed by the "Texas Engineering Practice Act". No warranty any purpose whatsoever, TxD01 assumes no responsibility for the other formats or for incorrect results or damages resulting from

is by sto ASTM A27 Gr.65-35 or A148 Gr.80-50,
A576 Gr.1021 ③, or A36 (Arm only)

ASTM A53 Gr.B, A501, A1008
HSLAS-F Gr.50 ④, or A1011 HSLAS-F Gr.50 ④

ASTM A36, A572 Gr.50 ④, or A588

ASTM designations as noted

MATERIALS

- (1) Dimensional limits are given to show acceptable variation in design. All of a Fabricator's production of a particular arm length shall have the same dimensions within specified tolerances.
- ② Any of the materials listed for plates may be used where the drawings do not specify a particular ASTM designation.
- (3) A576 must be suitable for forging and also meet minimum tensile strength of 65 ksi, minimum yield of 35 ksi, and elongation in 2 inches of 22 percent.
- (4) ASTM A572, A1008 HSLAS-F, and A1011 HSLAS-F may have higher yield strengths but shall not have less elongation than the grade indicated.

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Revisions thereto. Design Wind Speed equals 90 mph plus a 1.3 gust factor. Arms are designed to support a 60 lb. luminaire having an effective projected area (actual area times drag coefficient) of 1.6 sq. ft.

Materials and fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. In the absense of specified Fabricaton tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.

Unless otherwise noted, all parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing".

Deviation from the details and dimensions shown herein require submission of shop drawings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.

Each pole simplex fitting shall be supplied with 2 ASTM A325 bolts and 2 lock washers of the size specified. The bolts and lock washers shall be secured to the pole with the other hardware items called for in the plans. When clamp attachment is specified, the Fabricator shall ship the clamp assembly securely attached to the pole at the location shown on the plans.


If clamp assemblies are ordered without poles, the Fabricator shall ship one upper and one lower clamp assembly together in a single package, including all nuts and washers required for the clamps and simplex fittings.




ARM DETAILS

LUM-A-12

C TxDOT August 1995	DN: LEH		CK: JSY	DW: LTT		CK: TEB
96 REVISIONS	CONT	SECT	JOB		ніс	CHWAY
99 12	0184	01	065			36
	DIST		COUNTY	•	,	SHEET NO.
	WAC		CORYEL	.L		46



#### POLE SIMPLEX DETAILS




#### OTHER MATERIALS:

- 1. Pole simplex shall be ASTM A27 GR65-35 or A148 GR80-50 or A576 GR1021. ASTM A576 must be suitable for forging and also meet minimum tensile of 65ksi, minimum yield of 35ksi, and a minimum elongation of 22 percent in 2 inches.
- 2. Welded tabs and backplates shall be ASTM A-36 steel or better.
- 3. Nylon insert locknuts shall conform to ASTM A563.

#### GENERAL NOTES:

- 1. Materials and fabrication shall be in accordance with Standard Sheet "MA-C" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. In the absence of specified fabrication tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.
- 2. All parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing". The throat of the Simplex shall be made free of all rough or sharp edges resulting from the galvanizing process.
- 3. Each simplex fitting shall be supplied with 2 ASTM A325 bolts,  $\frac{1}{2}$  in. X  $\frac{1}{2}$  in. and 2 lock washers. The bolts and lock washers shall be secured to the clamp with the other hardware items. The Fabricator shall ship clamp assembly together in a single package, including all bolts, nuts, and washers required for the clamp and simplex fitting.
- 4. Design conforms to 1994 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals" and interim revisions thereto. Design Wind Speed equals 80 mph plus a 1.3 gust factor. Clamps are designed to support a 60 lb. luminaire having an effective projected area (actual area times drag coefficient) of 1.6 sq.ft.,12 ft. maximum arm length.
- 5. Each assembly shall consist of one upper piece simplex fitting having a smooth lip and one lower piece simplex fitting with the lip removed.
- 6. Approximately 2 in. diameter hole in upper mast arm clamp.



**PROJECTION** 

For 8.9 - 12 inch diameter Signal Poles (Two req'd for each mast arm)




#### CLAMP ON FITTING ASSEMBLY FOR LUMINAIRE MAST ARM


CFA-12

© T×DOT	DN: KAB		CK: RES	DW:	FDN	CK: CAL
REVISIONS -99	CONT	SECT	JOB		HIO	HWAY
-12	0184	01	065		SH	36
	DIST		COUNTY			SHEET NO.
	WAC		CORYEL	.L		47

Backplate louvers based on wind and vibration rating.-


Retroreflective border. See general note 1→






#### FOUR-SECTION HEAD HORIZONTAL OR VERTICAL

**CLUSTER** 






Backplate with

border

retroreflective

Vented backplate with

retroreflective border



#### GENERAL NOTES:

- 1. Backplates are optional for traffic signals and pedestrian hybrid beacons. When backplates are used, a 2-inch wide fluorescent yellow AASHTO Type  $B_{FL}$  or  $C_{FL}$  retroreflective border conforming to TxDOT DMS-8300 is required. Place on all approaches when used.
- 2. Signal head and backplate compatability must be verified by the contractor prior to installation.
- 3. When using backplates on signal heads, venting is preferred to reduce cyclic vibration stress.
- 4. When a vented backplate is used, the retroreflective border must not be placed over the louvers.
- 5. This standard sheet applies to all signal heads with backplates, including but not limited to:
  - Pole mounted
  - Overhead mounted
  - Span wire mounted
  - Mast arm mounted
  - Vertical signal heads

Backplate louvers based on wind and

vibration rating.

-Retroreflective

general note 1

border. See

**BEACON** 

- Horizontal signal heads
- Clustered signal heads
- Pedestrian hybrid beacons



TRAFFIC SIGNAL HEAD WITH BACKPLATE

Traffic Safety Division Standard

TS-BP-20

	_						
FILE: †s-bp-20.dgn	DN: TxDOT		CK: TXDOT DW:		TxDOT ck: TxDO		
CTxDOT June 2020	CONT	SECT	JOB		HIGHWAY		
REVISIONS	0184	01	065		SH	SH 36	
	DIST	COUNTY		SHEET NO.			
	WAC		CORYE	LL		48	

#### EROSION AND SEDIMENT CONTROLS

# PROJECT LIMITS; CSJ 0184-01-065; SH 36 AT FM 107 INTERSECTION LOCATION MAPS; Refer to the TITLE SHEET for project location map. PROJECT DESCRIPTION; CSJ 0184-01-065 SAFETY IMPROVEMENT PROJECTS CONSISTING OF THE INSTALLATION OF FLASHING BEACONS MAJOR SOIL DISTURBING ACTIVITIES; No major soil disturbing activities on this project.

TOTAL PROJECT AREA:

TOTAL AREA TO BE DISTURBED:

0.5 AC

#### EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

CSJ: 0184-01-065

Based on 0.00 AC to be disturbed, identification of existing soil conditions and vegetative cover is not applicable to this project.

#### NAME OF RECEIVING WATERS:

Based on the project scope, identification of receiving waters is not applicable to this project.

#### SOIL STABILIZATION PRACTICES:

TEMPORARY SEEDING
PERMANENT PLANTING, SODDING, OR SEEDING
MULCHING
SOIL RETENTION BLANKET
NATURAL BARRIERS OR BUFFER ZONES
PRESERVATION OF NATURAL RESOURCES

OTHER: TXR 150000, Part III, Section G, 2 Stabilization of disturbed areas must, at a minimum, be initiated immediately whenever any clearing, grading, excavating, or other earth disturbing activities have permanently ceased on any portion of the site, or temporarily ceased on any portion of the site and Willnot resume for a period exceeding 14 calendar days. Temporary stabilization must be completed no more than 14 calendar days after initiation of soil stabilization measures, and final stabilization must be achieved prior to termination of permit coverage.

#### <u>STRUCTURAL PRACTICES</u>; ... (Select T = Temporary or P = Permanent, As Applicable)

T   . :	SILT FENCES	 TIMBER MATTING AT CONSTRUCTION EX
	HAY BALES	 CHANNEL LINERS
	SANDBAG OR ROCK BERMS	 SEDIMENT TRAPS
1	DIVERSION, INTERCEPTOR, OR PERIMETER DIKES	SEDIMENT BASINS
	DIVERSION, INTERCEPTOR, OR PERIMETER SWALES.	 STORM INLET SEDIMENT TRAP
	DIVERSION DIKE AND SWALE COMBINATIONS	 STONE OUTLET STRUCTURES
	PIPE SLOPE DRAINS	 CURBS AND GUTTERS
	PAVED FLUMES	 STORM SEWERS
	ROCK BEDDING AT CONSTRUCTION EXIT	 VELOCITY CONTROL DEVICES
THER:		

#### NARRATIVE-SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:


The order of activities will be as follows:

- 1. Preserve existing vegetative cover as much as possible.
- 2. Repair and upgrade illumination systems.

#### STORM WATER MANAGEMENT:

An integral part of the SWPPP for this project includes the EPIC Sheet, Item 506, Waco District Waters of the US Notes, Waco District Typical Applications for Best Management Practices, Form 218 TxD0T inspection forms, Contractor daily inspection forms, miscellaneous general notes on environmental requirements, TxD0T EC Standards, 2014 Standard Specifications, TxD0T roadway design drawings, SWPPP design and working BMP drawings, Site Manager Data Base, EMS Stage Gate Inspections and the Waco District environmental folders. The requirements of the TxD0T EMS Will be fully implemented including training requirements for Contractors and TxD0T staff.

#### STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING



#### OTHER EROSION AND SEDIMENT CONTROLS:

#### MAINTENANCE:

All erosion and sediment best management practices (BMPs) will be maintained in good working order per the environmental notes, details and standards included as part of the project plans and contract documents. BMP repairs will be made at the earliest possible date, but no later than seven calendar days after the inspection report has been completed and immediately after the ground has dried sufficiently to allow equipment access. BMPs admaged by the Contractor will be repaired or replaced immediately. The installation and repair of BMPs at creeks and outfalls will be given priority.

#### INSPECTION:

TxDOT Form 2118 inspections to support TXRI50000 and 404 permits Will be conducted on a seven day intervalon the same day of the week, until permits are terminated. The Contractor Will provide daily BMP inspection reports on work days. Stage Gate Inspections and other BMP inspections Will be conducted by the District and Area Office Staff based on requirements of the TxDOT Environmental Management System (EMS).

#### WASTE MATERIALS:

Any waste materials generated during construction will be disposed of in accordance with existing federal, state, and local laws.

#### HAZARDOUS WASTE (INCLUDING SPILL REPORTING):

At a minimum, any products in the following categories are considered to be hazardous: Fuels, Lubricating products, Asphalt products, or Concrete curing compounds and any additives. In the event of a spill which may be hazardous, clean-up Will be done in accordance with federal, state, and local regulations. The Contractor will maintain a list of all chemicals and wastes required for the project; including chemicals used by sub-contractors, and Will implement written spill prevention and clean-up plans.

#### SANITARY WASTE:

Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor.

#### OFF SITE VEHICLE TRACKING:

	HAUL ROADS DAMPENED FOR DUST CONTROL
	LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
Χ	EXCESS DIRT ON ROAD REMOVED DAILY
	STABILIZED CONSTRUCTION ENTRANCE


#### REMARKS:

Disposal areas, stockpiles, and haulroads will be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas will not be located in any wetland, waterbody or streambed. Construction staging area and vehicle maintenance area will be constructed by the contractor in a manner to minimize the runoff pollutants.

Furnish one SW3P permit posting sign and sign support as detailed on the SW3P Sheet. Install this sign in a location selected by the Engineer. The sign and support should be removed upon completion of the project and is the property of the Contractor. The purchase of the sign and support, installation, relocation(s) if determined necessary by the Engineer and removal at project end will be by erosion control maintenance force account

#### SEDIMENTATION BASINS:

Since the area disturbed is less than 10 acres, per outfall location, a sedimentation basin is not required,





## STORM WATER POLLUTION PREVENTION PLAN (SW3P)

		WACO		CORYELL		49
		DIST		COUNTY		SHEET NO.
6	TEXAS	0184	01 065		SH 36	
FED.RD. IV. NO.	STATE	CONT	SECT JOB			HIGHWAY

ЭOС

- 1. Prior to TxDOT allowing the Contractor to start construction, the Contractor will provide the required storm water and 404 permit documentation and support activities, including but not limited to the following:
  - Provide a list of all chemicals, construction and waste products that will be generated, stored or brought upon TxDOT ROW. The list includes expected construction debris, sanitary wastes, construction chemicals and petroleum products used or generated by the Contractor and sub-contractors. Along with the list, the Contractor will supply a spill prevention plan and clean up procedures that will include each of these chemical products or generated waste.
  - Provide in the construction schedule the necessary line items that will comply with the schedule and planning requirements of the storm water permit.
  - Post the IxDOI storm water permit and any Contractor permits, per permit requirements.
  - Provide copies of storm water permits for Contractor PSL(s). As new PSL(s) may be obtained for the project, provide copies of new or amended permits to TxDOT. The Contractor will not disturb soil without the proper permits.
  - Provide scale drawings of off ROW PSL's within one mile of the project, for field offices, borrow sources, plant sites or other uses,
  - Provide permit information on any Contractor batch plants or concrete crushing plants to be located at a Contractor PSL(s) within one mile of the project limits or boundaries. Copies of the air and water permits are to be provided to TxDOT before materials will be used on the project. No asphalt or concrete batch plants or concrete crushing plants will be located on TxDOT ROW.
  - Provide a letter indicating a Contractor Responsible Person for environmental compliance (CRP) for the project, and maintain a CRP throughout the project duration,
  - Provide all environmental documentation including certification of compliance and EMS training documents/certificates prior to starting work. The Contractor is to provide daily BMP inspection reports that document all field BMPs needing repair or replacement. The Contractor is to clearly document specific BMPs needing repair and location each work day.

    The Contractor is encouraged to be proactive in fixing BMPs without TxDOI direction.
  - Provide documentation required for Waters of the US, Note #3 and submittals for Item 496 bridge removal. Bridge removal methods submitted will follow all Waters of the US note requirements. The Contractor is not to start construction within the Ordinary High Water Marks of any stream until receiving approval for stream channel construction methods from IxDOI.
  - Provide a written procedure for managing all chemicals and construction items placed in vertical containment structures. Also, provide methods to be used for the treatment, disposal, collection or release of storm water.
  - Provide an estimated date by letter, for the submittal of marked up bridge drawings, indicating cut locations for any structural steel requiring cutting or torching of steel, coated with lead containing paints.
- 2. Place and maintain trash cans and portable sanitary facilities at locations where there is active construction. Worker generated trash and construction debris will be kept from being transported by storm water and will be collected daily from the ground and routinely hauled from the work area.
- 3. Contractor will provide TxDOT copies of all correspondence with MS4s, TCEO, EPA, DSHS and Corps of Engineers regarding activities on this project.
- 4. Contractor to conduct storm water inspections and develop SWPPP documents to support Contractor permits obtained for the project including PSL(s).
- 5. Contractor will maintain written documentation of locations of all portable sanitary facilities. The Contractor is required to document the location and disposition of all spills and cleanups from portable sanitary facilities.
- 6. Contractor will not store chemicals on TxDOT ROW, unless chemicals are stored following all environmental and safety regulations. Fuels for construction equipment will not be stored on TxDOT ROW.
- 7. The Contractor will store fuels and bulk chemicals on Contractor PSL(s) using a secondary containment method, such as double lined tanks and/or free standing containment reservoirs made of plastic or steel designed to hold bulk chemicals or drums.
- 8. The Contractor will not remove sediment controls without the prior approval of TxDOT, except for a sediment control that may back up water and cause safety or traffic problems.

SCALE = NTS SHEET 1 OF 10

Texas Department of Transportation

Waco District Standard

TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES

LE: BMPLAYOUTS.dgn	DN: T	(DOT	ck: TxDOT	DW:	T×DOT	ck: TxDOT
C) TxDOT 2009	CONT	SECT	JOB		ніс	CHWAY
REVISIONS DEC 2013	0184	01 065		SH	36	
EB 2015	DIST		COUNTY		SHEET NO.	
	WAC		COBVEL	_		7

- 9. Any sediment controls removed by the Contractor must be re-installed before the next rainfall event or by the end of day, as approved in advance,
- 10. Vegetative buffer strips may be used in place of temporary sediment controls such as silt fences and rock filter dams. The amount of disturbed soil area will be limited to 1/3 of an acre or less for a minimum of 50 feet of grassed ditch and 2/3 of an acre of disturbed soil for a minimum of 100 feet of grassed ditch.
- 11. Construction equipment found to be leaking oil, fuel or coolant will be immediately stopped, the leaking fluid collected and the equipment fixed. Equipment continuing to leak will be removed from the project at no cost to TxDOT. Leaking fluids from equipment will be collected and removed from the project or PSL.
- 12. Earth berms or mounds typically used to stockpile topsoil and used in place of boundary silt fence will be seeded upon being constructed. Long term use of earth berms or mounds will not be continued without establishing grass on the control.
- 13. The Contractor will inform TxDOT of new areas where soil will be disturbed to facilitate planning for new sediment controls. Areas of vegetated soil will not be disturbed by the Contractor, unless adequate sediment controls can be installed before the next rainfall event. The Contractor will assist TxDOT in keeping an accurate set of working SWPPP drawings that show the locations of all temporary sediment and erosion controls.
- 14. The Contractor will maintain an adequate amount of temporary sediment controls on hand at the field office or project staging area for critical SWPPP maintenance, including silt fence (minimum of 200 feet) and rock / fabric for rock filter dams (minimum for 100 feet of Type [1] dams).

The requirement for BMP rock quantities on hand is waived for small projects for on and off system bridge installations. The Contractor having a BMP Subcontractor does not eliminate the requirement for the Contractor to have the required silt fence and rock on hand, typically stored at the Contractor PSL.

- 15. Failure of a sub-contractor to complete storm water work on time will require the Contractor to start storm water sediment control work immediately and complete the work with high priority, or be subject to stop work on the entire project.
- 16. Earth materials on roads as a result of soil tracking will not be allowed to be transported off ROW in storm water. Soil or rock material found on roadways deposited from Contractor equipment will be removed daily.
- 17. Unless approved, completed concrete curb inlets will not be blocked by sediment controls. The contractor will frequently sweep the completed or partially completed roadway to keep sediment out of drainage pipes.
- 18. The Contractor will be responsible for proper dust control and will route construction traffic in a manner that minimizes dust generation.
- 19. Water for dust control will contain no pollutants, but may be non-potable from upland stock ponds. No quantity of water to be used for construction purposes may be taken from a 404 stream, prior to the proper authorizations or permits being obtained by the Contractor.
- 20. Contractor is to direct workers and sub-contractors to use portable sanitary facilities provided by the Contractor and not to trespass off ROW.
- 21. Contractor will provide written verification to TxDOT that earth borrow pits and disposal sources meet environmental and regulatory requirements, prior to use. Excavations will meet all OSHA requirements and the current safety guidelines established for TxDOT Quarries and Pits.
- 22. Boundary silt fences that are terminated down slope, with one end being at the lowest elevation, will be installed with an L hook to contain sediment. Boundary silt fences that are installed on flat ground will have L-hooks on both ends.
- 23. Rock filter dams across ditches will be constructed where the rock filter dam ends are embedded within the ditch side slopes and ditch bottom. The top center elevation of the rock filter dam will be at least 6 inches lower than the elevations on the rock filter dam ends.
- 24. Silt fence will be constructed in a U or V pattern across ditch lines and up the ditch side slope to keep storm water from flowing around the ends of the silt fence. Small silt fences that do not adequately span the ditch and allows storm water around the end(s) will not be used. Where there is adequate space, large U pattern silt fences are preferred to facilitate sediment collection and sediment removal with equipment.
- 25. Sediment controls (RFDs or silt fences) will be located along road ditches as marked on the SWPPP drawings. Modifications to the sediment control spacing will be adjusted during the project based on sediment control effectiveness. The installation and maintenance of sediment controls at or near outfalls, where storm water leaves TxDOT ROW, takes persistent over ditch line sediment controls.

SCALE = NTS SHEET 2 OF 10



## TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMF

FILE: BMPLAYOUTS.dgn	DN: T	kDOT.	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT 2009	CONT	SECT	JOB		HIGHWAY	
REVISIONS DEC 2013	0184	01	01 065 S			36
FEB 2015	DIST		COUNTY		SHEET NO.	
	WAC		CORVEI	1		51

- 26. Storm water draining sheet flow over disturbed soil sloped towards the ROW property line, will be intercepted by a boundary silt fence typically installed with L-shaped ends.
- 27. For ditch grading and shoulder up work, the Contractor is limited during good weather to remove up to one mile (limited to five acres of disturbed soil) of ditch line sediment controls; on one side of the roadway. Outfall controls cannot be removed during this activity. Ditch line controls must be replaced upon completion of work and before the next rain event.
- 28. Sediment controls damaged by the Contractor, as defined by permit, must be fixed or replaced immediately upon discovery.
- 29. Notches in silt fences are not typically allowed. Specific silt fences that back up water onto lanes of traffic may be notched if approved.
- 30. For silt fence maintenance, the Contractor will leave approximately 4 inches of deposited sediment up stream of silt fences and not over excavate around silt fences or rock filter dams.
- 31. The Contractor will inform TxDOT of new construction areas and where soil is planned to be disturbed. Sediment controls will be installed at outfalls prior to the Contractor beginning soil disturbing activities up slope from the outfall.
- 32. Water from concrete saw cutting, concrete grinding and concrete coring activities; or fine materials from concrete chipping and salvage will not be allowed to enter storm drains or enter streams.
- 33. Storm water containing suspended sediment and turbidity needing to be removed from excavations or low areas will be pumped or gravity drained through vegetated buffer strips (50 foot minimum) or placed in ditches with temporary sediment controls, prior to the water being discharged into a stream.
- 34. Uncontaminated water from natural groundwater seepage, springs, foundations and drains that does not contain suspended sediment or any pollutants may be discharged without storm water controls.
- 35. Lime or cement if spilled in ditches or outside the defined limits of application is considered a pollutant and will be excavated and removed the same day, to avoid contaminating streams.
- 36. If located along the project ROW, RAP stockpiles will be located where there is a minimum 100 feet of vegetative buffer strip before storm water will reach a stream. RAP will not be used as a construction material within the Ordinary High Water Marks of a stream channel of a 404 designated stream.
- 37. If allowed on the project, concrete truck wash out areas will have adequate volume to allow 12 inch freeboard for rain and will be lined with 6 mils of plastic. No concrete will be stored higher than the 12 inch freeboard. Cleaning of truck chutes and equipment does not constitute concrete truck wash out and this activity may be completed at the concrete placement location. Wash out areas will not be located closer than 50 ft from down slope inlets or stream channels.
- 38. For outfalls near stock ponds closer than 50 foot from disturbed soil at the ROW line, redundant sediment controls will be provided, typically a combination of rock filter dam and a silt fence constructed in line of the flow.
- 39. Earth stockpiles will utilize silt fence sediment controls, positioned on the low end of the stockpile drainage area with L-hooks or silt fence installed around the entire stockpile.
- 40. Sediment controls including rock filter dams and silt fences will not be installed across any 404 streams. Sediment controls at 404 streams will be positioned to limit sediment entering the stream from the banks and around structures/culverts, and will allow free flow of storm water to pass through the ROW without being dammed by any sediment controls. Remove loose materials from stream channels prior to each rain event.
- 41. Sediment controls for non-404 streams may be constructed across the drainage channel in unlimited locations. It is appropriate to use sediment control details typically used for 404 streams for non-404 streams when flow velocities are high. Remove loose material from stream channels prior to each rain event.
- 42. Incomplete drainage pipe installation across the roadway does not remove the requirement for having sediment controls around the ends of the pipe. To stay within permit requirements, sediment controls should be installed over and around the terminated end and along each side of the banks as soon as construction on the pipe has been completed. Remove loose material from stream channels prior to each rain event.
- 43. Safety end / headwall construction temporarily will require the removal of part of the sediment control placed over and around the pipe end. Retain in place as much functioning sediment control as possible. Replace the silt fence over and around the top of the pipe, immediately upon concrete placement and form removal. Do not remove culvert sediment controls that cannot be replaced before the next rain event. Sediment control at the ends of culverts must be in place and available for any rain event until the disturbed soil areas are re-vegetated.

SCALE = NTS SHEET 3 OF 10

Texas Department of Transportation

Waco District Standard

TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES

ILE: BMPLAYOUTS.dgn	DN: T)	(DOT	ck: TxDOT	DW:	TXDOT	ck: TxDOT
C)TxDOT 2009	CONT	SECT	JOB		Н	IGHWAY
REVISIONS DEC 2013	0184	01	065		S	н 36
FEB 2015	DIST		COUNTY			SHEET NO.
	WAC		CORYEL	L		52

- 44. Between the Ordinary High Water Marks of a 404 stream channel, the Contractor will disturb only the minimum amount of stream channel that is necessary to complete the work.
- 45. Rock riprap for erosion control does not replace the requirements to maintain sediment control until vegetation is re-established. Replace sediment controls immediately after installing erosion rock.
- 46. At the direction of TxDOT, sediment deposited into existing and new culverts will be removed subsidiary to Item 506. Sediment to be removed is either pre-existing material before construction starts or sediment generated as a part of this project.
- 47. Provide treated 2X4 cross bracing for rectangular inlet silt fence, subsidiary to Item 506.
- 48. Loose or granular earth materials will not be used to repair silt fence undercuts. Silt fence undercut repairs will be conducted with well compacted soils or the silt fence will be reset in a nearby location.
- 49. Silt fence steel I posts of approximately 1.25 pounds per foot are allowed at a spacing of 8 feet or less. Silt fence steel I posts between approximately 1.25 pounds per foot and 0.85 pounds per foot are allowed for I post spacing of 5 feet or less.
- 50. Silt fence to be used to slow the flow of storm water down slopes will be positioned approximately horizontal (on the contour) with L hooks on the ends and limited to approximately 200 feet in length. Multiple sections and levels of silt fence may be required in addition to temporary / permanent erosion control flumes.
- 51. Soil retention blankets will be installed rolled down the slope with the small dimension side embedded at the top of slope, unless recommended otherwise by the manufacturer. Excess grass, rocks, trash, debris or clods will be removed before seeding and installing soil retention blankets. All installations will be by the manufacturer recommendations. Contractor equipment, including tractor mowers will be kept off areas with soil retention blankets until the grass is established.


SCALE = NTS SHEET 4 OF 10



## TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMF

FILE: BMPLAYOUTS.dgn	DN: T	kDOT.	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT 2009	CONT	SECT	JOB		HIC	CHWAY
REVISIONS DEC 2013	0184	01	065		SH	36
FEB 2015	DIST		COUNTY		SHEET NO.	
	WAC		CORYFI	1		53




#### BEST MANAGEMENT PRACTICE (BMP) #1

FOR NON-404 STREAMS ONLY ~ SEDIMENT CONTROL AT EXIT OF CULVERT

## EDGE OF PAVEMENT RFD2 OR ② RFD3 R, O. W. LINE


#### BEST MANAGEMENT PRACTICE (BMP) #2

FOR NON-404 STREAMS ONLY ~ SEDIMENT CONTROL AT EXIT OF CULVERT




#### BEST MANAGEMENT PRACTICE (BMP) #3

FOR 404 OR NON-404 STREAMS ~ SEDIMENT CONTROL AT EXIT OR ENTRANCE OF CULVERT



#### BEST MANAGEMENT PRACTICE (BMP) #4

FOR 404 OR NON-404 STREAMS ~ SEDIMENT CONTROL AT EXIT OR ENTRANCE OF CULVERT



#### NOTES:

- ① EXTEND SILT FENCE SO STORM WATER DOES NOT GO AROUND THE ENDS. USE L-HOOKS ON ENDS AS REQUIRED.
- ② EXTEND ROCK FILTER DAM SO STORM WATER DOES NOT GO AROUND THE ENDS.


SCALE = NTS SHEET 5 OF 10



TYPICAL APPLICATIONS


### FOR BEST MANAGEMENT PRACTICES

FILE: BMPLAYOUTS.dgn	DN: TxDOT		ck: TxDOT	DW:	T×DOT	ck: TxDOT	
	CONT SECT		JOB		HIGHWAY		
REVISIONS DEC 2013	0184	01	065		SH	36	
FEB 2015	DIST		COUNTY			SHEET NO.	
	WAC		CORYEL	.L		54	




#### BEST MANAGEMENT PRACTICE (BMP) #5

FOR NON-404 STREAMS ONLY ~ SEDIMENT CONTROL AT EXIT OF CULVERT




#### BEST MANAGEMENT PRACTICE (BMP) #7

FOR NON-404 STREAMS ONLY - SEDIMENT CONTROL AT ENTRANCE OF CULVERT




#### BEST MANAGEMENT PRACTICE (BMP) #6

FOR NON-404 STREAMS ONLY ~ SEDIMENT CONTROL AT EXIT OF CULVERT



#### BEST MANAGEMENT PRACTICE (BMP) #8

FOR 404 STREAMS - SEDIMENT CONTROL DURING PROJECT CLEARING AND GRUBBING



#### NOTES:


- 1 PROVIDE OVERLAP OF SILT FENCE WITH ROCK FILTER DAM.
- ② USE SILT FENCE L-HOOKS ON ENDS TO BLOCK STORM WATER SEDIMENT

SCALE = NTS SHEET 6 OF 10




## TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

LE: BMPLAYOUTS.dgn	DN: TxDOT		ck: TxDOT	DW:	TxDOT	ck: TxDOT
)TxDOT 2009	CONT	SECT	JOB		HIC	HWAY
REVISIONS EC 2013	0184	01	065	SH	36	
EB 2015	DIST		COUNTY		9	SHEET NO.
	WAC		CORYEL	.L		55




#### BEST MANAGEMENT PRACTICE (BMP) #9

STOCKPILE SEDIMENT CONTROL




#### BEST MANAGEMENT PRACTICE (BMP) #10

FOR 404 OR NON-404 STREAMS ONLY ~ SEDIMENT CONTROL AT PHASED CONSTRUCTION OF BRIDGE CLASS CULVERTS



BEST MANAGEMENT PRACTICE (BMP) #11

BOUNDRY SEDIMENT CONTROL - BOTH ENDS OF CONTROL TERMINATED UP SLOPE



#### BEST MANAGEMENT PRACTICE (BMP) #12

BOUNDRY SEDIMENT CONTROL - BOTH ENDS OF CONTROL TERMINATED DOWN SLOPE

—(12)	SEDIMENT CONTROL FENCE
RF D2	ROCK FILTER DAM (TY 2)
RFD.	ROCK FILTER DAM (TY 3)
~	DIRECTION OF FLOW

#### NOTES:

- (1) START SEDIMENT CONTROL AT LOCATION SO ALL STORM WATER WITH SEDIMENT IS COLLECTED
- 2 ROCK FILTER DAMS OR EARTH/GRASSED EMBANKMENTS CAN BE SUBSTITUTED AS DIRECTED.
- 3 PROVIDE A SMOOTH TRANSITION FROM THE INVERT ELEVATIONS BETWEEN CULVERTS. REMOVE LOOSE SOIL FROM EXCAVATED AREA BETWEEN CULVERTS.
- 4 PROVIDE AND INSTALL PNEUMATICALLY PLACED CONCRETE ON THE DITCH BOTTOM AND SIDE SLOPES BETWEEN TEMPORARY TERMINATIONS BETWEEN OLD AND NEW CULVERTS. PNEUMATICALLY PLACED CONCRETE WILL BE PLACED TO THE HEIGHT OF THE LARGEST CULVERT ON THE DITCH SIDE SLOPES: AND TO A LIMIT 10 FEET OUTSIDE THE LOCATION OF BMPS ALONG THE DITCH BOTTOM. CEMENT STABILIZED SAND MAY BE SUBSTITUTED FOR PNEUMATICALLY PLACED CONCRETE. IN AREAS WHERE INSTALLATION WORKS AND AT THE OPTION OF TXDOT.


SCALE = NTS SHEET 7 OF 10



≠ Texas Department of Transportation Waco District Standard

TYPICAL APPLICATIONS FOR **BEST MANAGEMENT PRACTICES** 

FILE: BMPLAYOUTS.dgn	DN: TxDOT		ck: TxDOT	DW:	T×DOT	ck: TxDOT	
€ TxDOT 2009	CONT SECT		JOB		HIGHWAY		
REVISIONS DEC 2013	0184	01	065		SH	36	
FEB 2015	DIST		COUNTY		9	SHEET NO.	
	WAC		CORYEL	L		56	



DISTURBED AREA

DIRECTION OF FLOW

SEDIMENT CONTROL FENCE


- (1) FOR H DIMENSIONS LESS THAN 1.5'
  SILT FENCE MAY NEED TO BE NOTCHED
  AS SHOWN IN VIEW A-A. ADD EXTRA
  POSTS AT NOTCH.
- ② BMP #14 MAY BE USED AT CROSS DRAINAGE STRUCTURES AS DIRECTED.

SCALE = NTS SHEET 8 OF 10



TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES

FILE: BMPLAYOUTS.dgn	DN: TxDOT		ck: TxDOT	DW:	T×DOT	ck: TxDOT	
	CONT SECT		JOB		HIGHWAY		
REVISIONS DEC 2013	0184	01	065		SH	36	
FEB 2015	DIST		COUNTY			SHEET NO.	
	WAC		CORYEL	L		57	



(TREATED 2×4 LUMBER)

BEST MANAGEMENT PRACTICE (BMP) #17

HORIZONTAL INLET SEDIMENT CONTROL

(SCF)

BEST MANAGEMENT PRACTICE (BMP) #18

LANDOWNER STOCKPOND SEDIMENT CONTROL (2)

R.O.W. LINE-

 $\vee$   $\vee$   $\vee$   $\vee$   $\vee$ FULLY GRASSED DITCH DIRECTION OF FLOW **(33)** SEDIMENT CONTROL FENCE ROCK FILTER DAM (TY 2) ROCK FILTER DAM (TY 3)

- 1 PUMPED STROM WATER FROM AN EXCAVATION AREA SHOULD BE DISCHARGED IN A 50' VEGETATIVE BARRIER OR THROUGH TWO TEMPORARY SEDIMENT CONTROLS BEFORE ENTERING A 404 STREAM.
- (2) FOR LANDOWNER STOCKPONDS WITHIN 50 OF THE RIGHT OF WAY LINE, PROVIDE REDUNDANT SEDIMENT CONTROLS AT THE CONVEYANCE OF THE POND. MINIMUM OF TWO SEDIMENT CONTROLS.
- 3 WHEN CONTAINMENT AREA REACHES 1' FREEBOARD, DISCONTINUE WASHOUT PLACEMENT AND REMOVE MATERIAL UPON SOLIDIFICATION.
- 4 EACH TIME SOLIDIFIED MATERIAL IS REMOVED REPLACE PLASTIC SHEETING.


SCALE = NTS SHEET 9 OF 10


TYPICAL APPLICATIONS FOR **BEST MANAGEMENT PRACTICES** 

TA-BMP


TILE: BMPLAYOUTS.dgn	DN: TxDOT		ck: TxDOT	DW:	T×DOT	ck: TxDOT
CTxDOT 2009	CONT SECT		JOB		HIGHWAY	
REVISIONS DEC 2013	0184	01	065		SH	36
FEB 2015	DIST		COUNTY			SHEET NO.
	WAC		CORYEL	L		58

₹ Texas Department of Transportation Waco District Standard





- THAY BALES MAY BE SUBSTITUTED FOR SILT FENCE OVER THE STREAM CROSSING.
- ② CROSSING WILL BE AS PER REQUIREMENTS OF THE WATERS OF THE US GENERAL NOTES.
- (3) INSTALL SILT FENCE SLIGHTLY UP FROM OHW MARK FROM R.O.W. TO R.O.W.
- USE SILT FENCE L-HOOKS ON LEVEL OR DOWN SLOPING ENDS TO BLOCK STORM WATER SEDIMENT
- (S) INSTALL LARGE V OR U SHAPED BMP'S FROM ABUTMENT AS SHOWN. IF THERE IS STEEP DITCH CONDITIONS DECREASE SPACING AND CONSIDER RFD'S. ADD ADDITIONAL BMP'S IF GRADE IS STEEP OR IF FLOW IS HIGH.



FOR 404 STREAMS ~ BMP'S AT BRIDGES


SCALE = NTS SHEET 10 OF 10

Texas Department of Transportation

Waco District Standard

TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES

FILE: BMPLAYOUTS.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
€ TxDOT 2009	CONT	SECT	JOB		н	GHWAY	
REVISIONS DEC 2013	0184	01 065			SH 36		
FEB 2015	DIST	COUNTY				SHEET NO.	
	WAC		CORYEL	.L		59	



#### HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA.SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

#### SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.


Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.

#### **LEGEND**

Sediment Control Fence —(SCF)—

#### **GENERAL NOTES**

- 1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
- 2. Perform vertical tracking on slopes to temporarily stabilize soil.
- 3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
- 4. Do not exceed 12" between track impressions.
- 5. Install continous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING



TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING

EC(1) - 16

ILE: ec116	DN: TxDOT		ck: KM	DW: \	/P	DN/CK: LS	ı
TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY		l
REVISIONS	0184	01	1 065		SH 36		1
	DIST	COUNTY				SHEET NO.	1
	WAC		CORYEL	.L		60	]

ያ ያ

made sults

warranty of any kind ats or for incorrect

.•	1		
ever se.		I.	STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402
or any purpose whatsoever resulting from its use.			TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.
ny puri			List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.
for g			1.
TxDOT fo damages			
by day			2. ☐ No Action Required ☐ Required Action
			Action No.
nd is made ct results			<ol> <li>Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000</li> </ol>
f any kind incorrect			<ol><li>Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.</li></ol>
anty of or for	dgn		<ol> <li>Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.</li> </ol>
No warranty of formats or for	ic-15.d		4. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.
Act".	də∖sp.	11.	WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404
actic rd to	tandar		USACE Permit required for filling, dredging, excavating or other work in any
P Prodo	5\S+		water bodies, rivers, creeks, streams, wetlands or wet areas.  The Contractor must adhere to all of the terms and conditions associated with
Engineering Practice of this standard to	-01-065\		the following permit(s):
Engi of †	.0184-		No Permit Required
S Co.	اے		☐ Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or
the "Texas conversion	8 HS		wetlands affected)
5 a	7\2018		Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters
ed by	107		☐ Individual 404 Permit Required ☐ Other Nationwide Permit Required: NWP#
governed ity for 1	Ā		
The use of this standard is go TXDOI assumes no responsibilit	н 36 а†		Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.
stand	s\s		1.
this a	Beacon		2.
of .			3.
e use	ashi		4.
SEX	20/2021 WACTRAFF\TRAFFIC\Traffic Control Devices\Flashing		The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.
	0 0		Best Management Practices:
	on tr		Erosion Sedimentation Post-Construction TS
	υ		☐ Temporary Vegetation ☐ Silt Fence ☐ Vegetative Filter Strips
	)ff:		Blankets/Matting Rock Berm Retention/Irrigation Syst
	\Tr		☐ Mulch ☐ Triangular Filter Dike ☐ Extended Detention Basin
	FIC		Sodding Sand Bag Berm Constructed Wetlands
	RAF		☐ Interceptor Swale ☐ Straw Bale Dike ☐ Wet Basin
	.F.T		☐ Diversion Dike ☐ Brush Berms ☐ Erosion Control Compost
Š	IRAF		☐ Erosion Control Compost ☐ Erosion Control Compost ☐ Mulch Filter Berm and Soc
,	4AC1		☐ Mulch Filter Berm and Socks ☐ Mulch Filter Berm and Socks ☐ Compost Filter Berm and S
	\ \ !		$\square$ Compost Filter Berm and Socks $\square$ Compost Filter Berm and Socks $\square$ Vegetation Lined Ditches

Stone Outlet Sediment Traps Sand Filter Systems

Grassy Swales

NOI: Notice of Intent

Sediment Basins

#### III. CULTURAL RESOURCES Refer to TxDOT Standard Specifications in the event historical issues or Comply with the Hazard Communication Act (the Act) for personnel who will be working with archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately. Required Action ☐ No Action Required Action No. IV. VEGETATION RESOURCES Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments. ☐ No Action Required Required Action Action No. V. FEDERAL LISTED. PROPOSED THREATENED. ENDANGERED SPECIES. CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS. Required Action ☐ No Action Required Action No. If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately. LIST OF ABBREVIATIONS Best Management Practice SPCC: Spill Prevention Control and Countermeasure Storm Water Pollution Prevention Plan Construction General Permit DSHS: Texas Department of State Health Services PCN: Pre-Construction Notification FHWA: Federal Highway Administration Project Specific Location MOA: Memorandum of Agreement TCFQ: Texas Carmission on Environmental Quality ocks Memorandum of Understanding TPDES: Texas Pollutant Discharge Elimination System Texas Parks and Wildlife Department Municipal Separate Stormwater Sewer System TPWD: MBTA: Migratory Bird Treaty Act TxDOT: Texas Department of Transportation Notice of Termination Threatened and Endangered Species Nationwide Permit USACE: U.S. Army Corps of Engineers

USFWS: U.S. Fish and Wildlife Service

#### VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes

If "No", then no further action is required.

If "Yes", then  $\mathsf{TxDOT}$  is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required	Required Action
Action No.	
1.	

2.

#### VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required

Required Action

Action No.

Texas Department of Transportation

ENVIRONMENTAL PERMITS.

ISSUES AND COMMITMENTS EPIC

FILE: epic.dgn	DN:		CK:	DW:		CK:
©ĭxDOT: February 2015	CONT	SECT	JOB	H]GHWAY		SHWAY
REVISIONS 12-12-2011 (DS)	0184	01	065		SH 36	
05-07-14 ADDED NOTE SECTION IV.	DIST	IST COUNTY			SHEET NO.	
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	WAC (		CORYELL			61