

FHWA TEXAS DIVISION	PROJECT NO.	SHEET NO.	
	BR 2B20(125)	1	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	SHELBY	
CONTROL	SECTION	JOB	HIGHWAY NO.
0911	39	063	CR

SEE SHEET 2 FOR INDEX OF SHEETS

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT

PROJECT NO. BR 2B20(125)

CR
SHELBY COUNTY

FUNCTIONAL CLASS: LOCAL ROAD
DESIGN SPEED = MEET OR EXCEED EXISTING CONDITIONS
ADT(2013) = 55



1575 HERITAGE DRIVE, STE. 308
MCKINNEY, TEXAS 75069
P 972.569.9193 F 972.569.9197
TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



02/04/2022

Trevor L. Castilla

CSJ	ROADWAY		BRIDGE		TOTALS	
	FT	MI	FT	MI	FT	MI
0911-39-063	280.00	0.053	75.00	0.014	355.00	0.067


FINAL PLANS

LETTING DATE: _____
DATE CONTRACTOR BEGAN WORK: _____
DATE WORK WAS COMPLETED: _____
DATE WORK WAS ACCEPTED: _____
FINAL CONTRACT COST: \$ _____
CONTRACTOR: _____

CONSTRUCTION WORK ON THIS PROJECT WAS PERFORMED IN ACCORDANCE WITH PLANS, CONTRACT AND APPROVED CHANGE ORDERS.

LIMITS: CR 4123 AT BEAR BAYOU

FOR THE CONSTRUCTION OF BRIDGE REPLACEMENT
CONSISTING OF REPLACE BRIDGE AND APPROACHES




BEGIN PROJECT
CR 4123 AT BEAR BAYOU
CSJ: 0911-39-063
STA 11+75.00
LAT: 31.8060593°
LONG: -94.4035064°
END PROJECT
STA 15+30.00
LAT: 31.8057121°
LONG: -94.4024386°

_____ DATE _____

BARRICADES AND WARNING SIGNS

PROVIDE AND ERECT BARRICADES AND WARNING SIGNS IN ACCORDANCE WITH THE BARRICADE & CONSTRUCTION STANDARDS, TCP STANDARDS, THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" AND AS DIRECTED.



CONCURRENCE: 2/28/2022

DocuSigned by:
Allison Harbison

SHELBY COUNTY JUDGE

RECOMMENDED FOR LETTING: _____ APPROVED FOR LETTING: _____

DocuSigned by:
celm31.P.E. 3/3/2022
AF852E728AEC4C0...
DISTRICT DESIGN ENGINEER

DocuSigned by:
Kelly O. Morris, P.E. 3/3/2022
F044211639424B4...
DISTRICT ENGINEER

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY 2012).

NO EXCEPTIONS
NO EQUATIONS
NO RAILROAD CROSSINGS

© 2022 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED

FILENAME: ...\\01 General\PS&E2*INDEX.dgn

DRAWING DATE: 2/22/2022

SHEET NO. DESCRIPTION

GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3 TYPICAL SECTIONS
- 4, 4A-4C GENERAL NOTES
- 5 - 5A ESTIMATE & QUANTITY SHEET
- 6 - 7 SUMMARY OF QUANTITIES

TRAFFIC CONTROL PLAN

- 8 TRAFFIC CONTROL PLAN
- * 9 - 20 BC(1)-21 THRU BC(12)-21

ROADWAY DETAILS

- 21 HORIZONTAL & VERTICAL CONTROL INDEX
- 22 HORIZONTAL & VERTICAL CONTROL SHEET
- 23 HORIZONTAL ALIGNMENT DATA
- 24 PLAN & PROFILE
- 25 GRADING LAYOUT
- * 26 GF(31)-19
- * 27 GF(31)DAT-19
- * 28 SGT(11S)31-18
- * 29 SGT(12S)31-18
- * 30 SGT(15)31-20
- * 31 WF(2)-10

DRAINAGE DETAILS

- 32 DRAINAGE AREA MAP
- 33 HYDRAULIC DATA SHEET
- 34 SCOUR PROFILE

SHEET NO. DESCRIPTION

BRIDGE DETAILS

- 35 BRIDGE LAYOUT
- 36 BORING LOGS
- 37 ESTIMATED QUANTITIES AND CAP ELEVATIONS
- * 38 - 39 ABB-24
- * 40 - 42 BB-B28
- * 43 BBEB
- * 44 BBRAS
- * 45 BBSDS-B28-24
- * 46 - 47 CSAB
- * 48 - 49 FD
- * 50 - 51 SBBS-B28-24
- * 52 - 53 SRR
- * 54 - 55 TYPE T631LS

TRAFFIC DETAILS


- * 56 D & OM(1)-20
- * 57 D & OM(2)-20
- * 58 D & OM(3)-20
- * 59 D & OM(5)-20
- * 60 D & OM(VIA)-20

ENVIRONMENTAL ISSUES

- 61 TXDOT SWP3 INDEX
- 62 SWP3 LAYOUT
- 63 - 64 EPIC
- * 65 EC(1)-16
- * 66 EC(2)-16

CROSS SECTIONS

- 67 - 74 CROSS SECTIONS




THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE BY A * HAVE BEEN ISSUED BY ME, OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Trevor L. Castilla

TREVOR L. CASTILLA, P.E.

02/23/2022

DATE





THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE BY A * HAVE BEEN ISSUED BY ME, OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

James B. Hall II






JAMES B. HALL II, P.E.

02/22/2022

DATE

 CIVIL CONSULTING GROUP 1575 HERITAGE DRIVE, STE. 308 MCKINNEY, TEXAS 75069 P 972.569.9193 F 972.569.9197 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356		
 Texas Department of Transportation © 2022		
<h2>INDEX OF SHEETS</h2>		
FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO. 2

FILENAME: ...\\01 General\PS&E2*TYP01.dgn
DRAWING DATE: 2/22/2022



02/23/2022

Trevor L. Castilla

CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



TYPICAL SECTIONS
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO.
		3

GENERAL NOTES:

Existing regulatory, warning and guide signs within project limits are to remain visible to the traveling public at all times. If a sign must be repositioned during construction operations, move and install the sign to an approved location. Use care when working near existing signs and repair or replace signs damaged by work operations. All work involved repositioning existing signs will be subsidiary to various bid items.

Furnish materials and make repairs to the existing roadway at any location damaged by construction operations. This work shall be done in an approved manner and will be subsidiary to various bid items.

Ensure drainage structures and outfall channels constructed on this project are free of silt and debris at the time of project acceptance. Final clean out work will be subsidiary to various bid items.

Maintain adequate surface drainage throughout the project limits during all phases of construction.

Roadway cross slopes shall conform approximately to the existing surface, unless otherwise directed.

Provide suitable access at all times to adjacent businesses, private property and side roads.

Remove dirt, silt, rocks, debris and other foreign matter that accumulates in structures due to the Contractor's operations as directed. Keep stream channels open at all times. This work will not be paid for directly, but will be subsidiary to pertinent Items.

The bridge at Bear Bayou has a posted weight limit of 12,500 lbs. per tandem axle. This weight limit shall not be exceeded during project construction.

Contractor questions on this project are to be addressed to the following individual(s):

Matt Brazil, Interim Area Engineer

Matt.Brazil@txdot.gov

Randal Cooper, Asst. Area Engineer

Randal.Cooper@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

The contractor's attention is directed to the EPIC sheet(s) included in this plan set for additional information regarding environmental permits, issues, and commitments.

Project Mowing

Mow the right of way within the project limits a maximum of 3 cycles per year as directed. Mowing will not be measured or paid for directly, but will be subsidiary to various bid items.

The equipment used for mowing shall consist of approved mowing units capable of mowing on slopes without marring finished slope surfaces or injuring existing growth. The minimum cutting width shall not be less than 5 ft., unless otherwise approved.

Mow all areas of existing vegetation and vegetation placed during the project as directed. The mowing height shall be 5 in. unless otherwise directed. Repair portions of sod or grass that are injured during mowing operations as directed.

Mow as close as possible to all fixed objects, exercising extreme care not to damage trees, plants, shrubs, signs, delineators or other appurtenances which are part of the facility. Hand trim around such objects, unless otherwise specified.

Use safety chains or other manufacturer's safety device to prevent damage to people or property caused by flying debris propelled out from under rotary mowers. Chains shall be a minimum size of 5/16 in. and links spaced side by side around the mower's front, sides and rear. When mowing at the specified cutting height, the chains shall be long enough to drag the ground. If at any time, it is determined mowing or trimming equipment is defective to the point that it may affect the quality of work or create an unsafe condition, then that equipment shall be immediately repaired or replaced.

Litter Pickup

Remove litter from the right of way in the limits of this project a maximum of 3 cycles per year as directed. Litter pickup will not be measured or paid for directly, but will be subsidiary to various bid items.

The equipment used for litter pickup shall be approved.

Collect and dispose of all litter deposited by construction operations or the traveling public including cans, bottles, paper, plastic items, metal scraps, lumber, etc. from within the project right of way or as directed. Properly dispose of all collected litter. Do not dump or stockpile collected litter on State property.

Precast Alternate Proposals.

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an

alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

Item 5: Control of the Work

In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others. An extension of working time may be granted for any delays caused by the utility adjustments if deemed necessary.

Item 7: Legal Relations and Responsibilities

No significant traffic generator events identified.

The proposed work of this project is to replace the bridge and approaches at CR 4123 over Bear Bayou. The total disturbed area is 0.445 acres. The disturbed area in this project and the contractor project specific locations (PSLs) within 1 mile of the project limits for the contract will further establish the authorization requirements for storm water discharges. As the disturbed area including PSLs is less than 1 acre, the TPDES CGP does not apply; however, the contractor shall place BMPs as directed to adhere to water quality requirements associated with section 404/401 permits. If the total area disturbed shown in the plans and PSLs within 1 mile of the project limits exceed 1 acre, the engineer will develop a SWP3 site plan and post a small construction site notice for the construction activities.

Dispose of all vegetative matter and any other materials removed from State Right of Way in accordance with applicable environmental laws, rules, regulations and requirements.

Burning locations must be approved by the Engineer prior to beginning. Burning activities must be conducted in compliance with Texas Commission on Environmental Quality (TCEQ) regulations. Notify the Engineer when burning activities will take place.

Two old growth trees are present within and adjacent to the project area. See SW3P layout for locations. Place construction fencing around both trees. Do not remove, trim, or disturb trees.

In order to maintain compliance with Chapter 64 of the Texas Parks and Wildlife Code and Migratory Bird Treaty Act (MBTA), construction activities that may affect nests (i.e. tree removal, tree limbing, bridge work) shall be conducted outside of the nesting season (March 15 to September 15). In the event birds or active nests (eggs and/or nestlings present) are encountered, contact the engineer prior to conducting work.

Item 8: Prosecution and Progress

For this project, working days will be computed and charged in accordance with Item 8, Section 3.1.4, "Standard Workweek".

Submit monthly progress schedules no later than the 20th calendar day of the month. Failure to comply with this deadline may result in the Engineer withholding progress (monthly) payments.

A 90 day delay has been included to give contractors flexibility of when to start work due to the time needed for the fabrication of beams.

Provide a Critical Path Method (CPM) Construction Schedule unless otherwise approved.

Item 100: Preparing Right of Way

The equipment used to trim limbs shall be approved. A boom axe will not be allowed.

The contractor shall locate all utilities and exercise extreme caution when working near utilities.

Item 110: Excavation

Item 132: Embankment

Hauling materials with scrapers across or along existing roadways will not be permitted without written permission.

Drying of material deeper than 6 inches below subgrade elevations will not be permitted without written permission.

Grading required for shaping driveways and side road turnouts for pipe culverts at all access locations, will be subsidiary to various bid items.

All blading, rolling, and scraper work to construct and remove temporary slopes adjacent to pavement drop-offs, will be subsidiary to various bid items.

Compact embankment material used to reshape existing slopes to a density comparable with adjacent undisturbed material to the satisfaction of the Engineer.

Item 162: Sodding for Erosion Control

Provide Bermuda block sod unless St. Augustine is the prevailing grass cover at particular placement locations. Provide St. Augustine block sod at those locations.

Item 166: Fertilizer

Fertilize all seeded or sodded areas.

Item 168: Vegetative Watering

Equip water trucks with sprinkler systems capable of watering all of the entire seeded or sodded areas from the roadway.

Water all newly placed sodded or seeded areas at the time of installation. Thereafter, maintain the sodded or seeded areas in a well-watered condition, at no time allow the areas to dry to a condition where water stress is evident.

Item 169: Soil Retention Blankets

In areas designated for soil retention blankets (SRB) in the plans, furnish only spray-on products listed on the Approved Product List for Erosion Control Products based upon the Class and Type specified in the plans. Any substitution to spray-on products must be approved in writing, be listed on the Approved Product List for Erosion Control Products based upon Class and Type, and shall not contain UV degradable, photodegradable or polypropylene materials.

Item 247: Flexible Base

Provide flexible base with a minimum plasticity index of 2.

Provide flexible base material with a minimum Bar Linear Shrinkage of 2% as determined by Test Method Tex-107-E, Part II.

Stockpiling of base material will not be required if testing has been performed and the material has been approved at the source. Deliver approved specified materials to the project.

Compaction requirements for flexible base are ordinary compaction.

Item 421: Hydraulic Cement Concrete

The Engineer will provide curing facilities and strength testing equipment for acceptance testing. Nacogdoches Area Office, 918 Industrial Blvd., Nacogdoches, TX.

Item 422: Concrete Superstructures

Saw-cut grooves are not required.

Item 427: Surface Finishes for Concrete

Provide a rub finish for Surface Area I.

Item 432: Riprap

Stone riprap will require the placement of filter fabric prior to placement of stones.

Welded wire fabric will not be allowed for reinforcing concrete riprap. Reinforcing shall consist of No. 3 or 4 bars meeting the requirements of grade 60 reinforcing steel. Place bars on 12 in. centers in each direction, supported on reinforcing chairs.

Item 496: Removing Structures

Lead and Asbestos were not detected on CR 4123 at Bear Bayou Bridge; therefore, the requirements of Item 6 provisions are not required. Contractor may request a copy of the Asbestos and Lead Paint Inspection Report from the Area Engineer. Steel girders and other materials to be removed, which the Engineer deems salvageable, shall remain the property of

Shelby County. Neatly stack all items deemed salvageable by the engineer within the project limits at a location designated by the Engineer.

Item 502: Barricades, Signs, and Traffic Handling

Traffic Control Plan (TCP):

Ensure the Contractor's Responsible Person (CRP) or their alternate for Barricades, Signs and Traffic Handling is available at all times and able to receive instructions from the Engineer or authorized Department representative. The CRP shall be a person that is usually at the project site during normal working hours.

For protection of the traveling public, direct traffic through the work area using signs, flaggers and other devices. Required signs are shown in the plans on the Barricade and Construction Standards and Traffic Control Plan Sheets. The latest edition of the "Texas Manual on Uniform Traffic Control Devices" shall also be used as a guide for handling traffic on this project.

Provide adequate flaggers to protect the traveling public when working on or near a roadway carrying traffic. All flaggers shall wear hardhats and reflective vests.

Install "Be Prepared to Stop" (CW3-4) and "Flagger Ahead" (CW20-7aD) signs when flaggers are present. Position the signs where good visibility and traffic control can be maintained.

Provide one high-intensity yellow, rotating dome-light on all equipment such as distributors, spreader boxes, lay-down machines, dump trucks, rollers, backhoes, road graders, loaders, etc. within the work zone. Mount lights high enough to be visible from all directions and operating when the equipment is in the work zone. On all other equipment such as automobiles, trailers, etc. use emergency flashers while within the work zone.

All blading, rolling and scraper work to construct and remove temporary slopes adjacent to pavement drop-offs, will be considered subsidiary to various bid items.

Notify the Engineer prior to placing any materials or equipment on the right of way. Any equipment, stockpiles, or materials placed within 30 ft. of the driving lane must have adequate signs, barricades or other warning devices as approved. As a minimum place an 8 ft. wide TY III Barricade or barrels on the approach side of each site that is within 30 ft. of the driving lane. Use TY III Barricade or barrels for the site similarly on the departure side if the location is within 30 ft. of the opposing traffic lane.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Texas Transportation Code 547.105 authorizes the use of warning lights to promote safety and provides an effective means of gaining the travelling public's attention as they drive in areas where construction crews are present. In order to influence the public to move over when high risk construction activities are taking place, minimize the utilization of blue warning lights. These lights must be used only while performing work on or near the travel lanes or shoulder where the travelling public encounters construction crews that are not protected by a standard work zone set up such as a lane closure, shoulder closure, or one-way traffic control. Refrain from leaving the warning lights engaged while travelling from one work location to another or while parked on the right of way away from the pavement or a work zone.

All workers shall wear reflective clothing meeting ANSI Class II requirements during the day and ANSI Class III requirements during the night.

Item 506: Temporary Erosion, Sedimentation, and Environmental Controls

Locations and types of BMPs may require adjustments prior to or after placement as directed by the Engineer. Adjustments should be made to ensure BMPs are working effectively and maintain compliance with the Construction General Permit. Notify the Engineer prior to making adjustments.

Other erosion or sediment control measures deemed necessary by the Engineer will be paid for in accordance with article 4.4, "Changes in the Work".

Item 540: Metal Beam Guard Fence

Use round timber posts.

Use timber post on all metal beam guard fence installations except where steel posts are required.

At the close of work each day, protect the ends of metal beam guard fence in an approved manner, so that no blunt ends are exposed to approaching traffic. Plastic drums will be required at these locations.

Item 552: Wire Fence

Remove temporary fencing upon completion of permanent fencing unless otherwise directed. Removal of temporary fencing will be considered subsidiary to Item 552, "Wire Fence". All materials used in the temporary fence will remain the property of the Contractor.

Item 658: Delineator and Object Marker Assemblies

Install delineators on the departure side of the posts when mounting to metal beam guard fence and guardrail end treatments.

Install D-SW delineators on the departure side of steel bridge rail posts.



CONTROLLING PROJECT ID 0911-39-063

DISTRICT Lufkin
HIGHWAY CR 4123

COUNTY Shelby

Estimate & Quantity Sheet

CONTROL SECTION JOB				0911-39-063		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061489			
COUNTY				Shelby			
HIGHWAY				CR 4123			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6002	PREPARING ROW	STA	3.550		3.550	
	110-6001	EXCAVATION (ROADWAY)	CY	301.000		301.000	
	132-6003	EMBANKMENT (FINAL)(ORD COMP)(TY B)	CY	298.000		298.000	
	160-6003	FURNISHING AND PLACING TOPSOIL (4")	SY	886.000		886.000	
	162-6002	BLOCK SODDING	SY	150.000		150.000	
	164-6009	BROADCAST SEED (TEMP) (WARM)	SY	507.000		507.000	
	164-6011	BROADCAST SEED (TEMP) (COOL)	SY	507.000		507.000	
	164-6021	CELL FBR MLCH SEED(PERM)(RURAL)(SANDY)	SY	1,013.000		1,013.000	
	168-6001	VEGETATIVE WATERING	MG	44.000		44.000	
	169-6002	SOIL RETENTION BLANKETS (CL 1) (TY B)	SY	808.000		808.000	
	247-6073	FL BS (CMP IN PLC)(TY D GR 1-2) (6")	SY	667.000		667.000	
	400-6005	CEM STABIL BKFL	CY	65.300		65.300	
	416-6003	DRILL SHAFT (30 IN)	LF	150.000		150.000	
	420-6013	CL C CONC (ABUT)	CY	31.400		31.400	
	422-6005	REINF CONC SLAB (BOX BEAM)	SF	1,962.000		1,962.000	
	422-6023	SHEAR KEY	CY	20.000		20.000	
	425-6003	PRESTR CONC BOX BEAM (4B28)	LF	298.000		298.000	
	425-6004	PRESTR CONC BOX BEAM (5B28)	LF	149.000		149.000	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	314.000		314.000	
	450-6019	RAIL (TY T631LS)	LF	190.000		190.000	
	496-6009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000		1.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	6.000		6.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	45.000		45.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	45.000		45.000	
	506-6034	CONSTRUCTION PERIMETER FENCE	LF	182.000		182.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	269.000		269.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	269.000		269.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	47.500		47.500	
	540-6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	2.000		2.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	2.000		2.000	
	552-6003	WIRE FENCE (TY C)	LF	203.000		203.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	2.000		2.000	
	658-6016	INSTL DEL ASSM (D-SW)SZ (BRF)GF1 (BI)	EA	6.000		6.000	
	658-6053	INSTL OM ASSM (OM-3L)(TWT)GND	EA	2.000		2.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	

DISTRICT	COUNTY	CCSJ	SHEET
Lufkin	Shelby	0911-39-063	5



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0911-39-063

DISTRICT Lufkin
HIGHWAY CR 4123

COUNTY Shelby

CONTROL SECTION JOB				0911-39-063		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00061489			
COUNTY				Shelby			
HIGHWAY				CR 4123			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	

FILENAME: ...\\01 General\PS&E2\SUM01.dgn
 DRAWING DATE: 2/22/2022


ROADWAY QUANTITIES								
ITEM DESCRIPTION	100	110	132	247	540	540	544	552
	6002	6001	6003	6073	6001	6016	6001	6003
	PREPARING ROW	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY B)	FL BS (CMP IN PLC) (TY D GR 1-2) (6")	MTL W-BEAM GD FEN (TIM POST)	DOWNSTREAM ANCHOR TERMINAL SECTION	GUARDRAIL END TREATMENT (INSTALL)	WIRE FENCE (TY C)
	STA	CY	CY	SY	LF	EA	EA	LF
CR 4123 AT BEAR BAYOU								
STA 11+75.00 TO STA 13+12.00	1.37	167	53	326	17.5	1	1	112
STA 13+12.00 TO STA 13+87.00	0.75	107						
STA 13+87.00 TO STA 15+30.00	1.43	27	245	341	30.0	1	1	91
PROJECT TOTAL	3.55	301	298	667	47.5	2	2	203

REMOVAL QUANTITIES		
ITEM DESCRIPTION	496	644
	6009	6076
	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	REMOVE SM RD SN SUP&AM
	EA	EA
CR 4123 AT BEAR BAYOU	1	2
PROJECT TOTAL	1	2


NOTES:

1. MATERIALS TO BE REMOVED, WHICH THE ENGINEER DEEMS SALVAGEABLE, SHALL REMAIN THE PROPERTY OF THE COUNTY. NEATLY STACK ALL ITEMS DEEMED SALVAGEABLE BY THE ENGINEER WITHIN THE PROJECT LIMITS AT A LOCATION DESIGNATED BY THE ENGINEER.

DELINEATOR AND OBJECT MARKER QUANTITIES		
ITEM DESCRIPTION	658	658
	6016	6053
	INSTL DEL ASSM (D-SW) SZ (BRF) GF1 (BI)	INSTL OM ASSM (OM-3L) (TWT) GND
	EA	EA
CR 4123 AT BEAR BAYOU		
STA 11+75.00 TO STA 13+12.00	2	1
STA 13+12.00 TO STA 13+87.00	2	
STA 13+87.00 TO STA 15+30.00	2	1
PROJECT TOTAL	6	2



1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



Texas Department of Transportation
© 2022

SUMMARY OF QUANTITIES

(SHEET 1 OF 2)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	LFK	SHELBY	6
CONTROL	SECTION	JOB	
0911	39	063	

SWP3 QUANTITIES												
ITEM DESCRIPTION	160	162	164	164	164	168	169	506	506	506	506	506
	6003	6002	6009	6011	6021	6001	6002	6002	6011	6034	6038	6039
	FURNISHING AND PLACING TOPSOIL (4")	BLOCK SODDING	BROADCAST SEED (TEMP) (WARM)	BROADCAST SEED (TEMP) (COOL)	CELL FBR MLCH SEED (PERM) (RURAL) (SANDY)	VEGETATIVE WATERING	SOIL RETENTION BLANKETS (CL 1) (TY B)	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (REMOVE)	CONSTRUCTION PERIMETER FENCE	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	SY	SY	SY	SY	SY	MG	SY	LF	LF	LF	LF	LF
CR 4123 AT BEAR BAYOU	886	150	507	507	1,013	44	808	45	45	182	269	269
PROJECT TOTAL	886	150	507	507	1,013	44	808	45	45	182	269	269

* BLOCK SODDING TO BE USED ONLY AS DIRECTED.


NOTES:

1. LOCATIONS AND TYPES OF BMPs MAY REQUIRE ADJUSTMENTS PRIOR TO OR AFTER PLACEMENT AS DIRECTED BY THE ENGINEER. ADJUSTMENTS SHOULD BE MADE TO ENSURE BMPs ARE WORKING EFFECTIVELY AND MAINTAIN COMPLIANCE WITH THE CONSTRUCTION GENERAL PERMIT AND WATER QUALITY REQUIREMENTS ASSOCIATED TO SECTION 404/401 PERMITS. NOTIFY THE ENGINEER PRIOR TO MAKING ADJUSTMENTS.


BRIDGE QUANTITIES									
ITEM DESCRIPTION	400	416	420	422	422	425	425	432	450
	6005	6003	6013	6005	6023	6003	6004	6033	6019
	CEM STABIL BKFL	DRILL SHAFT (30 IN)	CL C CONC (ABUT)	REINF CONC SLAB (BOX BEAM)	SHEAR KEY	PRESTR CONC BOX BEAM (4B28)	PRESTR CONC BOX BEAM (5B28)	RIPRAP (STONE PROTECTION) (18 IN)	RAIL (TY T631LS)
	CY	LF	CY	SF	CY	LF	LF	CY	LF
NBI: 11-210-0-AA02-17-002									
CR 4123 AT BEAR BAYOU	65.3	150	31.4	1,962	20.0	298	149	314	190
PROJECT TOTAL	65.3	150	31.4	1,962	20.0	298	149	314	190

FILENAME: ...\\01 General\PS&E2\SUM02.dgn

DRAWING DATE: 2/3/2022



1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



Texas Department of Transportation
© 2022



SUMMARY OF QUANTITIES

(SHEET 2 OF 2)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	LFK	SHELBY	7
CONTROL	SECTION	JOB	
0911	39	063	

BRIDGE OUT
 ½ MILES AHEAD
 LOCAL TRAFFIC ONLY
 R11-3b
 60" X 30"

BRIDGE OUT
 2½ MILES AHEAD
 LOCAL TRAFFIC ONLY
 R11-3b
 60" X 30"



NOTES:

- IT IS THE INTENT OF THIS PROJECT TO CLOSE CR 4123 AT THE BRIDGE SITE FOR A MINIMUM LENGTH OF TIME. DO NOT CLOSE THE ROAD UNTIL CONTRACTOR IS MOBILIZED FOR BRIDGE CONSTRUCTION. SIGNS AND BARRICADES SHOWN HERE ARE TO BE IN PLACE PRIOR TO THE ROAD CLOSURE AND SHALL REMAIN IN PLACE FOR THE DURATION OF CONSTRUCTION. REFER TO BC STANDARDS FOR ADVANCED WARNING SIGNS.

SEQUENCE OF WORK



- SET BARRICADES AND ADVANCED WARNING SIGNS
- CLOSE ROAD
- PREPARE ROW AND PLACE SWP3 MEASURES
- REMOVE EXISTING BRIDGE
- CONSTRUCT PROPOSED BRIDGE
- CONSTRUCT APPROACH ROADWAYS
- INSTALL T631LS, MBGF, DAT, AND SGT
- SEED AND FERTILIZE
- CLEAN UP
- REMOVE BARRICADES/SIGNS AND OPEN BRIDGE

NAME
 ADDRESS
 CITY
 STATE
 CONTRACTOR

G20-6T
 48" X 30"

**BRIDGE
 CLOSED**

R11-2b
 48" X 30"



CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



TRAFFIC CONTROL PLAN
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO.
		8

FILENAME: ...4123*DET01.dgn
 DRAWING DATE: 2/2/2022

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
 FILE: ...\\Standards\bc-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

BC (1) -21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
4-03	7-13	0911	39	063	CR				
9-07	8-14	DIST	COUNTY		SHEET NO.				
5-10	5-21	LFK	SHELBY		9				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "ROAD WORK NEXT X MILES" (G20-1aT) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			80	1000 ²
*			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	10	

DATE: 2/2/2022 \$TIME\$
 FILE: ...Standards\bc-21.dgn

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 - 40 mph and greater 0.2 to 2 miles
 - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
FILE: ...Standards\bc-21.dgn

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) -21

FILE:	bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0911	39	063	CR
9-07	8-14	DIST	COUNTY	SHEET NO.	
7-13	5-21	LFK	SHELBY	11	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	12	


DATE: 2/2/2022 \$TIME\$ FILE: ...Standards\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.






SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- ### GENERAL NOTES
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	13	

DATE: 2/2/2022 \$TIME\$ FILE: ...Standards\bc-21.dgn

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM - X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) -21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	14	

DATE: 2/2/2022 \$TIME\$ FILE: ...Standards\bc-21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	15	

DATE: 2/2/2022 \$TIME\$
 FILE: ...Standards\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
 FILE: ...Standards\bc-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign
substrates shall NOT be used on
plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
4-03 8-14	DIST	COUNTY	SHEET NO.	
9-07 5-21	LFK	SHELBY	16	
7-13				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
FILE: ...Standards\bc-21.dgn



FIXED
(Rigid or self-righting)

DRIVEABLE




(Rigid or self-righting)

PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

**Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	17	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	SHELBY	18	

DATE: 2/2/2022 \$TIME\$ FILE: ...Standards\bc-21.dgn

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	LFK	SHELBY	19	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
FILE: ...Standards\bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS






Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS


TWO-WAY LEFT TURN LANE

STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	LFK	SHELBY	20	
11-02 8-14				

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
FILE: ...Standards\bc-21.dgn

FILENAME: N:\Civil Consulting Group 572\21824004\A - CR 4123 at Bear Bayou\CAD\H&V Control\H&V Index Sheet.dgn
 DRAWING DATE: 2/2/2022

BEGIN PROJECT
 CSJ: 0911-39-063
 STA=11+75.00
 N=10,670,029.27
 E=4,138,000.32
 LAT=31° 48' 21.8135" N
 LONG=94° 24' 12.6232" W

END PROJECT
 CSJ: 0911-39-063
 STA=15+30.00
 N=10,669,924.84
 E=4,138,339.42
 LAT=31° 48' 20.6027" N
 LONG=94° 24' 08.7638" W



PI STATION = 11+77.64
 DELTA = 5° 20' 11.40" (RT)
 DEGREE OF CURVE = 11° 27' 32.96"
 TANGENT = 23.30
 LENGTH = 46.57
 RADIUS = 500.00
 PC STATION = 11+54.34
 PT STATION = 12+00.91

PI STATION = 14+74.63
 DELTA = 7° 11' 18.56" (LT)
 DEGREE OF CURVE = 17° 06' 11.58"
 TANGENT = 21.04
 LENGTH = 42.03
 RADIUS = 335.00
 PC STATION = 14+53.59
 PT STATION = 14+95.62



PI STATION = 15+15.95
 DELTA = 6° 56' 46.89" (RT)
 DEGREE OF CURVE = 17° 06' 11.58"
 TANGENT = 20.33
 LENGTH = 40.61
 RADIUS = 335.00
 PC STATION = 14+95.62
 PT STATION = 15+36.23

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (2011 ADJ.).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE TxDOT COMBINED ADJUSTMENT FACTOR (CAF) FOR SHELBY COUNTY, CAF = 1.00003, USING THE FORMULA: SURFACE / CAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TxDOT CORS TXC1 DURING NOVEMBER 2020.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS AND ADJUSTED WITH DIGITAL LEVELING, CONSTRAINED TO THE GPS DERIVED ELEVATION FOR CP-1.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy Walton



FOR ROADWAY GEOMETRY


RODS Surveying, Inc. 6810 LEE RD, STE 100 SPRING, TEXAS 77379
 TEL (281) 257-4020 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. NO. 10030700



HORIZONTAL & VERTICAL CONTROL INDEX
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LKF	SHELBY
CONTROL	SECTION	JOB
0911	39	063
SHEET NO. 21		

MATCHLINE A




From	To	Direction	Distance
CP-1	CP-2	S 74° 08' 39" E	1,067.71'
CP-2	CP-3	S 73° 14' 06" E	645.04'
CP-3	CP-4	N 33° 09' 49" E	17.20'
CP-4	CP-5	S 71° 21' 58" E	653.70'
CP-5	CP-6	S 74° 04' 08" E	637.74'

Point	North	East	Elevation	Station	Offset	Description
CP-3	10,669,939.91	4,138,273.24	303.87'	14+62.16	1.12' RT	SET 5/8" IR W/RODS CAP
CP-4	10,669,954.31	4,138,282.65	304.14'	14+67.30	15.33' LT	SET 5/8" IR W/RODS CAP
CP-5	10,669,745.44	4,138,902.08	305.36'	Off Chain	Off Chain	SET 5/8" IR W/RODS CAP
CP-2	10,670,125.97	4,137,655.62	327.49'	Off Chain	Off Chain	SET 5/8" IR W/RODS CAP
CP-6	10,669,570.39	4,139,515.33	310.00'	Off Chain	Off Chain	SET 5/8" IR W/RODS CAP
CP-1	10,670,417.69	4,136,628.53	329.79'	Off Chain	Off Chain	SET 5/8" IR W/RODS CAP
BY0047	10,706,172.74	4,138,113.33	407.66'	Off Chain	Off Chain	FND NGS DISK IN BRICK WALL (K 68)
TXC1	10,676,908.50	4,213,306.21	318.39'	Off Chain	Off Chain	TXC1


Control Name	Published Coordinate Information			Measured Coordinate Information			Deferent (Published - Measured)		
	North	East	Elev.	North	East	Elev.	North	East	Elev.
BY0047	10,706,271	4,138,010	407.57	10,706,172.74	4,138,113.33	407.66	98	-103	-0.09

Notes: Measured values are based on redundant GPS VRS observations. NGS monument BY0047 is of First Vertical Order, Class II, based on NAD83(1986 Adj), NAVD88; published horizontal values are scaled and approximate; published elevation (orthometric height) is based on differential leveling performed in June 1991.


FILENAME: N:\Civil Consulting Group 572\21824004A - CR 4123 at Bear Bayou\CAD\HV Control\HV Sketches.dgn
DRAWING DATE: 2/2/2022




STATION IS LOCATED ON THE SOUTH SIDE OF PARK PLAZA ST, AND LYING 0.12 MILE SOUTH OF SH 87.




STATION IS LOCATED ON THE SOUTH SIDE OF CR 4123, AND LYING 212 FEET EAST OF FM 415.




STATION IS LOCATED ON THE NORTH SIDE OF CR 4123, AND LYING 0.24 MILE EAST OF FM 415.




STATION IS LOCATED ON THE NORTH SIDE OF CR 4123, AND LYING 0.36 MILE EAST OF FM 415.



STATION IS LOCATED ON THE NORTH SIDE OF CR 4123, AND LYING 0.37 MILE EAST OF FM 415.



STATION IS LOCATED ON THE SOUTH SIDE OF CR 4123, AND LYING 0.49 MILE EAST OF FM 415.



STATION IS LOCATED ON THE SOUTH SIDE OF CR 4123, AND LYING 0.61 MILE EAST OF FM 415.


- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (2011 ADJ.).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE TxDOT COMBINED ADJUSTMENT FACTOR (CAF) FOR SHELBY COUNTY, CAF = 1.00003, USING THE FORMULA: SURFACE / CAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TxDOT CORS TXC1 DURING NOVEMBER 2020.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS AND ADJUSTED WITH DIGITAL LEVELING, CONSTRAINED TO THE GPS DERIVED ELEVATION FOR CP-1.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy D. Walton

SCALE: N. T. S.



FOR ROADWAY GEOMETRY

RODS Surveying, Inc. 6810 LEE RD, STE 100 SPRING, TEXAS 77379
TEL (281) 257-4020 FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700



HORIZONTAL & VERTICAL CONTROL SHEET
(CR 4123 AT BEAR BAYOU)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO.
		22

Chain CR4123 contains:
 CR412301 CUR CR41231 CUR CR41232 CUR CR41233 CR412302

Beginning chain CR4123 description

Point CR412301 N 10,670,068.23 E 4,137,829.72 Sta 10+00.00

Course from CR412301 to PC CR4123-1 S 77° 16' 30.59" E Dist 154.34

Curve Data

Curve CR4123-1
 P.I. Station 11+77.64 N 10,670,029.10 E 4,138,002.99
 Delta = 5° 20' 11.40" (RT)
 Degree = 11° 27' 32.96"
 Tangent = 23.30
 Length = 46.57
 Radius = 500.00
 External = 0.54
 Long Chord = 46.55
 Mid. Ord. = 0.54
 P.C. Station 11+54.34 N 10,670,034.24 E 4,137,980.26
 P.T. Station 12+00.91 N 10,670,021.88 E 4,138,025.15
 C.C. N 10,669,546.52 E 4,137,870.13
 Back = S 77° 16' 30.59" E
 Ahead = S 71° 56' 19.19" E
 Chord Bear = S 74° 36' 24.89" E

Course from PT CR4123-1 to PC CR4123-2 S 71° 56' 19.19" E Dist 252.68

Curve Data

Curve CR4123-2
 P.I. Station 14+74.63 N 10,669,937.02 E 4,138,285.38
 Delta = 7° 11' 18.56" (LT)
 Degree = 17° 06' 11.58"
 Tangent = 21.04
 Length = 42.03
 Radius = 335.00
 External = 0.66
 Long Chord = 42.00
 Mid. Ord. = 0.66
 P.C. Station 14+53.59 N 10,669,943.54 E 4,138,265.37
 P.T. Station 14+95.62 N 10,669,933.05 E 4,138,306.05
 C.C. N 10,670,262.03 E 4,138,369.24
 Back = S 71° 56' 19.19" E
 Ahead = S 79° 07' 37.75" E
 Chord Bear = S 75° 31' 58.47" E

Curve Data

Curve CR4123-3
 P.I. Station 15+15.95 N 10,669,929.21 E 4,138,326.01
 Delta = 6° 56' 46.89" (RT)
 Degree = 17° 06' 11.58"
 Tangent = 20.33
 Length = 40.61
 Radius = 335.00
 External = 0.62
 Long Chord = 40.59
 Mid. Ord. = 0.62
 P.C. Station 14+95.62 N 10,669,933.05 E 4,138,306.05
 P.T. Station 15+36.23 N 10,669,922.99 E 4,138,345.37
 C.C. N 10,669,604.06 E 4,138,242.85
 Back = S 79° 07' 37.75" E
 Ahead = S 72° 10' 50.86" E
 Chord Bear = S 75° 39' 14.30" E


Course from PT CR4123-3 to CR412302 S 72° 10' 50.86" E Dist 157.63

Point CR412302 N 10,669,874.75 E 4,138,495.44 Sta 16+93.86

Ending chain CR4123 description

FILENAME: ...\\4123*HAD01.dgn

DRAWING DATE: 2/2/2022



CG CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



HORIZONTAL ALIGNMENT DATA
 (CR 4123 AT BEAR BAYOU)



FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	LFK	SHELBY	23
CONTROL	SECTION	JOB	
0911	39	063	

LEGEND

- ➔ PROPOSED TRAFFIC DIRECTION
- ➔ CHANNEL FLOW DIRECTION
- XXXX-# HORIZONTAL CURVE #
- STONE PROTECTION
- X— EXISTING FENCE
- XX— PROPOSED FENCE
- UGT— UNDERGROUND TELEPHONE LINE
- G— GAS PIPELINE
- W— WATER LINE
- DITCH FLOW
- DEL ASSM (D-SW) SZ (BRF) (GF1) (BI)
- INSTL OM ASSM (OM-3L) (TWT) GND

NOTES:

1. APPARENT RIGHT OF WAY SHOWN IS A PRESCRIBED WIDTH BASED ON EXISTING FENCE LINES. A BOUNDARY SURVEY WAS NOT PERFORMED, NO CONVEYANCE OR EASEMENT OF THE PUBLIC ROAD TO THE COUNTY COULD BE FOUND.
2. ALL UTILITIES TO BE LOCATED AND CONFIRMED BY THE CONTRACTOR IN THE FIELD PRIOR TO CONSTRUCTION.
3. WHEN BRIDGE IS REMOVED, REMOVE EXISTING LOAD ZONE SIGNS APPROACHING THE BRIDGE.



0' 25' 50'

SCALE: 1"=50' H
1"=10' V

CIVIL CONSULTING GROUP

1575 HERITAGE DRIVE, STE. 308
MCKINNEY, TEXAS 75069
P 972.569.9193 F 972.569.9197
TEXAS REGISTERED ENGINEERING FIRM NO. F-9356


Texas Department of Transportation
© 2022

PLAN & PROFILE
(CR 4123 AT BEAR BAYOU)


FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063

SHEET NO. **24**

FILENAME: ...4123*PP01.dgn
 DRAWING DATE: 2/4/2022



****CAUTION****
UNDERGROUND
GAS LINE





****CAUTION****
WATER LINE

LEGEND

- PROP 5' CONTOUR
- PROP 1' CONTOUR
- EXIST 5' CONTOUR
- EXIST 1' CONTOUR
- STONE PROTECTION
- UGT UNDERGROUND TELEPHONE LINE
- G GAS PIPELINE
- W WATER LINE

NOTES:

1. ALL UTILITIES TO BE LOCATED AND CONFIRMED BY THE CONTRACTOR IN THE FIELD PRIOR TO CONSTRUCTION.



CIVIL CONSULTING GROUP
1575 HERITAGE DRIVE, STE. 308
MCKINNEY, TEXAS 75069
P 972.569.9193 F 972.569.9197
TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



GRADING LAYOUT
(CR 4123 AT BEAR BAYOU)


FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO.
		25

FILENAME: ...4123*GL01.dgn

DRAWING DATE: 2/2/2022


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 2/2/2022
 FILE: ...Standards\gf3119.dgn




TYPICAL POST PLACEMENT

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25' - 0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



ELEVATION 25' - 0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.

SPLICE BOLT LENGTH VARIES

FBB01 = 1 1/4"

FBB02 = 2"


POST & BLOCK LENGTH

FBB03 = 10"

FBB04 = 18"


BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.




WOOD BLOCK TO RECTANGULAR WOOD POST

ROUTED WOOD BLOCK TO I-BEAM STEEL POST

WOOD BLOCK TO ROUND WOOD POST

- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

				Design Division Standard
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19				
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	26	

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 2/2/2022
 FILE: ...Standards\gf31dat19.dgn



DOWNSTREAM ANCHOR TERMINAL (DAT)








NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.

- GENERAL NOTES**
1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
 2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
 3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
 4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
 5. REFER TO GF (31) SHEET FOR TERMINAL CONNECTION DETAILS.

MOW STRIP INSTALLATION

IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.




#	(DAT) PARTS LIST	QTY
1	STEEL FOUNDATION TUBE	2
2	DAT TERMINAL POST	2
3	CHANNEL STRUT	2
4	TERMINAL RAIL ELEMENT	1
5	SHELF ANGLE BRACKET	1
6	BCT BEARING PLATE	1
7	BCT POST SLEEVE	1
8	GUARDRAIL ANCHOR BRACKET	1
9	(ROUNDED) W-BEAM END SECTION	1
10	BCT CABLE ANCHOR	1
11	RECESSED NUT, GUARDRAIL	20
12	1 1/4" BUTTON HEAD BOLT	4
13	10" BUTTON HEAD BOLT	2
14	5/8" X 2" HEX HEAD BOLT	8
15	5/8" X 8" HEX HEAD BOLT	4
16	5/8" X 10" HEX HEAD BOLT	2
17	5/8" FLAT WASHER	18



		<i>Design Division Standard</i>	
METAL BEAM GUARD FENCE (DOWNSTREAM ANCHOR TERMINAL) TL-3 MASH COMPLIANT GF (31) DAT-19			
FILE: gf31dat19.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT: 0911	SECT: 39	JOB: 063
REVISIONS	DIST: LFK	COUNTY: SHELBY	SHEET NO.: 27

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022
FILE: ...Standards\sgt11s3118.dgn



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
 - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL. P/N MANMAX REV D (ECN 3516).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
 - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
 - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
 - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
 - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
 - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM#	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT.-GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	$\frac{5}{8}$ " X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	$\frac{3}{4}$ " X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	$\frac{5}{8}$ " X 1 $\frac{1}{4}$ " GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	$\frac{5}{8}$ " X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	$\frac{5}{8}$ " WASHER F436 STRUCTURAL MGAL	2
20	4001116	$\frac{5}{8}$ " RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	$\frac{5}{8}$ " X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	$\frac{1}{4}$ " X $\frac{3}{4}$ " SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
** ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS


Texas Department of Transportation
Design Division Standard

**MAX-TENSION END TERMINAL
MASH - TL-3
SGT (11S) 31-18**

FILE: sgt11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
DIST	COUNTY		SHEET NO.	
LFK	SHELBY		28	

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. THE USE OF THIS STANDARD ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: 2/2/2022
 FILE: ...Standard\sgt12s3118.dgn




- NOTES:
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSF PANELS, ONE 25'-0" MBSF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. *
 * ITEM (P) 8" WOOD-BLOCKOUT
 ** ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

SINGLE GUARDRAIL TERMINAL
MSKT-MASH-TL-3
SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	29	

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.






DATE: 2/2/2022
FILE: ...Standard.dwg\153120.dgn



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CB08
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WB08
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/16"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GR17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81

ITEM	QTY	SMALL HARDWARE	ITEM #
a	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPlice BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563HDG HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.


Texas Department of Transportation
Design Division Standard

SPIG INDUSTRY, LLC SINGLE GUARDRAIL TERMINAL SGET - TL-3 - MASH SGT (15) 31-20


FILE: sg153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	30	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022
FILE: ...Standards\wf210.dgn




SECTION GALVANIZED BARBED WIRE FENCE WITH METAL POSTS
BRACING DETAIL USED AT ENDS AND GATES
TYPE "C" FENCE
(See General Note 8)




SECTION GALVANIZED WOVEN WIRE FENCE WITH METAL POSTS
BRACING DETAIL USED AT ENDS AND GATES
TYPE "D" FENCE
(See General Note 8)

Note:
For Steel pipe and
T-Post requirements.
(See General Notes 6 & 7)


Metal gate shall consist of 5 panels not less than 4'-4" high and shall be aluminum or galvanized metal and of good quality. Gate and hardware shall meet the approval of the engineer.




DETAIL TYPE 1 GATE




DETAIL TYPE 2 GATE




DETAIL TYPE 3 GATE




CORNER OR PULL POST ASSEMBLY




DETAIL OF FENCE TREATMENT AT STRUCTURES



DETAIL OF STAY (Barbed Wire Fence)



DETAIL OF FENCE SAG




DETAIL OF EYE BOLT


GENERAL NOTES

- Any high point which interferes with the placing of wire mesh shall be excavated to provide a 2 inch clearance.
 - Latches for Type 1 and Type 2 gates shall be good commercial quality and design latch of the spring, fork or chain type. All latches shall be suitable to the gate and shall be approved by the Engineer.
 - Hinges for Type 2 gates shall be a commercial design approved by the Engineer suitable for post and gate.
 - Concrete shall be of the design and consistency approved by the Engineer and shall contain not less than 4 sacks of cement per cubic yard. Concrete footings are to be crowned at the top to shed water.
 - Steel anchor plates shall be of a design and thickness sufficient to prevent turning of the post in firm soil.
 - Steel pipe end posts, corner and pull posts shall be a minimum of 2" Std. pipe (2.375" O.D., 0.154" wall thickness) with a 1/4" Std. pipe brace (1.660" O.D., 0.140" wall thickness), with a 2"x2"x1/4" angle, or other as approved by the Engineer. Fasteners for securing barbed wire or woven wire fence to metal posts shall be a minimum of 11 gauge galvanized steel wire. Tubular posts shall be fitted with water malleable iron caps.
 - If Steel pipe is used for posts and braces, use standard pipe in accordance with ASTM A 53, Class B or A 501. For T-Posts use steel that meets ASTM A 702. Metal line posts shall be not less than 6'-6" in length and shall weigh not less than (1.33 lbs./lin.ft.). These items shall be in accordance with Item 552, "Wire Fence."
 - Barbed Wire shall be in accordance with ASTM A 121, Class 1 Design designation 12-2-4-1 4R or 12-2-5-1 4R, or as approved by the Engineer.
- Woven Wire Fence (Type D) shall be in accordance with ASTM A 116, Class 1 No. 12-1/2 Grade 60 (See Table 1 ASTM A 116) to the height and design shown on the plans, or as approved by the Engineer.
- The location of gates and corner posts will be as indicated elsewhere in these plans.

		Design Division Standard	
BARBED WIRE AND WOVEN WIRE FENCE (STEEL POSTS) WF (2) - 10			
FILE: wf210.dgn	DN: TxDOT	CK: AM	DW: VP
© TxDOT 1996	CONT SECT	JOB	HIGHWAY
REVISIONS	0911 39	063	CR
	DIST	COUNTY	SHEET NO.
	LFK	SHELBY	31



OMEGA EM REGRESSION EQUATION PARAMETERS (DESIGN METHOD)	
DRAINAGE AREA (A)	6.48 SQ MI
ANNUAL PRECIPITATION (P)	51.00 INCHES
CHANNEL SLOPE (S)	0.0068 FT/FT
OMEGA EM (Ω)	-0.120
OMEGA EM REGRESSION EQUATIONS	
$Q_2 = p^{1.398} s^{0.270} \times 10^{0.776 \Omega} + 50.98 - 50.30A^{-0.0058}$	853.6
$Q_5 = p^{1.308} s^{0.372} \times 10^{0.885 \Omega} + 16.62 - 15.32A^{-0.0215}$	1677.0
$Q_{10} = p^{1.203} s^{0.403} \times 10^{0.918 \Omega} + 13.62 - 11.97A^{-0.0289}$	2239.1
$Q_{25} = p^{1.140} s^{0.446} \times 10^{0.945 \Omega} + 11.79 - 9.819A^{-0.0374}$	3166.5
$Q_{50} = p^{1.105} s^{0.476} \times 10^{0.961 \Omega} + 11.17 - 8.997A^{-0.0424}$	3966.5
$Q_{100} = p^{1.071} s^{0.507} \times 10^{0.969 \Omega} + 10.82 - 8.448A^{-0.0467}$	4918.7
$Q_{500} = p^{0.988} s^{0.569} \times 10^{0.976 \Omega} + 10.40 - 7.605A^{-0.0554}$	7583.2



LEGEND

- ID
XXX DRAINAGE AREA
SQUARE MILES
- DRAINAGE AREA BOUNDARY
- STREAM CENTERLINE
- DIRECTION OF FLOW

TOPOGRAPHY SOURCE - USGS QUAD MAPS
QUAD MAPS: ARCADIA, GARRISON EAST



HYDROLOGIC COMPUTATIONS (CHECK METHOD)

HYDROLOGIC CHECK METHOD: SCS UNIT HYDROGRAPH
 DRAINAGE AREA: 6.48 SQ MI
 DESIGN FREQUENCY: MEET OR EXCEED EXISTING, 100-YR CHECK
 SUMMARY OF SOIL CONDITIONS AND LAND USE:
 CONDITIONS OF THE WATERSHED CONSISTED OF RURAL UNDEVELOPED WOODLANDS AND PASTURES.
 THE SOIL CONDITIONS WITHIN THE WATERSHED CONSISTED OF PREDOMINATELY SOIL TYPE D. SOILS DATA WAS OBTAINED FROM THE NRCS WEB SOIL SURVEY.
 SUMMARY OF INPUT PARAMETERS:
 DRAINAGE AREA -- LAND USE REMAINED CONSISTENT THROUGHOUT THE BASIN. THE 6.48 SQ MI WATERSHED WAS ANALYZED AS A SINGLE BASIN WITH A COMPOSITE RCN VALUE OF 80. THE TIME OF CONCENTRATION WAS CALCULATED USING THE KIRBY-KIRPICH METHOD. THE CALCULATED TIME OF CONCENTRATION AT THE STREAM CROSSING IS 3.02 HOURS.
 AN RCN ADJUSTMENT WAS NOT NECESSARY BASED ON THE TXDOT HYDRAULIC DESIGN MANUAL, FIGURE 4-20.
 PRECIPITATION -- THE STORM FREQUENCIES ANALYZED INCLUDE THE 2, 5, 10, 25, 50, AND 100-YEAR RETURN PERIOD STORM EVENTS. FREQUENCY STORM RAINFALL DEPTHS ARE INPUT FOR EACH OF THESE RETURN PERIODS FOR A 24 HOUR EVENT. THE RAINFALL DEPTH-DURATION FREQUENCY DATA WAS TAKEN FROM NOAA'S PRECIPITATION FREQUENCY DATA SERVER (ATLAS 14) FOR 5 MIN, 15 MIN, 1 HR, 2 HR, 3 HR, 6 HR, 12 HR, AND 24 HR DURATION. THE STORM DISTRIBUTION USED WAS A BALANCED STORM.

BASIN	AREA (SQ MI)	Tc (HR)	LAG TIME (MIN)	BASE RCN	IMPERVIOUS (%)
4123	6.48	3.02	108.8	80	1%

RUNOFF DISCHARGES AT THE CROSSING WERE CALCULATED FROM THE INPUT PARAMETERS USING HEC-HMS (VER. 4.3).

SUMMARY OF DISCHARGES						
ANNUAL RECURRENCE INTERVAL (ARI)	2-YR	5-YR	10-YR	25-YR	50-YR	100-YR
Q (CFS)	1276.1	2031.2	2650.8	3536.1	4233.6	5009.9





CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356




DRAINAGE AREA MAP
(CR 4123 AT BEAR BAYOU)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	LFK	SHELBY	32
CONTROL	SECTION	JOB	
0911	39	063	

FILENAME: ...4123*DMAP01.dgn
 DRAWING DATE: 2/2/2022



EXISTING



PROPOSED

NOTES:

1. PROPOSED BRIDGE IS LOCATED AT HEC-RAS STA 1507. UPSTREAM CROSS SECTION IS AT HEC-RAS STA 1525 & DOWNSTREAM CROSS SECTION IS AT HEC-RAS STA 1467.
2. PROPOSED OVERALL BRIDGE WIDTH IS 26.17 FEET.
3. PROPOSED BRIDGE LENGTH IS 75 FEET.
4. EXISTING BRIDGE STRUCTURE CONVEYS THE CALCULATED 100-YR ARI STORM FREQUENCY.

HYDRAULIC METHOD:

WATER SURFACE ELEVATIONS COMPUTED USING A HEC-RAS (V.5.0.7) MODEL CREATED FOR BEAR BAYOU, FILE: 4123HECRAS.PRJ. THE HEC-RAS MODEL WAS DEVELOPED USING FIELD SURVEY, TNRS LIDAR, AND PROPOSED BRIDGE GEOMETRY.

EXISTING CONDITION WATER SURFACE ELEVATIONS COMPUTED FROM HEC-RAS MODEL PLAN "EXISTING".

PROPOSED CONDITION WATER SURFACE ELEVATIONS COMPUTED FROM HEC-RAS MODEL PLAN "PROPOSED".

BOUNDARY CONDITIONS BASED ON NORMAL DEPTH WITH A SLOPE OF 0.0068 FT/FT.

FLOOD HAZARD AREA:

BEAR BAYOU IS IDENTIFIED ON FEMA FIRM PANEL 4810040004A, DATED JUNE 1, 2017. CR 4123 CROSSES A FLOOD HAZARD AREA WITH ZONE "A" DESIGNATION.

THE LOCAL FLOODPLAIN ADMINISTRATOR, _____ LUCIANA BARR _____

WAS NOTIFIED OF THE PROJECT ON 09/10/2021. FINAL H&H REPORT WILL

BE SUBMITTED TO FLOOD PLAIN ADMINISTRATOR WHEN DESIGN IS COMPLETED.

HEC-RAS SUMMARY TABLE												
STA	FLOWS (CFS)	DESIGN FREQUENCY (25-YR ARI)					CHECK FREQUENCY (100-YR ARI)					
		WATER SURFACE ELEVATIONS (FT)			VELOCITIES (FPS)		FLOWS (CFS)	WATER SURFACE ELEVATION (FT)			VELOCITIES (FPS)	
		EXIST	PROP	DIFFERENCE	EXIST	PROP		EXIST	PROP	DIFFERENCE	EXIST	PROP
3419	3166.50	306.54	306.54	0.00	6.17	6.17	4918.70	309.17	309.17	0.00	5.58	5.58
2692	3166.50	304.40	304.39	-0.01	8.54	8.54	4918.70	306.47	306.46	-0.01	10.35	10.36
2243	3166.50	303.11	303.10	-0.01	7.57	7.59	4918.70	305.63	305.61	-0.02	7.82	7.84
2029	3166.50	302.43	302.42	-0.01	7.63	7.65	4918.70	305.22	305.20	-0.02	7.60	7.65
1804	3166.50	302.34	302.32	-0.02	5.36	5.37	4918.70	305.23	305.20	-0.03	5.23	5.26
1564	3166.50	300.86	300.83	-0.03	9.27	9.31	4918.70	303.29	303.24	-0.05	10.66	10.73
1525	3166.50	301.16	301.13	-0.03	7.00	7.02	4918.70	303.57	303.52	-0.05	8.67	8.70
CR 4123 @ BEAR BAYOU (HEC-RAS STA 1507)												
1467	3166.50	300.93	300.93	0.00	7.23	7.23	4918.70	303.32	303.32	0.00	8.61	8.61
1438	3166.50	300.78	300.78	0.00	7.60	7.60	4918.70	303.18	303.18	0.00	8.86	8.86
1362	3166.50	301.05	301.05	0.00	4.85	4.85	4918.70	303.63	303.63	0.00	5.42	5.42
1261	3166.50	300.92	300.92	0.00	5.09	5.09	4918.70	303.60	303.60	0.00	5.13	5.13
1004	3166.50	299.05	299.05	0.00	10.35	10.35	4918.70	300.97	300.97	0.00	12.31	12.31
761	3166.50	298.93	298.93	0.00	6.29	6.29	4918.70	301.82	301.82	0.00	5.31	5.31
334	3166.50	295.68	295.68	0.00	11.65	11.65	4918.70	298.70	298.70	0.00	12.35	12.35



CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



HYDRAULIC DATA SHEET
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
SHEET NO. 33		

FILENAME: ...4123*HD01.dgn

DRAWING DATE: 2/2/2022

SCOUR ANALYSIS - 50-YR (DESIGN)

SCOUR ANALYSIS DETERMINED BY UTILIZING EQUATIONS FROM HEC-18 MANUAL, 5TH EDITION COMPUTED USING HYDRAULIC TOOLBOX VERSION 4.2

LIVE-BED CONTRACTION SCOUR EQUATIONS (EQNS. 6.1 & 6.2)

D50 = 0.200 mm
K1 = 0.69

SCOUR DEPTH Y_s (CHANNEL) = 0.00 FT

SCOUR ANALYSIS - 100-YR (CHECK)

SCOUR ANALYSIS DETERMINED BY UTILIZING EQUATIONS FROM HEC-18 MANUAL, 5TH EDITION COMPUTED USING HYDRAULIC TOOLBOX VERSION 4.2


LIVE-BED CONTRACTION SCOUR EQUATIONS (EQNS. 6.1 & 6.2)

D50 = 0.200 mm
K1 = 0.69

SCOUR DEPTH Y_s (CHANNEL) = 0.00 FT

NOTES:



1. THERE IS NO EVIDENCE OF SCOUR FOR THE EXISTING BRIDGE.
2. ABUTMENTS TO BE PROTECTED WITH RIPRAP (STONE PROTECTION). ABUTMENT SCOUR IS NOT REQUIRED PER TXDOT GEOTECHNICAL MANUAL.
3. SHELBY COUNTY SHOULD REGULARLY INSPECT THE STONE RIPRAP PROTECTION TO ENSURE SLOPE STABILITY.



FILENAME: ...4123*SCOUR01.dgn

DRAWING DATE: 2/2/2022


FILENAME: G:\TXC\Projects\TXDOT\6071-05\WAS4\CRBridges\03\CADD\01*Shfts\07-BRDG\CR4123*BL*01.dgn
 DRAWING DATE: 2/22/2022




ABUTMENTS ARE ON A BEARING OF S 18° 03' 40.80" W

EXIST NBI NO.: 11-210-0-AA02-17-001
 PROP NBI NO.: 11-210-0-AA02-17-002
 DESIGN SPEED: MEET OR EXCEED EXISTING CONDITIONS
 EXIST ADT: (2013)=55
 FUNCTIONAL CLASSIFICATION: LOCAL ROAD
 TERRAIN: ROLLING

TYPE A JOINT IS SUBSIDIARY TO ITEM 422
 HL 93 LOADING



THE CONTRACTOR SHALL BE ADVISED THAT GROUND WATER AND INUNDATION DUE TO FLOODING MAY BE EXPERIENCED DURING DRILLED SHAFT CONSTRUCTION. THE USE OF CASING AND/OR DRILLING SLURRY, IN ACCORDANCE WITH TXDOT ITEM 416, IS EXPECTED TO BE NECESSARY. HOLE STABILITY IS THE RESPONSIBILITY OF THE CONTRACTOR.



STATE OF TEXAS
 REGISTERED PROFESSIONAL ENGINEER
 JAMES B. HALL II
 62722
 2/22/2022

BGE, Inc.
 1701 Directors Blvd., Suite 1000, Austin, TX 78744
 Tel: 512-879-0400 • www.bgeinc.com
 TBPE Registration No. F-1046




BRIDGE LAYOUT
 (CR 4123 AT BEAR BAYOU)


HYDRAULIC DATA TABLE

EXIST HW25 = 301.16 FT	PROP HW25 = 301.13 FT
EXIST Q25 = 3,166.50 CFS	PROP Q25 = 3,166.50 CFS
EXIST V25 = 7.00 FPS	PROP V25 = 7.02 FPS
EXIST HW100 = 303.57 FT	PROP HW100 = 303.52 FT
EXIST Q100 = 4,918.70 CFS	PROP Q100 = 4,918.70 CFS
EXIST V100 = 8.67 FPS	PROP V100 = 8.70 FPS


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
SHEET NO.		
35		




PLAN



FILENAME: G:\TXC\Projects\TXDOT\6071-05\WA5\4CRBridges\03\CADD\01*SHts\07-BRDG\CR4123*BORL*01.dgn
 DRAWING DATE: 2/1/2022



HL 93 LOADING



Terracon
 1809 S. CHESTNUT ST., SUITE 107
 LUFKIN, TEXAS 75901
 P 936.634.5044 F 936.634.8177
 TEXAS REGISTERED ENGINEERING FIRM NO. F-3272




BORING LOGS
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
SHEET NO.		
36		

FILENAME: G:\TxC\Projects\TxDOT\6071-05\WA5*4CRBridges\03\CADD\01*Shts\07-BRDG\CR4123*EQ*01.dgn
 DRAWING DATE: 2/1/2022

SUMMARY OF BRIDGE ITEMS										
	400	416	420	422	422	425	425	432	450	496
	6005	6003	6013	6005	6023	6003	6004	6033	6019	6009
CR 4123 AT BEAR BAYOU NBI: 11-210-0-AA02-17-002	CEM STABIL BKFL	DRILL SHAFT (30 IN)	CL C CONC (ABUT)	REINF CONC SLAB (BOX BEAM)	SHEAR KEY	PRESTR CONC BOX BEAM (4B28)	PRESTR CONC BOX BEAM (5B28)	RIPRAP (STONE PROTECTION) (18 IN)	RAIL (TY T631LS)	REMOV STR (BRIDGE 0 - 99 FT LENGTH)
	CY	LF	CY	SF	CY	LF	LF	CY	LF	EA
2 ~ ABUTMENTS	65.3	150	31.4							
1 ~ 75' PRESTR CONC BOX BEAM SPAN				1,962	20.0	298.00	149.00	314	190.0	
PROJECT TOTALS	65.3	150	31.4	1,962	20.0	298.00	149.00	314	190.0	1



CAP ELEVATIONS

SEE ABUTMENT SHEET FOR CAP ELEVATION LOCATIONS AT OUTSIDE EDGE OF BEAM

HL 93 LOADING

BGE, Inc.
 1701 Directors Blvd., Suite 1000, Austin, TX 78744
 Tel: 512-879-0400 • www.bgeinc.com
 TBPE Registration No. F-1046

Texas Department of Transportation
 © 2022

ESTIMATED QUANTITIES AND CAP ELEVATIONS
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063

SHEET NO. 37

DATE: 2/1/2022 5:16:29 PM
 FILE: G:\TXDOT\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\03-Sub\08-Abutment.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of drawings to PDF format. TXDOT is not responsible for incorrect results or damages resulting from its use.








TABLE OF WINGWALL LENGTHS "WL"	
Beam Type	"WL"
B20	8.000'
B28	10.000'
B34	11.000'

TABLE OF FOUNDATION LOADS ⑧		
Span Length	Drilled Shaft Load	Battered Pile Load
Ft	Tons/DS	Tons/Pile
30	50	38
35	55	41
40	60	43
45	64	45
50	68	47
55	73	50
60	77	52
65	81	54
70	85	56
75	89	58
80	93	60
85	97	62
90	101	64
95	105	66

- ① Top of Cap Elevations are based on section depths shown on Span Details.
- ② See Bridge Layout for Joint type and to determine if Approach Slab is present.
- ③ See Span details for "Y" value.
- ④ Increase as required to maintain 3 3/4" from Finished Grade.
- ⑤ With pile foundations, replace Bar A, located at bottom centerline of cap with 2 ~ #11 x 5'-0" bars placed between pile groups. Deduct 93 Lbs from reinforcing steel total.
- ⑥ 1/2" Preformed Bituminous Fiber material between beam and earwall. Bond to beam with an approved adhesive. Inside face of earwall to be cast with vertical side of beam.
- ⑦ Surface finish for the top of Cap will be a textured wood float finish. The surface must be level in the direction of the centerline of Beams.
- ⑧ Foundation loads are based on B34 beams.
- ⑨ Use 2 Eq Spa for B28 and B34 beams. Use 1 space for B20 beams.
- ⑩ Do not cast earwalls until beams are erected in their final position.
- ⑪ This set of Bars L only required for B28 and B34 beams.

GENERAL NOTES:

Designed according to AASHTO LRFD Specifications.
 Concrete strength $f'_c = 3,600$ psi.
 All reinforcing must be Grade 60.
 Designed for normal embankment header slope of 3:1 or 2:1.
 See Bridge Layout for beam type and foundation type, size and length.
 See standard FD for all foundation details and notes.
 See applicable rail details for rail anchorage cast in wingwalls.
 See standard CRR for riprap attachment details, if applicable.
 These abutment details may be used only with the following standards:
 SBBS-B20-24 or SBBO-B20-24
 SBBS-B28-24 or SBBO-B28-24
 SBBS-B34-24 or SBBO-B34-24


HL93 LOADING SHEET 1 OF 2

ABUTMENTS
PRESTR CONC BOX BEAMS
24' RDWY


ABB-24

FILE: bbstde17.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
©TXDOT December, 2006	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
04-11: Span length.	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	38	

DATE: 2/11/2022 5:16:30 PM
 FILE: G:\TXC\Projects\TXDOT\6071-05_WA5_4CRBridges\03_CADD\01_Shts\07-BRDG\05-10-SHELVY\05-10-24.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.



CORNER DETAILS



WINGWALL ELEVATION
(Earwall omitted for clarity)

TABLE OF ESTIMATED QUANTITIES (TYPE B20 BEAMS)⁽¹²⁾

BAR	NO.	SIZE	LENGTH	WEIGHT
A (5)	8	#11	27'-7"	1,172
E	4	#5	2'-5"	10
F	10	#5	6'-1"	63
H	4	#6	25'-10"	155
L	12	#6	4'-0"	72
S	32	#4	9'-8"	207
U	4	#6	7'-3"	44
V	25	#5	7'-6"	191
wH1	14	#6	9'-0"	189
wH2	12	#6	7'-8"	138
wS	18	#4	7'-9"	93
wV	18	#5	7'-9"	145
Reinforcing Steel				Lb 2,479
Class "C" Concrete (w/Slab)				CY 12.6
Class "C" Concrete (w/ACP)				CY 12.3


TABLE OF ESTIMATED QUANTITIES (TYPE B28 BEAMS)⁽¹²⁾

BAR	NO.	SIZE	LENGTH	WEIGHT
A (5)	8	#11	27'-7"	1,172
E	4	#5	2'-5"	10
F	10	#5	6'-1"	63
H	6	#6	25'-10"	233
L	18	#6	4'-0"	108
S	32	#4	9'-8"	207
U	4	#6	7'-3"	44
V	25	#5	8'-9"	226
wH1	14	#6	11'-0"	231
wH2	16	#6	9'-8"	232
wS	22	#4	7'-9"	114
wV	22	#5	9'-0"	207
Reinforcing Steel				Lb 2,847
Class "C" Concrete (w/Slab)				CY 14.7
Class "C" Concrete (w/ACP)				CY 14.4


TABLE OF ESTIMATED QUANTITIES (TYPE B34 BEAMS)⁽¹²⁾

BAR	NO.	SIZE	LENGTH	WEIGHT
A (5)	8	#11	27'-7"	1,172
E	4	#5	2'-5"	10
F	10	#5	6'-1"	63
H	6	#6	25'-10"	233
L	18	#6	4'-0"	108
S	32	#4	9'-8"	207
U	4	#6	7'-3"	44
V	25	#5	9'-10"	254
wH1	14	#6	12'-0"	252
wH2	16	#6	10'-8"	256
wS	24	#4	7'-9"	124
wV	24	#5	10'-1"	252
Reinforcing Steel				Lb 2,975
Class "C" Concrete (w/Slab)				CY 16.2
Class "C" Concrete (w/ACP)				CY 15.9

- (3) See Span details for "Y" value.
- (5) With pile foundations, replace Bar A, located at bottom centerline of cap, with 2 - #11 x 5'-0" bars placed between pile groups. Deduct 93 Lbs from reinforcing steel total.
- (6) 1/2" Preformed Bituminous Fiber material between beam and earwall. Bond to beam with an approved adhesive. Inside face of earwall to be cast with vertical side of beam.
- (9) Use 2 Eq Spa for B28 and B34 beams and 1 space for B20 beams.
- (10) Do not cast earwalls until beams are erected in their final position.
- (11) This set of Bars L only required for B28 and B34 beams.
- (12) Quantities shown are for one Abutment only (with Approach Slab). With no Approach Slab, add 1.0 CY Class "C" concrete and 78 Lb reinforcing steel for 2 additional Bars H.



SECTION B-B



HL93 LOADING SHEET 2 OF 2


Texas Department of Transportation
 Bridge Division Standard

ABUTMENTS
 PRESTR CONC BOX BEAMS
 24' RDWY


ABB-24

FILE: bbstd17.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
0911	39	063	CR	
04-11: Span length.				
LFK	SHELBY			39


DATE: 2/1/2022 5:16:31 PM
 FILE: G:\TXC\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Sht.s\07-BRDG\515_SHEBY\bbstds02.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of drawings to other formats or for incorrect results or damages resulting from its use.




PARTIAL PLAN
(Showing Type 4B28)



ELEVATION



TYPICAL SECTION ~ TYPE 4B28



TYPICAL SECTION ~ TYPE 5B28

BEAM PROPERTIES			
	Type 4B28	Type 5B28	
Area	in ²	678.8	804.8
Y top	in	14.38	14.26
Y bott	in	13.62	13.74
I	in ⁴	68,745	85,370
Weight	lb/ft	707	838

- ① Bars Z are required for beams topped with a cast-in-place concrete slab only.
- ② Post-tensioning tendons are required for beams not topped with a Min 5" cast-in-place concrete slab. See span details for number and spacing of transverse tendons. Cast interior diaphragms in exterior beams and beams that serve temporarily as exterior beams in staged constructed bridges. See "Blockout, Interior Diaphragm, and Drain Details". Form 3" Dia holes in interior beams. See standard BBPT for details.
- ③ Place drain holes (1" Dia PVC Sch 40 Pipe) as shown in all beam void corners including each side of interior diaphragms. See "Blockout, Interior Diaphragm, and Drain Details".
- ④ Blockouts required at ends of all beams. Extend beam reinforcement into blockouts.
- ⑤ 90° at conventional Interior Bents. Ends of beams shall be vertical at Abutment backwall and Inverted Tee Bent Stems.
- ⑥ Showing void modification required in exterior beams not topped with a Min 5" cast-in-place concrete slab. See standard BBRAO for void modification dimensions.
- ⑦ Based on 150 pcf weight density of concrete. Weight of end blocks and interior diaphragms is not included.


GENERAL NOTES:
 Designed according to AASHTO LRFD Specifications. Use Class H concrete. Use Class H (HPC) if required elsewhere in plans. All reinforcing steel must be Grade 60.
 Two-stage monolithic casting is required. The concrete in the first stage cast (bottom beam flange) must remain plastic until the second stage cast (webs and top beam flange) is placed. Vibrate as required to ensure consolidation between the two casts.
 1 1/4" clear cover to reinforcement is required unless noted otherwise.
 See standard BBRAS or BBRAO for railing anchorage at bridge edges to be cast in beams.
 An equal area of welded wire reinforcement (WWR) meeting the requirements of ASTM A1064 may be substituted for Bars A, B, C, and D.
 These details are applicable for skews up to 30 degrees only.
 Chamfer bottom beam corners 3/4" or round to a 3/4" radius.

Bridge Division Standard
PRESTRESSED CONCRETE BOX BEAM DETAILS (TYPE B28)
BB-B28


FILE: bbstds02.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT December, 2006	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
01-12: Bars Z.	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	40	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings or specifications for use on any project other than that for which they were prepared.


DATE: 2/11/2022 5:16:31 PM
 FILE: G:\TXDOT\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\05-18-2021\BB-B28.dgn




PARTIAL PLAN ~ 15° SKEW
 (Showing Type 4B28)
 (use for skew angles of 15° or less)



PARTIAL PLAN ~ 30° SKEW
 (Showing Type 4B28)
 (use for skew angles greater than 15° and less than or equal to 30°)



SECTION THRU BLOCKOUT ~ TYPE 4B28
 (Showing End Mat Reinforcing)



SECTION THRU BLOCKOUT ~ TYPE 5B28
 (Showing End Mat Reinforcing)


- ① Bars Z are required for beams topped with a cast-in-place concrete slab only.
- ② Post-tensioning tendons are required for beams not topped with a Min 5" cast-in-place concrete slab. See span details for number and spacing of transverse tendons. Cast interior diaphragms in exterior beams and beams that serve temporarily as exterior beams in staged constructed bridges. See "Blockout, Interior Diaphragm, and Drain Details". Form 3" Dia holes in interior beams. See standard BBPT for details.
- ⑧ Cut as required to maintain one inch clear between bars.
- ⑨ Bars M may be adjusted vertically as required to avoid pretensioning strands in web.
- ⑩ See standard BBND or appropriate Prestressed Concrete Box Beam Standard Designs sheet for locations of pretensioning strands.
- ⑪ For Type 4B28 Box Beams: Bars N may be reduced to 4 bars per row when beam design contains fewer than 22 strands. In this case, place Bars N at the 5-6 and 8-9 strand locations.
 For Type 5B28 Box Beams: Bars N may be reduced to 5 bars per row when beam design contains fewer than 28 strands. In this case, place Bars N at the 4-5, 9-10 and 14-14 strand locations.

HL93 LOADING SHEET 2 OF 3


		Bridge Division Standard	
PRESTRESSED CONCRETE BOX BEAM DETAILS (TYPE B28)			
BB-B28			
FILE: bbstds02.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT December, 2006	CONT	SECT	JOB
0911	39	063	CR
01-12: Bars Z.	DIST	COUNTY	SHEET NO.
LFK	SHELBY		41

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions.


DATE: 2/11/2022 5:16:32 PM
 FILE: G:\TXC\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\05-05_SHELFY\bbst02.dgn



BLOCKOUT, INTERIOR DIAPHRAGM AND DRAIN DETAILS
 (Showing 30° skew)











POST-TENSION ANCHORAGE DETAIL



DETAIL A


- ① Bars Z are required for beams topped with a cast-in-place concrete slab only.
- ② Post-tensioning tendons are required for beams not topped with a Min 5" cast-in-place concrete slab. See span details for number and spacing of transverse tendons. Cast interior diaphragms in exterior beams and beams that serve temporarily as exterior beams in staged constructed bridges. Form 3" Dia holes in interior beams. See "Blockout, Interior Diaphragm, and Drain Details". See standard BBPT for details.
- ③ Place drain holes (1" Dia PVC Sch 40 Pipe) as shown in all beam void corners including each side of interior diaphragms. See "Blockout, Interior Diaphragm, and Drain Details".
- ④ Blockouts required at ends of all beams. Extend beam reinforcement into blockouts.
- ⑧ Cut as required to maintain one inch clear between bars.
- ⑫ 5" (Typ) or sufficient depth to provide 1" Cover on cut-off tendon. See BBPT for details.
- ⑬ Dimension will vary slightly with skew. Adjust as necessary.




At fabricator's option, Bars Z pairs may be fabricated using one continuous bar. If this option is used, Bars B at Bar Z locations (only) may be omitted.

		Bridge Division Standard	
PRESTRESSED CONCRETE BOX BEAM DETAILS (TYPE B28)			
BB-B28			
FILE: bbst02.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT December, 2006	CONT	SECT	JOB
0911	39	063	CR
01-12: Bars Z.	DIST	COUNTY	SHEET NO.
LFK	SHELBY		42

DATE: 2/1/2022 5:16:33 PM
 FILE: G:\TXC\Projects\TXDOT\6071-05_WA5_4CRBridges\03_CADD\01_Shts\07-BRDG\05-SHEBY\05E08.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to metric units.




AT ABUTMENT OR INVERTED TEE BENTS



AT CONVENTIONAL INTERIOR BENTS ①

ELASTOMERIC BEARING PLACEMENT DIAGRAMS

The Forward Station Beam End will have one bearing and the Back Station Beam End will have two bearings.



ELASTOMERIC BEARING SECTION

(50 DUROMETER)
 The use of Polyisoprene (natural rubber), for the manufacture of bearing pads, is not permitted.

- ① For Transition Bents with backwall, beams and elastomeric bearings will receive the same treatment as shown for Abutment Bents.
- ② Maximum and minimum layer thicknesses shown are for elastomer only, on tapered layers.
- ③ Indicate BEARING TYPE on all pads. For tapered pads, BEARING TYPE will be located on the high side. The Fabricator will include the value of "N" (amount of taper in 1/8" increments) in this mark. Examples: N=0, (for 0" taper)
 N=1, (for 1/8" taper)
 N=2, (for 1/4" taper)
 (etc.)
 Fabricated pad top surface slope must not vary from plan beam slope by more than $(\frac{0.0625}{\text{Length}})$ IN/IN.
- ④ Locate Permanent Mark here.

ELASTOMERIC BEARING DIMENSIONS					
BEARING TYPE	BEAM TYPE	ONE BEARING		TWO BEARINGS	
		L	W	L	W
B20-"N"	4B20	6"	12"	6"	6"
	5B20	6"	12"	6"	6"
B28-"N"	4B28	6"	14"	6"	7"
	5B28	6"	14"	6"	7"
B34-"N"	4B34	6"	16"	6"	8"
	5B34	6"	16"	6"	8"
B40-"N"	4B40	6"	20"	6"	10"
	5B40	6"	20"	6"	10"


GENERAL NOTES:
 Set beams on elastomeric bearings of the dimensions shown. Center bearings as near nominal \bar{c} bearing as possible within limits shown.
 Constant thickness bearings may be used for moderate beam slopes up to 0.0113 ft/ft.
 For skewed supports, Bearings beveled for beam slope may not provide uniform contact. However, predicted contact is considered within allowable tolerances.
 Shop drawings for approval are required. A bearing layout which identifies location and orientation of all bearings will be developed by the bearing fabricator. Permanently mark each bearing in accordance with the bearing layout. A copy of the bearing layout is to be provided to the Engineer.
 Cost of furnishing and installing elastomeric bearings is to be included in unit price bid for "Prestressed Concrete Box Beams".
 Details are drawn showing right forward skew. See Bridge Layout for actual direction.
 These details are applicable for skews up to 30 degrees only.

HL93 LOADING


				Bridge Division Standard	
ELASTOMERIC BEARING DETAILS PRESTR CONC BOX BEAMS					
BBEB					
FILE: bbstae08.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
©TxDOT December, 2006	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0911	39	063	CR	
	DIST	COUNTY	SHEET NO.		
	LFK	SHELBY	43		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information shown on this drawing. If any error or omission is noted, the user shall be responsible for correcting the same. File: G:\TXDOT\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\03-18_Shts\07-09.dgn

DATE: 2/1/2022 5:16:33 PM
 FILE: G:\TXDOT\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\03-18_Shts\07-09.dgn




CAST-IN-PLACE ANCHORAGE OPTION




ADHESIVE ANCHORAGE OPTION

T631LS & T631 RAIL ANCHORAGE PLACEMENT (2)(7)



PART SPAN ELEVATION




SECTION


TYPICAL CONCRETE RAIL ANCHORAGE

(Showing typical concrete rail anchorage)

5/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563).



T631LS & T631 RAIL C-I-P ANCHOR BOLT



PLAN OF CONCRETE RAILS AT EXPANSION JOINTS

- ① Cast-in-place slab thickness varies due to beam camber (5" minimum).
- ② Replace cast-in-place anchor bolts shown on T631LS or T631 Rail standard with an adhesive anchor system or cast-in-place anchor bolts shown on this sheet.
- ③ Bar length shown on rail standard, minus 1 1/4". Adjust bar length for a raised sidewalk.
- ④ See Rail standard for projection from finished grade or top of sidewalk.
- ⑤ Place additional (#5) longitudinal bar.
- ⑥ Excess bolt length has been provided to accommodate a variable slab thickness due to beam camber. If slab thickness on span details exceed 10", bolt length must be increased accordingly. After posts have been set and bolts tightened, bolt projection above nuts of more than 1/2" must be cut off and painted with two coats of zinc-rich paint conforming to the Item 445 "Galvanizing".
- ⑦ Distance from end of top outside edge of slab to center of first bolt group can not be less than 9", except: 15° Skew: 1'-0" (acute corner only)
30° Skew: 1'-3" (acute corner only)
- ⑧ Location of Rail Expansion Joint must be at the intersection of Slab Expansion Joint, Rail Footprint and perpendicular to slab outside edge.
- ⑨ Cross-hatched area must have 1/2" Preformed Bituminous Fiber Material under concrete rail, as shown.

CONSTRUCTION NOTES:

Rail anchorage bars may be field bent as required to clear rail reinforcing or provide minimum cover shown on standard rail detail sheets.
 Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.

MATERIAL NOTES:

Galvanize all steel components of steel rail system.
 Provide Grade 60 reinforcing steel.
 Cast-in-place anchorage system for T631LS and T631 Rail must be 5/8" Dia heavy hex head anchor bolts (ASTM F3125 Gr 325 or A449) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed anchor bolts 4 1/2" minimum.
 Adhesive anchors for T631LS and T631 Rail must be 5/8" Dia ASTM A193 Gr B7 or F1554 Gr 105 fully threaded rods with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed fully threaded rod into slab and/or abutment wingwall using a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4 1/4". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 8 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing."
 Epoxy coat or galvanize reinforcing steel shown on this standard if rail reinforcement is epoxy coated or galvanized.

GENERAL NOTES:

Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 This standard is for use with structures with a 5" minimum cast-in-place concrete slab.
 This standard may require modification for interior rails. This standard does not apply to median barriers.
 This standard does not provide details for Type T221P, T224, T80HT, T80SS, C412, PR11, PR22 and PR3 rails on box beam bridges.
 See rail standards for approved speed restrictions, notes and details not shown.

Cover dimensions are clear dimensions, unless noted otherwise.


				Bridge Division Standard	
RAIL ANCHORAGE DETAILS PRESTR CONC BOX BEAMS (WITH SLAB) BBRAS					
FILE: bstd09-18.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH	
©TxDOT December 2006	CONT	SECT	JOB	HIGHWAY	
	0911	39	063	CR	
REVISIONS		DIST		COUNTY	
04-90: Updated for new rails.		LFK		SHELBY	
01-12: rails anchor bars.				SHEET NO.	
07-14: Removed T101 & T16. Added T631.				44	
03-16: Class D, E, or F epoxy in material notes: T221P & T224 in general notes.					
03-18: Updated adhesive anchor notes.					

DATE: 2/11/2022 5:16:35 PM
 FILE: G:\TXC\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDC\05-Std\BBSDS-B28-24.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.


STANDARD SBBS-B28-24	DESIGNED BEAMS (STRAIGHT STRANDS)																	OPTIONAL DESIGN							
	SPAN LENGTH (ft)	BEAM NO.	BEAM TYPE	PRESTRESSING STRANDS						DEBONDED STRAND PATTERN PER ROW					CONCRETE		DESIGN LOAD COMP STRESS (TOP ϵ) (SERVICE I) fct(ksi)	DESIGN LOAD TENSILE STRESS (BOTT ϵ) (SERVICE III) fcb(ksi)	REQUIRED MINIMUM ULTIMATE MOMENT CAPACITY (STRENGTH I) (ft-kips)	LIVE LOAD DISTRIBUTION FACTOR (2)					
				NON- STD STRAND PATTERN	TOTAL NO.	SIZE (in)	STRGTH fpu (ksi)	"e" CL (in)	"e" END (in)	TOT NO. DEB	DIST FROM BOTTOM (in)	NO. OF STRANDS		NUMBER OF STRANDS DEBONDED TO (ft from end)						RELEASE STRGTH ① f'ci (ksi)	MINIMUM 28 DAY COMP STRGTH f'c (ksi)	②			
												TOTAL	DE- BONDED	3	6	9						12	15	Moment	Shear
24' Roadway 5" Slab	30	1&6	5B28		8	0.6	270	11.24	11.24	0	2.50	8	0	0	0	0	0	0	4.000	5.000	0.438	-0.522	736	0.461	0.699
	30	2-5	4B28		6	0.6	270	11.12	11.12	0	2.50	6	0	0	0	0	0	0	4.000	5.000	0.489	-0.566	640	0.384	0.517
	35	1&6	5B28		8	0.6	270	11.24	11.24	0	2.50	8	0	0	0	0	0	0	4.000	5.000	0.571	-0.672	920	0.446	0.688
	35	2-5	4B28		8	0.6	270	11.12	11.12	0	2.50	8	0	0	0	0	0	0	4.000	5.000	0.642	-0.733	804	0.372	0.505
	40	1&6	5B28		10	0.6	270	11.24	11.24	0	2.50	10	0	0	0	0	0	0	4.000	5.000	0.722	-0.839	1120	0.434	0.679
	40	2-5	4B28		8	0.6	270	11.12	11.12	0	2.50	8	0	0	0	0	0	0	4.000	5.000	0.815	-0.919	982	0.362	0.494
	45	1&6	5B28		10	0.6	270	11.24	11.24	0	2.50	10	0	0	0	0	0	0	4.000	5.000	0.893	-1.028	1343	0.423	0.670
	45	2-5	4B28		8	0.6	270	11.12	11.12	0	2.50	8	0	0	0	0	0	0	4.000	5.000	1.010	-1.130	1077	0.353	0.487
	50	1&6	5B28		10	0.6	270	11.24	11.24	0	2.50	10	0	0	0	0	0	0	4.000	5.000	1.088	-1.246	1330	0.414	0.663
	50	2-5	4B28		8	0.6	270	11.12	11.12	0	2.50	8	0	0	0	0	0	0	4.000	5.000	1.235	-1.373	1068	0.346	0.482
	55	1&6	5B28		12	0.6	270	11.24	11.24	0	2.50	12	0	0	0	0	0	0	4.000	5.000	1.301	-1.480	1467	0.406	0.657
	55	2-5	4B28		10	0.6	270	11.12	11.12	0	2.50	10	0	0	0	0	0	0	4.000	5.000	1.478	-1.635	1255	0.339	0.477
	60	1&6	5B28		12	0.6	270	11.24	11.24	0	2.50	12	0	0	0	0	0	0	4.000	5.000	1.529	-1.731	1642	0.399	0.651
	60	2-5	4B28		12	0.6	270	11.12	11.12	0	2.50	12	0	0	0	0	0	0	4.000	5.000	1.741	-1.916	1453	0.333	0.473
	65	1&6	5B28		14	0.6	270	11.24	11.24	0	2.50	14	0	0	0	0	0	0	4.000	5.000	1.775	-1.999	1875	0.393	0.645
	65	2-5	4B28		14	0.6	270	11.12	11.12	0	2.50	14	0	0	0	0	0	0	4.000	5.000	2.031	-2.227	1676	0.333	0.469
	70	1&6	5B28		18	0.6	270	11.24	11.24	0	2.50	18	0	0	0	0	0	0	4.000	5.000	2.036	-2.283	2118	0.387	0.641
	70	2-5	4B28		16	0.6	270	11.12	11.12	0	2.50	16	0	0	0	0	0	0	4.000	5.000	2.341	-2.560	1911	0.333	0.465
75	1&6	5B28		20	0.6	270	11.24	11.24	0	2.50	20	0	0	0	0	0	0	4.000	5.000	2.314	-2.583	2372	0.381	0.636	
75	2-5	4B28		20	0.6	270	11.12	11.12	2	2.50	20	2	0	2	0	0	0	4.000	5.000	2.673	-2.913	2158	0.333	0.462	

DESIGN NOTES:
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 Prestress losses for the designed beams have been calculated for a relative humidity of 60 percent. Optional designs must likewise conform.
 Beam designs are applicable for 5" concrete slabs without overlay and 0 degree skew.

FABRICATION NOTES:
 Provide Class H concrete.
 Provide Grade 60 reinforcing steel bars.
 Use low relaxation strands, each pretensioned to 75 percent of fpu.
 When shown on this sheet, the Fabricator has the option of furnishing either the designed beam or an approved optional beam design. All optional design submittals and shop drawings must be signed, sealed and dated by a Professional Engineer registered in the State of Texas.
 Locate strands for the designed beam as low as possible on the 2" grid system unless a non-standard stand pattern is indicated. Fill row "2.5", then row "4.5", then row "6.5", etc. Place strands within a row as follows:
 1) Locate a strand in each "1" position.
 2) Place strand symmetrically about vertical centerline of box.
 3) Space strands as equally as possible across the entire width.
 Strand debonding must comply with Item 424.4.2.2.4.
 Do not debond strands in position "1". Distribute debonded strands equally about the vertical centerline. Decrease debonded lengths working inward, with debonding staggered in each row.
 Full-length debonded strands are only permitted in positions marked Δ .



TxDOT 4B28 BOX BEAM



TxDOT 5B28 BOX BEAM


- ① Based on the following allowable stresses (ksi):
 Compression = $0.65 f'ci$
 Tension = $0.24 \sqrt{f'ci}$
- Optional designs must likewise conform.
- ② Portion of full HL93.

HL93 LOADING


Texas Department of Transportation		Bridge Division Standard	
PRESTR CONC BOX BEAM STANDARD DESIGNS			
TYPE B28		24' RDWY (WITH SLAB)	
BBSDS-B28-24			
FILE: bbstds13.dgn	DN: SRW	CK: BMP	DW: SFS
©TxDOT December 2006	CONT	SECT	JOB
REVISIONS	0911	39	063
04-11: f'ci and LLDF. 01-16: Notes, 0.6" strand designs.	DIST	COUNTY	SHEET NO.
	LFK	SHELBY	45

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information. www.txdot.gov/standards/standard-specifications/2011-2012-specifications-for-bridges-and-structures/

DATE: 2/1/2022 5:16:36 PM
 FILE: G:\TXDOT\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\05-Sub\01-20.dgn




OPTION 1 ~ PLAN WITH WINGWALLS
 Cast-in-place retaining walls similar.




OPTION 1 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a) If flowable backfill is to be placed over MSE backfill then a filter fabric will be placed over the flowable fill; and
 - b) Place flowable fill in lifts not exceeding 2 feet in height, place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).

GENERAL NOTES:
 See the Bridge Layout for selected Option. Option 2 is intended for new construction requiring high plasticity embankment fill with a plasticity index (PI) greater than 30 or pavement built in poor native soil. Poor soils are defined as high plasticity clays or expansive clays. Option 1 is intended for construction only requiring PI controlled embankment fill or excavation in competent soils/rocks in order to construct the abutment.
 Provide Cement Stabilized Backfill (CSB) meeting the requirements of Item 400, "Excavation and Backfill for Structures", to the limits shown at bridge abutments.
 If required elsewhere in the plans, provide Flowable Backfill meeting the requirements of Item 401, "Flowable Backfill", to the limits shown at bridge abutments.
 Details are drawn showing left forward skew. See Bridge Layout for actual skew direction.
 These details do not apply when Concrete Block retaining walls are used in lieu of wingwalls.



WITHOUT APPROACH SLAB




SECTION A-A

WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)

		Bridge Division Standard	
CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT			
CSAB			
FILE: csabste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT	REVISIONS	CONTRACT	JOB
0911	39	063	CR
02-20: Added Option 2.	DIST:	COUNTY	SHEET NO.
	LFK	SHELBY	46


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. The user of this standard is advised to verify the accuracy of the information contained herein.

DATE: 2/1/2022 5:16:37 PM
 FILE: G:\TXC\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\CSAB\shelby\csabste1-20.dgn




OPTION 2 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.




OPTION 2 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a). If flowable backfill is to be placed over MSE backfill then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b). Place flowable fill in lifts not exceeding 2 feet in height, place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).



WITHOUT APPROACH SLAB




SECTION B-B

WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)


SHEET 2 OF 2

		Bridge Division Standard	
CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT			
CSAB			
FILE: csabste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT	April 2019	CONTRACT: 0911	SECTION: 39
REVISIONS		JOB: 063	HIGHWAY: CR
02-20: Added Option 2.		DIST: LFK	COUNTY: SHELBY
		SHEET NO. 47	


DATE: 2/1/2022 5:16:38 PM
 FILE: G:\TXDOT\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\518_SHEBY\FD\01-20.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of incorrect results or damages resulting from its use.




ABUTMENTS, WINGWALLS AND MULTI-DRILLED SHAFT FOOTINGS




INTERIOR BENTS DRILLED SHAFT DIA EQUAL TO COLUMN DIA



INTERIOR BENTS DRILLED SHAFT DIA GREATER THAN COLUMN DIA



OPTIONAL INTERIOR BENT DRILLED SHAFT DETAIL




DRILLED SHAFT SECTIONS


DRILLED SHAFT DETAILS

TABLE OF PILE EMBEDMENT	
Pile Type	Embedment Depth (Ft)
16" Sq Concrete 18" Sq Concrete HP14 Steel HP16 Steel	1'-0"
20" Sq Concrete 24" Sq Concrete HP18 Steel	1'-6"


See Prestressed Concrete Piling (CP) standard for additional details on concrete pile embedment.



ORIENTATION OF STEEL H-PILING




PILING DETAILS
(Concrete or steel H)




DETAIL "A"
(Showing plan view of a 30° skewed abutment)


- ① #3 spiral at 6" pitch (one and a half flat turns top and bottom).
- ② Min extension into supported element:
#6 Bars = 1'-11"
#7 Bars = 2'-0"
#9 Bars = 2'-3"
- ③ Min lap with column reinf:
#7 Bars = 2'-11"
#9 Bars = 3'-9"
#11 Bars = 4'-8"
- ④ Min extension into supported element:
#6 Bars = 1'-11"
#7 Bars = 2'-3"
#9 Bars = 2'-9"
- ⑤ Drilled shafts may extend to the bottom of bent caps for "H" heights of 6 ft and less (as shown on the Bridge Layout), if approved. This option can only be used when the drilled shaft diameter equals the column diameter. Obtain approval of the forming method above the ground line prior to construction. No adjustments in payment will be made if this option is used.
- ⑥ 1'-0" Min, unless shown otherwise on plans.
- ⑦ Or as shown on plans.




ELEVATION




SECTION A-A



SECTION B-B



STEEL H-PILE SPLICE DETAIL
Use when required.





SECTION THRU FLANGE OR WEB

STEEL H-PILE TIP REINFORCEMENT
See Item 407 "Steel Piling" to determine when tip reinforcement is required and for options to the details shown.


		Bridge Division Standard	
COMMON FOUNDATION DETAILS			
FD			
FILE: fdstd01-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT April 2019	CONTRACT	SECTION	HIGHWAY
0911	39	063	CR
01-20: Added #11 bars to the FD bars.		DIST:	COUNTY
		LFK	SHELBY
		SHEET NO. 48	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard.


DATE: 2/1/2022 5:16:39 PM
 FILE: G:\TXC\Projects\TxDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\03-SHELVY\FD\01-20.dgn





THREE PILE FOOTING^⑧
 For 36" Dia and smaller columns.



FOUR PILE FOOTING^⑧
 For 42" Dia and smaller columns.



FIVE PILE FOOTING^⑧
 For 42" Dia and smaller columns.



- ③ Min lap with column reinforcing:
 #7 Bars = 2'-11"
 #9 Bars = 3'-9"
 #11 Bars = 4'-8"
- ⑥ 1'-0" Min, unless shown otherwise on plans.
- ⑦ Or as shown on plans.
- ⑧ See Bridge Layout for type, size and length of piling.
- ⑨ Number and size of FD bars must match column reinforcing. Tie FD bars to the top of the bottom reinforcing mat.
- ⑩ Adjust FD quantity, size and weight as needed to match column reinforcing.

TABLE OF FOOTING QUANTITIES FOR 30" COLUMNS

ONE 3 PILE FOOTING					
Bar	No.	Size	Length	Weight	
F1	11	#4	3'- 2"	23	
F2	6	#4	8'- 2"	33	
F3	6	#4	6'- 11"	28	
F4	8	#9	3'- 2"	86	
F5	4	#9	6'- 11"	94	
F6	4	#9	8'- 2"	111	
FC	12	#4	3'- 6"	28	
FD ^⑩	8	#9	8'- 1"	220	
Reinforcing Steel				Lb	623
Class "C" Concrete				CY	4.8
ONE 4 PILE FOOTING					
Bar	No.	Size	Length	Weight	
F1	20	#4	7'- 2"	96	
F2	16	#8	7'- 2"	306	
FC	16	#4	3'- 6"	37	
FD ^⑩	8	#9	8'- 1"	220	
Reinforcing Steel				Lb	659
Class "C" Concrete				CY	6.3
ONE 5 PILE FOOTING					
Bar	No.	Size	Length	Weight	
F1	20	#4	8'- 2"	109	
F2	16	#9	8'- 2"	444	
FC	24	#4	3'- 6"	56	
FD ^⑩	8	#9	8'- 1"	220	
Reinforcing Steel				Lb	829
Class "C" Concrete				CY	8.0

CONSTRUCTION NOTES:

- See Bridge Layout for foundation type required. Use these foundation details unless shown otherwise.
- Drive piling under abutment wingwalls to a minimum resistance of 10 Tons/Pile unless shown otherwise.
- Provide Class C Concrete ($f'_c = 3,600$ psi), unless shown otherwise.
- Provide Grade 60 reinforcing steel.
- Galvanize reinforcing if shown elsewhere in the plans.
- Provide bar laps for drilled shaft reinforcing, where required, as follows:
 Uncoated or galvanized (#6) ~ 2'-6"
 Uncoated or galvanized (#7) ~ 2'-11"
 Uncoated or galvanized (#9) ~ 3'-9"

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications.
- Cover dimensions are clear dimensions, unless noted otherwise.
- Reinforcing bar dimensions shown are out-to-out of bar.

DESIGNER NOTES:

- Do not use the drilled shaft details shown on this standard for retaining wall, noise wall, barrier, or sign foundations without structural evaluation.
- Do not use the footings shown on this standard in direct contact with salt water or exposed to salt water spray.
- Maximum allowable pile loads for the footings shown are:
 72 Tons/Pile with 24" Dia Columns
 80 Tons/Pile with 30" Dia Columns
 100 Tons/Pile with 36" Dia Columns
 120 Tons/Pile with 42" Dia Columns

SHEET 2 OF 2




COMMON FOUNDATION DETAILS

FD


FILE: fdstd01-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
01-20: Added #11 bars to the FD bars.	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	49	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.


DATE: 2/1/2022 5:16:40 PM
 FILE: G:\TXC\Projects\TxDOT\6071-05_WA5_4CRBridges\03_CADD\01_Shts\07-BRDG\51-51-SBBS-B28-24.dgn



TYPICAL END DIAPHRAGM SECTIONS
 (along centerline of Box Beam)



CONTINUOUS SLAB DETAIL
 (Diaphragm reinforcing not shown for clarity)



TYPE A JOINT DETAIL 5

TABLE OF ESTIMATED QUANTITIES					
SPAN LENGTH	SHEAR KEY	REINF CONC SLAB (BOX BEAM)	PRESTR CONCRETE BOX BEAMS (TY 4B28) 13	PRESTR CONCRETE BOX BEAMS (TY 5B28) 13	TOTAL REINF STEEL 14
FT	CY	SF	LF	LF	Lb
30	7.9	785	118.00	59.00	1,570
35	9.3	916	138.00	69.00	1,832
40	10.6	1,047	158.00	79.00	2,094
45	12.0	1,177	178.00	89.00	2,354
50	13.3	1,308	198.00	99.00	2,616
55	14.7	1,439	218.00	109.00	2,878
60	16.0	1,570	238.00	119.00	3,140
65	17.4	1,701	258.00	129.00	3,402
70	18.7	1,832	278.00	139.00	3,664
75	20.0	1,962	298.00	149.00	3,924


- 5 If using Type A expansion joints, the maximum distance between joints is 100 ft.
- 7 Slab reinforcing omitted for clarity.
- 8 See Bridge Layout for Joint type.
- 9 Provide 1 1/2" end cover to Bars H. After all beams have been placed, weld one Bar H to two Bars D at each end of all beams.
- 10 Lap Bars DT 9" Min with each Beam Bar D at Interior Bents without Expansion Joints. Bars DT shown bent for clarity only.
- 11 Backer rod must be 25% larger than joint opening and must be compatible with the sealant.
- 12 Use Class 7 silicone sealant. Prepare joint and seal in accordance with Item 438 "Cleaning and Sealing Joints".
- 13 Fabricator must adjust beam lengths for beam slopes as required.
- 14 Reinforcing steel weight is based on an approximate factor of 2.0 lbs per square foot of slab.

HL93 LOADING SHEET 2 OF 2


		Bridge Division Standard	
PRESTRESSED CONCRETE BOX BEAM SPANS TYPE B28 24' RDWY (WITH SLAB)			
SBBS-B28-24			
FILE: bbst0s21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT December, 2066	CONT	SECT	JOB
REVISIONS	0911	39	063
01-12: Cover	DIST	COUNTY	SHEET NO.
10-15: Table of Est Quantities, Notes.	LFK	SHELBY	51

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this drawing. The user of this drawing shall be responsible for its use.


DATE: 2/1/2022 5:16:41 PM
 FILE: G:\TXDOT\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\03-SRR\std1-19.dgn




PLAN



ELEVATION




SECTION A-A AT CAP



SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A

CAP OPTION B

DETAIL C


① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2


					Bridge Division Standard	
<h1>STONE RIPRAP</h1>						
<h2>SRR</h2>						
FILE: srrstd1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES		
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY		
REVISIONS	0911	39	063	CR		
	DIST	COUNTY	SHEET NO.			
	LFK	SHELBY	52			

DATE: 2/1/2022 5:16:42 PM
 FILE: G:\TXDOT\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\05-Traffic\T631LS.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of units or for any errors, omissions, or damages resulting from its use.




- ① 9" Min, 5'-9" Max
- ② Maintain 6'-3" Rail Post spacing wherever possible for use with nominal 25'-0" or 12'-6" W-Beam sections. Symmetry of post spacing on both sides and along the structure is not necessary.
- ③ Increase 2" for structures with overlay.
- ④ Tighten the first hex nut by hand until the top and bottom edges of the W-Beam engage the Backer Plate (Backer Plate should be snug against the post). Then tighten hex nut one revolution with wrench and secure with the second hex nut.
- ⑤ PL 1/8" x 1 3/4" x 1 3/4" with 3/8" Dia Hole centered in PL (ASTM A36). Square Guardrail Washer (FWR01).
- ⑥ The post nearest to a slab joint or end of structure may be shifted up to 9" in order to satisfy the minimum offset dimension. Drill a new 3/4" Dia hole in the centerline of W-beam for shifted post. Paint hole with two coats of zinc-rich paint conforming to the Item "Galvanizing". All other posts must remain on the typical spacing.
- ⑦ 3/8" Dia formed holes for 3/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ASTM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod. See "Cast-In-Place & Formed Hole Anchor Bolt Options".
- ⑧ 3/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ASTM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod. See "Cast-In-Place & Formed Hole Anchor Bolt Options".

The use of this railing is restricted to speeds of 45 mph or less.



RAIL SECTION **TRAFFIC SIDE RAIL VIEW**
RAIL DETAILS ON BRIDGE SLAB
 Showing without overlay.




RAIL SECTION ON ABUTMENT WINGWALL
 Showing without overlay.


SHEET 1 OF 2

Texas Department of Transportation		Bridge Division Standard		
TRAFFIC RAIL				
TYPE T631LS				
FILE: r1std037-20.dgn	DN: TXDOT	CK: AES	DW: JTR	CK: AES
©TXDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
07-20: Allowing 9'-4" or 6'-3" W-Beam sections.	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	54	


DATE: 2/1/2022 5:16:43 PM
 FILE: G:\TXDOT\Projects\TXDOT\6071-05_WA5_4CRBR\ldges\03_CADD\01_Shts\07-BRDG\CS+BS_SHEBY\15100317-20.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this drawing to any other format.




W-BEAM ELEVATION




W-BEAM SPLICE ELEVATION



POST ELEVATION




SECTION A-A




WASHER PLATE DETAIL

$\frac{3}{8}$ " Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ATSM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod.



CAST-IN-PLACE & FORMED HOLE ANCHOR BOLT OPTIONS (10)

- 9 See "Rail Details On Bridge Slab" and/or "Rail Section On Abutment Wingwall".
- 10 See "Material Notes" for anchor bolt information.
- 11 Backer PL 1/8" x 8 x 1'-3" (ASTM A1011 CS or SS Gr 33, or A1008 CS or SS Gr 33 (11 Gage acceptable)).
- 12 Used for structures with overlay.
- 13 Used for structures without overlay.
- 14 At the nominal end of the bridge rail for payment, one 9'-4 1/2" or 6'-3" W-beam section is permitted in order to achieve the required W-Beam splice location on the MBGF.



BACKER PLATE

MBGF AND END TREATMENT NOTES:

This traffic railing must be anchored by metal beam guard fence (MBGF) and/or guard fence end treatments. Determine MBGF length of need in accordance with the Roadway Design Manual, unless otherwise specified. The minimum MBGF length of need required for anchoring the railing is: SGT; or DAT plus 12.5' of MBGF, as applicable. Provide CRT posts as shown in "Roadway Elevation of Rail."

CONSTRUCTION NOTES:

Face of rail post must be plumb unless otherwise approved by the Engineer. Post must be perpendicular to adjacent roadway grade. Use epoxy mortar under post base plates if gaps larger than 1/16" exist. Fully anchored guardrail must be attached to each end of rail. A metal beam guard fence transition is not used with this rail. At the Contractor's option anchor bolts may be an adhesive anchor system. See "Material Notes". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed. It is recommended to show a Rail Layout with rail posts and W-beam splices. Fabricator must submit erection drawings to the Engineer for approval. Round or chamfer exposed edges of rail post and backer plate to approximately 1/16" by grinding. Shop drawings are not required for this rail.

MATERIAL NOTES:

Galvanize all steel components. Anchor bolts for base plate must be 3/8" Dia ASTM F3125 Gr A325 or A449 bolts (or ASTM A193 Gr B7 or F1554 Gr 105 threaded rods with one tack welded heavy hex nut each) with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Optional adhesive anchorage system must be 3/8" Dia ASTM A193 Gr B7 or F1554 Gr 105 fully threaded rods with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed fully threaded rod into slab and/or abutment wingwall using a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4 3/4". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 8 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." W-beam must meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified in the plans. The Contractor may furnish rail elements of 25'-0" or 12'-6" (Nominal) lengths and a single rail element of 9'-4 1/2" or 6'-3" (Nominal) length. W-Beam must have slotted holes at 3'-1 1/2". Some part numbers from the "Task Force 13" Guide to Standardized Highway Barrier Hardware have been furnished for quick reference.

GENERAL NOTES:

This railing has been successfully evaluated by full-scale crash test to meet MASH TL-2 criteria. This railing can be used for speeds of 45 mph and less. This rail is designed to deflect approximately 2' to 2'-6" as it contains and redirects the errant vehicle. This rail may not be installed on top of or behind curbs that project above finished grade, on bridges with expansion joints providing more than 5" movement, on retaining walls, or on grade separations and interchanges. Repairs to impact-damaged post and base plate unit are not permitted. Replace all impact-damaged posts with a new post and base plate unit. Average weight of railing with no overlay: 13 plf total.

SHEET 2 OF 2

		Bridge Division Standard	
<h1>TRAFFIC RAIL</h1>			
<h2>TYPE T631LS</h2>			
FILE: r1std037-20.dgn	DN: TXDOT	CK: AES	DW: JTR
0911	39	063	CR
07-20: Allowing 9'-4 1/2" or 6'-3" W-Beam sections.	DIST: LFK	COUNTY: SHELBY	SHEET NO: 55

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$ FILE: ...Standards\dom1-20.dgn

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		
									INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back
SHEETING	Yellow, White or Red Type B or C reflective sheeting				SHEETING Yellow, White or Red Type B or C Reflective Sheeting				INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE WC YFLX, WFLX WC YFLX, WFLX				
					MOUNT TYPE GND GND, SRF GND GND, SRF				

OBJECT MARKERS														
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)						
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4						
								SHEETING Yellow-Type B _{FL} or C _{FL} Sheeting POST TYPE TWT MOUNT TYPE WAS, WAP						
	SHEETING Yellow - Type B or C Sheeting			SHEETING Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			SHEETING Red -Type B _{FL} or C _{FL} Sheeting	DEPARTMENTAL MATERIAL SPECIFICATIONS <table border="1"> <tr> <td>FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)</td> <td>DMS-4400</td> </tr> <tr> <td>SIGN FACE MATERIALS</td> <td>DMS-8300</td> </tr> <tr> <td>DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS</td> <td>DMS-8600</td> </tr> </table>	FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400	SIGN FACE MATERIALS	DMS-8300	DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400													
SIGN FACE MATERIALS	DMS-8300													
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600													
	POST TYPE TWT	POST TYPE WC	POST TYPE WC	POST TYPE WFLX	POST TYPE TWT			POST TYPE TWT						
	MOUNT TYPE WAS, WAP	MOUNT TYPE GND	MOUNT TYPE GND	MOUNT TYPE GND, SRF	MOUNT TYPE WAS, WAP			MOUNT TYPE WAS, WAP						

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.
DEVICE	GF1	GF2	CTB	W1-8				W1-6	
SHEETING	Yellow, White, Red			SIZE (W x L) 18"x 24" (Conventional) 24"x 30" (Conventional Oversize) 30"x 36" (Expressway) 36" x 48" (Freeway)				SIZE (W x L) 48" x 24" (Conventional) 60" x 30" (Expressway & Freeway)	
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			MOUNTING HEIGHT 4'-0" or 7'-0" 7'-0" Only				MOUNTING HEIGHT 7'-0"	
				NOTE				1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).	

Texas Department of Transportation
 Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION











D & OM(1)-20


FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	LFK	SHELBY	56	

20A

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
 FILE: ...Standards\dom2-20.dgn

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS		
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT	
GND	GND	SRF	WAS	WAP	GF1	
						
	EMBEDDED	SURFACE MOUNT	STEEL	PLASTIC	CONCRETE TRAFFIC BARRIER (CTB)	
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.			NOTE 1. Install per manufacturer's recommendations.		GENERAL NOTES 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.	
NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.						
TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS		
						
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		NOTE See general notes 1, 2 and 3.		



Texas Department of Transportation
Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	LFK	SHELBY	57	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022 \$TIME\$
 FILE: ...Standards\dom3-20.dgn

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation
Traffic Safety Division Standard


DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20

FILE: dom3-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	LFK	SHELBY	58	

20C


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**

D & OM(5)-20





FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
7-20	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	59	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




DATE: 2/2/2022 \$TIME\$
FILE: ...Standards\dom5-20.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/2/2022 \$TIME\$
 FILE: ...Standards\domvia-20.dgn





Object marker installed per manufacturer's recommendations.



* Adjust to fit attenuator per manufacturer's recommendation, or as directed by the Engineer




OBJECT MARKERS SMALLER THAN 3 FT²



NOTES

- *1. Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- 2. Mounting should be flush with top of attenuator. Minimum size 96" x 24".



NOTES

- 1. Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- 2. Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- 3. Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- 4. Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- 5. Object Marker at nose of attenuator is subsidiary to the attenuator.
- 6. See D & OM (1-4) for required barrier reflectors.


		Traffic Safety Division Standard	
DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS D & OM(VIA)-20			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT	SECT	JOB
REVISIONS		0911	39
4-92	8-04	063	CR
8-95	3-15	DIST	COUNTY
4-98	7-20	LFK	SHELBY
			SHEET NO. 60
20G			

CR 4123 AT BEAR BAYOU (CSJ: 0911-39-063)

THE PROPOSED WORK OF THIS PROJECT IS TO REPLACE THE BRIDGE AND APPROACHES AT CR 4123 OVER BEAR BAYOU. THE TOTAL DISTURBED AREA IS 0.445 ACRES. THE DISTURBED AREA IN THIS PROJECT AND THE CONTRACTOR PROJECT SPECIFIC LOCATIONS (PSLS) WITHIN 1 MILE OF THE PROJECT LIMITS FOR THE CONTRACT WILL FURTHER ESTABLISH THE AUTHORIZATION REQUIREMENTS FOR STORM WATER DISCHARGES. AS THE DISTURBED AREA INCLUDING PSLS IS LESS THAN 1 ACRE, THE TPDES CGP DOES NOT APPLY; HOWEVER, THE CONTRACTOR SHALL PLACE BMPs AS DIRECTED TO ADHERE TO WATER QUALITY REQUIREMENTS ASSOCIATED WITH SECTION 404/401 PERMITS. IF THE TOTAL AREA DISTURBED SHOWN IN THE PLANS AND PSLS WITHIN 1 MILE OF THE PROJECT LIMITS EXCEED 1 ACRE, THE ENGINEER WILL DEVELOP A SWP3 SITE PLAN AND POST A SMALL CONSTRUCTION SITE NOTICE FOR THE CONSTRUCTION ACTIVITIES.

FILENAME: ...\\10 SWP3\SWP3*INDEX01.dgn

DRAWING DATE: 2/4/2022



CG CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356





TXDOT SWP3 INDEX
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	LFK	SHELBY	61
CONTROL	SECTION	JOB	
0911	39	063	

FILENAME: ...\\10 SWP3\4123*SWP301.dgn

DRAWING DATE: 2/22/2022



- LEGEND**
- DISTURBED AREA/ PREP ROW
 - SEEDING
 - STONE RIPRAP
 - SOIL RETENTION BLANKET
 - POTENTIAL WETLANDS
 - SEDIMENT CONTROL FENCE
 - ROCK FILTER DAM (TY 2)
 - CONSTRUCTION FENCE
 - DITCH FLOW
 - SURFACE FLOW

- NOTES:**
1. SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCING ANY SOIL DISTURBING ACTIVITIES.
 2. ALL CONTROLS TO BE PLACED AS SHOWN ON STANDARDS EC(1)-16 AND EC(2)-16.
 3. ALL PERIMETER SEDIMENT CONTROLS TO REMAIN IN PLACE UNTIL END OF WORK.
 4. SOIL RETENTION BLANKET TO BE PLACED ON TOP OF TOPSOIL LIMITS IMMEDIATELY FOLLOWING THE SEEDING OPERATION.
 5. LOCATIONS OF EROSION CONTROL MEASURES MAY BE ADJUSTED IN THE FIELD AS DIRECTED BY ENGINEER.



02/23/2022

Trevor L. Castilla

CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



SWP3 LAYOUT
 (CR 4123 AT BEAR BAYOU)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	LFK	SHELBY	62
CONTROL	SECTION	JOB	
0911	39	063	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/4/2022 \$TIME\$
 .\09\FH\B-063*EPIC_1of2.dgn

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. N/A

No Action Required Required Action

Action No.

1. The proposed work of this project is to replace the bridge and approaches at CR 4123 over Bear Bayou. The total disturbed area is 0.445 acres. The disturbed area in this project and contractor project specific locations (PSLs) within 1 mile of the project limits for the contract will further establish the authorization requirements for storm water discharges. As the disturbed area including PSLs is less than 1 acre, the TPDES CGP does not apply; however, the contractor shall place BMPs as directed to adhere to water quality requirements associated with section 404/401 permits. If the total disturbed area shown in plans and PSLs within 1 mile of the project limits exceed 1 acre, the engineer will develop a SWP3 site plan and post a small construction site notice for the construction activities.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- The project area contains Bear Bayou
- Potential wetlands are present adjacent to the project area located Southeast of the bridge and East of Bear Bayou (See SWP3 layout). Avoid this area.
- Work MUST be conducted within the project area shown in plans.
- Refer to EPIC sheet 2 of 2 for Nationwide Permit #14 non-PCN requirements.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input checked="" type="checkbox"/> Blankets/Matting	<input checked="" type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input checked="" type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input checked="" type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required Required Action

Action No.

1. N/A

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required Required Action

Action No.

1. N/A

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

If any federally listed species are observed, cease work in the area immediately, do not disturb species or habitat and contact the Engineer.

No Action Required Required Action

Action No.

1. In order to maintain compliance with Chapter 64 of the Texas Parks and Wildlife Code and Migratory Bird Treaty Act (MBTA), construction activities that may affect nests (i.e. tree removal, tree limbing, bridge work) shall be conducted outside of the nesting season (March 15 to September 15). In the event birds or active nests (eggs and/or nestlings present) are encountered, contact the engineer prior to conducting work.

TPWD Commitment Notes:

1. Big brown bat, Eastern red bat, Tricolored bat, Eastern spotted skunk, Long-tailed weasel, and Swamp rabbit may occur in the project area. Avoid harming species if encountered. Avoid or minimize disturbing or removing downed logs, leaf litter, stumps, and dens, where feasible. Retain mature, large diameter hardwood forest trees, where feasible.

2. Eastern box turtle, Pigmy rattlesnake, and Timber rattlesnake may occur in the project area. Avoid harming species if encountered. If the species are found on project site, allow species to safely leave the project area. Visually inspect excavation areas for trapped wildlife prior to backfilling. Avoid or minimize disturbing or removing down trees, rotting stumps, and leaf litter, where feasible.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SWP3: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required Required Action

Action No.

- Bridge Testing complete. Lead and Asbestos were NOT detected on CR 4123 at Bear Bayou Bridge; therefore, the requirements of item 6 provisions are not required. Contractor may request a copy of the Asbestos and Lead Paint Inspection Report from the Area Engineer.


VII. OTHER ENVIRONMENTAL ISSUES

Two Old Growth Trees are present within and adjacent to the project area. See SWP3 layout for locations. The following actions are required:

No Action Required Required Action

Action No.

- Place construction fencing around both trees.
- Do NOT remove, trim, or disturb trees.

		Design Division Standard		
<p>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</p> <p>EPIC</p> <p>SHEET 1 OF 2</p>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0911	39	063	CR
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	LFK	SHELBY		63

NWP GENERAL CONDITIONS

AS APPLICABLE TO
THIS PROJECT

2. AQUATIC LIFE MOVEMENTS. NO ACTIVITY MAY SUBSTANTIALLY DISRUPT THE NECESSARY LIFE CYCLE MOVEMENTS OF THOSE SPECIES OF AQUATIC LIFE INDIGENOUS TO THE WATERBODY, INCLUDING THOSE SPECIES THAT NORMALLY MIGRATE THROUGH THE AREA, UNLESS THE ACTIVITY'S PRIMARY PURPOSE IS TO IMPOUND WATER.
3. SPAWNING AREAS. ACTIVITIES IN SPAWNING AREAS DURING SPAWNING SEASONS MUST BE AVOIDED TO THE MAXIMUM EXTENT PRACTICABLE. ACTIVITIES THAT RESULT IN THE PHYSICAL DESTRUCTION (E.G., THROUGH EXCAVATION, FILL, OR DOWNSTREAM SMOTHERING BY SUBSTANTIAL TURBIDITY) OF AN IMPORTANT SPAWNING AREA ARE NOT AUTHORIZED.
6. SUITABLE MATERIAL. NO ACTIVITY MAY USE UNSUITABLE MATERIAL (E.G., TRASH, DEBRIS, CAR BODIES, ASPHALT, ETC.). MATERIAL USED FOR CONSTRUCTION OR DISCHARGED MUST BE FREE FROM TOXIC POLLUTANTS IN TOXIC AMOUNTS (SEE SECTION 307 OF THE CLEAN WATER ACT).
8. ADVERSE EFFECTS FROM IMPOUNDMENTS. IF THE ACTIVITY CREATES AN IMPOUNDMENT OF WATER, ADVERSE EFFECTS TO THE AQUATIC SYSTEM DUE TO ACCELERATING THE PASSAGE OF WATER, AND/OR RESTRICTING ITS FLOW MUST BE MINIMIZED TO THE MAXIMUM EXTENT PRACTICABLE.
9. MANAGEMENT OF WATER FLOWS. TO THE MAXIMUM EXTENT PRACTICABLE, THE PRE-CONSTRUCTION COURSE, CONDITION, CAPACITY, AND LOCATION OF OPEN WATERS MUST BE MAINTAINED FOR EACH ACTIVITY, INCLUDING STREAM CHANNELIZATION AND STORM WATER MANAGEMENT ACTIVITIES, EXCEPT AS PROVIDED BELOW. THE ACTIVITY MUST BE CONSTRUCTED TO WITHSTAND EXPECTED HIGH FLOWS. THE ACTIVITY MUST NOT RESTRICT OR IMPEDE THE PASSAGE OF NORMAL OR HIGH FLOWS, UNLESS THE PRIMARY PURPOSE OF THE ACTIVITY IS TO IMPOUND WATER OR MANAGE HIGH FLOWS. THE ACTIVITY MAY ALTER THE PRE-CONSTRUCTION COURSE, CONDITION, CAPACITY, AND LOCATION OF OPEN WATERS IF IT BENEFITS THE AQUATIC ENVIRONMENT (E.G., STREAM RESTORATION OR RELOCATION ACTIVITIES).
11. EQUIPMENT. HEAVY EQUIPMENT WORKING IN WETLANDS OR MUD FLATS MUST BE PLACED ON MATS, OR OTHER MEASURES MUST BE TAKEN TO MINIMIZE SOIL DISTURBANCE.
12. SOIL EROSION AND SEDIMENT CONTROLS. APPROPRIATE SOIL EROSION AND SEDIMENT CONTROLS MUST BE USED AND MAINTAINED IN EFFECTIVE OPERATING CONDITION DURING CONSTRUCTION, AND ALL EXPOSED SOIL AND OTHER FILLS, AS WELL AS ANY WORK BELOW THE ORDINARY HIGH WATER MARK OR HIGH TIDE LINE, MUST BE PERMANENTLY STABILIZED AT THE EARLIEST PRACTICABLE DATE. PERMITTEES ARE ENCOURAGED TO PERFORM WORK WITHIN WATERS OF THE UNITED STATES DURING PERIODS OF LOW-FLOW OR NO-FLOW.
13. REMOVAL OF TEMPORARY FILLS. TEMPORARY FILLS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO PRE-CONSTRUCTION ELEVATIONS. THE AFFECTED AREAS MUST BE REVEGETATED, AS APPROPRIATE.
14. PROPER MAINTENANCE. ANY AUTHORIZED STRUCTURE OR FILL SHALL BE PROPERLY MAINTAINED, INCLUDING MAINTENANCE TO ENSURE PUBLIC SAFETY AND COMPLIANCE WITH APPLICABLE NWP GENERAL CONDITIONS, AS WELL AS ANY ACTIVITY-SPECIFIC CONDITIONS ADDED BY THE DISTRICT ENGINEER TO AN NWP AUTHORIZATION.
23. MITIGATION. THE DISTRICT ENGINEER WILL CONSIDER SEVERAL FACTORS WHEN DETERMINING APPROPRIATE AND PRACTICABLE MITIGATION NECESSARY TO ENSURE THAT ADVERSE EFFECTS ON THE AQUATIC ENVIRONMENT ARE MINIMAL.
25. WATER QUALITY. WHERE STATES AND AUTHORIZED TRIBES, OR EPA WHERE APPLICABLE, HAVE NOT PREVIOUSLY CERTIFIED COMPLIANCE OF AN NWP WITH CWA SECTION 401, INDIVIDUAL 401 WATER QUALITY CERTIFICATION MUST BE OBTAINED OR WAIVED (SEE 33 CFR 330.4(C)). THE DISTRICT ENGINEER OR STATE OR TRIBE MAY REQUIRE ADDITIONAL WATER QUALITY MANAGEMENT MEASURES TO ENSURE THAT THE AUTHORIZED ACTIVITY DOES NOT RESULT IN MORE THAN MINIMAL DEGRADATION OR WATER QUALITY.
27. REGIONAL AND CASE-BY-CASE CONDITIONS. THE ACTIVITY MUST COMPLY WITH ANY REGIONAL CONDITIONS THAT MAY HAVE BEEN ADDED BY THE DIVISION ENGINEER (SEE 33 CFR 330.4(E)) AND WITH ANY CASE SPECIFIC CONDITIONS ADDED BY THE CORPS OR BY THE STATE, INDIAN TRIBE, OR U.S. EPA IN ITS SECTION 401 WATER QUALITY CERTIFICATION, OR BY THE STATE IN ITS COASTAL ZONE MANAGEMENT ACT CONSISTENCY DETERMINATION.

FOR A COMPLETE LIST OF GENERAL CONDITIONS GO TO:

<http://www.swf.usace.army.mil/Missions/Regulatory/Permitting/NationwideGeneralPermits.aspx>

USACE - PERMIT #14

AS APPLICABLE TO
THIS PROJECT

ACTIVITIES REQUIRED FOR CROSSINGS OF WATERS OF THE UNITED STATES ASSOCIATED WITH THE CONSTRUCTION, EXPANSION, MODIFICATION, OR IMPROVEMENT OF LINEAR TRANSPORTATION PROJECTS (E.G., ROADS, HIGHWAYS, RAILWAYS, TRAILS, AIRPORT RUNWAYS, AND TAXIWAYS) IN WATERS OF THE U.S. FOR LINEAR TRANSPORTATION PROJECTS IN NON-TIDAL WATERS, THE DISCHARGE CANNOT CAUSE THE LOSS OF GREATER THAN 1/2-ACRE OF WATERS OF THE U.S. ANY STREAM CHANNEL MODIFICATION, INCLUDING BANK STABILIZATION, IS LIMITED TO THE MINIMUM NECESSARY TO CONSTRUCT OR PROTECT THE LINEAR TRANSPORTATION PROJECT; SUCH MODIFICATIONS MUST BE IN THE IMMEDIATE VICINITY OF THE PROJECT.

THIS NWP ALSO AUTHORIZES TEMPORARY STRUCTURES, FILLS, AND WORK NECESSARY TO CONSTRUCT THE LINEAR TRANSPORTATION PROJECT. APPROPRIATE MEASURES MUST BE TAKEN TO MAINTAIN DOWNSTREAM FLOWS AND MINIMIZE FLOODING TO THE MAXIMUM EXTENT PRACTICABLE, WHEN TEMPORARY STRUCTURES, WORK, AND DISCHARGES, INCLUDING COFFERDAMS, ARE NECESSARY FOR CONSTRUCTION ACTIVITIES, ACCESS FILLS, OR DEWATERING OF CONSTRUCTION SITES. TEMPORARY FILLS MUST CONSIST OF MATERIALS, AND BE PLACED IN A MANNER THAT WILL NOT BE ERODED BY EXPECTED HIGH FLOWS. TEMPORARY FILLS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO PRE-CONSTRUCTION ELEVATIONS. THE AREAS AFFECTED BY TEMPORARY FILLS MUST BE REVEGETATED, AS APPROPRIATE.

THIS NWP CANNOT BE USED TO AUTHORIZE NON-LINEAR FEATURES COMMONLY ASSOCIATED WITH TRANSPORTATION PROJECTS, SUCH AS VEHICLE MAINTENANCE OR STORAGE BUILDINGS, PARKING LOTS, TRAIN STATIONS, OR AIRCRAFT HANGARS.

NOTIFICATION: THE PERMITTEE MUST SUBMIT A PRE-CONSTRUCTION NOTIFICATION (PCN) TO THE DISTRICT ENGINEER PRIOR TO COMMENCING THE ACTIVITY IF: (1) THE LOSS OF WATERS OF THE U.S. EXCEEDS 1/10-ACRE; OR (2) THERE IS A DISCHARGE IN A SPECIAL AQUATIC SITE, INCLUDING WETLANDS.

NOTE:

THE PROJECT CROSSES JURISDICTIONAL WATERS OF THE U.S. AND A NWP #14 WITH NO PCN HAS BEEN UTILIZED. THIS PERMIT AUTHORIZES THE ACTIVITIES WHICH WILL IMPACT WATERS OF THE U.S. THE NWP GENERAL CONDITIONS AND THE NWP #14 LIMITS MUST BE FOLLOWED IN ORDER TO MAINTAIN COMPLIANCE WITH THE NWP. NO COORDINATION HAS TAKEN PLACE WITH THE USACE BECAUSE IMPACTS WILL NOT EXCEED THE ABOVE CRITERIA. IF COORDINATION MAY BE NEEDED, CONTACT THE TXDOT LUFKIN DISTRICT ENVIRONMENTAL SECTION AT 1-800-687-8087.

ENVIRONMENTAL PERMITS,
ISSUES AND COMMITMENTS (EPIC) □

USACE



EPIC
(ENVIRONMENTAL PERMITS,
ISSUES AND COMMITMENTS)


SHEET 2 OF 2

FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0911	39	063	CR
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	LFK	SHELBY		64

DATE: 2/2/2022 \$TIME\$ FILE: ...\\0911-39-063_EPIC_2of2_NWP14_non-PCN.dgn


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE 2/2/2022
 FILE ...\\10_SWP3\Standards\ec116.dgn



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16

FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	39	063	CR
	DIST	COUNTY	SHEET NO.	
	LFK	SHELBY	65	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/2/2022
FILE: \\10 SWP3\Standards\ec216.dgn



FILTER DAM AT TOE OF SLOPE



(RFD1)



"V" SHAPE PLAN VIEW


PLAN VIEW

SECTION B-B




TYPE 4 (SACK GABIONS)

(RFD4)




SECTION A-A




FILTER DAM AT SEDIMENT TRAP

(RFD2) OR (RFD1)



PROFILE



SECTION C-C

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.


Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.



FILTER DAM AT CHANNEL SECTIONS

(RFD3) OR (RFD2) OR (RFD1)

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.



PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC (2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT: 0911	SECT: 39	JOB: 063
REVISIONS	DIST: LFK	COUNTY: SHELBY	SHEET NO.: 66

FILENAME: ...PS&E2*XSEC.dgn

DRAWING DATE: 2/2/2022



CIVIL CONSULTING GROUP
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356




CROSS SECTIONS
 (CR 4123 AT BEAR BAYOU)

(SHEET 1 OF 8)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	SHELBY	
CONTROL	SECTION	JOB	
0911	39	063	
			SHEET NO.
			67

FILENAME: ...PS&E2*XSEC.dgn
DRAWING DATE: 2/2/2022



0' 5' 10'

SCALE: 1"=10' H
1"=10' V

Civil Consulting Group
1575 HERITAGE DRIVE, STE. 308
MCKINNEY, TEXAS 75069
P 972.569.9193 F 972.569.9197
TEXAS REGISTERED ENGINEERING FIRM NO. F-9356

Texas Department of Transportation
© 2022



CROSS SECTIONS
(CR 4123 AT BEAR BAYOU)

(SHEET 3 OF 8)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO. 69

FILENAME: ...PS&E2*XSEC.dgn

DRAWING DATE: 2/2/2022



Civil Consulting Group
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356





CROSS SECTIONS
 (CR 4123 AT BEAR BAYOU)

(SHEET 4 OF 8)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	SHELBY	
CONTROL	SECTION	JOB	
0911	39	063	
			SHEET NO.
			70

FILENAME: ...PS&E2*XSEC.dgn

DRAWING DATE: 2/2/2022



Civil Consulting Group
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356





CROSS SECTIONS
 (CR 4123 AT BEAR BAYOU)

(SHEET 5 OF 8)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	SHELBY	
CONTROL	SECTION	JOB	
0911	39	063	
			SHEET NO.
			71

FILENAME: ...PS&E2*XSEC.dgn

DRAWING DATE: 2/2/2022



Civil Consulting Group
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356





CROSS SECTIONS
 (CR 4123 AT BEAR BAYOU)

(SHEET 6 OF 8)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	SHELBY	
CONTROL	SECTION	JOB	
0911	39	063	
			SHEET NO.
			72

FILENAME: ...PS&E2*XSEC.dgn

DRAWING DATE: 2/2/2022



Civil Consulting Group
 1575 HERITAGE DRIVE, STE. 308
 MCKINNEY, TEXAS 75069
 P 972.569.9193 F 972.569.9197
 TEXAS REGISTERED ENGINEERING FIRM NO. F-9356






CROSS SECTIONS
 (CR 4123 AT BEAR BAYOU)

(SHEET 7 OF 8)

FED. RD. DIST. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		CR	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	SHELBY	
CONTROL	SECTION	JOB	
0911	39	063	
			SHEET NO.
			73

FILENAME: ...PS&E2*XSEC.dgn
DRAWING DATE: 2/2/2022



CG CIVIL CONSULTING GROUP
1575 HERITAGE DRIVE, STE. 308
MCKINNEY, TEXAS 75069
P 972.569.9193 F 972.569.9197
TEXAS REGISTERED ENGINEERING FIRM NO. F-9356



CROSS SECTIONS
(CR 4123 AT BEAR BAYOU)

(SHEET 8 OF 8)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		CR
STATE	DISTRICT	COUNTY
TEXAS	LFK	SHELBY
CONTROL	SECTION	JOB
0911	39	063
		SHEET NO.
		74