

DATE: 4/28/2022 2:59:41 PM
 FILE: D:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DWGNS CREATED\0218-04-kt19_INDEX OF SHEETS.dgn

INDEX OF SHEETS

| SHEET | DESCRIPTION | SHEET | DESCRIPTION |
|-----------------------------|--|----------------------------------|--|
| GENERAL | | ROADWAY DETAILS CONTINUED | |
| 1 | TITLE SHEET | # 47-48 | GF(31)TR TL3-20 |
| 2 | INDEX OF SHEETS | # 49 | GF(31)MS-19 |
| 3 | TYPICAL SECTIONS | 50 | C-RAIL-R (MOD) |
| 4, 4A - 4F | GENERAL NOTES | # 51-52 | TYPE SSTR |
| 5, 5A | ESTIMATE & QUANTITY | 53-95 | ROADWAY CROSS SECTIONS |
| 6-8 | MISCELLANEOUS SUMMARIES | | |
| TRAFFIC CONTROL PLAN | | TRAFFIC ITEMS | |
| 9 | SEQUENCE OF WORK | # 96 | PM(2)-20 |
| 10 | TREATMENT FOR VARIOUS EDGE CONDITIONS | # 97 | PM(3)-20 |
| 11 | CRASH CUSHION SUMMARY SHEET | # 98 | CPM(1)-14 |
| 12 | TRAFFIC CONTROL PLAN FOR BRIDGE RAIL REPLACEMENT | # 99 | D & OM(1)-20 |
| # 13-24 | BC(1)-21 THRU BC(12)-21 | # 100 | D & OM(2)-20 |
| # 25 | TCP(ATL-12)-14 | # 101 | D & OM(3)-20 |
| # 26 | TCP(ATL-16)-15 | # 102 | D & OM(6)-20 |
| # 27 | TCP(ATL-19)-15 | # 103 | D & OM(VIA)-20 |
| # 28 | TCP(3-1)-13 | # 104 | RS(1)-13 |
| # 29 | TCP(3-3)-14 | # 105 | OMMITED |
| # 30 | WZ(STPM)-13 | | |
| # 31 | WZ(UL)-13 | 106 | ENVIRONMENTAL ISSUES |
| # 32 | WZ(RS)-22 | 107 | TxDOT STORM WATER POLLUTION PREVENTION PLAN (SWP3) |
| # 33-33A | SSCB(2)-10 | # 108 | ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS |
| # 34 | ABSORB-19 | | EC(1)-16 |
| # 35 | SLED-19 | | |
| # 36 | VIA(SFPM)-19 | | |
| ROADWAY DETAILS | | | |
| 37-38 | US 59 HORIZONTAL AND VERTICAL CONTROL | | |
| 39 | US 59 SURVEY CONTROL SHEET | | |
| 40 | ROADWAY DETAILS | | |
| 41 | MBGF LAYOUTS | | |
| # 42 | SGT(10S)31-16 | | |
| # 43 | SGT(11S)31-18 | | |
| # 44 | SGT(12S)31-18 | | |
| # 45 | SGT(15S)31-20 | | |
| # 46 | GF(31)-19 | | |

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A POUND "#" HAVE BEEN ISSUED BY ME, OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.





Glenn R. Yowell, P.E.
 4-28-22

INDEX OF SHEETS

| | | | |
|---------------------|-------------|-----------|-------------|
| © 2022 | | | |
| | | | |
| FHWA TEXAS DIVISION | PROJECT NO. | SHEET NO. | |
| | C218-4-119 | 2 | |
| STATE | DISTRICT | COUNTY | |
| TEXAS | ATL | CASS | |
| CONTROL | SECTION | JOB | HIGHWAY NO. |
| 0218 | 04 | 119 | US 59 |

FILE: \\f\tdot\project\wiseon1\ine.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\0218-04-119*TYPICAL SECTIONS.DWG
 DATE: 4/22/2022 11:26:33 AM




TAPERED LONGITUDINAL JOINT DETAIL

SEE GENERAL NOTES FOR ADDITIONAL INFORMATION

NOTE: THE TAPERED LONGITUDINAL JOINT DETAIL IS FOR 2" SMA-D PG76-22


PROPOSED SECTION

STA. 100+00.00 TO STA. 164+40.00
 STA. 167+20.00 TO STA. 221+80.00




PLANING SECTION

STA. 100+00.00 TO STA. 164+40.00
 STA. 167+20.00 TO STA. 221+80.00



EXISTING SECTION


STA. 112+00.00 TO STA. 164+40.00
 STA. 167+20.00 TO STA. 221+80.00



| SUPERELEVATION TABLE | | |
|----------------------|-------|------------|
| STATION | "E" | TRANSITION |
| 100+00.00 | 0.029 | 200' |
| 107+52.00 | 0.029 | 200' |
| 208+80.00 | 0.029 | 300' |
| 214+42.00 | 0.029 | 300' |

NOTE:
 SEE SURVEY CONTROL SHEETS FOR PROPOSED
 CONSTRUCTION HORIZONTAL ALIGNMENT
 AND VERTICAL ALIGNMENT.

* SEE CROSS SECTION SHEETS FOR ADDITIONAL INFORMATION.




Glenn R. Yowell, P.E.

4-22-22

TYPICAL SECTIONS

NOT TO SCALE



| | | |
|---------------------|-------------------------|-------------|
| FHWA TEXAS DIVISION | FEDERAL AID PROJECT NO. | SHEET NO. |
| | | 3 |
| STATE | DISTRICT | COUNTY |
| TEXAS | ATL | CASS |
| CONTROL | SECTION | JOB |
| 0218 | 04 | 119 |
| | | HIGHWAY NO. |
| | | US 59 |

GENERAL NOTES:

General Requirements and Covenants:

An inspection to determine the presence of asbestos was performed on the bridge structure(s) with the following results:

A: None found

Contractor questions on this project are to be addressed to the following individuals:

Thomas Bruce P.E. – Area Engineer
Tommy.Bruce@Txdot.gov
Dana Moore – Assistant Area Engineer
Dana.Moore@Txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type Construction (Construction or Maintenance), Letting Date, CCSJ/Project Name.

All roadside signs, mailbox supports, delineators, and object markers located within the project limits shall be plumbed as part of the final cleanup. This work will not be paid for separately but will be considered subsidiary to the various bid items.

ITEM 5 – Control of the Work:

Prior to contract letting, bidders may request a free electronic copy of the files that contain the surface model, cross slope and proposed profile information from the District Office in Atlanta. If printed copies of the actual cross-sections in addition to, or instead of, the electronic files are requested, prospective bidders may purchase prints of the cross sections from the District Office in Atlanta.

Place construction points, stakes, and marks at intervals of no more than 100 ft. for the work areas per phase, or as directed. Place stakes and marks so as not to interfere with normal maintenance operations.

It is the Contractor's responsibility to verify the accuracy of any department provided control points prior to use.

It is the intent of the plans to plane the existing roadway to 7 inches below the proposed profile grade line (PGL), place 5 inches of SP-C and 2 inches of SMA-D to the proposed lines and grades shown in the plans.

The intent of the Phase 2 and 2A variable depth planing to 2 inches below the proposed PGL as shown on Sequence of Work is to ensure that each pass of the subsequent 5-inch planing and 5-inch placement of the SP-C will match the adjacent planed surface. This will eliminate a pavement drop off between proposed and existing lanes during the Intermediate Term Stationary TCP phases and allow a uniform surface prior to placement of the final 2-inch SMA-D surface.

The following is the verification process to be used on this project to check elevations and cross slope for each phase of the pavement structure operation. The proposed elevations and cross slopes shall be measured at a minimum frequency of one measurement every 100 feet and for each phase of the pavement structure operation. The number of measurements may be reduced by demonstrating consistently acceptable results, with the approval of the Engineer. Furnish a digital measuring device approved by the Engineer for the measurement of cross slope and elevations. Make this measuring device available at the jobsite for the Engineer's use. Report the cross slope to the nearest 0.01% and elevations to the nearest 0.01 feet. Record all measurements on an approved form signed and dated certifying correct and submit to the Engineer the next working day for documentation. The Engineer will determine the number of verification measurements.

Tolerance
Elevation: Plus or minus 0.03ft
Cross slope: Plus or Minus 0.25%

All corrections to the elevations or cross slopes that do not meet the tolerance's shown above shall be corrected as approved by Engineer prior to beginning the next phase of construction.

When Phase 2 and 2A variable depth planing is complete, verify roadway elevations and cross slopes match the proposed cross sections using the verification process described above and all planed surfaces match the adjacent planed surface.

Once Plane Asph Conc Pav (5") is completed in subsequent phases the same measurements as described above will be repeated and verified.

After placement of each lift of the 5 inch SP-C, verify roadway elevations and cross slope as described above.

After placement of the 2 inch SMA-D, verify roadway elevations and cross slope as described above.

ITEM 7 – Legal Relations and Responsibilities:

This project is considered a maintenance activity and is exempt from the Construction General Permit (CGP) coverage.

The Contractor will not remove active nests from bridges and other structures during nesting season of the birds associated with the nests.

RAP material generated may be used for ingress and egress to drives and intersections or construction exits. When removed, stockpile this material separately from other RAP material.

No significant traffic generator events.

ITEM 8 – Prosecution and Progress:

Working days will be charged in accordance with Section 8.3.1.4, "Standard Workweek".

Refer to SP 008---003 for additional information regarding beginning of working day charges. The 90-day delay for this project is to allow for warmer weather for placement of the SMA surface course.

The road-user cost liquidated damages are \$10,826.00 per day.

ITEM 132 – Embankment:

Furnish material with an organic content less than 1.0%. The Engineer will test using UV-VIS equipment and procedure determined by TxDOT. Allow two weeks for testing.

Test borrow sources and furnish results to the Engineer.

Remove deleterious material, organic matter, and sediment, etc., from all ponds, lakes, sloughs, channels, and existing roadway ditches prior to placement of embankment. This work will be subsidiary to this item.

ITEM 134 – Backfilling Pavement Edges:

After the application of fertilizer apply an emulsified asphalt treatment, consisting of SS-1 asphalt, at a rate of 0.3 gal. per sq. yd.

ITEM 164 – Seeding for Erosion Control:

PERMANENT PLANTING MIXTURE

Species and Rates
(lb. PLS/ac.)

(Season: February 1 to May 15)

| | |
|----------------------|------|
| Green Sprangletop | 0.4 |
| Bermudagrass | 2.4 |
| Sand Lovegrass | 1.0 |
| Lance-Leaf Coreopsis | 1.25 |

(Season: September 1 to November 30)

| | |
|--------------------|----|
| Bermuda (Unhulled) | 12 |
| Crimson Clover | 10 |

TEMPORARY SEEDING FOR EROSION CONTROL

Warm Season

(Season: May 15 to August 31)

| | |
|----------------|----|
| Bermudagrass | 6 |
| Foxtail Millet | 34 |

Cool Season

(Season: September 1 to November 30)

| | |
|-------------|-----|
| Tall Fescue | 4.5 |
| Oats | 24 |
| Wheat | 34 |

Adjust the seeding mixture and rates if directed.

Inoculate crimson clover seed with a legume inoculant. Sow inoculated seed dry, with either hand operated or mechanical equipment, after the fertilizer is placed.

Do not use Bahia grass.

Use crimper immediately after spreading mulch. Apply ballast to machine to achieve an anchoring depth of 2 to 3 inches to form soil-binding mulch and to prevent loss or bunching of the mulch by wind. Anchor the machine to prevent the formation of ridges and ruts. Use coulters at least ten inches in diameter. Traverse slopes horizontally. The number of passes needed, not to exceed three, will be as directed. In areas where an anchoring machine cannot be used, the Department will require a tacking agent be used in the mulch as directed.

Use broadcast seeding for temporary erosion control, when and as directed. This will not be paid for directly but is subsidiary to the various bid items.

Use additional temporary seeding if permanent seeding is placed outside the optimum growing season shown for this item, if directed.

Finish slopes with a tracked vehicle running vertically up and down the slope.

After the application of fertilizer, apply an emulsified asphalt treatment, consisting of SS-1 asphalt, at a rate of 0.3 gal. per sq. yd.

Mow tall growing vegetation as directed, to provide optimum growing conditions for temporary or permanent seeded areas in accordance with Item 730 "Roadside Mowing" except for measurement and payment. This work will be subsidiary to pertinent bid items.

ITEM 166 - Fertilizer:

When seeding between September 1 and January 1, place one-half of the amount of fertilizer specified for seeding with the seeds and place the remainder the following spring unless otherwise directed. When seeding is placed between January 1 and June 1, place one-half the amount of fertilizer specified for seeding with the seeds and place the remainder 30 days later unless otherwise directed.

Apply fertilizer (13-13-13) at a rate of 300 lbs. /5000 sq. yds.

ITEM 301 – Asphalt Antistripping Agents:

Add hydrated lime to the aggregate by the following method only: mix in an approved pug mill mixer with damp aggregate containing water at least 2% above saturated surface dry conditions.

ITEM 320 – Equipment for Asphalt Concrete Pavement:

Provide a Material Transfer Device (MTD) with remixing capability.

ITEM 354 – Planing and Texturing Pavement:

The Department shall retain ownership of 12,000CY of the material removed under this Item to be stockpiled at the following location: North of Spur 236 at US 59 North bound side of the roadway. LAT. 33° 9'38.94"N, LONG. 94° 9'0.62"W.

Approximately 1,289 CY of planned material will be retained for use for BACKFILL PAVEMENT EDGES TY B.

Contractor shall retain the remaining quantity of the planed ACP.

ITEM 421 – Hydraulic Cement Concrete:

The Department will furnish and maintain concrete compressive strength testing equipment.

ITEM 427 – Surface Finishes for Concrete:

Provide a brushed finish for surface area III.

ITEM 432 - Riprap:

Provide ½" expansion joint material with an area equal to the area of contact between the two concrete surfaces. The joint material will be visually inspected for approval.

ITEM 440 – Reinforcement for Concrete:

The following bridge elements require epoxy-coated reinforcement: Bridge Railing

ITEM 502 – Barricades, Signs, and Traffic Handling:

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Install temporary rumble strips in accordance with WZ(RS) whenever short duration or short-term stationary lane closures are in place and workers are present.

The Contractor's responsible person (CRP) will be responsible for ensuring that the signs and traffic control devices are in place and functioning properly.

The CRP will inspect and ensure any deficiencies are corrected each and every day throughout the duration of this contract. Notify the Engineer in writing of the name, address, and telephone number of this employee or these employees.

No partial lane widths are to remain unplanned at the end of each day’s planning operations. Plane only a length of roadway that can be completed a full lane width by the end of the working day.

Begin ACP laydown operations after the planing operations as soon as it is feasible. The distance that the planing operation is ahead of the ACP laydown operation may be adjusted by the Engineer.

Length of lane closures will be as directed based on the demonstrated ability to prosecute the work within the closed section.

Plan and coordinate ACP surface placements so that traffic lanes will not be left with open longitudinal joints for more than 2 days placement.

Maintenance of driveways and intersections will not be paid for directly but is subsidiary to the pertinent bid items.

Restrict the movement of equipment across traffic lanes to an absolute minimum.

Use strobe lights or rotating beacons on all motorized equipment, operating on or adjacent to the road surface.

Place and maintain U.S. mailboxes within project limits in such a manner as to ensure continuous mail service. See BC Standard for more information.

ITEM 506 – Temporary Erosion, Sedimentation, and Environmental

Controls:

Sprinkle water for dust control. Meet the requirements of Item 204, “Sprinkling” except for measurement and payment. Sprinkling will be considered subsidiary to this Item.

Provide the following Item(s), as directed, to be used for erosion and water pollution control measures and any additional erosion or water pollution control measure deemed necessary by the Engineer:

Temporary sediment control fence

Provide and install additional erosion or water pollution control measures deemed necessary by the Engineer as prescribed by this item and in accordance with the appropriate specification. Payment for erosion control measures for which applicable pay items are not included in the Contract shall be made in accordance with Article 9.7, “Payment for Extra Work and Force Account Method”.

ITEM 512 – Portable Traffic Barrier:

Replace any traffic barrier which, in the opinion of the engineer, is damaged to the extent that it is no longer serviceable. This work will be measured and paid for in accordance with item 512, “Portable Concrete Traffic Barrier.”

ITEM 540 – Metal Beam Guard Fence:

Furnish round timber posts unless otherwise shown.

Place sufficient dry batch concrete mix in holes to ensure minimum of 2-inch embedment of tubes and posts.

ITEM 544 – Guardrail End Treatments:

Place sufficient dry batch concrete mix in holes to ensure minimum of 2-inch embedment of tubes and posts.

ITEM 585 – Ride Quality for Pavement Surfaces:

Use surface test Type B pay adjustment schedule 1 to evaluate ride quality of the travel lanes in accordance with this Item.

Before placing the final lift of ACP, profile the roadway for approval or corrective action, if necessary, at no cost to the Department.

ITEM 658 – Delineator and Object Marker Assemblies:

Install only round posts meeting the requirements of DMS-4400 or as directed.

ITEM 662 – Work Zone Pavement Markings:

Non-removable pavement markings may be paint and beads.

ITEM 666 - Reflectorized Pavement Markings:

Furnish and place a double drop of Type II and Type III drop-on glass beads.

Place pavement markings only after the surface treatment has cured to the satisfaction of the Engineer.

Place pavement markings within 14 days after completion of the final surface.

Mark the lateral locations of pavement markings with pilot lines. Obtain approval of the location and alignment of the pilot lines before application of permanent markings.

A mobile unit will be required to take reflectivity readings, readings will be taken on all lines in both directions. The mobile reflectivity readings will not be paid for separately but will be subsidiary to this bid item. Strict compliance with report output will be exercised in accordance to this general note. Information for each road must be together in the same file and submitted on a USB thumb drive. Submit a table of contents for each USB thumb drive. Each thumb drive will contain a customer interactive report that generates a color-coded map where the user can verify passing and failing sections of roadway. The color-coded map should match the color-coded graphs generated by the data in the computer. The graphs should have a color-coded portion or shaded area representing failing and passing. The map should be standard Google earth maps or equal. Reports need to be in numerical order by reference number, concurrent with direction, labeled and separated by color, and include the posting date. The format will require prior acceptance by the Engineer.

ITEM 677 – Eliminating Existing Pavement Markings and Markers:

Furnish a high-pressure water blasting system for removing paint, thermoplastic, epoxy, and preformed tape materials from the following surfaces without causing any grooves or trenching of that surface, including asphalt, concrete, friction coarse asphalt, grooved asphalt, and grooved concrete.

Use a high-pressure water blasting system that consist of a vacuum recovery system that must provide for a nearly dry surface eliminating the possibility of uncontained run-off blasting water and debris.

All components required for the complete operation of the water blasting system – Ultra High Pressure (UHP) pump, vacuum system, clean water supply, vacuum recovery storage, blasting components will be mounted and transported on a single, fully self-contained and supporting truck chassis, thereby eliminating the need for any additional water, vacuum, or other transport vehicles.

ITEM 3077 - Superpave Mixtures:

Use field sand with a sand equivalent value of at least 35 when sampled and tested in accordance with Tex-203-F.

The plant is the designated aggregate sampling location, unless otherwise approved by the Engineer.

Construct longitudinal joints in the surface course as shown in the plans. Construct longitudinal joints in all other courses by tapering the bituminous mat as shown in the plans or providing a 6-inch minimum offset from lift to lift. Extend the tapered portion of the mat beyond the normal lane width. Construct the tapered portion of the mat using an approved strike-off device that will provide a uniform slope and will not restrict the main screed. Apply tack coat to the in-place taper before the adjacent mat is placed. Final density requirements for the entire pavement, including the taper area will not change. Compaction of the initial taper section will be required to be as near to final density as possible. Use a small static roller (approximately 200 lbs.) located immediately behind the paver for pre-compaction of the notched wedge joint.

Tack between all layers of ACP lifts (rate-approximately 0.1gal/sy)

The Engineer will determine the correction when the total thickness of the ACP at any location, is deficient by more than 1/4". Correct by adjusting the profile grade or removing and replacing the pavement structure to the correct grade, lines and thickness as shown on the plans. Correction

of defective work will be in accordance with Section 5.3.2, "Correction of Defective or Unauthorized Work".

Furnish clean 5-gallon plastic buckets with lids and wire handles for sampling, transporting, and shipping aggregate and base to the District Lab.

For hot-mix items, in place of typical tack material shown in Table 18 under Item 300, use a tracking resistant asphalt interlayer (TRAIL) material as a tack coat. Approved TRAIL products are found on TxDOT's Material Producer List under Asphalt Interlayer (Tracking Resistant) through <http://www.txdot.gov/business/resources/materials.html>.

There should be little to no evidence of tracking or pickup of the tack coat on the wheels of the equipment as determined by the Engineer. Use approved release agents or misters on equipment tires as necessary.

Construct longitudinal joints so that the hot side overlaps the cold side by 0.5 inch minimum at the joint.

ITEM 3080– Stone-Matrix Asphalt:

Furnish clean 5-gallon plastic buckets with lids and wire handles for sampling, transporting, and shipping aggregate and base to the District Lab.

The Plant is the designated aggregate sampling location, unless otherwise approved by the Engineer.

Construct longitudinal joints in the surface course as shown in the plans. Construct longitudinal joints in all other courses by tapering the bituminous mat as shown in the plans or providing a 6 in. minimum offset from lift to lift. Extend the tapered portion of the mat beyond the normal lane width. Construct the tapered portion of the mat using an approved strike-off device that will provide a uniform slope and will not restrict the main screed. Apply tack coat to the in-place taper before the adjacent mat is placed. Final density requirements for the entire pavement, including the taper area will not change. Compaction of the initial taper section will be required to be as near to final density as possible. Use a small static roller (approximately 200 lbs) located immediately behind the paver for pre-compaction of the notched wedge joint.

For hot-mix items, in place of typical tack material shown in Table 18 under Item 300, use a tracking resistant asphalt interlayer (TRAIL) material as a tack coat. Approved TRAIL products are found on TxDOT's Material Producer List under Asphalt Interlayer (Tracking Resistant) through <http://www.txdot.gov/business/resources/materials.html>.

There should be little to no evidence of tracking or pickup of the tack coat on the wheels of the equipment as determined by the Engineer. Use approved release agents or misters on equipment tires as necessary.

Construct longitudinal joints so that the hot side overlaps the cold side by 0.5 inch minimum at the joint.

ITEM 6001 – Portable Changeable Message Sign:

Portable Changeable Message signs will be used on this contract. The Portable Changeable Message Signs will be used in advance of signal work where changing conditions may warrant the use of message boards. They may also be required at other locations as directed by the Engineer. The Engineer will provide the Contractor with the location and the messages to be displayed for each specific event. The Engineer or his representative will inspect each location once the Contractor has placed the message boards to verify that the placement and message is correct. The Contractor will change the message board location and modify the message being displayed as directed before leaving the location to the satisfaction of the Engineer or his representative. The Portable Changeable Message Signs will be paid for by the day after installed and fully operational. All locations that the Contractor will be called upon to use the Portable Changeable Message Signs will be for a minimum of 10 days. The Engineer will notify the Contractor when the Portable Changeable Message Signs are needed, and the Contractor will have the Portable Changeable Message Signs on location and fully operational in 5 working days. In cases of emergency the Contractor will have the Portable Changeable Message Signs on location and fully operational in 3 working days. Refer to traffic control plan sheets for typical temporary portable changeable message sign layout.

Item 6056 – Preformed In-Lane (Transversers)/Centerline Rumble Strips:

Supply all equipment and materials necessary for placement of In-Lane or Transverse Rumble Strips.

Use transverse rumble strips as centerline rumble strips. The rumble strips will be black in color.

Place rumble strips as 12-inch segments centered on 4-foot spacings.

Ensure strict placement for centering and aligning all centerline transverse rumble strips. Placement of material will be strictly enforced. Irregular bars not centered or aligned properly will not be accepted.

Do not place pavement markings until rumble strips are accepted by written acceptance.

Control:0218-04-119
County: CASS
Highway: US 59

Sheet:

Provide a 90-day performance period that begins the day following written acceptance for each separate location. The written acceptance does not constitute final acceptance.

Replacement of all In-Lane or Transverse Rumble Strips within in a separate location will be required when 30% loss of an individual rumble strips exists on 20% of the length of a location or when 500 mil thickness is not maintained. Visual evaluation will be used for these determinations. Upon request, the Engineer will allow a Contractor representative to accompany the Engineer on these evaluations.

Replace all In-Lane or Transverse Rumble Strips identified during the performance period within 30 days after notification. The end of the performance period does not relieve the Contractor from the performance deficiencies requiring corrective action identified during the performance period.

No additional payment will be made for replacement of In-Lane or Transverse Rumble Strips failing to meet the performance requirements.

ITEM 6149 – All-Weather Thermoplastic Pavement Markings:

A mobile unit will be required to take reflectivity readings, readings will be taken on all lines in both directions. The mobile reflectivity readings will not be paid for separately but will be subsidiary to this bid item. Strict compliance with report output will be exercised in accordance to this general note. Information for each road must be together in the same file and submitted on a USB thumb drive. Submit a table of contents for each USB thumb drive. Each thumb drive will contain a customer interactive report that generates a color-coded map where the user can verify passing and failing sections of roadway. The color-coded map should match the color-coded graphs generated by the data in the computer. The graphs should have a color-coded portion or shaded area representing failing and passing. The map should be standard Google earth maps or equal. Reports need to be in numerical order by reference number, concurrent with direction, labeled and separated by color, and include the posting date. The format will require prior acceptance by the Engineer.

Use a mobile retroreflectometer that is prequalified at the Texas A&M Transportation Institute test facility. The prequalification is at the contractor's expense.

The required values of wet and dry readings will be strictly measured within this contract as per manufacturer's recommendations.

Install a seal coat RPM cover or any other method approved on any line having Raised Pavement Markers. Remove and dispose of the covers after the stripe is complete.

Control:0218-04-119
County: CASS
Highway: US 59

Sheet: 4F

Placement of markings in proper alignment will be strictly enforced. Irregular lines placed on both sides of the existing markings or pilot line will not be accepted.

ITEM 6185–Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA):

The shadow vehicle with truck mounted attenuator (TMA) will not be optional but will be required as shown on the appropriate traffic control plan sheets.

A total of one (1) shadow vehicle with TMA will be required for work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.

A total of two (2) shadow vehicles with TMA will be required for Pavement Marking Operations.

**SPECIFICATION DATA
TEST TO BE IN ACCORDANCE WITH DEPARTMENT OF
TRANSPORTATION TEST METHODS**

| ITEM | DESCRIPTION | GRADING REQUIREMENTS | | | | SOIL CONSTANTS | | |
|------|---------------------|---------------------------|--------|-------|--------|----------------|------|------|
| | | PERCENT RETAINED - SIEVES | | | | L.L. | P.I. | MIN. |
| | | 2-1/2" | 1-3/4" | No. 4 | No. 40 | | | |
| 132 | Embankment (Type C) | 50 | 25 | 4 | | | | |



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0218-04-119

DISTRICT Atlanta
HIGHWAY US 59

COUNTY Cass

| CONTROL SECTION JOB | | | | 0218-04-119 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|--|------|-------------|-------|-------------|-------------|
| PROJECT ID | | | | A00065008 | | | |
| COUNTY | | | | Cass | | | |
| HIGHWAY | | | | US 59 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 132-6021 | EMBANKMENT (VEHICLE)(ORD COMP)(TY C) | CY | 50.000 | | 50.000 | |
| | 134-6002 | BACKFILL (TY B) | STA | 119.000 | | 119.000 | |
| | 164-6054 | BOND FBR MTRX SEED (PERM)(RURAL)(SAND) | SY | 7,934.000 | | 7,934.000 | |
| | 164-6055 | BONDED FBR MTRX SEED (TEMP)(WARM) | SY | 1,984.000 | | 1,984.000 | |
| | 164-6056 | BONDED FBR MTRX SEED (TEMP)(COOL) | SY | 1,984.000 | | 1,984.000 | |
| | 168-6001 | VEGETATIVE WATERING | MG | 192.000 | | 192.000 | |
| | 351-6013 | FLEXIBLE PAVEMENT STRUCTURE REPAIR(4") | SY | 2,934.000 | | 2,934.000 | |
| | 354-6088 | PLANE ASPH CONC PAV (0" TO 5") | SY | 111,728.000 | | 111,728.000 | |
| | 354-6100 | PLANE ASPH CONC PAV (5") | SY | 113,050.000 | | 113,050.000 | |
| | 401-6001 | FLOWABLE BACKFILL | CY | 24.000 | | 24.000 | |
| | 432-6045 | RIPRAP (MOW STRIP)(4 IN) | CY | 28.000 | | 28.000 | |
| | 451-6024 | RETROFIT RAIL (TY SSTR) | LF | 520.000 | | 520.000 | |
| | 500-6001 | MOBILIZATION | LS | 1.000 | | 1.000 | |
| | 502-6001 | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO | 9.000 | | 9.000 | |
| | 506-6038 | TEMP SEDMT CONT FENCE (INSTALL) | LF | 400.000 | | 400.000 | |
| | 506-6039 | TEMP SEDMT CONT FENCE (REMOVE) | LF | 400.000 | | 400.000 | |
| | 512-6001 | PORT CTB (FUR & INST)(SGL SLOPE)(TY 1) | LF | 510.000 | | 510.000 | |
| | 512-6025 | PORT CTB (MOVE)(SGL SLP)(TY 1) | LF | 510.000 | | 510.000 | |
| | 512-6049 | PORT CTB (REMOVE)(SGL SLP)(TY 1) | LF | 510.000 | | 510.000 | |
| | 533-6001 | RUMBLE STRIPS (SHOULDER) | LF | 23,800.000 | | 23,800.000 | |
| | 540-6001 | MTL W-BEAM GD FEN (TIM POST) | LF | 300.000 | | 300.000 | |
| | 540-6006 | MTL BEAM GD FEN TRANS (THRIE-BEAM) | EA | 2.000 | | 2.000 | |
| | 542-6001 | REMOVE METAL BEAM GUARD FENCE | LF | 750.000 | | 750.000 | |
| | 542-6004 | RM MTL BM GD FENCE TRANS (THRIE-BEAM) | EA | 2.000 | | 2.000 | |
| | 544-6001 | GUARDRAIL END TREATMENT (INSTALL) | EA | 2.000 | | 2.000 | |
| | 544-6003 | GUARDRAIL END TREATMENT (REMOVE) | EA | 2.000 | | 2.000 | |
| | 545-6003 | CRASH CUSH ATTEN (MOVE & RESET) | EA | 1.000 | | 1.000 | |
| | 545-6005 | CRASH CUSH ATTEN (REMOVE) | EA | 1.000 | | 1.000 | |
| | 545-6019 | CRASH CUSH ATTEN (INSTL)(S)(N)(TL3) | EA | 1.000 | | 1.000 | |
| | 658-6014 | INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI) | EA | 6.000 | | 6.000 | |
| | 658-6062 | INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI) | EA | 6.000 | | 6.000 | |
| | 662-6005 | WK ZN PAV MRK NON-REMOV (W)6"(BRK) | LF | 6,092.000 | | 6,092.000 | |
| | 662-6008 | WK ZN PAV MRK NON-REMOV (W)6"(SLD) | LF | 52,100.000 | | 52,100.000 | |
| | 662-6035 | WK ZN PAV MRK NON-REMOV (Y)6"(BRK) | LF | 11,866.000 | | 11,866.000 | |
| | 662-6037 | WK ZN PAV MRK NON-REMOV (Y)6"(SLD) | LF | 49,980.000 | | 49,980.000 | |
| | 662-6060 | WK ZN PAV MRK REMOV (W)4"(BRK) | LF | 7,270.000 | | 7,270.000 | |
| | 662-6093 | WK ZN PAV MRK REMOV (Y)4"(BRK) | LF | 19,374.000 | | 19,374.000 | |



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0218-04-119

DISTRICT Atlanta
HIGHWAY US 59

COUNTY Cass

| CONTROL SECTION JOB | | | | 0218-04-119 | | TOTAL EST. | TOTAL FINAL |
|---------------------|-----------|--|------|-------------|-------|-------------|-------------|
| PROJECT ID | | | | A00065008 | | | |
| COUNTY | | | | Cass | | | |
| HIGHWAY | | | | US 59 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 662-6109 | WK ZN PAV MRK SHT TERM (TAB)TY W | EA | 462,837.000 | | 462,837.000 | |
| | 662-6110 | WK ZN PAV MRK SHT TERM (TAB)TY Y | EA | 617,115.000 | | 617,115.000 | |
| | 662-6112 | WK ZN PAV MRK SHT TERM RMV (W)(4") | LF | 16,444.000 | | 16,444.000 | |
| | 662-6113 | WK ZN PAV MRK SHT TERM RMV (Y)(4") | LF | 37,758.000 | | 37,758.000 | |
| | 666-6036 | REFL PAV MRK TY I (W)8"(SLD)(100MIL) | LF | 75.000 | | 75.000 | |
| | 666-6227 | PAVEMENT SEALER 10" | LF | 140.000 | | 140.000 | |
| | 668-6010 | PREFAB PAV MRK TY B (W)(6")(BRK)CNTST | LF | 140.000 | | 140.000 | |
| | 668-6076 | PREFAB PAV MRK TY C (W) (24") (SLD) | LF | 160.000 | | 160.000 | |
| | 668-6077 | PREFAB PAV MRK TY C (W) (ARROW) | EA | 16.000 | | 16.000 | |
| | 672-6007 | REFL PAV MRKR TY I-C | EA | 305.000 | | 305.000 | |
| | 672-6009 | REFL PAV MRKR TY II-A-A | EA | 610.000 | | 610.000 | |
| | 677-6002 | ELIM EXT PAV MRK & MRKS (6") | LF | 4,780.000 | | 4,780.000 | |
| | 677-6004 | ELIM EXT PAV MRK & MRKS (10") | LF | 140.000 | | 140.000 | |
| | 3077-6033 | SP MIXESSP-CSAC-A PG76-22 | TON | 31,193.000 | | 31,193.000 | |
| | 3077-6075 | TACK COAT | GAL | 22,610.000 | | 22,610.000 | |
| | 3080-6007 | STONE-MTRX-ASPH SMA-D SAC-A PG76-22 | TON | 12,218.000 | | 12,218.000 | |
| | 3080-6029 | TACK COAT | GAL | 11,106.000 | | 11,106.000 | |
| | 6001-6002 | PORTABLE CHANGEABLE MESSAGE SIGN | EA | 2.000 | | 2.000 | |
| | 6056-6001 | PREFORMED IN-LANE(TRANS) RUMBLE STRIP | LF | 11,525.000 | | 11,525.000 | |
| | 6149-6016 | REFL PAV MRK AWT (W) (6")(SLD)(125 MIL) | LF | 24,360.000 | | 24,360.000 | |
| | 6149-6017 | REFL PAV MRK AWT (W) (6")(BRK)(125 MIL) | LF | 7,161.000 | | 7,161.000 | |
| | 6149-6022 | REFL PAV MRK AWT (Y) (6")(SLD)(125 MIL) | LF | 24,990.000 | | 24,990.000 | |
| | 6149-6023 | REFL PAV MRK AWT (Y) (6")(BRK)(125 MIL) | LF | 6,091.000 | | 6,091.000 | |
| | 6185-6002 | TMA (STATIONARY) | DAY | 130.000 | | 130.000 | |
| | 6185-6005 | TMA (MOBILE OPERATION) | DAY | 6.000 | | 6.000 | |
| | 08 | CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING) | LS | 1.000 | | 1.000 | |
| | | CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING) | LS | 1.000 | | 1.000 | |

ROADWAY SUMMARY

| WORK LIMITS | STATION AND LOCATION | RT / LT | SURFACE AREA | 5 | 354 | 354 | 2 | 351 | 5 | 3077 | 3077 | 3080 | 3080 | 533 | 4 | 6056 | 6 | 134 | 164 | 164 | 164 | 168 | 1 | 166 | | | |
|-------------|----------------------|---------|--------------|--------------------------|--------------------------------|---|-----------------------------|-----------|--------------------------------------|-----------|-------------------------|---------------------------------------|-----------------|--|-----------------------------------|-----------------------------------|-------------------------------------|------------|-----|-----|-----|-----|---|-----|--|--|--|
| | | | | 6100 | 6088 | 6013 | 6033 | 6075 | 6007 | 6029 | 6001 | 6001 | 6002 | 6054 | 6055 | 6056 | 6001 | | | | | | | | | | |
| | | | | PLANE ASPH CONC PAV (5") | PLANE ASPH CONC PAV (0" TO 5") | FLEXIBLE PAVEMENT STRUCTURE REPAIR (4") | SP MIXES SP-C SAC-A PG76-22 | TACK COAT | STONE-MTRX- ASPH SMA-D SAC-A PG76-22 | TACK COAT | RUMBLE STRIP (SHOULDER) | PREFORMED IN-LANE(TRANS) RUMBLE STRIP | BACKFILL (TY B) | BOND FBR MTRX SEED (PERM)(RURAL)(SAND) | BONDED FBR MTRX SEED (TEMP)(WARM) | BONDED FBR MTRX SEED (TEMP)(COOL) | VEGETATIVE WATERING (80 MG/5000 SY) | FERTILIZER | | | | | | | | | |
| | SY | SY | SY | SY | TON | GAL | TON | GAL | LF | LF | STA | SY | SY | SY | MG | MG | | | | | | | | | | | |
| | 100+00.00 | - | 112+00.00 | LT | 5,600 | 5,700 | 5,633 | - | 1,554 | 1,140 | 616 | 560 | 1,200 | 600 | 6.00 | 400 | 100 | 100 | 100 | 10 | 36 | | | | | | |
| | 112+00.00 | - | 164+40.00 | LT | 24,453 | 24,890 | 24,599 | - | 6,785 | 4,978 | 2,690 | 2,445 | 5,240 | 2,620 | 26.20 | 1,747 | 437 | 437 | 437 | 42 | 157 | | | | | | |
| | 164+40.00 | - | 167+20.00 | LT | - | - | - | - | - | - | - | - | - | 70 | - | - | - | - | - | - | - | | | | | | |
| | 167+20.00 | - | 221+80.00 | LT | 25,480 | 25,935 | 25,632 | 1,467 | 7,111 | 5,187 | 2,803 | 2,548 | 5,460 | 2,730 | 27.30 | 1,820 | 455 | 455 | 455 | 44 | 164 | | | | | | |
| | 100+00.00 | - | 112+00.00 | RT | 5,600 | 5,700 | 5,633 | - | 1,554 | 1,140 | 616 | 560 | 1,200 | 600 | 6.00 | 400 | 100 | 100 | 100 | 10 | 36 | | | | | | |
| | 112+00.00 | - | 164+40.00 | RT | 24,453 | 24,890 | 24,599 | - | 6,785 | 4,978 | 2,690 | 2,445 | 5,240 | 1,310 | 26.20 | 1,747 | 437 | 437 | 437 | 42 | 157 | | | | | | |
| | 164+40.00 | - | 167+20.00 | RT | - | - | - | - | - | - | - | - | - | 70 | - | - | - | - | - | - | - | | | | | | |
| | 167+20.00 | - | 221+80.00 | RT | 25,480 | 25,935 | 25,632 | 1,467 | 7,070 | 5,187 | 2,803 | 2,548 | 5,460 | 2,730 | 27.30 | 1,820 | 455 | 455 | 455 | 44 | 164 | | | | | | |
| | 5 6" JOINT OFFSET | | | | 2,030 | - | - | - | 279 | - | - | - | - | - | - | - | - | - | - | - | - | | | | | | |
| | DRIVEWAYS | | | | 994 | - | - | - | 55 | - | - | - | - | - | - | - | - | - | - | - | - | | | | | | |
| | TOTAL: | | | | 113,050 | 111,728 | 2,934 | 31,193 | 22,610 | 12,218 | 11,106 | 23,800 | 11,525 | 119 | 7,934 | 1,984 | 1,984 | 1,984 | 192 | 714 | | | | | | | |

- 1 FOR CONTRACTORS INFORMATION
- 2 FLEXIBLE PAVEMENT STRUCTURE REPAIR FROM STA.299+75 TO STA.302+50 BOTH TRAVEL LANES 24 FT WIDTH NORTH AND SOUTH BOUND. EXACT NUMBER OF PAVEMENT REPAIRS AND LIMITS OF EACH PAVEMENT REPAIR WILL BE DETERMINED BY THE ENGINEER. (SEE ROADWAY DETAILS)
- 3 FOR DRIVEWAYS DETAILS (SEE ROADWAY DETAILS)
- 4 4 FT SPACING FOR PREFORMED CENTERLINE RUMBLE STRIP.
- 5 QUANTITIES INCLUDE 1.5 FT TOTAL WIDTH FOR ALL THREE 6 INCH TCP PHASED JOINT OFFSETS WIDE JOINT OFFSET.
- 6 BACKFILL TY B MATERIAL WILL BE PROVIDED BY TXDOT THE STOCKPILE IS LOCATED AT FM 2328 S

TCP EQUIPMENT SUMMARY

| WORK LIMITS | 6001 | 6185 | 6185 |
|----------------------|----------------------------------|------------------|------------------------|
| | 6002 | 6002 | 6005 |
| | PORTABLE CHANGEABLE MESSAGE SIGN | TMA (STATIONARY) | TMA (MOBILE OPERATION) |
| STATION AND LOCATION | EA | DAY | DAY |
| VARIOUS | 2 | 130 | 6 |
| TOTAL: | 2 | 130 | 6 |

THE USE OF PORTABLE CHANGEABLE MESSAGE SIGNS AND TMAS SHALL BE DIRECTED BY THE ENGINEER. PCMS AND TMA (STATIONARY) SHALL BE USED DURING THE PLANING, OVERLAY AND BRIDGE RAIL REPLACEMENT PHASES. TMA (MOBILE OPERATION) SHALL BE USED DURING MOBILE OPERATIONS.

FILE: C:\Users\thoma1\Desktop\US 59 0218-04-119_Safety_Review\Plans\0218-04-119_quantities_100_PERCENTS_4_8_2022.xlsm\ROADWAY
DATE: 4/29/2022 1:56:49 PM #####

MISCELLANEOUS SUMMARIES



| | | | |
|--------------|--------|---------|-------|
| SHEET 1 OF 3 | | | |
| CONT | SECT | JOB | SHEET |
| 0218 | 04 | 119 | |
| DISTRICT | COUNTY | HIGHWAY | 6 |
| ATL | BOWIE | US 59 | |

| PAVEMENT MARKING SUMMARY | | | | | | | | | | | | | |
|---------------------------|-------------------------------|----------------------------|--|--|--|--|---|--|---|---|------------------------|------------------------------------|-------------------------------------|
| WORK LIMITS | 672 | 672 | 6149 | 6149 | 6149 | 6149 | 666 | 668 | 668 | 668 | 666 | 677 | 677 |
| | 6009 | 6007 | 6022 | 6023 | 6017 | 6016 | 6036 | 6077 | 6076 | 6010 | 6227 | 6002 | 6004 |
| | REFL PAV MRKR TY II-A-A | REFL PAV MRKR TY I-C | REFL PAV MRK AWT (Y) (6") (SLD) (125 MIL) | REFL PAV MRK AWT (Y) (6") (BRK) (125 MIL) | REFL PAV MRK AWT (W) (6") (BRK) (125 MIL) | REFL PAV MRK AWT (W) (6") (SLD) (125 MIL) | REFL PAV MRK TY I (W) 8" (SLD) (100MIL) | PREFAB PAV MRK TY C (W) (ARROW) | PREFAB PAV MRK TY C (W) (24") (SLD) | PREFAB PAV MRK TY B (W) (6") (BRK) CNTST | PAVEMENT SEALER 10" | ELIM EXT PAV MRK & MRKS (6") | ELIM EXT PAV MRK & MRKS (10") |
| STATION TO STATION | EA | EA | LF | LF | LF | LF | LF | EA | LF | LF | LF | LF | LF |
| 100+00.00 - 115+75.00 | 79 | 39 | 3,780 | 788 | 788 | 3,150 | - | 4 | - | - | - | - | - |
| 115+75.00 - 118+90.00 | 16 | 8 | 630 | 158 | 158 | 630 | 75 | - | - | - | - | - | - |
| 118+90.00 - 164+40.00 | 228 | 114 | 9,100 | 2,275 | 2,275 | 9,100 | - | 6 | - | - | - | - | - |
| 164+40.00 - 167+20.00 | 14 | 7 | 560 | 140 | 1,210 | 560 | - | - | - | 140 | 140 | 1,400 | 140 |
| 167+20.00 - 221+80.00 | 273 | 137 | 10,920 | 2,730 | 2,730 | 10,920 | - | 6 | - | - | - | - | - |
| COUNTY ROAD / FARM MARKET | - | - | - | - | - | - | - | - | 160 | - | - | - | - |
| TOTAL: | 610 | 305 | 24,990 | 6,091 | 7,161 | 24,360 | 75 | 16 | 160 | 140 | 140 | 1,400 | 140 |

| WORK ZONE MARKING SUMMARY | | | | | | | | | | | | | |
|---------------------------------|--|--|--|--|--|--|---|--|---|--|---------------------------------|-------|------------------------------------|
| WORK LIMITS | 662 | 662 | 662 | 662 | 662 | 662 | 662 | 662 | 662 | 662 | 662 | 677 | |
| | 6005 | 6008 | 6035 | 6037 | 6060 | 6093 | 6109 | 6110 | 6112 | 6113 | 6002 | | COMMITTS |
| | WK ZN PAV MRK NON- REMOV (W) 6" (BRK) | WK ZN PAV MRK NON- REMOV (W) 6" (SLD) | WK ZN PAV MRK NON- REMOV (Y) 6" (BRK) | WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) | WK ZN PAV MRK REMOV (W) 4" (BRK) | WK ZN PAV MRK REMOV (Y) 4" (BRK) | WK ZN PAV MRK SHT TERM (TAB) TY W | WK ZN PAV MRK SHT TERM (TAB) TY Y | WK ZN PAV MRK SHT TERM RMV (W) 4" | WK ZN PAV MRK SHT TERM RMV (Y) 4" | ELIM EXT PAV MRK & MRKS (6") | | |
| STATION TO STATION | LF | LF | LF | LF | LF | LF | EA | EA | LF | LF | LF | | |
| BRIDGE RAIL REPLACEMENT PHASE 1 | | | | | | | | | | | | | SHOULDER AND OUTSIDE LANE |
| 142+60.00 - 159+50.00 | - | 1,690 | - | - | - | - | - | - | - | - | - | 1,690 | LT SOUTH BOUND |
| 172+10.00 - 189+00.00 | - | 1,690 | - | - | - | - | - | - | - | - | - | 1,690 | RT NORTH BOUND |
| INITIAL PLANNING PHASE 2, 2A | | | | | | | | | | | | | PLANNING NB AND SB |
| 100+00.00 - 115+75.00 | 394 | 3,150 | 788 | 3,150 | - | - | 67,950 | 90,600 | 709 | 2,126 | - | - | |
| 115+75.00 - 118+90.00 | 79 | 630 | - | 1,260 | - | - | 69,604 | 92,805 | 142 | 425 | - | - | |
| 118+90.00 - 164+40.00 | 1,138 | 9,100 | 2,275 | 9,100 | - | - | 96,857 | 129,142 | 2,048 | 6,143 | - | - | |
| 164+40.00 - 167+20.00 | 70 | 560 | 140 | 560 | - | - | 97,854 | 130,472 | 126 | 378 | - | - | |
| 167+20.00 - 221+80.00 | 1,365 | 10,920 | 2,730 | 10,920 | - | - | 130,572 | 174,096 | 2,457 | 7,371 | - | - | |
| PHASE 3 | | | | | | | | | | | | | INSIDE LANE AND HALF OF THE MEDIAN |
| 100+00.00 - 115+75.00 | - | - | - | - | 197 | - | - | - | 177 | 315 | - | - | |
| 115+75.00 - 118+90.00 | - | - | - | - | 39 | - | - | - | 35 | 63 | - | - | |
| 118+90.00 - 164+40.00 | - | - | - | - | 1,138 | - | - | - | 512 | 910 | - | - | |
| 164+40.00 - 167+20.00 | - | - | - | - | 35 | - | - | - | 32 | 56 | - | - | |
| 167+20.00 - 221+80.00 | - | - | - | - | 683 | - | - | - | 614 | 1,092 | - | - | |
| PHASE 3A | | | | | | | | | | | | | OUTSIDE LANE AND SHOULDER |
| 100+00.00 - 115+75.00 | - | - | - | - | - | 591 | - | - | 177 | - | - | - | |
| 115+75.00 - 118+90.00 | - | - | - | - | - | 315 | - | - | 35 | - | - | - | |
| 118+90.00 - 164+40.00 | - | - | - | - | - | 1,706 | - | - | 512 | - | - | - | |
| 164+40.00 - 167+20.00 | - | - | - | - | - | 105 | - | - | 32 | - | - | - | |
| 167+20.00 - 221+80.00 | - | - | - | - | - | 2,048 | - | - | 614 | - | - | - | |
| PHASE 4 | | | | | | | | | | | | | INSIDE LANE AND HALF OF THE MEDIAN |
| 100+00.00 - 115+75.00 | - | - | - | - | 197 | - | - | - | 177 | 315 | - | - | |
| 115+75.00 - 118+90.00 | - | - | - | - | 79 | - | - | - | 35 | 63 | - | - | |
| 118+90.00 - 164+40.00 | - | - | - | - | 1,138 | - | - | - | 512 | 910 | - | - | |
| 164+40.00 - 167+20.00 | - | - | - | - | 35 | - | - | - | 32 | 56 | - | - | |
| 167+20.00 - 221+80.00 | - | - | - | - | 683 | - | - | - | 614 | 1,092 | - | - | |
| PHASE 4 A | | | | | | | | | | | | | OUTSIDE LANE AND SHOULDER |
| 100+00.00 - 115+75.00 | - | - | - | - | - | 591 | - | - | 177 | - | - | - | |
| 115+75.00 - 118+90.00 | - | - | - | - | - | 315 | - | - | 35 | - | - | - | |
| 118+90.00 - 164+40.00 | - | - | - | - | - | 1,706 | - | - | 512 | - | - | - | |
| 164+40.00 - 167+20.00 | - | - | - | - | - | 105 | - | - | 32 | - | - | - | |
| 167+20.00 - 221+80.00 | - | - | - | - | - | 2,048 | - | - | 614 | - | - | - | |
| FINAL PHASE | | | | | | | | | | | | | 2" ACP OVERLAY OF SMA |
| 100+00.00 - 115+75.00 | 394 | 3,150 | 788 | 3,150 | 394 | 1,181 | - | - | 709 | 2,126 | - | - | |
| 115+75.00 - 118+90.00 | 79 | 630 | - | 1,260 | 79 | 945 | - | - | 142 | 425 | - | - | |
| 118+90.00 - 164+40.00 | 1,138 | 9,100 | 2,275 | 9,100 | 1,138 | 3,413 | - | - | 2,048 | 6,143 | - | - | |
| 164+40.00 - 167+20.00 | 70 | 560 | 140 | 560 | 70 | 210 | - | - | 126 | 378 | - | - | |
| 167+20.00 - 221+80.00 | 1,365 | 10,920 | 2,730 | 10,920 | 1,365 | 4,095 | - | - | 2,457 | 7,371 | - | - | |
| TOTAL: | 6,092 | 52,100 | 11,866 | 49,980 | 7,270 | 19,374 | 462,837 | 617,115 | 16,444 | 37,758 | 3,380 | | |

MISCELLANEOUS SUMMARIES



SHEET 2 OF 3

| | | | |
|----------|------|--------|---------|
| CONT | SECT | JOB | HIGHWAY |
| 0218 | 04 | 119 | US 59 |
| DISTRICT | | COUNTY | SHEET |
| ATL | | BOWIE | 7 |


| MBGF, BRIDGE RAIL, AND DELINEATORS SUMMARY | | | | | | | | | | | | | | |
|--|-----------|--------------------------------------|---|-------------------|---------------------------|-------------------------|------------------------------|------------------------------------|-------------------------------|---------------------------------------|-----------------------------------|----------------------------------|---------------------------------------|---|
| WORK LIMITS | NBL / SBL | 132 | 6 | 401 | 432 | 451 | 540 | 540 | 542 | 544 | 544 | 658 | 658 | |
| | | 6021 | | 6001 | 6045 | 6024 | 6001 | 6006 | 6001 | 6004 | 6001 | 6003 | 6014 | 6062 |
| STATION AND LOCATION | | EMBANKMENT (VEHICLE)(ORD COMP)(TY C) | | FLOWABLE BACKFILL | RIPRAP (MOW STRIP) (4 IN) | RETROFIT RAIL (TY SSTR) | MTL W-BEAM GD FEN (TIM POST) | MTL BEAM GD FEN TRANS (THRIE-BEAM) | REMOVE METAL BEAM GUARD FENCE | RM MTL BM GD FENCE TRANS (THRIE-BEAM) | GUARDRAIL END TREATMENT (INSTALL) | GUARDRAIL END TREATMENT (REMOVE) | INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI) | INSTL DEL ASSM (D-SW)SZ 1 (BRF)GF2 (BI) |
| | | CY | | CY | CY | LF | LF | EA | LF | EA | EA | EA | EA | EA |
| 159+50.00 - 164+60.00 | SBL | 25 | | 12 | 14 | 260 | 150 | 1 | 375 | 1 | 1 | 1 | 3 | 3 |
| 172+10.00 - 167+00.00 | NBL | 25 | | 12 | 14 | 260 | 150 | 1 | 375 | 1 | 1 | 1 | 3 | 3 |
| TOTAL: | | 50 | | 24 | 28 | 520 | 300 | 2 | 750 | 2 | 2 | 2 | 6 | 6 |

6 24 CY OF FLOWABLE BACKFILL TO BE USED AT JOHN'S CREEK APPROACHES FOR EROSION AS DIRECTED BY THE ENGINEER.


| TRAFFIC BARRIER, EROSION CONTROL SUMMARY | | | | | | | | | |
|--|-----------|--|--------------------------------|----------------------------------|-------------------------------------|---------------------------------|---------------------------|---------------------------------|--------------------------------|
| WORK LIMITS | NBL / SBL | 512 | 512 | 512 | 545 | 545 | 545 | 506 | 506 |
| | | 6001 | 6025 | 6049 | 6019 | 6003 | 6005 | 6038 | 6039 |
| STATION AND LOCATION | | PORT CTB (FUR & INST)(SGL SLOPE)(TY 1) | PORT CTB (MOVE)(SGL SLP)(TY 1) | PORT CTB (REMOVE)(SGL SLP)(TY 1) | CRASH CUSH ATTEN (INSTL)(S)(N)(TL3) | CRASH CUSH ATTEN (MOVE & RESET) | CRASH CUSH ATTEN (REMOVE) | TEMP SEDMT CONT FENCE (INSTALL) | TEMP SEDMT CONT FENCE (REMOVE) |
| | | LF | LF | LF | EA | EA | EA | LF | LF |
| 159+50.00 - 164+60.00 | SBL | 510 | 510 | - | 1 | 1 | - | 200 | 200 |
| 172+10.00 - 167+00.00 | NBL | - | - | 510 | - | - | 1 | 200 | 200 |
| TOTAL: | | 510 | 510 | 510 | 1 | 1 | 1 | 400 | 400 |

MISCELLANEOUS SUMMARIES


FILE: \\f\tdot\project\wiseon1\ine.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\0218-04-119*SEQUENCE*OF*WORK* DATE: 4/28/2022 7:29:55 PM




**PHASE 2 AND 2A
STA. 200+00 TO 321+80**




**PHASE 3
STA. 200+00 TO 321+80**



**PHASE 3A
STA. 200+00 TO 321+80**



**PHASE 4
STA. 200+00 TO 321+80**



**PHASE 4A
STA. 200+00 TO 321+80**

TRAFFIC CONTROL PLAN NARRATIVE

GENERAL

WORK ZONE CHANNELIZATION DEVICES SHALL BE PER THE TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

INITIAL TRAFFIC CONTROL

INSTALL PROJECT LIMIT TRAFFIC CONTROL DEVICES PER THE BC STANDARDS. UTILIZE THE APPLICABLE TCP'S PROVIDED IN THIS PLAN SET AS PER THE TYPE OF WORK TO BE DONE. ENSURE THAT AT LEAST ONE TRAVEL LANE IS OPEN IN THE SOUTHBOUND AND NORTHBOUND LANES AT ALL TIMES. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ACCESS TO ALL FARM MARKET ROADS, COUNTY ROADS AND DRIVEWAYS.

ROADWAY PHASING

REFER TO THE TRAFFIC CONTROL PLAN TCP STANDARDS: (ATL-16)-15, FOR CONSTRUCTION GUIDANCE. SEE TYPICAL SECTIONS FOR CONSTRUCTION WORK AREA AND TRAFFIC FLOW.

WORK LIMITS ON ROADWAY TO BE CONTROLLED BY APPLICABLE TCP STANDARDS FOR EACH PHASE OR AS DIRECTED BY THE ENGINEER.

PHASE 1: REPLACE BRIDGE RAIL AND METAL BEAM GUARD FENCE NORTH AND SOUTH BOUND. (SEE TRAFFIC CONTROL PLAN FOR BRIDGE RAIL REPLACEMENT)

PHASE 2 AND PHASE 2A: PLANE HALF OF THE ROADWAY WIDTH EACH DAY, 2" BELOW THE PROPOSED PROFILE GRADE LINE. RESTORE ALL FOUR LANES OF TRAFFIC TO ITS ORIGINAL LOCATION AT THE END OF EACH WORKDAY. THE 16' FLUSH MEDIAN SHALL REMAINED CLOSED EACH NIGHT TO PROTECT THE UNEVEN LANES AT THE CENTERLINE OF THE ROADWAY. PLANING OPERATIONS SHALL BE PERFORMED IN A MANNER THAT TRAFFIC WILL NOT CROSS AN UNEVEN LONGITUDINAL JOINT.

PHASE 3: ESTABLISH TRAFFIC CONTROL CONFIGURATION UTILIZING TCP (ATL-16b)-15. MOVE SOUTHBOUND TRAFFIC TO THE OUTSIDE LANE. PER THE TCP TYPICAL SECTIONS. PLANE 5", PERFORM FLEXIBLE PAVEMENT REPAIR AS DIRECTED, PLACE 5" SP-C IN TWO EQUAL LIFTS.

PHASE 3A: MOVE SOUTHBOUND TRAFFIC FROM THE PRIOR PHASE 3 OUTSIDE LANE TO THE SOUTHBOUND INSIDE LANE USING TCP(ATL-16b)-15 CONFIGURATION, AND AS SHOWN IN THE TCP TYPICAL SECTIONS, PLANE 5", PERFORM FLEXIBLE PAVEMENT REPAIR AS DIRECTED, PLACE 5" SP-C IN TWO EQUAL LIFTS.


PHASE 4: PLACE NORTH BOUND AND SOUTHBOUND TRAFFIC TO THE OUTSIDE LANE USING (ATL-16b)-15 AS SHOWN ON THE TCP TYPICAL SECTIONS. PLANE 5", PERFORM FLEXIBLE PAVEMENT REPAIR AS DIRECTED, PLACE 5" SP-C IN TWO EQUAL LIFTS.

PHASE 4A: ESTABLISH TRAFFIC CONTROL CONFIGURATION UTILIZING TCP (ATL-16a)-15. MOVE NORTHBOUND TRAFFIC TO THE INSIDE LANE. PER THE TCP TYPICAL SECTIONS. PLANE 5", PERFORM FLEXIBLE PAVEMENT REPAIR AS DIRECTED, PLACE 5" SP-C IN TWO EQUAL LIFTS.

PHASE 5: PLACE THE FINAL TWO INCHES OF SMA ACCORDING TO TCP (ATL-16b)-15 AND TCP (ATL-16a)-15. DAYTIME OPERATION.


PLACE PAVEMENT MARKINGS ACCORDING TO THE PAVEMENT MARKING SUMMARY SHEETS AND STANDARDS.

CONTRACTOR MAY CHANGE THE ORDER OF PROGRESSION OF PHASE 3, 3A, 4 AND 4A AS APPROVED BY THE ENGINEER.



DURING PHASE 3-4 THE PLANING OPERATIONS THE CONTRACTOR SHALL PLANE THIS AREA OF THE NEWLY PLACED 2.5" LIFT OF ACP SP-C 76-22 TO CREATE A 6" OFFSET BETWEEN THE ACP LAYERS

NOTE: SEE TYPICAL SECTIONS SMA TAPERED LONGITUDINAL JOINT DETAIL FOR SMA OFFSET.



SEQUENCE OF WORK

NOT SCALE









| | | |
|---------------------|-------------------------|-------------|
| FHWA TEXAS DIVISION | FEDERAL AID PROJECT NO. | SHEET NO. |
| | | 9 |
| STATE | DISTRICT | COUNTY |
| TEXAS | ATL | CASS |
| CONTROL | SECTION | JOB |
| 0218 | 04 | 119 |
| | | HIGHWAY NO. |
| | | US 59 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any units of measurement or for the accuracy of any data or information provided by the user.

DATE: 4/15/2022 9:03:00 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\19-0218-04\19-0218-04.dgn

DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS

Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet



| Zone | Treatment Types Guidelines: |
|------|---|
| ① | No treatment |
| ② | CW 8-11 "Uneven Lanes" signs. |
| ③ | CW 8-9a Shoulder Drop-Off" or CW 8-11 signs plus vertical panels. |
| ④ | CW8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge slope to that of the proferred Edge Condition I. |
| ⑤ | Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone-4 may be used after consideration of other applicable factors. |


FACTORS CONSIDERED IN THE GUIDELINES:

- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ([Cross-hatched])



- $E = ADT \times T$
 Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within the clear zone.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.

Engineer's Seal

GLENN R. YOWELL
 92077
 LICENSED PROFESSIONAL ENGINEER

Date *Glenn R. Yowell, P.E.*
 4-22-22


Texas Department of Transportation

Traffic Safety Division Standard

TREATMENT FOR VARIOUS EDGE CONDITIONS

| | | | | |
|------------------------|------|--------|-----------|---------|
| FILE: edgecon.dgn | DN: | CK: | DW: | CK: |
| © TxDOT August 2000 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 03-01 08-01 9-21 | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 10 | |

DATE: 4/15/2022
 FILE: - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\0218-01-096*TCP*BRGD*RAIL*RP\CMNT.dgn



*A shadow vehicle equipped with a TMA is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting work performance. See note 12.

Not to Scale

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |
| | Crash Cushion | | Concrete Traffic Barrier |


| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 75 | L = WS | 750' | 825' | 900' | 75' | 150' | 540' |

**Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | | | | ✓ |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums are the typical channelizing devices. For Long Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Duplicate construction warning signs should be erected on both sides of freeways where median width will permit and traffic volume justifies the signing.
- Warning signs should be mounted at 7' to the bottom of the sign.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project. See note 10 on BC(1) for required CSJ limit signing.
- There shall be TY C steady burn lights on every 3rd channelizing device in a Taper.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
- Conflicting pavement markings shall be removed for long-term projects.



Glenn R. Yowell, P.E.

4-22-22

Texas Department of Transportation

TRAFFIC CONTROL PLAN

FOR BRIDGE RAIL REPLACEMENT

| | | | | | |
|---------|-----------|------|--------|-----|-----------|
| © TxDOT | 2018 | CONT | SECT | JOB | HIGHWAY |
| 10-15 | REVISIONS | 0218 | 04 | 119 | US 59 |
| | | DIST | COUNTY | | SHEET NO. |
| | | ATL | CASS | | 12 |

DATE: 4/15/2022 9:04:01 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\021800119\4 - Design\Master Design Files\01 - STD\RDOS New Standards\bc-21.dgn
 No. warranty of any kind is made by TxDOT or any person who discovers. TxDOT assumes no responsibility for the conversion of this standard to any other format or for the use of this standard in any project.

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


| |
|---|
| THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov |
| COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) |
| DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) |
| MATERIAL PRODUCER LIST (MPL) |
| ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" |
| STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) |
| TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) |
| TRAFFIC ENGINEERING STANDARD SHEETS |

SHEET 1 OF 12

| | | | |
|--|---------------|----------------------------------|-----------|
|  Texas Department of Transportation | | Traffic Safety Division Standard | |
| BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS | | | |
| BC (1) - 21 | | | |
| FILE: | bc-21.dgn | DN: | TxDOT |
| © TxDOT | November 2002 | CK: | TxDOT |
| | | DW: | TxDOT |
| | | CK: | TxDOT |
| REVISIONS | CONT | SECT | JOB |
| 4-03 7-13 | 0218 | 04 | 119 |
| 9-07 8-14 | | | US 59 |
| 5-10 5-21 | DIST | COUNTY | SHEET NO. |
| | ATL | CASS | 13 |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project. Design File: 0218041902.dgn, Project: 0218041902, Revision: 04, Date: 4/15/2022 9:04:02 AM, File: pw:\t\tdot\project\wisonline.com:TXDOT5\Documents\19 - ATL\Design Projects\0218041902.dgn

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

| Sign Number or Series | SIZE | | SPACING | |
|---------------------------------------|-------------------|--------------------|------------------|----------------------------------|
| | Conventional Road | Expressway/Freeway | Posted Speed MPH | Sign Δ Spacing "x" Feet (Apprx.) |
| CW20 ⁴ | 48" x 48" | 48" x 48" | 30 | 120 |
| CW21 | | | 35 | 160 |
| CW22 | | | 40 | 240 |
| CW23 | | | 45 | 320 |
| CW25 | | | 50 | 400 |
| CW1, CW2, CW7, CW8, CW9, CW11, CW14 | 36" x 36" | 48" x 48" | 55 | 500 ² |
| CW3, CW4, CW5, CW6, CW8-3, CW10, CW12 | 48" x 48" | 48" x 48" | 60 | 600 ² |
| | | | 65 | 700 ² |
| | | | 70 | 800 ² |
| | | | 75 | 900 ² |
| | | | 80 | 1000 ² |
| | | | * | * ³ |


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

| | |
|-------|---|
| — | Type 3 Barricade |
| ○ ○ ○ | Channelizing Devices |
| ■ | Sign |
| X | See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements. |

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 14 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect use of this standard resulting in damage or injury.

DATE: 4/15/2022 9:04:04 AM
 FILE: pw:\txdot\project\wiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflective when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



| SHEETING REQUIREMENTS (WHEN USED AT NIGHT) | | |
|--|--------|--|
| USAGE | COLOR | SIGN FACE MATERIAL |
| BACKGROUND | RED | TYPE B OR C SHEETING |
| BACKGROUND | ORANGE | TYPE B _{FL} OR C _{FL} SHEETING |
| LEGEND & BORDER | WHITE | TYPE B OR C SHEETING |
| LEGEND & BORDER | BLACK | ACRYLIC NON-REFLECTIVE FILM |

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTC list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTC) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTC lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTC list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12


Texas Department of Transportation
 Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 16 | |

DATE: 4/15/2022 9:04:05 AM
 FILE: \\txdot\project\wiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\0218041194 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats, including electronic, resulting from its design.




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- * See BC(4) for definition of "Work Duration."
- ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 17 | |

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

| | |
|-----------------------|--------------------------|
| FREEWAY CLOSED X MILE | FRONTAGE ROAD CLOSED |
| ROAD CLOSED AT SH XXX | SHOULDER CLOSED XXX FT |
| ROAD CLSD AT FM XXXX | RIGHT LN CLOSED XXX FT |
| RIGHT X LANES CLOSED | RIGHT X LANES OPEN |
| CENTER LANE CLOSED | DAYTIME LANE CLOSURES |
| NIGHT LANE CLOSURES | I-XX SOUTH EXIT CLOSED |
| VARIOUS LANES CLOSED | EXIT XXX CLOSED X MILE |
| EXIT CLOSED | RIGHT LN TO BE CLOSED |
| MALL DRIVEWAY CLOSED | X LANES CLOSED TUE - FRI |
| XXXXXXXXX BLVD CLOSED | |

Other Condition List

| | |
|--------------------------|-------------------------|
| ROADWORK XXX FT | ROAD REPAIRS XXXX FT |
| FLAGGER XXXX FT | LANE NARROWS XXXX FT |
| RIGHT LN NARROWS XXXX FT | TWO-WAY TRAFFIC XX MILE |
| MERGING TRAFFIC XXXX FT | CONST TRAFFIC XXX FT |
| LOOSE GRAVEL XXXX FT | UNEVEN LANES XXXX FT |
| DETOUR X MILE | ROUGH ROAD XXXX FT |
| ROADWORK PAST SH XXXX | ROADWORK NEXT FRI-SUN |
| BUMP XXXX FT | US XXX EXIT X MILES |
| TRAFFIC SIGNAL XXXX FT | LANES SHIFT * |

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

| | |
|----------------------|----------------------|
| MERGE RIGHT | FORM X LINES RIGHT |
| DETOUR NEXT X EXITS | USE XXXXX RD EXIT |
| USE EXIT XXX | USE EXIT I-XX NORTH |
| STAY ON US XXX SOUTH | USE I-XX E TO I-XX N |
| TRUCKS USE US XXX N | WATCH FOR TRUCKS |
| WATCH FOR TRUCKS | EXPECT DELAYS |
| EXPECT DELAYS | PREPARE TO STOP |
| REDUCE SPEED XXX FT | END SHOULDER USE |
| USE OTHER ROUTES | WATCH FOR WORKERS |
| STAY IN LANE * | |

Location List

| |
|--------------------------|
| AT FM XXXX |
| BEFORE RAILROAD CROSSING |
| NEXT X MILES |
| PAST US XXX EXIT |
| XXXXXXXXX TO XXXXXXX |
| US XXX TO FM XXXX |

Warning List

| |
|-----------------------|
| SPEED LIMIT XX MPH |
| MAXIMUM SPEED XX MPH |
| MINIMUM SPEED XX MPH |
| ADVISORY SPEED XX MPH |
| RIGHT LANE EXIT |
| USE CAUTION |
| DRIVE SAFELY |
| DRIVE WITH CARE |

** Advance Notice List

| |
|-----------------------|
| TUE-FRI XX AM-X PM |
| APR XX-XX X PM-X AM |
| BEGINS MONDAY |
| BEGINS MAY XX |
| MAY X-X XX PM - XX AM |
| NEXT FRI-SUN |
| XX AM TO XX PM |
| NEXT TUE AUG XX |
| TONIGHT XX PM-XX AM |

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for any errors or omissions resulting from its use.

| WORD OR PHRASE | ABBREVIATION | WORD OR PHRASE | ABBREVIATION |
|------------------------|--------------|----------------|--------------|
| Access Road | ACCS RD | Major | MAJ |
| Alternate | ALT | Miles | MI |
| Avenue | AVE | Miles Per Hour | MPH |
| Best Route | BEST RTE | Minor | MNR |
| Boulevard | BLVD | Monday | MON |
| Bridge | BRDG | Normal | NORM |
| Cannot | CANT | North | N |
| Center | CTR | Northbound | (route) N |
| Construction Ahead | CONST AHD | Parking | PKING |
| CROSSING | XING | Road | RD |
| Detour Route | DETOUR RTE | Right Lane | RT LN |
| Do Not | DONT | Saturday | SAT |
| East | E | Service Road | SERV RD |
| Eastbound | (route) E | Shoulder | SHLDR |
| Emergency | EMER | Slippery | SLIP |
| Emergency Vehicle | EMER VEH | South | S |
| Entrance, Enter | ENT | Southbound | (route) S |
| Express Lane | EXP LN | Speed | SPD |
| Expressway | EXPWY | Street | ST |
| XXXX Feet | XXXX FT | Sunday | SUN |
| Fog Ahead | FOG AHD | Telephone | PHONE |
| Freeway | FRWY, FWY | Temporary | TEMP |
| Freeway Blocked | FWY BLKD | Thursday | THURS |
| Friday | FRI | To Downtown | TO DWNTN |
| Hazardous Driving | HAZ DRIVING | Traffic | TRAF |
| Hazardous Material | HAZMAT | Travelers | TRVLRs |
| High-Occupancy Vehicle | HOV | Tuesday | TUES |
| Highway | HWY | Time Minutes | TIME MIN |
| Hour(s) | HR, HRS | Upper Level | UPR LEVEL |
| Information | INFO | Vehicles (s) | VEH, VEHS |
| It Is | ITS | Warning | WARN |
| Junction | JCT | Wednesday | WED |
| Left | LFT | Weight Limit | WT LIMIT |
| Left Lane | LFT LN | West | W |
| Lane Closed | LN CLOSED | Westbound | (route) W |
| Lower Level | LWR LEVEL | Wet Pavement | WET PVMT |
| Maintenance | MAINT | Will Not | WONT |

Roadway designation # IH-number, US-number, SH-number, FM-number




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CR: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 18 | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/15/2022 9:04:08 AM
 FILE: \\txdotproject\wisonline.com\TXDOT5\Documents\19 - ATL\Design Projects\0218041194 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

| REQUIREMENTS | | | |
|--------------|--------------|-------------------------------|-----------------------------|
| TYPE | MINIMUM SIZE | MINIMUM NUMBER OF PANEL LAMPS | MINIMUM VISIBILITY DISTANCE |
| B | 30 x 60 | 13 | 3/4 mile |
| C | 48 x 96 | 15 | 1 mile |

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation
 Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 19 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/15/2022 9:04:09 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\0218041194 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

| | | | | | | | | | |
|-----------|---------------|------|--------|-----------|---------|-----|-------|-----|-------|
| FILE: | bc-21.dgn | DW: | TxDOT | CK: | TxDOT | DW: | TxDOT | CK: | TxDOT |
| © TxDOT | November 2002 | CONT | SECT | JOB | HIGHWAY | | | | |
| REVISIONS | | 0218 | 04 | 119 | US 59 | | | | |
| 4-03 | 8-14 | DIST | COUNTY | SHEET NO. | | | | | |
| 9-07 | 5-21 | ATL | CASS | 20 | | | | | |
| 7-13 | | | | | | | | | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/15/2022 9:04:10 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn



FIXED
(Rigid or self-righting)

DRIVEABLE




(Rigid or self-righting)

PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

CHEVRONS

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

| Posted Speed | Formula | Minimum Desirable Taper Lengths * * | | | Suggested Maximum Spacing of Channelizing Devices | |
|--------------|--------------------------|-------------------------------------|------------|------------|---|--------------|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' |
| 35 | | 205' | 225' | 245' | 35' | 70' |
| 40 | | 265' | 295' | 320' | 40' | 80' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' |
| 50 | | 500' | 550' | 600' | 50' | 100' |
| 55 | | 550' | 605' | 660' | 55' | 110' |
| 60 | | 600' | 660' | 720' | 60' | 120' |
| 65 | | 650' | 715' | 780' | 65' | 130' |
| 70 | | 700' | 770' | 840' | 70' | 140' |
| 75 | | 750' | 825' | 900' | 75' | 150' |
| 80 | | 800' | 880' | 960' | 80' | 160' |

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 21 | |

DATE: 4/15/2022 9:04:11 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

| LEGEND | |
|--------|---|
| | Plastic drum |
| | Plastic drum with steady burn light or yellow warning reflector |
| | Steady burn warning light or yellow warning reflector |

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ATL | CASS | 22 | |

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

| DEPARTMENTAL MATERIAL SPECIFICATIONS | |
|--|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| TRAFFIC BUTTONS | DMS-4300 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |
| TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS | DMS-8242 |

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12




BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CR: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT February 1998 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 2-98 9-07 5-21 | DIST | COUNTY | SHEET NO. | |
| 1-02 7-13 | ATL | CASS | 23 | |
| 11-02 8-14 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/15/2022 9:04:12 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\0218041194 - Design\Master Design Files\04 - STANDARDS\New Standards\bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21


| | | | | |
|----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| ©TxDOT February 1998 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 1-97 9-07 5-21 | DIST | COUNTY | SHEET NO. | |
| 2-98 7-13 | ATL | CASS | 24 | |
| 11-02 8-14 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect or damaged markings resulting from its use.


DATE: 4/15/2022 9:04:13 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\0218041194 - Design\Master Design Files\04 STANDARDS\New Standards\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/27/2022 10:28:32 AM
 FILE: C:\Users\thom1\Desktop\STANDARDS US 59\TCP (ATL-12) - Work On Shoulder.dgn



**TYPICAL UNDIVIDED OR FLUSH MEDIAN
 WORK ON SHOULDER**



**TYPICAL DEPRESSED MEDIAN
 WORK ON SHOULDER**

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Drum |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans or when approved by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- High level warning flags should be used on advance warning signs during daytime operations. Warning lights may be used to add emphasis to advance warning signs during nighttime operations.
- Duplicate construction warning signs should be erected on the median side where median width will permit and traffic volume justifies the signing.
- See BC Standards for additional sign details.
- Drums are the typical channelizing device. Cones or other devices may be used if approved by the Engineer. Drums shall be used during nighttime operations. Channelizing devices shall also be placed in accordance with "WORKSHEET FOR EDGE CONDITION TREATMENT TYPES."
- Neither work activity nor storage of equipment, vehicles, or materials shall occur within the buffer space.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

#A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used and positioned per the Manufacturer's Roll Ahead Distance (MRAD) in advance of the area of crew exposure without adversely affecting the work performance.

If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.



Texas Department of Transportation
Atlanta District Standard

**TRAFFIC CONTROL PLAN
 WORK ON SHOULDER**

TCP (ATL-12)-14

| | | | | |
|---------------------|-----------|-----------|-----------|-----------|
| FILE: atl-12.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| ©TxDOT January 2014 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| DIST | COUNTY | SHEET NO. | | |
| ATL | CASS | | | 25 |

DATE: 4/17/2022 8:27:52 PM
 FILE: \\txdot\project\seon\line.com\TXDOTS\Documents\19 - ATL\Design Projects\021804\19 - Pavement Repairs\021804\19 - Pavement Repairs



LEGEND

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Drum |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | $L = WS$ | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | | ✓ | ✓ | |

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans or when approved by the Engineer.
 - All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
 - The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
 - High level warning flags should be used on advance warning signs during daytime operations. Warning lights may be used to add emphasis to advance warning signs during nighttime operations.
 - Duplicate construction warning signs shall be erected on the median side.
 - See BC Standards for additional sign details.
 - Drums are the typical channelizing device. Cones or other devices may be used if approved by the Engineer. Drums shall be used during nighttime operations. Channelizing devices shall also be placed in accordance with "WORKSHEET FOR EDGE CONDITION TREATMENT TYPES."
 - Neither work activity nor storage of equipment, vehicles, or materials shall occur within the buffer space.
 - When signs are mounted at 1' height for short term stationary, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
 - The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.
 - For TCP (ATL-16b) Flush Median, median side signs shall be mounted at 7' height.

#A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used and positioned per the Manufacturer's Roll Ahead Distance (MRAD) in advance of the area of crew exposure without adversely affecting the work performance.

If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.


Texas Department of Transportation
 Atlanta District Standard

**TRAFFIC CONTROL PLAN
 PAVEMENT REPAIRS
 (FLUSH MEDIAN)**

TCP (ATL-16)-15

| | | | | |
|---------------------|------------|-----------|--------------|----------------|
| FILE: 0218-16.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| ©TxDOT January 2014 | CONT: 0218 | SECT: 04 | JOB: 119 | HIGHWAY: US 59 |
| 4-15 | REVISIONS: | DIST: ATL | COUNTY: CASS | SHEET NO.: 26 |

DATE: 4/17/2022 8:45:20 PM
 FILE: \\txdot\projectwise\line.com\TXDOTS\Documents\19 - ATL\Design Projects\0180419\0180419.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided. For more information, contact the Texas Department of Transportation, 1201 North East Street, Austin, Texas 78701-1099, or call 1-800-392-0011.



‡ For nighttime closures, place CW1-8 (18"x24") on drums in accordance with BC(8) standard.

TCP (ATL-19a)
**TYPICAL FLUSH MEDIAN
 TWO LANES CLOSED**

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Drum |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | L = WS | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | L = WS | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | L = WS | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | L = WS | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | | ✓ | ✓ | ✓ |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans or when approved by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- High level warning flags should be used on advance warning signs during daytime operations. Warning lights may be used to add emphasis to advance warning signs during nighttime operations.
- See BC Standards for additional sign details.
- Drums are the typical channelizing device. Cones or other devices may be used if approved by the Engineer. Drums shall be used during nighttime operations. Channelizing devices shall also be placed in accordance with "WORKSHEET FOR EDGE CONDITION TREATMENT TYPES."
- Neither work activity nor storage of equipment, vehicles, or materials shall occur within the buffer space.
- When signs are mounted at 1' height for short term stationary, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where two-way traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting pavement markings, not the entire workzone.

#A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used and positioned per the Manufacturer's Roll Ahead Distance (MRAD) in advance of the area of crew exposure without adversely affecting the work performance.

 If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.





**TRAFFIC CONTROL PLAN
 MULTIPLE LANE CLOSURE
 (FLUSH MEDIAN)**

TCP (ATL-19)-15

| | | | | | | | | | |
|--------|--------------|--------|-----------|-----|---------|-----|-------|-----|-------|
| FILE: | 01-19.dgn | DN: | TxDOT | CR: | TxDOT | DW: | TxDOT | CK: | TxDOT |
| ©TxDOT | January 2014 | CONT | SECT | JOB | HIGHWAY | | | | |
| 4-15 | REVISIONS | 0218 | 04 | 119 | US 59 | | | | |
| | DIST | COUNTY | SHEET NO. | | | | | | |
| | ATL | CASS | 27 | | | | | | |





DATE: 4/15/2022 9:04:23 AM
 FILE: \\txdot\project\wiseon\line.com\TXDOT5\Documents\19 - ATL\Design\Projects\19041901\19041901.dwg
 PROJECT: 19041901
 DRAWING: 19041901.dwg
 TITLE: TRAFFIC CONTROL PLAN MOBILE OPERATIONS UNDIVIDED HIGHWAYS
 SHEET: 28 OF 28
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of any information derived from this drawing.



| LEGEND | | | |
|--------|--------------------------------|---------------------|---|
| * | Trail Vehicle | ARROW BOARD DISPLAY | |
| ** | Shadow Vehicle | | |
| *** | Work Vehicle | | RIGHT Directional |
| | Heavy Work Vehicle | | LEFT Directional |
| | Truck Mounted Attenuator (TMA) | | Double Arrow |
| | Traffic Flow | | CAUTION (Alternating Diamond or 4 Corner Flash) |

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| ✓ | | | | |

- GENERAL NOTES**
- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
 - The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
 - The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
 - Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
 - Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
 - Each vehicle shall have two-way radio communication capability.
 - When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
 - Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
 - "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
 - On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



Traffic Operations Division Standard









**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
UNDIVIDED HIGHWAYS**

TCP(3-1)-13

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: tcp3-1.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 2-94 4-98 | DIST | COUNTY | | SHEET NO. |
| 8-95 7-13 | ATL | CASS | | 28 |
| 1-97 | | | | |

175

DATE: 4/15/2022 9:04:31 AM
 FILE: \\txdot\project\wisonline.com\TXDOT5\Documents\19 - ATL\Design\Projects\19-001\19-001.dwg
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from a digital or analog format to a digital format.



| LEGEND | | |
|--------------------------------|--|---|
| * Trail Vehicle | | ARROW BOARD DISPLAY |
| ** Shadow Vehicle | | |
| *** Work Vehicle | | RIGHT Directional |
| Heavy Work Vehicle | | LEFT Directional |
| Truck Mounted Attenuator (TMA) | | Double Arrow |
| Traffic Flow | | CAUTION (Alternating Diamond or 4 Corner Flash) |

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| ✓ | | | | |

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation

Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/REMOVAL
TCP (3-3) - 14

| | | | | |
|------------------------|-----------|-----------|-----------|-----------|
| FILE: tcp3-3.dgn | DN: TxDOT | CK: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT September 1987 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 2-94 4-98 | DIST | COUNTY | | SHEET NO. |
| 8-95 7-13 | ATL | CASS | | 29 |
| 1-97 7-14 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein. For more information, contact the Texas Department of Transportation, 1201 North East Street, Austin, Texas 78701.

DATE: 4/15/2022 9:04:41 AM
 FILE: \\txdot.projectwiseonline.com:TXDOT15\Documents\19 - ATL\Design Projects\19-04-001-19-04-001-19-04-001.dgn

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm





WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13



| | | | | | | | | | |
|------------|---------------|-------|-------|---------|-------|------------|-------|-----|-------|
| FILE: | wzstpm-13.dgn | DN: | TxDOT | CK: | TxDOT | OW: | TxDOT | CK: | TxDOT |
| © TxDOT | April 1992 | CONT: | 0218 | SECT: | 04 | JOB: | 119 | US: | 59 |
| REVISIONS: | | DIST: | ATL | COUNTY: | CASS | SHEET NO.: | | | 30 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/27/2022
 FILE: C:\Users\atthomal\Desktop\STANDARDS US 59\sscb210.dgn











Note:
 V1 Bars above the drainage slots may be bent to accommodate 1 1/2" clear cover as directed by the Engineer.




Single Slope Concrete Traffic Barrier
 Precast SSCB barrier may be connected to cast-in-place SSBC. The joint connection "Types" may be used in the cast-in-place barrier, to match the precast barrier connection.

General Notes

- Concrete shall be Class H with a minimum compressive strength of 3,600 psi.
- Where used, rebar reinforcement shall be Grade 60 and conform to ASTM A615.
- Precast barrier length shall be 30 ft. unless otherwise specified on the plans.
- All precast barrier edges shall have a 3/4" chamfer or a tooled radius.
- All concrete, reinforcement, joint connection systems, grout etc. as shown, are considered as part of the barrier payment.
- Conduit trough when required shall be shown elsewhere on the plans, or as directed by the Engineer.
- Regardless of the method of handling, barrier lifting points shall be approx. 7.5 feet from the ends of the barrier. Lifting devices and attachments to barrier sections shall be approved by the Engineer.
- Surface finishing and grouting (where required) shall be two parts sand and one part cement with enough water to make the mixture plastic. Grouting shall be done in a manner that will assure a smooth surface. Surface finishing shall be considered subsidiary to the various bid items.
- All steel assemblies shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."




Weight of one precast 30 ft. (SSCB) segment = Approx. 10.5 Tons or 717 lbs per ft.



Welded Wire Reinforcement (WWR) Option for Bars R and V1

(WWR) General Notes


- Deformed Welded Wire Reinforcement (WWR) shall conform to ASTM A497.
- Welded wire cage may be cut or bent to accommodate the Type X joint connection and drainage slots, as directed by the Engineer.
- All reinforcement shall comply with Item 440, "Reinforcing Steel."
- Combinations of reinforcing steel and WWR will be permitted, as directed by the Engineer. The dimension from the end of the barrier section to the first wire shall not exceed 3".




| | | | |
|---|-----------|--------------------------|---------|
| | | Design Division Standard | |
| SINGLE SLOPE CONCRETE BARRIER PRECAST BARRIER (TYPE 1) SSCB(2)-10 | | | |
| FILE: sscb210.dgn | DN: TxDOT | CR: AM | DW: BD |
| © TxDOT December 2010 | CONT SECT | JOB | HIGHWAY |
| REVISIONS | 0218 04 | 119 | US 59 |
| DIST | COUNTY | SHEET NO. | |
| ATL | CASS | 33 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/27/2022
 FILE: C:\Users\atthoma\l\Desktop\STANDARDS US 59\sscb210.dgn



END VIEW
 "QUICK-BOLT" POCKET LOCATIONS




ELEVATION VIEW
 "QUICK-BOLT" (SSCB)
 See Manufacturer's shop drawing for additional details




ELEVATION VIEW SHOWING JOINT CONNECTION
 "QUICK-BOLT"


Joint Connection (Type Q)



TOP VIEW
 PRECAST (SSCB) WITH J-J HOOKS
 See Manufacturer's shop drawing for additional details



VIEW FROM ABOVE
 J-J HOOK CONNECTION




END VIEW

Proprietary Joint Connections (SSCB)


Two proprietary joint connections are acceptable as alternates to the (Type X) connection shown, here on. These joint connections types are:

J-J Hooks by Easi-Set Industries, (800)547-4045
 Quick-Bolt by Bexar Concrete, (210)497-3773


If one of these connection systems are exclusively specified in the plans, prior approval for sole source use must be obtained. Details of the connection components and barrier reinforcement for these systems, will be shown on the manufacturer's shop drawing(s) furnished to the Engineer.




SECTION A-A
 Showing (Type R)
 Rebar Grid




ELEVATION
 V1 Bars (See Sheet 1)



TOP VIEW
 JOINT CONNECTION
 Typical at both ends of barrier segment



(#4) V2 BARS
 6 ~ two piece bars per barrier segment



WELDED REBAR GRID



Joint Connection (Type R)

SINGLE SLOPE CONCRETE BARRIER
 PRECAST BARRIER (TYPE 1)
 SSCB(2) - 10

| | | | | |
|-----------------------|-----------|--------|-----------|---------|
| FILE: sscb210.dgn | DN: TxDOT | CK: AM | DW: VP | CK: |
| © TxDOT December 2010 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 33A | |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 4/17/2022
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - DesignMaster Design Files\04 STANDARDS\New Standards\absorbml19.dgn




THE ABSORB-M IS A NON-REDIRECTIVE, GATING, CRASH CUSHION DESIGNED TO MEET THE LATEST TL-3 & TL-2 MASH REQUIREMENTS.

THE SYSTEM IS DESIGNED TO ACCOMMODATE A VARIETY OF F-SHAPE AND SINGLE SLOPE CONCRETE BARRIERS. CONTACT THE MANUFACTURER FOR GUIDANCE REGARDING OTHER ALLOWABLE SHAPES.

| TEST LEVEL | NUMBER OF ELEMENTS | EFFECTIVE LENGTH | MAXIMUM LENGTH |
|------------|--------------------|------------------|----------------|
| TL-2 | 2 | 14' - 7 3/4" | 17' - 4" |
| TL-3 | 3 | 20' - 11 3/4" | 23' - 8" |

NOTE: CROSS SLOPES OF UP TO 8% (OR 1:12 SLOPE) CAN BE ACCOMMODATED WITH STANDARD HARDWARE SHOWN WITHIN THE INSTRUCTIONS MANUAL. FOR SLOPES WITH EXCESS OF 8% (OR 1:12) CONTACT, LINDSAY TRANSPORTATION SOLUTIONS.




NOTE: APPLY A HIGH REFLECTIVE DECAL TO THE NOSE PLATE. DELINEATION DECAL ORIENTATION IS SHOWN ON THE CONSTRUCTION PLAN SET AND SHALL BE IN ACCORDANCE WITH THE TEXAS MUTCD FOR (TRAFFIC CONTROL DEVICES). DECALS ARE AVAILABLE FOR TRAFFIC FLOW ON THE LEFT-SIDE, BOTH -SIDES AND RIGHT-SIDE.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING THE INSTALLATION AND TECHNICAL GUIDANCE, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800. 180 RIVER ROAD, RIO VISTA, CA 94571
- THE ABSORB-M SYSTEM IS ONLY APPROVED FOR USE IN (TEMPORARY WORK ZONE) LOCATIONS.
- THE ABSORB-M IS A WATER FILLED NON-REDIRECTIVE, GATING CRASH CUSHION THAT DOES NOT NEED TO BE ATTACHED TO A FOUNDATION AND CAN BE INSTALLED ON TOP OF CONCRETE, ASPHALT, OR ANY SURFACE CAPABLE OF BEARING THE WEIGHT OF THE SYSTEM.
- MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
- THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
- THE ABSORB-M SHOULD BE LOCATED APPROXIMATELY PARALLEL WITH THE BARRIER.
- THE USE OF THE ABSORB-M IS RESTRICTED TO A BARRIER HEIGHT OF UP TO 42 INCHES.
- DO NOT ADD WATER TO FRONT ELEMENT (TL-2 OR TL-3 UNIT).

| BILL OF MATERIALS (BOM) ABSORB-M TL-3 & TL-2 SYSTEMS | | | QTY | QTY |
|--|----------------|--|-------------|-------------|
| ITEM # | PART NUMBER | PART DESCRIPTION | TL-2 SYSTEM | TL-3 SYSTEM |
| 1 | BSI-1809036-00 | TRANSITION - (GALV) | 1 | 1 |
| 2 | BSI-1808002-00 | PRE-ASSEMBLED ABSORBING (ELEMENTS) | 2 | 3 |
| 3 | BSI-4004598 | FILL CAPS | 8 | 12 |
| 4 | BSI-4004599 | DRAIN PLUGS | 2 | 3 |
| 5 | BSI-1809053-00 | TENSION STRAP - (GALV) | 8 | 12 |
| 6 | BSI-2001998 | C-SCR FH 3/8-16 X 1 1/2 GR5 PLT | 8 | 12 |
| 7 | BSI-2001999 | C-SCR FH 3/8-16 X 1 GR5 PLT | 8 | 12 |
| 8 | BSI-1809035-00 | MIDNOSE - (GALV) | 1 | 1 |
| 9 | BSI-1808014-00 | NOSE PLATE | 1 | 1 |
| 10 | BSI-1809037-00 | TRANSITION STRAP (LEFT-HAND) - (GALV) | 1 | 1 |
| 11 | BSI-1809038-00 | TRANSITION STRAP (RIGHT-HAND) - (GALV) | 1 | 1 |
| 12 | BSI-1808005-00 | PIN ASSEMBLY | 8 | 10 |
| 13 | BSI-2002001 | ANC MECH 5/8-11X5 (GALV) | 6 | 6 |
| 14 | ABSORB-M | INSTALLATION AND INSTRUCTIONS MANUAL | 1 | 1 |

* COMPONENTS PRE-ASSEMBLED WITH ELEMENT ASSEMBLY




SACRIFICIAL

Texas Department of Transportation
 Design Division Standard


**LINDSAY TRANSPORTATION SOLUTIONS
 CRASH CUSHION
 (MASH TL-3 & TL-2)
 TEMPORARY - WORK ZONE
 ABSORB (M) - 19**

| | | | | |
|--------------------|-----------|--------|-----------|---------|
| FILE: absorbml19 | DN: TxDOT | CK: KM | DW: VP | CK: |
| © TxDOT: JULY 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 34 | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. DATE: 4/15/2022 FILE: \\txdotprojectwiseonline.com:TXDOT15\Documents\19 - ATL\Design Projects\0218041194 - Design\Master Design Files\04 STANDARDS\New Standards\sled19.dgn



PLAN VIEW



ELEVATION VIEW



NOTE:
SEE INSTALLATION MANUAL FOR CUSTOMIZED DELINEATION NOSE SHEETING FOR DECAL PLACEMENT.


| TEST LEVEL | NUMBER OF SECONDARY MODULES | SYSTEM LENGTH |
|------------|-----------------------------|---------------|
| TL-3 | 3 | 25' 3" |

GENERAL NOTES

- REFER TO THE INSTALLATION MANUAL FOR SPECIFIC SYSTEM ASSEMBLY AND MODULE ORIENTATION. FOR ADDITIONAL INFORMATION, CONTACT TRAFFIX, INC. AT (949) 361-5663.
- THE SLED SYSTEM IS A MASH APPROVED TEST LEVEL 3 (TL-3) CRASH CUSHION APPROVED FOR USE IN TEMPORARY WORK ZONES. THE SLED SYSTEM IS A NON-REDIRECTIVE, GATING CRASH CUSHION THAT DOES NOT NEED TO BE ATTACHED TO THE GROUND AND CAN BE INSTALLED ON CONCRETE, ASPHALT, GRAVEL OR COMPACTED SOIL.
- MAXIMUM PERMISSIBLE CROSS SLOPE IS 8° (DEGREES) (14%).
- THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
- THE SLED SYSTEM CAN BE ATTACHED TO:
 - CONCRETE BARRIER, TEMPORARY OR PERMANENT, 45" MAXIMUM HEIGHT
 - STEEL BARRIER
 - PLASTIC BARRIER
 - CONCRETE BRIDGE ABUTMENTS
 - W-BEAM GUARD RAIL
 - THRIE BEAM GUARD RAIL

| BILL OF MATERIAL | | |
|------------------|---|-----------|
| PART NUMBER | DESCRIPTION | QTY: TL-3 |
| 45131 | TRANSITION FRAME, GALVANIZED | 1 |
| 45150 | TRANSITION PANEL, GALVANIZED | 2 |
| 45147-CP | TRANSITION SHORT DROP PIN W/ KEEPER PIN, GALVANIZED | 2 |
| 45148-CP | TRANSITION LONG DROP PIN W/ KEEPER PIN, GALVANIZED | 1 |
| 45050 | ANCHOR BOLTS | 9 |
| 12060 | WASHER, 3/4" ID X 2" OD | 9 |
| 45044-Y | SLED YELLOW WATER FILLED MODULE | 3 |
| 45044-YH | SLED YELLOW "NO FILL" MODULE | 1 |
| 45044-S | CIS (CONTAINMENT IMPACT SLED), GALVANIZED | 1 |
| 45043-CP | T-PIN W/ KEEPER PIN | 4 |
| 18009-B-I | FILL CAP W/ "DRIVE BY" FLOAT INDICATOR | 3 |
| 45033-RC-B | DRAIN PLUG | 3 |
| 45032-DPT | DRAIN PLUG REMOVAL TOOL | 1 |

| TRANSITION OPTIONS |
|---|
| SLED TRANSITION TO CONCRETE TRAFFIC BARRIER (TEMPORARY OR PERMANENT) |
| SLED TRANSITION TO STEEL TRAFFIC BARRIER (CONTACT MFGR FOR PROPER TRANSITION) |
| SLED TRANSITION TO PLASTIC TRAFFIC BARRIER (CONTACT MFGR FOR PROPER TRANSITION) |
| SLED TRANSITION TO W-BEAM OR THRIE BEAM GUARD RAIL (CONTACT MFGR FOR PROPER TRANSITION) |
| SLED TRANSITION TO CONCRETE BRIDGE ABUTMENT |



SLED TRANSITION COMPONENTS FOR ATTACHMENT TO CMB

NOTE:
SEE MANUFACTURER'S INSTALLATION MANUAL FOR FURTHER DETAILS.

NOTE:
THIS STANDARD IS A BASIC REPRESENTATION OF THE SLED, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.

SACRIFICIAL

Design Division Standard




SLED
 CRASH CUSHION
 TL-3 MASH COMPLIANT
 (TEMPORARY, WORK ZONE)
 SLED-19

| | | | | |
|------------------------|-----------|-----------|--------|---------|
| FILE: sled19.dgn | DN: TxDOT | CK: KM | DW: VP | CK: |
| © TxDOT: DECEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| DIST | COUNTY | SHEET NO. | | |
| ATL | CASS | | | 35 |

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 4/27/2022
 FILE: C:\User\s\thoma1\Desktop\STANDARDS US 59\viasfpm19.dgn

| SITE CONDITIONS AND PLACEMENT GUIDELINES | | |
|---|--|---|
| CONDITION | RECOMMENDATION | ILLUSTRATION |
| 1. ANGLE OF ARRAY IN RELATION TO CENTER LINE OF OBSTACLE | NOT RECOMMENDED FOR MORE THAN 10° | |
| 2. MODULE SPACING: MODULE TO FIXED OBJECT MODULE TO MODULE | 12" TO 24" SEE DIAGRAM | |
| 3. BI-DIRECTIONAL TRAFFIC | OFFSET ARRAY TO AVOID REAR CORNER MODULE SNAGGING, POTENTIAL BY TRAFFIC IN THE UPSTREAM DIRECTION OF FLOW. | SEE (DETAIL B) SHOWING BI-DIRECTIONAL TRAFFIC |
| 4. "COFFIN" CORNER | SHIELD 30" MINIMUM OUTSIDE OF FIXED OBJECT | |
| 5. SLOPING SITES: LATERAL AND LONGITUDINAL FOR MORE INFORMATION READ GENERAL NOTE: 7 | 1:10 MAXIMUM (V: H:) | |
| 6. CURB: RAISED ISLAND: | NO MORE THAN 4" HIGH (REMOVE IF POSSIBLE) | |
| 7. FOUNDATION PADS: | FLAT SURFACE: CONCRETE OR ASPHALT | |
| 8. MAINTENANCE: | KEEP SITE CLEAR OF TRASH, ROAD DEBRIS, ETC | |
| 9. SAND DENSITIES | 100 LBS / CF | |
| 10. VANDALISM | CHECK PERIODICALLY FOR DAMAGES, GRAFFITI. | |



GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE AVAILABLE MASH COMPLIANT SYSTEMS, CONTACT: Traffic DEVICES, INC. AT (949) 361-5663 OR PSS INNOVATIONS, INC. AT (800) 662-6338.
- REAR MODULES SHOULD OVERLAP THE HAZARDOUS FIXED OBJECT IN WIDTH ON EACH SIDE BY A MINIMUM OF 30 INCHES. SEE DETAILS A, B.
- BARRIERS CAN BE INSTALLED AT ANY DISTANCE FROM THE SHOULDER, AT ROADSIDE AND MEDIAN LOCATIONS FROM ZERO FT UP TO 30 FT, DEPENDING UPON THE LOCATION OF THE HAZARDOUS FIXED OBJECT.
- ANGLING THE BARRIER TOWARDS ON-COMING TRAFFIC IS SUGGESTED, 3-DEGREES UP TO 10-DEGREES DEPENDING ON SPACE AVAILABLE.
- WHENEVER POSSIBLE, CURBS 4 INCHES AND HIGHER SHOULD BE REMOVED FROM THE HAZARDOUS SITES. HOWEVER, WHEN REMOVAL IS NOT POSSIBLE, MODULES CAN BE SEPARATED ALONG THE BARRIER AXIS TO FIT THE SITUATION.
- LONGITUDINAL SPACING OF MODULES MAY BE INCREASED WHERE SPACE PERMITS, E.G., 2 FT UP TO 3 FT SPACING OF SELECTED MODULES MAY PERMIT THE DESIGNER TO USE ALL THE SPACE ALLOCATED FOR AN ENERGY-ABSORBING BARRIER.
- THE ENTIRE AREA OF THE CRASH CUSHION INSTALLATION AND APPROACHES SHALL BE GRADED SO THAT THE MAXIMUM SLOPE DOES NOT EXCEED 1V:10H VERTICALLY OR HORIZONTALLY IN ANY DIRECTION.
- WHERE REQUIRED, SUPPORT PADS, CONCRETE, ASPHALT, ETC, WILL BE MEASURED AND PAID FOR IN ACCORDANCE WITH PERTINENT BID ITEMS.
- Traffic DEVICES AND PSS INNOVATIONS SAND BARREL SYSTEMS HAVE BEEN ASSESSED AS MASH COMPLIANT.

Texas Department of Transportation
 Design Division Standard

**VEHICLE IMPACT ATTENUATOR
 SAND FILLED PLASTIC
 MODULES
 MASH TL-3 & TL-2
 VIA (SFPM) - 19**


| | | | | |
|------------------------|-----------|--------|-----------|---------|
| FILE: viasfpm19.dgn | DN: TxDOT | CK: KM | DN: VP | CK: CL |
| © TxDOT: DECEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 36 | |

SACRIFICIAL

DATE: 4/27/2022 3:24:05 PM
 FILE: \\atl\dot\project\wiseon\line.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\0218-04-kt:19 Survey control.she

| Alignment Name: US 59 | | | |
|-------------------------------------|----------------------------|---------------------|------------|
| Alignment Description: | | | |
| Alignment Style: Alignment\Baseline | | | |
| | Station | Northing | Easting |
| Element: Linear | | | |
| POT | () 96+76.10 R1 | 7108779.2 | 3277042.83 |
| PC | () 99+77.53 R1 | 7108539.84 | 3276859.62 |
| | Tangential Direction: | S37 | |
| | Tangential Length: | 301.426 | |
| Element: Circular | | | |
| PC | () 99+77.53 R1 | 7108539.84 | 3276859.62 |
| PI | () 103+76.18 R1 | 7108223.28 | 3276617.30 |
| CC | () | 7111749.04 | 3272667.08 |
| PT | () 107+73.32 R1 | 7107946.70 | 3276330.21 |
| | Radius: | 5279.8 | |
| | Delta: | 08°38'09.158" Right | |
| | Degree of Curvature (Arc): | 01°05'06.678" | |
| | Length: | 795.795 | |
| | Tangent: | 398.653 | |
| | Chord: | 795.042 | |
| | Middle Ordinate: | 14.986 | |
| | External: | 15.029 | |
| | Back Tangent Direction: | S37 | |
| | Back Radial Direction: | N52 | |
| | Chord Direction: | S41 | |
| | Ahead Radial Direction: | N43 | |
| | Ahead Tangent Direction: | S46 | |
| Element: Linear | | | |
| PT | () 107+73.32 R1 | 7107946.70 | 3276330.21 |
| | EQNBK 108+07.16 R1 | 7107923.22 | 3276305.84 |
| | EQNAHD 108+02.38 R2 | 7107923.22 | 3276305.84 |
| PI | () 163+05.02 R3 | 7104110.74 | 3272348.47 |
| | Tangential Direction: | S46 | |
| | Tangential Length: | 5528.908 | |
| Element: Linear | | | |
| PI | () 163+05.02 R3 | 7104110.74 | 3272348.47 |
| | EQNBK 162+97.45 R2 | 7104110.74 | 3272348.47 |
| | EQNAHD 163+05.02 R3 | 7104110.74 | 3272348.47 |
| PC | () 208+59.66 R3 | 7100958.23 | 3269061.16 |
| | Tangential Direction: | S46 | |
| | Tangential Length: | 4554.636 | |
| Element: Circular | | | |
| PC | () 208+59.66 R3 | 7100958.23 | 3269061.16 |
| PI | () 211+61.34 R3 | 7100749.42 | 3268843.41 |
| CC | () | 7104768.77 | 3265406.88 |

| | | | |
|-------------------|----------------------------|---------------------|------------|
| PT | () 214+62.38 R3 | 7100566.77 | 3268603.30 |
| | Radius: | 5279.578 | |
| | Delta: | 06°32'27.330" Right | |
| | Degree of Curvature (Arc): | 01°05'06.843" | |
| | Length: | 602.72 | |
| | Tangent: | 301.688 | |
| | Chord: | 602.393 | |
| | Middle Ordinate: | 8.599 | |
| | External: | 8.613 | |
| | Back Tangent Direction: | S46 | |
| | Back Radial Direction: | N43 | |
| | Chord Direction: | S49 | |
| | Ahead Radial Direction: | N37 | |
| | Ahead Tangent Direction: | S52 | |
| Element: Linear | | | |
| PT | () 214+62.38 R3 | 7100566.77 | 3268603.30 |
| | EQNBK 214+89.86 R3 | 7100550.13 | 3268581.43 |
| | EQNAHD 214+82.89 R4 | 7100550.13 | 3268581.43 |
| PC | () 233+37.24 R4 | 7099427.44 | 3267105.55 |
| | Tangential Direction: | S52 | |
| | Tangential Length: | 1881.84 | |
| Element: Circular | | | |
| PC | () 233+37.24 R4 | 7099427.44 | 3267105.55 |
| PI | () 238+65.27 R4 | 7099107.76 | 3266685.30 |
| CC | () | 7097794.40 | 3268347.79 |
| PT | () 243+70.86 R4 | 7098624.93 | 3266471.57 |
| | Radius: | 2051.83 | |
| | Delta: | 28°51'46.430" Left | |
| | Degree of Curvature (Arc): | 02°47'32.724" | |
| | Length: | 1033.615 | |
| | Tangent: | 528.021 | |
| | Chord: | 1022.72 | |
| | Middle Ordinate: | 64.742 | |
| | External: | 66.852 | |
| | Back Tangent Direction: | S52 | |
| | Back Radial Direction: | N37 | |
| | Chord Direction: | S38 | |
| | Ahead Radial Direction: | N66 | |
| | Ahead Tangent Direction: | S23 | |
| Element: Linear | | | |
| PT | () 243+70.86 R4 | 7098624.93 | 3266471.57 |
| POT | () 244+47.70 R4 | 7098554.66 | 3266440.46 |
| | Tangential Direction: | S23 | |
| | Tangential Length: | 76.845 | |



Glenn R. Yowell, P.E.
4-28-22

**US 59
HORIZONTAL
AND VERTICAL
CONTROL**

SHEET 1 OF 2

| | | |
|------|--------|-----------|
| | | |
| CONT | SECT | HIGHWAY |
| 0218 | 04 | US 59 |
| DIST | COUNTY | SHEET NO. |
| ATL | CASS | 37 |

NOTE: THIS IS A CONSTRUCTION ALIGNMENT AND USE IS INTENDED FOR USE ONLY ON THIS PROJECT.


DATE: 4/27/2022 3:41:08 PM
 FILE: P:\t\dot\project\wiseon\line.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\0218-04\19 Survey control.she

| Vertical Alignment: | | US 59 | |
|-------------------------------|-------------|--------------------|----------|
| Vertical Description: | | Alignment\Baseline | |
| Vertical Style: | | Station | Elevatio |
| Element: Linear | | | |
| POT | 99+99.80 R1 | 333.047 | |
| VPC | 106+05.87 | 315.65 | |
| Tangent Grade: | -0.029 | | |
| Tangent Length: | 606.067 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 106+05.87 | 315.65 | |
| VPI | 108+05.87 | 309.909 | |
| EQNBK | 108+07.16 | | |
| EQNAHD | 108+02.38 | | |
| VPT | 110+01.09 | 308.915 | |
| Length: | 400 | | |
| Entrance Grade: | -0.029 | | |
| Exit Grade: | -0.005 | | |
| $r = 100 * (g2 - g1) / L:$ | 0.593 | | |
| $K = 1 / (g2 - g1):$ | 168.535 | | |
| Middle Ordinate: | 1.187 | | |
| Element: Linear | | | |
| VPT | 110+01.09 | 308.915 | |
| VPC | 121+44.15 | 303.233 | |
| Tangent Grade: | -0.005 | | |
| Tangent Length: | 1143.058 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 121+44.15 | 303.233 | |
| VPI | 125+44.15 | 301.244 | |
| VPT | 129+44.15 | 291.228 | |
| Length: | 800 | | |
| Entrance Grade: | -0.005 | | |
| Exit Grade: | -0.025 | | |
| $r = 100 * (g2 - g1) / L:$ | -0.251 | | |
| $K = 1 / (g2 - g1):$ | 398.625 | | |
| Middle Ordinate: | -2.007 | | |
| Element: Linear | | | |
| VPT | 129+44.15 | 291.228 | |
| VPC | 136+44.89 | 273.682 | |
| Tangent Grade: | -0.025 | | |
| Tangent Length: | 700.746 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 136+44.89 | 273.682 | |
| VPI | 138+44.89 | 268.674 | |
| VPT | 140+44.89 | 267.672 | |
| Length: | 400 | | |
| Entrance Grade: | -0.025 | | |
| Exit Grade: | -0.005 | | |
| $r = 100 * (g2 - g1) / L:$ | 0.501 | | |
| $K = 1 / (g2 - g1):$ | 199.69 | | |
| Middle Ordinate: | 1.002 | | |
| Element: Linear | | | |
| VPT | 140+44.89 | 267.672 | |

| | | | |
|-------------------------------|-----------|---------|--|
| VPC | 158+54.39 | 258.608 | |
| Tangent Grade: | -0.005 | | |
| Tangent Length: | 1809.494 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 158+54.39 | 258.608 | |
| VPI | 162+54.39 | 256.604 | |
| EQNBK | 162+97.45 | | |
| EQNAHD | 163+05.02 | | |
| VPT | 166+61.96 | 256.663 | |
| VLP | 166+39.15 | 256.662 | |
| Length: | 800 | | |
| Entrance Grade: | -0.005 | | |
| Exit Grade: | 0 | | |
| $r = 100 * (g2 - g1) / L:$ | 0.064 | | |
| $K = 1 / (g2 - g1):$ | 1551.59 | | |
| Middle Ordinate: | 0.516 | | |
| Element: Linear | | | |
| VPT | 166+61.96 | 256.663 | |
| VPC | 180+01.40 | 256.86 | |
| Tangent Grade: | 0 | | |
| Tangent Length: | 1339.444 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 180+01.40 | 256.86 | |
| VPI | 182+01.40 | 256.889 | |
| VPT | 184+01.40 | 260.77 | |
| Length: | 400 | | |
| Entrance Grade: | 0 | | |
| Exit Grade: | 0.019 | | |
| $r = 100 * (g2 - g1) / L:$ | 0.481 | | |
| $K = 1 / (g2 - g1):$ | 207.706 | | |
| Middle Ordinate: | 0.963 | | |
| Element: Linear | | | |
| VPT | 184+01.40 | 260.77 | |
| VPC | 184+89.60 | 262.482 | |
| Tangent Grade: | 0.019 | | |
| Tangent Length: | 88.205 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 184+89.60 | 262.482 | |
| VPI | 189+77.70 | 271.954 | |
| VPT | 194+65.80 | 269.513 | |
| VHP | 192+65.80 | 270.013 | |
| Length: | 976.2 | | |
| Entrance Grade: | 0.019 | | |
| Exit Grade: | -0.005 | | |
| $r = 100 * (g2 - g1) / L:$ | -0.25 | | |
| $K = 1 / (g2 - g1):$ | 400 | | |
| Middle Ordinate: | -2.978 | | |
| Element: Linear | | | |
| VPT | 194+65.80 | 269.513 | |
| VPC | 196+04.42 | 268.82 | |
| Tangent Grade: | -0.005 | | |
| Tangent Length: | 138.617 | | |
| Element: Symmetrical Parabola | | | |

| | | | |
|-------------------------------|-----------|---------|--|
| VPC | 196+04.42 | 268.82 | |
| VPI | 200+04.42 | 266.82 | |
| VPT | 204+04.42 | 280.82 | |
| VLP | 197+04.42 | 268.57 | |
| Length: | 800 | | |
| Entrance Grade: | -0.005 | | |
| Exit Grade: | 0.035 | | |
| $r = 100 * (g2 - g1) / L:$ | 0.5 | | |
| $K = 1 / (g2 - g1):$ | 200 | | |
| Middle Ordinate: | 4 | | |
| Element: Linear | | | |
| VPT | 204+04.42 | 280.82 | |
| VPC | 207+67.67 | 293.534 | |
| Tangent Grade: | 0.035 | | |
| Tangent Length: | 363.251 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 207+67.67 | 293.534 | |
| VPI | 211+67.67 | 307.534 | |
| EQNBK | 214+89.86 | | |
| EQNAHD | 214+82.89 | | |
| VPT | 215+60.70 | 311.481 | |
| Length: | 800 | | |
| Entrance Grade: | 0.035 | | |
| Exit Grade: | 0.01 | | |
| $r = 100 * (g2 - g1) / L:$ | -0.314 | | |
| $K = 1 / (g2 - g1):$ | 318.332 | | |
| Middle Ordinate: | -2.513 | | |
| Element: Linear | | | |
| VPT | 215+60.70 | 311.481 | |
| VPC | 231+93.02 | 327.591 | |
| Tangent Grade: | 0.01 | | |
| Tangent Length: | 1632.323 | | |
| Element: Symmetrical Parabola | | | |
| VPC | 231+93.02 | 327.591 | |
| VPI | 233+26.85 | 328.912 | |
| VPT | 234+60.67 | 331.241 | |
| Length: | 267.649 | | |
| Entrance Grade: | 0.01 | | |
| Exit Grade: | 0.017 | | |
| $r = 100 * (g2 - g1) / L:$ | 0.282 | | |
| $K = 1 / (g2 - g1):$ | 355 | | |
| Middle Ordinate: | 0.252 | | |
| Element: Linear | | | |
| VPT | 234+60.67 | 331.241 | |
| POT | 240+56.90 | 341.621 | |
| Tangent Grade: | 0.017 | | |
| Tangent Length: | 596.225 | | |

NOTE: THIS IS A CONSTRUCTION ALIGNMENT PROFILE GRADE LINE AND USE IS INTENDED FOR USE ONLY ON THIS PROJECT.



Glenn R. Yowell, P.E.

4-28-22

**US 59
HORIZONTAL
AND VERTICAL
CONTROL**

SHEET 2 OF 2

| | | |
|---------|------|-----------|
| | | ©2022 |
| CONT | SECT | JOB |
| 0218 | 04 | 119 |
| DIST | | COUNTY |
| ATL | | CASS |
| HIGHWAY | | SHEET NO. |
| US 59 | | 38 |

NOTES


ALL COORDINATES AND BEARINGS ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983 (NAD83) (2011 ADJUSTMENT, 2010 EPOCH), NORTH CENTRAL ZONE (4202), AS ESTABLISHED BY GPS OBSERVATIONS AND BASED ON TXDOT RTN MOUNT POINT NAD83 (2010)-NORTH+VRS+RTCM.

ALL ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) (2011 ADJUSTMENT, 2010 EPOCH) GEOID 12B, AS ESTABLISHED BY GPS OBSERVATIONS AND BASED ON TXDOT RTN MOUNT POINT NAD83 (2010)-NORTH+VRS+RTCM, HOLDING POINTS 0340060 AND 0340065.


THE UNIT OF MEASURE IS THE U.S. SURVEY FOOT.

ALL COORDINATES AND DISTANCES ARE SURFACE VALUES AND CAN BE CONVERTED TO GRID VALUES BY DIVIDING BY THE PROJECT SURFACE ADJUSTMENT FACTOR OF 1.000120.


REVISED: DECEMBER 20, 2021.




FROM THE INTERSECTION OF US 59 AND PROGRESS DRIVE, GO NORTHEAST ALONG US 59 0.10 MILES TO MONUMENT ON SOUTH SIDE OF ROAD.




MONUMENT AT NORTHEAST CORNER OF INTERSECTION OF US 59 AND COUNTY ROAD 3111.




FROM THE INTERSECTION OF US 59 AND FM 2328 N. GO SOUTHWEST ALONG US 59 1.17 MILES TO MONUMENT ON NORTH SIDE OF ROAD.



FROM THE INTERSECTION OF US 59 AND FM 2328 N, GO SOUTHWEST ALONG US 59 1.7 MILES TO MONUMENT ON SOUTH SIDE OF ROAD.



MONUMENT AT NORTHWEST CORNER OF THE INTERSECTION OF US 59 AND COUNTY ROAD 1111.



FROM THE INTERSECTION OF US 59 AND COUNTY ROAD 1111, GO SOUTHWEST ALONG US 59 0.32 MILES TO MONUMENT ON NORTH SIDE OF ROAD.



I HEREBY CERTIFY THAT THIS SURVEY WAS PERFORMED ON THE GROUND UNDER MY SUPERVISION AND THAT THIS PLAT REPRESENTS THE FACTS AS FOUND AT THE TIME OF THE SURVEY.

Darcy B. Weilnau
DARCY B. WEILNAU, DECEMBER 20, 2021
REGISTERED PROFESSIONAL LAND SURVEYOR
TEXAS REGISTRATION NO. 5607

SHEET 1 OF 1




LANDTECH
2525 North Loop West, Suite 300,
Houston, Texas 77008
T: 713-861-7068 F: 713-861-4131
TBPLS Registration No. 10019100

**US 59
SURVEY CONTROL
SHEET**

| | | | | |
|-------------------|--------|-------------------------|-------------|-------------------|
| FED. RD. DIV. NO. | STATE | FEDERAL AID PROJECT NO. | | HIGHWAY NO. |
| 6 | TX | | | US 59 |
| STATE DIST. NO. | COUNTY | CONTROL NO. | SECTION NO. | JOB NO. SHEET NO. |
| 19 | CASS | 0218 | 04 | 119 39 |

DATE: 4/17/2022 7:04:15 PM
 FILE: pw:\txdot\projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\0218-04-19_ROW\WAY DETAILS\1.1



TAPER
 COMMERCIALY AVAILABLE ACP MIXTURE FROM 2" AT
 EDGE OF PAVEMENT TO 0"


**NOTE: THE ASHALT USE FOR PUBLIC ROAD AND DRIVEWAY
 WILL BE PAID UNDER SUPERPAVE ITEM 3077**

**TYPICAL
 PUBLIC ROAD AND
 DRIVEWAY DETAIL**

**NOTE: ROADWAY TO BE PLANED APPROXIMATELY 7" BELOW THE PROPOSED
 PGL PRIOR TO FLEXIBLE PAVEMENT REPAIR ACTIVITIES.**

PROPOSED 2" SMA-D SAC-A PG76-22 (SURFACE)
 AND 5" SP-C PG76-22 WILL BE PLACED ABOVE THE
 PAVEMENT REPAIR LIFTS.
 (SEE MISCELLANEOUS SUMMARIES FOR LOCATIONS)

FLEXIBLE PAVEMENT REPAIR FROM STA. 299+75
 TO STA. 302+50 BOTH TRAVEL LANES 24' WIDTH
 NORTH AND SOUTH BOUND. THE EXACT NUMBER OF
 PAVEMENT REPAIRS AND LIMITS WILL BE DETERMINED
 BY THE ENGINEER. (SEE ROADWAY SUMMARY)




Glenn R. Yowell, P.E.
 4-22-22

**ROADWAY
 DETAILS**

| | | | |
|------|--------|-----|-----------|
| | | | |
| CONT | SECT | JOB | HIGHWAY |
| 0218 | 04 | 119 | US 59 |
| DIST | COUNTY | | SHEET NO. |
| ATL | CASS | | 40 |

DATE: 4/15/2022 9:07:20 AM
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\01 PLANSHEETS\DGNS CREATED\18-04-11\19_MBGF.dgn




**JOHN'S CREEK
 NBI: 190340021804071**

NOTE:
 FLOWABLE FILL TO BE PLACED AROUND BRIDGE APPROACHES FOR EROSION AS DIRECTED BY THE ENGINEER.
 (SEE MBGF, BRIDGE RAIL, AND DELINEATORS SUMMARY)

| MBGF LAYOUT | | | | | | | COMMENTS |
|-------------|-----|-----------------------|--------------------------|---------------------------|--|---|----------|
| LOCATION | SGT | THRIE-BEAM TRANSITION | MBGF (TIM POST) APPROACH | RIPRAP (MOW STRIP) (4 IN) | INSTL DEL ASSM D-SW) SZ (BRF) CTB (BI) | INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI) | |
| | EA | LF | LF | CY | EA | EA | |
| NORTH BOUND | 1 | 1 | 150 | 20 | 3 | 3 | SEE NOTE |
| SOUTH BOUND | 1 | 1 | 150 | 20 | 3 | 3 | SEE NOTE |

NOTE: SEE RAIL C-RAIL-R FOR RAIL DETAILS AND SSTR FOR RAIL STANDARD.










Glenn R. Yowell, P.E.
 4-29-22

MBGF LAYOUTS

NOT TO SCALE

| | | | |
|------|--------|-----------|---------|
| CONT | SECT | JOB | HIGHWAY |
| 0218 | 04 | 119 | US 59 |
| DIST | COUNTY | SHEET NO. | |
| ATL | CASS | 41 | |

DATE: 4/27/2022
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\19040101\19040101.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of any information derived from this standard.



GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
- FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
- SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
- COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
- IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
- MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
- IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
- THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
- A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

| ITEM # | PART NUMBER | DESCRIPTION | QTY |
|--------|----------------|--|-----|
| 1 | BSI-1610060-00 | SOIL ANCHOR - GALVANIZED | 1 |
| 2 | BSI-1610061-00 | GROUND STRUT - GALVANIZED | 1 |
| 3 | BSI-1610062-00 | MAX-TENSION IMPACT HEAD | 1 |
| 4 | BSI-1610063-00 | W6x9 I-BEAM POST 6FT.-GALVANIZED | 1 |
| 5 | BSI-1610064-00 | TSS PANEL - TRAFFIC SIDE SLIDER | 1 |
| 6 | BSI-1610065-00 | ISS PANEL - INNER SIDE SLIDER | 1 |
| 7 | BSI-1610066-00 | TOOTH - GEOMET | 1 |
| 8 | BSI-1610067-00 | RSS PLATE - REAR SIDE SLIDER | 1 |
| 9 | B061058 | CABLE FRICTION PLATE - HEAD UNIT | 1 |
| 10 | BSI-1610069-00 | CABLE ASSEMBLY - MASH X-TENSION | 2 |
| 11 | BSI-1012078-00 | X-LITE LINE POST-GALVANIZED | 8 |
| 12 | B090534 | 8" W-BEAM COMPOSITE-BLOCKOUT XT110 | 8 |
| 13 | BSI-4004386 | 12'-6" W-BEAM GUARD FENCE PANELS 12GA. | 4 |
| 14 | BSI-1102027-00 | X-LITE SQUARE WASHER | 1 |
| 15 | BSI-2001886 | 3/8" X 7" THREAD BOLT HH (GR.5)GEOMET | 1 |
| 16 | BSI-2001885 | 3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET | 4 |
| 17 | 4001115 | 5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL | 48 |
| 18 | 2001840 | 5/8" X 10" GUARD FENCE BOLTS MGAL | 8 |
| 19 | 2001636 | 5/8" WASHER F436 STRUCTURAL MGAL | 2 |
| 20 | 4001116 | 5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL | 59 |
| 21 | BSI-2001888 | 3/8" X 2" ALL THREAD BOLT (GR.5)GEOMET | 1 |
| 22 | BSI-1701063-00 | DELINEATION MOUNTING (BRACKET) | 1 |
| 23 | BSI-2001887 | 1/4" X 3/4" SCREW SD HH 410SS | 7 |
| 24 | 4002051 | GUARDRAIL WASHER RECT AASHTO FWRO3 | 1 |
| 25 | SEE NOTE BELOW | HIGH INTENSITY REFLECTIVE SHEETING | 1 |
| 26 | 4002337 | 8" W-BEAM TIMBER-BLOCKOUT, PDB01B | 8 |
| 27 | BSI-4004431 | 25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA. | 2 |
| 28 | MANMAX Rev-(D) | MAX-TENSION INSTALLATION INSTRUCTIONS | 1 |

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN. ITEM(26) 8" WOOD-BLOCKOUTS ITEM(27) 25' GUARD FENCE PANELS


Texas Department of Transportation
 Design Division Standard

**MAX-TENSION END TERMINAL
 MASH - TL-3
 SGT (11S) 31-18**

| | | | | |
|------------------------|-----------|--------|-----------|---------|
| FILE: sg11s3118.dgn | DN: TxDOT | CK: KM | DW: TxDOT | CK: CL |
| © TxDOT: FEBRUARY 2018 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 04 | 119 | US 59 | |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 43 | |



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.
 DATE: 4/27/2022
 FILE: pw:\txdot\projectwiseonline.com:TXDOTS\Documents\19 - ATL\Design Projects\0218041119\4 - Design\Master Design Files\04 STANDARDS\New Standards\sgt12s3118.dgn



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN THEIR PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

| ITEM | QTY | MAIN SYSTEM COMPONENTS | ITEM NUMBERS |
|----------------|-----|---|--------------|
| A | 1 | MSKT IMPACT HEAD | MS3000 |
| B | 1 | W-BEAM GUARDRAIL END SECTION, 12 Go. | SF1303 |
| C | 1 | POST 1 - TOP (6" X 6" X 1/8" TUBE) | MTPHP1A |
| D | 1 | POST 1 - BOTTOM (6' W6X15) | MTPHP1B |
| E | 1 | POST 2 - ASSEMBLY TOP | UHP2A |
| F | 1 | POST 2 - ASSEMBLY BOTTOM (6' W6X9) | HP2B |
| G | 1 | BEARING PLATE | E750 |
| H | 1 | CABLE ANCHOR BOX | S760 |
| J | 1 | BCT CABLE ANCHOR ASSEMBLY | E770 |
| K | 1 | GROUND STRUT | MS785 |
| L | 6 | W6x9 OR W6x8.5 STEEL POST | P621 |
| M | 6 | COMPOSITE BLOCKOUTS | CBSP-14 |
| N | 1 | W-BEAM MGS RAIL SECTION (9'-4 1/2") | G12025 |
| O | 2 | W-BEAM MGS RAIL SECTION (12'-6") | G1203A |
| P | 6 | WOOD BLOCKOUT 6" X 8" X 14" | P675 |
| Q | 1 | W-BEAM MGS RAIL SECTION (25'-0") | G1209 |
| SMALL HARDWARE | | | |
| a | 2 | 3/16" x 1" HEX BOLT (GRD 5) | B5160104A |
| b | 4 | 3/16" WASHER | W0516 |
| c | 2 | 3/16" HEX NUT | N0516 |
| d | 25 | 3/8" Dia. x 1 1/4" SPLICE BOLT (POST 2) | B580122 |
| e | 2 | 3/8" Dia. x 9" HEX BOLT (GRD A449) | B580904A |
| f | 3 | 3/8" WASHER | W050 |
| g | 33 | 3/8" Dia. H.G.R NUT | N050 |
| h | 1 | 3/4" Dia. x 8 1/2" HEX BOLT (GRD A449) | B340854A |
| j | 1 | 3/4" Dia. HEX NUT | N030 |
| k | 2 | 1 ANCHOR CABLE HEX NUT | N100 |
| l | 2 | 1 ANCHOR CABLE WASHER | W100 |
| m | 8 | 1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER | SB12A |
| n | 8 | 1/2" STRUCTURAL NUTS | N012A |
| o | 8 | 1 1/16" O.D. x 3/8" I.D. STRUCTURAL WASHERS | W012A |
| p | 1 | BEARING PLATE RETAINER TIE | CT-100ST |
| q | 6 | 3/8" x 10" H.G.R. BOLT | B581002 |
| r | 1 | OBJECT MARKER 18" X 18" | E3151 |



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.


Design Division Standard

SINGLE GUARDRAIL TERMINAL MSKT-MASH-TL-3

SGT (12S) 31-18






| | | | | |
|----------------------|------------|--------------|--------------|----------------|
| FILE: sgt12s3118.dgn | DN: TXDOT | CK: KM | DW: VP | CK: CL |
| © TXDOT: APRIL 2018 | CONT: 0218 | SECT: 04 | JOB: 119 | HIGHWAY: US 59 |
| REVISIONS | DIST: ATL | COUNTY: CASS | SHEET NO. 44 | |

DATE: 4/15/2022
 FILE: \\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\0218041194 - DesignMaster Design Files\04 STANDARDS\New Standards\sgt153120.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

| ITEM | QTY | MAIN SYSTEM COMPONENTS | ITEM # |
|----------------|-----|--|----------|
| A | 1 | SGET IMPACT HEAD | SIH1A |
| B | 1 | MODIFIED GUARDRAIL PANEL 12'-6" 12GA | 126SPZGP |
| B2 | 1 | MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA | GP94 |
| C | 2 | STANDARD GUARDRAIL PANEL 12'-6" 12GA | GP126 |
| D | 1 | STANDARD GUARDRAIL PANEL 25'-0" 12GA | GP25 |
| E | 7 | MODIFIED YIELDING I-BEAM POST W6x8.5 | YP6MOD |
| F | 6 | COMPOSITE BLOCKOUT 6" X 8" X 14" | CBO8 |
| G | 6 | WOOD BLOCKOUT 6" X 8" X 14" | WBO8 |
| H | 1 | STRUT 3" X 3" X 80" X 1/4" A36 ANGLE | STR80 |
| I | 1 | FOUNDATION TUBE 6" X 8" X 72" X 3/8" | FNDT6 |
| J | 1 | WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50" | WBRK50 |
| K | 1 | WOOD STRIKE BLOCK | WSBK14 |
| L | 1 | STRIKE PLATE 1/4" A36 BENT PLATE | SPLT8 |
| M | 1 | REINFORCEMENT PLATE 12 GA. GR55 | REPLT17 |
| N | 1 | GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2" | GGR17 |
| O | 1 | BEARING PLATE 8" X 8 5/8" X 5/8" A36 | BPLT8 |
| P | 1 | PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.) | PSLV4 |
| Q | 1 | BCT CABLE 3/4" X 81" LENGTH | CBL81 |
| SMALL HARDWARE | | | |
| o | 1 | 5/8" X 12" GUARDRAIL BOLT 307A HDG | 12GRBLT |
| b | 7 | 5/8" X 10" GUARDRAIL BOLT 307A HDG | 10GRBLT |
| c | 33 | 5/8" X 1 1/4" GR SPlice BOLTS 307A HDG | 1GRBLT |
| d | 3 | 5/8" FLAT WASHER F436 A325 HDG | 58FW436 |
| e | 1 | 5/8" LOCK WASHER HDG | 58LW |
| f | 39 | 5/8" GUARDRAIL HEX NUT HDG | 58HN563 |
| g | 2 | 1/2" X 2" STRUT BOLT A325 HDG | 2BLT |
| h | 6 | 1/2" X 1 1/4" PLATE BOLT A325 HDG | 125BLT |
| i | 16 | 1/2" FLAT WASHER F436 A325 HDG | 12FWF436 |
| j | 8 | 1/2" LOCK WASHER HDG | 12LW |
| k | 8 | 1/2" HEX NUT A563 HDG | 12HN563 |
| l | 4 | 3/8" X 3" HEX LAG SCREW GR5 HDG | 38LS |
| m | 4 | 3/8" FLAT WASHER F436 A325 HDG | 38FW844 |
| n | 2 | 1" FLAT WASHER F436 A325 HDG | 1FWF436 |
| o | 2 | 1" HEX NUT A563HD HDG | 1HN563 |
| p | 1 | 18" TO 24" LONG ZIP TIE RATED 175-200LB | ZPT18 |
| q | 1 | 1 1/2" X 4" SCH-40 PVC PIPE | PSPCR4 |
| r | 1 | RFID CHIP RATED MIL-STD-810F | RFID810F |
| s | 1 | IMPACT HEAD REFLECTIVE SHEETING | RS30M |




NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.


SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15) 31-20

| | | | | |
|---------------------|------------|--------------|--------------|----------------|
| FILE: sgt153120.dgn | DN: TXDOT | CK: KM | DW: VP | CK: VP |
| © TXDOT: APRIL 2020 | CONT: 0218 | SECT: 04 | JOB: 119 | HIGHWAY: US 59 |
| REVISIONS | DIST: ATL | COUNTY: CASS | SHEET NO. 45 | |

DATE: 4/15/2022
 FILE: \\txdot.projectwiseonline.com\txdot\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\04 STANDARDS\New Standards\gf3119.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




TYPICAL POST PLACEMENT



WOOD BLOCK TO ROUND WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**


GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.




ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




BUTTON HEAD BOLT



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.







1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.

| | | | | |
|---|-----------|--------|-----------|--------------------------------|
| | | | | Design Division Standard |
| METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19 | | | | |
| FILE: gf3119.dgn | DN: TxDOT | CK: KM | DW: VP | CK: CGL/AG |
| © TXDOT: NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 46 | |


DATE: 4/15/2022
 FILE: \\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119.4 - DesignMaster Design Files\04 STANDARDS\New Standards\gf31tr+1320.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



| THRIE-BEAM TERMINAL - CURB TABLE | |
|--|--|
| PRECAST CURB FULL LENGTH EQUALS 12'- 2" | |
| THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS. | |
| CURB (1) LENGTH | 5'- 8" |
| CURB (2) LENGTH | 6'- 6" |
| TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7 | |
| CONNECTING PRECAST CURB SECTIONS (1) & (2): | |
| FORM OR CORE | 1" DIA. HOLE 9" LONG INTO EACH CURB END. |
| USE | (1) #5 GR.60 REBAR 18" LONG TO CONNECT BOTH CURBS. |
| SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE *: | |
| FORM OR CORE | (4) 1" DIA. HOLES, SEE PLAN AND ELEVATION VIEWS FOR HOLE LOCATIONS. DRIVE (4) #5 GR.60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB. |
| | FILL HOLES WITH APPROVED GROUT MIXTURE. |

* NOTES: NOT NEEDED FOR CAST-IN-PLACE. SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS. PERCUSSION DRILLING IS NOT PERMITTED WITH: TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.

TYPE II CURB DETAILS



NOTE: OPTIONS FOR TYPE II CURB:
 1. PRECAST
 2. CAST-IN-PLACE

GENERAL NOTES


- CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
- CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5- 3/4" HEIGHT); SEE CURRENT CCGG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE:17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
- CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
- UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
- FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
- THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF (31) STANDARD SHEET.
- THE POST LENGTH SHALL BE MARKED ON ALL 7'- 0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 5/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
- POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
- RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
- BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
- FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
- CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
- WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
- UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TXDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
- REFER TO GF (31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
- THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
- IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION, (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED) (TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED) (STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT.2 FOR ADDITIONAL INFORMATION.

HIGH-SPEED TRANSITION
SHEET 1 OF 2


| | | | |
|---|-----------|--------------------------|--------|
| | | Design Division Standard | |
| METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT GF (31) TR TL3-20 | | | |
| FILE: gf31tr+1320.dgn | DN: TxDOT | CK: KM | DW: VP |
| © TXDOT: NOVEMBER 2020 | CONT | SECT | JOB |
| REVISIONS | 0218 | 04 | 119 |
| DIST | COUNTY | SHEET NO. | |
| ATL | CASS | 47 | |

DATE: 4/15/2022
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\04 STANDARDS\New Standards\gf31tr+1320.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)



ELEVATION VIEW



SECTION D-D



THRIE BEAM TRANSITION BLOCKOUT DETAILS

HIGH-SPEED TRANSITION


SHEET 2 OF 2



METAL BEAM GUARD FENCE
 THRIE-BEAM TRANSITION
 TL-3 MASH COMPLIANT
 GF(31)TR TL3-20


| | | | | |
|-----------------------|-----------|--------|-----------|------------|
| FILE: gf31tr+1320.dgn | DN: TXDOT | CK: KM | DW: KM | CK: CGL/AG |
| ©TXDOT: NOVEMBER 2020 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 48 | |

DATE: 4/15/2022
 FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\19 - ATL\Design Projects\021804119\4 - Design\Master Design Files\04 STANDARDS\New Standards\gf31ms19.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)



SECTION A-A


Typical



MOW STRIP DETAIL


Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
 2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
 3. The leave-out behind the post shall be a minimum of 7".
 4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
 5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
 6. Thickness of the mow strip will be 4".
 7. The limits of payment for reinforced concrete will include leave-outs for the posts.
 8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type I or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)

Curb shown on top of mow strip




CURB OPTION (3)


| | | | |
|---|----------|--------------------------|-----------|
| | | Design Division Standard | |
| METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF(31)MS-19 | | | |
| FILE: gf31ms19.dgn | DN:TXDOT | CK:KM | DW:VP |
| ©TXDOT: NOVEMBER 2019 | CONT | SECT | JOB |
| REVISIONS | 0218 | 04 | 119 |
| | DIST | COUNTY | SHEET NO. |
| | ATL | CASS | 49 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2022 7:59:30 AM
 FILE: C:\Users\stthoma\OneDrive\Documents\STANDARDS US 59\1std014-19.dgn




ROADWAY ELEVATION OF RAIL




INTERMEDIATE WALL JOINT DETAIL


Provide at all interior bents without slab expansion joints.



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT



**SECTION
ELEVATION
TERMINAL CONNECTION DETAILS**



PLAN OF RAIL AT EXPANSION JOINTS

Example showing Slab Expansion Joints without breakbacks.


- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Increase 2" for structures with Overlay.
- ③ Back of rail offset may, with Engineer's approval, be continued to the end of the railing.
- ④ Place 4 additional Bars R(#4) 3'-8" in length inside Bars S(#4) and centered 2'-0" from end of rail when Terminal Connections are required.

SHEET 1 OF 2


| | | | |
|--|-----------|---------------------------------|---------|
| | | Bridge Division Standard | |
| <h2>TRAFFIC RAIL SINGLE SLOPE</h2> | | | |
| <h3>TYPE SSTR</h3> | | | |
| FILE: r1std014-19.dgn | DN: TxDOT | CK: TxDOT | DW: JTR |
| ©TxDOT September 2019 | CONT | SECT | JOB |
| REVISIONS | 0218 | 04 | 119 |
| DIST | COUNTY | SHEET NO. | |
| ATL | CASS | 51 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2022 7:59:58 AM
 FILE: C:\Users\stthoma\Desktop\STANDARDS US 59.r\1std014-19.dgn




ON ABUTMENT WINGWALLS
OR CIP RETAINING WALLS




ON BRIDGE SLAB


SECTIONS THRU RAIL




BARS S (#4)



BARS U (#4)



BARS WU (#4)



OPTIONAL WELDED WIRE REINFORCEMENT (WWR)

- ② Increase 2" for structures with Overlay.
- ⑤ 5/8" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑥ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars must be furnished at the Contractor's expense.
- ⑦ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑧ No longitudinal wires may be within upper bend.
- ⑨ Bend or cut as required to clear drain slots.
- ⑩ Space U(#4) bars at 4" Max when end region of panel length is less than 6'-0" to side slot drain. Space U(#4) bars at 6" Max when end region of panel length is 6'-0" and greater to side slot drain.

CONSTRUCTION NOTES:

This railing may be constructed by the slipform process when approved by the Engineer, with equipment approved by the Engineer. Provide sensor control for both line and grade. Tack welding to provide bracing for slipform operations is acceptable. Welding may be performed at a minimum spacing of 3 ft between the cage and the anchorage. It is permissible to weld to bars U, WU and S at any location on the cage. If increased bracing is needed, provide additional anchorage devices and weld in the upper two thirds of the cage. Paint welded areas on epoxy coated and/or galvanized reinforcing with an organic zinc rich paint in accordance with Item 445 "Galvanizing".
 If rail is slipformed, apply a heavy epoxy bead 1" behind toe of traffic side of rail to concrete deck just prior to slip forming. Provide a 3/8" width x 1/4" tall heavy epoxy bead with Type III, Class C or a Type V epoxy.
 The back of railing must be vertical unless otherwise shown in the plans or approved by the Engineer.


MATERIAL NOTES:

Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.
 Provide Grade 60 reinforcing steel.
 Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized.
 Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars U and WU unless noted otherwise. Deformed WWR (ASTM A1064) may be substituted for Bars R and S, as shown. Combinations of reinforcing steel and WWR or configurations of WWR other than shown are permitted if conditions in the table are satisfied. Provide the same laps as required for reinforcing bars.
 Provide bar laps, where required, as follows:
 Uncoated or galvanized ~ #4 = 1'-7"
 Epoxy coated ~ #4 = 2'-5"

GENERAL NOTES:


This rail has been successfully evaluated by full-scale crash test to meet MASH TL-4 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.
 Do not use this railing on bridges with expansion joints providing more than 5" movement.
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
 Shop drawings will not be required for this rail.
 Average weight of railing with no overlay is 376 pcf.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.



OPTIONAL SIDE SLOT DRAIN DETAIL

Note: Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. Drains should not be placed over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.






SECTION THRU OPTIONAL SIDE SLOT DRAIN

| DESCRIPTION | LONGITUDINAL WIRES | VERTICAL WIRES |
|--------------------------------------|---|---------------------|
| Minimum (Cumulative Total) Wire Area | 1.067 Sq In. | 0.267 Sq In. per Ft |
| Minimum | No. of Wires | Spacing |
| Maximum | 8 | 4" |
| Maximum Wire Size Differential | 10 | 8" |
| | The smaller wire must have an area of 40% or more of the larger wire. | |


| | | | |
|------------------------------------|-----------|---------------------------------|-----------|
| | | Bridge Division Standard | |
| <h2>TRAFFIC RAIL SINGLE SLOPE</h2> | | | |
| <h3>TYPE SSTR</h3> | | | |
| FILE: r1std014-19.dgn | DN: TxDOT | CK: TxDOT | DW: JTR |
| ©TxDOT September 2019 | CONT | SECT | JOB |
| REVISIONS | 0218 | 04 | 119 |
| | DIST | COUNTY | SHEET NO. |
| | ATL | CASS | 52 |

CK: DW: CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES

**ROADWAY
CROSS
SECTIONS**




SHEET 01 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 53 |



CK: DW: CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES


SHEET 06 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 58 |

**ROADWAY
CROSS
SECTIONS**




CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES\$


\$TIMES

**ROADWAY
CROSS
SECTIONS**




SHEET 07 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 59 |



DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 08 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 60 |

CK: DW: CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES\$


SHEET 09 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 61 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW: CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES

**ROADWAY
CROSS
SECTIONS**



SHEET 10 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 62 |



DATE: \$DATE\$
FILE: \$FILES


**ROADWAY
CROSS
SECTIONS**



SHEET 11 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 63 |

CK: DW: CK: DW: CK: DW: CK:




DATE: \$DATE\$
FILE: \$FILES

**ROADWAY
CROSS
SECTIONS**




SHEET 13 OF 43


| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 65 |



**ROADWAY
CROSS
SECTIONS**



DW:
 CK:
 DW:
 CK:



DATE: \$DATE\$
 FILE: \$FILES\$
 \$TIMES\$


ROADWAY CROSS SECTIONS



SHEET 16 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 68 |

CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES


**ROADWAY
CROSS
SECTIONS**



SHEET 17 OF 43


| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 69 |

CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 18 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 70 |

DW: CK: DW: CK: CK:



DATE: \$DATE\$
FILE: \$FILES\$


SHEET 20 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 72 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES


**ROADWAY
CROSS
SECTIONS**



SHEET 21 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 73 |

CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 23 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 75 |


CK: DW: CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES

SHEET 24 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 76 |



CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES


SHEET 25 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 77 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES


SHEET 26 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 78 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES


SHEET 27 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 79 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES\$




SHEET 28 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 80 |

**ROADWAY
CROSS
SECTIONS**




CK: DW: CK: DW: CK: DW: CK:



DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 29 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 81 |

CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 30 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 82 |


DW: CK: DW: CK: CK:




DATE: \$DATE\$
FILE: \$FILES

SHEET 32 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 84 |





DATE: \$DATE\$
FILE: \$FILES\$


SHEET 33 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 85 |

**ROADWAY
CROSS
SECTIONS**




CK: DW: CK: DW: CK:




DATE: \$DATE\$
FILE: \$FILES\$

**ROADWAY
CROSS
SECTIONS**



SHEET 34 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 86 |




DATE: \$DATE\$
FILE: \$FILES


SHEET 35 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 87 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW: CK: DW: CK: DW:



DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 36 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 88 |

CK: DW: CK: DN:



DATE: \$DATE\$
FILE: \$FILES


**ROADWAY
CROSS
SECTIONS**




SHEET 38 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST. | COUNTY | SHEET NO. |
|------|------|-----|---------|-------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 90 |


CK: DW: CK: DW: CK: DW:



STA 214+00.00 R3



STA 213+00.00 R3



STA 212+00.00 R3

DATE: \$DATE\$
FILE: \$FILES\$


**ROADWAY
CROSS
SECTIONS**



SHEET 40 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 92 |

CK: DW: CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES


SHEET 41 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST. | COUNTY | SHEET NO. |
|------|------|-----|---------|-------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 93 |

**ROADWAY
CROSS
SECTIONS**



CK: DW: CK: DW:




DATE: \$DATE\$
FILE: \$FILES

**ROADWAY
CROSS
SECTIONS**



SHEET 42 OF 43

| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 94 |



DATE: \$DATE\$
FILE: \$FILES

**ROADWAY
CROSS
SECTIONS**




SHEET 43 OF 43


| CONT | SECT | JOB | HIGHWAY | DIST | COUNTY | SHEET NO. |
|------|------|-----|---------|------|--------|-----------|
| 0218 | 04 | 119 | US 59 | ATL | CASS | 95 |

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided. This standard is for informational purposes only and does not constitute a contract.




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



RAISED PAVEMENT MARKERS


GENERAL NOTES

1. All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.




POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

| | | | | |
|---------------------|------|--------|-----------|---------|
| FILE: pm2-20.dgn | DN: | CK: | DW: | CK: |
| © TxDOT April 1977 | CONT | SECT | JOB | HIGHWAY |
| 4-92 2-10 REVISIONS | 0218 | 04 | 119 | US 59 |
| 5-00 2-12 | DIST | COUNTY | SHEET NO. | |
| 8-00 6-20 | ATL | CASS | 96 | |




**REFLECTORIZED PROFILE
PATTERN DETAIL
USING REFLECTIVE PROFILE PAVEMENT MARKINGS**



NOTE
Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT reserves the right to modify this standard without notice.

DATE: 4/17/2022 9:58:08 PM
 FILE: \\txdot\project\wisonline.com\TXDOT5\Documents\19 - ATL\Design Projects\19-0218-04\19-0218-04.dgn



LANE REDUCTION

NOTES


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE




TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY



TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A

DETAIL B


Texas Department of Transportation
 Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 20

| | | | | |
|--------------------|------|--------|-----------|---------|
| FILE: pm3-20.dgn | DN: | CK: | DW: | CK: |
| © TxDOT April 1998 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 5-00 2-10 | DIST | COUNTY | SHEET NO. | |
| 8-00 2-12 | ATL | CASS | | 97 |
| 3-03 6-20 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided herein. TxDOT reserves the right to change the information herein without notice.

DATE: 4/17/2022 10:00:48 PM
 FILE: \\txdot.projectwiseonline.com:TXDOT\Documents\19 - ATL\Design Projects\021804\04119\US 59\CPM(1)-14.dgn




CONTRAST LANE LINE DESIGN

* See contrast line dimensions table for width of black line.

| CONTRAST LINE DIMENSIONS | | |
|--------------------------|------------------|-------------|
| White | Black (per side) | Total Width |
| 4" | 1.5" | 7" |
| 6" | 2" | 10" |

- GENERAL NOTES**
1. Contrast and Shadow markings may only be used on concrete pavements.
 2. Contrast and Shadow markings shall not be used on edge lines.
 3. Contrast lane lines shall be permanent prefabricated pavement markings meeting DMS 8240.
 4. Shadow lane line designs shall be a liquid markings system approved by TxDOT.
 5. All raised reflective pavement markers placed in broken lines shall be placed in line with and midway between the white stripes.
 6. See PM(2) for raised reflective pavement markings installation details.



SHADOW LANE LINE DESIGN

| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.













CONTRAST AND SHADOW PAVEMENT MARKINGS


CPM(1) - 14

| | | | | |
|--------------------|-----------|-----------|-----------|-----------|
| FILE: CPM(1)14.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT May 2014 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| | DIST | COUNTY | SHEET NO. | |
| | ATL | CASS | 98 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided.

DATE: 4/17/2022 10:04:24 PM
 FILE: \\txdot.projectwiseonline.com:TXDOT5\Documents\19 - ATL\Design Projects\19-000000-000000-000000.dwg

| POST TYPE AND SUPPORT FOUNDATION DETAILS | | | | TYPE OF BARRIER MOUNTS | | |
|--|---|---|--|--|--|--|
| WING CHANNEL (WC) | FLEXIBLE POSTS (YFLX, WFLX) | | WEDGE ANCHOR SYSTEMS | | GUARD FENCE ATTACHMENT | |
| GND | GND | SRF | WAS | WAP | GF 1 | |
|  <p style="text-align: center;">2'-0" Usual</p> |  <p style="text-align: center;">Reflective material</p> <p style="text-align: center;">Post</p> <p style="text-align: center;">Stub</p> |  <p style="text-align: center;">Reflective material</p> <p style="text-align: center;">Post</p> <p style="text-align: center;">Base</p> |  <p style="text-align: center;">12" Dia.</p> <p style="text-align: center;">27" 30"</p> |  <p style="text-align: center;">3" (Approx.)</p> <p style="text-align: center;">15" 17" 20"</p> <p style="text-align: center;">12" Dia.</p> <p style="text-align: center;">3.5" 17" 30° 2" 1"</p> |  <p style="text-align: center;">Centerline of MBCF rail element</p> |  <p style="text-align: center;">Attached to post or block</p> <p style="text-align: center;">2'-6" Min.</p> <p style="text-align: center;">4" Min.</p> <p style="text-align: center;">4'-0"</p> |
| | EMBEDDED | SURFACE MOUNT | STEEL | PLASTIC | CONCRETE TRAFFIC BARRIER (CTB) | |
| NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499. | | | NOTE 1. Install per manufacturer's recommendations. | | GENERAL NOTES 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane. | |
| NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow. | | | | | | |
| TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS | | CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN | | DELINEATORS AND TYPE 2 OBJECT MARKERS | | |
|  <p style="text-align: center;">4'-0"</p> <p style="text-align: center;">Pavement surface</p> <p style="text-align: center;">Ground Line</p> | |  <p style="text-align: center;">7'-0"</p> <p style="text-align: center;">Pavement surface</p> <p style="text-align: center;">Ground Line</p> | |  <p style="text-align: center;">Approximately 4'-0"</p> <p style="text-align: center;">Pavement surface</p> <p style="text-align: center;">Ground Line</p> <p style="text-align: center;">2'-0" to 8'-0" or in front of object being marked</p> | | |
| NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller) | | NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644. | | NOTE See general notes 1, 2 and 3. | | |



Traffic Safety Division Standard








DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20


| | | | | |
|---------------------|-----------|-----------|-----------|-----------|
| FILE: dom2-20.dgn | DN: TXDOT | CK: TXDOT | DW: TXDOT | CR: TXDOT |
| © TXDOT August 2004 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 10-09 3-15 | DIST | COUNTY | SHEET NO. | |
| 4-10 7-20 | ATL | CASS | 100 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT reserves the right to modify this standard without notice.

DATE: 4/17/2022 10:09:23 PM
 FILE: \\txdot.projectwiseonline.com:TXDOT\Documents\19 - ATL\Design Projects\19041722\19041722.dgn



OBJECT MARKERS SMALLER THAN 3 FT²




NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

| | | | |
|--|-----------|---|-----------|
| | | Traffic Safety Division Standard | |
| DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS D & OM(VIA) -20 | | | |
| FILE: domvia20.dgn | DN: TXDOT | CK: TXDOT | DW: TXDOT |
| © TXDOT December 1989 | CONT | SECT | JOB |
| REVISIONS | 0218 | 04 | 119 |
| 4-92 8-04 | DIST | COUNTY | SHEET NO. |
| 8-95 3-15 | ATL | CASS | 103 |
| 4-98 7-20 | | | |
| 20G | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/28/2022 4:36:59 PM
 FILE: C:\Users\stthoma\Documents\STANDARDS US 59\rs(1)-13 (1).dgn




TYPICAL RUMBLE STRIP PLACEMENT AT EXIT AND ENTRANCE RAMP

GENERAL NOTES


- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
 - Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
 - Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
 - See the table below for determining what options may be used for edgeline rumble strips.
- WHEN INSTALLING MILLED DEPRESSION EDGELINE RUMBLE STRIPS:**
- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
 - Pavement markings can be applied over milled shoulder rumble strips to create an edgeline rumble stripe.
 - Breaks in edgeline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks when installed on conventional highways.
 - Rumble strips shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
 - Consideration should be given to noise levels when edgeline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inches depth of milled rumble strip may be considered in these areas.
 - On roadways with high bicycle activity, consideration should be given before the installation of edgeline rumble strips. Things to consider include size of rumble strips, rumble strip material and location of rumble strips on the shoulder. If the designer determines that gaps are needed in the rumble strips due to bicycle use of the road, then follow the requirement shown in FHWA Technical Advisory T5040.39, or latest version. A detail of the spacing shall be included in the plans.

WHEN INSTALLING RAISED OR PROFILE EDGELINE RUMBLE STRIPS:

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edgeline when used as a rumble strip. The color of the button should match the color of the adjacent edgeline marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Breaks in edgeline rumble strips using raised traffic buttons shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks when installed on conventional highways.
- The minimum distance between the edgeline and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edgelines may substitute for buttons.




PLAN VIEW




**PROFILE VIEW
OPTION 1**

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW

* This distance may vary based on width of shoulder




**PROFILE VIEW
OPTION 2**

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW

* This distance may vary based on width of shoulder




**PROFILE VIEW
OPTION 3**

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW




**PROFILE VIEW
OPTION 4**

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)



**PLAN VIEW
OPTION 5**

RAISED EDGELINE RUMBLE STRIPS



**PLAN VIEW
OPTION 6**

PROFILE EDGELINE MARKINGS

| SHOULDER WIDTH TABLE | | |
|------------------------------|--------------------------------------|---------------------------------|
| EQUAL TO OR LESS THAN 2 FEET | GREATER THAN 2 FEET LESS THAN 4 FEET | EQUAL TO OR GREATER THAN 4 FEET |
| Option 1, 5 OR 6 | Option 1, 2, 3, 5 or 6 | Option 2, 4, 5 OR 6 |



EDGELINE RUMBLE STRIPS ON FREEWAYS AND DIVIDED HIGHWAYS RS(1)-13

| | | | | |
|--------------------|-----------|-----------|-----------|-----------|
| FILE: rs(1)-13.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| ©TxDOT April 2006 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0218 | 04 | 119 | US 59 |
| 2-10 | DIST | COUNTY | | SHEET NO. |
| 10-13 | ATL | CASS | | 104 |

DATE: 4/17/2022 10:32:07 PM
 FILE: \\txdot\projectwise\seon\line.com\TXDOTS\Documents\19 - ATL\Design Projects\0218041919\0218041919.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this drawing to a different format or for the use of this drawing for any purpose other than that intended.

SITE DESCRIPTION

PROJECT LIMITS: FROM: 0.1 MI. S. OF FM 2328N TO: 1.9 MI. S. OF FM 2328S

PROJECT DESCRIPTION: RESURFACE EXISTING 4-LANE ROADWAY

MAJOR SOIL DISTURBING ACTIVITIES: MAINTENANCE ACTIVITIES

TOTAL PROJECT AREA: 0.0 ACRES

TOTAL AREA TO BE DISTURBED: 0.0 ACRES

EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER: THE EXISTING SOIL IS SANDY CLAY

NAME OF RECEIVING WATERS: _____

ANTICIPATED EFFECT OF STORM WATER ON THREATENED AND ENDANGERED SPECIES AND WILDLIFE HABITAT: REFER TO EPIC SHEET

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES: _____

STORM WATER MANAGEMENT: _____

DETAILED SITE MAP OR LAYOUT INDICATING THE FOLLOWING: (SEE SWP3 SITE MAP OR LAYOUT)

- LOCATION(S) OF ALL MAJOR STRUCTURAL CONTROLS EITHER PLANNED OR IN PLACE
- LOCATIONS WHERE TEMPORARY OR PERMANENT STABILIZATION PRACTICES ARE EXPECTED TO BE USED
- LOCATIONS OF CONCRETE VEHICLE WASHOUT AREAS
- LOCATIONS OF PORTABLE SANITARY WASTE UNITS
- LOCATIONS OF TRASH DUMPSTERS

EROSION AND SEDIMENT CONTROLS

SOIL STABILIZATION PRACTICES:

- PERMANENT PLANTING, SODDING, OR SEEDING
- TEMPORARY SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- BUFFER ZONES
- PRESERVATION OF NATURAL RESOURCES
- SLOPE TEXTURING

OTHER: EROSION CONTROL AND STABILIZATION MEASURES MUST BE INITIATED IMMEDIATELY IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY CEASED AND WILL NOT RESUME FOR A PERIOD EXCEEDING 14 CALENDAR DAYS. STABILIZATION MEASURES THAT PROVIDE A PROTECTIVE COVER MUST BE INITIATED IMMEDIATELY IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED.

STRUCTURAL PRACTICES:

- SILT FENCES
- HAY BALES
- ROCK BERMS
- PAVED FLUMES
- CHANNEL LINERS
- SEDIMENT TRAPS
- FILTER DAMS
- CURBS AND GUTTERS
- STORM SEWERS
- ROCK BEDDING AT CONSTRUCTION EXIT
- TIMBER MATTING AT CONSTRUCTION EXIT
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION DIKE AND SWALE COMBINATIONS
- STORM INLET SEDIMENT TRAP
- VELOCITY CONTROL DEVICES
- EROSION CONTROL LOGS

OTHER: _____

MAINTENANCE: ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER. IF MAINTENANCE IS NECESSARY, IT WILL BE DONE PRIOR TO THE NEXT RAIN EVENT IF FEASIBLE. IF MAINTENANCE PRIOR TO THE NEXT ANTICIPATED STORM EVENT IS IMPRACTICABLE, THE REASON SHALL BE DOCUMENTED IN THE SWP3 AND MAINTENANCE MUST BE SCHEDULED AND ACCOMPLISHED AS SOON AS PRACTICABLE. EROSION AND SEDIMENT CONTROLS THAT HAVE BEEN INTENTIONALLY DISABLED, RUN-OVER, REMOVED OR OTHERWISE RENDERED INEFFECTIVE MUST BE REPLACED OR CORRECTED IMMEDIATELY UPON DISCOVERY. REFER TO APPLICABLE TPDES GENERAL PERMIT FOR ADDITIONAL INFORMATION.

INSPECTION: ITEM 506 AN INSPECTION WILL BE PERFORMED EVERY 7 CALENDAR DAYS. A MAINTENANCE REPORT WILL BE MADE PER EACH INSPECTION. BASED ON INSPECTION RESULTS, THE CONTROLS SHALL BE REVISED PER THE INSPECTION REPORT.

OFFSITE VEHICLE TRACKING: THE CONTRACTOR SHALL BE REQUIRED, ON A REGULAR BASIS OR AS MAY BE DIRECTED BY THE ENGINEER, TO DAMPEN HAUL ROADS FOR DUST CONTROL, STABILIZE CONSTRUCTION ENTRANCES, REMOVE EXCESS DIRT FROM THE ROADWAY, AND COVER LOADED HAUL TRUCKS WITH TARPULIN.

CONCRETE TRUCK WASHOUT AREAS: THE CONTRACTOR WILL BE REQUIRED TO CONTAIN WASH WATER FROM CONCRETE TRUCKS AS DETAILED IN THE GENERAL PERMIT. SPECIFIC LOCATIONS MAY BE DETERMINED IN THE FIELD BUT MUST BE SHOWN ON THE SWP3 SITE MAP OR LAYOUT PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES.

WASTE MATERIALS


HAZARDOUS WASTE (INCLUDING SPILL REPORTING): AT A MINIMUM, ANY PRODUCTS IN THE FOLLOWING CATEGORIES ARE CONSIDERED TO BE HAZARDOUS: PAINTS, ACIDS FOR CLEANING MASONRY SURFACES, CLEANING SOLVENTS, ASPHALT PRODUCTS, CHEMICAL ADDITIVES FOR SOIL STABILIZATION, CONCRETE CURING COMPOUNDS AND ADDITIVES OR MOTOR OIL. MATERIALS SHALL BE STORED IN ACCORDANCE WITH APPLICABLE REGULATIONS. IN THE EVENT OF A SPILL WHICH MAY BE HAZARDOUS, IMMEDIATELY REPORT SPILL IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS.

WASTE MATERIALS: THE BURYING OF CONSTRUCTION WASTE MATERIAL ON SITE WILL NOT BE PERMITTED. DISPOSAL OF WASTE MATERIALS SHALL MEET ALL STATE AND LOCAL SOLID WASTE MANAGEMENT REGULATIONS. WASTE MATERIALS STORED ON SITE SHALL BE COLLECTED IN A METAL DUMPSTER WITH A LOCKING, SECURE COVER AND A DRAIN PLUG IN PLACE.

SANITARY WASTE: ALL SANITARY WASTE WILL BE DISPOSED OF IN ACCORDANCE WITH ALL STATE AND LOCAL REGULATIONS. SPECIFIC LOCATIONS OF PORTABLE UNITS MUST BE SHOWN ON THE SWP3 SITE MAP OR LAYOUT.

REMARKS: DISPOSAL AREAS, STOCKPILES, AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT MAY ENTER RECEIVING WATERS. DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WETLAND, WATERBODY OR STREAMBED. CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED BY THE CONTRACTOR IN A MANNER TO MINIMIZE THE RUNOFF OF POLLUTANTS. ALL WATERWAYS SHALL BE CLEARED AS SOON AS PRACTICAL OF TEMPORARY EMBANKMENT, TEMPORARY BRIDGES, MATTING FALSEWORK, PILING, DEBRIS OR OTHER OBSTRUCTIONS PLACED DURING CONSTRUCTION OPERATIONS THAT ARE NOT A PART OF THE FINISHED WORK.

NOTES: THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL SUBCONTRACTORS ARE AWARE OF AND COMPLY WITH ALL COMPONENTS OF THE SWP3.



Glenn R. Yowell, P.E.
4-22-22

Texas Department of Transportation
 © 2022
TxDOT STORM WATER POLLUTION PREVENTION PLAN
 (LESS THAN ONE ACRE)
SWP3

| | | | | | |
|-------------------------|-----------|-----------|-----------|-----------|---------|
| FILE: swp3less1acre.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT | |
| Revisions | | CONT | SECT | JOB | HIGHWAY |
| May 2017 | | 0218 | 04 | 119 | US 59 |
| | | DIST | COUNTY | SHEET NO. | |
| | | ATL | CASS | 106 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. The project is not located within the boundary of an MS4.

2. No Action Required Required Action

Action No.

1. This project is considered a maintenance activity and is exempt from the requirements of TPDES TXR 150000.

Commitment No.

1. Refer to the SWP3 Plan Sheet, BMPs, and Detail. It will address sweeping, chemical storage, sanitary waste, and all other management practices.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# 3

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 1.
- 2.
- 3.
- 4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

| | | |
|--|--|--|
| Erosion | Sedimentation | Post-Construction TSS |
| <input type="checkbox"/> Temporary Vegetation | <input checked="" type="checkbox"/> Silt Fence | <input type="checkbox"/> Vegetative Filter Strips |
| <input type="checkbox"/> Blankets/Matting | <input type="checkbox"/> Rock Berm | <input type="checkbox"/> Retention/Irrigation Systems |
| <input type="checkbox"/> Mulch | <input type="checkbox"/> Triangular Filter Dike | <input type="checkbox"/> Extended Detention Basin |
| <input type="checkbox"/> Sodding | <input type="checkbox"/> Sand Bag Berm | <input type="checkbox"/> Constructed Wetlands |
| <input type="checkbox"/> Interceptor Swale | <input type="checkbox"/> Straw Bale Dike | <input type="checkbox"/> Wet Basin |
| <input type="checkbox"/> Diversion Dike | <input type="checkbox"/> Brush Berms | <input type="checkbox"/> Erosion Control Compost |
| <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Mulch Filter Berm and Socks |
| <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks |
| <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Vegetation Lined Ditches |
| | <input type="checkbox"/> Stone Outlet Sediment Traps | <input type="checkbox"/> Sand Filter Systems |
| | <input type="checkbox"/> Sediment Basins | <input type="checkbox"/> Grassy Swales |

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required Required Action

Action No.

- 1.
- 2.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required Required Action

Action No.

- 1.
- 2.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

| | |
|---|---|
| BMP: Best Management Practice | SPCC: Spill Prevention Control and Countermeasure |
| CGP: Construction General Permit | SWSP: Storm Water Pollution Prevention Plan |
| DSHS: Texas Department of State Health Services | PCN: Pre-Construction Notification |
| FHWA: Federal Highway Administration | PSL: Project Specific Location |
| MOA: Memorandum of Agreement | TCEQ: Texas Commission on Environmental Quality |
| MOU: Memorandum of Understanding | TPDES: Texas Pollutant Discharge Elimination System |
| MS4: Municipal Separate Stormwater Sewer System | TPWD: Texas Parks and Wildlife Department |
| MBTA: Migratory Bird Treaty Act | TxDOT: Texas Department of Transportation |
| NOT: Notice of Termination | T&E: Threatened and Endangered Species |
| NWP: Nationwide Permit | USACE: U.S. Army Corps of Engineers |
| NOI: Notice of Intent | USFWS: U.S. Fish and Wildlife Service |

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required Required Action

Action No.

- 1.
- 2.
- 3.


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required Required Action

Action No.

- 1.
- 2.
- 3.

| | | | |
|---|-----------|---------------------------------|-----------|
|  | | Design Division Standard | |
| ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC | | | |
| FILE: epic.dgn | DN: TxDOT | CK: RG | DW: VP |
| ©TxDOT: February 2015 | CONT | SECT | JOB |
| 12-12-2011 (DS) REVISIONS | 0218 | 04 | 119 |
| 05-07-14 ADDED NOTE SECTION IV. | DIST | COUNTY | SHEET NO. |
| 01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES. | ATL | CASS | 107 |

