

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|-----------|-----------------|
| 1 | TITLE SHEET |
| 2 | INDEX OF SHEETS |

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT


FEDERAL PROJECT: F2022(888)
 HILL, ETC.
LIMITS: AT SH 171/HOUSTON ST, ETC.

CSJ: 0121-02-062, ETC.

FOR THE CONSTRUCTION OF SAFETY CONSISTING OF IMPROVE TRAFFIC SIGNAL

| | | | | | |
|------------------|-------------|-------------|-------------|-------------|-------------|
| BELL COUNTY: | 0231-10-019 | 0836-02-080 | 0836-02-081 | 0836-02-082 | 2304-02-046 |
| | 3534-01-016 | 3534-01-017 | 3534-01-018 | 3534-01-019 | 3534-01-020 |
| | 3534-02-006 | | | | |
| CORYELL COUNTY: | 0184-01-069 | 0724-01-057 | 0724-01-058 | | |
| HILL COUNTY: | 0121-02-062 | | | | |
| MCLENNAN COUNTY: | 0162-01-101 | | | | |

TOTAL LENGTH: 0.03 MILES
158 FT



SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, WILL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL - AID CONSTRUCTION CONTRACTS(FORM FHWA 1273, MAY 2012).

EXCEPTIONS: NONE
 EQUATIONS: NONE
 RR CROSSINGS: NONE
 SCALE: 1" = 20,000'

| DESIGN | FED. RD. DIV. NO. | FEDERAL PROJECT NO. | | HIGHWAY NO. |
|----------|-------------------|---------------------|------------|-------------|
| GRAPHICS | 6 | F2022(888) | | SH 22, ETC. |
| CHECK | STATE | DISTRICT | COUNTY | SHEET NO. |
| CHECK | TEXAS | WACO | HILL, ETC. | 1 |
| CHECK | CONTROL | SECTION | JOB | |
| | 0121 | 02 | 062, ETC. | |



Recommended for Letting **5/31/2022**

DocuSigned by: **Josh Voiles**
 AC8604F84EC2483...
 Area Engineer

Recommended for Letting **06/01/2022**

DocuSigned by: **Uita Yankel, P.E.**
 Director of Transportation Planning & Development

Approved for Letting **6/1/2022**

DocuSigned by: **Stanley Swiatek**
 B69BD796DD564C9...
 District Engineer

\$TIME\$


\$DATE\$

\$FILE\$

NODE

| <u>SHEET NO.</u> | <u>DESCRIPTION</u> |
|--|-------------------------------------|
| <u>GENERAL</u> | |
| 1 | TITLE SHEET |
| 2 | INDEX OF SHEETS |
| 3, 3A-3B | GENERAL NOTES |
| 4, 4A-4B | ESTIMATE & QUANTITY |
| 5 | CONSOLIDATED SUMMARIES |
| 6 | SEQUENCE OF CONSTRUCTION |
| <u>TRAFFIC CONTROL PLAN STANDARDS</u> | |
| 7 - 8 | * WZ(BTS-1)-13 THROUGH WZ(BTS-2)-13 |
| 9 | * WZ(RS)-22 |
| 10 - 11 | * TCP(1-1)-18 THROUGH TCP(1-2)-18 |
| 12 | * TCP(1-4)-18 |
| 13 | * TCP(1-5)-18 |
| 14 - 15 | * TCP(2-1)-18 THROUGH TCP(2-2)-18 |
| 16 | * TCP(2-4)-18 |
| <u>TRAFFIC</u> | |
| 17 | LOCATION MAP-KILLEEN |
| 18 | SIGNAL SUMMARY-KILLEEN |
| 19 | LOCATION MAP-HARKER HEIGHTS |
| 20 | SIGNAL SUMMARY-HARKER HEIGHTS |
| 21 | LOCATION MAP-COPPERAS COVE |
| 22 | SIGNAL SUMMARY-COPPERAS COVE |
| 23 | LOCATION MAP-GATESVILLE |
| 24 | SIGNAL SUMMARY-GATESVILLE |
| 25 | LOCATION MAP-BELLMEAD |
| 26 | SIGNAL SUMMARY-BELLMEAD |
| 27 | LOCATION MAP-HILLSBORO |
| 28 | SIGNAL SUMMARY-HILLSBORO |
| <u>TRAFFIC STANDARDS</u> | |
| 29 | * TS-BP-20 |
| 30 | * RID(1)-20 |
| 31 - 34 | * RIP(1)-19 THRU RIP(4)-19 |
| 35 - 36 | * SP-80(1)-12 & SP-80(2)-12 |
| 37 - 38 | * SMA-80(1)-12 & SMA-80(2)-12 |
| 39 | * LUM-A-12 |
| 40 | * SMD(GEN)-08 |
| 41 | * SMD(SLIP-1)-08 |
| 42 | * SMD(SLIP-2)-08 |
| 43 | * SMD(SLIP-3)-08 |
| 44 | * SMD(TWT)-08 |
| <u>ENVIRONMENTAL DETAILS</u> | |
| 45 | SW3P |
| 46 - 55 | * TA-BMP (WACO DISTRICT STANDARDS) |
| 56 - 57 | * EC(1)-16 THROUGH EC(2)-16 |
| 58 | EPIC |

* THE STANDARD SHEET SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY DIRECT SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



Chris O. Pruitt, P.E. 7/01/2022
 SIGNATURE OF REGISTRANT & DATE



INDEX OF SHEETS

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 2 |

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 0.00 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

Contractor questions on this project are to be emailed to the Waco District at the following address:

Bill Compton - Wacoprebid@txdot.gov, 254-867-2707, 100 S. Loop Dr., Waco, TX
Carmen Chau - Wacoprebid@txdot.gov, 254-867-2794, 100 S. Loop Dr., Waco, TX

All contractor questions will be reviewed by the Area Engineer or Assistant Area Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:
<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

Or Via phone to the following individual:
District Traffic Engineer: Chris Pruitt, P.E., 254-867-2802

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

ITEM 4: SCOPE OF WORK

This project includes the installation of signal backplates with reflective borders, upgrade from 5-section signal heads to 4-section signal heads for implementation of the Flashing Yellow Arrow (FYA), and installation of Battery Backup Units.

Locations being upgraded to FYA will require controller and timing modifications. Coordinate these locations with the TxDOT Signal Supervisor (254-939-3691), at least 10 business days prior to performing work at these locations.

ITEM 5: CONTROL OF THE WORK

Submit all fabrication and shop drawings per TxDOT's online shop drawing submittal system and copy the Area Engineer on the email submittal, unless otherwise directed.

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (254-867-2808) for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (254-867-2808) for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

ITEM 6: CONTROL OF MATERIALS

References to manufacturer's trade name or catalog numbers are for the purpose of identification only and the contractor will be permitted to furnish like materials of other manufacturers provided they are of equal quality and comply with specifications for this project.

ITEM 7: LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

If utilizing private property for waste disposal sites, equipment storage sites or for any other purpose involved with this project, provide to the Engineer written proof of the property owner's approval of the use of this property. This proof may be in the form of a letter or agreement signed by the property owner or other documents acceptable to the Engineer.

Personal vehicles of the contractor's employees will not be parked within the right of way at any time including any section closed to public traffic, unless the vehicle is being utilized for construction procedures. However, the contractor's employees may park on the right of way at the sites where the contractor has his office, equipment and materials storage yard.

Law Enforcement Personnel.

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site. A minimum number of hours is not guaranteed. Payment is for work performed. If the Contractor has a field office, provide an office location for a supervisory officer when event requires a supervising officer. This work is subsidiary.

Cancel law enforcement personnel when the event is canceled. Cancellation, minimums or "show up" fees will not be paid when cancellation is made 12 hours prior to beginning of the event. Failure to cancel within 12 hours will not be cause for payment for cancellation, minimums, or "show up" time. Payment of actual "show up" time to the event site due to cancellation will be on a case-by-case basis at a maximum of 2 hours per officer.

Alterations to the cancellation and maximum rate must be approved by the Engineer or pre-determined by official policy of the officer's governing authority.

ITEM 8: PROSECUTION AND PROGRESS

The 60-Day Delay Start provision is included for material acquisition.

This Project will be a Standard Workweek in accordance with Article 8.3.1.4.

Meet at intervals as agreed upon with the Engineer to notify of planned work for the upcoming 3-week period.

For this project, provide a Bar Chart progress schedule.

ITEM 500: MOBILIZATION

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

ITEM 502: BARRICADES, SIGNS, AND TRAFFIC HANDLING

Barricade and Construction Standard Sheets (BC Sheets) are not required for this project. Installation, maintenance, and removal of the applicable Traffic Control Plan (TCP)/WZ and Typical Advance Signal Project Signing are required and paid under Item 502.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times.

Provide written proposed lane closure information by 1:00 pm on the business day prior to the proposed closures. Do not close lanes when this requirement is not met.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

As approved by the Engineer, provide uniformed off duty police officers and squad cars during lane or ramp closures, nighttime work or other situations that indicate a need for additional traffic

control to protect the traveling public or the construction workforce. Provide documentation such as payroll, log sheets with signatures and badge number, or invoices from the government entity providing the officers for reimbursement. Complete the weekly tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Reimbursement will not be made for coordination fees charged by any party.

The Contractor Responsible Person(s) (CRP) for Work Zone Traffic Controls will inspect and ensure any deficiencies are corrected each and every day throughout the duration of this contract. Any misaligned or damaged traffic control devices will be repaired as soon as practical after deficiency is discovered.

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee(s) available to respond on the project for emergencies and for taking corrective measures within one (1) hour.

Traffic Control Plans with Lane Closures causing backups of 20 minutes or greater in duration will be modified by the Engineer.

Work in other areas of the project is not restricted to this time frame.

ITEM 506: TEMPORARY EROSION, SEDIMENTATION AND ENVIRONMENTAL CONTROLS

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7

ITEM 682: VEHICLE AND PEDESTRAIN SIGNAL HEADS

Locations being upgraded to FYA will require controller and timing modifications. Coordinate these locations with the TxDOT Signal Supervisor (254-939-3691), at least 10 business days prior to performing work at these locations.

The retroreflective backplates are to be purchased new and conform to TxDOT DMS-8300. The use of stick-on retroreflective tape, split backplates, or any other method to avoid removing the signal head assembly will not be allowed.

Cover all signal heads installed, but not in operation, in an approved manner from the time of installation until the signal is placed in operation. This will not be paid for directly, but will be subsidiary to Item 682, "Vehicle and Pedestrian Signal Heads".

Provide and install standard detachable tunnel visors on all signal heads. Provide and install all necessary mounting hardware to insure proper mounting of all signal heads. The mounting hardware and attachments will be new (no reuse of old existing attachment hardware) and the same color as the signal head housings. Use signal heads made of aluminum with 12-inch LED indications and aluminum back plates.

Install signal heads mounted on mast arms, as described on the Traffic Signal Support Structures Details, or as approved. Mount signal heads mounted on end of arm with a 90-degree mast arm elbow fitting as shown on the Structure Assembly on the Traffic Signal Support Structures Details.

Ensure that each signal head has a minimum vertical clearance of 18.5 feet and a maximum vertical clearance of 19 feet between the bottom edge of the signal head and the surface of the roadway.

ITEM 690: MAINTENANCE OF TRAFFIC SIGNALS

All signal head assemblies must be installed in accordance with Item 682, "Vehicle and Pedestrian Signal Heads," as shown on the plans, or as directed.

Item 690-6024 (Removal of Signal Head Assm) refers to the removal of the signal head assembly to allow for installation of the new backplate with reflective border and new signal heads.

ITEM 6058: BATTERY BACK-UP SYSTEM FOR SIGNAL CABINETS

Locations requiring new Battery Back-Up Systems (BBU) must be compatible with the systems that are currently being used by the City of Killeen and on the approved TxDOT Material Producer List. The City currently uses Myers Power Products.

ITEM 6185: TRUCK MOUNTED ATTENUATORS

The total number of truck mounted attenuators (TMA) required when utilizing the traffic control standards are shown in the tables below.

| TCP 1 Series | Scenario | | Required TMA | |
|--------------------------------|----------|---|--------------|---|
| (1-1)-18 / (1-2)-18 | | | 1 | |
| (1-3)-18 | A | B | 1 | 2 |
| (1-4)-18 / (1-5)-18 / (1-6)-18 | | | 1 | |

| TCP 2 Series | Scenario | | Required TMA | |
|--|----------|---|--------------|---|
| (2-1)-18 / (2-2)-18 / (2-4)-18 / (2-5)-18 / (2-6)-18 | All | | 1 | |
| (2-3)-18 | A | B | 1 | 2 |

Shadow vehicles equipped for truck mounted attenuators (TMA) for stationary operations will be paid for by the day and must be available for use at any time as determined by the Engineer.

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project for those times per plan requirements. Additional TMAs used that are not specified in the plans for which the contractor expects compensation will require prior approval from the Engineer.

THIS PAGE IS INTENTIONALLY LEFT BLANK



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0121-02-062

DISTRICT Waco

COUNTY Bell, Coryell, Hill, McLennan

HIGHWAY BU 190F, FM 116, FM 2410, FM 3470, SH 195, SH 201, SH 22, SH 36, US 84

| CONTROL SECTION JOB | | | | 0121-02-062 | | 0162-01-101 | | 0184-01-069 | | 0231-10-019 | | 0724-01-057 | | 0724-01-058 | |
|---------------------|-----------|---|------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|
| PROJECT ID | | | | A00183531 | | A00183534 | | A00183532 | | A00183556 | | A00183533 | | A00183535 | |
| COUNTY | | | | Hill | | McLennan | | Coryell | | Bell | | Coryell | | Coryell | |
| HIGHWAY | | | | SH 22 | | US 84 | | SH 36 | | BU 190F | | FM 116 | | FM 116 | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL |
| | 500-6001 | MOBILIZATION | LS | 0.070 | | 0.062 | | 0.062 | | 0.062 | | 0.062 | | 0.062 | |
| | 502-6001 | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO | 2.000 | | | | | | | | | | | |
| | 610-6102 | REPLACE LUMINAIRE W/LED (250W EQ) | EA | | | | | | | | | | | | |
| | 636-6007 | REPLACE EXISTING ALUMINUM SIGNS(TY A) | SF | | | 21.000 | | | | | | 10.500 | | 21.000 | |
| | 682-6001 | VEH SIG SEC (12")LED(GRN) | EA | 6.000 | | 12.000 | | 10.000 | | 8.000 | | 6.000 | | 6.000 | |
| | 682-6002 | VEH SIG SEC (12")LED(GRN ARW) | EA | 2.000 | | 2.000 | | 4.000 | | 2.000 | | 1.000 | | 2.000 | |
| | 682-6003 | VEH SIG SEC (12")LED(YEL) | EA | 6.000 | | 12.000 | | 12.000 | | 8.000 | | 6.000 | | 6.000 | |
| | 682-6004 | VEH SIG SEC (12")LED(YEL ARW) | EA | 4.000 | | 4.000 | | 4.000 | | 4.000 | | 2.000 | | 4.000 | |
| | 682-6005 | VEH SIG SEC (12")LED(RED) | EA | 6.000 | | 12.000 | | 10.000 | | 8.000 | | 6.000 | | 6.000 | |
| | 682-6006 | VEH SIG SEC (12")LED(RED ARW) | EA | 2.000 | | 2.000 | | 4.000 | | 2.000 | | 1.000 | | 2.000 | |
| | 682-6051 | BACKPLATE W/REFL BRDR(3 SEC)ALUM | EA | 6.000 | | 12.000 | | 12.000 | | 8.000 | | 6.000 | | 6.000 | |
| | 682-6052 | BACKPLATE W/REFL BRDR(4 SEC)ALUM | EA | 2.000 | | 2.000 | | 2.000 | | 2.000 | | 1.000 | | 2.000 | |
| | 684-6012 | TRF SIG CBL (TY A)(12 AWG)(7 CONDR) | LF | | | 50.000 | | | | | | 50.000 | | 50.000 | |
| | 690-6024 | REMOVAL OF SIGNAL HEAD ASSM | EA | 8.000 | | 14.000 | | 14.000 | | 10.000 | | 7.000 | | 8.000 | |
| | 6058-6001 | BBU SYSTEM (EXTERNAL BATT CABINET) | EA | | | 1.000 | | | | 1.000 | | 1.000 | | 1.000 | |
| | 6185-6002 | TMA (STATIONARY) | DAY | 2.000 | | 2.000 | | 2.000 | | 2.000 | | 2.000 | | 2.000 | |
| 18 | | SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | 1.000 | | | | | | | | | | | |
| | | LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | 1.000 | | | | | | | | | | | |



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0121-02-062

DISTRICT Waco

COUNTY Bell, Coryell, Hill, McLennan

HIGHWAY BU 190F, FM 116, FM 2410, FM 3470, SH 195, SH 201, SH 22, SH 36, US 84

| CONTROL SECTION JOB | | | | 0836-02-080 | | 0836-02-081 | | 0836-02-082 | | 2304-02-046 | | 3534-01-016 | | 3534-01-017 | |
|---------------------|-----------|---|------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|
| PROJECT ID | | | | A00183537 | | A00183539 | | A00183540 | | A00183536 | | A00183543 | | A00183544 | |
| COUNTY | | | | Bell | | Bell | | Bell | | Bell | | Bell | | Bell | |
| HIGHWAY | | | | SH 195 | | SH 195 | | SH 195 | | FM 2410 | | FM 3470 | | FM 3470 | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL |
| | 500-6001 | MOBILIZATION | LS | 0.062 | | 0.062 | | 0.062 | | 0.062 | | 0.062 | | 0.062 | |
| | 502-6001 | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO | | | | | | | | | | | | |
| | 610-6102 | REPLACE LUMINAIRE W/LED (250W EQ) | EA | 4.000 | | | | 4.000 | | | | 2.000 | | 2.000 | |
| | 636-6007 | REPLACE EXISTING ALUMINUM SIGNS(TY A) | SF | 21.000 | | | | 21.000 | | | | 21.000 | | | |
| | 682-6001 | VEH SIG SEC (12")LED(GRN) | EA | 8.000 | | 8.000 | | 12.000 | | 8.000 | | 8.000 | | 8.000 | |
| | 682-6002 | VEH SIG SEC (12")LED(GRN ARW) | EA | 4.000 | | 2.000 | | 2.000 | | 4.000 | | 4.000 | | 4.000 | |
| | 682-6003 | VEH SIG SEC (12")LED(YEL) | EA | 8.000 | | 8.000 | | 12.000 | | 8.000 | | 8.000 | | 8.000 | |
| | 682-6004 | VEH SIG SEC (12")LED(YEL ARW) | EA | 8.000 | | 4.000 | | 4.000 | | 8.000 | | 8.000 | | 8.000 | |
| | 682-6005 | VEH SIG SEC (12")LED(RED) | EA | 8.000 | | 8.000 | | 12.000 | | 8.000 | | 8.000 | | 8.000 | |
| | 682-6006 | VEH SIG SEC (12")LED(RED ARW) | EA | 4.000 | | 2.000 | | 2.000 | | 4.000 | | 4.000 | | 4.000 | |
| | 682-6051 | BACKPLATE W/REFL BRDR(3 SEC)ALUM | EA | 8.000 | | 8.000 | | 12.000 | | 8.000 | | 8.000 | | 8.000 | |
| | 682-6052 | BACKPLATE W/REFL BRDR(4 SEC)ALUM | EA | 4.000 | | 2.000 | | 2.000 | | 4.000 | | 4.000 | | 4.000 | |
| | 684-6012 | TRF SIG CBL (TY A)(12 AWG)(7 CONDR) | LF | 50.000 | | | | 50.000 | | | | 50.000 | | | |
| | 690-6024 | REMOVAL OF SIGNAL HEAD ASSM | EA | 12.000 | | 10.000 | | 14.000 | | 12.000 | | 12.000 | | 12.000 | |
| | 6058-6001 | BBU SYSTEM (EXTERNAL BATT CABINET) | EA | 1.000 | | 1.000 | | 1.000 | | 1.000 | | 1.000 | | 1.000 | |
| | 6185-6002 | TMA (STATIONARY) | DAY | 2.000 | | 2.000 | | 2.000 | | 2.000 | | 2.000 | | 2.000 | |
| 18 | | SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | | | | | | | | | | | | |
| | | LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | | | | | | | | | | | | |



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0121-02-062

DISTRICT Waco

COUNTY Bell, Coryell, Hill, McLennan

HIGHWAY BU 190F, FM 116, FM 2410, FM 3470, SH 195, SH 201, SH 22, SH 36, US 84

| CONTROL SECTION JOB | | | | 3534-01-018 | | 3534-01-019 | | 3534-01-020 | | 3534-02-006 | | TOTAL EST. | TOTAL FINAL |
|---------------------|-----------|---|------|-------------|-------|-------------|-------|-------------|-------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00183551 | | A00183552 | | A00183553 | | A00183555 | | | |
| COUNTY | | | | Bell | | Bell | | Bell | | Bell | | | |
| HIGHWAY | | | | FM 3470 | | FM 3470 | | SH 201 | | SH 201 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | EST. | FINAL | EST. | FINAL | EST. | FINAL | | |
| | 500-6001 | MOBILIZATION | LS | 0.062 | | 0.062 | | 0.062 | | 0.062 | | 1.000 | |
| | 502-6001 | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO | | | | | | | | | 2.000 | |
| | 610-6102 | REPLACE LUMINAIRE W/LED (250W EQ) | EA | 2.000 | | 2.000 | | 1.000 | | 1.000 | | 18.000 | |
| | 636-6007 | REPLACE EXISTING ALUMINUM SIGNS(TY A) | SF | 21.000 | | | | | | | | 136.500 | |
| | 682-6001 | VEH SIG SEC (12")LED(GRN) | EA | 8.000 | | 8.000 | | 4.000 | | 4.000 | | 124.000 | |
| | 682-6002 | VEH SIG SEC (12")LED(GRN ARW) | EA | 4.000 | | 4.000 | | 2.000 | | 2.000 | | 45.000 | |
| | 682-6003 | VEH SIG SEC (12")LED(YEL) | EA | 8.000 | | 8.000 | | 4.000 | | 4.000 | | 126.000 | |
| | 682-6004 | VEH SIG SEC (12")LED(YEL ARW) | EA | 8.000 | | 8.000 | | 4.000 | | 4.000 | | 86.000 | |
| | 682-6005 | VEH SIG SEC (12")LED(RED) | EA | 8.000 | | 8.000 | | 4.000 | | 4.000 | | 124.000 | |
| | 682-6006 | VEH SIG SEC (12")LED(RED ARW) | EA | 4.000 | | 4.000 | | 2.000 | | 2.000 | | 45.000 | |
| | 682-6051 | BACKPLATE W/REFL BRDR(3 SEC)ALUM | EA | 8.000 | | 8.000 | | 4.000 | | 4.000 | | 126.000 | |
| | 682-6052 | BACKPLATE W/REFL BRDR(4 SEC)ALUM | EA | 4.000 | | 4.000 | | 2.000 | | 2.000 | | 43.000 | |
| | 684-6012 | TRF SIG CBL (TY A)(12 AWG)(7 CONDR) | LF | 50.000 | | | | | | | | 350.000 | |
| | 690-6024 | REMOVAL OF SIGNAL HEAD ASSM | EA | 12.000 | | 12.000 | | 6.000 | | 6.000 | | 169.000 | |
| | 6058-6001 | BBU SYSTEM (EXTERNAL BATT CABINET) | EA | 1.000 | | | | 1.000 | | | | 11.000 | |
| | 6185-6002 | TMA (STATIONARY) | DAY | 2.000 | | 2.000 | | 2.000 | | 2.000 | | 32.000 | |
| 18 | | SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | | | | | | | | | 1.000 | |
| | | LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | | | | | | | | | 1.000 | |

\$DATE\$ \$TIME\$

\$FILES\$

NODE

| SUMMARY OF TRAFFIC ITEMS | | | | | | | | | | | | | |
|--------------------------|-----------------------------------|--|----------------------------|--------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|------------------------------------|------------------------------------|---------------------------------------|-----------------------------|------------------------------------|
| CSJ | 610 | 636 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 684 | 690 | 6058 |
| | 6102 | 6007 | 6001 | 6002 | 6003 | 6004 | 6005 | 6006 | 6051 | 6052 | 6012 | 6024 | 6001 |
| | REPLACE LUMINAIRE W/LED (250W EQ) | REPLACE EXISTING ALUMINUM SIGNS (TY A) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | TRF SIG CBL (TY A) (12 AWG) (7 CONDR) | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) |
| | EA | SF | EA | EA | EA | EA | EA | EA | EA | EA | LF | EA | EA |
| 0121-02-062 | | | 6 | 2 | 6 | 4 | 6 | 2 | 6 | 2 | | 8 | |
| ** 0162-01-101 | | 21 | 12 | 2 | 12 | 4 | 12 | 2 | 12 | 2 | 50 | 14 | 1 |
| 0184-01-069 | | | 10 | 4 | 12 | 4 | 10 | 4 | 12 | 2 | | 14 | |
| 0231-10-019 | | | 8 | 2 | 8 | 4 | 8 | 2 | 8 | 2 | | 10 | 1 |
| ** 0724-01-057 | | 10.5 | 6 | 1 | 6 | 2 | 6 | 1 | 6 | 1 | 50 | 7 | 1 |
| ** 0724-01-058 | | 21 | 6 | 2 | 6 | 4 | 6 | 2 | 6 | 2 | 50 | 8 | 1 |
| 0836-02-080 | 4 | 21 | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 50 | 12 | 1 |
| * ** 0836-02-081 | | | 8 | 2 | 8 | 4 | 8 | 2 | 8 | 2 | | 10 | 1 |
| ** 0836-02-082 | 4 | 21 | 12 | 2 | 12 | 4 | 12 | 2 | 12 | 2 | 50 | 14 | 1 |
| 2304-02-046 | | | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | | 12 | 1 |
| ** 3534-01-016 | 2 | 21 | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 50 | 12 | 1 |
| 3534-01-017 | 2 | | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | | 12 | |
| ** 3534-01-018 | 2 | 21 | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 50 | 12 | 1 |
| 3534-01-019 | 2 | | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | | 12 | |
| 3534-01-020 | 1 | | 4 | 2 | 4 | 4 | 4 | 2 | 4 | 2 | | 6 | 1 |
| 3534-02-006 | 1 | | 4 | 2 | 4 | 4 | 4 | 2 | 4 | 2 | | 6 | |
| PROJECT TOTALS | 18 | 136.5 | 124 | 45 | 126 | 86 | 124 | 45 | 126 | 43 | 350 | 169 | 11 |


NOTE:

- * SPAN WIRE
- ** CONVERT TO FLASHING YELLOW ARROW

© 2022
 Texas Department of Transportation

CONSOLIDATED SUMMARIES

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 5 |




VICINITY MAP

NOTES:

1. ALL TRAFFIC CONTROL DEVICES WILL CONFORM WITH THE TEXAS "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" (TMUTCD), AND WILL BE MAINTAINED AS DIRECTED. ADDITIONAL GUIDELINES FOR TRAFFIC CONTROL DEVICES MAY BE FOUND IN THE TMUTCD.
2. FOR CHANNELING DEVICE PLACEMENT AND SPACING FOR ALL PHASES, REFER TO THE TCP STANDARDS.
3. SIGNS G20-1T WITH PLAQUE OR G20-5T, G20-6, G20-2a, G20-2b, CW20-ID, R20-3, R20-5, G20-9T AND R20-5 PLAQUE WILL BE REQUIRED AT PROJECT LIMITS.
4. CW20-ID AND G20-2a WILL BE REQUIRED AT ALL CROSSROADS.
5. G20-1a WILL BE REQUIRED AT ALL MAJOR CROSSROADS.

GENERAL

- A. INSTALL ALL SIGNS, BARRICADES AND TRAFFIC CONTROL DEVICES AS SHOWN AND IN ACCORDANCE WITH THE STANDARD BC SHEETS AND AS DIRECTED.
- B. ADDITIONAL SIGNS, BARRICADES OR TRAFFIC CONTROL DEVICES OTHER THAN THOSE SPECIFIED MAY BE REQUIRED FOR THE SAFE MOVEMENT OF TRAFFIC THROUGH THE PROJECT. PAYMENT FOR ALL SUCH SIGNS, BARRICADES OR TRAFFIC CONTROL DEVICES WILL BE CONSIDERED SUBSIDIARY TO THE ITEM "BARRICADES, SIGNS AND TRAFFIC HANDLING".
- C. WORK SITES SHOULD BE CAREFULLY MONITORED TO ENSURE THAT TRAFFIC CONTROL MEASURES ARE OPERATING EFFECTIVELY AND THAT ALL DEVICES USED ARE CLEARLY VISIBLE, CLEAN AND IN GOOD REPAIR.
- D. THE CONTRACTOR WILL PROVIDE SAFE ACCESS TO AND FROM ALL PRIVATE PROPERTY AT ALL TIMES AND IN ALL WEATHER CONDITIONS.
- E. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK PRIOR TO THE BEGINNING OF CONSTRUCTION WHICH GENERALLY CONFORMS TO THE SEQUENCE SHOWN ON THE TCP SEQUENCE OF OPERATION BELOW.
- F. COMPLETE ALL WORK ON PROJECT AS SHOWN ON THE VARIOUS PLAN SHEETS AND IN COMPLIANCE WITH THE GENERAL NOTES OF THIS CONTRACT.
- G. ANY REQUEST TO ALTER THE SEQUENCE OF OPERATION OR TRAFFIC CONTROL PLAN WILL BE SUBMITTED TO THE ENGINEER FOR WRITTEN APPROVAL.




PAV EDGE DROP-OFF DETAIL

1. LESS THAN 2 INCHES: CW 8-II SIGNS ARE REQUIRED.
2. GREATER THAN 2 INCHES BUT LESS THAN 24 INCHES: VERTICAL PANELS AND EITHER CW 8-9a OR CW 8-II SIGNS ARE REQUIRED.
3. GREATER THAN 24 INCHES: POSITIVE BARRIER REQUIRED.
4. THE SAFETY SLOPE WILL BE CONSTRUCTED WITH AN ALL-WEATHER MATERIAL SUCH AS RAP, WHICH IS CLEAN AND FREE OF DEBRIS AND LARGE ROCKS.

SEQUENCE OF CONSTRUCTION

- A. THIS PROJECT CONSISTS OF VARIOUS WORK AREAS AS DEFINED BY VARIOUS CSJ:
 1. (CSJ: 0121-02-062, ETC)
(LIMITS: VARIOUS LOCATIONS IN BELL, CORYELL, HILL AND MCLENNAN COUNTY)
- B. THE CONTRACTOR MAY WORK IN MORE THAN ONE AREA AT A TIME, BUT THE WORK MUST PROGRESS AT EACH LOCATION.
- C. FINISH PROPOSED WORK IN EACH WORK AREA BEFORE PROCEEDING TO PERFORM WORK IN ANOTHER WORK AREA.
- D. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK TO THE AREA ENGINEER PRIOR TO THE BEGINNING OF CONSTRUCTION, WHICH GENERALLY CONFORMS TO THE FOLLOWING SEQUENCE:
 1. ORDER ALL EQUIPMENT FOR ALL LOCATIONS.
 2. PROVIDE AND INSTALL REQUIRED TRAFFIC CONTROL.
 3. COMPLETE TRAFFIC SIGNAL IMPROVEMENTS.
 4. COMPLETE ALL OTHER WORK AS DIRECTED.
 5. FINAL CLEAN UP.




Chris O. Pruitt, P.E. 7/01/2022
SIGNATURE OF REGISTRANT & DATE




SEQUENCE OF CONSTRUCTION

| | | | | | |
|--------------|-------------------|------|------------|-----------|-------------|
| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 6 |


DATE: 5/24/2022 11:05:07 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal\Standard\WZ (BTS) - 13.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units.



NEAR SIDE LANE CLOSURE
SHORT DURATION OR SHORT TERM STATIONARY



FAR SIDE RIGHT LANE CLOSURE
SHORT DURATION OR SHORT TERM STATIONARY




FAR SIDE LEFT LANE CLOSURE
SHORT DURATION OR SHORT TERM STATIONARY

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |


| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.



OPERATIONS IN THE INTERSECTION
SHORT DURATION



GENERAL NOTES

- The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.
- Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- High level warning devices (flag trees) may be used at corners of the vehicle.
- When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P) signs may be implemented when approved by the engineer.
- For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.
- Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.


TRAFFIC SIGNAL WORK TYPICAL DETAILS

WZ (BTS-1) - 13

| | | | | |
|--------------------|-----------|------------|-----------|-------------|
| FILE: wzbts-13.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT April 1992 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 2-98 10-99 7-13 | DIST | COUNTY | SHEET NO. | |
| 4-98 3-03 | WACO | HILL, ETC. | 7 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project. This standard is based on the current Texas Standard Specifications for Highway Construction (TSSD) and the Texas Standard Specifications for Traffic Control Devices (TSTD).

DATE: 5/24/2022 11:05:08 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal\Standard\WZ (BTS) - 13.dgn



TYPICAL ADVANCE SIGNAL PROJECT SIGNING
 FOR LONG TERM and INTERMEDIATE-TERM STATIONARY WORK OPERATIONS

- NOTES**
1. Project signing as shown shall be in place whenever signal contract work is in progress.
 2. For closely adjoining projects, advance signing may not be required in advance of each intersection, but only in advance of the intersections at the project limits. Actual locations will be as directed by the Engineer.
 3. Advance signs shall be removed when signal construction operations are no longer under way, as directed by the Engineer.
 4. Warning sign spacing shown is typical for both directions.
 5. See the Table on sheet 1 of 2 for Typical warning sign spacing.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Signs shall be installed and maintained in a straight and plumb condition.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. Nails shall NOT be used to attach signs to any support.
5. All signs shall be installed in accordance with the plans or as directed by the Engineer.
6. The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).
7. The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.
8. Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as directed by the Engineer.
9. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".
10. Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

DURATION OF WORK

1. Work zone durations are defined in Part 6, Section 60.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

SIGN MOUNTING HEIGHT

1. Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.
2. Sign height of Short-term/Short Duration warning signs shall be as shown on Figure 6F-2 of the TMUTCD.
3. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.
2. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs.
3. Duct tape or other adhesive material shall NOT be affixed to a sign face.
4. Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

SIGN SUPPORT WEIGHTS

1. Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber, such as tire inner tubes, shall not be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

LEGEND




| | |
|--|----------------------|
| | Sign |
| | Channelizing Devices |
| | Type 3 Barricade |

DEPARTMENTAL MATERIAL SPECIFICATIONS

| | |
|-----------------------------------|----------|
| SIGN FACE MATERIALS | DMS-8300 |
| FLEXIBLE ROLL-UP REFLECTIVE SIGNS | DMS-8310 |

| COLOR | USAGE | SHEETING MATERIAL |
|--------|------------------|---|
| ORANGE | BACKGROUND | TYPE B _{FL} OR TYPE C _{FL} SHEETING |
| WHITE | BACKGROUND | TYPE A SHEETING |
| BLACK | LEGEND & BORDERS | ACRYLIC NON-REFLECTIVE SHEETING |

Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:
http://www.txdot.gov/txdot_library/publications/construction.htm



PEDESTRIAN CONTROL

1. Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.
2. "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation.
3. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic substrates, they may be mounted on top of a plastic drum at or near the location shown.
4. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9) and manufacturer's recommendations.
5. Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.
6. Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.
7. The width of existing sidewalk should be maintained if practical.
8. Pavement markings for mid-block crosswalks shall be paid for under the appropriate bid items.
9. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.

SHEET 2 OF 2

Texas Department of Transportation Traffic Operations Division Standard

TRAFFIC SIGNAL WORK BARRICADES AND SIGNS


WZ (BTS-2) - 13

| | | | | | | | | | |
|-----------|--------------|-------|-------|-----------------------|-----------|-----|-------|-----|-------|
| FILE: | wzBts-13.dgn | DN: | TxDOT | CR: | TxDOT | DW: | TxDOT | CK: | TxDOT |
| © TxDOT | April 1992 | CONT: | SECT: | JOB: | HIGHWAY: | | | | |
| REVISIONS | | 0121 | 02 | 062, ETC. SH 22, ETC. | | | | | |
| 2-98 | 10-99 | 7-13 | DIST: | COUNTY: | SHEET NO. | | | | |
| 4-98 | 3-03 | | WACO | HILL, ETC. | 8 | | | | |


DATE: 5/24/2022 11:05:09 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal Data\Phis\Standard\WZ (RS) -22-
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units.

Warning sign and rumble strip sequence in opposite direction is same as below.

| Flagger to Flagger (Length of Work Area) | ADT | # of Rumble Strip Arrays |
|--|---------|--------------------------|
| 1/8 Mile | < 4,500 | 1 |
| | ≥ 4,500 | 2 |
| 1/4 Mile | < 3,500 | 1 |
| | ≥ 3,500 | 2 |
| 1/2 Mile | < 2,600 | 1 |
| | ≥ 2,600 | 2 |
| 1 Mile | < 1,600 | 1 |
| | ≥ 1,600 | 2 |
| > 1 Mile | N/A | 2 |



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

| Speed | Approximate distance between strips in an array |
|---------------------|---|
| ≤ 40 MPH | 10' |
| > 40 MPH & ≤ 55 MPH | 15' |
| = 60 MPH | 20' |
| ≥ 65 MPH | * 35' + |

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Panel | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | L = WS/60 | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | ✓ | ✓ | | |

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.




Texas Department of Transportation Traffic Safety Division Standard

TEMPORARY RUMBLE STRIPS

WZ (RS) - 22

| | | | | |
|-----------------------|-----------|------------|-----------|-------------|
| FILE: wzrs22.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT November 2012 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 2-14 1-22 | DIST | COUNTY | SHEET NO. | |
| 4-16 | WACO | HILL, ETC. | 9 | |

DATE: 5/24/2022 11:05:09 AM
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data\Phase\Standard\TCP (1-1)-18.dgn
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other file formats or for any errors in the original standard.



LEGEND

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | ✓ | ✓ | | |

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK



TCP (1-1) - 18

| | | | | |
|-----------------------|------|------------|-----------|-------------|
| FILE: tcp1-1-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 2-94 4-98 | DIST | COUNTY | SHEET NO. | |
| 8-95 2-12 | WACO | HILL, ETC. | 10 | |
| 1-97 2-18 | | | | |

DATE: 5/24/2022 11:05:10 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal\Standards\TCP (1-2)-1-

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units.

Warning Sign Sequence in Opposite Direction Same as Below



LEGEND

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * * | Formula L = WS ² / 60 | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" | Stopping Sight Distance |
|---------------------|-------------------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|-------------------------|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | | |
| 30 | | 150' | 165' | 180' | 30' | 60' | 120' | 90' | 200' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' | 250' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' | 305' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' | 360' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' | 425' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' | 495' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' | 570' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' | 645' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' | 730' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' | 820' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | ✓ | ✓ | | |

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
 - Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 150 feet.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- TCP (1-2a)**
- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
 - R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.
- TCP (1-2b)**
- Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
 - Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.



Texas Department of Transportation Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP (1-2) - 18

| | | | | |
|-----------------------|------|------------|-----------|-------------|
| FILE: tcp1-2-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 4-90 4-98 | DIST | COUNTY | SHEET NO. | |
| 2-94 2-12 | WACO | HILL, ETC. | 11 | |
| 1-97 2-18 | | | | |

DATE: 5/24/2022 11:05:11 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal Data\This standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units. This standard is based on the Texas Department of Transportation Standard Specifications for Road and Bridge Construction, 2002 Edition, Section 201-1.1.1.



LEGEND

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | ✓ | ✓ | | |

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

TCP (1-4b)

- Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

Texas Department of Transportation
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
 LANE CLOSURES ON MULTILANE
 CONVENTIONAL ROADS**

TCP (1-4) - 18


| | | | | | |
|-----------|---------------|------|------------|-----------------------|---------|
| FILE: | tcp1-4-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT | December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| 2-94 | 4-98 | DIST | COUNTY | SHEET NO. | |
| 8-95 | 2-12 | WACO | HILL, ETC. | 12 | |
| 1-97 | 2-18 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project. This standard is subject to change without notice. TxDOT reserves the right to modify this standard at any time without notice. TxDOT reserves the right to modify this standard at any time without notice.


DATE: 5/24/2022 11:05:11 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal Data\Traffic Control Plans\TCP (1-5)-18.dgn



ONE LANE CLOSURE



LANE CLOSURE NEAR EXIT RAMP



LANE CLOSURE NEAR ENTRANCE RAMP

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | | ✓ | | |

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation

Traffic Operations Division Standard


TRAFFIC CONTROL PLAN LANE CLOSURES FOR DIVIDED HIGHWAYS

TCP (1-5) - 18

| | | | | |
|-----------------------|------|------------|-----------|-------------|
| FILE: tcp1-5-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT February 2012 | CONT | SECT | JOB | HIGHWAY |
| 2-18 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | DIST | COUNTY | SHEET NO. | |
| | WACO | HILL, ETC. | 13 | |


DISCLAIMER:

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units. This standard is not intended to be used in conjunction with any other standard.




TCP (2-1a)

WORK SPACE NEAR SHOULDER
 Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
 Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
 Conventional Roads

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | ✓ |

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Additional work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK



TCP (2-1) - 18

| | | | | |
|-----------------------|------|------------|-----------------------|---------|
| FILE: tcp2-1-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| 2-94 4-98 | DIST | COUNTY | SHEET NO. | |
| 8-95 2-12 | WACO | HILL, ETC. | 14 | |
| 1-97 2-18 | | | | |

DATE: 5/24/2022 11:05:13 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal Data\TC2-2-18.dgn

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project.

Warning Sign Sequence in Opposite Direction Same as Below



LEGEND

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" | Stopping Sight Distance |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|-------------------------|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | | |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' | 120' | 90' | 200' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' | 250' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' | 305' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' | 360' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' | 425' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' | 495' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' | 570' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' | 645' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' | 730' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' | 820' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | ✓ | ✓ | ✓ | |

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.


Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP (2-2) - 18

| | | | | |
|---------------------|-----------|------------|-----------|-------------|
| FILE: tcp2-2-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT | REVISIONS | CONT | SECT | JOB |
| 8-95 3-03 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 1-97 2-12 | DIST | COUNTY | SHEET NO. | |
| 4-98 2-18 | WACO | HILL, ETC. | 15 | |


DATE: 5/24/2022 11:05:14 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal Data\This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to a different format or for any errors or omissions in this standard. (2-4) - 1




CW20-1D
48" X 48"
(Flags-
See note 1)

X for 50 MPH or less
3X for over 50 MPH

Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. (See notes 5 & 6)



TCP (2-4a)
ONE LANE CLOSED




CW20-1D
48" X 48"
(Flags-
See note 1)

CW20-5TL
48" X 48"

CW16-3aP
30" X 12"
(See note 4)

CW1-6aT
36" X 36"

Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. (See notes 5 & 6)



TCP (2-4b)
TWO LANES CLOSED

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | | ✓ | ✓ | |

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

TCP (2-4b)

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.


Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 LANE CLOSURES ON MULTILANE
 CONVENTIONAL ROADS**

TCP (2-4) - 18

| | | | | |
|-----------------------|------|------------|-----------|-------------|
| FILE: tcp2-4-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 8-95 3-03 | DIST | COUNTY | SHEET NO. | |
| 1-97 2-12 | WACO | HILL, ETC. | 16 | |
| 4-98 2-18 | | | | |

NOTE: 1. CONVERT TO FLASHING YELLOW ARROW



LOCATION 1-3
0836-02-081
SH 195 @ HALLMARK AVE
(CONVERT TO FLASHING YELLOW ARROW)
(SPAN WIRE)

LOCATION 1-1
0231-10-019
BUS 190 @ GRAY ST

LOCATION 1-9
3534-01-020
SH 201 @ FM 3470

LOCATION 1-10
3534-02-006
SH 201 @ FM 3470

LOCATION 1-8
3534-01-019
FM 34070 @ JACK SPOON DR

LOCATION 1-2
0836-02-080
SH 195 @ ELMS RD


LOCATION 1-7
3534-01-018
FM 3470 @ TRIMMIER RD
(CONVERT TO FLASHING YELLOW ARROW)

LOCATION 1-6
3534-01-017
FM 3470 @ OAK VALLEY RD



LOCATION 1-5
3534-01-016
FM 3470 @ ELMS RD
(CONVERT TO FLASHING YELLOW ARROW)

LOCATION 1-4
0836-02-082
SH 195 @ SH 201/CLEAR CREEK RD
(CONVERT TO FLASHING YELLOW ARROW)

EXISTING TRAFFIC SIGNAL SIGN (TYP.)



PROPOSED TRAFFIC SIGNAL SIGN (TYP.)



Chris O. Pruitt, P.E. 7/01/2022
SIGNATURE OF REGISTRANT & DATE



LOCATION MAP
KILLEEN

SCALE: 1" = 2500' HORIZ.

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------|------------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | | COUNTY | SHEET NO. |
| | TEXAS | WACO | | HILL, ETC. | 17 |

\$DATE \$ TIME \$

| CSJ | ID | COUNTY | CITY | STREET 1 | STREET 2 | LATITUDE | LONGITUDE | Item Bid Codes | | | | | | | | | | | | |
|---------------|------|--------|---------|----------|-----------------------|-----------|------------|--|---|-------------------------------------|---|-------------------------------------|---|-------------------------------------|---|---|---|--|--------------------------------------|---|
| | | | | | | | | 610 6102 | 636 6007 | 682 6001 | 682 6002 | 682 6003 | 682 6004 | 682 6005 | 682 6006 | 682 6051 | 682 6052 | 684 6012 | 690 6024 | 6058 6001 |
| | | | | | | | | REPLACE LUMINAIRE W/LED (250W EQ) | REPLACE EXISTING ALUMINUM SIGNS (TY A) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | TRF SIG CBL (TY A) (12 AWG) (7 CONDR) | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) |
| EA | SF | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | | | | | | |
| 0231-10-019 | 1-1 | Bell | Killeen | BUS 190 | Gray St | 31.117264 | -97.728852 | | | 8 | 2 | 8 | 4 | 8 | 2 | 8 | 2 | | 10 | 1 |
| 0836-02-080 | 1-2 | Bell | Killeen | SH 195 | Elms Rd | 31.086304 | -97.755674 | 4 | 21 | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 50 | 12 | 1 |
| *0836-02-081 | 1-3 | Bell | Killeen | SH 195 | Hallmark Ave | 31.115976 | -97.744865 | | 21 | 8 | 2 | 8 | 4 | 8 | 2 | 8 | 2 | 50 | 10 | 1 |
| **0836-02-082 | 1-4 | Bell | Killeen | SH 195 | SH 201/Clear Creek Rd | 31.057088 | -97.765625 | 4 | 21 | 12 | 2 | 12 | 4 | 12 | 2 | 12 | 2 | 50 | 14 | 1 |
| **3534-01-016 | 1-5 | Bell | Killeen | FM 3470 | Elms Rd | 31.074146 | -97.706287 | 2 | 21 | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 50 | 12 | 1 |
| 3534-01-017 | 1-6 | Bell | Killeen | FM 3470 | Oak Valley Rd | 31.071460 | -97.709423 | 2 | | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | | 12 | |
| **3534-01-018 | 1-7 | Bell | Killeen | FM 3470 | Trimmier Rd | 31.072933 | -97.740383 | 2 | 21 | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 50 | 12 | 1 |
| 3534-01-019 | 1-8 | Bell | Killeen | FM 3470 | Jack Spoon Dr | 31.086275 | -97.787456 | 2 | | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | | 12 | |
| 3534-01-020 | 1-9 | Bell | Killeen | SH 201 | FM 3470 | 31.092209 | -97.807734 | 1 | | 4 | 2 | 4 | 4 | 4 | 2 | 4 | 2 | | 6 | 1 |
| 3534-02-006 | 1-10 | Bell | Killeen | SH 201 | FM 3470 | 31.092209 | -97.807734 | 1 | | 4 | 2 | 4 | 4 | 4 | 2 | 4 | 2 | | 6 | |


NOTE:


*SPAN WIRE AT INTERSECTION

**CONVERT TO FLASHING YELLOW ARROW


\$FILES \$

NODE

| | | | | | |
|--|----------------------|------|------------|----------|-------------|
|  <p>© 2022 Texas Department of Transportation</p> | | | | | |
| <h2>SIGNAL SUMMARY</h2> <h3>KILLEEN</h3> | | | | | |
| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
| | 6 | 0121 | 02 | 062, ETC | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 18 |



LOCATION 2-1
2304-02-046
FM 2410 @ FM 3481/VERNA LEE BLVD



Chris O. Pruitt, P.E. 7/01/2022
SIGNATURE OF REGISTRANT & DATE



LOCATION MAP
HARKER HEIGHTS

SCALE: FEET
1" = 1500' HORIZ.

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 19 |

DATE \$ TIME \$

FILES \$

NOTE

| CSJ | ID | COUNTY | CITY | STREET 1 | STREET 2 | LATITUDE | LONGITUDE | Item Bid Codes | | | | | | | | | | |
|-------------|-----|--------|----------------|----------|------------------------|-----------|------------|-----------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|------------------------------------|------------------------------------|-----------------------------|------------------------------------|
| | | | | | | | | 610 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 690 | 6058 |
| | | | | | | | | 6102 | 6001 | 6002 | 6003 | 6004 | 6005 | 6006 | 6051 | 6052 | 6024 | 6001 |
| | | | | | | | | REPLACE LUMINAIRE W/LED (250W EQ) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) |
| 2304-02-046 | 2-1 | Bell | Harker Heights | FM 2410 | FM 3481/Verna Lee Blvd | 31.056241 | -97.654095 | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA |
| | | | | | | | | | 8 | 4 | 8 | 8 | 8 | 4 | 8 | 4 | 12 | 1 |




SIGNAL SUMMARY

HARKER HEIGHTS

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 20 |


NOTE: 1. CONVERT TO FLASHING YELLOW ARROW





LOCATION 3-1
0724-01-057
FM 116 @ LUTHERAN CHURCH RD
(CONVERT TO FLASHING YELLOW ARROW)

LOCATION 3-2
0724-01-058
FM 116 @ FM 1113
(CONVERT TO FLASHING YELLOW ARROW)

EXISTING TRAFFIC SIGNAL SIGN (TYP.)



PROPOSED TRAFFIC SIGNAL SIGN (TYP.)



Chris O. Pruitt, P.E. **7/01/2022**
SIGNATURE OF REGISTRANT & DATE



LOCATION MAP
COPPERAS COVE

SCALE: FEET
1" = 1500' HORIZ.

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------|------------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | | COUNTY | SHEET NO. |
| | TEXAS | WACO | | HILL, ETC. | 21 |

\$DATE \$ TIME \$

| CSJ | ID | COUNTY | CITY | STREET 1 | STREET 2 | LATITUDE | LONGITUDE | Item Bid Codes | | | | | | | | | | | | |
|---------------|-----|---------|---------------|----------|-------------------|-----------|------------|-----------------------------------|--|----------------------------|--------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|------------------------------------|------------------------------------|---------------------------------------|-----------------------------|------------------------------------|
| | | | | | | | | 610 | 636 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 684 | 690 | 6058 | |
| | | | | | | | | 6102 | 6007 | 6001 | 6002 | 6003 | 6004 | 6005 | 6006 | 6051 | 6052 | 6012 | 6024 | 6001 |
| | | | | | | | | REPLACE LUMINAIRE W/LED (250W EQ) | REPLACE EXISTING ALUMINUM SIGNS (TY A) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | TRF SIG CBL (TY A) (12 AWG) (7 CONDR) | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) |
| EA | SF | EA | EA | EA | EA | EA | EA | EA | EA | LF | EA | EA | | | | | | | | |
| **0724-01-057 | 3-1 | Coryell | Copperas Cove | FM 116 | Luthern Church Rd | 31.156970 | -97.909593 | | 10.5 | 6 | 1 | 6 | 2 | 6 | 1 | 6 | 1 | 50 | 7 | 1 |
| **0724-01-058 | 3-2 | Coryell | Copperas Cove | FM 116 | FM 1113 | 31.126003 | -97.902761 | | 21 | 6 | 2 | 6 | 4 | 6 | 2 | 6 | 2 | 50 | 8 | 1 |

NOTE:

**CONVERT TO FLASHING YELLOW ARROW





SIGNAL SUMMARY

COPPERAS COVE

| | | | | | |
|--------------|-------------------|------|------------|-----------|-------------|
| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 22 |


\$FILES \$

NODE



GATESVILLE
Pop 11,492

LOCATION 4-1
0184-01-069
SH 36 @ BUS 36



Chris O. Pruitt, P.E. **7/01/2022**
SIGNATURE OF REGISTRANT & DATE



LOCATION MAP
GATESVILLE

SCALE: FEET
1" = 1500' HORIZ.


| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 23 |

\$DATE \$ TIME \$

| CSJ | ID | COUNTY | CITY | STREET 1 | STREET 2 | LATITUDE | LONGITUDE | Item Bid Codes | | | | | | | | | | | |
|-------------|-----|---------|------------|----------|----------|-----------|------------|-----------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|------------------------------------|------------------------------------|-----------------------------|------------------------------------|----|
| | | | | | | | | 610 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 690 | 6058 | |
| | | | | | | | | 6102 | 6001 | 6002 | 6003 | 6004 | 6005 | 6006 | 6051 | 6052 | 6024 | 6001 | |
| | | | | | | | | REPLACE LUMINAIRE W/LED (250W EQ) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) | |
| 0184-01-069 | 4-1 | Coryell | Gatesville | SH 36 | BUS 36 | 31.425790 | -97.715917 | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA |

\$FILES \$

NODE


 © 2022
Texas Department of Transportation

SIGNAL SUMMARY


GATESVILLE

| | | | | | |
|--------------|-------------------|------|------------|-----------|-------------|
| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 24 |



NOTE: 1. CONVERT TO FLASHING YELLOW ARROW



EXISTING TRAFFIC SIGNAL SIGN (TYP.)



PROPOSED TRAFFIC SIGNAL SIGN (TYP.)



Chris O. Pruitt, P.E. 7/01/2022
SIGNATURE OF REGISTRANT & DATE



LOCATION MAP
BELLMEAD

SCALE: FEET
1" = 1500' HORIZ.

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------|------------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | | COUNTY | SHEET NO. |
| | TEXAS | WACO | | HILL, ETC. | 25 |

\$DATE \$ TIME \$


| CSJ | ID | COUNTY | CITY | STREET 1 | STREET 2 | LATITUDE | LONGITUDE | Item Bid Codes | | | | | | | | | | | | | |
|---------------|-----|----------|----------|----------|----------------------|-----------|------------|-----------------------------------|--|----------------------------|--------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|------------------------------------|------------------------------------|--------------------------------------|-----------------------------|------------------------------------|----|
| | | | | | | | | 610 | 636 | 682 | 682 | 682 | 682 | 682 | 682 | 682 | 684 | 690 | 6058 | | |
| | | | | | | | | 6102 | 6007 | 6001 | 6002 | 6003 | 6004 | 6005 | 6006 | 6051 | 6052 | 6012 | 6024 | 6001 | |
| | | | | | | | | REPLACE LUMINAIRE W/LED (250W EQ) | REPLACE EXISTING ALUMINUM SIGNS (TY A) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | TRF SIG CBL (TY A) (12AWG) (7 CONDR) | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) | |
| | | | | | | | | EA | SF | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA |
| **0162-01-101 | 5-1 | McLennan | Bellmead | US 84 | Loop 340 Frontage Rd | 31.598989 | -97.089431 | | 21 | 12 | 2 | 12 | 4 | 12 | 2 | 12 | 2 | 50 | 14 | 1 | |

NOTE:

**CONVERT TO FLASHING YELLOW ARROW

\$FILES


NODE

 © 2022
 Texas Department of Transportation


SIGNAL SUMMARY

BELLMEAD

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 26 |



LOCATION 6-1
 0121-02-062
 SH 22/ELM ST @
 SH 171/HOUSTON ST



Chris O. Pruitt, P.E. 7/01/2022
 SIGNATURE OF REGISTRANT & DATE



LOCATION MAP
 HILLSBORO

SCALE: FEET
 1" = 1500' HORIZ.


| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|-------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 27 |

\$DATE \$TIME\$

| CSJ | ID | COUNTY | CITY | STREET 1 | STREET 2 | LATITUDE | LONGITUDE | Item Bid Codes | | | | | | | | | | |
|-------------|-----|--------|-----------|--------------|-------------------|-----------|------------|--|-------------------------------------|---|-------------------------------------|---|-------------------------------------|---|---|---|--------------------------------------|---|
| | | | | | | | | 610 6102 | 682 6001 | 682 6002 | 682 6003 | 682 6004 | 682 6005 | 682 6006 | 682 6051 | 682 6052 | 690 6024 | 6058 6001 |
| | | | | | | | | REPLACE LUMINAIRE W/LED (240W EQ) | VEH SIG SEC(12") LED (GRN) | VEH SIG SEC(12") LED (GRN ARW) | VEH SIG SEC(12") LED (YEL) | VEH SIG SEC(12") LED (YEL ARW) | VEH SIG SEC(12") LED (RED) | VEH SIG SEC(12") LED (RED ARW) | BACKPLATE W/REFL BRDR (3 SEC) ALUM | BACKPLATE W/REFL BRDR (4 SEC) ALUM | REMOVAL OF SIGNAL HEAD ASSM | BBU SYSTEM (EXTERNAL BATT CABINET) |
| EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | | | | | | | |
| 0121-02-062 | 6-1 | Hill | Hillsboro | SH 22/ELM ST | SH 171/HOUSTON ST | 32.010735 | -97.135188 | | 6 | 2 | 6 | 4 | 6 | 2 | 6 | 2 | 8 | |

\$FILES\$

NODE


 © 2022
 Texas Department of Transportation

SIGNAL SUMMARY


HILLSBORO

| CHANGE ORDER | FED. RD. DIV. NO. | CONT | SECT | JOB | HIGHWAY |
|--------------|----------------------|------|------------|-----------|-------------|
| | 6 | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | STATE | DIST | COUNTY | | SHEET NO. |
| | TEXAS | WACO | HILL, ETC. | | 28 |

DATE: 5/24/2022 11:05:15 AM
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data\TS-BP-20.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein.




Vented backplate with retroreflective border




Backplate with retroreflective border

THREE-SECTION HEAD
HORIZONTAL OR VERTICAL




Vented backplate with retroreflective border




Backplate with retroreflective border

FOUR-SECTION HEAD
HORIZONTAL OR VERTICAL




Vented backplate with retroreflective border




Backplate with retroreflective border

FIVE-SECTION HEAD
HORIZONTAL OR VERTICAL




Vented backplate with retroreflective border




Backplate with retroreflective border

FIVE-SECTION HEAD
CLUSTER



Backplate louvers based on wind and vibration rating.

Vented backplate with retroreflective border



Backplate with retroreflective border

PEDESTRIAN HYBRID
BEACON

GENERAL NOTES:

1. Backplates are optional for traffic signals and pedestrian hybrid beacons. When backplates are used, a 2-inch wide fluorescent yellow AASHTO Type B_{FL} or C_{FL} retroreflective border conforming to TxDOT DMS-8300 is required. Place on all approaches when used.
2. Signal head and backplate compatibility must be verified by the contractor prior to installation.
3. When using backplates on signal heads, venting is preferred to reduce cyclic vibration stress.
4. When a vented backplate is used, the retroreflective border must not be placed over the louvers.
5. This standard sheet applies to all signal heads with backplates, including but not limited to:
 - Pole mounted
 - Overhead mounted
 - Span wire mounted
 - Mast arm mounted
 - Vertical signal heads
 - Horizontal signal heads
 - Clustered signal heads
 - Pedestrian hybrid beacons

| | | | | | |
|---|-----------|---|-----------|---|--|
| | | Texas Department of Transportation | | Traffic Safety Division Standard | |
| TRAFFIC SIGNAL HEAD WITH BACKPLATE | | | | | |
| TS-BP-20 | | | | | |
| FILE: ts-bp-20.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT | |
| © TxDOT June 2020 | CONT | SECT | JOB | HIGHWAY | |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. | |
| | DIST | COUNTY | SHEET NO. | | |
| | WACO | HILL, ETC. | 29 | | |

DATE: 5/24/2022 11:05:16 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal\Traffic Control Devices\Traffic Signal\Traffic Control Devices\RID(1)-20-2022.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of units in this standard.

ROADWAY ILLUMINATION ASSEMBLY NOTES

- Details apply to roadway lighting installations bid or referenced under Item 610, "Roadway Illumination Assemblies." Provide, furnish, and install all other materials not shown on the plans which may be necessary for complete and proper construction. Where manufacturers provide warranties or guarantees as a customary trade practice, furnish to the State such warranties or guarantees.
- The locations of poles and fixtures may be shifted by the Engineer to accommodate local conditions. Install or remove poles and luminaires located near overhead electrical lines using established industry and utility safety practices and in accordance with laws governing such work. Consult with the appropriate utility company prior to beginning such work.
- Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association, Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection.
- Provide Roadway Illumination Light Fixtures as per TxDOT Departmental Material Specification (DMS) 11010, Item 610, and as shown on the Material Producers List (MPL) for Roadway Illumination and Electrical Supplies.
- Fabricate steel roadway illumination poles in accordance with Roadway Illumination Poles (RIP) standards and Item 610. Poles fabricated according to RIP standards do not require shop drawing submittals.
 - Alternate designs to RIP standards or the use of aluminum to fabricate poles will require the submission of shop drawings electronically. For instructions on submitting shop drawings electronically see "Guide to Electronic Shop Drawing Submittal" on the TxDOT web site.
 - Limitations on use of the RIP standard: The RIP standard details were developed for installations in locations where the 3-second gust basic maximum wind speed is 110 mph, and where the elevation of the base of the pole is less than (i.e. not more than) 25' above the elevation of the surrounding terrain, in accordance with the "AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals," 6th Edition (2013) of the AASHTO Design Specifications. For poles to be installed in regions where the maximum basic wind speed exceeds 110 mph or to be mounted more than 25' above the surrounding terrain, provide poles meeting the following requirements:
 - Submittals. Following the electronic shop drawing submittal process (see Guide to Electronic Shop Drawing Submittal on the TxDOT web site), submit to the Engineer for approval fabrication drawings and calculations for the poles, sealed by a Texas licensed professional engineer (P.E.).
 - Luminaire Structural Support Requirements. Provide light poles, arms, and anchor bolt assemblies with a 25 year design life to safely resist dead loads, ice loads and the required basic wind speeds at the location of installation in accordance with the 6th edition (2013) of the AASHTO Design Specifications. For transformer base poles, include transformer base and connecting hardware in calculations and shop drawing submittals. Structurally test all transformer bases to resist the theoretical plastic moment capacity of the pole. Submit certification of the plastic moment load test and FHWA breakaway requirement test of the model of base being furnished with the shop drawings. Show breakaway base model number, manufacturer's name, and logo on shop drawings. Include on manufacturer's shop drawings the ASTM designations for all materials to be used.
- For both transformer and shoe-base type illumination poles, provide and install double-pole breakaway fuse holders as specified by DMS-11040. Breakaway fuse holders are listed on the MPL for Roadway Illumination and Electrical Supplies under Items 610 & 620. Provide 10 amp time delay fuses for breakaway connectors in light poles, or inside the light fixture for underpass luminaires. In each pole, connect luminaires to the breakaway connector with continuous stranded 12 AWG copper conductors as listed on the MPL. Bond all equipment grounding conductors together and to the ground lug in the transformer base or hand hole.
- Tighten anchor bolts for shoe base, concrete traffic barrier base, and bridge mount roadway illumination poles, in accordance with Item 449.
- Install T-Base with following procedure:
 - Anchor Bolt Tightening.
 - Coat the threads of the anchor bolts with electrically conductive lubricant.
 - Place the T-base over the anchor bolts. Foundation must be level and flat. The maximum permissible gap under any one corner of the t-base is 1/8" before nuts are tightened.
 - Coat the bearing surfaces of the nuts and washers with electrically conductive lubricant. Install (1) 1/2" hold down washer, (1) lock washer, and (1) nut on each anchor bolt. Turn the nuts onto the bolts so that each is hand-tight against the washer.
 - Using a torque wrench, tighten each nut to 150 ft-lb. Uniform contact is required between the foundation and the T-base in the corner regions of the T-base, and all corner gaps must be closed after applying torque. If a gap still exists after torquing to 150 ft-lbs, continue torquing each bolt incrementally until gap is closed or maximum allowable torque of 250 ft. pound is reached, whichever comes first. If 250 ft-lbs is not enough to close the gap the foundation must be leveled. Gaps along the straight sides of the T-bases and the foundation are permissible. Ensure that no high point of contact occurs between the straight sides of the T-base and the foundation.
 - Check top of T-base for level. If not level then foundation must be leveled.
 - Top Bolt Procedure
 - Erect pole over T-base with crane. Coat bolts, nuts, washers, and lock washers with electrically conductive lubricant.


- Install bolts and 1/2" connecting washers from the inside of the T-base, thread up through the pole base. Install flat washers, lock washers and nuts snug tight according to Item 447, "Structural Bolting."
 - Tighten each nut to 150 ft-lb. using a torque wrench.
- c. Level and Plumb
- Ensure pole is plumb and mast arm is perpendicular to the roadway according to plans to within 5 degrees.
- Construct luminaire pole foundations in accordance with Item 416, "Drilled Shaft Foundations," and TxDOT standard sheet RID(2).
 - Provide and install underpass luminaires in accordance with Item 610, DMS-11010, and TxDOT standard sheet RID(3). Typical luminaire size for underpass luminaires is 150W HPS or 150W EQ LED.
 - Mount luminaires on arms level as shown by the luminaire level indicator.
 - Orient luminaires perpendicular to the roadway intended to be lit unless otherwise shown on the plans.

Wiring Diagram Notes:

- Use 1/2 in. -13 UNC threaded, copper or tin-plated copper, pole bonding connector, sized appropriately for conductors, bonded to T-base, or use ground lug in handhole as available.
- Use pre-qualified two-pole breakaway connectors for all luminaire pole installations. For luminaires fed by a circuit with a neutral conductor, use double pole breakaway connectors with the neutral side unfused and marked white.
- Split Bolt or other connector.


Decorative LED Lighting Notes:

- LED Drivers in Remote Outdoor enclosures (for drivers that do not include an enclosure as part of a factory assembly):
 - Provide NEMA 3R outdoor enclosure or as approved.
 - Install enclosure at least 12" above ground or other horizontal surface. Mount vertically or on ceiling, and avoid direct sun where possible.
 - Install drivers with at least 2 inches of space from enclosure walls.
 - For multiple drivers in an enclosure, provide at least 4 inches side to side and 1 inch end to end from other drivers or electronic equipment
 - For drivers mounted on back wall of enclosure, mount enclosure on 1 5/8" strut or other standoff to dissipate heat, or mount driver to side of the enclosure or to the metal cover.
 - Provide remote drivers with a maximum of 100 watts
 - Provide drivers with documentation of 100,000 hr lifetime at Tcase of 65C or higher.



TYPICAL WIRING DIAGRAM


LUMINAIRES SERVED AT 480V ON 240/480 VOLT SERVICE OR LUMINAIRES SERVED AT 240V FOR 120/240 VOLT SERVICE.



Driver Spacing In Remote Enclosure


| | | | |
|--|-----------|---|---------------------------|
| | | Traffic Safety Division Standard | |
| <h1>ROADWAY ILLUMINATION DETAILS</h1> <h2>RID(1)-20</h2> | | | |
| FILE: rid1-20.dgn | DN: 0121 | CK: 02 | HW: 062, ETC. SH 22, ETC. |
| © TxDOT January 2007 | REVISIONS | CONTRACT | HIGHWAY |
| 7-17 | DIST | COUNTY | SHEET NO. |
| 12-20 | WACO | HILL, ETC. | 30 |

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard.




SHOE BASE POLE

| Luminaire Mounting Height (Nominal) (ft) | Base Diameter (in) | Top Diameter (in) | Length (ft) | Pole Thickness (in) | Design Moment (K-ft) |
|--|--------------------|-------------------|-------------|---------------------|----------------------|
| 20.00 | 7.00 | 4.90 | 15.00 | 0.1196 | 7.1 |
| 30.00 | 7.50 | 4.00 | 25.00 | 0.1196 | 13.2 |
| 31.00-39.00 | 8.00 | 4.36-3.24 | 26.00-34.00 | 0.1196 | 20.7 |
| 40.00 | 8.50 | 3.60 | 35.00 | 0.1196 | 20.7 |
| 50.00 | 10.50 | 4.20 | 45.00 | 0.1196 | 30.3 |



TRANSFORMER BASE POLE

| Luminaire Mounting Height (Nominal) (ft) | Base Diameter (in) | Top Diameter (in) | Length (ft) | Pole Thickness (in) | Design Moment (K-ft) |
|--|--------------------|-------------------|-------------|---------------------|----------------------|
| 20.00 | 7.00 | 5.11 | 13.50 | 0.1196 | 7.1 |
| 30.00 | 7.50 | 4.21 | 23.50 | 0.1196 | 13.2 |
| 31.00-39.00 | 8.00 | 4.57-3.45 | 24.50-32.50 | 0.1196 | 20.7 |
| 40.00 | 8.50 | 3.81 | 33.50 | 0.1196 | 20.7 |
| 50.00 | 10.00 | 3.91 | 43.50 | 0.1196 | 30.3 |



CONCRETE TRAFFIC BARRIER BASE POLE

| Luminaire Mounting Height (Nominal) (ft) | Base Diameter (in) | Top Diameter (in) | Length (ft) | Pole Thickness (in) | Design Moment (K-ft) | |
|--|--------------------|-------------------|-------------|---------------------|----------------------|---------------|
| | | | | | About C of Rail | Perp. to Rail |
| 28.00 | 9.00 | 5.78 | 23.00 | 0.1196 | 10.3 | 13.2 |
| 38.00 | 9.00 | 4.38 | 33.00 | 0.1196 | 16.6 | 20.8 |
| 48.00 | 10.50 | 4.48 | 43.00 | 0.1345 | 25.1 | 30.5 |

GENERAL NOTES:

- Designs conform to AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 6th Edition (2013) and Interim Revisions thereto. Design 3-Second Gust Wind Speed equals 110 mph with a 1.14 gust factor. A wind importance factor of 0.80 is applied to adjust the wind speed to a 25 year recurrence interval. Design moments listed in tables assume base of pole is 25' above natural ground level.
- Structures are designed to support two 12' luminaire mast arms and luminaires. Mast arms are designed to support a 60-pound luminaire having an effective projected area of 1.6 square feet.
- Fabrication shall be in accordance with the Specifications and with the details, dimensions, and weld procedures shown herein. Do not submit shop drawings for roadway illumination pole assemblies fabricated in accordance with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of these sheets and the Specifications. In the absence of specified fabrication tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.
- For mounting heights between values shown in the tables, use base diameter and thickness values for the larger height.
- Unless otherwise noted, all steel parts shall be galvanized in accordance with Item 445, "Galvanizing."
- Steel poles shall be fabricated in accordance with Item 441, "Steel Structures." Longitudinal seam welds for pole sections shall have 60% minimum penetration. All welding shall be in accordance with AWS D1.1, Structural Welding Code-Steel.
- Two-section poles joined by circumferential welds will not be permitted, unless otherwise shown on the plans. Poles may be fabricated in two sections and field-assembled by the lap-joint method. The two sections shall telescope together with a lap length of not less than 1-1/2 times the shaft diameter at the lap joint.
- Alternate material equal to or better than material specified may be substituted with the approval of the Engineer.
- Lubricate and tighten anchor bolts, when erecting shoe base poles and concrete traffic barrier base poles, in accordance with Item 449, "Anchor Bolts."
- All poles, except Transformer Base Poles, shall have hand holes with reinforcing frames and covers. For ground mounted shoe base poles, hand holes shall be placed 90 degrees to mast arm unless otherwise noted on the plans. For poles mounted on a concrete traffic barrier with one luminaire arm, hand holes shall be located 180 degrees from luminaire arm. For poles mounted on a concrete traffic barrier with two luminaire arms, all hand holes shall be on the same side of the barrier. For poles mounted on a bridge lighting bracket or a retaining wall lighting bracket, hand hole shall be on traffic side of the pole, at a height that will clear the barrier.
- The finished pole shall have a smooth, uniform finish free of pits, blisters, or other defects. Scratched, chipped, and other damaged galvanized areas on poles and mast arms shall be repaired in accordance with Item 445, "Galvanizing."
- Pole length is based on a 5'-6" luminaire arm rise. 4 ft. luminaire arms have a 2'-6" rise. A pole with 4 ft. luminaire arms will have an actual mounting height 3'-0" less than the nominal mounting height. Increasing the pole length to meet the nominal mounting height is allowed, but unnecessary unless otherwise directed by the engineer.
- Erect transformer base poles in accordance with sheet RID(1).

MATERIAL DATA

| COMPONENT | ASTM DESIGNATION | MIN. YIELD (ksi) |
|-------------------------------|--|------------------|
| Pole Shaft (0.14"/ft. Taper) | A572 Gr 50, A595 Gr A, A1011 HSLAS Gr 50 Cl 2 (3), or A1008 HSLAS Gr 50 Cl 2 | 50 |
| Base Plate and Handhole Frame | A572 Gr.50, or A36 | 36 |
| T-Base Connecting Bolts | F3125 Gr A325 | 92 |
| Anchor Bolts | F1554 Gr 55, A193-B7 or A321 | 55 105 |
| Anchor Bolt Templates | A36 | 36 |
| Heavy Hex (H.H.) Nuts | A194 Gr 2H, or A563 Gr DH | |
| Flat Washers | F436 | |

NOTES:

- 2'-6" rise for 4 ft. luminaire arms.
- Before ovalized as shown on Concrete Traffic Barrier Base Baseplate details, Sheet 4 of 4.
- A1011 SS Gr 50 may be used instead of HSLAS, provided the material meets the elongation requirements for HSLAS.

POLE ASSEMBLY FABRICATION TOLERANCES TABLE

| DIMENSION | TOLERANCE |
|--|----------------|
| Shaft length | +1" |
| I.D. of outside piece of slip fitting pieces | +1/8", -1/16" |
| O.D. of inside piece of slip fitting pieces | +1/32", -1/8" |
| Shaft diameter: other | +3/16" |
| Out of "round" | 1/4" |
| Straightness of shaft | ±1/4" in 10 ft |
| Twist in multi-sided shaft | 4° in 50 ft |
| Perpendicular to baseplate | 1/8" in 24" |
| Pole centered on baseplate | ±1/4" |
| Location of Attachments | ±1/4" |
| Bolt hole spacing | ±1/16" |

SHEET 2 OF 4

Texas Department of Transportation

Traffic Safety Division Standard


ROADWAY ILLUMINATION POLES

RIP(2) - 19

| | | | | |
|----------------------|------|------------|-----------|-------------|
| FILE: rip-19.dgn | DN: | CK: | DW: | CK: |
| © TxDOT January 2007 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 7-17 | DIST | COUNTY | SHEET NO. | |
| 12-19 | WACO | HILL, ETC. | 32 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units of measurements. This standard is based on the current requirements of the Texas Department of Transportation (TxDOT) and is subject to change without notice.

DATE: 5/24/2022 11:05:18 AM
 FILE: T:\WACTRAFF\TRAFFIC\Traffic Control Devices\Traffic Signal\Signal\Traffic Signal Standards\TRIP (1-4)-1




LUMINAIRE ARM

LUMINAIRE ARM DIMENSIONS


| Nominal Arm Length | Arm Length | Rise |
|--------------------|------------|-------|
| 4'-0" | 3'-6" | 2'-6" |
| 6'-0" | 5'-6" | 5'-6" |
| 8'-0" | 7'-6" | 5'-6" |
| 10'-0" | 9'-6" | 5'-6" |
| 12'-0" | 11'-6" | 5'-6" |

ARM ASSEMBLY FABRICATION TOLERANCES TABLE


| DIMENSION | TOLERANCE |
|-----------------------|-------------|
| Arm Length | ±1" |
| Arm Rise | ±1" |
| Deviation from flat | 1/8" in 12" |
| Spacing between holes | ±1/32" |




UPPER SIMPLEX FITTING
(Gusset not shown for clarity)






LOWER SIMPLEX FITTING
(Gusset not shown for clarity)
SECTION B-B




POLE SIMPLEX DETAIL ③




ARM SIMPLEX DETAIL ③




SIMPLEX ATTACHMENT DETAIL



POLE TOP



ELEVATION



SECTION A-A

NOTES:

- ④ Any of the materials listed for plates may be used where the drawings do not specify a particular ASTM designation.
- ⑤ A576 must be suitable for forging and also meet minimum tensile strength of 65 ksi, minimum yield of 35 ksi, and elongation in 2 inches of 22 percent.
- ⑥ A572, A1008 HSLAS-F, and A1011 HSLAS-F materials may have higher yield strengths but shall not have less elongation than the grade indicated.
- ⑦ Dimensional limits are given to show acceptable variation in design. All of a Fabricator's production of a particular arm length shall have the same dimensions within specified tolerances.
- ⑧ Each pole simplex fitting shall be supplied with 2 bolts and 2 lock washers of the size specified. The bolts and lock washers shall be secured to the pole with the other hardware items called for in the plans.
- ⑨ Proposed deviations in arm simplex dimensions or materials must be submitted to the Department for approval.
- ⑩ A welded handhole frame is permissible. Maximum of two (2) CJP weld splices is allowed.

MATERIALS

| | |
|--------------------------------|---|
| Pole or Arm Simplex | ASTM A27 Gr 65-35 or Gr 70-36, A148 Gr 80-50, A576 Gr 1021 ⑤, or A36 (Arm only) |
| Arm Pipes | ASTM A53 Gr A or B, A500 Gr B, A501, A 1008 HSLAS-F Gr 50 ⑥, or A1011 HSLAS-F Gr 50 ⑥ |
| Arm Struts and Gusset Plates ④ | ASTM A36, A572 Gr 50 ⑥, or A588 |
| Misc. | ASTM designations as noted |

Texas Department of Transportation
 Traffic Safety Division Standard


**ROADWAY ILLUMINATION POLES
RIP (3) - 19**

| FILE: | DN: | CK: | DW: | CK: |
|----------------------|------|------------|-----------|-------------|
| rip-19.dgn | | | | |
| © TxDOT January 2007 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| 7-17 | DIST | COUNTY | CITY | SHEET NO. |
| 12-19 | WACO | HILL, ETC. | | 33 |


DATE: 5/24/2022 11:05:19 AM
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021*FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\SP-80(1)-2
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

| STRAIN POLE DESCRIPTION | Pole Type | Founda-tion Type | Maximum Permissible Span Wire Load (lbs.) |
|-----------------------------------|-----------|------------------|---|
| 26' Pole | A | 36-A | 5200 |
| 30' Pole | B | 36-A | 4600 |
| 30' Pole with Lum. | B | 36-A | 4400 |
| 30' Pole with 20' Mast Arm | C | 36-B | 5600 |
| 30' Pole with 24' Mast Arm | C | 36-B | 5500 |
| 30' Pole with 28' Mast Arm | C | 36-B | 5300 |
| 30' Pole with 32' Mast Arm | C | 36-B | 5100 |
| 30' Pole with 36' Mast Arm | C | 36-B | 4900 |
| 30' Pole with 20' Mast Arm & Lum. | C | 36-B | 5300 |
| 30' Pole with 24' Mast Arm & Lum. | C | 36-B | 5200 |
| 30' Pole with 28' Mast Arm & Lum. | C | 36-B | 5000 |
| 30' Pole with 32' Mast Arm & Lum. | C | 36-B | 4800 |
| 30' Pole with 36' Mast Arm & Lum. | C | 36-B | 4500 |
| 34' Pole | D | 36-B | 5600 |
| 34' Pole with Lum. | D | 36-B | 5400 |

② Numbers on Load Span Charts indicate the number of signal heads on the span. The total span wire design load is based on one 5-section head and one or more additional 3-section head(s). Design wind pressures on cables are assumed as 1.0 lb/ft. Weight of span wire cables (one per signal head) is assumed as 0.65 lb/ft which includes an allowance for conductor cables and miscellaneous hardware. The effect of the sway cable on load distribution is ignored as it is assumed to break at design wind conditions. When a pole supports 2 spans, the span wire design loads for both spans should be added vectorially to determine the design load for that pole.




STRAIN POLE ELEVATIONS HORIZONTAL SIGNALS




STRAIN POLE ELEVATIONS VERTICAL SIGNALS

(Mast arms are not used with vertical signals)



② SIGNALS WITH 12-INCH LENS



② SIGNALS WITH 8-INCH LENS

| Signal Head Type | Wt. Per Head | Wind Area |
|---------------------|--------------|--------------|
| 5-Section, 12" Lens | 125 lbs | 9.6 sq. ft. |
| 5-Section, 8" Lens | 70 lbs | 4.8 sq. ft. |
| 3-Section, 12" Lens | 75 lbs | 5.64 sq. ft. |
| 3-Section, 8" Lens | 45 lbs | 3.0 sq. ft. |

Effective projected design wind area (actual area times drag coefficient)

- Sag = 4'-6" (26' or 30' Pole)
- Sag = 8'-0" (30' or 34' Pole)
- - - Sag = 11'-6" (34' Pole)

| Pole Type | ROUND POLES | | | | POLYGONAL POLES | | | |
|-----------|----------------|----------------|--------|----|-----------------|----------------|--------|----|
| | D _B | D _T | (4)thk | H | D _B | D _T | (4)thk | H |
| A | 12.5 | 8.9 | .239 | 26 | 13.0 | 9.0 | .239 | 26 |
| B | 13.5 | 9.3 | .239 | 30 | 14.0 | 9.0 | .239 | 30 |
| C | 15.5 | 11.3 | .239 | 30 | 16.0 | 11.0 | .239 | 30 |
| D | 15.5 | 10.7 | .239 | 34 | 16.0 | 11.0 | .239 | 34 |

D_B = Pole Base O.D. D_T = Pole Top O.D. H = Pole Height

④ Thickness shown are minimum, thicker materials may be used.

SHIPPING PARTS LIST

| Poles (Without Traffic Signal Arm) | | | | | | |
|------------------------------------|-----------------------------|-------------|----------|--------------------------------|-------------|----------|
| Pole Type | Strain poles with Luminaire | | | Strain poles without Luminaire | | |
| | Description | Designation | Quantity | Description | Designation | Quantity |
| A | | | | 26' Strain Pole | SP 26 A-80 | |
| B | 30' Strain Pole | SPL 30 B-80 | | 30' Strain Pole | SP 30 B-80 | |
| D | 34' Strain Pole | SPL 34 D-80 | | 34' Strain Pole | SP 34 D-80 | |

| Poles (With Traffic Signal Arm) | | | | | | |
|---------------------------------|-----------------------------|-------------|----------|--------------------------------|-------------|----------|
| Pole Type | Strain poles with Luminaire | | | Strain poles without Luminaire | | |
| | Description | Designation | Quantity | Description | Designation | Quantity |
| C | 30' SPw/TS Arm | SPL 30 C-80 | | 30' SPw/TS Arm | SP 30 C-80 | |

| Traffic Signal Arms (For Type C poles) | | | | | | |
|--|-----------------------|-------------|-------------------------|----------|--------------------------|----------|
| Nominal Arm Length | Type I Arm (1 Signal) | | Type II Arm (2 Signals) | | Type III Arm (3 Signals) | |
| | ft. | Designation | Designation | Quantity | Designation | Quantity |
| 20 | 20I-80 | | | | | |
| 24 | 24I-80 | | 24 II -80 | | | |
| 28 | 28I-80 | | 28 II -80 | | | |
| 32 | | | 32 II -80 | | 32 III -80 | |
| 36 | | | 36 II -80 | | 36 III -80 | |

Anchor Bolt Assemblies (1 per pole)

| Anchor Bolt Diameter | Anchor Bolt Length | Quantity |
|----------------------|--------------------|----------|
| 1 3/4" | 3'-10" | |
| 2" | 4'-3" | |

Luminaire Arms

| Nominal Arm Length | Quantity |
|--------------------|----------|
| 8' Arm | |




Each Anchor Bolt Assembly consists of the following: Top and Bottom templates, 4 anchor bolts, 8 nuts, 8 flat washers, and 4 nut anchor devices (Type 2) per Standard Drawing "TS-FD".

① See Sheet "DMA-80"



TRAFFIC SIGNAL SUPPORT STRUCTURES STRAIN POLE ASSEMBLIES
 (80 MPH WIND ZONE)
SP-80(1)-12

| | | | | |
|--------------------|--------|------------|-----------------------|---------|
| © TxDOT March 1996 | DN: MS | CK: JSY | DW: BR | CK: JSY |
| REVISIONS | CONT | SECT | JOB | HIGHWAY |
| 6-96 1-12 | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| | DIST | COUNTY | SHEET NO. | |
| | WACO | HILL, ETC. | 35 | |

DATE: 5/24/2022 11:05:20 AM
 FILE: I:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021-FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\SP-80(1-2)



| Arm Length | 24' | 28' | 32' | 36' |
|--------------|-----|-----|-----|-----|
| Arm Type II | 10' | 11' | 12' | 13' |
| Arm Type III | | | 10' | 11' |



| MATERIALS | |
|---|---|
| Round Shafts or Polygonal Shafts ⁹ | ASTM A595 Gr. A, A588, A1008 HSLAS Gr. 50 Class 2, A1011 HSLAS Gr. 50 Class 2, A572 Gr. 50 or A1011 SS Gr. 50 ¹⁰ |
| Plates ⁹ | ASTM A36, A588, or A572 Gr. 50 |
| Connection Bolts | ASTM A325 except where noted |
| Pin Bolts | ASTM A325 |
| Pipe ⁹ | ASTM A53 Gr. B, A501, A1008 HSLAS-F Gr. 50, A1011 HSLAS-F Gr. 50 |
| Steel Cable | ASTM A475, 7 Wire Utilities Grade |
| Misc. Hardware | Galvanized steel or stainless steel or as noted |

⁹ ASTM A572, A1008 HSLAS, A1011 HSLAS, A1008 HSLAS-F, A1011 HSLAS-F, or A1011 SS may have higher yield strengths but shall not have less elongation than the grade indicated.

¹⁰ ASTM A1011 SS Gr. 50 shall also have a minimum elongation of 18 percent in 8 inches or 23 percent in 2 inches. Material thickness in excess of those stipulated under A1011 SS will be acceptable providing the material meets all other A1011 SS requirements and the requirements of this item.

GENERAL NOTES

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications thereto. Design Wind Speed equals 80 mph plus a 1.3 gust factor. The maximum permissible span wire design loads tabulated are calculated at a stress load of 1.4 times the basic allowable stress. A simultaneous wind on the pole, mast arm, and luminaire is also included.

See standard sheet "DMA-80" for details of clamp-on traffic signal arms, sheet "MA-C" for traffic signal arm connection details, sheet "LUM-A" for luminaire arm and connection details, and sheet "TS-FD" for anchor bolt and foundation details.

Fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of this sheet and Item 686, "Traffic Signal Pole Assemblies (Steel)".

Unless otherwise noted, all parts shall be galvanized in accordance with Item 445, "Galvanizing", after fabrication.

Deviation from the details and dimensions shown herein require submission of shop drawings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.

| Foundation Type | Anchor Bolt Diameter | Bolt Hole Diameter | Bolt Circle Diameter | Base Pl. Dim. L x T |
|-----------------|----------------------|--------------------|----------------------|---------------------|
| 36-A | 1 3/4" | 2" | 19" | 19" x 1 3/4" |
| 36-B | 2" | 2 1/4" | 21" | 21" x 2" |

SHEET 2 OF 2

Texas Department of Transportation
 Traffic Operations Division
TRAFFIC SIGNAL SUPPORT STRUCTURES STRAIN POLE ASSEMBLIES
 (80 MPH WIND ZONE)
SP-80(2)-12

| | | | | | |
|--------------------|------|------------|-----------|-------------|---------|
| © TxDOT March 1996 | | DN: MS | CK: JSY | DW: BR | CK: JSY |
| REVISIONS | | | | | |
| 6-96 | 0121 | 02 | 062, ETC. | SH 22, ETC. | |
| 1-12 | | | | | |
| DIST | | COUNTY | | SHEET NO. | |
| WACO | | HILL, ETC. | | 36 | |

120B


DATE: 5/24/2022 11:05:20 AM
 FILE: I:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021*FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\SMA-80(1)-12

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


| Arm Length | ROUND POLES | | | | | POLYGONAL POLES | | | | | Foundation Type |
|------------|----------------|-----------------|-----------------|-----------------|-------|-----------------|-----------------|-----------------|-----------------|-------|-----------------|
| | D _B | D ₁₉ | D ₂₄ | D ₃₀ | ① thk | D _B | D ₁₉ | D ₂₄ | D ₃₀ | ① thk | |
| ft. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | |
| 20 | 10.5 | 7.8 | 7.1 | 6.3 | .179 | 11.5 | 8.5 | 7.7 | 6.8 | .179 | 30-A |
| 24 | 11.0 | 8.3 | 7.6 | 6.8 | .179 | 12.0 | 9.0 | 8.2 | 7.3 | .179 | 30-A |
| 28 | 11.5 | 8.8 | 8.1 | 7.3 | .179 | 12.5 | 9.5 | 8.7 | 7.8 | .179 | 30-A |
| 32 | 12.5 | 9.8 | 9.1 | 8.3 | .179 | 12.0 | 9.0 | 8.2 | 7.3 | .239 | 30-A |
| 36 | 12.0 | 9.3 | 8.6 | 7.8 | .239 | 12.5 | 9.5 | 8.7 | 7.8 | .239 | 36-A |
| 40 | 12.0 | 9.3 | 8.6 | 7.8 | .239 | 13.5 | 10.5 | 9.7 | 8.8 | .239 | 36-A |
| 44 | 12.5 | 9.8 | 9.1 | 8.3 | .239 | 14.0 | 11.0 | 10.2 | 9.3 | .239 | 36-A |
| 48 | 13.0 | 10.3 | 9.6 | 8.8 | .239 | 15.0 | 12.0 | 11.2 | 10.3 | .239 | 36-A |

| Arm Length | ROUND ARMS | | | | | POLYGONAL ARMS | | | | |
|------------|----------------|----------------|----------------|-------|--------|----------------|----------------|------------------|-------|--------|
| | L ₁ | D ₁ | D ₂ | ① thk | Rise | L ₁ | D ₁ | ② D ₂ | ① thk | Rise |
| ft. | ft. | in. | in. | in. | | ft. | in. | in. | in. | |
| 20 | 19.1 | 6.5 | 3.8 | .179 | 1'-9" | 19.1 | 7.0 | 3.5 | .179 | 1'-8" |
| 24 | 23.1 | 7.5 | 4.3 | .179 | 1'-10" | 23.1 | 7.5 | 3.5 | .179 | 1'-9" |
| 28 | 27.1 | 8.0 | 4.2 | .179 | 1'-11" | 27.1 | 8.0 | 3.5 | .179 | 1'-10" |
| 32 | 31.0 | 9.0 | 4.7 | .179 | 2'-1" | 31.0 | 9.0 | 3.5 | .179 | 2'-0" |
| 36 | 35.0 | 9.5 | 4.6 | .179 | 2'-4" | 35.0 | 10.0 | 3.5 | .179 | 2'-1" |
| 40 | 39.0 | 9.5 | 4.1 | .239 | 2'-8" | 39.0 | 9.5 | 3.5 | .239 | 2'-3" |
| 44 | 43.0 | 10.0 | 4.1 | .239 | 2'-11" | 43.0 | 10.0 | 3.5 | .239 | 2'-6" |
| 48 | 47.0 | 10.5 | 4.1 | .239 | 3'-4" | 47.0 | 11.0 | 3.5 | .239 | 2'-9" |

- D_B = Pole Base O.D.
- D₁₉ = Pole Top O.D. with no Luminaire and no ILSN
- D₂₄ = Pole Top O.D. with ILSN w/out Luminaire
- D₃₀ = Pole Top O.D. with Luminaire
- D₁ = Arm Base O.D.
- D₂ = Arm End O.D.
- L₁ = Shaft Length
- L = Nominal Arm Length
- ① Thickness shown are minimums, thicker materials may be used.
- ② D₂ may be increased by up to 1" for polygonal arms.



TRAFFIC SIGNAL ARM
(Fixed Mount)



③ Threaded Coupling for CGB Connector See "ARM COUPLING DETAILS" Sheet 2 of 2

| Arm Length | 24' | 28' | 32' | 36' | 40' | 44' | 48' |
|--------------|-----|-----|-----|-----|-----|-----|-----|
| Arm Type II | 10' | 11' | 12' | 13' | | | |
| Arm Type III | | | 10' | 11' | 12' | 12' | 12' |

STRUCTURE ASSEMBLY

SHIPPING PARTS LIST

Ship each pole with the following attached: enlarged hand hole, pole cap, fixed-arm connection bolts and washers and any additional hardware listed in the table.

| Nominal Arm Length | 30' Poles With Luminaire | | 24' Poles With ILSN | | 19' Poles With No Luminaire and No ILSN | |
|--------------------|--|----------|---|----------|---|----------|
| | Above hardware plus: One (or two if ILSN attached) small hand hole, clamp-on simplex | | Above hardware plus one small hand hole | | See note above | |
| ft | Designation | Quantity | Designation | Quantity | Designation | Quantity |
| 20 | 20L-80 | | 20S-80 | | 20-80 | |
| 24 | 24L-80 | | 24S-80 | | 24-80 | |
| 28 | 28L-80 | | 28S-80 | | 28-80 | |
| 32 | 32L-80 | | 32S-80 | | 32-80 | |
| 36 | 36L-80 | | 36S-80 | | 36-80 | |
| 40 | 40L-80 | | 40S-80 | | 40-80 | |
| 44 | 44L-80 | | 44S-80 | | 44-80 | |
| 48 | 48L-80 | | 48S-80 | | 48-80 | |

Traffic Signal Arms (1 per Pole) Ship each arm with the listed equipment attached

| Nominal Arm Length | Type I Arm (1 Signal) | | Type II Arm (2 Signals) | | Type III Arm (3 Signals) | |
|--------------------|-----------------------|----------|---|----------|---|----------|
| | 1 CGB connector | | 1 Bracket Assembly and 2 CGB Connectors | | 2 Bracket Assemblies and 3 CGB Connectors | |
| ft | Designation | Quantity | Designation | Quantity | Designation | Quantity |
| 20 | 20I-80 | | | | | |
| 24 | 24I-80 | | 24II-80 | | | |
| 28 | 28I-80 | | 28II-80 | | | |
| 32 | | | 32II-80 | | 32III-80 | |
| 36 | | | 36II-80 | | 36III-80 | |
| 40 | | | | | 40III-80 | |
| 44 | | | | | 44III-80 | |
| 48 | | | | | 48III-80 | |

Luminaire Arms (1 per 30' pole)

| Nominal Arm Length | Quantity |
|--------------------|----------|
| 8' Arm | |

ILSN Arm (Max. 2 per pole) Ship with clamps, bolts and washers

| Nominal Arm Length | Quantity |
|--------------------|----------|
| 7' Arm | |
| 9' Arm | |

Anchor Bolt Assemblies (1 per pole)

| Anchor Bolt Diameter | Anchor Bolt Length | Quantity |
|----------------------|--------------------|----------|
| 1 1/2" | 3'-4" | |
| 1 3/4" | 3'-10" | |


Each anchor bolt assembly consists of the following: Top and Bottom templates, 4 anchor bolts, 8 nuts, 8 flat washers, and 4 nut anchor devices (Type 2) per Standard Drawing "TS-FD".

Templates may be removed for shipment.


TRAFFIC SIGNAL SUPPORT STRUCTURES
SINGLE MAST ARM ASSEMBLY
(80 MPH WIND ZONE)
SMA-80(1)-12

| | | | | | |
|---------------------|------------|--------|-----------|-------------|---------|
| © TxDOT August 1995 | | DN: MS | CK: JSY | DW: MMF | CK: JSY |
| REVISIONS | | | | | |
| 5-96 | 0121 | 02 | 062, ETC. | SH 22, ETC. | |
| 11-99 | | | | | |
| 1-12 | | | | | |
| DIST | COUNTY | | SHEET NO. | | |
| WACO | HILL, ETC. | | | | 37 |

DATE: 5/24/2022 11:05:21 AM
 FILE: I:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021*FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\SMA-80 (1-1-2)




SLIP JOINT DETAIL



TENON DETAIL


Stainless steel bands (or Cables) and cast bracket as in "Astro-Brac", "Sky Bracket" or "Easy Bracket" with 1 1/2" Dia Threaded Coupling.

BRACKET ASSEMBLY



ARM WELD DETAIL

④ 60% Min. penetration
100% penetration within 6" of circumferential base welds.



ARM COUPLING DETAILS

VIBRATION WARNING

Mast Arms of SMA and DMA structures and clamp-on Arms of LMA structures of approximately 40 ft or longer are subject to harmonic vertical vibrations in light wind conditions due to the aeroelastic characteristics of a few of the myriads of possible combinations of the following: signal numbers, weights and positions; existence/solidity of backplates; presence of additional attachments to the arm, such as signs and cameras; arm-wind orientation; and arm-pole stiffness.

Such vibrations may cause fatigue damage to the structure and may lead to galloping in moderate wind conditions which may further damage the structure and alarm the public. Tests have indicated that when wind is blowing toward the back side of signal heads having un-vented backplates attached the probability of unacceptable harmonic vibration and/or galloping is rather high.

If backplates are not required for improved visibility they should not be applied to the signal heads or, if they must be applied, they should be vented as a first and inexpensive measure to mitigate vibrations.

The traffic signal mast arms shall be visually inspected in 5 to 20 mph wind conditions after installation of signal heads and any attachments, including any required backplates. If vertical movements with a total excursion (maximum upward excursion to maximum downward excursion) of more than approximately 8" are observed at the arm tip, a damping plate shall be fitted to the arm. See "Damping Plate Mounting Details" on standard sheet, MA-DP-10.

This visual inspection shall be repeated after each modification of the structure that could affect its aeroelastic response. Excessive vibrations shall not be allowed to continue for more than two days.

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications thereto. Design Wind Speed equals 80 mph plus a 1.3 gust factor.

Poles are designed to support one 8'-0" luminaire arm, one 9'-0" internally lighted street name sign and one traffic signal arm with a length as tabulated. The specified luminaire load applied at the end of the luminaire arm equals 60 lbs vertical dead load plus the horizontal wind load on an effective projected area of 1.6 sq ft. The specified internally lighted street name sign load applied 4.5 ft from the centerline of the pole equals 85 lbs vertical dead load plus horizontal wind load on an effective projected area of 11.5 sq ft. The specified signal load applied at the end of the traffic signal arm equals 180 lbs vertical dead load plus the horizontal wind load on an effective projected area of 32.4 sq ft (actual area times drag coefficient).

See Standard Sheet "MA-D" for pole details, "MA-C" for traffic signal arm connection details, "MA-C (ILSN)" for internally lighted street name sign arm connection details, "LUM-A" for luminaire arm and connection details, "SNS" for internally lighted street name sign details, and "TS-FD" for anchor bolt and foundation details. See "MA-C" for material specifications.

Fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of this sheet and Item 686, "Traffic Signal Pole Assemblies (Steel)".

Unless otherwise noted, all parts shall be galvanized in accordance with Item 445, "Galvanizing", after fabrication.

Deviation from the details and dimensions shown herein require submission of shop drawings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.




TRAFFIC SIGNAL SUPPORT STRUCTURES SINGLE MAST ARM ASSEMBLY (80 MPH WIND ZONE)


SMA-80 (2) - 12

| | | | | | |
|---------------------|-----------|---------|------------|-----------|-------------|
| © TxDOT August 1995 | DN: MS | CK: JSY | DW: MMF | CK: JSY | |
| 5-96 1-12 | REVISIONS | CONT | SECT | JOB | HIGHWAY |
| | | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | | DIST | COUNTY | SHEET NO. | |
| | | WACO | HILL, ETC. | 38 | |


DATE: 5/24/2022 11:05:22 AM
 FILE: I:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021\FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\LUM-A-12-1.




8-FOOT LUMINAIRE ARM




10-FOOT LUMINAIRE ARM




DIRECT ATTACHMENT DETAIL




CLAMP ATTACHMENT DETAIL NO. 1 (HALF SECTION)
CLAMP ATTACHMENT DETAIL NO. 2 (HALF SECTION)



CLAMP ATTACHMENT DETAIL NO. 3 (HALF SECTION)
CLAMP ATTACHMENT DETAIL NO. 4 (HALF SECTION)




UPPER SIMPLEX FITTING




LOWER SIMPLEX FITTING

SECTION A-A

SECTION B-B



POLE SIMPLEX DETAIL



ARM SIMPLEX DETAIL

| MATERIALS | |
|----------------------|---|
| Pole or Arm Simplex | ASTM A27 Gr. 65-35 or A148 Gr. 80-50, A576 Gr. 1021 (3), or A36 (Arm only) |
| Arm Pipes | ASTM A53 Gr. B, A501, A1008 HSLAS-F Gr. 50 (4), or A1011 HSLAS-F Gr. 50 (4) |
| Arm Strut Plates (2) | ASTM A36, A572 Gr. 50 (4), or A588 |
| Misc. | ASTM designations as noted |

- Dimensional limits are given to show acceptable variation in design. All of a Fabricator's production of a particular arm length shall have the same dimensions within specified tolerances.
- Any of the materials listed for plates may be used where the drawings do not specify a particular ASTM designation.
- A576 must be suitable for forging and also meet minimum tensile strength of 65 ksi, minimum yield of 35 ksi, and elongation in 2 inches of 22 percent.
- ASTM A572, A1008 HSLAS-F, and A1011 HSLAS-F may have higher yield strengths but shall not have less elongation than the grade indicated.

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Revisions thereto. Design Wind Speed equals 90 mph plus a 1.3 gust factor. Arms are designed to support a 60 lb. luminaire having an effective projected area (actual area times drag coefficient) of 1.6 sq. ft.

Materials and fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. In the absence of specified Fabricator tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.

Unless otherwise noted, all parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing".

Deviation from the details and dimensions shown herein require submission of shop drawings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.

Each pole simplex fitting shall be supplied with 2 ASTM A325 bolts and 2 lock washers of the size specified. The bolts and lock washers shall be secured to the pole with the other hardware items called for in the plans. When clamp attachment is specified, the Fabricator shall ship the clamp assembly securely attached to the pole at the location shown on the plans.

If clamp assemblies are ordered without poles, the Fabricator shall ship one upper and one lower clamp assembly together in a single package, including all nuts and washers required for the clamps and simplex fittings.

Texas Department of Transportation
 Traffic Operations Division
STANDARD ASSEMBLY DRAWINGS FOR LUMINAIRE SUPPORT STRUCTURES
ARM DETAILS
LUM-A-12

| | | | | | |
|---------------------|------|------------|-------------|---------|---------|
| © TxDOT August 1995 | | DN: LEH | CK: JSY | DW: LTT | CK: TEB |
| 5-96 | 1-99 | 1-12 | REVISIONS | | |
| 0121 | 02 | 062, ETC. | SH 22, ETC. | HIGHWAY | |
| DIST | | COUNTY | SHEET NO. | | |
| WACO | | HILL, ETC. | 39 | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

Post Type

FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)


Anchor Type

UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.


No more than 2 sign posts should be located within a 7 ft. circle.



BEHIND BARRIER




BEHIND GUARDRAIL



BEHIND CONCRETE BARRIER

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


| Pipe Diameter | Approximate Bolt Length | |
|----------------|-------------------------|-----------------|
| | Specific Clamp | Universal Clamp |
| 2" nominal | 3" | 3 or 3 1/2" |
| 2 1/2" nominal | 3 or 3 1/2" | 3 1/2 or 4" |
| 3" nominal | 3 1/2 or 4" | 4 1/2" |

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND




RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.



* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

Texas Department of Transportation
 Traffic Operations Division


SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD(GEN)-08

| | | | | |
|-------------------|-----------|------|------------|-----------------------|
| © TxDOT July 2002 | DN: | CK: | DW: | CK: |
| 9-08 | REVISIONS | CONT | SECT | JOB |
| | | 0121 | 02 | 062, ETC. SH 22, ETC. |
| | | DIST | COUNTY | SHEET NO. |
| | | WACO | HILL, ETC. | 40 |

DATE: 5/24/2022 11:05:23 AM
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021\FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\slip-1.p
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm
 The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



5/8" diameter Concrete Anchor - 8 places (embed a minimum of 5 1/2" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)
















Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

Texas Department of Transportation
 Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM SMD(SLIP-1)-08

| | | | | | |
|-------------------|-----------|------|------------|-----------|-------------|
| © TxDOT July 2002 | | DN: | CK: | DW: | CK: |
| 9-08 | REVISIONS | CONT | SECT | JOB | HIGHWAY |
| | | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | | DIST | COUNTY | | SHEET NO. |
| | | WACO | HILL, ETC. | | 41 |

DATE: 5/24/2022 11:05:24 AM
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021*FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\slip-2.dwg



- GENERAL NOTES:**
1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA

| | | |
|--------|---|-------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
 2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
 3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
 4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
 5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
 6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
 7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
 8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
 9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
 10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
 11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
 12. Post open ends shall be fitted with Friction Caps.
 13. Sign blanks shall be the sizes and shapes shown on the plans.

| REQUIRED SUPPORT | | |
|----------------------------------|--|---|
| SIGN DESCRIPTION | SUPPORT | |
| Regulatory | 48-inch STOP sign (R1-1) | TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM) |
| | 60-inch YIELD sign (R1-2) | TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM) |
| | 48x16-inch ONE-WAY sign (R6-1) | TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM) |
| Warning | 36x48, 48x36, and 48x48-inch signs | TY 10BWG(1)XX(T) |
| | 48x60-inch signs | TY S80(1)XX(T) |
| | 48x48-inch signs (diamond or square) | TY 10BWG(1)XX(T) |
| | 48x60-inch signs | TY S80(1)XX(T) |
| | 48-inch Advance School X-ing sign (S1-1) | TY 10BWG(1)XX(T) |
| 48-inch School X-ing sign (S2-1) | TY 10BWG(1)XX(T) | |
| Large Arrow sign (W1-6 & W1-7) | TY 10BWG(1)XX(T) | |

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.











Texas Department of Transportation
 Traffic Operations Division

SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-2)-08

| | | | | | |
|-------------------|-----------|------|------------|-----------|-------------|
| © TxDOT July 2002 | | DW: | CK: | DW: | CK: |
| 9-08 | REVISIONS | CONT | SECT | JOB | HIGHWAY |
| | | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | | DIST | COUNTY | | SHEET NO. |
| | | WACO | HILL, ETC. | | 42 |

DATE: 5/24/2022 11:05:25 AM
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021*FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\slip-3.dwg

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

| REQUIRED SUPPORT | | |
|------------------|--|---|
| | SIGN DESCRIPTION | SUPPORT |
| Regulatory | 48-inch STOP sign (R1-1) | TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM) |
| | 60-inch YIELD sign (R1-2) | TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM) |
| | 48x16-inch ONE-WAY sign (R6-1) | TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM) |
| | 36x48, 48x36, and 48x48-inch signs | TY 10BWG(1)XX(T) |
| Warning | 48x60-inch signs | TY S80(1)XX(T) |
| | 48x48-inch signs (diamond or square) | TY 10BWG(1)XX(T) |
| | 48x60-inch signs | TY S80(1)XX(T) |
| | 48-inch Advance School X-ing sign (S1-1) | TY 10BWG(1)XX(T) |
| | 48-inch School X-ing sign (S2-1) | TY 10BWG(1)XX(T) |
| | Large Arrow sign (W1-6 & W1-7) | TY 10BWG(1)XX(T) |




**SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-3)-08**


| | | | | | |
|-------------------|-----------|------|------------|-----------|-------------|
| © TxDOT July 2002 | DN: | CK: | DW: | CK: | |
| 9-08 | REVISIONS | CONT | SECT | JOB | HIGHWAY |
| | | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | | DIST | COUNTY | | SHEET NO. |
| | | WACO | HILL, ETC. | | 43 |

DATE: 5/24/2022 11:05:25 AM
 FILE: I:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\Signal Data Files\021*FM 116 at Lutheran Church Rd\RTZ Phase 5_Signal Improvements\0121-02-062\Standards\smd(twt)-01-01.dwg



Wedge Anchor Steel System



Wedge Anchor High Density Polyethylene (HDPE) System




Universal Anchor System with Thin-Walled Tubing Post




Plastic insert must be used when using the TWT with either the Universal Anchor System or the Bolt Down Universal Anchor System. The insert should be approx. 10" long and cover the tubing from just above the top of the stub pipe to the bottom of the sign post when using the Universal Anchor System. The insert should be cut to approx. 4 1/2" when used with the Bolt Down Universal Anchor System.



5/8" diameter Concrete Anchor - 4 places (embed a min. of 3 3/8" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.



Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. A heavy hex nut per ASTM A563 and hardened washer per ASTM F436. The stud bolt shall have minimum yield and ultimate tensile strengths of 50 and 75 ksi, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Top of bolt shall extend at least flush with top of nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 3 3/8" minimum embedment, shall have a minimum allowable tension and shear of 2450 and 1525 psi, respectively. Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxy and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations.



Sign Installation Using a Prefabricated T-Bracket for Thin-Wall Tubing Post



NOTE

The devices shall be installed per manufacturer's recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- The Wedge Anchor System and the Universal Anchor System with thin wall tubing post may be used to support up to 10 square feet of sign area.
- The tubular socket, wedge and prefabricated T-bracket shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to the approval of the TxDOT Traffic Standards Engineer.
- Except for posts (13 BWG Tubing), clamps, nuts and bolts, all components shall be prequalified. A list of prequalified vendors may be obtained from the Material Producer List web page. The website address is: http://www.txdot.gov/business/producer_list.htm
- Material used as post with this system shall conform to the following specifications:
 - 13 BWG Tubing (2.375" outside diameter) (TWT)
 - 0.095" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing
 - Steel shall be HSLA Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 18% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of .083" to .099"
 - Outside diameter (uncoated) shall be within the range of 2.369" to 2.381"
 - Galvanization per ASTM 123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24" high signs. Place clamp at least 3" above bottom of sign when possible.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- See the Traffic Operations Division website for detailed drawings of sign clamps and Wedge Anchor System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>

WEDGE ANCHOR SYSTEM INSTALLATION PROCEDURE

- Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Place concrete into hole until it is approximately flush with the ground. Concrete shall be Class A.
- Insert tubular socket into concrete until top of socket is approximately 1/4" above the concrete footing.
- Plumb the socket. Allow a minimum 4 days for concrete to set, unless otherwise directed by Engineer.
- Attach the sign to the sign post.
- Insert the sign post into socket and align sign face with roadway.
- Drive the wedge into the socket to secure post. This will leave approximately 3 inches of the wedge exposed.

UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURE

- Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- Insert base post in hole to depths shown and backfill hole with concrete.
- Level and plumb the base post using a torpedo level and allow concrete adequate time to set. The bottom of the slots provided in the stub pipe shall remain above the top of the concrete foundation.
- Attach the sign to the sign post.
- Install plastic insert around bottom of post.
- Insert sign post into base post. Lower until the post comes to rest on steel rod.
- Seat compression ring using a hammer. Typically, the top of compression ring will be approximately level with top of stub post when optimally installed.
- Check sign post by hand to ensure it is unable to turn. If loose, increase the tightening of the compression ring.



SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS WEDGE & UNIVERSAL ANCHOR WITH THIN WALL TUBING POST SMD(TWT) - 08

| | | | | | |
|-------------------|-----------|------|------------|-----------|-------------|
| © TxDOT July 2002 | DN: | CK: | DW: | CK: | |
| 9-08 | REVISIONS | CONT | SECT | JOB | HIGHWAY |
| | | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | | DIST | COUNTY | SHEET NO. | |
| | | WACO | HILL, ETC. | 44 | |

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS:

CSJ 0121-02-062: HILL, ETC.

LOCATION MAPS:

Refer to the TITLE SHEET for project location map.

PROJECT DESCRIPTION:

CSJ 0121-02-062

INSTALLATION OF SIGNAL BACKPLATE WITH REFLECTIVE BORDER

MAJOR SOIL DISTURBING ACTIVITIES:

No major soil disturbing activities on this project.

TOTAL PROJECT AREA:

| |
|---------|
| 0.5 AC |
| 0.00 AC |

TOTAL AREA TO BE DISTURBED:

EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

CSJ : 0121-02-062

Based on 0.00 AC to be disturbed, identification of existing soil conditions and vegetative cover is not applicable to this project.

NAME OF RECEIVING WATERS:

Based on the project scope, identification of receiving waters is not applicable to this project.

SOIL STABILIZATION PRACTICES:

| | |
|--|---|
| <input type="checkbox"/> TEMPORARY SEEDING | <input type="checkbox"/> SOIL RETENTION BLANKET |
| <input type="checkbox"/> PERMANENT PLANTING, SODDING, OR SEEDING | <input type="checkbox"/> NATURAL BARRIERS OR BUFFER ZONES |
| <input type="checkbox"/> MULCHING | <input checked="" type="checkbox"/> PRESERVATION OF NATURAL RESOURCES |

OTHER: TXR 150000, Part III, Section G, 2 Stabilization of disturbed areas must, at a minimum, be initiated immediately whenever any clearing, grading, excavating, or other earth disturbing activities have permanently ceased on any portion of the site, or temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days. Temporary stabilization must be completed no more than 14 calendar days after initiation of soil stabilization measures, and final stabilization must be achieved prior to termination of permit coverage.

STRUCTURAL PRACTICES: (Select T = Temporary or P = Permanent, As Applicable)

| | |
|--|--|
| <input checked="" type="checkbox"/> SILT FENCES | <input type="checkbox"/> TIMBER MATTING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> HAY BALES | <input type="checkbox"/> CHANNEL LINERS |
| <input type="checkbox"/> SANDBAG OR ROCK BERMS | <input type="checkbox"/> SEDIMENT TRAPS |
| <input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER DIKES | <input type="checkbox"/> SEDIMENT BASINS |
| <input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER SWALES | <input type="checkbox"/> STORM INLET SEDIMENT TRAP |
| <input type="checkbox"/> DIVERSION DIKE AND SWALE COMBINATIONS | <input type="checkbox"/> STONE OUTLET STRUCTURES |
| <input type="checkbox"/> PIPE SLOPE DRAINS | <input type="checkbox"/> CURBS AND GUTTERS |
| <input type="checkbox"/> PAVED FLUMES | <input type="checkbox"/> STORM SEWERS |
| <input type="checkbox"/> ROCK BEDDING AT CONSTRUCTION EXIT | <input type="checkbox"/> VELOCITY CONTROL DEVICES |

OTHER:

NARRATIVE-SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:


The order of activities will be as follows:

1. Preserve existing vegetative cover as much as possible.
2. Repair and upgrade illumination systems.

STORM WATER MANAGEMENT:

An integral part of the SWPPP for this project includes the EPIC Sheet, Item 506, Waco District Waters of the US Notes, Waco District Typical Applications for Best Management Practices, Form 2118 TxDOT Inspection forms, Contractor daily inspection forms, miscellaneous general notes on environmental requirements, TxDOT EC Standards, 2014 Standard Specifications, TxDOT roadway design drawings, SWPPP design and working BMP drawings, Site Manager Data Base, EMS Stage Gate Inspections and the Waco District environmental folders. The requirements of the TxDOT EMS will be fully implemented including training requirements for Contractors and TxDOT staff.

STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING



OTHER EROSION AND SEDIMENT CONTROLS:

MAINTENANCE:

All erosion and sediment best management practices (BMPs) will be maintained in good working order per the environmental notes, details and standards included as part of the project plans and contract documents. BMP repairs will be made at the earliest possible date, but no later than seven calendar days after the inspection report has been completed and immediately after the ground has dried sufficiently to allow equipment access. BMPs damaged by the Contractor will be repaired or replaced immediately. The installation and repair of BMPs at creeks and outfalls will be given priority.

INSPECTION:

TxDOT Form 2118 Inspections to support TXR150000 and 404 permits will be conducted on a seven day interval on the same day of the week, until permits are terminated. The Contractor will provide daily BMP inspection reports on work days. Stage Gate Inspections and other BMP inspections will be conducted by the District and Area Office Staff based on requirements of the TxDOT Environmental Management System (EMS).

WASTE MATERIALS:

Any waste materials generated during construction will be disposed of in accordance with existing federal, state, and local laws.

HAZARDOUS WASTE (INCLUDING SPILL REPORTING):

At a minimum, any products in the following categories are considered to be hazardous: Fuels, Lubricating products, Asphalt products, or Concrete curing compounds and any additives. In the event of a spill which may be hazardous, clean-up will be done in accordance with federal, state, and local regulations. The Contractor will maintain a list of all chemicals and wastes required for the project, including chemicals used by sub-contractors, and will implement written spill prevention and clean-up plans.

SANITARY WASTE:

Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor.

OFF SITE VEHICLE TRACKING:

| |
|--|
| <input type="checkbox"/> HAUL ROADS DAMPENED FOR DUST CONTROL |
| <input type="checkbox"/> LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN |
| <input checked="" type="checkbox"/> EXCESS DIRT ON ROAD REMOVED DAILY |
| <input type="checkbox"/> STABILIZED CONSTRUCTION ENTRANCE |


REMARKS:

Disposal areas, stockpiles, and haulroads will be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas will not be located in any wetland, waterbody or streambed. Construction staging area and vehicle maintenance area will be constructed by the contractor in a manner to minimize the runoff pollutants.

Furnish one SW3P permit posting sign and sign support as detailed on the SW3P Sheet. Install this sign in a location selected by the Engineer. The sign and support should be removed upon completion of the project and is the property of the Contractor. The purchase of the sign and support, installation, relocations if determined necessary by the Engineer and removal at project end will be by erosion control/maintenance force account.

SEDIMENTATION BASINS:

Since the area disturbed is less than 10 acres, per outfall location, a sedimentation basin is not required.



The seal appearing on this document was authorized by CHRIS O. PRUITT P.E. 126063, on

Chris O. Pruitt, P.E. 7/01/2022

Signature of Registrant & Date

© 2022
Texas Department of Transportation

**WACO DISTRICT
STORM WATER POLLUTION
PREVENTION PLAN
(SW3P)**

| FED. RD. DIV. NO. | STATE | CONT | SECT | JOB | HIGHWAY |
|-------------------|-------|------|------------|-----------|-------------|
| 6 | TEXAS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| | | DIST | COUNTY | SHEET NO. | |
| | | WACO | HILL, ETC. | 45 | |

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

1. Prior to TxDOT allowing the Contractor to start construction, the Contractor will provide the required storm water and 404 permit documentation and support activities, including but not limited to the following:
 - Provide a list of all chemicals, construction and waste products that will be generated, stored or brought upon TxDOT ROW. The list includes expected construction debris, sanitary wastes, construction chemicals and petroleum products used or generated by the Contractor and sub-contractors. Along with the list, the Contractor will supply a spill prevention plan and clean up procedures that will include each of these chemical products or generated waste.
 - Provide in the construction schedule the necessary line items that will comply with the schedule and planning requirements of the storm water permit.
 - Post the TxDOT storm water permit and any Contractor permits, per permit requirements.
 - Provide copies of storm water permits for Contractor PSL(s). As new PSL(s) may be obtained for the project, provide copies of new or amended permits to TxDOT. The Contractor will not disturb soil without the proper permits.
 - Provide scale drawings of off ROW PSL's within one mile of the project, for field offices, borrow sources, plant sites or other uses.
 - Provide permit information on any Contractor batch plants or concrete crushing plants to be located at a Contractor PSL(s) within one mile of the project limits or boundaries. Copies of the air and water permits are to be provided to TxDOT before materials will be used on the project. No asphalt or concrete batch plants or concrete crushing plants will be located on TxDOT ROW.
 - Provide a letter indicating a Contractor Responsible Person for environmental compliance (CRP) for the project, and maintain a CRP throughout the project duration.
 - Provide all environmental documentation including certification of compliance and EMS training documents/certificates prior to starting work. The Contractor is to provide daily BMP inspection reports that document all field BMPs needing repair or replacement. The Contractor is to clearly document specific BMPs needing repair and location each work day. The Contractor is encouraged to be proactive in fixing BMPs without TxDOT direction.
 - Provide documentation required for Waters of the US, Note #3 and submittals for Item 496 bridge removal. Bridge removal methods submitted will follow all Waters of the US note requirements. The Contractor is not to start construction within the Ordinary High Water Marks of any stream until receiving approval for stream channel construction methods from TxDOT.
 - Provide a written procedure for managing all chemicals and construction items placed in vertical containment structures. Also, provide methods to be used for the treatment, disposal, collection or release of storm water.
 - Provide an estimated date by letter, for the submittal of marked up bridge drawings, indicating cut locations for any structural steel requiring cutting or torching of steel, coated with lead containing paints.
2. Place and maintain trash cans and portable sanitary facilities at locations where there is active construction. Worker generated trash and construction debris will be kept from being transported by storm water and will be collected daily from the ground and routinely hauled from the work area.
3. Contractor will provide TxDOT copies of all correspondence with MS4s, TCEQ, EPA, DSHS and Corps of Engineers regarding activities on this project.
4. Contractor to conduct storm water inspections and develop SWPPP documents to support Contractor permits obtained for the project including PSL(s).
5. Contractor will maintain written documentation of locations of all portable sanitary facilities. The Contractor is required to document the location and disposition of all spills and cleanups from portable sanitary facilities.
6. Contractor will not store chemicals on TxDOT ROW, unless chemicals are stored following all environmental and safety regulations. Fuels for construction equipment will not be stored on TxDOT ROW.
7. The Contractor will store fuels and bulk chemicals on Contractor PSL(s) using a secondary containment method, such as double lined tanks and/or free standing containment reservoirs made of plastic or steel designed to hold bulk chemicals or drums.
8. The Contractor will not remove sediment controls without the prior approval of TxDOT, except for a sediment control that may back up water and cause safety or traffic problems.

SCALE = NTS SHEET 1 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 46 | |

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

9. Any sediment controls removed by the Contractor must be re-installed before the next rainfall event or by the end of day, as approved in advance.
10. Vegetative buffer strips may be used in place of temporary sediment controls such as silt fences and rock filter dams. The amount of disturbed soil area will be limited to 1/3 of an acre or less for a minimum of 50 feet of grassed ditch and 2/3 of an acre of disturbed soil for a minimum of 100 feet of grassed ditch.
11. Construction equipment found to be leaking oil, fuel or coolant will be immediately stopped, the leaking fluid collected and the equipment fixed. Equipment continuing to leak will be removed from the project at no cost to TxDOT. Leaking fluids from equipment will be collected and removed from the project or PSL.
12. Earth berms or mounds typically used to stockpile topsoil and used in place of boundary silt fence will be seeded upon being constructed. Long term use of earth berms or mounds will not be continued without establishing grass on the control.
13. The Contractor will inform TxDOT of new areas where soil will be disturbed to facilitate planning for new sediment controls. Areas of vegetated soil will not be disturbed by the Contractor, unless adequate sediment controls can be installed before the next rainfall event. The Contractor will assist TxDOT in keeping an accurate set of working SWPPP drawings that show the locations of all temporary sediment and erosion controls.
14. The Contractor will maintain an adequate amount of temporary sediment controls on hand at the field office or project staging area for critical SWPPP maintenance, including silt fence (minimum of 200 feet) and rock / fabric for rock filter dams (minimum for 100 feet of Type III dams).

The requirement for BMP rock quantities on hand is waived for small projects for on and off system bridge installations. The Contractor having a BMP Subcontractor does not eliminate the requirement for the Contractor to have the required silt fence and rock on hand, typically stored at the Contractor PSL.
15. Failure of a sub-contractor to complete storm water work on time will require the Contractor to start storm water sediment control work immediately and complete the work with high priority, or be subject to stop work on the entire project.
16. Earth materials on roads as a result of soil tracking will not be allowed to be transported off ROW in storm water. Soil or rock material found on roadways deposited from Contractor equipment will be removed daily.
17. Unless approved, completed concrete curb inlets will not be blocked by sediment controls. The contractor will frequently sweep the completed or partially completed roadway to keep sediment out of drainage pipes.
18. The Contractor will be responsible for proper dust control and will route construction traffic in a manner that minimizes dust generation.
19. Water for dust control will contain no pollutants, but may be non-potable from upland stock ponds. No quantity of water to be used for construction purposes may be taken from a 404 stream, prior to the proper authorizations or permits being obtained by the Contractor.
20. Contractor is to direct workers and sub-contractors to use portable sanitary facilities provided by the Contractor and not to trespass off ROW.
21. Contractor will provide written verification to TxDOT that earth borrow pits and disposal sources meet environmental and regulatory requirements, prior to use. Excavations will meet all OSHA requirements and the current safety guidelines established for TxDOT Quarries and Pits.
22. Boundary silt fences that are terminated down slope, with one end being at the lowest elevation, will be installed with an L - hook to contain sediment. Boundary silt fences that are installed on flat ground will have L-hooks on both ends.
23. Rock filter dams across ditches will be constructed where the rock filter dam ends are embedded within the ditch side slopes and ditch bottom. The top center elevation of the rock filter dam will be at least 6 inches lower than the elevations on the rock filter dam ends.
24. Silt fence will be constructed in a U or V pattern across ditch lines and up the ditch side slope to keep storm water from flowing around the ends of the silt fence. Small silt fences that do not adequately span the ditch and allows storm water around the end(s) will not be used. Where there is adequate space, large U pattern silt fences are preferred to facilitate sediment collection and sediment removal with equipment.
25. Sediment controls (RFDs or silt fences) will be located along road ditches as marked on the SWPPP drawings. Modifications to the sediment control spacing will be adjusted during the project based on sediment control effectiveness. The installation and maintenance of sediment controls at or near outfalls, where storm water leaves TxDOT ROW, takes persistent over ditch line sediment controls.

SCALE = NTS SHEET 2 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 47 | |

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

26. Storm water draining sheet flow over disturbed soil sloped towards the ROW property line, will be intercepted by a boundary silt fence typically installed with L-shaped ends.
27. For ditch grading and shoulder up work, the Contractor is limited during good weather to remove up to one mile (limited to five acres of disturbed soil) of ditch line sediment controls; on one side of the roadway. Outfall controls cannot be removed during this activity. Ditch line controls must be replaced upon completion of work and before the next rain event.
28. Sediment controls damaged by the Contractor, as defined by permit, must be fixed or replaced immediately upon discovery.
29. Notches in silt fences are not typically allowed. Specific silt fences that back up water onto lanes of traffic may be notched if approved.
30. For silt fence maintenance, the Contractor will leave approximately 4 inches of deposited sediment up stream of silt fences and not over excavate around silt fences or rock filter dams.
31. The Contractor will inform TxDOT of new construction areas and where soil is planned to be disturbed. Sediment controls will be installed at outfalls prior to the Contractor beginning soil disturbing activities up slope from the outfall.
32. Water from concrete saw cutting, concrete grinding and concrete coring activities; or fine materials from concrete chipping and salvage will not be allowed to enter storm drains or enter streams.
33. Storm water containing suspended sediment and turbidity needing to be removed from excavations or low areas will be pumped or gravity drained through vegetated buffer strips (50 foot minimum) or placed in ditches with temporary sediment controls, prior to the water being discharged into a stream.
34. Uncontaminated water from natural groundwater seepage, springs, foundations and drains that does not contain suspended sediment or any pollutants may be discharged without storm water controls.
35. Lime or cement if spilled in ditches or outside the defined limits of application is considered a pollutant and will be excavated and removed the same day, to avoid contaminating streams.
36. If located along the project ROW, RAP stockpiles will be located where there is a minimum 100 feet of vegetative buffer strip before storm water will reach a stream. RAP will not be used as a construction material within the Ordinary High Water Marks of a stream channel of a 404 designated stream.
37. If allowed on the project, concrete truck wash out areas will have adequate volume to allow 12 inch freeboard for rain and will be lined with 6 mils of plastic. No concrete will be stored higher than the 12 inch freeboard. Cleaning of truck chutes and equipment does not constitute concrete truck wash out and this activity may be completed at the concrete placement location. Wash out areas will not be located closer than 50 ft from down slope inlets or stream channels.
38. For outfalls near stock ponds closer than 50 foot from disturbed soil at the ROW line, redundant sediment controls will be provided, typically a combination of rock filter dam and a silt fence constructed in line of the flow.
39. Earth stockpiles will utilize silt fence sediment controls, positioned on the low end of the stockpile drainage area with L-hooks or silt fence installed around the entire stockpile.
40. Sediment controls including rock filter dams and silt fences will not be installed across any 404 streams. Sediment controls at 404 streams will be positioned to limit sediment entering the stream from the banks and around structures/culverts, and will allow free flow of storm water to pass through the ROW without being dammed by any sediment controls. Remove loose materials from stream channels prior to each rain event.
41. Sediment controls for non-404 streams may be constructed across the drainage channel in unlimited locations. It is appropriate to use sediment control details typically used for 404 streams for non-404 streams when flow velocities are high. Remove loose material from stream channels prior to each rain event.
42. Incomplete drainage pipe installation across the roadway does not remove the requirement for having sediment controls around the ends of the pipe. To stay within permit requirements, sediment controls should be installed over and around the terminated end and along each side of the banks as soon as construction on the pipe has been completed. Remove loose material from stream channels prior to each rain event.
43. Safety end / headwall construction temporarily will require the removal of part of the sediment control placed over and around the pipe end. Retain in place as much functioning sediment control as possible. Replace the silt fence over and around the top of the pipe, immediately upon concrete placement and form removal. Do not remove culvert sediment controls that cannot be replaced before the next rain event. Sediment control at the ends of culverts must be in place and available for any rain event until the disturbed soil areas are re-vegetated.

SCALE = NTS SHEET 3 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 48 | |

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

44. Between the Ordinary High Water Marks of a 404 stream channel, the Contractor will disturb only the minimum amount of stream channel that is necessary to complete the work.
45. Rock riprap for erosion control does not replace the requirements to maintain sediment control until vegetation is re-established. Replace sediment controls immediately after installing erosion rock.
46. At the direction of TxDOT, sediment deposited into existing and new culverts will be removed subsidiary to Item 506. Sediment to be removed is either pre-existing material before construction starts or sediment generated as a part of this project.
47. Provide treated 2X4 cross bracing for rectangular inlet silt fence, subsidiary to Item 506.
48. Loose or granular earth materials will not be used to repair silt fence undercuts. Silt fence undercut repairs will be conducted with well compacted soils or the silt fence will be reset in a nearby location.
49. Silt fence steel T posts of approximately 1.25 pounds per foot are allowed at a spacing of 8 feet or less. Silt fence steel T posts between approximately 1.25 pounds per foot and 0.85 pounds per foot are allowed for T post spacing of 5 feet or less.
50. Silt fence to be used to slow the flow of storm water down slopes will be positioned approximately horizontal (on the contour) with L hooks on the ends and limited to approximately 200 feet in length. Multiple sections and levels of silt fence may be required in addition to temporary / permanent erosion control flumes.
51. Soil retention blankets will be installed rolled down the slope with the small dimension side embedded at the top of slope, unless recommended otherwise by the manufacturer. Excess grass, rocks, trash, debris or clods will be removed before seeding and installing soil retention blankets. All installations will be by the manufacturer recommendations. Contractor equipment, including tractor mowers will be kept off areas with soil retention blankets until the grass is established.





SCALE = NTS SHEET 4 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------|-------------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. | SH 22, ETC. |
| DEC 2013 | DIST | COUNTY | | SHEET NO. |
| FEB 2015 | WACO | HILL, ETC. | | 49 |



| | |
|--|------------------------|
| | SEDIMENT CONTROL FENCE |
| | ROCK FILTER DAM (TY 2) |
| | ROCK FILTER DAM (TY 3) |
| | DIRECTION OF FLOW |

- NOTES:
- ① EXTEND SILT FENCE SO STORM WATER DOES NOT GO AROUND THE ENDS. USE L-HOOKS ON ENDS AS REQUIRED.
 - ② EXTEND ROCK FILTER DAM SO STORM WATER DOES NOT GO AROUND THE ENDS.





SCALE = NTS SHEET 5 OF 10

Texas Department of Transportation
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 50 | |



| | |
|--|------------------------|
| | SEDIMENT CONTROL FENCE |
| | ROCK FILTER DAM (TY 2) |
| | ROCK FILTER DAM (TY 3) |
| | DIRECTION OF FLOW |

- NOTES:
- PROVIDE OVERLAP OF SILT FENCE WITH ROCK FILTER DAM.
 - USE SILT FENCE L-HOOKS ON ENDS TO BLOCK STORM WATER SEDIMENT


SCALE = NTS SHEET 6 OF 10




TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 51 | |




BEST MANAGEMENT PRACTICE (BMP) #9
STOCKPILE SEDIMENT CONTROL




BEST MANAGEMENT PRACTICE (BMP) #10
FOR 404 OR NON-404 STREAMS ONLY ~
SEDIMENT CONTROL AT PHASED CONSTRUCTION OF BRIDGE CLASS CULVERTS

| | |
|--|------------------------|
| | SEDIMENT CONTROL FENCE |
| | ROCK FILTER DAM (TY 2) |
| | ROCK FILTER DAM (TY 3) |
| | DIRECTION OF FLOW |

- NOTES:
- START SEDIMENT CONTROL AT LOCATION SO ALL STORM WATER WITH SEDIMENT IS COLLECTED
 - ROCK FILTER DAMS OR EARTH/GRASSED EMBANKMENTS CAN BE SUBSTITUTED AS DIRECTED.
 - PROVIDE A SMOOTH TRANSITION FROM THE INVERT ELEVATIONS BETWEEN CULVERTS. REMOVE LOOSE SOIL FROM EXCAVATED AREA BETWEEN CULVERTS.
 - PROVIDE AND INSTALL PNEUMATICALLY PLACED CONCRETE ON THE DITCH BOTTOM AND SIDE SLOPES BETWEEN TEMPORARY TERMINATIONS BETWEEN OLD AND NEW CULVERTS. PNEUMATICALLY PLACED CONCRETE WILL BE PLACED TO THE HEIGHT OF THE LARGEST CULVERT ON THE DITCH SIDE SLOPES; AND TO A LIMIT 10 FEET OUTSIDE THE LOCATION OF BMPs ALONG THE DITCH BOTTOM. CEMENT STABILIZED SAND MAY BE SUBSTITUTED FOR PNEUMATICALLY PLACED CONCRETE, IN AREAS WHERE INSTALLATION WORKS AND AT THE OPTION OF TXDOT.



BEST MANAGEMENT PRACTICE (BMP) #11
BOUNDRY SEDIMENT CONTROL ~ BOTH ENDS OF CONTROL TERMINATED UP SLOPE



BEST MANAGEMENT PRACTICE (BMP) #12
BOUNDRY SEDIMENT CONTROL ~ BOTH ENDS OF CONTROL TERMINATED DOWN SLOPE


SCALE = NTS SHEET 7 OF 10

Texas Department of Transportation
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| ©TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 52 | |




BEST MANAGEMENT PRACTICE (BMP) #13

USE OF VEGETATIVE BUFFERS IN PLACE OF TEMPORARY SEDIMENT CONTROLS SUCH AS SILT FENCE AND ROCK FILTER DAMS

| | |
|--|------------------------|
| | FULLY GRASSED DITCH |
| | DISTURBED AREA |
| | DIRECTION OF FLOW |
| | SEDIMENT CONTROL FENCE |

- ① FOR H DIMENSIONS LESS THAN 1.5' SILT FENCE MAY NEED TO BE NOTCHED AS SHOWN IN VIEW A-A. ADD EXTRA POSTS AT NOTCH.
- ② BMP #14 MAY BE USED AT CROSS DRAINAGE STRUCTURES AS DIRECTED.



BEST MANAGEMENT PRACTICE (BMP) #14

NON-404 STREAMS AND DITCHES ONLY - SEDIMENT CONTROL AT PARALLEL DRAINAGE STRUCTURE ENTRANCE ②


SCALE = NTS SHEET 8 OF 10

Texas Department of Transportation
Waco District Standard


TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 53 | |




BEST MANAGEMENT PRACTICE (BMP) #15
CONCRETE TRUCK WASHOUT AREA




BEST MANAGEMENT PRACTICE (BMP) #16
PUMPED STORM WATER SEDIMENT CONTROLS ①

| | |
|--|------------------------|
| | FULLY GRASSED DITCH |
| | DIRECTION OF FLOW |
| | SEDIMENT CONTROL FENCE |
| | ROCK FILTER DAM (TY 2) |
| | ROCK FILTER DAM (TY 3) |

- ① PUMPED STORM WATER FROM AN EXCAVATION AREA SHOULD BE DISCHARGED IN A 50' VEGETATIVE BARRIER OR THROUGH TWO TEMPORARY SEDIMENT CONTROLS BEFORE ENTERING A 404 STREAM.
- ② FOR LANDOWNER STOCKPONDS WITHIN 50' OF THE RIGHT OF WAY LINE, PROVIDE REDUNDANT SEDIMENT CONTROLS AT THE CONVEYANCE OF THE POND. MINIMUM OF TWO SEDIMENT CONTROLS.
- ③ WHEN CONTAINMENT AREA REACHES 1' FREEBOARD, DISCONTINUE WASHOUT PLACEMENT AND REMOVE MATERIAL UPON SOLIDIFICATION.
- ④ EACH TIME SOLIDIFIED MATERIAL IS REMOVED REPLACE PLASTIC SHEETING.



BEST MANAGEMENT PRACTICE (BMP) #17
HORIZONTAL INLET SEDIMENT CONTROL



BEST MANAGEMENT PRACTICE (BMP) #18
LANDOWNER STOCKPOND SEDIMENT CONTROL ②


SCALE = NTS SHEET 9 OF 10

Texas Department of Transportation
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES


TA-BMP

| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| ©TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 54 | |



| | |
|--|------------------------|
| | DIRECTION OF FLOW |
| | SEDIMENT CONTROL FENCE |
| | ROCK FILTER DAM |
| | SECURITY FENCING |

- ① HAY BALES MAY BE SUBSTITUTED FOR SILT FENCE OVER THE STREAM CROSSING.
- ② CROSSING WILL BE AS PER REQUIREMENTS OF THE WATERS OF THE US GENERAL NOTES.
- ③ INSTALL SILT FENCE SLIGHTLY UP FROM OHW MARK FROM R.O.W. TO R.O.W.
- ④ USE SILT FENCE L-HOOKS ON LEVEL OR DOWN SLOPING ENDS TO BLOCK STORM WATER SEDIMENT
- ⑤ INSTALL LARGE V OR U SHAPED BMP'S FROM ABUTMENT AS SHOWN. IF THERE IS STEEP DITCH CONDITIONS DECREASE SPACING AND CONSIDER RFD'S. ADD ADDITIONAL BMP'S IF GRADE IS STEEP OR IF FLOW IS HIGH.



SCALE = NTS SHEET 10 OF 10




TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP


| | | | | |
|----------------------|-----------|------------|-----------------------|-----------|
| FILE: BMPLAYOUTS.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT 2009 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| DEC 2013 | DIST | COUNTY | SHEET NO. | |
| FEB 2015 | WACO | HILL, ETC. | 55 | |

502422022
 T:\116\TRAFFIC\Traffic Control Devices\Traffic Signal Data Files\021_FM_116 at Lutheran Church Rd\RTZ_Phase 5 Signal Improvements\0121-02-062\Standards\EC(1)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES


1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING


| | | | | | |
|--|-----------|------------|--------|--------------------------|--|
| | | | | Design Division Standard | |
| TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16 | | | | | |
| FILE: ec116 | DN: TxDOT | CK: KM | DW: VP | DN/CK: LS | |
| © TxDOT: JULY 2016 | CONT | SECT | JOB | HIGHWAY | |
| REVISIONS | | 0121 | 02 | 062, ETC. SH 22, ETC. | |
| | DIST | COUNTY | | SHEET NO. | |
| | WACO | HILL, ETC. | | 56 | |

DATE: 5/24/2022
 FILE: T:\WACTRAFF\TRAFFIC Control Devices\Traffic Signal\021-FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062-Standards\EC(2)-16.
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




FILTER DAM AT TOE OF SLOPE

(RFD1)




FILTER DAM AT SEDIMENT TRAP

(RFD1) OR (RFD2)




FILTER DAM AT CHANNEL SECTIONS


(RFD1) OR (RFD2) OR (RFD3)




PLAN VIEW




"V" SHAPE PLAN VIEW




SECTION B-B



PROFILE




SECTION C-C



TYPE 4 (SACK GABIONS)

(RFD4)



SECTION A-A

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)

| | | | |
|---|-----------|--------------------------|-----------------------|
| | | Design Division Standard | |
| TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC(2)-16 | | | |
| FILE: ec216 | DN: TxDOT | CK: KM | DW: VP |
| © TxDOT: JULY 2016 | CONT | SECT | JOB |
| REVISIONS | 0121 | 02 | 062, ETC. SH 22, ETC. |
| | DIST | COUNTY | SHEET NO. |
| | WACO | HILL, ETC. | 57 |

DATE: 5/24/2022
 FILE: T:\WACTRAFFIC\Traffic Control Devices\Signal\Signal Data Files\021_FM 116 at Lutheran Church Rd\RTZ Phase 5 Signal Improvements\0121-02-062\Standards\EPIC.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- 1.
2. No Action Required Required Action

Action No.

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
4. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 1.
- 2.
- 3.
- 4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

| Erosion | Sedimentation | Post-Construction TSS |
|--|--|--|
| <input type="checkbox"/> Temporary Vegetation | <input type="checkbox"/> Silt Fence | <input type="checkbox"/> Vegetative Filter Strips |
| <input type="checkbox"/> Blankets/Matting | <input type="checkbox"/> Rock Berm | <input type="checkbox"/> Retention/Irrigation Systems |
| <input type="checkbox"/> Mulch | <input type="checkbox"/> Triangular Filter Dike | <input type="checkbox"/> Extended Detention Basin |
| <input type="checkbox"/> Sodding | <input type="checkbox"/> Sand Bag Berm | <input type="checkbox"/> Constructed Wetlands |
| <input type="checkbox"/> Interceptor Swale | <input type="checkbox"/> Straw Bale Dike | <input type="checkbox"/> Wet Basin |
| <input type="checkbox"/> Diversion Dike | <input type="checkbox"/> Brush Berms | <input type="checkbox"/> Erosion Control Compost |
| <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Mulch Filter Berm and Socks |
| <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks |
| <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Vegetation Lined Ditches |
| | <input type="checkbox"/> Stone Outlet Sediment Traps | <input type="checkbox"/> Sand Filter Systems |
| | <input type="checkbox"/> Sediment Basins | <input type="checkbox"/> Grassy Swales |

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required
- Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required
- Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required
- Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

| | |
|---|---|
| BMP: Best Management Practice | SPCC: Spill Prevention Control and Countermeasure |
| CGP: Construction General Permit | SW3P: Storm Water Pollution Prevention Plan |
| DSHS: Texas Department of State Health Services | PCN: Pre-Construction Notification |
| FHWA: Federal Highway Administration | PSL: Project Specific Location |
| MOA: Memorandum of Agreement | TCEQ: Texas Commission on Environmental Quality |
| MOU: Memorandum of Understanding | TPDES: Texas Pollutant Discharge Elimination System |
| MS4: Municipal Separate Stormwater Sewer System | TPWD: Texas Parks and Wildlife Department |
| MBTA: Migratory Bird Treaty Act | TxDOT: Texas Department of Transportation |
| NOT: Notice of Termination | T&E: Threatened and Endangered Species |
| NWP: Nationwide Permit | USACE: U.S. Army Corps of Engineers |
| NOI: Notice of Intent | USFWS: U.S. Fish and Wildlife Service |

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes
- No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes
- No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required
- Required Action

Action No.

- 1.
- 2.
- 3.


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required
- Required Action

Action No.

- 1.
- 2.
- 3.

| | | | |
|--|------|---|-----------------------|
|  Texas Department of Transportation | | <i>Design Division Standard</i> | |
| ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC | | | |
| FILE: epic.dgn | DN: | CK1: | CK2: |
| ©TxDOT: February 2015 | CONT | SECT | HIGHWAY |
| 12-12-2011 (DS) 05-07-14 ADDED NOTE SECTION IV. 01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES. | 0121 | 02 | 062, ETC. SH 22, ETC. |
| | DIST | COUNTY | SHEET NO. |
| | WACO | HILL, ETC. | 58 |