

FHWA TEXAS DIVISION	PROJECT NO.	SHEET NO.	
	C 911-00-113	1	
STATE	DISTRICT	COUNTY	
TEXAS	LFK	ANGELINA	
CONTROL	SECTION	JOB	HIGHWAY NO.
0911	00	113	VA

SEE SHEET 2 FOR INDEX OF SHEETS

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT
STATE PROJECT NO. C 911-00-113

VARIOUS
ANGELINA COUNTY

FUNCTIONAL CLASS.: N/A
DESIGN SPEED = N/A

FINAL PLANS

LETTING DATE: _____
DATE CONTRACTOR BEGAN WORK: _____
DATE WORK WAS COMPLETED: _____
DATE WORK WAS ACCEPTED: _____
FINAL CONTRACT COST: \$ _____
CONTRACTOR: _____

CONSTRUCTION WORK ON THIS PROJECT WAS PERFORMED IN ACCORDANCE WITH PLANS, CONTRACT AND APPROVED CHANGE ORDERS.

_____ DATE _____

LIMITS: VARIOUS LOCATIONS DISTRICTWIDE

FOR THE CONSTRUCTION OF BRIDGE MAINTENANCE
CONSISTING OF BRIDGE REPAIR MAINTENANCE

FOR LOCATION MAP
SEE SHEETS 3-5

BARRICADES AND WARNING SIGNS

PROVIDE AND ERECT BARRICADES AND WARNING SIGNS IN ACCORDANCE WITH THE BARRICADE & CONSTRUCTION STANDARDS, TCP STANDARDS, THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" AND AS DIRECTED.

RAILROAD CROSSINGS

SITE	COUNTY	STRUCTURE ID	LATITUDE	LONGITUDE	HIGHWAY
2	ANGELINA	11-003-0-2553-01-012	31.37115118	-94.73132054	SL 287



RECOMMENDED FOR LETTING: 7/7/2022 APPROVED FOR LETTING: 7/7/2022

NO EXCEPTIONS
NO EQUATIONS

DocuSigned by:
Jennifer Adams
CE1DDBE07C00426...
DISTRICT ADVANCE TRANSPORTATION
PLANNING DIRECTOR

DocuSigned by:
Kelly A. Morris, P.E.
F044211639424B4...
DISTRICT ENGINEER

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION ON NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: SPECIAL LABOR PROVISIONS FOR STATE PROJECTS (000---008).

© 2022 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED

FILE: c:\txdot\pwworking\one\txdot\3\cathy_loerch\d0521927\LFK*TitleSheet*Dist Rev.dgn
DATE: 7/6/2022 10:48:34 PM

SHEET NO. DESCRIPTION

GENERAL
 1 TITLE SHEET
 2 INDEX OF SHEETS
 3-5 LOCATION MAPS
 6, 6A-6C GENERAL NOTES
 7 ESTIMATE & QUANTITY SHEET
 8 QUANTITY SUMMARIES

TRAFFIC CONTROL PLAN
 # 9-20 BC(1)-21 THRU BC(12)-21
 # 21 TCP(2-1)-18
 # 22 TCP(2-2)-18
 # 23 TCP(2-3)-18
 # 24 TCP(2-4)-18
 # 25 TCP(2-5)-18
 # 26 TCP(2-6)-18
 # 27 WZ(BRK)-13
 # 28 WZ(RS)-22

BRIDGE
 29-54 BRIDGE LAYOUTS
 55 SITE 12 GABION DETAILS
 56 T501 BRIDGE RAIL

ENVIRONMENTAL ISSUES
 57 TXDOT SWP3 INDEX
 58-59 EPIC
 # 60 EC(1)-16

MISCELLANEOUS
 61 RAILROAD SCOPE OF WORK
 62-63 RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS



DocuSigned by:
 Mitchell L. Randall, P.E.
 FF6D8503742F43A...

7/25/2022

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED BY # HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

DocuSigned by:
 Mitchell L. Randall, P.E. 7/25/2022
 FF6D8503742F43A...
 MITCHELL L. RANDALL, P.E. DATE

7/24/2022 4:06:31 PM c:\txdot\pwworking\line\txdot3\cathy. loerch\0521927\index of sheets.dgn

INDEX OF SHEETS			
TEXAS DEPARTMENT OF TRANSPORTATION ©2022			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY		SHEET NO.
LFK	ANGELINA		2

GENERAL NOTES:

Existing regulatory, warning and guide signs within project limits are to remain visible to the traveling public at all times. If a sign must be repositioned during construction operations, move and install the sign to an approved location. Use care when working near existing signs and repair or replace signs damaged by work operations. All work involved repositioning existing signs will be subsidiary to various bid items.

Furnish materials and make repairs to the existing roadway at any location damaged by construction operations. This work shall be done in an approved manner and will be subsidiary to various bid items.

Ensure drainage structures and outfall channels constructed on this project are free of silt and debris at the time of project acceptance. Final clean out work will be subsidiary to various bid items.

Maintain adequate surface drainage throughout the project limits during all phases of construction.

Provide suitable access at all times to adjacent businesses, private property and side roads.

When construction work necessitates the moving of mailboxes, temporarily relocate them as necessary to keep them clear of construction operations and convenient for the mail carrier. Mounts for temporarily relocating mailboxes shall conform to the Department's "Compliant Work Zone Traffic Control Device List" or the mailbox standard. Temporary relocation of mailboxes will be subsidiary to various bid items.

Remove dirt, silt, rocks, debris and other foreign matter that accumulates in structures due to the Contractor's operations as directed. Keep stream channels open at all times. This work will not be paid for directly, but will be subsidiary to pertinent Items.

Contractor questions on this project are to be addressed to the following individual(s):

Clint Jones, Area Engineer Clint.Jones@txdot.gov
Homar Munoz, Asst. Area Engineer Homar.Munoz@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

The contractor's attention is directed to the EPIC sheet(s) included in this plan set for additional information regarding environmental permits, issues, and commitments.

Project Mowing

Mow at locations where contract work, equipment or stockpiles conflict with TxDOT's mowing operations. Mowing will not be measured or paid for directly, but will be subsidiary to various bid items.

The equipment used for mowing shall consist of approved mowing units capable of mowing on slopes without marring finished slope surfaces or injuring existing growth. The minimum cutting width shall not be less than 5 ft., unless otherwise approved.

Mow all areas of existing vegetation and vegetation placed during the project as directed. The mowing height shall be 5 in. unless otherwise directed. Repair portions of sod or grass that are injured during mowing operations as directed.

Mow as close as possible to all fixed objects, exercising extreme care not to damage trees, plants, shrubs, signs, delineators or other appurtenances which are part of the facility. Hand trim around such objects, unless otherwise specified.

Use safety chains or other manufacturer's safety device to prevent damage to people or property caused by flying debris propelled out from under rotary mowers. Chains shall be a minimum size of 5/16 in. and links spaced side by side around the mower's front, sides and rear. When mowing at the specified cutting height, the chains shall be long enough to drag the ground. If at any time, it is determined mowing or trimming equipment is defective to the point that it may affect the quality of work or create an unsafe condition, then that equipment shall be immediately repaired or replaced.

Litter Pickup

In addition to the requirements in Item 5, Section 11, Final Cleanup; remove litter from the right of way at locations where the Contractor may be required to mow. Litter pickup will not be measured or paid for directly, but will be subsidiary to various bid items.

The equipment used for litter pickup shall be approved.

Collect and dispose of all litter deposited by construction operations or the traveling public including cans, bottles, paper, plastic items, metal scraps, lumber, etc. from within the project right of way or as directed. Properly dispose of all collected litter. Do not dump or stockpile collected litter on State property.

For removal of large dead animals, contact nearest TxDOT maintenance section for disposal instructions. Do not bury animal carcasses on State property.

Item 5: Control of the Work

In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others. An extension of working time may be granted for any delays caused by the utility adjustments if deemed necessary.

Precast Alternate Proposals.

“When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with “Standard Operating Procedure for Alternate Precast Proposal Submission” found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.”

Item 7: Legal Relations and Responsibilities

No significant traffic generator events identified.

To prevent the spread of Zebra Mussels and other exotic species:

1. Spray/rinse all equipment and vehicles, using hot and/or high-pressure water as soon as possible after exiting the waterbody.
2. Drain all water from receptacles before leaving the area.
3. Allow all equipment to dry completely before use in another waterbody.
4. If Zebra Mussels are encountered at the project location, contractor will not transport any equipment from the site and will notify the TxDOT project engineer immediately.

For more detailed information, see Texas Parks and Wildlife Website.

Work in this contract is required to be done on railroad property. Cooperate with the railroads and comply with all of their requirements including obtaining required insurance and training before performing work on railroad property.

This project consists of discrete construction projects separated a minimum ¼ mile by undisturbed areas: therefore they are treated as separate plans of development. These separate plans of development disturb less than 1 acre, however, the contractor shall place BMP's as directed. The disturbed area in the plans and the Contractor project specific locations (PSLs) within 1 mile of the project limits will further establish the authorization requirements for storm water discharges. If the total area disturbed shown in the plans and PSLs within 1 mi. of the project limits exceeds 1 acre, the engineer will develop an SWP3 site plan and post a small construction site notice for the construction activities.

Dispose of all vegetative matter and any other materials removed from State Right of Way in accordance with applicable environmental laws, rules, regulations and requirements.

Burning locations must be approved by the Engineer prior to beginning. Burning activities must be conducted in compliance with Texas Commission on Environmental Quality (TCEQ) regulations. Notify the Engineer when burning activities will take place.

In order to maintain compliance with Chapter 64 of the Texas Parks and Wildlife Code and Migratory Bird Treaty Act (MBTA), construction activities that may affect nests (i.e. tree removal, tree limbing, bridge work) shall be conducted outside of the nesting season (March 15 to September 15). In the event birds or active nests (eggs and/or nestlings present) are encountered, contact the engineer prior to conducting work.

Item 8: Prosecution and Progress

For this project, working days will be computed and charged in accordance with Item 8, Section 3.1.4 “Standard Workweek”.

No lane closures will be allowed after Noon on Fridays or on days preceding National Holidays on US 59 unless otherwise approved.

Submit monthly progress schedules no later than the 20th calendar day of the month. Failure to comply with this deadline may result in the Engineer withholding progress (monthly) payments.

Provide a Critical Path Method (CPM) Construction Schedule unless otherwise approved.

Item 110: Excavation**Item 132: Embankment**

Hauling materials with scrapers across or along existing roadways will not be permitted without written permission.

Compact embankment material used to reshape existing slopes to a density comparable with adjacent undisturbed material to the satisfaction of the Engineer.

Item 400: Excavation and Backfill for Structures

Replace excavated material deemed unsuitable for backfilling with material approved by the Engineer, paid for under the pertinent bid items or as extra work. This provision does not apply to excavated materials that are too wet and are replaced for the contractor's convenience to expedite the work.

When excavation does not generate enough material to complete the backfill, additional material must be approved prior to use. Additional material will be subsidiary to various bid items.

Item 432: Riprap

Stone riprap will require the placement of filter fabric prior to placement of stones.

Welded wire fabric will not be allowed for reinforcing concrete riprap. Reinforcing shall consist of No. 3 or 4 bars meeting the requirements of grade 60 reinforcing steel. Place bars on 12 in. centers in each direction, supported on reinforcing chairs.

Item 438: Cleaning and Sealing Existing Joints

Cleaning and sealing of existing joints shall be performed during the cooler months to avoid excess expansion as directed by the engineer.

Item 459: Gabions and Gabion Mattresses

Type 2 filter fabric will be required beneath all gabions and gabion mattresses.

Anchor pins for securing the fabric shall be 3/16 in. diameter steel bars pointed at one end and fabricated with a head to retain a steel washer having an outside diameter of not less than 1.5 in. The pin length shall be not less than 18 in. U-shaped pins will be an acceptable option.

Item 480: Cleaning Existing Culverts

Certain box culverts will require cleaning to remove silt and other debris. Waters carried by these box culverts have been determined to be waters of the United States and are under jurisdiction of the U.S. Army Corps of Engineers. Silt and other debris removal shall be immediately hauled to an upland location for dumping. Material will not be side cast into either the water channel or its banks. Removal of the sediment is limited to the minimum necessary to restore the waterway to its configuration when the structure was built. No work will be allowed outside of the right-of-way. This work shall also be restricted to a distance of no more than 10 ft. from the end of the structure.

Item 502: Barricades, Signs, and Traffic Handling

Traffic Control Plan (TCP):

Ensure the Contractor's Responsible Person (CRP) or their alternate for Barricades, Signs and Traffic Handling is available at all times and able to receive instructions from the Engineer or authorized Department representative. The CRP shall be a person that is usually at the project site during normal working hours.

For protection of the traveling public, direct traffic through the work area using signs, flaggers and other devices. Required signs are shown in the plans on the Barricade and Construction Standards and Traffic Control Plan Sheets. The latest edition of the "Texas Manual on Uniform Traffic Control Devices" shall also be used as a guide for handling traffic on this project.

Restrict construction work to single lane widths with only minor disruptions in traffic flow. Lane closures shall conform to the Traffic Control Plan for lane closures as shown in the plans. No overnight closures will be permitted.

Limit lane closures for multilane roads (4 or more lanes) to 2 mi. in length, unless otherwise approved.

Limit lane closures for 2 lane roads to 1 mi. in length, unless otherwise approved.

Lane closure lengths can exclude the end tapers.

Plan the sequence of work to minimize the time lane closures are in place. Install lane closures only where construction operations are anticipated to start within 1 hr. and limited to the amount of lane that can be reached by the construction activity within 2 hr. unless otherwise approved.

Provide flashing arrow panels to supplement required signs and devices for lane closures.

Provide temporary rumble strips as shown on work zone rumble strip standards.

Provide adequate flaggers to protect the traveling public when working on or near a roadway carrying traffic. All flaggers shall wear hardhats and reflective vests.

Install "Be Prepared to Stop" (CW3-4) and "Flagger Ahead" (CW20-7aD) signs when flaggers are present. Position the signs where good visibility and traffic control can be maintained.

Use a flashing arrow board in addition to the required signs to warn motorists of flaggers.

Use additional flaggers at roadway intersections to direct traffic entering the work area, when deemed necessary by the Engineer.

Open all traffic lanes to traffic at the close of work each day.

Provide one high-intensity yellow, rotating dome-light on all equipment such as distributors, spreader boxes, lay-down machines, dump trucks, rollers, backhoes, road graders, loaders, etc. within the work zone. Mount lights high enough to be visible from all directions and operating when the equipment is in the work zone. On all other equipment such as automobiles, trailers, etc. use emergency flashers while within the work zone.

Install "Slow Down on Wet Road" (CW8-5aT), "Shoulder Drop-Off" (CW8-17), "Uneven Lanes" (CW8-11), "Bump" (CW8-1) and "Soft Shoulder" (CW8-4) signs during construction as directed.

Restrict construction operations so that no drop off along the edge of pavement will remain overnight.

Notify the Engineer prior to placing any materials or equipment on the right of way. Locate equipment, stockpiles or other materials not in use as far as possible from the driving lanes and in no case closer than 30 ft. unless otherwise authorized. Any equipment, stockpiles, or materials placed within 30 ft. of the driving lane must have adequate signs, barricades or other warning devices as approved. As a minimum place an 8 ft. wide TY III Barricade or barrels on the approach side of each site that is within 30 ft. of the driving lane. Use TY III Barricade or

barrels for the site similarly on the departure side if the location is within 30 ft. of the opposing traffic lane.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Texas Transportation Code 547.105 authorizes the use of warning lights to promote safety and provides an effective means of gaining the travelling public's attention as they drive in areas where construction crews are present. In order to influence the public to move over when high risk construction activities are taking place, minimize the utilization of blue warning lights. These lights must be used only while performing work on or near the travel lanes or shoulder where the travelling public encounters construction crews that are not protected by a standard work zone set up such as a lane closure, shoulder closure, or one-way traffic control. Refrain from leaving the warning lights engaged while travelling from one work location to another or while parked on the right of way away from the pavement or a work zone.

Temporary stop lines as shown on TCP (2-2)-18 should be omitted.

Provide an illuminated flagger station when nighttime work is performed.

All workers on TxDOT right-of-way shall wear reflective clothing meeting ANSI Class II requirements during the day and ANSI Class III requirements during the night.

Item 506: Temporary Erosion, Sedimentation, and Environmental Controls

Locations and types of BMPs may require adjustments prior to or after placement as directed by the Engineer. Adjustments should be made to ensure BMPs are working effectively and maintain compliance with Section 404/401 permit requirements. Notify the Engineer prior to making adjustments.

This project does not require coverage under the CGP; however, any erosion or sediment controls deemed necessary by the Engineer shall be installed as directed. Should this work become necessary, it will be paid for in accordance with Article 4.4, "Changes in the Work".

Other erosion or sediment control measures deemed necessary by the Engineer will be paid for in accordance with article 4.4, "Changes in the Work".

Place temporary sediment control fence at locations as directed.

Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

Two (2) TMAs (stationary) will be required for this project. The contractor will be responsible for determining if multiple operations will be ongoing at the same time to determine the total number of TMAs needed for the project.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0911-00-113

DISTRICT Lufkin
HIGHWAY Various

COUNTY Angelina

CONTROL SECTION JOB				0911-00-113		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00140123			
COUNTY				Angelina			
HIGHWAY				Various			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	104-6009	REMOVING CONC (RIPRAP)	SY	90.000		90.000	
	132-6003	EMBANKMENT (FINAL)(ORD COMP)(TY B)	CY	20.000		20.000	
	401-6001	FLOWABLE BACKFILL	CY	24.000		24.000	
	429-6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	150.500		150.500	
	432-6027	RIPRAP (STONE COMMON)(DRY)(24 IN)	CY	395.000		395.000	
	438-6001	CLEANING AND SEALING EXISTING JOINTS	LF	730.000		730.000	
	459-6001	GABIONS (GALV)	CY	54.000		54.000	
	459-6009	GABIONS (3' X 3')(GALV)	CY	70.000		70.000	
	466-6153	WINGWALL (FW - 0) (HW=6 FT)	EA	1.000		1.000	
	466-6159	WINGWALL (FW - S) (HW=12 FT)	EA	2.000		2.000	
	480-6001	CLEAN EXIST CULVERTS	EA	2.000		2.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	10.000		10.000	
	506-6020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	500.000		500.000	
	506-6024	CONSTRUCTION EXITS (REMOVE)	SY	500.000		500.000	
	778-6021	CONCRETE RAIL REPLACEMENT (TYPE 501)	LF	4.000		4.000	
	6185-6002	TMA (STATIONARY)	DAY	33.000		33.000	
	7000-6001	REML & DISPL DRIFTWOOD & DEBRIS	CY	30.000		30.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	

SUMMARY OF BRIDGE MAINTENANCE

SITE	COUNTY	STRUCTURE ID	HIGHWAY	FEATURE CROSSED	ITEM NO.	104	132	401	429	432	438	459	459	466	466	480	778	7000
					BID CODE	6009	6003	6001	6007	6027	6001	6001	6009	6153	6159	6001	6021	6001
					REMOVING CONC (RIPRAP)	EMBANKMENT (FINAL) (ORD COMP) (TY B)	FLOWABLE BACKFILL	CONC STR REPAIR (VERTICAL & OVERHEAD)	RIPRAP (STONE COMMON) (DRY) (24 IN)	CLEANING AND SEALING EXISTING JOINTS	GABIONS (GALV)	GABIONS (3' X 3') (GALV)	WINGWALL (FW - 0) (HW=6 FT)	WINGWALL (FW - S) (HW=12 FT)	CLEAN EXIST CULVERTS	CONCRETE RAIL REPLACEMENT (TYPE 501)	REML & DISPL DRIFTWOOD & DEBRIS	
					SY	CY	CY	SF	CY	LF	CY	CY	EA	EA	EA	LF	CY	
1	ANGELINA	11-003-0-0319-04-064	SL 287	SH 94 & TSE RR												4		
2	ANGELINA	11-003-0-2553-01-012	SL 287	DRAW											1			
3	ANGELINA	11-003-0-2662-01-001	FM 2109	POPHERS CREEK	90				60									
4	HOUSTON	11-114-0-0931-02-032	FM 1280	WHITE ROCK CREEK					209									
5	POLK	11-187-0-0176-05-049	US 59	SAND CREEK			3		1									
6	POLK	11-187-0-0176-05-050	US 59 SB	WILLS CREEK			3	15.50										
7	POLK	11-187-0-0177-12-038	SL 393	SANSON CREEK									2					
8	POLK	11-187-0-0213-03-096	US 190	KICKAPOO CREEK				15.00										
9	POLK	11-187-0-1193-01-013	FM 942	HICKMAN CREEK			3		4									
10	POLK	11-187-0-1194-01-003	FM 943	MENARD CREEK			3	40.00	24									
11	POLK	11-187-0-1876-01-001	FM 1988	TEMPE CREEK				45.00										
12	POLK	11-187-0-1876-01-004	FM 1988	LONG KING CREEK		20	3		22	160	54	70						
13	POLK	11-187-0-2591-01-001	FM 2610	MENARD CREEK			3	3.00	9								30	
14	SAN JACINTO	11-204-0-2443-02-004	FM 980	POOL CREEK			6											
15	SABINE	11-202-0-0304-03-071	SH 87	PALO GAUCHO BAYOU				32.00	21	570								
16	SHELBY	11-210-0-0742-03-015	FM 2572	STYLES CREEK											1			
17	SHELBY	11-210-0-0743-02-001	FM 138	DRAW					45			1						
PROJECT TOTALS					90	20	24	150.50	395	730	54	70	1	2	2	4	30	

SWP3 SUMMARY

ITEM NO.	506	506
BID CODE	6020	6024
LOCATION	CONSTRUCTION EXITS (INSTALL) (TY 1)	CONSTRUCTION EXITS (REMOVE)
	SY	SY
VARIOUS-AS DIRECTED	500	500
PROJECT TOTALS	500	500

TMA SUMMARY

ITEM NO.	6185
BID CODE	6002
LOCATION	TMA (STATIONARY)
	DAY
VARIOUS-AS DIRECTED	33
PROJECT TOTALS	33

LOCATIONS AND TYPES OF BMP'S MAY REQUIRE ADJUSTMENTS PRIOR TO OR AFTER PLACEMENT AS DIRECTED BY THE ENGINEER. ADJUSTMENTS SHOULD BE MADE TO ENSURE BMP'S ARE WORKING EFFECTIVELY AND MAINTAIN COMPLIANCE WITH SECTION 401 REQUIREMENTS. NOTIFY THE ENGINEER PRIOR TO MAKING ADJUSTMENTS.

QUANTITY SUMMARIES

 TEXAS DEPARTMENT OF TRANSPORTATION ©2022			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY		SHEET NO.
LFK	ANGELINA		8

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:53:54 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) - 21			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
		DW:	TxDOT
		CR:	TxDOT
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
REVISIONS		DIST	COUNTY
4-03	7-13		
9-07	8-14		
5-10	5-21	LFK	ANGELINA
			SHEET NO.
			9


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	091100		113	VA
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	ANGELINA	10	

DATE: 6/17/2022 8:53:56 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\g0521931\bc-21.dgn

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 6/17/2022 8:53:57 PM
FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) -21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT SECT	JOB HIGHWAY
REVISIONS	0911 00	113	VA
9-07 8-14			
7-13 5-21			
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	11	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		091100	113		VA				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	LFK	ANGELINA		12				


DATE: 6/17/2022 8:53:59 PM
FILE: c:\t\tdot\pw_online\t\dot3\catny_loerch\0521921\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	ANGELINA	13	

DATE: 6/17/2022 8:54:00 PM
FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:02 PM
FILE: c:\t\dot\p\online\txdot\catny_loerch\051921\bc-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT


Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CR:	TxDOT
REVISIONS	0911 00	DW:	TxDOT
9-07	8-14	CK:	TxDOT
7-13	5-21	CONT	SECT
		JOB	HIGHWAY
		113	VA
		DIST	COUNTY
		LFK	ANGELINA
		SHEET NO.	14

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 6/17/2022 8:54:04 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



Install a minimum of 3 Barrier Reflectors as per manufacturer's recommendations.

DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0911	00	113	VA				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	LFK	ANGELINA		15				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:05 PM
 FILE: c:\t\dot\pw_online\t\dot\catny_loerch\0521931\bc-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign
substrates shall NOT be used on
plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0911	00	113	VA				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	LFK	ANGELINA	16					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	ANGELINA	17	


DATE: 6/17/2022 8:54:07 PM
FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	LFK	ANGELINA	18	

DATE: 6/17/2022 8:54:08 PM
 FILE: c:\t\dot\pw_online\t\dot3\catny_loerch\0521931\bc-21.dgn

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12

Texas Department of Transportation		Traffic Safety Division Standard
<h1 style="margin: 0;">BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS</h1> <h2 style="margin: 0;">BC(11)-21</h2>		
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT
REVISIONS	JOB	HIGHWAY
2-98 9-07 5-21	0911 00	113 VA
1-02 7-13	DIST	COUNTY
11-02 8-14	LFK	ANGELINA
		SHEET NO. 19


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:10 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	091100		113	VA
1-97 9-07 5-21				
2-98 7-13	DIST	COUNTY		SHEET NO.
11-02 8-14	LFK	ANGELINA		20


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:12 PM
FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\bc-21.dgn

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:19 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\tcp2-1-18.dgn




TCP (2-1a)

WORK SPACE NEAR SHOULDER
 Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
 Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Additional work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.




TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18


FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	0911	00	113	VA
2-94 4-98	DIST:	COUNTY:	SHEET NO.:	
8-95 2-12	LFK	ANGELINA	21	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:26 PM
 FILE: c:\t\dot\pw_online\txdot3\catny_loerch\0521931\tcp2-2-18.dgn



TCP (2-2a)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH YIELD SIGNS
 (Less than 2000 ADT - See Note 9)



TCP (2-2b)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	



GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL			
TCP (2-2) - 18			
FILE:	tcp2-2-18.dgn	DN:	CK:
© TxDOT	December 1985	CON:	SECT:
REVISIONS 8-95 3-03 1-97 2-12 4-98 2-18		JOB 0911 00 113	HIGHWAY VA
		DIST:	SHEET NO.
		LFK	ANGELINA 22

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:34 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\tcp2-3-18.dgn



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	70'	120'	90'
35		205'	225'	245'	35'	80'	160'	120'
40		265'	295'	320'	40'	90'	240'	155'
45	L = WS	450'	495'	540'	45'	100'	320'	195'
50		500'	550'	600'	50'	110'	400'	240'
55		550'	605'	660'	55'	120'	500'	295'
60		600'	660'	720'	60'	130'	600'	350'
65		650'	715'	780'	65'	140'	700'	410'
70		700'	770'	840'	70'	150'	800'	475'
75		750'	825'	900'	75'	160'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Traffic Operations Division Standard

TEXAS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS



TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	LFK	ANGELINA	23	
4-98 2-18				

163

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:41 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\tcp2-4-18.dgn



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

TCP (2-4b)

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.




**TRAFFIC CONTROL PLAN
 LANE CLOSURES ON MULTILANE
 CONVENTIONAL ROADS**

TCP (2-4) - 18


FILE: tcp2-4-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	LFK	ANGELINA	24	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:54:49 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\tcp2-5-18.dgn



TCP (2-5a)
ONE LANE CLOSED



TCP (2-5b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths X X			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.
 - The downstream taper is optional. When used, it should be 100 feet approximately per lane, with channelizing devices spaced at 20 feet.

- TCP (2-5a)**
- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic, with the arrow board placed in the closed lane near the end of the merging taper.
- TCP (2-5b)**
- Conflicting pavement markings shall be removed for long-term projects.

Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 LONG TERM LANE CLOSURES
 MULTILANE CONVENTIONAL RDS.**


TCP (2-5) - 18

FILE: tcp2-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
8-95 2-12 REVISIONS	0911	00	113	VA
1-97 3-03	DIST	COUNTY	SHEET NO.	
4-98 2-18	LFK	ANGELINA	25	


165

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 6/17/2022 8:54:56 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\tcp2-6-18.dgn



TCP (2-6a)
ONE LANE CLOSURE



TCP (2-6b)
LANE CLOSURE NEAR EXIT RAMP



TCP (2-6c)
LANE CLOSURE NEAR ENTRANCE RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
 - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

TCP (2-6) - 18

FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	LFK	ANGELINA	26	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 6/17/2022 8:55:03 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\wzbrk-13.dgn



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

BACKGROUND COLOR	SIGN DESIGNATION	SIGN	SIGN DIMENSIONS	REFLECTIVE SHEETING	SQ FT	GALVANIZED STRUCTURAL STEEL		DRILLED SHAFT
						Size	(LF)	
							① ②	24" DIA. (LF)
Orange	G20-7T		96" X 48"	Type B _{FL} or C _{FL}	32	▲	▲ ▲	▲
Orange	G20-7T		192" X 96"	Type B _{FL} or C _{FL}	128	W8x18	16 17	12

▲ See Note 6 Below

LEGEND

	Sign
	Large Sign
	Traffic Flow

DEPARTMENTAL MATERIAL SPECIFICATIONS

PLYWOOD SIGN BLANKS	DMS-7100
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL}
BLACK	LEGEND & BORDERS	NON-REFLECTIVE ACRYLIC FILM

GENERAL NOTES


1. See BC and SMD sheets for additional sign support details.
2. Sign locations shall be approved by the Engineer.
3. For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
4. Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
5. Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
6. The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
7. The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:
 Item 636 - Aluminum Signs
 Item 647 - Large Roadside Sign Supports and Assemblies.
 Item 416 - Drilled Shaft Foundations
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.

		Traffic Operations Division Standard	
WORK ZONE "GIVE US A BRAKE" SIGNS			
WZ (BRK) - 13			
FILE: wzbrk-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT August 1995	CONT	SECT	JOB
REVISIONS	0911	00	113
6-96	5-98	7-13	
8-96	3-03		
	DIST	COUNTY	SHEET NO.
	LFK	ANGELINA	27


DATE: 6/17/2022 8:55:11 PM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521931\wzrs22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
 * For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.


Texas Department of Transportation
 Traffic Safety Division Standard

TEMPORARY RUMBLE STRIPS


WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0911	00	113	VA
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	LFK	ANGELINA	28	


105



* 1'-6" FROM TOE OF CTB TO 4"x6" FORMED DRAIN. (TYP)



NO WORK THIS SHEET



Permit No. # 64
**BRIDGE LAYOUT
 SH 94
 AND T.S.E. R.R.
 OVERPASS**
 SHEET 2 OF 3
 SCALE: 1" = 20'-0"
 VERT. & HORIZ.



N. T. S.


7/25/2022

BRIDGE LAYOUTS

SITE 1 - ANGELINA COUNTY
 SL 287 @ SH 94 & TSE RR
 11-003-0-0319-04-064
 (SHEET 2 OF 3)

TEXAS DEPARTMENT OF TRANSPORTATION		SHEET 2 OF 26	
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST		COUNTY	SHEET NO.
LFK		ANGELINA	30


7/23/2022 10:01:48 PM c:\txd01\pwworkon\line\txd01\cathy_1oerch\d0521936\02-brglay-site-1.dgn




106



NO WORK THIS SHEET



Perm. Str. # 64
**BRIDGE LAYOUT
 SH 94
 AND T.S.E. R.R.
 OVERPASS**
 SHEET 3 OF 3
 SCALE: 1"=20'-0"
 VERT. & HORIZ.




7/25/2022

BRIDGE LAYOUTS

**SITE 1 - ANGELINA COUNTY
 SL 287 @ SH 94 & TSE RR
 11-003-0-0319-04-064
 (SHEET 3 OF 3)**


TEXAS DEPARTMENT OF TRANSPORTATION			
©2022 SHEET 3 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST		COUNTY	SHEET NO.
LFK		ANGELINA	31

7/23/2022 10:04:06 PM c:\txdot\pwworking\line\txdot\3\cathy_1oerch\d0521936\03-brglay-site-1.dgn



003-2553-01-012

10	15	20	25	30	35	40	45	50	55	60	65	70	75	80	85	90	95	100	105	110	115	120	125	130	135	140	145	150	155	160	165	170	175	180	185	190	195	200	205	210	215	220	225	230	235	240	245	250	255	260	265	270	275	280	285	290	295	300	305	310	315	320	325	330	335	340	345	350	355	360	365	370	375	380	385	390	395	400	405	410	415	420	425	430	435	440	445	450	455	460	465	470	475	480	485	490	495	500	505	510	515	520	525	530	535	540	545	550	555	560	565	570	575	580	585	590	595	600	605	610	615	620	625	630	635	640	645	650	655	660	665	670	675	680	685	690	695	700	705	710	715	720	725	730	735	740	745	750	755	760	765	770	775	780	785	790	795	800	805	810	815	820	825	830	835	840	845	850	855	860	865	870	875	880	885	890	895	900	905	910	915	920	925	930	935	940	945	950	955	960	965	970	975	980	985	990	995	1000
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------



NO WORK THIS SHEET

0	5	10	15	20	25	30	35	40	45	50	55	60	65	70	75	80	85	90	95	100	105	110	115	120	125	130	135	140	145	150	155	160	165	170	175	180	185	190	195	200	205	210	215	220	225	230	235	240	245	250	255	260	265	270	275	280	285	290	295	300	305	310	315	320	325	330	335	340	345	350	355	360	365	370	375	380	385	390	395	400	405	410	415	420	425	430	435	440	445	450	455	460	465	470	475	480	485	490	495	500	505	510	515	520	525	530	535	540	545	550	555	560	565	570	575	580	585	590	595	600	605	610	615	620	625	630	635	640	645	650	655	660	665	670	675	680	685	690	695	700	705	710	715	720	725	730	735	740	745	750	755	760	765	770	775	780	785	790	795	800	805	810	815	820	825	830	835	840	845	850	855	860	865	870	875	880	885	890	895	900	905	910	915	920	925	930	935	940	945	950	955	960	965	970	975	980	985	990	995	1000
---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------

Master Copy

14

C253-14 14

SITE 2 - ANGELINA COUNTY
SL 287 @ DRAW
11-003-0-2553-01-012
(SHEET 1 OF 2)



7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION			
©2022 SHEET 4 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY		SHEET NO.
LFK	ANGELINA		32


7/23/2022 10:06:56 PM C:\TXDOT\pwworking\line\TXdot3\cathy_loerch\0521936\04-brglay-site-2.dgn




REMOVE SEDIMENT BUILDUP
IN CULVERT BARRELS
CLEAN CULVERT = 1 EA

ESTIMATED QUANTITIES
BRIDGE QUANTITIES

Uncl. Str. Excav.	71 CY
Cl. C. Conc.	386.83 CY
Reinf. Steel	66,886 Lbs
Uncl. (Grav. Excav. (Ty. I))	100 CY
Cl. C. Conc. (Grav.)	88 CY
ROADWAY QUANTITIES	
Com. Chan. Excav.	48 CY
18" R.C. Pipe (Cl. III)	12 LF
Inlet (Comp.) (Ty. II)	2 EA
Grate (Ty. II)	2 EA



ELEVATION
STA 672+55.5 TO STA 672+42.0 ~ PROP. 5-10'x4'x126'-0" MBC
USING SPECIAL DESIGN AND MCW-FI WINGS
SCALE 1"=5'



ELEVATION
STA. 663+19.75 TO STA. 663+73.25 ~ PROP. 5 BARREL MBC
126'-0" CLEAR ROADWAY USING SPECIAL DESIGN & MCW-FI
WINGS (FOUR BARREL 10'x4' AND ONE 10'x7' BARREL)
Scale: 1"=10'

ESTIMATED QUANTITIES
BRIDGE QUANTITIES

Uncl. Str. Excav.	171 CY
Cl. C. Conc.	414.03 CY
Reinf. Steel	57,387 Lbs
Uncl. (Grav. Excav. (Ty. I))	100 LF
ROADWAY QUANTITIES	
Com Chan Excav.	452 CY
18" R.C. Pipe (Cl. III)	12 LF
Inlet (Comp.) (Ty. II)	2 EA
Grate (Ty. II)	2 EA

BRIDGE CULVERT LAYOUT

Master Copy

STATE	02553-1-10
DATE	
SCALE	
APP	


2353-01-014 # 011 & 012

003-2553-01012

28

7/23/2022 10:10:04 PM
C:\TXD01\pwworkon\line\TXD003\cathy_loerch\d0521936\05-brglay-site-2.dgn

SITE 2 - ANGELINA COUNTY
SL 287 @ DRAW
11-003-0-2553-01-012
(SHEET 2 OF 2)




DocuSigned by:
Mitchell L. Randall, P.E.
FF6D8503742F43A...

7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION
©2022 SHEET 5 OF 26

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	33	



RUBBERIZE FAILED CONCRETE RIPRAP @ NORTH ABUTMENT; REMOVE CONC RIPRAP-40' X 20' = 90 SY * ADD 24" ROCK RIPRAP-40' X 20' X 24" = 60 CY

ESTIMATED QUANTITIES

- Com. Chan Excav = 2,000 CY
- Uncl. Str. Excav = 16 CY
- Cl. B Conc. Slabs = 1290 CY
- Cl. B Conc. Bents = 35.5 CY
- Reinf. Steel = 30,625 LB
- 15" Conc. Piling = 610 LF
- 15" Conc. Test Piling = 90 LF
- Cl. B Conc. Rip-Rap = 72 CY

Net water way below normal H.W. = 768 Square Feet.
 D.A. = 9,621 Acre.
 Length = 26,379 feet
 Slope = 0.538%
 Rational (10) = 3,403 C.F.S.
 Manning = 3.812 C.F.S.
 Velocity = $\frac{3403}{768} = 4.43$ ft/s

POPPERS CREEK BRIDGE LAYOUT
 STATION 160+67.5 to STATION 161+92.5
 5-25' FS-8-24-25 SLAB SPAN, H-15 LOAD

NOTE:


No. 2 Test hole location @ Sta. 162+05

* NOTES:
 IN ACCORDANCE WITH APPLICABLE SPECIFICATIONS, BREAK EXIST CONC RIPRAP INTO MAXIMUM OF 24" PIECES. BROKEN CONC RIPRAP TO BE LEFT IN PLACE.

NEW STONE RIPRAP WILL REQUIRE THE PLACEMENT OF FILTER FABRIC PRIOR TO PLACEMENT OF STONES.

Master Copy

SITE 3 - ANGELINA COUNTY
 FM 2109 @ POPPERS CREEK
 11-003-0-2662-01-001





7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION		
©2022 SHEET 6 OF 26		
CONT	SECT	JOB
0911	00	113
DIST	COUNTY	SHEET NO.
LFK	ANGELINA	34

7/23/2022 10:13:54 PM
 C:\TXDOT\pwork\line\TXdot\3\cathy. loerch\d0521936\06-brglay-site-3.dgn



NOTES:


- DESIGNED IN ACCORDANCE WITH AASHTO LRFD SPECIFICATIONS.
- BEAM END CONDITIONS:
 D: DENOTES DOWEL AT EXTERIOR BEAM.
 BLANK: DENOTES NO DOWELS.

DESIGN SPEED : 50 MPH
 FUNCTIONAL CLASS: RURAL MAJOR COLLECTOR
 ADT (20YR) : 700

STATE OF TEXAS
 CORBETT L. FREEMAN
 86913
 The seal appearing on this document was authorized by CORBETT L. FREEMAN, P.E. 86913 for foundation design.

HL 93 LOADING

ARCADIS
 2710 South Medford
 Lufkin, Texas 75901
 Tel: 936.632.9722
 Fax: 936.634.4116
 www.arcadis-us.com



TEXAS DEPARTMENT OF TRANSPORTATION
 ©2007

STATE OF TEXAS
 KELLY O. MORRIS
 88590
 The seal appearing on this document was authorized by KELLY O. MORRIS, P.E. 88590 for roadway design.

**BRIDGE LAYOUT
 FM 1280
 WHITE ROCK
 CREEK**

NEW NBI NO. 11-114-0-0931-02-032
 SCALE: 1" = 40' HORIZ & VERT
 SHEET 1 OF 2

PROJECT NO.	SHEET NO.		
6	80		
STATE	DIST.	COUNTY	
TEXAS	LFK	HOUSTON	
CONT.	SECT.	JOB	HIGHWAY NO.
0931	02	016, ETC.	FM 1280

MASTER COPY

SITE 4 - HOUSTON COUNTY
 FM 1280 @ WHITE ROCK CREEK
 11-114-0-0931-02-032
 (SHEET 1 OF 2)

NO WORK THIS SHEET

N. T. S.

STATE OF TEXAS
 MITCHELL L. RANDALL
 129397
 LICENSED PROFESSIONAL ENGINEER



7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION
 ©2022 SHEET 7 OF 26

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	35	

7/23/2022 10:48:03 PM
 C:\TXDOT\pwworking\line\TXdot3\cathy_loerch\d0521936\07-brglay-site-4.dgn




NOTES:
 1. DESIGNED IN ACCORDANCE WITH AASHTO LRFD SPECIFICATIONS.
 2. BEAM END CONDITIONS:
 D: DENOTES DOWEL AT EXTERIOR BEAM.
 BLANK: DENOTES NO DOWELS.

DESIGN SPEED : 50 MPH
 FUNCTIONAL CLASS: RURAL MAJOR COLLECTOR
 ADT (20YR) : 700

HL 93 LOADING

STATE OF TEXAS
 CORBETT L. FREEMAN
 86913
 The seal appearing on this document was authorized by CORBETT L. FREEMAN, P.E., 86913 for foundation design.



ARCADIS
 2710 South Medford
 Lufkin, Texas 75901
 Tel: 936.632.9722
 Fax: 936.634.4116
 www.arcadis-us.com

TEXAS DEPARTMENT OF TRANSPORTATION
 ©2007

STATE OF TEXAS
 KELLY O. MORRIS
 88590
 The seal appearing on this document was authorized by KELLY O. MORRIS, P.E., 88590 for roadway design.

BRIDGE LAYOUT
 FM 1280
 WHITE ROCK CREEK

NEW NBI NO. 11-114-0-0931-02-032
 SCALE: 1"=40' HORIZ & VERT
 SHEET 2 OF 2

FED. RD. DIST. NO.	PROJECT NO.	SHEET NO.
6		B1
STATE	DIST.	COUNTY
TEXAS	LFK	HOUSTON
CONT.	SECT.	JOB
0931	02	016, ETC.

MASTER COPY

N. T. S.

STATE OF TEXAS
 MITCHELL L. RANDALL
 129397
 LICENSED PROFESSIONAL ENGINEER

DocuSigned by
 Mitchell L. Randall, P.E.
 FFD8503742F43A

7/25/2022

BRIDGE LAYOUTS


TEXAS DEPARTMENT OF TRANSPORTATION
 ©2022 SHEET 8 OF 27

CONT.	SECT.	JOB	HIGHWAY
0911	00	113	VA
DIST.	COUNTY	SHEET NO.	
LFK	ANGELINA	36	

EXISTING BARBED WIRE FENCING EXISTS IN THE PROJECT AREA. FENCING TO BE REMOVED TO GAIN ACCESS AND REPLACED IN EQUAL OR BETTER CONDITION WHEN WORK IS COMPLETED. CARE IS TO BE TAKEN TO CONTAIN ANY LIVESTOCK WITHIN THE FENCED AREA. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO VARIOUS BID ITEMS.

SITE 4 - HOUSTON COUNTY
 FM 1280 @ WHITE ROCK CREEK
 11-114-0-0931-02-032
 (SHEET 2 OF 2)

7/23/2022 10:50:39 PM
 C:\Txdot\pwworking\line\Txdot3\cathy_loerch\0521936\08-brglay-site-4.dgn




CROSS SECTION DATA									
STATION NUMBER	DEPTH (FEET)	WIDTH (FEET)	DEPTH (FEET)						
794+00	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+10	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+20	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+30	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+40	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+50	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+60	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+70	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+80	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
794+90	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+00	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+10	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+20	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+30	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+40	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+50	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+60	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+70	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+80	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
795+90	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0
796+00	1.0	12.0	1.0	12.0	1.0	12.0	1.0	12.0	1.0

ESTIMATED QUANTITIES		
ITEM	UNIT	QUANTITY
CL. CONC. FOR EXT. STR.	C.Y.	169.54
REINFORCING STEEL	LB	22,898
UNIT STAG. PAV.	C.Y.	39



LAYOUT SAND CREEK BRIDGE
STA. 794+00 TO 795+00
U.S. 59 POLK COUNTY

STATE	PROJECT NO.	DATE
TX	176.5	11/25/22



ITEM	STANDARD	UNCL. STR. EXCAV (CULV) C.Y.	CL. CONC. FOR EXT. STR. (CULV) C.Y.	REINF. STL. LB	CON. CHAN. EXCAV. CY	INLET COMPL. EA.	METAL GRATE EA.
3-6x16B	MCB-2-15'	39	169.54	22,898	78	1	1

LENGTHENING LAYOUT SAND CREEK BRIDGE
3-3x7x33' MCB-2-15'
STA 795+04.54




DocuSigned by:
Mitchell L. Randall, P.E.
FF608503742F43A...

7/25/2022

BRIDGE LAYOUTS

SITE 5 - POLK COUNTY
US 59 @ SAND CREEK
11-187-0-0176-05-049

TEXAS DEPARTMENT OF TRANSPORTATION		
©2022 SHEET 9 OF 26		
CONT.	SECT.	HIGHWAY
0911	00	113 VA
DIST.	COUNTY	SHEET NO.
LFK	ANGELINA	37



7/23/2022 10:55:08 PM c:\txdot\pwworking\line\txdot\3\cathy_1oerch\0521936\10-brglay-site-6.dgn

N. T. S.


DocuSigned by
 Mitchell L. Randall, P.E.
 FF6D8503742F43A

7/25/2022

BRIDGE LAYOUTS		
TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 10 OF 26		
CONT	SECT	JOB
0911	00	113
DIST	COUNTY	SHEET NO.
LFK	ANGELINA	38

SITE 6 - POLK COUNTY
 US 59 SB @ WILLS CREEK
 11-187-0-0176-05-050


CONTRACT NO.	11-187-0-0177-12-038
STATE	TEXAS
COUNTY	POLK
DATE	7/25/2022



**REMOVE & REPLACE
FAILED WINGWALLS**


QUANTITIES

Excavation	14.00	cu yd
Structural Excavation	75.00	cu yd
Concrete	11.7	cu yd



**LAYOUT
SANSON CREEK BRIDGE
HIGHWAY NO. 35
POLK COUNTY
2-10 x 12 x 79-45° RT SKEW SPEC.
STA. 383+06.14**

187-0177-12-038



DocuSigned by:
Mitchell L. Randall, P.E.
FF6D503742F43A


7/25/2022

**BRIDGE
LAYOUTS**

**SITE 7 - POLK COUNTY
SL 393 @ SANSON CREEK
11-187-0-0177-12-038**


TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 11 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	39	

7/23/2022 11:20:53 PM
c:\txdot\pwworking\line\txdot\3\cathy_loerch\d0521936\11-brglay-site-7.dgn



TEST HOLE LEGEND
(Holes Located On E U.S. 190)

1. Loose tan, fine sand, organic.
2. Hard dark gray, sandy clay, organic.
3. Loose tan, fine sand, light gray, slightly silty, w/occ. thin sandy clay seams below 18.5'.
4. Loose pea gravel and coarse sand.
5. Hard greenish-gray sandy clay, slightly silty (Miocene).
6. Hard greenish-gray cemented sand.
7. Hard greenish-gray, very sandy clay.
8. Hard greenish-gray cemented sand, dense greenish-gray, very silty fine sand.
9. Loose tan sand (fill).
10. Coarse loose tan sand.
11. Hard dark greenish-gray silty clay (Miocene).
12. Very dense dark greenish-gray cemented sand, laminated.
13. Loose tan clayey fine sand, organic, fill.
14. Loose tan, medium coarse sand.
15. Loose gray fine sand.
16. Loose dark gray clayey fine sand, w/numerous sand seams.
17. Hard greenish-gray silty clay, slightly sandy (Miocene).
18. Dense greenish-gray clayey fine sand, partially cemented.
19. Medium dense greenish-gray, very silty fine sand, slightly clayey, partially cemented below 63.0'.
20. Very stiff dark gray & tan clay, slightly silty w/numerous thin sand seams & pebbles to 18.0'. Slightly sandy below 18.0'.
21. Firm dark gray clay, slightly silty-Traces of decayed wood & organic matter below 28.5'.
22. Medium dense light gray, fine sand.
23. Very hard greenish-gray cemented sand.
24. Very dense greenish-gray silty, fine sand w/numerous thin cemented sand seams.
25. Dense greenish-gray, clayey silt, slightly sandy.




GENERAL NOTES:
S.H.O. Specifications 1961 as Amended December 1965

LOADING:
20-44

WIND DATA:
Wind Water Surface 131.0
Designing Tolerance 3.0
Design Height (Based on overland wind velocity of 40 mph) 4.0
Tide 0.9
Minimum Water Surface 138.9
Design Flood
Q = 44,300 cfs (100 yrs)
Area of bridge opening (below Elev. 134.00) = 56,200 sf

TABLE OF ESTIMATED QUANTITIES

QUANT.	PILING	ABUT.	PIERS	SLABS	TYPE C	HEAVY	STRUC.	RAIL	CONC.
TYPE	CL. P.	CL. P.	CL. P.	CL. P.					
BEATS	25.2	1,232	37.8	---	---	7,266	75.2	27	---
BEATS	256.0	2,340	206.8	---	---	35,548	303.8	---	---
TOTAL	---	---	---	358	2,090	42,814	779.0	---	2,796.9
TOTAL	281.2	3,572	344.6	394	2,090	130,258	880.0	757	2,796.9



TRINITY RIVER AUTHORITY
LIVINGSTON DAM AND RESERVOIR
TRINITY RIVER

U. S. HIGHWAY 190
KICKAPOO CREEK BRIDGE
LAYOUT - SHEET 1

FORREST AND COTTON, INC. - CONSULTING ENGINEERS
DALLAS, TEXAS

DESIGNED BY: *Forrest and Cotton*
DRAWN BY: *Forrest and Cotton*
FILE: 218-27-25 DATE: JUNE 1967
CONTRACT NO. 1110 PROJECT NO. 218-3-26 SHEET 48 OF 84

STATE	COUNTY	SECTION	SECTION NO.	JOB NO.	WEEKDAY NO.
TEXAS	POLK	218	3	26	48

48

NO WORK THIS SHEET

N. T. S.



DocuSigned by:
Mitchell L. Randall, P.E.
FF6B503742F43A

7/25/2022


BRIDGE LAYOUTS

SITE 8 - POLK COUNTY
US 190 @ KICKAPOO CREEK
11-187-0-0213-03-096
(SHEET 1 OF 2)

TEXAS DEPARTMENT OF TRANSPORTATION
©2022 SHEET 12 OF 26

CONT.	SECT.	JOB	HIGHWAY
0911	00	113	VA
DIST.	COUNTY	SHEET NO.	
LFK	ANGELINA	40	


7/23/2022 10:58:49 PM C:\txdot\pwworking\line\txdot3\cathy_loerch\d0521936\12-brglay-si-re-8.dgn



ESTIMATED QUANTITIES		
DESCRIPTION	UNIT	EST
CONC SURF TRMT	SY	197
CL C CONC (BENT)	CY	4.6
CL C CONC (LENT)	CY	14.0
CL S CONC (FAN GIRL)	CY	76.8
RI PRAP CONC CL B	CY	511
REINF STEEL	LB	19,249
RAIL TY T 80Z	LF	47.54
CONC PILE 18" SQ	LF	248
STR EXCAV	CY	58
CHAL T (CA)	CY	87

ROADWAY ITEMS		
DESCRIPTION	UNIT	EST
CL A CONC (APPR SLAB)	CY	23.4
TEMP ANCH SECT	EA	2
METAL BEAM SP FINE (26A)	LF	400
REINF STEEL	LB	3218

FOR CONTRACTOR'S INFORMATION ONLY.



Permit No. 113
 FM 942
 HICKMAN CREEK
 BRIDGE LAYOUT
 7/25/2022

SITE 9 - POLK COUNTY
 FM 942 @ HICKMAN CREEK
 11-187-0-1193-01-013

N. T. S.

DocuSigned by:
 Mitchell L. Randall, P.E.
 FF8D8503742F43A...



7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION
 ©2022 SHEET 14 OF 26

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	42	

7/23/2022 11:02:34 PM
 C:\txdot\pwworking\line\txdot3\cathy_loerch\0521936\14-brglay-site-9.dgn



NOTE: ENSURE ANY REPAIRS MAINTAIN A 1" BUFFER BETWEEN CONCRETE SLAB AND REPAIR AREA

SITE 10 - POLK COUNTY
FM 943 @ MENARD CREEK
11-187-0-1194-01-003

N. T. S.

DocuSigned by:
Mitchell L. Randall, P.E.
FF0D8503742F43A



7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION
©2022 SHEET 15 OF 26

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	43	

7/23/2022 11:05:00 PM c:\txdot\pwworking\11\15-brglay-si-re-10.dgn




BRIDGE ESTIMATE SUMMARY		
Item	Unit	Quant
COM CHAN EXCAV	CY	2,186
UNCL STR. EXCAV (B.R)	CY	10
CONC PIL (15 IN SQ)	LF	552
CL C CONC FOR EXT STR (SLAB)	CY	105.00
CL C CONC FOR EXT STR (BENT)	CY	11.25
CL C CONC FOR EXT STR (ABUT)	CY	8.25
RIPRAP (CONC) (CL B)	CY	33.10
REINF STL	LB	22,442
RAIL (TY-T2)	LF	108
RAIL (TY-T2 MOD)	LF	100
METAL BEAM GD FENCE (CL B) (STL POST)	LF	97,166.8
CONC SURF TREAT	SY	304
REMOVE OLD (CONC) RIPRAP	SY	105
ROADWAY ITEMS		

BRIDGE WIDENING LAYOUT
 TEMPE CREEK BRIDGE
 4 SPANS FS-8-20-25 TO BE
 WIDENED TO 40'-0" CLEAR RDWY

STATE	STATE	PROJECT NO.	SHEET NO.
11	TEXAS	C 1876-1-11	32
COUNTY	CONTRACT	SECTION	JOB
POLK	1876	1	FM 150

7/23/2022 11:07:14 PM c:\txdot\pwworking\line\txdot3\cathy.1oerch\d0521936\16-brglay-site-11.dgn

32





DocuSigned by:
 Mitchell L. Randall, P.E.
 FF8D8503742F43A

7/25/2022

BRIDGE LAYOUTS


SITE 11 - POLK COUNTY
 FM 1988 @ TEMPE CREEK
 11-187-0-1876-01-001

TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 16 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	44	




TEST HOLE LEGEND

- Test Hole No.1 20' Rt c, Sta.38+39:**
- 1 SAND Lt.brown,very loose, coarse, moist.
 - 2 SAND Clayey, brown-gray, fine, loose, moist.
 - 3 SAND Coarse lt.gray,very loose, moist.
 - 4 CLAY Gray-tan silty,hard,moist.
 - 5 SAND Clayey, reddish-brown, fine, slight comp, moist
 - 6 CLAY Sandy, blue-green, very stiff, moist.
 - 7 CLAY CLAY Gray-tan, silty, hard, moist.
 - 8 CLAY Sandy, gray-tan, traces soft sandstone, fine, very hard, moist.
 - 9 CLAY Gray-tan, silty
- Test Hole No.2 8' Rt c, Sta 39+46**
- 1 SAND Fine, brown, loose, moist.
 - 2 CLAY Sandy, red-brown, gray, fine, soft, moist.
 - 3 CLAY Fine, red-gray, stiff, moist.
 - 4 SAND Clayey, w/ thin layer stone, br-tan, comp, moist.
 - 5 CLAY Sandy, gray, very stiff, moist.
 - 6 CLAY Fine, gray-red, hard, moist.
 - 7 SAND Clayey, red-brown, very dense, moist.
 - 8 CLAY Fine, gray-red, hard, moist.
- Test Hole No.3 17' Lt c, Sta 41+77**
- 1 CLAY Sandy, red, coarse, soft, moist.
 - 2 CLAY Silty, fine, red-gray, stiff
 - 3 SAND Coarse, gray, slightly compact, moist.
 - 4 CLAY Sandy, red-gray, stiff, moist.
 - 5 SAND Clayey w/ gravel, slightly compact, moist.
 - 6 SANDSTONE, Brown-gray, hard, dry.
 - 7 SAND Tan-gray, very dense, moist.
 - 8 SAND Clayey, red-brown, fine, w/ gravel, dense, moist.
 - 9 SAND Fine, tan-brown, compact, moist.
 - 10 CLAY w/ coarse sand strata, gray, stiff, moist.
 - 11 CLAY Silty, gray, very stiff, moist, w/ traces of calcareous nodules



INSTALL GABION @ BENT 2
(SEE SITE 12 GABION
DETAIL SHEET)



DocuSigned by:
Mitchell L. Randall, P.E.
FF08503742F43A

7/25/2022


BRIDGE LAYOUTS

NOTE: CLEANING AND SEALING OF EXISTING JOINTS SHALL BE PERFORMED DURING THE COOLER MONTHS TO AVOID EXCESS EXPANSION AS DIRECTED BY THE ENGINEER

SITE 12 - POLK COUNTY
FM 1988 @ LONG KING CREEK
11-187-0-1876-01-004
(SHEET 1 OF 2)

TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 17 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	45	

7/23/2022 11:25:43 PM C:\txdot\pwworking\11e\17xdot3\cathy.1oerch\d0521936\17-brglay-si-re-12.dgn



Bent No	Snuff Size	Bell Size	Shaft Tip Elev	Drill Shaft Length	H
1	2.5'	5'	48.8	38'	
2	2.5'	6'	42.6	30'	14'
3	2.5'	6'	42.6	24'	20'
4	2.5'	5'	48.8	38'	
Abut 1 Wings	1.5'		48.8	38'	
Abut 2 Wings	1.5'		48.8	38'	

BRIDGE ESTIMATE SUMMARY

Item	Unit	Quant.
UNCL STR EXCAV (BR)	CY	60
DRILL SHAFT (18 IN)	LF	152
DRILL SHAFT (30 IN)	LF	390
BELL FTG	CY	14.2
CLC CONC (SLAB)	CY	241.9
CLC CONC (BENT)	CY	40.1
CLC CONC (ABUT)	CY	42.4
PRESTR CONC BEAMS (TYC)	LF	1,374
RIPRAP (CONC) (CLB)	CY	67.70
REINF STL	LB	67,468
STR STL (SHOE AND ARMOR JT)	LB	2,860
RAIL (TY T1)	LF	483.33
CONC SURF TREAT	SY	1,080


ROADWAY ITEMS

BRIDGE APPR SLABS	
CONC FOR APPR SLAB	44.4 CY
REINF STL	4,380 LB


LONG KING CREEK BRIDGE
STA. 38+88.63 TO STA. 41+21.37
170' & 280' PREST. CONC BEAM SPANS
Scale 1"=20' Horiz & Vert.

NOTE: IN ACCORDANCE WITH SPECIFICATIONS, CONC RIPRAP TO BE BROKEN UP INTO MAXIMUM 24" STONE AND LEAVE IN PLACE. PLACE FILTER FABRIC PRIOR TO PLACING NEW ROCK RIPRAP

NOTE: CLEANING AND SEALING OF EXISTING JOINTS SHALL BE PERFORMED DURING THE COOLER MONTHS TO AVOID EXCESS EXPANSION AS DIRECTED BY THE ENGINEER



N. T. S.





DocuSigned by:
Mitchell L. Randall, P.E.
FF8D8503742F43A

7/25/2022

BRIDGE LAYOUTS

SITE 12 - POLK COUNTY
FM 1988 @ LONG KING CREEK
11-187-0-1876-01-004
(SHEET 2 OF 2)

TEXAS DEPARTMENT OF TRANSPORTATION			
©2022 SHEET 18 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	46	



ESTIMATED QUANTITIES
 CL. A CONC. (GIRD.) = 273.6 CY
 CL. A CONC. (BENTS) = 328 CY
 CL. B CONC. RIPRAP = 107.5 CY
 REINF. STEEL = 58,068 LBS.
 14" PRE-CAST CONC. PILING = 827 L.F.
 14" PRE-CAST CONC. TEST PILING = 82 L.F.
 COMMON CHAN. EXCAV. = 75 C.Y.
 UNCL. STRUG. EXCAV. = 6 C.Y.

MENARD CREEK
 STA. 250+10 TO 252+80
 CGC-15 & AGC
 SCALE: 1" = 10' VER. & HOR.

NO WORK THIS SHEET

N. T. S.



Mitchell L. Randall, P.E.
 FFD8503742F43A


7/25/2022

BRIDGE LAYOUTS

SITE 13 - POLK COUNTY
 FM 2610 @ MENARD CREEK
 11-187-0-2591-01-001
 (SHEET 2 OF 2)

TEXAS DEPARTMENT OF TRANSPORTATION		
©2022 SHEET 20 OF 26		
CONT. 0911	SECT. 00	JOB. 113
DIST. LFK		COUNTY. ANGELINA
		SHEET NO. 48

7/23/2022 11:32:31 PM
 C:\Txdot\pwworking\lne\ltxdot3\cathy. loerch\d0521936\20-brglay-si-re-13.dgn




Widen surface from 20' to 26'
with a 150' transition at
each end of structure (Est @
133 SY). Refer to Struct
1/2 LB for widening details

PLACE FLOWABLE FILL AT
SOUTH RIPRAP ON EAST SIDE
= 2 CY

PLACE FLOWABLE FILL AT
SOUTH RIPRAP ON WEST SIDE
= 4 CY

PROPOSED DESIGN
3 EA CG-0-34-40 (H-20) SLABS
2 EA BCG-0-34-40 Surf Benches (Mod)
2 EA BCG-0-34-40 with Seams 160
RIPRAP RR-8
Riprap (Type 1)
5' x 5' x 5' x 5'



STA. 728+00
PERM. STR. POOL'S CREEK
NO. 4 (H.20 LOADING)
S 1447 (2) A
11 Sep 2013 2 1 56
244302001 #004

7/23/2022 11:34:23 PM C:\txdot\pwworking\line\txdot3\cathy_loerch\0521936\21-brglay-site-14.dgn


SITE 14 - SAN JACINTO COUNTY
FM 980 @ POOL CREEK
11-204-0-2443-02-004

N. T. S.

Mitchell L. Randall, P.E.
7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 21 OF 26		
CONT	SECT	JOB
0911	00	113
DIST	COUNTY	SHEET NO.
LFK	ANGELINA	49



NOTE: CLEANING AND SEALING OF EXISTING JOINTS SHALL BE PERFORMED DURING THE COOLER MONTHS TO AVOID EXCESS EXPANSION AS DIRECTED BY THE ENGINEER

SITE 15 - SABINE COUNTY
 SH 87 @ PALO GAUCHO BAYOU
 11-202-0-0304-03-071
 (SHEET 1 OF 2)

N. T. S.



DocuSigned by
 Mitchell L. Randall, P.E.
 FFD8503742F43A

7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 22 OF 26			
CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	50	

7/23/2022 11:47:01 PM
 c:\txdot\pwworking\l\cathy.1oerch\d0521936\22-brglay-site-15.dgn



50 YR. FREQUENCY
 DA = 81,234 AC.
 L = 100,000
 T = 667 MIN.
 H = 0.75 IHR.
 Q = 24.97 cfs
 V = 3.5 fsec.
 W = 6802"

Item Description	Quan	Unit
Common Channel Excavation	4,448	CY
Unclassified Structural Excavation	17	CY
Class "A" Concrete (Pier Gliders)	682.2	CY
Class "A" Concrete (Bents)	93.9	CY
Class "A" Concrete (Bridge Approach)	42.6	CY
Reinforcing Steel (Pier Gliders)	152,768	LB
Reinforcing Steel (Bridge Approach)	4,102	LB
15" Sq Concrete Piling	2,577	LF
15" Sq Concrete Test Piling	175	LF
Railing - Type 6	1,092.0	LF
Class "B" Concrete (Riprap)	140.0	CY
Class "A" Concrete (Tie Beam)	6.5	CY
Reinforcing Steel (Tie Beam)	10,685	LB
Reinforcing Steel (Bent)	1,184	LB

PALO GAUCHO BAYOU
 BRIDGE LAYOUT
 SHWY NO 87
 SABINE COUNTY

NOTE: CLEANING AND SEALING OF EXISTING JOINTS SHALL BE PERFORMED DURING THE COOLER MONTHS TO AVOID EXCESS EXPANSION AS DIRECTED BY THE ENGINEER

SITE 15 - SABINE COUNTY
 SH 87 @ PALO GAUCHO BAYOU
 11-202-0-0304-03-071
 (SHEET 2 OF 2)







DocuSigned by:
 Mitchell L. Randall, P.E.
 FFD80803742F43A

7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 23 OF 26		
CONT	SECT	HIGHWAY
0911	00	113 VA
DIST	COUNTY	SHEET NO.
LFK	ANGELINA	51

7/23/2022 11:54:46 PM c:\txdot\pwworking\line\txdot\3\cathy_loersch\d0521936\23-brglay-site-15.dgn



7/24/2022 3:17:11 PM c:\txdot\pwworking\line\txdot3\cathy. loerch\d0521936\25-brgl\lay-site-16.dgn

SITE 16 - SHELBY COUNTY
FM 2572 @ STYLES CREEK
11-210-0-0742-03-015
(SHEET 2 OF 2)

N. T. S.

DocuSigned by:
Mitchell L. Randall, P.E.
FFD8503742F43A...


7/25/2022

BRIDGE LAYOUTS

TEXAS DEPARTMENT OF TRANSPORTATION
©2022 SHEET 25 OF 26

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	53	


C 33.8



Bridge 210-0743-02-001

ESTIMATED QUANTITIES			
Description	Unclass. Sta. Excess Cu. Yds.	Class II Conc. Cu. Yds.	Reinforcing Steel Lbs.
4-5'x5'x24" MBC-E-24	32	60.79	8,190

ESTIMATED QUANTITIES			
Description	Unclass. Sta. Excess Cu. Yds.	Class II Conc. Cu. Yds.	Reinforcing Steel Lbs.
5-5'x5'x24" MBC-E-24	38	72.26	9,674



LAYOUT FOR BRIDGES FROM STA. 16+22.08 TO STA. 16+45.00 & STA. 79+05.50 TO STA. 79+34.00 F.M. HWY 138 SHELBY COUNTY Scale: Hor. 1"=10' Vert. 1"=10'

N. T. S.

DocuSigned by Mitchell L. Randall, P.E. FFD6503742F43A




7/25/2022

BRIDGE LAYOUTS

SITE 17 - SHELBY COUNTY FM 138 @ DRAW CREEK 11-210-0-0743-02-001

TEXAS DEPARTMENT OF TRANSPORTATION ©2022 SHEET 26 OF 26

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY		SHEET NO.
LFK	ANGELINA		54



SECTION A-A
GABION BASKETS AT BENTS 2 AND 3

N. T. S.

DocuSigned by:
Mitchell L. Randall, P.E.
FF6D8903742F43A...

7/25/2022


**SITE 12
GABION
DETAILS**

TEXAS DEPARTMENT OF TRANSPORTATION
©2022

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY		SHEET NO.
LFK	ANGELINA		55

7/24/2022 3:37:13 PM
c:\txdot\pwworking\lne\ltxdot\3\cathy.l\oerch\0521936\SITE 12 DETAILS.dgn

7/26/2022 12:41:57 PM
 c:\txdot\pwworking\line\txdot3\cathy_loerch\0521936\T501 Bridge Rail.dgn



GENERAL NOTES:
 Designed according to AASHTO 1977 Standard and current Interim Specifications.
 All parts of the railing including concrete parapet wall, reinforcing, terminal connector, bolts, nuts and washers are included in the price bid per linear foot of rail.
 All steel components except reinforcing shall be galvanized unless otherwise shown in plans.
 All concrete for railing wall shall be Class "C".
 Dimensions relating to reinforcing steel are to centers of bars.
 Metal Beam Guard Fence or Concrete Traffic Barrier is usually attached to the abutment wingwall panel. See plan sheet for details and length for payment. The splice between the approach guard fence and the terminal connector shall be with the normal eight bolts. The dowel connection to the approach traffic barrier shall be grouted the same as other barrier joints.
 Shop drawings will not be required for this rail.
 This railing may be constructed with slip-forms with equipment approved by the Engineer. Sensor control for both line and grade must be provided. When slip-forming is used, the concrete may be cured with membrane curing compound.
 The back of railing shall be vertical unless otherwise shown in plans.
 Welded wire fabric may be used as an option to conventional reinforcement and shall be made in accordance with ASTM A497.
 Welded Wire Fabric Detail shown is for D8.4 longitudinal wires and D8.3 vertical wires. Combinations of Reinforcing Steel and Welded Wire Fabric or configurations of Welded Wire Fabric other than shown will be permitted when the conditions in the table are satisfied and the dimension from end of section to first welded vertical wire does not exceed 3".
 Additional reinforcing may be tack welded to the upper two thirds of the reinforcing cage to provide bracing when slip-forming is used. Additional anchorage devices may be added when welding is necessary in the lower one third of the cage. Do not weld to U or S bars in the lower one third of the cage.
 P.L.F. weight of railing (with no overlay increase) is 326 plf.

142

STATE DEPARTMENT OF HIGHWAYS AND PUBLIC TRANSPORTATION

TRAFFIC RAIL

TYPE T501

ORIGINAL DRAWING DATE	JUNE 1985	STATE PROJECT	11 6	FEDERAL AID PROJECT #		SHEET	142
DESIGNER	EDDY	DISTRICT	ANGELINA	SECTION	ES&D	DATE	11/21/20

N. T. S.

FOR INFORMATION ONLY


T501 BRIDGE RAIL

TEXAS DEPARTMENT OF TRANSPORTATION ©2022

CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	56	

THIS PROJECT CONSISTS OF DISCRETE CONSTRUCTION PROJECTS SEPARATED A MINIMUM 1/4 MILE BY UNDISTURBED AREAS; THEREFORE THEY ARE TREATED AS SEPARATE PLANS OF DEVELOPMENT. THESE SEPARATE PLANS OF DEVELOPMENT DISTURB LESS THAN 1 ACRE, HOWEVER, THE CONTRACTOR SHALL PLACE BMP'S AS DIRECTED. THE DISTURBED AREA IN THE PLANS AND THE CONTRACTOR PROJECT SPECIFIC LOCATIONS (PSLS) WITHIN 1 MILE OF THE PROJECT LIMITS WILL FURTHER ESTABLISH THE AUTHORIZATION REQUIREMENTS FOR STORM WATER DISCHARGES. IF THE TOTAL AREA DISTURBED SHOWN IN THE PLANS AND PSLS WITHIN 1 MI. OF THE PROJECT LIMITS EXCEEDS 1 ACRE, THE ENGINEER WILL DEVELOP AN SWP3 SITE PLAN AND POST A SMALL CONSTRUCTION SITE NOTICE FOR THE CONSTRUCTION ACTIVITIES.

7/24/2022 3:43:20 PM
c:\txdot\pwworking\line\txdot3\cathy. loerch\d0521938\SWP3Index*small\disturbance.dgn



DocuSigned by
Mitchell L. Randall, P.E.

FF6D8503742F43A...

7/25/2022

TXDOT
SWP3
INDEX



CONT	SECT	JOB	HIGHWAY
0911	00	113	VA
DIST	COUNTY	SHEET NO.	
LFK	ANGELINA	57	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. N/A
- No Action Required Required Action

Action No.

1. N/A

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP 3A and 3C-PCN not required

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1. Site 2: SL 287 at Draw, Site 3: FM 2109 at Pophers Creek, Site 4: FM 1280 at White Rock Creek, Site 5: US 59 at Sand Creek, Site 6: US 59 SB at Willis Creek, Site 7: Sanson Creek at SL 393, Site 8: US 190 at Kickapoo Creek, Site 9: FM 942 at Hickman Creek, Site 10: FM 943 at Menard Creek, Site 11: FM 1988 at Tempe Creek, Site 12: FM 1988 at Long King Creek, Site 13: FM 2610 at Menard Creek, Site 14: FM 980 at Pool Creek, Site 15: SH 7 at Atascoso Creek, Site 16: SH 87 at Palo Gaucho Bayou, Site 17: FM 2572 at Styles Creek, and Site 18: FM 138 at Draw

2. No fill or equipment shall be placed within the stream for use of temporary work access. If methods are deemed necessary, contractor shall develop and provide access plan to Area Engineer for approval. Methods must not obstruct stream flow or life cycles of aquatic species.

3. Wetlands are present at Site 4: FM 1280 at White Rock Creek from Bent 2 to Bent 5 width of ROW and Site 16: SH 87 at Palo Gaucho Bayou from Bent 17 to Bent 9 width of ROW. If access for equipment is required, contractor must submit an access plan to Area Engineer for approval. Access through wetlands will require the use of mats or non-erodible fill with filter fabric placed beneath.

4. Refer to EPIC Sheet 2 of 2 for Nation Wide Permit (NWP) 3A and 3C requirements in regard to maintaining stream flow, temporary work, temporary access, suitable material, and general conditions.

5. All work must be conducted within the existing Right-of-Way.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input checked="" type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

1. Site 7: Sanson Creek Bridge at SL 393: Old Bridge Structure of eligible historic age is present outside of the project area Southwest (downstream) of Sanson Creek Bridge on Old Highway 35 S road. NO stockpiling or storage of materials and equipment at this bridge location.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

1. Site 10: FM 943 at Menard Creek and Site 13: FM 2610 at Menard Creek are located in areas where boundaries of the Big Thicket National Preserve (BTNP) is adjacent to the Right-of-Way (ROW). Work shall be conducted within th ROW. No tree removal or trimming at these locations. Area Engineer shall notify BTNP prior to starting work at these locations

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately.

- No Action Required Required Action

1. In order to maintain compliance with Chapter 64 of the Texas Parks and Wildlife Code and Migratory Bird Treaty Act (MBTA), construction activities that may affect nests (i.e. tree removal, tree limbing, bridge work) shall be conducted outside of the nesting season (March 15 to September 15). In the event birds or active nests (eggs and/or nestlings present) are encountered, contact the engineer prior to conducting work.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SWP3: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):
 Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.
 If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

1. Lead was detected in paint greater than 90 ppm on Site 15: Atascoso Creek Bridge at SH 7. The contractor is responsible for completing all associated abatement activities in accordance to Item 6, Item 446, and other pertinent items. Contractor may request a copy of the Asbestos and Lead Paint Inspection Report from the Area Engineer.

VII. OTHER ENVIRONMENTAL ISSUES

- No Action Required Required Action

1. Site 3: Pophers Creek Bridge FM 2109: NO stock piling or storage of materials and equipment within the boundaries of the Angelina National Forest from 2.50 miles North of Bridge, 0.06 miles South of Bridge, and 0.17 miles to 1.65 miles South of Bridge. Area Engineer shall notify United States Forest prior to starting work in Angelina National Forest. No trees shall be removed without the approval from Area Engineer and the United States Forest Service.

2. Site 3: Pophers Creek Bridge FM 2109: USACE Sam Rayburn Lake Manager has approved the work below their 179-foot flowage easement as shown on Site 3: Pophers Creek bridge layout. No changes in work at this location or work outside this location shall occur without approval of the USACE.

Design Division Standard

ENVIRONMENTAL PERMITS,
 ISSUES AND COMMITMENTS
 EPIC

SHEET 1 OF 2

FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0911	00	113	VA
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.	
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	LFK	ANGELINA	58	

NWP GENERAL CONDITIONS

AS APPLICABLE TO
THIS PROJECT

2. AQUATIC LIFE MOVEMENTS. NO ACTIVITY MAY SUBSTANTIALLY DISRUPT THE NECESSARY LIFE CYCLE MOVEMENTS OF THOSE SPECIES OF AQUATIC LIFE INDIGENOUS TO THE WATERBODY, INCLUDING THOSE SPECIES THAT NORMALLY MIGRATE THROUGH THE AREA, UNLESS THE ACTIVITY'S PRIMARY PURPOSE IS TO IMPOUND WATER.

3. SPAWNING AREAS. ACTIVITIES IN SPAWNING AREAS DURING SPAWNING SEASONS MUST BE AVOIDED TO THE MAXIMUM EXTENT PRACTICABLE. ACTIVITIES THAT RESULT IN THE PHYSICAL DESTRUCTION (E.G., THROUGH EXCAVATION, FILL, OR DOWNSTREAM SMOTHERING BY SUBSTANTIAL TURBIDITY) OF AN IMPORTANT SPAWNING AREA ARE NOT AUTHORIZED.

6. SUITABLE MATERIAL. NO ACTIVITY MAY USE UNSUITABLE MATERIAL (E.G., TRASH, DEBRIS, CAR BODIES, ASPHALT, ETC.). MATERIAL USED FOR CONSTRUCTION OR DISCHARGED MUST BE FREE FROM TOXIC POLLUTANTS IN TOXIC AMOUNTS (SEE SECTION 307 OF THE CLEAN WATER ACT).

8. ADVERSE EFFECTS FROM IMPOUNDMENTS. IF THE ACTIVITY CREATES AN IMPOUNDMENT OF WATER, ADVERSE EFFECTS TO THE AQUATIC SYSTEM DUE TO ACCELERATING THE PASSAGE OF WATER, AND/OR RESTRICTING ITS FLOW MUST BE MINIMIZED TO THE MAXIMUM EXTENT PRACTICABLE.

9. MANAGEMENT OF WATER FLOWS. TO THE MAXIMUM EXTENT PRACTICABLE, THE PRE-CONSTRUCTION COURSE, CONDITION, CAPACITY, AND LOCATION OF OPEN WATERS MUST BE MAINTAINED FOR EACH ACTIVITY, INCLUDING STREAM CHANNELIZATION AND STORM WATER MANAGEMENT ACTIVITIES, EXCEPT AS PROVIDED BELOW. THE ACTIVITY MUST BE CONSTRUCTED TO WITHSTAND EXPECTED HIGH FLOWS. THE ACTIVITY MUST NOT RESTRICT OR IMPEDE THE PASSAGE OF NORMAL OR HIGH FLOWS, UNLESS THE PRIMARY PURPOSE OF THE ACTIVITY IS TO IMPOUND WATER OR MANAGE HIGH FLOWS. THE ACTIVITY MAY ALTER THE PRE-CONSTRUCTION COURSE, CONDITION, CAPACITY, AND LOCATION OF OPEN WATERS IF IT BENEFITS THE AQUATIC ENVIRONMENT (E.G., STREAM RESTORATION OR RELOCATION ACTIVITIES).

11. EQUIPMENT. HEAVY EQUIPMENT WORKING IN WETLANDS OR MUD FLATS MUST BE PLACED ON MATS, OR OTHER MEASURES MUST BE TAKEN TO MINIMIZE SOIL DISTURBANCE.

12. SOIL EROSION AND SEDIMENT CONTROLS. APPROPRIATE SOIL EROSION AND SEDIMENT CONTROLS MUST BE USED AND MAINTAINED IN EFFECTIVE OPERATING CONDITION DURING CONSTRUCTION, AND ALL EXPOSED SOIL AND OTHER FILLS, AS WELL AS ANY WORK BELOW THE ORDINARY HIGH WATER MARK OR HIGH TIDE LINE, MUST BE PERMANENTLY STABILIZED AT THE EARLIEST PRACTICABLE DATE. PERMITTEES ARE ENCOURAGED TO PERFORM WORK WITHIN WATERS OF THE UNITED STATES DURING PERIODS OF LOW-FLOW OR NO-FLOW.

13. REMOVAL OF TEMPORARY FILLS. TEMPORARY FILLS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO PRE-CONSTRUCTION ELEVATIONS. THE AFFECTED AREAS MUST BE REVEGETATED, AS APPROPRIATE.

14. PROPER MAINTENANCE. ANY AUTHORIZED STRUCTURE OR FILL SHALL BE PROPERLY MAINTAINED, INCLUDING MAINTENANCE TO ENSURE PUBLIC SAFETY AND COMPLIANCE WITH APPLICABLE NWP GENERAL CONDITIONS, AS WELL AS ANY ACTIVITY-SPECIFIC CONDITIONS ADDED BY THE DISTRICT ENGINEER TO AN NWP AUTHORIZATION.

23. MITIGATION. THE DISTRICT ENGINEER WILL CONSIDER SEVERAL FACTORS WHEN DETERMINING APPROPRIATE AND PRACTICABLE MITIGATION NECESSARY TO ENSURE THAT ADVERSE EFFECTS ON THE AQUATIC ENVIRONMENT ARE MINIMAL.

25. WATER QUALITY. WHERE STATES AND AUTHORIZED TRIBES, OR EPA WHERE APPLICABLE, HAVE NOT PREVIOUSLY CERTIFIED COMPLIANCE OF AN NWP WITH CWA SECTION 401, INDIVIDUAL 401 WATER QUALITY CERTIFICATION MUST BE OBTAINED OR WAIVED (SEE 33 CFR 330.4(C)). THE DISTRICT ENGINEER OR STATE OR TRIBE MAY REQUIRE ADDITIONAL WATER QUALITY MANAGEMENT MEASURES TO ENSURE THAT THE AUTHORIZED ACTIVITY DOES NOT RESULT IN MORE THAN MINIMAL DEGRADATION OR WATER QUALITY.

27. REGIONAL AND CASE-BY-CASE CONDITIONS. THE ACTIVITY MUST COMPLY WITH ANY REGIONAL CONDITIONS THAT MAY HAVE BEEN ADDED BY THE DIVISION ENGINEER (SEE 33 CFR 330.4(E)) AND WITH ANY CASE SPECIFIC CONDITIONS ADDED BY THE CORPS OR BY THE STATE, INDIAN TRIBE, OR U.S. EPA IN ITS SECTION 401 WATER QUALITY CERTIFICATION, OR BY THE STATE IN ITS COASTAL ZONE MANAGEMENT ACT CONSISTENCY DETERMINATION.

FOR A COMPLETE LIST OF GENERAL CONDITIONS GO TO:

<http://www.swf.usace.army.mil/Missions/Regulatory/Permitting/NationwideGeneralPermits.aspx>

USACE - PERMIT #3(A) & (C)

AS APPLICABLE TO
THIS PROJECT

(A) THE REPAIR, REHABILITATION, OR REPLACEMENT OF ANY PREVIOUSLY AUTHORIZED, CURRENTLY SERVICEABLE STRUCTURE, OR FILL, OR OF ANY CURRENTLY SERVICEABLE STRUCTURE OR FILL AUTHORIZED BY 33 CFR 330.3, PROVIDED THAT THE STRUCTURE OR FILL IS NOT TO BE PUT TO USES DIFFERING FROM THOSE USES SPECIFIED OR CONTEMPLATED FOR IT IN THE ORIGINAL PERMIT OR THE MOST RECENTLY AUTHORIZED MODIFICATION. MINOR DEVIATIONS IN THE STRUCTURE'S CONFIGURATION OR FILLED AREA, INCLUDING THOSE DUE TO CHANGES IN MATERIALS, CONSTRUCTION TECHNIQUES, REQUIREMENTS OF OTHER REGULATORY AGENCIES, OR CURRENT CONSTRUCTION CODES OR SAFETY STANDARDS THAT ARE NECESSARY TO MAKE THE REPAIR, REHABILITATION, OR REPLACEMENT ARE AUTHORIZED. ANY STREAM CHANNEL MODIFICATION IS LIMITED TO THE MINIMUM NECESSARY FOR THE REPAIR, REHABILITATION, OR REPLACEMENT OF THE STRUCTURE OR FILL; SUCH MODIFICATIONS, INCLUDING THE REMOVAL OF MATERIAL FROM THE STREAM CHANNEL, MUST BE IMMEDIATELY ADJACENT TO THE PROJECT. THIS NWP ALSO AUTHORIZES THE REMOVAL OF ACCUMULATED SEDIMENT AND DEBRIS WITHIN, AND IN THE IMMEDIATE VICINITY OF, THE STRUCTURE OR FILL. THIS NWP ALSO AUTHORIZES THE REPAIR, REHABILITATION, OR REPLACEMENT OF THOSE STRUCTURES OR FILLS DESTROYED OR DAMAGED BY STORMS, FLOODS, FIRE OR OTHER DISCRETE EVENTS, PROVIDED THE REPAIR, REHABILITATION, OR REPLACEMENT IS COMMENCED, OR IS UNDER CONTRACT TO COMMENCE, WITHIN TWO YEARS OF THE DATE OF THEIR DESTRUCTION OR DAMAGE. IN CASES OF CATASTROPHIC EVENTS, SUCH AS HURRICANES OR TORNADOES, THIS TWO-YEAR LIMIT MAY BE WAIVED BY THE DISTRICT ENGINEER, PROVIDED THE PERMITTEE CAN DEMONSTRATE FUNDING, CONTRACT, OR OTHER SIMILAR DELAYS.

(C) THIS NWP ALSO AUTHORIZES TEMPORARY STRUCTURES, FILLS AND WORK, INCLUDING THE USE OF TEMPORARY MATS, NECESSARY TO CONDUCT THE MAINTENANCE ACTIVITY. APPROPRIATE MEASURES MUST BE TAKEN TO MAINTAIN NORMAL DOWNSTREAM FLOWS AND MINIMIZE FLOODING TO THE MAXIMUM EXTENT PRACTICABLE, WHEN TEMPORARY STRUCTURES, WORK AND DISCHARGES, INCLUDING COFFERDAMS, ARE NECESSARY FOR CONSTRUCTION ACTIVITIES, ACCESS FILLS, OR DEWATERING OF CONSTRUCTION SITES. TEMPORARY FILLS MUST CONSIST OF MATERIALS, AND BE PLACED IN A MANNER, THAT WILL NOT BE ERODED BY EXPECTED HIGH FLOWS. TEMPORARY FILLS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO PRE-CONSTRUCTION ELEVATIONS. THE AREAS AFFECTED BY TEMPORARY FILLS MUST BE REVEGETATED, AS APPROPRIATE.

NOTE: THIS NWP AUTHORIZES THE REPAIR, REHABILITATION, OR REPLACEMENT OF ANY PREVIOUSLY AUTHORIZED STRUCTURE OR FILL THAT DOES NOT QUALIFY FOR THE CLEAN WATER ACT SECTION 404(F) EXEMPTION FOR MAINTENANCE.

NOTE:

THE PROJECT CROSSES JURISDICTIONAL WATERS OF THE U.S. AND A NWP #3A and C WILL BE UTILIZED. THIS PERMIT AUTHORIZES THE REPAIR, REHABILITATION, OR REPLACEMENT OF CURRENTLY SERVICEABLE STRUCTURES OR FILL THAT WERE PREVIOUSLY AUTHORIZED. THE NWP GENERAL CONDITIONS AND THE NWP GUIDELINES MUST BE FOLLOWED IN ORDER TO MAINTAIN COMPLIANCE WITH NWP. NO COORDINATION HAS TAKEN PLACE WITH THE USACE. IF COORDINATION MAY BE NEEDED, CONTACT THE TXDOT LUFKIN DISTRICT ENVIRONMENTAL SECTION AT 1-800-687-8087.

**ENVIRONMENTAL PERMITS, (EPIC) □
ISSUES AND COMMITMENTS**


USACE

				
EPIC				
(ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS)				
SHEET 2 OF 2				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
© TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0911	00	113	VA
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	LFK	ANGELINA		59

DATE: 7/26/2022 10:49:41 AM
FILE: c:\txdot\pww\online\txdot3\contry_loerch\0521913\0911-00-113 EPIC-2_NWP3.dgn


DISCLAIMER: This standard is made by TxDOT for any purpose whatsoever. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.

7/28/2022
 cf116dot1pw_online\txdot3\cathy_loerch\d0521938\ec116.dgn



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1) - 16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0911	00	113	VA	
	DIST	COUNTY		SHEET NO.	
	LFK	ANGELINA		60	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

DOT #: N/A
 Crossing Type: N/A
 RR Company Owning Track at Crossing: ANGELINA AND NECHES RIVER RAILROAD
 Operating RR Company at Track: ANGELINA AND NECHES RIVER RAILROAD
 RR MP: N/A
 RR Subdivision: LUFKIN
 City: LUFKIN
 County: ANGELINA
 CSJ at this Crossing: 2553-01
 Highway/Roadway name crossing the railroad: US 69/SL 287
 # of regularly scheduled trains per day at this crossing: 4
 # of switching movements per day at this crossing: 0
 % of estimated contract cost of work within railroad ROW: 0.40%

Scope of Work at this Crossing to Be Performed by State Contractor:
THIS PROJECT IS FOR BRIDGE PREVENTATIVE MAINTENANCE (BPM) CONSISTING OF
CLEANING AND REMOVING SEDIMENT BUILD UP IN THE CULVERTS. WORK TO BE
PARALLEL TO THE RAILROAD RIGHT OF WAY.

Scope of Work at this Crossing to Be Performed by Railroad Company:
PROVIDE FLAGGING SERVICES WHENEVER THE WORK IS WITHIN 25 FEET
OF THE NEAREST RAIL.

** Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian,
 or Closed/Abandoned

II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)

N/A

III. FLAGGING & INSPECTION

of Days of Railroad Flagging Expected: 0

On this project, night or weekend flagging is:

- Expected
 Not Expected

Flagging services will be provided by:

- Railroad Company: TxDOT will pay flagging invoices
 Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule.
 The Railroad requires a 30 day notice if their flaggers are to be utilized.
 If Contractor falls behind schedule due to their own negligence and is not
 ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

- UPRR - UP.info@railpros.com
 Call Center 877-315-0513, Select #1 for flagging
 - UP.request@nrssinc.net
 Call Center 877-984-6777

 BNSF - BNSF.info@railpros.com
 Call Center 877-315-0513, Select #1 for flagging

 KCS - KCS.info@railpros.com
 Call Center 877-315-0513, Select #1 for flagging
 - Bottom Line On-Track Safety Services
 bottomline076@aol.com, 903-767-7630

OTHERS _____

Contractor must incorporate Construction Inspection into anticipated construction schedule.

- Not Required
 Required: Contact Information for Construction Inspection:

IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

On this project, construction work to be performed by a railroad company is:

- Required
 Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company.
 TxDOT must issue a work order for any work done by the Railroad Company
 prior to the work being performed.

V. RAILROAD INSURANCE REQUIREMENTS

Railroad reference number shall be provided by TxDOT CST or DO.

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies must be issued for and on behalf of the Railroad. Where
 more than one Railroad Company is operating on the same right of way or
 where several Railroad Companies are involved and operate on their own
 separate rights of way, provide separate insurance policies in the name of
 each Railroad Company.

No direct compensation will be made to the Contractor for providing the
 insurance coverages shown below or any deductibles. These costs are
 incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$2,000,000 / \$4,000,000
Business Automobile	\$2,000,000 combined single limit

Railroad Protective Liability	
<input checked="" type="checkbox"/> Not Required	
<input type="checkbox"/> Non - Bridge Projects	\$2,000,000 / \$6,000,000
<input type="checkbox"/> Bridge Projects	\$5,000,000 / \$10,000,000
<input type="checkbox"/> Other	

VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT

On this project, an ROE agreement is:

- Not Required

 Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)
 Required: UPRR Maintenance Consent Letter. TxDOT CST to assist.

 Required: Contractor to obtain (see Item 5, Article 8.4)

With the following railroad companies: _____

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

<http://www.txdot.gov/inside-txdot/division/rail/samples.html>

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed
 Construction & Maintenance Agreement between the State and the Railroad and
 an executed ROE agreement between the Contractor and the Railroad if required
 on project.

VII. RAILROAD COORDINATION MEETING

On this project, a Railroad Coordination Meeting is:

- Not Required
 Required

See Item 5, Article 8.1 for more details.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT.
 Subcontractors are required to maintain the same insurance coverage
 as required of the Contractor.

IX. EMERGENCY NOTIFICATION

**IN CASE OF RAILROAD EMERGENCY
 CALL ANGELINA AND NECHES RIVER RAILROAD
 RAILROAD EMERGENCY LINE AT 936-634-4403
 LOCATION DOT#: N/A
 RR MILEPOINT: N/A
 SUBDIVISION: LUFKIN**

Texas Department of Transportation				Rail Division
<h2 style="margin: 0;">RAILROAD SCOPE OF WORK</h2> <h3 style="margin: 0;">PROJECT SPECIFIC DETAILS</h3>				
FILE: RR Scope of Work.dgn	DN: TxDOT	CK: _____	DW: _____	CK: _____
© TxDOT June 2014	CONT	SECT	JOB	HIGHWAY
9/2021	REVISIONS	0911 00	113	VA
DIST	COUNTY	SHEET NO.		
LFK	ANGELINA	61		

PART 1 - GENERAL

1.01 DESCRIPTION

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

1.02 REQUEST FOR INFORMATION / CLARIFICATION

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

1.03 PLANS / SPECIFICATIONS

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

PART 2 - UTILITIES AND FIBER OPTIC

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

PART 3 - CONSTRUCTION

3.01 GENERAL

- A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.
- B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.
- C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.
- D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.
- E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.
- F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.
- G. All permanent clearances shall be verified before project closing.

3.02 RAILROAD OPERATIONS

- A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.
- B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.
- C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:
 - 1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.
 - 2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES

- A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.
- B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.
- C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.
- D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
 - 1. Exactly what the work entails.
 - 2. The days and hours that work will be performed.
 - 3. The exact location of work, and proximity to the tracks.
 - 4. The type of window requested and the amount of time requested.
 - 5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.
- E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

3.04 INSURANCE

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

3.05 RAILROAD SAFETY ORIENTATION

- A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."
- B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

3.06 COOPERATION

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES

Abide by the following minimum temporary clearances during the course of construction:
A. 15' - 0" (BNSF) (UPRR) and 14' - 0" (KCS) horizontal from centerline of track
B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

3.08 APPROVAL OF REDUCED CLEARANCES

- A. Maintain minimum track clearances during construction as specified in Section 3.07.
- B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.
- C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

 Texas Department of Transportation				Rail Division	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS March 2020	0911	00	113	VA	
	DIST	COUNTY	SHEET NO.		
	LFK	ANGELINA	62		

DATE: 7/26/2022 10:51:55 AM
FILE: c:\ttdot\p_w_online\ttdot3\catny_loerch\0521928\Non Bridge-Projects.dgn

3.09 MAINTENANCE OF RAILROAD FACILITIES

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractor's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
 1. Pre-construction meetings.
 2. Pile driving/drilling of caissons or drilled shafts.
 3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
 4. Erection of precast concrete or steel bridge superstructure.
 5. Placement of waterproofing (prior to placing ballast on bridge deck).
 6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

3.11 RAILROAD REPRESENTATIVES

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

3.12 COMMUNICATIONS AND SIGNAL LINES

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

3.13 TRAFFIC CONTROL

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193
7:00 AM to 9:00 PM CST Monday-Friday except holidays,
staffed 24 hrs/day for emergencies
48 hrs notice required

BNSF 1-800-533-2891
24 hour number
5 working days notice required

KCS 1-800-344-8377
Texas One Call, a 24 hour number
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

3.15 RAILROAD FLAGGING

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

3.16 CLEANING OF RIGHT-OF-WAY

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

 Texas Department of Transportation				Rail Division	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
©TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0911	00	113	VA	
March 2020	DIST	COUNTY	SHEET NO.		
	LFK	ANGELINA	63		

DATE: 7/26/2022 10:52:36 AM
 FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521928\Non Bridge-Projects.dgn

3.09 MAINTENANCE OF RAILROAD FACILITIES

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractor's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
 1. Pre-construction meetings.
 2. Pile driving/drilling of caissons or drilled shafts.
 3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
 4. Erection of precast concrete or steel bridge superstructure.
 5. Placement of waterproofing (prior to placing ballast on bridge deck).
 6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

3.11 RAILROAD REPRESENTATIVES

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

3.12 COMMUNICATIONS AND SIGNAL LINES

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

3.13 TRAFFIC CONTROL

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193
7:00 AM to 9:00 PM CST Monday-Friday except holidays,
staffed 24 hrs/day for emergencies
48 hrs notice required

BNSF 1-800-533-2891
24 hour number
5 working days notice required

KCS 1-800-344-8377
Texas One Call, a 24 hour number
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

3.15 RAILROAD FLAGGING

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

3.16 CLEANING OF RIGHT-OF-WAY

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

DATE: 7/7/2022 2:05:34 PM
FILE: c:\txdot\pw_online\txdot3\catny_loerch\0521928\Non Bridge-Projects.dgn

 Texas Department of Transportation				Rail Division	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0911	00	113	VA	
March 2020	DIST	COUNTY	SHEET NO.		
	LFK	ANGELINA	64		