

INDEX OF SHEETS
SEE SHEET 2

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION
PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT

PROJECT NO. F2023(008)

US83, ETC.
JONES, ETC

LIMITS: NEAR 10TH ST TO NEAR 13TH ST, ETC

FOR THE CONSTRUCTION OF: MILL AND OVERLAY
CONSISTING OF: MILL AND OVERLAY

DESIGN SPEED = N/A
CURRENT A.D.T. N/A
PROJECTED A.D.T. N/A
FUNCTIONAL CLASS = N/A
EXISTING NBI# = (N/A)
PROPOSED NBI# = (N/A)

PROJECT NO.		SHEET NO.	
F2023(008)		1	
STATE	DISTRICT	COUNTY	
TEXAS	ABL	JONES, ETC.	
CONTROL	SECTION	JOB	HIGHWAY NO.
0033	04	072, ETC	US 83, ETC

FINAL PLANS

LETTING DATE: **SEPTEMBER 2022**

DATE CONTRACTOR BEGAN WORK: _____

DATE WORK WAS COMPLETED: _____

DATE WORK WAS ACCEPTED: _____

FINAL CONTRACT COST: \$ _____

CONTRACTOR : _____

CERTIFICATION FOR FINAL PLANS

THIS PROJECT WAS BUILT ACCORDING TO THE PLANS AND SPECIFICATIONS. THESE FINAL PLANS REFLECT THE WORK DONE AND THE QUANTITIES SHOWN THEREON AND ON THE FINAL ESTIMATE ARE FINAL QUANTITIES.

AREA ENGINEER _____ DATE _____

THE DISTRICT TRAFFIC SAFETY COMMITTEE HAS REVIEWED THE TRAFFIC CONTROL PLAN FOR THIS PROJECT AND IT IS IN COMPLIANCE WITH CURRENT TRAFFIC CONTROL STANDARDS.

DocuSigned by:
Casey McGee 7/5/2022
2377E0837A304A6... COMMITTEE CHAIRMAN DATE



RECOMMENDED FOR LETTING: 7/5/2022

DocuSigned by:
Paul N. Norman, P.E.
25E04E8F4A644... AREA ENGINEER

RECOMMENDED FOR LETTING: 7/5/2022


DocuSigned by:
Michael Haithcock
5757E2874584... AREA ENGINEER
DIRECTOR OF T P & D

SUBMITTED FOR LETTING: 7/5/2022

DocuSigned by:
Jerry Mitchell
C9CF1E58740C4A3... TxDOT PROJECT MANAGER

APPROVED FOR LETTING: 7/5/2022

DocuSigned by:
Thomas S. Allbritton, P.E.
0F6FT0A83D630... DISTRICT ENGINEER



EXCEPTIONS: N/A

EQUATIONS: NONE
RAILROAD CROSSINGS: N/A

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 5, 2022).

PENTABLET:
DATE: 6/29/2022
FILE: F:\engdot\pcc\projects\0033-04\072\CSJ_0033-04-072_ETC_PLAN_SET\01_TITLE_SHEET.dgn

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\02 INDEX OF SHEETS.dgn
4/11/2022 11:35:52 AM

GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3 PROJECT LAYOUT
- 4 TYPICAL SECTION CA1
- 5 TYPICAL SECTION CA2
- 6-7 TYPICAL SECTION CA3
- 8-15 TYPICAL SECTION HA1
- 16-17 TYPICAL SECTION J1
- 18-19 TYPICAL SECTION J2
- 20-21 TYPICAL SECTION J3
- 22-26 TYPICAL SECTION J4
- 27-31 GENERAL NOTES
- 32-33 ESTIMATE & QUANTITY
- 34 QUANTITY SUMMARY CA1
- 35 QUANTITY SUMMARY CA2
- 36 QUANTITY SUMMARY CA3
- 37 QUANTITY SUMMARY HA1
- 38 QUANTITY SUMMARY J1
- 39 QUANTITY SUMMARY J2
- 40 QUANTITY SUMMARY J3
- 41 QUANTITY SUMMARY J4

TRAFFIC CONTROL PLAN

- 42 SUGGESTED SEQUENCE OF WORK
- 43 TREATMENT FOR EDGE CONDITIONS
- 44 PILOT VEHICLE OPERATION

TRAFFIC CONTROL PLAN STANDARDS

- ## 45-56 BC (1-12)-21
- ## 57 TCP (2-1)-18
- ## 58 TCP (2-2)-18
- ## 59 TCP (2-3)-18
- ## 60 TCP (2-4)-18
- ## 61 TCP (2-5)-18
- ## 62 TCP (3-1)-13
- ## 63 TCP (3-3)-14
- ## 64 TCP (3-4)-13
- ## 65 WZ (STMP)-13
- ## 66 WZ (UL)-13

ROADWAY DETAILS

- 67-70 ROADWAY LAYOUT CA1
- 71-73 ROADWAY LAYOUT CA2
- 74-75 ROADWAY LAYOUT CA3
- 76-78 ROADWAY LAYOUT HA1
- 79 ROADWAY LAYOUT J1
- 80-81 ROADWAY LAYOUT J2
- 82 ROADWAY LAYOUT J3
- 83-86 ROADWAY LAYOUT J4


PAVEMENT MARKINGS & DELINEATION

PAVEMENT MARKINGS & DELINEATION STANDARDS

- ## 87-89 PM (1-3)-20
- ## 90 PM (4)-22

ENVIRONMENTAL ISSUES

- 91-92 STORMWATER POLLUTION PREVENTION PLAN (SW3P)
- 93 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET WITH A ** HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

DocuSigned by:
Paul N Norman, P.E., P.E. 4/11/2022
25E04E8F4AB6444... (NAME) DATE


INDEX OF SHEETS



FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		US 83, ETC
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC.		2
DISTRICT	CONTROL	SECTION	
ABL	0033	04	
			JOB
			072, ETC

BEGIN CONTROL CA1
CSJ: 0006-11-025
REF MRK: 428+1.43 mi.

STA: 391+50.45




END CONTROL CA1
CSJ: 0006-11-025
REF MRK: 430+0.706 mi.

STA: 476+90.00

BEGIN CONTROL CA2
CSJ: 0452-02-043
REF MRK: 334+1.944 mi.

STA: 1676+15.20




END CONTROL CA2
CSJ: 0452-02-043
REF MRK: 336+1.307 mi.

STA: 1748+76.30

END CONTROL CA3
CSJ: 0480-03-051
REF MRK: 316+1.899 mi.

STA: 55+00.00



BEGIN CONTROL CA3
CSJ: 0480-03-051
REF MRK: 316+0.858 mi.

STA: 0+00.00

END CONTROL J2
CSJ: 0157-07-006
REF MRK: 266+1.555 mi.

STA: 00+00.00

BEGIN CONTROL J2
CSJ: 0157-08-012
REF MRK: 270+0.051 mi.


STA: 47+36.28

END CONTROL HA1
CSJ: 0157-07-006
REF MRK: 270+0.051 mi.

STA: 62+20.00

BEGIN CONTROL HA1
CSJ: 0157-08-012
REF MRK: 266+1.555 mi.

STA: 00+00.00



BEGIN CONTROL J4
CSJ: 0107-01-039
REF MRK: 270+0.958 mi.

LINE A STA: 833+70.80
LINE B STA: 00+00.00

END CONTROL J4
CSJ: 0107-01-039
REF MRK: 272+0.475 mi.


LINE A STA: 698+00.25

END CONTROL J4
CSJ: 0107-01-039
REF MRK: 272+0.475 mi.

LINE B STA: 8+50.98

END CONTROL J1
CSJ: 0033-04-072
REF MRK: 302+1.173 mi.

STA: 1172+53.55



BEGIN CONTROL J1
CSJ: 0033-04-072
REF MRK: 302+1.385 mi.

STA: 1161+27.00

DS

Documented by:
Paul N. Norman, P.E.
25E04E8F4AB6444...




6/21/2022

PROJECT LAYOUT

© 2022 Texas Department of Transportation

NO SCALE		SHEET 1 OF 1	
FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC		3
DISTRICT	CONTROL	SECTION	
ABL	0033	04	072, ETC

**NOTE: SEE ROADWAY LAYOUT SHEETS FOR ADDITIONAL DETAILS



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED

DS

Paul N Norman, P.E.

25E04E8F4AB8444...

4/2/2022




**TYPICAL SECTION
CA1**



SCALE: 1 = 10 SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		4	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\04 TYP SEC CA1.dgn
 4/2/2022 1:03:02 PM



**ITEM #351
SPOT REPAIR DETAIL**

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED

DS

Paul N. Norman, P.E.
25E04E0F4AB6444...

6/21/2022




**TYPICAL
SECTION
CA2**

© 2022 Texas Department of Transportation

SCALE: 1" = 10' SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC		5	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

\$FILES\$
\$DATES\$
\$TIME\$



**ITEM #351
SPOT REPAIR DETAIL**

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED

DS

Designed by:
Paul N. Norman, P.E.
25E04E8F4AB6444...

4/2/2022

TYPICAL SECTION CA3





SCALE: 1" = 10' SHEET 1 OF 2

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	6	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\06 TYP SEC CA3.dgn 4/2/2022 1:03:04 PM

T:\Engdata\Projects\0033-04\072\CSJ_0033-04-072 ETC PLAN SET\06 TYP SEC CA3.dgn
7/11/2022 9:31:17 AM



**ITEM #351
SPOT REPAIR DETAIL**

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED

DS



Paul N. Norman, P.E.
25E04E8F4AB6444...
7/11/2022

**TYPICAL
SECTION
CA3**

© 2022 Texas Department of Transportation

SCALE: 1" = 10' SHEET 2 OF 2


FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		7	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

Paul N. Norman, P.E.

25E04E8F4AB6444...

4/2/2022


TYPICAL SECTION
HA1

© 2022 Texas Department of Transportation


SCALE: 1 = 10 SHEET 1 OF 8

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.		
6	SEE TITLE SHEET	US 83, ETC		
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		8	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
4/2/2022 1:03:06 PM




EXISTING PAVEMENT
 STA 2+00.00 - 14+75.0
 TRANSITION 14+75.00 - 18+00.0



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



PROPOSED TYPICAL SECTION
 STA 2+00.00 - 14+75.0
 TRANSITION 14+75.00 - 18+00.0

DS

Paul N Norman, P.E.

4/2/2022


**TYPICAL SECTION
 HA1**

© 2022 Texas Department of Transportation


SCALE: 1 = 10 SHEET 2 OF 8

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.		
6	SEE TITLE SHEET	US 83, ETC		
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		9	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
 4/2/2022 1:03:07 PM




EXISTING PAVEMENT
 STA 18+00.00 - 31+90.0
 TRANSITION 31+90.00 - 34+29.00



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



PROPOSED TYPICAL SECTION
 STA 18+00.00 - 31+90.0
 TRANSITION 31+90.00 - 34+29.00

DS

Paul N. Norman, P.E.
 25E04E8F-4AB6444...
 4/2/2022

TYPICAL SECTION
 HA1





SCALE: 1" = 10' SHEET 3 OF 8

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	10	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
 4/2/2022 1:03:08 PM


T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
4/2/2022 1:03:09 PM



**ITEM #351
SPOT REPAIR DETAIL**

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS


Paul N. Norman, P.E.
25E04E8F4AB6444...
4/2/2022

**TYPICAL SECTION
HA1**


© 2022 Texas Department of Transportation

SCALE: 1 = 10 SHEET 4 OF 8

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	11	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC




EXISTING PAVEMENT
 STA 37+40.00 - 42+47.00
 TRANS 42+47.00 - 45+13.00



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



PROPOSED TYPICAL SECTION
 STA 37+40.00 - 42+47.00
 TRANS 42+47.00 - 45+13.00

DS

Designed by:
Paul N. Norman, P.E.
 25E04E8F-4AB6444...
 4/2/2022

TYPICAL SECTION
 HA1





SCALE: 1 = 10 SHEET 5 OF 8


FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	12	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC


T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
 4/2/2022 1:03:10 PM

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
4/2/2022 1:03:11 PM



ITEM #351
SPOT REPAIR DETAIL
LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.
**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED





DS

Paul N. Norman, P.E.
 4/2/2022

**TYPICAL SECTION
HA1**

© 2022  Texas Department of Transportation

SCALE: 1 = 10 SHEET 6 OF 8


FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	13	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

DocuSigned by:
Paul N Norman, P.E.
25E04E8F4AB6444...
4/2/2022


TYPICAL SECTION
HA1

© 2022 Texas Department of Transportation


SCALE: 1 = 10 SHEET 7 OF 8

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	14	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
4/2/2022 1:03:12 PM




EXISTING PAVEMENT
 STA 51+93.00 - 60+66.00
 TRANS 60+66.00 - 62+20.00



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



PROPOSED TYPICAL SECTION
 STA 51+93.00 - 60+66.00
 TRANS 60+66.00 - 62+20.00

DS

Paul N. Norman, P.E.
 25E04E8F4AB6444...
 4/2/2022



TYPICAL SECTION
 HA1



SCALE: 1 = 10 SHEET 8 OF 8

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.		
6	SEE TITLE SHEET	US 83, ETC		
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		15	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC


T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\07 TYP SEC HA1.dgn
 4/2/2022 1:03:13 PM



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

DocuSigned by:
Paul N Norman, P.E.
 25E04E8F4AB6444...

4/2/2022



TYPICAL SECTION
 J1

© 2022 Texas Department of Transportation

SCALE: 1" = 10' SHEET 1 OF 2


FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	16	
DISTRICT	CONTROL SECTION	JOB	
ABL	0033	04	072, ETC

T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\08 TYP SEC J1.dgn
 4/2/2022 1:03:14 PM



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.



DS

Paul N. Norman, P.E.

25E04E8F-4AB6444...

4/2/2022



TYPICAL SECTION
J1

© 2022 Texas Department of Transportation

SCALE: 1" = 10' SHEET 2 OF 2

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	17	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC


I:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\08 TYP SEC J1.dgn
4/2/2022 1:03:15 PM



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

DocuSigned by:
Paul N Norman, P.E.
25E04E8F4AB6444...

4/2/2022

TYPICAL SECTION
J2



© 2022 Texas Department of Transportation

SCALE: 1 = 10 SHEET 1 OF 2

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	JONES, ETC.		SHEET NO.
TEXAS	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

18


T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\09 TYP SEC J2.dgn
4/2/2022 1:03:16 PM



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

Designed by:
Paul N. Norman, P.E.
25E04E8F4AB6444...

4/2/2022



TYPICAL SECTION
J2



SCALE: 1 = 10 SHEET 2 OF 2

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	TEXAS		SHEET NO.	
	JONES, ETC.		19	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC


T:\Engdata\Projects\0033-04\CSJ_0033-04-072 ETC PLAN SET\09 TYP SEC J2.dgn
4/2/2022 1:03:17 PM



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

DocuSigned by:
Paul N Norman, P.E.
 25E04E8F4AB6444...

4/2/2022



**TYPICAL SECTION
 J3**

© 2022 Texas Department of Transportation

SCALE: 1 = 10 SHEET 1 OF 2


FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	20	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\10 TYP SEC J3.dgn
 4/2/2022 1:03:18 PM



ITEM #351
SPOT REPAIR DETAIL
 LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

Paul N Norman, P.E.
 25E04E8F4AB6444...
 4/2/2022




**TYPICAL SECTION
 J3**

© 2022 Texas Department of Transportation

SCALE: 1 = 10 SHEET 2 OF 2

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	21	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\10 TYP SEC J3.dgn
 4/2/2022 1:03:19 PM



ITEM #351
SPOT REPAIR DETAIL
LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED

DS

Paul N. Norman, P.E.
25E04E8F4AB6444...

6/21/2022


**TYPICAL SECTION
J4**

© 2022 Texas Department of Transportation


SCALE: 1 = 10 SHEET 1 OF 5

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC		22	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

\$FILES\$ \$DATES\$ \$TIME\$




EXISTING PAVEMENT
 STA 829+50.20 - 825+30.90 (LINE A)
 STA 4+20.69 - 8+50.98 (LINE B)



ITEM #351
 SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



PROPOSED TYPICAL SECTION
 STA 829+50.20 - 825+30.90 (LINE A)
 STA 4+20.69 - 8+50.98 (LINE B)

DS

Paul N. Norman, P.E.
 25E04E8F4AB6444...

6/21/2022



TYPICAL SECTION
 J4




SCALE: 1 = 10 SHEET 2 OF 5


FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC		23	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

\$FILES\$ \$DATES\$ \$TIME\$



ITEM #351
SPOT REPAIR DETAIL
 LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.
 **PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

Paul N Norman, P.E.
 23E04E8F4AB0444...
 6/21/2022




TYPICAL SECTION J4

© 2022  Texas Department of Transportation

SCALE: 1 = 10 SHEET 3 OF 5

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC		24	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

\$FILES\$ \$DATES\$ \$TIME\$



ITEM #351
SPOT REPAIR DETAIL

LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.

**PRIME SHOULD BE USED IF BASE IS ENCOUNTERED

DS

Paul N. Norman, P.E.

25E04E8F4AB6444...

4/2/2022



**TYPICAL SECTION
J4**




SCALE: 1 = 10 SHEET 4 OF 5

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		25	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\11 TYP SEC J4.dgn
4/2/2022 1:03:23 PM



ITEM #351
SPOT REPAIR DETAIL
 LOCATIONS AND SIZE OF SPOT REPAIRS TO BE DETERMINED BY THE ENGINEER. REMOVAL OF EXISTING MATERIAL, SP-D, PROOF ROLLING, AND TACK** SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 351.
 **PRIME SHOULD BE USED IF BASE IS ENCOUNTERED



DS

 Paul N. Norman, P.E.
 25E04E8F4AB6444...
 4/2/2022

**TYPICAL SECTION
 J4**

© 2022 Texas Department of Transportation

SCALE: 1 = 10 SHEET 5 OF 5

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	26	
DISTRICT	CONTROL SECTION JOB		
ABL	0033 04 072, ETC		

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\11 TYP SEC J4.dgn
 4/2/2022 1:03:24 PM

Project Number: See Title Sheet
 Control: 0033-04-072 ETC
 County: JONES
 Highway: US83

**ABILENE DISTRICT GENERAL NOTES
 2014 SPECIFICATIONS**

Contractor questions on this project are to be addressed to the following individual(s):

Paul Norman, P.E.: Paul.Norman@txdot.gov
 Chad Carter, P.E.: Chad.W.Carter@txdot.gov
 (Abilene Area Office)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:
<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by:
 District
 Project Type (Construction or Maintenance)
 Letting Date
 CCSJ/Project Name.

Failure to make necessary corrections to SW3P based on SW3P inspections will be cause for withholding the monthly estimate until such corrections have been made.

Failure to make necessary corrections to traffic control items based on barricade inspections will be cause for withholding the monthly estimate until such corrections have been made.

Provide ingress/egress to the adjacent properties in areas under construction. Phased construction of driveways and streets shall be required to provide uninterrupted access to adjacent properties. Coordinate work with the property owners before beginning any construction in the vicinity of the drive.

Cut neat, straight lines with vertical faces along pavement edges or along joints between existing asphalt or concrete pavement and new pavement perpendicular or parallel to the direction of traffic by methods described in applicable bid items, or as directed. Provide clean edges or joints without jagged appearance or chunks broken out. This work is considered subsidiary to various bid items.

Project Number: See Title Sheet
 Control: 0033-04-072 ETC
 County: JONES
 Highway: US83

**Environmental
 Endangered and Protected Species**

1. Migratory Birds
 - a. **Bird nesting season is typically 15Feb through 15Sep annually.**
 - b. The Contractor will avoid disturbing, destroying, removing, or relocating migratory birds and active nests found in trees, culverts, bridges, on the ground, or anywhere they are encountered.
 - c. Perform all tree trimming and other vegetation clearing activities during the non-breeding season (typically 15Sep-15Feb annually). Perform any inactive nest removal and bird exclusion methods to prevent birds from establishing nests. Phasing of work during construction may be necessary to stay in compliance.
 - d. When active nests are unexpectedly encountered on-site during construction, the Contractor will stop work and immediately notify the Engineer. Take measures to avoid disturbance of these birds, their occupied nest, eggs, and/or young, in accordance with the Migratory Bird Treaty Act, Texas Parks and Wildlife Code, and TxDOT policy.
 - e. The Engineer will notify the Contractor when work may resume.
 - f. The Contractor should be prepared to prevent migratory birds from building nests by utilizing nest prevention methods, such as bird-deterrent netting and bird-repelling sprays and/or gels, between 15Feb and 15Sep. The Contractor can discuss other preventative measures with the Engineer and/or District Environmental Staff.

Best Management Practices

1. Bird BMPs
 - a. Not disturbing, destroying, or removing active nests, including ground nesting birds, during the nesting season.
 - b. Avoiding the removal of unoccupied, inactive nests, as practicable.
 - c. Preventing the establishment of active nests during the nesting season on TxDOT owned and operated facilities and structures proposed for replacement or repair.
 - d. Not collecting, capturing, relocating, or transporting birds, eggs, young, or active nests without a permit.

Item 5, "Control of Work"

Use Method C for construction surveying.

All known utilities are identified in the plans, including the crossing of power lines. Use this information to identify potential issues with power poles and power lines prior to bidding. Make necessary arrangements with utility owners regarding temporary protections such as bracing power poles, and de-energizing power lines. The Department will not reimburse the cost of such temporary protections to the Contractor, unless the Engineer determines that inadequate information was available at the time the project was bid. **"Call Before You Dig" "Call 811"**

CONT	SECT	JOB	HIGHWAY
0033	04	072, ETC	US 83, ETC
DIST	COUNTY		SHEET NO.
ABL	JONES, ETC.		27

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

Provide notification to the District Traffic Engineering Section by telephone at 325-676-6991 and by email at ABL_TrafficFix@txdot.gov when planning drilling or excavation work in areas where existing TxDOT underground utilities exist. Visual evidence of TxDOT underground utilities in the area include illumination poles, ground boxes, flashing beacons, traffic signals, etc. This notification must be provided 72 hours in advance of performing the work.

Item 7, "Legal Relations and Responsibilities"

(1) Restricted Use of Materials for the Previously Evaluated Permit Areas.

Document both the project specific location (PSL) and their authorization. Maintain copies for review by the department or any regulatory agency. When an area within the project limits has been evaluated by the USACE as part of the permit process for this project:

- a. Suitable excavation of required material in the areas shown on the plans and cross sections as specified in Item 110 is used for permanent or temporary fill (Item 132, Embankment) within a USACE permit area;
- b. Suitable embankment (Item 132) from within the USACE permit area is used as fill within a USACE evaluated area; and,
- c. Unsuitable excavation or excess excavation ["Waste"] (Item 110) that is disposed of at a location approved by the Engineer within a USACE evaluated area.

(2) Contractor Materials from Areas Other than Previously Evaluated Areas.

Provide the department with a copy of all USACE coordination or approval(s) prior to initiating any activities for an area within the project limits that has not been evaluated by the USACE or for any off right of way locations used for the following, but not limited to, haul roads, equipment staging areas, borrow and disposal sites:

- a. Item 132, Embankment, used for temporary or permanent fill within a USACE permit area; and,
- b. Unsuitable excavation or excess excavation ["Waste"] (Item 110, Excavation) that is disposed of outside a USACE evaluated area.

The total area disturbed for this project is **0.0** acres. The disturbed area in this project, all project locations in the Contract, and the Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the ROW. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer and to the government that operates a separate storm sewer system.

Provide one SW3P Notification Board for this project. Notification Boards are to be placed at locations within the right-of-way but outside the clear zone as directed by the Engineer. Consider this work to be subsidiary to the various bid items of the contract.

General Notes

Sheet C

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

The Contractor's attention is directed to the Texas Aggregate Quarry Pit Safety Act. Any pit or quarry meeting the definition of an unacceptable unsafe location as defined in the Act is subject to regulations set forth in this Act. A copy of the Texas Administrative Code, Title 43, Part, 1, Chapter 21, Subchapter M may be viewed at [http://info.sos.state.tx.us/pls/pub/readtac\\$ext.ViewTAC](http://info.sos.state.tx.us/pls/pub/readtac$ext.ViewTAC).

Significant traffic generator events identified.

Stamford Tx—June 25th thru July 5th (Cowboy Reunion)

Anson Tx—Monday thru Friday 7am-4pm while school is in session

Hard hats are required at all times during construction when construction personnel are in TxDOT Right-of-Way.

Item 8 "Prosecution and Progress"

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process and/or execute all contracts at the same time.

Coordinate and update the work schedule with the project inspector daily. Give a minimum of 24 hours of notice to project inspector if work requiring inspection or testing is to be performed. Failure to do so may cause that work to be delayed or postponed if TxDOT personnel are not available. Work performed without suitable inspection, as determined by the Engineer, may be ordered removed and replaced at Contractor's expense.

Item 9, "Measurement and Payment"

The progress payment period shall end on the 25th of each month, unless directed by the Area Office Engineer. Material on Hand (MOH) is due two business days before estimate cut off.

Item 134, "Backfilling"

Backfill pavement edges no later than 2 weeks after the construction of the final surface. Apply emulsion at a 50/50 of water to emulsion; emulsion rate = 0.15 gal/sy residual emulsion.

Item 320, "Equipment for Hot Mix Asphalt Materials"

Use of a motor grader is allowed for spot repair of asphalt base.

Item 351, "Flexible Pavement Structure Repair"

The quantity shown in the plans for pavement structure repair is estimated. The Engineer will determine specific locations to be repaired. Unless otherwise shown in the plans, multiple locations throughout the project will be repaired, and may vary significantly in length and width.

General Notes

Sheet D

\$ DATES \$
\$ TIME \$
\$ FILES \$



GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
0033	04	072, ETC	US 83, ETC
DIST	COUNTY		SHEET NO.
ABL	JONES, ETC.		28

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

Item 354, “Planning and Texturing Pavement”

TxDot will retain ownership of planed material from CA2,CA3. Contractor to deliver and stockpile approx .88miles South of the city of Crossplains Tx and approx 251’ Southwest of the intersection SH206 and SH279 on TxDot ROW.

Contractor to retain ownership of excess RAP and remove the unused material from the project site upon completion of the paving work from J1,J2,J3,J4,CA1,HA1.

Item 502, “Barricades, Signs and Traffic Handling”

Mobile traffic control in accordance with TPC 3 series will be required for placement of short duration, short term, intermediate term, and long-term traffic control.

Provide the Engineer with written notification seven (7) days in advance of major traffic changes. A major traffic change is defined as the temporary (greater than one day) or permanent relocation of traffic lanes typically in an urban setting. The notice will, at a minimum, include the expected date, time and scope of the traffic change. The Department will utilize the information provided to inform the traveling public of the changes. Failure to provide advance notice, or to provide accurate information, will result in delaying the work until such time that the public has been notified.

Additional signs, barricades and traffic handling may be necessary to complete the work shown herein and will be provided by the contractor as required and will be considered subsidiary to this item.

Provide separate attenuators for each work area within a common lane closure as approved or directed by the Engineer.

In sections where traffic is restricted to one lane, two-way traffic, flaggers will be stationed at each end of that section with two-way communication devices and a pilot car will control operations.

Relocate existing roadside signs to temporary supports as approved by the engineer.

All safety appurtenances such as signs, delineators, object markers and route markers will be in place prior to opening each phase of the construction to traffic, unless otherwise directed.

During construction on all underpass structures erect and maintain accurate clearance signs in accordance with the “Texas Manual on Uniform Traffic Control Device for Streets and Highways”. The mounting method for the temporary clearance sign is subject to approval of the Engineer. Temporary clearance signs are considered subsidiary to the various bid items. Movement of construction equipment and haul trucks will be prohibited from crossing the median unless specifically authorized by the Engineer. Ingress and egress to main lanes will be at entrance and exit ramps.

General Notes

Sheet E

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The Contractor's person responsible for TCP compliance must be available by local telephone and have a response time within 45 minutes.

Work will not be allowed on both sides of the roadbed at the same time.

Equip all work vehicles within 30 feet of the traveled way with a functioning amber strobe light or rotating beacon visible from all directions.

Repair barricades within the timeline shown on the barricade inspection report. Failure to comply will cease all work until barricades are repaired to the satisfaction of the Department.

Replace all damaged traffic control devices immediately. Remove any damaged traffic control devices from the project within 24 hours.

Conflicting guide signs shall be covered as approved by the Engineer. This work shall be subsidiary to Item 502.

Pilot car is subsidiary to item 502.

Reduced regulatory speed limit signs should only be posted in the vicinity of ongoing work activity as shown on BC (3)-21 and not throughout the entire project. Removing, relocating or covering speed limit signs shall be considered subsidiary to item 502.

Item 504, “Field Office for Laboratory”

Field Laboratory:

Furnish a “Type D” structure for the asphalt mix control laboratory for the Engineer’s exclusive use. In addition to the requirements of Item 504, furniture and equipment to be furnished by the Contractor shall include:

- eye wash station
- first-aid kit
- two fire extinguishers
- Provide internet connectivity for use by TxDOT lab testing personnel at all laboratory structures on this project.

General Notes

Sheet F

\$ DATES \$
\$ TIME \$
\$ FILES \$



GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
0033	04	072, ETC	US 83, ETC
DIST	COUNTY		SHEET NO.
ABL	JONES, ETC.		29

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

Item 506, “Temporary Erosion, Sedimentation, and Environmental Controls”

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7.

Item 530, “Intersections, Driveways, and Turnouts”

Excavation and embankment necessary to construct the intersections and driveways according to the details shown elsewhere shall be considered subsidiary to this item.

Item 585, “Ride Quality for Pavement Surfaces”

The Engineer reserves the right to prohibit corrective work and assess the penalty for each occurrence of localized roughness per Article 585.3.4.2.3.2.

Use pay adjustment schedule **(3 (three))** for Ride Quality bonus/penalty calculation.

Item 662, “Work Zone Pavement Markings”

Dispose of tabs and paper in an approved trash receptacle. (Reference Standard **SW3P**, waste material)

Item 666, “Retro reflectorized Pavement Markings”

Provide a complete system of thermoplastic pavement markings at locations indicated on the plans and as directed by the engineer. The plans are intended to show typical conditions, which can be extended to similar conditions throughout this project as approved or directed.

All longitudinal pavement markings (including profile pavement markings) must meet minimum retro reflectivity requirements.

Establish a true and correct alignment with a method approved by the Engineer. This work will be considered subsidiary.

Contractor is responsible for re-establishing location and alignment for new pavement markings matching pavement marking alignment prior to construction activities. This work will be considered subsidiary.

Item 672, “Raised Pavement Markers”

Provide a complete system of raised pavement markers at locations indicated on the plans and as directed by the engineer. The plans are intended to show typical conditions, which can be extended to similar conditions throughout this project as approved or directed.

Bituminous adhesive shall be used on this project.

General Notes

Sheet G

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

Item 677, “Eliminating Existing Pavement Markings and Markers”

Remove the existing raised pavement markings (RPMs) and profile pavement markings as the work progresses, or as directed by the Engineer. Removal methods shall be approved by the Engineer. Properly dispose of materials removed. Removal of existing profile pavement markings will be paid for directly. Removal of RPMs will not be paid for directly but will be subsidiary to the pertinent bid items.

Item 6185, “Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)”

Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA) will not be considered a major item of work on this project.

TMA,s will only be paid while workers are present or to protect a blunt object.

BASIS OF ESTIMATE FOR STATIONARY TMAs					
			TMA (Stationary)		
Phase	Standard	Standard	Required	Additional	TOTAL
1 -CA1	TCP(2-3A)-18		1		1
1 -CA2,CA3	TCP(2-3A)-18		1		1
1 -J1	TCP(2-4)-18		1		1
1 -J2,J3,J4,HA1	TCP(2-3A)-18	TCP(2-4)-18	2		2
2 -CA1	TCP(2-3A)-18		1		1
2 -CA2,CA3	TCP(2-3A)-18		1		1
2 -J1	TCP(2-4)-18		1		1
2 -J2,J3,J4,HA1	TCP(2-3A)-18	TCP(2-4)-18	2		2
3 -CA1	TCP(2-3A)-18		1		1
3 -CA2,CA3	TCP(2-3A)-18		1		1
3 -J1	TCP(2-4)-18		1		1
3 -J2,J3,J4,HA1	TCP(2-3A)-18	TCP(2-4)-18	2		2
BASIS OF ESTIMATE FOR MOBILE TMAs					
			TMA (Mobile)		
Phase	Standard	Standard	Required	Additional	TOTAL
3 -CA1	TCP(3-1)-13	TCP(3-3)-14	4		4
3 -CA2,CA3	TCP(3-1)-13	TCP(3-3)-14	4		4
3 -J1	TCP(3-1)-13	TCP(3-3)-14	4		4
3 -J2,J3,J4,HA1	TCP(3-1)-13	TCP(3-3)-14	4		4

General Notes

Sheet H

\$ DATES \$
\$ TIME \$
\$ FILES \$



GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
0033	04	072, ETC	US 83, ETC
DIST	COUNTY		SHEET NO.
ABL	JONES, ETC.		30

Project Number: See Title Sheet
Control: 0033-04-072 ETC
County: JONES
Highway: US83

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project. The Contractor must get approval from the Engineer for any changes in the number of TMA as shown in the plans.

If a TMA is used for both mobile and stationary traffic control on the same day, it will be paid for as stationary for that day.

General Notes

Sheet I

\$ DATES \$
\$ TIME \$
\$ FILES \$



GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
0033	04	072, ETC	US 83, ETC
DIST	COUNTY		SHEET NO.
ABL	JONES, ETC.		31



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0033-04-072

DISTRICT Abilene
HIGHWAY BU 277G, FM 18, SH 206, SH 36, SH 6, US 83

COUNTY Callahan, Haskell, Jones

CONTROL SECTION JOB				0006-11-025		0033-04-072		0107-01-039		0157-07-006		0157-08-011		0157-08-012	
PROJECT ID				A00140699		A00182941		A00182943		A00185036		A00182942		A00185035	
COUNTY				Callahan		Jones		Jones		Haskell		Jones		Jones	
HIGHWAY				FM 18		US 83		SH 6		SH 6		BU 277G		SH 6	
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL
	134-6004	BACKFILL (TY A OR B)	STA	171.000						90.000					
	351-6013	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SY	3,788.000		102.000		691.000		327.000		174.000		289.000	
	354-6183	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	SY	37,951.000		7,467.000		77,077.000		27,121.000		14,256.000		25,550.000	
	500-6001	MOBILIZATION	LS			1.000									
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO			7.000									
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA			370.000		553.000		474.000		441.000		1,258.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,560.000		110.000		1,304.000		1,941.000		536.000		986.000	
	666-6300	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	LF			2,461.000		1,852.000		3,166.000		3,164.000		8,388.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	17,044.000		1,353.000		21,442.000		9,135.000		7,910.000		9,466.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF					2,379.000		3,815.000					
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	17,044.000		1,354.000		12,217.000		13,388.000		5,570.000		9,758.000	
	668-6014	PREFAB PAV MRK TY B (W)(8")(SLD)	LF	200.000		1,453.000		416.000		296.000				193.000	
	668-6016	PREFAB PAV MRK TY B (W)(12")(SLD)	LF			173.000		820.000							
	668-6018	PREFAB PAV MRK TY B (W)(24")(SLD)	LF			195.000		681.000		20.000		25.000		55.000	
	668-6019	PREFAB PAV MRK TY B (W)(ARROW)	EA	2.000				10.000		2.000				2.000	
	668-6027	PREFAB PAV MRK TY B (W)(WORD)	EA	2.000				6.000		6.000				2.000	
	668-6091	PREFAB PAV MRK TY C (W) (18")(YLD TRI)	EA							7.000					
	672-6007	REFL PAV MRKR TY I-C	EA	12.000		18.000		32.000		58.000		78.000		114.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	306.000		22.000		294.000		534.000		97.000		122.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA			12.000		17.000							
	3077-6053	SP MIXESSP-DSAC-B PG70-22	TON	4,175.000		821.000		8,478.000		2,983.000		1,568.000		2,811.000	
	3077-6075	TACK COAT	GAL	7,590.000		1,493.000		15,415.000		5,424.000		2,851.000		5,110.000	
	6185-6002	TMA (STATIONARY)	DAY	14.000		4.000		16.000		8.000		5.000		7.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	4.000		4.000		4.000		4.000		4.000		4.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS			1.000									
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS			1.000									



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0033-04-072

DISTRICT Abilene
HIGHWAY BU 277G, FM 18, SH 206, SH 36, SH 6, US 83

COUNTY Callahan, Haskell, Jones

CONTROL SECTION JOB				0452-02-043		0480-03-051		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00182940		A00184109			
COUNTY				Callahan		Callahan			
HIGHWAY				SH 36		SH 206			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	134-6004	BACKFILL (TY A OR B)	STA	145.000		112.000		518.000	
	351-6013	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SY	660.000		239.000		6,270.000	
	354-6183	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	SY	37,112.000		23,097.000		249,631.000	
	500-6001	MOBILIZATION	LS					1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO					7.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA					3,096.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,499.000		1,100.000		9,036.000	
	666-6300	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	LF					19,031.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	13,306.000		10,814.000		90,470.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF	1,057.000		98.000		7,349.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	11,442.000		10,544.000		81,317.000	
	668-6014	PREFAB PAV MRK TY B (W)(8")(SLD)	LF	555.000		125.000		3,238.000	
	668-6016	PREFAB PAV MRK TY B (W)(12")(SLD)	LF					993.000	
	668-6018	PREFAB PAV MRK TY B (W)(24")(SLD)	LF	50.000		118.000		1,144.000	
	668-6019	PREFAB PAV MRK TY B (W)(ARROW)	EA	4.000		2.000		22.000	
	668-6027	PREFAB PAV MRK TY B (W)(WORD)	EA	2.000		5.000		23.000	
	668-6091	PREFAB PAV MRK TY C (W) (18")(YLD TRI)	EA					7.000	
	672-6007	REFL PAV MRKR TY I-C	EA	14.000		7.000		333.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	182.000		136.000		1,693.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA					29.000	
	3077-6053	SP MIXESSP-DSAC-B PG70-22	TON	4,082.000		2,541.000		27,459.000	
	3077-6075	TACK COAT	GAL	7,422.000		4,619.000		49,924.000	
	6185-6002	TMA (STATIONARY)	DAY	10.000		8.000		72.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	4.000		4.000		32.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS					1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS					1.000	

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\14 QUANTITY SUMMARY CA1.dgn
4/2/2022 1:04:19 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS			
CSJ 0006-11-025	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	DAY	DAY
STA 391+50.45-476+89.94	1560	14	4
PROJECT TOTALS	1560	14	4

SUMMARY OF ROADWAY ITEMS					
CSJ 0006-11-025	351 6013	3077 6053	354 6183	3077 6075	134 6004
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT	BACKFILL (TY A OR B)
	SY	TON	SY	GAL	STA
STA 391+50.45-476+89.94	3788	4175	37951	7590	171
PROJECT TOTALS	3788	4175	37951	7590	171

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF PAVEMENT MARKING ITEMS							
CSJ 0006-11-025	672 6009	668 6027	668 6019	672 6007	668 6014	666 6303	666 6315
	REFL PAV MRKR TY II-A-A	PREFAB PAV MRK TY B (W)(WORD)	PREFAB PAV MRK TY B (W)(ARROW)	REFL PAV MRKR TY I-C	PREFAB PAV MRK TY B (W)(8")(SLD)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	EA	EA	EA	EA	LF	LF	LF
STA 391+50.45-476+89.94	306	2	2	12	200	17044	17044
PROJECT TOTALS	306	2	2	12	200	17044	17044

BASIS OF ESTIMATE							
CSJ 0006-11-025	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT
	3077 6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	37951	SY	4175	GAL
	3077 6075	TACK COAT	0.2 GAL/SY	37951	SY	7590	GAL

QUANTITY SUMMARY CA1



NO SCALE			SHEET 1 OF 1			
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY		SHEET NO.			
TEXAS	JONES, ETC.		34			
DISTRICT	CONTROL	SECTION				JOB
ABL	0033	04				072, ETC

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\15 QUANTITY SUMMARY CA2.dgn
4/2/2022 1:04:20 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS			
CSJ 0452-02-043	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	DAY	DAY
STA 1676+15.20-1748+76.30			
PROJECT TOTALS	1499	10	4

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF ROADWAY ITEMS					
CSJ 0452-02-043	351 6013	3077 6053	354 6183	3077 6075	134 6004
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT	BACKFILL (TY A OR B)
	SY	TON	SY	GAL	STA
STA 1676+15.20-1748+76.30					
PROJECT TOTALS	660	4082	37112	7422	145

SUMMARY OF PAVEMENT MARKING ITEMS									
CSJ 0452-02-043	668 6018	668 6014	672 6007	672 6009	668 6027	668 6019	666 6303	666 6312	666 6315
	PREFAB PAV MRK TY B (W)(24")(SLD)	PREFAB PAV MRK TY B (W)(8")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	PREFAB PAV MRK TY B (W)(WORD)	PREFAB PAV MRK TY B (W)(ARROW)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	LF	LF	EA	EA	EA	EA	LF	LF	LF
STA 1676+15.20-1748+76.30	50	555	14	182	2	4	13306	1057	11442
PROJECT TOTALS	50	555	14	182	2	4	13306	1057	11442

BASIS OF ESTIMATE								
CSJ 0452-02-043	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT	
	3077 6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	37112	SY	4082	GAL	
	3077 6075	TACK COAT	0.2 GAL/SY	37112	SY	7422	GAL	

QUANTITY SUMMARY CA2



NO SCALE				SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY			SHEET NO.		
TEXAS	JONES, ETC.			35		
DISTRICT	CONTROL	SECTION	JOB			
ABL	0033	04	072, ETC			

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\16 QUANTITY SUMMARY CA3.dgn
4/2/2022 1:04:21 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS			
CSJ 0480-03-051	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	DAY	DAY
STA 0+00.00-55+00.00	1100	8	4
PROJECT TOTALS	1100	8	4

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF ROADWAY ITEMS					
CSJ 0480-03-051	351 6013	3077 6053	354 6183	3077 6075	134 6004
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT	BACKFILL (TY A OR B)
	SY	TON	SY	GAL	STA
STA 0+00.00-55+00.00	239	2541	23097	4619	112
PROJECT TOTALS	239	2541	23097	4619	112

SUMMARY OF PAVEMENT MARKING ITEMS									
CSJ 0480-03-051	668 6018	668 6014	672 6007	672 6009	668 6027	668 6019	666 6303	666 6312	666 6315
	PREFAB PAV MRK TY B (W)(24")(SLD)	PREFAB PAV MRK TY B (W)(8")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	PREFAB PAV MRK TY B (W)(WORD)	PREFAB PAV MRK TY B (W)(ARROW)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	LF	LF	EA	EA	EA	EA	LF	LF	LF
STA 0+00.00-55+00.00	118	125	7	136	5	2	10814	98	10544
PROJECT TOTALS	118	125	7	136	5	2	10814	98	10544

BASIS OF ESTIMATE								
CSJ 0480-03-051	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT	
	3077	6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	23097	SY	2541	GAL
	3077	6075	TACK COAT	0.2 GAL/SY	23097	SY	4619	GAL

QUANTITY SUMMARY CA3



NO SCALE			SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.		
6	SEE TITLE SHEET		US 83, ETC		
STATE	COUNTY		SHEET NO.		
TEXAS	JONES, ETC.		36		
DISTRICT	CONTROL	SECTION	JOB		
ABL	0033	04	072, ETC		

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\17 QUANTITY SUMMARY HA1 .dgn
4/2/2022 1:04:23 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS				
CSJ 0157-07-006	662 6109	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY W	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	EA	DAY	DAY
STA 0+00.00-62+20.00	474	1941	8	4
PROJECT TOTALS	474	1941	8	4

SUMMARY OF ROADWAY ITEMS					
CSJ 0157-07-006	351 6013	3077 6053	354 6183	3077 6075	134 6004
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT	BACKFILL (TY A OR B)
	SY	TON	SY	GAL	STA
STA 0+00.00-62+20.00	327	2983	27121	5424	90
PROJECT TOTALS	327	2983	27121	5424	90

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF PAVEMENT MARKING ITEMS											
CSJ 0157-07-006	668 6091	668 6018	668 6014	672 6007	672 6009	668 6027	668 6019	666 6300	666 6303	666 6312	666 6315
	PREFAB PAV MRK TY C (W)(18")(YLD TRI)	PREFAB PAV MRK TY B (W)(24")(SLD)	PREFAB PAV MRK TY B (W)(8")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	PREFAB PAV MRK TY B (W)(WORD)	PREFAB PAV MRK TY B (W)(ARROW)	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	EA	LF	LF	EA	EA	EA	EA	LF	LF	LF	LF
STA 0+00.00-62+20.00	7	20	296	58	534	6	2	3166	9135	3815	13388
PROJECT TOTALS	7	20	296	58	534	6	2	3166	9135	3815	13388

BASIS OF ESTIMATE								
CSJ 0157-07-006								
ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT		
3077 6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	27121	SY	2983	GAL		
3077 6075	TACK COAT	0.2 GAL/SY	27121	SY	5424	GAL		

QUANTITY SUMMARY HA1



NO SCALE				SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY			SHEET NO.		
TEXAS	JONES, ETC.			37		
DISTRICT	CONTROL	SECTION	JOB			
ABL	0033	04	072, ETC			

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\18 QUANTITY SUMMARY J1 .dgn
4/2/2022 1:04:24 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS				
CSJ 0033-04-072	662 6109	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY W	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	EA	DAY	DAY
STA 1161+27.47-1173+20.70	370	110	4	4
PROJECT TOTALS	370	110	4	4

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF ROADWAY ITEMS				
CSJ 0033-04-072	351 6013	3077 6053	354 6183	3077 6075
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT
	SY	TON	SY	GAL
STA 1161+27.47-1173+20.70	102	821	7467	1493
PROJECT TOTALS	102	821	7467	1493

SUMMARY OF PAVEMENT MARKING ITEMS									
CSJ 0033-04-072	666 6300	666 6315	666 6303	668 6018	668 6014	668 6016	672 6007	672 6009	672 6010
	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	PREFAB PAV MRK TY B (W)(24")(SLD)	PREFAB PAV MRK TY B (W)(8")(SLD)	PREFAB PAV MRK TY B (W)(12")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	REFL PAV MRKR TY II-C-R
	LF	LF	LF	LF	LF	LF	EA	EA	EA
STA 1161+27.47-1173+20.70	2461	1354	1153	195	1453	173	18	22	12
PROJECT TOTALS	2461	1354	1153	195	1453	173	18	22	12

QUANTITY SUMMARY J1

BASIS OF ESTIMATE							
CSJ 0033-04-072	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT
	3077 6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	7467	SY	821	GAL
	3077 6075	TACK COAT	0.2 GAL/SY	7467	SY	1493	GAL



NO SCALE				SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY			SHEET NO.		
TEXAS	JONES, ETC.			38		
DISTRICT	CONTROL	SECTION	JOB			
ABL	0033	04	072, ETC			

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\19 QUANTITY SUMMARY J2 .dgn
4/2/2022 1:04:25 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS				
CSJ 0157-08-012	662 6109	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	EA	DAY	DAY
STA 47+73.50-0+00.00	1258	986	7	4
PROJECT TOTALS	1258	986	7	4

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF ROADWAY ITEMS				
CSJ 0157-08-012	351 6013	3077 6053	354 6183	3077 6075
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT
	SY	TON	SY	GAL
STA 47+73.50-0+00.00	289	2811	25550	5110
PROJECT TOTALS	289	2811	25550	5110

SUMMARY OF PAVEMENT MARKING ITEMS									
CSJ 0157-08-012	668 6018	668 6014	672 6007	672 6009	668 6027	668 6019	666 6300	666 6303	666 6315
	PREFAB PAV MRK TY B (W)(24")(SLD)	PREFAB PAV MRK TY B (W)(8")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	PREFAB PAV MRK TY B (W)(WORD)	PREFAB PAV MRK TY B (W)(ARROW)	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	LF	LF	EA	EA	EA	EA	LF	LF	LF
STA 47+73.50-0+00.00	55	193	114	122	2	2	8388	9466	9758
PROJECT TOTALS	55	193	114	122	2	2	8388	9466	9758

BASIS OF ESTIMATE							
CSJ 0157-08-012	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT
	3077 6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	25550	SY	2811	GAL
	3077 6075	TACK COAT	0.2 GAL/SY	25550	SY	5110	GAL

QUANTITY SUMMARY J2



NO SCALE				SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY			SHEET NO.		
TEXAS	JONES, ETC.			39		
DISTRICT	CONTROL	SECTION	JOB			
ABL	0033	04	072, ETC			

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\20 QUANTITY SUMMARY J3 .dgn
4/2/2022 1:04:26 PM

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS				
CSJ 0157-08-011	662 6109	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY W	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	EA	DAY	DAY
STA 834+16.10-860+80.60	441	536	5	4
PROJECT TOTALS	441	536	5	4

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF ROADWAY ITEMS				
CSJ 0157-08-011	351 6013	3077 6053	354 6183	3077 6075
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT
	SY	TON	SY	GAL
STA 834+16.10-860+80.60	174	1568	14256	2851
PROJECT TOTALS	174	1568	14256	2851

SUMMARY OF PAVEMENT MARKING ITEMS						
CSJ 0157-08-011	668 6018	672 6007	672 6009	666 6300	666 6303	666 6315
	PREFAB PAV MRK TY B (W)(24")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	LF	EA	EA	LF	LF	LF
STA 834+16.10-860+80.60	25	78	97	3164	7910	5570
PROJECT TOTALS	25	78	97	3164	7910	5570

BASIS OF ESTIMATE							
CSJ 0157-08-011	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT
	3077 6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	14256	SY	1568	GAL
	3077 6075	TACK COAT	0.2 GAL/SY	14256	SY	2851	GAL

QUANTITY SUMMARY J3



NO SCALE				SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY			SHEET NO.		
TEXAS	JONES, ETC.			40		
DISTRICT	CONTROL	SECTION	JOB			
ABL	0033	04	072, ETC			

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS				
CSJ 0107-01-039	662 6109	662 6111	6185 6002	6185 6005
	WK ZN PAV MRK SHT TERM (TAB)TY W	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	EA	DAY	DAY
LINE A 747+00.00-834+16.10	329	776	10	2
LINE B STA 0+00.00-8+50.98	224	528	6	2
PROJECT TOTALS	553	1304	16	4

NOTE: ITEM 662-6109 AND 662-6111 AMOUNTS HAVE BEEN DOUBLED TO ALLOW FOR APPLICATION AFTER MILLING AND PAVING

SUMMARY OF ROADWAY ITEMS				
CSJ 0107-01-039	351 6013	3077 6053	354 6183	3077 6075
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SP MIXES SP-D SAC-B PG70-22	PLANE ASPH CONC PAV(1/2" TO 1-1/2")	TACK COAT
	SY	TON	SY	GAL
LINE A 747+00.00-834+16.10	411	5047	45885	9177
LINE B STA 0+00.00-8+50.98	280	3431	31192	6238
PROJECT TOTALS	691	8478	77077	15415

SUMMARY OF PAVEMENT MARKING ITEMS												
CSJ 0107-01-039	668 6018	668 6016	668 6014	672 6010	672 6007	672 6009	668 6027	668 6019	666 6300	666 6303	666 6312	666 6315
	PREFAB PAV MRK TY B (W)(24")(SLD)	PREFAB PAV MRK TY B (W)(12")(SLD)	PREFAB PAV MRK TY B (W)(8")(SLD)	REFL PAV MRKR TY II-C-R	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	PREFAB PAV MRK TY B (W)(WORD)	PREFAB PAV MRK TY B (W)(ARROW)	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)
	LF	LF	LF	EA	EA	EA	EA	EA	LF	LF	LF	LF
LINE A 747+00.00-834+16.10	405	488	248	10	19	175	4	6	1102	12765	1416	7273
LINE B STA 0+00.00-8+50.98	276	332	168	7	13	119	2	4	750	8677	963	4944
PROJECT TOTALS	681	820	416	17	32	294	6	10	1852	21442	2379	12217

QUANTITY SUMMARY J4

BASIS OF ESTIMATE								
CSJ 0107-01-039	ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT	
	3077	6053	SP MIXES SP-D SAC-B	EST @ 220 LBS/SY	77077	SY	8478	GAL
	3077	6075	TACK COAT	0.2 GAL/SY	77077	SY	15415	GAL



NO SCALE				SHEET 1 OF 1		
FHWA DIVISION	PROJECT NO.		HIGHWAY NO.			
6	SEE TITLE SHEET		US 83, ETC			
STATE	COUNTY			SHEET NO.		
TEXAS	JONES, ETC.			41		
DISTRICT	CONTROL	SECTION	JOB			
ABL	0033	04	072, ETC			

\$FILES \$DATES \$TIME\$

SEQUENCE OF WORK

GENERAL

1. ALL ROADWORK TO BE COMPLETED DURING DAYTIME HOURS WITH FOLLOWING CRITERIA:
USE FLAGGERS FOR ROAD INTERSECTIONS. BUSINESS AND RESIDENTIAL DRIVES TO REMAIN OPEN.
2. PLACE ADVANCE WARNING SIGNS AND BARRICADES IN ACCORDANCE WITH TMUTCD AND APPLICABLE STANDARDS.
3. FOLLOW THE REQUIREMENTS OF THE EDGE CONDITION WORKSHEET AS WORK PROGRESSES.
4. THE STEPS OF THE CONSTRUCTION SEQUENCE MAY BE MODIFIED AS APPROVED, IN WRITING, BY THE ENGINEER. ANY CHANGES IMPLEMENTED, SHALL HAVE DETAILS THAT ARE SIGNED AND SEALED BY A LICENSED PROFESSIONAL ENGINEER.

PHASE 1: MILLING

1. LOCATE AREAS FOR PAVEMENT REPAIR PRIOR TO MILLING OPERATIONS.
2. MILLING OPERATIONS SHALL PROGRESS IN SEGMENT LENGTHS THAT WILL ALLOW THE FULL WIDTH OF THE PAVEMENT TO BE MILLED IN ONE DAY. DO NOT MILL MORE THEN ONE TOWN AHEAD OF THE PAVING OPERATION.
3. TAPER MILLING DEPTH AT THE END OF EACH SEGMENT TO PROVIDE A SMOOTH TRANSITION FROM THE MILLED TO EXISTING SURFACE.
4. REMOVE ALL LOOSE DEBRIS AND PLACE TEMPORARY PAVEMENT MARKINGS PRIOR TO OPENING ANY LANE TO TRAFFIC OR AS DIRECTED.


PHASE 2: PAVEMENT REPAIR

1. COMPLETE PAVEMENT REPAIRS AT LOCATIONS DIRECTED BY THE ENGINEER.
2. REMOVE ALL LOOSE DEBRIS FROM CLOSED LANES BEFORE OPENING TO TRAFFIC.
3. MAINTAIN TEMPORARY PAVEMENT MARKINGS AS NEEDED.

PHASE 3: HMA & MISC. CONSTRUCTION

1. PLACEMENT OF HOTMIX MAY PROCEED BEFORE COMPLETION OF THE TACKCOAT OPERATIONS AS APPROVED BY THE ENGINEER.
2. PLACE TEMPORARY PAVEMENT MARKINGS BEFORE OPENING CLOSED LANES TO TRAFFIC OR AS DIRECTED.
3. PLACE FINAL STRIPING.
4. COMPLETE FINAL CLEANUP AND PROJECT PUNCHLIST.

DS



4/2/2022

US83 SEQUENCE OF WORK




SCALE: N/A SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.	
6	SEE TITLE SHEET		US 83, ETC	
STATE	COUNTY		SHEET NO.	
TEXAS	JONES, ETC.		42	
DISTRICT	CONTROL	SECTION		JOB
ABL	0033	04		072, ETC



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS


Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet





Edge Condition I
S = (3:1) (or flatter)



Edge Condition II
S = ((2.99):1) to (1:1)



Edge Condition III
S is steeper than (1:1)



FACTORS CONSIDERED IN THE GUIDELINES:


- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

Zone	Treatment Types Guidelines:
①	No treatment.
②	CW 8-11 "Uneven Lanes" signs.
③	CW 8-9a "Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.
④	CW 8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge fill may be provided to change the edge slope to that of the preferable Edge Condition I.
⑤	Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone- 4 may be used after consideration of other applicable factors.

Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ([Cross-hatched symbol])



- E = ADT x T
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within a lateral offset of 20 feet from the edge of the travel lane.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.

DATE:
FILE:

DS

DocuSigned by:
Paul N Norman, P.E.
25E04E8F4AB0444...
4/2/2022


Texas Department of Transportation
Traffic Operations Division

TREATMENT FOR VARIOUS EDGE CONDITIONS


© TxDOT 2022		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS					
CONT	SECT	JOB		HIGHWAY	
0033	04	072, ETC		US 83, ETC	
DIST		COUNTY		SHEET NO.	
ABL		JONES, ETC.		43	

03-01
08-01 correct typos


Warning Sign Sequence in opposite direction same as below.



UNPAVED INACTIVE WORK AREA



INTERSECTING STATE HIGHWAY OR COUNTY ROAD WITHIN ACTIVE WORK AREA



ONE LANE TWO-WAY CONTROL WITH PILOT CAR

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Pilot Vehicle
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- A Shadow Vehicle with a TMA shall be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- Flaggers shall hold traffic until the pilot vehicle is prepared to lead traffic through the work area.
- Pilot vehicle shall have the name of the Contractor prominently displayed and shall utilize flashing light bar.
- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.
- Place additional signs at State Highway and County Road intersections. Place additional signs every mile to the end of the unpaved area.
- Unless otherwise shown on the plans, the work performed and materials furnished in accordance with this Item will not be paid for directly but will be subsidiary to pertinent items.
- Perform all work in accordance with Item 510, "One-Way Traffic Control".

DocuSigned by

 Paul N. Norman, P.E.
 25E04E6F4AD6444...
 4/2/2022

Texas Department of Transportation
 Abilene District

**TRAFFIC CONTROL PLAN
 PILOT VEHICLE OPERATION**

SHEET 1 OF 1 NOT TO SCALE

REVISIONS	CONT	SECT	JOB	HIGHWAY
8-17	0033	04	072, J ETC	US 90W ETC
	DIST		COUNTY	SHEET NO.
	DBT		JONESTY ETC.	44

02/20/2022 05:52 PM T:\Engdat\Project\0033-04\CSJ_0033-04-072_ETC_PLAN_SET\23A_PILOT_VEHICLE_OPERATION.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
 FILE: DOCUMENT NAME

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

BC (1) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
4-03	7-13	0033	04	072, ETC	US	83,	ETC		
9-07	8-14	DIST	COUNTY		SHEET NO.				
5-10	5-21	ABL	JONES, ETC.		45				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL LOCATION OF CROSSROAD SIGNS



May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
□	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	46	

DATE: DATE TIME
FILE: DOCUMENT NAME

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0033	04	072, ETC	US 83, ETC				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ABL	JONES, ETC.	47					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	48	


DATE: DATE TIME FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	49	

DATE: DATE TIME
FILE: DOCUMENT NAME

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	50	

DATE TIME DOCUMENT NAME


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE: DATE TIME
FILE: DOCUMENT NAME

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	51	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CWI-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:		SECT:		JOB:		HIGHWAY:	
REVISIONS		0033	04	072, ETC		US 83, ETC			
4-03	8-14			DIST:		COUNTY:		SHEET NO.	
9-07	5-21			ABL		JONES, ETC.		52	
7-13									


DATE: DATE TIME
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



CHEVRONS

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	53	


DATE: DATE TIME
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ABL	JONES, ETC.	54	

DATE: DATE TIME
FILE: DOCUMENT NAME

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	ABL	JONES, ETC.	55	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	ABL	JONES, ETC.	56	
11-02 8-14				




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
 - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.




TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK


TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
2-94 4-98	DIST	COUNTY		SHEET NO.
8-95 2-12	ABL	JONES, ETC.		57
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-2a)
2-LANE ROADWAY WITHOUT PAVED SHOULDERS
ONE LANE TWO-WAY
CONTROL WITH YIELD SIGNS
(Less than 2000 ADT - See Note 9)



TCP (2-2b)
2-LANE ROADWAY WITHOUT PAVED SHOULDERS
ONE LANE TWO-WAY
CONTROL WITH FLAGGERS

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 ONE-LANE TWO-WAY
 TRAFFIC CONTROL**


TCP (2-2) - 18

FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
8-95 3-03	DIST	COUNTY		SHEET NO.
1-97 2-12	ABL	JONES, ETC.		58
4-98 2-18				


DATE: DATE TIME
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME



TCP (2-3a)
2-LANE ROADWAY WITH PAVED SHOULDERS
ONE LANE CLOSED
ADEQUATE FIELD OF VIEW



TCP (2-3b)
2-LANE ROADWAY WITH PAVED SHOULDERS
ONE LANE CLOSED
INADEQUATE FIELD OF VIEW

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	120'	90'	
35		205'	225'	245'	35'	160'	120'	
40		265'	295'	320'	40'	240'	155'	
45	L = WS	450'	495'	540'	45'	320'	195'	
50		500'	550'	600'	50'	400'	240'	
55		550'	605'	660'	55'	500'	295'	
60		600'	660'	720'	60'	600'	350'	
65		650'	715'	780'	65'	700'	410'	
70		700'	770'	840'	70'	800'	475'	
75		750'	825'	900'	75'	900'	540'	

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓
				TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN TRAFFIC SHIFTS ON TWO-LANE ROADS


TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	ABL	JONES, ETC.	59	
4-98 2-18				


163

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion or application of this standard to any particular project or location. See the project manual for more information.


DATE: 0922202018 11:24:56 PM
FILE: Project\Operations\Traffic Control Plans\TCP\03\03-13.dwg




TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY



TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS




TRAIL/SHADOW VEHICLE A
with RIGHT Directional display Flashing Arrow Board

LEGEND		
*	Trail Vehicle	ARROW BOARD DISPLAY
**	Shadow Vehicle	
***	Work Vehicle	→ RIGHT Directional
□	Heavy Work Vehicle	← LEFT Directional
◊	Truck Mounted Attenuator (TMA)	↔ Double Arrow
◁	Traffic Flow	⚠ CAUTION (Alternating Diamond or 4 Corner Flash)


TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



TRAIL/SHADOW VEHICLE B
with Flashing Arrow Board in CAUTION display



STRIPING FOR TMA

Texas Department of Transportation
Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
UNDIVIDED HIGHWAYS**

TCP(3-1)-13


FILE:	tcp3-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	December 1985	CONT.	SECT.	JOB	HIGHWAY				
REVISIONS	0033	04	072, ETC	US 83, ETC					
2-94	4-98								
8-95	7-13								
1-97									
ABL	JONES, ETC.			SHEET NO.	62				

DATE: 0922202018 1124568PM
 FILE: D:\Projects\0922202018\0922202018.dwg
 PROJECT: 0922202018
 DRAWING: 0922202018-01
 TITLE: TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
 TCD: 0922202018
 SHEET: 01
 OF: 03
 PROJECT: 0922202018
 DRAWING: 0922202018-01
 TITLE: TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL
 TCD: 0922202018
 SHEET: 01
 OF: 03


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of the standard.




TCP (3-3a)
TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)







TCP (3-3b)
TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)



TCP (3-3c)
DIVIDED MULTILANE HIGHWAY



TCP (3-3d)
UNDIVIDED MULTILANE HIGHWAY



LEGEND			
* Trail Vehicle		ARROW BOARD DISPLAY	
** Shadow Vehicle			
*** Work Vehicle		RIGHT	Directional
	LEFT	Directional	
	DOUBLE	Arrow	
	CAUTION (Alternating Diamond or 4 Corner Flash)		

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.




Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/
REMOVAL
TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	ABL	JONES, ETC.	63	
1-97 7-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information presented herein.



LEGEND		
*	Trail Vehicle	ARROW BOARD DISPLAY
**	Shadow Vehicle	
***	Work Vehicle	RIGHT Directional
	Heavy Work Vehicle	LEFT Directional
	Truck Mounted Attenuator (TMA)	Double Arrow
	Traffic Flow	Channelizing Devices


Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. This traffic control plan is for use on conventional roads posted at 45 mph or less and is intended for mobile operations that move continuously or intermittently (stopping up to approximately 15 minutes) such as short-line striping and in-lane rumble strips. When activities are anticipated to take longer amounts of time or traffic conditions warrant, a short duration or short-term stationary traffic control plan should be used.
2. A Truck Mounted Attenuator shall be used on Shadow Vehicle. Striping on the back panel of all truck mounted attenuators shall be 8" red and white reflective sheeting placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental material specification DMS-8300, Type A.
3. All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.
4. The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the drivers side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
5. Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C as per BC Standards. The arrow board operation shall be controlled from inside the truck.



Texas Department of Transportation
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS FOR
 ISOLATED WORK AREAS
 UNDIVIDED HIGHWAYS
 TCP(3-4)-13**

FILE: tcp3-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT July, 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
DIST	COUNTY		SHEET NO.	
ABL	JONES, ETC.		64	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of the information herein.

DATE: 0922202018 1126561PM
 FILE: P:\Engineering\Projects\09222020\09222020.dwg

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)



- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	0033	SECT:	04	JOB:	072, ETC	US:	83, ETC
REVISIONS:		DIST:		COUNTY:		SHEET NO.:			
1-97		ABL:	JONES, ETC.						65
3-03									
7-13									




**ROADWAY LAYOUT
CA1**


© 2022  Texas Department of Transportation

SCALE 1:100 SHEET 1 OF 4

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	67	
DISTRICT	CONTROL	SECTION	JOB
0033	0033	04	072, ETC

DS

 Licensed by
Paul N Norman, P.E.
 20E04E8F4AB6444...
 4/2/2022

FILE:
DATE:



DS

Paul N Norman, P.E.

4/2/2022


**ROADWAY LAYOUT
CA1**

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 2 OF 4

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		US 83, ETC
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC.		68
DISTRICT	CONTROL	SECTION	
ABL	0033	04	072, ETC

FILE:
DATE:



DS


 Licensed by
Paul N Norman, P.E.
 20E04E8F4AB6444...
 4/2/2022



**ROADWAY LAYOUT
CA1**

© 2022  Texas Department of Transportation

SCALE 1 : 100 SHEET 3 OF 4

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	69	
DISTRICT	CONTROL SECTION JOB		
ABL	0033 04 072, ETC		

FILE:
DATE:




**ROADWAY LAYOUT
CA1**


© 2022  Texas Department of Transportation

SCALE 1 : 100 SHEET 4 OF 4


FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		US 83, ETC
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC.		70
DISTRICT	CONTROL	SECTION	
ABL	0033	04	072, ETC

DS

Paul N Norman, P.E.
 20E04E8F4AB0444...
 4/2/2022

FILE:
DATE:



**ROADWAY LAYOUT
CA2**


DS

Paul N Norman, P.E.
 20E04E8F4AB6444...
 4/2/2022

© 2022  Texas Department of Transportation


SCALE 1 : 100 SHEET 1 OF 3

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	71	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

FILE:
DATE:



**ROADWAY LAYOUT
CA2**




DS

Paul N Norman, P.E.
 4/2/2022

© 2022  Texas Department of Transportation

SCALE 1 : 100 SHEET 2 OF 3

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		US 83, ETC
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC.		72
DISTRICT	CONTROL	SECTION	
ABL	0033	04	072, ETC

FILE:
DATE:



**ROADWAY LAYOUT
CA2**

DS


 Licensed by
Paul N Norman, P.E.
 20E04E8F4AB6444...
 4/2/2022

© 2022 Texas Department of Transportation

SCALE 1 : 100 SHEET 3 OF 3

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	73	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

FILE:
DATE:



**ROADWAY LAYOUT
CA3**

DS


 Paul N. Norman, P.E.
 4/2/2022

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 1 OF 2

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	US 83, ETC
STATE	COUNTY	SHEET NO.
TEXAS	JONES, ETC.	74
DISTRICT	CONTROL SECTION JOB	
ABL	0033 04 072, ETC	

FILE:
DATE:



**ROADWAY LAYOUT
CA3**


DS

 Licensed by
Paul N Norman, P.E.
 20E04E8F4AB6444...
 4/2/2022

© 2022  Texas Department of Transportation


SCALE 1 : 100 SHEET 2 OF 2

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		US 83, ETC
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC.		75
DISTRICT	CONTROL	SECTION	
ABL	0033	04	072, ETC


FILE:
DATE:



FILE:
DATE:


DS

 Paul N. Norman, P.E.
 25E04E0F4AB0444...
 4/2/2022

**ROADWAY LAYOUT
HA1**


© 2022  Texas Department of Transportation

SCALE 1 : 100 SHEET 1 OF 3

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	US 83, ETC
STATE	COUNTY	SHEET NO.
TEXAS	JONES, ETC.	76
DISTRICT	CONTROL SECTION JOB	
ABL	0033 04 072, ETC	



FILE:
DATE:


DS

 Paul N. Norman, P.E.
 25E04E0F4A86444...
 4/2/2022

**ROADWAY LAYOUT
HA1**

© 2022  Texas Department of Transportation

SCALE 1 : 100 SHEET 2 OF 3

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	US 83, ETC
STATE	COUNTY	SHEET NO.
TEXAS	JONES, ETC.	77
DISTRICT	CONTROL SECTION JOB	
ABL	0033 04	072, ETC



**ROADWAY LAYOUT
HA1**

© 2022 Texas Department of Transportation



SCALE 1 : 100 SHEET 3 OF 3

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	78	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

DS

Paul N Norman, P.E.
 25E04E0F4AB0444...
 4/2/2022

FILE:
DATE:



FILE: PLEM MILL ANSON C-HOUSE
DATE: 8-25-21

DS


 Paul N. Norman, P.E.
 4/2/2022

**ROADWAY LAYOUT
J1**

© 2022 Texas Department of Transportation

SCALE: 1 : 100 SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	79	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC



**ROADWAY LAYOUT
J2**

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 1 OF 2

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		US 83, ETC
STATE	COUNTY		SHEET NO.
TEXAS	JONES, ETC.		80
DISTRICT	CONTROL	SECTION	
ABL	0033	04	
			JOB
			072, ETC

DS

 Paul N. Norman, P.E.
 4/2/2022

FILE:
DATE:



**ROADWAY LAYOUT
J2**

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 2 OF 2

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	81	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

DS

 Paul N. Norman, P.E.
 25E04E0F4AB0444...
 4/2/2022

FILE:
DATE:



**ROADWAY LAYOUT
J3**

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	82	
DISTRICT	CONTROL SECTION JOB		
ABL	0033 04 072, ETC		

DS

Paul N Norman, P.E.
 25E04E0F4AB0444...
 4/2/2022

FILE:
DATE:



DS

Paul W. Norman, P.E.

6/21/2022


ROADWAY LAYOUT J4

© 2022 Texas Department of Transportation

SCALE 1 : 100 SHEET 1 OF 4

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	US 83, ETC
STATE	COUNTY	SHEET NO.
TEXAS	JONES, ETC.	41
DISTRICT	CONTROL SECTION JOB	
ABL	0033 04 072, ETC	

FILE:
DATE:



**ROADWAY LAYOUT
J4**

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 2 OF 4

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	84	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

DS

Paul N Norman, P.E.
 25E04E0F4AB0444...
 4/2/2022

FILE:
DATE:



**ROADWAY LAYOUT
J4**

© 2022 Texas Department of Transportation


SCALE 1 : 100 SHEET 3 OF 4

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	85	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

DS

 Paul N. Norman, P.E.
 25E04E0F4AB6444...
 4/2/2022

FILE:
DATE:




**ROADWAY LAYOUT
J4**

© 2022  Texas Department of Transportation


SCALE 1 : 100 SHEET 4 OF 4

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	86	
DISTRICT	CONTROL SECTION JOB		
ABL	0033 04 072, ETC		


DS

 DocuSigned by:
Paul N Norman, P.E.
 25E04E0F4AB6444...
 4/2/2022

FILE:
DATE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.


YIELD LINES

GENERAL NOTES

1. Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1) - 20

FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	0033	04	072, ETC	US 83, ETC
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	ABL	JONES, ETC.		87

NOTES

1. Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
2. Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
3. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown in the plans or as directed by the Engineer.




FOUR LANE DIVIDED ROADWAY CROSSOVERS


DATE: DATE TIME
 FILE: DOCUMENT NAME

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS




POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	0033	04	072, ETC	US 83, ETC
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	ABL	JONES, ETC.		88


GENERAL NOTES

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



REFLECTORIZED PROFILE PATTERN DETAIL

USING REFLECTIVE PROFILE PAVEMENT MARKINGS




NOTE

Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

DATE: DATE TIME
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

LANE REDUCTION

NOTES


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES

- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE



TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A

DETAIL B


Texas Department of Transportation
Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 20

FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0033	04	072, ETC	US 83, ETC
5-00 2-10	DIST	COUNTY		
8-00 2-12	ABL	JONES, ETC.		89
3-03 6-20				

DATE: DATE TIME
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



HIGH-VISIBILITY LONGITUDINAL CROSSWALK AT CONTROLLED APPROACH


GENERAL NOTES

1. Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
3. For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
5. Each crosswalk shall be a minimum of 6' wide.
6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
7. Final placement of Stop Bar and Crosswalk shall be approved by the Engineer in the field.

MATERIAL SPECIFICATIONS

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



UNSIGNALIZED MID BLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK

NOTES:

1. Use stop bars with "Stop Here for Pedestrians" signs at unsignalized mid block crosswalks.
2. Use stop bars with "Stop Here on Red" signs at mid block crosswalks controlled by traffic signals or pedestrian hybrid beacons.

Texas Department of Transportation Traffic Safety Division Standard

CROSSWALK PAVEMENT MARKINGS

PM(4) - 22

FILE: pm4-22.dgn	DN:	CK:	DW:	CK:
© TxDOT June 2020	CONT	SECT	JOB	HIGHWAY
3-22 REVISIONS	0033	04	072, ETC	US 83, ETC
	DIST	COUNTY	SHEET NO.	
	ABL	JONES, ETC.	90	

DATE:
FILE:

SITE DESCRIPTION

PROJECT LIMITS:
THE PROJECT LIMITS SHOWN ON THE TITLE SHEET AND LIMITS OF TXDOT RIGHT OF WAY SHALL ALSO BE THE LIMITS OF COVERAGE OF THE SW3P.

PROJECT LOCATION MAPS: TITLE SHEET

DRAINAGE PATTERNS: N/A

APPROX. SLOPES ANTICIPATED AFTER MAJOR GRADING AND AREAS OF SOIL DISTURBANCE: TYPICAL SECTIONS

MAJOR CONTROLS AND LOCATIONS OF STABILIZATION PRACTICES: N/A

PROJECT SPECIFIC LOCATIONS: TO BE SPECIFIED BY PROJECT FIELD OFFICE AND LOCATED IN THE PROJECT SW3P FILE.

SURFACE WATERS AND DISCHARGE LOCATIONS: N/A

TYPICAL AREAS WHICH WILL NOT BE DISTURBED: N/A

ENDANGERED SPECIES, DESIGNATED CRITICAL HABITAT AND HISTORIC PROPERTY: EPIC SHEET

ESTIMATED START DATES AND DURATION OF ACTIVITIES IN THE INTENDED SCHEDULE/SEQUENCE OF EARTH-DISTURBING ACTIVITIES: CONTRACT TIME ESTIMATE

NATURE OF ACTIVITY:
<PROJECT DESCRIPTION FROM TITLE SHEET>

MAJOR SOIL DISTURBING ACTIVITIES:
N/A

TOTAL PROJECT AREA:
N/A

TOTAL AREA TO BE DISTURBED (AT EACH SITE):
0.00 ACRES

WEIGHTED RUNOFF COEFFICIENT BEFORE CONSTRUCTION:
N/A

WEIGHTED RUNOFF COEFFICIENT AFTER CONSTRUCTION:
N/A

EXISTING CONDITION OF SOIL & VEGETATIVE COVER:
N/A

% OF EXISTING VEGETATIVE COVER:
N/A

NAME OF RECEIVING WATERS:
*J2-4, HA1 SEG1232C PAINT CREEK BRAZOS RIVER BASIN
*J1 SEG1232A CALIFORNIA CREEK BRAZOS RIVER BASIN
*CA1 SEG1420 PECAN BAYOU ABOVE BROWNWOOD COLORADO RIVER BASIN
*CA2-3 SEG1420 PECAN BAYOU ABOVE BROWNWOOD COLORADO RIVER BASIN

EROSION AND SEDIMENT CONTROLS

USE "T" OR "P" IN THE BLANKS BELOW IF APPLICABLE (T= TEMPORARY, P= PERMANENT)

SOIL STABILIZATION PRACTICES:

<input type="checkbox"/> P	BUFFER ZONES	<input type="checkbox"/> P	PERMANENT PLANTING, SODDING, OR SEEDING
<input type="checkbox"/>	MULCHING	<input type="checkbox"/>	PRESERVATION OF NATURAL RESOURCES
<input type="checkbox"/>	TEMPORARY SEEDING	<input type="checkbox"/>	SOIL RETENTION BLANKET
<input type="checkbox"/>	OTHER	<input type="checkbox"/>	OTHER

OTHER: N/A

FOR CONSTRUCTION PROJECTS, THIS DISTRICT OF THE TEXAS DEPARTMENT OF TRANSPORTATION USES SITEMANAGER, A COMPUTER BASED CONSTRUCTION RECORD-KEEPING SYSTEM, AS PART OF RECORD FOR PROJECT WORK INCLUDING ENVIRONMENTAL RELATED ACTIVITIES. DOCUMENTATION DESCRIBING MAJOR GRADING ACTIVITIES, TEMPORARY OR PERMANENT CESSATION OF CONSTRUCTION AND STABILIZATION MEASURE IS PART OF THIS SYSTEM AND IS INCORPORATED BY REFERENCE INTO THIS SW3P.

STRUCTURAL PRACTICES:

<input type="checkbox"/>	CHANNEL LINERS	<input type="checkbox"/>	DIVERSION DIKE AND SWALE COMBINATIONS
<input type="checkbox"/>	CURBS AND GUTTERS	<input type="checkbox"/>	DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
<input type="checkbox"/>	HAY BALES	<input type="checkbox"/>	DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
<input type="checkbox"/>	PAVED FLUMES	<input type="checkbox"/>	ROCK BEDDING AT CONSTRUCTION EXIT
<input type="checkbox"/>	PIPE SLOPE DRAINS	<input type="checkbox"/>	STONE OUTLET STRUCTURES
<input type="checkbox"/>	STORM SEWERS	<input type="checkbox"/>	STORM INLET SEDIMENT TRAP
<input type="checkbox"/>	SEDIMENT BASINS	<input type="checkbox"/>	TEMPORARY EROSION CONTROL LOGS (BIOLOGS)
<input type="checkbox"/>	SEDIMENT TRAPS	<input type="checkbox"/>	TIMBER MATTING AT CONSTRUCTION EXIT
<input type="checkbox"/>	SILT FENCES	<input type="checkbox"/>	VEGETATIVE FILTER STRIPS
<input type="checkbox"/>	ROCK FILTER DAMS	<input type="checkbox"/>	VELOCITY CONTROL DEVICES
<input type="checkbox"/>	EROSION CONTROL LOGS	<input type="checkbox"/>	LINED CONCRETE WASHOUT

OFFSITE VEHICLE TRACKING CONTROLS:

HAUL ROADS DAMPENED FOR DUST CONTROL
 EXCESS DIRT ON ROAD REMOVED DAILY
 LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
 STABILIZED CONSTRUCTION ENTRANCE
 OTHER

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:

THE ORDER OF ACTIVITIES WILL BE AS FOLLOWS:
N/A

STORM WATER MANAGEMENT:
N/A

OTHER EROSION AND SEDIMENT CONTROLS:

MAINTENANCE: N/A

INSPECTION: N/A

WASTE MATERIALS:

ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL STATE AND LOCAL CITY SOLID WASTE MANAGEMENT REGULATIONS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED AS NECESSARY OR AS REQUIRED BY LOCAL REGULATION AND THE TRASH WILL BE HAULED TO A PERMITTED LANDFILL. NO CONSTRUCTION WASTE MATERIAL WILL BE BURIED ON SITE. CONSTRUCTION DEBRIS AND LITTER SHOULD BE PICKED UP ON A DAILY BASIS UNLESS OTHERWISE DIRECTED BY THE ENGINEER. WASTE AND DIRT PILES SHOULD BE REMOVED ON A WEEKLY BASIS.

HAZARDOUS WASTE (INCLUDING SPILL REPORTING):

NO LONG TERM WATER QUALITY IMPACTS ARE EXPECTED AS A RESULT OF THE PROPOSED PROJECT. SEE THE NEXT PLAN SHEET FOR A LIST OF POTENTIAL POLLUTANTS. IN THE EVENT OF A MAJOR SPILL, NOTIFY THE TXDOT ENGINEER IMMEDIATELY. ALL PERSONNEL WILL BE INSTRUCTED IN THE PROCEDURES FOR SPILL HANDLING AND DISPOSING OF ANY HAZARDOUS MATERIALS THEY WILL BE USING. ALL SPILLS, INCLUDING THOSE OF LESS THAN 25 GALLONS SHALL BE CLEANED IMMEDIATELY AND ANY CONTAMINATED SOIL SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND BE DISPOSED OF PROPERLY. DESIGNATED AREAS SHALL BE DETERMINED BY THE AREA ENGINEER FOR SPOILS DISPOSAL AND MATERIAL STORAGE. THESE AREAS SHALL BE PROTECTED FROM RUN-ON AND RUN-OFF. MATERIALS RESULTING FROM THE DESTRUCTION OF EXISTING ROADS AND BEING REMOVED AND/OR DISPOSED OF BY THE CONTRACTOR WILL BE DONE SO IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL LAWS, ORDINANCES AND REGULATIONS AND WITH THE APPROVAL OF THE PROJECT ENGINEER. ANY CHANGES TO AMBIENT WATER QUALITY DURING CONSTRUCTION OF THE PROPOSED PROJECT SHALL BE PROHIBITED AND MAY RESULT IN ADDITIONAL WATER QUALITY CONTROL MEASURES, WHICH SHALL BE MITIGATED AS SOON AS POSSIBLE AND SHALL BE REPORTED TO THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) WITHIN 24 HOURS OF BECOMING AWARE OF IMPACTS.


SANITARY WASTE:

ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NECESSARY OR AS REQUIRED BY LOCAL REGULATION BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

REMARKS:

CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED BY THE CONTRACTOR IN A MANNER TO MINIMIZE THE RUNOFF OF POLLUTANTS. ALL WATERWAYS SHALL BE CLEARED AS SOON AS PRACTICABLE OF TEMPORARY EMBANKMENT, TEMPORARY BRIDGES, MATTING, FALSEWORK PILING, DEBRIS OR OTHER OBSTRUCTIONS PLACED DURING CONSTRUCTION OPERATIONS THAT ARE NOT PART OF THE FINISHED WORK. DISPOSAL AREAS, STOCKPILES, AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT MAY ENTER RECEIVING WATERS. DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WETLAND, WATER BODY OR STREAMBED.

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\45 SW3P.dgn 4/2/2022 1:05:30 PM

DS

Paul N. Norman, P.E.
 4/2/2022



NO SCALE SHEET 1 OF 2

TxDOT STORM WATER POLLUTION PREVENTION PLAN (SW3P)


FHWA DIVISION	PROJECT NO.	HIGHWAY NO.		SHEET NO. 91
6	SEE TITLE SHEET	US 83, ETC		
STATE	COUNTY	JOB		
TEXAS	JONES, ETC.	072, ETC		
DISTRICT	CONTROL	SECTION	JOB	
ABL	0033	04	072, ETC	

LIST OF POTENTIAL POLLUTANTS

POTENTIAL POLLUTANT	RELATED SOURCE	CONTROLS
CEMENTATEOUS MATERIAL AND CEMENTATEOUS AGGREGATES (BROKEN CONCRETE)	REMOVAL OF CONCRETE RIPRAP, CULVERT COMPONENTS, BRIDGE COMPONENTS, ETC.	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
MILLED ASPHALTIC CEMENT PAVEMENT (MILLINGS)	OBLITERATION OF ABANDONED ROAD AND PLANING OF ASPHALT	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
VIRGIN ASPHALTIC MATERIAL INCLUSIVE OF PRIME OILS, PRECOAT AGGREGATES, AND HOT MIX BITUMINOUS MIXTURES	APPLICATIONS OF PRIME COATS, SEAL COAT, AND PAVING OPERATIONS	THIS MATERIAL SHALL BE APPLIED AT APPROPRIATE RATES FOR CONSTRUCTION PURPOSES WHICH WILL PRECLUDE THESE MATERIALS FROM ENTERING RUNOFF. IN THE EVENT OF ANY UNINTENDED DISCHARGE, CONTROLS TO CONTAIN RUNOFF WILL BE IMMEDIATELY PLACED AND TCEQ WILL BE IMMEDIATELY NOTIFIED.
CONCRETE, REBAR, WIRE, WIRE FABRIC LUMBER, NAILS, STYROFOAM BLOCK, FIBERBOARD, CURING COMPOUND AND LINSEED OIL	CONSTRUCTION OF CONCRETE BRIDGE COMPONENTS SUCH AS DRILLED SHAFTS, CULVERTS, ABUTMENTS, BENTS, REINFORCED CONCRETE SLABS, RAIL, INLET, CONCRETE TRAFFIC BARRIERS, CURB AND GUTTER, RIPRAP AND SIGN FOUNDATIONS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF. ANY TEMPORARY FILLS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO THEIR PREEXISTING CONDITION/ELEVATION.
MASONRY CONCRETE BLOCK, GEOGRID FABRIC, CARDBOARD, AND PLASTIC RAP	CONSTRUCTION OF MODULAR RETAINING WALL SYSTEMS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
WOOD POSTS, STEEL POSTS, BARRELS, CONES, SIGN BOARDS (ALUMINUM AND PLYBOARD), FASTENERS, NUTS, BOLTS, AND WASHERS	PLACEMENT AND/OR REMOVAL OF BARRICADES, SIGNS AND TRAFFIC CONTROL DEVICES	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
WOOD POST, STEEL POST, STEEL FASTENERS, NUTS, BOLTS, AND WASHERS	CONSTRUCTION OF METAL BEAM GUARD FENCE	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
STRUCTURAL STEEL I-BEAM, SIGN BOARDS, AND CONCRETE FOUNDATIONS	REMOVAL OF ROADSIDE SIGN ASSEMBLIES LARGE AND SMALL	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
THERMOPLASTIC PAINT, GLASS BEADS, REFLECTIVE TABS, AND RAISED REFLECTIVE PAVEMENT MARKERS	APPLICATION OF PAVEMENT MARKINGS/MARKERS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
PETROLEUM PRODUCTS (SMALL QUANTITIES INTRODUCED BY CONTRACTOR)	EQUIPMENT FAILURE, MAINTENANCE AND REPAIR	ALL EQUIPMENT AND VEHICLE MAINTENANCE SHALL BE PERFORMED IN A DESIGNATED AREA WITH APPROPRIATE MEASURES FOR CONTAINMENT AND PROPER DISPOSAL OF ALL WASTE MATERIALS INCLUDING HYDRAULIC OIL AND OTHER LIQUIDS IN ACCORDANCE STATE AND LOCAL WASTE MANAGEMENT REGULATIONS. ALL MATERIAL STORED PRIOR TO DISPOSAL SHALL BE CONTAINED IN A CONTAINER WITH A SECURE COVER MEETING ALL STATE AND LOCAL WASTE MANAGEMENT REGULATIONS.
ELIGIBLE NON-STORM WATER DISCHARGES INCLUDING BUT NOT LIMITED TO NON-POTABLE WATER AND NON-STORM WATER DISCHARGE	MOISTURE APPLICATIONS FOR DUST CONTROL, DENSITY, VEGETATION WATERING, NON-DETERGENT VEHICLE WASHING, AND AIR CONDITIONING CONDENSATE	THIS MATERIAL SHALL BE APPLIED AT APPROPRIATE RATES FOR CONSTRUCTION PURPOSES WHICH WILL PRECLUDE THESE MATERIALS FROM ENTERING RUNOFF. IN THE EVENT OF ANY UNINTENDED DISCHARGE, CONTROLS TO CONTAIN RUNOFF WILL BE IMMEDIATELY PLACED AND THE NON-POTABLE WATER WILL BE RECOVERED AND PROPERLY STORED FOR REUSE.
SURVEY STAKE, FLAGGING TAPE AND PAINT	SURVEY STAKING, ALIGNMENT ESTABLISHMENT	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
WASTEWATER	WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
SOAPS AND SOLVENTS	VEHICLE AND EQUIPMENT WASHING	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
UNSUITABLE FILL MATERIAL	EXCAVATION - ROADWAY, SPECIAL AND EROSION CONTROL	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.

T:\Engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET\45 SW3P.dgn
4/2/2022 1:05:31 PM

DS



Paul N. Norman, P.E.

25E04E0F4AB0444...

4/2/2022

TxDOT STORM WATER POLLUTION PREVENTION PLAN (SW3P)

REV. DATE: 02/27/2014

© 2022  Texas Department of Transportation

NO SCALE		SHEET 2 OF 2	
FHWA DIVISION	PROJECT NO.	HIGHWAY NO.	
6	SEE TITLE SHEET	US 83, ETC	
STATE	COUNTY	SHEET NO.	
TEXAS	JONES, ETC.	92	
DISTRICT	CONTROL	SECTION	JOB
ABL	0033	04	072, ETC

PREPARED BY (NAME OF DESIGNER) X
 DATE: 4/2/2022
 FILE: T:\engdata\Projects\0033-04\CSJ 0033-04-072 ETC PLAN SET

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. STORM WATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Storm water Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. No Action Required Required Action

Action No.

- The project disturbs less than one acre of surface area. The contractor is responsible for the PSL as defined in the Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges (2014 Edition, Section 7.6., Page 44). The total disturbed acreage is the combined acreage to be disturbed on the project and the contractors PSL.
- Prevent storm water pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATER BODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

-
-

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Sedimentation Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw & Hay Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost & Mulch
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Sand Filter Systems
<input type="checkbox"/> Temporary Erosion Control Logs (BIOLOGS)	<input type="checkbox"/> Temporary Erosion Control Logs (BIOLOGS)	<input type="checkbox"/> Temporary Erosion Control Logs (BIOLOGS)
<input checked="" type="checkbox"/> Preservation of Natural Resources	<input type="checkbox"/> Sediment Traps	<input type="checkbox"/> Permanent Vegetation (Planting, Sodding, or Seeding)
<input type="checkbox"/> Construction Exits	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action No.

-
-
-
-

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

Action No.

- COMPLY WITH E013112 ON USE NATIVE VEGETATION
-
-
-

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

- No Action Required Required Action

Action No.

- COMPLY WITH MBTA
-
-
-

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Storm water Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

-
-
-

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action No.

- MS4 - BMP's
-
-

**US83, ETC.
ENVIRONMENTAL PERMITS,
ISSUES AND COMMITMENTS
EPIC**



NO SCALE SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	US 83, ETC
STATE	COUNTY	SHEET NO.
TEXAS	JONES, ETC.	93
DISTRICT	CONTROL	SECTION
ABL	0033	04
		JOB
		072, ETC