SEE SHEET NO. 2 FOR INDEX OF SHEETS

# STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

# PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO. = F 2023(285)

# FM 3247 ORANGE COUNTY

NET LENGTH OF ROADWAY= 6,841.00 FT. \*.296 MI.
NET LENGTH OF PROJECT= 6,841.00 FT. \*.296 MI.

LIMITS: FROM: BU 90Y, SOUTH, TO EOM

FOR THE CONSTRUCTION OF AN OVERLAY PROJECT

CONSISTING OF FULL DEPTH BASE REPAIR, OVERLAY, AND PAVEMENT MARKINGS

BEGIN PROJECT

CSJ: 2701-02-025

STA: 243-54

REF MRK: 450-0, 86

END PROJECT

CSJ: 2701-02-025

STA: 311-95

REF MRK: 452-0, 121

EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE

105

SCALE IN MILES

//2

© 2022 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED. F 2023 (285)

CONT SECT JOB HIGHWAY

2701 02 025 FM 3247

DIST COUNTY SHEET NO.

BMT ORANGE 1

DESIGN CRITERIA = PM DESIGN SPEED = N/A A.D.T. (2021) = 2067 A.D.T. (2041) = 2894

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1) - 21 THRU BC (12) - 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

SUBMITTED FOR LETTING: 9/25/2022

Jason D. Walter, F.E.

PROJECT ENGINEER

PECONOMISSINGUAL BYOR LETTING: 9/28/2022

LAM JACK

DISTRICT STRANSPORTATION
PLANNING AND DEVELOPMENT
9/28/2022

le: 9/12/2022 | 11:3/103 AM Le: T:\BMTDESGN\Projec+s\2701-02-025 FM 3247\DGN\Ti+le\$

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, JULY 5, 2022 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

578CD7495**D6t54FR91.CT ENGINEER** 

Martin N. Grob, P.E.

**GENERAL** TITLE SHEET INDEX OF SHEETS 3-4 TYPICAL SECTIONS 5-9 GENERAL NOTES 10 ESTIMATE & QUANTITY 11-13 QUANTITY SUMMARY

TRAFFIC CONTROL PLAN

SEQUENCE OF WORK \*\* 15-26 BC (1)-21 THRU BC (12)-21

**\*\*** 27 TCP(2-1)-18 **##** 28 TCP(2-2)-18 **##** 29 TCP(3-1)-13 **\*\*** 30 TCP(3-3)-14 **\*\*** 31 WZ(RS)-22 \*\* 32 WZ(STPM)-13 ## 33 WZ(UL)-13

ROADWAY DETAILS

34-36 ROADWAY LAYOUT DRIVEWAY DETAILS 37 ## 38 RS(3)-13

**\*\*** 39 RS(4)-13

PAVEMENT MARKINGS & DELINEATION

**\*\*** 4Ø PM(1)-20 **\*\*** 41 PM(2)-20 **\*\*** 42 PM(3)-2Ø

ENVIRONMENTAL ISSUES

43 EPIC \*\* 44-46 EC(9)-16



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A """ HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

NAME


09/08/2022


DATE

INDEX OF SHEETS



2701 02 025 FM 3247





Highway: FM 3247 Control: 2701-02-025

#### **GENERAL NOTES:**

Contractor questions on this project are to be addressed to the following individual(s):

Name Bryce Broussard, P.E.

Email Bryce.Broussard@txdot.gov

Name Jim Grissom, P.E.

Email Jim.Grissom@txdot.gov

Contractor questions will be accepted through email, phone and in person by the above individuals.

All contractor questions will be reviewed by the Area Engineer or Assistant Area Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: <a href="https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/">https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/</a>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Assume full responsibility for the preservation of all sod, shrubbery, and trees at the site during construction. Carefully preserve and replace, in their original position, all sod and shrubbery removed. Replace all Contractor damaged sod or shrubbery at the Contractor's own expense.

Maintain adequate drainage throughout the limits of the project during all construction phases.

Provide a weekly a list of equipment, including idle equipment, used on the project each week.

#### Item 000 Utilities

Consider the locations of utilities depicted on the plans as approximate and employ responsible care to avoid damaging or accommodate utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities. If utility damage (breaks, leaks, nicks, dents, gouges, etc.) occurs, contact the utility facility owner or operator immediately. In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others.

#### **Item 4 Scope of Work**

Remove all vegetation from pavement edges, intersections and driveways before plaining or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

General Notes Sheet A General Notes Sheet B

County: Orange SHEET 5

Highway: FM 3247 Control: 2701-02-025

It is the contractor's responsibility to mark the location of all existing striping and place proposed striping back in the same location or as shown in the plans.

#### **Item 5 Control of the Work**

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

Verify all horizontal and vertical control, approach grades to structures and driveways before beginning work. Notify the Engineer immediately if discrepancies are discovered.

#### **Item 6 Control of Materials**

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html for clarification on material categorization.

Buy America material classification sheet

The Buy America material classification sheet categorizes materials as iron and steel, construction material, or manufactured product on a per item basis.

#### Item 7 Legal Relations and Responsibilities

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Maintain ingress and egress to the adjacent property at all times. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in

Highway: FM 3247 Control: 2701-02-025

the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

Personal vehicles of the contractor's employees will not be parked within the right of way at any time including any section closed to public traffic, unless the vehicle is being used for construction procedures. However, the Contractor's employees may park on the right of way at sites where the contractor has their office, equipment and materials storage yard.

No significant traffic generator events have been identified in the project limits.

#### **Item 8 Prosecution and Progress**

Working days will be charged during all observed curing times, even if no other work is being performed

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Notify the Engineer 72 hours in advance of any temporary or permanent lane, ramp or connector affected by closures, detours, or restrictions to lane widths, alterations to vertical clearances or modifications to alignment/radii. Any other modification to the roadway that may adversely affect the mobility of oversized/overweight trucks will require 5 business day advance written notice to the Engineer.

Maintain one lane open to traffic during construction, unless otherwise approved.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

Limit lane closures to 1/2 mile unless otherwise approved.

All edges must be backfilled by the end of the day with a 3:1 or flatter slope. No drop offs will be left overnight.

The Engineer will suspend time charges after completion of all work and removal of the barricades. The Department will grant final acceptance when all performance periods are complete.

Accrue Contract time charges through the Contractor's completion of the final punch list. Time will not be suspended until all work is completed.

Submit a work schedule to the Engineer at the preconstruction meeting indicating completion dates for each location, and the number of crews required for the completion of the contract within the contract time period. If at any time during the contract the work progress is behind the initial schedule, submit documentation indicating how the project will be accelerated to ensure project completion in the remaining contract time.

General Notes Sheet C General Notes Sheet D

County: Orange SHEET 6

Highway: FM 3247 Control: 2701-02-025

Provide a sequence of work with an estimated project schedule to the Engineer at the preconstruction meeting. By noon of each Wednesday, provide the Engineer a written outline of the proposed work schedule for the following week. This outline will also list the times and places for any proposed traffic control changes.

Monthly critical path method (CPM) updates are a very important aspect of managing the progress of this project. CPM planning schedule software will be required on this project as stipulated in the special provisions to the plans. An updated electronic schedule will be provided to the Engineer by the tenth day of each month. The Engineer may withhold the monthly estimate if the schedule update has not been received.

For this project, create and maintain the critical path method (CPM) schedule.

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

The construction sequence may be modified as directed and approved.

Provide 3:1 maximum edge tapers as shown on the typical section before opening lanes to traffic. Provide a 100-foot minimum temporary longitudinal grade taper at the end of the section being reworked before opening the lanes to traffic.

#### **HURRICANE**

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

#### **Item 134 Backfilling Pavement Edges**

Use RAP salvaged from within the project limits to the maximum extent possible. Size RAP so that all material passes the two-inch sieve. Use RAP that does not contain deleterious material such as clay or organic material.

Embankment quantity by station includes both sides of the roadway. No deduction in payment will be made when in the opinion of the Engineer only one side of a roadbed section requires backfilling.

Backfill the pavement edges daily so that no drop-off conditions exist. Type A or B material will meet one of the following requirements:

- 1. Item 132, Type C:
- Liquid Limit 40 maximum
- Plasticity Index 25 maximum, 8 minimum

Highway: FM 3247 Control: 2701-02-025

A cohesionless sand will not be permitted

#### **Item 164 Seeding for Erosion Control**

Final grading and stabilization (seeding) will be achieved as soon as possible and not scheduled only for the end of the project. Final grading and stabilization should be initiated as the overall work progresses.

Multiple mobilizations of the seeding crews will be expected to comply with the Construction General Permit of the Texas Pollution Elimination Discharge System requirements for revegetating disturbed soils.

#### Item 166 Fertilizer

Fertilize all the seeded or sodded areas of project.

#### **Item 168 Vegetative Watering**

Equip water trucks with sprinkler systems capable of covering the entire area to be seeded or sodded from the roadway.

Water all newly placed sod or seeded areas the same day of installation. Thereafter, maintain the sod or seeded areas in a well-watered condition and at no time allow the areas to dry to the condition that water stress is evident.

Mechanical watering may not be required during periods of adequate moisture as determined.

Furnish and apply water at a rate of 6.788 Mega gallons per acre per cycle or as directed on the plans.

Comply with stabilization requirements for 70% grass coverage; uniform vegetative coverage is required. During this period, meter and operate water equipment under pumping pressure capable of delivering the required quantities of water necessary. For Permanent seeding each cycle will be executed weekly for 12 weeks, unless directed otherwise. For Temporary seeding each cycle will be executed weekly for 6 weeks, unless directed otherwise.

Provide a logbook showing daily water usage and receipts of water applied, in addition to metering the water equipment.

#### **Item 247 Flexible Base**

Use of RAP is allowed

Use ordinary compaction.

County: Orange SHEET 7

Highway: FM 3247 Control: 2701-02-025

Do not damage existing or proposed structures during base operations.

#### **Item 351 Flexible Pavement Structure Repair**

The repair areas will require full depth saw-cut when milling is not used. Consider this work to be subsidiary to the various bid items of the contract.

Provide Flexible Pavement Repair that meets the requirements of Item 3076, D-GR HMA TY-B (PG 64-22) unless approved otherwise. Place Hot Mix with a constant longitudinal surface grade and tie in flush with the existing surface at each end and both sides of the repair area.

Unless otherwise directed, place new ASB with maximum 4" lifts. The minimum patch sizes will be 6' in width and 10' in length.

Match the existing cross slope in the repair areas, unless directed otherwise.

All repair locations must be filled the same day they are excavated. No open cut areas will be allowed overnight.

All excavated materials will be removed from the project daily.

Ordinary compaction will be used on this project.

Station limits may be adjusted as directed to meet varying field conditions

Seal the perimeter of the repair areas with hot poured rubber in accordance with Item 712. Consider this work to be subsidiary to the various bid items of the contract.

#### Item 502 Barricades, Signs, and Traffic Handling

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

Square Feet	Minimum Thickness
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible

General Notes Sheet E General Notes Sheet F

Highway: FM 3247 Control: 2701-02-025

Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Arrange asphalt laydown schedule to meet plan striping requirements.

Restrict work to one side of the roadway at a time.

Use drums as channelizing devices.

Remove all traffic control devices from the right of way when they are not in use. Devices scheduled to be used within 3 days may be placed along the shoulder of the roadway or along the right of way when not in use or stored in other approved areas on the project. Cover any construction signs that are not in effect and are installed in a fashion that will not allow them to be removed from the right of way easily.

Arrange construction operations to prevent the hauling of materials through the completed pavement sections unless otherwise approved.

Provide all flaggers and pilot vehicle drivers with two-way radio communication capability. Provide flaggers at each side road intersection.

#### Item 506 Temporary Erosion, Sedimentation, and Environmental Controls

When specified, the Contractor will implement storm water pollution prevention plan measures using the Items listed below as specified in Item 506 and as directed:

Erosion Control Logs.

#### **Item 585 Ride Quality for Pavement Surfaces**

Use Surface Test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

#### **Item 666 Retro reflectorized Pavement Markings**

Furnish Type II drop-on glass beads.

#### **Item 672 Raised Pavement Markers**

Remove all existing traffic buttons before the Overlay Operations begin. Consider this work to be subsidiary to the various bid items of the contract. Location and details of the existing buttons are available at the Area Engineer's office.

#### **Item 3076 Dens Graded Hot Mix Asphalt**

Prepare Mix Designs and QC testing using the Superpave Gyratory compactor.

#### **Item 3077 Superpave Mixtures**

General Notes Sheet G

County: Orange SHEET 8

Highway: FM 3247 Control: 2701-02-025

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC" Superpave Gyratory Compactor" and TGC "Texas Gyratory Compactor". All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68°F through 72°F).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

- 1. A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
- 2. Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
- 3. Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
- 4. An operational telephone system.
- 5. Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
- 6. Water (for testing purposes) from an approved source
- 7. Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and

General Notes Sheet H

Highway: FM 3247 Control: 2701-02-025

fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.

- 8. A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment
- 9. A laboratory sink measuring  $24 \times 30$  in. and 12 in. deep
- 10. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's, then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.

#### 11. Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes.

RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements.

Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

A material transfer device (MTD) will be required for all surface courses of HMA on this project. An MTD is defined as a self-propelled, wheel-mounted vehicle capable of receiving HMA from the haul trucks separate from the paver. The MTD will have a minimum storage capacity of approximately 25 tons and will be equipped with a pivoting discharge conveyor and a means of completely remixing the HMA before placement. The Engineer may approve an alternative device on a trial basis for the surface course. This device will be capable of receiving HMA separate from the paver and must have remixing capabilities. For all other courses of HMA, other than the

SHEET 9

Highway: FM 3247 Control: 2701-02-025

surface, an alternative device may be used as long as it is capable of receiving HMA separate from the paver.

Overlay across the ends of any curb ramps must not create a barrier to their use. Changes in level up to ½" may be vertical; between ½" and ½" must be beveled with a slope no greater than 1:2; greater than ½" will require a "ramp".

Station limits may be adjusted as directed to meet varying field conditions

Arrange laydown operations to leave existing centerline markings in place for the maximum time feasible.

#### **Item 6185 Truck Mounted Attenuator**

County: Orange

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMAs for mobile operations.

Therefore, 2 total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.

General Notes Sheet I General Notes Sheet J



# **Estimate & Quantity Sheet**

**CONTROLLING PROJECT ID** 2701-02-025

**DISTRICT** Beaumont HIGHWAY FM 3247

**COUNTY** Orange

Report Created On: Sep 12, 2022 10:37:49 AM

	of Iransport	ution			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	134-6004	BACKFILL (TY A OR B)	STA	67.910	
	164-6025	CELL FBR MLCH SEED(PERM)(URBAN)(SANDY)	SY	3,049.000	
	168-6001	VEGETATIVE WATERING	MG	25.660	
	351-6004	FLEXIBLE PAVEMENT STRUCTURE REPAIR(8")	SY	1,603.000	
	354-6130	PLANE ASPH CONC PAV (0"-1.75")	SY	2,458.000	
	500-6001	MOBILIZATION	LS	1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	2.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	120.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	120.000	
	530-6011	INTRSCT, DRVWAYS, & TURNOUT (ACP)	SY	337.000	
	530-6016	DRIVEWAYS (BASE)	SY	19.000	
	533-6004	RUMBLE STRIPS (CENTERLINE) ASPHALT	LF	6,041.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	49.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	688.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	398.000	
	666-6224	PAVEMENT SEALER 4"	LF	68.000	
	666-6225	PAVEMENT SEALER 6"	LF	50.000	
	666-6226	PAVEMENT SEALER 8"	LF	100.000	
	666-6230	PAVEMENT SEALER 24"	LF	42.000	
	666-6231	PAVEMENT SEALER (ARROW)	EA	2.000	
	666-6285	REF PROF PAV MRK TY I(W)6"(SLD)(090MIL)	LF	13,501.000	
	666-6299	RE PM W/RET REQ TY I (W)4"(BRK)(090MIL)	LF	30.000	
	666-6311	RE PM W/RET REQ TY I (Y)4"(BRK)(090MIL)	LF	1,150.000	
	666-6314	RE PM W/RET REQ TY I (Y)4"(SLD)(090MIL)	LF	6,895.000	
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	54.000	
	668-6077	PREFAB PAV MRK TY C (W) (ARROW)	EA	4.000	
	668-6085	PREFAB PAV MRK TY C (W) (WORD)	EA	4.000	
	672-6007	REFL PAV MRKR TY I-C	EA	22.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	688.000	
	677-6001	ELIM EXT PAV MRK & MRKS (4")	LF	68.000	
	677-6003	ELIM EXT PAV MRK & MRKS (8")	LF	100.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	42.000	
	677-6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA	2.000	
	3077-6065	SP MIXESSP-DSAC-A PG76-22	TON	3,272.000	
	3077-6075	TACK COAT	GAL	2,039.000	
	6185-6002	TMA (STATIONARY)	DAY	26.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	5.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Beaumont	Orange	2701-02-025	10

|--|

ROADWAITIL							134	351	354	530	530	533	30	77
							6004	6004	6130	6011	6016	6004	6065*	6075*
STA	то	STA	LENGTH (FT)	WIDTH (FT)	OFFSET (LT/RT)	SURFACE AREA (SY)	BACKFILL (TY A OR B)	FLEXIBLE PAVEMENT STRUCTURE REPAIR(8")	PLANE ASPH CONC PAV (0"-1.75")	INTRSCT, DRVWAYS, & TURNOUT (ACP)	DRIVWAYS (BASE)	RUMBLE STRIPS (CENTERLINE) ASPHALT	SP MIXES SP-D SAC-A PG 76-22	TACK COAT
							STA	SY	SY	SY	SY	LF	SY	SY
235+54	TO	244+04	850	58		5,478	1	-	-	-	-	_	-	-
244+04	TO	246+70	266	58		1,714	2.66	-	1289	54	-	-	1714	1714
246+70	TO	249+09	239	51		1,354	2.39	-	-	-	-	-	1354	1354
249+09	TO	311+52	6,243	44		30,521	62.43	-	768	283	19	6041	30521	30521
311+52	TO	311+95	43	84		401	0.43	-	401	-	-	-	401	401
252+81	TO	253+45	64	12	RT	85	-	85	-	-	-	-	-	-
261+11	TO	261+93	82	12	RT	109	-	109	-	-	-	-	-	-
262+56	TO	262+84	28	12	LT	37	-	37	-	-	-	-	-	-
271+66	TO	272+71	105	12	RT	140	-	140	-	-	-	-	-	-
272+41	TO	273+30	89	12	LT	119	1	119	-	-	-	-	-	-
279+60	TO	280+00	40	12	LT	53	-	53	-	-	-	-	-	-
280+70	TO	281+48	78	12	LT	104	-	104	-	-	-	-	-	-
282+95	TO	284+03	108	12	RT	144	-	144	-	-	-	_	-	-
283+37	TO	284+35	98	12	LT	131	-	131	-	-	-	-	-	-
289+32	TO	289+49	17	12	RT	23	-	23	-	-	-	_	-	-
290+47	TO	290+97	50	12	RT	67	-	67	-	-	-	-	-	-
292+63	TO	293+45	82	12	LT	109	-	109	-	-	-	-	-	-
293+38	TO	294+18	80	12	RT	107	-	107	-	-	-	-	-	-
296+82	TO	297+08	26	12	RT	35	-	35	-	-	_	-	-	-
298+47	TO	299+23	76	12	RT	101	-	101	-	-	-	-	-	-
301+33	TO	301+66	33	13	RT	48	-	48	-	-		-	-	-
303+63	TO	304+31	68	12	RT	91	1	91	-	-	-	-	-	-
304+45	TO	304+87	42	12	RT	56	-	56	-	-	_	-	-	-
305+97	TO	306+30	33	12	RT	44	-	44	-	-	-	-	-	-
					PROJ	ECT TOTAL:	67.91	1,603	2,458	337	19	6,041	33,990	33,990

<sup>\*</sup> FOR THE CONTRACTORS INFORMATION ONLY

**BASIS OF ESTIMATE** 

ITEM	CODE	DESCRIPTION	QUANTITY	RATE	DEPTH	QUANTITY
168	6001	VEGETATIVE WATERING	0.63 AC	6.788 MG/AC/CYCLE, 6 CYCLES	-	25.66 MG
3077	6065	SP MIXES SP-D SAC-A PG 76-22	33,990 SY	110 LB/SY/IN	1.75 IN	3,272 TON
3077	6075	TACK COAT	33,990 SY	0.06 GAL/SY	-	2,039 GAL

FM 3247

QUANTITY SUMMARY



<b>PAVEMENT</b>	MAR	KINGS ITEM	IS .												
				662	662			666				668		67	72
				6109	6111	6035	6285	6299	6311	6314	6076	6077	6085	6007	6009
STA	то	STA	LENGTH (FT)	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	REF PROF PAV MRK TY I(W) 6"(SLD)	RE PM W/RET REQ TY I (W) 4" (BRK) (090MIL)	RE PM W/RET REQ TY I (Y) 4" (BRK) (090MIL)	RE PM W/RET REQ TY I (Y) 4" (SLD) (090MIL)	PREFAB PAV MRK TY C (W) (24") (SLD)	PREFAB PAV MRK TY C (W) (ARROW)	PREFAB PAV MRK TY C (W) (WORD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A
				EA	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA
243+54	TO	245+53	199	40	20	398	348	-	-	398	42	4	4	20	20
245+53	TO	249+09	356	9	64	-	712	30	-	1,274	-	-	1	2	64
249+09	TO	265+34	1,625	-	163	-	3,250	-	-	3,250	-	-	-	-	163
265+34	TO	272+07	673	-	84	-	1,346	-	170	673	-	-	-	-	84
272+07	TO	272+52	45	-	-	-	45	-	-	-	-	-	-	-	-
272+52	TO	278+82	630	-	79	-	1,260	-	160	630	-	-	-	-	79
278+82	TO	304+82	2,600	-	195	-	5,200	-	650	-	-	-	-	-	195
304+82	TO	311+52	670	-	84	_	1,340	-	170	670	12	-	-	-	84
		PRO	JECT TOTAL	: 49	688	398	13,501	30	1,150	6,895	54	4	4	22	688

PAVEIVIE	<u> </u>	ARKING	S ITEMS CON	NIINOED		666				6	77	
				# 6224	# 6225	# 6226	# 6230	# 6231	# 6001	# 6003	# 6007	# 6008
STA	то	STA	LENGTH (FT)	PAVEMENT SEALER 4"	PAVEMENT SEALER 6"		PAVEMENT SEALER 24"		MRK &	ELIM EXT PAV MRK & MRKS 8"	ELIM EXT PAV MRK & MRKS 24"	ELIM EXT PAV MRK & MRKS (ARROW)
				LF	LF	LF	LF	EA	LF	LF	LF	EA
243+54	ТО	244+04	50	68	50	100	42	2	68	100	42	2
		PRO	JECT TOTAL:	68	50	100	42	2	68	100	42	2


			61	<u>85                                    </u>
			6002	6005
			TMA (STATIONARY)	TMA (MOBILE OPERATION)
STA	то	STA	DAY	DAY
		244 25	26	L
243+54	TO	311+95	26	5
243+54	TO	311+95	26	ס
243+54		311+95 ROJECT TOTAL:		5

MISCELLANOUS ITEMS

# - THESE ITEMS ARE INTENDED FOR USE ON THE CONCRETE PAVEMENT SECTION ONLY.

FM 3247

QUANTITY SUMMARY



# \*\*DRIVEWAY & INTERSECTION ITEMS

										247	30	
										6001 *	6065*	6075*
STA	DESCRIPTION	SIDE OF ROAD	MATERIAL	R1	R2	W2	W1	L	AREA (SY)	FL BS (CMP IN PLACE)( TYA GR1-2) (IN VEH)	SP MIXES SP-D SAC-A PG 76-22	TACK COAT
										СҮ	SY	SY
243+75	1	RT	CONC	5	5	45	35	5	22	-	-	-
244+30	2	LT	CONC	4	4	33	25	5	16	-	16	16
245+00	3	RT	CONC	5	5	45	35	5	22	-	22	22
245+64	4	LT	CONC	4	4	33	25	5	16	-	16	16
249+39	5	LT	GRASS	5	5	25	15	5	11	4	-	-
249+50	6	RT	CONC	15	15	54	24	5	22	-	22	22
250+75	7	RT	CONC	15	15	85	55	5	39	-	39	39
252+80	8	RT	GRAVEL	5	5	20	10	5	8	3	-	-
259+30	9	RT	GRAVEL	5	5	25	15	5	11	4	-	-
265+90	10	RT	CONC	15	15	50	20	5	19	-	19	19
266+90	11	LT	CONC	5	5	25	15	5	11	-	11	11
267+05	12	RT	CONC	10	10	40	20	5	17	-	17	17
269+00	13	LT	CONC	5	5	25	15	5	11	-	11	11
269+10	14	RT	CONC	8	8	32	15	5	13	-	13	13
271+10	15	RT	CONC	8	8	32	15	5	13	-	13	13
271+85	16	RT	GRAVEL	5	5	25	15	5	11	4	-	-
272+30	ANDERSON VILLA ST	Ţ	CONC	12	12	49	25	5	21	-	21	21
275+45	17	RT	GRAVEL	5	5	25	15	5	11	-	-	-
293+00	18	LT	CONC	20	20	82	42	5	34	-	34	34
293+85	19	RT	CONC	15	15	54	24	5	22	-	22	22
300+50	20	LT	CONC	20	20	82	42	5	34	-	34	34
302+25	21	LT	CONC	13	13	62	36	5	27	-	27	27
308+25	22	LT	GRASS	5	5	25	15	5	11	4	-	-
									TOTAL:	19	337	337

<sup>\*</sup> FOR THE CONTRACTORS INFORMATION ONLY. FOR ADDITIONAL INFORMATION SEE SHEET - 37


#### **EROSION CONTROL ITEMS**

			164	168	50	06
	STA TO STA		6025	6001*	6041	6043
STA			CELL FBR MLCH SEED (PERM) (URBAN)	VEGETATIVE WATERING	BIODEG EROSN CONT LOGS (INSTL) (12")	BIODEG EROSN CONT LOGS (REMOVE)
			SY	AC	LF	LF
243+54	TO	311+95	3,049	0.63	-	-
DISCF	DISCRETIONARY				120	120
PROJECT TOTAL:		3049	0.63	120	120	

<sup>\*</sup> FOR THE CONTRACTORS INFORMATION ONLY - SEE BASIS OF ESTIMATE

FM 3247

QUANTITY SUMMARY




<sup>\*\*</sup> PAY FOR THESE ITEMS UTILIZING ITEM 530 INTERSECTIONS, DRIVEWAYS, AND TURNOUTS.

## SEQUENCE OF WORK:

- 1. INSTALL PROJECT LIMIT SIGNING/TRAFFIC CONTROL PLAN.
  - A. MAINTAIN THESE SIGNS FOR THE DURATION OF THE PROJECT.
- 2. INSTALL SW3P.
- 3. PERFORM BASE REPAIRS.
- 4. INSTALL OVERLAY (MILLED BUTT JOINTS FOR EACH END AS SHOWN ELSEWHERE).
- A. INSTALL WORKZONE PAVEMENT MARKINGS (TABS).
- 5. PERFORM DRIVEWAY/CITY STREET CONSTRUCTION.
- 6. BACKFILL PAVEMENT EDGES.
  - A. INSTALL MILLED CENTERLINE RUMBLE STRIPS.
  - B. PERFORM SEEDING OPERATIONS.
  - C. WATER AS SHOWN ELSEWHERE AND AS DIRECTED.
- 7. INSTALL FINAL PAVEMENT MARKINGS.
- 8. FINAL CLEAN-UP

## NOTES:


1. SEQUENCE OF WORK MAY BE MODIFIED WITH ENGINEER'S APPROVAL.



09/12/2022

FM 3247

SEQUENCE OF WORK



#### BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travellanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

#### **WORKER SAFETY NOTES:**

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

#### COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

# THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




Safety Division Standard

# BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC(1)-21

		<b>-</b>	_	•				
E:	bc-21.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxDOT	ск: ТхDОТ	
)TxDOT	November 2002	CONT	SECT	JOB		HIGHWAY		
-03	REVISIONS 7-13	2701	02	025		FM	3247	
-07	8-14	DIST		COUNTY			SHEET NO.	
5-10	5-21	BMT		ORANG	Ε	•	15	

3-10



- (See note 2 below)
- 1. The lypical minimum signing on a crossrood approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK"(G20-2) sign on low volume crossroods (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- 3. Bosed on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGCER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- 4. The "ROAD WORK NEXT X MILES"(G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- 5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads. 6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

#### BEGIN T-INTERSECTION WORK \* \*G20-9TP \* \*R20-5T FINES DOUBLE \* \*R20-50TP ROAD WORK ← NEXT X NALES \* \*G20-26T WORK ZONE G20-1bTL $\Diamond$ INTERSECTED 1000'-1500' - Hwy 1 Block - City 1000'-1500' - Hwy ROADWAY ➾ 1 Block - City G20-16TR ROAD WORK WORK ZONE G20-26T \* \* 80. BEGIN G20-5T \* \* G20-9TP ZONE TRAFFIC G20-6T FINES \* \* R20-5T IDOUBLE \* \* R20-5oTP ROAD WORK G20-2

#### CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

#### TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING

#### SIZE

#### **SPACING**

J-2 L			
onventional Road	Expressway/ Freeway	Posted Speed	Sign # Spacing "X"
		MPH	Feet (Apprx.)
48" × 48"	48" × 48"	30	120
40 × 40		35	160
		40	240
		45	320
" × 36" 48'	x 48"	50	400
55	" ' '	55	500 <sup>2</sup>
		60	600 <sup>2</sup>
		65	700 <sup>2</sup>
" × 48" 48'	× 48"	70	800 <sup>2</sup>
		75	900 <sup>2</sup>
		80	1000 <sup>2</sup>
		*	* 3

- # For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

#### GENERAL NOTES

Sign

Number

or Series

CW204

CW21

CW22

**CW23** 

CW25

CW14

CW1, CW2,

CW7, CW8,

CW9, CW11,


CW3, CW4,

CW5, CW6,

CW10, CW12

CW8-3,

- 1. Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCO", Sign Appendix or the "Slandard Highway Sign Designs for Texas" manual for complete list of available sign design



\* \*G20-5T

\* \*G20-9TP ZONE STAY ALERT BEGIN ROAD WOR NEXT X MILES OBEY SPEED RAFFIC ROAD LIMIT ROAD ROAD X XR20-5T FINES SKINS WORK WORK CLOSED R11-2 CW1-4 DOUBLE STATE LAW りっ MILE TALK OR TEXT LATER ¥ ¥R20-5aTP \* \*G20-6T R20-3T G20-10T CW20-10 Borricode or CW13-1P CW2Ŏ-1E devices -CSJ Limit ➾ SPEED R2:1 END ROAD WORK LIMIT END G20-2bT \*\* G20-2 \* \*

to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES"(G20-5T)sign for each specific project. This distance shall replace the " $\ddot{\text{X}}$ " and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

- ☐ The "BEGIN WORK ZONE"(G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D)sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND					
г Туре 3 Barricade					
0	Channelizing Devices				
<b>þ</b>	Sign				
x	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.				

#### SHEET 2 OF 12




# BARRICADE AND CONSTRUCTION PROJECT LIMIT

# BC(2)-21

DN: T	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
CONT	SECT	JOB		н	GHWAY
2701	02	025		FM	3247
DIST		COUNTY			SHEET NO.
BMT	ORANGE				16
	2701 DIST	CONT SECT 2701 02 DIST	CONT SECT JOB  2701 02 025  DIST COUNTY	CONT SECT JOB 2701 02 025 DIST COUNTY	CONT SECT JOB H  2701 02 025 FM  DIST COUNTY

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



## **GUIDANCE FOR USE:**

#### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged povement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width

f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.


#### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

#### **GENERAL NOTES**

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of traveland are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:
  - 40 mph and greater 0.2 to 2 miles
- - 35 mph and less
- 0.2 to 1 mile
- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- 6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A Law enforcement.
  - B. Flagger stationed next to sign.
  - C. Portable changeable message sign (PCMS).
  - D. Low-power (drone) radar transmitter.
- E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form \*1204 in the TxDOT e-form system.






Texas Department of Transportation


# BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC(3)-21


	bc-21.dgn	DN: TxC	OT	ck: TxDOT	DW:	TxDOT	ck: TxD01
TxDOT	November 2002	CONT	SECT	JOB		H	HIGHWAY
	REVISIONS	2701	02	025		FN	1 3247
9-07	8-14 5-21	DIST		COUNTY			SHEET NO.
·-13 5·21		BMT	T ORANGE				17

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS










- \* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.
  - x x When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travellane. lemental plaques (advisory or distance) should not cover the surface of the parent sign.



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two SIDE ELEVATION

Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or monufacturer's recommended procedures for attaching sign substrates to other types of sign supports

> Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

#### STOP/SLOW PADDLES

of at least the same gauge material.


1. STOP/SLOW poddles are the primary method to control traffic by flaggers. The STOP/SLOW poddle size should be 24" x 24".


obove and two below the spice point. Splice must be located entirely behind

should be at least 5 times nominal post size, centered on the splice and

the sign substrate, not near the base of the support. Splice insert lengths

- 2. STOP/SLOW poddles shall be retroreflectorized when used at night. 3. STOP/SLOW poddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.





24" SLOW
24"
Background - Orange Legend & Border - Block

SHEETING REC	UIREMENTS	(WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BL ACK	ACRYLIC NON-REFLECTIVE FILM

#### CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction

Wood

- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- permanent signs are to be removed and relocated using temporary supports. the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic controldevice that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

#### GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in occordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been amitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the inspector's TxDOT diary and having both the inspector and Contractor initial and date the agreed upon changes.
- The Controctor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- 9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

#### <u>QURATION OF WORK (as defined by the "Texas Manualan Uniform Traffic Control Devices" Part 6)</u>

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- b. Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nightlime work losting more than one hour.
- c. Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
- d. Short, duration work that occupies a location up to 1 hour.
- e. Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

- SIGN MOUNTING HEIGHT.

  1. The bottom of Long-term/intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except
- as shown for supplemental plaques mounted below other signs.

  2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground.
  3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

#### SIZE OF SIGNS . The Controctor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- 1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide. fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the spice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

#### REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- While sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background. 3. Orange sheeting, meeting the requirements of DMS-8300 Type B or Type G, , shall be used for rigid signs with orange backgrounds.

#### SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

#### REMOVING OR COVERING

- 1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.

  2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- . Burlao shall NOT be used to cover sians.
- i. Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

#### SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.

  The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight.
- 3. Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights.

  Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.

  Sandbags shall be made of a durable material that tears upon vehicular
- impact. Rubber (such as lire inner tubes) shall NOT be used. Rubber ballasts designed for channelizing devices should not be used for
- bollost on portable sign supports. Sign supports designed and monifoctured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbaas shall be placed along the length of the skids to weigh down the sign support.

  Sandbags shall NOT be placed under the skid and shall not be used to level
- sion supports placed on slopes.

#### FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be arange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face. SHEET 4 OF 12




Traffic Safety Division Standard


# BARRICADE AND CONSTRUCTION **TEMPORARY SIGN NOTES**

BC(4)-21

			_				
E:	bc-21.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
)TxDOT	November 2002	CONT	SECT	JOB		HIGI	HWAY
	REVISIONS	2701	02	025		FM	3247
9-07	8-14	DIST		COUNTY		,	SHEET NO.
7-13	5-21	BMT	ORANGE				18








## GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square foologe shall adhere to the manufacturer's recom Two post installations can be used for larger signs.



## WEDGE ANCHORS

Both steeland plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary on the SMD Standard Sheets may be used as tempor sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

## OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

#### GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" log screws must be used on every joint for final
- . No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- . When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
  - See BC(4) for definition of "Work Durotion."
  - Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

#### SHEET 5 OF 12

Traffic Safety Division Standard



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

ILE:	bc-21.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDO	CK: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB			HIGHWAY
		2701	02	025		FN	A 3247
	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	BMT		ORANG	Ε		19

SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS \* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32'

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

#### PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- 2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway: i.e., "EXIT CLOSED." Do not use the term "RAMP."
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- 6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnigh Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flosh" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message: i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message. 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phroses that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.

  16. Each line of text should be centered on the message board rather than
- left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bors is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Rood A	CCS RD	Najor MAJ	
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking Road	PK ING
CROSSING	XING	Right Lane	RT LN
Detour Route	DETOUR RTE	Saturday	SAT
Do Not	DONT	Service Road	SERV RD
East	F	Shoulder	SHLDR
Eastbound	(route) E	Slippery	SLIP
Emergency	EMER	South	S
Emergency Vehicle		Southbound	(route) S
Entrance, Enter	ENT	Speed	SPD SPD
Express Lone	EXP LN	Street	IST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving	HAZ DRIVING	Trovelers	TRVLRS
Hazardous Material	HAZMAT	Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway	nw i	Vehicles (s)	VEH, VEHS
Hour (s)	HR, HRS	Warning	WARN
Information	INFO	Wednesday	WED
it is	ITS	Weight Limit	WT LIMIT
Junction	JCT	Weight Limit	A CIMII
Left	LFT	Westbound	(route) W
Left Lone	LFT LN	Westbound Wet Pavement	WET PVMT
Lane Closed	LN CLOSED	Wet Povement	WEI PAMI
Lower Level	LWR LEVEL	1 WIII NOT	IWUNI

Roadway designation . IH-number, US-number, SH-number, FM-number

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

#### Phase 1: Condition Lists

	Closure List	Other Condit	ion List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	L ANES SHIFT

#### APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phose Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phose selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

# Phase 2: Possible Component Lists

ction to Take/Effo Lis		Location List	Warning List	<ul><li>* * Advance</li><li>Notice List</li></ul>
MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- XX X PM-X AM
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE	NEXT TUE AUG XX
USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM- XX AM
STAY IN LANE *		x x Se	ee Application Guidelines No	te 6.

#### WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate. 2. Roadway designations IH, US, SH, FM and LP can be interchanged as
- appropriate.
- 3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary. 7. FT and MI, MILE and MILES interchanged as appropriate
- 8. AT, BEFORE and PAST interchanged as needed.
  9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS

SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

same size arrow.

BLVD

CLOSED

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute
- for, or replace that sign. 4. A full matrix PCMS may be used to simulate a floshing arrow board provided it meets the visibility, flosh rate and dimming requirements on BC(7), for the

SHEET 6 OF 12



# BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21

		• • •	_	• -			
FILE:	bc-21.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxD0	CK: TxDOT
© TxD0T	November 2002	CONT	SECT	JOB			HIGHWAY
	REVISIONS	2701	02	025		FN	A 3247
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	BMT		ORANG	E		20


Warning reflector may be round

or square.Must have a yellow

30 square inches

reflective surface area of at least


- 1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



#### CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB.

  An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional)while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Povement markers or temporary flexible-reflective roodway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10.Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer
- 11. Single slope barriers shall be delineated as shown on the above detail.




#### LOW PROFILE CONCRETE BARRIER (LPCB)

Attach the delineators as per

manufacturer's recommendations

IN WORK ZONES



#### DELINEATION OF END TREATMENTS

#### **END TREATMENTS FOR** CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apparapriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

# BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

#### WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Floshing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hozardous orea. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B or C Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control
- devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".

  5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the worning lights meet the requirements of the lotest ITE Purchase Specifications for Floshing and Steady-Burn Worning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

#### WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.

  3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive floshing of the sequential warning lights should occur from the beginning of the laper to the end of the merging laper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travellane on detours on lone changes, on lane closures, and on other similar conditions.
- 5. Type Á, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.


#### WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The worning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder toper or merging toper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Floshing Arrow Board should be used for all lane closures on multi-lane roadways, or slow
- moving maintenance or construction activities on the travellanes.

  2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Floshing Arrow Board.
- 4. The Floshing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- 5. The straight line caution display is NOT ALLOWED.
- The Floshing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage.
   The floshing rate of the lamps shall not be less than 25 nor more than 40 floshes per minute.

   Minimum lamp "on time" shall be approximately 50 percent for the floshing arrow and equal

- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
   The sequential arrow display is NOT ALLOWED.
   The flashing arrow display is the TxDOT standard: however, the sequential chevron display may be used during daylight operations.
   The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
   A flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
   A full matrix PCMS may be used to simulate a flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
   Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.
- to boltom of panel.

REQUIREMENTS							
TYPE MINIMUM MINIMUM NUMBER VISIBILIT OF PANEL LAMPS DISTANCE							
В	30 × 60	13	3/4 mile				
С	48 × 96	15	1 mile				

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

# FLASHING ARROW BOARDS

SHEET 7 OF 12

#### TRUCK-MOUNTED ATTENUATORS

- I. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for
- Assessing Sofety Hordwore (MASH).

  2. Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted
- in the plans.

  5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- 6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



Traffic Safety Division Standard Texas Department of Transportation

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC(7)-21

ILE:	bc-21.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		ни	CHWAY
	REVISIONS	2701	02	025		FM	3247
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	BMT	ORANGE				21



# 1. For long term stationary work zones on freeways, drums shall be used as

- the primary channelizing device.

  2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the
- cones in proper position and location.

  3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

#### GENERAL DESIGN REQUIREMENTS

**GENERAL NOTES** 

Pre-qualified plastic drums shall meet the following requirements:


- Plastic drums shall be a two-piece design: the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or oir turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in stripes.
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, arange, high-density polyethylene (HDPE) or other approved material.
  9. Drum body shall have a maximum unballasted weight of 11 lbs.
  10.Drum and base shall be marked with manufacturer's name and model number.

#### RETROREFLECTIVE SHEETING


- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

#### BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stocking of sandbags will be allowed, however height of sandbags above povement surface may not exceed 12 inches.
- Boses with built-in bollast shall weigh between 40 lbs. and 50 lbs.
   Built-in bollast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballost on drums approved for this type of ballost on the CWZTCD list.
- The bollost shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to povement.








#### DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrions with visual disabilities normally use the closed sidewalk, a Detectable Pedestrion Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5. Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rais as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B or Type C Orange, sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lone.
- 4. Other sign messages (lext or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12





Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

	• •	_	-			
E: bc-21.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxDOT	ск: ТхDОТ
TxDOT November 2002	CONT	SECT	JOB		HIGI	YAWH
REVISIONS -03 8-14	2701	02	025	FM	3247	
-03 8-14 -07 5-21	DIST		COUNTY		,	SHEET NO.
-13	BMT		ORANG	E		22






- 2. VP's may be used in daylime or nightlime situations. They may be used at the edge of shoulder drop-offs and other areas such as lone transitions where positive daylime and nightlime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lone roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travellane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
   Self-righting supports are available with portable base.
- Self-righting supports are available with portable base.
   See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeling for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

# VERTICAL PANELS (VPs)


36"



PORTABLE

- 1. Opposing Traffic Lane Dividers (OTLD) are defineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the povement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B or Type C configring to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the for side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B or Aype C configring to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on topers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

#### CHEVRONS

#### GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone oreas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, foded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Povement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the povement surface.
   Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final povement surfaces, including povement surface discoloration or surface integrity. Driveable bases shall not be permitted on final povement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



#### LONGITUDINAL CHANNELIZING DEVICES (LCD)

36"

Fixed Base w/ Approved Adhesive

Support can be used?

(Driveoble Bose, or Flexible

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travellanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

#### WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballosted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballosted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation
  or channelizing devices to improve daytime/nightlime visibility. They may also be supplemented with povement markings.
   Water ballosted systems used as barriers shall be placed in accordance to application and installation requirements
- specific to the device, and used only when shown on the CWZTCD list.

  4. Water ballosted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH)
- urbon areas. When used on a toper in a low speed urbon area, the toper shall be delineated and the toper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballosted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula		esirable er Leng x x		Spacine Channeli Devi	g of zing
		10° Offset	11 <sup>.</sup> Offset	12' Offset	On a Taper	On a Tangent
30	2	150 <sup>-</sup>	165'	180'	30'	60.
35	L- <u>WS<sup>2</sup></u>	205'	225'	245	35'	70.
40	60	265	295	320	40'	80.
45		450'	495'	540	45'	90.
50		500	550'	600.	50'	100'
55	L-WS	550'	605	660	55'	110'
60	] - " 3	600.	660	720	60.	120 <sup>-</sup>
65	]	650'	715'	780'	65'	130'
70	]	700'	770'	840	70'	140'
75	]	750'	825'	900.	75'	150'
80		800.	880.	960'	80.	160'
	Tonas lan	alba ba	a bass	anadad a	.11	

\*\* Toper lengths have been rounded off.
L-Length of Toper (FT.) W-Width of Offset (FT.)
S-Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF
CHANNELIZING DEVICES AND
MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Traffic Safety Division Standard


Suggested Maximum


# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21

		. • .	_	_			
:	bc-21.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		HIG	HWAY
	REVISIONS	2701	02	025		FM	3247
-07	8-14	DIST	DIST COUNTY			SHEET NO.	
-13	5-21	BMT	ORANGE 23				23

Stiffener










Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

#### TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION






Two-Piece cones

3" min. 2" to 6" 3" min.

One-Piece cones

Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- 1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- 2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two piece cones have a cone shaped body and a separate rubber base. or ballast, that is added to keep the device upright and in place.
- 3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a sma outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- 7. Cones or tubular markers used on each project should be of the same size and shape.





Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

# BC(10)-21

	bc-21.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		ни	CHWAY
	REVISIONS	2701	02	025		FM	3247
-07	8-14	DIST		COUNTY			SHEET NO.
-13	5-21	BMT		ORANG	Ε		24

#### WORK ZONE PAVEMENT MARKINGS

#### **GENERAL**

- The Contractor shall be responsible for maintaining work zone and existing povement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental povement marking details may be found in the plans or specifications.
- Povement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard povement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- 7. All work zone povement markings shall be installed in accordance with Item 662, "Work Zone Povement Markings."

#### RAISED PAVEMENT MARKERS

- Raised povement markers are to be placed according to the patterns on BC(12).
- All raised povement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

#### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated povement markings (foil back) shall meet the requirements of DMS-8240.


#### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone povement markings within the work limits.
- Work zone povement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification them 662

#### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion
  or direct a motorist toward or into the closed portion of the roadway
  shall be removed or obilerated before the roadway is opened to traffic.
- The above shall not apply to detaurs in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detaur route.
- Povement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Povement Markings and Markers".
- The removal of povement markings may require resurfacing or seal coating portions of the roodway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type povement may be used.
- Blost cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised povement markers shall be as directed by the Engineer.
- Removal of existing povement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Block-out marking tope may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- 2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - 8. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic povement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new povements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

#### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Roised povement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised povement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.
- Guidemarks shall be designated as:
  YELLOW (two amber reflective surfaces with yellow body).
  WHITE (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised povement markers, non-reflective traffic buttons, roadway marker tobs and other povement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12

División Standard




Texas Department of Transportation


BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11)-21

DC(11)-Z1						
FILE: bc-21.dgn	DN: To	DOT	ск: TxDOT	DW:	TxDO	T CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB			HIGHWAY
REVISIONS 2-98 9-07 5-21	2701	02	025		FI	M 3247
1-02 7-13	DIST		COUNTY			SHEET NO.
11-02 8-14	BMT		ORANG	E		25

105







Type 3 Barricade

Type 3 Barricade

Channelizing Devices

Truck Mounted Attenuator (TMA)

Trailer Mounted Flashing Arrow Board

Sign

Flag

Flag

Flag

Flag

Flagger

Posted Speed	ed x x		Suggested Spacin Channeli Devi	g of zing	Minimum Sign Spacing	Suggested Longitudinal Buffer Space			
*		10" Offset	11 <sup>.</sup> Offset	12° Offset	On a Taper	On a Tangent	Distance	"B"	
30	2	150'	165'	180'	30.	60.	120'	90.	
35	L. ws²	205'	225	245	35'	70'	160'	120'	
40	1 🐃	265	295'	320	40'	80.	240	155 <sup>-</sup>	
45		450 <sup>°</sup>	495'	540	45'	90.	320.	195 <sup>-</sup>	
50		200.	550	600.	50'	100'	400'	240'	
55	l.ws	550	605	660.	55'	110'	500'	295'	
60	] - " - " -	600,	660	720'	60.	120'	600,	350	
65		650'	715'	780	65 <sup>.</sup>	130'	700'	410 <sup>-</sup>	
70		700 <sup>.</sup>	770 <sup>.</sup>	840	70 <sup>.</sup>	140	800.	475'	
75		750 <sup>.</sup>	825'	900.	75 <sup>.</sup>	150 <sup>-</sup>	900,	540'	

- × Conventional Roads Only
- × Taper lengths have been rounded off.
- L-Length of Toper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

	TYPICAL USAGE							
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	1	1	<b>√</b>	1				

#### GENERAL NOTES

- 1. Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those
  denoted with the triangle symbol may be amitted when stated in the
  plans, or for routine maintenance work, when approved by the Engineer.
- plans, or for routine maintenance work, when approved by the Engineer.

  3. Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- nearest traveled way.

  4. Shodow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shodow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shodow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
   See TCP(5-1) for shoulder work on divided highways, expressways and
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- right-of-way line and not parked on the paved shoulder.

  8. CW21-5 "SHOULDER WORK" signs may be used in place of CW20-10
  "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation


Traffic Operations Division Standard


TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(2-1)-18

	tcp2-1-18.dgn	DN:		CK:	DW:		CK:
۲xD	OT December 1985	CONT	SECT	JOB		HIC	HWAY
4	REVISIONS 4-98	2701	02	025		FM	3247
5	2-12	DIST		COUNTY			SHEET NO.
7	2-18	BMT		ORANG	Ε	- 1	27

161





ONE LANE TWO-WAY

CONTROL WITH FLAGGERS

	LEGEND							
		Type 3 Barricade	••	Channelizing Devices				
		Heavy Work Vehicle		Truck Mounted Attenuator (TMA)				
		Trailer Mounted Flashing Arrow Board	(2)	Portable Changeable Message Sign (PCMS)				
ı	þ	Sign	∿	Traffic Flow				
	Ø	Flog	Ф	Flagger				

Posted Speed	De		Minimum Desiroble Der Lengths		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance
×		10° Offset	11 <sup>.</sup> Offset	12° Offset	On a Taper	On a Tangent	Distance	B	
30	2	150	165	180'	30.	60'	120 <sup>-</sup>	<b>30</b> ,	200.
35	L• <u>ws²</u>	205	225	245	35'	70'	160'	120 <sup>-</sup>	250'
40	80	265	295'	320	40'	80.	240'	155'	305'
45		450'	495	540	45'	90.	320'	195 <sup>-</sup>	360 <sup>-</sup>
50		500'	550 <sup>.</sup>	600	50 <sup>.</sup>	100	400'	240 <sup>.</sup>	425 <sup>.</sup>
55	L-WS	550'	605'	660.	55'	110'	500 <sup>.</sup>	295 <sup>.</sup>	495'
60	L 3	<b>600</b> .	660.	720	60'	120'	600·	350	570 <sup>.</sup>
65		650	715	780'	65'	130'	700'	410'	645'
70		<b>700</b> .	770'	840	70'	140'	800.	475 <sup>.</sup>	730 <sup>.</sup>
75		750'	825	900.	75'	150'	900.	540 <sup>.</sup>	820'

- Conventional Roads Only
- **x x** Toper lengths have been rounded off.
  - L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

TYPICAL USAGE						
MOBILE SHORT DURATION		SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		

#### GENERAL NOTES

- l. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
  4. Flaggers should use two-way radios or other methods of communication to control traffic.
- 5. Length of work space should be based on the ability of flaggers to communicate. 6. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet
- in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricodes or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- . Additional Shodow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

#### TCP (2-2a)

- 8. The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet. 9. The R1-2oP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum.

#### TCP (2-2b)

- 10.Channelizing devices on the center line may be omitted when a pilot car is leading traffic and opproved by the Engineer
- 11.If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles.
- 12.Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situlations.




Traffic Operations Division Standard


TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP(2-2)-18

: tcp2-2-18.dgn	DN:		CK:	DW:	CK:	
TxDOT December 1985	CONT	SECT	JOB		HIGHWAY	
REVISIONS 95 3-03	2701	02	025		M 3247	
33 3-03 17 2-12	DIST		COUNTY		SHEET NO.	
98 2-18	BMT		ORANG	Ε	28	



# TCP (3-10) UNDIVIDED MULTILANE ROADWAY




OR

WORK

CONVOY


X VEHICLE


CONVOY



TCP (3-1b)

TWO-WAY ROADWAY WITH PAVED SHOULDERS





TRAIL/SHADOW VEHICLE B


with Flashing Arrow Board in CAUTION display

	LEGEND						
*	* Trail Vehicle     ARROW BOARD DISPLAY						
* *	Shodow Vehicle	ARROW BOARD DISPLAT					
* * *	Work Vehicle	₽	RIGHT Directional				
	Heavy Work Vehicle	<b>E</b>	LEFT Directional				
	Truck Mounted Attenuator (TMA)	₩	Double Arrow				
♦	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)				

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
1						

#### GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Floshing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- 6. Each vehicle shall have two-way radio communication capability.
- 7. When work convoys must change lones, the TRAIL VEHICLE should change lones first to shadow the other convoy vehicles.
- 8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- 9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY"(CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- 10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
UNDIVIDED HIGHWAYS


Texas Department of Transportation


TCP(3-1)-13

Traffic Operation

Division Standard


175






# TRAIL/SHADOW VEHICLE A

with RIGHT Directional display




## TRAIL/SHADOW VEHICLE B

with Flashing Arrow Board in Caution Mode



ADVANCE WARNING VEHICLE



	LEGEND							
*	Troil Vehicle		ADDOM: DOADD DIEDLAY					
* *	Shodow Vehicle		ARROW BOARD DISPLAY					
* * *	Work Vehicle	<b>₽</b>	RIGHT Directional					
	Heavy Work Vehicle	<b>F</b>	LEFT Directional					
	Truck Mounted Attenuator (TMA)	₩	Double Arrow					
♦	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)					

TYPICAL USAGE						
MOBILE	SHORT DURATION		INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
1						

#### GENERAL NOTES

- 1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.

  2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.

  3. The use of truck mounted attenuators (TMA) on the SMADOW VEHICLE ADVANCE was
- 3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING
- ond TRAIL VEHICLE ore required.

  4. Reflective sheeting on the reor of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Floshing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the

- 6. Each vehicle shall have two-way radio communication copability.
  7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
  8. Vehicle space sight distance contributions. Malariets approaching the convoy. depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change
- should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.

  X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.

  D. For divided highways with two or three lanes in one direction, the appropriate
- 10.For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.

  11.A double arrow shall not be displayed on the arrow board on the Advance Warning
- 12.For divided highways with three or four lanes in each direction, use TCP(3-2).
  13.Standard diamond shape versions of the CW20-5 series signs may be used as an
- option if the rectangular signs shown are not available.


  14.The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessory.
- 15.On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.



Traffic Operation Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL TCP(3-3)-14

FILE: tcp3-3.dgn	DN: Tx	:DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT September 1987	CONT	SECT	JOB		н	IGHWAY
REVISIONS 2-94 4-98	2701	02 025			FM 3247	
8-95 7-13	DIST	COUNTY				SHEET NO.
1-97 7-14	BMT	ORANGE			30	



#### GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lone at locations shown.
- 2. The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices
- 4. Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lone two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- 9. Replace defective Temporary Rumble Strips as directed by the Engineer.
- 10.Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

LEGEND						
<del></del>	Type 3 Barricade	•	Channelizing Devices			
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)			
	Trailer Mounted Flashing Arrow Panel	<b>(</b>	Portable Changeable Message Sign (PCMS)			
<b>þ</b>	Sign	∿	Traffic Flow			
$\Diamond$	Flag	Ъ	Fl agger			

Posted Speed	Formula	Desiroble		Suggested Spacine Channeli Devi	g of zing	Minimum Sign Spocing "x"	Suggested Longitudinal Buffer Space	
×		10° Offset	11 <sup>.</sup> Offset	12" Offset	On a Taper	On a Tangent	Distance	8
30	2	150'	165'	180	30.	60,	120'	<b>90</b> .
35	L. <u>ws²</u>	205	225'	245'	35'	70'	160'	120'
40	1 👯	265	295'	320'	40'	80.	240'	155'
45		450°	495'	540	45'	90.	320'	195'
50		500'	550	600.	50.	100	400	240'
55	l.ws	550	605	660	55'	110'	500'	295'
60	] - " " 3	<b>600</b> .	660	720 <sup>.</sup>	60.	120 <sup>-</sup>	600.	350
65		650'	715'	780'	65'	130'	700'	410'
70		700 <sup>.</sup>	770	840	70'	140'	800.	475'
75		750	825	900.	75 <sup>.</sup>	150'	900·	540°

- ■ Conventional Roads Only
- x x Toper lengths have been rounded off. L-Length of Toper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE LONG TELE TERM STATIONARY STATIONARY			
	1	<b>√</b>				

- Signs are for illustrative purposes only. Signs required may vary depending on the TCP,TMUTCD Typical Application, or project specific details for the project.
- For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

TABLE 2					
Speed	Approximate distance between strips in an array				
< 40 MPH	10'				
> 40 MPH & <_55 MPH	15′				
= 60 MPH	20′				
≥ 65 MPH	* 35'+				




TEMPORARY RUMBLE STRIPS

Traffic Safety Division Standard

WZ(RS)-22

wzrs22.dgn	DN: Tx[	TOC	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT November 2012	CONT	SECT	JOB		ни	CHWAY
REVISIONS	2701	02	025		FM	3247
·14 1-22 ·16	DIST		COUNTY			SHEET NO.
-10	BMT		ORANG	Έ		31

117




#### NOTES:

- 1. Short term povement markings may be prefabricated markings (stick down tape) or temporary flexiblereflective roadway marker tabs unless otherwise specified elsewhere in plans.
- 2. Short term povement markings shall NOT be used to simulate edge lines.
- 3. Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- 4. Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- 5. No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 colendar days. The Contractor will be responsible for maintaining short term povement markings until permanent povement markings are in place. When the Contractor is responsible for placement of permanent povement markings, no segment of roadway shall remain without permanent povement markings for a period greater than 14 colendar days unless weather conditions prohibit placement. Permanent povement markings shall be placed as soon as weather permits.
- 6. For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where possing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent povement markings should then be placed.
- 7. For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- 8. For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

#### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- 1. Temporary flexible-reflective roadway marker labs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- 2. Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- 3. When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway
- . No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.



- 1. Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240
  "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Costruction-Grade
  Prefabricated Pavement Markings."

#### RAISED PAVEMENT MARKERS

1. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

#### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

1. DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:


http://www.txdot.gov/business/contractors\_consultants/material\_specifications/default.htm



PAVEMENT MARKINGS

WZ(STPM)-13

FILE:	wzstpm-13.dgn	DN: T	OOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT	April 1992	CONT	SECT	JOB		HIG	HWAY
1-97	REVISIONS	2701	02	025		FM	3247
3-03		DIST		COUNTY			SHEET NO.
7-13		BMT		ORANG	Ε		32



DEPARTMENTAL MATERIAL SPECIFICATIONS					
PERMANENT PREFABRICATED PAVEMENT MARKINGS DMS-8240					
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241				
SIGN FACE MATERIALS	DMS-8300				

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

#### **GENERAL NOTES**

- 1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
- UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) ploque or Advisory Speed (CW13-1P) ploque.
- NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are
- 4. Signs shall be spaced at the distances recommended as per BC standards.
- Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
- 6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices"
- 7. Short term markings shall not be used to simulate edge lines.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1							
Edge Condition	Edge Height (D)	* Warning Devices					
0	Less than or equal to: 11/4" (maximum-planing) 11/2" (typical-overlay)	Sign: CW8-11					
7/// 🕇 0	Distance "D" may be a maximum of 1 1/4 " for planing operations and 2" for overlay operations if uneven lanes with edge condition 1 are open to traffic after work operations cease.						
② >3 T D	Less than or equal to 3"	Sign: CW8-11					
O" to 3/4"  12"  Notched Wedge Joint	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".						

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.


MINIMUM	WARNING	SIGN	SIZE
Conventional	roods	36" ×	36"
Freeways/exp divided roo	ressways, idways	48" x	48"


Texas Department of Transportation


SIGNING FOR UNEVEN LANES Traffic Operations Division Standard


WZ(UL)-13

TILE:	wzul-13.dgn	DN: T	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© ⊺xD0T	April 1992	CONT	SECT	JOB		н	IIGHWAY
	REVISIONS	2701	02	025		FM	3247
8-95 2-98		DIST		COUNTY			SHEET NO.
1-97 3-03		BMT		ORANG	Ε		33
110							












JASON D. WALDREP




CONT SECT JOB HIGHWAY


701 02 025 FM 3247


DIST COUNTY SHEET NO.

NOTE:

FOR MORE DETAILS SEE \*\*DRIVEWAY & INTERSECTION ITEMS SUMMARY ON SHEET: 13








PROFILE VIEW OPTION 1

1/2" Typ.

5/8" Max.

CONTINUOUS MILLED **DEPRESSIONS** (Rumble Stripes)


7"( 1/2")




This distance may vary based on width of shoulder

> PROFILE VIEW OPTION 2

CONTINUOUS MILLED **DEPRESSIONS** (Rumble Stripes)





\* This distance may vary based on width of shoulder



PROFILE VIEW OPTION 3


CONTINUOUS MILLED **DEPRESSIONS** (Rumble Strips)






PROFILE VIEW OPTION 4

CONTINUOUS MILLED **DEPRESSIONS** (Rumble Strips)




PLAN VIEW OPTION 5

RAISED EDGELINE RUMBLE STRIPS



PLAN VIEW OPTION 6

PROFILE EDGELINE **MARKINGS** 



#### GENERAL NOTES

- 1. Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- 2. Milled rumble strips are preferred when adequate povement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- 3. Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised povement markers, povement markings, and profile markings.
- 4. See the table below for determining what options may be used for edgeline rumble strips.

#### WHEN INSTALLING MILLED DEPRESSION EDGELINE RUMBLE STRIPS:

- 5. See dimensions for milled rumble strips, Other shapes and dimensions may be used if approved by the Traffic Operations
- 6. Pavement markings can be applied over milled shoulder rumble strips to create an edgeline rumble stripe.
- 7. Breaks in edgeline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks when installed on conventional highways.
- 8. Rumble strips shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- 9. Consideration should be given to noise levels when edgeline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inches depth of milled rumble strip may be considered in these areas.
- On roadways with high bicycle activity, consideration should be given before the installation of edgeline rumble strips. Things to consider include size of rumble strips, rumble strip material and location of rumble strips on the shoulder. If the designer determines that gaps are needed in the rumble strips due to bicycle use of the road, then follow the requirement shown in FHWA Technical Advisory T5040.39, or latest version. A detail of the spacing shall be included in the plans.

#### WHEN INSTALLING RAISED OR PROFILE EDGELINE RUMBLE STRIPS:


- 11. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- 12. Non-reflective traffic buttons shall be placed adjacent to the povement marking delineating the edgeline when used as a rumble strip. The color of the button should match the color of the adjacent edgeline marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- 13. Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- 14. Breaks in edgeline rumble strips using roised traffic buttons shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks when installed on
- 15. The minimum distance between the edgeline and the buttons should be used if the shoulder is less than 8 feet in width.
- 16. Raised profile thermoplastic markings used as edgelines may substitute for buttons.




Traffic Operations Division Standard

**EDGELINE** RUMBLE STRIPS ON UNDIVIDED OR TWO LANE HIGHWAYS RS(4) - 13

LE:	rs(4)-13.dgn	DN: Txl	TOC	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
C) TxDOT	October 2013	CONT	SECT	JOB HIGHWAY		JOB		HWAY
	REVISIONS	2701	02	025		FM	3247	
		DIST		COUNTY			SHEET NO.	
		BMT		ORANG	Ε	,	39	



# MARKINGS THROUGH INTERSECTIONS





 $\langle \neg$ 


## CENTERLINE AND LANE LINES FOUR LANE TWO-WAY ROADWAY WITH OR WITHOUT SHOULDERS

WITH OR WITHOUT SHOULDERS

# TYPICAL MULTI-LANE, TWO-WAY PAVEMENT MARKINGS THROUGH INTERSECTIONS







For posted speed on road being marked equal to or less than 40 MPH.

For posted speed on road being marked equal to or greater than 45 MPH.

## YIELD LINES

# WITH OR WITHOUT SHOULDERS Pavement Edge

—See Note 1-

Storage

Deceleration

10′

 $\Rightarrow$ 

-6" Solid White∕

Edge Line

Taper

8" Solid White Line

See note 3

6" Solid Yellow ≠

6" Solid White\_

Ēdge Line─

Edge Line

6" Solid Yellow

Edge Line

Optional

Dotted 8" White

Extension

- 1. Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- 2. Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield traingles shall only be used with yield signs.
- 3. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


## NOTES

#### **GENERAL NOTES**

- 1. Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- 2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



## GUIDE FOR PLACEMENT OF STOP LINES. EDGE LINE & CENTERLINE

Based on Traveled Way and Pavement Widths for Undivided Highways



Humet & Aviences



Texas Department of Transportation

PM(1)-22(MOD)

: bmtdistrictpm-22.dgn	DN:		CK:	DW:	CK:		
TXDOT JUNE 2022	CONT	SECT	JOB		HIGHWAY		
REVISIONS	2701	02	025	025 FN			
	DIST		COUNTY		COUNTY SHEE		SHEET NO.
	RMT	ORANGE		iE.	40		

FOUR LANE DIVIDED ROADWAY CROSSOVERS

-See Note 2-

10" min.

ΔΔΔΔΔΔΙ

**4**48" min.

line to

from edge

stop/yield

4" White Lane Line.

-4" Solid Yellow Line

Triangles

White Lane Line

\_\_\_

# $\langle \neg$ See Detail A See Detail B Type II-A-A 80. CENTERLINE FOR ALL TWO LANE ROADWAYS $\hookrightarrow$ -Type I-C See Detail C 80. CENTERLINE & LANE LINES FOR FOUR LANE TWO-WAY HIGHWAYS 1"-4" Type II-A-A

DETAIL "B'

18"•\_1"

2 to 3" --

OPTIONAL 6" EDGE LINE, CENTER LINE


OR LANE LINE

# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


40'

DETAIL "C"

CENTER OR EDGE LINE



# CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



# LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

BROKEN LANE LINE

# PERMANENT PREFABRICATED PAVEMENT MARKINGS as specified by the plans.

EPOXY AND ADHESIVES

HOT APPLIED THERMOPLASTIC

TRAFFIC PAINT

All pavement marking materials shall meet the required Departmental Material Specifications

BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS

MATERIAL SPECIFICATIONS

DMS-4200

DMS-6100


DMS-6130

DMS-8200


DMS-8220


DMS-8240

PAVEMENT MARKERS (REFLECTORIZED)



Type I(Top View)





RAISED PAVEMENT MARKERS



Traffic Safety Division Standard

POSITION GUIDANCE USING RAISED MARKERS RELECTORIZED PROFILE **MARKINGS** PM(2)-20

FILE: pm2-20.dgn	DN:		CK:	DW:		CK:
© TxDOT April 1977	CONT	SECT	JOB		HIGH	YAW
4-92 2-10 REVISIONS	2701	02	025		FM	3247
5-00 2-12	DIST		COUNTY		5	SHEET NO.
B-00 6-20	BMT		ORANG	Ε		41

# **GENERAL NOTES**

- All raised povement markers placed in broken lines shall be placed in line with and midway between
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



DETAIL

12"• 1"


31/4"-3/4"


2 to 3" —

4" EDGE LINE,


OR LANE LINE

CENTER LINE





- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, on additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- 3. Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and lost lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.



A two-way left-turn (TWLT) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


# TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY

#### GENERAL NOTES


- 1. Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn boys for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- 2. When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised povement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All povement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



# TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS





# WO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS

Traffic Safety Division Standard

PM(3)-20

22C

	111.	CULTURAL RESOURCES	,
		☐ No Action Required	
		Action No.	
		<ol> <li>Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon dis- covery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.</li> </ol>	
	   1v.	VEGETATION RESOURCES	1
	'''	□ No Action Required ☑ Required Action	•
		Action No.	,
		<ol> <li>No vegetation removal or trimming of any kind is allowed.     Exceptions are allowed for mowed and maintained grass.</li> </ol>	
	٧.	FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.	
		☐ No Action Required                       Required Action	
		Action No.	
)		<ol> <li>If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own.</li> </ol>	
		<ol> <li>If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEQC for guidance.</li> <li>Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.</li> <li>Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and the Texas Parks and Wildlife (TPW) Code Section 64.002.         The full MBTA guidance may be found here: https://ftp.dot.state.tx.us/pub/txdot-info/env/toolkit/350-01-gui.pdf     </li> </ol>	
5		5. Resource specific BMPs (Section I) and Pavement BMPs (Section II,F) from the "Updated Best Management Practices (BMPs) for TxDOT Maintenance Activities" guidance under the TxDOT Maintenance Program EA shall be reviewed and implemented where appropriate. The maintenance EA BMPs may be found here: https://ftp.txdot.gov/pub/txdot-info/env/080-01-bmp.pdf	
-			
ems			
		LIST OF ABBREVIATIONS	
ks ocks	CGP: DSHS: FHWA: MOA: MOU: MS4: MBTA: NOT: NWP:	Best Management Practice Construction General Permit SMSP: Storm Water Pollution Prevention Plan Texas Department of State Health Services Federal Highway Administration Memorandum of Agreement Memorandum of Understanding Memorandum of Understanding Memorandum of Understanding Memorandum of Store Sever System Municipal Separate Stormwater Sewer System Municipal Separate Sewer System Municipal	
		Company Compan	_

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

☐ No Action Required

Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances
- \* Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
NONE				

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

- 1. Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous
- materials or contamination is noted during construction.
- 2. Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.

#### VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

☐ No Action Required

Required Action

1. Comply with "General Construction" section found in the Beaumont District Environmental Field Guide



ENVIRONMENTAL PERMITS. ISSUES AND COMMITMENTS


EPIC



8/23/2022

DIS RI O' E NVI ROMMETAL DERA RI MENT

epic.dgn DN: TxDOT CK: AM DW: VP © TxDOT February 2019 CONT SECT JOB HIGHWAY 2701 02 025 FM 3247



STAKE LOG ON DOWNHILL

SIDE AT THE CENTER,

AT EACH END, AND AT

ADDITIONAL POINTS AS

(4' MAX. SPACING), OR

ENGINEER.

AS DIRECTED BY THE

NEEDED TO SECURE LOG


ADDITIONAL UPSTREAM

STAKES FOR HEAVY


RUNOFF EVENTS

FLOW ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE AS DISTURBED AREA DIRECTED BACK OF CURB LIP OF GUTTER STAKE ON DOWNHILL SIDE OF TEMP. EROSION LOG AT 8' (ON CENTER) MAX. CONTROL LOG AS NEEDED TO SECURE LOG. OR AS DIRECTED BY THE **ENGINEER** 

PLAN VIEW




#### PLAN VIEW



SECTION B-B EROSION CONTROL LOG AT BACK OF CURB

(CL-BOC)




EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY



MINIMUM

COMPACTED

DIAMETER



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

# SHEET 1 OF 3

**GENERAL NOTES:** 1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S

RECOMMENDATIONS, OR AS DIRECTED BY THE

2. LENGTHS OF EROSION CONTROL LOGS SHALL

BIODEGRADABLE OR PHOTODEGRADABLE

USE RECYCLABLE CONTAINMENT MESH.

STAKES SHALL BE 2" X 2" WOOD OR

SIZE TO HOLD LOGS IN PLACE.

FOR HEAVY RUNOFF EVENTS, ADDITIONAL

LOG FROM FOLDING IN ON ITSELF.

UNLESS OTHERWISE DIRECTED, USE

THE PURPOSE INTENDED.

BE IN ACCORDANCE WITH MANUFACTURER'S

RECOMMENDATIONS AND AS REQUIRED FOR

CONTAINMENT MESH ONLY WHERE LOG WILL

FILL LOGS WITH SUFFICIENT FILTER MATERIAL

TO ACHIEVE THE MINIMUM COMPACTED DIAMETER

SPECIFIED IN THE PLANS WITHOUT EXCESSIVE

\*3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT

2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY

DO NOT PLACE STAKES THROUGH CONTAINMENT

SANDBAGS USED AS ANCHORS SHALL BE PLACED

TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE

TO PREVENT RUNOFF FROM FLOWING AROUND THE

UPSTREAM STAKES MAY BE NECESSARY TO KEEP

ON TOP OF LOGS & SHALL BE OF SUFFICIENT

COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.

REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS,

ENGINEER.

DEFORMATION.

THE ENGINEER.




TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES

**EROSION CONTROL LOG** 

EC(9)-16

FILE: ec916	DN: TxD	OΤ	CK: KM	DW:	LS/PT		ck: LS
C TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY		IWAY
REVISIONS	2701	02	025		FM 3247		3247
	DIST		COUNTY			s	HEET NO.
	BMT		ORANG	Ε		44	4



REBAR STAKE DETAIL

# LEGEND

CL-D -EROSION CONTROL LOG DAM

TEMP. EROSION

CONTROL LOG

1' (TYP.)

COMPOST CRADLE UNDER EROSION

CONTROL LOG

-(CL-BOC) -EROSION CONTROL LOG AT BACK OF CURB

SECTION A-A

**EROSION CONTROL LOG DAM** 

CL-D

- -(CL-ROW) -EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING CL-SST
- EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING CL-SSL
- -(CL-DI - EROSION CONTROL LOG AT DROP INLET
- CL-CI -EROSION CONTROL LOG AT CURB INLET
- -EROSION CONTROL LOG AT CURB & GRATE INLET CL-GI

#### SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion controllog sediment trop may be used to filter sediment out of runoff draining from an unstabilized area.


Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Controllogs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets
- 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.



ORANGE

DISCLAMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is mode by TxDOT for any purpose whols TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

JE: 9/8/2022


DATE: 9/8/2022 FILE: T:\BMIDESGN\Projects\2701-02-025 FM 3247\ SECURE END
OF LOG TO
STAKE AS
DIRECTED

TEMP. EROSION
CONTROL LOG

FLOW

FLOW

STAKE OR USE SANDBAGS
ON DOWNHILL SIDE OF
LOG AS NEEDED TO HOLD
IN PLACE (TYPICAL)





#### EROSION CONTROL LOG AT DROP INLET




#### EROSION CONTROL LOG AT CURB INLET


#### EROSION CONTROL LOG AT CURB INLET








## EROSION CONTROL LOG AT CURB & GRADE INLET



NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



SHEET 3 OF 3



TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

EROSION CONTROL LOG

EC(9)-16

FILE: ec916	DN: TxDOT		ск: КМ	DW: LS/PT			ck: LS
© TxDOT: JULY 2016	CONT	SECT	JOB			HIGH	WAY
REVISIONS	2701	02	025	F		M 3247	
	DIST	COUNTY				SHEET NO.	
	DMT		OPANC	E		A 1	2