FHWA TEXAS DIVISION	PROJECT NO.		SHEET NO.
	F 2023 (104)		001
STATE	DISTRICT	COUNTY	
TEXAS	ABL	HOWARD	
CONTROL	SECTION	JOB	HIGHWAY NO.
0005	05	113, ETC	IH 20

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT

PROJECT NO: F 2023 (104)

IH 20
HOWARD COUNTY

FOR THE CONSTRUCTION OF: OVERLAY

CONSISTING OF: SPOT REPAIR, MILL AND FILL, FOG SEAL SHOULDERS

INDEX OF SHEETS

SEE SHEET 2

DESIGN SPEED = N/A
CURRENT A.D.T. N/A
PROJECTED A.D.T. N/A
FUNCTIONAL CLASS = INTERSTATE
EXISTING NBI# = N/A

CSJ: 0005-05-113
LIMITS FROM: 0.38 MILES EAST OF US 87 RELIEVER ROUTE
TO: .5 MILES WEST OF SH 350
ROADWAY LENGTH = 22,860.00 FT = 4.329 MI.
BRIDGE LENGTH = 0.00 FT = 0.000 MI.
PROJECT LENGTH = 22,860.00 FT = 4.329 MI.

CSJ: 0005-06-122
LIMITS FROM: .5 MILES WEST OF SH 350
TO: 0.24 MILES WEST OF FM 700
ROADWAY LENGTH = 15,321.98 FT = 2.901 MI.
BRIDGE LENGTH = 0.00 FT = 0.000 MI.
PROJECT LENGTH = 15,321.98 FT = 2.901 MI.

NET LENGTH OF PROJECT = 38,181.98 FT = 7.231MI.





END CONTROL
CSJ: 0005-05-113
STA: 772+30.00
RM: 178 -0.050

BEGIN CONTROL
CSJ: 0005-06-122
STA: 772+30.00
RM: 178 -0.050

BEGIN PROJECT
CSJ: 0005-05-113
STA: 543+70.00
RM: 173 +0.610

END PROJECT
CSJ: 0005-06-122
STA: 887+57.50
RM: 181 +0.60

EXCEPTIONS: N/A
EQUATIONS: STA 839+07.06 BK = STA 840+08.64 AH = -101.58 FT
STA 898+86.67 BK = STA 859+84.51 AH = +3,902.16 FT
RAILROAD CROSSINGS: BSRR STA 638+77.52
UPRR STA 672+60.60
UPRR STA 869+73.60

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 5, 2022).

FILE:
DATE:

FINAL PLANS

LETTING DATE: JANUARY 2023

DATE CONTRACTOR BEGAN WORK: _____

DATE WORK WAS COMPLETED: _____

DATE WORK WAS ACCEPTED: _____

FINAL CONTRACT COST: $ _____

CONTRACTOR : _____

CERTIFICATION FOR FINAL PLANS

THIS PROJECT WAS BUILT ACCORDING TO THE PLANS AND SPECIFICATIONS. THESE FINAL PLANS REFLECT THE WORK DONE AND THE QUANTITIES SHOWN THEREON AND ON THE FINAL ESTIMATE ARE FINAL QUANTITIES.

_____
AREA ENGINEER DATE

THE DISTRICT TRAFFIC SAFETY COMMITTEE HAS REVIEWED THE TRAFFIC CONTROL PLAN FOR THIS PROJECT AND IT IS IN COMPLIENCE WITH CURRENT TRAFFIC CONTROL STANDARDS

DocuSigned by: Casey L. McGee, P.E. 3/3/2022
2377E0857A804A6... DATE

 Texas Department of Transportation

RECOMMENDED FOR LETTING: 3/3/2022
DocuSigned by: LaRissa Halford
9AAFAAF9BA04413...
LARISSA HALFORD
TxDOT PROJECT MANAGER

APPROVED FOR LETTING: 3/3/2022
DocuSigned by: Michael A. Haithcock, P.E.
5757E28879884FD...
MICHAEL A. HAITHCOCK, P.E.
DIRECTOR OF T P & D

RECOMMENDED FOR LETTING: 3/3/2022
DocuSigned by: Ryan Sayles
EBF7BBC5154947E...
RYAN ROY SAYLES, P.E.
AREA ENGINEER

APPROVED FOR LETTING: 3/3/2022
DocuSigned by: Thomas G. Allbritton, P.E.
0F6F7E74C37D430...
THOMAS G. ALLBRITTON, P.E.
DISTRICT ENGINEER

INDEX OF SHEETS

GENERAL

TRAFFIC CONTROL PLAN

TRAFFIC CONTROL STANDARDS

ROADWAY

ROADWAY STANDARDS

TRAFFIC STANDARDS

RAILROAD

ENVIROMENTAL

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

T-THE STANDARD SHEETS SPECIFICALLY IDENTIFIED IN THIS INDEX OF SHEETS HAVE BEEN SELECTED BY ME UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

DocuSigned by:
Ryan Sayles ,P.E. 10/26/2022
EBE7BBC5154947E...
RYAN ROY SAYLES DATE

INDEX OF SHEETS

 Texas Department of Transportation

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		002
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:





* GEOGRAPHIC COORDINATE SYSTEM - WGS 84

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...
3/1/2022

PROJECT LAYOUT

 Texas Department of Transportation

NOT TO SCALE SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		003
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC



EXISTING TYPICAL SECTION

CSJ: 0005 05 113

STA 543+70.00 TO STA 559+79.00
STA 681+17.00 TO STA 727+30.00





PROPOSED TYPICAL SECTION

CSJ: 0005 05 113

STA 543+70.00 TO STA 559+79.00
STA 681+17.00 TO STA 727+30.00

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles

10/11/2022

TYPICAL SECTIONS

Texas Department of Transportation

NO SCALE SHEET 1 OF 4

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		004
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



EXISTING TYPICAL SECTION

CSJ: 0005 05 113

STA 562+07.00 TO STA 669+85.00
STA 727+70.00 TO STA 772+10.00





PROPOSED TYPICAL SECTION

CSJ: 0005 05 113

STA 562+07.00 TO STA 669+85.00
STA 727+70.00 TO STA 772+10.00

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by: Ryan Sayles
10/11/2022

TYPICAL SECTIONS

NO SCALE

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		005
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



EXISTING TYPICAL SECTION

CSJ: 0005 06 122

**** STA 772+30 - STA 846+89**



** EQUATIONS: STA 839+07.06 BK = STA 840+08.64 AH = -101.58 FT

STA 898+86.67 BK = STA 859+84.51 AH = +3,902.16 FT



PROPOSED TYPICAL SECTION

CSJ: 0005 06 122

**** STA 772+30 - STA 846+89**

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by: Ryan Sayles

10/11/2022

TYPICAL SECTIONS

Texas Department of Transportation

NO SCALE

SHEET 3 OF 4

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		006
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



EXISTING TYPICAL SECTION

CSJ: 0005 06 122

	STA	847+19	- STA	865+78
	STA	873+47	- STA	876+57
	STA	883+98	- STA	897+75
**	STA	898+05	- STA	869+01
	STA	875+84	- STA	886+00

** EQUATIONS: STA 839+07.06 BK = STA 840+08.64 AH = -101.58 FT

STA 898+86.67 BK = STA 859+84.51 AH = +3,902.16 FT





PROPOSED TYPICAL SECTION

CSJ: 0005 06 122

	STA	847+19	- STA	865+78
	STA	873+47	- STA	876+57
	STA	883+98	- STA	897+75
**	STA	898+05	- STA	869+01
	STA	875+84	- STA	886+00

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by: Ryan Sayles

10/11/2022

TYPICAL SECTIONS

Texas Department of Transportation

NO SCALE

SHEET 4 OF 4

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		007
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

ABILENE DISTRICT GENERAL NOTES
2014 SPECIFICATIONS

General
Contractor questions on this project are to be addressed to the following individual(s):

Ryan R. Sayles, P.E.: Ryan.Sayles@txdot.gov
LaRissa Halford: larissa.halford@txdot.gov
(Big Spring Area Office)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:
https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/

All questions submitted that generate a response will be posted through this site.
The site is organized by:
District: Abilene
Project Type: Construction
Letting Date: January 2023
CCSJ/Project Name: 0005-05-113,etc

Failure to make necessary corrections to SW3P based on SW3P inspections will be cause for withholding the monthly estimate until such corrections have been made.

Failure to make necessary corrections to traffic control items based on barricade inspections will be cause for withholding the monthly estimate until such corrections have been made.

Provide ingress/egress to the adjacent properties in areas under construction. Phased construction of driveways and streets shall be required to provide uninterrupted access to adjacent properties. Coordinate work with the property owners before beginning any construction in the vicinity of the drive.

Cut neat, straight lines with vertical faces along pavement edges or along joints between existing asphalt or concrete pavement and new pavement perpendicular or parallel to the direction of traffic by methods described in applicable bid items, or as directed. Provide clean edges or joints without jagged appearance or chunks broken out. This work is considered subsidiary to various bid items.

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

Environmental

Endangered and Protected Species
Migratory Birds

a. **Bird nesting season is typically 15Feb through 15Sep annually.**
b. The Contractor will avoid disturbing, destroying, removing, or relocating migratory birds and active nests found in trees, culverts, bridges, on the ground, or anywhere they are encountered.
c. Perform all tree trimming and other vegetation clearing activities during the non-breeding season (typically 15Sep–15Feb annually). Perform any inactive nest removal and bird exclusion methods to prevent birds from establishing nests. Phasing of work during construction may be necessary to stay in compliance.
d. When active nests are unexpectedly encountered on-site during construction, the Contractor will stop work and immediately notify the Engineer. Take measures to avoid disturbance of these birds, their occupied nest, eggs, and/or young, in accordance with the Migratory Bird Treaty Act, Texas Parks and Wildlife Code, and TxDOT policy.
e. The Engineer will notify the Contractor when work may resume.
f. The Contractor should be prepared to prevent migratory birds from building nests by utilizing nest prevention methods, such as bird-deterrent netting and bird-repelling sprays and/or gels, between 15Feb and 15Sep. The Contractor can discuss other preventative measures with the Engineer and/or District Environmental Staff.

Best Management Practices

1. Bird BMPs
   a. Not disturbing, destroying, or removing active nests, including ground nesting birds, during the nesting season;
   b. Avoiding the removal of unoccupied, inactive nests, as practicable;
   c. Preventing the establishment of active nests during the nesting season on TxDOT owned and operated facilities and structures proposed for replacement or repair;
   d. Not collecting, capturing, relocating, or transporting birds, eggs, young, or active nests without a permit.

Item 5, "Control of Work"
Use Method C for construction surveying.

All known utilities are identified in the plans, including the crossing of power lines. Use this information to identify potential issues with power poles and power lines prior to bidding. Make necessary arrangements with utility owners regarding temporary protections such as bracing power poles, and de-energizing power lines. The Department will not reimburse the cost of such

GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
000505	113,	ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		008

temporary protections to the Contractor, unless the Engineer determines that inadequate information was available at the time the project was bid. **"Call Before You Dig" "Call 811"**

Provide notification to the District Traffic Engineering Section by telephone at 325-676-6991 and by email at ABL-TrafficFix@txdot.gov when planning drilling or excavation work in areas where existing TxDOT underground utilities exist. Visual evidence of TxDOT underground utilities in the area include illumination poles, ground boxes, flashing beacons, traffic signals, etc. This notification must be provided 72 hours in advance of performing the work.

Item 6, "Control of Materials"
To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html for clarification on material categorization.

Item 7, "Legal Relations and Responsibilities"
Do not initiate activities in a project specific location (PSL), associated with a U.S. Army Corps of Engineers (USACE) permit area that has not been previously evaluated by the USACE as part of the permit review of this project. Such activities include, but are not limited to, haul roads, equipment staging areas, borrow and disposal sites. Associated defined here means materials are delivered to or from the PSL. The permit area includes all waters of the U.S. or associated wetlands affected by activities associated with this project. Special restrictions may be required for such work. Be responsible for any and all consultations with the USACE regarding activities, including project specific locations (PSLs) that have not been previously evaluated by the USACE. Provide the department with a copy of all consultation(s) or approval(s) from the USACE prior to initiating activities.

The contractor may proceed with activities in PSLs that do not affect a USACE permit area if a self determination has been made that the PSL is non-jurisdictional or proper USACE clearances have been obtained in jurisdictional areas or have been previously evaluated by the USACE as part of the permit review of this project. The contractor is solely responsible for documenting any determination(s) that their activities do not affect a USACE permit area. Maintain copies of their determination(s) for review by the department or any regulatory agency.

Document and coordinate with the USACE, if required, prior to any excavation hauled from or embankment hauled into a USACE permit area by either **(1)** or **(2)** below.

(1) Restricted Use of Materials for the Previously Evaluated Permit Areas. Document both the project specific location (PSL) and their authorization. Maintain

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

copies for review by the department or any regulatory agency. When an area within the project limits has been evaluated by the USACE as part of the permit process for this project:

a. Suitable excavation of required material in the areas shown on the plans and cross sections as specified in Item 110 is used for permanent or temporary fill (Item 132, Embankment) within a USACE permit area;
b. Suitable embankment (Item 132) from within the USACE permit area is used as fill within a USACE evaluated area; and,
c. Unsuitable excavation or excess excavation ["Waste"] (Item 110) that is disposed of at a location approved by the Engineer within a USACE evaluated area.

(2) Contractor Materials from Areas Other than Previously Evaluated Areas. Provide the department with a copy of all USACE coordination or approval(s) prior to initiating any activities for an area within the project limits that has not been evaluated by the USACE or for any off right of way locations used for the following, but not limited to, haul roads, equipment staging areas, borrow and disposal sites:

a. Item 132, Embankment, used for temporary or permanent fill within a USACE permit area; and,
b. Unsuitable excavation or excess excavation ["Waste"] (Item 110, Excavation) that is disposed of outside a USACE evaluated area.

The total area under the MBGF disturbed for this project is less than 1 acre. The disturbed area in this project, all project locations in the Contract, and the Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the ROW. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer and to the government that operates a separate storm sewer system.

The Contractor's attention is directed to the Texas Aggregate Quarry Pit Safety Act. Any pit or quarry meeting the definition of an unacceptable unsafe location as defined in the Act is subject to regulations set forth in this Act. A copy of the Texas Administrative Code, Title 43, Part, 1, Chapter 21, Subchapter M may be viewed at http://info.sos.state.tx.us/pls/pub/readtac$ext.ViewTAC.

Roadway closures during the following key dates and/or special events are prohibited:

New Year's Day, Martin Luther King, Jr., President's Day, Memorial Day, Juneteenth, Independence Day, Labor Day, Columbus Day

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		009

GENERAL NOTES

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

Hard hats are required at all times during construction when construction personnel are in TxDOT Right-of-Way.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

LIGHTING STANDARDS FOR HIGHWAY MAINTENANCE OR CONSTRUCTION VEHICLES AND SERVICE VEHICLES

VEHICLE LIGHTING SUMMARY
Vehicle Color of Flashing Lights Transportation Code
Police Vehicles Red/Blue/White/Amber 547.305 & 547.702
Fire/EMS Vehicles Red/Blue/White/Amber 547.305 & 547.702
Volunteer Fire/EMS Red/Blue/White/Amber 547.305 & 547.702
School Bus Red/White (rooftop)/Amber 547.305 & 547.701
Highway Maintenance or Construction Vehicles1 and Service Vehicles2 Amber/Blue 547.105 & TxDOT

Item 8 "Prosecution and Progress"
Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process and/or execute all contracts at the same time.

The Contractor is hereby authorized to begin work prior to the expiration of the number of calendar days provided in the Special Provision to Item 8, Article 8.1. Notify the Engineer in writing of the date to begin work. Time charges will commence when work begins or on the expiration of the number of calendar days provided, whichever occurs first.

Maintain and submit a project schedule monthly. Submit to the Engineer the updated project schedule no later than the 25th calendar day of the following month.

Coordinate and update the work schedule with the project inspector daily. Give a minimum of 24 hours of notice to project inspector if work requiring inspection or testing is to be performed. Failure to do so may cause that work to be delayed or postponed if TxDOT personnel are not available. Work performed without suitable inspection, as determined by the Engineer, may be ordered removed and replaced at Contractor's expense.

Prepare the progress schedule as a Critical Path Method (CPM).

Item 9, "Measurement and Payment"

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

The progress payment period shall end on the 25th of each month, unless directed by the Area Office Engineer. Material on Hand (MOH) is due two business days before estimate cut off.

Item 354, "Planning and Texturing Pavement"
Grade referencing shall be required as specified in 354.3.1. Milling operations shall not advance faster than 30 feet per minute (fpm) or be based as a function of the RPMs of the milling drum such that the full uniform texture pattern is achieved with the speed of the milling operation in fpm limited to 30% of the drums RPMs. Any proposal to advance faster than this speed shall be discussed with the Engineer and proven on a test strip of the Engineer's choosing, and shall result in no repeated inconsistencies in texture during production milling. If inconsistencies are present, the machine speed will be reduced as directed by the Engineer.

Stockpile millings in Howard County at IH 20 and FM 700 and remove the unused material from the project site upon completion of the paving work.

Upstream and downstream transition slopes should not be steeper than 10:1 slope.

Item 502, "Barricades, Signs and Traffic Handling"
Mobile traffic control in accordance with TPC 3 series will be required for placement of short duration, short term, intermediate term, and long-term traffic control.

Provide the Engineer with written notification seven (7) days in advance of major traffic changes. A major traffic change is defined as the temporary (greater than one day) or permanent relocation of traffic lanes typically in an urban setting. The notice will, at a minimum, include the expected date, time and scope of the traffic change. The Department will utilize the information provided to inform the traveling public of the changes. Failure to provide advance notice, or to provide accurate information, will result in delaying the work until such time that the public has been notified.

Additional signs, barricades and traffic handling may be necessary to complete the work shown herein and will be provided by the contractor as required and will be considered subsidiary to this item.

Provide separate attenuators for each work area within a common lane closure as approved or directed by the Engineer.

In sections where traffic is restricted to one lane, two-way traffic, flaggers stationed at each end of that section will control operations with two-way communication devices.

All safety appurtenances such as signs, delineators, object markers and route markers will be in place prior to opening each phase of the construction to traffic, unless otherwise directed.

GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		010

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The Contractor's person responsible for TCP compliance must be available by local telephone and have a response time within 45 minutes.

Work will not be allowed on both sides of the roadbed at the same time.

Equip all work vehicles within 30 feet of the traveled way with a functioning amber strobe light or rotating beacon visible from all directions.
Repair barricades within the timeline shown on the barricade inspection report. Failure to comply will cease all work until barricades are repaired to the satisfaction of the Department.

Replace all damaged traffic control devices immediately. Remove any damaged traffic control devices from the project within 24 hours.

Conflicting guide signs shall be covered as approved by the Engineer.

Pilot car is subsidiary to item 502.

Reduced regulatory speed limit signs should only be posted in the vicinity of ongoing work activity as shown on BC (3)-19 and not throughout the entire project. Removing, relocating or covering speed limit signs shall be considered subsidiary to item 502.

Item 504, "Field Office for Laboratory"

Field Laboratory:
Furnish a "Type D" structure for the asphalt mix control laboratory for the Engineer's exclusive use. In addition to the requirements of Item 504, furniture and equipment to be furnished by the Contractor shall include*:*

- eye wash station
- first-aid kit
- two fire extinguishers
- Provide internet connectivity for use by TxDOT lab testing personnel at all laboratory structures on this project.

Item 585, "Ride Quality for Pavement Surfaces"

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

The Engineer reserves the right to prohibit corrective work and assess the penalty for each occurrence of localized roughness per Article 585.3.4.2.3.2.

Use pay adjustment schedule three (3) for Ride Quality bonus/penalty calculation.

Item 658, "Delineator and Object Marker Assemblies"
Delineators and object marker assemblies will use winged channel posts. The winged channel posts will be 1.12 lb/ft and 6.5 ft in length.

All MBGF delineation shall be GF2 mounted on posts.

Use a minimum 2-inch long lag screws with washers to attach flexible GF2 barrier reflectors to wooden post. For steel posts, use an approved adhesive, or other method approved by Engineer.

Concrete Barrier Reflectors shall be equivalent to Shure-tite CTB "Cup Mount" Delineator (8"). Attach delineators to concrete rail with concrete anchors as approved by the Engineer.

Item 662, "Work Zone Pavement Markings"
Place work zone pavement markings (flexible tabs) prior to the seal coat operation.

Dispose of tabs and paper in an approved trash receptacle. (Reference Standard **SW3P**, waste material)

Item 666, "Retro reflectorized Pavement Markings"
Provide a complete system of thermoplastic pavement markings at locations indicated on the plans and as directed by the engineer. The plans are intended to show typical conditions, which can be extended to similar conditions throughout this project as approved or directed.

Establish a true and correct alignment with a method approved by the Engineer. This work will be considered subsidiary.

Contractor is responsible for re-establishing location and alignment for new pavement markings matching pavement marking alignment prior to construction activities. This work will be considered subsidiary.

Item 672, "Raised Pavement Markers"
Provide a complete system of raised pavement markers at locations indicated on the plans and as directed by the engineer. The plans are intended to show typical conditions, which can be extended to similar conditions throughout this project as approved or directed.

Bituminous adhesive shall be used on this project.

GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
000505	113,	ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		011

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

Item 677, "Eliminating Existing Pavement Markings and Markers"
Remove the existing raised pavement markings (RPMs) and profile pavement markings as the work progresses, or as directed by the Engineer. Removal methods shall be approved by the Engineer. Properly dispose of materials removed. Removal of existing profile pavement markings will be paid for directly. Removal of RPMs will not be paid for directly but will be subsidiary to the pertinent bid items.

Item 3077, "Super pave Mixtures"
The Engineer reserves the right to test all sources even if the source is listed in the Bituminous Source Rated Quality Catalog.

Provide the testing lab samples to calibrate the ignition oven no later than five **(5)** working days prior to mix design verification.

Paving operations will not be allowed to begin until TxDOT has tested and obtained passing Hamburg results on the trial batch.
A maximum of 0.50% anti-stripping agent will be allowed for each specified mix type.

Dilution of tack coat is not allowed.

Do not exceed a laydown width of 16' per pass.

Substitute Binders will not be allowed unless RAP or RAS is used in the production of the mixture.
RAS will not be allowed in surface mixes.

A warm mix additive will be required for hot mix hauls over 50 miles.

Unless otherwise directed by the engineer, a warm mix additive will be required when paving during November 1st through March 15th.

The maximum allowable dust / asphalt ratio that will be allowed is 0.6 to 1.2.

The use of a tapered longitudinal joint will be required for pavement thicker than 2 inches.

Use a self-propelled, wheel-mounted material transfer vehicle (MTV) capable of receiving hot mix from the haul trucks separate from the paver on this project.

Minimum requirements for the MTV are a storage capacity of approximately 25 tons, a pivoting discharge conveyor, and a means of completely remixing the ACP prior to placement.

Mill in 12:1 transverse joints at the ends of each land.

Provide PG 64-22 tack coat at a rate of 0.10 gal/sy.

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

The Contractor will be required to tack 100% of the surfaces with uniform coverage prior to the subsequent lift. The type and grade of tack will be approved by the Engineer prior to use.

Fog seal shoulders using CSS-1H at a rate of .15 gal/sy.

Tack all vertical joints unless otherwise directed.

Cement and kiln dust will not be allowed to be used as mineral fillers.

Item 3080, "Stone Matrix Asphalt"
A minimum of 6.0% asphalt content is required for all SMA mixtures.

Provide additional SGC molds as necessary to allow for proper cooling and testing of laboratory densities.

Furnish aggregate for final surfaces with a surface aggregate classification of "**A**".

The Engineer reserves the right to test all sources even if the source is listed in the Bituminous Source Rated Quality Catalog.

Provide the testing lab samples to calibrate the ignition oven no later than five **(5)** working days prior to mix design verification.

Do not exceed a laydown width of 16' per pass.

RAP will not be allowed for this project.

The use of a tapered longitudinal joint will be required for pavement thicker than 2 inches.

Use a self-propelled, wheel-mounted material transfer vehicle (MTV) capable of receiving hot mix from the haul trucks separate from the paver on this project. Minimum requirements for the MTV are a storage capacity of approximately 25 tons, a pivoting discharge conveyor, and a means of completely remixing the ACP prior to placement.

Provide PG 64-22 tack coat at a rate of 0.10 gal/sy.

The Contractor will be required to tack 100% of the surfaces with uniform coverage prior to the subsequent lift. The type and grade of tack will be approved by the Engineer prior to use.

Tack all vertical joints unless otherwise directed.

Cement and kiln dust will not be allowed to be used as mineral fillers.

Final surface of driveway shall not be placed prior to adjoining surface.

GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
000505	113, ETC		IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		012

Project Number: See Title Sheet
Control: 0005-05-113,ETC
County: HOWARD
Highway: IH 20

Item 6185, "Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)"
Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA) will not be considered a major item of work on this project.

TMA,s will only be paid while workers are present or to protect a blunt object

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project. The Contractor must get approval from the Engineer for any changes in the number of TMA as shown in the plans.

If a TMA is used for both mobile and stationary traffic control on the same day, it will be paid for as mobile for that day.

Basis of Estimate for Stationary TMAs				
		TMA (Stationary)		
Phase	Standard	Required	Additional	TOTAL

Basis of Estimate for Mobile TMAs				
		TMA (Mobile)		
Phase	Standard	Required	Additional	TOTAL
I, III	TCP 2-6-18	1		1
III, IV	TCP 3-2-18	2		2
III, IV	TCP 3-3-14	2		2

GENERAL NOTES

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		013

Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0005-05-113 **DISTRICT** Abilene **COUNTY** Howard
HIGHWAY IH 20

			CONTROL SECTION JOB		**0005-05-113**		**0005-06-122**		TOTAL EST.	TOTAL FINAL
			PROJECT ID		**A00065418**		**A00065419**			
			COUNTY		**Howard**		**Howard**			
			HIGHWAY		**IH 20**		**IH 20**			
ALT	**BID CODE**	**DESCRIPTION**	**UNIT**	EST.	FINAL	EST.	FINAL			
	315-6004	FOG SEAL (CSS-1H)	GAL	10,267.000		7,121.000		17,388.000		
	354-6045	PLANE ASPH CONC PAV (2")	SY	117,269.000		80,428.000		197,697.000		
	500-6001	MOBILIZATION	LS	1.000				1.000		
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4.000				4.000		
	658-6010	INSTL DEL ASSM (D-SW)SZ 2(WC)GND	EA	95.000		163.000		258.000		
	658-6011	INSTL DEL ASSM (D-SW)SZ 2(WC)GND(BI)	EA	12.000		24.000		36.000		
	658-6024	INSTL DEL ASSM (D-SY)SZ 2(WC)GND	EA	36.000		33.000		69.000		
	658-6040	INSTL DEL ASSM (D-DW)SZ 2(WC)GND	EA	42.000		27.000		69.000		
	658-6044	INSTL DEL ASSM (D-DY)SZ 2(WC)GND	EA	30.000		29.000		59.000		
	658-6061	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2	EA	146.000		80.000		226.000		
	658-6064	INSTL DEL ASSM (D-SY)SZ 1(BRF)GF2	EA	33.000		44.000		77.000		
	658-6083	INSTL DEL ASSM (D-SW)SZ 1(WFLX)SRF	EA	29.000		40.000		69.000		
	658-6088	INSTL DEL ASSM (D-SY)SZ 1(YFLX)SRF	EA	32.000		40.000		72.000		
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	31,349.000		21,806.000		53,155.000		
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	6,065.000		3,407.000		9,472.000		
	666-6042	REFL PAV MRK TY I (W)12"(SLD)(100MIL)	LF	1,359.000		609.000		1,968.000		
	666-6300	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	LF	11,542.000		7,647.000		19,189.000		
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	43,989.000		29,149.000		73,138.000		
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	45,702.000		30,516.000		76,218.000		
	668-6084	PREFAB PAV MRK TY C (W) (NUMBER)	EA	21.000		16.000		37.000		
	672-6007	REFL PAV MRKR TY I-C	EA	578.000		383.000		961.000		
	672-6010	REFL PAV MRKR TY II-C-R	EA	157.000		86.000		243.000		
	3080-6007	STONE-MTRX-ASPH SMA-D SAC-A PG76-22	TON	13,486.000		9,250.000		22,736.000		
	3080-6029	TACK COAT	GAL	11,727.000		8,043.000		19,770.000		
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1.000		1.000		2.000		
	6185-6005	TMA (MOBILE OPERATION)	DAY	49.000		49.000		98.000		
	12	RAILROAD FLAGGING: RAILROAD FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000		
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000		
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000		

ASPHALT SURFACE AREA SUMMARY

PLAN LAYOUT SHEET NUMBER	315 FOG SEAL (CSS-1H)	354 6045 PLANE ASPH CONC PAV (2")	3080 STONE-MTRX-ASPH SMA-D SAC-A PG76-22	3080 TACKCOAT
	SY	SY	SY	SY
0005-05-113				
SHEET 1	2359	4961	4961	4961
SHEET 2	3111	5334	5334	5334
SHEET 3	3111	5334	5334	5334
SHEET 4	3111	5312	5312	5312
SHEET 5	3111	5308	5308	5308
SHEET 6	3111	5325	5325	5325
SHEET 7	3111	5334	5334	5334
SHEET 8	3111	5334	5334	5334
SHEET 9	3111	5334	5334	5334
SHEET 10	3111	5334	5334	5334
SHEET 11	3111	5334	5334	5334
SHEET 12	3111	5334	5334	5334
SHEET 13	3111	4085	4085	4085
SHEET 14	3111	1273	1273	1273
SHEET 15	3111	5315	5315	5315
SHEET 16	3111	5315	5315	5315
SHEET 17	3111	5315	5315	5315
SHEET 18	3111	5327	5327	5327
SHEET 19	3111	5334	5334	5334
SHEET 20	3111	5334	5334	5334
SHEET 21	3111	5333	5333	5333
SHEET 22	3111	5332	5332	5332
SHEET 23	3111	5332	5332	5332
TOTAL	**68442**	**117269**	**117269**	**117269**
0005-06-122				
SHEET 24	3111	5334	5334	5334
SHEET 25	3111	5334	5334	5334
SHEET 26	3111	5333	5333	5333
SHEET 27	3111	5319	5319	5319
SHEET 28	3111	5319	5319	5319
SHEET 29	3111	5319	5319	5319
SHEET 30	3111	5325	5325	5325
SHEET 31	3111	5334	5334	5334
SHEET 32	3111	5316	5316	5316
SHEET 33	3111	5329	5329	5329
SHEET 34	3111	5320	5320	5320
SHEET 35	3111	5317	5317	5317
SHEET 36	3111	5334	5334	5334
SHEET 37	3111	5257	5257	5257
SHEET 38	3111	5243	5243	5243
SHEET 39	802	695	695	695
TOTAL	47467	**80428**	**80428**	**80428**
PROJECT TOTAL	**115909**	**197697**	**197697**	**197697**

BASIS OF ESTIMATE

ITEM NO.	DESCRIPTION	RATE	AREA (SY)	TOTAL QUANTITY	UNIT
315-6004	FOG SEAL (CSS-1H)	.15 GAL / SY	115909	17387	GAL
3080-6007	STONE-MTRX-ASPH SMA-D SAC-A PG76-22	230 LB / SY	197697	22736	TONS
3080-6029	TACKCOAT	.1 GAL / SY	197697	19770	GAL

QUANTITY SUMMARY

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		016
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

SUMMARY OF TRAFFFIC CONTROL QUANTITIES			
PLAN LAYOUT	662 6109	6001 6002	6182 6005
SHEET NUMBER	WK ZN PAV MRK SHT TERM (TAB) TY W	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (MOBILE OPERATION)
	EA	EA	DAY
0005-05-113			
SHEET 1	1363		
SHEET 2	1363		
SHEET 3	1363		
SHEET 4	1363		
SHEET 5	1363		
SHEET 6	1363		
SHEET 7	1363		
SHEET 8	1363		
SHEET 9	1363		
SHEET 10	1363		
SHEET 11	1363		
SHEET 12	1363		
SHEET 13	1363		
SHEET 14	1363		
SHEET 15	1363		
SHEET 16	1363		
SHEET 17	1363		
SHEET 18	1363		
SHEET 19	1363		
SHEET 20	1363		
SHEET 21	1363		
SHEET 22	1363		
SHEET 23	1363		
TOTAL	**31349**	**1**	**49**
0005-06-122			
SHEET 24	1363		
SHEET 25	1363		
SHEET 26	1363		
SHEET 27	1363		
SHEET 28	1363		
SHEET 29	1363		
SHEET 30	1363		
SHEET 31	1363		
SHEET 32	1363		
SHEET 33	1363		
SHEET 34	1363		
SHEET 35	1363		
SHEET 36	1363		
SHEET 37	1363		
SHEET 38	1363		
SHEET 39	1361		
TOTAL	**21806**	**1**	**49**
PROJECT TOTAL	**53155**	**2**	**98**

FILE:
DATE:

QUANTITY SUMMARY

Texas Department of Transportation

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		017
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

SUMMARY OF ROADWAY PAVEMENT MARKINGS

PLAN LAYOUT SHEET NUMBER	666 6300	666 6303	666 6315	666 6036	666 6042	668 6084	672 6007	672 6010
	RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)	RE PM W/RET REQ TY 1 (W) 4" (SLD) (100MIL)	RE PM W/RET REQTY 1 (Y) 4" (SLD) (100MIL)	REFL PAV MRK TY 1 (W)8" (SLD) (100MIL)	REFL PAV MRK TY I (W) (12")(SLD) (100 MIL)	PREFAB PAV MRK TY C (W) (NUMBER)	REFL PAV MRK TY I-C	REFL PAV MRK TY II-C-R
	LF	LF	LF	LF	LF	EA	EA	EA
000-05-113								
SHEET 1	465	1263	1860	962	481	3	24	24
SHEET 2	500	2000	2000				25	
SHEET 3	500	1802	2000	509			25	13
SHEET 4	500	1628	1998	489	141	3	25	13
SHEET 5	500	1864	1998	218	110	3	25	6
SHEET 6	500	1832	1999	668			25	17
SHEET 7	500	2000	2000				25	
SHEET 8	500	2000	2000				25	
SHEET 9	500	2000	2000				25	
SHEET 10	500	2000	2000				25	
SHEET 11	500	2000	2000				25	
SHEET 12	500	2000	1998				25	
SHEET 13	500	2000	2000				25	
SHEET 14	500	2000	1998				25	
SHEET 15	578	2182	1998	362	181	3	29	9
SHEET 16	499	1994	1998	406			25	11
SHEET 17	500	2000	2000				25	
SHEET 18	500	1767	2000	409	40	3	25	11
SHEET 19	500	1708	2000	493	101		25	13
SHEET 20	500	2217	1855	841	176	3	25	22
SHEET 21	500	2000	2000				25	
SHEET 22	500	2000	2000				25	
SHEET 23	500	1732	2000	708	129	3	25	18
TOTAL	**11542**	**43989**	**45702**	**6065**	**1359**	**21**	**578**	**157**
0005-06-122								
SHEET 24	500	2000	2000				25	
SHEET 25	517	2001	2000	917	155	3	26	23
SHEET 26	500	2000	2000				25	
SHEET 27	500	2000	2000				25	
SHEET 28	500	2000	2000	197	100	3	25	5
SHEET 29	500	2000	2000				25	
SHEET 30	500	2000	2000				25	
SHEET 31	500	2000	2000				25	
SHEET 32	500	2000	2000				25	
SHEET 33	500	2000	2000				25	
SHEET 34	500	2000	2000				25	
SHEET 35	501	1824	2000	359	82	3	25	9
SHEET 36	500	1241	2000	1174	148	3	25	30
SHEET 37	500	2000	2000				25	
SHEET 38	500	1567	2000	760	124	4	25	19
SHEET 39	129	516	516				7	
TOTAL	**7647**	**29149**	**30516**	**3407**	**609**	**16**	**383**	**86**
PROJECT TOTAL	**19189**	**73138**	**76218**	**9472**	**1968**	**37**	**961**	**243**

QUANTITY SUMMARY

Texas Department of Transportation

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		018
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

SUMMARY OF ROADWAY PAVEMENT MARKINGS
(DELINEATORS)

RAMP #	658 6010	658 6024	658 6040	658 6044
	INSTL DEL ASSM (D-SW)SZ 2 (WC) GND	INSTL DEL ASSM (D-SY)SZ 2 (WC) GND	INSTL DEL ASSM (D-DW)SZ 2 (WC) GND	INSTL DEL ASSM (D-DY)SZ 2 (WC) GND
	EA	EA	EA	EA
000-05-113				
1	3		3	
2	6	3	3	3
3			3	3
4	3	3	3	3
5	3	3	3	3
6	3	6	3	3
7	3	3	4	
8	3	3	3	3
9	3	3	3	3
10	3	3	3	3
11	4	3	5	3
12	3	3	3	3
13	3	3	3	
TOTAL	40	36	42	30
0005-06-122				
14	3	3	3	3
15	3	5		5
16	3	7	3	
17	3	3	3	3
18			3	3
19	3	3	3	3
20	3	3	3	3
21	3	3	3	3
22	3	3	3	3
23	3	3	3	3
TOTAL	27	33	27	29
PROJECT TOTAL		69	69	59

CURVE	STA (PI)	658 6010	658 6011
		INSTL DEL ASSM (D-SW)SZ 2 (WC) GND	INSTL DEL ASSM (D-SW)SZ 2 (WC) GND (BI)
		EA	EA
CSJ: 0005-05-113			
1	586+15	22	6
2	699+45	33	6
TOTAL		95	12
CSJ: 0005-06-122			
3	818+77	44	6
4	858+75	22	6
5	887+78	35	6
6	859+90	35	6
TOTAL		163	24
PROJECT TOTAL		258	36

QUANTITY SUMMARY

Texas Department of Transportation

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		019
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

SUMMARY OF ROADWAY PAVEMENT MARKINGS (DELINEATORS)

MBGF	658 6061 INSTL DEL ASSM (D-SW)SZ 1 (BRF)GF2	658 6064 INSTL DEL ASSM (D-SY)SZ 1 (BRF)GF2
	EA	EA
000-05-113		
1		3
2	3	
3	3	
4	3	
5	3	
6		3
7	8	
8	3	
9	9	
10	3	
11		3
12		3
13	24	
14	10	
15		3
16	13	
17		3
18	17	
19	9	
20	7	
21		3
22	4	
23		3
24	4	
25	3	
26	3	
27		3
28	6	
29		3
30	3	
31	3	
32		3
33	5	
TOTAL	**146**	**33**

MBGF	658 6061 INSTL DEL ASSM (D-SW)SZ 1 (BRF)GF2	658 6064 INSTL DEL ASSM (D-SY)SZ 1 (BRF)GF2
	EA	EA
000-06-122		
34	5	
35		3
36	3	
37		3
38	3	
39	4	
40	17	
41	3	
42		3
43		3
44		3
45	4	
46	5	
47		3
48		3
49		3
50		3
51		3
52	6	
53	14	
54		3
55	3	
56		3
57	7	
58		5
59	3	
60		3
61	3	
TOTAL	**80**	**44**
PROJECT TOTAL	**226**	**77**

BRIDGE RAIL	658 6083 INSTL DEL ASSM (D-SW)SZ 1 (WFLX)SRF	658 6088 INSTL DEL ASSM (D-SY)SZ 1 (YFLX)SRF
0005-05-113	EA	EA
1	3	
2		3
3		3
4	3	
5	3	
6		3
7		3
8		
9	10	
10		10
11		10
12	10	
TOTAL	**29**	**32**
0005-06-122		
13	6	
14		6
15		5
16	5	
17	6	
18		6
19		6
20	6	
21	5	
22		5
23		6
24	6	
25	3	
26		3
27		3
28	3	
TOTAL	40	40
PROJECT TOTAL	**69**	**72**

QUANTITY SUMMARY

 Texas Department of Transportation

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		020
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

SUGGESTED SEQUENCE OF WORK

PHASE I

1) SET TCP AND BARRICADES IN WESTBOUND LANE PASSING LANE
2) MILL 2" DEEP INSIDE WESTBOUND PASSING LANE, LEAVING CENTER STRIPE
3) TACK
4) OVERLAY 2" SMA
5) LANE CLOSURES SHALL REMAIN OPEN ON WEEKENDS
6) MOVE DOWN THE ROAD TO NEXT SECTION UNTIL END OF PROJECT

PHASE II

1) SETUP UP TCP AND BARRICADES IN WESTBOUND DRIVING LANE
2) MILL 2" DEEP INCLUDING CENTER STRIPE
3) TACK
4) OVERLAY 2" SMA AND PLACE TABS
5) LANE CLOSURES SHALL REMAIN OPEN ON WEEKENDS
6) MOVE TO NEXT SECTION

PHASE III

1) SET TCP AND BARRICADES IN EASTBOUND LANE
2) REPEAT ABOVE STEPS FOR EASTBOUND LANES

PHASE IV

1) FOG SEAL SHOULDERS
2) STRIPING OF LANES / GORES

PHASE V

1) REMOVE / REPLACE DELINEATORS
2) CLEAN UP
3) REMOVE TRAFFIC CONTROL

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

Docu Signed by:
Ryan Sayles
10/11/2022

NOTE:

1) NO LANE CLOSURES LONGER THAN 3 CONSECUTIVE DAYS AT A TIME.

2) NO LANE CLOSURES ON WEEKENDS.

SUGGESTED SEQUENCE OF WORK

Texas Department of Transportation

SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		021
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

DATE:
FILE:

DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS

Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet



Edge Condition I
S = (3:1) (or flatter)





Edge Condition II
S = ((2.99):1) to (1:1)





Edge Condition III
S is steeper than (1:1)





FACTORS CONSIDERED IN THE GUIDELINES:

1. The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height is the depth of the drop-off "D".

2. Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.

3. In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.

4. The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.

5. If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

Zone	Treatment Types Guidelines:
①	No treatment.
②	CW 8-11 "Uneven Lanes" signs.
③	CW 8-9a "Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.
④	CW 8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge fill may be provided to change the edge slope to that of the preferable Edge Condition I.
⑤	Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone- 4 may be used after consideration of other applicable factors.

Edge Condition Notes:

1. Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.

2. Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exeeds 24 inches, the possibility for rollover is greater in most vehicles.

3. Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.

4. Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 (▨)



1 E = ADT x T
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.

2 Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.

3 An approved end treatment should be provided for any positive barrier end located within a lateral offset of 20 feet from the edge of the travel lane.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.

Engineer's Seal

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

Date 3/1/2022

Texas Department of Transportation
Traffic Operations Division

TREATMENT FOR VARIOUS EDGE CONDITIONS

REVISIONS	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
03-01	CONT	SECT	JOB	HIGHWAY
08-01 correct typos	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		022

DATE:
FILE:

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).

2. The development and design of the Traffic Control Plan (TCP)is the responsibility of the Engineer.

3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.

4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.

5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.

6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.

7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.

8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.

9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.

10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.

11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.

12. The Engineer has the final decision on the location of all traffic control devices.

13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.

2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.

2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC(1)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-03 7-13 9-07 8-14 5-10 5-21	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		023

TYPICAL LOCATION OF CROSSROAD SIGNS



May be mounted on back of "ROAD WORK AHEAD"(CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK"(G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES"(G20-1aT)sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING[1,5,6]

SIZE

Sign Number or Series	Conventional Road	Expressway/ Freeway
CW20[4] CW21 CW22 CW23 CW25	48" x 48"	48" x 48"
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"

SPACING

Posted Speed	Sign △ Spacing "X"
MPH	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500[2]
60	600[2]
65	700[2]
70	800[2]
75	900[2]
80	1000[2]
*	*[3]

* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

△ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD"(CW20-1D)signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS

NOTES

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES"(G20-5T)sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

□ The "BEGIN WORK ZONE"(G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.

** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.

◊ Area for placement of "ROAD WORK AHEAD" (CW20-1D)sign and other signs or devices as called for on the Traffic Control Plan.

◊◊ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
⊢⊣	Type 3 Barricade
○ ○ ○	Channelizing Devices
▬	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		024

DATE:
FILE:

DATE:
FILE:

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project.

Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

a) rough road or damaged pavement surface
b) substantial alteration of roadway geometrics (diversions)
c) construction detours
d) grade
e) width
f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered.
(See Removing or Covering on BC(4)).

GENERAL NOTES

1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
4. Frequency of work zone speed limit signs should be:
   40 mph and greater 0.2 to 2 miles
   35 mph and less 0.2 to 1 mile
5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
6. Fabrication, erection and maintenance of the"ADVANCE SPEED LIMIT"(CW3-5)sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
8. Techniques that may help reduce traffic speeds include but are not limited to:
   A. Law enforcement.
   B. Flagger stationed next to sign.
   C. Portable changeable message sign (PCMS).
   D. Low-power (drone) radar transmitter.
   E. Speed monitor trailers or signs.
9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		025

DATE:
FILE:

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS





Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectorized when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B_{FL} OR C_{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
   a. Long-term stationary - work that occupies a location more than 3 days.
   b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
   c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
   d. Short, duration - work that occupies a location up to 1 hour.
   e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		026

DATE:
FILE:





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



PERFORATED SQUARE METAL TUBING

GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support.
The maximum sign square footage shall adhere to the manufacturer's recommendation.
Two post installations can be used for larger signs.







SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

* See BC(4) for definition of "Work Duration."

** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.

☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

Texas Department of Transportation | Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		027

DATE:
FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
11. Do not use the word "Danger" in message.
12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
13. Do not display messages that scroll horizontally or vertically across the face of the sign.
14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
16. Each line of text should be centered on the message board rather than left or right justified.
17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD
Alternate	ALT
Avenue	AVE
Best Route	BEST RTE
Boulevard	BLVD
Bridge	BRDG
Cannot	CANT
Center	CTR
Construction Ahead	CONST AHD
CROSSING	XING
Detour Route	DETOUR RTE
Do Not	DONT
East	E
Eastbound	(route) E
Emergency	EMER
Emergency Vehicle	EMER VEH
Entrance, Enter	ENT
Express Lane	EXP LN
Expressway	EXPWY
XXXX Feet	XXXX FT
Fog Ahead	FOG AHD
Freeway	FRWY, FWY
Freeway Blocked	FWY BLKD
Friday	FRI
Hazardous Driving	HAZ DRIVING
Hazardous Material	HAZMAT
High-Occupancy	HOV
Vehicle Highway	HWY
Hour(s)	HR, HRS
Information	INFO
It Is	ITS
Junction	JCT
Left	LFT
Left Lane	LFT LN
Lane Closed	LN CLOSED
Lower Level	LWR LEVEL
Maintenance	MAINT
Major	MAJ
Miles	MI
Miles Per Hour	MPH
Minor	MNR
Monday	MON
Normal	NORM
North	N
Northbound	(route) N
Parking	PKING
Road	RD
Right Lane	RT LN
Saturday	SAT
Service Road	SERV RD
Shoulder	SHLDR
Slippery	SLIP
South	S
Southbound	(route) S
Speed	SPD
Street	ST
Sunday	SUN
Telephone	PHONE
Temporary	TEMP
Thursday	THURS
To Downtown	TO DWNTN
Traffic	TRAF
Travelers	TRVLRS
Tuesday	TUES
Time Minutes	TIME MIN
Upper Level	UPR LEVEL
Vehicles (s)	VEH, VEHS
Warning	WARN
Wednesday	WED
Weight Limit	WT LIMIT
West	W
Westbound	(route) W
Wet Pavement	WET PVMT
Will Not	WONT

Roadway designation * IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

- FREEWAY CLOSED X MILE
- FRONTAGE ROAD CLOSED
- ROAD CLOSED AT SH XXX
- SHOULDER CLOSED XXX FT
- ROAD CLSD AT FM XXXX
- RIGHT LN CLOSED XXX FT
- RIGHT X LANES CLOSED
- RIGHT X LANES OPEN
- CENTER LANE CLOSED
- DAYTIME LANE CLOSURES
- NIGHT LANE CLOSURES
- I-XX SOUTH EXIT CLOSED
- VARIOUS LANES CLOSED
- EXIT XXX CLOSED X MILE
- EXIT CLOSED
- RIGHT LN TO BE CLOSED
- MALL DRIVEWAY CLOSED
- X LANES CLOSED TUE - FRI
- XXXXXXXX BLVD CLOSED

Other Condition List

- ROADWORK XXX FT
- ROAD REPAIRS XXXX FT
- FLAGGER XXXX FT
- LANE NARROWS XXXX FT
- RIGHT LN NARROWS XXXX FT
- TWO-WAY TRAFFIC XX MILE
- MERGING TRAFFIC XXXX FT
- CONST TRAFFIC XXX FT
- LOOSE GRAVEL XXXX FT
- UNEVEN LANES XXXX FT
- DETOUR X MILE
- ROUGH ROAD XXXX FT
- ROADWORK PAST SH XXXX
- ROADWORK NEXT FRI-SUN
- BUMP XXXX FT
- US XXX EXIT X MILES
- TRAFFIC SIGNAL XXXX FT
- LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

- MERGE RIGHT
- FORM X LINES RIGHT
- DETOUR NEXT X EXITS
- USE XXXXX RD EXIT
- USE EXIT XXX
- USE EXIT I-XX NORTH
- STAY ON US XXX SOUTH
- USE I-XX E TO I-XX N
- TRUCKS USE US XXX N
- WATCH FOR TRUCKS
- WATCH FOR TRUCKS
- EXPECT DELAYS
- EXPECT DELAYS
- PREPARE TO STOP
- REDUCE SPEED XXX FT
- END SHOULDER USE
- USE OTHER ROUTES
- WATCH FOR WORKERS
- STAY IN LANE *

Location List

- AT FM XXXX
- BEFORE RAILROAD CROSSING
- NEXT X MILES
- PAST US XXX EXIT
- XXXXXXX TO XXXXXXX
- US XXX TO FM XXXX

Warning List

- SPEED LIMIT XX MPH
- MAXIMUM SPEED XX MPH
- MINIMUM SPEED XX MPH
- ADVISORY SPEED XX MPH
- RIGHT LANE EXIT
- USE CAUTION
- DRIVE SAFELY
- DRIVE WITH CARE

** Advance Notice List

- TUE-FRI XX AM- X PM
- APR XX-XX X PM-X AM
- BEGINS MONDAY
- BEGINS MAY XX
- MAY X-X XX PM - XX AM
- NEXT FRI-SUN
- XX AM TO XX PM
- NEXT TUE AUG XX
- TONIGHT XX PM- XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

1. Only 1 or 2 phases are to be used on a PCMS.
2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
2. Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
4. Highway names and numbers replaced as appropriate.
5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
6. AHEAD may be used instead of distances if necessary.
7. FT and MI, MILE and MILES interchanged as appropriate.
8. AT, BEFORE and PAST interchanged as needed.
9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		028

DATE:
FILE:

1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional)while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
7. Maximum spacing of Barrier Reflectors is forty (40) feet.
8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
10. Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
11. Single slope barriers shall be delineated as shown on the above detail.



Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square.Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

1. Warning lights shall meet the requirements of the TMUTCD.
2. Warning lights shall NOT be installed on barricades.
3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
3. The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
4. The Flashing Arrow Board should be able to display the following symbols:



5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
6. The straight line caution display is NOT ALLOWED.
7. The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
8. Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
9. The sequential arrow display is NOT ALLOWED.
10. The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION

Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

TRUCK-MOUNTED ATTENUATORS

1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
2. Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
3. Refer to the CWZTCD for a list of approved TMAs.
4. TMAs are required on freeways unless otherwise noted in the plans.
5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation — Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC(7)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		029

DATE:
FILE:

GENERAL NOTES

1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:

1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
9. Drum body shall have a maximum unballasted weight of 11 lbs.
10. Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
6. Ballast shall not be placed on top of drums.
7. Adhesives may be used to secure base of drums to pavement.







DETECTABLE PEDESTRIAN BARRICADES

1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
5. Warning lights shall not be attached to detectable pedestrian barricades.
6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24"
Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
4-03 8-14	DIST	COUNTY		SHEET NO.
9-07 5-21	ABL	HOWARD		030
7-13				

DATE:
FILE:



FIXED
(Rigid or self-righting)

DRIVEABLE



(Rigid or self-righting)

PORTABLE

1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)



1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
2. The OTLD may be used in combination with 42" cones or VPs.
3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
4. To be effective, the chevron should be visible for at least 500 feet.
5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
2. LCDs may be used instead of a line of cones or drums.
3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

1. Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	Minimum Desirable Taper Lengths ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices On a Taper	On a Tangent
30	$L = \frac{WS^2}{60}$	150′	165′	180′	30′	60′
35		205′	225′	245′	35′	70′
40		265′	295′	320′	40′	80′
45	L = WS	450′	495′	540′	45′	90′
50		500′	550′	600′	50′	100′
55		550′	605′	660′	55′	110′
60		600′	660′	720′	60′	120′
65		650′	715′	780′	65′	130′
70		700′	770′	840′	70′	140′
75		750′	825′	900′	75′	150′
80		800′	880′	960′	80′	160′

** Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

Texas Department of Transportation | Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ABL	HOWARD		031

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.



TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW

The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic.
Barricade striping should slant downward in the direction of detour.



PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW

1. Where positive redirectional capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.



LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
SB	Steady burn warning light or yellow warning reflector

PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS



28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

DATE:
FILE:

Texas Department of Transportation — Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS 9-07 8-14 7-13 5-21	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		032

DATE:
FILE:

WORK ZONE PAVEMENT MARKINGS

GENERAL

1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
2. Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
3. Additional supplemental pavement marking details may be found in the plans or specifications.
4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
7. All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

1. Raised pavement markers are to be placed according to the patterns on BC(12).
2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
2. Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.

MAINTAINING WORK ZONE PAVEMENT MARKINGS

1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
3. Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
7. Over-painting of the markings SHALL NOT BE permitted.
8. Removal of raised pavement markers shall be as directed by the Engineer.
9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
10. Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
   A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
   B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
3. Small design variances may be noted between tab manufacturers.
4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

1. Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
2. All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
3. Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body).
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
2-98 9-07 5-21	DIST	COUNTY		SHEET NO.
1-02 7-13	ABL	HOWARD		033
11-02 8-14				

105

DATE:
FILE:

PAVEMENT MARKING PATTERNS

REFLECTORIZED PAVEMENT MARKINGS - PATTERN A



RAISED PAVEMENT MARKERS - PATTERN A



REFLECTORIZED PAVEMENT MARKINGS - PATTERN B



RAISED PAVEMENT MARKERS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer.
Prefabricated markings may be substituted for reflectorized pavement markings.

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

EDGE & LANE LINES FOR DIVIDED HIGHWAY



REFLECTORIZED PAVEMENT MARKINGS



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

TWO-WAY LEFT TURN LANE

STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS

SOLID LINES

DOUBLE NO-PASSING LINE



EDGE LINE OR SINGLE NO-PASSING LINE



WIDE LINE

(FOR LEFT TURN CHANNELIZING LINE OR CHANNELIZING LINE USED TO DISCOURAGE LANE CHANGING.)



BROKEN LINES

CENTER LINE OR LANE LINE



AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



Centerline only - not to be used on edge lines

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

SHEET 12 OF 12

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS 1-97 9-07 5-21 2-98 7-13 11-02 8-14	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		034



NOTES:

1. Length of Safety Glare screen will be specified elsewhere in the plans.
2. The cumulative nominal length of the modular safety glare screen units shall equal the length of the individual sections of temporary concrete traffic barrier on which they are installed so the joint between barrier sections will not be spanned by any one safety glare screen unit.
3. Screen Panel/blades will be designed such that reflective sheeting conforming with Departmental Material Specification DMS-8300, Sign Face Materials, Type B or C Yellow, minimum size of 2 inches by 12 inches can be attached to the edge of the panel/blade. The sheeting shall be attached to one glare screen panel/blade per section of concrete barrier not to exceed a spacing of 30 feet. Barrier reflectors are not necessary when panel/blades are installed with reflective sheeting as described.
4. Payment for these devices will be under statewide Special Specification "Modular Glare Screens for Headlight Barrier."
5. This detail is only intended to show types of locations where Glare Screens would be appropriate. Required signing and other devices shall be as shown elsewhere in the plans.

BARRIER DELINEATION WITH MODULAR GLARE SCREENS

LEGEND	
	Type 3 Barricade
• • •	Channelizing Devices
	Trailer Mounted Flashing Arrow Board
	Sign
\\\\	Safety glare screen

DEPARTMENTAL MATERIAL SPECIFICATIONS	
SIGN FACE MATERIALS	DMS-8300
DELINEATORS AND OBJECT MARKERS	DMS-8600
MODULAR GLARE SCREENS FOR HEADLIGHT BARRIER	DMS-8610

Only pre-qualified products shall be used. A copy of the Compliant Work Zone Traffic Control Devices List" CWZTCD)describes pre-qualified products and their sources and may be found at the following web address:

http://www.txdot.gov/business/resources/producer-list.html



VERTICAL PANELS & OPPOSING TRAFFIC LANE DIVIDERS (OTLD) SEPARATING TWO-WAY TRAFFIC ON NORMALLY DIVIDED HIGHWAYS

NOTES:

1. When two-lane, two way traffic control must be maintained on one roadway of a normally divided highway, opposing traffic shall be separated with either temporary traffic barriers, channelizing devices, or a temporary raised island throughout the length of the two way operation. The above Typical Application is intended to show the appropriate application of channelizing devices when they are used for this purpose. This is not a traffic control plan. If this detail is to be used for other types of roads or applications, those locations should be stated elsewhere in the plans.

△2. Space devices according to the Tangent Spacing shown on the Device Spacing table on BC(9) but not exceeding 100'.

3. Every fifth device should be an OTLD except when spaced closer to accommodate an intersection. An OTLD should be the first device on each side of intersecting streets or roads.
4. Locations where surface mount bases with adhesives or self-righting devices will be required in order to maintain them in their proper position should be noted elsewhere in the plans.
5. Channelizing devices are to be vertical panels, 42" cones or tubular markers that are at least 36" tall. Tubular markers used to separate traffic should have a rubber base weighing at least 30 pounds. Tubular markers that are 42" tall or more shall have four bands of reflective material as detailed for 42" cones on BC(10). Tubular markers less than 42" but at least 36" tall shall have three bands of 3" wide white reflective material spaced 2" apart. Reflective material shall meet DMS-8300, Type A.

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN TYPICAL DETAILS

WZ(TD)-17

FILE:	wztd-17.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-98 2-17 3-03 7-13		0005	05	113, ETC	IH 20
		DIST	COUNTY		SHEET NO.
		ABL	HOWARD		035

DATE:
FILE:

DATE: 2/9/2022 3:22:38 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\0500WZSTPM-13.dgn

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS



NOTES:

1. Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
2. Short term pavement markings shall NOT be used to simulate edge lines.
3. Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
4. Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
5. No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
6. For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
7. For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
8. For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

1. Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
2. Tabs shall meet requirements of Departmental Material Specification DMS-8242.
3. When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
4. No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS



LANE LINES FOR DIVIDED HIGHWAY



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



TWO-WAY LEFT TURN LANE



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

1. Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
2. Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Costruction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

1. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

1. DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
   http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm

Texas Department of Transportation

Traffic Operations Division Standard

WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ(STPM)-13

FILE:	wzstpm-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS		0005	05	113, ETC	IH 20
1-97		DIST	COUNTY		SHEET NO.
3-03		ABL	HOWARD		036
7-13					

DATE: 2/9/2022 3:23:17 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\wzul-13.dgn



UNEVEN LANES
TWO LANE CONVENTIONAL ROAD



UNEVEN LANES
FOUR LANE CONVENTIONAL ROAD



NO CENTER LINE
TWO LANE CONVENTIONAL ROAD



UNEVEN LANES
DIVIDED ROADWAY

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B_{FL} OR TYPE C_{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1

Edge Condition	Edge Height (D)	* Warning Devices
① 	Less than or equal to: 1¼" (maximum-planing) 1½" (typical-overlay)	Sign: CW8-11
	Distance "D" may be a maximum of 1 1/4 " for planing operations and 2" for overlay operations if uneven lanes with edge condition 1 are open to traffic after work operations cease.	
② 	Less than or equal to 3"	Sign: CW8-11
③  Notched Wedge Joint	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"

Texas Department of Transportation

Traffic Operations Division Standard

SIGNING FOR UNEVEN LANES

WZ(UL)-13

FILE: wzul-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
8-95 2-98 7-13	DIST	COUNTY		SHEET NO.
1-97 3-03	ABL	HOWARD		037

DATE:
FILE:



ROAD CLOSURE BEYOND THE INTERSECTION

Signing for a Numbered Route with an Off-Site Detour



ROAD CLOSURE AT THE INTERSECTION

Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

GENERAL NOTES

1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.

Texas Department of Transportation

Traffic Operations Division Standard

WORK ZONE ROAD CLOSURE DETAILS

WZ(RCD)-13

FILE: wzrcd-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
1-97 4-98 7-13	DIST	COUNTY		SHEET NO.
2-98 3-03	ABL	HOWARD		038

DATE: 2/18/2022 1:20:34 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\0599tcp2246.dgn



TCP (2-6a)

ONE LANE CLOSURE



TCP (2-6b)

LANE CLOSURE NEAR EXIT RAMPS



TCP (2-6c)

LANE CLOSURE NEAR ENTRANCE RAMPS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices: On a Taper	On a Tangent	Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
30	$L=\frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L=WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

1. Flags attached to signs where shown, are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
3. Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
4. Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on everyother channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
5. The placement of pavement markings may be omitted on Intermediate-term stationary work zones with the approval of the Engineer.
6. Shadow Vehicle with TMA and high intensity rotating, flashing,oscillating or strobe lights. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
7. Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

TCP(2-6)-18

FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-94 4-98 8-95 2-12 1-97 2-18	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		039

DATE:
FILE:



RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)



INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
2. For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
3. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
4. The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
5. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
9. Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
10. The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
12. The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
13. Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
14. The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.



STRIPING FOR TMA

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS DIVIDED HIGHWAYS

TCP(3-2)-13

FILE: tcp3-2.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-94 4-98 8-95 7-13 1-97	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		040



TCP (3-3a)

TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)



TCP (3-3b)

TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)



TCP (3-3c)

DIVIDED MULTILANE HIGHWAY



TCP (3-3d)

UNDIVIDED MULTILANE HIGHWAY

DATE:
FILE:



TRAIL/SHADOW VEHICLE A

with RIGHT Directional display
Flashing Arrow Board



TRAIL/SHADOW VEHICLE B

with Flashing Arrow Board
in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
12. For divided highways with three or four lanes in each direction, use TCP(3-2).
13. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
14. The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
15. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL
TCP(3-3)-14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
2-94 4-98	DIST	COUNTY		SHEET NO.
8-95 7-13	ABL	HOWARD		041
1-97 7-14				

DATE:
FILE:



TCP (6-1a)

TYPICAL FREEWAY ONE LANE CLOSURE



TCP (6-1b)

TYPICAL FREEWAY TWO LANE CLOSURE

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices: On a Taper	On a Tangent	Suggested Longitudinal Buffer Space "B"
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
2. Drums or 42"cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
3. All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
4. The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
5. Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
6. Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
7. Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
8. The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
9. Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
10. Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
11. When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
12. For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
13. The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN FREEWAY LANE CLOSURES

TCP(6-1)-12

FILE: tcp6-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS 8-12	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		042

DATE:
FILE:



TCP (6-2a)

ENTRANCE RAMP OPEN
WORK WITHIN 500' OF RAMP



TCP (6-2b)

ENTRANCE RAMP CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices: On a Taper	On a Tangent	Suggested Longitudinal Buffer Space "B"
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
2. ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainlane can be seen from both roadways.
3. See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
4. The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
WORK AREA NEAR RAMP

TCP(6-2)-12

FILE: tcp6-2.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
1-97 8-98	DIST	COUNTY		SHEET NO.
4-98 8-12	ABL	HOWARD		043

DATE:
FILE:



TCP (6-3a)

ENTRANCE RAMP OPEN



TCP (6-3b)

EXIT RAMP CLOSED

TRAFFIC EXITS PRIOR TO CLOSED RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices: On a Taper	On a Tangent	Suggested Longitudinal Buffer Space "B"
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES:

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
WORK AREA BEYOND RAMP

TCP(6-3)-12

FILE: tcp6-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
1-97 8-98	DIST	COUNTY		SHEET NO.
4-98 8-12	ABL	HOWARD		044

DATE: 2/18/2022 1:24:02 PM
FILE: I:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\tcp6-4-12.dgn



TCP (6-4a)

EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP



TCP (6-4b)

EXIT RAMP OPEN

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices: On a Taper	On a Tangent	Suggested Longitudinal Buffer Space "B"
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
2. See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP(6-4)-12

FILE: tcp6-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT Feburary 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
1-97 8-98	DIST	COUNTY		SHEET NO.
4-98 8-12	ABL	HOWARD		045

DATE: 2/18/2022 1:24:25 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\tcp6-5-12.dgn



TCP (6-5a)

EXIT RAMP OPEN



TCP (6-5b)

EXIT RAMP OPEN
TWO LANE CLOSURE WITHIN 1500' PAST EXIT RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices: On a Taper	On a Tangent	Suggested Longitudinal Buffer Space "B"
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
2. See BC standards for sign details.
3. If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
WORK AREA BEYOND EXIT RAMP

TCP(6-5)-12

FILE: tcp6-5.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT Feburary 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
1-97 8-98	DIST	COUNTY		SHEET NO.
4-98 8-12	ABL	HOWARD		046

DATE: 2/18/2022 1:24:49 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\tcp6-8.dgn



TCP (6-8a)



TCP (6-8b)



TCP (6-8c)

LEGEND

	Type 3 Barricade	▪▪	Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices On a Taper	On a Tangent	Suggested Longitudinal Buffer Space "B"
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT)
S=Posted Speed(MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Place channelizing devices in the gore at 20' spacing.
2. See the Standard Highway Sign Design for Texas (SHSD) for sign details.
3. The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
4. When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) for traffic control details.
5. Truck mounted attenuator is required.
6. The PCMS may be omitted if replaced with a "RAMP CLOSED" AHEAD (CW20RP-3D) Sign.
7. Roadway ADT should be greater than 10,000.

Texas Department of Transportation

Traffic Operations Division Standard

WORK IN EXIT GORE FOR ADT GREATER THAN 10,000

TCP(6-8)-14

FILE: tcp6-8.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		047

DATE: 2/18/2022 1:25:19 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\048 TCP(S-1)-08A.dgn



TCP (S-1a)
WORK OFF SHOULDER OR PAVED SURFACE



TCP (S-1b)
WORK ON SHOULDER

LEGEND

Type III Barricade ■ ■ Channelizing Devices Flag
Heavy Work Vehicle Truck Mounted Attenuator (TMA)
Trailer Mounted Flashing Arrow Panel (M) Portable Changeable Message Sign (PCMS)
Flagger Sign Post

Posted Speed*	Formula	Minimum Desirable Taper Lengths** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Device On a Taper	On a Tangent	Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
30	$L=\frac{WS^2}{60}$	150'	165'	180'	30'	60'-75'	120'	90'
35		205'	225'	245'	35'	70'-90'	160'	120'
40		265'	295'	320'	40'	80'-100'	240'	155'
45	L=WS	450'	495'	540'	45'	90'-110'	320'	195'
50		500'	550'	600'	50'	100'-125'	400'	240'
55		550'	605'	660'	55'	110'-140'	500'	295'
60		600'	660'	720'	60'	120'-150'	600'	350'
65		650'	715'	780'	65'	130'-165'	700'	410'
70		700'	770'	840'	70'	140'-175'	800'	475'
75		750'	825'	900'	75'	150'-185'	900'	540'

* Conventional Roads Only

** Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
SHORT DURATION - work that occupies a location up to 1 hour.
SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

GENERAL NOTES:

1. The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
2. Channelizing devices on the shoulder taper and tangent section may be omitted for short duration (less than 1 hour) work.
3. If line-of-sight requirements for surveying operations will preclude the placement of the Work Vehicle to protect workers, the channelizing devices mentioned in Note 2 are required.
4. ⚠ A Shadow Vehicle with a Truck Mounted Attenuator and flashing warning lights/arrow panel in caution mode may be used in lieu of the Work Vehicle to protect the work space.
5. The CW20-1D "ROAD WORK AHEAD" sign may be substituted for the CW21-6D "SURVEY CREW AHEAD" sign.
6. This plan may also be used for shoulder work or off shoulder work for multilane undivided roadways.
7. The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

TCP(S-1a)

8. Cones may be placed at edge of pavement adjacent to the work space to enhance safety.

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECCESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision
⚠ Corrected misspelling.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

TCP(S-1)-08A

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

REVISIONS
8-08

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		048

DATE: 2/18/2022 1:25:39 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\049 TCP(2-1)-08A.dgn



TCP (S-2a)
ROAD CLOSED FOR LESS THAN 20 MINUTES -
OFF PEAK TRAFFIC HOURS
WITH OR WITHOUT SHOULDERS



TCP (S-2b)
WORK IN ROADWAY
OFF PEAK TRAFFIC HOURS
WITH OR WITHOUT SHOULDERS

Stopping Sight Distance	
Posted Speed (mph)	Distance (ft)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820
80	910

LEGEND

Type III Barricade ■ ■ Channelizing Devices Flag
Heavy Work Vehicle Truck Mounted Attenuator (TMA)
Trailer Mounted Flashing Arrow Panel
Portable Changeable Message Sign (PCMS)
Flagger Sign Post

Posted Speed ✳	Formula	Minimum Desirable Taper Lengths ✳✳ 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Device On a Taper	On a Tangent	Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
30	$L=\frac{WS^2}{60}$	150'	165'	180'	30'	60'-75'	120'	90'
35		205'	225'	245'	35'	70'-90'	160'	120'
40		265'	295'	320'	40'	80'-100'	240'	155'
45	L=WS	450'	495'	540'	45'	90'-110'	320'	195'
50		500'	550'	600'	50'	100'-125'	400'	240'
55		550'	605'	660'	55'	110'-140'	500'	295'
60		600'	660'	720'	60'	120'-150'	600'	350'
65		650'	715'	780'	65'	130'-165'	700'	410'
70		700'	770'	840'	70'	140'-175'	800'	475'
75		750'	825'	900'	75'	150'-185'	900'	540'

✳ Conventional Roads Only

✳✳ Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
SHORT DURATION - work that occupies a location up to 1 hour.
SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

GENERAL NOTES:
1. The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
2. Adequate Stopping Sight Distance (see Stopping Sight Distance table) should be maintained from approaching traffic to the flagger or a queue of stopped vehicles. The Buffer Space "B" should be extended around curves or other obstacles, when necessary, to have adequate Stopping Sight Distance to the flagger station.
3. Flaggers should use two-way radios or other means of communication while flagging.
4. The length of the work space should be based on the ability of the flaggers to communicate.
5. CW20-1D "ROAD WORK AHEAD" signs may be substituted for CW21-6D "SURVEY CREW AHEAD" signs.
6. The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

TCP(S-2a)

7. Road closures shall be less than 20 minutes. Closures less than 5 minutes are desirable.
8. Sign spacing should be increased if traffic repeatedly queues past the CW20-7b "BE PREPARED TO STOP" sign.
9. The surveying instrument should not be located on the paved surface.

TCP (S-2B)

10. For short duration work the Shadow Vehicle with a TMA may be replaced by another Work Vehicle with high intensity rotating, flashing or strobe lights.
11. Shadow Vehicles with a TMA are desirable when workers or equipment are in the work space. When approved by the engineer, Type III barricades or other channelizing devices may be substituted for the Shadow Vehicle.
12. The CW20-7b "BE PREPARED TO STOP" sign is optional. When used, it should be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign.

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECCESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision
1 Corrected referrence to notes.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

TCP(S-2)-08A

REVISIONS	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
8-08	CONT	SECT	JOB	HIGHWAY
	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		049

DATE: 2/18/2022 1:26:04 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\050 TCP(S-3)-08.dgn



TCP (S-3a)
RIGHT LANE CLOSED
WITH OR WITHOUT SHOULDERS



TCP (S-3b)
WORK ON CENTERLINE

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECCESSARY PERIODS OF TIME ON THE ROAD SURFACE.

LEGEND

Type III Barricade ■ ■ Channelizing Devices Flag
Heavy Work Vehicle Truck Mounted Attenuator (TMA)
Trailer Mounted Flashing Arrow Panel Portable Changeable Message Sign (PCMS)
Flagger Sign Post

Posted Speed*	Formula	Minimum Desirable Taper Lengths** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Device On a Taper	On a Tangent	Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'-75'	120'	90'
35		205'	225'	245'	35'	70'-90'	160'	120'
40		265'	295'	320'	40'	80'-100'	240'	155'
45	L=WS	450'	495'	540'	45'	90'-110'	320'	195'
50		500'	550'	600'	50'	100'-125'	400'	240'
55		550'	605'	660'	55'	110'-140'	500'	295'
60		600'	660'	720'	60'	120'-150'	600'	350'
65		650'	715'	780'	65'	130'-165'	700'	410'
70		700'	770'	840'	70'	140'-175'	800'	475'
75		750'	825'	900'	75'	150'-185'	900'	540'

* Conventional Roads Only

** Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
SHORT DURATION - work that occupies a location up to 1 hour.
SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

GENERAL NOTES:
1. The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
2. For short duration work the Shadow Vehicle with TMA may be replaced by another Work Vehicle with high intensity rotating, flashing or strobe lights.
3. Shadow Vehicles with a TMA are desirable when workers or equipment are in the work space. When approved by the engineer, Type III barricades or other channelizing devices may be substituted for the Shadow Vehicle.
4. CW20-1D "ROAD WORK AHEAD" signs may be substituted for CW21-6D "SURVEY CREW AHEAD" signs.
5. The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

TCP(S-3a)
6. If shoulders are not present, the 1/3L shoulder taper is to be omitted and four channelizing devices shall be placed in front of the arrow panel, perpendicular to traffic.

TCP(S-3b)
7. One CW20-5L "LEFT LANE CLOSED" sign in each direction may be omitted when the posted speed is less than 45mph and volume is less then 2000 ADT.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

TCP(S-3)-08

REVISIONS

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20

DIST	COUNTY	SHEET NO.
ABL	HOWARD	050

DATE: 2/18/2022 1:26:31 PM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\3 TRAFFIC CONTROL STANDARDS\051 TCP(S-4)-08A.dgn



TCP (S-4a)
WORK OFF RIGHT SHOULDER
OF DIVIDED ROADWAYS



TCP (S-4b)
WORK IN MEDIAN
OF DIVIDED ROADWAYS

LEGEND

Type III Barricade ■ ■ Channelizing Devices Flag
Heavy Work Vehicle Truck Mounted Attenuator (TMA)
Trailer Mounted Flashing Arrow Panel
Portable Changeable Message Sign (PCMS)
Flagger Sign Post

Posted Speed ✳	Formula	Minimum Desirable Taper Lengths ✳✳ 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Device On a Taper	On a Tangent	Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'-75'	120'	90'
35		205'	225'	245'	35'	70'-90'	160'	120'
40		265'	295'	320'	40'	80'-100'	240'	155'
45	L=WS	450'	495'	540'	45'	90'-110'	320'	195'
50		500'	550'	600'	50'	100'-125'	400'	240'
55		550'	605'	660'	55'	110'-140'	500'	295'
60		600'	660'	720'	60'	120'-150'	600'	350'
65		650'	715'	780'	65'	130'-165'	700'	410'
70		700'	770'	840'	70'	140'-175'	800'	475'
75		750'	825'	900'	75'	150'-185'	900'	540'

✳ Conventional Roads Only

✳✳ Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
SHORT DURATION - work that occupies a location up to 1 hour.
SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

GENERAL NOTES:

1. The G20-2a "END ROAD WORK" sign may be omitted for short duration (less than 1 hour) work.
2. When median work is protected on one side by existing median barriers, signing and protection vehicle may be omitted for the protected direction only.
3. CW20-1D "ROAD WORK AHEAD" signs may be substituted for "SURVEY CREW AHEAD" signs.
4. ⚠1 A Shadow Vehicle with a TMA and flashing warning lights/arrow panel in caution mode may be used in lieu of the Work Vehicle to protect the work space.
5. The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.
6. The CW21-6D "SURVEY CREW AHEAD" sign placed at 1000' ahead of the work space is optional, at the discretion of the Engineer. The signs shown at 2600' from the work space are required.
7. Cones may be placed at edge of pavement adjacent to the work space to enhance safety.

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECCESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision
⚠1 Corrected misspelling.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

TCP(S-4)-08A

REVISIONS
8-08

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20

DIST	COUNTY	SHEET NO.
ABL	HOWARD	051

DATE:
FILE:



TCP (S-5a)
WORK ON RIGHT SHOULDER
OF DIVIDED ROADWAYS



TCP (S-5b)
WORK ON MEDIAN SHOULDER
OF DIVIDED ROADWAYS

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECCESSARY PERIODS OF TIME ON THE ROAD SURFACE.

LEGEND

Type III Barricade ■ ■ Channelizing Devices Flag
Heavy Work Vehicle Truck Mounted Attenuator (TMA)
Trailer Mounted Flashing Arrow Panel
Portable Changeable Message Sign (PCMS)
Flagger Sign Post

Posted Speed ✳	Formula	Minimum Desirable Taper Lengths ✳✳ 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Device On a Taper	On a Tangent	Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'-75'	120'	90'
35		205'	225'	245'	35'	70'-90'	160'	120'
40		265'	295'	320'	40'	80'-100'	240'	155'
45	L=WS	450'	495'	540'	45'	90'-110'	320'	195'
50		500'	550'	600'	50'	100'-125'	400'	240'
55		550'	605'	660'	55'	110'-140'	500'	295'
60		600'	660'	720'	60'	120'-150'	600'	350'
65		650'	715'	780'	65'	130'-165'	700'	410'
70		700'	770'	840'	70'	140'-175'	800'	475'
75		750'	825'	900'	75'	150'-185'	900'	540'

✳ Conventional Roads Only

✳✳ Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
SHORT DURATION - work that occupies a location up to 1 hour.
SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

GENERAL NOTES:

1. The G20-2a "END ROAD WORK" sign may be omitted for short duration (less than 1 hour) work.
2. For short duration work, the Shadow Vehicle with TMA may be replaced by another Work Vehicle with high intensity rotating, flashing or strobe lights.
3. Shadow Vehicles with a TMA are desirable when workers or equipment are in the work space. When approved by the engineer, Type III barricades or other channelizing devices may be substituted for the Shadow Vehicle.
4. If shoulders are not present, the 1/3L shoulder taper is to be omitted and four channelizing devices shall be placed in front of the arrow panel, perpendicular to traffic.
5. CW20-1D "ROAD WORK AHEAD" signs may be substituted for CW21-6D "SURVEY CREW AHEAD" signs.
6. The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

TCP(S-5)-08

REVISIONS

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		052



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 1 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		053
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 2 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		054
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 3 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		055
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- (XX) - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 4 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		056
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- (XX) - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 5 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		057
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 6 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		058
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 7 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		059
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 8 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		060
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 9 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		061
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 10 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		062
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 11 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		063
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...
3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 12 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		064
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 13 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		065
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 14 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		066
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

IH 20 WB LANES

LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 15 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		067
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 16 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		068
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 17 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		069
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:

LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 18 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		070
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 19 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		071
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 20 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		072
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 21 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		073
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 22 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		074
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- (XX) - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 23 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		075
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 24 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		076
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 25 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		077
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 26 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		078
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 27 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		079
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- (XX) - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 28 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		080
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 29 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		081
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 30 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		082
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS
(SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 31 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		083
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 32 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		084
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 33 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		085
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- XX BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 34 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		086
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 35 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		087
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 36 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		088
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- (XX) - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 37 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		089
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- XX - RAMP / DELINEATORS (SEE QUANTITY SUMMARY SHEET 19)
- XX - BRIDGE RAIL / DELINEATORS (SEE QUANTITY SUMMARY SHEET 20)



STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

 Texas Department of Transportation

SCALE: 1" = 50' SHEET 38 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		090
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- MILL 2", TACK COAT, SMA 2"
- FOG SEAL (SHOULDER ONLY)
- TRAFFIC DIRECTION
- EXISTING CABLE BARRIER
- ℄ IH 20
- EXISTING MBGF
- PROP 4" W BRK W/RPM
- PROP 12" W SLD
- (XX) - RAMP / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 19)
- (XX) - BRIDGE RAIL / DELINEATORS
  (SEE QUANTITY SUMMARY SHEET 20)

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ROADWAY LAYOUT

Texas Department of Transportation

SCALE: 1" = 50' SHEET 39 OF 39

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		091
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

DATE: 2/18/2022
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\5 ROADWAY STANDARDS\092 TE(HMAC)-11.dgn



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 1
THIN HMAC SURFACES OR HMAC OVERLAY WITH THICKNESS OF 2.5" OR LESS



** EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.

*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 2
OVERLAY OF EXISTING PAVEMENT HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 3
NEW OR RECONSTRUCTED PAVEMENT HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 4
NEW OR RECONSTRUCTED PAVEMENT HMAC THICKNESS 5" OR GREATER

(NOT TO SCALE)

GENERAL NOTES

1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

Texas Department of Transportation

Design Division Standard

TAPERED EDGE DETAILS HMAC PAVEMENT

TE(HMAC)-11

FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:		
© TxDOT January 2011	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0005	05	113, ETC		IH 20	
	DIST	COUNTY			SHEET NO.	
	ABL	HOWARD			092	

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS

	SIZE 1	SIZE 2	SIZE 3	SIZE 4
DEVICE				
SHEETING	Yellow, White or Red Type B or C reflective sheeting			
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.			

DELINEATORS

	SINGLE		DOUBLE	
DEVICE				
	1-Size 2 reflector unit	1-Size 1 reflector unit	2-Size 2 reflector units	2-Size 1 reflector units
SHEETING	Yellow, White or Red Type B or C Reflective Sheeting			
POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX
MOUNT TYPE	GND	GND, SRF	GND	GND, SRF

D & OM DESCRIPTIVE CODES

INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX)

NUMBER OF REFLECTORS
S = Single
D = Double

COLOR OF REFLECTORS
W = White
Y = Yellow
R = Red

REFLECTOR UNIT SIZE
1 or 2

TYPE OF POST OR DELINEATOR
WC = Wing Channel Post
YFLX = Yellow Flexible Post
WFLX = White Flexible Post
BRF = Barrier Reflector

TYPE OF MOUNT
GND = Embedded (drivable or set in concrete)
CTB = Concrete Barrier Mount
GF1 or GF2 = Guard Fence Attachment
SRF = Surface Mount

DIRECTION
If Required
BI = Bi-Directional
BR = Bi-Directional with red on back

INSTL OM ASSM (OM-XX) (XXXX)XXX(XX)

TYPE OF OBJECT MARKER
1, 2, 3, or 4

NUMBER OF REFLECTORS OR DIRECTION
X = 3-Size 2 reflector units (Type 2 only)
Y = 1-Size 3 reflector unit (Type 2 only)
Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only)
L = Left Side (Type 3 Object Marker only)
R = Right Side (Type 3 Object Marker only)
C = Center (Type 3 Object Marker only)

TYPE OF POST
WC = Wing Channel Post
WFLX = White Flexible Post
TWT = Thin Walled Tubing

TYPE OF MOUNT
GND = Embedded (drivable)
SRF = Surface Mount
WAS = Wedge Anchor Steel
WAP = Wedge Anchor Plastic

DIRECTION
If Required
BI = Bi-Directional

OBJECT MARKERS

	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4
DEVICE								
		3-Size 2 reflector units	1-Size 3 reflector unit	3-Size 1 reflector units or 1-Size 4 reflector unit				
SHEETING	Yellow-Type B_{FL} or C_{FL} Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroflective yellow - Type B_{FL} or C_{FL} Sheeting			Red -Type B_{FL} or C_{FL} Sheeting
POST TYPE	TWT	WC	WC	WFLX	TWT			TWT
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP

BARRIER REFLECTORS (BRF)

	GF1	GF2	CTB
DEVICE			
	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.		
SHEETING	Yellow, White, Red		
NOTE	1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.		

CHEVRONS

DEVICE



W1-8

SIZE (W x L)	18"x 24" (Conventional)	24"x 30" (Conventional Oversize)	30"x 36" (Expressway)	36" x 48" (Freeway)
MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only	

NOTE

1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies).
2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).

ONE DIRECTION LARGE ARROW

DEVICE



W1-6

SIZE (W x L)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
MOUNTING HEIGHT	7'-0"	

NOTE:

Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.

DEPARTMENTAL MATERIAL SPECIFICATIONS

FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

D & OM(1)-20

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
©TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
10-09 3-15	DIST	COUNTY		SHEET NO.
4-10 7-20	ABL	HOWARD		093

DATE:
FILE:

POST TYPE AND SUPPORT FOUNDATION DETAILS

WING CHANNEL (WC)

GND



NOTES

1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only.
2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.

FLEXIBLE POSTS (YFLX, WFLX)

GND



EMBEDDED

SRF



SURFACE MOUNT

NOTES

1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices.
2. Install per manufacturer's recommendations.
3. Post length may vary to meet field conditions.
4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.

WEDGE ANCHOR SYSTEMS

WAS



STEEL

WAP



PLASTIC

NOTE

1. Install per manufacturer's recommendations.

TYPE OF BARRIER MOUNTS

GUARD FENCE ATTACHMENT

GF1



GF2



CONCRETE TRAFFIC BARRIER (CTB)



GENERAL NOTES

1. Place delineators on a section of roadway at a consistent distance from the edge of pavement.
2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS



NOTE

Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN



NOTE

Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

DELINEATORS AND TYPE 2 OBJECT MARKERS



See general notes 1, 2 and 3.

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
10-09 3-15	DIST	COUNTY		SHEET NO.
4-10 7-20	ABL	HOWARD		094

20B

DATE:
FILE:

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons

SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN

Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	——
2	2865	160	320	——
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN

Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp.Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete)and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100'max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100'max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

1. Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
2. Barrier reflectors may be used to replace required delineators.
3. Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND

	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20

FILE: dom3-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
3-15 8-15	DIST	COUNTY		SHEET NO.
8-15 7-20	ABL	HOWARD		095

20C

DATE:
FILE:

CROSSOVERS



DETAIL 1

FOR CULVERTS WITHOUT MBGF



DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES



DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

1. Barricade striping shall be red and white reflective sheeting for all permanent road closures.
2. Barricade striping is red and white sloping toward the center of the roadway.
3. Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4)-20

FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
©TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
3-15	DIST	COUNTY		SHEET NO.
7-20	ABL	HOWARD		096

DATE:
FILE:

20D

DATE:
FILE:

TWO-WAY, TWO LANE ROADWAY WITH REDUCED WIDTH APPROACH RAIL



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

TWO-WAY, TWO LANE ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

TWO-WAY, TWO LANE ROADWAY BRIDGE WITH NO APPROACH RAIL



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(5)-20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
7-20	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		097

20E

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

CONTINUOUS CONCRETE OR STEEL BARRIER



MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



EMERGENCY CROSSOVER



NOTES

1. Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delineators. On Continuos Barrier, equal spacing (100' max.)
2. Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delineators.
3. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3)in front of the terminal end.

LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(6)-20

FILE: dom6-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
7-20	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		098



EDGE LINE AND LANE LINES ONE-WAY ROADWAY WITH OR WITHOUT SHOULDERS



TYPICAL TWO-LANE, TWO-WAY PAVEMENT MARKINGS THROUGH INTERSECTIONS



CENTERLINE AND LANE LINES FOUR LANE TWO-WAY ROADWAY WITH OR WITHOUT SHOULDERS



TYPICAL MULTI-LANE, TWO-WAY PAVEMENT MARKINGS THROUGH INTERSECTIONS



TWO LANE TWO-WAY ROADWAY WITH OR WITHOUT SHOULDERS



For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.

YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES

1. Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.

2. Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield traingles shall only be used with yield signs.

3. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

GENERAL NOTES

1. Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.

2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



GUIDE FOR PLACEMENT OF STOP LINES, EDGE LINE & CENTERLINE

Based on Traveled Way and Pavement Widths for Undivided Highways

Texas Department of Transportation

Traffic Safety Division Standard

TYPICAL STANDARD PAVEMENT MARKINGS

PM(1)-20

FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
REVISIONS 8-95 3-03	0005	05	113, ETC	IH 20
5-00 2-12	DIST	COUNTY		SHEET NO.
8-00 6-20	ABL	HOWARD		099

22A

DATE: 2/18/2022 11:19:55 AM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\7 TRAFFIC STANDARDS\099 PM1-20.dgn

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



CENTERLINE FOR ALL TWO LANE ROADWAYS



CENTERLINE & LANE LINES FOR FOUR LANE TWO-WAY HIGHWAYS



DETAIL "A" **DETAIL "B"** **DETAIL "C"**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS



REFLECTORIZED PROFILE PATTERN DETAIL

USING REFLECTIVE PROFILE PAVEMENT MARKINGS

A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

4" EDGE LINE, CENTER LINE OR LANE LINE

OPTIONAL 6" EDGE LINE, CENTER LINE OR LANE LINE

NOTE

Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

GENERAL NOTES

1. All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.

Texas Department of Transportation

Traffic Safety Division Standard

POSITION GUIDANCE USING RAISED MARKERS RELECTORIZED PROFILE MARKINGS PM(2)-20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
©TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-92 2-10 5-00 2-12 8-00 6-20	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		100

22B

DATE: 2/18/2022 11:20:32 AM
FILE: I:\Big Spring Area\DESIGN PROJECTS\0005 05 113\7 TRAFFIC STANDARDS\100 PM2s 20.dgn



PAVEMENT MARKERS (REFL) TYPE II-C-R SHALL BE SPACED ON 80' CENTERS WITH THE CLEAR FACE TOWARD NORMAL TRAFFIC AND THE RED FACE TOWARD WRONG WAY TRAFFIC.

TRAFFIC LANE LINES PAVEMENT MARKING DETAILS

EDGELINES SHOULD TYPICALLY BE 4" WIDE AND THE MATERIALS SHALL BE AS SPECIFIED IN THE PLANS.
IF RAISED PROFILE PAVEMENT MARKINGS ARE USED SEE DETAILS BELOW.



EDGELINE PAVEMENT MARKINGS



ALL RAISED MARKERS IN THE WRONG WAY ARROW SHALL BE TYPE I-R REFLECTORIZED PAVEMENT MARKERS WITH THE REFLECTORIZED SURFACE FACING THE WRONG WAY TRAFFIC. TYPE II-C-R SHALL NOT BE USED.

REFLECTORIZED WRONG WAY ARROWS, NOT TO EXCEED TWO, MAY BE PLACED ON EXIT RAMPS.
LOCATION OF THE ARROWS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER.

WRONG WAY ARROW DETAIL



PARALLEL ACCELERATION LANE



TYPICAL EXIT RAMP GORE MARKING



TYPICAL ENTRANCE RAMP GORE MARKING

EXTEND THE EDGELINE FROM RAMP UNTIL IT INTERSECTS WITH EDGELINE FROM MAIN LANES



TAPERED ACCELERATION LANE

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS

Texas Department of Transportation
Traffic Operations Division

TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS WITH RAISED PAVEMENT MARKERS

FPM(1)-12

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

REVISIONS
4-92 2-10
5-00 2-12
8-00
2-08

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		101

23A

DATE: 2/18/2022 11:21:08 AM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\7 TRAFFIC STANDARDS\101 FMP1-12.dgn



SINGLE LANE EXIT WITH AUXILIARY LANE

(See Note 2)



TAPERED DECELERATION LANE



PARALLEL DECELERATION LANE



DETAIL A



DETAIL B

Wide (12") Dotted Lane Line (See Note 3)



DETAIL C

Normal (4") Dotted Lane Line (See Note 4)

GENERAL NOTES

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") Dotted Lane Line (See Detail B) is used to separate a through lane from a lane drop at normal exit ramp and from an auxiliary lane between an entrance and exit ramp.
4. Normal (4") Dotted Lane Line (See Detail C) is used at parallel acceleration and deceleration lanes.

LEGEND	
⇦	Denotes direction of traffic.
↱	Pavement marking arrows (white)
✳	Arrow markings are optional, however "ONLY" is required if arrow is used

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

Texas Department of Transportation
Traffic Operations Division

TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS ENTRANCE AND EXIT RAMPS

FPM(2)-12

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

REVISIONS
4-92 2-10
8-95 2-12
5-00
8-00

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		102

23B

DATE: 2/18/2022 11:21:31 AM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\7 TRAFFIC STANDARDS\102 FMP2-12.dgn



SINGLE LANE EXIT - LANE DROP OR EXIT ONLY



SINGLE LANE EXIT - LANE DROP OR EXIT ONLY (LEFTHAND)

LEGEND	
⇦	Denotes direction of traffic.
↱	Pavement marking arrows (white)
✳	Arrow markings are optional, however "ONLY" is required if arrow is used

GENERAL NOTES

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") Dotted Lane Line (See Detail B) is used to separate a through lane from a lane drop at normal exit ramp and from an auxiliary lane between an entrance and exit ramp.



DETAIL A



DETAIL B

Wide (12") Dotted Lane Line (See Note 3)

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

Texas Department of Transportation
Traffic Operations Division

TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS LANE DROP (EXIT ONLY) EXIT RAMPS

FPM(3)-12

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT

REVISIONS
5-00
8-00
2-10
2-12

CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20

DIST	COUNTY	SHEET NO.
ABL	HOWARD	103

DATE:
FILE:

23C



MULTIPLE LANE EXIT - EXIT ONLY WITH OPTION LANE



MULTIPLE LANE EXIT ONLY

LEGEND	
⇦	Denotes direction of traffic
	Pavement marking arrow (white)
	Optional Pavement Marking Arrows (white)
✳	Arrow markings are optional, however "ONLY" is required if arrow is used

GENERAL NOTES

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") Dotted Lane Line (See Detail B) is used to separate a through lane from a lane drop at normal exit ramp and from an auxiliary lane between an entrance and exit ramp.



DETAIL A



DETAIL B

Wide (12") Dotted Lane Line (See Note 3)

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

Texas Department of Transportation
Traffic Operations Division

TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS LANE DROP (EXIT ONLY) DETAILS

FPM(4)-12

REVISIONS
5-00
8-00
2-10
2-12

DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
CONT	SECT	JOB	HIGHWAY
0005	05	113, ETC	IH 20
DIST	COUNTY		SHEET NO.
ABL	HOWARD		104

23D

DATE: 2/18/2022 11:22:30 AM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\7 TRAFFIC STANDARDS\104 FMP4-12.dgn

DATE: 2/18/2022 11:22:45 AM
FILE: T:\Big Spring Area\DESIGN PROJECTS\0005 05 113\7 TRAFFIC STANDARDS\fpm(5)-19.dgn

EXIT NUMBER PAVEMENT MARKING NOTES

1. Minimum 8 foot white markings should be used, unless otherwise noted.
2. Spacing between letters and numbers should be approximately 4 inches.
3. Pavement markings are to be located as specified elsewhere in the plans.
4. All pavement marking materials shall meet the required Departmental Material Specifications or as specified in these plans.
5. Numbers and Letters details can be found in the Standard Highway Design for Texas (SHSD) Chapter 12 at http://www.txdot.gov



MARKINGS WITH EXIT NUMBER



NOTES

1. Raised pavement markers shall be centered between chevron or gore lines.
2. For more information, see Reflectorized Raised Pavement Marker Detail.

DETAIL A

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

LEGEND	
⇦	Traffic flow
▫	Reflectorized Raised Markers (RPM) Type II-C-R



Type II (Top View)



SECTION A

REFLECTORIZED RAISED PAVEMENT MARKER (RPM)



MARKINGS WITHOUT EXIT NUMBER

Texas Department of Transportation

Traffic Safety Division Standard

EXIT GORE PAVEMENT MARKINGS

FPM(5)-19

FILE: fpm(5)-19.dgn	DN:	CK:	DW:	CK:
© TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		105

PART 1 - GENERAL

1.01 DESCRIPTION

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

1.02 REQUEST FOR INFORMATION / CLARIFICATION

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

1.03 PLANS / SPECIFICATIONS

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

PART 2 - UTILITIES AND FIBER OPTIC

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

PART 3 - CONSTRUCTION

3.01 GENERAL

A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.

B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.

C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.

D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.

E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.

F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.

G. All permanent clearances shall be verified before project closing.

3.02 RAILROAD OPERATIONS

A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.

B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.

C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:

1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.

2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES

A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.

B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.

C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.

D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
1. Exactly what the work entails.
2. The days and hours that work will be performed.
3. The exact location of work, and proximity to the tracks.
4. The type of window requested and the amount of time requested.
5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.

E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

3.04 INSURANCE

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

3.05 RAILROAD SAFETY ORIENTATION

A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."

B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

3.06 COOPERATION

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES

Abide by the following minimum temporary clearances during the course of construction:
A. 15' - 0" (BNSF)(UPRR)and 14'-0" (KCS) horizontal from centerline of track
B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

3.08 APPROVAL OF REDUCED CLEARANCES

A. Maintain minimum track clearances during construction as specified in Section 3.07.

B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.

C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

Texas Department of Transportation | Rail Division

RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
	CONT	SECT	JOB	HIGHWAY
REVISIONS March 2020	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		106

DATE:
FILE:

3.09 MAINTENANCE OF RAILROAD FACILITIES

A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.

B. Perform all such maintenance and repair of damages due to the Contractors's operations at Contractor's expense.

C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

3.10 SITE INSPECTIONS BY RAILROAD's DESIGNATED REPRESENTATIVE

A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
   1. Pre-construction meetings.
   2. Pile driving/drilling of caissons or drilled shafts.
   3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
   4. Erection of precast concrete or steel bridge superstructure.
   5. Placement of waterproofing (prior to placing ballast on bridge deck).
   6. Completion of the bridge structure.

B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.

C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

3.11 RAILROAD REPRESENTATIVES

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.

B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.

C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.

D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.

E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

3.12 COMMUNICATIONS AND SIGNAL LINES

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

3.13 TRAFFIC CONTROL

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK

A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".

B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

   UPRR 1-800-336-9193
   7:00 AM to 9:00 PM CST Monday-Friday except holidays,
   staffed 24 hrs/day for emergencies
   48 hrs notice required

   BNSF 1-800-533-2891
   24 hour number
   5 working days notice required

   KCS 1-800-344-8377
   Texas One Call, a 24 hour number
   48 hrs notice required, excluding weekends and holidays

   If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of $\frac{1}{4}$ inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

3.15 RAILROAD FLAGGING

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

3.16 CLEANING OF RIGHT-OF-WAY

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

DATE:
FILE:

Texas Department of Transportation | Rail Division

RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS March 2020	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		107

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

DOT #: 796376T
Crossing Type:** HIGHWAY OVERPASS
RR Company Owning Track at Crossing: BIG SPRING RAIL SYSTEM (BSR)
Operating RR Company at Track: BSR
RR MP: 1.02
RR Subdivision: WAREHOUSE TK
City: BIG SPRING
County: HOWARD
CSJ at this Crossing: 0005-05-113
Highway/Roadway name crossing the railroad: IH 0020
# of regularly scheduled trains per day at this crossing: 0
# of switching movements per day at this crossing: 0
% of estimated contract cost of work within railroad ROW: 3%

Scope of Work at this Crossing to Be Performed by State Contractor:
MILL AND FILL, FOG SEAL SHOULDERS, REPLACE DELINEATORS
(ALL WORK IS ON HIGHWAY BRIDGE DECK ONLY)

Scope of Work at this Crossing to Be Performed by Railroad Company:
N/A

** Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian, or Closed/Abandoned

II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)

NONE

III. FLAGGING & INSPECTION

of Days of Railroad Flagging Expected: 0
On this project, night or weekend flagging is:

☐ Expected
☒ Not Expected

Flagging services will be provided by:

☐ Railroad Company: TxDOT will pay flagging invoices
☐ Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30 day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

☐ UPRR - UP.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging

☐ BNSF - BNSF.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging

☐ KCS - KCS.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
- Bottom Line On-Track Safety Services
bottomline076@aol.com, 903-767-7630

☐ OTHERS _____

Contractor must incorporate Construction Inspection into anticipated construction schedule.

☒ Not Required

☐ Required: Contact Information for Construction Inspection:

_____

IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

On this project, construction work to be performed by a railroad company is:

☐ Required
☒ Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

V. RAILROAD INSURANCE REQUIREMENTS

Railroad reference number shall be provided by TxDOT CST or DO.

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies must be issued for and on behalf of the Railroad. Where more than one Railroad Company is operating on the same right of way or where several Railroad Companies are involved and operate on their own separate rights of way, provide separate insurance policies in the name of each Railroad Company.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	$500,000 / $500,000 / $500,000
Commercial General Liability	$2,000,000 / $4,000,000
Business Automobile	$2,000,000 combined single limit

Railroad Protective Liability

☒ Not Required
☐ Non - Bridge Projects — $2,000,000 / $6,000,000
☐ Bridge Projects — $5,000,000 / $10,000,000
☐ Other

VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT

On this project, an ROE agreement is:

☒ Not Required
☐ Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)
☐ Required: Contractor to obtain (see Item 5, Article 8.4)
With the following railroad companies: _____

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

http://www.txdot.gov/inside-txdot/division/rail/samples.html

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed ROE agreement between the Contractor and the Railroad if required on project.

VII. RAILROAD COORDINATION MEETING

On this project, a Railroad Coordination Meeting is:

☒ Not Required
☐ Required

See Item 5, Article 8.1 for more details.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are required to maintain the same insurance coverage as required of the Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call Big Spring Rail
Railroad Emergency Line at 432-818-0212
Location: DOT 796376T
RR Milepost 1.02
Subdivision Warehouse TK

Texas Department of Transportation | Rail Division

RAILROAD SCOPE OF WORK
PROJECT SPECIFIC DETAILS

FILE: RR Scope of Work.dgn	DN: TxDOT	CK:	DW:	CK:
©TxDOT June 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS 3/2020	0005	05	113, ETC	IH 20
	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		108

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

DOT #: 796371J
Crossing Type:** HIGHWAY OVERPASS
RR Company Owning Track at Crossing: UNION PACIFIC
Operating RR Company at Track: UPRR
RR MP: 515.490
RR Subdivision: TOYAH
City: BIG SPRING
County: HOWARD
CSJ at this Crossing: 0005-05-113
Highway/Roadway name crossing the railroad: IH 0020
# of regularly scheduled trains per day at this crossing: 20
# of switching movements per day at this crossing: 0
% of estimated contract cost of work within railroad ROW: 3%

Scope of Work at this Crossing to Be Performed by State Contractor:
MILL AND FILL, FOG SEAL SHOULDERS, REPLACE DELINEATORS
(ALL WORK IS ON HIGHWAY BRIDGE DECK ONLY)

Scope of Work at this Crossing to Be Performed by Railroad Company:
NONE

** Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian, or Closed/Abandoned

II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)

NONE

III. FLAGGING & INSPECTION

of Days of Railroad Flagging Expected: 1
On this project, night or weekend flagging is:

- [ ] Expected
- [X] Not Expected

Flagging services will be provided by:

- [ ] Railroad Company: TxDOT will pay flagging invoices
- [X] Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30 day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

- [ ] UPRR - UP.info@railpros.com
  Call Center 877-315-0513, Select #1 for flagging
- [ ] BNSF - BNSF.info@railpros.com
  Call Center 877-315-0513, Select #1 for flagging
- [ ] KCS - KCS.info@railpros.com
  Call Center 877-315-0513, Select #1 for flagging
  - Bottom Line On-Track Safety Services
  bottomline076@aol.com, 903-767-7630
- [X] OTHERS RAIL PROS
  UPFLAG@RAILPROSFS.COM
  (877) 315-0513 EXT 116

Contractor must incorporate Construction Inspection into anticipated construction schedule.

- [X] Not Required
- [ ] Required: Contact Information for Construction Inspection:

IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

On this project, construction work to be performed by a railroad company is:

- [ ] Required
- [X] Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

V. RAILROAD INSURANCE REQUIREMENTS

Railroad reference number shall be provided by TxDOT CST or DO.

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies must be issued for and on behalf of the Railroad. Where more than one Railroad Company is operating on the same right of way or where several Railroad Companies are involved and operate on their own separate rights of way, provide separate insurance policies in the name of each Railroad Company.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	$500,000 / $500,000 / $500,000
Commercial General Liability	$2,000,000 / $4,000,000
Business Automobile	$2,000,000 combined single limit

Railroad Protective Liability

- [ ] Not Required
- [X] Non - Bridge Projects — $2,000,000 / $6,000,000
- [ ] Bridge Projects — $5,000,000 / $10,000,000
- [ ] Other

VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT

On this project, an ROE agreement is:

- [ ] Not Required
- [X] Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)
- [ ] Required: Contractor to obtain (see Item 5, Article 8.4)

With the following railroad companies: _____

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

http://www.txdot.gov/inside-txdot/division/rail/samples.html

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed ROE agreement between the Contractor and the Railroad if required on project.

VII. RAILROAD COORDINATION MEETING

On this project, a Railroad Coordination Meeting is:

- [X] Not Required
- [ ] Required

See Item 5, Article 8.1 for more details.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are required to maintain the same insurance coverage as required of the Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call UPRR
Railroad Emergency Line at 888 877 7267
Location: DOT 796371J
RR Milepost 515.490
Subdivision TOYAH

Texas Department of Transportation — Rail Division

RAILROAD SCOPE OF WORK
PROJECT SPECIFIC DETAILS

FILE: RR Scope of Work.dgn	DN: TxDOT	CK:	DW:	CK:
©TxDOT June 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
3/2020	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		109

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

DOT #: 859609P
Crossing Type: ** HIGHWAY OVERPASS
RR Company Owning Track at Crossing: UNION PACIFIC
Operating RR Company at Track: UPRR
RR MP: 512.360
RR Subdivision: TOYAH
City: BIG SPRING
County: HOWARD
CSJ at this Crossing: 0005-06-122
Highway/Roadway name crossing the railroad: IH 0020
# of regularly scheduled trains per day at this crossing: 20
# of switching movements per day at this crossing: 0
% of estimated contract cost of work within railroad ROW: 3%

Scope of Work at this Crossing to Be Performed by State Contractor:
MILL AND FILL, FOG SEAL SHOULDERS, REPLACE DELINEATORS
(ALL WORK IS ON HIGHWAY BRIDGE DECK ONLY)

Scope of Work at this Crossing to Be Performed by Railroad Company:
NONE

** Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian, or Closed/Abandoned

II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)

NONE

III. FLAGGING & INSPECTION

of Days of Railroad Flagging Expected: 1
On this project, night or weekend flagging is:

☐ Expected
☒ Not Expected

Flagging services will be provided by:

☐ Railroad Company: TxDOT will pay flagging invoices
☒ Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30 day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

☐ UPRR - UP.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging

☐ BNSF - BNSF.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging

☐ KCS - KCS.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
- Bottom Line On-Track Safety Services
bottomline076@aol.com, 903-767-7630

☒ OTHERS RAIL PROS
UPFLAG@RAILPROSFS.COM
(877) 315-0513 EXT 116

Contractor must incorporate Construction Inspection into anticipated construction schedule.

☒ Not Required

☐ Required: Contact Information for Construction Inspection:

IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

On this project, construction work to be performed by a railroad company is:

☐ Required
☒ Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

V. RAILROAD INSURANCE REQUIREMENTS

Railroad reference number shall be provided by TxDOT CST or DO.

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies must be issued for and on behalf of the Railroad. Where more than one Railroad Company is operating on the same right of way or where several Railroad Companies are involved and operate on their own separate rights of way, provide separate insurance policies in the name of each Railroad Company.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	$500,000 / $500,000 / $500,000
Commercial General Liability	$2,000,000 / $4,000,000
Business Automobile	$2,000,000 combined single limit

Railroad Protective Liability

☐	Not Required	
☒	Non - Bridge Projects	$2,000,000 / $6,000,000
☐	Bridge Projects	$5,000,000 / $10,000,000
☐	Other	

VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT

On this project, an ROE agreement is:

☐ Not Required
☒ Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)
☐ Required: Contractor to obtain (see Item 5, Article 8.4)
With the following railroad companies: _____

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

http://www.txdot.gov/inside-txdot/division/rail/samples.html

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed ROE agreement between the Contractor and the Railroad if required on project.

VII. RAILROAD COORDINATION MEETING

On this project, a Railroad Coordination Meeting is:

☒ Not Required
☐ Required

See Item 5, Article 8.1 for more details.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are required to maintain the same insurance coverage as required of the Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call UPRR
Railroad Emergency Line at 888 877 7267
Location: DOT 859609P
RR Milepost 512.360
Subdivision TOYAH

Texas Department of Transportation — Rail Division

RAILROAD SCOPE OF WORK
PROJECT SPECIFIC DETAILS

FILE: RR Scope of Work.dgn	DN: TxDOT	CK:	DW:	CK:
©TxDOT June 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0005	05	113, ETC	IH 20
3/2020	DIST	COUNTY		SHEET NO.
	ABL	HOWARD		110



LEGEND

- TRAFFIC DIRECTION
- EXISTING RAILROAD
- PROPOSED CONSTRUCTION

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...
3/1/2022

RAILROAD DETAILS

Texas Department of Transportation

BIG SPRING RAIL
RAILROAD CROSSING
STA 638+77.52

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		HWY
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		111
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- TRAFFIC DIRECTION
- EXISTING RAILROAD
- PROPOSED CONSTRUCTION

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

RAILROAD DETAILS

CSJ: 0005-05-113

Texas Department of Transportation

UNION PACIFIC
RAILROAD CROSSING
STA 672+60.60

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		HWY
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		112
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

FILE:
DATE:



LEGEND

- TRAFFIC DIRECTION
- EXISTING RAILROAD
- PROPOSED CONSTRUCTION

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

RAILROAD DETAILS

CSJ: 0005-06-122

Texas Department of Transportation

UNION PACIFIC
RAILROAD CROSSING
STA 869+72.61

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		HWY
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		113
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

DATE:
FILE:

I. STORM WATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Storm water Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.

☒ No Action Required ☐ Required Action

Action No.

1. The project disturbs less than one acre of surface area. The contractor is responsible for the PSL as defined in the Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges (2014 Edition, Section 7.6., Page 44). The total disturbed acreage is the combined acreage to be disturbed on the project and the contractors PSL.
2. Prevent storm water pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
3. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
4. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
5. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATER BODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

☒ No Permit Required

☐ Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)

☐ Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)

☐ Individual 404 Permit Required

☐ Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.

2.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
☐ Temporary Vegetation	☐ Silt Fence	☐ Vegetative Filter Strips
☐ Blankets/Matting	☐ Rock Berm	☐ Retention/Irrigation Systems
☐ Mulch	☐ Triangular Filter Dike	☐ Sedimentation Basin
☐ Sodding	☐ Sand Bag Berm	☐ Constructed Wetlands
☐ Interceptor Swale	☐ Straw & Hay Bale Dike	☐ Wet Basin
☐ Diversion Dike	☐ Brush Berms	☐ Erosion Control Compost/Mulch
☐ Erosion Control Compost	☐ Erosion Control Compost	☐ Compost Filter Berm and Socks
☐ Compost Filter Berm and Socks	☐ Compost Filter Berm and Socks	☐ Sand Filter Systems
☐ Temporary Erosion Control Logs (BIOLOGS)	☐ Temporary Erosion Control Logs (BIOLOGS)	☐ Temporary Erosion Control Logs (BIOLOGS)
☒ Preservation of Natural Habitat	☐ Sediment Traps	☐ Permanent Vegetation (Planting, Sodding, or Seeding)
☐ Construction Exits	☐ Sediment Basins	☐ Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

☐ No Action Required ☐ Required Action

Action No.

1.

2.

3.

4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical.
Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

☐ No Action Required ☒ Required Action

Action No.

1. Comply with EO13112 on use of native vegetation.
2. Minimize impacts to vegetation by removing/altering only what is necessary to complete the project.
3.
4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

☐ No Action Required ☒ Required Action

Action No.

1. Comply with Migratory Bird Treaty Act.
2. If any species of skunks are encountered, avoid harming the animal as well as avoid any unnecessary impacts to dens along the roadway.
3.
4.

LIST OF ABBREVIATIONS

BMP:	Best Management Practice	SPCC:	Spill Prevention Control and Countermeasure
CGP:	Construction General Permit	SW3P:	Storm Water Pollution Prevention Plan
DSHS:	Texas Department of State Health Services	PCN:	Pre-Construction Notification
FHWA:	Federal Highway Administration	PSL:	Project Specific Location
MOA:	Memorandum of Agreement	TCEQ:	Texas Commission on Environmental Quality
MOU:	Memorandum of Understanding	TPDES:	Texas Pollutant Discharge Elimination System
MS4:	Municipal Separate Storm water Sewer System	TPWD:	Texas Parks and Wildlife Department
MBTA:	Migratory Bird Treaty Act	TxDOT:	Texas Department of Transportation
NOT:	Notice of Termination	T&E:	Threatened and Endangered Species
NWP:	Nationwide Permit	USACE:	U.S. Army Corps of Engineers
NOI:	Notice of Intent	USFWS:	U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

* Dead or distressed vegetation (not identified as normal)
* Trash piles, drums, canister, barrels, etc.
* Undesirable smells or odors
* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

☐ Yes ☒ No

If "No", then no further action is required.
If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

☐ Yes ☒ No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC

Texas Department of Transportation

NO SCALE SHEET 1 OF 1

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		114
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

REV. DATE: 02/2015

SITE DESCRIPTION

PROJECT LIMITS:
THE PROJECT LIMITS SHOWN ON THE TITLE SHEET AND LIMITS OF TXDOT RIGHT OF WAY SHALL ALSO BE THE LIMITS OF COVERAGE OF THE SW3P.

PROJECT LOCATION MAPS: TITLE SHEET

DRAINAGE PATTERNS: N/A

APPROX. SLOPES ANTICIPATED AFTER MAJOR GRADING AND AREAS OF SOIL DISTURBANCE: TYPICAL SECTIONS

MAJOR CONTROLS AND LOCATIONS OF STABILIZATION PRACTICES: N/A

PROJECT SPECIFIC LOCATIONS: N/A

SURFACE WATERS AND DISCHARGE LOCATIONS:
N/A

TYPICAL AREAS WHICH WILL NOT BE DISTURBED:
N/A

ENDANGERED SPECIES, DESIGNATED CRITICAL HABITAT AND HISTORIC PROPERTY: EPIC SHEET

ESTIMATED START DATES AND DURATION OF ACTIVITIES IN THE INTENDED SCHEDULE/SEQUENCE OF EARTH-DISTURBING ACTIVITIES: CONTRACT TIME ESTIMATE

NATURE OF ACTIVITY:
<PROJECT DESCRIPTION FROM TITLE SHEET>

MAJOR SOIL DISTURBING ACTIVITIES:
NA

TOTAL PROJECT AREA:
438.27 ACRES

TOTAL AREA TO BE DISTURBED (AT EACH SITE):
0.00 ACRES

WEIGHTED RUNOFF COEFFICIENT BEFORE CONSTRUCTION:
NA

WEIGHTED RUNOFF COEFFICIENT AFTER CONSTRUCTION:
NA

EXISTING CONDITION OF SOIL & VEGETATIVE COVER:
NA

% OF EXISTING VEGETATIVE COVER:
NA

NAME OF RECEIVING WATERS:

STREAM SEGMENT 1412B OF THE COLORADO RIVER BASIN

EROSION AND SEDIMENT CONTROLS

USE "T" OR "P" IN THE BLANKS BELOW IF APPLICABLE (T= TEMPORARY, P= PERMANENT)

SOIL STABILIZATION PRACTICES:

P	BUFFER ZONES	____	PERMANENT PLANTING, SODDING, OR SEEDING
____	MULCHING	P	PRESERVATION OF NATURAL RESOURCES
____	TEMPORARY SEEDING	____	SOIL RETENTION BLANKET
____	OTHER	____	OTHER

OTHER:

FOR CONSTRUCTION PROJECTS, THIS DISTRICT OF THE TEXAS DEPARTMENT OF TRANSPORTATION USES SITEMANAGER, A COMPUTER BASED CONSTRUCTION RECORD-KEEPING SYSTEM, AS PART OF RECORD FOR PROJECT WORK INCLUDING ENVIRONMENTAL RELATED ACTIVITIES. DOCUMENTATION DESCRIBING MAJOR GRADING ACTIVITES, TEMPORARY OR PERMANENT CESSATION OF CONSTRUCTION AND STABILIZATION MEASURE IS PART OF THIS SYSTEM AND IS INCORPORATED BY REFERENCE INTO THIS SW3P.

STRUCTURAL PRACTICES:

____	CHANNEL LINERS	____	DIVERSION DIKE AND SWALE COMBINATIONS
____	CURBS AND GUTTERS	____	DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
____	HAY BALES	____	DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
____	PAVED FLUMES	____	ROCK BEDDING AT CONSTRUCTION EXIT
____	PIPE SLOPE DRAINS	____	STONE OUTLET STRUCTURES
____	STORM SEWERS	____	STORM INLET SEDIMENT TRAP
____	SEDIMENT BASINS	____	TEMPORARY EROSION CONTROL LOGS (BIOLOGS)
____	SEDIMENT TRAPS	____	TIMBER MATTING AT CONSTRUCTION EXIT
____	SILT FENCES	____	VEGETATIVE FILTER STRIPS
____	ROCK FILTER DAMS	____	VELOCITY CONTROL DEVICES
____	EROSION CONTROL LOGS	____	LINED CONCRETE WASHOUT

OFFSITE VEHICLE TRACKING CONTROLS:

____ HAUL ROADS DAMPENED FOR DUST CONTROL
____ EXCESS DIRT ON ROAD REMOVED DAILY
____ LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
____ STABILIZED CONSTRUCTION ENTRANCE
____ OTHER

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:

THE ORDER OF ACTIVITIES WILL BE AS FOLLOWS:
NA

STORM WATER MANAGEMENT:
NA

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF78BC5154947E...
3/1/2022

OTHER EROSION AND SEDIMENT CONTROLS:

MAINTENANCE:

N/A

INSPECTION:

N/A

WASTE MATERIALS:
ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL STATE AND LOCAL CITY SOLID WASTE MANAGEMENT REGULATIONS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED AS NECESSARY OR AS REQUIRED BY LOCAL REGULATION AND THE TRASH WILL BE HAULED TO A PERMITTED LANDFILL. NO CONSTRUCTION WASTE MATERIAL WILL BE BURIED ON SITE. CONSTRUCTION DEBRIS AND LITTER SHOULD BE PICKED UP ON A DAILY BASIS UNLESS OTHERWISE DIRECTED BY THE ENGINEER. WASTE AND DIRT PILES SHOULD BE REMOVED ON A WEEKLY BASIS.

HAZARDOUS WASTE (INCLUDING SPILL REPORTING):
NO LONG TERM WATER QUALITY IMPACTS ARE EXPECTED AS A RESULT OF THE PROPOSED PROJECT. SEE THE NEXT PLAN SHEET FOR A LIST OF POTENTIAL POLLUTANTS. IN THE EVENT OF A MAJOR SPILL, NOTIFY THE TXDOT ENGINEER IMMEDIATELY. ALL PERSONNEL WILL BE INSTRUCTED IN THE PROCEDURES FOR SPILL HANDLING AND DISPOSING OF ANY HAZARDOUS MATERIALS THEY WILL BE USING. ALL SPILLS, INCLUDING THOSE OF LESS THAN 25 GALLONS SHALL BE CLEANED IMMEDIATELY AND ANY CONTAMINATED SOIL SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND BE DISPOSED OF PROPERLY. DESIGNATED AREAS SHALL BE DETERMINED BY THE AREA ENGINEER FOR SPOILS DISPOSAL AND MATERIAL STORAGE. THESE AREAS SHALL BE PROTECTED FROM RUN-ON AND RUN-OFF. MATERIALS RESULTING FROM THE DESTRUCTION OF EXISTING ROADS AND BEING REMOVED AND/OR DISPOSED OF BY THE CONTRACTOR WILL BE DONE SO IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL LAWS, ORDINANCES AND REGULATIONS AND WITH THE APPROVAL OF THE PROJECT ENGINEER. ANY CHANGES TO AMBIENT WATER QUALITY DURING CONSTRUCTION OF THE PROPOSED PROJECT SHALL BE PROHIBITED AND MAY RESULT IN ADDITIONAL WATER QUALITY CONTROL MEASURES, WHICH SHALL BE MITIGATED AS SOON AS POSSIBLE AND SHALL BE REPORTED TO THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) WITHIN 24 HOURS OF BECOMING AWARE OF IMPACTS.

SANITARY WASTE:
ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NECESSARY OR AS REQUIRED BY LOCAL REGULATION BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

REMARKS:
CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED BY THE CONTRACTOR IN A MANNER TO MINIMIZE THE RUNOFF OF POLLUTANTS.
ALL WATERWAYS SHALL BE CLEARED AS SOON AS PRACTICABLE OF TEMPORARY EMBANKMENT, TEMPORARY BRIDGES, MATTING, FALSEWORK PILING, DEBRIS OR OTHER OBSTRUCTIONS PLACED DURING CONSTRUCTION OPERATIONS THAT ARE NOT PART OF THE FINISHED WORK. DISPOSAL AREAS, STOCKPILES, AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT MAY ENTER RECEIVING WATERS. DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WETLAND, WATER BODY OR STREAMBED.

Texas Department of Transportation

NO SCALE

TxDOT STORM WATER POLLUTION PREVENTION PLAN (SW3P)

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		115
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC

LIST OF POTENTIAL POLLUTANTS

POTENTIAL POLLUTANT	RELATED SOURCE	CONTROLS
CEMENTATEOUS MATERIAL AND CEMENTATEOUS AGGREGATES (BROKEN CONCRETE)	REMOVAL OF CONCRETE RIPRAP, CULVERT COMPONENTS, BRIDGE COMPONENTS, ETC.	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
MILLED ASPHALTIC CEMENT PAVEMENT (MILLINGS)	OBLITERATION OF ABANDONED ROAD AND PLANING OF ASPHALT	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
VIRGIN ASPHALTIC MATERIAL INCLUSIVE OF PRIME OILS, PRECOAT AGGREGATES, AND HOT MIX BITUMINOUS MIXTURES	APPLICATIONS OF PRIME COATS, SEAL COAT, AND PAVING OPERATIONS	THIS MATERIAL SHALL BE APPLIED AT APPROPRIATE RATES FOR CONSTRUCTION PURPOSES WHICH WILL PRECLUDE THESE MATERIALS FROM ENTERING RUNOFF. IN THE EVENT OF ANY UNINTENDED DISCHARGE, CONTROLS TO CONTAIN RUNOFF WILL BE IMMEDIATELY PLACED AND TCEQ WILL BE IMMEDIATELY NOTIFIED.
CONCRETE, REBAR, WIRE, WIRE FABRIC LUMBER, NAILS, STYROFOAM BLOCK, FIBERBOARD, CURING COMPOUND AND LINSEED OIL	CONSTRUCTION OF CONCRETE BRIDGE COMPONENTS SUCH AS DRILLED SHAFTS, CULVERTS, ABUTMENTS, BENTS, REINFORCED CONCRETE SLABS, RAIL, INLET, CONCRETE TRAFFIC BARRIERS, CURB AND GUTTER, RIPRAP AND SIGN FOUNDATIONS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF. ANY TEMPORARY FILLS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO THEIR PREEXISTING CONDITION/ELEVATION.
MASONRY CONCRETE BLOCK, GEOGRID FABRIC, CARDBOARD, AND PLASTIC RAP	CONSTRUCTION OF MODULAR RETAINING WALL SYSTEMS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
WOOD POSTS, STEEL POSTS, BARRELS, CONES, SIGN BOARDS (ALUMINUM AND PLYBOARD), FASTENERS, NUTS, BOLTS, AND WASHERS	PLACEMENT AND/OR REMOVAL OF BARRICADES, SIGNS AND TRAFFIC CONTROL DEVICES	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
WOOD POST, STEEL POST, STEEL FASTENERS, NUTS, BOLTS, AND WASHERS	CONSTRUCTION OF METAL BEAM GUARD FENCE	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
STRUCTURAL STEEL I-BEAM, SIGN BOARDS, AND CONCRETE FOUNDATIONS	REMOVAL OF ROADSIDE SIGN ASSEMBLIES LARGE AND SMALL	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
THERMOPLASTIC PAINT, GLASS BEADS, REFLECTIVE TABS, AND RAISED REFLECTIVE PAVEMENT MARKERS	APPLICATION OF PAVEMENT MARKINGS/MARKERS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
PETROLEUM PRODUCTS (SMALL QUANTITIES INTRODUCED BY CONTRACTOR)	EQUIPMENT FAILURE, MAINTENANCE AND REPAIR	ALL EQUIPMENT AND VEHICLE MAINTENANCE SHALL BE PERFORMED IN A DESIGNATED AREA WITH APPROPRIATE MEASURES FOR CONTAINMENT AND PROPER DISPOSAL OF ALL WASTE MATERIALS INCLUDING HYDRAULIC OIL AND OTHER LIQUIDS IN ACCORDANCE STATE AND LOCAL WASTE MANAGEMENT REGULATIONS. ALL MATERIAL STORED PRIOR TO DISPOSAL SHALL BE CONTAINED IN A CONTAINER WITH A SECURE COVER MEETING ALL STATE AND LOCAL WASTE MANAGEMENT REGULATIONS.
ELIGIBLE NON-STORM WATER DISCHARGES INCLUDING BUT NOT LIMITED TO NON-POTABLE WATER AND NON-STORM WATER DISCHARGE	MOISTURE APPLICATIONS FOR DUST CONTROL, DENSITY, VEGETATION WATERING, NON-DETERGENT VEHICLE WASHING, AND AIR CONDITIONING CONDENSATE	THIS MATERIAL SHALL BE APPLIED AT APPROPRIATE RATES FOR CONSTRUCTION PURPOSES WHICH WILL PRECLUDE THESE MATERIALS FROM ENTERING RUNOFF. IN THE EVENT OF ANY UNINTENDED DISCHARGE, CONTROLS TO CONTAIN RUNOFF WILL BE IMMEDIATELY PLACED AND THE NON-POTABLE WATER WILL BE RECOVERED AND PROPERLY STORED FOR REUSE.
SURVEY STAKE, FLAGGING TAPE AND PAINT	SURVEY STAKING, ALIGNMENT ESTABLISHMENT	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
WASTEWATER	WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
SOAPS AND SOLVENTS	VEHICLE AND EQUIPMENT WASHING	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.
UNSUITABLE FILL MATERIAL	EXCAVATION - ROADWAY, SPECIAL AND EROSION CONTROL	THIS CONSTRUCTION WASTE SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS. WHEN STORED ON SITE PRIOR TO DISPOSAL, IT SHALL BE CONTAINED SO AS TO ENSURE THAT IT CANNOT ENTER SURFACE RUNOFF.

STATE OF TEXAS
RYAN ROY SAYLES
121548
LICENSED
PROFESSIONAL ENGINEER

DocuSigned by:
Ryan Sayles
EBF7BBC5154947E...

3/1/2022

Texas Department of Transportation

NO SCALE

SHEET 2 OF 2

TxDOT STORM WATER POLLUTION PREVENTION PLAN (SW3P)

REV. DATE: 02/27/2014

FHWA DIVISION	PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		IH 20
STATE	COUNTY		SHEET NO.
TEXAS	HOWARD		116
DISTRICT	CONTROL	SECTION	JOB
ABL	0005	05	113, ETC