

|                   |          |                   |             |
|-------------------|----------|-------------------|-------------|
| FED. RD. DIV. NO. | STATE    | PROJECT NO.       | SHEET NO.   |
| 6                 | TEXAS    | F 2023(376), Etc. | 1           |
| STATE DIST. NO.   | COUNTY   | STATE CONTROL NO. | HIGHWAY NO. |
| 23                | LAMPASAS | 2786-01-018, etc  | FM 2657     |

# TEXAS DEPARTMENT OF TRANSPORTATION

## INDEX OF SHEETS

| SHEET NO. | DESCRIPTION              |
|-----------|--------------------------|
| 1         | TITLE SHEET              |
| 2         | SUPPLEMENTAL INDEX SHEET |

## PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

PROJECT NO. F 2023(376), Etc.  
 FM 2657  
 CSJ 2786-01-018, Etc.  
 LAMPASAS COUNTY

FM 2657: DESIGN SPEED 50 MPH  
 FUNCTIONAL CLASS-URBAN COLLECTOR  
 ADT: (2010) (2030)  
 CSJ: 2786-01-018 5300 7420  
 CSJ: 3131-03-013 5300 7420


CONTRACTOR: \_\_\_\_\_  
 LETTING DATE: \_\_\_\_\_  
 DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_  
 DATE WORK WAS COMPLETED AND ACCEPTED: \_\_\_\_\_  
 FINAL CONTRACT COST: \_\_\_\_\_

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

FOR THE CONSTRUCTION OF RESURFACE ROADWAY  
 CONSISTING OF MILL, SEAL COAT, AND ACP OVERLAY

FROM: 0.329 MI. SOUTH OF US190 SOUTH TO 0.1 MI. SOUTH OF COUNTY ROAD 4744  
 NET LENGTH OF PROJECT = 14,377.71 = 2.723 MI.

| CONTROL | 2786-01-018         | 3131-03-013         |
|---------|---------------------|---------------------|
| ROADWAY | 7817.33' = 1.481 mi | 6463.00' = 1.224 mi |
| BRIDGE  | 97.38' = 0.018 mi   | 0.00' = 0.00 mi     |
| TOTAL   | 7914.71' = 1.499 mi | 6463.00' = 1.224 mi |



STA 17+35.29 BEGIN CSJ: 2786-01-018  
 REF MRKR: 384+0.286  
 STA 312+73.59 A 2786-01-018

STA 96+50.00 END CSJ: 2786-01-018  
 STA 96+50.00 BEGIN CSJ: 3131-03-013  
 REF MRKR: 384+1.785  
 STA 25+00.00 A 3131-03-013

PROJECT  
 STA 161+13.00 END CSJ: 3131-03-013  
 REF MRKR: 386+0.944  
 STA. 89+63.00 A 3131-03-013



SUBMITTED FOR LETTING: 11/18/2022

DocuSigned by:  
*AH STG, P.E.*  
 77D14777832626E  
 DISTRICT DESIGN ENGINEER

RECOMMENDED FOR LETTING: 11/18/2022

DocuSigned by:  
*AH STG, P.E.*  
 77D14777832626E  
 DISTRICT DIRECTOR OF TRANSPORTATION  
 PLANNING AND DEVELOPMENT

RECOMMENDED FOR LETTING: 11/18/2022

DocuSigned by:  
 Elias H. Rueli  
 BB9FD402431A4A3  
 DISTRICT ENGINEER

THE CONSTRUCTION WORK WAS PERFORMED IN ACCORDANCE WITH THE PLANS & CONTRACT.

AREA ENGINEER \_\_\_\_\_ P. E. \_\_\_\_\_ DATE \_\_\_\_\_

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

NO EQUATIONS  
 NO EXCEPTIONS  
 NO RAILROAD CROSSINGS

LEVELS DISPLAYED  
 1 16 17 19 111 121 131 141 151 161  
 171 181 192 202 212 22 23 24 26 27 28 29 30 31 32  
 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48  
 49 50 51 52 53 54 55 56 57 58 59 60 61 62  
 FILENAME: brwrtt1e.dgn  
 PLOTTED: sssssssyttime.ssss

# INDEX OF SHEETS

| <u>SHEET NO.</u>                 | <u>DESCRIPTION</u>               | <u>SHEET NO.</u>             | <u>DESCRIPTION</u>         |
|----------------------------------|----------------------------------|------------------------------|----------------------------|
| <b>GENERAL</b>                   |                                  |                              |                            |
| 1                                | TITLE SHEET                      | 36                           | PAVEMENT MARKING STANDARDS |
| 2                                | PROJECT INDEX                    | 37                           | PM(1)-20                   |
| 3-6                              | TYPICAL SECTIONS                 | 38                           | PM(2)-20                   |
| 7-10                             | GENERAL NOTES                    | 39                           | PM(3)-20                   |
| 11                               | ESTIMATE & QUANTITIES            |                              | PM(4)-22                   |
| <br>                             |                                  |                              |                            |
| <b>TRAFFIC CONTROL DETAILS</b>   |                                  |                              |                            |
| 12-13                            | DETOUR TCP                       | <b>ENVIRONMENTAL DETAILS</b> |                            |
| <br>                             |                                  |                              |                            |
| <b>TRAFFIC CONTROL STANDARDS</b> |                                  |                              |                            |
| 14-25                            | BC(1) - BC(12)-21                | 40                           | EPIC                       |
| 26-27                            | TCP(2-4), TCP(2-6)-18            | 41                           | SW3P                       |
| 28                               | TCP(3-2)-13                      |                              |                            |
| 29                               | TCP(3-3)-14                      |                              |                            |
| 30                               | TREATMENT FOR VARIOUS EDGE COND. |                              |                            |
| 31                               | WZ(STPM)-13                      |                              |                            |
| 32                               | WZ(UL)-13                        |                              |                            |
| 33                               | WZ(RS)-22                        |                              |                            |
| <br>                             |                                  |                              |                            |
| <b>ROADWAY DETAILS</b>           |                                  |                              |                            |
| 34                               | PIPE UNDER DRAIN                 |                              |                            |
| <br>                             |                                  |                              |                            |
| <b>PAVEMENT MARKING DETAILS</b>  |                                  |                              |                            |
| 35                               | PAVEMENT MARKING SUMMARY         |                              |                            |

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.



*JH Scantling, P.E.*

11/18/2022


**IH 20  
PROJECT INDEX**



|      |          |          |           |
|------|----------|----------|-----------|
| CONT | SECT     | JOB      | HIGHWAY   |
| 2786 | 01       | 018, ETC | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| 23   | EASTLAND |          | 2         |


DATE: \$DATE\$ \$TIME\$  
FILE: \$FILE\$

DNR:  CK:  DW:  CK:



**EXISTING TYPICAL SECTION #2**

FM 2657  
STA 139+10 TO STA 151+20



**EXISTING TYPICAL STATIONS #1**

FM 2657  
(CSJ: 2786-01-018) STA 17+35.29 TO STA 96+50.00  
(CSJ: 3131-03-013) STA 96+50.00 TO STA 139+10.00



*J.H. Scantling, P.E.*


11/18/2022

**F.M. 2657  
TYPICAL  
SECTION**



| CONT | SECT     | JOB      | HIGHWAY   |
|------|----------|----------|-----------|
| 2786 | 01       | 018 ETC. | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 3         |

DATE: 11/17/2022 5:19:20 PM  
FILE: ...Typical Section.dgn



EXISTING TYPICAL SECTION #3  
 FM 2657  
 STA 151+20 TO STA 161+13.00

DATE: 11/17/2022 5:20:12 PM  
 FILE: ...Typical Section.dgn





11/18/2022

F.M. 2657  
 TYPICAL  
 SECTION



|      |          |          |           |
|------|----------|----------|-----------|
| CONT | SECT     | JOB      | HIGHWAY   |
| 2786 | 01       | 018 ETC. | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 4         |



**FLEXIBLE PAVEMENT STRUCTURE REPAIR DETAIL**

LOCATIONS  
SOUTH BOUND OUTSIDE LANE  
CSJ 2786-01-018 RM 384+0.706 ~ RM 384+0.911 (1241')  
CSJ 2786-01-018 RM 384+1.219 ~ RM 384+1.767 (2888')

LOCATIONS  
NORTH BOUND OUTSIDE LANE  
CSJ 2786-01-018 RM 384+0.706 ~ RM 384+1.785 (4221')  
CSJ 3131-01-013 RM 384+1.785 ~ RM 384+1.909 (655')




11/18/2022

**F.M. 2657  
TYPICAL  
SECTION**



| CONT | SECT | JOB      | HIGHWAY   |
|------|------|----------|-----------|
| 2786 | 01   | 018 ETC. | FM 2657   |
| DIST |      | COUNTY   | SHEET NO. |
| BWD  |      | LAMPASAS | 5         |

DATE: 11/17/2022 5:21:36 PM  
FILE: ...Typical Section.dgn



**PROPOSED TYPICAL SECTION #3**  
 FM 2657  
 STA 151+20 TO STA 161+13.00

**BASE CROWN TABLE**

|            | OFFSET LT | OFFSET RT |
|------------|-----------|-----------|
| STA 140+00 | 36.78'    | 36.78'    |
| STA 141+00 | 35.05'    | 35.78'    |
| STA 142+00 | 33.43'    | 35.41'    |
| STA 143+00 | 31.82'    | 35.04'    |
| STA 144+00 | 30.20'    | 34.67'    |
| STA 145+00 | 28.59'    | 34.30'    |
| STA 146+00 | 26.97'    | 33.93'    |
| STA 147+00 | 25.35'    | 33.56'    |
| STA 148+00 | 23.74'    | 33.19'    |
| STA 149+00 | 22.12'    | 32.82'    |
| STA 150+00 | 22.00'    | 32.44'    |
| STA 151+00 | 18.80'    | 32.07'    |
| STA 152+00 | 19.52'    | 32.00'    |
| STA 153+00 | 18.91'    | 32.00'    |
| STA 154+00 | 18.31'    | 31.60'    |
| STA 155+00 | 17.71'    | 27.82'    |
| STA 156+00 | 17.11'    | 24.31'    |
| STA 157+00 | 16.51'    | 21.40'    |
| STA 158+00 | 15.91'    | 19.10'    |
| STA 159+00 | 15.30'    | 17.45'    |
| STA 160+00 | 14.70'    | 16.40'    |
| STA 161+00 | 14.33'    | 15.66'    |
| STA 161+13 | 14.13'    | 15.31'    |



11/18/2022

**F.M. 2657  
 TYPICAL  
 SECTION**



|      |          |          |           |
|------|----------|----------|-----------|
| CONT | SECT     | JOB      | HIGHWAY   |
| 2786 | 01       | 018 ETC. | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 6         |

DATE: 11/17/2022 5:22:16 PM  
 FILE: ...Typical Section.dgn

**GENERAL NOTES**

(CSJ 2786-01-018) Asphalt Surface Areas-SY

| Item | Description                            | Course               | Roadway |
|------|--|----------------------|---------|
| 351  | PRIME COAT (MC-30)                     | Prime                | 65079   |
| 316  | Asph (CRS-2H OR CRS-2)                 | 1st                  | 65079   |
| 316  | Aggr (TY-B GR-3)(SAC-B)                | 1st                  | 65079   |
| 351  | FLEXIBLE PAVEMENT REPAIR (4")          | Repair               | 15859   |
| 354  | PLANE ASPH CONC PAV (2")               | Plane                | 65079   |
| 3077 | SUPERPAVE MIXTURES SP-C SAC-B PG 76-22 | 2 <sup>nd</sup> Lift | 65079   |

CSJ 2786-01-018) Basis of Estimate

| Item | Description                            | Course               | Rate          | SY    | Quantity    |
|------|--|----------------------|---------------|-------|-------------|
| 310  | Prime Coat (MC-30)                     | Prime                | 0.15 Gal/SY   | 65079 | 9762 Gal    |
| 316  | Asph (CRS-2H OR CRS-2)                 | 1st                  | 0.35 Gal/Sy   | 65079 | 22778 Gal   |
| 316  | Aggr (TY-B GR-3)(SAC-B)                | 1st                  | 125 SY/CY     | 65079 | 521 CY      |
| 351  | FLEXIBLE PAVEMENT REPAIR (4")          | Repair               | --            |       | 15859 SY    |
| 354  | PLANE ASPH CONC PAV (2")               | Plane                | --            | 65079 | 65079 SY    |
| 3077 | SUPERPAVE MIXTURES SP-C SAC-B PG 76-22 | 2 <sup>nd</sup> Lift | 115 lbs/sy/in | 65079 | 7484.1 TONS |

(CSJ 3131-03-013) Asphalt Surface Areas-SY

| Item | Description                   | Course | Roadway |
|------|-------------------------------|--------|---------|
| 310  | Prime Coat (MC-30)            | Prime  | 47585   |
| 316  | Asph (CRS-2H OR CRS-2)        | 1st    | 47585   |
| 316  | Aggr (TY-PB GR-3)(SAC-B)      | 1st    | 47585   |
| 351  | FLEXIBLE PAVEMENT REPAIR (4") | Repair | 1237    |
| 354  | PLANE ASPH CONC PAV (2")      | Plane  | 47585   |

|      |  |                      |       |
|------|--|----------------------|-------|
| 3077 | SUPERPAVE MIXTURES SP-C SAC-B PG 76-22 | 2 <sup>nd</sup> Lift | 47585 |
|------|--|----------------------|-------|

(CSJ 3131-03-013) Basis of Estimate

| Item | Description                            | Course               | Rate          | SY    | Quantity    |
|------|--|----------------------|---------------|-------|-------------|
| 310  | Prime Coat (MC-30)                     | Prime                | 0.35 Gal/SY   | 47585 | 7138 Gal    |
| 316  | Asph (CRS-2H OR CRS-2)                 | 1st                  | 0.35 Gal/Sy   | 47585 | 16655 Gal   |
| 316  | Aggr (TY-PB GR-3)(SAC-B)               | 1st                  | 125 SY/CY     | 47585 | 381 CY      |
| 351  | FLEXIBLE PAVEMENT REPAIR (4")          | Repair               | --            | 1237  | 1237 SY     |
| 351  | PLANE ASPH CONC PAV (2")               | Plane                | --            | 47585 | 47585       |
| 3077 | SUPERPAVE MIXTURES SP-C SAC-B PG 76-22 | 2 <sup>nd</sup> Lift | 115 lbs/sy/in | 47585 | 5472.3 TONS |

The Contractor will not be allowed to store equipment, materials, incidentals, hazardous chemicals, petroleum products, concrete washouts, etc. in the Department's R.O.W. without written permission from the Engineer.

**See the "Environmental" section of the plans for additional information.**

**TEXAS ONE CALL**

Fiber optic cable systems, gas lines, underground power lines, water lines, sewer lines, and other various utilities may be buried within the project limits. Protection of these utility systems is of extreme importance since any break could disrupt service to users resulting in business interruption and loss of revenue and profits. The Contractor will telephone Texas One Call at 1-800-344-8377 (a 24-hour number), to determine if utilities are buried anywhere on the project in accordance with all UNDERGROUND FACILITY DAMAGE PREVENTION AND SAFETY laws. This action; however, will in no way be interpreted as relief of responsibilities under the terms of the Contract as set out in the plans and specifications. Coordinate the repair of all damages caused by daily operations and have facilities restored to service in a timely manner as directed at no additional cost to TxDOT.

**GENERAL**

Unless specifically noted as applying to only a certain project or projects, these general notes will apply to all projects associated to this contract.

Contractor questions on this project are to be addressed to the following individual(s):

| <u>Name</u>    | <u>Email Address</u>   |
|----------------|--|
| Bart Fris P.E. | <a href="mailto:bart.fris@txdot.gov">bart.fris@txdot.gov</a> |

Contractor questions will be accepted through email, phone, and in person by the above individual(s).

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

The term "Article" or "Section" referred to hereon is defined in the forward of the Standard Specifications for Construction and Maintenance of Highways, Streets, And Bridges adopted by the Texas Department of Transportation November 2014.

A "Regulatory Construction Speed Zone" has been requested for this project.

Saw-Cutting with approved equipment as directed by the Engineer will be required at project limits, longitudinally, and/or at notch downs to establish clean and straight joints. This work will not be paid for directly but will be considered subsidiary to various bids.

**ITEM 5 CONTROL OF WORK**

The responsibility for the construction surveying on this contract will be in accordance with Section 5.9.1. "Method A".

**ITEM 6 CONTROL OF MATERIALS**

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. <https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

**ITEM 7 LEGAL RELATIONS AND RESPONSIBILITIES**

No significant traffic generator events identified.

**ITEM 8 PROSECUTION AND PROGRESS**

Working days will be computed and charged in accordance with Section 8.3.1.4. "Standard Workweek".

Work will not be performed without time being charged unless otherwise exempted by the Section as defined above.

Working day charges will be in accordance with **SP 008---002** (60 calendar days after the date of the written authorization to begin work. Do not begin any work before the end of this period unless authorized in writing by the Engineer.) **This delay is for mix design and material production.**

PROJECT SCHEDULES



Critical Path Method (CPM) scheduling will be required to be submitted and maintained monthly by the Contractor unless otherwise directed by the Engineer. (8.5.2.) For monthly submittals, the Contractor will provide the schedule in an Adobe Acrobat compatible format (PDF file). If the Engineer requests the schedule in an electronic format, the Contractor will submit a schedule that is fully compatible with Primavera P6 Professional Release 15.

#### ITEM 9 MEASUREMENT AND PAYMENT

Monthly estimates will be computed from the 28th of the previous month through the 27th of the current month unless otherwise approved in writing by the Engineer.

#### ITEM 310 PRIME COAT

Cure prime placed with a cutback asphalt binder for 21 days before placing subsequent surface courses unless otherwise directed by the Engineer.

Finished base must be dampened before the application of a cutback asphalt binder is placed. This work will not be paid for directly but will be considered subsidiary to Item 310.

#### ITEM 316 SURFACE TREATMENTS

All precoated aggregate will use PG 64-22 asphalt.

Furnish aggregate with a minimum B surface aggregate classification.

Warm season asphalts are not to be placed between September 1<sup>st</sup> and April 30<sup>th</sup> unless otherwise directed/approved.

Protect all existing bridges, and other exposed concrete surfaces within the limits of this project(s), as much as practical, from asphalt materials by any means approved by the Engineer at the contractor's expense.

Use a medium pneumatic roller meeting the requirements of Item 210 as directed by the Engineer. This work will be subsidiary to the various bid items.

#### ITEM 354 PLANING AND TEXTURING PAVEMENT

The planed asphaltic material will become property of the Contractor.

#### ITEM 500 MOBILIZATION

The final 3% mobilization payment will not be paid on the Final Estimate unless all required paperwork and documents are received within 45 calendar days of Final Acceptance.

#### ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING

The Contractor will be required to keep all TCP devices clean. If notified by the Engineer to clean the TCP devices, the Contractor will have until the end of that daylight period to comply. Failure to comply will result in a suspension of all work until the TCP devices are clean. Time will not be suspended.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The Engineer will determine the locations of regulatory construction speed zone signs. The Contractor will furnish, install and remove speed zone signs at locations as directed by the Engineer.

Excavations in Intersections adjacent to travel lanes will not be exposed or open overnight. Backfilling will take place the day excavations are made. The Contractor will be responsible for maintaining the edge of the roadway throughout the project in a traversable condition and/or as directed by the Engineer. Salvaged milling may be used as directed by the Engineer. This work will not be paid for directly and will be considered subsidiary to Item 502 "Barricades, Signs, and Traffic Handling".

All devices shown on the TCP Standards are required and considered subsidiary to Item 502 unless specifically outlined elsewhere in the plans.

All signs will be constructed in accordance with the details shown in the current Standard Highway Sign Designs for Texas manual.

**ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS**

Stockpile sites may be cleared of cover vegetation, but the vegetation root system will not be destroyed.

*It is not anticipated that any erosion, sedimentation, or environmental control devices will be needed on this project. However, in the event that such controls are necessary, the SW3P for this project will consist of the use of any temporary erosion control measures deemed necessary by the Engineer and as provided under this item. Payment for this work will be determined in accordance with Article 4.4, "Changes in the Work".*

**ITEM 662 WORK ZONE PAVEMENT MARKINGS**

Removable work zone pavement markings will be raised pavement markers unless otherwise approved by the Engineer.

Removable work zone pavement markings will be pavement tape markings unless otherwise approved by the Engineer.

Temporary tabs will not be placed on a road more than 24 hours prior to operations beginning on the road.

The temporary tabs will be removed by an acceptable method approved by the Engineer once final striping has been placed.

Temporary tabs will be placed in accordance with WZ (STPM) standard.

**ITEM 666 RETROREFLECTORIZED PAVEMENT MARKINGS**

A mobile retroreflectometer is not required for this project.

**ITEM 672 RAISED PAVEMENT MARKERS**

Place raised pavement markers no sooner than 24 hours after final striping has been placed or as directed.

**ITEM 3077 SUPERPAVE MIXTURES**

Binder substitution is not allowed.

RAP and RAS will not be allowed.

Superpave Mix to be placed in one lift.

Surge Volume and Remixing MTV will be required for this project.

During paving operations; proper adjustment of Surge Volume and Remixing MTV is required to ensure clean pickup of HMAC and to have residual HMAC not be in excess of 1/4" to 3/8" as approved by the Engineer. HMAC will not be dumped in a windrow that is determined by the Engineer to be an excessive distance from the paving operation.

Belly dumps will not be allowed if a spray paver is used.

See item 504 for additional structure requirements located at HMAC plant(s).

**ITEM 6185 TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA)**

Provide the number of vehicles with truck mounted attenuators (TMA) listed in the table below. The Contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

| STANDARD / PHASE | # TMA'S REQUIRED |
|------------------|------------------|
| TCP(2-4)         | 1                |
| TCP(2-6)         | 1                |
| TCP(3-2)         | 3                |
| TCP(3-3)         | 2 or 3           |

Stationary shadow vehicle(s) with TMA are estimated at 88 days for this project. (44 days x 2 TMA's)

Mobile shadow vehicle(s) with TMA are estimated at 96 hours for this project. (6 days x 8 hrs/day x 2 TMA's)



# Estimate & Quantity Sheet


CONTROLLING PROJECT ID 2786-01-018

DISTRICT Brownwood  
HIGHWAY FM 2657

COUNTY Lampasas

| CONTROL SECTION JOB |           |   |      | 2786-01-018 |       | 3131-03-013 |       | TOTAL EST. | TOTAL FINAL |
|---------------------|-----------|---|------|-------------|-------|-------------|-------|------------|-------------|
| PROJECT ID          |           |   |      | A00189838   |       | A00189842   |       |            |             |
| COUNTY              |           |   |      | Lampasas    |       | Lampasas    |       |            |             |
| HIGHWAY             |           |   |      | FM 2657     |       | FM 2657     |       |            |             |
| ALT                 | BID CODE  | DESCRIPTION   | UNIT | EST.        | FINAL | EST.        | FINAL |            |             |
|                     | 310-6012  | PRIME COAT (RC-250)   | GAL  | 13,016.000  |       |             |       | 13,016.000 |             |
|                     | 316-6222  | AGGR(TY-PB GR-3 SAC-B)  | CY   | 543.000     |       | 5,217.000   |       | 5,760.000  |             |
|                     | 316-6226  | AGGR(TY-PB GR-5 SAC-B)  | CY   | 521.000     |       |             |       | 521.000    |             |
|                     | 316-6405  | ASPH (AC-20-5TR OR AC-20XP)                                       | GAL  | 22,777.000  |       | 15,216.000  |       | 37,993.000 |             |
|                     | 354-6045  | PLANE ASPH CONC PAV (2")  | SY   | 65,077.000  |       |             |       | 65,077.000 |             |
|                     | 432-6001  | RIPRAP (CONC)(4 IN)   | CY   | 8.000       |       |             |       | 8.000      |             |
|                     | 500-6001  | MOBILIZATION  | LS   | 1.000       |       |             |       | 1.000      |             |
|                     | 502-6001  | BARRICADES, SIGNS AND TRAFFIC HANDLING                            | MO   | 3.000       |       |             |       | 3.000      |             |
|                     | 556-6007  | PIPE UNDERDRAINS (TY 7) (6")                                      | LF   | 1,057.000   |       |             |       | 1,057.000  |             |
|                     | 662-6109  | WK ZN PAV MRK SHT TERM (TAB)TY W                                  | EA   | 300.000     |       | 639.000     |       | 939.000    |             |
|                     | 662-6111  | WK ZN PAV MRK SHT TERM (TAB)TY Y-2                                | EA   | 984.000     |       | 852.000     |       | 1,836.000  |             |
|                     | 666-6078  | REFL PAV MRK TY I (W)(WORD)(100MIL)                               | EA   | 2.000       |       | 2.000       |       | 4.000      |             |
|                     | 666-6181  | REFL PAV MRK TY II (W) 18" (SLD)                                  | LF   |             |       | 186.000     |       | 186.000    |             |
|                     | 666-6182  | REFL PAV MRK TY II (W) 24" (SLD)                                  | LF   |             |       | 724.000     |       | 724.000    |             |
|                     | 666-6184  | REFL PAV MRK TY II (W) (ARROW)                                    | EA   | 2.000       |       | 2.000       |       | 4.000      |             |
|                     | 666-6300  | RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)                           | LF   | 1,070.000   |       | 2,125.000   |       | 3,195.000  |             |
|                     | 666-6303  | RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)                           | LF   | 4,277.000   |       | 12,272.000  |       | 16,549.000 |             |
|                     | 666-6312  | RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)                           | LF   | 4,277.000   |       | 2,600.000   |       | 6,877.000  |             |
|                     | 666-6315  | RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)                           | LF   | 4,277.000   |       | 14,942.000  |       | 19,219.000 |             |
|                     | 672-6007  | REFL PAV MRKR TY I-C  | EA   | 179.000     |       | 107.000     |       | 286.000    |             |
|                     | 672-6009  | REFL PAV MRKR TY II-A-A   | EA   | 107.000     |       | 311.000     |       | 418.000    |             |
|                     | 3077-6034 | SP MIXESSP-CSAC-B PG76-22   | TON  | 7,483.000   |       | 4,999.000   |       | 12,482.000 |             |
|                     | 6185-6002 | TMA (STATIONARY)  | DAY  | 88.000      |       |             |       | 88.000     |             |
|                     | 6185-6003 | TMA (MOBILE OPERATION)  | HR   | 96.000      |       |             |       | 96.000     |             |
| 18                  |           | SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS   | 1.000       |       |             |       | 1.000      |             |
|                     |           | EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART) | LS   | 1.000       |       |             |       | 1.000      |             |

DATE: 11/18/2022 1:52:23 PM  
 FILE: I:\BWD\SGTEAM\Design Projects\Composos\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4.0\Design\Reference Files\TCPTYPICAL.dgn




### DETOUR TYPICAL SECTION #1

FM 2657

(CSJ: 2786-01-018) STA 17+35.29 TO STA 96+50.00

(CSJ: 3131-03-013) STA 96+50.00 TO STA 139+10.00



### DETOUR TYPICAL SECTION #2

FM 2657

(CSJ: 2786-01-018) STA 17+35.29 TO STA 96+50.00

(CSJ: 3131-03-013) STA 96+50.00 TO STA 139+10.00

**TRAFFIC CONTROL PLAN - DETOUR: SEQUENCE OF WORK WITH PLANNING**

**RECONSTRUCT INDIVIDUAL TRAFFIC LANES**

1. INSTALL PIPE UNDERDRAINS USING TCP(2-4)-18.
2. DETOUR SECTION TYPICAL #1 USING TCP (2-4)-18
  - PLANE ACP 2" SURFACE
  - PAVEMENT STRUCTURE REPAIR
  - 1 CST
  - PLACE WK ZN PAV MRK AND SHT TERM (TAB) WHEN APPLICABLE.
3. DETOUR SECTION TYPICAL #2 USING TCP (2-4)-18
  - PLANE ACP 2" SURFACE
  - PAVEMENT STRUCTURE REPAIR
  - 1 CST
  - PLACE WK ZN PAV MRK AND SHT TERM (TAB) WHEN APPLICABLE.
4. PLACE SUPERPAVE MIXTURE SP-C SAC-B PG76-22 USING TCP(2-4)-18.
5. PLACE WK ZN PAV MRK AND SHT TERM (TAB) WHEN APPLICABLE.
6. FINAL STRIPING PLACED WITHIN 14 DAYS AFTER TABS ARE INSTALLED USING TCP(3-3)-14.

**NOTES:**

ALL OPERATIONS SHALL MOVE IN THE SAME DIRECTION AS THE ADJACENT TRAVEL LANES.  
 PRIOR TO PLACEMENT OF 1 CST CONTRACTOR WILL PREP THE EXPOSED FLEX BASE SURFACE BY SKEETING THE SURFACE WITH WATER, BLADING, AND COMPACTING ANY LOOSE MATERIAL WITH PNEUMATIC AND STEEL WHEEL ROLLERS.  
 WHEN PERFORMING PAVEMENT STRUCTURE REPAIR, CONTRACTOR WILL REMOVE FLEX BASE AND REPLACE WITH ACP TY B THE SAME DAY. OVERNIGHT EDGE CONDITIONS GREATER THAN 2" WILL NOT BE ALLOWED.  
 SHUTTLE BUGGY IS MANDATORY ON THIS PROJECT.  
 PLASTIC DRUMS OR TALL CONES SPACED AT A MAXIMUM DISTANCE OF 50' ON TANGENT FOR DAYTIME OPERATION AND A 3:1 TAPER WILL BE MAINTAINED ONLY AT INTERSECTIONS AND ENTRANCES AND TCP (2-4)-18 SHALL BE UTILIZED. AT LEAST ONE ACCESS POINT SHALL BE OPEN TO EVERY BUSINESS THROUGHOUT THE DAYTIME PAVING

**BARRICADES AND WARNING SIGNS**

1. SEE BC STANDARDS FOR PROJECT LIMIT DEVICES AND WARNING SIGN SPACING (X).
2. DRUMS, PANELS, AND CONES SHALL BE USED AS DIRECTED BY THE ENGINEER.
3. SEE BC, WZ, AND TCP SHEETS FOR ADDITIONAL TRAFFIC CONTROL DETAILS.

| CONSTRUCTION DETOUR | STATION                 | ITEM 0662-6004 WK ZN PAV MRK NON-REMOV (W)4"(SLD) LF | ITEM 0662-6032 WK ZN PAV MRK NON-REMOV (Y)4"(BRK) LF | ITEM 0662-6034 WK ZN PAV MRK NON-REMOV (Y)4"(SLD) LF | ITEM 0662-6111 WK ZN PAV MRK SHT TERM TAB Y-2 EA |
|---------------------|-------------------------|--|--|--|--|
| CSJ: 2786-01-018    |                         |  |  |  |  |
| FM 2657 TYPICAL #1  | 17+35.29.00 TO 96+50.00 |  |  | 15830  | 792  |
| FM 2657 TYPICAL #2  | 17+35.29.00 TO 96+50.00 | 15830  | 3958   | 15830  | 1980   |
| SUBTOTALS           |                         | 15830  | 3958   | 31660  | 2772   |
| CSJ: 3131-03-013    |                         |  |  |  |  |
| FM 2657 TYPICAL #1  | 96+50.00 TO 139+10.00   |  |  | 8520   | 426  |
| FM 2657 TYPICAL #2  | 96+50.00 TO 139+10.00   | 8520   | 2130   | 8520   | 1704   |
| FM 2657 TYPICAL #3  | 139+10.00 TO 151+20.00  |  |  |  | 552  |
| SUBTOTALS           |                         | 8520   | 2130   | 17040  | 2682   |
| TOTALS              |                         | 24350  | 6088   | 48700  | 5454   |

WORK ZONE PAVEMENT MARKINGS SHALL BE PLACED ACCORDING TO THE PAVEMENT MARKING DETAIL SHEETS - WZ(STPM)-13




*J.H. Scantling, P.E.*

11/18/2022

**F.M. 2657  
DETOUR TCP**

DATE: 11/18/2022 9:53:02 AM  
 FILE: I:\BWD\SGTEAM\Design Projects\Composos\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. Design\Reference Files\TCPTYPICAL.dgn



**TRAFFIC CONTROL PLAN - DETOUR: SEQUENCE OF WORK WITH NO PLANNING**

**RECONSTRUCT INDIVIDUAL TRAFFIC LANES**

1. ESTABLISH TRAFFIC CONTROL PLAN TCP (2-4)-18 (LENGTH SHALL BE CONFINED TO A MAXIMUM OF THE PROJECT LENGTH OR CONTRACTORS PROPOSED DAILY PRODUCTION RATE. LENGTH OF THE WORK AREA MAY BE REDUCED BY THE ENGINEER AT ANYTIME.
2. THE FIRST PRODUCTION DAY SHALL BE APPROX. HALF THE LENGTH OF PROJECT. THE ENGINEER WILL DETERMINE IF THE WORK AREA CAN BE INCREASED.
3. PLACE 1 CST
4. PLACE SUPERPAVE MIXTURE SP-C SAC-B PG76-22.
5. PLACE WK ZN PAV MRK SHT TERM (TAB), WHEN APPLICABLE.
6. FINAL STRIPING PLACED WITHIN 14 DAYS AFTER TABS ARE INSTALLED

**BARRICADES AND WARNING SIGNS**

1. SEE BC STANDARDS FOR PROJECT LIMIT DEVICES AND WARNING SIGN SPACING (X).
2. DRUMS, PANELS, AND CONES SHALL BE USED AS DIRECTED BY THE ENGINEER.
3. SEE BC, WZ, AND TCP SHEETS FOR ADDITIONAL TRAFFIC CONTROL DETAILS.



*JH Scantling, P.E.*

12/01/2022

**F.M. 2657  
 DETOUR TCP**



|      |          |          |           |
|------|----------|----------|-----------|
| CONT | SECT     | JOB      | HIGHWAY   |
| 2786 | 01       | 018 ETC. | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 13        |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any person, firm, or organization for the conversion of this standard to any other standard. The design of any project is the responsibility of the designer.

DATE: 9/20/2022 1:27:24 PM  
 FILE: I:\BWPDS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of CR 474\2786-01-018.dgn

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

|  |
|--|
| <p><b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b><br/> <a href="http://www.txdot.gov">http://www.txdot.gov</a></p> |
| COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)  |
| DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)   |
| MATERIAL PRODUCER LIST (MPL)   |
| ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"   |
| STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)   |
| TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)   |
| TRAFFIC ENGINEERING STANDARD SHEETS  |


SHEET 1 OF 12

|  |               |   |
|--|---------------|---|
| <span style="font-size: small; vertical-align: middle;">Texas Department of Transportation</span>        |               | <span style="font-size: x-small;">Traffic<br/>Safety<br/>Division<br/>Standard</span> |
| <p><b>BARRICADE AND CONSTRUCTION<br/>GENERAL NOTES<br/>AND REQUIREMENTS</b></p> <p><b>BC (1) -21</b></p> |               |   |
| FILE:  | bc-21.dgn     | DN: TxDOT   |
| © TxDOT  | November 2002 | ck: TxDOT   |
| REVISIONS  | 2786 01       | JOB   |
| 4-03 7-13  | 018 ETC.      | HIGHWAY   |
| 9-07 8-14  | FM 2657       | SHEET NO.   |
| 5-10 5-21  | BWD           | LAMPASAS  |
|  |               | 14  |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein. South of CR 744 Cr. 0.329 Mi. South of US 77 in Borden County, Texas.

DATE: 12/1/2022 9:53:15 AM  
 FILE: I:\BWDSDTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 77 in Borden County, Texas.dgn


TYPICAL LOCATION OF CROSSROAD SIGNS



## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>


| Sign Number or Series                 | SIZE              |                    | SPACING          |  |
|---------------------------------------|-------------------|--------------------|------------------|--|
|                                       | Conventional Road | Expressway/Freeway | Posted Speed MPH | Sign $\Delta$ Spacing "x"<br>Feet (Apprx.) |
| CW20 <sup>4</sup>                     | 48" x 48"         | 48" x 48"          | 30               | 120  |
| CW21                                  |                   |                    | 35               | 160  |
| CW22                                  |                   |                    | 40               | 240  |
| CW23                                  |                   |                    | 45               | 320  |
| CW25                                  | 36" x 36"         | 48" x 48"          | 50               | 400  |
| CW1, CW2, CW7, CW8, CW9, CW11, CW14   |                   |                    | 55               | 500 <sup>2</sup>                           |
| CW3, CW4, CW5, CW6, CW8-3, CW10, CW12 |                   |                    | 60               | 600 <sup>2</sup>                           |
|                                       |                   |                    | 65               | 700 <sup>2</sup>                           |
|                                       |                   |                    | 70               | 800 <sup>2</sup>                           |
|                                       |                   |                    | 75               | 900 <sup>2</sup>                           |
|                                       | 80                | 1000 <sup>2</sup>  |                  |  |
| * * *                                 | * * *             | * * *              | * * *            |  |

\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.  
 $\Delta$  Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



**LEGEND**

|     |   |
|-----|---|
| —   | Type 3 Barricade  |
| ○○○ | Channelizing Devices  |
| ■   | Sign  |
| x   | See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements. |

NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC (2) - 21**

|                                   |            |                  |               |                  |
|-----------------------------------|------------|------------------|---------------|------------------|
| FILE: bc-21.dgn                   | DWG: TxDOT | CHK: TxDOT       | DWG: TxDOT    | CHK: TxDOT       |
| © TxDOT November 2002             | CONT: 2786 | SECT: 01         | JOB: 018 ETC. | HIGHWAY: FM 2657 |
| REVISIONS: 9-07 8-14<br>7-13 5-21 | DIST: BWD  | COUNTY: LAMPASAS | SHEET NO. 15  |                  |

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

### GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

|                    |                |
|--------------------|----------------|
| 40 mph and greater | 0.2 to 2 miles |
| 35 mph and less    | 0.2 to 1 mile  |
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DATE: 9/20/2022 1:35:06 PM  
 FILE: T:\BWDSS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190\001.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of any information derived from this use.

SHEET 3 OF 12


|   |               |                                  |                  |
|---|---------------|----------------------------------|------------------|
|   |               | Traffic Safety Division Standard |                  |
| <h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2> |               |                                  |                  |
| <h3>BC (3) - 21</h3>                                      |               |                                  |                  |
| FILE:   | bc-21.dgn     | DW:                              | TxDOT            |
| © TxDOT   | November 2002 | CONT SECT                        | JOB HIGHWAY      |
| REVISIONS   |               | 2786 01                          | 018 ETC. FM 2657 |
| 9-07  | 8-14          | DIST                             | COUNTY SHEET NO. |
| 7-13  | 5-21          | BWD                              | LAMPASAS 16      |



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/20/2022 1:37:38 PM  
 FILE: T:\BWDSD\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. DesignStandards\bc-21.dgn


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




**Nails shall NOT be allowed.**  
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



| SHEETING REQUIREMENTS (WHEN USED AT NIGHT) |        |  |
|--|--------|--|
| USAGE                                      | COLOR  | SIGN FACE MATERIAL                               |
| BACKGROUND                                 | RED    | TYPE B OR C SHEETING                             |
| BACKGROUND                                 | ORANGE | TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING |
| LEGEND & BORDER                            | WHITE  | TYPE B OR C SHEETING                             |
| LEGEND & BORDER                            | BLACK  | ACRYLIC NON-REFLECTIVE FILM                      |

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short, duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12

Texas Department of Transportation  
 Traffic Safety Division Standard


**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**

|           |               |         |          |           |         |     |       |     |       |
|-----------|---------------|---------|----------|-----------|---------|-----|-------|-----|-------|
| FILE:     | bc-21.dgn     | DN:     | TxDOT    | CR:       | TxDOT   | OW: | TxDOT | CK: | TxDOT |
| © TxDOT   | November 2002 | CONT    | SECT     | JOB       | HIGHWAY |     |       |     |       |
| REVISIONS |               | 2786 01 | 018 ETC. | FM 2657   |         |     |       |     |       |
| 9-07      | 8-14          | DIST    | COUNTY   | SHEET NO. |         |     |       |     |       |
| 7-13      | 5-21          | BWD     | LAMPASAS | 17        |         |     |       |     |       |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats, including electronic formats, or for any errors or omissions resulting from its use.

DATE: 9/20/2022 1:39:11 PM  
 FILE: T:\BWDSDTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi., South of US 190 To 0.1 Mi., South of CR 4744\4. Design\Standards\BC-21.dgn




**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS




**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**WEDGE ANCHORS**

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

**GENERAL NOTES**

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- \* See BC(4) for definition of "Work Duration."
- \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC(5) - 21**

|           |               |          |          |           |         |     |       |     |       |
|-----------|---------------|----------|----------|-----------|---------|-----|-------|-----|-------|
| FILE:     | bc-21.dgn     | DN:      | TxDOT    | CK:       | TxDOT   | DW: | TxDOT | CR: | TxDOT |
| © TxDOT   | November 2002 | CONT     | SECT     | JOB       | HIGHWAY |     |       |     |       |
| REVISIONS | 2786 01       | 018 ETC. | FM       | 2657      |         |     |       |     |       |
| 9-07      | 8-14          | DIST     | COUNTY   | SHEET NO. |         |     |       |     |       |
| 7-13      | 5-21          | BWD      | LAMPASAS | 18        |         |     |       |     |       |

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

|                       |                          |
|-----------------------|--------------------------|
| FREEWAY CLOSED X MILE | FRONTAGE ROAD CLOSED     |
| ROAD CLOSED AT SH XXX | SHOULDER CLOSED XXX FT   |
| ROAD CLSD AT FM XXXX  | RIGHT LN CLOSED XXX FT   |
| RIGHT X LANES CLOSED  | RIGHT X LANES OPEN       |
| CENTER LANE CLOSED    | DAYTIME LANE CLOSURES    |
| NIGHT LANE CLOSURES   | I-XX SOUTH EXIT CLOSED   |
| VARIOUS LANES CLOSED  | EXIT XXX CLOSED X MILE   |
| EXIT CLOSED           | RIGHT LN TO BE CLOSED    |
| MALL DRIVEWAY CLOSED  | X LANES CLOSED TUE - FRI |
| XXXXXXXX BLVD CLOSED  |                          |

### Other Condition List

|                          |                         |
|--------------------------|-------------------------|
| ROADWORK XXX FT          | ROAD REPAIRS XXXX FT    |
| FLAGGER XXXX FT          | LANE NARROWS XXXX FT    |
| RIGHT LN NARROWS XXXX FT | TWO-WAY TRAFFIC XX MILE |
| MERGING TRAFFIC XXXX FT  | CONST TRAFFIC XXX FT    |
| LOOSE GRAVEL XXXX FT     | UNEVEN LANES XXXX FT    |
| DETOUR X MILE            | ROUGH ROAD XXXX FT      |
| ROADWORK PAST SH XXXX    | ROADWORK NEXT FRI-SUN   |
| BUMP XXXX FT             | US XXX EXIT X MILES     |
| TRAFFIC SIGNAL XXXX FT   | LANES SHIFT *           |

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

|                      |                      |
|----------------------|----------------------|
| MERGE RIGHT          | FORM X LINES RIGHT   |
| DETOUR NEXT X EXITS  | USE XXXXX RD EXIT    |
| USE EXIT XXX         | USE EXIT I-XX NORTH  |
| STAY ON US XXX SOUTH | USE I-XX E TO I-XX N |
| TRUCKS USE US XXX N  | WATCH FOR TRUCKS     |
| WATCH FOR TRUCKS     | EXPECT DELAYS        |
| EXPECT DELAYS        | PREPARE TO STOP      |
| REDUCE SPEED XXX FT  | END SHOULDER USE     |
| USE OTHER ROUTES     | WATCH FOR WORKERS    |
| STAY IN LANE *       |                      |

### Location List

|                          |
|--------------------------|
| AT FM XXXX               |
| BEFORE RAILROAD CROSSING |
| NEXT X MILES             |
| PAST US XXX EXIT         |
| XXXXXXXX TO XXXXXX       |
| US XXX TO FM XXXX        |

### Warning List

|                       |
|-----------------------|
| SPEED LIMIT XX MPH    |
| MAXIMUM SPEED XX MPH  |
| MINIMUM SPEED XX MPH  |
| ADVISORY SPEED XX MPH |
| RIGHT LANE EXIT       |
| USE CAUTION           |
| DRIVE SAFELY          |
| DRIVE WITH CARE       |

### \*\* Advance Notice List

|                       |
|-----------------------|
| TUE-FRI XX AM-X PM    |
| APR XX-XX X PM-X AM   |
| BEGINS MONDAY         |
| BEGINS MAY XX         |
| MAY X-X XX PM - XX AM |
| NEXT FRI-SUN          |
| XX AM TO XX PM        |
| NEXT TUE AUG XX       |
| TONIGHT XX PM-XX AM   |

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats for use in other states. Design Standards BC-21.dgn


| WORD OR PHRASE         | ABBREVIATION | WORD OR PHRASE | ABBREVIATION |
|------------------------|--------------|----------------|--------------|
| Access Road            | ACCS RD      | Major          | MAJ          |
| Alternate              | ALT          | Miles          | MI           |
| Avenue                 | AVE          | Miles Per Hour | MPH          |
| Best Route             | BEST RTE     | Minor          | MNR          |
| Boulevard              | BLVD         | Monday         | MON          |
| Bridge                 | BRDG         | Normal         | NORM         |
| Canal                  | CANT         | North          | N            |
| Center                 | CTR          | Northbound     | (route) N    |
| Construction Ahead     | CONST AHD    | Parking        | PKING        |
| CROSSING               | XING         | Road           | RD           |
| Detour Route           | DETOUR RTE   | Right Lane     | RT LN        |
| Do Not                 | DONT         | Saturday       | SAT          |
| East                   | E            | Service Road   | SERV RD      |
| Eastbound              | (route) E    | Shoulder       | SHLDR        |
| Emergency              | EMER         | Slippery       | SLIP         |
| Emergency Vehicle      | EMER VEH     | South          | S            |
| Entrance, Enter        | ENT          | Southbound     | (route) S    |
| Express Lane           | EXP LN       | Speed          | SPD          |
| Expressway             | EXPWY        | Street         | ST           |
| XXXX Feet              | XXXX FT      | Sunday         | SUN          |
| Fog Ahead              | FOG AHD      | Telephone      | PHONE        |
| Freeway                | FRWY, FWY    | Temporary      | TEMP         |
| Freeway Blocked        | FWY BLKD     | Thursday       | THURS        |
| Friday                 | FRI          | To Downtown    | TO DWNTN     |
| Hazardous Driving      | HAZ DRIVING  | Traffic        | TRAF         |
| Hazardous Material     | HAZMAT       | Travelers      | TRVLR        |
| High-Occupancy Vehicle | HOV          | Tuesday        | TUES         |
| Highway                | HWY          | Time Minutes   | TIME MIN     |
| Hour(s)                | HR, HRS      | Upper Level    | UPR LEVEL    |
| Information            | INFO         | Vehicles (s)   | VEH, VEHS    |
| It Is                  | ITS          | Warning        | WARN         |
| Junction               | JCT          | Wednesday      | WED          |
| Left                   | LFT          | Weight Limit   | WT LIMIT     |
| Left Lane              | LFT LN       | West           | W            |
| Lane Closed            | LN CLOSED    | Westbound      | (route) W    |
| Lower Level            | LWR LEVEL    | Wet Pavement   | WET PVMT     |
| Maintenance            | MAINT        | Will Not       | WONT         |

Roadway designation # IH-number, US-number, SH-number, FM-number

|   |               |            |          |
|---|---------------|------------|----------|
|   |               |            |          |
| <h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3> |               |            |          |
| <h2>BC (6) - 21</h2>  |               |            |          |
| FILE:   | bc-21.dgn     | DN:        | TxDOT    |
| © TxDOT   | November 2002 | CONT:      | 2786     |
| REVISIONS   |               | SECT:      | 01       |
| 9-07  | 8-14          | JOB:       | 018 ETC. |
| 7-13  | 5-21          | HIGHWAY:   | FM 2657  |
|   |               | DIST:      | BWD      |
|   |               | COUNTY:    | LAMPASAS |
|   |               | SHEET NO.: | 19       |


DATE: 9/20/2022 1:44:42 PM  
 FILE: T:\BWDSD\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 MI. South of US 190 to 0.1 Mi. South of CR 4744\4. DesignStandards\bc-21.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**  
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

| REQUIREMENTS |              |                               |                             |
|--------------|--------------|-------------------------------|-----------------------------|
| TYPE         | MINIMUM SIZE | MINIMUM NUMBER OF PANEL LAMPS | MINIMUM VISIBILITY DISTANCE |
| B            | 30 x 60      | 13                            | 3/4 mile                    |
| C            | 48 x 96      | 15                            | 1 mile                      |

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

|           |               |      |          |           |         |     |       |     |       |
|-----------|---------------|------|----------|-----------|---------|-----|-------|-----|-------|
| FILE:     | bc-21.dgn     | DN:  | TxDOT    | CR:       | TxDOT   | OW: | TxDOT | CK: | TxDOT |
| © TxDOT   | November 2002 | CONT | SECT     | JOB       | HIGHWAY |     |       |     |       |
| REVISIONS |               | 2786 | 01       | 018 ETC.  | FM 2657 |     |       |     |       |
| 9-07      | 8-14          | DIST | COUNTY   | SHEET NO. |         |     |       |     |       |
| 7-13      | 5-21          | BWD  | LAMPASAS | 20        |         |     |       |     |       |

DATE: 9/20/2022 1:45:50 PM  
 FILE: T:\BWDSDTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. DesignStandards\bc-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.



**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

|           |               |      |          |           |         |     |       |     |       |
|-----------|---------------|------|----------|-----------|---------|-----|-------|-----|-------|
| FILE:     | bc-21.dgn     | DN:  | TxDOT    | CR:       | TxDOT   | OW: | TxDOT | CK: | TxDOT |
| © TxDOT   | November 2002 | CONT | SECT     | JOB       | HIGHWAY |     |       |     |       |
| REVISIONS |               | 2786 | 01       | 018 ETC.  | FM 2657 |     |       |     |       |
| 4-03      | 8-14          | DIST | COUNTY   | SHEET NO. |         |     |       |     |       |
| 9-07      | 5-21          | BWD  | LAMPASAS | 21        |         |     |       |     |       |
| 7-13      |               |      |          |           |         |     |       |     |       |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/20/2022 1:46:30 PM  
 FILE: T:\BWDSD\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. Design\Standards\bc-21.dgn



**FIXED**  
(Rigid or self-righting)

**DRIVEABLE**




(Rigid or self-righting)

**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

| Posted Speed | Formula                  | Minimum Desirable Taper Lengths * * |            |            | Suggested Maximum Spacing of Channelizing Devices |              |
|--------------|--------------------------|-------------------------------------|------------|------------|---|--------------|
|              |                          | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |
| 30           | L = WS <sup>2</sup> / 60 | 150'                                | 165'       | 180'       | 30'   | 60'          |
| 35           |                          | 205'                                | 225'       | 245'       | 35'   | 70'          |
| 40           |                          | 265'                                | 295'       | 320'       | 40'   | 80'          |
| 45           | L = WS                   | 450'                                | 495'       | 540'       | 45'   | 90'          |
| 50           |                          | 500'                                | 550'       | 600'       | 50'   | 100'         |
| 55           |                          | 550'                                | 605'       | 660'       | 55'   | 110'         |
| 60           |                          | 600'                                | 660'       | 720'       | 60'   | 120'         |
| 65           |                          | 650'                                | 715'       | 780'       | 65'   | 130'         |
| 70           |                          | 700'                                | 770'       | 840'       | 70'   | 140'         |
| 75           |                          | 750'                                | 825'       | 900'       | 75'   | 150'         |
| 80           |                          | 800'                                | 880'       | 960'       | 80'   | 160'         |

\* \* \* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

|           |               |      |          |           |       |         |       |     |       |
|-----------|---------------|------|----------|-----------|-------|---------|-------|-----|-------|
| FILE:     | bc-21.dgn     | DN:  | TxDOT    | CK:       | TxDOT | DW:     | TxDOT | CK: | TxDOT |
| © TxDOT   | November 2002 | CONT | SECT     | JOB       | SECT  | HIGHWAY |       |     |       |
| REVISIONS | 2786          | 01   | 018 ETC. | FM        | 2657  |         |       |     |       |
| 9-07      | 8-14          | DIST | COUNTY   | SHEET NO. |       |         |       |     |       |
| 7-13      | 5-21          | BWD  | LAMPASAS | 22        |       |         |       |     |       |

DATE: 9/20/2022 1:47:15 PM  
 FILE: T:\BWDSS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. DesignStandards\bc-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

Each roadway of a divided highway shall be barricaded in the same manner.



**PERSPECTIVE VIEW**


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




**PLAN VIEW**

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



**PERSPECTIVE VIEW**




**PLAN VIEW**

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

| LEGEND |   |
|--------|---|
|        | Plastic drum  |
|        | Plastic drum with steady burn light or yellow warning reflector |
|        | Steady burn warning light or yellow warning reflector           |

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**



**Two-Piece cones**

**One-Piece cones**

**Tubular Marker**

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

|                       |           |           |           |           |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn       | DN: TxDOT | CK: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT      | SECT      | JOB       | HIGHWAY   |
| REVISIONS             | 2786      | 01        | 018 ETC.  | FM 2657   |
| 9-07 8-14             | DIST      | COUNTY    | SHEET NO. |           |
| 7-13 5-21             | BWD       | LAMPASAS  | 23        |           |

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

| DEPARTMENTAL MATERIAL SPECIFICATIONS                 |          |
|--|----------|
| PAVEMENT MARKERS (REFLECTORIZED)                     | DMS-4200 |
| TRAFFIC BUTTONS                                      | DMS-4300 |
| EPOXY AND ADHESIVES                                  | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS             | DMS-6130 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS            | DMS-8240 |
| TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS   | DMS-8242 |

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**

|                       |           |           |           |           |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn       | DN: TxDOT | CR: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT February 1998 | CONT      | SECT      | JOB       | HIGHWAY   |
| REVISIONS             | 2786      | 01        | 018 ETC.  | FM 2657   |
| 2-98 9-07 5-21        | DIST      | COUNTY    | SHEET NO. |           |
| 1-02 7-13             | BWD       | LAMPASAS  | 24        |           |
| 11-02 8-14            |           |           |           |           |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 9/20/2022 1:47:57 PM  
 FILE: T:\BWDSDSTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. DesignStandards\bc-21.dgn



## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS



BC(12)-21

|                      |           |           |           |           |
|----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn      | DN: TxDOT | CK: TxDOT | OW: TxDOT | CR: TxDOT |
| ©TxDOT February 1998 | CONT      | SECT      | JOB       | HIGHWAY   |
| REVISIONS            | 2786      | 01        | 018 ETC.  | FM 2657   |
| 1-97 9-07 5-21       |           |           |           |           |
| 2-98 7-13            |           |           |           |           |
| 11-02 8-14           |           |           |           |           |
| DIST                 | COUNTY    | SHEET NO. |           |           |
| BWD                  | LAMPASAS  | 25        |           |           |

DATE: 9/20/2022 1:48:35 PM  
 FILE: I:\BWD\SGTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. Design\Standards\bc-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard after its effective date.

DATE: 9/20/2022 3:42:23 PM  
 FILE: T:\BWD\SGTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 474 near 474 and 474



**LEGEND**

|  |                                      |  |   |
|--|--------------------------------------|--|---|
|  | Type 3 Barricade                     |  | Channelizing Devices                    |
|  | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|  | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|  | Sign                                 |  | Traffic Flow                            |
|  | Flag                                 |  | Flagger                                 |

| Posted Speed * | Formula                  | Minimum Desirable Taper Lengths ** |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
|                |                          | 10' Offset                         | 11' Offset | 12' Offset | On a Taper  | On a Tangent |                                   |   |
| 30             | L = WS <sup>2</sup> / 60 | 150'                               | 165'       | 180'       | 30'   | 60'          | 120'                              | 90'                                     |
| 35             |                          | 205'                               | 225'       | 245'       | 35'   | 70'          | 160'                              | 120'                                    |
| 40             |                          | 265'                               | 295'       | 320'       | 40'   | 80'          | 240'                              | 155'                                    |
| 45             | L = WS                   | 450'                               | 495'       | 540'       | 45'   | 90'          | 320'                              | 195'                                    |
| 50             |                          | 500'                               | 550'       | 600'       | 50'   | 100'         | 400'                              | 240'                                    |
| 55             |                          | 550'                               | 605'       | 660'       | 55'   | 110'         | 500'                              | 295'                                    |
| 60             |                          | 600'                               | 660'       | 720'       | 60'   | 120'         | 600'                              | 350'                                    |
| 65             |                          | 650'                               | 715'       | 780'       | 65'   | 130'         | 700'                              | 410'                                    |
| 70             |                          | 700'                               | 770'       | 840'       | 70'   | 140'         | 800'                              | 475'                                    |
| 75             |                          | 750'                               | 825'       | 900'       | 75'   | 150'         | 900'                              | 540'                                    |

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**TYPICAL USAGE**

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
|        |                | ✓                     | ✓                            |                      |

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

**TCP (2-4a)**

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

**TCP (2-4b)**

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.


Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
 LANE CLOSURES ON MULTILANE  
 CONVENTIONAL ROADS**


**TCP (2-4) - 18**

|                       |      |          |           |         |
|-----------------------|------|----------|-----------|---------|
| FILE: tcp2-4-18.dgn   | DN:  | CK:      | DW:       | CK:     |
| © TxDOT December 1985 | CONT | SECT     | JOB       | HIGHWAY |
| REVISIONS             | 2786 | 01       | 018 ETC.  | FM 2657 |
| 8-95 3-03             | DIST | COUNTY   | SHEET NO. |         |
| 1-97 2-12             | BWD  | LAMPASAS | 26        |         |
| 4-98 2-18             |      |          |           |         |


DATE: 9/20/2022 3:44:13 PM  
 FILE: T:\BWD\SS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 474 near the intersection of Highway 474 and Highway 100.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any other project.



TCP (2-6a)  
**ONE LANE CLOSURE**



TCP (2-6b)  
**LANE CLOSURE NEAR EXIT RAMP**



TCP (2-6c)  
**LANE CLOSURE NEAR ENTRANCE RAMP**

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed * | Formula               | Minimum Desirable Taper Lengths ** |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
|                |                       | 10' Offset                         | 11' Offset | 12' Offset | On a Taper  | On a Tangent |                                   |   |
| 30             | $L = \frac{WS^2}{60}$ | 150'                               | 165'       | 180'       | 30'   | 60'          | 120'                              | 90'                                     |
| 35             |                       | 205'                               | 225'       | 245'       | 35'   | 70'          | 160'                              | 120'                                    |
| 40             |                       | 265'                               | 295'       | 320'       | 40'   | 80'          | 240'                              | 155'                                    |
| 45             | L = WS                | 450'                               | 495'       | 540'       | 45'   | 90'          | 320'                              | 195'                                    |
| 50             |                       | 500'                               | 550'       | 600'       | 50'   | 100'         | 400'                              | 240'                                    |
| 55             |                       | 550'                               | 605'       | 660'       | 55'   | 110'         | 500'                              | 295'                                    |
| 60             |                       | 600'                               | 660'       | 720'       | 60'   | 120'         | 600'                              | 350'                                    |
| 65             |                       | 650'                               | 715'       | 780'       | 65'   | 130'         | 700'                              | 410'                                    |
| 70             |                       | 700'                               | 770'       | 840'       | 70'   | 140'         | 800'                              | 475'                                    |
| 75             |                       | 750'                               | 825'       | 900'       | 75'   | 150'         | 900'                              | 540'                                    |

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               |                |                       | ✓                            | ✓                    |

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
  - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
  - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
  - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation  
 Traffic Operations Division Standard



## TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

### TCP (2-6) - 18



|                       |      |          |           |         |
|-----------------------|------|----------|-----------|---------|
| FILE: tcp2-6-18.dgn   | DN:  | CK:      | DW:       | CK:     |
| © TxDOT December 1985 | CONT | SECT     | JOB       | HIGHWAY |
| REVISIONS             | 2786 | 01       | 018 ETC.  | FM 2657 |
| 2-94 4-98             | DIST | COUNTY   | SHEET NO. |         |
| 8-95 2-12             | BWD  | LAMPASAS | 27        |         |
| 1-97 2-18             |      |          |           |         |

166

DATE: 9/20/2022 3:45:53 PM  
 FILE: I:\BWDSS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 474 near the intersection of Highway 474 and Highway 100.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other software or file formats.



**RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)**



**INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)**


| LEGEND |                                |                     |   |  |
|--------|--------------------------------|---------------------|---|--|
| *      | Trail Vehicle                  | ARROW BOARD DISPLAY |   |  |
| **     | Shadow Vehicle                 |                     |   |  |
| ***    | Work Vehicle                   |                     | RIGHT Directional                               |  |
|        | Heavy Work Vehicle             |                     | LEFT Directional                                |  |
|        | Truck Mounted Attenuator (TMA) |                     | Double Arrow                                    |  |
|        | Traffic Flow                   |                     | CAUTION (Alternating Diamond or 4 Corner Flash) |  |

| TYPICAL USAGE                       |                          |                          |                              |                          |
|-------------------------------------|--------------------------|--------------------------|------------------------------|--------------------------|
| MOBILE                              | SHORT DURATION           | SHORT TERM STATIONARY    | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY     |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/>     | <input type="checkbox"/> |

**GENERAL NOTES**









- ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
- For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
- Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
- The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
- Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
- The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.



**STRIPING FOR TMA**

|  |           |   |           |
|--|-----------|---|-----------|
|  |           | <b>Traffic Operations Division Standard</b> |           |
| <b>TRAFFIC CONTROL PLAN<br/>MOBILE OPERATIONS<br/>DIVIDED HIGHWAYS</b> |           |   |           |
| <b>TCP(3-2)-13</b>   |           |   |           |
| FILE: tcp3-2.dgn   | DN: TxDOT | CK: TxDOT                                   | DW: TxDOT |
| © TxDOT December 1985  | CONT      | SECT  | JOB       |
| REVISIONS  | 2786 01   | 018 ETC.                                    | FM 2657   |
| 2-94 4-98  | DIST      | COUNTY                                      | SHEET NO. |
| 8-95 7-13  | BWD       | LAMPASAS                                    | 28        |
| 1-97   |           |   |           |

DATE: 9/20/2022 3:47:25 PM  
 FILE: T:\BWPDS\TEAM\Design Projects\Lampasos\2786-01-018 - 0.329 Mi. South of Highway 49 at 74 near 49th Street\Traffic Control Plan.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other software applications.



| LEGEND            |                     |   |
|-------------------|---------------------|---|
| * Trail Vehicle   | ARROW BOARD DISPLAY |   |
| ** Shadow Vehicle |                     |   |
| *** Work Vehicle  |                     | RIGHT Directional                               |
|                   |                     | LEFT Directional                                |
|                   |                     | Double Arrow                                    |
|                   |                     | CAUTION (Alternating Diamond or 4 Corner Flash) |

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| ✓             |                |                       |                              |                      |

**GENERAL NOTES**

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN  
MOBILE OPERATIONS  
RAISED PAVEMENT  
MARKER INSTALLATION/  
REMOVAL  
TCP (3-3) - 14**

|                        |           |           |           |           |
|------------------------|-----------|-----------|-----------|-----------|
| FILE: tcp3-3.dgn       | DN: TxDOT | CK: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT September 1987 | CONT      | SECT      | JOB       | HIGHWAY   |
| 2-94 4-98              | 2786 01   | 018 ETC.  | FM 2657   |           |
| 8-95 7-13              | DIST      | COUNTY    | SHEET NO. |           |
| 1-97 7-14              | BWD       | LAMPASAS  | 29        |           |



DATE: 9/20/2022 3:49:30 PM  
 FILE: I:\BWDSDTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. DesignStandards\TREATMENT FOR VARIOUS EDGE CONDITIONS.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

### DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS


Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet





Edge Condition I  
S = (3:1) (or flatter)



Edge Condition II  
S = ((2.99):1) to (1:1)



Edge Condition III  
S is steeper than (1:1)



#### FACTORS CONSIDERED IN THE GUIDELINES:

- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8T "Narrow Lanes Ahead" sign), or 2) provide an edge slope such as Edge Condition 1.


#### Zone Treatment Types Guidelines:

- | Zone | Treatment Types Guidelines:   |
|------|---|
| ①    | No treatment.   |
| ②    | CW 8-17 "Shoulder Drop-Off <Symbol>" with CW 8-17P "Shoulder Drop-Off <Plaque>" or CW 8-11 "Uneven Lanes" signs.  |
| ③    | CW 8-17 with CW 8-17P or CW 8-11 signs plus vertical panels.  |
| ④    | CW 8-17 with CW 8-17P or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge fill may be provided to change the edge slope to that of the preferable Edge Condition 1. |
| ⑤    | Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone-4 may be used after consideration of other applicable factors.                                 |

#### Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ( [Cross-hatched symbol] )



- $E = ADT \times T$   
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within a lateral offset of 20 feet from the edge of the travel lane.



*A.H. Scantling, P.E.*

11/18/2022

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exist parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's online manuals.




## TREATMENT FOR VARIOUS EDGE CONDITIONS

|                                |      |           |           |           |           |
|--------------------------------|------|-----------|-----------|-----------|-----------|
| © TxDOT August 2000            |      | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| REVISIONS                      |      |           |           |           |           |
| 03-01                          | 2786 | 01        | 018 ETC.  | FM        | 2657      |
| 08-01 correct typos            |      |           |           |           |           |
| 11-13 update sign nomenclature | BWD  |           | LAMPASAS  |           | 30        |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard after its publication.

DATE: 9/20/2022 3:51:30 PM  
 FILE: T:\BWDSS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 74 near 495\STPM\113.dgn

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:  
[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)







## WORK ZONE SHORT TERM PAVEMENT MARKINGS

### WZ (STPM) - 13

|            |               |       |       |         |          |            |          |     |       |
|------------|---------------|-------|-------|---------|----------|------------|----------|-----|-------|
| FILE:      | wzstpm-13.dgn | DN:   | TxDOT | CK:     | TxDOT    | DW:        | TxDOT    | CK: | TxDOT |
| © TxDOT    | April 1992    | CONT: | 2786  | SECT:   | 01       | JOB:       | 018 ETC. | FM: | 2657  |
| REVISIONS: |               | DIST: | BWD   | COUNTY: | LAMPASAS | SHEET NO.: | 31       |     |       |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units of measurements. The use of this standard is subject to the terms and conditions of the contract. DATE: 9/20/2022 3:53:01 PM FILE: T:\BWDSS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of this station\Signing\Signing Plans\Signing Plans.dgn



| DEPARTMENTAL MATERIAL SPECIFICATIONS                  |          |
|---|----------|
| PERMANENT PREFABRICATED PAVEMENT MARKINGS             | DMS-8240 |
| TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| SIGN FACE MATERIALS                                   | DMS-8300 |

| COLOR  | USAGE            | SHEETING MATERIAL                                     |
|--------|------------------|---|
| ORANGE | BACKGROUND       | TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING |
| BLACK  | LEGEND & BORDERS | ACRYLIC NON-REFLECTIVE SHEETING                       |

**GENERAL NOTES**

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

| TABLE 1        |   |                   |
|----------------|---|-------------------|
| Edge Condition | Edge Height (D)   | * Warning Devices |
| ①              | Less than or equal to:<br>1/4" (maximum-planing)<br>1/2" (typical-overlay)  | Sign: CW8-11      |
| ②              | Less than or equal to 3"  | Sign: CW8-11      |
| ③              | Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3". |                   |

**TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.**

| MINIMUM WARNING SIGN SIZE              |           |
|--|-----------|
| Conventional roads                     | 36" x 36" |
| Freeways/expressways, divided roadways | 48" x 48" |

**Texas Department of Transportation** Traffic Operations Division Standard

## SIGNING FOR UNEVEN LANES

### WZ (UL) - 13


|                    |           |           |           |           |
|--------------------|-----------|-----------|-----------|-----------|
| FILE: wzu1-13.dgn  | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT April 1992 | CONT      | SECT      | JOB       | HIGHWAY   |
| REVISIONS          | 2786 01   | 018 ETC.  | FM 2657   |           |
| 8-95 2-98 7-13     | DIST      | COUNTY    | SHEET NO. |           |
| 1-97 3-03          | BWD       | LAMPASAS  | 32        |           |




DATE: 9/20/2022 3:55:14 PM  
 FILE: T:\BWDSD\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 49 at 74th Street\Drawings\RS\22-1.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

| Flagger to Flagger (Length of Work Area) | ADT     | # of Rumble Strip Arrays |
|--|---------|--------------------------|
| 1/8 Mile                                 | < 4,500 | 1                        |
|  | ≥ 4,500 | 2                        |
| 1/4 Mile                                 | < 3,500 | 1                        |
|  | ≥ 3,500 | 2                        |
| 1/2 Mile                                 | < 2,600 | 1                        |
|  | ≥ 2,600 | 2                        |
| 1 Mile                                   | < 1,600 | 1                        |
|  | ≥ 1,600 | 2                        |
| > 1 Mile                                 | N/A     | 2                        |



**RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION**



**RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY**

**GENERAL NOTES**

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

| Speed               | Approximate distance between strips in an array |
|---------------------|---|
| ≤ 40 MPH            | 10'   |
| > 40 MPH & ≤ 55 MPH | 15'   |
| = 60 MPH            | 20'   |
| ≥ 65 MPH            | * 35' +   |

|  |                                      |  |   |
|--|--------------------------------------|--|---|
|  | Type 3 Barricade                     |  | Channelizing Devices                    |
|  | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|  | Trailer Mounted Flashing Arrow Panel |  | Portable Changeable Message Sign (PCMS) |
|  | Sign                                 |  | Traffic Flow                            |
|  | Flag                                 |  | Flagger                                 |

| Posted Speed * | Formula   | Minimum Desirable Taper Lengths ** |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
|                |           | 10' Offset                         | 11' Offset | 12' Offset | On a Taper  | On a Tangent |                                   |   |
| 30             | L = WS/60 | 150'                               | 165'       | 180'       | 30'   | 60'          | 120'                              | 90'                                     |
| 35             |           | 205'                               | 225'       | 245'       | 35'   | 70'          | 160'                              | 120'                                    |
| 40             |           | 265'                               | 295'       | 320'       | 40'   | 80'          | 240'                              | 155'                                    |
| 45             | L = WS    | 450'                               | 495'       | 540'       | 45'   | 90'          | 320'                              | 195'                                    |
| 50             |           | 500'                               | 550'       | 600'       | 50'   | 100'         | 400'                              | 240'                                    |
| 55             |           | 550'                               | 605'       | 660'       | 55'   | 110'         | 500'                              | 295'                                    |
| 60             |           | 600'                               | 660'       | 720'       | 60'   | 120'         | 600'                              | 350'                                    |
| 65             |           | 650'                               | 715'       | 780'       | 65'   | 130'         | 700'                              | 410'                                    |
| 70             |           | 700'                               | 770'       | 840'       | 70'   | 140'         | 800'                              | 475'                                    |
| 75             |           | 750'                               | 825'       | 900'       | 75'   | 150'         | 900'                              | 540'                                    |

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT)  
 S=Posted Speed (MPH)

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
|        | ✓              | ✓                     |                              |                      |

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.  
 \* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.






Texas Department of Transportation  
 Traffic Safety Division Standard

## TEMPORARY RUMBLE STRIPS

### WZ (RS) - 22

|                       |           |           |           |           |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: wzrs22.dgn      | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT November 2012 | CONT      | SECT      | JOB       | HIGHWAY   |
| REVISIONS             | 2786      | 01        | 018 ETC.  | FM 2657   |
| 2-14 1-22             | DIST      | COUNTY    | SHEET NO. |           |
| 4-16                  | BWD       | LAMPASAS  | 33        |           |



DATE: 11/17/2022 4:58:29 PM  
 FILE: I:\BWD\SCTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 3594\Reference Files\ROADWAY DETAILS.dgn



**PIPE UNDERDRAIN DETAILS  
 OUTSIDE PAVEMENT STRUCTURE**

The pipe underdrain that maintenance installed behind the curb is located from RM 384+1.34 to RM 384+1.40. The pipe underdrain needs to be lengthed to the west side of road starting at CR 3594 RM 384+1.43 to RM 384+1.50 ending at CR 4889. On the East side of road pipe underdrains needed from RM 384+1.34 to RM 384+1.47 ending roughly across from CR 4889. Locations may be adjusted as required by the Engineer.

**PIPE UNDERDRAIN DETAILS  
 UNDER PAVEMENT S**



11/18/2022

**F.M. 2657  
 PIPE UNDERDRAIN**

| 2786-01-018 |      |                        |       |      |
|-------------|------|------------------------|-------|------|
| ITEM        | CODE | DESCRIPTION            | QUANT | UNIT |
| 432         | 6001 | RIPRAP (CONC) (4 IN)   | 0.8   | CY   |
| 556         | 6007 | PIPE UNDDR (TY 7) (6") | 1157  | LF   |

NOTE: QUANTITIES ARE APPROXIMATED AT THREE LOCATIONS. PLACE AS DIRECTED BY THE ENGINEER AND MAY BE ADJUSTED IN THE FIELD.

| © 2023 Texas Department of Transportation |          |          |           |
|---|----------|----------|-----------|
| CONT                                      | SECT     | JOB      | HIGHWAY   |
| 2786                                      | 01       | 018 ETC. | FM 2657   |
| DIST                                      | COUNTY   |          | SHEET NO. |
| BWD                                       | LAMPASAS |          | 34        |

### CSJ: 2786-01-018 STRIPING SUMMARY

|                                    |          | 0666 6078<br>Refl Pav<br>Mrk Ty I<br>(W) WORD<br>LF | 0666 6054<br>Refl Pav<br>Mrk Ty I<br>(W) ARROW<br>LF | 0666 6303<br>Re Pm W/Ret<br>Req Ty I<br>(W) 4" (Slid)<br>(100Mil)<br>LF | 0666 6303<br>Re Pm W/Ret<br>Req Ty I<br>(W) 4" (Brk)<br>(100Mil)<br>LF | 0666 6312<br>Re Pm W/Ret<br>Req Ty I<br>(Y) 4" (Brk)<br>(100Mil)<br>LF | 0666 6315<br>Re Pm W/Ret<br>Req Ty I<br>(Y) 4" (Slid)<br>(100Mil)<br>LF | 0672 6004<br>REFL PAV<br>MRKR<br>TY II - C - R<br>EA | 0672 6009<br>REFL PAV<br>MRKR<br>TY II - A - A<br>EA |
|------------------------------------|----------|---|--|---|--|--|---|--|--|
| CSJ 2786-01-018<br>FM 2657 EB & WB |          |   |  |   |  |  |   |  |  |
| STATION:                           |          |   |  |   |  |  |   |  |  |
| 17+35.00                           | 93+07.00 | 2   | 2  | 4277  | 1070   | 1070   | 4277  | 54   | 107  |
| 93+07.00                           | 96+50.00 |   |  |   |  |  |   | 18   |  |
| <b>TOTAL</b>                       |          | <b>2</b>  | <b>2</b>   | <b>4277</b>   | <b>1070</b>  | <b>1070</b>  | <b>4277</b>   | <b>72</b>  | <b>107</b>   |

### CSJ: 3131-03-013 STRIPING SUMMARY

|                                    |           | 0666 6181<br>Refl Pav<br>Mrk Ty II<br>(W) 18" (Slid)<br>LF | 0666 6182<br>Refl Pav<br>Mrk Ty II<br>(W) 24" (Slid)<br>LF | 0666 6078<br>Refl Pav<br>Mrk Ty I<br>(W) WORD<br>LF | 0666 6184<br>Refl Pav<br>Mrk Ty II<br>(W) ARROW<br>LF | 0666 6303<br>Re Pm W/Ret<br>Req Ty I<br>(W) 4" (Slid)<br>(100Mil)<br>LF | 0666 6303<br>Re Pm W/Ret<br>Req Ty I<br>(W) 4" (Brk)<br>(100Mil)<br>LF | 0666 6312<br>Re Pm W/Ret<br>Req Ty I<br>(Y) 4" (Brk)<br>(100Mil)<br>LF | 0666 6315<br>Re Pm W/Ret<br>Req Ty I<br>(Y) 4" (Slid)<br>(100Mil)<br>LF | 0672 6004<br>REFL PAV<br>MRKR<br>TY II - C - R<br>EA | 0672 6009<br>REFL PAV<br>MRKR<br>TY II - A - A<br>EA |
|------------------------------------|-----------|--|--|---|---|---|--|--|---|--|--|
| CSJ 3131-03-013<br>FM 2657 EB & WB |           |  |  |   |   |   |  |  |   |  |  |
| STATION:                           |           |  |  |   |   |   |  |  |   |  |  |
| 96+50                              | 139+00.00 | 186  | 186  |   |   | 8500  | 2125   | 2125   | 8500  | 107  | 212  |
| 139+00.00                          | 148+50.00 |  |  |   |   | 1900  |  | 475  | 1900  |  | 48   |
| 148+50.00                          | 149+50.00 |  | 113  |   |   |   |  |  | 200   |  | 10   |
| 149+50.00                          | 151+05.00 |  |  | 2   | 2   | 310   |  |  | 310   |  | 16   |
| 151+05.00                          | 161+13.00 |  | 425  |   |   | 2016  |  |  | 4032  |  | 25   |
| <b>TOTAL</b>                       |           | <b>186</b>   | <b>724</b>   | <b>2</b>  | <b>2</b>  | <b>12272</b>  | <b>2125</b>  | <b>2600</b>  | <b>14942</b>  | <b>107</b>   | <b>311</b>   |

DATE: 9/22/2022 5:03:43 PM  
FILE: ... \STRIPING SUMMARY.dgn


### FM 2657 PAVEMENT MARKING SUMMARY




|      |          |          |           |
|------|----------|----------|-----------|
| CONT | SECT     | JOB      | HIGHWAY   |
| 2786 | 01       | 018 ETC. | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 35        |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any project.


DATE: 9/20/2022 3:56:41 PM  
 FILE: T:\BWDSD\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 281 at 4th Street\PM(1)-20.dgn




**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.

**YIELD LINES**



**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

**NOTES**


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

**GENERAL NOTES**

- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

| MATERIAL SPECIFICATIONS                   |          |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED)          | DMS-4200 |
| EPOXY AND ADHESIVES                       | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS  | DMS-6130 |
| TRAFFIC PAINT                             | DMS-8200 |
| HOT APPLIED THERMOPLASTIC                 | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD  
PAVEMENT MARKINGS**

**PM(1)-20**


|                       |      |          |           |         |
|-----------------------|------|----------|-----------|---------|
| FILE: pm1-20.dgn      | DN:  | CK:      | DW:       | CK:     |
| © TxDOT November 1978 | CONT | SECT     | JOB       | HIGHWAY |
| 8-95 3-03 REVISIONS   | 2786 | 01       | 018 ETC.  | FM 2657 |
| 5-00 2-12             | DIST | COUNTY   | SHEET NO. |         |
| 8-00 6-20             | BWD  | LAMPASAS | 36        |         |

# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard after its publication.




**CENTERLINE FOR ALL TWO LANE ROADWAYS**



**CENTERLINE & LANE LINES  
FOR FOUR LANE TWO-WAY HIGHWAYS**



**CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE**




**LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)**


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

| MATERIAL SPECIFICATIONS                   |          |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED)          | DMS-4200 |
| EPOXY AND ADHESIVES                       | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS  | DMS-6130 |
| TRAFFIC PAINT                             | DMS-8200 |
| HOT APPLIED THERMOPLASTIC                 | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**Type I (Top View)**



**Type II (Top View)**



**SECTION A**

## RAISED PAVEMENT MARKERS




## POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

|                     |      |          |           |         |
|---------------------|------|----------|-----------|---------|
| FILE: pm2-20.dgn    | DN:  | CK:      | DW:       | CK:     |
| © TxDOT April 1977  | CONT | SECT     | JOB       | HIGHWAY |
| 4-92 2-10 REVISIONS | 2786 | 01       | 018 ETC.  | FM 2657 |
| 5-00 2-12           | DIST | COUNTY   | SHEET NO. |         |
| 8-00 6-20           | BWD  | LAMPASAS | <b>37</b> |         |


### GENERAL NOTES

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



### REFLECTORIZED PROFILE PATTERN DETAIL

USING REFLECTIVE PROFILE PAVEMENT MARKINGS




### NOTE

Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard after its publication date.

DATE: 9/20/2022 4:00:08 PM  
 FILE: T:\BWD\SGTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of Highway 74 near 490th Street\PM(3)-20.dgn



| Posted Speed | D (ft) | L (ft)                |
|--------------|--------|-----------------------|
| 30 MPH       | 460    | $L = \frac{WS^2}{60}$ |
| 35 MPH       | 565    |                       |
| 40 MPH       | 670    | L = WS                |
| 45 MPH       | 775    |                       |
| 50 MPH       | 885    |                       |
| 55 MPH       | 990    |                       |
| 60 MPH       | 1,100  |                       |
| 65 MPH       | 1,200  |                       |
| 70 MPH       | 1,250  |                       |
| 75 MPH       | 1,350  |                       |

**LANE REDUCTION**

**NOTES**


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

**GENERAL NOTES**

- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


| MATERIAL SPECIFICATIONS                   |          |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED)          | DMS-4200 |
| EPOXY AND ADHESIVES                       | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS  | DMS-6130 |
| TRAFFIC PAINT                             | DMS-8200 |
| HOT APPLIED THERMOPLASTIC                 | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


**TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY**




**TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE**



**TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS**



**TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP**



DETAIL A

DETAIL B

Texas Department of Transportation


Traffic Safety Division Standard

**TWO-WAY LEFT TURN LANES,  
 RURAL LEFT TURN BAYS,  
 AND LANE REDUCTION  
 PAVEMENT MARKINGS  
 PM(3) - 20**

|                    |      |          |           |         |
|--------------------|------|----------|-----------|---------|
| FILE: pm3-20.dgn   | DN:  | CK:      | DW:       | CK:     |
| © TxDOT April 1998 | CONT | SECT     | JOB       | HIGHWAY |
| REVISIONS          | 2786 | 01       | 018 ETC.  | FM 2657 |
| 5-00 2-10          | DIST | COUNTY   | SHEET NO. |         |
| 8-00 2-12          | BWD  | LAMPASAS | 38        |         |
| 3-03 6-20          |      |          |           |         |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard into a computer program or for any errors that may appear in this standard.

DATE: 9/20/2022 4:01:47 PM  
 FILE: I:\BWDSDS\TEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi. South of this station\2786-01-018.dgn




**HIGH-VISIBILITY LONGITUDINAL CROSSWALK AT CONTROLLED APPROACH**

**GENERAL NOTES**

1. Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
3. For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
5. Each crosswalk shall be a minimum of 6' wide.
6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
7. Final placement of Stop Bar and Crosswalk shall be approved by the Engineer in the field.

| MATERIAL SPECIFICATIONS                   |          |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED)          | DMS-4200 |
| EPOXY AND ADHESIVES                       | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS  | DMS-6130 |
| TRAFFIC PAINT                             | DMS-8200 |
| HOT APPLIED THERMOPLASTIC                 | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**UNSIGNALIZED MID BLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK**

**NOTES:**

1. Use stop bars with "Stop Here for Pedestrians" signs at unsignalized mid block crosswalks.
2. Use stop bars with "Stop Here on Red" signs at mid block crosswalks controlled by traffic signals or pedestrian hybrid beacons.

|  |          |      |           |
|--|----------|------|-----------|
|  |          |      |           |
| <p><b>CROSSWALK PAVEMENT MARKINGS</b></p> <p><b>PM(4) - 22</b></p> |          |      |           |
| FILE: pm4-22.dgn   | DN:      | CK:  | DW:       |
| © TxDOT June 2020  | CONT     | SECT | JOB       |
| 3-22   | 2786     | 01   | 018 ETC.  |
| DIST   | COUNTY   |      | SHEET NO. |
| BWD  | LAMPASAS |      | 36        |

Prepared by \*\*\*\*\*  
 DATE: 9/20/2022 3:33:10 PM  
 FILE: I:\BWDSDTEAM\Design Projects\Lampasas\2786-01-018 - 0.329 Mi., South of US 190 to 0.1 Mi., South of CR 4744\4. Design\Reference Files\EPIC.d\UPDATED 6/1/2017

During the planning phase of project development the following environmental permits, issues, and commitments have been developed during coordination with resource agencies, local governmental entities, and the general public. Any change orders and/or deviations from the final design must be reported to the Engineer prior to the commencement of construction activities, as additional environmental clearances may be required.

### I. Clean Water Act, Sec. 402 Texas Pollutant Discharge Elimination System

(Addresses CGP and MS4 Storm Water requirements for the project.)  
 (In the event that the Contractor implements a PSL on or within one mile of the project, a Site Notice and/or a NOI will apply.)

No Action Required  Required Action

|  |   |
|--|---|
| <p>Action No. 1</p> <p>The project disturbs less than one acre of surface area. The contractor is responsible for the PSL as defined in the Standard Specifications for Construction and Maintenance of Highways, Street, and Bridges (2014 Edition, Item 7 (7.6) Page 42). The total disturbed acreage is the combined acreage to be disturbed on the project and the contractor's PSL.</p> | <p>Commitment No. 1</p> <p>Refer to the SW3P Plan Sheet, BMPs and Detail. It will address sweeping, chemical storage, sanitary waste, and all other management practices.</p> |
|--|---|

This EPIC must be updated if the disturbed area increases to one or more acres during the course of construction. It may become necessary to post a site notice/or NOI for the project and/or PSL.

### II. Clean Water Act, Section 401 and 404 Compliance

(Addresses Nationwide Permits, Individual Permits, and Wetlands.)  
 (Filling, dredging, or excavating in any water bodies, rivers, creeks, streams, wetlands, or wet area is prohibited unless specified in the USACE permit and approved by the Engineer.)  
 (When temporary fills implemented, only stated TxDOT standards will be used unless written authorization for an alternative is obtained from the Engineer. No equipment is allowed in any stream channel below the Ordinary High Water Mark except on temporary stream crossings or drill pads.)

No Action Required  404 Permit and 401 Certification Required

|        |                 |                  |                    |
|--------|-----------------|------------------|--------------------|
| Permit | Required Action | Waters of the US | App. Plan Sheet(s) |
|--------|-----------------|------------------|--------------------|

Best Management Practices for applicable 401 General Conditions:

General Condition 12 - Categories I and II BMPs required

Category I (Erosion Control)

- |   |   |
|---|---|
| <input type="checkbox"/> Temporary Vegetation           | <input type="checkbox"/> Blankets, Matting            |
| <input type="checkbox"/> Mulch                          | <input type="checkbox"/> Sod                          |
| <input type="checkbox"/> Interceptor Swale              | <input type="checkbox"/> Diversion Dike               |
| <input type="checkbox"/> Erosion Control Compost        | <input type="checkbox"/> Mulch Filter Berms and Socks |
| <input type="checkbox"/> Compost Filter Berms and Socks | <input type="checkbox"/> Compost Blankets             |

Category II (Sedimentation Control)

- |   |   |
|---|---|
| <input type="checkbox"/> Sand Bag Berm                  | <input type="checkbox"/> Rock Berm                    |
| <input type="checkbox"/> Silt Fence                     | <input type="checkbox"/> Hay Bale Dike                |
| <input type="checkbox"/> Triangular Filter Dike         | <input type="checkbox"/> Brush Berms                  |
| <input type="checkbox"/> Stone Outlet Sediment Traps    | <input type="checkbox"/> Sediment Basins              |
| <input type="checkbox"/> Erosion Control Compost        | <input type="checkbox"/> Mulch Filter Berms and Socks |
| <input type="checkbox"/> Compost Filter Berms and Socks |   |

General Condition 25 - Category III BMPs required

Category III (Post-Construction TSS Control)

- |   |   |
|---|---|
| <input type="checkbox"/> Retention/Irrigation           | <input type="checkbox"/> Constructed Wetlands         |
| <input type="checkbox"/> Extended Detention Basin       | <input type="checkbox"/> Wet Basins                   |
| <input type="checkbox"/> Vegetative Filter Strips       | <input type="checkbox"/> Vegetation-Lined Ditches     |
| <input type="checkbox"/> Grassy Swales                  | <input type="checkbox"/> Sand Filter Systems          |
| <input type="checkbox"/> Erosion Control Compost        | <input type="checkbox"/> Mulch filter Berms and Socks |
| <input type="checkbox"/> Compost Filter Berms and Socks | <input type="checkbox"/> Sedimentation Chambers       |

### III. Cultural Resources

(Addresses any special circumstances associated with cultural resources, such as archeological or historic sites.)  
 (Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.)

No Action Required  Required Action

|            |                 |            |
|------------|-----------------|------------|
| Action No. | Station (Rt/Lt) | Commitment |
| 1.         | ---             | ---        |

### IV. Vegetation Resources

(Addresses any special circumstances associated with vegetation, such as large trees to be avoided, or mitigation that will occur as part of the project.)

No Action Required  Required Action

|            |                 |  |
|------------|-----------------|--|
| Action No. | Station (Rt/Lt) | Commitment   |
| 1.         | All             | Avoid non-mow locations for stockpiles and equipment parking/storage.  |
| 2.         | Project Limits  | Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments. |

### V. Federal Listed, Proposed, Threatened, Endangered Species, Critical Habitat, State Listed Species, Candidate Species, and Migratory Bird Treaty Act (MBTA)

(Addresses any special habitat that may need to be avoided, lists any threatened or endangered species whose habitat was observed and might be impacted within the project area, and lists any precautions such as nesting seasons for migratory birds.)

No Action Required  Required Action

|   |                     |
|---|---------------------|
| Species Potentially within Project Area & Description | Habitat Description |
| ---   | ---                 |

The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. Migration patterns would not be affected by the proposed project. The contractor will remove all old migratory bird nests from any structure where work would be done from September 1 through the end of February. In addition, the contractor will be prepared to prevent migratory birds from building nests between March 1 and August 31, per the Environmental Permits, Issues, and Commitments (EPIC) plans. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young shall be avoided.

### VI. Hazardous Material or Contamination Issues

(Addresses any previously identified high risk sites associated with hazardous materials that may be encountered during construction.)

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contractor will follow all applicable storage and management requirements for liquid oil products, liquid petroleum products, and other chemical liquids as per 40 CFR 112 (a.k.a. SPCC) and/or TCEQ Construction General Permit for storm water management.

Contact the Engineer if any of the following are detected:  
 Dead or distressed vegetation (not identified as normal)  
 Trash piles, drums, canisters, barrels, etc.  
 Undesirable smells/odors  
 Underground storage tanks  
 Evidence of leaching or seepage of substances  
 Any other evidence indicating possible hazardous materials or contamination discovered on-site

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structure not including box culverts)?

Yes  No

If "No", then no further action is required.  
 If "Yes", then TxDOT is responsible for completing an asbestos assessment/inspection. Are the results of the asbestos inspection positive (is asbestos present)?

Yes  No

If "Yes", then TxDOT must retain a Texas Department of State Health Services (DSHS) licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled abatement and/or demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Bridges on this project may contain Lead-Containing Paint (LCP) or other items that contain lead. The location of (LCP) is identified in the General Notes. Item 6.10.1.2 in the 2014 TxDOT Standard Specifications shall be utilized for this project.

### VII. Other Environmental Issues

(Addresses any other environmental issues that may not have been covered in other sections.)

No Action Required  Required Action

|            |                 |            |
|------------|-----------------|------------|
| Action No. | Station (Rt/Lt) | Commitment |
| 1.         | ---             | ---        |

#### LIST OF ABBREVIATIONS

- BMP: Best Management Practice
- CGP: Construction General Permit
- DSHS: Texas Department of State Health Services
- FEMA: Federal Emergency Management Agency
- FHWA: Federal Highway Administration
- MOA: Memorandum of Agreement
- MOU: Memorandum of Understanding
- MS4: Municipal Separate Stormwater Sewer System
- MBTA: Migratory Bird Treaty Act
- NOI: Notice of Intent
- NOT: Notice of Termination
- NWP: Nationwide Permit
- SPCC: Spill Prevention Control and Countermeasure
- SW3P: Storm Water Pollution Prevention Plan
- PCN: Pre-Construction Notification
- PSL: Project Specific Location
- TCEQ: Texas Commission on Environmental Quality
- TPDES: Texas Pollutant Discharge Elimination System
- TPWD: Texas Parks and Wildlife Department
- TxDOT: Texas Department of Transportation
- T&E: Threatened and Endangered Species
- USACE: U.S. Army Corp of Engineers
- USFWS: U.S. Fish and Wildlife Service

## F.M. 2657 ENVIRONMENTAL PERMITS, ISSUES, AND COMMITMENTS (EPIC)

|  |          |          |           |
|--|----------|----------|-----------|
| <br>Texas Department of Transportation<br>BROWNWOOD DISTRICT |          |          |           |
| CONT   | SECT     | JOB      | HIGHWAY   |
| 2786   | 01       | 018 ETC. | FM 2657   |
| DIST   | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 40        |



DATE: 9/20/2022 3:37:54 PM FILE: I:\BWDSDTEAM\Design Projects\Lampasos\2786-01-018 - 0.329 Mi. South of US 190 to 0.1 Mi. South of CR 4744\4. Design\Reference Files\STORMWATER\PREVENTION PLAN.dwg

**SITE DESCRIPTION**

**PROJECT LIMITS:**

CSJ 2786-01-XXX, ETC. 0.329 Mi. SOUTH OF US 190 SOUTH TO 0.1 Mi. SOUTH OF COUNTY ROAD 4744

Begin Latitude = 31.095097° Longitude = -97.925236°  
 End Latitude = 31.055691 33/64 Longitude = -97.925074°

**LOCATION MAPS:**

Refer to title sheet for project location map.

**PROJECT DESCRIPTION:**

CSJ 2786-01-XXX, ETC.

For the construction of the rehabilitation of an existing roadway consisting of planing asphaltic concrete overlay, and striping.

**MAJOR SOIL DISTURBING ACTIVITIES:**

There is no major soil disturbing activities for this project. This project is considered preventive maintenance.

TOTAL PROJECT AREA: 66.0 AC.

TOTAL AREA TO BE DISTURBED: 0.0 AC.

**EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:**

CSJ 2786-01-XXX, ETC.

The existing soil is predominantly clay and sand overlying limestone with 85% vegetative cover.

**NAME OF RECEIVING WATERS:**

CSJ 2786-01-XXX, ETC.  
 Runoff from project ultimately flows into Stream Segment Number 1217 of the Brazos River Basin.

**EROSION AND SEDIMENT CONTROLS**

**OTHER EROSION AND SEDIMENT CONTROLS:**

**MAINTENANCE:**

All erosion controls will be maintained in good working order. If a repair is necessary, it will be made at the earliest possible date, but no later than seven (7) calendar days after the ground has dried sufficiently to prevent further damage from equipment. The areas around creeks and drainage ways shall have priority over other areas on the project site.

**INSPECTION:**

An inspection will be performed by a TxDOT inspector at least once every seven (7) calendar days. An inspection and maintenance report will be made per each inspection. Stormwater controls will be modified as directed by the Engineer based on these reports.

**WASTE MATERIALS:**

Any waste materials generated during construction will be disposed of in accordance with existing federal, state, and local laws.

**HAZARDOUS WASTE (INCLUDING SPILL REPORTING):**

At a minimum, any products in the following categories are considered to be hazardous: Fuels, Lubricating products, Asphalt products, or Concrete curing compounds and any additives. In the event of a spill which may be hazardous, clean-up will be done in accordance with federal, state, and local regulations.

**SANITARY WASTE:**

Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor.

**VEHICLE TRACKING AND DUST CONTROL (ON & OFF SITE):**

Watering for dust control (on site) will be required as Directed by the Engineer and shall be considered subsidiary to various bid items. Other requirements are as follows:

- DUST CONTROL (OFF SITE) AS NEEDED- PER ENGINEER
- HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPULIN
- EXCESS DIRT ON ROAD REMOVED DAILY
- STABILIZED CONSTRUCTION ENTRANCE

**REMARKS:**

Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, water body or stream bed. Construction staging area and vehicle maintenance area shall be constructed by the contractor in a manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, false work, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.

For off R.O.W. facilities the contractor shall comply with TCEQ requirements.

The contractor is responsible for ensuring that all subcontractors are aware of and comply with all components of the SW3P per Item 506.

Furnish one SW3P permit posting sign and sign support as detailed on the SW3P Sheet. Install this sign in a location selected by the Engineer. The sign and support should be removed upon completion of the project and is the property of the Contractor. The purchase of the sign and support, installation, relocation(s) if determined necessary by the Engineer and removal at project end shall be subsidiary to Item 506.

Sedimentation Basins - Since the area disturbed is less than 10 acres per drainage area; a sedimentation basin is not required.

**Best Management Practices:**

**Erosion**

- Temporary Vegetation
- Blankets/Matting
- Mulch
- Sodding
- Interceptor Swale
- Diversion Dike
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks

**Sedimentation**

- Silt Fence
- Rock Berm
- Triangular Filter Dike
- Sand Bag Berm
- Straw Bale Dike
- Brush Berms
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Stone Outlet Sediment Traps
- Sediment Basins

**Post-Construction TSS**

- Vegetative Filter Strips
- Retention/Irrigation Systems
- Extended Detention Basin
- Constructed Wetlands
- Wet Basin
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Vegetation Lined Ditches
- Sand Filter Systems

**NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:**

The order of activities will be as follows:


1. Perform asphaltic concrete pavement planing, place bonding course Place stone-mrx-asph sma-c sac- b pg76-22

**STORM WATER MANAGEMENT:**

Storm water will be carried to cross drainage structures by side road ditches and culverts which will empty into the various natural runoff channels.

**STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING**

No Permanent Installation Allowed. Sign to be Removed After Project Completion. Other variations of the SW3P sign may be used if Approved by the Engineer.



Texas Department of Transportation  
 Brownwood District Office  
 2495 Highway 183 North  
 Brownwood Texas, 76802



*J.H. Scantling, P.E.*

11/18/2022

**BROWNWOOD DIST. STORM WATER POLLUTION PREVENTION PLAN**



|      |          |          |           |
|------|----------|----------|-----------|
| CONT | SECT     | JOB      | HIGHWAY   |
| 2786 | 01       | 018 ETC. | FM 2657   |
| DIST | COUNTY   |          | SHEET NO. |
| BWD  | LAMPASAS |          | 41        |