

FEDERAL AID PROJECT NO.			
F 2023(461),Etc			
CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY		SHEET NO.
TYL	GREGG		1

DESIGN SPEED = VARIES
 A.D.T. (2021) = 21,388
 A.D.T. (2041) = 29,943

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	SUPPLEMENTAL INDEX OF SHEETS

**STATE OF TEXAS
 DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED
 STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT NO. F 2023(461),Etc

**US 80
 GREGG COUNTY**

NET LENGTH OF PROJECT = 37,562 FT. = 7.114 MI.

US 80 - 0096-06-075
 ROADWAY 8,149 FT = 1.544 MI.
 BRIDGE 22.5 FT = 0.004 MI.
 8,171.5 FT = 1.548 MI.

US 80 - 0096-04-072
 ROADWAY 21,731 FT = 4.115 MI.
 BRIDGE 120 FT = 0.023 MI.
 21,851 FT = 4.138 MI.

US 80 - 0096-04-069
 ROADWAY 7,449 FT = 1.411 MI.
 BRIDGE 90 FT = 0.017 MI.
 7,539 FT = 1.428 MI.

FINAL PLANS

LETTING DATE: _____
 DATE CONTRACTOR BEGAN WORK: _____
 DATE WORK WAS COMPLETED & ACCEPTED: _____
 FINAL CONTRACT COST: \$ _____
 CONTRACTOR: _____
 USED _____ OF _____ ALOTTED DAYS: _____

FINAL AS BUILT PLANS


THE CONSTRUCTION WAS PERFORMED UNDER MY SUPERVISION
 IN ACCORDANCE WITH THE PLANS AND CONTRACT

DATE: _____

 AREA ENGINEER

* REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH
 BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS
 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

LIMITS: FROM LOCKER PLANT RD (IN SEGMENTS), EAST TO SH 300
 FOR THE CONSTRUCTION OF REHABILITATION OF EXISTING ROAD
 CONSISTING OF PLANING, RESURFACING, PAVEMENT MARKINGS,
 MBGF AND SAFETY IMPROVEMENTS



EXCEPTIONS: NONE
 EQUATIONS: NONE
 RAILROAD CROSSINGS: NONE



RECOMMENDED FOR LETTING: 11/29/2022

APPROVED FOR LETTING: 12/2/2022

DocuSigned by:
 Rolando Mendez
 DISTRICT DESIGN ENGINEER

DocuSigned by:
 Vernon Well
 DISTRICT ENGINEER

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,
 NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS,
 SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL
 FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

GENERAL

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	SUPPLEMENTAL INDEX OF SHEETS
3 - 12	TYPICAL SECTIONS
13,13A-	GENERAL NOTES
14,14A-	ESTIMATE AND QUANTITY SHEET
15 - 30	QUANTITY SUMMARY SHEETS
31	SUMMARY OF SMALL SIGNS

TRAFFIC CONTROL PLAN

SHEET NO.	DESCRIPTION
32	CONSTRUCTION SEQUENCE
33	TRAFFIC CONTROL TYPICALS
34	TRAFFIC CONTROL PLANS
SHEET NO.	STANDARDS
35 - 46	BC (1)-21 THRU BC (12)-21
47 - 49	TCP (1-1)-18,TCP (1-2)-18,TCP (1-3)-18
50 - 52	TCP (2-1)-18,TCP (2-2)-18,TCP (2-3)-18
53 - 54	TCP (3-1)-13,TCP (3-3)-14
55	TCP (7-1)-13
56 - 57	TCP (S-1)-08A,TCP (S-2)-08A
58	WZ (STPM)-13
59	WZ (UL)-13
60	WZ (RS)-22

ROADWAY DETAILS

SHEET NO.	DESCRIPTION
61	INTERSECTION DETAILS
62	CURB INLET TOP (SPL) REPAIR DETAILS
63	MISCELLANEOUS DETAILS
64 - 66	MBGF LAYOUT DETAILS
SHEET NO.	STANDARDS
67	GF (31)-19
68	GF (31)MS-19
69 - 70	GF (31)TR TL3-20
71	SGT (10S)31-16
72	SGT (11S)31-18
73	SGT (12S)31-18
74	BED-14
75 - 76	LPCB-13
77	CCCG-22

BRIDGE ITEMS

SHEET NO.	DESCRIPTION
78	SUMMARY OF REPAIRS (LAKE DEVERNIA)
79	BRIDGE REPAIR LAYOUT (LAKE DEVERNIA)
80	BRIDGE CONDITION PHOTOS (LAKE DEVERNIA)
81	SUMMARY OF REPAIRS (HAWKINS CREEK)
82	BRIDGE REPAIR LAYOUT (HAWKINS CREEK)
83	BRIDGE CONDITION PHOTOS (HAWKINS CREEK)
84	SUMMARY OF REPAIRS (HARRIS CREEK)
85	BRIDGE REPAIR LAYOUT (HARRIS CREEK)
86	BRIDGE CONDITION PHOTOS (HARRIS CREEK)
87	HAWKINS CREEK RAIL AS-BUILT (TYPE 4) - FOR CONTRACTOR'S INFORMATION ONLY
88	PILE ENCASEMENT DETAILS

SHEET NO.	DESCRIPTION
89	CLEANING AND SEALING EXISTING BRIDGE JOINTS (MOD)
90 - 91	TRAFFIC RAIL SINGLE SLOPE TYPE SSTR
92	T5/T501/T502 TRANSITION RETROFIT GUIDE (MOD)
93 - 94	RETROFIT GUIDE FOR CONCRETE RAILS (MOD)
95 - 96	SRR

TRAFFIC ITEMS

SHEET NO.	STANDARDS
97	D&OM (1)-20
98	D&OM (2)-20
99	D&OM (3)-20
100	D&OM (6)-20
101	D&OM (VIA)-20
102 - 104	PM (1)-20,PM (2)-20,PM (3)-20
105	SMD (GEN)-08
106 - 108	SMD (SLIP-1)-08,SMD (SLIP-2)-08,SMD (SLIP-3)-08
109 - 110	TSR (3)-13,TSR (4)-13

ENVIRONMENTAL ISSUES

SHEET NO.	DESCRIPTION
111	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)
112	STORMWATER POLLUTION PREVENTION PLAN (SW3P)
113	CONCRETE WASHOUT DETAILS
SHEET NO.	STANDARDS
114	EC (1)-16
115	EC (2)-16
116 - 118	EC (9)-16

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.




US 80
SUPPLEMENTAL
INDEX OF SHEETS

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	2	


DW: CK: DW: CK:



A1

US 80 (CSJ 0096-04-069)
EXISTING TYPICAL SECTION



STA 96+30 TO STA 165+96
 STA 166+86 TO STA 171+69



A2

US 80 (CSJ 0096-04-069)
EXISTING TYPICAL SECTION
(LAKE DEVERNIA BRIDGE)

STA 165+96 TO STA 166+86




Texas Department of Transportation
US 80
EXISTING TYPICAL SECTIONS

SHEET 1 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	3	


11/11/2022 09:19 AM
 DOCUMENT NAME

CK:
DW:
CK:
DW:





B1
US 80 (CSJ 0096-04-072)
EXISTING TYPICAL SECTION

STA 245+78 TO STA 288+50
 STA 288+50 TO STA 293+00
 TRANSITION FROM B1 STA 288+50 TO B2 STA 293+00



B2
US 80 (CSJ 0096-04-072)
EXISTING TYPICAL SECTION

STA 293+00 TO STA 302+83



Texas Department of Transportation

US 80


EXISTING TYPICAL SECTIONS

SHEET 2 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	4	


11/11/2022 09:19 AM
 DOCUMENT NAME

CK:
DW:
CK:
DW:





B3

US 80 (CSJ 0096-04-072)
EXISTING TYPICAL SECTION
(HAWKINS CREEK BRIDGE)
STA 302+83 TO STA 304+03



B4

US 80 (CSJ 0096-04-072)
EXISTING TYPICAL SECTION
STA 304+03 TO STA 388+00



US 80





EXISTING TYPICAL SECTIONS

SHEET 3 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	5	

11/11/2022 09:19 AM
DOCUMENT NAME

CK: DW: CK: DW:




US 80
EXISTING
TYPICAL
SECTIONS

SHEET 4 OF 5


CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	6

11/11/2022 09:19 AM
 DOCUMENT NAME



CK:
DW:
CK:
DW:



C2
 US 80 (CSJ 0096-06-075)
 EXISTING TYPICAL SECTION
 (HARRIS CREEK BRIDGE)
 STA 505+95.8 TO STA 506+18.3



C3
 US 80 (CSJ 0096-06-075)
 EXISTING TYPICAL SECTION
 STA 543+40 TO STA 546+00



Texas Department of Transportation

US 80


EXISTING TYPICAL SECTIONS

SHEET 5 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	7

11/11/2022 09:19 AM
DOCUMENT NAME


CK:
DW:
CK:
DW:



A1

US 80 (CSJ 0096-04-069)
PROPOSED TYPICAL SECTION

STA 96+30 TO STA 165+96
STA 166+86 TO STA 171+69




A2

US 80 (CSJ 0096-04-069)
PROPOSED TYPICAL SECTION
(LAKE DEVERNIA BRIDGE)


STA 165+96 TO STA 166+86

LEGEND

- (A) PROPOSED PLANE ASPH CONC PAV (2")
- (B) PROPOSED PLANE ASPH CONC PAV (4")
- (C) PROPOSED 2" CRACK ATTENUATING MIXTURE
- (D) PROPOSED OCST
- (E) PROPOSED TACK COAT
- (F) PROPOSED 2" SUPERPAVE TY C
- (G) PROPOSED 2" SUPERPAVE TY C (SURFACE)



SCALE: 1" = 10' H



US 80

PROPOSED
TYPICAL
SECTIONS

SHEET 1 OF 5



CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	8

11/10/2022 09:33 AM
DOCUMENT NAME

CK:
DW:
CK:
DW:

LEGEND


- (A) PROPOSED PLANE ASPH CONC PAV (2")
- (B) PROPOSED PLANE ASPH CONC PAV (4")
- (C) PROPOSED 2" CRACK ATTENUATING MIXTURE
- (D) PROPOSED OCST
- (E) PROPOSED TACK COAT
- (F) PROPOSED 2" SUPERPAVE TY C
- (G) PROPOSED 2" SUPERPAVE TY C (SURFACE)



B1

**US 80 (CSJ 0096-04-072)
PROPOSED TYPICAL SECTION**


STA 245+78 TO STA 288+50
STA 288+50 TO STA 293+00 STRIPING TRANSITION FROM B1 STA 288+50 TO B2 STA 293+00



B2

**US 80 (CSJ 0096-04-072)
PROPOSED TYPICAL SECTION**

STA 293+00 TO STA 302+83



US 80



**PROPOSED
TYPICAL
SECTIONS**

SHEET 2 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	9


11/10/2022 09:33 AM
DOCUMENT NAME

CK:
DW:
CK:
DW:




B3

US 80 (CSJ 0096-04-072)
PROPOSED TYPICAL SECTION
(HAWKINS CREEK BRIDGE)
STA 302+83 TO STA 304+03



B4

US 80 (CSJ 0096-04-072)
PROPOSED TYPICAL SECTION
STA 304+03 TO STA 388+00



US 80

PROPOSED
TYPICAL
SECTIONS

SHEET 3 OF 5



CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	10	

11/10/2022 09:33 AM
DOCUMENT NAME

CK:
DW:
CK:
DW:


LEGEND

- (A) PROPOSED PLANE ASPH CONC PAV (2")
- (B) PROPOSED PLANE ASPH CONC PAV (4")
- (C) PROPOSED 2" CRACK ATTENUATING MIXTURE
- (D) PROPOSED OCST
- (E) PROPOSED TACK COAT
- (F) PROPOSED 2" SUPERPAVE TY C
- (G) PROPOSED 2" SUPERPAVE TY C (SURFACE)




B5

US 80 (CSJ 0096-04-072)
PROPOSED TYPICAL SECTION
 STA 388+00 TO STA 451+00



C1

US 80 (CSJ 0096-06-075)
PROPOSED TYPICAL SECTION
 STA 451+00 TO STA 505+95.8
 STA 506+18.3 TO STA 543+40



US 80


**PROPOSED
 TYPICAL
 SECTIONS**

SHEET 4 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	11	


11/10/2022 09:33 AM
 DOCUMENT NAME

CK: DW: CK: DW:



C2



US 80 (CSJ 0096-06-075)
 PROPOSED TYPICAL SECTION
 (HARRIS CREEK BRIDGE)
 STA 505+95.8 TO STA 506+18.3



C3

US 80 (CSJ 0096-06-075)
 PROPOSED TYPICAL SECTION
 STA 543+40 TO STA 546+00

- LEGEND**
- (A) PROPOSED PLANE ASPH CONC PAV (2")
 - (B) PROPOSED PLANE ASPH CONC PAV (4")
 - (C) PROPOSED 2" CRACK ATTENUATING MIXTURE
 - (D) PROPOSED OCST
 - (E) PROPOSED TACK COAT
 - (F) PROPOSED 2" SUPERPAVE TY C
 - (G) PROPOSED 2" SUPERPAVE TY C (SURFACE)



US 80

PROPOSED TYPICAL SECTIONS

SHEET 5 OF 5

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	12

11/10/2022 01:41 PM
 DOCUMENT NAME

Project Number:

Sheet 13

County: Gregg

Control: 0096-06-075

Highway: US 80

GENERAL NOTES:

GENERAL.

Contractor questions on this project are to be addressed to the following individuals:

Kyle Dykes, P.E.

kyle.dykes@txdot.gov

Stacey Wylie, P.E.

stacy.wylie1@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

For this Contract, the following standard sheets have been modified:

Cleaning and Sealing Existing Bridge Joints, Retrofit Guide for Concrete Rails,
T5/T501/T502 Transition Retrofit Guide

All stockpiles within TxDOT right of way, must not exceed 12 ft. in height and must have 3:1 slopes unless otherwise directed. Place stockpiles in a manner that will be outside the horizontal clear zone, will not obstruct traffic or sight distance, and will not interfere with roadway drainage.

Remove all vegetation from pavement edges, intersections, and driveways prior to planing operations, seal coat, or ACP operations. This work will not be paid for directly, but will be subsidiary to the bid items of the Contract.

ATTN: Provide a 20-ft. length per 1-in. depth temporary taper at all transverse joints in the travel lane before opening to traffic. This work will not be paid for directly, but will be subsidiary to the bid items of the Contract.

Project Number:

Sheet 13

County: Gregg

Control: 0096-06-075

Highway: US 80

LITTER PICKUP

Remove litter from the right of way in the project limits a maximum of 3 cycles per year as directed. Litter pickup will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Equipment used for litter pickup must be approved.

Collect and properly dispose of all litter deposited by construction operations or the traveling public from within the right of way as directed. This includes cans, bottles, paper, plastic items, metal scraps, lumber, etc. Do not dump or stockpile collected litter on Department property.

ITEM 4. SCOPE OF WORK

During final clean up, remove all foreign material that has accumulated at bridge abutments and bent caps as approved. All work and equipment involved in the removal of this material is subsidiary to the bid items of the Contract.

ITEM 6. CONTROL OF MATERIALS

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the link below:

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html>

ITEM 7. LEGAL RELATIONS AND RESPONSIBILITIES

Concrete truck drivers and concrete pump operators are required to wash out only in designated areas specifically constructed for eliminating run-off. Dispose of materials in accordance with federal, state, and local requirements.

Placement of any fill material within the channel is not allowed. A temporary crossing must clear span from channel bank to channel bank.

Maintain positive drainage for permanent and temporary work for the duration of the project. The Contractor will be responsible for any items associated with the temporary or interim drainage and all related maintenance. This work will be subsidiary to various bid items.

The total disturbed area for this project is 0.53 acres. The disturbed area in this project and the Contractor Project Specific Locations (PSL's) within 1 mile of the project limits for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any Contractor PSL for construction support activities on or off the ROW. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceed 5 acres, before disturbance, provide a copy of the Contractor NOI for PSLs on the ROW and within 1 mile of the project limits to the Engineer and to any local government that operates a Municipal Separate Storm Sewer System (MSSS).

No significant traffic generator events identified.

ITEM 8. PROSECUTION AND PROGRESS

The hours that one lane can be closed are 8 A.M. to 1 hour prior to sunset.

A lane closure that exceeds the lane restrictions defined in Item 8 is subject to a fee of \$500 per 15 minutes.

Prepare the progress schedule as a bar chart.

ITEM 9. MEASUREMENT & PAYMENT

In accordance with Article 9.1., "Measurement of Quantities," furnish the tare and maximum gross weights as well as the volume capacity of all vehicles, trucks, truck-tractors, trailers, semi-trailers, or combination of such vehicles used to deliver materials for this Contract. Also, furnish calculations supporting these weights and capacities. Provide all measurements required for pay a minimum of 2 days before the trucks are used.

ITEM 104. REMOVING CONCRETE

Before removing existing curb & gutter or laydown curb, saw cut between the gutter pan and the roadbed to eliminate the possibility of damage to the pavement structure. When the existing pavement edge has to be removed to facilitate the curb & gutter transition from existing to the proposed ramp landing, remove the old and replace the new pavement structure the same day unless otherwise directed. The use of temporary material may be allowed as approved. This work will be subsidiary to Item 104.

ITEM 164. SEEDING FOR EROSION CONTROL

The rates, types of seed, asphalt, and locations for the straw mulch and broadcast seed items will be determined if temporary erosion control is needed.

Mow tall vegetation prior to placement of erosion control measures in order to provide optimal growing conditions. This work will not be paid for directly, but will be subsidiary to the bid items of the Contract.

The season and seed mixture for "Broadcast Seeding (Temporary Erosion Control) (Cool Season)" and "Broadcast Seeding (Temporary Erosion Control) (Warm Season)" is specified below:

Cool Season - September 1 thru November 30
 Warm Season - May 15 thru August 31

Permanent Planting Mixture	
Species and Rates	
(lb. PLS/ac.)	
(Season: February 1 to May 15)	
Green Sprangletop	0.5
Bermudagrass	5.0
Weeping Lovegrass (Ermelo)	0.5
Sand Lovegrass	0.5
Lance-Leaf Coreopsis	1.0
(Season: September 1 to February 1)	
Bermuda (unhulled)	12
Crimson Clover	10

Temporary Seeding for Erosion Control	
Warm Season	
(Season: May 15 to August 31)	
Bermudagrass	10
Foxtail Millet	30
Cool Season	
(Season: September 1 to November 30)	
Tall Fescue	4.5
Oats	24
Wheat	34

Place topsoil before temporary seeding unless otherwise directed.

Do not use Bahiagrass.

Use additional temporary seeding if permanent seeding is placed outside the optimum growing season shown for this Item as directed.

Use crimping as the tacking method for hay or straw mulch.

Provide a Bonded Fiber Matrix that meets the current requirements of the Approved Products List for Item 169, "Soil Retention Blanket, Class 1, Type D, Spray Type Blanket," for both permanent and temporary seeding. Install according to manufacturer's recommendations based on a slope steeper than 3:1 with sandy soils. This Item will be paid for under Item 164.

ITEM 166. FERTILIZER

Place fertilizer at the rate of 1 lb. per 9 sq. yd. on prepared area before placing mulch sod and 1 lb. per 9 sq. yd. top dressing after placing mulch sod.

Place fertilizer at the rate of 1 lb. per 9 sq. yd. on areas prepared for seeding.

Place fertilizer at the rate of 1 lb. per 9 sq. yd. on areas prepared for block sod.

ITEM 168. VEGETATIVE WATERING

Apply water to all newly placed sod or seeded areas the same day of installation. Maintain the sod or seeded areas in a sufficiently watered condition. Do not allow sod or seeded areas to dry out so that water stress is evident.

ITEM 316. SEAL COAT

Protect all existing bridges, curbs, and other exposed concrete surfaces from asphaltic materials by any acceptable method. Removal of excessive asphaltic materials deposited on these surfaces will be at the Contractor's expense.

Perform rolling as directed with equipment complying with Section 210.2.4.2, "Medium Pneumatic Tire." This work will not be paid for directly, but will be subsidiary to pertinent Items.

Do not apply asphalt later than 1 hour before sunset unless otherwise approved.

Provide aggregate for shoulders and mainlanes from the same source unless otherwise directed.

Place surface treatments between May 1 and August 31 unless otherwise directed.

The rates shown on the plans for asphalt and aggregate are for estimating purposes only. The rates may be varied as directed.

ITEM 320. EQUIPMENT FOR ASPHALT CONCRETE PAVEMENT

Provide either a material transfer vehicle or material transfer paver for the surface course of this project. The material transfer vehicle must be self-propelled, wheel mounted and capable of receiving material from haul trucks separate from the paver. The 20-ton minimum capacity hopper must be equipped with a pivoting discharge conveyor and must have a means of remixing the asphaltic material before placement. The material transfer paver, if supplied, must consist of a mobile, self-propelled asphalt paver incorporating an integral mix loadout elevator (conveyor) having a minimum rated capacity of 750 ton per hour. The conveyor system must have a means

of remixing the asphaltic concrete material before discharging into the paver hopper and must be equipped with either a truck dump hopper attachment or a minimum 20-ton capacity surge hopper. If a material transfer paver utilizing the truck dumper hopper attachment is used, the haul trucks must stop a minimum of 1 foot into the truck. In addition, paving will not be allowed to begin until the paver has reached its full storage capacity.

ITEM 351. FLEXIBLE PAVEMENT STRUCTURE REPAIR

Replace the unstable pavement structure with 6 in. of asphaltic concrete pavement base (Super Pave SP-C), unless otherwise directed. The Engineer will determine the exact locations and limits of pavement repair in the field prior to beginning this Item of work.

Apply a tack coat with a rate of 0.10 gal/sy of residual asphalt between each layer of ACP pavement unless otherwise directed.

Furnish planing equipment to remove existing material in accordance with Item 354, as directed. The planing equipment will be subsidiary to Item 351.

Furnish an asphalt paver on full lane width pavement repair sections in accordance with Item 320 unless otherwise directed.

ITEM 354. PLANING AND TEXTURING PAVEMENT

Use a front-end loader or other suitable equipment at the stockpile site to properly stockpile the planed material as required.

ATTN: Vary planing locations to meet field conditions as directed. Begin and end planing at a sawed or planed vertical joint to provide a smooth transition to existing pavement. Provide a 20-ft. length per 1-in. depth temporary taper at all transverse joints in the travel lane before opening to traffic.

Before opening planed areas to traffic, bevel vertical or near vertical longitudinal faces in the pavement surface.

The Department retains ownership of planed material generated on this project. The stockpile site for RAP is located at the corner of SH 349 and SH 31. The Engineer will determine the exact stockpile location within the designated area.

Furnish a small planing machine as approved for planing small areas and street intersections.

Overlay all planed areas by the end of each day unless otherwise approved.

If unsuitable weather or other unexpected conditions do not allow planed areas to be overlaid, provide and maintain warning signs for overnight lane closures in accordance with the traffic control plan sheets until overlay operations are complete.

Retain all RAP generated from this project.

ITEM 361. REPAIR OF CONCRETE PAVEMENT

Furnish evidence of concurrence by the owner of the disposal site.

ITEM 432. RIPRAP

Locations and quantities may be varied as directed by the Engineer to accommodate field conditions.

ITEM 451. RETROFIT RAILING

All rail is deemed non-salvageable and is the property of the Contractor.

Refinish the outside face of the concrete slabs and curbs on the underpasses where railing is removed to leave a neat surface. Grind the existing anchor bolts flush with the concrete. Paint the ends of the anchor bolts 2 coats of zinc dust-zinc rich oxide paint as described under Item 450. This work will not be paid for directly, but will be subsidiary to this Item.

Clean the drill holes for the T631 retrofit traffic rail anchor bolts in accordance with Section 420.4.7.10., "Installation of Dowels and Anchor Bolts."

ITEMS 451 & 496. RETROFIT RAILING & REMOVING STRUCTURES

Remove structural steel railing and posts. Removed railing and posts are the property of the Contractor in accordance with Items 451 and 496.

ITEM 502. BARRICADES, SIGNS, AND TRAFFIC HANDLING

The traffic control plan for this Contract consists of: the installation and maintenance of warning signs and other traffic control devices shown on the plans; specification data, which may be included in the general notes; applicable provisions of the Texas Manual on Uniform Traffic Control Devices (TMUTCD); traffic control plan sheets included on the plans; standard BC sheets; Compliant Work Zone Traffic Control Device List, and Item 502 of the standard specifications.

Use ground-mounted sign mounts with two posts for all temporary work zone signs unless otherwise directed.

County: Gregg**Control:** 0096-06-075**Highway:** US 80

Inspect and correct deficiencies each day throughout the duration of the Contract. In accordance with Article 502.4., "Payment," no payment will be made for the month if the Contractor fails to provide or properly maintain signs and devices in compliance with Contract requirements. Temporary warning signs that are visible when conditions do not apply will be considered improper maintenance of signs.

Provide at least one employee on call nights and weekends (or any other time that work is not in progress) for maintenance of signs and traffic control devices. This employee must have an address and telephone number near the project, as approved. Notify the Engineer in writing of the name, address, and telephone number of this employee. The Engineer will furnish this information to local law enforcement officials.

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 30 minutes.

Sign all roads intersecting the project in accordance with current BC standards.

Refer to the traffic control plan sheets for traffic handling through the work area. Contractor may vary the signing arrangement and spacing as necessary to fit field conditions; however, any proposed changes in the traffic control plan must be approved before implementation.

When the sequence of work is shown on the plans, the Contractor may submit an alternate proposal for approval. Submit in writing all proposed variations and revisions.

High-visibility safety apparel is required for workers in accordance with the General Notes on current BC standards.

Place and maintain signs, channelizing devices, and flaggers to direct and route traffic at any location and for any period of time as may be required or directed.

When operations require a lane closure, provide cones, vertical panels, drums, signs, flaggers, and flashing arrow panels as necessary to route traffic around the closed lane as shown on the plans and as directed. Lane closures will be limited to one specific lane as directed.

Lane closures will not be allowed before 8 A.M. unless otherwise directed.

Unless otherwise approved, construction operations will not be allowed on Good Friday, Easter weekend, the Friday before Memorial Day thru Memorial Day, July 4th, the Friday before Labor Day thru Labor Day, the Wednesday before Thanksgiving Day thru Sunday, Christmas Eve, Christmas Day, New Year's Eve, New Year's Day, or on any other high traffic days or holidays as determined by the Engineer.

County: Gregg**Control:** 0096-06-075**Highway:** US 80

Erect R4-1 (Do Not Pass) and R4-2 (Pass With Care) signs to mark existing no-passing zones as directed. (These signs will not be required if these zones will not be eliminated during construction.)

Maintain existing roadside signs within this project's limits during this Contract. In order to accommodate the grading or other operations, temporarily relocate these signs in accordance with the TMUTCD as directed. Use ground-mounted sign mounts with two posts for all relocated signs unless otherwise directed. This work will not be paid for directly, but will be subsidiary to Item 502.

Provide truck-mounted attenuators (TMA) as shown on the appropriate traffic control plan sheets. Provide a letter certifying that all TMA used on this project meet NCHRP 350 or AASHTO Manual for Assessing Safety Hardware (MASH) requirements.

Regulate all construction activities and equipment to minimize inconvenience to the traveling public. At points where it is necessary for trucks to stop, load, or unload, provide warning signs and flaggers to protect the traveling public.

The pavement must be entirely open to traffic each night. Remove or clearly barricade all material stockpiles, equipment left overnight, or any obstruction within 30 ft. of a travelway as approved.

The Contractor Force Account "Safety Contingency" is intended to be used for work zone enhancements that could not be foreseen in the project planning and design stage for the purpose of improving the effectiveness of the Traffic Control Plan. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

With prior approval, provide uniformed law enforcement officers for traffic control during construction operations at the high-volume intersections unless other traffic control measures are approved. The law enforcement officer's intersection control force account is under control 0096-06-075.

Furnish and install work zone/reduce speed ahead and work zone/speed limit signs in accordance with current BC standards at locations as established by the Engineer. Signs must be ground-mounted.

Provide work zone speed limit signs that meet sizing requirements in accordance with Table 2B-1 of the TMUTCD.

County: Gregg

Control: 0096-06-075

Highway: US 80

When excavation is required next to a travel lane carrying traffic and widening is not completed by the end of the day's operation, place sufficient backfill against the edge of the travel lane in order to provide a 3:1 slope, unless otherwise permitted on the plans. Provide backfill containing a durable crushed stone type of flexible base or other materials as approved. When work resumes on this excavated area, carefully remove and dispose of the backfill material. Materials and labor for this work will not be paid for directly, but will be subsidiary to the various bid items of the Contract.

Refer to the traffic control details for surfacing operations shown on the plans. Install signs as required by this standard or plan sheet. Keep signs in place until after completion of the surface course operation and until placement of the standard pavement markings. Place standard pavement markings within 7 days of surface treatment application. The placement of acceptable permanent pavement markings and the completion of the final cleanup will be considered a part of the surface course operation. These signs are in addition to the signs and barricades that may be required on standard BC sheets. Short-term stationary/short duration portable signs will be required during the removal of the temporary pavement markings.

Open the repaired concrete pavement areas of 1 lane to traffic as soon as the new concrete attains the specified strength. Do not open a repaired area to traffic until all shoulder material removed for the repair has been replaced with ACP. Plan and coordinate the work in such a manner that the shoulder work will not delay opening the repaired areas to traffic.

Prior to beginning work, the Contractor and Engineer must agree on the allowable length of lane closure.

During ACP operations, provide and place additional cones at the required spacing in order to close the continuous left turn lane when an inside lane closure is in place.

The use of Law Enforcement Officers (LEOs) will be required for this project. Before the preconstruction meeting, coordinate with local agencies to be prepared for staffing needs.

Provide uniformed LEOs with marked vehicles during work zone activities. The officer in marked vehicle will be located as approved to monitor or direct traffic during the closure. The Engineer will approve the method used to direct traffic at signalized intersections. Additional officers and vehicles may be provided when directed.

Complete the daily tracking form provided by the Department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case-by-case basis.

All law enforcement personnel used in work zone traffic control must be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement

County: Gregg

Control: 0096-06-075

Highway: US 80

Personnel in Work Zones" (Course #133119) which can be found online at the following site: www.nhi.fhwa.dot.gov.

Certificates of completion should be available to all who finish the course. These should be kept by the officers to verify completion when reporting to the work site.

Provide the Engineer 72-hour notice of lane or ramp closures to provide advance notice to the traveling public by way of media and for any dynamic message sign programming. Place Portable Changeable Message Signs (PCMS) at locations as directed a minimum of 3 days in advance of entrance ramp closures on the affected crossroad. These signs are to remain in place during the ramp closures.

All work required by these general notes, except as provided for by Item 502, will not be paid for directly, but will be subsidiary to Item 502 unless otherwise shown on the plans.

ITEM 504. FIELD OFFICE AND LABORATORY

Provide a facility at the asphalt concrete pavement plant for use by the Engineer as a laboratory. This is an existing requirement of Item 6, Article 5, "Plant Inspection and Testing," of the Standard Specifications. Provide a facility meeting the requirements of Item 504. At a minimum meet the requirements of 504.2.2.4, "Ty D Structure (Asphalt Mix Control Laboratory)" and 504.2.2.4.1, "Asphalt Content by Ignition Method." In addition, provide the following: At least one exterior door opening with a 48-in. minimum width. If steps are required to gain access to the facility's 48-in. door, provide a landing dock with minimum dimensions of 60 in. wide by 60 in. deep. The strong floor and landing of the facility should support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations, acceptable to the Engineer. This facility will be required of all projects with plant produced asphalt concrete pavement.

No direct payment will be made for Engineer field labs. All construction, maintenance, utilities, custodial services, security, and permits necessary to establish and maintain readiness of this facility is the responsibility of the Contractor. This building/facility is required by the standard specifications and is considered a standard part of any asphalt concrete pavement plant producing materials for Department projects.

ITEM 506. TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

Remove dirt, silt, rocks, debris, and other foreign matter that accumulates in all structures due to project erosion and Contractor's operations. Keep stream channels open at all times. This work will not be paid for directly, but will be subsidiary to this Item.

County: Gregg

Control: 0096-06-075

Highway: US 80

The total disturbed area for this project is 0.53 acres. The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs) within 1 mile of the project limits for the Contract, will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any Contractor PSLs for the construction support activities on or off right of way. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, before disturbance, provide a copy of the Contractor NOI for PSLs on the right of way to the Engineer (to the appropriate MS4 operator when on an off-State system route).

The Engineer will provide copies of documents to meet TxDOT's posting requirements. Laminate, post, and maintain these documents at the project limits and at major roadways intersecting the project as directed. Post required Contractor documents in the same manner and location. This work will be subsidiary to Item 506.

ITEM 512. PORTABLE CONCRETE TRAFFIC BARRIER

Remove, transport, and stockpile barrier no longer required for the Contract at the South Tyler Area Office, 15986 SH 155 S, Tyler, TX 75703. Notify the Area Engineer a minimum of 4 days prior to barrier delivery.

Supply all dowel bars and mounting hardware necessary to connect the portable concrete traffic barrier. Upon completion of this Contract, all mounting hardware will become the property of the Department. When the PCTB is no longer necessary, remove and deliver the mounting hardware to a location as specified.

ITEMS 540 & 542. METAL BEAM GUARD FENCE & REMOVING METAL BEAM GUARD FENCE

Prior to removal of existing MBGF and associated appurtenances, submit to the Engineer for approval a work plan, including a detailed timeline, outlining removal and reinstallation of safety features. It is the intent that the Contractor has the necessary materials and labor force available to reinstall the safety features prior to beginning the removal process.

Where existing MBGF is being removed and not replaced with new MBGF due to proposed roadside safety improvements, do not remove the existing MBGF prior to completion of the planned roadside safety improvements at that location unless otherwise approved in writing.

Regardless of when the Contractor installs proposed MBGF, set the rail height to account for any subsequent surfacing work in order to be in accordance with standard MBGF upon completion of the Contract.

County: Gregg

Control: 0096-06-075

Highway: US 80

When replacing guard rail, ensure that all segments of guard rail removed are replaced the same work day before opening to traffic.

ITEM 542. REMOVING METAL BEAM GUARD FENCE

All metal beam guard fence is non-salvageable and will become the property of the Contractor.

The existing bridge has MBGF elements that have been tested and confirmed to contain lead-based paint. These items are deemed non-salvageable and are required to be disposed of by the Contractor according to local, state and federal laws. Furnish written documentation detailing the removal and disposal of the lead-based paint elements.

ITEM 585. RIDE QUALITY FOR PAVEMENT SURFACES

Use Surface Test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

ITEM 644. SMALL ROADSIDE SIGN ASSEMBLIES

Sign types for which details are not shown on the plans must conform to "Standard Highway Sign Designs for Texas," latest edition.

Stake all sign locations for approval prior to placement.

ITEM 658. DELINEATOR AND OBJECT MARKER ASSEMBLIES

Accept ownership of unsalvageable delineator and object marker assemblies and remove from the right of way.

ITEM 662. WORK ZONE PAVEMENT MARKINGS

For this project, Contractor may use paint and beads for work zone pavement markings (non-removable).

Dispose of all empty paint containers and unused paint in accordance with federal, state, and local requirements.

Do not use foil backed pavement markings as removable work zone pavement markings. Removable work zone pavement markings must be pliant polymer detour grade (removable) material or other markings that can be obliterated or removed to the satisfaction of the Engineer.

Use tape for short-term removable pavement markings on hot mix & PFC surfacing applications.

Tabs may be used before surface treatment application.

ITEM 666. RETROREFLECTORIZED PAVEMENT MARKINGS

Use the spray method for application of the thermoplastic compound for lane lines, barrier lines, edge lines and channelizing lines.

In high traffic volume areas, do not begin work before 9 A.M. and do not continue work after 4 P.M. unless otherwise approved. In other areas, the Engineer will approve and direct the time of work.

Extrude hot to the pavement surface thermoplastic compound for arrows, stop lines, yield triangles, transverse lines, crosswalk lines, words and symbols.

For lengths greater than 300-ft, provide guide markings that will not leave a permanent mark on the roadway. Have the guide marking material and equipment used for placement approved prior to use. Provide adequate notification for approval of the guide markings prior to placement of the permanent pavement markings.

Provide a crew experienced in the work of installing pilot guideline markings and in the necessary traffic control. Supply all the equipment, personnel, traffic control, and materials necessary for the placement of pilot guideline markings as directed. All work will be in conformance with Part 6 of the TMUTCD.

The Engineer will establish beginning and ending points of no passing zones.

Correct deficiencies in the alignment of pavement markings at Contractor's expense, as directed. Use a strip seal with aggregate and asphalt types and rates as directed to eliminate the deficient pavement markings.

ITEM 672. RAISED PAVEMENT MARKERS

Provide dispensing equipment such that the bituminous material can be directly applied from the melting pot to the pavement surface without secondary handling. Dispensing material from the melting pot into a separate container and then to the pavement surface will not be permitted. Intermittent agitation of the bituminous material will be by a method approved by the Engineer to ensure even heat distribution and must be such that the adhesive is agitated at approved and consistent intervals.

ITEM 677. ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS

Unless otherwise directed, utilize Surface Treatment Method for removal on asphaltic surfaces. The Engineer will approve materials and rates prior to use.

Furnish a high-pressure water blasting system for removing paint, thermoplastic, epoxy and preformed tape material from the following surfaces without causing any grooves or trenching of the surface: asphalt, concrete, permeable friction course, grooved asphalt and grooved concrete.

Use a high-pressure water blasting system that consists of a vacuum recovery system that must provide for a nearly dry surface eliminating the possibility of uncontained run-off blasting water or debris, or the need for any secondary clean-up vehicles or operations.

All components required for the complete operation of the water blasting system (ultra-high-pressure pump, vacuum system, clean water supply, vacuum recovery storage, primary truck-mounted and optional secondary tractor-mounted blasting components) must be mounted and transported on a single, fully self-contained and supporting single truck chassis, thereby eliminating the need for any additional water, vacuum or other transport vehicles.

ITEM 3077. SUPERPAVE MIXTURES

When using crushed gravel as a coarse aggregate for ACP, use 1% lime as an antistripping agent.

Provide coarse aggregate for the final surface course from the same source or blended sources unless otherwise directed.

Give the State inspector at the spreading and finishing machine one weight ticket for each load of material. When directed, weigh asphaltic concrete loads on public scales to ensure the proper weight of material.

For materials paid for by the ton, provide a summary spreadsheet in accordance with Article 520.2, "Equipment."

Provide Class A coarse aggregate for the surface as listed in the Department's *Bituminous Rated Source Quality Catalog* (BRSQC).

Use an electrical impedance (non-nuclear) measurement gauge to determine mat segregation and joint density for Part V and Part VIII of test procedure Tex-207-F. Do not use nuclear density gauges or thin lift gauges for segregation or joint density determinations. Data reporting for mat segregation and joint density must be performed on Department templates.

Project Number:

Sheet 13H

County: Gregg

Control: 0096-06-075

Highway: US 80

All RAP used on this project must be fractionated. If an existing mix design is submitted for use as Warm Mix Asphalt (WMA), then a new trial batch with passing Hamburg Wheel test results is required.

Apply a tack coat with a rate of 0.10 gal/sy of residual asphalt between each layer of ACP pavement unless otherwise directed.

On Table 1, under 3077.2.1.3, the Sand equivalent, % Min is voided and not replaced. The minimum percent for the sand equivalent must be 45 for the combined aggregate.

ITEM 6001. PORTABLE CHANGEABLE MESSAGE SIGN

Provide 3 electronic Portable Changeable Message Sign (PCMS) units adjacent to the mainlanes in advance of each lane closure. PCMS units must be in accordance with Section 6F.60 of the TMUTCD, applicable standards and special provisions. Depending on conditions, one or all message boards may have to be relocated during operations. Messages will be in accordance with current BC standards. When not in use, remove PCMS units from the right of way. Measurement and payment for the PCMS noted above will be in accordance with Item 6001. The term "operational" is defined as displaying a message in direct support of current project operations as approved and directed by the Engineer.

Provide a non-erodible, stable surface to place the Portable Changeable Message Sign (PCMS) units adjacent to the roadway as directed. Payment for this surface is incidental to Item 6001.

ITEM 6185. TRUCK MOUNTED ATTENUATOR (TMA)

Shadow vehicles with truck mounted attenuator (TMA) are required on the traffic control plan and TCP standards for this project. The Contractor will be responsible for determining if one or more of these traffic control operations will be ongoing at the same time to determine the total number of TMAs needed for the project. Additional truck mounted attenuators (TMAs) may be required as deemed necessary by the Engineer.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0096-06-075

DISTRICT Tyler
HIGHWAY US 80

COUNTY Gregg

CONTROL SECTION JOB				0096-04-069		0096-04-072		0096-06-075		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00130062		A00189591		A00189492			
COUNTY				Gregg		Gregg		Gregg			
HIGHWAY				US 80		US 80		US 80			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	104-6022	REMOVING CONC (CURB AND GUTTER)	LF	180.000		420.000		120.000		720.000	
	132-6021	EMBANKMENT (VEHICLE)(ORD COMP)(TY C)	CY	112.000		121.000				233.000	
	164-6001	BROADCAST SEED (PERM) (RURAL) (SANDY)	SY	1,223.000		1,322.000				2,545.000	
	164-6054	BOND FBR MTRX SEED (PERM)(RURAL)(SAND)	SY	1,223.000		1,322.000				2,545.000	
	164-6055	BONDED FBR MTRX SEED (TEMP)(WARM)	SY	612.000		661.000				1,273.000	
	164-6056	BONDED FBR MTRX SEED (TEMP)(COOL)	SY	612.000		661.000				1,273.000	
	168-6001	VEGETATIVE WATERING	MG	40.000		44.000				84.000	
	316-6406	ASPH (AC-20XP, AC-10-2TR, OR AC-20-5TR)	GAL	22,897.000		65,699.000		24,169.000		112,765.000	
	316-6407	AGGR (TY-PD GR-3 OR TY-PL GR-3)	CY	545.000		1,564.000		576.000		2,685.000	
	351-6002	FLEXIBLE PAVEMENT STRUCTURE REPAIR(6")	SY	100.000		400.000		200.000		700.000	
	354-6045	PLANE ASPH CONC PAV (2")	SY	2,047.000		10,937.000		64,476.000		77,460.000	
	354-6057	PLANE ASPH CONC PAV (4")	SY	54,518.000		154,243.000				208,761.000	
	361-6060	FULL - DEPTH REPAIR CRCP (6")	SY	200.000		200.000		100.000		500.000	
	401-6001	FLOWABLE BACKFILL	CY					10.000		10.000	
	420-6158	CL C CONC(PILE ENCASEMENT)	LF			48.000				48.000	
	429-6001	CONC STR REPAIR(CLEAN & COAT WTH EPOXY)	SF			15.000				15.000	
	429-6005	CONC STR REPAIR(DECK REP (FULL DEPTH))	SF			8.000				8.000	
	429-6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF			96.000		36.000		132.000	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	60.000						60.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	27.500		29.400				56.900	
	438-6001	CLEANING AND SEALING EXISTING JOINTS	LF	288.000		288.000				576.000	
	451-6024	RETROFIT RAIL (TY SSTR)	LF			260.000				260.000	
	479-6002	ADJUSTING INLETS	EA	5.000		5.000		1.000		11.000	
	496-6002	REMOV STR (INLET)	EA	5.000		5.000		1.000		11.000	
	500-6001	MOBILIZATION	LS	0.330		0.330		0.340		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO					8.000		8.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	55.000		55.000		50.000		160.000	
	506-6029	EARTHWORK (EROSN & SEDMT CONT, IN VEH)	CY	33.000		33.000		34.000		100.000	
	506-6030	BACKHOE WORK (EROSION & SEDMT CONT)	HR	17.000		17.000		16.000		50.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	667.000		667.000		666.000		2,000.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	667.000		667.000		666.000		2,000.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	167.000		167.000		166.000		500.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	167.000		167.000		166.000		500.000	
	506-6046	TRACKHOE WORK (EROSION & SEDMT CONT)	HR	17.000		17.000		16.000		50.000	
	506-6053	ROCK FILTER DAMS (INSTALL) (TY 2) (6:1)	LF	55.000		55.000		50.000		160.000	
	512-6009	PORT CTB (FUR & INST)(LOW PROF)(TY 1)	LF			220.000				220.000	
	512-6010	PORT CTB (FUR & INST)(LOW PROF)(TY 2)	LF			40.000				40.000	

DISTRICT	COUNTY	CCSJ	SHEET
Tyler	Gregg	0096-06-075	14



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0096-06-075

DISTRICT Tyler
HIGHWAY US 80

COUNTY Gregg

CONTROL SECTION JOB				0096-04-069		0096-04-072		0096-06-075		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00130062		A00189591		A00189492			
COUNTY				Gregg		Gregg		Gregg			
HIGHWAY				US 80		US 80		US 80			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	512-6033	PORT CTB (MOVE)(LOW PROF)(TY 1)	LF			220.000				220.000	
	512-6034	PORT CTB (MOVE)(LOW PROF)(TY 2)	LF			40.000				40.000	
	512-6045	PORT CTB (STKPL)(LOW PROF)(TY 1)	LF			220.000				220.000	
	512-6046	PORT CTB (STKPL)(LOW PROF)(TY 2)	LF			40.000				40.000	
	529-6008	CONC CURB & GUTTER (TY II)	LF	180.000		420.000		120.000		720.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	75.000		150.000		100.000		325.000	
	540-6022	MTL THRIE-BEAM GD FEN (STEEL POST)	EA	4.000		4.000		4.000		12.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	75.000		200.000		100.000		375.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000		2.000		10.000	
	544-6003	GUARDRAIL END TREATMENT (REMOVE)	EA	3.000		4.000				7.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA			1.000				1.000	
	658-6013	INSTL DEL ASSM (D-SW)SZ (BRF)CTB	EA			4.000				4.000	
	658-6061	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2	EA	18.000		18.000		8.000		44.000	
	662-6001	WK ZN PAV MRK NON-REMOV (W)4"(BRK)	LF	3,770.000		10,674.000		5,491.000		19,935.000	
	662-6012	WK ZN PAV MRK NON-REMOV (W)8"(SLD)	LF	220.000		2,092.000		1,842.000		4,154.000	
	662-6016	WK ZN PAV MRK NON-REMOV (W)24"(SLD)	LF			849.000		1,046.000		1,895.000	
	662-6032	WK ZN PAV MRK NON-REMOV (Y)4"(BRK)	LF	3,120.000		7,503.000		3,368.000		13,991.000	
	662-6034	WK ZN PAV MRK NON-REMOV (Y)4"(SLD)	LF	12,761.000		43,738.000		17,157.000		73,656.000	
	662-6071	WK ZN PAV MRK REMOV (W)8"(SLD)	LF	99.000		1,114.000		772.000		1,985.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	1,142.000		3,316.000		1,361.000		5,819.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,600.000		4,579.000		1,916.000		8,095.000	
	662-6112	WK ZN PAV MRK SHT TERM RMV (W)(4")	LF	3,392.000		9,579.000		3,825.000		16,796.000	
	662-6113	WK ZN PAV MRK SHT TERM RMV (Y)(4")	LF	8,771.000		27,709.000		11,177.000		47,657.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	220.000		2,092.000		1,842.000		4,154.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF	270.000		1,376.000		1,320.000		2,966.000	
	666-6147	REFL PAV MRK TY I (Y)24"(SLD)(100MIL)	LF			50.000				50.000	
	666-6300	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	LF	3,770.000		10,674.000		5,491.000		19,935.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF			18,399.000				18,399.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF	3,120.000		7,503.000		3,368.000		13,991.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	12,761.000		43,738.000		17,157.000		73,656.000	
	668-6077	PREFAB PAV MRK TY C (W) (ARROW)	EA	23.000		57.000		26.000		106.000	
	668-6085	PREFAB PAV MRK TY C (W) (WORD)	EA	2.000		19.000		18.000		39.000	
	668-6092	PREFAB PAV MRK TY C (W) (36")(YLD TRI)	EA			6.000		14.000		20.000	
	668-6101	PREFAB PAV MRK TY C (Y) (4") (SLD)	LF			230.000				230.000	
	672-6007	REFL PAV MRKR TY I-C	EA	199.000		707.000		360.000		1,266.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	312.000		1,302.000		517.000		2,131.000	
	780-6002	CNC CRACK REPAIR (DISCRETE)(INJECT)	LF	3.000						3.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0096-06-075

DISTRICT Tyler
HIGHWAY US 80

COUNTY Gregg

CONTROL SECTION JOB				0096-04-069		0096-04-072		0096-06-075		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00130062		A00189591		A00189492			
COUNTY				Gregg		Gregg		Gregg			
HIGHWAY				US 80		US 80		US 80			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	3000-6001	CAM (ASPHALT) PG(70-22)	TON			1,273.000				1,273.000	
	3000-6004	CAM (AGGREGATE)	TON			15,694.000				15,694.000	
	3077-6011	SP MIXESSP-CPG64-22	TON	5,997.000						5,997.000	
	3077-6022	SP MIXESSP-CSAC-A PG70-22	TON	6,222.000		18,169.000		7,093.000		31,484.000	
	3077-6075	TACK COAT	GAL	5,656.000		16,299.000		694.000		22,649.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	14.000		14.000		14.000		42.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1.000		1.000		2.000		4.000	
	6185-6002	TMA (STATIONARY)	DAY	13.000		35.000		23.000		71.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	20.000		20.000		20.000		60.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS					1.000		1.000	
		LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS					1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS					1.000		1.000	


DW: CK: DW: CK: DW: CK:

BASIS OF ESTIMATE						
ITEM	DESCRIPTION	RATE	DESIGN QUANTITY	DESIGN UNIT	PAY QUANTITY	PAY UNIT
[1] 166	FERTILIZER	1 LB/9 SY	2545	SY	0.14	TON
[2] 168	VEGETATIVE WATERING	11 GAL/SY	7635	SY	84	MG
316	ASPH (AC-20XP, AC-10-2TR, OR AC-20-5TR)	0.42 GAL/SY	268489	SY	112765	GAL
316	AGGR (TY-PD GR-3 OR TY-PL GR-3)	1 CY/100 SY	268489	SY	2685	CY
3000	CAM (ASPHALT) PG(70-22)	16.5 LB/SY	154243	SY	1273	TON
3000	CAM (AGGREGATE)	203.5 LB/SY	154243	SY	15694	TON
3077	TACK COAT	0.1 GAL/SY	226493	SY	22649	GAL
3077	SP MIXES SP-C PG64-22 (2")	220 LB/SY	54518	SY	5997	TON
3077	SP MIXES SP-C SAC-A PG70-22 (SURFACE)(2")	220 LB/SY	286221	SY	31484	TON
500	MOBILIZATION				1	LS
502	BARRICADES, SIGNS AND TRAFFIC HANDLING				8	MO

[1] FOR INFORMATION ONLY.
 [2] FOR TWO APPLICATIONS.

VEGETATION SUMMARY								
LOCATION	LENGTH	ITEM 164				ITEM 166	ITEM 168	REMARKS
		[1] BOND FBR MTRX SEED (PERM) (RURAL) (SAND)	[1] BONDED FBR MTRX SEED (TEMP) (WARM)	[1] BONDED FBR MTRX SEED (TEMP) (COOL)	[1] BROADCAST SEED (PERM) (RURAL) (SANDY)	[1][2] FERTILIZER	[1][2] VEGETATIVE WATERING	
STA	FT	SY	SY	SY	SY	SY	SY	
LAKE DEVERNIA	125	278	139	139	278	278	834	APPROACH LEFT
	135	300	150	150	300	300	900	DEPARTURE LEFT
	165	367	184	184	367	367	1101	APPROACH LEFT
	125	278	139	139	278	278	834	DEPARTURE LEFT
HAWKINS CREEK	125	278	139	139	278	278	834	APPROACH LEFT
	235	522	261	261	522	522	1566	DEPARTURE LEFT
	110	244	122	122	244	244	732	APPROACH LEFT
	125	278	139	139	278	278	834	DEPARTURE LEFT
TOTALS		2545	1273	1273	2545	2545	7635	

[1] MULTIPLE MOVE-INS WILL BE REQUIRED TO MAINTAIN ADEQUATE VEGETATION IN COMPLIANCE WITH THE CONSTRUCTION GENERAL PERMIT.
 [2] QUANTITY INCLUDED IN BASIS OF ESTIMATE.



Texas Department of Transportation

US 80

QUANTITY SUMMARY

SHEET 1 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY		SHEET NO.
TYL	GREGG		15

DATE: 11/15/2022 5:19:16 PM
 FILE: c:\tdot\pw_onlinetx\d03\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn


DW: CK: DW: CK: DW: CK:

TABULATION OF SURFACE AREAS CSJ 0096-04-069 - PAGE 1 OF 3

FROM	TO	LENGTH	ITEM 316		3000		ITEM 3077				REMARKS		
			[1] OCST		[1] CRACK ATTENUATING MIXTURE (2")		[1] TACK COAT		[1] SP MIXES SP-C PG64-22 (2")			[1] SP MIXES SP-C PG70-22 (SAC-A) (SURFACE) (2")	
			WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)		WIDTH (FT)	AREA (SY)
STA	STA	FT											
CSJ 0096-04-069													
96+30	165+96	6966	65	50310			65	50310	65	50310	65	50310	BEGIN PROJECT (LOCKER PLANT ROAD)
165+96	166+86	90	72	720			72	720	72	720	72	720	DEVERNIA LAKE BRIDGE
166+86	171+69	483	65	3488			65	3488	65	3488	65	3488	END PROJECT (1.1 MI. E OF SL 485)
INTERSECTIONS													
PIERCE ST (LT)								129				129	
LOCKER PLANT RD (RT)								160				160	
LEASE RD (LT)								114				114	
ALLEN ST (RT)								141				141	
GRIFFIN ST (RT)								134				134	
TEXAS ST (LT)								139				139	
TEXAS ST (RT)								33				33	
PELPHREY DR (LT)								125				125	
PELPHREY DR (RT)								333				333	
OAKWOOD LN (LT)								73				73	
JONES ST (LT)								49				49	
WHITE ST (RT)								148				148	
PELPHREY DR (RT)								374				374	
E LAKE DEVERNIA RD (RT)								95				95	
0096-04-069 TOTALS				54518	0		56565	54518	56565				

[1] QUANTITY INCLUDED IN BASIS OF ESTIMATE.

DATE: 11/16/2022 8:47:17 AM
 FILE: c:\tdot\pw_online\tdot\3\will_lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn


 Texas Department of Transportation			
US 80			
QUANTITY SUMMARY			
SHEET 2 OF 16			
CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	16	

DATE: 11/16/2022 8:47:42 AM
 FILE: c:\tdot\pw_online\txdot3\will_lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn

TABULATION OF SURFACE AREAS CSJ 0096-04-072 - PAGE 2 OF 3

FROM	TO	LENGTH	ITEM 316		3000		ITEM 3077				REMARKS		
			[1] OCST		[1] CRACK ATTENUATING MIXTURE (2")		[1] TACK COAT		[1] SP MIXES SP-C PG64-22 (2")			[1] SP MIXES SP-C PG70-22 (SAC-A) (SURFACE) (2")	
			WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)		WIDTH (FT)	AREA (SY)
STA	STA	FT											
CSJ 0096-04-072													
245+78	288+50	4272	65	30853	65	30853	65	30853			65	30853	BEGIN PROJECT (US 80, W OF FM 3272 AT PAVMENT JOINT)
288+50	293+00	450	65	3250	65	3250	65	3250			65	3250	STRIPING TRANSITION ONLY
293+00	302+83	983	65	7099	45	4915	45	4915			65	7099	SHOULDERS MILLED 2" - MAIN LANES MILLED 4"
302+83	304+03	120	72	960	72	960	72	960			72	960	HAWKINS CREEK AREA
304+03	310+00	597	65	4312	65	4312	65	4312			65	4312	
310+00	396+50	8650	65	62472	65	62472	65	62472			65	62472	
396+50	399+00	250	64 AVG	1778	64 AVG	1778	64 AVG	1778			64 AVG	1778	
399+00	464+29	6529	63	45703	63	45703	63	45703			63	45703	END PROJECT FM 1845 (PINE TREE RD.)
INTERSECTIONS													
S WHITE OAK RD (FM 3272)(LT)													
S WHITE OAK RD (FM 3272)(RT)													
NOTTINGHAM ST (RT)													
SH 42 S (LT)													
SH 42 S (RT)													
S SHELL ST (LT)													
WILLOW LAKE DRIVE (RT)													
S HOLLANDSWORTH ST (LT)													
INDUSTRIAL ST (RT)													
LAKE HARRIS CIR (LT)													
S LAKE HARRIS RD (LT)													
S LAKE HARRIS RD (RT)													
S MOODY BLVD (RT)													
FISHER RD (LT)													
FISHER RD (RT)													
OLD HWY 80													
COOLANT LN (RT)													
SILVER FALLS RD (LT)													
STEVENS ST (RT)													
BARBARA DR (LT)													
DEBRA DR (LT)													
EDGEWOOD ST (RT)													
CUPIT DR (LT)													
PREMIER RD (RT)													
SCENIC DR (LT)													
WATKINS ST (RT)													
PAGE ST (RT)													
BIRDIE PL (LT)													
N LANE WELLS DR (LT)													
S LANE WELL DR (RT)													
CAMERON ST (LT)													
LP 281 (LT)													
LP 281 (RT)													
SUPPLY ST. (RT)													
S. SUPPLY ST. (LT)													
0096-04-072 TOTALS				156427		154243		162996		0		165180	

[1] QUANTITY INCLUDED IN BASIS OF ESTIMATE.



US 80

QUANTITY SUMMARY

SHEET 3 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	17	


DW: CK: DW: CK: DW: CK:

TABULATION OF SURFACE AREAS CCSJ 0096-06-075 - PAGE 3 OF 3

FROM	TO	LENGTH	ITEM 316		3000		ITEM 3077				REMARKS		
			[1] OCST		[1] CRACK ATTENUATING MIXTURE (2")		[1] TACK COAT		[1] SP MIXES SP-C PG64-22 (2")			[1] SP MIXES SP-C PG70-22 (SAC-A) (SURFACE) (2")	
			WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)		WIDTH (FT)	AREA (SY)
STA	STA	FT											
CSJ 0096-06-075													
464+29	473+90	961	63	6727							63	6727	BEGIN CCSJ AT FM 1845 (PINE TREE RD.)
473+90	522+25	4835	63	33845							63	33845	CL / AVENUE B
522+25	543+40	2115	63	14805							63	14805	CL / HG MOSELY PKWY
543+40	546+00	260	75	2167							75	2167	CL / SH 300, E TO END OF RT TURN BAY (END OF PROJECT)
INTERSECTIONS													
FM 1845 (LT)								473				473	
CHEROKEE ST (RT)								420				420	
URBAN AVE. (LT)								86				86	
N. AVE A (LT)								86				86	
S. AVE A (RT)								96				96	
AVENUE B (LT)								172				172	
AVENUE C (LT)								70				70	
SIMMS ST. (RT)								78				78	
AVENUE D (LT)								70				70	
ENTERPRISE ST. (RT)								129				129	
FOREST PARK DR. (LT)								74				74	
MCKAY DR. (RT)								88				88	
MONTIE ST. (LT)								72				72	
BOSCO ST. (LT)								74				74	
LOOP DR. (RT)								78				78	
LOOP DR. (RT)								69				69	
S. WARD DR. (RT)								91				91	
N. WARD DR. (LT)								190				190	
ROCKWALL DR. (LT)								180				180	
BENBROOK LN. (LT)								161				161	
HG MOSLEY PKWY (LT)								1685				1685	
HG MOSLEY PKWY (RT)								251				251	
SH 300								2239				2239	
0096-06-075 TOTALS				57544	0			6932	0			64476	
0096-04-069 AND 0096-04-072 TOTALS				210945	154243			219561	54518			221745	
PROJECT TOTALS				268489	154243			226493	54518			286221	

[1] QUANTITY INCLUDED IN BASIS OF ESTIMATE.

DATE: 11/16/2022 8:48:06 AM
 FILE: c:\tdot\pw_onlinetx\dot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn



US 80

QUANTITY SUMMARY

SHEET 4 OF 16


CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	18	

DW: CK: DW: CK:

EROSION CONTROL SUMMARY									
ITEM 506									
LOCATION	TEMP SEDMT CONT FENCE (INSTALL) LF	TEMP SEDMT CONT FENCE (REMOVE) LF	EARTHWORK (EROSN & SEDMT CONT, IN VEH) CY	BACKHOE WORK (EROSION & SEDMT CONT) HR	TRACKHOE WORK (EROSION & SEDMT CONT) HR	BIODEG EROSN CONT LOGS (12") (INSTALL) LF	BIODEG EROSN CONT LOGS (REMOVE) LF	ROCK FILTER DAMS (INSTALL) (TY 2) (6:1) LF	ROCK FILTER DAMS (REMOVE) LF
AS DIRECTED	2000	2000	100	50	50	500	500	160	160
TOTALS	2000	2000	100	50	50	500	500	160	160

NOTE: TO BE PLACED AT LOCATIONS AS DIRECTED.

REPAIR AND REMOVAL SUMMARY							
LOCATION	ITEM 351	ITEM 361	ITEM 104	ITEM 529	ITEM 479	ITEM 496	REMARKS
	FLEXIBLE PAVEMENT STRUCTURE REPAIR (6") SY	FULL- DEPTH REPAIR CRCP (6") SY	REMOVING CONC (CURB AND GUTTER) LF	CONC CURB & GUTTER (TY II) LF	ADJUSTING INLETS EA	REMOV STR (INLET) EA	
AS DIRECTED	100	200	180	180	5	5	FLEX PAV REPAIR APPROX 12' WIDE AS DIRECTED
CSJ 0096-04-069 SUBTOTAL	100	200	180	180	5	5	
AS DIRECTED	400	200	420	420	5	5	FLEX PAV REPAIR APPROX 12' WIDE AS DIRECTED
CSJ 0096-04-072 SUBTOTAL	400	200	420	420	5	5	
AS DIRECTED	200	100	120	120	1	1	FLEX PAV REPAIR APPROX 12' WIDE AS DIRECTED
CSJ 0096-06-075 SUBTOTAL	200	100	120	120	1	1	
TOTALS	700	500	720	720	11	11	



US 80

QUANTITY SUMMARY

SHEET 5 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	19	


DATE: 11/28/2022 3:55:58 PM
 FILE: c:\tdot\pw_online\tdot3\josh.fulton\0547866\US80_GEN_QUANTITY_SUMMARY.dgn

CK: DW: CK: DW: CK: DW:

PLANING SUMMARY CSJ 0096-04-069 - PAGE 1 OF 3

FROM	TO	LENGTH	ITEM 354				REMARKS
			PLANE ASPH CONC PAV (2")		PLANE ASPH CONC PAV (4")		
			WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	
STA	STA	FT					
<i>CSJ 0096-04-069</i>							
96+30	165+96	6966			65	50310	BEGIN PROJECT (LOCKER PLANT ROAD)
165+96	166+86	90			72	720	DEVERNIA LAKE BRIDGE
166+86	171+69	483			65	3488	END PROJECT (1.1 MI. E OF SL 485)
<i>INTERSECTIONS</i>							
PIERCE ST (LT)				129			
LOCKER PLANT RD (RT)				160			
LEASE RD (LT)				114			
ALLEN ST (RT)				141			
GRIFFIN ST (RT)				134			
TEXAS ST (LT)				139			
TEXAS ST (RT)				33			
PELPHREY DR (LT)				125			
PELPHREY DR (RT)				333			
OAKWOOD LN (LT)				73			
JONES ST (LT)				49			
WHITE ST (RT)				148			
PELPHREY DR (RT)				374			
E LAKE DEVERNIA RD (RT)				95			
0096-04-069 TOTALS				2047		54518	

DATE: 11/15/2022 5:19:32 PM
 FILE: c:\tdot\pw_online\tdot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn


 Texas Department of Transportation			
US 80			
QUANTITY SUMMARY			
SHEET 6 OF 16			
CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY		SHEET NO.
TYL	GREGG		20

DW: CK: DW: CK: DW: CK:

PLANING SUMMARY CSJ 0096-04-072 - PAGE 2 OF 3

FROM	TO	LENGTH	ITEM 354				REMARKS
			PLANE ASPH CONC PAV (2")		PLANE ASPH CONC PAV (4")		
			WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	
			STA	STA	FT		
CSJ 0096-04-072							
245+78	288+50	4272			65	30853	BEGIN PROJECT (US 80, E OF FM 3272 AT END OF LT TRN BAY)
288+50	293+00	450			65	3250	
293+00	302+83	983	20	2184	45	4915	
302+83	304+03	120			72	960	HAWKINS CREEK AREA
304+03	310+00	597			65	4312	
310+00	396+50	8650			65	62472	
396+50	399+00	250			64 AVG	1778	
399+00	464+29	6529			63	45703	END PROJECT FM 1845 (PINE TREE RD.)
INTERSECTIONS							
S WHITE OAK RD (FM 3272)(LT)							NO WORK
S WHITE OAK RD (FM 3272)(RT)							NO WORK
NOTTINGHAM ST (RT)							205
SH 42 S (LT)							334
SH 42 S (RT)							1125
S SHELL ST (LT)							85
WILLOW LAKE DRIVE (RT)							NO WORK
S HOLLANDSWORTH ST (LT)							112
INDUSTRIAL ST (RT)							88
LAKE HARRIS CIR (LT)							NO WORK
S LAKE HARRIS RD (LT)							115
S LAKE HARRIS RD (RT)							126
S MOODY BLVD (RT)							213
FISHER RD (LT)							198
FISHER RD (RT)							275
OLD HWY 80							1110
COOLANT LN (RT)							HAS RAISED MEDIAN
							NO WORK
SILVER FALLS RD (LT)							185
STEVENS ST (RT)							122
BARBARA DR (LT)							205
DEBRA DR (LT)							127
EDGEWOOD ST (RT)							100
CUPIT DR (LT)							32
PREMIER RD (RT)							168
SCENIC DR (LT)							161
WATKINS ST (RT)							108
PAGE ST (RT)							97
BIRDIE PL (LT)							145
N LANE WELLS DR (LT)							141
S LANE WELL DR (RT)							110
CAMERON ST (LT)							124
LP 281 (LT)							1530
LP 281 (RT)							1248
SUPPLY ST.							88
S. SUPPLY ST.							76
0096-04-072 TOTALS				10937		154243	

DATE: 11/15/2022 5:19:35 PM
 FILE: c:\tdot\pw_online\txdot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn



US 80

QUANTITY SUMMARY

SHEET 7 OF 16


CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	21	

CK: DW: CK: DW: CK: DW:

PLANING SUMMARY CCSJ 0096-06-075 - PAGE 3 OF 3

FROM	TO	LENGTH	ITEM 354				REMARKS
			PLANE ASPH CONC PAV		PLANE ASPH CONC PAV		
			2"		4"		
			WIDTH (FT)	AREA (SY)	WIDTH (FT)	AREA (SY)	
STA	STA	FT					
0096-06-075							
464+29	473+90	961	63	6727		BEGIN CCSJ AT FM 1845 (PINE TREE RD.)	
473+90	522+25	4835	63	33845		CL / AVENUE B	
522+25	543+40	2115	63	14805		CL / HG MOSELY PKWY	
543+40	546+00	260	75	2167		CL / SH 300, E TO END OF RT TURN BAY (END OF PROJECT)	
INTERSECTIONS							
FM 1845 (LT)				473			
CHEROKEE ST (RT)				420			
URBAN AVE.				86			
N. AVE A				86			
S. AVE A				96			
AVENUE B				172			
AVENUE C				70			
SIMMS ST.				78			
AVENUE D				70			
ENTERPRISE ST.				129			
FOREST PARK DR.				74			
MCKAY DR.				88			
MONTIE ST.				72			
BOSCO ST.				74			
LOOP DR.				78			
LOOP DR.				69			
S. WARD DR.				91			
N. WARD DR.				190			
ROCKWALL DR.				180			
BENBROOK LN.				161			
HG MOSLEY PKWY (LT)				1685			
HG MOSLEY PKWY (RT)				251			
SH 300				2239			
0096-06-075 TOTALS				64476	0		
0096-04-069 AND 0096-04-072 TOTALS				12984	208761		
PROJECT TOTALS				77460	208761		

DATE: 11/15/2022 5:19:39 PM
 FILE: c:\tdot\pw_online\txdot\3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn

 Texas Department of Transportation

US 80

QUANTITY SUMMARY

SHEET 8 OF 16


CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	22	

BRIDGE SUMMARY																	
LOCATION	STA		ITEM 401	ITEM 420	ITEM 429			ITEM 432	ITEM 438	ITEM 451	ITEM 512						ITEM 780
			FLOWABLE BACKFILL	CL C CONC (PILE ENCASEMENT)	CONC STR REPAIR (CLEAN & COAT WTH EPOXY)	CONC STR REPAIR (DECK REP (FULL DEPTH))	CONC STR REPAIR (VERTICAL & OVERHEAD)	RIPRAP (STONE PROTECTION) (18 IN)	CLEANING AND SEALING EXIST JOINTS	RETROFIT STR (RAIL) (TY SSTR)	PORT CTB (FUR & INST) (LOW PROF) (TY 1)	PORT CTB (FUR & INST) (LOW PROF) (TY 2)	PORT CTB (MOVE) (LOW PROF) (TY 1)	PORT CTB (MOVE) (LOW PROF) (TY 2)	[1] PORT CTB (STKPL) (LOW PROF) (TY 1)	[1] PORT CTB (STKPL) (LOW PROF) (TY 2)	CNC CRACK REPAIR (DISCRETE) (INJECT)
	FROM	TO	CY	LF	SF	SF	SF	CY	LF	LF	LF	LF	LF	LF	LF	LF	LF
CSJ: 0096-04-069 LAKE DEVERNIA BRIDGE	165+96	166+86						60	288								3
CSJ: 0096-04-072 HAWKINS CREEK BRIDGE	302+80	304+00		48	15	8	96		288	260	220	40	220	40	220	40	
CSJ: 0096-06-075 HARRIS CREEK BRIDGE	505+95.8	506+18.3	10				36										
TOTALS			10	48	15	8	132	60	576	260	220	40	220	40	220	40	3

[1] REFER TO GENERAL NOTES FOR STOCKPILE LOCATION AND ADDRESS

METAL BEAM GUARD FENCE SUMMARY											
LOCATION	STATION		ITEM 132	ITEM 432	ITEM 540		ITEM 542	ITEM 544		ITEM 658	
			EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	RIPRAP (MOW STRIP) (4 IN)	[2] MTL W-BEAM GD FEN (STEEL POST)	MTL THRIE-BEAM GD FEN (STEEL POST)	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL END TREATMENT (INSTALL)	GUARDRAIL END TREATMENT (REMOVE)	INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)	INSTL DEL ASSM (D-SW) SZ (BRF) CTB
	FROM	TO	CY	CY	LF	EA	LF	EA	EA	EA	EA
CSJ: 0096-04-069 LAKE DEVERNIA BRIDGE	165+96	166+86	112	27.5	75	4	75	4	3	18	
CSJ: 0096-04-072 HAWKINS CREEK BRIDGE	302+80	304+00	121	29.4	150	4	200	4	4	18	4
CSJ: 0096-06-075 HARRIS CREEK BRIDGE	505+95.80	506+18.30			100	4	100	2		8	
TOTALS			233	56.9	325	12	375	10	7	44	4

[2] GROUT SHALL BE SUBSIDIARY TO ITEM 540 MBGF AT HARRIS CREEK BRIDGE



US 80

QUANTITY SUMMARY

SHEET 9 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	23	

TRUCK MOUNTED ATTENUATOR SUMMARY			
STAGE OF PROJECT	NUMBER OF TRUCKS	ITEM 6185	
		TMA (STATIONARY)	TMA (MOBILE OPERATIONS)
		DAY	DAY
MBGF	1	3	
PAVING	1	10	
STRIPING	2		10
CSJ 0096-04-069 SUBTOTAL		13	20
BRIDGE PHASE 1	1	5	
BRIDGE PHASE 2	1	5	
PAVING	1	25	
STRIPING	2		10
CSJ 0096-04-072 SUBTOTAL		35	20
MBGF	1	3	
PAVING	1	20	
STRIPING	2		10
CSJ 0096-06-075 SUBTOTAL		23	20
PROJECT TOTALS		71	60


NOTE: MOBILE OPERATIONS TOTAL IS COMBINED DAYS OF TOTAL TRUCKS.

SIGN SUMMARY	
LOCATION	ITEM 644
	IN SM RD SN SUP&AM TY10BWG(1) SA(P)
	EA
OLD US 80	1
TOTALS	1

NOTE: SEE SOSS SHEETS FOR DETAILS. SEE INTERSECTION DETAILS FOR LOCATION.

PORTABLE CHANGEABLE MESSAGE SIGN			
SIGN	LOCATION	ITEM 6001	ITEM 6001
		PORTABLE CHANGEABLE MESSAGE SIGN	PORTABLE CHANGEABLE MESSAGE SIGN
		EACH	DAYS
[1] BEGIN AND END LIMITS	AS DIRECTED		14
WHERE NEEDED	AS DIRECTED	1	
CSJ 0096-04-069 SUBTOTAL		1	14
[1] BEGIN AND END LIMITS	AS DIRECTED		14
WHERE NEEDED	AS DIRECTED	1	
CSJ 0096-04-072 SUBTOTAL		1	14
[1] BEGIN AND END LIMITS	AS DIRECTED		14
WHERE NEEDED	AS DIRECTED	2	
CSJ 0096-06-075 SUBTOTAL		2	14
PROJECT TOTALS		4	42

[1] NOTE: TO BE PLACED 7 DAYS PRIOR TO START DATE OR AS DIRECTED.



US 80

QUANTITY SUMMARY

SHEET 10 OF 16


CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	24	

DW: CK: DW: CK: DW: CK:

SUMMARY OF PERMANENT PAVEMENT MARKINGS 0096-04-069 - PAGE 1 OF 3

STATION		ITEM 666						ITEM 668				ITEM 672		
		REFL PAV MRK TY I (W)8" (SLD) (100MIL)	REFL PAV MRK TY I (W)24" (SLD) (100MIL)	REFL PAV MRK TY I (Y)24" (SLD) (100MIL)	RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)	RE PM W/RET REQ TY I (W) 4"(SLD) (100MIL)	RE PM W/RET REQ TY I (Y) 4"(BRK) (100MIL)	RE PM W/RET REQ TY I (Y) 4"(SLD) (100MIL)	PREFAB PAV MRK TY C (W) (ARROW)	PREFAB PAV MRK TY C (W) (WORD)	PREFAB PAV MRK TY C (W)36" (YLD TRI)	PREFAB PAV MRK TY C (Y) (4") (SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A
		LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	LF	EA	EA
0096-04-069														
96+30	165+96	220			3483		2873	11492	21	2		185	287	
165+96	166+86				45		45	180				2	5	
166+86	171+69				242		202	806	2			12	20	
INTERSECTIONS														
PIERCE ST (LT)			24											
LOCKER PLANT RD (RT)			24											
LEASE RD (LT)			20											
ALLEN ST (RT)			16											
GRIFFIN ST (RT)			20											
TEXAS ST (LT)			20					28						
TEXAS ST (RT)														
PELPHREY DR (LT)			12					36						
PELPHREY DR (RT)			44					46						
OAKWOOD LN (LT)			14											
JONES ST (LT)			10											
WHITE ST (RT)			20					34						
PELPHREY DR (RT)			30					117						
E LAKE DEVERNIA RD (RT)			16					22						
0096-04-069 TOTALS		220	270	0	3770	0	3120	12761	23	2	0	199	312	

DATE: 11/15/2022 5:19:48 PM
 FILE: c:\tdot\pw_online\txdot\3will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn



Texas Department of Transportation

ROADWAY NAME


QUANTITY SUMMARY

SHEET 11 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06,Etc	075,Etc	US 80
DIST	COUNTY		SHEET NO.
10	GREGG		25

DATE: 11/15/2022 5:19:51 PM
 FILE: c:\tdot\pw_online\tdot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn

SUMMARY OF PERMANENT PAVEMENT MARKINGS 0096-04-072 - PAGE 2 OF 3														
STATION		ITEM 666						ITEM 668				ITEM 672		
		REFL PAV MRK	REFL PAV MRK	REFL PAV MRK	RE PM W/RET	RE PM W/RET	RE PM W/RET	RE PM W/RET	PREFAB PAV	PREFAB PAV	PREFAB PAV	PREFAB PAV	REFL PAV	REFL PAV
		TY I (W)8" (SLD) (100MIL)	TY I (W)24" (SLD) (100MIL)	TY I (Y)24" (SLD) (100MIL)	REQ TY I (W) 4" (BRK) (100MIL)	REQ TY I (W) 4"(SLD) (100MIL)	REQ TY I (Y) 4"(BRK) (100MIL)	REQ TY I (Y) 4"(SLD) (100MIL)	MRK TY C (W) (ARROW)	MRK TY C (W) (WORD)	MRK TY C (W)36" (YLD TRI)	MRK TY C (Y) (4") (SLD)	MRKR TY I-C	MRKR TY II-A-A
FROM	TO	LF	LF	LF	LF	LF	LF	EA	EA	EA	LF	EA	EA	
0096-04-072														
245+78	288+50	703	170		2038		1473	8110	13	5		230	137	266
288+50	293+00				225			1727					11	84
293+00	302+83				492	1940		2038					25	25
302+83	304+03				60	240		240					3	3
304+03	388+00	130	40		4199	16219		3700	23	1			216	477
388+00	464+29	645	390		3551			2300	17	9			231	408
INTERSECTIONS														
S WHITE OAK RD (FM 3272)(LT)														
S WHITE OAK RD (FM 3272)(RT)														
NOTTINGHAM ST (RT)														
SH 42 S (LT)														
SH 42 S (RT)														
S SHELL ST (LT)														
WILLOW LAKE DRIVE (RT)														
S HOLLANDSWORTH ST (LT)														
INDUSTRIAL ST (RT)														
LAKE HARRIS CIR (LT)														
S LAKE HARRIS RD (LT)														
S LAKE HARRIS RD (RT)														
S MOODY BLVD (RT)														
FISHER RD (LT)														
FISHER RD (RT)														
OLD HWY 80														
COOLANT LN (RT)														
SILVER FALLS RD (LT)														
STEVENS ST (RT)														
BARBARA DR (LT)														
DEBRA DR (LT)														
EDGEWOOD ST (RT)														
CUPIT DR (LT)														
PREMIER RD (RT)														
SCENIC DR (LT)														
WATKINS ST (RT)														
PAGE ST (RT)														
BIRDIE PL (LT)														
N LANE WELLS DR (LT)														
S LANE WELL DR (RT)														
CAMERON ST (LT)														
LP 281 (LT)														
LP 281 (RT)														
SUPPLY ST.														
S. SUPPLY ST.														
0096-04-072 TOTALS		2092	1376	50	10675	18399	7503	43738	57	19	6	230	707	1302



US 80


QUANTITY SUMMARY

SHEET 12 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06,Etc	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	26

DATE: 11/15/2022 5:19:54 PM
 FILE: c:\tdot\ipw_online\tdot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn

SUMMARY OF PERMANENT PAVEMENT MARKINGS 0096-06-075 - PAGE 3 OF 3														
STATION		ITEM 666						ITEM 668				ITEM 672		
		REFL PAV MRK	REFL PAV MRK	REFL PAV MRK	RE PM W/RET	RE PM W/RET	RE PM W/RET	PREFAB PAV	PREFAB PAV	PREFAB PAV	PREFAB PAV	REFL PAV	REFL PAV	
		TY I (W)8" (SLD) (100MIL)	TY I (W)24" (SLD) (100MIL)	TY I (Y)24" (SLD) (100MIL)	REQ TY I (W) 4" (BRK) (100MIL)	REQ TY I (W) 4"(SLD) (100MIL)	REQ TY I (Y) 4"(BRK) (100MIL)	REQ TY I (Y) 4"(SLD) (100MIL)	MRK TY C (W) (ARROW)	MRK TY C (W) (WORD)	MRK TY C (W)36" (YLD TRI)	MRK TY C (Y) (4") (SLD)	MRKR TY I-C	MRKR TY II-A-A
FROM	TO	LF	LF	LF	LF	LF	LF	EA	EA	EA	LF	EA	EA	
0096-06-075														
464+29	473+90	397	78		1667		261	1787	2	2			97	63
473+90	522+25	377	185		2418		2051	9212	7	3			140	255
522+25	543+40	237	204		990		809	3948	5	3			61	117
543+40	546+00	204	168		252		247	986	4	2			23	25
INTERSECTIONS														
FM 1845 (LT)			88					114			7			6
CHEROKEE ST (RT)			14					122			7			6
URBAN AVE.			14											
N. AVE A			14											
S. AVE A			14											
AVENUE B			24					48						
AVENUE C			14											
SIMMS ST.			12											
AVENUE D			12											
ENTERPRISE ST.		9	20					18						
FOREST PARK DR.			12											
MCKAY DR.			14											
MONTIE ST.			12											
BOSCO ST.			12											
LOOP DR.			12											
LOOP DR.			12											
S. WARD DR.			14											
N. WARD DR.			20											
ROCKWALL DR.			16											
BENBROOK LN.			12											
HG MOSLEY PKWY (LT)		138	42		100			400	2	2			12	20
HG MOSLEY PKWY (RT)			124											
SH 300		480	157		66			522	6	6			27	26
0096-06-075 TOTALS		1842	1320	0	5491	0	3368	17157	26	18	14	0	360	517
0096-04-069 & 0096-04-072 TOTALS		2312	1646	50	14444	18399	10623	56499	80	21	6	230	906	1614
PROJECT TOTALS		4154	2966	50	19935	18399	13991	73656	106	39	20	230	1266	2131



US 80

QUANTITY SUMMARY

SHEET 13 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	27


DW: CK: DW: CK: DW: CK:

SUMMARY OF WORK ZONE PAVEMENT MARKINGS 0096-04-069 - PAGE 1 OF 3

STATION		ITEM 662									
		WK ZN PAV MRK NON- REMOV (W)4"(BRK)	WK ZN PAV MRK NON- REMOV (W) 8" (SLD)	WK ZN PAV MRK NON- REMOV (W) 24" (SLD)	WK ZN PAV MRK NON- REMOV (Y) 4"(BRK)	WK ZN PAV MRK NON- REMOV (Y) 4"(SLD)	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	WK ZN PAV MRK SHT TERM RMV (W) 4"	WK ZN PAV MRK REMOV (W) 8" (SLD)	WK ZN PAV MRK SHT TERM RMV (Y) 4"
FROM	TO	LF	LF	LF	LF	LF	EA	EA	LF	LF	LF
<i>(0096-04-069)</i>											
<i>MILLING THEN IMMED CAM/BASE</i>											
96+30	171+69								1696	50	4385
<i>SEAL COAT</i>											
96+30	171+69	3770	220	0	3120	12761	1142	1600			
<i>2" SURFACE</i>											
96+30	171+69								1696	50	4385
0096-04-069 TOTALS		3770	220	0	3120	12761	1142	1600	3392	99	8771

NOTE: MULTIPLE MOVE-INS WILL BE REQUIRED TO MAINTAIN ADEQUATE STRIPING.

DATE: 11/15/2022 5:19:58 PM
 FILE: c:\tdot\pw_online\txdot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn



US 80

QUANTITY SUMMARY

SHEET 14 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY		SHEET NO.
TYL	GREGG		28


DW: CK: DW: CK: DW: CK:

SUMMARY OF WORK ZONE PAVEMENT MARKINGS 0096-04-072 - PAGE 2 OF 3

STATION		ITEM 662									
		WK ZN PAV MRK NON- REMOV (W)4"(BRK)	WK ZN PAV MRK NON- REMOV (W) 8" (SLD)	WK ZN PAV MRK NON- REMOV (W) 24" (SLD)	WK ZN PAV MRK NON- REMOV (Y) 4"(BRK)	WK ZN PAV MRK NON- REMOV (Y) 4"(SLD)	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	WK ZN PAV MRK SHT TERM RMV (W) 4"	WK ZN PAV MRK REMOV (W) 8" (SLD)	WK ZN PAV MRK SHT TERM RMV (Y) 4"
FROM	TO	LF	LF	LF	LF	LF	EA	EA	LF	LF	LF
(0096-04-072)											
MILLING THEN IMMED CAM/BASE											
245+78	464+29								4790	557	13855
SEAL COAT											
245+78	464+29	10675	2092	849	7503	43738	3317	4580			
2" SURFACE											
245+78	464+29								4790	557	13855
0096-04-072 TOTALS		10675	2092	849	7503	43738	3317	4580	9579	1114	27710

NOTE: MULTIPLE MOVE-INS WILL BE REQUIRED TO MAINTAIN ADEQUATE STRIPING.

DATE: 11/15/2022 5:20:01 PM
 FILE: c:\tdot\pw_online\txdot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn



US 80

QUANTITY SUMMARY

SHEET 15 OF 16

CONT	SECT	JOB	HIGHWAY
0096	06,Etc	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	29	


DW: CK: DW: CK: DW: CK:

SUMMARY OF WORK ZONE PAVEMENT MARKINGS 0096-06-075 - PAGE 3 OF 3

STATION		ITEM 662									
		WK ZN PAV MRK NON- REMOV (W)4"(BRK)	WK ZN PAV MRK NON- REMOV (W) 8" (SLD)	WK ZN PAV MRK NON- REMOV (W) 24" (SLD)	WK ZN PAV MRK NON- REMOV (Y) 4"(BRK)	WK ZN PAV MRK NON- REMOV (Y) 4"(SLD)	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	WK ZN PAV MRK SHT TERM RMV (W) 4"	WK ZN PAV MRK REMOV (W) 8" (SLD)	WK ZN PAV MRK SHT TERM RMV (Y) 4"
FROM	TO	LF	LF	LF	LF	LF	EA	EA	LF	LF	LF
(0096-06-075)											
MILLING THEN IMMEDIATE CAM/BASE											
464+29	546+00								1913	386	5588
SEAL COAT											
464+29	546+00	5491	1842	1046	3368	17157	1361	1916			
2" SURFACE											
464+29	546+00								1913	386	5588
0096-06-075 TOTALS		5491	1842	1046	3368	17157	1361	1916	3825	772	11177
0096-04-069 & 0096-04-072 TOTALS		14444	2312	849	10623	56499	4459	6179	12971	1213	36480
PROJECT TOTALS		19935	4154	1895	13991	73656	5819	8095	16796	1985	47657

NOTE: MULTIPLE MOVE-INS WILL BE REQUIRED TO MAINTAIN ADEQUATE STRIPING.


DATE: 11/15/2022 5:20:05 PM
 FILE: c:\tdot\pw_onlinetx\dot3\will.lakin\0547866\US80_GEN_QUANTITY_SUMMARY.dgn

 Texas Department of Transportation			
ROADWAY NAME			
QUANTITY SUMMARY			
SHEET 16 OF 16			
CONT	SECT	JOB	HIGHWAY
0096	06,Etc	075,Etc	US 80
DIST	COUNTY		SHEET NO.
TYL	GREGG		30

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:20:18 PM
 FILE: c:\txdotpw\onlinetxdot3\will.lakin\0547866\US80_GEN_SOSS_01.dgn

SUMMARY OF SMALL SIGNS

STATION	OFFSET	LOCATION	SIGN NOMENCLATURE	SIGN	SIGN DIMENSIONS	TOTAL SQ. FT.	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
									POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
									FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
397+50	LT	OLD US 80	R1-1		36 X 36	9.00	X		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).

FILE: sums16.dgn	Traffic Operations Division Standard
CTxDOT May 1987	
REVISIONS: 4-16 8-16	



ROADWAY NAME

SUMMARY OF SMALL SIGNS


COUNT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	31	

SEQUENCE OF WORK

1. INSTALL TCP SIGNAGE.
2. PLACE SW3P MEASURES AT PROPOSED BRIDGE RAIL AND MBGF LOCATIONS, AS THE PROJECT PROGRESSES.
3. PERFORM CURB & GUTTER AND INLET REPAIR AS DIRECTED.
4. MILL PAVEMENT TO THE DEPTH AS SHOWN IN THE PLANS.
 - a. DO NOT MILL MORE PAVEMENT THAN WHAT CAN BE INLAYED WITH 2" CAM (OR SP TY C) IN ONE DAY.
 - b. PERFORM BASE REPAIR AS DIRECTED.
 - c. PERFORM CONCRETE REPAIR AS DIRECTED.
5. PLACE 2" CAM (OR SP TY C).
6. BEFORE OPENING PLANED AREAS TO TRAFFIC, BEVEL VERTICAL OR NEAR VERTICAL LONGITUDINAL FACES IN THE PAVEMENT SURFACE.
7. PLACE APPROPRIATE WZ PAVEMENT MARKINGS BY THE END OF EACH DAY.
8. PLACE ONE COURSE SURFACE TREATMENT.
9. PLACE FINAL SURFACE.
10. PLACE PERMANENT PAVEMENT MARKINGS.
11. PERFORM FINAL CLEANUP AND REMOVE PROJECT SIGNS.

NOTE:
 MILLING OPERATIONS:
 DO NOT WORK ON BOTH SIDES OF THE ROADWAY AT THE SAME TIME.
 DURING NONWORKING HOURS, AND WHEN A LANE CLOSURE IS NOT IN PLACE, NO EDGE DROP OFFS
 GREATER THAN 2 INCHES WILL BE ALLOWED. TAPERS SHALL BE FILLED IN ON THE SAME DAY PERFORMED.

THE CONTRACTOR IS RESPONSIBLE FOR APPROPRIATE DRAINAGE IN MILLED AREAS AND DRAINAGE
 STRUCTURE AREAS.



DATE: 11/15/2022 5:20:31 PM
 FILE: c:\tdot\pw_online\txdot\3\will.akm\0547870\US80_TCP_SEQUENCE OF WORK-ORD.dgn

Texas Department of Transportation


US 80

**SEQUENCE
OF WORK**



SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	32	

CK:
DW:
CK:
DW:



PHASE 1
TCP TYPICAL SECTION
AT HAWKINS CREEK BRIDGE



PHASE 2
TCP TYPICAL SECTION
AT HAWKINS CREEK BRIDGE



SEE TCP LAYOUT SHEETS FOR LIMITS OF LPCB INSTALLATION

Texas Department of Transportation


US 80

TCP TYPICAL

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	33	

11/04/2022 01:58 PM
DOCUMENT NAME




LEGEND

- TYPE 3 BARRICADE
- LPCB (TYPE 1)
- LPCB (TYPE 2)
- DRUMS
- SIGNS
- TMA

GENERAL NOTES

1. A Shadow Vehicle with a TMA to be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely effecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.

N.T.S.



STATE OF TEXAS
 Joshua D. Fulton
 127936
 LICENSED PROFESSIONAL ENGINEER
 11/18/2022

Texas Department of Transportation

US 80
 TCP LAYOUT
 HAWKINS CREEK

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	34

11/11/2022 11:41 AM
 DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:17 PM
 FILE: c:\txdot\pw_online\txdot3\w111.ak\in\0586855\US80_TCP_BC-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS		
BC (1) - 21		
FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT SECT	JOB
REVISIONS	0096 06	075, Etc
4-03 7-13		US 80
9-07 8-14	DIST	COUNTY
5-10 5-21	TYL	GREGG
		SHEET NO.
		35


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	TYL	GREGG	36	

DATE: 11/15/2022 5:05:21 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_BC-21.dgn

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:24 PM
FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_BC-21.dgn


SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CON:	0096 06
REVISIONS		SECT:	075, Etc
9-07	8-14	JOB:	US 80
7-13	5-21	DIST:	GREGG
		COUNTY:	
		SHEET NO.:	37

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:27 PM
 FILE: c:\ttdot\p_w_online\ttdot3\will.aklin\40586855\US80_TCP_BC-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflective when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12




BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0096	06	075, Etc	US 80				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	TYL	GREGG	38					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:30 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_BC-21.dgn




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	TYL	GREGG	39	

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:33 PM
FILE: c:\vtdot\pww_online\txdot3\will.akn\40586855\US80_ICP_BC-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT


Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CR:	TxDOT
REVISIONS	0096 06	DW:	TxDOT
9-07	8-14	JOB	HIGHWAY
7-13	5-21	075, Etc	US 80
		DIST	COUNTY
		TYL	GREGG
		SHEET NO.	40

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/15/2022 5:05:36 PM
 FILE: c:\txdot\p_w_online\txdot3\will.ak\in\0586855\US80_ICP_BC-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation
 Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0096 06	075, Etc	US 80
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	TYL	GREGG	41	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:40 PM
 FILE: c:\t\dot\pw_online\t\dot3\will.ak\in\40586855\US80_ICP_BC-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.



BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension)
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer
 12" x 24" Vertical Panel
 mount with diagonals sloping down towards travel way

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS


- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12

		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES			
BC (8) - 21			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT:	SECT:
REVISIONS		0096	06
4-03	8-14	075	E+tc
9-07	5-21	DIST:	COUNTY:
7-13		TYL	GREGG
			SHEET NO.
			42


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:42 PM
 FILE: c:\t\dot\pw_online\t\dot3\will.ak\in\40586855\US80_TCP_BC-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	SECT	HIGHWAY			
REVISIONS	0096	06	075	Etc	US	80			
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	TYL	GREGG	43					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:45 PM
 FILE: c:\ttdot\p_w_online\ttdot3\will.ak\in\058855\US80_TCP_BC-21.dgn


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0096	06	075, Etc	US 80				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	TYL	REGG	44					

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		0096 06	075, Etc	US 80
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	TYL	GREGG	45	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:48 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_BC-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	TYL	REGG	46	
11-02 8-14				


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:05:51 PM
FILE: c:\txdot\pw_online\txdot3\will.ak\in\40586855\US80_TCP_BC-21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:06:05 PM
 FILE: c:\txdot\pw_online\txdot3\will.akln\40586855\US80_TCP_1-1-18.dgn




TCP (1-1a)

WORK SPACE NEAR SHOULDER
 Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
 Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		



- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (1-1) - 18

FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
2-94 4-98				
8-95 2-12				
1-97 2-18				
	DIST	COUNTY		SHEET NO.
	TYL	GREGG		47

DATE: 11/15/2022 5:06:18 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP1-2-18.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = WS ² / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45		450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55	L = WS	550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)


- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

TCP (1-2b)


- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN			
ONE-LANE TWO-WAY			
TRAFFIC CONTROL			
TCP (1-2) - 18			
FILE: tcp1-2-18.dgn	DN:	CK:	DW:
© TxDOT December 1985	CONT	SECT	JOB
REVISIONS	0096	06	075, Etc
4-90 4-98			US 80
2-94 2-12	DIST	COUNTY	SHEET NO.
1-97 2-18	TYL	GREGG	48

DATE: 11/15/2022 5:06:30 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_ICP1-3-18.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



BE PREPARED TO STOP
 CW3-4 48" X 48"
 CW20-7 48" X 48"
 For either TCP(1-3a) or TCP(1-3b)
USE ONLY WHEN FLAGGERS CONTROL TRAFFIC
 (See Notes 2 & 3)



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		


- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Additional flaggers may be positioned in advance of traffic queues to alert traffic to reduce speed.
 - DO NOT PASS, PASS WITH CARE and construction regulatory speed zone signs may be installed downstream of the ROAD WORK AHEAD signs.
 - When the work zone is made up of several work spaces, channelizing devices should be placed laterally across the closed lane to re-emphasize closure. Laterally placed channelizing devices should be repeated every 500 to 1000 feet in urban areas and every 1/4 to 1/2 mile in rural areas.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20', or 15' if posted speed are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the area of conflicting markings not the entire work zone.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO LANE ROADS
TCP (1-3) - 18

FILE: tcp1-3-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
2-94 4-98				
8-95 2-12				
1-97 2-18	TYL		GREGG	SHEET NO. 49


DATE: 11/15/2022 5:06:42 PM
 FILE: c:\txdot\pw_online\txdot3\will.akn\40586855\US80_ICP2-1-18.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-1a)
WORK SPACE NEAR SHOULDER
 Conventional Roads



TCP (2-1b)
WORK SPACE ON SHOULDER
 Conventional Roads



TCP (2-1c)
WORK VEHICLES ON SHOULDER
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
 - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18


FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT	December 1985	CONT	SECT	JOB
REVISIONS	0096	06	075, Etc	US 80
2-94 4-98				
8-95 2-12				
1-97 2-18				
	DIST	COUNTY		SHEET NO.
	TYL	GREGG		50

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:06:54 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\40586855\US80_TCP_2-2-18.dgn



TCP (2-2a)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH YIELD SIGNS
 (Less than 2000 ADT - See Note 9)



TCP (2-2b)
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS
 ONE LANE TWO-WAY
 CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	



GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL			
TCP (2-2) - 18			
FILE:	tcp2-2-18.dgn	DN:	CK:
© TxDOT	December 1985	CON:	SECT:
REVISIONS		0096	06
8-95	3-03	JOB	
1-97	2-12	HIGHWAY	
4-98	2-18	DIST:	COUNTY:
		TYL	GREGG
		SHEET NO.	
		51	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:07:05 PM
 FILE: c:\txdot\p_w_online\txdot3\will.akln\d0586855\US80_TCP2-3-18.dgn



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	70'	120'	90'
35		205'	225'	245'	35'	80'	160'	120'
40		265'	295'	320'	40'	90'	240'	155'
45	L = WS	450'	495'	540'	45'	100'	320'	195'
50		500'	550'	600'	50'	110'	400'	240'
55		550'	605'	660'	55'	120'	500'	295'
60		600'	660'	720'	60'	130'	600'	350'
65		650'	715'	780'	65'	140'	700'	410'
70		700'	770'	840'	70'	150'	800'	475'
75		750'	825'	900'	75'	160'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 TRAFFIC SHIFTS ON
 TWO-LANE ROADS**


TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	0096	06	075, Etc	US 80
8-95 3-03	DIST:	COUNTY:	SHEET NO.:	
1-97 2-12	TYL	GREGG	52	
4-98 2-18				


163

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:07:17 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_ICP3-1.dgn



TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY




TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display Flashing Arrow Board

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)


TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES


1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.




TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board in CAUTION display



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



STRIPING FOR TMA









Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS
 UNDIVIDED HIGHWAYS**

TCP (3-1)-13

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
2-94 4-98				
8-95 7-13				
1-97				
TYL		COUNTY	GREGG	SHEET NO. 53

DATE: 11/15/2022 5:07:30 PM
 FILE: c:\txdot\p_w_online\tdot3\will.akfn\40586855\US80_TCP_3-3.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.


Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/
REMOVAL
TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096 06	075, Etc	US 80	
2-94 4-98				
8-95 7-13				
1-97 7-14	TYL	COUNTY	GREGG	SHEET NO. 54


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:07:41 PM
 FILE: c:\txdot\pw_online\tdot3\will.akfn\0586855\US80_ICP7-1.dgn



NOTE
 Signing shown for one direction of travel only.

NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS



TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS
 For seal coat, micro-surface or similar operations

"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- A. Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- B. At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- D. R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- A. Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- B. At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- C. The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- A. When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- A. Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- B. Tabs shall not be used to simulate edge lines.
- C. Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- A. The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- B. Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

1. The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
2. The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
3. Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
4. When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
5. Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.




TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS
TCP (7-1) - 13


FILE:	tcp7-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	March 1991	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS:	0096 06	075, Etc		US 80					
4-92 4-98	1-97 7-13	DIST:	COUNTY:	SHEET NO.					
		TYL:	GREGG	55					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:07:53 PM
 FILE: c:\txdot\pww\online\tdot3\will.ak\in\0586855\US80*TCP*TCP(S-1).dgn



TCP (S-1a)
 WORK OFF SHOULDER
 OR PAVED SURFACE



TCP (S-1b)
 WORK ON SHOULDER

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision
 Corrected misspelling.

LEGEND

	Type III Barricade		Channelizing Devices		Flag
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)		
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)		
	Flagger		Sign Post		

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Device		Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60' - 75'	120'	90'
35		205'	225'	245'	35'	70' - 90'	160'	120'
40		265'	295'	320'	40'	80' - 100'	240'	155'
45		450'	495'	540'	45'	90' - 110'	320'	195'
50		500'	550'	600'	50'	100' - 125'	400'	240'
55		550'	605'	660'	55'	110' - 140'	500'	295'
60		600'	660'	720'	60'	120' - 150'	600'	350'
65	650'	715'	780'	65'	130' - 165'	700'	410'	
70	700'	770'	840'	70'	140' - 175'	800'	475'	
75	750'	825'	900'	75'	150' - 185'	900'	540'	

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
 SHORT DURATION - work that occupies a location up to 1 hour.
 SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

- GENERAL NOTES:
- The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
 - Channelizing devices on the shoulder taper and tangent section may be omitted for short duration (less than 1 hour) work.
 - If line-of-sight requirements for surveying operations will preclude the placement of the Work Vehicle to protect workers, the channelizing devices mentioned in Note 2 are required.
 - A Shadow Vehicle with a Truck Mounted Attenuator and flashing warning lights/arrow panel in caution mode may be used in lieu of the Work Vehicle to protect the work space.
 - The CW20-1D "ROAD WORK AHEAD" sign may be substituted for the CW21-6D "SURVEY CREW AHEAD" sign.
 - This plan may also be used for shoulder work or off shoulder work for multilane undivided roadways.
 - The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

- TCP (S-1a)
- Cones may be placed at edge of pavement adjacent to the work space to enhance safety.

Texas Department of Transportation
 Traffic Operations Division


TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

TCP (S-1) - 08A


© TxDOT August 2008		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
8-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0096	06	075, Etc	US 80
		DIST	COUNTY	SHEET NO.	
		TYL	GREGG	56	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:08:05 PM
 FILE: c:\txdot\pww\online\txdot3\will.ak\in\0586855\US80*TCP*TCPS2.dgn



TCP (S-2a)
 ROAD CLOSED FOR LESS THAN 20 MINUTES -
 OFF PEAK TRAFFIC HOURS
 WITH OR WITHOUT SHOULDERS



TCP (S-2b)
 WORK IN ROADWAY
 OFF PEAK TRAFFIC HOURS
 WITH OR WITHOUT SHOULDERS

Posted Speed (mph)	Distance (ft)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820
80	910

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision
 ⚠ Corrected reference to notes.

LEGEND

- Type III Barricade
- Channelizing Devices
- Flag
- Heavy Work Vehicle
- Truck Mounted Attenuator (TMA)
- Trailer Mounted Flashing Arrow Panel
- Portable Changeable Message Sign (PCMS)
- Flagger
- Sign Post

Posted Speed \times	Formula	Minimum Desirable Taper Lengths \times			Suggested Maximum Spacing of Device		Min. Sign Spacing "x" Distance	Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'-75'	120'	90'
35		205'	225'	245'	35'	70'-90'	160'	120'
40		265'	295'	320'	40'	80'-100'	240'	155'
45	L=WS	450'	495'	540'	45'	90'-110'	320'	195'
50		500'	550'	600'	50'	100'-125'	400'	240'
55		550'	605'	660'	55'	110'-140'	500'	295'
60		600'	660'	720'	60'	120'-150'	600'	350'
65		650'	715'	780'	65'	130'-165'	700'	410'
70		700'	770'	840'	70'	140'-175'	800'	475'
75		750'	825'	900'	75'	150'-185'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:
 SHORT DURATION - work that occupies a location up to 1 hour.
 SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

- GENERAL NOTES:
- The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
 - Adequate Stopping Sight Distance (see Stopping Sight Distance table) should be maintained from approaching traffic to the flagger or a queue of stopped vehicles. The Buffer Space "B" should be extended around curves or other obstacles, when necessary, to have adequate Stopping Sight Distance to the flagger station.
 - Flaggers should use two-way radios or other means of communication while flagging.
 - The length of the work space should be based on the ability of the flaggers to communicate.
 - CW20-1D "ROAD WORK AHEAD" signs may be substituted for CW21-6D "SURVEY CREW AHEAD" signs.
 - The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.
- TCP (S-2a)
- Road closures shall be less than 20 minutes. Closures less than 5 minutes are desirable.
 - Sign spacing should be increased if traffic repeatedly queues past the CW20-7b "BE PREPARED TO STOP" sign.
 - The surveying instrument should not be located on the paved surface.
- TCP (S-2b)
- For short duration work the Shadow Vehicle with a TMA may be replaced by another Work Vehicle with high intensity rotating, flashing or strobe lights.
 - Shadow Vehicles with a TMA are desirable when workers or equipment are in the work space. When approved by the engineer, Type III barricades or other channelizing devices may be substituted for the Shadow Vehicle.
 - The CW20-7b "BE PREPARED TO STOP" sign is optional. When used, it should be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign.

Texas Department of Transportation
 Traffic Operations Division

TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS


TCP (S-2) -08A

© TxDOT August 2008	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
8-08	REVISIONS	CONT. SECT.	JOB	HIGHWAY
	0096 06	075, Etc	US 80	
	DIST.	COUNTY	SHEET NO.	
	TYL	GREGG	57	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:08:17 PM
 FILE: c:\txdot\pw_online\txdot3\will.akr\40586855\US80_ICP_WZSTPM-13.dgn

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm




WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13


FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0096	06	075, Etc	US 80				
1-97		DIST	COUNTY	SHEET NO.					
3-03		TYL	GREGG	58					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/15/2022 5:08:28 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_WZUL-13.dgn




UNEVEN LANES
TWO LANE CONVENTIONAL ROAD



UNEVEN LANES
FOUR LANE CONVENTIONAL ROAD



NO CENTER LINE
TWO LANE CONVENTIONAL ROAD



UNEVEN LANES
DIVIDED ROADWAY

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"



SIGNING FOR UNEVEN LANES


WZ (UL) - 13

FILE: WZUL-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT	APRIL 1992	CONT SECT	JOB	HIGHWAY
REVISIONS	0096 06	075, Etc	US 80	
8-95 2-98 7-13	DIST	COUNTY	SHEET NO.	
1-97 3-03	TYL	GREGG	59	


DATE: 11/15/2022 5:08:41 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586855\US80_TCP_WZRS22.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
 * For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.


Texas Department of Transportation
 Traffic Safety Division Standard

TEMPORARY RUMBLE STRIPS



WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	TYL	GREGG	60	

CK: DW: CK: DW:



SEE STANDARDS PM(1)-20, PM(2)-20, AND PM(3)-20 FOR GUIDANCE ON SPACING AND PLACEMENT OF PAVEMENT MARKINGS/MARKERS.




US 80
INTERSECTION
LAYOUT
OLD HWY 80


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075.Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	61



11/11/2022 07:58 AM
DOCUMENT NAME




Typical for curb inlet at box culvert. See culvert details for location and position. All details not noted are same as Standard.




SECTION A-A



BAR A
4 Bars #12




BAR L1 & L2
5 Bars




BAR B
4 Bars @ 12"


The Contractor shall provide temporary drainage openings in the proposed gutter at inlet locations as directed by the Engineer.




THROAT DETAIL




TYPE 'A' & 'B' INLET ELEVATION



RING & COVER DETAIL




TOP INLET REINFORCING STEEL PARTIAL PLAN



TYPE 'C' & 'D' INLET ELEVATION


GENERAL NOTES - All gutter depressions on State maintained highways shall be 3" as noted, except 5" gutter depressions shall be on all city side streets. All concrete shall be Class "A". All exposed corners shall be chamfered 3/4". The 2 - #5 bars developed in the inlet top shall be doweled and epoxied 12" into the existing curb and gutter or mono curb on each side of the inlet. In the depressed throat section of gutter at all inlets, concrete shall be placed as directed by the Engineer. Ladder Rungs & Rings and Covers should be located on the upstream side. In the areas of conflict between reinforcing steel, block outs, pipes, anchor bolts or other steel, the reinforcement shall be bent or adjusted to clear. Any Standard City Ring and Cover conforming to Item 471 may be used. Reinforcing Steel shall have a minimum of 1 1/2 inches of clear cover. Stud anchors shall be electric arc welded to the plates with complete fusion. Existing reinforcing steel at construction joint shall be cleaned and tied to proposed reinforcing steel. If existing steel is broke or damaged dowels must be epoxied into existing concrete as directed by the engineer.




Texas Department of Transportation
© 2023
**CURB INLET TOP (SPL)
REPAIR DETAILS**

INLET TOP		SHEET NO.	
FED. RD. DIV. NO.	PROJECT NO.	62	
6			
STATE	DIST.	COUNTY	
TEXAS	10	GREGG	
CONT.	SECT.	JOB	HIGHWAY NO.
0096	06	075, Etc	US 80


DW: _____
 CK: _____
 DW: _____
 CK: _____



TYPICAL SECTION




SECTION A-A




INTERSECTION DETAILS
EXIST ASPHALT INTERSECTION
NOT TO SCALE

NOTE: USUAL MEASUREMENT FOR "L" DIMENSION IS TO ROW OR PAVEMENT JOINT, BUT IS OTHERWISE AS DIRECTED



PAVEMENT MARKING TREATMENT
AT STATE MAINTAINED HIGHWAY INTERSECTIONS

REVISED: 05/2018



DATE TIME DOCUMENT NAME





US 80
MISCELLANEOUS
DETAILS

SHEET 1 OF 1			
CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
10	GREGG	63	

CK:
DW:
CK:
DW:


SW3P LEGEND

- C US 80
- ~> OUTFALL DIRECTION
- FLOW DIRECTION
- SCF SEDIMENT CONTROL FENCE
- RFD2 ROCK FILTER DAM TY 2 (20'TYP)



LAKE DEVERNIA

11/16/2022 08:16 AM
DOCUMENT NAME



Texas Department of Transportation

US 80




MBGF LAYOUT
LAKE DEVERNIA

SHEET 1 OF 3


CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST		COUNTY	SHEET NO.
TYL		GREGG	64

CK: DW: CK: DW:

- SW3P LEGEND**
- C US 80
 - ~> OUTFALL DIRECTION
 - FLOW DIRECTION
 - SCF SEDIMENT CONTROL FENCE
 - RFD2 ROCK FILTER DAM TY 2 (20'TYP)



DATE TIME DOCUMENT NAME






Texas Department of Transportation

US 80
MBGF LAYOUT
HAWKINS CREEK


SHEET 2 OF 3

CONT	SECT	JOB	HIGHWAY
0096	06,Etc	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
10	RUSK	65	

CK:
DW:
CK:
DW:



NOTE:
 ONLY REMOVE PAVERS THAT ARE NECESSARY TO INSTALL MBGF.
 GROUT IS SUBSIDIARY TO MTL W-BEAM GD FEN (STEEL POST) ITEM.
 CONSTRUCT SGT SECTIONS PARALLEL TO ROADWAY WITHOUT FLARING.



Texas Department of Transportation


US 80
MBGF LAYOUT
HARRIS CREEK

SHEET 3 OF 3

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	66	


11/16/2022 08:22 AM
 DOCUMENT NAME

DATE: 11/15/2022
 FILE: c:\txdot\p_w_online\txdot3\will.akfn\0552636\US80_RDW_GF3119-ORD.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




TYPICAL POST PLACEMENT

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25' - 0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




ELEVATION 25' - 0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.




WOOD BLOCK TO ROUND WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.

- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25' - 0", OR 12' - 6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.


				Design Division Standard
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19				
FILE: gf3119.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	67	

DATE: 11/15/2022
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0552636\US80_RDW_GF31MS19-ORD.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS


Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.



PLAN


GENERAL NOTES

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




SECTION A-A

Typical




MOW STRIP DETAIL

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)


Curb shown on top of mow strip



CURB OPTION (3)

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF (31) MS-19			
FILE: gf31ms19.dgn	DN: TxDOT	CK: KM	DW: VP
© TxDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0096	06	075, Etc
	DIST	COUNTY	HIGHWAY
	TYL	GREGG	US 80
			SHEET NO.
			68






11/15/2022
 DATE: 11/15/2022
 FILE: c:\txdot\p_w_online\txdot3\will.ak\in\0552636\US80_RDW_GF31TRTL320-ORD.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- (5) 1" DIA. HOLES.
- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (FACING TRAFFIC SIDE) (ASTM F3125 GR A325 OR A449).
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 7/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563).


NOTE:
HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE:
CURB IS A REQUIRED COMPONENT FOR THE TRANSITION TO FUNCTION PROPERLY. SEE GENERAL NOTES: 2-4 AND 16-17.



THRIE-BEAM TERMINAL - CURB TABLE	
PRECAST CURB FULL LENGTH EQUALS 12'- 2"	
THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS.	
CURB (1) LENGTH	5'- 8"
CURB (2) LENGTH	6'- 6"
TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7	
CONNECTING PRECAST CURB SECTIONS (1) & (2):	
FORM OR CORE	1" DIA. HOLE 9" LONG INTO EACH CURB END.
USE	(1) #5 GR.60 REBAR 18" LONG TO CONNECT BOTH CURBS.
SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE *:	
FORM OR CORE	(4) 1" DIA. HOLES, SEE PLAN AND ELEVATION VIEWS FOR HOLE LOCATIONS. DRIVE (4) #5 GR.60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB.
	FILL HOLES WITH APPROVED GROUT MIXTURE.

* NOTES: NOT NEEDED FOR CAST-IN-PLACE. SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS. PERCUSSION DRILLING IS NOT PERMITTED WITH: TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.



NOTE: OPTIONS FOR TYPE II CURB:
1. PRECAST
2. CAST-IN-PLACE

GENERAL NOTES

1. CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
2. CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5- 3/4" HEIGHT); SEE CURRENT CCGG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE:17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
3. CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
4. UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
5. FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
6. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF (31) STANDARD SHEET.
7. THE POST LENGTH SHALL BE MARKED ON ALL 7'- 0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 5/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
8. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
9. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
10. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
11. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
12. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
13. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
14. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TXDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
15. REFER TO GF (31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
16. THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
17. IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION, (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED) (TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED) (STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT.2 FOR ADDITIONAL INFORMATION.

**HIGH-SPEED TRANSITION
SHEET 1 OF 2**

		Design Division Standard	
METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT			
GF (31) TR TL3-20			
FILE: gf31trtl320.dgn	DN: IxD01	CK: KM	DW: VP
©TXDOT: NOVEMBER 2020	CONT: 06	JOB: 075, Etc	US 80
REVISIONS	DIST: TYL	COUNTY: GREGG	SHEET NO. 69


DISCLAIMER:
 THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER.
 TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 11/15/2022
 FILE: c:\txdot\pw_online\txdot3\wil.ak\in\0552636\US80_RDW_GF31TRL320-ORD.dgn


REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)

END PAYMENT FOR METAL BEAM GUARD FENCE TRANSITION.
 BEGIN PAYMENT FOR METAL BEAM GUARD FENCE.


(SEE GF (31) STANDARD SHEET)



ELEVATION VIEW



SECTION D-D



THREE BEAM TRANSITION BLOCKOUT DETAILS

HIGH-SPEED TRANSITION







SHEET 2 OF 2



METAL BEAM GUARD FENCE
 THREE-BEAM TRANSITION
 TL-3 MASH COMPLIANT
 GF (31) TR TL3-20

FILE: gf31trtl320.dgn	DN: TXDOT	CK: KM	DW: KM	CK: CGL/AG
©TXDOT: NOVEMBER 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	70	

DATE: 11/15/2022
 FILE: c:\txdot\p\online\txdot3\will.ak\dw\sgt11s3118-ORD.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
 - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
 - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
 - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
 - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
 - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
 - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	5/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	5/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN. ITEM(26) 8" WOOD-BLOCKOUTS ITEM(27) 25' GUARD FENCE PANELS


Design Division Standard

MAX-TENSION END TERMINAL
 MASH - TL-3
 SGT (11S) 31-18

FILE: sgt11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096 06	075, E+e	US 80	
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	72	


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DATE: 11/15/2022
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0552636\US80_RDW_SG112S3118-ORD.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- * NOTES:**
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.





- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MOW STRIP STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.



NOTE: SEE (GENERAL NOTE 14) FOR DRIVING CAP INFORMATION.

SEE NOTES: *

ALTERNATIVE ITEMS NOT SHOWN. **
 * ITEM (P) 8" WOOD-BLOCKOUT
 ** ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.




ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	3/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	3/8" WASHER	W0516
c	2	3/8" HEX NUT	N0516
d	25	3/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	3/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	3/8" WASHER	W050
g	33	3/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	3/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151

SINGLE GUARDRAIL TERMINAL
MSKT-MASH-TL-3
SGT (12S) 31-18



FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT SECT	JOB	HIGHWAY	
REVISIONS	0096	06	075, Etc	US 80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG		73

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022 5:10:09 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0552636\US80_RDW_BED-14-ORD.dgn



- GENERAL NOTES**
- For more detail: See GF(31), SGT()31, GF(31)TR, and GF(31)TL2 standard sheets.
 - Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
 - Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
 - MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
 - Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
 - Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal, See Detail A)
 - The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
 - For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge location(s) shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
 - Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
 - A minimum 25' length of MBGF will be required.



Note: All rail elements shall be lapped in the direction of adjacent traffic.

Texas Department of Transportation

Design Division Standard


BRIDGE END DETAILS
(METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)

BED-14


FILE: bed14.dgn	DN: TxDOT	CK: AM	DW: BD/VP	CK: CGL
© TxDOT: December 2011	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
REVISED APRIL 2014 SEE (MEMO 0414)	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	74	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/15/2022
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0552636\US80_RDW_LPCB13.dgn



PLAN
(TYPE 1) BARRIER SEGMENT
 (SYMMETRICAL ABOUT CENTER LINES)




ELEVATION
(TYPE 1) BARRIER SEGMENT
 (SYMMETRICAL ABOUT CENTER LINES)




REINFORCING STEEL DETAILS
 TYPE 1 - BARRIER SEGMENT

Note: Use 2" Dia. Bending Pin, unless otherwise shown



SECTION A-A



SECTION B-B

GENERAL NOTES

1. Low Profile Concrete Barrier (LPCB), is approved for use in temporary work zone locations, where the posted speed is 45 mph, or less.
2. Concrete shall be Class H for precast barrier with a minimum compressive strength of 3,600 psi.
3. Where used, rebar reinforcement shall be Grade 60 and conform to ASTM A615.
4. Precast LPCB barrier length shall be 20 ft.
5. All barrier edges shall have 3/4" chamfer or a tooled radius.
6. Joint connection hardware shall be in accordance with Item 449, "Anchor Bolts." and is considered subsidiary.
7. Steel pipe required for joint connection bolts shall be galvanized in accordance with Item 445, "Galvanizing."
8. Welded wire reinforcement (WWR) may be used in lieu of conventional reinforcement for Type 1 barrier, and shall meet the requirements shown.

FOR CONTRACTORS INFORMATION ONLY


(TYPE 1) APPROX. QUANTITIES 20 FT. SECTION		
CONCRETE	CY	2.6
REINFORCING STEEL	LBS	330
TOTAL BARRIER WT.	LBS	11000

(WWR) GENERAL NOTES


1. Deformed Welded Wire Reinforcement shall conform to ASTM A497.
2. Welded wire cage may be cut or bent, if necessary, but must be approved by the Engineer.
3. Combinations of reinforcing steel and WWR are permitted, as directed by the Engineer. The dimensions from the end of the barrier section to the first wire shall not exceed 3".

REQUIRED (WWR) WIRE DESIGN

- 8 ~ (D31) Horizontal Wires (Equally spaced)
- 10 ~ (D20) Horizontal Wires (Equally spaced)
- 29 ~ (D20) Vertical Wires (Spaced as shown in Elevation View)



WELDED WIRE REINFORCEMENT (WWR) - OPTIONAL REINFORCING



Note: Rods, Hex nuts and Washers shall be Galvanized.




Texas Department of Transportation
 Design Division Standard

LOW PROFILE CONCRETE BARRIER PRECAST BARRIER (TYPE 1) LPCB-13

FILE: lpcb13.dgn	DN: TxDOT	CK: AM	DW: VP	CK: _____
© TxDOT December 2010	CONT SECT	JOB	HIGHWAY	
REVISIONS	0096 06	075, Etc	US 80	
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	75	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/15/2022
 FILE: c:\txdot\pw_online\txdot3\will.akfn\0552636\US80_RDW_LPCB13.dgn




TYPE 2 - NOTES


1. Welded wire reinforcement (WWR) is "not" an option for Type 2 Barrier.
2. Type 2 Barrier shall be used as an end treatment for the Type 1 barrier segments, when applicable.
3. The end treatment can be used without the anchor pins in locations that can accommodate approximately 4 ft. of lateral displacement of the end treatment. The use of non-pinned end treatment does not affect the performance or the deflection of the Low-Profile barrier system.
4. The anchor pins are all the same length and are to be driven flush with the top of the (Type 2) barrier surface.
5. The bends in the H3 and H1 bars are slight, no formal bend is necessary.
6. The Type 2 barrier segment must be lifted from the rear first, to prevent cracking of sloped section.
7. See LPCB sheet 1 for additional information.





BAR (#4)	X (IN.)	Y (IN.)
V3 BAR	20 1/4	14 1/2
V4 BAR	19 1/2	13 1/2
V5 BAR	18 1/2	12 1/4
V6 BAR	17 1/2	11 1/4
V7 BAR	17	10 1/4
V8 BAR	16 1/4	9
V9 BAR	15 1/2	8
V10 BAR	14 1/2	7
V11 BAR	13 3/4	6



REINFORCING STEEL DETAILS
TYPE 2 - END TERMINAL



Note: All V Bars are (#4)



FOR CONTRACTORS INFORMATION ONLY


(TYPE 2)		
APPROX. QUANTITIES 20 FT. SECTION		
CONCRETE	CY	1.65
REINFORCING STEEL	LBS	240
TOTAL BARRIER WT.	LBS	7000

SHEET 2 OF 2

Texas Department of Transportation
 Design Division Standard


LOW PROFILE CONCRETE BARRIER PRECAST BARRIER (TYPE 2) LPCB-13

FILE: lpcb13.dgn	DN: TxDOT	CK: AM	DW: VP	CK: _____
© TxDOT December 2010	CONT: 0096	SECT: 06	JOB: 075, Etc	HIGHWAY: US 80
REVISIONS	DIST: TYL	COUNTY: GREGG	SHEET NO. 76	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/15/2022
 FILE: c:\txdot\pw_online\txdot3\will.akf\0552636\US80_RDW_CCCG22-ORD.dgn




**TYPE I CURB (MONOLITHIC)
 2" - 4" HEIGHT**




**TYPE I CURB
 2" - 4" HEIGHT**




**TYPE I CURB AND GUTTER
 2" - 4" HEIGHT**




**TYPE II CURB (MONOLITHIC)
 5" - 5 3/4" HEIGHT**




**TYPE II CURB
 5" - 5 3/4" HEIGHT**




**TYPE II CURB AND GUTTER
 5" - 5 3/4" HEIGHT**




**TYPE III CURB (KEYED)
 2" - 4" HEIGHT**




**TYPE IIa CURB
 5" - 5 3/4" HEIGHT**




**TYPE IIa CURB AND GUTTER
 5" - 5 3/4" HEIGHT**



**TYPE IV CURB (KEYED)
 5" - 5 3/4" HEIGHT**



EXPANSION JOINT DETAIL




CURB TRANSITION

Note: To be paid for as Highest Curb

GENERAL NOTES

- All materials and construction shall be in accordance with Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- Concrete shall be Class A.
- When reinforcing bars are used, they shall be No.4 unless otherwise shown. The use of fiber reinforced concrete in lieu of reinforcing steel is acceptable. Use fibers meeting the requirements of DMS 4550, "Fibers for Concrete," and dose fibers in accordance with Material Producers List (MPL) "Fibers for Class A and B Concrete Applications."
- Round exposed sharp edges with a rounding tool, to a minimum radius of 1/4 inch.
- All existing curbs and driveways to be removed shall be sawed or removed at existing joints.
- Where concrete curb is to be placed on existing concrete pavement, Bar B may be drilled and grouted in place, or may be inserted into fresh concrete.
- Expansion and contraction joints shall be constructed to match pavement joints in all curbs and curb and gutter adjacent to jointed concrete pavement. Where placement of curb or curb and gutter is not adjacent to concrete pavement, expansion joints shall be provided at structures, curb returns at streets, and at locations directed by The Engineer.
- Vertical and horizontal dowel bars and transverse reinforcing bars shall be placed at four feet C-C.
- Dimension 'T' shown is the thickness of concrete pavement. When curb is installed adjacent to flexible pavement dimension 'T' is 8" maximum.
- Usual profile grade line. Refer to typical sections and plan-profile sheets for exact locations.
- One-half inch expansion joint material shall be provided where curb or curb and gutter is adjacent to sidewalk or riprap.
- When horizontal permissible construction joints are used, the longitudinal pavement steel shall be placed in accordance with pavement details shown elsewhere in the plans. Reinforcing steel for curb section shall then conform to that required for concrete curb.
- Bar B placement as needed (typically at four ft. C-C) to support curb reinforcing steel during concrete placement.



CURB TRANSITION NOTE:
 Field conditions may require a longer or shorter transition, and shall be shown elsewhere in the plans, or as directed by the Engineer.

				Design Division Standard	
CONCRETE CURB AND GUTTER					
CCCG-22					
FILE: cccg21.dgn	DN: TxDOT	CK: AN	DW: CS	CK: KM	
© TxDOT: JUNE 2022	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0096	06	075, Etc	US 80	
	DIST	COUNTY		SHEET NO.	
	TYL	REGG		77	

TABLE OF REPAIRS (NBI: 10-093-0-0096-04-056, CSJ: 0096-04-069)

REPAIR NO.	ITEM	BID ITEM DESCRIPTION	UNIT	QUANTITY	REPAIR DESCRIPTION/LOCATOR	DETAILS/NOTES
SP-1	0780 6002	CNC CRACK REPAIR (DISCRETE) (INJECT)	LF	3	Epoxy inject cracks in concrete diaphragms as shown on plans	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 5
M-1	0432 6033	RIPRAP (STONE PROTECTION) (18 IN)	CY	60	Place stone protection as shown on plans	

DATE:
FILE:




		Bridge Division	
SUMMARY OF REPAIRS			
NBI: 10-093-0-0096-04-056 US80 OVER LAKE DEVERNIA			
FILE:	DN: AA	CK:	DW: AA
JULY 2021 REVISIONS	CONT SECT 0096 06	JOB 075	HIGHWAY US80
	DIST	COUNTY	SHEET NO.
	TYL	GREGG	78

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.
6	TEXAS	F-21 (5)	54
STATE DIST. NO.	COUNTY	SECTION NO.	JOB NO.
10	Gregg	96 d 18	US-80

GENERAL NOTES

1. Layout, stations, and elevations shown are based on as-built plans. Copies of available portions of as-built plans may be provided upon request.
2. Repair locations and quantities are based on Condition Survey dated (10/2022). Current conditions may vary. Field verify locations and extent of repairs in the presence of the Engineer prior to ordering materials.
3. Existing Load Rating:
HS22.1 (INV)
HS36.8 (OR)


REPAIR CALL-OUT LEGEND



SYMBOL	APPLICABLE REPAIR AREAS
D-#	Deck, joints, overhangs, approach slabs
R-#	Rails, approach MBGF
SP-#	Superstructure elements, bearings
SB-#	Substructure elements
M-#	Miscellaneous (Riprap, shoulder drains, etc)

Description	ESTIMATED QUANTITIES						
	Unclass Struct Exc. C.Y.	C/A Con (Bents) C.Y.	C/A Con (Slabs) C.Y.	Reinf. Steel Lb.	Struct. Steel Lb.	16" Conc. Piling L.F.	Dry Riprap Type A C.Y.
2 End Bents	16	6.26		1,004		132	
2 Int. Bents		13.52		1,488		420	
2 End Slabs			55.20	10,364	30,880	140	
1 Int. Slab			25.02	4,730	15,485	60	
Total	16	19.78	80.22	17,566	46,365	552	123

Note:
Old Riprap shall become the property of the Contractor when removed. No compensation will be allowed for the removal, but the rock may be used as a portion of the New Riprap.



LAYOUT
CAMPBELLS LAKE BRIDGE

CONSTRUCTION NOTES

Perform concrete repairs in accordance with Item 780 "Concrete Crack Repair" and TxDOT's Concrete Repair Manual, Chapter 3, Section 5. A copy of this manual must be available onsite during all concrete repair operations.
Provide an approved Type IX epoxy conforming to DMS 6100 for pressure-injected crack repairs.
Additional damage caused to the structure during repair operations must be repaired at the Contractor's expense.

BRIDGE REPAIR LAYOUT
From As-Built




Texas Department of Transportation Bridge Division

BRIDGE REPAIR LAYOUT


NBI: 10-093-0-0096-04-056
US80 OVER LAKE DEVERNIA

FILE:	DN: AA	CK:	DW: AA	CK:
©TxDOT	JULY 2021	CONT	SECT	JOB
REVISIONS	0096	06	075	US80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	79	

DATE:
FILE:



CRACKING IN CONCRETE
DIAPHRAGM



EROSION AT NORTH-WEST
ABUTMENT



EROSION AT NORTH-EAST
ABUTMENT



EROSION AT NORTH-EAST
ABUTMENT

Note: Photos shown are not all encompassing of the damage and are for Contractor's information only to provide a general idea of existing conditions.



**BRIDGE CONDITION
PHOTOS**

NBI: 10-093-0-0096-04-056
US80 OVER LAKE DEVERNIA



FILE:	DW: AA	CK:	DW: AA	CK:
©TxDOT	JULY 2021	CONT	SECT	HIGHWAY
REVISIONS	0096	06	075	US80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	80	

TABLE OF REPAIRS (NBI: 10-093-0-0096-04-061, CSJ: 0096-04-072)

REPAIR NO.	ITEM	BID ITEM DESCRIPTION	UNIT	QUANTITY	REPAIR DESCRIPTION/LOCATOR	DETAILS/NOTES
SB-1	0420 6158	CL C CONC (PILE ENCASEMENT)	LF	48	Encase concrete piling at Bent 2 and 3 as shown on plans	
SB-2	0429 6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	80	Repair spalls throughout Bent 2 & 3 caps	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 2
SB-3	0429 6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	6	Repair spalling on NW & SW wingwalls	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 2
SP-1	0429 6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	10	Repair spalling in stem of beam 11 (facia beam) in span 2	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 2
R-1	0451 6024	RETROFIT RAIL (TY SSTR)	LF	260	Replace existing bridge rail with SSTR	See "RAIL RETROFIT" details
D-1	0429 6001	CONC STR REPAIR (CLEAN & COAT WTH EPOXY)	SF	15	Repair minor spalls throughout deck soffits of all spans	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 1
D-2	0429 6005	CONC STR REPAIR (DECK REP (FULL DEPTH))	SF	8	Repair deck overhang at North end of Bent 2 cap and South end of Bent 3 cap	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 3

DATE:
FILE:




		Bridge Division	
SUMMARY OF REPAIRS			
NBI: 10-093-0-0096-04-061 US80 OVER HAWKINS CREEK			
FILE:	DN: AA	CK:	HW: AA
JULY 2021 REVISIONS	CONT: 0096 SECT: 06	JOB: 075	HIGHWAY: US80
	DIST: TYL	COUNTY: GREGG	SHEET NO.: 81

STATE	COUNTY	SECTION	NO.	DATE
10	Gregg	96	4	19
				US80

GENERAL NOTES

- Layout, stations, and elevations shown are based on as-built plans. Copies of available portions of as-built plans may be provided upon request.
- Repair locations and quantities are based on Condition Survey dated (10/2022). Current conditions may vary. Field verify locations and extent of repairs in the presence of the Engineer prior to ordering materials.
- Existing Load Rating:
HS13.5 (INV)
HS22.5 (OR)

REPAIR CALL-OUT LEGEND




SYMBOL	APPLICABLE REPAIR AREAS
D-#	Deck, joints, overhangs, approach slabs
R-#	Rails, approach MBGF
SP-#	Superstructure elements, bearings
SB-#	Substructure elements
M-#	Miscellaneous (Riprap, shoulder drains, etc)

MATERIAL NOTES

Provide Class C concrete (f'c = 3600 psi) for full-depth deck repairs, concrete bridge railing, and concrete pile encasement.
Provide Type C concrete repair material conforming to DMS 4655, "Concrete Repair Materials", capable of achieving a minimum average 28-day compressive strength of 3600 psi for all vertical and overhead concrete repairs.
Provide Type X epoxy coating conforming to DMS 6100, "Epoxyes and Adhesives", for all deck soffit spill repairs.

CONSTRUCTION NOTES

Submit a detailed concrete repair procedure for approval prior to commencing work. All concrete repairs shall be performed in accordance with Item 429 and Chapter 3, Sections 1-3 of TxDOT's Concrete Repair Manual. A copy of the Concrete Repair Manual must be available on site during all repair operations.
Repair all damaged or loose concrete without damaging surrounding sound concrete that is to remain in place. Only use hand tools or power-driven chipping hammers (15 lb max) to remove concrete, unless otherwise approved by the Engineer.
Clean all reinforcing steel that is already exposed or that is exposed during chipping operations. Additional damage caused to the structure during repair operations must be repaired at the Contractor's expense.



BRIDGE REPAIR LAYOUT
From As-Built



BRIDGE REPAIR LAYOUT


NBI: 10-093-0-0096-04-061
US80 OVER HAWKINS CREEK

FILE:	DW: AA	CK:	DW: AA	CK:
©TxDOT	JULY 2021	CONT	SECT	JOB
REVISIONS	0096	06	075	HIGHWAY
	DIST	COUNTY		SHEET NO.
	TYL	GREGG		82

DATE:
FILE:




SPALLING IN DECK SOFFIT




CRACKING IN CONCRETE PILING



SPALLING IN BENT CAP SOFFIT



SPALLING IN DECK OVERHANG



SPALLING IN WINGWALL

STATE OF TEXAS
 SETH D. COLE
 131778
 LICENSED PROFESSIONAL ENGINEER
Seth Cole
 11/14/2022



Note: Photos shown are not all encompassing of the damage and are for Contractor's information only to provide a general idea of existing conditions.

BRIDGE CONDITION PHOTOS			
NBI: 10-093-0-0096-04-061 US80 OVER HAWKINS CREEK			
FILE:	DW: AA	CK:	CK:
JULY 2021 REVISIONS	CONT 0096	SECT 06	JOB 075 COUNTY GREGG
			HIGHWAY US80 SHEET NO. 83

TABLE OF REPAIRS (NBI: 10-093-0096-06-053, CSJ: 0096-06-075)

REPAIR NO.	ITEM	BID ITEM DESCRIPTION	UNIT	QUANTITY	REPAIR DESCRIPTION/LOCATOR	DETAILS/NOTES
M-1	0401 6001	FLOWABLE BACKFILL	CY	10	Repair undermined locations with flowable backfill	
M-2	0429 6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	6	Repair deteriorated concrete at North and South ends of culvert at interior wall	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 2
M-3	0429 6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	30	Repair various spalled and delaminated locations within Barrels 1 and 2	Refer to TxDOT's Concrete Repair Manual Chapter 3 Section 2




 Texas Department of Transportation		Bridge Division		
<h3>SUMMARY OF REPAIRS</h3> <p>NBI: 10-093-0-0096-06-053 US80 OVER HARRIS CREEK</p>				
FILE:	DN: AA	CK:	DW: AA	CK:
 JULY 2021 <small>REVISIONS</small>	CONT: 0096 SECT: 06	JOB: 075	HIGHWAY: US80	
	DIST: TYL	COUNTY: GREGG	SHEET NO.: 84	

DATE:
FILE:

PROJECT NO.	10-093-0-0096-06-053
DATE	11/14/2022
BY	SETH D. COLE
CHECKED BY	
SCALE	AS SHOWN

PROJECT NO.	10-093-0-0096-06-053
DATE	11/14/2022
BY	SETH D. COLE
CHECKED BY	
SCALE	AS SHOWN




PROJECT NO.	10-093-0-0096-06-053
DATE	11/14/2022
BY	SETH D. COLE
CHECKED BY	
SCALE	AS SHOWN

GENERAL NOTES

1. Layout, stations, and elevations shown are based on as-built plans. Copies of available portions of as-built plans may be provided upon request.
2. Repair locations and quantities are based on Condition Survey dated (10/2022). Current conditions may vary. Field verify locations and extent of repairs in the presence of the Engineer prior to ordering materials.
3. Existing Load Rating:
HS15 (INV)
HS20 (OR)

REPAIR CALL-OUT LEGEND



SYMBOL	APPLICABLE REPAIR AREAS
D-#	Deck, joints, overhangs, approach slabs
R-#	Rails, approach MBBF
SP-#	Superstructure elements, bearings
SB-#	Substructure elements
M-#	Miscellaneous (Riprap, shoulder drains, etc)

MATERIAL NOTES

Provide Type C concrete repair material conforming to DMS 4655, "Concrete Repair Materials", capable of achieving a minimum average 28-day compressive strength of 3600 psi for all vertical and overhead concrete repairs.

CONSTRUCTION NOTES

Submit a detailed concrete repair procedure for approval prior to commencing work. All concrete repairs shall be performed in accordance with Item 429 and Chapter 3, Section 2 of TxDOT's Concrete Repair Manual. A copy of the Concrete Repair Manual must be available on site during all repair operations.
Repair all damaged or loose concrete without damaging surrounding sound concrete that is to remain in place. Only use hand tools or power-driven chipping hammers (15 lb max) to remove concrete, unless otherwise approved by the Engineer.
Clean all reinforcing steel that is already exposed or that is exposed during chipping operations. Additional damage caused to the structure during repair operations must be repaired at the Contractor's expense.

BRIDGE REPAIR LAYOUT
From As-Built




Texas Department of Transportation
Bridge Division

BRIDGE REPAIR LAYOUT

NBI: 10-093-0-0096-06-053
US80 OVER HARRIS CREEK

FILE:	DN: AA	CK:	DW: AA	CK:
©TxDOT	JULY 2021	CONT	SECT	JOB
REVISIONS	0096	06	075	US80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	85	

DATE:
FILE:




SPALL IN TOP SLAB



UNDERMINING AT NORTH-WEST
CORNER SIDEWALK

North-East corner similar



DELAMINATION IN TOP SLAB



DETERIORATING CONCRETE AT
SOUTH END OF CULVERT

North end similar



Note: Photos shown are not all encompassing of the damage and are for Contractor's information only to provide a general idea of existing conditions.



11/14/2022

		Bridge Division	
BRIDGE CONDITION PHOTOS			
NBI: 10-093-0-0096-06-053 US80 OVER HARRIS CREEK			
FILE:	DW: AA	CK:	DW: AA
	CONT	SECT	HIGHWAY
JULY 2021 REVISIONS	0096	06	US80
	DIST	COUNTY	SHEET NO.
	TYL	GREGG	86

DATE:
FILE:



GENERAL NOTES:-
 All concrete shall be Class A. All corners for concrete posts shall be rubbed to 1/4" radius. Dimensions relating to reinforcing steel are to centers of bars.
 Vertical reinforcing for concrete posts shall be set when placing concrete in spans. All anchorage provisions are considered as part of the railing.
 Railing and other exposed metal surfaces shall be painted according to prevailing specifications; embedded metal shall not be painted.
 All Posts shall be set vertically.
 If the metal railing is properly cleaned by sandblasting or pickling, the shop coat of paint may be applied by spray.

DETAIL OF WF BEAM ANCHOR SECTION AND METHOD OF RAILERECTION
 Outside face of anchor section shall be aligned by transit or tight wire with such accuracy as to insure full bearing and true alignment of railing.
 All continuous lengths of railing between expansion joints of the structure or between expansion joints and end of railing shall be completely erected in an offset position & rigidly held to line and grade for a minimum of 48 hours after all posts are placed. The railing shall be completely supported independent of post forms.
 All spacer blocks shall be of identical thickness and each shall have parallel surfaces of contact.

TEXAS HIGHWAY DEPARTMENT
STANDARD RAILING
TYPE 4
R II
 (1946)

DW: - TRB	DRAWING	DATE	FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.
Dw: - RSG	Original	Jan. 1946	6	TEXAS	F 21(7)	40
Dw: - AHS	Revised	2-12-46				
Dw: - SER	Rev. - B-20-46 - C.H.B.					
TR: - RMP	(Post Spa. Joints)					
TR: - JTR	Revised	Aug. 1948	10	GREGG	96 4	19 US 80

FOR CONTRACTORS INFORMATION ONLY


Texas Department of Transportation

US 80
 HAWKINS CREEK RAIL
 AS-BUILT
 (TYPE 4)

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	87	

11/04/2022 06:07 AM
 DOCUMENT NAME




TYPICAL BENT ELEVATION
(Looking upstation)

TABLE OF PILE ENCASEMENT LENGTHS			
Bent	Pile	Length of Pile Encasement (ft)	Bent Total (ft)
Bent 2	3	6	42
	4	6	
	5	6	
	6	6	
	7	6	
	8	6	
Bent 3	6	6	6
	Total		48


- PILE ENCASEMENT PROCEDURE:**
- 1) Verify channel line elevations and report to the Engineer for possible adjustments.
 - 2) Submit a concrete mix design and procedures for casting the encasements for approval.
 - 3) Clean mud, grease, loose rust, and paint off the section of piling to be encased with hand tools and high pressure water.
 - 4) Place and secure the steel reinforcement and install formwork.
 - 5) Place the concrete in the encasement per approved procedures and in accordance with Item 420, "Concrete Substructures."
 - 6) Leave forms in-place for at least 48 hours.
 - 7) After encasements have obtained required strength, compact surrounding embankment match grade.

- CLEANING AND PREPARATION NOTES:**
- 1) Clean the entire contact area to be encased with hand tools and high pressure water blasting.
 - 2) Thoroughly clean all dust and debris from concrete surfaces before sealing all cracks.
 - 3) Apply a preapproved Type VIII or Type X Epoxy that meets the requirements of DMS 6100, Epoxies and Adhesives. Work the epoxy into the crack, then remove any excess epoxy from the surface before it sets. Place sealant while ambient temperature is between 55°F and 80°F and rising.
 - 4) Allow coating to cure a minimum of 24 hours prior to placing concrete.




ELEVATION OF PILE ENCASEMENT

- 1 See Table of Pile Encasement Lengths.
- 2 Field adjust encasement length based on actual conditions.
- 3 Seal gap with Class 4 or Class 7 joint sealant (DMS-6310).
- 4 Apply a preapproved Type VIII or Type X epoxy that meets the requirements of DMS 6100, Epoxies and Adhesives, to an area covering 3" above and 3" below the top of concrete encasement as shown. Refer to Painting Notes for more information. Payment for this work is subsidiary to Item 420, "Concrete Substructures."




ROUND ENCASEMENT
(Showing HP12x__ pile size)
This Option must be modified to ensure a minimum 2in clearance between reinforcing steel and piling.




SQUARE ENCASEMENT
(Showing 15" Option)

SECTION A-A




BAR C (#4)



BAR S (#4)


Arrange Bar C pairs to provide 1'-0" opening on opposite faces:
(Showing HP12x__ pile size)
This Option must be modified to ensure a minimum 2in clearance between reinforcing steel and piling.




- GENERAL NOTES:**
- Verify dimensions for piling encasements and ground elevations. Pile Encasement Length may be adjusted by the Engineer based on actual channel and ground line elevations.
 - Existing conditions may be under water. Contractor is responsible for dewatering. Payment for dewatering is subsidiary to Item 420, "Concrete Substructures." The Contractor may submit a plan that adequately demonstrates the ability to perform the repairs without dewatering to the Engineer for approval. If approved, dewatering may be waived.
 - Obtain approval for the mix design and the construction procedures before beginning work.
 - If underwater placement is approved, concrete mix should be designed for underwater placement and may require the use of anti-washout admixtures.
 - Provide concrete for the piling encasement capable of attaining an average concrete compressive strength of 3,000 psi within 24 hours and consisting of coarse aggregate grades not greater than No. 5 (3/4"). Provide a concrete mix with 2 gallons of corrosion inhibitor per CY.
 - Pile encasement will be paid for per the unit bid price for each linear foot of encasement, per Item 420, "CL C CONC(PILE ENCASEMENT)."
 - Provide Grade 60 reinforcing steel.

		Bridge Division	
<h2>PILE ENCASEMENT DETAILS</h2>			
NBI: 10-093-0-0096-04-061			
FILE: US80_BRG_PILING_COLLAR_DET	August 2022	CK:	DW:
CONT: 0096 06	SECT: 075, Etc	JOB: US 80	HIGHWAY:
DIST: TYL	COUNTY: GREGG	SHEET NO. 88	

DATE:
FILE:




**JOINT WITH
HOT Poured RUBBER SEAL**
(used with ACP Overlay)



DETAIL "B"


**PROCEDURE FOR CLEANING
AND SEALING EXISTING JOINT
WITH HOT Poured RUBBER SEAL**

- 1) Saw cut through the asphalt at the centerline of joint. Make multiple saw cuts to create a 1/2" minimum joint opening or match the existing joint opening. Clean joint opening of all old expansion materials/devices, bituminous materials, dirt, grease and all other deleterious materials in accordance with Item 438, "Cleaning and Sealing Joints."
- 2) Obtain approval of cleaned joint prior to proceeding with joint sealing operation.
- 3) Place backer rod into joint opening 1" below the top of concrete. Backer rod must be compatible with the hot poured rubber sealant and rated for a minimum of 400°F. The backer rod must be 25% larger than the joint opening. When sealing joints for slab spans, pan girder spans, or box beam spans, fill void below backer rod with extruded polystyrene foam.
- 4) Seal the joint opening with a Class 3, "Hot Poured Rubber." Seal flush to the top of the asphaltic concrete pavement.



AT CONCRETE BRIDGE RAIL

JOINT SEALANT TERMINATION DETAILS




JOINT SEAL UPTURN DETAIL

- 1) Backer rod must be 25% larger than joint opening and must be compatible with the sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as shown.
- 2) Use Class 3 hot poured rubber seal in accordance with DMS-6310, "Joint Sealants and Fillers". Prepare joint and seal in accordance with Item 438 "Cleaning and Sealing Joints."

GENERAL NOTES


Cleaning existing joint opening (full depth) of all debris, providing and placing backer rod, saw-cutting joint opening, and sealing joint is paid for by Item 438, "Cleaning and Sealing Joints" and measured by the foot of "Cleaning and Sealing of Existing Joints." Obtain approval for all tools, equipment, materials and techniques proposed for use to prepare the joint. For Class 3 Hot Poured Rubber Seal, provide backer rod compatible with the hot poured rubber sealant and rated for a minimum of 400°F. Provide Class 3 sealant in accordance with DMS-6310, "Joint Sealants and Fillers" for joints in asphalt overlay. Extend sealant up into rail or curb 3 inches on low side or sides of deck. Prepare surfaces where sealant is to be placed in accordance with manufacturer's specifications.




		Bridge Division	
CLEANING AND SEALING EXISTING BRIDGE JOINTS (MOD)			
FILE: cleanandseal/jts.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT AUGUST 2020	CONT: 0096	SECT: 06	JOB: 075, Etc
REVISIONS			HIGHWAY: US 80
	DIST: 10	COUNTY: GREGG	SHEET NO.: 89

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/18/2022 4:33:07 PM
 FILE: c:\txdot\pw_online\txdot3\w\l\l_aki\0586920\US80_BRG_RLSTD014-19.dgn




ROADWAY ELEVATION OF RAIL




INTERMEDIATE WALL JOINT DETAIL
 Provide at all interior bents without slab expansion joints.



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT



SECTION
ELEVATION
TERMINAL CONNECTION DETAILS



PLAN OF RAIL AT EXPANSION JOINTS
 Example showing Slab Expansion Joints without breakbacks.


- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Increase 2" for structures with Overlay.
- ③ Back of rail offset may, with Engineer's approval, be continued to the end of the railing.
- ④ Place 4 additional Bars R(#4) 3'-8" in length inside Bars S(#4) and centered 2'-0" from end of rail when Terminal Connections are required.

SHEET 1 OF 2


		Bridge Division Standard	
TRAFFIC RAIL SINGLE SLOPE			
TYPE SSTR			
FILE: r1std014-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONT	SECT	HIGHWAY
REVISIONS	0096	06	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	90	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:33:11 PM
 FILE: c:\txdot\pw_online\tdot3\w\l\l_akt\0586920\US80_BRG_RLSTD014-19.dgn




ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS




ON BRIDGE SLAB


SECTIONS THRU RAIL




BARS S (#4)



BARS U (#4)



BARS WU (#4)



OPTIONAL WELDED WIRE REINFORCEMENT (WWR)


- ② Increase 2" for structures with Overlay.
- ⑤ 5 1/4" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑥ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars must be furnished at the Contractor's expense.
- ⑦ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑧ No longitudinal wires may be within upper bend.
- ⑨ Bend or cut as required to clear drain slots.
- ⑩ Space U(#4) bars at 4" Max when end region of panel length is less than 6'-0" to side slot drain. Space U(#4) bars at 6" Max when end region of panel length is 6'-0" and greater to side slot drain.

CONSTRUCTION NOTES:
 This railing may be constructed by the slipform process when approved by the Engineer, with equipment approved by the Engineer. Provide sensor control for both line and grade. Tack welding to provide bracing for slipform operations is acceptable. Welding may be performed at a minimum spacing of 3 ft between the cage and the anchorage. It is permissible to weld to bars U, WU and S at any location on the cage. If increased bracing is needed, provide additional anchorage devices and weld in the upper two thirds of the cage. Paint welded areas on epoxy coated and/or galvanized reinforcing with an organic zinc rich paint in accordance with Item 445 "Galvanizing".
 If rail is slipformed, apply a heavy epoxy bead 1" behind toe of traffic side of rail to concrete deck just prior to slip forming. Provide a 3/8" width x 1/4" tall heavy epoxy bead with Type III, Class C or a Type V epoxy.
 The back of railing must be vertical unless otherwise shown in the plans or approved by the Engineer.

MATERIAL NOTES:
 Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.
 Provide Grade 60 reinforcing steel.
 Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized.
 Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars U and WU unless noted otherwise. Deformed WWR (ASTM A1064) may be substituted for Bars R and S, as shown. Combinations of reinforcing steel and WWR or configurations of WWR other than shown are permitted if conditions in the table are satisfied. Provide the same laps as required for reinforcing bars.
 Provide bar laps, where required, as follows:
 Uncoated or galvanized ~ #4 = 1'-7"
 Epoxy coated ~ #4 = 2'-5"


GENERAL NOTES:
 This rail has been successfully evaluated by full-scale crash test to meet MASH TL-4 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.
 Do not use this railing on bridges with expansion joints providing more than 5" movement.
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
 Shop drawings will not be required for this rail.
 Average weight of railing with no overlay is 376 pcf.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.



OPTIONAL SIDE SLOT DRAIN DETAIL

Note: Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. Drains should not be placed over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.



SECTION THRU OPTIONAL SIDE SLOT DRAIN

DESCRIPTION	LONGITUDINAL WIRES	VERTICAL WIRES
Minimum (Cumulative Total) Wire Area	1.067 Sq In.	0.267 Sq In. per Ft
Minimum	No. of Wires	Spacing
Maximum	8	4"
Maximum Wire Size Differential	10	8"
	The smaller wire must have an area of 40% or more of the larger wire.	

Texas Department of Transportation
 Bridge Division Standard


TRAFFIC RAIL SINGLE SLOPE

TYPE SSTR


FILE: r1std014-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: TxDOT
©TxDOT September 2019	CONTRACT	SECTION	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
	DIST	COUNTY	SHEET NO.	
	TYL	GREGG	91	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:33:28 PM
 FILE: c:\ttdot\pw_online\ttdot3\w\l\l_akt\0586920\US80_BRC_RLSTD039-19.dgn



SECTION **ELEVATION**
TERMINAL CONNECTION ON EXISTING RAIL WITHOUT OVERLAY




SECTION **ELEVATION**
TERMINAL CONNECTION ON EXISTING RAIL WITH OVERLAY

- ① 5 ~ 1" Dia holes and 2 1/2" Dia x 2" deep recesses. Holes and recesses must be core drilled. Percussion drilling is not permitted. Concrete spalls in rail exceeding 1/2" from edge of holes will be patched in accordance with Item 429, "Concrete Structure Repair" at the contractor's expense. Bolt recesses are only required when pedestrian sidewalks are adjacent to back of rail.
- ② 5 ~ 7/8" Dia F3125 Gr A325 Bolts with two 1 3/4" O.D. washers. Place washer under each head and nut. The 5 Terminal Connection Bolts must be tightened in a well distributed pattern so to prevent damage or distortion of the Thrie-Beam Connector and the MBGF Transition. Bolts must be cut off after installation so as to extend no more than 3/4" beyond nut. End of cut-off bolt must be painted with two coats of zinc-rich paint conforming to the Item "Galvanizing".
- ③ Existing anchor bolt holes in rail that can not be utilized and are within 3" of a new bolt hole must be filled with an epoxy grout prior to coring new holes.
- ④ If vertical taper is not present, then a vertical taper must be field cut to limits shown when the existing rail measurement is 2'-8". Rail measurement should be taken from behind rail as to not include overlay if present. If existing rail measurement is 2'-10" and existing rail does not have vertical taper, then add 2" to vertical dimensions and field cut vertical taper. Any exposed reinforcing steel from field cut taper must be ground flush and painted with two coats of zinc-rich paint conforming to the Item "Galvanizing".
- ⑤ 10 Gage Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Metal Beam Guard Fence Transitions must be attached to the bridge rail and extended along the embankment unless otherwise shown in the plans.
- ⑥ Terminal Connector must be modified for the Terminal Connection on Existing Rail with Overlay with two new 1" Dia holes as shown. Top new 1" Dia hole is used in lieu of existing top hole in terminal connector. All other existing holes in terminal connector must be used. Additional hole on bottom of terminal connector is used for other side for opposite hand. Damage to galvanization caused by this modification must be painted with two coats of zinc-rich paint conforming to the Item "Galvanizing".

CONSTRUCTION NOTES:
 Field verify dimensions before commencing work and ordering materials.
 Remove any MBGF (W-beam) and attachment hardware, from the face of rail if present, prior to installation of new MBGF Transition. Dispose of these materials as directed by the Engineer. Plugging of exposed existing bolt holes is not necessary except as stated herein or otherwise indicated on the plans. This work is considered subsidiary to the pertinent bid items.
 If vertical taper is not present, then a vertical taper must be field cut to limits shown and debris removed.
 Attach the MBGF Transition to the existing rail and extend along the embankment using the Thrie-Beam Terminal Connection unless shown otherwise on the plans. Splice the Approach Guard Rail and the Terminal Connection with the normal 12 connection bolts. Refer to Metal Beam Guard Fence detail sheets for additional details and information not shown herein.

MATERIAL NOTES:
 Galvanize all steel components unless otherwise noted.

GENERAL NOTES:
 These details are shown for retrofitting MBGF transitions to existing rails only and not used for new construction.
 Shop drawings are not required for this installation.
 Materials, fabrication and installation of this assembly are to be included in the price bid for "Metal Beam Guard Fence".




THRIE-BEAM TERMINAL CONNECTORS ⑤




		Bridge Division Standard	
T5/T501/T502 TRANSITION RETROFIT GUIDE (MOD)			
T5/T501/T502TR			
FILE: r1std039-19.dgn	DN: TxDOT	CK: APK	DW: JTR
CON: September 2019	SECT:	JOB:	HIGHWAY:
REVISIONS:	0096 06	075, Etc	US 80
DIST:	COUNTY:	SHEET NO.	
TYL	GREGG	92	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/18/2022 4:33:46 PM
 FILE: c:\txdot\pw_online\txdot3\w111_akt\0586920\US80_BRG_RLSTD022-20.dgn



SSTR RAIL



SSTR RAIL




ANCHOR BAR EA1 (#6)


RAIL RETROFIT SECTIONS ON CONCRETE SLABS USING ADHESIVE ANCHORS ⑨

RAIL RETROFIT SECTIONS ON WINGWALLS USING ADHESIVE ANCHORS ⑩


Rail retrofits on existing Traffic Rail Foundations (TRF) are similar.



ANCHOR BOLT OPTIONS AND ASSEMBLY DETAILS ⑬




RAIL RETROFIT SECTIONS ON SLABS USING ANCHOR BOLTS ⑭



ROADWAY ELEVATION OF T551 RAIL RETROFIT ⑦
 (SSTR Rail similar)

- ① When side slot drains are used, provide 8'-0" Min clear spacing between drain slots.
- ② Embed (#6) anchor bars with a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 5 1/4". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 20 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing".
- ⑤ See T551 or SSTR Rail Sections in "Rail Retrofit Section on Wingwalls using Adhesive Anchors" and/or "Rail Retrofit Section on Concrete Slabs using Adhesive Anchors".
- ⑦ Showing spacing of (#6) adhesive anchor in a rail retrofit condition. Secondary (#4) adhesive anchor in a rail retrofit not shown for clarity. Reinforcing steel and terminal connections not shown for clarity. See rail standard for details and notes not shown.
- ⑨ Showing location or locations of anchor bars in a rail retrofit condition. See appropriate rail standard for details and notes not shown.
- ⑩ Increase by amount of existing overlay/seal coat thickness, not to exceed 2". If thickness of existing overlay/seal coat is greater than 2" at toe of rail, taper overlay at a 1:10 or flatter slope over shoulder width to a thickness of 2" or less at toe of rail.
- ⑪ Do not cast rails or parapet walls on top of overlays/seal coats.
- ⑫ See appropriate rail standard for reinforcing steel. Modify length of vertical reinforcing bars as required to fit existing structure. Longitudinal reinforcing bars may be removed only if their position puts them in conflict with un-removed portions of existing structure.
- ⑬ Embed secondary (#4) anchor bars 1'-4" in length with a Type III Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 10 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing". (#4) anchor bars spaced longitudinally along rail at 4 ft Max (Spaced 3" longitudinally from outside edge and edge of side slot drains).
- ⑰ 1" Dia Anchor Bolt Spaced longitudinally along rail at 24" Max (Spaced 6" longitudinally from outside edge and edge of optional side slot drains, if required).
- ⑲ 1 1/16" to 1 1/4" Dia holes. Core drill holes through existing deck (percussion drilling not permitted). Concrete spalls in the bottom of the deck exceeding 1/2" from edge of holes will be patched in accordance with Item 429, "Concrete Structure Repair" at the Contractor's expense.
- ⑳ Showing location of anchor bars and anchor bolts in a rail retrofit condition. See appropriate rail standard for details and notes not shown.
- ㉑ 1" Dia ASTM F1554 Gr 55 Anchor Bolt or Threaded Rod. Nuts must conform to ASTM A563 requirements.
- ㉒ Plate Washer 3/8 x 3 x 3 ASTM A36 with 1 1/16" Dia Hole centered.
- ㉓ Galvanize anchor bolts, nuts and plate washers.




SHEET 1 OF 2

		Bridge Division Standard	
RETROFIT GUIDE FOR CONCRETE RAILS			
(SSTR) (MOD) C-RAIL-R			
FILE: r1std022-20.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
CON: TxDOT	SECT: September 2019	JOB: 0096 06	HIGHWAY: 075, Etc
REVISIONS:		DIST: TYL	COUNTY: GREGG
07-20: Text change from epoxy to adhesive and changed WASH Test Level note.			SHEET NO. 93

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/18/2022 4:33:50 PM
 FILE: c:\txdot\pw_online\txdot3\w\l\l_aki\0586920\US80_BRC_RLSTD022-20.dgn




T221 RAIL RETROFIT EXAMPLES 9

- 2 Embed (#6) anchor bars with a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 5 1/4". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 20 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing".
- 9 Showing location or locations of anchor bars in a rail retrofit condition. See appropriate rail standard for details and notes not shown.
- 10 Increase by amount of existing overlay/seal coat thickness, not to exceed 2". If thickness of existing overlay/seal coat is greater than 2" at toe of rail, taper overlay at a 1:10 or flatter slope over shoulder width to a thickness of 2" or less at toe of rail.
- 11 Do not cast rails or parapet walls on top of overlays/seal coats.
- 12 See appropriate rail standard for reinforcing steel. Modify length of vertical reinforcing bars as required to fit existing structure. Longitudinal reinforcing bars may be removed only if their position puts them in conflict with un-removed portions of existing structure.
- 13 Embed secondary (#4) anchor bars 1'-4" in length with a Type III Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 10 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing". (#4) anchor bars spaced longitudinally along rail at 4 ft Max (Spaced 3" longitudinally from outside edge and edge of side slot drains).
- 26 Remove existing rail, cut and grind anchor bolts flush, and paint ends with two coats of zinc-rich paint conforming to the Item "Galvanizing".
- 27 Void out area in rail retrofit to accommodate existing drain holes in deck.
- 28 Space (#4) stirrups at 8" Max. (Spaced 3 1/4" longitudinally from retrofitted ends of wingwall).
- 29 7 ~ (#5) bars with 3" end cover.
- 30 Space (#4) bars at 8" Max with 3" end cover, spaced with (#4) stirrups.
- 31 Remove all concrete and reinforcing steel from existing parapet wall. Existing reinforcing cut off from existing wingwall must be painted with two coats of a zinc-rich paint conforming to the Item "Galvanizing".
- 32 Face of rail and/or toe of rail. Location or placement of rail retrofit must match face of rail and/or toe of rail on bridge.

- Case (A): Permitted only with Type T221, T222, C221 and SSTR rails. Do not use this detail unless existing curb is at least 10" wide at its base and the flexural strength, Mn, of the curb at its base is at least 10.5 kip-ft per foot, with no strength reduction factor applied.
- Case (B): Locate anchor bar 2" from toe of curb.
- Case (C): Locate anchor bar no closer than 2" from toe of curb.
- Case (D): Do not remove any part of curb unless it has been determined to not be a structural element. Locate anchor bar 2" from toe of curb.



SECTION OF EXISTING PARALLEL WINGWALLS LESS THAN 12" THICK



SSTR RAIL
(On Assumed Existing Configuration)

- CONSTRUCTION NOTES:**
 Field verify dimensions before commencing work and ordering materials.
 By adding additional anchorage, welding can be performed at a minimum spacing of 3 ft between the cage and additional anchorage. By satisfying additional anchorage requirements slip forming is allowed. Do not weld to the required anchorage.
 Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.
- MATERIAL NOTES:**
 Provide Grade 60 reinforcing steel.
 Epoxy coat or galvanize all reinforcing steel if required elsewhere.
 (#6) and (#4) anchor bars used for the adhesive anchorage system must not be epoxy coated within the required embedment.
- GENERAL NOTES:**
 Use of these retrofit details will result in a railing acceptable for the MASH Test Level indicated on the applicable rail standard.
 Rail anchorage details shown on this guide may require modification for select structure types. See appropriate details elsewhere in plans for these modifications. Not all possible combinations of existing railing, curbs, parapets etc. have been shown on this sheet. Other combinations and reinforcement arrangements are permissible if they meet the same strength requirements as indicated on this guide.
 Do not remove any part of a curb until it has been evaluated to not be a load-carrying structural component.
 Removal and replacement of backfill, subgrade, and asphalt or concrete pavement necessary for this installation is considered subsidiary to the retrofit railing.
 Payment for a rail retrofit will be as per Item 451, "Retrofit Rail (Ty SSTR)".
 All details shown herein are subsidiary to rail retrofit.

Reinforcing bar dimensions shown are out-to-out of bar.




SHEET 2 OF 2


		Bridge Division Standard	
<h2>RETROFIT GUIDE FOR CONCRETE RAILS</h2>			
<p>(SSTR) (MOD) C-RAIL-R</p>			
FILE: r1std022-20.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONV	SECT	JOB
REVISIONS		0096 06	075, E+tc
07-20: Text change from epoxy to adhesive and changed MASH Test Level note.		DIST	COUNTY
		TYL	GREGG
		SHEET NO. 94	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/18/2022 4:40:05 PM
 FILE: c:\txdot\pw_online\txdot3\w11_0kfn\0586920\US80_BRG_SRRSTDE1-19.dgn




PLAN



ELEVATION




SECTION A-A AT CAP



SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A

CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2

		Bridge Division Standard	
<h1>STONE RIPRAP</h1>			
<h2>SRR</h2>			
FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH
©TxDOT April 2019	CONT	SECT	JOB
REVISIONS	0096	06	075, Etc
DIST	COUNTY	SHEET NO.	
TYL	GREGG	95	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:40:09 PM
 FILE: c:\t\dot\pw_online\txdot3\w\l\l\akIn\0586920\US80_BRG_SRRSTDE1-19.dgn




FIGURE 1 ~ TYPE R STONE RIPRAP
dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP
dry or mortared






FIGURE 3 ~ TYPE F STONE RIPRAP
grouted

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "Y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



MOUNDED TOE



EXTENDED ROCK FILLED TRENCH

PROTECTION STONE RIPRAP TOE OPTIONS ⑤




FIGURE 4 ~ COMMON STONE RIPRAP
dry or grouted




FIGURE 5 ~ PROTECTION STONE RIPRAP ⑤

STONE RIPRAP

SRR

FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES
CONT: April 2019	SECT: REVISIONS	JOB: 0096 06	HIGHWAY: 075, E+c	US 80
DIST: TYL	COUNTY: GREGG	SHEET NO.:	96	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:40:59 PM
 FILE: c:\txdot\pw_online\txdot3\will.akn\0586857\US80_TRE_DOM1-20.dgn











REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	DEVICE	SINGLE	DOUBLE	INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX)	
								NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount	
SHEETING: Yellow, White or Red Type B or C reflective sheeting				SHEETING: Yellow, White or Red Type B or C Reflective Sheeting				DIRECTION: If Required BI = Bi-Directional BR = Bi-Directional with red on back	
POST TYPE: WC, YFLX, WFLX				MOUNT TYPE: GND, SRF				INSTL OM ASSM (OM-XX) (XXXX)XXX(XX)	


OBJECT MARKERS								D & OM DESCRIPTIVE CODES			
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)	INSTL OM ASSM (OM-XX) (XXXX)XXX(XX)		
		OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4	TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION: If Required BI = Bi-Directional	
SHEETING: Yellow-Type B or C Sheeting		SHEETING: Yellow - Type B or C Sheeting			SHEETING: Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			SHEETING: Red -Type B _{FL} or C _{FL} Sheeting		DEPARTMENTAL MATERIAL SPECIFICATIONS FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES) DMS-4400 SIGN FACE MATERIALS DMS-8300 DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS DMS-8600	
POST TYPE: TWT		POST TYPE: WC			POST TYPE: WFLX			POST TYPE: TWT		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.	
MOUNT TYPE: WAS, WAP		MOUNT TYPE: GND			MOUNT TYPE: GND, SRF			MOUNT TYPE: WAS, WAP		Texas Department of Transportation Traffic Safety Division Standard	

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE:		
DEVICE	GF1	GF2	CTB	W1-8				W1-6		DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION D & OM(1)-20	
SHEETING: Yellow, White, Red			SHEETING: Yellow, White, Red				SHEETING: Yellow, White, Red		1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.		
NOTE: 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			NOTE: 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).				SIZE (W x L) 18"x 24" (Conventional) 24"x 30" (Conventional Oversize) 30"x 36" (Expressway) 36" x 48" (Freeway)		SIZE (W x L) 48" x 24" (Conventional) 60" x 30" (Expressway & Freeway)		
MOUNTING HEIGHT: 4'-0" or 7'-0"			MOUNTING HEIGHT: 4'-0" or 7'-0"				MOUNTING HEIGHT: 7'-0" Only		MOUNTING HEIGHT: 7'-0"		
REVISIONS: 0096 06 075, Etc US 80 DIST: COUNTY: SHEET NO.: 97 TYL: GREGG											

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:41:15 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586857\US80_TRE_DOM2-20.dgn

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS		
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT	
GND	GND	SRF	WAS	WAP	GF 1	
 <p style="text-align: center;">2'-0" Usual</p>						
	EMBEDDED	SURFACE MOUNT	STEEL	PLASTIC	CONCRETE TRAFFIC BARRIER (CTB)	
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.			NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		GENERAL NOTES 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.	
TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS			CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS	
 <p style="text-align: center;">4'-0"</p>			 <p style="text-align: center;">7'-0"</p>		 <p style="text-align: center;">Approximately 4'-0"</p>	
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)			NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		NOTE See general notes 1, 2 and 3.	



Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096 06		075, Etc	US 80
10-09 3-15	DIST	COUNTY		SHEET NO.
4-10 7-20	TYL	GREGG		98

20B


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:41:37 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586857\US80_TRE_DOM3-20.dgn

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation
Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS


D & OM(3)-20

FILE: dom3-20.dgn	DW: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	TYL	GREGG	99	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:42:03 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\40586857\US80_TRF_DOM6-20.dgn


CONTINUOUS CONCRETE OR STEEL BARRIER




MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



EMERGENCY CROSSOVER



NOTES

1. Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delineators. On Continuous Barrier, equal spacing (100' max.)
2. Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delineators.
3. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow










DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(6)-20

FILE: dom6-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
7-20	DIST	COUNTY	SHEET NO.	
	TYL	REGG	100	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:42:19 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\058685\US80_IRF_DOMVIA-20.dgn



OBJECT MARKERS SMALLER THAN 3 FT²

- NOTES**
- *1. Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
 - 2. Mounting should be flush with top of attenuator. Minimum size 96" x 24".




NOTES

1. Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
2. Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
3. Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
4. Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
5. Object Marker at nose of attenuator is subsidiary to the attenuator.
6. See D & OM (1-4) for required barrier reflectors.


<p>DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</p> <p>D & OM(VIA) -20</p>			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT	SECT	JOB
REVISIONS	0096	06	075, Etc
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	TYL	GREGG	101
4-98 7-20			
20G			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/18/2022 4:42:48 PM
 FILE: c:\txdot\pw_online\txdot3\w\l\l_aki\0586857\US80_TRE_PM1-20.dgn




**EDGE LINE AND LANE LINES
 ONE-WAY ROADWAY
 WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
 MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
 FOUR LANE TWO-WAY ROADWAY
 WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
 MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
 WITH OR WITHOUT SHOULDERS**




For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.

YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

GENERAL NOTES

- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
 EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD
 PAVEMENT MARKINGS**

PM(1) - 20


FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	0096	06	075, Etc	US 80
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	TYL	GREGG	102	

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 4:43:05 PM
 FILE: c:\txdot\pw_online\txdot3\will.akn\0586857\US80_TRE_PM2-20.dgn




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)





Type II (Top View)



RAISED PAVEMENT MARKERS

GENERAL NOTES

1. All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



NOTE
Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.




POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2) - 20

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	0096	06	075, Etc	US 80
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	TYL	GREGG	103	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:43:19 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586857\US80_TRE_PM3-20.dgn



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

LANE REDUCTION

NOTES


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES

- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE



TYPICAL TWO-LANE HIGHWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A

DETAIL B

Texas Department of Transportation
 Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 20

FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0096	06	075, Etc	US 80
5-00 2-10	DIST	COUNTY	SHEET NO.	
8-00 2-12	TYL	GREGG	104	
3-03 6-20				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


Post Type
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)

Anchor Type
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.


No more than 2 sign posts should be located within a 7 ft. circle.



BEHIND BARRIER




BEHIND GUARDRAIL



BEHIND CONCRETE BARRIER

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND




RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.



* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

Texas Department of Transportation
 Traffic Operations Division


SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD(GEN)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0096	06	075, Etc	US 80
		DIST	COUNTY		SHEET NO.
		TYL	GREGG		105

DATE: 11/18/2022 4:43:35 PM
 FILE: c:\txdot\pwworking\online\txdot3\will.ak\in\0586857\US80*TRF*SMDGEN.dgn

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



SM RD SGN ASSM TY XXXXX(X)SA(X-XXXX)

NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



5/8" diameter Concrete Anchor - 8 places (embed a minimum of 5 1/2" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:43:58 PM
FILE: c:\txdot\pwworking\online\txdot3\w111.akfn\0586857\US80*TRF*SMD51.dgn

Texas Department of Transportation
Traffic Operations Division





SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS		CONTRACT	SECTION	JOB
	0096	06	075, Etc		US 80
	DIST		COUNTY	SHEET NO.	
		TYL	GREGG	106	











DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:44:14 PM
 FILE: c:\txdot\pww\online\txdot3\will.ak\in\0586857\US80*TRF*SMD2.dgn



All dimensions are in english unless detailed otherwise.

SM RD SGN ASSM TY XXXX(1)XX(T)
 (* - See Note 12)



Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	













SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM
 SMD(SLIP-2)-08

© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0096	06	075, Etc	US 80
		DIST	COUNTY		SHEET NO.
		TYL	GREGG		107

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:44:27 PM
 FILE: c:\txdot\pww\online\txdot3\w\l\l.akfn\0586857\US80*TRF*SMD53.dgn



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Texas Department of Transportation
 Traffic Operations Division

**SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM**

SMD(SLIP-3)-08




© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0096	06	075, Etc	US 80
		DIST	COUNTY		SHEET NO.
		TYL	GREGG		108

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:44:47 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586857\US80_TRE_ISR3-13.dgn

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>


		Traffic Operations Division Standard	
<h3>TYPICAL SIGN REQUIREMENTS</h3>			
<h3>TSR(3) - 13</h3>			
FILE:	tsr3-13.dgn	DN:	TxDOT
©TxDOT	October 2003	CK:	TxDOT
REVISIONS		DW:	TxDOT
0096	06	CON:	SECT
075	Etc	JOB:	HIGHWAY
12-03	7-13	DIST:	US 80
9-08		COUNTY:	SHEET NO.
		TYL:	GREGG 109

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 4:45:04 PM
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586857\US80_IRF_ISR4-13.dgn

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

				<i>Traffic Operations Division Standard</i>	
<h2>TYPICAL SIGN REQUIREMENTS</h2>					
<h3>TSR(4) - 13</h3>					
FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT:	SECT:	JOB:	HIGHWAY:
REVISIONS		0096	06	075, Etc	US 80
12-03	7-13	DIST:	COUNTY:	SHEET NO.	
9-08		TYL	GREGG	110	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: _____
 FILE: _____

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. Longview MS4

2. No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Pose Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

-
-
-
-

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required Required Action

Action No.

- No Action necessary above those required by the 2004 Texas Standard for Specifications Construction and Maintenance of Highways. Streets & Bridges.
-
-
-

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required Required Action

Action No.

- ADHERE TO THE SPECS AS LISTED ABOVE
-
-
-

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required Required Action

Action No.

- ADHERE TO DIRECTION CONCERNING MIGRATORY BIRDS LISTED BELOW
- Possible habitat for the Monarch Butterfly and Northern Scarlet Snake
-
-

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required Required Action

Action No.

-
-
-

VII. OTHER ENVIRONMENTAL ISSUES


(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required Required Action

Action No.

-
-
-

US 80

 Texas Department of Transportation		Design Division Standard	
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC			
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (DS) REVISIONS	0096	06	075, Etc
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	TYL	GREGG	111

A. GENERAL SITE DATA

1. PROJECT LIMITS:
 FROM LOCKER PLANT RD (IN SEGMENTS), EAST TO SH 300
 PROJECT LENGTH = 37,562 FT. = 7.114 MILES
 PROJECT LOCATION:
 BEGIN PROJECT : R.M. 772+1.068
 END PROJECT : R.M. 780+1.297
 PROJECT COORDINATES:
 BEG LATITUDE: +32.530480 BEG LONGITUDE: -94.910133
 END LATITUDE: +32.504213 END LONGITUDE: -94.767828
2. PROJECT SITE MAPS:
 * PROJECT LOCATION MAP: **TITLE SHEET**
 * DRAINAGE PATTERNS: **MBGF LAYOUTS**
 * SLOPES ANTICIPATED AFTER MAJOR GRADINGS OR
 AREAS OF SOIL DISTURBANCE: **EXISTING AND PROPOSED TYPICAL SECTIONS**
 * LOCATION OF EROSION AND SEDIMENT CONTROLS: **MBGF LAYOUTS**
 * SURFACE WATERS AND DISCHARGE LOCATIONS: **MBGF LAYOUTS**
 * PROJECT SPECIFIC LOCATIONS: TO BE SPECIFIED BY THE PROJECT FIELD OFFICE
 DURING CONSTRUCTION AND LOCATED IN THE PROJECT SW3P FILE. REFERENCE
 ITEM #10 BELOW
3. PROJECT DESCRIPTION: **REPAIR AND RESURFACE ROADWAY**
4. MAJOR SOIL DISTURBING ACTIVITIES: **REMOVE AND REPLACE MBGF, INSTALL
 MOW STRIP, AND BRIDGE REPAIR WORK**
5. EXISTING CONDITION OF SOIL & VEGETATIVE
 COVER AND % OF EXISTING VEGETATIVE COVER: **PRIMARYLY SANDY LOAM,
 THE PROJECT SITE IS WELL VEGETATED**
6. TOTAL PROJECT AREA: **103 ACRES**
7. TOTAL AREA TO BE DISTURBED: **0.53 ACRES**
8. WEIGHTED RUNOFF COEFFICIENT
 BEFORE CONSTRUCTION: **N/A**
 AFTER CONSTRUCTION: **N/A**
9. NAME OF RECEIVING WATERS: (SEGMENT NUMBER OF RECEIVING WATERS)
THE RECEIVING WATERS ARE THE SABINE RIVER BASIN SEGMENT 0505.
10. PROJECT SW3P FILE: FOR PROJECTS DISTURBING ONE ACRE OR MORE,
 TXDOT WILL MAINTAIN AN SW3P FILE WITH ALL
 PERTINENT ENVIRONMENTAL DOCUMENTS,
 CORRESPONDENCE, ETC. AT THE PROJECT FIELD
 OFFICE. IF NO FIELD OFFICE IS AVAILABLE
 THEN THE SW3P FILE SHALL BE KEPT IN THE
 INSPECTOR'S TRUCK.

B. EROSION AND SEDIMENT CONTROLS

1. SOIL STABILIZATION PRACTICES:
 TEMPORARY SEEDING
 PERMANENT PLANTING, SODDING, OR SEEDING
 MULCHING
 SOIL RETENTION BLANKET
 BUFFER ZONES
 PRESERVATION OF NATURAL RESOURCES
 OTHER:
2. STRUCTURAL PRACTICES:
 SILT FENCES
 ROCK FILTER DAMS
 DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
 DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
 DIVERSION DIKE AND SWALE COMBINATIONS
 PIPE SLOPE DRAINS
 PAVED FLUMES
 ROCK BEDDING AT CONSTRUCTION EXIT
 TIMBER MATTING AT CONSTRUCTION EXIT
 CHANNEL LINERS
 SEDIMENT TRAPS
 SEDIMENT BASINS
 STORM INLET SEDIMENT TRAP
 STONE OUTLET STRUCTURES
 CURBS AND GUTTERS
 STORM SEWERS
 VELOCITY CONTROL DEVICES
 OTHER:
3. STORM WATER MANAGEMENT:
 STORM WATER DRAINAGE WILL BE PROVIDED BY **EXISTING DITCHES**
 THIS SYSTEM WILL CARRY THE DRAINAGE WITHIN THE RIGHT-OF-WAY TO
EXISTING OUTFALL CHANNELS
4. STORM WATER MANAGEMENT ACTIVITIES: (SEQUENCE OF CONSTRUCTION)
 1. **INSTALL EROSION CONTROL MEASURES AT LOCATION AS DIRECTED**
 2. **INSTALL MBGF, BRIDGE RAIL RETROFIT, BRIDGE REPAIRS**
 3. **PERFORM PLANING AND PLACE BASE IF APPLICABLE**
 4. **PLACE OCST AND ACP SURFACE**
 5. **PLACE SEEDING AND FERTILIZER AS DIRECTED**
 6. **WHEN ALL CONSTRUCTION ACTIVITY IS COMPLETE AND THE SITE IS
 STABILIZED AND APPROVED BY THE ENGINEER, REMOVE ALL TEMPORARY
 SEDIMENT CONTROLS AND RESEED ANY AREA DISTURBED DURING
 REMOVAL**
5. NON-STORM WATER DISCHARGES:
 FILTER NON-STORM WATER DISCHARGES, OR HOLD RETENTION BASINS,
 BEFORE BEING ALLOWED TO MIX WITH STORM WATER. THESE DISCHARGES
 CONSIST OF NON-POLLUTED GROUND WATER, SPRING WATER, FOUNDATION
 AND/OR FOOTING DRAIN WATER; AND WATER USED FOR DUST CONTROL,
 PAVEMENT WASHING AND VEHICLE WASHWATER CONTAINING NO DETERGENTS.

C. OTHER REQUIREMENTS & PRACTICES

1. MAINTENANCE:
 MAINTENANCE WILL BE PERFORMED AS INDICATED ON FIELD INSPECTION AND
 MAINTENANCE REPORT FORM 2118.
2. INSPECTION:
 INSPECTION WILL BE PERFORMED AS INDICATED ON FIELD INSPECTION AND
 MAINTENANCE REPORT FORM 2118.
3. WASTE MATERIALS:
 ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A
 LIDDED CONTAINER AND THEN DISPOSED OF IN A LEGAL AND
 PROPER MANNER. NO CONSTRUCTION WASTE MATERIAL WILL BE
 BURIED ON SITE.
4. HAZARDOUS WASTE (INCLUDING SPILL REPORTING):
 AT A MINIMUM, ANY PRODUCTS IN THE FOLLOWING CATEGORIES ARE
 CONSIDERED TO BE HAZARDOUS. PAINTS, ACIDS FOR CLEANING
 MASONRY SURFACES, CLEANING SOLVENTS, ASPHALT PRODUCTS,
 CHEMICAL ADDITIVES FOR SOIL STABILIZATION, OR CONCRETE
 CURING COMPOUNDS AND ADDITIVES. IN THE EVENT OF A SPILL
 WHICH MAY BE HAZARDOUS, THE SPILL COORDINATOR MUST BE
 CONTACTED IMMEDIATELY.
5. SANITARY WASTE:
 ALL SANITARY WASTE WILL BE COLLECTED FROM THE
 PORTABLE UNITS AS NECESSARY OR AS REQUIRED BY
 LOCAL REGULATION BY A LICENSED SANITARY WASTE
 MANAGEMENT CONTRACTOR.


OFFSITE VEHICLE TRACKING:

- HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- EXCESS DIRT ON ROAD REMOVED DAILY
- STABILIZED CONSTRUCTION ENTRANCE

OTHER:

REMARKS: DISPOSAL AREAS, STOCKPILES AND HAUL
 ROADS SHALL BE CONSTRUCTED IN A
 MANNER THAT WILL MINIMIZE AND
 CONTROL SEDIMENT FROM ENTERING
 RECEIVING WATERS. DISPOSAL AREAS
 SHALL NOT BE LOCATED IN ANY
 WATERBODY OR STREAMBED.

CONSTRUCTION STAGING AREAS AND
 VEHICLE MAINTENANCE AREAS SHALL
 BE CONSTRUCTED TO MINIMIZE THE
 RUNOFF OF POLLUTANTS.





**US 80
 STORM WATER
 POLLUTION
 PREVENTION
 PLAN (SW3P)**

©2023 Texas Department of Transportation
 SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075, Etc	US 80
DIST	COUNTY		SHEET NO.
TYL	GREGG		112

CK: DW: CK: DW:



CONCRETE WASHOUT AREA


NOT TO SCALE
(SEE NOTE 2)

NOTES

1. CONCRETE WASHOUT AREA(S) SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE. THE CONCRETE WASHOUT AREA SHALL BE ENTIRELY SELF-CONTAINED.
2. THE CONTRACTOR SHALL SUBMIT THE DESIGN, LOCATION AND SIZING OF THE CONCRETE WASHOUT AREA(S) WITH THE PROJECT'S EROSION AND SEDIMENTATION CONTROL PLAN AND SHALL BE APPROVED BY THE ENGINEER.

LOCATION: WASHOUT AREA(S) ARE TO BE LOCATED AT LEAST 50 FEET FROM ANY STREAM, WETLAND, STORM DRAINS, OR OTHER SENSITIVE RESOURCE. THE FLOOD CONTINGENCY PLAN MUST ADDRESS THE CONCRETE WASHOUT IF THE WASHOUT IS TO BE LOCATED WITHIN THE FLOODPLAN.

SIZE: THE WASHOUT MUST HAVE SUFFICIENT VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS INCLUDING, BUT NOT LIMITED TO, OPERATIONS ASSOCIATED WITH GROUT AND MORTAR.
3. SURFACE DISCHARGE IS UNACCEPTABLE, THEREFORE EARTH BERM OR OTHER CONTROL MEASURES, AS APPROVED BY THE ENGINEER, SHOULD BE USED AROUND THE PERIMETER OF THE CONCRETE WASHOUT AREA FOR CONTAINMENT.
4. SIGNS SHOULD BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CONCRETE AREA(S) AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CONCRETE WASHOUT TO OPERATORS OF CONCRETE TRUCKS AND PUMP RIGS. WASHOUT AREA(S) SHOULD BE FLAGGED WITH SAFETY FENCING OR OTHER APPROVED METHOD.
5. CONCRETE WASH-OUT AREAS SHALL BE LINED WITH IMPERVIOUS PLASTIC WITH A MINIMUM THICKNESS OF 6 MILS AND BE REPLACED IF DAMAGED DURING CLEAN-OUT OF HARDENED CONCRETE FROM THE WASH-OUT AREA.
6. WASHOUT AREA(S) ARE TO BE INSPECTED AT LEAST ONCE A WEEK FOR STRUCTURAL INTEGRITY, ADEQUATE HOLDING CAPACITY AND CHECKED FOR LEAKS, TEARS, OR OVERFLOWS. (AS DIRECTED BY THE CONSTRUCTION SITE ENVIRONMENTAL INSPECTION REPORT) WASHOUT AREA(S) SHOULD BE CHECKED AFTER HEAVY RAINS.
7. HARDENED CONCRETE WASTE SHOULD BE REMOVED AND DISPOSED OF WHEN THE WASTE HAS ACCUMULATED TO HALF OF THE CONCRETE WASHOUT'S HEIGHT. THE WASTE CAN BE STORED AT AN UPLAND LOCATION, AS APPROVED BY THE ENGINEER. ALL CONCRETE WASTE SHALL BE DISPOSED OF IN A MANNER CONSISTENT WITH ALL APPLICABLE LAWS, REGULATIONS, AND GUIDELINES.
8. PAYMENT FOR THIS ITEM IS TO BE INCLUDED UNDER THE GENERAL COST OF THE WORK FOR THE PROJECT, INCLUDING SITE RESTORATION.



Texas Department of Transportation

ROADWAY NAME


CONCRETE WASHOUT DETAIL

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0096	06	075,Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	113	


DATE: 11/18/2022 4:36:22 PM
FILE: c:\tdot\ipw_onlinetxdata\3\will.akm\054787\US80_ENV_CONCRETE WASHOUT DETAIL.dgn

10/18/2022
 c:\ttdot\pw_online\txdot3\will.akim\d0586919\US80_ENV_EC116.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF


GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1) - 16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0096	06	075, Etc	US 80	
	DIST	COUNTY		SHEET NO.	
	TYL	GREGG		114	

DATE: 11/19/2022
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586919\US80_ENV_EC216-ORD.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




FILTER DAM AT TOE OF SLOPE

(RFD1)




FILTER DAM AT SEDIMENT TRAP

(RFD1) OR (RFD2)




FILTER DAM AT CHANNEL SECTIONS

(RFD1) OR (RFD2) OR (RFD3)




PLAN VIEW

SECTION B-B




TYPE 4 (SACK GABIONS)


(RFD4)



SECTION A-A



PROFILE



SECTION C-C

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC(2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0096 06	075, Etc	US 80
	DIST	COUNTY	SHEET NO.
	TYL	GREGG	115

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/19/2022
 FILE: c:\txdot\p_w_online\txdot3\wil.akin\0586919\US80_ENV_EC916.dgn




PLAN VIEW



PLAN VIEW




PLAN VIEW



SECTION A-A

EROSION CONTROL LOG DAM


CL-D



SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



SECTION C-C


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
 - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
 - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
 - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
 - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
 - CL-DI EROSION CONTROL LOG AT DROP INLET
 - CL-CI EROSION CONTROL LOG AT CURB INLET
 - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.


- GENERAL NOTES:**
1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
 3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
 4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
 5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
 6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
 7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
 8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
 9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0096	06	075, Etc
	DIST	COUNTY	SHEET NO.
	TYL	GREGG	116


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/19/2022
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586919\US80_ENV_EC916.dgn



**EROSION CONTROL LOGS ON SLOPES
 STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


EROSION CONTROL LOG SPACING TABLE				
SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART





**EROSION CONTROL LOGS ON SLOPES
 STAKE AND LASHING ANCHORING**

CL-SSL




STAKE AND TRENCHING ANCHORING DETAIL

CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL



SHEET 2 OF 3


TRENCH DEPTH TABLE	
LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"



STAKE NOTCH DETAIL


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0096 06	075, Etc	US 80
DIST	COUNTY	SHEET NO.	
TYL	GREGG	117	

DATE: 11/19/2022
 FILE: c:\txdot\pw_online\txdot3\will.ak\in\0586919\US80_ENV_EC916.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0096 06	075, Etc	US 80
	DIST	COUNTY	SHEET NO.
	TYL	GREGG	118