

INDEX OF SHEETS

SEE SHEET 2

**STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT**

STATE AID PROJECT NO: C 28-15-59
CSJ 0028-15-059

NET LENGTH OF ROADWAY 6,267.36 FEET = 1.187 MILES
NET LENGTH OF PROJECT 6,267.36 FEET = 1.187 MILES

**BU 90Y
ORANGE COUNTY**

LIMITS: FROM 16TH STREET, EAST TO SIMMONS DRIVE

FOR THE CONSTRUCTION OF ROADWAY RESURFACING
CONSISTING OF A MILL, CLEAN AND SEAL JOINTS, OCST, AND 2" SUPERPAVE OVERLAY



BEGIN PROJECT
CSJ 0028-15-059
REF MK 480+0.504
STA 10+00

END PROJECT
CSJ 0028-15-059
REF MK 442 +1.109
STA 72+41

PROJECT NO.			
C 58-15-59			
CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		1

DESIGN CRITERIA: PM
DESIGN SPEED = N/A
A. D. T. (2023) = 12,000
A. D. T. (2043) = 16,600

FINAL PLANS

LETTING DATE: _____

DATE CONTRACTOR BEGAN WORK: _____

DATE WORK WAS COMPLETED & ACCEPTED: _____

FINAL CONTRACT COST: \$ _____

CONTRACTOR : _____



©2022 BY TEXAS DEPARTMENT OF TRANSPORTATION. ALL RIGHTS RESERVED.

SUBMITTED FOR LETTING: 12/1/2022
DocuSigned by: [Signature]
PROJECT ENGINEER
DB12FD46E9F04E5...

APPROVED FOR LETTING: 12/2/2022
DocuSigned by: [Signature]
DISTRICT ENGINEER
578CD749506D7F0...

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH
BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS
MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".


SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,
NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS,
SHALL GOVERN ON THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS
FOR ALL STATE CONSTRUCTION PROJECTS. (SP 000---007)

SCALE
0 0.4 0.8 MILE
EXCEPTIONS: STA 25+05 TO STA 26+24
EQUATIONS: NONE
RAILROAD CROSSINGS: UPRR

DATE: 12/1/2022 4:01:26 PM
FILE: c:\txdot\pww_online\smontno_harris\0646045\A_1\file.dgn

INDEX OF SHEETS

SHEET NO.	DESCRIPTION	SHEET NO.	DESCRIPTION
	<u>GENERAL</u>		<u>ENVIRONMENTAL ISSUES</u>
1	TITLE SHEET	65	SW3P-I
2	INDEX OF SHEETS	66	EPIC
3-4	TYPICAL SECTIONS	67-71	SW3P LAYOUT
5-10	GENERAL NOTES	72	INLET PROTECTION DETAIL
11-12	ESTIMATE & QUANTITY	## 73	EC (1)-16
13-16	QUANTITY SUMMARY	## 74-76	EC (9)-16
	<u>TRAFFIC CONTROL PLAN STANDARDS</u>		
17	SEQUENCE OF WORK		
## 18-29	BC (1)-21 THRU BC (12)-12		
## 30	TCP (2-4)-18		
## 31	TCP (3-1)-13		
## 32	TCP (3-3)-14		
## 33	WZ (STPM)-13		
## 34	WZ (RS)-22		
	<u>ROADWAY DETAILS</u>		
35-39	ROADWAY LAYOUT		
40	INTERSECTION DETAIL		
## 41	RS (5)-13		
	<u>PAVEMENT MARKINGS & DELINEATION</u>		
42-46	PAVEMENT MARKING LAYOUT AND SIGNING		
47-48	SUMMARY OF SMALL SIGNS		
## 49	PM (1)-22 (MOD)		
## 50	PM (2)-20		
## 51	PM (3)-20		
## 52	PM (4)-22		
## 53	SMD (GEN)-08		
## 54	SMD (SLIP-1)-08		
## 55	SMD (SLIP-2)-08		
## 56	SMD (SLIP-3)-08		
## 57	TSR (3)-13		
## 58	TSR (4)-13		
## 59	TSR (5)-13		
	<u>RAILROAD DETAILS</u>		
60	RAILROAD DETAILS		
61	RAILROAD SCOPE OF WORK		
62-63	RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECT		
## 64	RCD (1)-16		



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE WITH AN "##" HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

P.E. 11/20/2022
 NAME DATE

INDEX OF SHEETS




CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		2



DATE: 11/18/2022 6:14:26 PM
 FILE: c:\txdot\pw_online\txdot5\samantha_harris\d0646045\B_Index_of_Sheets.dgn

DATE: 11/18/2022 5:10:42 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Typical_Section.dgn



NOTE:
 "*" MEANS IT IS ATTACHED TO STA. 10+28 TO STA. 13+86
 "**" MEANS IT IS ATTACHED TO STA. 28+97 TO STA. 34+40



EXISTING TYPICAL SECTION
 STA. 10+00 TO STA. 10+28 NO WORK
 * STA. 10+28 TO STA. 13+86
 ** STA. 28+97 TO STA. 34+40




PROPOSED TYPICAL SECTION
 STA. 10+00 TO STA. 10+28 NO WORK
 * STA. 10+28 TO STA. 13+86
 ** STA. 28+97 TO STA. 34+40



BU 90Y
 TYPICAL SECTIONS
 SHEET 1 OF 2
 N. T. S


CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	3	

DATE: 11/18/2022 5:10:44 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\ND_Typical_Section.dgn




EXISTING TYPICAL SECTION

STA. 13+86 TO STA. 25+05
 STA. 25+05 TO STA. 26+24 (NO WORK)
 STA. 26+24 TO STA. 28+97
 STA. 34+40 TO STA. 72+40





EXIST VARIES FROM 1.5" TO 3.25" ACP OVERLAY
 EXIST 7.5" CONC. PAV.



PROPOSED TYPICAL SECTION

STA. 13+86 TO STA. 25+05
 STA. 25+05 TO STA. 26+24 (NO WORK)
 STA. 26+24 TO STA. 28+97
 STA. 34+40 TO STA. 72+40



11/20/2022

BU 90Y
TYPICAL SECTIONS
SHEET 2 OF 2
 N. T. S.

CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		4

Highway: BY 90Y

Control: 0028-15-059

GENERAL NOTES:

Contractor questions on this project are to be addressed to the following individual(s):

Name Bryce Broussard, P.E.

Email Bryce.Broussard@txdot.gov

Name Jim Grissom, P.E.

Email Jim.Grissom@txdot.gov

Contractor questions will be accepted through email, phone and in person by the above individuals.

All contractor questions will be reviewed by the Area Engineer or Assistant Area Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Maintain adequate drainage throughout the limits of the project during all construction phases. Provide a weekly a list of equipment, including idle equipment, used on the project each week.

BNSF, KCS, SRN, TR, AND UPRR.

The Union Pacific Railroad right of way is located within this project. Take necessary precautions to insure that no debris or material is dropped on the railroad's tracks.

Item 6 Control of Materials

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

Item 7 Legal Relations and Responsibilities

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Maintain ingress and egress to the adjacent property at all times. Consider this work to be subsidiary to the various bid items of the contract.

Highway: BY 90Y

Control: 0028-15-059

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

The following significant traffic generator events have been identified in the project limits: Art in the Park and the Orange Riverfront Car Show; Jimmy Fortune with Special Guests, The Malpass Brothers at the Lutcher Theater; Tootsi at the Lutcher Theater; July 4th Concert & Fireworks

Item 8 Prosecution and Progress

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Submit monthly progress schedules in accordance with 8.5.5.2.3. Failure to supply updated project schedule may result in the Engineer withholding progress (monthly) payments.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Notify the Engineer 72 hours in advance of any temporary or permanent lane closures, detours, or restrictions to lane widths, or alterations to vertical clearances. Any other modification to the roadway that may adversely affect the mobility of oversized/overweight trucks will require 5 business day advance written notice to the Engineer.

Night work may be required on all projects. If required, nighttime hours will be defined as 9:00 PM until 5:00 AM, Sunday night thru Thursday night. Ensure all lanes are reopened by 5:00 A.M.

Night work will be allowed.

Maintain one lane open to traffic during construction, unless otherwise approved.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

Limit lane closures to the length that can be worked full width in 1 night.

Supplemental lighting in addition to lighting on equipment and work vehicles will be required to insure adequate lighting for workers safety and inspection. All operations including planing and ACP placement must be adequately lighted using supplemental lighting. All supplemental lights are subject to the approval of the Engineer. Supplemental lighting will be added to the milling machine, asphalt distributor, aggregate spreader, rollers and laydown machine unless otherwise approved. This is considered subsidiary to the various bid Items of the contract.

Highway: BY 90Y**Control: 0028-15-059**

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

The construction sequence may be modified as directed and approved.

Law enforcement will be considered for this contract under the following conditions unless otherwise directed:

- Work involving controlled access facilities,
- Night work operations that create substantial traffic safety risks for workers and/or road users,
- Major traffic shifts involving high speed (greater than 55 MPH) and/or high volume roadways (ADT exceeds 10,000),
- Traffic shifts at intersections where unexpected or sudden queuing is anticipated,
- Complex intersections where flaggers may not be able to maintain adequate traffic control.

Provide one full-time, off-duty uniformed officer, with transportation jurisdiction and full police powers in the county or city in which the project is located, during construction as directed. The officer must be able to show proof of certification by the Texas Commission on Law Enforcement Officers Standards.

Officer will be paid by force account, and must be approved. The vehicle used must be a marked law enforcement vehicle in the city or county where the project is located. Complete the daily tracking form provided by the Department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

HURRICANE

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

Item 300 Asphalts, Oils, and Emulsions

Furnish non-tracking tack coat meeting the requirements of SP 300-020.

Highway: BY 90Y**Control: 0028-15-059****Item 316 Seal Coat**

Furnish medium pneumatic-tire rollers in accordance with Item 210, "Rolling."

All trucks hauling materials to be paid for by truck measurement will be "struck off" before delivery to the project.

Remove vegetation and blade pavement edges, including curb and gutters. This work will not be paid for directly but will be considered subsidiary to Item 316/318.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planing or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

The open season for the application of asphalt is May 1st through September 15th unless otherwise directed in writing.

Seal intersections and driveways before sealing the main lanes. Seal all existing roadway surfaces, including extra widths, crossovers, roadside parks, picnic areas, mailbox turnouts, public road intersections, and public drives, within the limits of each project. Do not seal intersections or driveways surfaced with ACP.

Sweep all roadways with a powered rotary broom before placement of the surface treatment to remove all loose or excess material or debris. After rolling, sweep as soon as aggregate has sufficiently bonded to remove excess. Use a vacuum broom on all roadway sections with curb and gutter and all roadway sections within the city limits of any city.

Station limits may be adjusted as directed to meet varying field conditions

Item 354 Planing and Texturing Pavement

Complete planing operations in adjacent lanes and shoulders to the same point at the end of each day.

Stockpile salvaged materials at SH 87 across from the Orange County Airport (approximate GPS location 30.066714°, -93.798198°). Contact Jodi Hand, Orange Maintenance Supervisor, at (409)883-3476 prior to stockpiling at this location.

Schedule the work so that Superpave is placed no more than two weeks after milling has been performed on any pavement surface, unless otherwise approved. The Engineer may require the seal coat to be placed sooner than two weeks in cases when base materials are exposed or when the pavement structure is showing signs of distress.

Remove any and all asphalt materials that may remain on the concrete surface after milling due to irregularities in the underlying section (i.e. scabbing). Up to 1 in of adjacent shifted or faulted concrete slabs may be milled to remove scabs and improve ride.

If the Engineer determines an adjacent driveway needs to be tapered back to prevent a drop-off an additional pass will need to be made to taper the driveway as directed or for a distance of 24" into the driveway. This work will be measured and paid for under Item 354.

Highway: BY 90Y**Control: 0028-15-059**

Cut and/or remove raised concrete repair areas, concrete curb, exposed rebar, etc. flush with the concrete pavement surface. This work will not be paid for directly but will be subsidiary to Item 354.

Item 361 Repair of Concrete Pavement

Schedule work so that concrete placement follows full-depth saw-cutting by no more than 72 hours on typical roadways unless otherwise approved. Repairs located within bridge approach slabs are to be replaced the day after sawing unless otherwise approved.

Complete repairs so that longitudinal joints fall on edge of travel lane or center of travel lane. No joints will be allowed in the wheel paths.

All material generated, including concrete slurry, as a result of saw cutting will be collected and kept from entering waterways, culverts, roadway inlets, and ditches.

Work will be conducted in such a manner so that all materials will be collected before the end of each day and especially before any rainfall event. Material from saw cutting will not be allowed to be tracked by traffic to other areas. Adequate sweeping, vacuuming and hauling equipment will be maintained on the project to conduct material collection and recovery on a continuous basis. Curb inlets will be blocked and protected during grinding and sweeping operations, but fully opened before a rainfall event. Disposal of the material produced by the sawing operation will be to a solid waste facility authorized to handle such material. The Contractor will, before beginning operations, provide a plan outlining the method of collection and disposal of this material for approval. The plan will also include the name and location of the facility receiving the solid waste. All work, equipment, materials and fees necessary to collect and dispose of this material will be considered subsidiary to this item and not paid for directly.

Provide Class HES concrete. The coarse aggregate will be either Grade 2 or 3. A set accelerating admixture or high range water reducer may be necessary to meet the compressive strength requirements: this will require the written approval of the Engineer and will be subsidiary to the bid item. A satisfactory work plan for control must be submitted by the Contractor and approved before use. An evaluation of the concrete containing the admixture will be performed by the Engineer. Design the Class HES concrete to meet the requirements of Class P and a minimum average compressive strength of 1800 psi in 4 hours.

Where repairs in jointed pavement require the removal of a transverse joint, construct a new joint at the same location.

Where patches in jointed pavement require the removal of an existing dowel basket assembly, install a new basket in the same location.

Saw-cutting will not be paid for directly, but will be considered subsidiary to this Item. Schedule work, such that concrete placement follows full-depth saw-cutting by no more than three days. Saw-cutting of existing concrete pavement across existing cracks will not be allowed unless approved.

Highway: BY 90Y**Control: 0028-15-059**

Placement of removed slabs onto concrete pavement which is to remain in place will not be allowed. All removed portions of concrete will be removed from the project the same day as removed from the roadway. Breaking removed portions of concrete on the top of the existing pavement will not be allowed.

Concrete removal will not be permitted when impending weather conditions may result in rainfall which will delay the concrete placement. If rainfall should occur after concrete placement operations have commenced, the Contractor will have ample covering on hand to protect the work.

For all concrete patches without an asphaltic concrete pavement overlay or seal coat, provide a vibratory screed at least two (2) feet longer than the width of the pavement to be used in finishing all repaired areas ten (10) feet or longer in length.

Station limits may be adjusted as directed to meet varying field conditions

The size, location, and number of patches are approximate and subject to change as directed. Any additional sawing required as a result of these changes will not be paid for directly, but will be considered subsidiary to this Item.

Saw and seal completed patches around the perimeter of the patch (Method B) for all patches without an asphaltic concrete pavement overlay. Fill all joints with Class 3 hot poured rubber and backer rod for all patches without an asphaltic concrete pavement overlay. This work will not be paid for directly, but will be considered subsidiary to this Item.

Maturity Testing

Maturity testing, Tex-426-A, will be allowed for concrete pavement. Unless otherwise approved, use the maturity method in accordance with test method Tex-426-A to estimate concrete strength. The Maturity system will not be paid for directly, but is considered subsidiary to this item.

Provide to the Engineer, the Intellirock or Command Center maturity system (or approved equivalent) for testing concrete maturity. This system will include the logger/sensor, handheld reader, and software. The Intellirock system can be obtained from Nomadics Construction Labs (405-372-9535) and the Command Center system can be obtained from the Transtec Group (512- 451-6233). Provide two (2) sensors per mix design and one (1) sensor to be placed in the last concrete pour per location site per day. Up to ten (10) additional sensors may be required and placed as directed. Furnish the concrete necessary to establish the maturity curve for testing. This work is to be performed before any concrete being placed and will not be paid for directly, but will be considered subsidiary to this Item.

Item 438 Cleaning and Sealing Joints

Allow the Joint Seal to cure a minimum of 7 days before applying the One Course Surface Treatment.

Provide Class 3 "Hot Poured Rubber", in accordance with DMS-6310. Existing joint seal material to be removed by sawing unless otherwise approved.

Clean and seal entire length of all joints in concrete pavement. After the removal of the existing joint sealant

Highway: BY 90Y**Control: 0028-15-059**

material is complete, the vertical joint faces will be cleaned by sandblasting.

Collect and dispose of all the removed material on a daily basis.

After sandblasting the joints, water blast each joint to ensure removal of all fines and dust. Follow water blasting with air blasting to ensure a dry joint prior to placing the hot poured rubber. Ensure a surface dry joint prior to placing the hot poured rubber.

Item 502 Barricades, Signs, and Traffic Handling

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

<u>Square Feet</u>	<u>Minimum Thickness</u>
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Arrange asphalt laydown schedule to meet plan striping requirements.

Restrict work to one side of the roadway at a time.

The following roadways have been determined to be high volume for the purpose identified in Note 4 of the "Typical Location of Crossroad Signs" on the BC(2) standard sheet: SH 87, 16th St, 10th St, FM 1006/8th St, 6th St, BU90Y

The following roadways have been determined to be low volume for the purpose identified in Note 2 of the "Typical Location of Crossroad Signs" on the BC(2) standard sheet: 15th St, 14th St, 13th St, 12th St, 11th St, 9th St, 7th St, 5th St, 4th St, 3rd St, 2nd St, 1st St, Mill St

Use drums as channelizing devices.

Remove all traffic control devices from the right of way when they are not in use. Devices scheduled to be used within 3 days may be placed along the shoulder of the roadway or along the right of way when not in

use, or stored in other approved areas on the project. Cover any construction signs that are not in effect and are installed in a fashion that will not allow them to be removed from the right of way easily.

Highway: BY 90Y**Control: 0028-15-059**

Provide construction fencing as approved at all work locations to protect pedestrian or bicycle traffic. This material and its placement will be considered subsidiary to Item 502.

Arrange construction operations to prevent the hauling of materials through the completed pavement sections unless otherwise approved.

Provide all flaggers and pilot vehicle drivers with two-way radio communication capability. Provide flaggers at each side road intersection.

Item 506 Temporary Erosion, Sedimentation, and Environmental Controls

The Contractor will designate a clean out area for concrete trucks. No other area will be allowed without approval of the Engineer.

Item 585 Ride Quality for Pavement Surfaces

Use Surface Test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

Item 666 Retroreflectorized Pavement Markings

Furnish Type II drop-on glass beads.

Item 672 Raised Pavement Markers

Remove all existing traffic buttons before the application of the seal coat. Consider this work to be subsidiary to the various bid items of the contract.

Item 720 Repair of Spalling in Concrete Pavement

Provide rapid-set concrete that meets DMS-4655, for patches with a volume of 0.30 cubic feet or more AND 3 inches minimum in the least dimension. Otherwise, provide polymeric patching material that meets DMS-6170, Type II, semi-rigid material.

Item 3077 Superpave Mixtures

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC "Superpave Gyration Compactor" and TGC "Texas Gyration Compactor". All other equipment must be provided by TxDOT. TxDOT

Highway: BY 90Y**Control: 0028-15-059**

will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68°F through 72°F).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

1. A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
2. Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
3. Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
4. An operational telephone system.
5. Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
6. Water (for testing purposes) from an approved source
7. Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.

Highway: BY 90Y**Control: 0028-15-059**

8. A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment
 9. A laboratory sink measuring 24 × 30 in. and 12 in. deep
 10. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.
- Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes.

RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements.

Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

A material transfer device (MTD) will be required for all surface courses of HMA on this project. An MTD is defined as a self-propelled, wheel-mounted vehicle capable of receiving HMA from the haul trucks separate from the paver. The MTD will have a minimum storage capacity of approximately 25 tons and will be equipped with a pivoting discharge conveyor and a means of completely remixing the HMA before placement. The Engineer may approve an alternative device on a trial basis for the surface course. This device will be capable of receiving HMA separate from the paver and must have remixing capabilities. For all other courses of HMA, other than the surface, an alternative device may be used as long as it is capable of receiving HMA separate from the paver.

Highway: BY 90Y

Control: 0028-15-059

Overlay across the ends of any curb ramps must not create a barrier to their use. Changes in level up to ¼” may be vertical; between ¼” and ½” must be beveled with a slope no greater than 1:2; greater than ½” will require a “ramp”.

Station limits may be adjusted as directed to meet varying field conditions

Item 6185 Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMA’s for mobile operations.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0028-15-059

DISTRICT Beaumont

COUNTY Orange

HIGHWAY BU 90Y

CONTROL SECTION JOB				0028-15-059		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00134264			
COUNTY				Orange			
HIGHWAY				BU 90Y			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	316-6404	AGGR (TY-PB GR-4 OR TY-PL GR-4 SAC-A)	CY	243.000		243.000	
	316-6405	ASPH (AC-20-5TR OR AC-20XP)	GAL	10,365.000		10,365.000	
	354-6024	PLANE ASPH CONC PAV(2" TO 4")	SY	34,549.000		34,549.000	
	354-6035	PLANE CONC PAV(0" TO 1")	SY	5,635.000		5,635.000	
	361-6034	FULL - DEPTH REPAIR CPCD (9")	SY	214.000		214.000	
	438-6001	CLEANING AND SEALING EXISTING JOINTS	LF	35,642.000		35,642.000	
	479-6003	ADJUSTING MANHOLES & INLETS	EA	22.000		22.000	
	500-6001	MOBILIZATION	LS	0.150		0.150	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		5.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	80.000		80.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	80.000		80.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	390.000		390.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	390.000		390.000	
	506-6047	TEMP SDMT CONT FENCE (INLET PROTECTION)	LF	80.000		80.000	
	644-6009	IN SM RD SN SUP&AM TY10BWG(1)SB(P)	EA	33.000		33.000	
	644-6015	IN SM RD SN SUP&AM TY10BWG(1)SB(U)	EA	1.000		1.000	
	644-6045	IN SM RD SN SUP&AM TYS80(1)SB(U-1EXT)	EA	1.000		1.000	
	644-6046	IN SM RD SN SUP&AM TYS80(1)SB(U-2EXT)	EA	1.000		1.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	37.000		37.000	
	662-6005	WK ZN PAV MRK NON-REMOV (W)6"(BRK)	LF	17,070.000		17,070.000	
	662-6008	WK ZN PAV MRK NON-REMOV (W)6"(SLD)	LF	11,062.000		11,062.000	
	662-6010	WK ZN PAV MRK NON-REMOV (W)8"(DOT)	LF	1,671.000		1,671.000	
	662-6012	WK ZN PAV MRK NON-REMOV (W)8"(SLD)	LF	1,442.000		1,442.000	
	662-6016	WK ZN PAV MRK NON-REMOV (W)24"(SLD)	LF	4,141.000		4,141.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	826.000		826.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,241.000		1,241.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	1,442.000		1,442.000	
	666-6176	REFL PAV MRK TY II (W) 8" (DOT)	LF	1,671.000		1,671.000	
	666-6308	RE PM W/RET REQ TY I (W)6"(SLD)(090MIL)	LF	134.000		134.000	
	666-6317	RE PM W/RET REQ TY I (Y)6"(BRK)(090MIL)	LF	3,010.000		3,010.000	
	666-6320	RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL)	LF	11,214.000		11,214.000	
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	4,141.000		4,141.000	
	668-6077	PREFAB PAV MRK TY C (W) (ARROW)	EA	7.000		7.000	
	668-6079	PREFAB PAV MRK TY C (W) (TPL ARROW)	EA	2.000		2.000	
	668-6085	PREFAB PAV MRK TY C (W) (WORD)	EA	9.000		9.000	
	668-6088	PREFAB PAV MRK TY C (W) (ISLAND)	EA	1.000		1.000	
	668-6089	PREFAB PAV MRK TY C (W) (RR XING)	EA	4.000		4.000	

DISTRICT	COUNTY	CCSJ	SHEET
Beaumont	Orange	0028-15-059	11



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0028-15-059

DISTRICT Beaumont

COUNTY Orange

HIGHWAY BU 90Y

CONTROL SECTION JOB				0028-15-059		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00134264			
COUNTY				Orange			
HIGHWAY				BU 90Y			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	668-6092	PREFAB PAV MRK TY C (W) (36")(YLD TRI)	EA	10.000		10.000	
	672-6007	REFL PAV MRKR TY I-C	EA	166.000		166.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	350.000		350.000	
	720-6001	SPALLING REPAIR (HYDRAULIC CEMENT)	CF	150.000		150.000	
	3076-6036	D-GR HMA TY-D SAC-A PG64-22	TON	361.000		361.000	
	3077-6014	SP MIXESSP-CPG64-22 (LEVEL-UP)	TON	1,337.000		1,337.000	
	3077-6034	SP MIXESSP-CSAC-B PG76-22	TON	3,973.000		3,973.000	
	3077-6075	TACK COAT	GAL	2,073.000		2,073.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	6056-6001	PREFORMED IN-LANE(TRANS) RUMBLE STRIP	LF	160.000		160.000	
	6185-6002	TMA (STATIONARY)	DAY	68.000		68.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	3.000		3.000	
	02	RAILROAD FORCE ACCOUNT WORK (NON PARTICIPATING)	LS	1.000		1.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	

DATE: 11/18/2022 5:12:23 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YV_Quantity_Summary.dgn

ROADWAY ITEMS

STA	TO	STA	LENGTH (FT)	WIDTH (FT)	316	316	354	354	361	438	479	720	3077	3077	3077
					6404 AGGR (TY-PB GR-4 OR TY-PL GR-4 SAC-A)	6405 ASPH (AC-20-5TR OR AC-20XP)	6024 PLANE ASPH CONC PAV(2" TO 4")	6035 PLANE CONC PAV(0" TO 1")	6034 FULL - DEPTH REPAIR CPCD (9")	6001 CLEANING AND SEALING EXISTING JOINTS	6003 ADJUSTING MANHOLES & INLETS	6001 SPALLING REPAIR (HYDRAULIC CEMENT)	6014 SP MIXES SP-C PG64-22 (LEVEL-UP)	6034 SP MIXES SP-C SAC-B PG76-22	6075 TACK COAT
					SY	SY	SY	SY	SY	LF	EA	CF	SY	SY	SY
10+00	TO	10+28	28	76	0	0	0	0	0	0	0	0	0	0	0
10+28	TO	13+86	358	76	3,024	3,024	3,024	318	0	2,287	2	0	1,313	3,024	3,024
13+86	TO	15+57	171	66	1,254	1,254	1,254	152	0	2,287	2	0	627	1,254	1,254
15+57	TO	25+05	948	47	4,951	4,951	4,951	843	0	2,287	2	0	3,476	4,951	4,951
25+05	TO	26+24	119	0	0	0	0	106	0	2,287	2	0	437	0	0
26+24	TO	28+97	273	47	1,426	1,426	1,426	243	0	2,287	2	0	1,001	1,426	1,426
28+97	TO	29+88	91	53	536	536	536	81	0	2,287	2	0	334	536	536
29+88	TO	33+09	321	59	2,105	2,105	2,105	285	0	2,287	2	0	1,177	2,105	2,105
33+09	TO	34+40	131	53	772	772	772	116	0	2,287	2	0	481	772	772
34+40	TO	63+90	2950	47	15,406	15,406	15,406	2,622	0	2,287	2	0	10,817	15,406	15,406
63+90	TO	72+41	851	47	4,445	4,445	4,445	756	0	2,287	2	0	3,121	4,445	4,445
72+41	TO	73+67	126	45	630	630	630	112	0	2,287	2	0	462	630	630
***			---	---	---	---	---	---	214	---	---	150	---	---	---
PROJECT TOTALS:					34,549	34,549	34,549	5,635	214	35,642	22	150	23,246	34,549	34,549

MISCELLANEOUS ITEMS

STA	TO	STA	6001	6056	6185	
			6002	6001	6002	6005
			PORTABLE CHANGEABLE MESSAGE SIGN	PREFORMED IN-LANE (TRANS) RUMBLE STRIP	TMA (STATIONARY)	TMA (MOBILE OPERATION)
			EA	LF	DAY	DAY
10+00	TO	13+86	---	---	---	---
13+86	TO	15+57	---	---	---	---
15+57	TO	25+20	---	---	---	---
25+20	TO	26+09	---	---	---	---
26+09	TO	28+97	---	---	---	---
28+97	TO	29+88	---	---	---	---
29+88	TO	33+09	---	---	---	---
33+09	TO	34+40	---	---	---	---
34+40	TO	63+90	---	160	---	---
63+90	TO	72+41	---	---	---	---
72+41	TO	73+67	---	---	---	---
TRAFFIC CONTROL			2	---	68	3
PROJECT TOTALS:			2	160	68	3

SIGNS MARKINGS ITEMS

LOCATION	STA	TO	STA	644				
				6009	6015	6045	6046	6076
				IN SM RD SN SUP&AM TY10BWG (1) SB (P)	IN SM RD SN SUP&AM TY10BWG (1) SB (U)	IN SM RD SN SUP&AM TYS80(1)SB(U- 1EXT)	IN SM RD SN SUP&AM TYS80(1)SB(U- 2EXT)	REMOVE SM RD SN SUP&AM
				EA	EA	EA	EA	EA
10+00	TO	72+41		33	1	1	1	36
PROJECT TOTALS:				33	1	1	1	36

SUMMARY FOR CLEAN & SEAL EXIST JOINTS ITEM # 438-6001


WIDTH	STA TO STA.	LENGTH	LONGITUDINAL		TOTALS
			LF	LF	
65	10+28 - 13+86	358	1074	1213	2287
56	13+86 - 15+57	171	342	836	1178
47	15+57 - 25+20	963	1926	4707	6633
0	25+20 - 26+09	89	---	---	---
47	26+09 - 28+97	288	576	1412	1988
53	28+97 - 29+88	91	364	369	733
59	29+88 - 33+09	321	1284	1299	2583
53	33+09 - 34+40	131	524	530	1054
47	34+40 - 63+90	2950	5900	10339	16239
47	63+90 - 72+40	850	850	2097	2947
45	72+40 - 73+67	127	254	286	540
				TOTAL LF	35642

*FOR CONTRACTOR'S INFORMATION ONLY

BASIS OF ESTIMATE

ITEM	CODE	DESCRIPTION	QUANTITY	RATE	DEPTH	
316	6404	AGGR (TY-PB GR-4 OR TY-PL GR-4 SAC-A)	34,074 SY	140 SY/CY		243 CY
316	6405	ASPH (AC-20-5TR OR AC-20XP)	34,549 SY	0.3 GAL/SY		10365 GAL
3076	6036	D-GR HMA TY-D SAC-A PG64-22	6,571 SY	110 LB/SY-IN	1	361 TON
3077	6014	SP MIXES SP-C PG64-22 (LEVEL-UP)	23,246 SY	115 LB/SY-IN	1	1,337 TON
3077	6034	SP MIXES SP-C SAC-B PG76-22	34,549 SY	115 LB/SY-IN	2	3,973 TON
3077	6075	TACK COAT	34,549 SY	0.06 GAL/SY		2,073 GAL

BU 90Y
QUANTITY SUMMARY
 SHEET 1 OF 4



CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		13

DATE: 11/18/2022 10:53:24 PM
 FILE: c:\ttdot\p_w_online\ttdot5\c:\indya\omonte\d0646045\Quantity_Summary.dgn

DRIVEWAY



DRIVEWAY	STATION	SIDE OF ROAD	R1	R2	W1 (TOP; ALONG ROW)	W2 (BOTTOM; FROM THE ENDS OF R1 TO R2)	L (FROM EDGE OF PAVEMENT TO ROW)	SKEW ANGLE	SPANDREL	AREA (SY)	3076	666
											6036	6047
											D-GR HMA TY-D SAC-A PG64-22	REFL PAV MRK TY I (W) 24" (SLD) (090MIL)
											SY	LF
15TH ST	13+57	RT	11.0	13.0	32.0	61.0	61.0	0.0	2014.2	224	224	78
14TH ST	17+17	RT	14.0	15.0	31.0	60.0	60.0	0.0	1950.3	217	217	72
13TH ST	20+80	RT	9.0	8.0	34.0	50.0	50.0	0.0	1731.1	192	192	60
12TH ST	24+39	LT	7.0	9.0	38.0	54.0	54.0	0.0	2079.9	231	231	66
11TH ST	26+88	LT	3.0	11.0	35.0	55.0	55.0	60.0	1952.9	217	217	66
11TH ST	28+00	RT	10.0	11.0	36.0	52.0	52.0	0.0	1919.4	213	213	66
9TH ST	35+18	LT	2.0	3.0	45.0	40.0	40.0	0.0	1802.8	200	200	48
9TH ST	35+18	RT	7.0	10.0	38.0	55.0	55.0	0.0	2122.0	236	236	66
8TH ST	38+80	LT	8.0	11.0	39.0	59.0	59.0	0.0	2340.7	260	260	72
8TH ST	38+80	RT	11.0	10.0	38.0	59.0	59.0	0.0	2289.4	254	254	72
6TH ST	46+04	LT	12.0	8.0	36.0	56.0	56.0	0.0	2060.6	229	229	72
6TH ST	46+04	RT	11.0	11.0	40.0	62.0	62.0	0.0	2531.9	281	281	78
5TH ST	49+63	LT	8.0	6.0	39.0	54.0	54.0	0.0	2127.5	236	236	66
5TH ST	49+63	RT	10.0	8.0	39.0	58.0	58.0	0.0	2297.2	255	255	72
N 4TH ST	53+23	LT	6.0	5.0	38.0	50.0	50.0	0.0	1913.1	213	213	60
N 4TH ST	53+23	RT	9.0	11.0	37.0	57.0	57.0	0.0	2152.3	239	239	72
N 3RD ST	56+85	LT	8.0	8.0	36.0	52.0	52.0	0.0	1899.5	211	211	66
2ND ST	60+46	LT	6.0	6.0	38.0	51.0	51.0	0.0	1953.5	217	217	66
1ST ST	64+02	LT	11.0	10.0	29.0	51.0	51.0	0.0	1526.4	170	170	66
1ST ST	64+02	RT	12.0	11.0	31.0	55.0	55.0	0.0	1761.9	196	196	66
N MILL ST	67+43	LT	9.0	8.0	29.0	46.0	46.0	0.0	1365.1	152	152	60
N MILL ST	67+43	RT	11.0	16.0	29.0	57.0	57.0	0.0	1733.9	193	193	72
SIMMONS DR	72+84	LT	52.0	15.0	65.0	134.0	134.0	0.0	9338.6	1038	1038	162
SIMMONS DR	72+84	RT	60.0	36.0	39.0	134.0	134.0	0.0	6276.7	697	697	162
PROJECT TOTALS:											6,571	1,806

SW3P ITEMS

CONTROL NUMBER	506														
	6038	6039	6041	6043	6047										
	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)	BIODEG EROSN CONT LOGS (INSTL) (12")	BIODEG EROSN CONT LOGS (REMOVE)	TEMP SDMT CONT FENCE (INLET PROTECTION)										
											LF	LF	LF	LF	LF
1	-	-	20	20	-										
2	-	-	20	20	-										
3	-	-	20	20	-										
4	-	-	20	20	-										
5	-	-	40	40	-										
6	10	10	-	-	10										
7	20	20	-	-	20										
8	-	-	10	10	-										
9	-	-	20	20	-										
10	-	-	10	10	-										
11	-	-	20	20	-										
12	-	-	20	20	-										
13	-	-	20	20	-										
14	-	-	20	20	-										
15	20	20	-	-	20										
16	-	-	20	20	-										
17	-	-	10	10	-										
18	10	10	-	-	10										
19	-	-	20	20	-										
20	-	-	20	20	-										
21	-	-	20	20	-										
22	-	-	20	20	-										
23	-	-	20	20	-										
24	20	20	-	-	20										
25	-	-	20	20	-										
PROJECT TOTAL:	80	80	390	390	80										

FULL-DEPTH REPAIR LOCATIONS

LOCATION	STATION	EAST/ WEST	LENGTH	WIDTH	SURFACE AREA
1	19+00	EASTBOUND	15	12	20
2	19+24	EASTBOUND	15	12	20
3	21+00	EASTBOUND	15	12	20
4	23+00	EASTBOUND	25	12	34
5	28+37	EASTBOUND	15	12	20
6	37+64	EASTBOUND	15	12	20
7	49+15	EASTBOUND	15	12	20
8	63+55	EASTBOUND	15	12	20
9	60+88	WESTBOUND	15	12	20
10	53+00	WESTBOUND	15	12	20
TOTAL:					214



BU 90Y
 QUANTITY SUMMARY
 SHEET 2 OF 4

Texas Department of Transportation


CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		14

DATE: 11/18/2022 5:12:28 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YV_Quantity_Summary.dgn

SUMMARY OF PAVEMENT MARKINGS

STA	STA	662							666					668						672		
		6005 WK ZN PAV MRK NON-R EMOV (W)6"(B RK)	6008 WK ZN PAV MRK NON-RE MOV (W)6"(SL D)	6010 WK ZN PAV MRK NON-RE MOV (W) 8" (DOT)	6012 WK ZN PAV MRK NON-RE MOV (W) 8" (SLD)	6016 WK ZN PAV MRK NON-RE MOV (W)24" (SLD)	6109 WK ZN PAV MRK SHT TERM (TAB) TY W	6111 WK ZN PAV MRK SHT TERM (TAB)TY Y-2	6035 REFL PAV MRK TY I (W)8" (SLD) (090MIL)	6176 REFL PAV MRK TY II (W) 8" (DOT)	6308 RE PM W/RET REQ TY I (W)6" (SLD) (090MIL)	6317 RE PM W/RET REQ TY I (Y)6"(B RK)(090MD IL)	6320 RE PM W/RET REQ TY I (Y)6"(SL (090MIL)	6076 PREFAB PAV MRK TY C (W) (24") (SLD)	6077 PREFAB PAV MRK TY C (W) (ARROW)	6079 PREFAB PAV MRK TY C (W) (TPL ARROW)	6085 PREFAB PAV MRK TY C (W) (WORD)	6088 PREFAB PAV MRK TY C (W) (ISLAND)	6089 PREFAB PAV MRK TY C (W) (RR XING)	6092 PREFAB PAV MRK TY C (W) (36") (YLD TRI)	6007 REFL PAV MRKR TY I-C	6009 REFL PAV MRKR TY II-A-A
		LF	LF	LF	LF	LF	EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA
10+00	10+90	60	180	24	180	170	14	28	180	24	0	60	180	170	1	0	0	0	0	0	3	6
10+90	11+00	20	20	3	0	0	2	2	0	3	0	20	20	0	0	0	0	0	0	0	2	4
11+00	13+19	720	438	57	0	0	34	55	0	57	134	120	438	0	0	0	0	0	0	0	4	8
13+19	13+39	20	40	6	0	0	4	4	0	6	0	20	40	0	0	0	0	0	0	0	2	4
13+39	13+84	0	0	12	0	60	0	0	0	12	0	0	0	60	0	0	0	0	0	0	2	4
13+84	16+94	1,280	620	78	0	0	48	62	0	78	0	160	620	0	0	0	0	0	0	0	5	10
16+94	17+42	20	0	12	0	0	4	0	0	12	0	20	0	0	0	0	0	0	0	0	2	4
17+42	20+50	1,280	616	78	0	0	48	62	0	78	0	160	616	0	0	0	0	0	0	0	5	10
20+50	21+07	0	0	15	0	0	0	0	0	15	0	0	0	0	0	0	0	0	0	0	2	4
21+07	21+63	80	112	15	0	0	10	12	0	15	0	40	112	0	0	0	0	0	0	0	2	4
21+63	22+23	40	120	15	60	48	10	15	60	15	0	40	120	48	0	0	0	0	2	0	2	4
22+23	24+15	250	384	48	192	0	30	50	192	48	0	100	384	0	0	0	0	0	0	0	4	8
24+15	24+65	0	0	15	50	0	0	3	50	15	0	0	0	0	0	0	0	0	0	0	2	4
24+65	25+23	40	116	15	58	24	10	15	58	15	0	40	116	24	0	0	0	0	0	0	2	4
25+23	26+05	30	0	21	0	0	7	0	0	21	0	30	0	0	0	0	0	0	0	0	3	6
26+05	26+72	40	134	18	67	24	12	18	67	18	0	40	134	24	0	0	0	0	0	0	2	4
26+72	27+17	20	0	12	0	60	4	0	0	12	0	20	0	60	0	0	0	0	0	0	2	4
27+17	29+00	250	366	48	183	60	28	48	183	48	0	100	366	60	0	0	0	0	0	0	4	8
29+00	29+70	40	280	18	70	48	12	32	70	18	0	40	280	48	0	0	0	0	2	0	2	8
29+70	30+15	60	180	12	0	0	8	20	0	12	0	40	180	0	0	0	0	0	0	0	2	8
30+15	30+64	20	98	15	0	0	4	10	0	15	0	20	98	0	0	0	0	0	0	0	2	4
30+64	31+19	60	110	15	55	36	10	15	55	15	0	40	110	36	1	0	0	0	0	0	2	4
31+19	32+01	0	0	21	0	144	0	0	0	21	0	0	0	144	0	0	0	0	0	0	3	6
32+01	32+12	10	0	3	11	280	1	1	11	3	0	10	0	280	0	0	0	0	0	0	2	4
32+12	32+52	20	80	12	40	0	6	10	40	12	0	20	80	0	1	0	0	0	0	0	2	4
32+52	32+80	0	112	9	0	0	0	12	0	9	0	0	112	0	0	0	0	0	0	0	2	8
32+80	34+38	320	632	42	0	0	24	64	0	42	0	80	632	0	0	0	0	0	0	0	3	12
34+38	35+00	80	124	18	0	0	10	14	0	18	0	40	124	0	0	0	0	0	0	0	2	4
35+00	35+49	0	0	15	0	0	0	0	0	15	0	0	0	0	0	0	0	0	0	0	2	4
35+49	38+50	1,280	602	78	0	0	46	62	0	78	0	160	602	0	0	0	0	0	0	0	5	10
38+50	39+08	0	0	15	0	60	0	0	0	15	0	0	0	60	0	0	0	0	0	0	2	4
39+08	40+00	180	184	24	0	24	14	20	0	24	0	60	184	24	0	0	0	0	0	0	3	6
SUBTOTAL #1:		6,220	5,548	789	966	1,038	400	634	966	789	134	1,480	5,548	1,038	3	0	0	0	4	0	84	186

BU 90Y
 QUANTITY SUMMARY
 SHEET 3 OF 4




CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		15

DATE: 11/18/2022 5:12:30 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Quantity_Summary.dgn

SUMMARY OF PAVEMENT MARKINGS

STA	STA	662							666					668							672	
		6005 WK ZN PAV MRK NON-R EMOV (W)6"(B RK)	6008 WK ZN PAV MRK NON-RE MOV (W)6"(SL D)	6010 WK ZN PAV MRK NON-RE MOV (W) 8" (DOT)	6012 WK ZN PAV MRK NON-RE MOV (W) 8" (SLD)	6016 WK ZN PAV MRK NON-RE MOV (W)24" (SLD)	6109 WK ZN PAV MRK SHT TERM (TAB)TY W	6111 WK ZN PAV MRK SHT TERM (TAB)TY Y-2	6035 REFL PAV MRK TY I (W)8" (SLD) (090MIL)	6176 REFL PAV MRK TY II (W) 8" (DOT)	6308 RE PM W/RET REQ TY I (W)6" (SLD) (090MIL)	6317 RE PM W/RET REQ TY I (Y)6"(B RK)(090MD IL)	6320 RE PM W/RET REQ TY I (Y)6"(SL L)	6076 PREFAB PAV MRK TY C (W) (24") (SLD)	6077 PREFAB PAV MRK TY C (W) (ARROW)	6079 PREFAB PAV MRK TY C (W) (TPL ARROW)	6085 PREFAB PAV MRK TY C (W) (WORD)	6088 PREFAB PAV MRK TY C (W) (ISLAND)	6089 PREFAB PAV MRK TY C (W) (RR XING)	6092 PREFAB PAV MRK TY C (W) (36")(Y LD TRI)	6007 REFL PAV MRKR TY I-C	6009 REFL PAV MRKR TY II-A-A
		LF	LF	LF	LF	EA	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA
40+00	41+31	40	0	33	0	280	10	0	0	33	0	40	0	280	0	0	0	0	0	0	3	6
41+31	41+34	0	0	3	0	24	0	0	0	3	0	0	0	24	0	0	0	0	0	0	2	4
41+34	45+68	2,420	868	111	0	0	66	88	0	111	0	220	868	0	0	0	0	0	0	0	7	14
45+68	46+37	0	0	18	0	120	0	0	0	18	0	0	0	120	0	0	0	0	0	0	2	4
46+37	49+32	1,280	590	75	0	0	46	60	0	75	0	160	590	0	0	0	0	0	0	0	5	10
49+32	49+93	0	0	18	0	120	0	0	0	18	0	0	0	120	0	0	0	0	0	0	2	4
49+93	49+97	20	8	3	0	0	2	2	0	3	0	20	8	0	0	0	2	0	0	0	2	4
49+97	50+37	20	80	12	0	0	6	8	0	12	0	20	80	0	0	0	2	0	0	0	2	4
50+37	52+86	840	498	63	0	24	38	50	0	63	0	140	498	24	0	0	0	0	0	0	5	10
52+86	53+58	0	0	18	0	360	0	0	0	18	0	0	0	360	0	0	0	0	0	0	2	4
53+58	55+59	960	402	51	0	0	32	42	0	51	0	120	402	0	0	0	0	0	0	0	4	8
55+59	56+13	20	0	15	0	12	5	0	0	15	0	20	0	12	0	0	0	0	0	0	2	4
56+13	57+39	320	252	33	0	0	20	26	0	33	0	80	252	0	0	0	2	0	0	0	3	6
57+39	57+79	20	80	12	0	0	6	8	0	12	0	20	80	0	0	0	2	0	0	0	2	4
57+79	60+21	420	484	63	0	0	38	50	0	63	0	140	484	0	0	0	0	0	0	0	5	10
60+21	60+68	0	0	12	0	12	0	0	0	12	0	0	0	12	0	0	0	0	0	0	2	4
60+68	63+86	1,280	636	81	0	0	48	64	0	81	0	160	636	0	0	0	0	0	0	0	5	10
63+86	64+30	0	0	12	0	24	0	0	0	12	0	0	0	24	0	0	0	0	0	0	2	4
64+30	67+24	1,280	588	75	0	0	46	60	0	75	0	160	588	0	0	0	0	0	0	0	5	10
67+24	67+65	0	0	12	0	48	0	0	0	12	0	0	0	48	0	0	0	0	0	0	2	4
67+65	71+35	1,900	740	93	370	0	56	93	370	93	0	200	740	0	0	0	1	0	0	0	6	12
71+35	71+74	10	78	12	39	0	3	10	39	12	0	10	78	0	0	0	0	0	0	0	2	4
71+74	71+74	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	1	2
71+74	72+27	20	106	15	53	0	4	15	53	15	0	20	106	0	1	1	0	0	0	0	2	4
72+27	72+41	0	28	6	14	33	0	5	14	6	0	0	28	33	0	0	0	0	0	0	2	4
72+41	73+29	0	0	24	0	0	0	0	0	24	0	0	0	0	0	0	0	0	0	0	3	6
73+29	73+67	0	76	12	0	240	0	26	0	12	0	0	228	240	2	0	0	1	0	10	2	4
CROSSWALK PAVEMENT						1,806								1,806								
SUBTOTAL #2:		10,850	5,514	882	476	3,103	426	607	476	882	0	1,530	5,666	3,103	4	2	9	1	0	10	82	164
SUBTOTAL #1:		6,220	5,548	789	966	1,038	400	634	966	789	134	1,480	5,548	1,038	3	0	0	0	4	0	84	186
TOTAL:		17,070	11,062	1,671	1,442	4,141	826	1,241	1,442	1,671	134	3,010	11,214	4,141	7	2	9	1	4	10	166	350

BU 90Y
 QUANTITY SUMMARY
 SHEET 4 OF 4



CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		16


DATE: 11/20/2022 2:49:04 PM
FILE: c:\txdot\pw_online\txdot5\samantha_harris\d0646049\E_Sequence_of_Work.dgn

CONSTRUCTION SEQUENCE:

1. INSTALL CONSTRUCTION SIGNS & BARRICADES AND SW3P ITEMS AS REQUIRED. MAINTAIN THESE ITEMS THROUGHOUT THE CONSTRUCTION OF THIS PROJECT.
2. PERFORM MILLING, FULL DEPTH CONCRETE REPAIRS, CLEANING & SEALING JOINTS, AND SEAL COAT, IN AN EFFICIENT LOGICAL SEQUENCE TO MINIMIZE IMPACT TO THE TRAVELING PUBLIC.
 - i. NIGHTTIME WORK WILL BE REQUIRED. PLAN WORK SO ALL LANES OF TRAFFIC ARE OPENED DAILY. PERFORM MILLING FULL WIDTH ONLY AS FAR AS CAN BE COMPLETED IN ONE NIGHT OR BETWEEN INTERSECTIONS.
 - ii. PLACE WORK ZONE STRIPING NIGHTLY DURING MILLING OPERATIONS PRIOR TO OPENING TO TRAFFIC. PLACE SHORT TERM PAVEMENT MARKINGS (WZ(STPM)) NIGHTLY DURING PAVEMENT OPERATIONS PRIOR TO OPENING TO TRAFFIC. ENSURE THAT THE EXISTING OR WORK ZONE PAVEMENT MARKINGS ARE PRESENT EACH NIGHT.
 - iii. PROVIDE TEMPORARY TRANSITIONS AT THE END OF EACH WORK DAY PRIOR TO OPENING TO TRAFFIC.
 - iv. PLAN WORK SO THAT PONDING DOES NOT OCCUR.
3. INSTALL SUPERPAVE.
4. PLACE PERMANENT PAVEMENT MARKINGS & MARKERS.
5. CLEAN UP PROJECT SITE. REMOVE ALL SIGNS, BARRICADES, TRAFFIC CONTROL & SW3P ITEMS.

NOTES:

- 1 REFER TO GENERAL NOTES AND PLAN SHEETS FOR ADDITIONAL REQUIREMENTS.
- 2 CHANGES TO PROPOSED SEQUENCE OF WORK MAY BE ALLOWED IF APPROVED BY THE ENGINEER.



BU 90Y
SEQUENCE OF WORK



CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		17

DATE: 11/18/2022 5:12:35 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BUS90Y-BC-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other formats or for incorrect results or damages resulting from its use.

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:



- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		 Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) - 21			
FILE:	bc-21.dgn	DN:	TxDOT
		CR:	TxDOT
		DW:	TxDOT
		CK:	TxDOT
© TxDOT	November 2002	CONT	SECT
		0028	15
		JOB	BU 90Y
		DIST	COUNTY
4-03	7-13		
9-07	8-14		
5-10	5-21	BMT	ORANGE
			SHEET NO.
			18


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BC(2)-21.dgn
 DATE: 11/18/2022 5:12:37 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BC(2)-21.dgn

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "ROAD WORK NEXT X MILES" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation
Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	19	

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 5:12:52 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\Barricade and Construction Work Zone Speed Limit.dgn


SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT	SECT
REVISIONS		JOB	HIGHWAY
9-07	8-14	0028 15	059 BU 90Y
7-13	5-21	DIST	COUNTY SHEET NO.
		BMT	ORANGE 20

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 5:12:54 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12


Texas Department of Transportation Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21



FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	15	059	BU 90Y				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	ORANGE	21					

DATE: 11/18/2022 5:12:56 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS





GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0028	15	059	BU	90Y				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	ORANGE	22					

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	23	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 5:13:01 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	15	059	BU 90Y				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	ORANGE	24					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 5:13:03 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0028	15	059	BU 90Y				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	BMT	ORANGE	25					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 5:13:05 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

**Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	26	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	27	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	ORANGE	28	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 5:13:09 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS


BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	BMT	ORANGE	29	
11-02 8-14				

DATE: 11/18/2022 5:13:11 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90YF_BC-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 5:13:13 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\Buis\092422\TCPCP (2-4) (1) (1).dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to digital format or for incorrect results or damages resulting from its use.



TCP (2-4a)
ONE LANE CLOSED



TCP (2-4b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'



* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
 - For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-4a)**
- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.
- TCP (2-4b)**
- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS			
TCP (2-4) - 18			
FILE: tcp2-4-18.dgn	DN:	CK:	DW:
© TxDOT December 1985	CONT	SECT	HIGHWAY
REVISIONS	0028	15	059 BU 90Y
8-95 3-03	DIST	COUNTY	SHEET NO.
1-97 2-12	BMT	ORANGE	30
4-98 2-18			




DATE: 11/18/2022 5:13:15 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\Bureaucracy\TCP (3-1) - 13.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for incorrect results or damages resulting from its use.



LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

- GENERAL NOTES**
- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
 - The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
 - The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
 - Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
 - Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
 - Each vehicle shall have two-way radio communication capability.
 - When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
 - Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
 - "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
 - On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



Texas Department of Transportation


Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS UNDIVIDED HIGHWAYS


TCP (3-1) - 13

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	ORANGE	31	
1-97				


DATE: 11/18/2022 5:13:20 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\Bldg\CP\CP3-3.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any kind of information into digital format or for incorrect results or damages resulting from its use.




TCP (3-3a)
TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3b)
TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3c)
DIVIDED MULTILANE HIGHWAY




TCP (3-3d)
UNDIVIDED MULTILANE HIGHWAY




TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display
 Flashing Arrow Board



TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board
 in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND		
* Trail Vehicle		ARROW BOARD DISPLAY
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
Heavy Work Vehicle		LEFT Directional
Truck Mounted Attenuator (TMA)		Double Arrow
Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.


Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/
REMOVAL
TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	ORANGE	32	
1-97 7-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard into a digital format or for incorrect results or damages resulting from its use.

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13


FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	0028	SECT:	15	JOB:	059	HIGHWAY:	BU 90Y
REVISIONS:		DIST:		COUNTY:		SHEET NO.:			
1-97		BMT:		ORANGE					33
3-03									
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 11/18/2022 5:13:22 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\Buisness\WZ (RS) (11/18/2022).dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation Traffic Safety Division Standard


TEMPORARY RUMBLE STRIPS

WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	BMT	ORANGE	34	



DATE: 11/18/2022 5:13:27 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Roadway_Layout.dgn

DWG: C&G DWG: C&G



LEGEND

	INLET		MANHOLE		PIPE		MILL & OVERLAY		UTILITY		STREET LIGHT
--	-------	--	---------	--	------	--	----------------	--	---------	--	--------------



SJH P.E.
 11/20/2022

MATCHLINE
 STA. 22+00

**BU 90Y
 ROADWAY LAYOUT**
 N. T. S

SHEET 1 OF 5






CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	35	

DATE: 11/18/2022 5:13:30 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Roadway_Layout.dgn

DWG: C&G
 DWG: C&G

LEGEND

	INLET		MANHOLE		PIPE		MILL & OVERLAY
	UTILITY		STREET LIGHT				



SAMANTHA JO HARRIS P.E.
 11/20/2022

MATCHLINE
 STA. 28+50

**BU 90Y
 ROADWAY LAYOUT
 N. T. S**

SHEET 2 OF 5












CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		36

DATE: 11/18/2022 5:13:32 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Roadway_Layout.dgn

DN:
 CK:
 DW:
 CK:

LEGEND

	INLET		MANHOLE		PIPE		MILL & OVERLAY		UTILITY		STREET LIGHT
--	-------	--	---------	--	------	---	----------------	--	---------	--	--------------



SJ Harris P.E.
 11/20/2022

**BU 90Y
 ROADWAY LAYOUT**
 N. T. S

SHEET 3 OF 5












CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	37	

DATE: 11/18/2022 5:13:35 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Roadway_Layout.dgn

DN:
 CK:
 DW:
 CK:

LEGEND

	INLET		MANHOLE		PIPE		MILL & OVERLAY		UTILITY		STREET LIGHT
--	-------	--	---------	--	------	---	----------------	--	---------	--	--------------



[Signature] P.E.
 11/20/2022

MATCHLINE
 STA. 61+00

**BU 90Y
 ROADWAY LAYOUT**
 N. T. S







SHEET 4 OF 5






CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	38	

DATE: 11/18/2022 5:13:37 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Roadway_Layout.dgn

LEGEND


	INLET		MANHOLE		PIPE		MILL & OVERLAY		UTILITY		STREET LIGHT
--	-------	--	---------	--	------	---	----------------	--	---------	--	--------------



SJ Harris P.E.
 11/20/2022


**BU 90Y
 ROADWAY LAYOUT**
 N. T. S

SHEET 5 OF 5





CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		39


DATE: 11/18/2022 5:13:40 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\0_Intersection_Detail.dgn



LEGEND

 MILL & OVERLAY

 SHOWS DOWNWARD SLOPE



[Signature] P.E.

11/20/2022

**BU 90Y
 INTERSECTION DETAIL**
 N. T. S





CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	40	

STA. 73+67
 END PROJECT
 CSJ 0028-15-059


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 5:14:22 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BUI\09041519.dgn




* Adjust if placement interferes with driveway or intersection.

STANDARD PATTERN



ALTERNATIVE PATTERN



GENERAL NOTES

1. Transverse or in-lane rumble strips should only be used at high incident and special geometric locations. These special geometric locations may include: approaches to rural, high speed signalized or Stop-controlled intersections with sight restrictions and/or high crash rates, approaches to unexpected urban intersections, approaches to newly installed Stop or signalized controlled intersections, approaches to toll plazas, approaches to hazardous horizontal curves, and approaches to railroad grade crossings.
2. When used, the rumble strips shall be placed 200 feet prior to and after the placement of the warning device.
3. The use of rumble strips should not be widespread or used indiscriminately.
4. Preformed black raised rumble strips should be used. They should be installed in accordance with the manufacturer's recommendations.
5. A list of approved, preformed raised rumble strips can be obtained from the Traffic Operations Division.
6. Consideration should be given to noise levels when in-lane or transverse rumble strips are installed near residential areas, schools, churches, etc.
7. The use of the "Rumble Strips Ahead" sign may be used in advance of in-lane or transverse rumble strips, based on engineering judgement. This sign is typically not necessary for rumble strip installations built to the guidelines on this standard sheet. When used, this sign should be spaced in advance of the rumble strips based on the guidelines for advance placement of warning sign included in the "Texas Manual on Uniform Traffic Control Devices".



8. Consideration should be given to bicyclists. A 12 inch gap from the edge line may be used to accommodate bicyclists when a usable shoulder is not available. Additional gaps in the in-lane or transverse rumble strips are not recommended since they could cause motorists to swerve to avoid the rumble strips.
9. Other signs can be used as conditions warrant.

		Traffic Operations Division Standard	
<h2>TRANSVERSE OR IN-LANE RUMBLE STRIPS</h2> <h3>RS(5) - 13</h3>			
FILE: rs(5) - 13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT April 2006	CONT	SECT	HIGHWAY
REVISIONS	0028	15	059 BU 90Y
2-10	DIST	COUNTY	SHEET NO.
10-13	BMT	ORANGE	41

DATE: 11/18/2022 5:14:25 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Pavement_Markings\Layout.dgn

- REMOVE AND REPLACE
 STA. 10+56
- | | | | |
|----------|--------------|----|--------------|
| BUSINESS | M4-3 | TO | M4-5B |
| SOUTH | 24 X 12 | | 24 X 12 |
| TEXAS | M1-4 (2 DGT) | | M1-1 (2 DGT) |
| | 24 X 24 | | 24 X 24 |
| | M6-3 | | M6-1B |
| | 21 X 15 | | 21 X 15 |
| | M3-3 | | M3-1 |
| | 24 X 12 | | 24 X 12 |
| | M1-6T | | M1-6T |
| | 24 X 24 | | 24 X 24 |
| | M6-3 | | M6-1 |
| | 21 X 15 | | 21 X 15 |

- REMOVE AND REPLACE
 STA. 11+55
- | | |
|--------|---------|
| EM-1aT | 24 DIA. |
| M6-1B | 21 X 15 |




REMOVE AND REPLACE
 STA. 13+08

SPEED LIMIT
 R2-1
 30 X 36

- REMOVE AND REPLACE
 STA. 14+15
- | | |
|-------|---------|
| JCT | M2-1 |
| TEXAS | 21 X 15 |
| | M1-6T |
| | 24 X 24 |


- REMOVE AND REPLACE
 STA. 14+15
- | | |
|------|--------------|
| EAST | M3-2 |
| | 24 X 12 |
| | M1-4 (2 DGT) |
| | 24 X 24 |

- REMOVE AND REPLACE
 STA. 15+31
- | | |
|--|---------|
| | S4-3P |
| | 24 X 8 |
| | S5-1 |
| | 24 X 48 |
| | S7-1T |
| | 36 X 18 |



LEGEND

WB - WHITE BROKEN	YD - YELLOW DOUBLE SOLID	o PIPE	INGRATE
WS - WHITE SOLID	● MANHOLE	XX - SIGN NUMBER	






11/20/2022
 PE.

**BU 90Y
 PAVEMENT MARKING
 LAYOUT AND SIGNING**
 N. T. S

SHEET 1 OF 5

CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	42	

DATE: 11/18/2022 5:14:28 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Pavement_Markings\Layout.dgn



11/20/2022
 P.E.



MATCHLINE
 STA. 35+00

**BU 90Y
 PAVEMENT MARKING
 LAYOUT AND SIGNING**
 N. T. S

SHEET 2 OF 5


CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	43	

DATE: 11/18/2022 5:14:30 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Pavement_Markings\Layout.dgn



LEGEND

WB - WHITE BROKEN	YD - YELLOW DOUBLE SOLID	○ PIPE	▭ INGRATE
WS - WHITE SOLID	● MANHOLE	XX - SIGN NUMBER	




11/20/2022
 P.E.

**BU 90Y
 PAVEMENT MARKING
 LAYOUT AND SIGNING
 N. T. S**

SHEET 3 OF 5

CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	44	

DATE: 11/18/2022 5:14:33 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Pavement_Marking_Layout.dgn




LEGEND

WB - WHITE BROKEN	YD - YELLOW DOUBLE SOLID	○ PIPE	▭ INGRATE
WS - WHITE SOLID	● MANHOLE	XX - SIGN NUMBER	

TO

▭	M4-5B
▭	24 X 12
▭	M1-1 (2 DGT)
▭	24 X 24
▭	M6-1B
▭	21 X 5



11/20/2022
 PE.




**BU 90Y
 PAVEMENT MARKING
 LAYOUT AND SIGNING**
 N. T. S

SHEET 4 OF 5

CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	45	

DATE: 11/18/2022 5:14:36 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\Pavement_Markings_Layout.dgn

DN: []
 CK: []
 DW: []
 CK: []




REMOVE AND REPLACE
 STA. 73+29

STOP 36 X 36
 R1-3P
 18 X 6

**BU 90Y
 PAVEMENT MARKING
 LAYOUT AND SIGNING**
 N. T. S

SHEET 5 OF 5



LEGEND

WB - WHITE BROKEN	YD - YELLOW DOUBLE SOLID	o PIPE	INGRATE
WS - WHITE SOLID	● MANHOLE	XX - SIGN NUMBER	

REMOVE AND REPLACE
 STA. 71+35

M3-2	24 X 12
M1-4 (2 DGT)	24 X 24
M6-1	21 X 15

REMOVE AND REPLACE
 STA. 72+07

STOP	R1-1
	36 X 36
	R1-3P
	18 X 6

CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	46	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
	1	M4-5B	TO <BLUE AUX SIGN>	24 x 12	X		S80	1	SB	U	2EXT	
		M1-1(2 dgt)	INTERSTATE (ROUTE #)	24 x 24								
		M6-1B	<ARROW - HORIZ. STRGHT> <BLUE AUX SIGN>	21 x 15								
		M3-1	NORTH <AUXILIARY SIGN>	24 x 12								
		M1-6T	(ROUTE #) TEXAS	24 x 24								
		M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21 x 15								
		M4-3	BUSINESS <AUXILIARY SIGN>	24 x 12								
		M1-4(2 dgt)	<US HIGHWAY ROUTE SHIELD> (ROUTE #)	24 x 24								
		M6-3	<ARROW - VERTICAL STRGHT> <AUX. SIGN>	21 x 15								
		M3-3	SOUTH <AUXILIARY SIGN>	24 x 12								
		M1-6T	(ROUTE #) TEXAS	24 x 24								
		M6-3	<ARROW - VERTICAL STRGHT> <AUX. SIGN>	21 x 15								
	1	EM-1aT	EVACUATION ROUTE <w/ HURRICANE SYMBL>	24 DIA	X		10BWG	1	SB	P		
		M6-1B	<ARROW - HORIZ. STRGHT> <BLUE AUX SIGN>	21 x 15								
	1	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SB	P		
	1	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SB	P		
	1	M3-2	EAST <AUXILIARY SIGN>	24 x 12	X		10BWG	1	SB	P		
		M1-4(2 dgt)	<US HIGHWAY ROUTE SHIELD> (ROUTE #)	24 x 24								
	1	M2-1	JCT <AUXILIARY SIGN>	21 x 15	X		10BWG	1	SB	P		
		M1-6T	(ROUTE #) TEXAS	24 x 24								
	1	S4-3P	SCHOOL <PLAQUE>	24 x 8	X		10BWG	1	SB	P		
		S5-1	SCHOOL / SPEED LIMIT (SPEED) WHEN FLASHING	24 x 48								
		S7-1T	CELL PHONE USE PROHIBITED UP TO \$200 FINE	36 x 18								
	2	W10-1	SYMBOL - GRADE XING ADVANCED WARNING	36 diameter	X		10BWG	1	SB	P		
		10	R15-1	RAILROAD GRADE CROSSING <CROSSBUCK>	48 x 9							
	2	11	R15-1	RAILROAD GRADE CROSSING <CROSSBUCK>	48 x 9							
	2	12	S1-1	SYMBOL - PED CROSSING <PENTAGONAL>	36 x 36	X	10BWG	1	SB	P		
	2	13	W10-1	SYMBOL - GRADE XING ADVANCED WARNING	36 diameter	X	10BWG	1	SB	P		
	2	14	M2-1	JCT <AUXILIARY SIGN>	21 x 15	X	10BWG	1	SB	U		
		M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24								
	3	15	M3-4	WEST <AUXILIARY SIGN>	24 x 12	X	10BWG	1	SB	P		
		M1-4(2 dgt)	<US HIGHWAY ROUTE SHIELD> (ROUTE #)	24 x 24								
	3	16	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X	S80	1	SB	U	1EXT	
		M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21 x 15								
		M4-3	BUSINESS <AUXILIARY SIGN>	24 x 12								
		M1-4(2 dgt)	<US HIGHWAY ROUTE SHIELD> (ROUTE #)	24 x 24								
		M6-3	<ARROW - VERTICAL STRGHT> <AUX. SIGN>	21 x 15								
		17	R3-1	SYMBOL - NO RIGHT TURN	36 x 36	X	10BWG	1	SB	P		
	3											

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SHEET 1 OF 2

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	ORANGE	47	

SUMMARY OF SMALL SIGNS

DATE: 2022/11/18
 FILE: D:\txdot\project\wiseonline.com\TXDOTS\Documents\20 - BMT\Design Project\02210509\Signs\Signs.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into a digital format or for any damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
3	18	R6-1R R6-1L	ONE WAY <IN RIGHT ARROW> ONE WAY <IN LEFT ARROW>	54 x 18 54 x 18	X		10BWG	1	SB	P		
3	19	R6-1R M4-3 M1-4(2 dgt) M6-3 M1-6F M6-1	ONE WAY <IN RIGHT ARROW> BUSINESS <AUXILIARY SIGN> <US HIGHWAY ROUTE SHIELD> (ROUTE #) <ARROW - VERTICAL STRGHT> <AUX. SIGN> <FM SHIELD> FARM ROAD (ROUTE #) <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	54 x 18 24 x 12 24 x 24 21 x 15 24 x 24 21 x 15	X		10BWG	1	SB	U	1EXT	
3	20	R3-1 R6-1R	SYMBOL - NO RIGHT TURN ONE WAY <IN RIGHT ARROW>	36 x 36 54 x 18	X		10BWG	1	SB	P		
3	21	R6-1R	ONE WAY <IN RIGHT ARROW>	54 x 18	X		10BWG	1	SB	P		
3	22	R6-1L	ONE WAY <IN LEFT ARROW>	54 x 18	X		10BWG	1	SB	P		
3	23	M3-2 M1-4(2 dgt)	EAST <AUXILIARY SIGN> <US HIGHWAY ROUTE SHIELD> (ROUTE #)	24 x 12 24 x 24	X		10BWG	1	SB	P		
3	24	M2-1 M1-6F	JCT <AUXILIARY SIGN> <FM SHIELD> FARM ROAD (ROUTE #)	21 x 15 24 x 24	X		10BWG	1	SB	P		
4	25	W11-2	SYMBOL - BE ALERT FOR PEDESTIRANS	36 x 36	X		10BWG	1	SB	P		
4	26	W3-1	SYMBOL - STOP AHEAD	30 x 30	X		10BWG	1	SB	P		
4	27	R1-1	STOP	36 x 36	X							
4	28	W11-2	SYMBOL - BE ALERT FOR PEDESTIRANS	36 x 36	X		10BWG	1	SB	P		
4	29	W11-2	SYMBOL - BE ALERT FOR PEDESTIRANS	36 x 36	X		10BWG	1	SB	P		
4	30	R1-1	STOP	36 x 36	X							
4	31	R2-1	SPEED LIMIT (SPEED)	30 x 36								
4	32	W3-1	SYMBOL - STOP AHEAD	30 x 30			10BWG	1	SB	P		
4	33	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SB	P		
4	34	M4-5B M1-1(2 dgt) M6-1B	TO <BLUE AUX SIGN> INTERSTATE (ROUTE #) <ARROW - HORIZ. STRGHT> <BLUE AUX SIGN>	24 x 12 24 x 24 21 x 15	X		10BWG	1	SB	P		
4	35	W11-2	SYMBOL - BE ALERT FOR PEDESTIRANS	36 x 36	X		10BWG	1	SB	P		
5	36	W3-1	SYMBOL - STOP AHEAD	30 x 30	X		10BWG	1	SB	P		
5	37	M3-2 M1-4(2 dgt) M6-1	EAST <AUXILIARY SIGN> <US HIGHWAY ROUTE SHIELD> (ROUTE #) <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	24 x 12 24 x 24 21 x 15	X		10BWG	1	SB	P		
5	38	R1-1 R1-3P	STOP ALL WAY	36 x 36 18 x 6	X		10BWG	1	SB	P		
5	39	R1-1 R1-3P	STOP ALL WAY	36 x 36 18 x 6	X		10BWG	1	SB	P		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).




SUMMARY OF SMALL SIGNS


SHEET 2 OF 2

SOSS


FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	ORANGE	48	




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




YIELD LINES

GENERAL NOTES

1. Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**


Based on Traveled Way and Pavement Widths for Undivided Highways



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES

1. Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
2. Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
3. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.



DocuSigned by:
Ramona J. Williams
5F7D9606A1B04CF...
10/18/2022



**TYPICAL STANDARD
PAVEMENT MARKINGS
MODIFIED**


PM(1) - 20 (MOD)

FILE: bmtdistrictpm-22.dgn	DWG	CKE	DWG	CKE
© TXDOT JUNE 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU90Y
	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	49	


FILE:

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




CENTERLINE FOR ALL TWO LANE ROADWAYS



**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**




CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.




MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.





Type I (Top View)



Type II (Top View)



RAISED PAVEMENT MARKERS



**REFLECTORIZED PROFILE
PATTERN DETAIL**
USING REFLECTIVE PROFILE PAVEMENT MARKINGS


A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

NOTES

- Edge lines should typically be 6" wide and the materials shall be specified in the plans.
- Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

GENERAL NOTES

- All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
- Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.




DocuSigned by:
Rennett J. Williams
5F7D9606A1B04CF...
10/18/2022

**POSITION GUIDANCE USING
RAISED MARKERS
REFLECTORIZED PROFILE
MARKINGS MODIFIED
PM(2) - 20 MOD**

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10 REVISIONS	0028	15	059	BU 90-Y
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	BMT	ORANGE	50	

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	
45 MPH	775	
50 MPH	885	L = WS
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

NOTES


- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional W9-1R "RIGHT LANE ENDS" sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

GENERAL NOTES





- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.



Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS (MODIFICATION)
PM(3)-20 (MOD)

FILE: pm3-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90-Y
5-00 2-10	DIST	COUNTY	SHEET NO.	
8-00 2-12	BMT	ORANGE	51	
3-03 6-20				




DocuSigned by:
Ramona Williams
 10/18/2022

DATE:
 FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 6:05:48 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\Buisness\2020\2020-2021\2020-2021.dgn




HIGH-VISIBILITY LONGITUDINAL CROSSWALK AT CONTROLLED APPROACH

GENERAL NOTES

1. Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
3. For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
5. Each crosswalk shall be a minimum of 6' wide.
6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
7. Final placement of Stop Bar/Yield Triangles and Crosswalk shall be approved by the Engineer in the field.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



UNSIGNALIZED MID BLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK

NOTES

1. Use yield triangles with "Yield Here to Pedestrians" signs at unsignalized mid block crosswalks.
2. Use stop bars with "Stop Here on Red" signs at mid block crosswalks controlled by traffic signals or pedestrian hybrid beacons.

Traffic Safety Division Standard

CROSSWALK PAVEMENT MARKINGS

PM(4) - 20

FILE: pm4-20.dgn	DN:	CK:	DW:	CK:
© TxDOT June 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
	DIST	COUNTY		SHEET NO.
	BMT	ORANGE		\$PM(4) - 20\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 6:05:50 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90Y\smngen.dgn

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

Post Type

FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)


Anchor Type

UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))



REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT




To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).

SIGN LOCATION

PAVED SHOULDERS




T-INTERSECTION





When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




BEHIND BARRIER



**Sign clearance based on distance required for proper guard rail or concrete barrier performance.

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND




RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.



* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>




SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS SMD (GEN) - 08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0028	15	059	BU 90Y
		DIST	COUNTY		SHEET NO.
		BMT	ORANGE		53

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 6:05:53 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\smas1.dgn

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



SM RD SGN ASSM TY XXXXX(X)SA(X-XXXX)

NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm
 The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



5/8" diameter Concrete Anchor -
 8 places (embed a minimum of
 5 1/2" and torque to min. of
 50 ft-lbs). Anchor may be
 expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

















SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
9-08	REVISIONS		CONT	SECT	JOB	HIGHWAY
			0028	15	059	BU 90Y
			DIST	COUNTY		SHEET NO.
		BMT	ORANGE		54	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022 6:05:55 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\smas2.dgn



GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	













SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM
 SMD(SLIP-2)-08

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0028	15	059	BU 90Y
		DIST	COUNTY	SHEET NO.	
		BMT	ORANGE	55	

DATE: 11/18/2022 6:05:57 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90Y\smas3.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)



Texas Department of Transportation
 Traffic Operations Division
SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD (SLIP-3) -08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0028	15	059	BU 90Y
		DIST	COUNTY		SHEET NO.
		BMT	ORANGE		56

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another or for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 6:06:00 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BLS\092422\tsr3-13.dgn

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



TYPICAL SIGN REQUIREMENTS


TSR(3) - 13

FILE: tsr3-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	BMT	ORANGE	57	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 11/18/2022 6:06:02 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BLS\09092022\tsr4-13.dgn

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS

(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

GENERAL NOTES


- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES


SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

		Traffic Operations Division Standard	
<h2>TYPICAL SIGN REQUIREMENTS</h2>			
<h3>TSR(4) - 13</h3>			
FILE:	tsr4-13.dgn	DN:	TxDOT
© TxDOT	October 2003	CONT:	SECT
REVISIONS		0028	15
12-03	7-13	DIST:	COUNTY
9-08		BMT:	ORANGE
			SHEET NO.
			58


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings or specifications into other formats or for incorrect results or damages resulting from its use.

ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	


NOTE

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.

CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT


The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5



EXIT ONLY PANEL


MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

NOTE:

- Sheeting for legend, symbols, and borders must be cut at panel joints.
- Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".



SCREW ATTACHMENT




NUT/BOLT ATTACHMENT


NOTE:

Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.


TYPICAL SIGN REQUIREMENTS

TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	BMT	ORANGE	59	

DATE: 11/21/2022 8:34:22 AM
 FILE: c:\txdot\pw_online\txdot5\cindy.olmonte\d0647189\Railroad_Detail_version_3.dgn


DWG: C&G DWG: C&G



LEGEND

- TRACK BED
- MILL & OVERLAY

NOTE:
 1. CROSSING 762398X



S. J. Harris P.E.
 11/21/2022

BU 90Y
RAILROAD DETAIL
 N. T. S



CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.
BMT	ORANGE		60

DATE: 12/29/2022 10:47:23 AM
 FILE: c:\txdot\pw_online\txdot5\samantha_harris\d0647189\RR_Scope of Work (final).dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

DOT #: 762398X
 Crossing Type: **** AT GRADE**
 RR Company Owning Track at Crossing: UNION PACIFIC RAILROAD COMPANY
 Operating RR Company at Track: UNION PACIFIC RAILROAD COMPANY
 RR MP: 256.660
 RR Subdivision: LAFAYETTE
 City: ORANGE
 County: ORANGE
 CSJ at this Crossing: 0028-15-059
 Highway/Roadway name crossing the railroad: BU 90Y
 # of regularly scheduled trains per day at this crossing:
 # of switching movements per day at this crossing:
 % of estimated contract cost of work within railroad ROW: TBD

Scope of Work at this Crossing to Be Performed by State Contractor:
PAVEMENT MARKINGS ON EXISTING ROADWAY. TRAFFIC CONTROL PLAN WILL GO THROUGH RAILROAD RIGHT OF WAY.

Scope of Work at this Crossing to Be Performed by Railroad Company:
FLAGGING DURING PREVENTATIVE MAINTENANCE.

** Choose: Highway Overpass, Highway Underpass, At Grade, Pedestrian, or Closed/Abandoned

II. OTHER PROJECT WORK WITHIN RAILROAD RIGHTS-OF-WAY (ROW)

III. FLAGGING & INSPECTION

of Days of Railroad Flagging Expected: 60
 On this project, night or weekend flagging is:
 Expected
 Not Expected
 Flagging services will be provided by:
 Railroad Company: TxDOT will pay flagging invoices
 Outside Party: Contractor will pay flagging invoices, to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30 day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

- Contact Information for Flagging:
- UPRR - UP.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
- UP.request@nrssinc.net
Call Center 877-984-6777
 - BNSF - BNSF.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
 - KCS - KCS.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
- Bottom Line On-Track Safety Services
bottomline076@aol.com, 903-767-7630
 - OTHERS _____

Contractor must incorporate Construction Inspection into anticipated construction schedule.

- Not Required
 Required: Contact Information for Construction Inspection:

IV. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

On this project, construction work to be performed by a railroad company is:
 Required
 Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

V. RAILROAD INSURANCE REQUIREMENTS

Railroad reference number shall be provided by TxDOT CST or DO.
 The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice. Insurance policies must be issued for and on behalf of the Railroad. Where more than one Railroad Company is operating on the same right of way or where several Railroad Companies are involved and operate on their own separate rights of way, provide separate insurance policies in the name of each Railroad Company.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$2,000,000 / \$4,000,000
Business Automobile	\$2,000,000 combined single limit

Railroad Protective Liability	
<input type="checkbox"/> Not Required	
<input checked="" type="checkbox"/> Non - Bridge Projects	\$2,000,000 / \$6,000,000
<input type="checkbox"/> Bridge Projects	\$5,000,000 / \$10,000,000
<input type="checkbox"/> Other	

VI. CONTRACTOR'S RIGHT OF ENTRY (ROE) AGREEMENT

On this project, an ROE agreement is:
 Not Required
 Required: TxDOT CST to assist in obtaining with the UPRR (see Item 5, Article 8.3)
 Required: UPRR Maintenance Consent Letter. TxDOT CST to assist.
 Required: Contractor to obtain (see Item 5, Article 8.4)
 With the following railroad companies: _____

To view previously approved ROE Agreement templates agreed upon between the State and Railroad, see:

<http://www.txdot.gov/inside-txdot/division/rail/samples.html>

Approved ROE Agreement templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed ROE agreement between the Contractor and the Railroad if required on project.

VII. RAILROAD COORDINATION MEETING

On this project, a Railroad Coordination Meeting is:
 Not Required
 Required

See Item 5, Article 8.1 for more details.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are required to maintain the same insurance coverage as required of the Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call UNION PACIFIC RAILROAD COMPANY
Railroad Emergency Line at 1-800-848-8715
Location: DOT 762398X
RR Milepost *****
Subdivision *****

Rail Division

RAILROAD SCOPE OF WORK

PROJECT SPECIFIC DETAILS

FILE: RR Scope of Work.dgn	DN: TxDOT	CK: _____	DW: _____	CK: _____
© TxDOT June 2014	CONT	SECT	JOB	HIGHWAY
9/2021	REVISIONS	0028 15	059	BU 90Y
	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	61	

PART 1 - GENERAL

1.01 DESCRIPTION

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

1.02 REQUEST FOR INFORMATION / CLARIFICATION

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

1.03 PLANS / SPECIFICATIONS

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

PART 2 - UTILITIES AND FIBER OPTIC

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

PART 3 - CONSTRUCTION

3.01 GENERAL

- A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.
- B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.
- C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.
- D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.
- E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.
- F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.
- G. All permanent clearances shall be verified before project closing.

3.02 RAILROAD OPERATIONS

- A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.
- B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. Railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.
- C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:
 - 1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.
 - 2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES

- A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.
- B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.
- C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.
- D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
 - 1. Exactly what the work entails.
 - 2. The days and hours that work will be performed.
 - 3. The exact location of work, and proximity to the tracks.
 - 4. The type of window requested and the amount of time requested.
 - 5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.
- E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

3.04 INSURANCE

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

3.05 RAILROAD SAFETY ORIENTATION

- A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."
- B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

3.06 COOPERATION

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES



Abide by the following minimum temporary clearances during the course of construction:
A. 15' - 0" (BNSF) (UPRR) and 14' - 0" (KCS) horizontal from centerline of track
B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

3.08 APPROVAL OF REDUCED CLEARANCES

- A. Maintain minimum track clearances during construction as specified in Section 3.07.
- B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.
- C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

DATE: 11/18/2022 6:06:55 PM
FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90YR_Railroad_Requirements_for_Non-Bridge.dgn

					
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS March 2020	0028	15	059	BU	90Y
	DIST	COUNTY		SHEET NO.	
	BMT	ORANGE		62	

DATE: 11/18/2022 6:06:58 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90YR_Railroad_Requirements_for_Non-Bridge.dgn

3.09 MAINTENANCE OF RAILROAD FACILITIES

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractors's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
 1. Pre-construction meetings.
 2. Pile driving/drilling of caissons or drilled shafts.
 3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
 4. Erection of precast concrete or steel bridge superstructure.
 5. Placement of waterproofing (prior to placing ballast on bridge deck).
 6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

3.11 RAILROAD REPRESENTATIVES

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

3.12 COMMUNICATIONS AND SIGNAL LINES

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

3.13 TRAFFIC CONTROL

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193
 7:00 AM to 9:00 PM CST Monday-Friday except holidays,
 staffed 24 hrs/day for emergencies
 48 hrs notice required

BNSF 1-800-533-2891
 24 hour number
 5 working days notice required

KCS 1-800-344-8377
 Texas One Call, a 24 hour number
 48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

3.15 RAILROAD FLAGGING



Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

3.16 CLEANING OF RIGHT-OF-WAY


When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

Texas Department of Transportation				Rail Division	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT	October 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS		0028	15	059	BU 90Y
March 2020		DIST	COUNTY	SHEET NO.	
		BMT	ORANGE	63	


11/18/2022 6:07:00 PM
 DATE: 11/18/2022 6:07:00 PM
 FILE: C:\Users\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\Bureau\Projects\2016\002815\059\002815-059.dgn
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings or documents into digital formats or for incorrect results or damages resulting from its use.



2-WAY, MULTIPLE LANES EACH DIRECTION



2 LANES, 2-WAY



1-WAY STREET WITH CURB

- NOTES**
- T: Tip of gate to edge of curb: 1' max for Quiet Zone SSM, 90% of traveled way covered by gates for all other locations
 - U: Non-traversable curb length from gate: 100' min. for a Quiet Zone SSM, 10' min for all other locations.

NOTES

- A1: Center of RR mast to center of rail: 12' minimum, 15' typical.
- A2: Tip of gate to center of rail: 12' minimum, 15' typical.
- B: Center of mast (cantilever, gate, or mast flasher) of nearest active traffic control device to stop line: 8' (NOTE: Stop line may be moved as needed, but should be at least 8' back from gates, if present).
- C: Center of detectable warning device to nearest rail: 6' minimum
- D: Center of gate mast to center of cantilever mast: 6' typical. NOTE: Cantilever may be located in front or behind gates.
- E: Edge of median or curb to nearest rail: 10' typical. NOTE: Design median edge to be parallel with rail.
- F: Edge of planking panel from edge of pavement or sidewalk: 3' minimum. NOTE: Field panels need not be in line with gauge panels.
- G: Length of panels along rail: 8' typical.
- H: Width of field panel: 2' typical (check with railroad company).
- I: Distance between rails: 4'-8.5\".
- J: Tip of gate to tip of gate: 2' maximum for Quiet Zone SSM or 90% of traveled way covered by gates for all other locations.
- K: Nearest edge of RR cabin from edge of pavement: 30' typical. NOTE: Cabinet not required to be parallel to edge of pavement.
- L: Nearest edge of RR cabin from nearest rail: 25' typical.
- M: Center of RR mast to edge of sidewalk: 6' minimum.
- N: Center of gate mast to leading edge of non-traversable median: 100' minimum to qualify as a Quiet Zone SSM. NOTE: 60' will suffice if there is a street intersection within the 100' and all street intersections within 60' are closed.
- O: Width of median: 8'-6\" minimum, 10' typical when using median gates. NOTE: Center of gate mast minimum 4'-3\" from face of curb.
- P: Center of RR mast to face of curb: 4'-3\" minimum. Center of RR mast to edge of pavement (with shoulder): 6' minimum. Center of RR mast to edge of pavement (no shoulder): 8'-3\" minimum. NOTE: BNSF prefers 5'-3\", 7\", and 9'-3\" minimums, respectively.
- Q: Gate length: 28' or less typical, but railroad company may allow up to 32' under special circumstances.
- R: Stop line to first RR Crossing transverse line (bike lane): 50' typical.
- S: Stop line to GRADE CROSSING ADVANCE WARNING (W10-1) sign and adjacent RR Crossing pavement markings. See Table 1. See RCD(2) for other signs.

TABLE 1


Approach Speed (mph)	Desirable Placement (feet)
20	100
25	100
30	100
35	100
40	125
45	175
50	250
55	325
60	400
65	475
70	550
75	650

LEGEND

	Sign
	Object Marker
	Traffic Flow
	Cantilever
	Gate Assembly
	Mast Flasher Pair

GENERAL NOTES

- Medians and curbs must be non-traversable to qualify as a Quiet Zone Supplementary Safety Measure (SSM). Non-traversable curbs in Quiet Zones are 6\" tall minimum and used on roadways where speed does not exceed 40 mph.
- Raised pavement markers may be used to supplement striping. See PM(2) and PM(3) standard sheets.
- Medians preferred whenever possible to prevent vehicles from driving around gates.
- Longitudinal edge striping may be continued thru crossing as needed. Illumination may also be considered for nighttime visibility.
- See SMD standard sheets for sign mounting details.
- See the Standard Highway Sign Design for Texas (SHSD) manual for sign and pavement marking details.



Texas Department of Transportation

Traffic Operations Division Standard

RAILROAD CROSSING
 DETAILS
 SIGNING, STRIPING, AND
 DEVICE PLACEMENT
 RCD(1)-16

FILE: rcd1-16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT FEBRUARY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
DIST	COUNTY		SHEET NO.	
BMT	ORANGE		64	

SITE DESCRIPTION

Notes:

- (1) The Site Description is accomplished using various sheets, each revealing separate details. This Index Sheet's purpose is to point the user to the appropriate location where the information required by the TPDES CGP can be found.
- (2) The project limits shown on the Title Sheet and limits of TxDOT Right Of Way shall also be the limits of coverage of the SW3P.

NATURE OF ACTIVITY: Full Depth Concrete Repair, Clean and Seal Joints, Seal Coat, Mill & Overlay, Pavement Markings

INTENDED SEQUENCE OF MAJOR SOIL DISTURBING ACTIVITIES: None

TOTAL AREA OF SITE: 11.5 AC AREA TO BE DISTURBED: 0.0 AC

If area of disturbance can be expected to exceed 1.0 acres, Beaumont District Standard SW3P-B should be included in the plans.

PRE-CONSTRUCTION RUNOFF CO-EFFICIENT: 0.90

POST-CONSTRUCTION RUNOFF CO-EFFICIENT: 0.90

EXISTING SOIL DESCRIPTION: URLX - Urban Land

GENERAL LOCATION MAP: See Title Sheet

RECEIVING WATERS: SEGMENT NUMBER 0501/0508
SEGMENT NAME Sabine River/Adams Bayou

LOCATION OF WETLAND OR SPECIAL AQUATIC SITES: See EPIC/SW3P Layout

DRAINAGE PATTERNS: From Road to Gutter to Storm Sewer to Outfall

TYPICAL AREAS OF SOIL DISTURBANCE: No disturbance

TYPICAL AREAS WHICH WILL NOT BE DISTURBED: All areas - no disturbance

LOCATION OF OFF-SITE SURFACE RECEIVING WATERS: Sabine River or Adams Bayou

LOCATIONS WHERE STABILIZATION PRACTICES WILL OCCUR: See SW3P Layout.

LOCATIONS OF OFF-SITE STORAGE OF MATERIALS AND EQUIPMENT, WASTE, BORROW; OR DEDICATED MATERIAL PROCESSING PLANTS: To be determined by Contractor.

LOCATIONS WHERE STORM WATER DISCHARGES TO SURFACE WATERS: Sabine River or Adams Bayou

LOCATION OF POLLUTION CONTROL MEASURES: See SW3P Layout.

CONTROLS

SOIL STABILIZATION PRACTICES

INTERIM:

- | | |
|--|--|
| <input type="checkbox"/> TEMPORARY SEEDING | <input type="checkbox"/> PRESERVATION OF NATURAL RESOURCES |
| <input type="checkbox"/> MULCHING (Hay or Straw) | <input type="checkbox"/> FLEXIBLE CHANNEL LINER |
| <input type="checkbox"/> BUFFER ZONES | <input type="checkbox"/> OTHER |

PERMANENT:

- | | |
|------------------------------------|--|
| <input type="checkbox"/> SEEDING | <input type="checkbox"/> RETENTION BLANKET |
| <input type="checkbox"/> BLOCK SOD | <input type="checkbox"/> CHANNEL LINER |
| <input type="checkbox"/> OTHER | |

STRUCTURAL PRACTICES (T/P) *

- | | |
|--|--|
| <input type="checkbox"/> T SILT FENCE | <input type="checkbox"/> PAVED FLUMES |
| <input type="checkbox"/> HAY BALES | <input type="checkbox"/> ROCK BEDDING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> ROCK BERMS | <input type="checkbox"/> TIMBER MATTING AT CONSTRUCTION EXIT |
| <input type="checkbox"/> PIPE SLOPE DRAINS | <input type="checkbox"/> SEDIMENT TRAPS |
| <input type="checkbox"/> CHANNEL LINERS | <input type="checkbox"/> SEDIMENT BASINS |
| <input type="checkbox"/> STORM SEWERS | <input type="checkbox"/> CURB and GUTTER |
| <input type="checkbox"/> T STORM INLET SEDIMENT TRAP | <input type="checkbox"/> VELOCITY CONTROL DEVICES |
| <input type="checkbox"/> STONE OUTLET STRUCTURES | <input type="checkbox"/> T EROSION CONTROL LOGS |
| <input type="checkbox"/> DIVERSION, INTERCEPTOR, or PERIMETER SWALES | |
| <input type="checkbox"/> DIVERSION, INTERCEPTOR, or PERIMETER DIKES | |

* T means Temporary - P means Permanent

PERMANENT POST CONSTRUCTION TSS CONTROLS

- RETENTION / IRRIGATION
- EXTENDED DETENTION BASINS
- VEGETATIVE FILTER STRIPS / VEGETATIVE SWALES
- CONSTRUCTED WETLANDS
- WET BASINS

OTHER CONTROLS

- WATERING FOR DUST CONTROLS
- SEDIMENT REMOVAL FROM ROADWAY (SWEEPING)
- LOADED TRUCKS WILL BE COVERED WITH TARP

The above indicated practices are proposed to control pollutants in storm water discharges. These practices are based on information contained in TxDOT Storm Water Management Guidelines. The Schedule of implementation of these practices will be based on the intended Sequence of Major Soil Disturbing Activities. Stabilization measures shall be initiated no later than 14 days after construction activity of that portion of the site has temporarily or permanently ceased.

Describe construction and waste materials expected to be stored on site and proposed controls to reduce pollutants from these materials (include storage practices spill prevention and response. To be determined by Contractor.

Describe pollutant sources from areas other than construction and measures implemented at those sites to minimize pollutant discharges. All waste material will be disposed of in accordance with all State Laws and Regulations.

No construction waste will be buried on sites.

Describe measures necessary to protect listed endangered or threatened species, or critical habitat. See EPIC.

INFORMATION

MAINTENANCE:

All erosion and sediment control and other protective measures identified in the SW3P must be maintained in effective operating conditions. If site inspections required by this permit identify BMP's that are not operating effectively, maintenance shall be performed before the next anticipated storm event, or as necessary to maintain the continued effectiveness of storm water controls. If maintenance prior to the next anticipated storm event is unpracticable, maintenance must be scheduled and accomplished as soon as practical.

INSPECTION:

Qualified personnel shall inspect disturbed areas of the construction site that have not been finally stabilized, areas used for storage of materials that are exposed to precipitation, structural control measures, and locations where vehicles enter or exit the site.

Inspection Cycle Options:

- 1. At least every 14 calendar days or within 24 hrs after 0.5 inches or more of rainfall.
- 2. At least every 7 calendar days.
- 3. At least monthly (Engineer & DEQC approved revision to SW3P required).

a). Disturbed areas that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. Sediment and erosion control measures identified on the SW3P shall be observed to ensure that they are operating correctly. Locations where vehicles enter or exit the site shall be inspected for evidence of offsite sediment tracking. Sediments must be removed from sediment control structures no later than the time that the design capacity has been reduced by 50%.

b). Based on the result of the inspection, the SW3P shall be revised to include (show on Site Map) additional or modified BMP's designed to correct the observed deficiency. Revisions to the SW3P must be completed within seven (7) calendar days following the inspection.

c). A report summarizing the scope, date, name and qualifications of inspector, and major observations relating to the implementation of the SW3P shall be produced and retained as part of the SW3P for 3 years from date of final stabilization.

d). The following records must be maintained and either attached to or referenced in the SW3P, and made readily available upon request to the parties in Part III.D.1 of the CGP: 1). The dates when major grading activities occur; 2). The dates when construction activities temporarily or permanently cease on a portion of the site and; 3). The dates when stabilization measures are initiated.

INSPECTOR PAPERWORK CHECKLIST:


- Contact Form (1)
- Notice of Intent (1)(2)
- SW3P Certification Statement (signed by AE) (2)
- Delegation of Signature Authority (all Inspectors signing reports) (2)(3)
- TPDES General Permit (2)(3)
- Environmental Document (2)
- Inspection and Maintenance Report (2)(3)
- Notice of Termination (2)
- SW3P Plan (2)(3)
- Inspector Qualification Form (2)(3)
- Project Diary (2)(3)

- (1) The information should be displayed on the Project Bulletin Board.
- (2) The information should be a part of the permanent SW3P file maintained at the Area Office.
- (3) The information should be maintained at the Field Office.


STORM WATER POLLUTION PREVENTION PLAN is consistent with requirements specified in applicable sediment and erosion site plans or site permits, or storm water management site plans or site permits approved by State, Tribal or local officials (i.e. MS4 Permits).

Any reportable quantity of Hazardous Material release must be reported to the National Response Center at 1-800-424-8802. In addition the Beaumont District "Hazardous Material Spill Information Form" must be completed and mailed to the EPA Regional Office in Dallas, Tx.

A copy of the Construction General Permit is part of the SW3P.



[Signature]
P.E.
11/20/2022



REVISIONS	FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.
05/22/02 VW	6	6	65
11/08/02 VW			
03/06/03 VW			
06/11/04 VW			
09/15/15 MW			
STATE DIST. NO.		COUNTY	
TEXAS		ORANGE	
CONT. SECT.		JOB HIGHWAY NO.	
0028 15		059 BU 90Y	

DATE: 12/2/2022 9:08:05 AM
 FILE: c:\txdot\pw_online\txdot5\samantha_harris\0646056\EPIC_6-21-2019.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- 1. TxDOT - Beaumont District

- 2. City of Orange

No Action Required Required Action

Action No.

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
2. Comply with the SW3P and revise when necessary to control pollution or as required by the Engineer.
3. The project is estimated to involve less than one acre of soil disturbance. In the event the project disturbance acreage becomes equal to or greater than one acre, the CGP is applicable. Contact TxDOT project inspector for coordination with DEQC for necessary action.
4. Take measures to prevent construction materials and debris including, but not limited to wastewater (i.e., cooling liquid, etc.) associated with concrete removal from entering any inlets, ditches, or waterways.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions, including Regional conditions for the State of Texas, associated with the following permit(s):

No Permit Required

Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)

Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)

Individual 404 Permit Required: Permit # _____

Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1. Maintain a neat and clean worksite next to the water and do not allow any debris to fall into the water.
2. Comply with "Work In or Near Waters/Wetlands Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion

Temporary Vegetation

Blankets/Matting

Mulch

Sodding

Interceptor Swale

Diversion Dike

Erosion Control Compost

Mulch Filter Berm and Socks

Compost Filter Berm and Socks

Sedimentation

Silt Fence

Rock Berm

Triangular Filter Dike

Sand Bag Berm

Straw Bale Dike

Brush Berms

Erosion Control Compost

Mulch Filter Berm and Socks

Compost Filter Berm and Socks

Stone Outlet Sediment Traps

Sediment Basins

Post-Construction TSS

Vegetative Filter Strips

Retention/Irrigation Systems

Extended Detention Basin

Constructed Wetlands

Wet Basin

Erosion Control Compost

Mulch Filter Berm and Socks

Compost Filter Berm and Socks

Vegetation Lined Ditches

Sand Filter Systems

Sand Filter Systems

III. CULTURAL RESOURCES

No Action Required

Required Action

Action No.

1. Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

IV. VEGETATION RESOURCES

No Action Required

Required Action

Action No.

1. No vegetation removal or trimming of any kind is allowed. Exceptions are allowed for mowed and maintained grass.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required

Required Action

Action No.

1. If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own.
2. If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEQC for guidance.
3. Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
4. Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and Texas Parks and Wildlife (TPW) Code Section 64.002. The full MBTA guidance may be found here: <https://ftp.dot.state.tx.us/pub/txdot-info/env/toolkit/350-01-gui.pdf>
5. Resource specific BMPs (Section I) and Pavement BMPs (Section II, F) from the 'Updated Best Management Practices (BMPs) for TxDOT Maintenance Activities' guidance under the TxDOT Maintenance Program EA shall be reviewed and implemented where appropriate. The maintenance EA BMPs may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/080-01-bmp.pdf>

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

No Action Required

Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances
- * Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
None	N/A	N/A	N/A	N/A

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

Action No.

1. Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous materials or contamination is noted during construction.
2. Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required

Required Action

Action No.

1. Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.

Beaumont District Standard

ENVIRONMENTAL PERMITS,
 ISSUES AND COMMITMENTS
 EPIC

FILE: epic.dgn
 ©TxDOT February 2019

D#: TxDOT
 CONT: 0028
 SECT: 15
 DIST: BMT

CK: AM
 JOB: 059
 COUNTY: ORANGE

DW: VP
 HIGHWAY: BU 90Y
 SHEET NO.: 66



APPROVED BY

12/2/2022
 DATE

DISTRICT ENVIRONMENTAL DEPARTMENT




DATE: 11/18/2022 6:07:05 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\SW3P.dgn

DWG: CDS DWF: CDS



LEGEND

	INLET		MANHOLE		PIPE		EROSION CONTROL LOG		INLET PROTECTION
--	-------	--	---------	--	------	--	---------------------	--	------------------



Samantha Jo Harris
 P.E.
 11/20/2022

MATCHLINE
 STA. 22+00

BU 90Y
SW3P LAYOUT
 N. T. S

SHEET 1 OF 5






CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	67	

DATE: 11/18/2022 6:07:07 PM
 FILE: C:\Users\SAMANTHA\OneDrive - Texas Department of Transportation\Desktop\BU90Y\SW3P.dgn

CNS:
 DWG:
 CDS:
 DWS:

LEGEND

	INLET		MANHOLE		PIPE
	EROSION CONTROL LOG		INLET PROTECTION		



SAMANTHA JO HARRIS
 P.E.
 11/20/2022

MATCHLINE
 STA. 35+00

BU 90Y
SW3P LAYOUT
 N. T. S

SHEET 2 OF 5






CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	68	

DATE: 11/18/2022 6:07:10 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\SW3P.dgn

CN:
 DW:
 CS:
 DN:

LEGEND

	INLET		MANHOLE		PIPE		EROSION CONTROL LOG		INLET PROTECTION
--	-------	--	---------	---	------	--	---------------------	--	------------------



Samantha Jo Harris PE
 11/20/2022

MATCHLINE
 STA. 41+50

BU 90Y
SW3P LAYOUT
 N. T. S

SHEET 3 OF 5



CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	69	

DATE: 11/18/2022 6:07:12 PM
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\SW3P.dgn

LEGEND

	INLET		MANHOLE		PIPE		EROSION CONTROL LOG		INLET PROTECTION
--	-------	--	---------	---	------	--	---------------------	--	------------------

SW3P #14 INLET PROTECTION SILT FENCE (10',10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #11 EROSION CONTROL LOGS (10',10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #13 EROSION CONTROL LOGS (10',10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:


SW3P #12 EROSION CONTROL LOGS (10',10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #15 EROSION CONTROL LOGS (10',10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #18 EROSION CONTROL LOGS (10',10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #16 EROSION CONTROL LOGS (10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #17 INLET PROTECTION SILT FENCE (10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:



S. J. Harris P.E.
 11/20/2022

MATCHLINE
 STA. 61+00

BU 90Y
SW3P LAYOUT
 N. T. S

SHEET 4 OF 5




CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	70	

MATCHLINE
 STA. 48+00

MATCHLINE
 STA. 54+50

MATCHLINE
 STA. 54+50



DATE: 11/20/2022 3:09:46 PM
 FILE: c:\txdot\pw_online\txdot5\samantha.harris\d0646056\SW3P.dgn

LEGEND

 INLET	 MANHOLE	 PIPE	 EROSION CONTROL LOG	 INLET PROTECTION
--	--	--	--	---


MATCHLINE
STA. 61+00

SW3P #19 EROSION CONTROL LOGS (10', 10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #21 EROSION CONTROL LOGS (10', 10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:


SW3P #20 EROSION CONTROL LOGS (10', 10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

MATCHLINE
STA. 67+50



65+00

R.O.W.




MATCHLINE
STA. 67+50


SW3P #22 EROSION CONTROL LOGS (10', 10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

SW3P #25 INLET PROTECTION SILT FENCE (10', 10')
 INSTALLED DATE:
 INSPECTOR INITIAL:
 REMOVED DATE:
 INSPECTOR INITIAL:

STA. 73+67
 END PROJECT
 CSJ 0028-15-059



70+00



Samantha Jo Harris P.E.
 11/20/2022


BU 90Y
SW3P LAYOUT
 N. T. S

SHEET 5 OF 5




CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	71	

DWG:
 CHK:
 DWF:
 CDS:
 DGN:




SILT FENCE DETAIL


GALVANIZED WELDED WIRE MESH (W.W.M.)
 (12.5 GA. SWG MIN.) WITH A MAXIMUM
 OPENING SIZE OF 2" X 4" OR WOVEN MESH
 (W.M.)



SILT FENCE PLAN




ANCHORAGE DETAIL




ANCHORAGE PLAN

NOTES:


1. REMOVE SECTION OF FILTER FABRIC AS SHOWN OR AS DIRECTED. FASTEN FABRIC TO EXPOSED WIRE WITH HOG RINGS OR CORD AT A MAXIMUM SPACING OF 15".
2. PLACE SANDBAGS AS SHOWN AT A MAXIMUM OF 3' ON CENTER BOTH IN THE GUTTER AND ON THE INLET. SUBMIT ALTERNATIVE ANCHORING METHODS FOR APPROVAL PRIOR TO INSTALLATION.
3. INSPECT INLETS DAILY. REMOVE ACCUMULATED SEDIMENT 2" OR MORE DEEP. REPAIR OR REPLACE DAMAGED INLET PROTECTION AS NECESSARY.



SANDBAG DETAIL




SECTION B-B



P.E.
 11/21/2022


**INLET PROTECTION
SILT FENCE**



CONT	SECT	JOB	HIGHWAY
0028	15	059	BU 90Y
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	72	


DATE: 11/21/2022 11:19:12 AM
 FILE: c:\ttdot\p_w_online\ttdot5\cindy.olmonte\d0646056\Inlet ProtectionDetail.dgn

10/18/2022
 CF11UBerS\SHARRIS\OneDrive - Texas Department of Transportation\Desktop\BU90\EC(1)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES


1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0028	15	059	BU 90Y	
	DIST	COUNTY		SHEET NO.	
	BMT	ORANGE		73	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\BU90Y\EC(9) -16.dgn



PLAN VIEW




SECTION A-A
EROSION CONTROL LOG DAM


CL-D

LEGEND

- CL-D EROSION CONTROL LOG DAM
- CL-BOC EROSION CONTROL LOG AT BACK OF CURB
- CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
- CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
- CL-DI EROSION CONTROL LOG AT DROP INLET
- CL-CI EROSION CONTROL LOG AT CURB INLET
- CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



REBAR STAKE DETAIL




PLAN VIEW



SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<i>Design Division Standard</i>		
<p>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</p> <p>EROSION CONTROL LOG</p> <p>EC (9) - 16</p>				
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0028	15	059	BU 90Y
	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	74	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\EC(9) - 16.dgn



**EROSION CONTROL LOGS ON SLOPES
STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




**EROSION CONTROL LOGS ON SLOPES
STAKE AND LASHING ANCHORING**

CL-SSL




STAKE AND TRENCHING ANCHORING DETAIL

CL-SST




NOTE: COMPACT EXCAVATED SOIL TO PREVENT UNDERCUTTING.




STAKE AND LASHING ANCHORING DETAIL

CL-SSL



LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

TRENCH DEPTH TABLE




STAKE NOTCH DETAIL

SHEET 2 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC(9) - 16			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0028	15	059
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	75	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 11/18/2022
 FILE: C:\Users\SHARRIS1\OneDrive - Texas Department of Transportation\Desktop\BU90Y\EC(9)-16.dgn




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0028	15	059
	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	76