SUBMITT

00%

SEE SHEET 2 FOR INDEX OF SHEETS

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

DESIGN SPEED = 35 MPH A.A.D.T. (2017)= 22,760 A.A.D.T. (2040)= 31,864

644 COUNTY SHEET NO.

EL PASO

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO. STP 2023(521) HES

DARRINGTON RD TOWN OF HORIZON CITY EL PASO COUNTY


FINAL PLANS

CONTRACTOR:	
TIME CHARGES BEGAN:	
DATE WORK WAS COMPLETED:	
DATE WORK WAS ACCEPTED:	
TOTAL DAYS CHARGED:	
ORIGINAL CONTRACT AMOUNT: \$	
AMOUNT OF CONTRACT AMENDMENTS	: _\$
FINAL CONTRACT COST: _\$	

CCI	HIGHWAY	LIM	LENGTH	LENGTH	
CSJ	nighwai	FROM	TO	(MI)	(FT)
0924-06-644	DARRINGTON RD	ALBERTON AVE	0.04 MI S OF LTV RD	1.255	6,626.40
			TOTAL	1.255	6,626.40

AREA ENGINEER

FOR THE CONSTRUCTION OF SAFETY LIGHTING



BEGIN PROJECT CSJ: 0924-06-644 STA: 16+05.21 © DARRINGTON RD LAT: 31.6687419 LONG: -106.189384

> END PROJECT CSJ: 0924-06-644

LAT: 31.6533687

LONG: -106.1781140

KEY TO COUNTIES

Texas Department of Transportation

© 2022 TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED 1/5/2023

1/5/2023

DRECUSIONEUDED FOR LETTING: Eduardo Perales, P.E.

-2778C00AB5F7426EVIEW COMMITTEE CHAIRMAN

PECONMENDED FOR LETTING:

L. Raul Ortega Jr., P.E.

1/5/2023

-7A68C5EA0D940496.RICT ENGINEER

MININA ENGLE 12/21/2022 **ATKINS**

EXCEPTIONS: NONE

RAILROAD CROSSINGS: NONE

EQUATIONS: NONE

TDLR INSPECTION NOT REQUIRED

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1) - 21 THRU BC (12) - 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES"

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

INDEX OF SHEETS

SHEET NO.	<u>DESCRIPTION</u>
	GENERAL
1	TITLE SHEET
2	INDEX OF SHEETS
3	PROJECT LAYOUT
4	TYPICAL SECTIONS
5, 5A-5F	GENERAL NOTES
6	ESTIMATE & QUANTITY SHEET
7	SUMMARY OF QUANTITIES
8	ELECTRICAL SERVICE DATA SHEET
9	HORIZONTAL ALIGNMENT DATA SHEET
10	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC
	TRAFFIC CONTROL PLAN
11 - 12	TRAFFIC CONTROL PLAN
	TRAFFIC CONTROL PLAN STANDARDS
13 - 22	X BC (1) - 21 THRU BC (10) - 21
23	X TCP (2-4) - 18
24	XTCP (2-6) - 18
25	X WZ (BTS-2) -13
	ILLUMINATION
26 - 31	ILLUMINATION PLAN
32	CIRCUIT DIAGRAM
	ILLUMINATION STANDARDS
33	X ★ED (1) -14
34	★ ED (2) -14
35	X X ED (3) -14
36	X X ED (4) -14
37	X X ED (5) -14
38	X X ED (6) -14
39	X X BID (10) -14
40	★ ★RID (1) - 20 ★ ★RID (2) - 20
	$\times \times \text{RID} (2) = 20$ $\times \times \text{RIP} (1) = 19 \text{ THRU RIP} (4) = 19$
42 - 45	X X RIP (1) - 19 THRU RIP (4) - 19
	EROSION CONTROL / WATER QUALITY
46 - 47	STORM WATER POLLUTION PREVENTION PLAN (SWP3)
.0 71	S. S. M. M. C. C. SEESTION FRETERITION FEAT (SIII 3)
	EROSION CONTROL STANDARDS
48 - 50	X EC (9)-16



*THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

CESAR R. NEVAREZ, P.E.




12/21/2022

**THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

ZAHIDUL Q. SIDDIQUE, P.E.

DARRINGTON RD INDEX OF SHEETS





3.726

2.47

3.726

DARRINGTON RD

1.255

6,626.40



DARRINGTON RD PROJECT LAYOUT

SHEET 01 OF 01

InfraTECH
Engineers & Innovators, LLC
TBPE REGISTRATION NO. F-18368


///	TBPE REG. # F-474
→ *	©2022
Texas Departm	ent of Transportation

		•		
CONT	SECT	JOB	HIGHWAY	
0924	06	644	DAF	RRINGTON
DIST		COUNTY		SHEET NO.
ELP		EL PASO		3

0924-06-644

EL PASO

ALBERTON AVE | 0.04 MI S OF LTV RD/CLARET CUP PL





DARRINGTON RD TYPICAL SECTIONS



COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

General Requirements

Maintain the entire project area in a neat and orderly manner throughout the duration of the work. Remove all construction litter and undesirable vegetation within the right of way inside the project limits. This work will be subsidiary to the various bid items.

General Project Description – Project consists of Safety Lighting on Darrington Road, Horizon City in El Paso County.

Traffic

Contact the Engineer or the City when construction operations are within 400 feet of a signalized intersection to determine/verify the location of loop detectors, conduit, ground-boxes, etc. Repair or replace any signal equipment damaged by construction operations. The method of repair or replacement shall be pre-approved and inspected. This work shall be completed at the Contractor's expense.

Inform the Engineer and the respective utility companies, when it becomes apparent that the utility lines will interfere with the work in progress.

Contractor questions on this project are to be addressed to the following individual(s):

Rene Moreno Aldo Madrid, P.E. Monica Ruiz, P.E.

East El Paso Area Engineer
Rene.Romero@txdot.gov Aldo.Madrid@txdot.gov Monica.Ruiz@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors.

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Town of Horizon City does not have personnel to conduct utility locates, it will be the contractor's responsibility to contact and coordinate with the pertinent utility providers.

Contractor shall coordinate with El Paso Electric Co. (Luis Jimenez Cell#: 915-472-3864 Email: luis.jimenez@epelectric.com) for any power source drops or work near electric lines that will require the installation of protective sleeve(s) to cover energized lines and avoid any injury for construction personnel safety.

CONTROL: 0924-06-644 SHEET 5

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Item 4 - Scope of Work

Schedule and perform all work to assure proper drainage during the course of construction or maintenance operations. All labor, tools, equipment and supervision required, to ensure drainage, removal, and handling of water shall be considered incidental work.

Contractor shall field locate all existing underground utilities prior to any construction with all utility companies.

Item 5 – Control of Work

The Department will furnish horizontal and vertical reference points. Contractor must verify horizontal and vertical reference points with conventional survey methods before proceeding with construction activities.

Contractor is responsible to coordinate with utility providers prior to any construction activity.

Plan datum for this project is NAD 83 for horizontal and NAVD 88 for elevation based.

Keep traveled surfaces used in hauling operations clear and free of dirt or other material.

Existing pavement, utilities, structures, etc. damaged as a result of the operations will be repaired at no additional cost to the Department.

Protect from damage and destruction all areas of the right of way, which are not included in the actual limits of the proposed construction areas. Exercise care to prevent damage to trees, vegetation, and other natural features. Protect trees, shrubs, and other landscape features from abuse, marring, or damage within the actual construction and/or fenced protection areas designated for preservation.

Restore any area disturbed or damaged to a condition "as good as" or "better than" prior to start of construction operation. This work will be at the Contractor's expense.

Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

Any proposed lane closures shall be during Off Peak hours 9 AM to 4 PM, M-F, or nights 9 PM to 6 AM, Sunday – Thursday.

GENERAL NOTES SHEET A GENERAL NOTES SHEET B

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Item 6 – Control of Materials

Furnish all materials on this project.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html.

Item 7 – Legal Relations and Responsibilities

Comply with all requirements of the Environmental Permits Issues and Commitments (EPIC) Sheet.

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

Occupational Safety & Health Administration (OSHA) regulations prohibit operations that bring people or equipment within 10 ft. of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all necessary adjustments to ensure the safety of workers near the energized line.

No significant traffic generator events identified.

Law Enforcement Personnel

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site.

CONTROL: 0924-06-644 SHEET 5A

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Item 8 – Prosecution and Progress

This project includes 120 days delay start for acquisition of illumination poles.

Working days will be calculated in accordance with Section 8.3.1., "Standard Workweek."

Create and maintain a Bar Chart schedule.

Submit baseline schedule and obtain approval prior to beginning construction. The monthly progress payment will be held if the monthly update is not submitted.

Provide a Project Schedule Summary Report on a monthly basis along with the monthly progress schedule.

Contractor allowed lane closure times defined as daytime hours of 9 A.M. to 4 P.M. Monday through Friday or nighttime hours of 9 P.M. to 6 A.M. Sunday through Thursday, unless otherwise directed by the Engineer.

Failure of Substantial Completion of Work for the project within the established number of working days shown above will result in the assessment of disincentives using the daily road-user costs shown above for each working day in excess of those allowed for Substantial Completion of Work for the project.

Item 9 - Measurement and Payment

Monthly progress payments will be made for items of work completed by the 27th day of each month. Any work completed after the 27th will be included for payment in the subsequent monthly progress payment.

Submit Material on Hand (MOH) payment requests at least **two (2)** working days before the 27th of the month for payment consideration on that month's estimate.

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement

GENERAL NOTES SHEET C SHEET D

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Personnel in Work Zones" (Course #133119) which can be found online at the following site: www.nhi.fhwa.dot.gov

Certificates of completion should be available to all who finish the course. These should be kept by the officers in order to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case-by-case basis.

<u>Item 416 – Drilled Shaft Foundations</u>

Stake all foundations and locations prior to commencement of drilling operations for verification to ensure no conflicts with utility lines; approval by Engineer will be required for all non-bridge foundations.

Cover drilled shafts with plywood and delineate with pedestrian fence, to the satisfaction of the Engineer, when no work is being performed and after working hours. This work will be considered subsidiary to this item.

Remove spoils, daily, out of the drainage areas or as directed

<u>Item 502 – Barricades, Signs, and Traffic Handling</u>

Prior to beginning construction, the Engineer will approve the routing of traffic and sequence of work.

Additional signs and barricades, placed as directed, will be considered subsidiary to this Item.

In accordance with Section 7.2.6.1, designate, in writing, a Contractor Responsible Person (CRP) and a CRP alternate to take full responsibility for the set-up, maintenance, and necessary corrective measures of the traffic control plan. The CRP or CRP alternate must be present at site and implement the initial set up of every traffic control phase/stage, at each location, and/or each call out, for the entire duration of the project.

At the written request of the Engineer, immediately remove the CRP or CRP alternate from the project if, in the opinion of the Engineer, is not competent, not present at initial TCP set-ups, or does not perform in a proper, skillful, or safe manner. These individuals shall not be reinstated without written consent of the Engineer.

CRP and CRP alternate must be trained using Department approved training. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 1 for Department approved Training.

CONTROL: 0924-06-644 SHEET 5B

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Table 1

Contractor Responsible Person and Alternate

Provider	Provider Course Number Course Title		Duration	Notes
American Traffic Safety Services Association	TCS	Traffic Control Supervisor	2 days	
National Highway Institute	133112 133113	Design and Operation of Work Zone Traffic Control Work Zone Traffic Control for Maintenance Operations	1 day 1 day	Both courses are required to meet minimum required training.
Texas Engineering Extension Services	133112A	Design and Operation of Work Zone Traffic Control	3 days	
University of Texas Arlington Division for Enterprise Development	WKZ421	Traffic Control Supervisor	16 hours	Contact UTA for training needs.

All contractor workers involved with the traffic control implementation and maintenance must participate and complete a Department approved training course. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 2 for Department approved training.

GENERAL NOTES SHEET E GENERAL NOTES SHEET F

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Table 2
Other Work Zone Personnel

Provider	Course Number	Course Title	Duration	Notes
American Traffic Safety Services Association	ТСТ	Traffic Control Technician	1 day	
Texas Engineering Extension Services	HWS002	Work Zone Traffic Control	16 hours	Identical to HWS-410. Counts for 3 year CRP requirement.
National Highway Institute Maintenance of Traffic for Technicians Technicians		5 hours	Web based	
National Highway Institute	134109-I	Maintenance Training Series: Basics of Work Zone Traffic Control	1 hour	Free, Web based
University of Texas at Arlington, Division for Enterprise Development	WKZ100	Work Zone Safety: Temporary Traffic Control	4 hours	Note name change. Free, Web based
TxDOT/AGC Joint Development	N/A	Safe Workers Awareness Highway Construction Work Zone Hazards	16 minutes 18 minutes	Videos available through AGC of Texas offices. English & Spanish
AGC America	N/A	Highway Work Zone Safety Training	1 day	
Texas Engineering Extension Service	HWS400	Temporary Traffic Control Worker	4 hours	Contact TEEX, if interested in course
TxDOT/AGC Joint Development	N/A	Work Zone Fundamentals	10 minutes	Videos available through ACT of Texas offices. English & Spanish

CONTROL: 0924-06-644 SHEET 5C

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Contractor may choose to train workers involved with the traffic control implementation and maintenance with a contractor developed training in lieu of Department approved training. Contractor developed training must be equivalent to the Department approved training shown in Table 2. Provide the Engineer a copy of the course curriculum for pre-approval, prior to conducting the contractor developed training. Provide the Engineer a copy of the log of attendees after training completion for project records.

Existing regulatory signs, route marker auxiliaries, guide signs, and warning signs that must be removed due to widening shall be relocated temporarily and erected on approved supports at locations shown in the plans, or as directed. This work will not be paid for directly, but considered subsidiary to this Item.

Notify the Department officials when major traffic changes are to be made, such as detours. Coordinate with the Department on all traffic changes. Advance notification for the following week's work must be made by 5 P.M. on Wednesdays.

If Law Enforcement Personnel is required by the Engineer, coordinate with local law enforcement as directed or agreed. Complete the weekly tracking form provided by the Department and submit invoices with 5% allowance for Law Enforcement payments by Contractor that agree with the tracking form for payment at the end of each month where approved services were provided.

Provide access to intersecting side roads and driveways at all times, unless otherwise directed.

Any approved change to the sequence of work or TCP, must be signed and sealed by a Contractor's Licensed Professional Engineer assuming full responsibility for any additional barricade signs and devices needed.

Use striping operations to channelize traffic into the newly completed roadway, as directed. Maintain shoulders and median areas in a condition capable of serving as emergency paths, as approved. This work will be subsidiary to this Item.

Use portable changeable message signs (PCMS) to alert public of construction two weeks prior to construction.

Use flaggers when directed. Provide two-way radio communication for all flaggers.

Place and maintain sufficient additional warning signs, beacons, delineators, and barricades to warn and guide the public of all hazards through the construction zone at all times, and as directed.

Use flashing arrow boards on all tapers for each lane closure.

Some signs, barricades, and channelization devices may not be shown at the precise or measured position. Place the barricades, devices, or signs, with approval, in positions to meet field conditions.

Fill any holes left by barricade or sign supports and restore the area to its original condition.

GENERAL NOTES SHEET G GENERAL NOTES SHEET H

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Use Type A flashing warning lights or delineators to mark open excavation, footings, foundations, or other obstructions near lanes that may be open to traffic, as directed.

For additional information pertaining to channelization, signing, spacing details, and flagging procedures required to regulate, warn, and guide traffic through project, refer to the "Barricade and Construction Standards," BC(1)-21 and to the current *Texas Manual on Uniform Traffic Control Devices(TMUTCD)*.

Remove or cover signs that do not apply to current conditions at the end of each day's work.

Repair and/or replace all signs damaged by the public or due to weather events.

Safety Contingency

The contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancement, to improve the effectiveness of the TCP that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506 – Temporary Erosion, Sedimentation, and Environmental Controls

Place Best Method Practices (BMP's) in locations as designated in the plans or as directed to meet field conditions.

Place a weatherproof bulletin board containing the Texas Commission on Environmental Quality (TCEQ) required information on the project at a site as directed. Post the following documents:

- 1. TCEQ "TPDES Storm Water Program" Construction Site Notice; Primary Construction Site Notices from both Contractor and Department, completed and signed.
- 2. TCEQ "Primary Notice of Intents," from both Contractor and Department; and
- 3. TCEQ "TPDES Permit."

Place rain gauge(s) at locations as designated.

The total disturbed area for this project is **0.89** acres. Establish the authorization requirements for Storm Water Discharges for soil disturbed area in this project, all project locations in the

Contract, and Contractor Project Specific Locations (PSLs), within one mile of the project limits. Both the Department and the Contractor shall obtain an authorization to discharge storm water from TCEQ for the construction activities shown on the plans. Obtain required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off right of way. When the total area disturbed for all projects in the Contract and PSLs within one mile of the project

CONTROL: 0924-06-644 SHEET 5D

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

limits exceeds five acres, provide a copy of the Contractor Notice of Intent (NOI) PSLs on the right of way to the Engineer (to the appropriate Municipal Separate Storm Sewer System (MS4) Operator when on an Off-system State route).

Best Method Practices (BMP's) may be adjusted to meet field conditions, or as directed. Engineer will verify all locations prior to placement of BMPs. Within the project limits, keep all inlets functional as long as possible to accept storm water as part of the Storm Water Pollution Prevention Plan (SWP3), as directed.

The sedimentation fences will be paid at the time of their initial placement. Any required replacement will be paid by Force Account.

Grading operations will be limited to the catch point of the proposed cross-section.

Preserve any vegetation outside these limits.

<u>Item 610 – Roadway Illumination Assemblies</u>

Conductor runs in Illumination Layouts contain 5 ft. of slack.

Limitations on Use of the RIP-19 Standard

The Roadway Illumination Pole (RIP-19) Standard Details were developed for installations in locations where the 3-second gust basic maximum wind speed is 110 mph, and where the elevation of the base of the pole is less than (i.e. not more than) 25 ft. above the elevation of surrounding terrain, in accordance with the AASHTO *Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals*, 6th Edition (2013) (AASHTO Design Specifications). For poles to be installed in regions where the maximum basic wind speed exceeds 110 mph or to be mounted more than 25-ft. above the surrounding terrain, provide poles meeting the following requirements:

Submittals. Submit fabrication drawings and calculations sealed by a licensed professional engineer. Follow the electronic shop drawing submittal process (see Guide Electronic Shop Drawing Submittal), to submit fabrication drawings and calculations for approval.

Luminaire Structural Support Requirements. Lighting poles, arms, and anchor bolt assemblies shall have a 25-year design life to resist dead loads, ice loads, and the required basic wind speeds safely at the location of installation in accordance with the current edition of the

AASHTO Design Specifications. For transformer base poles, the fabricator shall include transformer base and connecting hardware in calculations and shop drawing submittals. All transformer bases shall have been structurally tested to resist the theoretical plastic moment capacity of the pole. Certification of the plastic moment load test and FHWA breakaway requirement test of the model of base being furnished shall be submitted with the shop drawings.

GENERAL NOTES SHEET I GENERAL NOTES SHEET J

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Shop drawings shall show breakaway base model number, and manufacturer's name and logo. Manufacturer's shop drawings shall include the ASTM designations for all materials to be used. Fabricate steel roadway illumination poles in accordance with Department standards RIP-2019 (Roadway Illumination Poles – RIP (1)-19). Poles fabricated according to RIP-2019 require no shop drawings. Alternate designs to RIP-2019 or the use of aluminum to fabricate poles will require the submission of shop drawings electronically.

For instructions on submitting shop drawings electronically go to the Texas Department of Transportation (TxDOT) home page, http://txdot.gov, Business with TxDOT, Bridge information, Shop drawings. File is titled: Guide to Electronic Shop Drawing Submittal.

Item 618 - Conduit

The location of conduit is diagrammatic and may be varied to meet local conditions upon approval of the Engineer.

When shown on the plans, use underground warning tape in the trench installation of conduit (PVC).

For conduit placement in pavement, an earth-saw may be used provided the cut does not exceed 6 in. Backfill as shown on the trench details in the plans.

For all underground conduit bends of 45°, provide rigid metal conduit. Where the rigid metal conduit is exposed at any point and where rigid metal extends into ground boxes, bond the metal conduit to the grounding conductor with grounding type bushings or by other UL-listed grounding connectors, approved by the Engineer. Rigid metal bends will not be paid for directly but will be considered incidental to the PVC conduit system.

Backfill roadway and driveway trench with cement-stabilized backfill at the end of each working day. Place an ACP patch at the end of the week or as directed by the Engineer.

All conduit elbows and rigid metal extensions required to be installed on PVC conduit systems will not be paid for separately but will be considered subsidiary to the various bid items.

All bore items shall be directional and shall be paid for under this item. Bore quantities include the distance beneath the roadway plus an additional 2 ft. on either side of the curb, sidewalk, or edge of pavement.

For conduits install by open trench method, backfill the trench as shown on the plans.

Place conduit at a minimum depth of 18 in. below the pavement surface. Place conduit prior to the new pavement construction.

Fit both ends of each raceway with a temporary cap to prevent dirt and debris from entering during construction.

CONTROL: 0924-06-644 SHEET 5E

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Install a continuous green insulated copper wire as shown on the plans in every conduit throughout the electrical system in accordance with the electrical detail sheets, and the latest edition of the National Electrical Code.

When conduit is to be installed where riprap presently exists, take care in breaking the existing riprap for placement of the conduit. Do not break out a greater area that is required for placement of the conduit. Replace broken riprap with Class "C" concrete to the exact slope, pattern, color and thickness of the existing riprap. Replacement of riprap will be subsidiary to this Item.

Item 620 - Electrical Conductors

Use NEC type XHHW for all conductors.

Insulate grounding conductors with a green jacket and neutral conductors with a white jacket.

At every accessible point, bond together the grounding conductors which share the same conduit, junction box, ground box or structure in accordance with the electrical detail sheets and the latest edition of the National Electrical Code.

For both transformer and shoe-base type illumination poles, provide double-pole breakaway fuse holder as shown on the Department's Materials Producers List under "Roadway Illumination and Electrical Supplies." category. Fuse holder is shown on the list under Item 610, "Roadway Illumination Assemblies," and Item 620, "Electrical Conductors." Provide 10 amp time delay fuses.

Include extra cable length in each ground box or foundation for each run, to provide adequate slack, as provided in the plans or as directed.

Ensure a properly bonded electrical system by running one wire (as shown in the plans) between foundations and grounding it at each foundation ground-rod.

Bond metal junction boxes and metal conduit to the circuit grounding conductors in accordance with the National Electrical Code.

Refer to Article 7.18, "Electrical Requirements," for electrical certification and electrical licensing requirements

The required electrical certifications course is available and is scheduled periodically by Texas Engineering Extension Service (TEEX). Alternatively, Contractors may purchase an entire course for their personnel to be held at a time and location of their choice as negotiated through TEEX. For more information contact:

Texas Engineering Extension Service (TEEX) TxDOT Electrical System Course (979) 845-6563

GENERAL NOTES SHEET K GENERAL NOTES SHEET L

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

<u>Item 624 – Ground Boxes</u>

Remove all conductors in ground boxes as shown on the plans to be abandoned. Payment for removal of conductors will be subsidiary to this Item.

Item 628 – Electrical Services

Meet at the service locations with representatives of the Department, Town of Horizon City, and electrical utility company at least twelve weeks before electric power is needed to finalize exact service pole placement and resolve any issues.

Any electrical costs for connection, test, and operation will be the responsibility of the government agency that will have the final operational control of the items built.

Remove the existing service enclosure and conduit on service poles that are to be reused or abandoned. Payment for removal will be considered subsidiary to this Item.

Item 6001 - Portable Changeable Message Sign

Provide 2 electronic Portable Changeable Message Sign (PCMS) unit adjacent to the mainlanes in advance of each lane closure. PCMS units must be in accordance with Section 6F.60 of the TMUTCD, applicable standards and special provisions. Depending on conditions, one or both message boards may have to be relocated during daily operations. Messages will be in accordance with current BC standards. When not in use, remove PCMS units from the right of way. Measurement and payment for the PCMAS noted above will be in accordance with Item 6001. The term "operational" is defined as displaying a message in direct support of current project operations as approved and directed by the Engineer.

<u>Item 6185 – Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)</u>

All TMA Operators must participate in a TMA workshop to be conducted by the El Paso District Safety Office, on the proper use of TMAs, prior to working on Department Right of Way (ROW). A certificate of completion will be issued to TMA Operators that successfully complete the TMA workshop. The certificate of completion must be carried by TMA Operators at all times while working on Department right of way.

Acquire the TCP and TMA Operator's certificates of completion prior to the authorization to begin work. No time suspension will be granted and no traffic control work will be allowed without certificates of completion.

The supporting vehicle for the TMA shall have a minimum gross (i.e., ballasted) vehicular weight of 19,000 pounds.

CONTROL: 0924-06-644 SHEET 5F

COUNTY: EL PASO

HIGHWAY: DARRINGTON ROAD

Basis of Estimate for Mobile TMAs							
TMA(Mobile)							
Standard	Required	Additional	TOTAL				
TCP(2-6)-18	1 TMA per lane closure per location		2				

GENERAL NOTES SHEET M GENERAL NOTES SHEET N



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0924-06-644

DISTRICT El PasoHIGHWAY DARRINGTON

COUNTY El Paso

Report Created On: Dec 21, 2022 3:53:33 PM

		CONTROL SECTION	N JOB	0924-0	6-644		
		PROJI	ECT ID	A0017	7458		
		CC	DUNTY	El Pa	iso	TOTAL EST.	TOTAL FINAL
		HIG	HWAY	DARRINGTON			TIVAL
ALT	BID CODE	DESCRIPTION	UNIT	EST. FINAL			
	110-6003	EXCAVATION (SPECIAL)	CY	0.900		0.900	
	416-6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	192.000		192.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	4.000		4.000	
	506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	15.000		15.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	15.000		15.000	
	610-6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED	EA	32.000		32.000	
	618-6023	CONDT (PVC) (SCH 40) (2")	LF	10,850.000		10,850.000	
	618-6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	1,120.000		1,120.000	
	620-6006	ELEC CONDR (NO.10) INSULATED	LF	36,960.000		36,960.000	
	624-6002	GROUND BOX TY A (122311)W/APRON	EA	8.000		8.000	
	628-6073	ELC SRV TY A 240/480 100(NS)SS(E)GC(O)	EA	2.000		2.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	40.000		40.000	
	6185-6002	TMA (STATIONARY)	DAY	60.000		60.000	
	14	PUBLIC UTILITY FORCE ACCT WORK (PARTICIPATING)	LS	1.000		1.000	
	18	LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	



DISTRICT	COUNTY	CCSJ	SHEET
El Paso	El Paso	0924-06-644	6

				SUMMARY C	F ILLUMINATION (QUANTITIES			
ITEM CODE	110	416	610	618	618	620	624	628	*
	6003	6029	6124	6023	6024	6006	6002	6041	
DESCRIPTION	EXCAVATION (SPECIAL)	DRILL SHAFT (RDWY ILL POLE) (30 IN)	IN RD IL (TY SA) 20T-4 (150W EQ) LED	CONDT (PVC) (SCH 40) (2")	CONDT (PVC) (SCH 40) (2") (BORE)	ELEC CONDR (NO.10) INSULATED	GROUND BOX TY A (122311) W/APRON	ELC SRV TY A 240/480 060(NS)SS(E)GC(0)	REMOVE TIMBERPOL LUMINAIRE ARM
UNIT	CY	LF	EA	LF	LF	LF	EA	EA	LS
CSJ: 0924-06-644									
SHEET 1 OF 6	0.15	24	4	830	60	2760			
SHEET 2 OF 6	0.15	30	5	2050	375	7500			
SHEET 3 OF 6	0.15	36	6	2305	90	7335	2		
SHEET 4 OF 6	0.15	42	7	2135	300	7620	3	1	1
SHEET 5 OF 6	0.15	36	6	2195	225	7500	3	1	
SHEET 6 OF 6	0.15	24	4	1335	70	4305			
PROJECT TOTAL	0.9	192	32	10850	1120	36960	8	2	1

^{*} FOR INFORMATION ONLY, TO BE REMOVED BY EL PASO ELECTRIC

SUMMARY OF TRAFFIC CONTROL QUANTITIES										
ITEM CODE	500 6001	502 6001	6001 6001	6185 6002						
DESCRIPTION	MOBILIZATION	BARRICADES, SIGNS AND TRAFFIC HANDLING	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)						
UNIT	LS	МО	DAY	DAY						
CSJ: 0924-06-644										
PROJECT TOTAL	1	4	40	60						

SUMMARY OF SWPPP QUANTITIES									
ITEM CODE	506 6040	506 6043							
DESCRIPTION	BIODEG EROSN CONT LOGS (INSTL)(8")	BIODEG EROSN CONT LOGS (REMOVE)							
UNIT	LF	LF							
CSJ: 0924-06-644									
PROJECT TOTAL	15	15							

DARRINGTON RD SUMMARY OF QUANTITIES



	ELECTRICAL SERVICE DATA SHEET											
Elec. Service No.	Sheet No.	Electrical Service Description	Service Conduit Size	Service Conductors No./Size	Safety Switch Amps	Main Ckt. Bkr. Pole/Amp	Two-Pole Contractor Amps	Panelbd/ Loadcenter Amp Rating	Branch Circuit ID	Branch Ckt. Bkr. Pole/Amps	Branch Circuit Amps	KVA Load Amps
1	4	ELC SRV TY A 240/480 060 (NS)SS(E)GC(0)	1 1/4"	3/#6	N/A	2P/60	60	N/A	А	2P/20	1.89	
									В	2P/20	1.68	1 '.'
2	5	ELC SRV TY A 240/480 060 (NS)SS(E)GC(0)	1 1/4"	3/#6	N/A	2P/60	60	N/A	С	2P/20	2.52	1.5
									D	2P/20	0.63	1.5



DARRINGTON RD ELECTRICAL SERVICE DATA SHEET



Beginning ch					ion					
Point 001		N	8,473,	947.3	30 E	-1,6	72,1	13.28	Sta	10+00.00
Course from	001 to PC	CUR_1	S 30°	03′ (09.48" E	Dis	+ 6,	146.6	1	
:	Curve Date									
Curve CUR_1 P.I. Static Delta Degree Tangent Length Radius External Long Chord	on = 1° = 2° = = =	20′ 1 51′ 5	69.96 6.28" 3.24" 23.35 46.70	N (RT)	8,	468,	606.	79 E		-1,669,023.39
Mid. Ord. P.C. Static P.T. Static C.C. Back Ahead Chord Bear	= on on = S 30° (= S 28° 4	71+ 03′09. 42′53.	0.14 46.61 93.31 48" E 20" E 34" E	N N N	8,	468, 468, 467,	586.	32 E		-1,669,035.09 -1,669,012.18 -1,670,766.22
Course from	PT CUR_1 - Curve Data	a	UR_2 S	28°	42′ 53.	20"	E Di	s† 82	6.11	
Curve CUR_2 P.I. Station Delta Degree Tangent Length Radius External Long Chord	= 1° = 2° = = = = = =	09′4 51′5	3.24" 20.27 40.54 00.00 0.10 40.54	N (RT)	8,	467,	844.	02 E		-1,668,605.53
Mid. Ord. P.C. Static P.T. Static C.C. Back Ahead Chord Bear	on = S 28° 4 = S 27° 3	80+ 42′53. 33′12.	0.10 19.42 59.96 20" E 48" E 84" E	N N N	8,	467, 467, 466,	826.	05 E		-1,668,615.27 -1,668,596.16 -1,670,369.32
Course from	PT CUR_2 -	to 002	S 27°	33′ 1	12.48" E	E Dis	+ 83	1.31		
Point 002		N	8,467,	089.0	03 E	-1,6	68,2	11.61	Sta	88+91.27

Ending chain DARRINGTON_CL description



DARRINGTON RD HORIZONTAL ALIGNMENT DATA SHEET



7707/	\CADD\SWP3\WA4_DAR-G-EPIC.dgn
ί	FILE:

Ι.	STORMWATER POLLUTION F	PREVENTION-CLEAN WATER	ACT SECTION 402	111.	CULTURAL RESOURCES
	required for projects with	r Discharge Permit or Constr 1 or more acres disturbed so for erosion and sedimentati	oil. Projects with any		Refer to TxDOT Standard Specifical archeological artifacts are found archeological artifacts (bones, but
		may receive discharges from ed prior to construction act	· · ·		work in the immediate area and con ✓ No Action Required
	1.				
	2.				Action No.
	☐ No Action Required	X Required Action			1.
	Action No.				2.
	1. Prevent stormwater pollu accordance with TPDES Pe	ution by controlling erosion ermit TXR 150000	and sedimentation in		3.
	2. Comply with the SW3P and required by the Engineer	d revise when necessary to co	ontrol pollution or		4.
		Notice (CSN) with SW3P inform the public and TCEQ, EPA or		IV.	VEGETATION RESOURCES Preserve native vegetation to the
		specific locations (PSL's) submit NOI to TCEQ and the			Contractor must adhere to Construction 164, 192, 193, 506, 730, 751, 752 invasive species, beneficial land
11.	. WORK IN OR NEAR STRE ACT SECTIONS 401 AND	AMS, WATERBODIES AND WI	ETLANDS CLEAN WATER		
		filling, dredging, excavati			Action No.
		eks, streams, wetlands or we e to all of the terms and co			1.
	the following permit(s):				2.
					3.
	No Permit Required	PCN not Required (less than	1/10th gara waters or		
	wetlands affected)	Tell flot Required Cress finding	1710111 doile waters of		4.
	☐ Nationwide Permit 14 -	PCN Required (1/10 to <1/2	acre, 1/3 in tidal waters)		
	☐ Individual 404 Permit F	Required		٧.	FEDERAL LISTED, PROPOSED TH
	Other Nationwide Permit	Required: NWP#			CRITICAL HABITAT, STATE LIS
		ers of the US permit applies Practices planned to control			No Action Required
					Action No.
	1.				ACTION NO.
	2.				1.
	3.				2.
	4.				3.
		ary high water marks of any ers of the US requiring the			4.
				1	any of the listed species are obse
	Best Management Practic	Sedimentation	Post-Construction TSS	1	o not disturb species or habitat and ork may not remove active nests from
	Temporary Vegetation	Silt Fence	Vegetative Filter Strips	1	esting season of the birds associate re discovered, cease work in the imm
	Blankets/Matting	Rock Berm	Retention/Irrigation Systems	1	ngineer immediately.
	Mulch	☐ Triangular Filter Dike	Extended Detention Basin		
	Sodding	Sand Bag Berm	Constructed Wetlands		LIST OF ABBR
	☐ Interceptor Swale	Straw Bale Dike	Wet Basin	BMP:	Best Management Practice
	Diversion Dike	☐ Brush Berms	Erosion Control Compost	CGP:	Construction General Permit Texas Department of State Health Services
	Erosion Control Compost	Erosion Control Compost	Mulch Filter Berm and Socks	FHWA:	Federal Highway Administration Memorandum of Agreement
	Mulch Filter Berm and Socks	☐ Biodeg Erosion Ctrl Logs	Compost Filter Berm and Socks	MOU:	Memorandum of Understanding
	Compost Filter Berm and Sock	S Compost Filter Berm and Sock		MBTA:	Municipal Separate Stormwater Sewer System Migratory Bird Treaty Act
		Stone Outlet Sediment Traps	Sand Filter Systems		Notice of Termination Nationwide Permit
		Sediment Basins	Grassy Swales	I NOT-	Notice of Intent

SOURCES Standard Specifications in the event historical issues or artifacts are found during construction. Upon discovery of artifacts (bones, burnt rock, flint, pottery, etc.) cease mmediate area and contact the Engineer immediately. Required Action on Required RESOURCES ve vegetation to the extent practical. st adhere to Construction Specification Requirements Specs 162, 506, 730, 751, 752 in order to comply with requirements for ies, beneficial landscaping, and tree/brush removal commitments. on Required Required Action TED. PROPOSED THREATENED. ENDANGERED SPECIES. ABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES RY BIRDS. n Required Required Action sted species are observed, cease work in the immediate area. pecies or habitat and contact the Engineer immediately. The ove active nests from bridges and other structures during the birds associated with the nests. If caves or sinkholes cease work in the immediate area, and contact the LIST OF ABBREVIATIONS

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Comply with the Hazard Communication Act (the Act) for personnel who will be working with

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

 No ☐ Yes

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

☐ No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required	Required Action
Action No.	
1.	

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required

Required Action

Action No.

SPCC: Spill Prevention Control and Countermeasure

Texas Carmission on Environmental Quality

TPDES: Texas Pollutant Discharge Elimination System

Texas Parks and Wildlife Department

SW3P: Storm Water Pollution Prevention Plan

Pre-Construction Notification

Project Specific Location

TxDOT: Texas Department of Transportation

T&E: Threatened and Endangered Species USACE: U.S. Army Corps of Engineers USFWS: U.S. Fish and Wildlife Service

PCN:

TCFQ:

Stormwater Sewer System TPWD:

12/20/2022


Texas Department of Transportation

ENVIRONMENTAL PERMITS. ISSUES AND COMMITMENTS EPIC

ILE: epic.dgn	DN: Tx[OT	ск: RG	DW: VP		ck: AR
CTxDOT: February 2015	CONT	SECT	JOB			HIGHWAY
REVISIONS 2-12-2011 (DS)	0924	06	644		DARRINGTON	
5-07-14 ADDED NOTE SECTION IV.	DIST		COUNTY			SHEET NO.
1-23-2015 SECTION [(CHANGED ITEM 1122 O ITEM 506, ADDED GRASSY SWALES.	ELP		EL PA	S0		10

DARRINGTON RD. EXISTING SPEED LIMIT

EXISTING SPEED ZONE 40 MPH



AVE

AVE

LEGEND

TRAFFIC FLOW ARROW

WORK ZONE

NOTES:

- 1. FIELD CONDITION MAY DICTATE ADJUSTMENT OF SIGN LOCATIONS.
 CONTRACTORS SHALL OBTAIN APPROVAL FROM THE ENGINEER
 PRIOR TO INSTALLATION OF ANY SIGNS.
- 2. REFER TO TRAFFIC CONTROL STANDARD SHEETS FOR OTHER REGULATORY AND WARNING SIGNS.
- 3. ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21, AND TMUCTD FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENT.
- COORDINATE WITH ONGOING CONSTRUCTION PROJECTS PRIOR TO SETTING UP LANE CLOSURES AND BEGINNING WORK ON ANY ROADWAY.
- 5. DO NOT STORE ANY EQUIPMENT OR STOCKPILE ANY MATERIAL ON THE OPPOSITE DIRECTION OF THE WORK OR ON THE LANE CLOSURE.

- 6. COVER DRILL SHAFT HOLES DURING NON-WORKING/OVERNIGHT HOURS.
- 7. COVER CONFLICTING INTERMEDIATE SPEED LIMIT SIGNS.
- 8. CONTRACTOR SHALL COORDINATE WITH NEARBY SCHOOLS AND LANE CLOSURES SHALL BE RESTRICTED TO OFF PEAK HOURS 9 AM TO 4 PM, M-F, OR NIGHTS 9 PM TO 6 AM, SUNDAY-THURSDAY.
- 9. REFER TO TCP (2-4a) & (2-6a) STANDARDS FOR ADDITIONAL INFORMATION ONLY.




TRAFFFIC CONTROL PLAN
NARRATIVE



Λ Τ	KI	NS TBPE REG.	# F-474
*			©

TYPE OF WORK	STANDARD SHEET	SHEET DESCRIPTION	SHEET	DIAGRAM DESCRIPTION	SUGGESTED USE
ILLUMINATION INSTALLATION		TRAFFIC CONTROL PLAN	SHEET 2 OF 2	WORK ZONE TYPICAL DETAILS	ONE CLOSURE IN BOTH DIRECTIONS WHEN INSTALLING LIGHTS ON THE OUTSIDE OF THE ROADWAY.
ILLUMINATION INSTALLATION AND REMOVAL	WZ (BTS 2)-13	TRAFFIC SIGNAL WORK BARRICADES AND SIGNS	WZ(BTS-2)-13	SIDEWALK DETOUR CROSSWALK CLOSURES	CONTRACTOR SHALL USE WZ (BTS-2)-13 WHEN ILLUMINATION CONSTRUCTION ACTIVITIES REQUIRE SIDEWALK CLOSURES WITH SIDEWALK DETOURS (ONLY DAILY AND OPEN BACK TO PEDESTRIAN TRAFFIC).



NOTES:

- APPLY TRAFFIC CONTROL PLAN AS DESCRIBED IN THE TCP SELECTION TABLE FOR DARRINGTON RD, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- COORDINATE WITH ONGOING CONSTRUCTION PROJECTS PRIOR TO SETTING UP LANE CLOSURES AND BEGINNING WORK ON ANY ROADWAY.
- 3. LIMIT WORK ZONE TO ONE (1) MILE LENGTHS, UNLESS OTHERWISE DIRECTED.
- 4. LANE CLOSURES WITHIN TOWN OF HORIZON CITY LIMITS SHALL BE RESTRICTED TO NON-PEAK OR NIGHT TIME HOURS. NON-PEAK HOURS ARE DEFINED AS MONDAY-FRIDAY FROM 9 A.M. TO 4 P.M. NIGHT TIME HOURS ARE DEFINED AS SUNDAY-THRUSDAY FROM 9 P.M. TO 6 A.M., UNLESS OTHERWISE DIRECTED.
- 5. CONRACTOR SHALL NOT STORE ANY EQUIPMENT OR STOCKPILE ANY MATERIAL ON THE OPPOSITE DIRECTION OF THE WORK OR ON THE LANE CLOSURE.
- 6. TCP DETAIL SHOWN TO BE APPLIED AT RIGHT LANE ON DARRINGTON RD.

	LEGEND										
	TYPE 3 BARRICADE		CHANNELIZING DEVICES								
	HEAVY WORK VEHICLE ATTENUATER (TMA)		TRUCK MOUNTED								
	TRAILER MOUNTED FLASHING ARROW BOARD	M	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)								
•	SIGN	J	TRAFFIC FLOW								
\Diamond	FLAG		FLAGGER								



TRAFFIC CONTROL PLAN

WORK ZONE TYPICAL DETAILS



Texas Department of Transportation											
CONT	SECT	JOB HIGHWAY									
0924	06	644	DARRINGTON								
DIST		COUNTY		SHEET NO.							
ELP		EL PASO		12							

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov

COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)

MATERIAL PRODUCER LIST (MPL)

ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)'

STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)

TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)

TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 10

Traffic Safety Division Standard



Texas Department of Transportation


BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS

BC(1)-21

E: bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT		
TxDOT November 2002	CONT	SECT	JOB		н	IGHWAY		
REVISIONS -03 7-13 -07 8-14	0924	06	644		DARF	DARRINGTON		
	DIST		SHEET NO.					
-10 5-21	ELP		EL PAS	50		13		

6:04:00

12/20/2022



- \sharp May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer.
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK"(G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- 4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- 5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- 6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

BEGIN T-INTERSECTION \times \times G20-9TP ZONE ★ R20-5T FINES DOLIBL ★ R20-5aTP WHEN WORKERS ARE PRESENT ROAD WORK <⇒ NEXT X MILES FND * X G20-25T WORK ZONE G20-1bT INTERSECTED 1000'-1500' 1 Block - City - Hwy 1000'-1500' - Hwy 1 Block - City ROADWAY \Rightarrow ROAD WORK G20-1bTR NEXT X MILES ⇒ 80' Limit WORK ZONE G20-2bT * * BEGIN WORK \times \times G20-9TP ZONE TRAFFI G20-6T \times \times R20-5T FINES DOUBLE ★ ★ R20-5aTP ROAD WORK G20-2

CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING 1,5,6

SIZE

Sign onventional Expressway. Number Freeway or Series CW201 CW21 48" × 48' CW22 48" x 48" CW23 CW25 CW1, CW2, CW7. CW8. 48" x 48' 36" × 36" CW9, CW11 CW14 CW3, CW4, CW5, CW6, 48" x 48" 48" x 48' CW8-3, CW10, CW12


Posted Speed	Sign∆ Spacing "X"	
MPH	Feet (Apprx.)	
30	120	
35	160	
40	240	
45	320	
50	400	
55	500 ²	
60	600 ²	
65	700 ²	
70	800 ²	
75	900 ²	
80	1000 ²	

SPACING

- * For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- \triangle Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS

★ ★G20-9TP ZONE STAY ALERT OBEY SPEED ROAD WORK TRAFFIC **X X** G20-5T ROAD LIMIT ROAD ROAD ¥ ¥R20-5T FINES SIGNS WORK CLOSED R11-2 WORK DOUBLE STATE LAW ⅓ MILE TALK OR TEXT LATER AHEAD \times \times R20-5aTF Type 3 $\times \times G20-6T$ R20-3 R2-1 Barricade or CW20-1D CW13-1P CONTRACTOR CW20-1E channelizing devices \triangleleft -CSJ Limi Channelizing \Rightarrow B SPEED R2-1 END ROAD WORK LIMIT END WORK ZONE G20-25T * G20-2 * *

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer

- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2b) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double workers are present.
- imes CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at the end of the work zone.

	LEGEND							
Ι	Type 3 Barricade							
000 Channelizing Devices								
4	Sign							
Х	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.							

SHEET 2 OF 10



Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE: bc-2	1.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ck: TxD0
	mber 2002	CONT	SECT	JOB		н	IGHWAY
REV	ISIONS	0924	06	644		DARF	RINGTON
9-07 8-14		DIST		COUNTY			SHEET NO.
7-13 5-2		ELP		EL PAS	SO		14

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:

40 mph and greater 0.2 to 2 miles

35 mph and less

- 0.2 to 1 mile
- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- 6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 10




Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

:	bc-21.dgn	DN: TxDOT		ck: TxDOT Dw:		TxD01	CK: TXDOT	
TxDOT	November 2002	CONT	SECT	JOB		1	HIGHWAY	
9-07 7-13	REVISIONS 8-14 5-21	0924	06	644		DARRINGTON		
		DIST	COUNTY				SHEET NO.	
		ELP		EL PAS		15		




* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb.

Objects shall NOT be placed under skids as a means of leveling.

* * When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane.

Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

OR SIDE ELEVATION


Wood

Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT
be allowed.
Each sign
shall be attached
directly to the sign
support. Multiple
signs shall not be
joined or spliced by
any means. Wood
supports shall not be
extended or repaired
by splicing or
other means.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
 STOP/SLOW paddles shall be retroreflectorized when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING RE	QU I REMEN	TS (WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{fl} OR C _{fl} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- 1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- 3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- . If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- 1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- 2. Wooden sign posts shall be painted white.
- 3. Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and
 guide the traveling public safely through the work zone.
- 5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the IMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDDT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- 6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- 8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- 1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- b. Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
- c. Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
- d. Short, duration work that occupies a location up to 1 hour.
- e. Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- 1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- 2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground
- the ground.
 3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Lona-term/Intermediate sign height.
- 5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

l. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
 "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- 3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- 2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- 3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL} , shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
 Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any
- intersections where the sign may be seen from approaching traffic.

 3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- covered when not required.

 4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- 5. Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
 Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

Where sign supports require the use of weights to keep from turning over, the use
of sandbags with dry, cohesionless sand should be used.
 The sandbags will be tied shut to keep the sand from spilling and to maintain a

- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- 3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights
- for use as sign support weights.
 Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
 Sandbags shall be made of a durable material that tears upon vehicular
- impact. Rubber (such as tire inner tubes) shall NOT be used.
 Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured
- with rubber bases may be used when shown on the CWZTCD list.
 7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

 Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face. SHEET 4 OF 10



BARRICADE AND CONSTRUCTION

Traffic Safety Division Standard

BC (4) -21

TEMPORARY SIGN NOTES




12/20/2022 6:04:19

Welds to start on

opposite sides going in opposite directions. Minimum weld, do not

back fill puddle.




-2" x 2"

12 ga.

SINGLE LEG BASE

upright

Post ∠ Post Post max. desirable max. desirable 34" min. in Optional strong soils, 48" reinforcing 55" min. in minimur sleeve -34" min. in weak soils. (1/2" larger strona soils than sian 55" min. in post) x 18' weak soils. Anchor Stub Anchor Stub (1/4" larger (1/4" larger than sign than sign post) post) OPTION 2 OPTION 1 OPTION 3 (Anchor Stub) (Direct Embedment) (Anchor Stub and Reinforcing Sleeve)) PERFORATED SQUARE METAL TUBING




GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support.

The maximum sign square footage shall adhere to the manufacturer's recommendation.

Two post installations can be used for larger signs.



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE
AND SHORT TERM SUPPORTS CAN BE FOUND ON THE
CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- . No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
 - See BC(4) for definition of "Work Duration."
- $\times\!\!\!\times$ Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 10



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE: bc-21.dgn	DN: T	×DOT	ck: TxDOT	DW:	TxDOT	ck: TxDO
ℂTxDOT November 20	02 CONT	SECT	JOB		ніс	GHWAY
REVISIONS	092	06	644		DARR	INGTON
9-07 8-14	DIST		COUNTY			SHEET NO.
7-13 5-21	ELP		EL PASO			17

SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32′

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message. 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" $^{\circ}$
- on a PCMS. Drivers do not understand the message
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S SPD
Express Lane	EXP LN	Speed	ST
Expressway	EXPWY	Street	SUN
XXXX Feet	XXXX FT	Sunday	
Fog Ahead	FOG AHD	Telephone	PHONE TEMP
Freeway	FRWY, FWY	Temporary	THURS
Freeway Blocked	FWY BLKD	Thursday	
Friday	FRI	To Downtown Traffic	TO DWNTN
Hazardous Driving			
Hazardous Material		Travelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour (s)	HR. HRS	Vehicles (s)	VEH, VEHS
Information	INFO	Warning	WARN
It Is	ITS	Wednesday	WED
Junction	JCT	Weight Limit	WT LIMIT
Left	LFT	Wes†	W
Left Lane	LFT LN	Westbound	(route) W
Lane Closed	LN CLOSED	Wet Pavement	WET PVMT
Lower Level	LWR LEVEL	Will Not	WONT
Maintenance	MAINT		

Roadway

designation # IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp	o Closure List	Other Cond	lition List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD	RIGHT LN	RIGHT LN	TWO-WAY
CLSD AT	CLOSED	NARROWS	TRAFFIC
FM XXXX	XXX FT	XXXX FT	XX MILE
RIGHT X	RIGHT X	MERGING	CONST
LANES	LANES	TRAFFIC	TRAFFIC
CLOSED	OPEN	XXXX FT	XXX FT
CENTER	DAYTIME	LOOSE	UNEVEN
LANE	LANE	GRAVEL	LANES
CLOSED	CLOSURES	XXXX FT	XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS	EXIT XXX	ROADWORK	ROADWORK
LANES	CLOSED	PAST	NEXT
CLOSED	X MILE	SH XXXX	FRI-SUN

EXIT RIGHT LN
TO BE
CLOSED

MALL X LANES

DRIVEWAY

CLOSED

XXXXXXX BLVD

CLOSED

X LANES CLOSED TUE - FRI

TRAFFIC SIGNAL XXXX FT

BUMP

XXXX FT

★ LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

	/Effect on Travel .ist	Location List	Warning List	* * Advance Notice List
MERGE RIGHT	FORM X LINES RIGHT	FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- XX X PM-X AM
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
REDUCE SPEED XXX FT	END SHOUL DER USE		DRIVE WITH CARE	NEXT TUE AUG XX
USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM- XX AM
STAY IN LANE	*	* * S	ee Application Guidelin	es Note 6.

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary.
- 7. FT and MI, MILE and MILES interchanged as appropriate.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4)

PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

US XXX

FXIT

X MILES


LANES

SHIFT

FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 10



Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21

	FILE:	bc-21.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxD01	ГС	k: TxDOT
	© TxDOT	November 2002	CONT	SECT JOB			HIGHWAY		
		REVISIONS	0924	06	644		DAR	RIN	NGTON
	9-07 8-14 7-13 5-21		DIST		COUNTY			SH	EET NO.
			ELP	EL PASO					18


6:04:35

- 1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of pregualified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- 4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10.Missing or damaged Barrier Reflectors shall be replaced as directed
- 11. Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacina of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)




DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- 5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- 2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- 3. The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- 4. The Flashing Arrow Board should be able to display the following symbols:



- 5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- 8. Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- 9. The sequential arrow display is NOT ALLOWED.
 10. The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.

- 11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
 12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
 13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- 14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

	REQUIREMENTS								
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE						
В	30 × 60	13	3/4 mile						
С	48 × 96	15	1 mile						

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimmina devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

TRUCK-MOUNTED ATTENUATORS

- 1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted n the plans
- 5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- 6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC(7) - 21

FILE:	bc-21.dgn	DN: T	OOT	ck: TxDOT	DW:	TxD0	T	ck: TxDOT
© TxD0T	November 2002	CONT	SECT	JOB		HIGHWAY		HWAY
	REVISIONS 8-14 5-21	0924	06	644	644 DAF		RRINGTON	
9-07 7-13		DIST	COUNTY			SHEET NO.		SHEET NO.
		ELP	EL PASO					19

1. For long term stationary work zones on freeways, drums shall be used as

- the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

GENERAL NOTES

Pre-qualified plastic drums shall meet the following requirements:


- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- 3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10.Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- 3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.





DETECTABLE PEDESTRIAN BARRICADES

- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- 2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian
- 5. Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sian (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24" Vertical Panel mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.

- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FI} or Type C_{FI} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- 3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- 5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each
- 6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- 8. R9-9. R9-10. R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 10




Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

E: bc-21.dgn	DN: TxDOT		CK: TxDOT DW:		TxDOT	ck: TxDOT
TxDOT November 2002	CONT SECT JOB		H	HIGHWAY		
REVISIONS -03 8-14	0924	06	644		DARR	INGTON
-03 8-14 -07 5-21	DIST		COUNTY			SHEET NO.
-13	ELP		EL PAS	50		20


6:04:49






- 1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- 4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- 5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List"
- 6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- 7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42"
- 3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black nonreflective legend. Sheeting for the OTLD shall be retroreflective Type $B_{\mathsf{FL}}\,\mathsf{or}\,\mathsf{Type}\,\,C_{\mathsf{FL}}\,\mathsf{conforming}$ to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the out side of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type Bri or Type Cri conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

36

Fixed Base w/ Approved Adhesive

(Driveable Base, or Flexible

Support can be used)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- 1. Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	D	Desirable Taper Lengths X X			Suggested Maximum Spacing of Channelizing Devices		
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	2	150′	165′	180′	30′	60′		
35	$L = \frac{WS^2}{60}$	205′	225′	245′	35′	70′		
40	60	265′	295′	320′	40′	80′		
45		450′	495′	540′	45′	90′		
50		500′	550′	600′	50′	100′		
55	L=WS	550′	605′	660′	55′	110′		
60		600′	660′	720′	60′	120′		
65		650′	715′	780′	65′	130′		
70		700′	770′	840′	70′	140′		
75		750′	825′	900′	75′	150′		
80		800′	880′	960′	80′	160′		

 $X \times Y$ Taper lengths have been rounded off. L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 10



Texas Department of Transportation

BARRICADE AND CONSTRUCTION

Traffic Safety Division Standard

DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO CONT SECT JOB C)TxDOT November 2002 HIGHWAY 0924 06 644 DARRINGTON 7-13 5-21


BC(9)-21

CHANNELIZING DEVICES


6:04:54

TYPE 3 BARRICADES

- 1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- 4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1"
- Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- Warning lights shall NOT be installed on barricades.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION

Two-Piece cones

1. Where positive redirectional capability is provided, drums may be omitted. 2. Plastic construction fencing may be used with drums for safety as required in the plans. 3. Vertical Panels on flexible support may be substituted for drums when the Typica shoulder width is less than 4 feet. Plastic Drum 4. When the shoulder width is greater than 12 feet, steady-burn lights PERSPECTIVE VIEW may be omitted if drums are used. 5. Drums must extend the length These drums are not required of the culvert widening. on one-way roadway LEGEND Plastic drum Plastic drum with steady burn liah work or vellow warnina reflector um of two dru across the v teady burn warning light or yellow warning reflector $\left\langle \cdot \right\rangle$ Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 A mi be u and maximum of 4 drums)

CONES _ 4" min. orange 2" min. 4" min. white 2" min. 4" min. orange 2" min. 2" min 4" min. white 42' min. 28' min.

4" min.


PLAN VIEW

2" to 6

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

One-Piece cones

Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- 1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- 2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base. or ballast, that is added to keep the device upright and in place.
- 3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- 7. Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 10



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

Traffic Safety Division Standard

BC(10)-21

ILE:	bc-21.dgn	DN: T>	(DOT	ck: TxDOT	DW:	TxDO	T CK: TxD0	ЭТ
TxDOT	November 2002	CONT	SECT	JOB			HIGHWAY	
	REVISIONS	0924	06	644		DAF	RRINGTO	N
9-07	8-14	DIST		COUNTY			SHEET NO.	
7-13	5-21	ELP		EL PAS	50		22	

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOI for any purpose whatsoever. TxDOI assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. WORK AHEAD CW20-1D 48" X 48" (Flags-See note 1) $\nabla |\nabla$ END WORK ROAD WORK AHEAD LANE CW20-1D 48" X 48" (Flags-See note 1) G20-2 48" X 24" CLOSED CW20-5T XXX FT CW16-3aP 30" X 12" (See note 4) X for 50 MPH or less 3X for over 50 MPH CW1-6aT 36" X 3 Shadow Vehicle with TMA and (See note 8) high intensity rotating, flashing, oscillating or strobe lights. (See notes 5 & 6) Shadow Vehicle with— TMA and high intensity rotating, flashing, oscillating or strobe lights. (See notes 5 & 6) RIGHT LANE CLOSED CW20-5TR 48" X 48' XXX FT CW16-3aP 30" X 12" (See note 4) END ROAD WORK END \bigcirc ROAD G20-2 48" X 24" ROAD WORK WORK G20-2 48" X 24' AHEAD CW20-1D (Flags-See note 12/20/2022 6:05:05 TCP (2-4a) TCP (2-4b) ONE LANE CLOSED TWO LANES CLOSED

	LEGEND							
	Type 3 Barricade		Channelizing Devices					
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)					
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)					
-	Sign	♡	Traffic Flow					
\Diamond	Flag		Flagger					

Posted Speed	Formula	Desirable Taper Lengths ***		Spacir Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	
*		10′ Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	ws ²	150′	165′	180′	30′	60′	120′	90′
35	L = WS	205′	225′	245′	35′	70′	160′	120′
40	80	265′	295′	320′	40′	80′	240′	155′
45		450′	495′	540′	45′	90′	320′	195′
50		500′	550′	600′	50′	100′	400′	240′
55	L=WS	550′	605′	660′	55′	110′	500′	295′
60	L 113	600′	660′	720′	60′	120′	600′	350′
65		650′	715′	780′	65′	130′	700′	410′
70		700′	770′	840′	70′	140′	800′	475′
75		750′	825′	900′	75′	150′	900′	540′

* Conventional Roads Only

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

		TYPICAL L	ISAGE	
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		1	✓	

GENERAL NOTES

CW13-1P 24" X 24

CW1-6aT

CW1-4L

XX MPH

RIGHT LANE

CLOSED

ROAD

WORK

AHEAD

48" X 48"

CW13-1P

CW20-5TR 48" X 48

note 4)

CW20-1D 48" X 48" (Flags-See note 1

XXX FT CW16-3aP 30" X 12"

X 36'

END ROAD WORK G20-2 48" X 24"

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- 4. For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

7. If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

TCP (2-4b)

8. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.




Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
LANE CLOSURES ON MULTILANE
CONVENTIONAL ROADS

TCP(2-4)-18

FILE: tcp2-4-18.dgn	DN:		CK:	DW:	CK:
◯TxDOT December 1985	CONT	SECT	JOB		HIGHWAY
REVISIONS 8-95 3-03	0924	06	644	DA	RRINGTON
1-97 2-12	DIST		COUNTY		SHEET NO.
4-98 2-18	ELP		EL PAS	SO	23

64





	LEGEND							
	Type 3 Barricade		Channelizing Devices					
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)					
F	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)					
•	Sign	⟨→	Traffic Flow					
\Diamond	Flag	LO	Flagger					

Posted Speed	Formula	Minimum Desirable Taper Lengths ***			Spacir Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30		150′	165′	180′	30′	60′	120′	90′
35	L = WS	205′	225′	245'	35′	70′	160′	120′
40	80	265′	295′	320′	40′	80′	240′	155′
45		450′	495′	540′	45′	90′	320′	195′
50		500′	550′	600′	50′	100′	400′	240′
55	L=WS	550′	605′	660′	55′	110′	500′	295′
60	L-W3	600′	660′	720′	60′	120′	600′	350′
65		650′	715′	780′	65′	130′	700′	410′
70		700′	770′	840′	70′	140′	800′	475′
75		750′	825′	900′	75′	150′	900′	540′

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH

		TYPICAL L	ISAGE	
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- . Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on everyother channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
- The placement of pavement markings may be omitted on Intermediate-term stationary work zones with the approval of the Engineer.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

TCP(2-6)-18

FILE:	tcp2-6-18.dgn	DN:		CK:	DW:		CK:
© TxD0T	December 1985	CONT	SECT	JOB		ΗI	GHWAY
2-94 4-9	REVISIONS	0924	06	644		DARR	INGTON
8-95 2-	-	DIST		COUNTY			SHEET NO.
1-97 2-	18	ELP		EL PA:	SO.		24

GENERAL NOTES FOR WORK ZONE SIGNS

Wooden sign posts shall be painted white.

directed by the Engineer.

DURATION OF WORK

SIGN MOUNTING HEIGHT

REMOVING OR COVERING

approved by the Engineer.

shown on Figure 6F-2 of the TMUTCD.

Barricades shall NOT be used as sign supports.

4. Nails shall NOT be used to attach signs to any support.

Signs shall be installed and maintained in a straight and plumb condition.

All signs shall be installed in accordance with the plans or as

Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as

Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).

The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.

Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".

Work zone durations are defined in Part 6, Section 66.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).


Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise

When signs are covered, the material used shall be opaque, such

Sign height of Short-term/Short_Duration warning signs shall be as



TYPICAL ADVANCE SIGNAL PROJECT SIGNING

FOR LONG TERM and INTERMEDIATE-TERM STATIONARY WORK OPERATIONS

SIGN SUPPORT WEIGHTS

- The sandbaas will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects will not be
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbaas shall be made of a durable material that tears upon
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fastners. Sandbags shall be placed along the length of the skids to weigh down the
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

	LEGEND
•	Sign
	Channelizing Devices
V////	Type 3 Barricade

DEPARTMENTAL MATERIAL	SPECIFICATIONS
SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
WHITE	BACKGROUND	TYPE A SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:

http://www.txdot.gov/txdot_library/publications/construction.htm

REFLECTIVE SHEETING

All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

warning sign spacing.

4. Warning sign spacing shown is typical for both

5. See the Table on sheet 1 of 2 for Typical

- Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
- permitted for use as sign support weights.
- vehicular impact. Rubber, such as tire inner tubes, shall not be used.

DEPARTMENTAL MATERIAL	SPECIFICATIONS
SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

When crosswalks or other pedestrian facilities are closed or relocated. temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.

SHEET 2 OF 2

Texas Department of Transportation

TRAFFIC SIGNAL WORK BARRICADES AND SIGNS

WZ(BTS-2)-13

Operation Division Standard

CW2OSG-

|| ↔

 $| \Diamond | \Diamond$

R9-11L


SIGNA


WORK


<>>

₹>

FILE: wzbts-13.dgn	DN: To	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
©⊺xDOT April 1992	CONT	SECT	JOB		ніс	SHWAY
REVISIONS	0924	06	644		DARRINGTON	
2-98 10-99 7-13	DIST		COUNTY			SHEET NO.
4-98 3-03	ELP		EL PAS	50		25







SIDEWALK DIVERSION

4′ Min.(See Note 7 below

SIDEWALK CLOSE

Temporary Traffic Barrier

See Note 4 below

10' Min.


 $\Diamond \| \Diamond$

♡ | ☆

 \Diamond

₹>

See Note 6



R9-11aR

PEDESTRIAN CONTROL

USE OTHER SIDE

Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.

CW2OSG-

"CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic

substrates, they may be mounted on top of a plastic drum at or near the location shown.

For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9) and manufacturer's recommendations.


Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.

Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.

The width of existing sidewalk should be maintained if practical. Pavement markings for mid-block crosswalks shall be paid for under the

appropriate bid items.

115



CON	CONDUIT, CONDUCTOR & CABLE SCHEDULE								
		CONDU	SHEET IT	1 O NUME		CONDUC	CTORS		
		ITEM SIZE/ COND	618 TYPE OUIT		ITEM ELECT CONDU	RICAL CTORS			
	SN.	TRENCH	BORED				RUN		
RUN NO.	CONDUIT STATUS	PVC SCHD 40 (2")	PVC SCHD 40 (2") (BORE)	CABLE STATUS	##NO.10 XHHW (INSULATED) (GROUND)	##NO.10 XHHW (INSULATED) (POWER)	LENGTH OF	RUN NO.	
1	I	1		I	1	2	275	1	
2	I	1		I	1	2	225	2	
3	I	1		I	1	2	10	3	
4	I		1	I	1	2	60	4	
5	I	1		I	1	2	245	5	
6	I	1		I	1	2	75	6	
TOTAL	I	830	60		920	1840		TOTAL	

STATUS: I = INSTALL ## INCLUDES 5 FT SLACK PER CABLE

IT	EM	DESCRIPTION
110	6003	EXCAVATION (SPECIAL)
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)
610	6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED
618	6023	CONDT (PVC) (SCH 40) (2")
618	6024	CONDT (PVC) (SCH 40) (2") (BORE)
620	6006	ELEC CONDR (NO.10) INSULATED

WARNING OVERHEAD POWER LINES

ILLUMINATION SUMMARY

CONTRACTOR SHALL COORDINATE WITH FERCO (LUIS JIMENEZ CELL# 915-472-3864
EMAIL: LUIS.Jimenez@epelectric.com) PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT
ARE TO BE PERFORMED BELOW POWER LINES FOR PROTECTIVE SLEEVE(S) TO
COVER ENERGIZED LINES AND AVOID ANY INJURY FOR CONSTRUCTION
PERSONNEL SAFETY.

EXISTING UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE INTENDED TO ILLUSTRATE THAT THEY ARE PRESENT. CONTRACTOR SHALL POTHOLE APPARENT UTILITY CONFLICTS AT INTERVALS NO MORE THAN 300 FT. TO VERIFY LOCATION DEPTH.

WARNING ! BEFORE YOU DIG NOTE: CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION WITH ALL UTILITY COMPANIES, TxDOT: (915) 790-4245

UNIT QUANTITY

0.15

24

4

830

60

2760

CY

LF

EΑ

LF

LF

LF

- 1. THE CONTRACTOR SHALL CONFIRM ALL UTILITY DEPTHS AND LOCATIONS PRIOR TO EXCAVATION.
- 2. THE LOCATIONS OF ROADWAY ILLUMINATION POLES, GROUND BOXES AND ELECTRICAL SERVICE POLES SHOWN ON THESE PLANS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED TO ACCOMMODATE LOCAL CONDITIONS. EXACT LOCATION OF ROADWAY ILLUMINATION EQUIPMENT SHALL BE APPROVED BY THE ENGINEER IN THE FIELD.
- 3. THE CONTRACTOR HAS THE OPTION TO BORE AT THE CONTRACTOR'S DISCRETION AND CONVENIENCE WHEN AN ITEM CALLS FOR A TRENCH. THIS WORK WILL BE PAID AS A TRENCH CONDUIT INSTALLATION.
- 4. REFER TO THE ILLUMINATION CIRCUIT DIAGRAM FOR SYSTEM DETAILS.
- 5. REFER TO THE ELECTRICAL SERVICE DATA SHEET FOR ELECTRICAL SERVICE DESCRIPTION.
- 6. CONTRACTOR SHALL REPAIR THE EXISTING IRRIGATION SYSTEM, SIDEWALK AND CURB & GUTTER TO AN EQUAL OR BETTER CONDITION IF IT IS DAMAGED DURING CONSTRUCTION. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO CONDUIT AND ROADWAY ILLUMINATION POLE INSTALLATION.
- 7. CONTRACTOR SHALL VERIFY THAT ALL EXISTING SYSTEMS ARE FUNCTIONAL AFTER INSTALLATION OF CONDUIT AND ILLUMINATION. ANY NON-FUNCTIONING SYSTEMS AS A RESULT OF THIS INSTALLATION MUST BE REPAIRED TO AN EQUAL OR BETTER CONDITION BY THE CONTRACTOR. THIS WORK WILL BE SUBSIDIARY TO VARIOUS BID TTFMS
- 8. ROW IS SHOWN FOR INFORMATION ONLY.
- 9. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING ILLUMINATION INFRASTRUCTURE.
- 10.ALL PAVEMENT CUTS OR PAVEMENT DAMAGE WILL NEED TO BE REPAIRED/REPLACED PER TOWN OF HORIZON CITY PAVEMENT CUT ORDINANCE.
- 11. CONTRACTOR TO COORDINATE WITH CLINT ISD AND ESTRADA MIDDLE SCHOOL PRIOR TO COMMENCING PROJECT.
- 12. IN SITUATIONS WHERE AN ILLUMINATION POLE NEEDS TO BE ON TOP OF SIDEWALK, CONTRACTOR IS TO CONSTRUCT FOUNDATION FLUSHED WITH THE SIDEWALK. A MINIMUM SIDEWALK CLEAR AREA OF 3.5 FEET TO BE MAINTAINED WHEN ANY PORTION OF A POLE IS WITHIN THE SIDEWALK. THIS WORK WILL BE SUBSIDIARY TO PAY ITEM 416 6029.



LEGEND

EXISTING RDWY ILL ASSEMBLY TO REMAIN PROPOSED RDWY ILL ASSEMBLY 20T-4 (150W LED EQ)

PROPOSED ELECTRICAL SERVICE

EXISTING ELECTRICAL SERVICE

PROPOSED CONDUIT (TRENCHED)

POLE DESIGNATION

PROPOSED CONDUIT (BORE)

— EXISTING ROW

1B-2

PROPOSED GROUND BOX TY A (W/APRON)

POLE OR LUMINAIRE NO

CIRCUIT NO.

SERVICE NO.

EXISTING POWER SOURCE

CONDUIT RUN NUMBER

(X)



DARRINGTON RD ILLUMINATION PLAN


BEGIN TO STA 22+00



			IBPE REG. # F-474				
	↓ 。		©2022				
	=						
	exas De	epartment of	Transportation				
CONT	SECT	JOB	HIGHWAY				
0924	06	644	DARRINGTON				

FL PASO

26



- 1. THE CONTRACTOR SHALL CONFIRM ALL UTILITY DEPTHS AND LOCATIONS PRIOR TO EXCAVATION.
- 2. THE LOCATIONS OF ROADWAY ILLUMINATION POLES, GROUND BOXES AND ELECTRICAL SERVICE POLES SHOWN ON THESE PLANS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED TO ACCOMMODATE LOCAL CONDITIONS. EXACT LOCATION OF ROADWAY ILLUMINATION EQUIPMENT SHALL BE APPROVED BY THE ENGINEER IN THE FIELD.
- 3. THE CONTRACTOR HAS THE OPTION TO BORE AT THE CONTRACTOR'S DISCRETION AND CONVENIENCE WHEN AN ITEM CALLS FOR A TRENCH. THIS WORK WILL BE PAID AS A TRENCH CONDUIT INSTALLATION.
- 4. REFER TO THE ILLUMINATION CIRCUIT DIAGRAM FOR SYSTEM DETAILS.
- 5. REFER TO THE ELECTRICAL SERVICE DATA SHEET FOR ELECTRICAL SERVICE DESCRIPTION.
- 6. CONTRACTOR SHALL REPAIR THE EXISTING IRRIGATION SYSTEM, SIDEWALK AND CURB & GUTTER TO AN EQUAL OR BETTER CONDITION IF IT IS DAMAGED DURING CONSTRUCTION. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO CONDUIT AND ROADWAY ILLUMINATION POLE INSTALLATION.
- 7. CONTRACTOR SHALL VERIFY THAT ALL EXISTING SYSTEMS ARE FUNCTIONAL AFTER INSTALLATION OF CONDUIT AND ILLUMINATION. ANY NON-FUNCTIONING SYSTEMS AS A RESULT OF THIS INSTALLATION MUST BE REPAIRED TO AN EQUAL OR BETTER CONDITION BY THE CONTRACTOR. THIS WORK WILL BE SUBSIDIARY TO VARIOUS BID TTFMS
- 8. ROW IS SHOWN FOR INFORMATION ONLY.
- 9. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING ILLUMINATION INFRASTRUCTURE.
- 10. ALL PAVEMENT CUTS OR PAVEMENT DAMAGE WILL NEED TO BE REPAIRED/REPLACED PER TOWN OF HORIZON CITY PAVEMENT CUT ORDINANCE.
- 11. CONTRACTOR TO COORDINATE WITH CLINT ISD AND ESTRADA MIDDLE SCHOOL PRIOR TO COMMENCING PROJECT.
- 12. IN SITUATIONS WHERE AN ILLUMINATION POLE NEEDS TO BE ON TOP OF SIDEWALK, CONTRACTOR IS TO CONSTRUCT FOUNDATION FLUSHED WITH THE SIDEWALK. A MINIMUM SIDEWALK CLEAR AREA OF 3.5 FEET TO BE MAINTAINED WHEN ANY PORTION OF A POLE IS WITHIN THE SIDEWALK. THIS WORK WILL BE SUBSIDIARY TO PAY ITEM 416 6029.

0 25 50 100 200 SCALE: 1" = 100'

LEGEND

EXISTING RDWY ILL ASSEMBLY TO REMAIN

PROPOSED RDWY ILL ASSEMBLY 20T-4 (150W LED EQ)

PROPOSED ELECTRICAL SERVICE

EXISTING ELECTRICAL SERVICE

PROPOSED CONDUIT (TRENCHED)

PROPOSED CONDUIT (BORE)

POLE DESIGNATION

EXISTING ROW

1B-2

PROPOSED GROUND BOX TY A (W/APRON)

POLE OR LUMINAIRE NO

CIRCUIT NO.

SERVICE NO.

EXISTING POWER SOURCE

CONDUIT RUN NUMBER

 \bigcirc

(0)

(X)




DARRINGTON RD ILLUMINATION PLAN

STA 22+00 TO STA 34+00



©2022 Texas Department of Transportation						
CONT	SECT	SECT JOB HIGHWAY				
0924	06 644 DARRINGTON			RRINGTON		
DIST	COUNTY SHEET NO			SHEET NO.		
ELP	EL PASO			27		



I

375

I 1 2

1 2

2500 5000

SHEET 2 OF 6

CONDUIT

CONDUCTOR & CABLE SCHEDULE

NUMBER OF CONDUCTORS

365

295

125

30 14

1 2 80 13

11

15

TOTAL

* SIDEWALK REMOVAL SHALL BE SUBSIDIARY TO PAY ITEM 416 6029

STATUS: I = INSTALL ## INCLUDES 5 FT SLACK PER CABLE

2050

11 I

12 I

13 I

14 I


	ILLUMINATION SUMMARY							
IT	ЕМ	DESCRIPTION	UNIT	QUANTITY				
110	6003	EXCAVATION (SPECIAL)	CY	0.15				
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	30				
610	6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED	EA	5				
618	6023	CONDT (PVC) (SCH 40) (2")	LF	2050				
618	6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	375				
620	6006	ELEC CONDR (NO.10) INSULATED	LF	7500				

WARNING OVERHEAD POWER LINES CONTRACTOR SHALL COORDINATE WITH EPECO (LUIS JIMENEZ CELL# 915-472-3864 EMAIL: LUIS.]Imenez@epelectrio.com) PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT ARE TO BE PERFORMED BELOW POWER LINES FOR PROTECTIVE SLEEVE(S) TO COVER ENERGIZED LINES AND AVOID ANY INJURY FOR CONSTRUCTION PERSONNEL SAFETY.

EXISTING UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE INTENDED TO ILLUSTRATE THAT THEY ARE PRESENT. CONTRACTOR SHALL POTHOLE APPARENT UTILITY CONFLICTS AT INTERVALS NO MORE THAN 300 FT. TO VERIFY LOCATION DEPTH.

WARNING ! BEFORE YOU DIG NOTE: CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION WITH ALL UTILITY COMPANIES, TxDOT: (915) 790-4245

POLE 1A-6 STA 34+79.77, 52.5' LT INSTALL: IN RD IL (TY SA) 20T-4 (150W EQ) POLE 1A-8 STA 42+99.77, 52.5' LT INSTALL: IN RD IL (TY SA) 20T-4 (150W EQ) STA 38+89.77, 58.72' LT INSTALL: IN RD IL (TY SA) 20T-4 (150W EQ) Õ ⋖ DARRINGTON RD <1 (/ (1) 35+00 45+00 Ш Z \equiv \circ R -(10) -(6) ΔM \forall POLE 2C-7 STA 45+04.77, 53.3' RT INSTALL: IN RD IL (TY SA) STA 36+84.66, 52.5' RT INSTALL: WERP - POLE 2C-6 STA 40+94.86, 52.5' RT INSTALL: IN RD IL (TY SA) 20T-4 (150W EQ) IN RD IL (TY SA) 20T-4 (150W EQ) IN RD IL (TY SA) 20T-4 (150W EQ)



CONDUIT, CONDUCTOR & CABLE SCHEDULE SHEET 3 OF 6 CONDUIT NUMBER OF CONDUCTORS

		ITEM SIZE/ COND	TYPE		LELECT	620 RICAL CTORS		
	SN.	TRENCH	BORED				RUN	
RUN NO.	CONDUIT STATUS	PVC SCHD 40 (2")	PVC SCHD 40 (2") (BORE)	CABLE STATUS	##NO.10 XHHW (INSULATED) (GROUND)	##NO.10 XHHW (INSULATED) (POWER)	LENGTH OF RI	RUN NO.
1	I	1		I	1	2	80	1
2	I	1		I	1	2	410	2
3	I	1		I	1	2	410	3
4	I	1		I	1	2	300	4
5	I	1		I	1	2	285	5
6	I	1		I	1	2	265	6
7	I		1	I	1	2	90	7
8	Ι	1		I	1	2	50	8
9	I	1		I	1	2	410	9
10	Ť	1		T	1	2	Q.F.	10

90

2445 | 4890

TOTAL

2305 STATUS: I = INSTALL ## INCLUDES 5 FT SLACK PER CABLE

TOTAL

	ILLUMINATION SUMMARY							
ΙT	ЕМ	DESCRIPTION	UNIT	QUANTITY				
110	6003	EXCAVATION (SPECIAL)	CY	0.15				
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	36				
610	6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED	EA	6				
618	6023	CONDT (PVC) (SCH 40) (2")	LF	2305				
618	6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	90				
620	6006	ELEC CONDR (NO.10) INSULATED	LF	7335				
624	6002	GROUND BOX TY A (122311) W/APRON	EA	2				

WARNING OVERHEAD POWER LINES

CONTRACTOR SHALL COORDINATE WITH FERCO (LUIS JIMENEZ CELL# 915-472-3864
EMAIL: LUIS.Jimenez@epelectric.com) PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT
ARE TO BE PERFORMED BELOW POWER LINES FOR PROTECTIVE SLEEVE(S) TO
COVER ENERGIZED LINES AND AVOID ANY INJURY FOR CONSTRUCTION
PERSONNEL SAFETY.

EXISTING UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE INTENDED TO ILLUSTRATE THAT THEY ARE PRESENT. CONTRACTOR SHALL POTHOLE APPARENT UTILITY CONFLICTS AT INTERVALS NO MORE THAN 300 FT. TO VERIFY LOCATION DEPTH.

WARNING ! BEFORE YOU DIG NOTE: CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION WITH ALL UTILITY COMPANIES, TxDOT: (915) 790-4245

- 1. THE CONTRACTOR SHALL CONFIRM ALL UTILITY DEPTHS AND LOCATIONS PRIOR TO EXCAVATION.
- 2. THE LOCATIONS OF ROADWAY ILLUMINATION POLES, GROUND BOXES AND ELECTRICAL SERVICE POLES SHOWN ON THESE PLANS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED TO ACCOMMODATE LOCAL CONDITIONS. EXACT LOCATION OF ROADWAY ILLUMINATION EQUIPMENT SHALL BE APPROVED BY THE ENGINEER IN THE FIELD.
- 3. THE CONTRACTOR HAS THE OPTION TO BORE AT THE CONTRACTOR'S DISCRETION AND CONVENIENCE WHEN AN ITEM CALLS FOR A TRENCH. THIS WORK WILL BE PAID AS A TRENCH CONDUIT INSTALLATION.
- 4. REFER TO THE ILLUMINATION CIRCUIT DIAGRAM FOR SYSTEM DETAILS.
- 5. REFER TO THE ELECTRICAL SERVICE DATA SHEET FOR ELECTRICAL SERVICE DESCRIPTION.
- 6. CONTRACTOR SHALL REPAIR THE EXISTING IRRIGATION SYSTEM, SIDEWALK AND CURB & GUTTER TO AN EQUAL OR BETTER CONDITION IF IT IS DAMAGED DURING CONSTRUCTION. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO CONDUIT AND ROADWAY ILLUMINATION POLE INSTALLATION.
- 7. CONTRACTOR SHALL VERIFY THAT ALL EXISTING SYSTEMS ARE FUNCTIONAL AFTER INSTALLATION OF CONDUIT AND ILLUMINATION. ANY NON-FUNCTIONING SYSTEMS AS A RESULT OF THIS INSTALLATION MUST BE REPAIRED TO AN EQUAL OR BETTER CONDITION BY THE CONTRACTOR. THIS WORK WILL BE SUBSIDIARY TO VARIOUS BID ITEMS.
- 8. ROW IS SHOWN FOR INFORMATION ONLY.
- 9. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING ILLUMINATION INFRASTRUCTURE.
- 10.ALL PAVEMENT CUTS OR PAVEMENT DAMAGE WILL NEED TO BE REPAIRED/REPLACED PER TOWN OF HORIZON CITY PAVEMENT CUT ORDINANCE.
- 11. CONTRACTOR TO COORDINATE WITH CLINT ISD AND ESTRADA MIDDLE SCHOOL PRIOR TO COMMENCING PROJECT.
- 12. IN SITUATIONS WHERE AN ILLUMINATION POLE NEEDS TO BE ON TOP OF SIDEWALK, CONTRACTOR IS TO CONSTRUCT FOUNDATION FLUSHED WITH THE SIDEWALK. A MINIMUM SIDEWALK CLEAR AREA OF 3.5 FEET TO BE MAINTAINED WHEN ANY PORTION OF A POLE IS WITHIN THE SIDEWALK. THIS WORK WILL BE SUBSIDIARY TO PAY ITEM 416 6029.





DARRINGTON RD ILLUMINATION PLAN

STA 34+00 TO STA 46+00



	★ °			©2022
T T	exas De	epartment of	Trans	sportation
ONT	SECT	JOB		HIGHWAY
924	06	644	DAF	RRINGTON
IST		COUNTY		CHEET NO

28

EL PASO

10 I

11 I

13 I

14 I

15 I


18 I

2135

INCLUDES 5 FT SLACK PER CABLE

STATUS: I = INSTALL

300



DESIERTO BELLO AVE	POLE 2C-10 STA 55+99.44, 52.0' RT INSTALL: IN RD IL (TY SA) 20T-4 (150W EQ)	
<u>:</u>		0 25 50 100
CONTRACTOR SHALL CONF	IRM ALL UTILITY DEPTHS AND LOCATIONS PRIO	R TO
CAVATION.		SCALE: 1" = 100

		CONDU:	ΙT	NUME	BER OF	CONDUC	CTORS									
										ITEM SIZE/ COND	TYPE		ELECT	RICAL CTORS		
	SN.	TRENCH	BORED] ,			RUN									
RUN NO.	CONDUIT STATUS	PVC SCHD 40 (2")	PVC SCHD 40 (2") (BORE)	CABLE STATUS	##NO.10 XHHW (INSULATED) (GROUND)	##NO.10 XHHW (INSULATED) (POWER)	LENGTH OF RU	RUN NO.								
1	I	1		I	1	2	110	1								
2	I	1		I	1	2	40	2								
3	I	1		I	1	4	10	3								
4	I	1		I	1	2	130	4								
5	I		1	I	1	2	75	5								
O)	I	1		I	1	2	125	6								
7	I	1		I	1	2	335	7								
8	Ι	1		I	1	2	370	8								
٥	T	1		T	1	2	20	9								

270 10

20 11

265 13

235 14

85 15

140 17

45 18

95

40

2

2

I 1

I 1 2

1 2 1 2

2530 5090

CONDUIT, CONDUCTOR & CABLE SCHEDULE

SHEET 4 OF 6

	ILLUMINATION SUMMARY					
IT	ЕМ	DESCRIPTION		QUANTITY		
110	6003	EXCAVATION (SPECIAL)	CY	0.15		
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	42		
610	6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED	EA	7		
618	6023	CONDT (PVC) (SCH 40) (2")	LF	2135		
618	6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	300		
620	6006	ELEC CONDR (NO.10) INSULATED	LF	7620		
624	6002	GROUND BOX TY A (122311)W/APRON	EA	3		
628	6041	ELC SRV TY A 240/480 060(NS)SS(E)GC(O)	EA	1		
+	+	REMOVE TIMBERPOLE LUMINAIRE ARM	LS	1		

* FOR INFORMATION ONLY, TO BE REMOVED BY EL PASO ELECTRIC

WARNING OVERHEAD POWER LINES CONTRACTOR SHALL COORDINATE WITH FERCO (LUIS JIMENEZ CELL# 915-472-3864
EMAIL: LUIS.Jimenez@epelectric.com) PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT
ARE TO BE PERFORMED BELOW POWER LINES FOR PROTECTIVE SLEEVE(S) TO
COVER ENERGIZED LINES AND AVOID ANY INJURY FOR CONSTRUCTION
PERSONNEL SAFETY.

EXISTING UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE INTENDED TO ILLUSTRATE THAT THEY ARE PRESENT. CONTRACTOR SHALL POTHOLE APPARENT UTILITY CONFLICTS AT INTERVALS NO MORE THAN 300 FT. TO VERIFY LOCATION DEPTH.

WARNING ! BEFORE YOU DIG NOTE: CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION WITH ALL UTILITY COMPANIES. TXDOT: (915) 790-4245

- 1. THE EXCAVATION.
- 2. THE LOCATIONS OF ROADWAY ILLUMINATION POLES, GROUND BOXES AND ELECTRICAL SERVICE POLES SHOWN ON THESE PLANS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED TO ACCOMMODATE LOCAL CONDITIONS. EXACT LOCATION OF ROADWAY ILLUMINATION EQUIPMENT SHALL BE APPROVED BY THE ENGINEER IN THE FIELD.
- 3. THE CONTRACTOR HAS THE OPTION TO BORE AT THE CONTRACTOR'S DISCRETION AND CONVENIENCE WHEN AN ITEM CALLS FOR A TRENCH. THIS WORK WILL BE PAID AS A TRENCH CONDUIT INSTALLATION.
- 4. REFER TO THE ILLUMINATION CIRCUIT DIAGRAM FOR SYSTEM DETAILS.
- 5. REFER TO THE ELECTRICAL SERVICE DATA SHEET FOR ELECTRICAL SERVICE DESCRIPTION.
- 6. CONTRACTOR SHALL REPAIR THE EXISTING IRRIGATION SYSTEM, SIDEWALK AND CURB & GUTTER TO AN EQUAL OR BETTER CONDITION IF IT IS DAMAGED DURING CONSTRUCTION. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO CONDUIT AND ROADWAY ILLUMINATION POLE INSTALLATION.
- 7. CONTRACTOR SHALL VERIFY THAT ALL EXISTING SYSTEMS ARE FUNCTIONAL AFTER INSTALLATION OF CONDUIT AND ILLUMINATION. ANY NON-FUNCTIONING SYSTEMS AS A RESULT OF THIS INSTALLATION MUST BE REPAIRED TO AN EQUAL OR BETTER CONDITION BY THE CONTRACTOR. THIS WORK WILL BE SUBSIDIARY TO VARIOUS BID ITEMS
- 8. ROW IS SHOWN FOR INFORMATION ONLY.
- 9. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING ILLUMINATION INFRASTRUCTURE.
- 10. ALL PAVEMENT CUTS OR PAVEMENT DAMAGE WILL NEED TO BE REPAIRED/REPLACED PER TOWN OF HORIZON CITY PAVEMENT CUT ORDINANCE.
- 11. CONTRACTOR TO COORDINATE WITH CLINT ISD AND ESTRADA MIDDLE SCHOOL PRIOR TO COMMENCING PROJECT.
- 12. IN SITUATIONS WHERE AN ILLUMINATION POLE NEEDS TO BE ON TOP OF SIDEWALK, CONTRACTOR IS TO CONSTRUCT FOUNDATION FLUSHED WITH THE SIDEWALK. A MINIMUM SIDEWALK CLEAR AREA OF 3.5 FEET TO BE MAINTAINED WHEN ANY PORTION OF A POLE IS WITHIN THE SIDEWALK. THIS WORK WILL BE SUBSIDIARY TO PAY ITEM 416 6029.



LEGEND

EXISTING RDWY ILL ASSEMBLY TO REMAIN

PROPOSED RDWY ILL ASSEMBLY 20T-4 (150W LED EQ)

PROPOSED ELECTRICAL SERVICE

EXISTING ELECTRICAL SERVICE

PROPOSED CONDUIT (TRENCHED)

POLE DESIGNATION

TE OF A

ZAHIDUL Q. SIDDIQUE

98635 CENSE NO TONAL ENGLAS

PROPOSED CONDUIT (BORE)

— EXISTING ROW

1B-2

PROPOSED GROUND BOX TY A (W/APRON)

POLE OR LUMINAIRE NO

200

12/20/2022

CIRCUIT NO.

SERVICE NO.

EXISTING POWER SOURCE

CONDUIT RUN NUMBER


 \bigcirc

(X)

STA 46+00 TO STA 58+00



	★ °			© LULL	
7 7	exas De	epartment of	Trans	sportation	
ONT	SECT	JOB	HIGHWAY		
924	06	644	DARRINGTON		
IST	COUNTY			SHEET NO.	
LP		EL PASO		29	



2. THE LOCATIONS OF ROADWAY ILLUMINATION POLES, GROUND BOXES AND ELECTRICAL SERVICE POLES SHOWN ON THESE PLANS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED TO ACCOMMODATE LOCAL CONDITIONS. EXACT LOCATION OF ROADWAY ILLUMINATION EQUIPMENT SHALL BE APPROVED BY THE ENGINEER IN THE FIELD.

3. THE CONTRACTOR HAS THE OPTION TO BORE AT THE CONTRACTOR'S DISCRETION AND CONVENIENCE WHEN AN ITEM CALLS FOR A TRENCH. THIS WORK WILL BE PAID AS A TRENCH CONDUIT INSTALLATION.

- 4. REFER TO THE ILLUMINATION CIRCUIT DIAGRAM FOR SYSTEM DETAILS.
- 5. REFER TO THE ELECTRICAL SERVICE DATA SHEET FOR ELECTRICAL SERVICE DESCRIPTION.
- 6. CONTRACTOR SHALL REPAIR THE EXISTING IRRIGATION SYSTEM, SIDEWALK AND CURB & GUTTER TO AN EQUAL OR BETTER CONDITION IF IT IS DAMAGED DURING CONSTRUCTION. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO CONDUIT AND ROADWAY ILLUMINATION POLE INSTALLATION.
- 7. CONTRACTOR SHALL VERIFY THAT ALL EXISTING SYSTEMS ARE FUNCTIONAL AFTER INSTALLATION OF CONDUIT AND ILLUMINATION. ANY NON-FUNCTIONING SYSTEMS AS A RESULT OF THIS INSTALLATION MUST BE REPAIRED TO AN EQUAL OR BETTER CONDITION BY THE CONTRACTOR. THIS WORK WILL BE SUBSIDIARY TO VARIOUS BID TTFMS.
- 8. ROW IS SHOWN FOR INFORMATION ONLY.
- 9. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING ILLUMINATION INFRASTRUCTURE.
- 10.ALL PAVEMENT CUTS OR PAVEMENT DAMAGE WILL NEED TO BE REPAIRED/REPLACED PER TOWN OF HORIZON CITY PAVEMENT CUT ORDINANCE.
- 11. CONTRACTOR TO COORDINATE WITH CLINT ISD AND ESTRADA MIDDLE SCHOOL PRIOR TO COMMENCING PROJECT.
- 12. IN SITUATIONS WHERE AN ILLUMINATION POLE NEEDS TO BE ON TOP OF SIDEWALK, CONTRACTOR IS TO CONSTRUCT FOUNDATION FLUSHED WITH THE SIDEWALK. A MINIMUM SIDEWALK CLEAR AREA OF 3.5 FEET TO BE MAINTAINED WHEN ANY PORTION OF A POLE IS WITHIN THE SIDEWALK. THIS WORK WILL BE SUBSIDIARY TO PAY ITEM 416 6029.

CONDUIT, CONDUCTOR & CABLE SCHEDULE SHEET 5 OF 6

		CONDU:	ΙT	NUME	BER OF	CONDU	CTORS					
						ITEM SIZE/ COND	TYPF		ITEM ELECT CONDU	620 RICAL CTORS		
	SN.	TRENCH	BORED				RUN					
RUN NO.	CONDUIT STATUS	PVC SCHD 40 (2")	PVC SCHD 40 (2") (BORE)	CABLE STATUS	##NO.10 XHHW (INSULATED) (GROUND)	##NO.10 XHHW (INSULATED) (POWER)		RUN NO.				
1	I	1		I	1		370	1				
2	I	1		I	1	2	410	2				
3	I	1		I	1	2	400	3				
4	I	1		I	1	2	20	4				
5	I	1		I	1	2	140	5				
6	I		1	I	1	2	55	6				
7	I	1		I	1	2	80	7				
8	I		1	I	1	2	75	8				
9	Ι	1		I	1	2	230	9				
10	I	1		I	1	2	110	10				
11	I	1		I	1	4	10	11				
12	I	1		I	1	2	200	12				
13	I		1	I	1	2	95	13				
14	I	1		I	1	2	225	14				
TOTAL		2195	225		2490	5010		TOTAL				

STATUS: I = INSTALL

INCLUDES 5 FT SLACK PER CABLE


		ILLUMINATION SUMMARY		
ITEM		DESCRIPTION	UNIT	QUANTITY
110	6003	EXCAVATION (SPECIAL)	CY	0.15
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	36
610	6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED	EA	6
618	6023	CONDT (PVC) (SCH 40) (2")	LF	2195
618	6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	225
620	6006	ELEC CONDR (NO.10) INSULATED	LF	7500
624	6002	GROUND BOX TY A (122311) W/APRON	EA	3
628	6041	ELC SRV TY A 240/480 060(NS)SS(E)GC(0)	EA	1

WARNING OVERHEAD POWER LINES

CONTRACTOR SHALL COORDINATE WITH FERCO (LUIS JIMENEZ CELL# 915-472-3864
EMAIL: LUIS.Jimenez@epelectric.com) PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT
ARE TO BE PERFORMED BELOW POWER LINES FOR PROTECTIVE SLEEVE(S) TO
COVER ENERGIZED LINES AND AVOID ANY INJURY FOR CONSTRUCTION
PERSONNEL SAFETY.

EXISTING UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE INTENDED TO ILLUSTRATE THAT THEY ARE PRESENT. CONTRACTOR SHALL POTHOLE APPARENT UTILITY CONFLICTS AT INTERVALS NO MORE THAN 300 FT. TO VERIFY LOCATION DEPTH.

NOTE: CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION WITH ALL UTILITY COMPANIES, TxDOT: (915) 790-4245



LEGEND

EXISTING RDWY ILL ASSEMBLY TO REMAIN PROPOSED RDWY ILL ASSEMBLY 20T-4 (150W LED EQ)

PROPOSED ELECTRICAL SERVICE

EXISTING ELECTRICAL SERVICE

PROPOSED CONDUIT (TRENCHED)

POLE DESIGNATION

PROPOSED CONDUIT (BORE)

PROPOSED GROUND BOX TY A (W/APRON)

POLE OR LUMINAIRE NO

CIRCUIT NO.

SERVICE NO.

EXISTING POWER SOURCE

CONDUIT RUN NUMBER

EXISTING ROW

1B-2



DARRINGTON RD ILLUMINATION PLAN


STA 58+00 TO STA 70+00



Texas Department of Transportation							
CONT	SECT	JOB	HIGHWAY				
0924	06	644	DARRINGTON				
DIST	COUNTY			SHEET NO.			

EL PASO

WARNING ! BEFORE YOU DIG



	NDUCTOR & CABLE SCHEDULE					ULE	ILLUMINATION SUMMARY						
		EET 6 OF 6		DESCRIPTION	UNIT	QUANTIT'							
UIT NUMBER OF CONDUCTOR			CTORS		110	6003	EXCAVATION (SPECIAL)	CY	0.15				
	618 TYPE			1 620 RICAL			416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	24		
	DUIT			JCTORS			610	6124	IN RD IL (TY SA) 20T-4 (150W EQ) LED	EA	4		
	BORED				 <u> </u>		618	6023	CONDT (PVC) (SCH 40) (2")	LF	1335		
	90	SD.	₹û	<u></u> ≨6	≥	RUN	618	6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	70		

6006 ELEC CONDR (NO.10) INSULATED

			SHEET O OF O								
			CONDU:	ΙT	NUME	BER OF	CONDUC	CTORS			
			ITEM SIZE/ COND	618 TYPE UIT		ELECT	RICAL CTORS				
		LUS	rus	TUS	TUS	TRENCH	BORED	٠,			RUN
	RUN NO.	CONDUIT STATUS	PVC SCHD 40 (2")	PVC SCHD 40 (2") (BORE)	CABLE STATUS	##NO.10 XHHW (INSULATED) (GROUND)	##NO.10 XHHW (INSULATED) (POWER)		RUN NO.		
	1	I	1		I	1	2	120	1		
	2	I		1	I	1	2	70	2		
	3	I	1		I	1	2	205	3		
	4	I	1		I	1	2	410	4		
	5	I	1		I	1	2	185	5		
	6	I	1		I	1	2	415	6		
	TOTAL		1335	70		1435	2870		TOTAL		

CONDUIT, CONDUCTOR & CABLE SCHEDULE

STATUS: I = INSTALL

INCLUDES 5 FT SLACK PER CABLE

WARNING OVERHEAD POWER LINES CONTRACTOR SHALL COORDINATE WITH FERCO (LUIS JIMENEZ CELL# 915-472-3864
EMAIL: LUIS.Jimenez@epelectric.com) PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT
ARE TO BE PERFORMED BELOW POWER LINES FOR PROTECTIVE SLEEVE(S) TO
COVER ENERGIZED LINES AND AVOID ANY INJURY FOR CONSTRUCTION
PERSONNEL SAFETY.

LF

4305

EXISTING UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE INTENDED TO ILLUSTRATE THAT THEY ARE PRESENT. CONTRACTOR SHALL POTHOLE APPARENT UTILITY CONFLICTS AT INTERVALS NO MORE THAN 300 FT. TO VERIFY LOCATION DEPTH.

WARNING ! BEFORE YOU DIG NOTE: CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION WITH ALL UTILITY COMPANIES, TxDOT: (915) 790-4245

- 1. THE CONTRACTOR SHALL CONFIRM ALL UTILITY DEPTHS AND LOCATIONS PRIOR TO EXCAVATION.
- 2. THE LOCATIONS OF ROADWAY ILLUMINATION POLES, GROUND BOXES AND ELECTRICAL SERVICE POLES SHOWN ON THESE PLANS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED TO ACCOMMODATE LOCAL CONDITIONS. EXACT LOCATION OF ROADWAY ILLUMINATION EQUIPMENT SHALL BE APPROVED BY THE ENGINEER IN THE FIELD.
- 3. THE CONTRACTOR HAS THE OPTION TO BORE AT THE CONTRACTOR'S DISCRETION AND CONVENIENCE WHEN AN ITEM CALLS FOR A TRENCH. THIS WORK WILL BE PAID AS A TRENCH CONDUIT INSTALLATION.
- 4. REFER TO THE ILLUMINATION CIRCUIT DIAGRAM FOR SYSTEM DETAILS.
- 5. REFER TO THE ELECTRICAL SERVICE DATA SHEET FOR ELECTRICAL SERVICE DESCRIPTION.
- 6. CONTRACTOR SHALL REPAIR THE EXISTING IRRIGATION SYSTEM, SIDEWALK AND CURB & GUTTER TO AN EQUAL OR BETTER CONDITION IF IT IS DAMAGED DURING CONSTRUCTION. THIS WORK WILL BE CONSIDERED SUBSIDIARY TO CONDUIT AND ROADWAY ILLUMINATION POLE INSTALLATION.
- 7. CONTRACTOR SHALL VERIFY THAT ALL EXISTING SYSTEMS ARE FUNCTIONAL AFTER INSTALLATION OF CONDUIT AND ILLUMINATION. ANY NON-FUNCTIONING SYSTEMS AS A RESULT OF THIS INSTALLATION MUST BE REPAIRED TO AN EQUAL OR BETTER CONDITION BY THE CONTRACTOR. THIS WORK WILL BE SUBSIDIARY TO VARIOUS BID ITEMS.
- 8. ROW IS SHOWN FOR INFORMATION ONLY.
- 9. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING ILLUMINATION INFRASTRUCTURE.
- 10. ALL PAVEMENT CUTS OR PAVEMENT DAMAGE WILL NEED TO BE REPAIRED/REPLACED PER TOWN OF HORIZON CITY PAVEMENT CUT ORDINANCE.
- 11. CONTRACTOR TO COORDINATE WITH CLINT ISD AND ESTRADA MIDDLE SCHOOL PRIOR TO COMMENCING PROJECT.
- 12. IN SITUATIONS WHERE AN ILLUMINATION POLE NEEDS TO BE ON TOP OF SIDEWALK, CONTRACTOR IS TO CONSTRUCT FOUNDATION FLUSHED WITH THE SIDEWALK. A MINIMUM SIDEWALK CLEAR AREA OF 3.5 FEET TO BE MAINTAINED WHEN ANY PORTION OF A POLE IS WITHIN THE SIDEWALK. THIS WORK WILL BE SUBSIDIARY TO PAY ITEM 416 6029.



LEGEND

EXISTING RDWY ILL ASSEMBLY TO REMAIN PROPOSED RDWY ILL ASSEMBLY 20T-4 (150W LED EQ)

PROPOSED ELECTRICAL SERVICE

EXISTING ELECTRICAL SERVICE

PROPOSED CONDUIT (TRENCHED)

PROPOSED CONDUIT (BORE)

POLE DESIGNATION

— EXISTING ROW

1B-2

PROPOSED GROUND BOX TY A (W/APRON)

POLE OR LUMINAIRE NO

CIRCUIT NO.

SERVICE NO.

EXISTING POWER SOURCE

CONDUIT RUN NUMBER

(X)




DARRINGTON RD ILLUMINATION PLAN

STA 70+00 TO END



Texas Department of Transportation JOB H I GHWA 644 DARRINGTON 0924 06

FL PASO



GENERAL NOTES FOR ALL ELECTRICAL WORK

- 1. The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
- 2. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TXDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
- 3. Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is $\frac{1}{2}$ in. or less in diameter.
- 4. Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
- 5. Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
- 6. When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

CONDUIT

- A. MATERIALS
- 1. Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
- 2. Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
- 3. Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.

AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS		
#1	10" × 10" × 4"	12" × 12" × 4"	16" × 16" × 4"		
#2	8" × 8" × 4"	10" × 10" × 4"	12" × 12" × 4"		
#4	8" × 8" × 4"	10" × 10" × 4"	10" × 10" × 4"		
#6	8" × 8" × 4"	8" × 8" × 4"	10" × 10" × 4"		
#8	8" × 8" × 4"	8" × 8" × 4"	8" × 8" × 4"		

- 4. Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
- 5. Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
- 6. Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
- 7. Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

- 8. Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
- 9. When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
- 10. Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.
- B. CONSTRUCTION METHODS
- 1. Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
- 2. Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
- 3. Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
- 4. Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
- 5. When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
- 6. Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
- 7. During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
- 8. Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
- 9. Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
- 10. Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
- 11. At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
- 12. Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
- 13. Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
- 14. File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.



F A T L C


Traffic

Operation Division Standard

ELECTRICAL DETAILS CONDUITS & NOTES

ED(1)-14


			•					
:	ed1-14.dgn	DN:		ck:	DW:		CK:	
T×DOT	October 2014	CONT	SECT	ECT JOB		HIGHWAY		
	REVISIONS	0924	06	644		DARRINGTON		
		DIST		COUNTY			SHEET NO.	
		ELP	EL PASO				33	




CONDUIT HANGING DETAIL

CONDUIT MOUNTING CHANNEL						
"SPAN"	"W" × "H"	"T"				
less than 2'	1 5/8" × 1 3/8"	12 Ga.				
2'-0" to 2'-6"	1 5/8" × 1 5/8"	12 Ga.				
>2'-6" to 3'-0"	1 ½" × 2 ½"	12 Ga.				

Channels with round or short slotted hole patterns are allowed, if the load carrying capacity is not reduced by more than 15%.







Bridge Deck

HANGER ASSEMBLY DETAIL


ELECTRIC CONDUIT TO BRIDGE DECK ATTACHMENT





CONDUIT MOUNTING OPTIONS

Attachment to concrete surfaces See ED(1)B.2



TYPICAL CONDUIT ENTRY TO BRIDGE STRUCTURE DETAIL

EXPANSION ANCHOR NOTES FOR BRIDGE DECK ATTACHMENT

- 1. Use torque controlled mechanical expansion anchors that are approved for use in cracked concrete by the International Code Council, Evaluation Service (ICC-ES). The chosen anchor product shall have a designated ICC-ES Evaluation Report number, and its approval status shall be maintained on the ICC-ES website under Division 031600 for Concrete
- 2. Unless otherwise approved by the Engineer: do not use adhesive anchors; do not use expansion anchors that are not included in the ICC-ES approval list; and do not use expansion anchors that are only approved for use in
- 3. Use anchors manufactured with stainless steel expansion wedges. Anchors manufactured with carbon steel expansion wedges are not allowed. Anchor bodies can be either zinc-plated carbon steel or stainless steel. For application in marine environment, both the anchor body and expansion wedge shall be stainless steel.
- 4. Install anchors as shown on the plans and in accordance with the anchor manufacturer's published installation instructions. Arrange a field demonstration test to evaluate the procedures and tools. The test shall be witnessed and approved by the Engineer prior to furnishing anchors on
- 5. Prior to hole drilling, use rebar locator to ensure clearing of existing deck strands or reinforcement. Install anchors to ensure a minimum effective embedment depth, (hef), as shown. Increase (hef)as needed to ensure sufficient thread length for proper torqueing and tightening of anchors.
- 6. Use anchors of minimum 1600 Lbs tensile capacity (minimum of steel, concrete breakout, and concrete pullout strengths as determined by ACI 318 Appendix D) at the required minimum embedment depth (^hef). No lateral loads shall be introduced after conduit installation.



ELECTRICAL DETAILS CONDUIT SUPPORTS

Division Standard

ED(2)-14

E:	ed2-14.dgn	DN: TxDOT		ck: TxDOT	DW:	TxDOT	ck: TxDOT	
TxDOT	October 2014	CONT SECT		JOB		HIGHWAY		
	0924	06	644		DARRINGTON			
	DIST	DIST COUNTY SHEET N						
	FLP	FL PASO 34				34		

ELECTRICAL CONDUCTORS

- A. MATERIAL INFORMATION
- 1. Provide Type XHHW insulated conductors in accordance with Departmental Material Specification (DMS)11040 "Conductors" and Item 620 "Electrical Conductors." Provide conductors as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 620. Color code insulated conductors in conformance with the NEC. Identify grounded (neutral) conductors with white insulation. Identify grounding conductors (ground wires) with green insulation or bare conductors. Identify ungrounded (hot) conductors with any color insulation except green, white, or gray. Keep color scheme consistent throughout the wiring system. Identify conductors 6 American Wire Gauge (AWG) and smaller by continuous color jacket. Identify electrical conductors 4 AWG and larger by continuous color jacket or by colored tape. When identifying conductors with colored tape, mark at least 6 in. of the conductor's insulation with half laps of tape.
- 2. Provide a solid copper 6 AWG grounding electrode conductor to bond the electrical service equipment to the concrete encased grounding electrode or the ground rod at the service location. Connect the grounding electrode conductor to the ground rod with a UL listed connector in accordance with DMS 11040. Connect the grounding electrode conductor to the concrete encased grounding electrode as shown in the plans.
- 3. Where two or more circuits are present in one conduit or enclosure, permanently identify the conductors of each branch circuit by attaching a non-metallic tag around both circuit conductors at each accessible location. Provide tags with two straps, large enough to indicate circuit number, letter, or other identification as shown in the plans. Print circuit identification on the tag with a permanent marker.
- 4. Use listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors for splicing as specified in DMS 11040. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Provide UL listed gel-filled insulating splice covers. Splicing materials, insulating materials, breakaway disconnects, splice covers, and fuse holders are subsidiary to various bid items.
- B. CONSTRUCTION METHODS
- 1. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the conduit system. After installing conductors in conduit, perform conductor pull test. If a conductor cannot be freely pulled, make any needed alterations or repairs at no additional cost to the department. Perform insulation resistance tests in accordance with Item 620. Coordinate with the Engineer to witness the tests.
- 2. Leave 2 ft. minimum, 3 ft. maximum length for each conductor up to the splice in ground boxes. Leave 3 ft. minimum, 4 ft. maximum length of conductor in ground boxes when pulled through with no splice. Leave 1 ft. minimum, 1.5 ft. maximum length of conductor at enclosures, weatherheads and pole bases.
- 3. Make splices only in junction boxes, ground boxes, pole bases, or electrical enclosures and use only listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors. Insulate splices with heavy wall heat shrink tubing or gel-filled insulating splice covers to provide a watertight splice. Overlap conductor insulation with heat shrink tubing a minimum of 2 in. past both sides of the splice. Where heat shrink tubing may not shrink sufficiently to provide a watertight seal around the individual conductors, prior to heating the tubing, increase the diameter of the conductor insulation using hot melt adhesive tape to provide a watertight seal between the individual conductors and the heat shrink tubing. Ensure the tape extends past the heat shrink tubing. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Heat shrink tubing that appears to have been burned, or overheated, is considered defective and must be replaced.
- 4. Size and install gel-filled insulating splice covers according to manufacturer's specifications when used in place of heat shrink tubing.
- 5. Wire nuts with factory applied waterproof sealant may be used for 8 AWG or smaller conductors in above ground junction boxes, but not in pole bases or ground boxes. Install wire nuts in an upright position to prevent the accumulation of water.
- Support conductors in illumination poles with a J-hook at the top of the pole.
- 7. When terminating conductors, remove the insulation and jacketing material without nicking the individual strands of the conductor. Conductors with nicked individual conductor strands or removed strands will be considered damaged.
- 8. Replace conductors and cables that are damaged beyond repair or that fail an insulation resistance test at no additional cost to the department.
- Do not repair damaged conductors with duct tape, electrical tape, or wire nuts. Use only approved splicing methods.
- 10. Do not terminate more than one conductor under a single connector, unless the connector is rated for multiple conductors. Do not exceed the pressure connector's listing for maximum number and size of conductors allowed.
- 11. Install breakaway connectors on conductors bid under Item 620 whenever those conductors pass through a breakaway support device. Follow manufacturer's instructions when terminating conductors to breakaway connectors. Properly torque threaded connections. Proper terminations are critical to the safe operation of breakaway devices. Trim waterproofing boots on breakaway connectors to fit snugly around the conductor to ensure waterproof connection. Only one conductor may enter a single opening in a boot. Provide waterproof boots with the correct number of openings. Leave unused openings factory sealed. Use prequalified breakaway connectors as shown on the MPL.

12. Provide and install a separate stranded equipment grounding conductor (EGC) in all conduits that contain circuit wiring of 50 volts or more. Unless shown elsewhere, size the EGC to be the same size as the largest current carrying conductor contained in the conduit. Ensure all EGCs are bonded together at every accessible location. For traffic signal installations, provide a minimum size 8 AWG EGC. The EGC is paid for under Item 620.

C. TEMPORARY WIRING


- 1. Install temporary conductors and electrical equipment in accordance with the NEC article "Temporary Installations" and Department standard sheets.
- 2. Provide a ground fault circuit interrupter (GFCI) for power outlets for portable electrical equipment, power tools, ice machines, ice storage bins and refrigerators located outdoors at grade. GFCI may be any one of the following: molded cord and plug set, receptacle, or circuit breaker type.
- 3. Use listed wire nuts with factory applied sealant for temporary wiring where approved.
- 4. Enclose conductor splices within a listed enclosure or ground box, or ensure the splices are more than 10 ft. above grade vertically and more than 5 ft. horizontally from any metal structure. Where installing temporary conductors in areas subject to vehicle traffic or mobile construction equipment, ensure the vertical clearance to ground is at least 18 ft. when measured at the lowest point. Ground messenger wires that support power conductors in conformance with the NEC.
- 5. Protect and when necessary repair any existing electrical conduits uncovered during the construction process in a timely manner and in conformance with the NEC.


GROUND RODS & GROUNDING ELECTRODES

- A. MATERIAL INFORMATION
- Provide and install a grounding electrode at electrical services. Provide ground rods according to DMS 11040 and the plans. Larger diameter or longer length rods may be called for in some specific locations, see the individual plans sheets. Concrete encased grounding electrodes may be called for in specific locations including electrical service, see individual plan sheets.


B. CONSTRUCTION METHODS

- 1. Furnish auxiliary ground rods for lightning protection and install in soil, concrete, or both, as called for in the plans. For ground rods installed in concrete, ensure the connection of the conductor to the ground rod is readily accessible for inspection or repairs. For ground rods installed in soil, ensure that the upper end is between 2 to 4 in. below finished grade.
- 2. Do not place ground rods in the same drilled hole as a timber pole.
- 3. Install ground rods so the imprinted part number is at the upper end of the rod.
- 4. Remove all non-conductive coatings such as concrete splatter from the rod at the clamp location.
- 5. Route all conductors as short and straight as possible for connection to lightning protection ground rods. When a bend is required, ensure a minimum radius bend of four inches for these conductors.
- 6. Unless otherwise called for in the plans, protect grounding electrode conductors with non-metallic conduit. When protecting grounding electrode conductors with metal conduit, provide and install a grounding type bushing and properly sized bonding jumper on each end of the metal conduit.
- 7. Written authorization is required before installing a ground rod in a horizontal trench for rocky soil or a solid rock bottom.






SPLICE OPTION 1 Compression Type




SPLICE OPTION 2 Split Bolt Type



Operation

ED(3)-14





APRON FOR GROUND BOX

- (1) Uniformly space ends of conduits within the ground box. Position ends of conduits so that ground box walls do not interfere with the installation of grounding bushings or bell end fittings.
- (2) Maintain sufficient space between conduits to allow for proper installation of bushing.
- (3) Place aggregate under the box, not in the box. Aggregate should not encroach on the interior volume of the box.
- (4) Install a grounding bushing on the upper end of all RMC terminating in a ground box. Ground RMC elbows when any part of the elbow is less than 18 in. below the bottom of the ground box. Install a PVC bushing or bell end fitting on the upper end of all PVC conduits terminating in a ground box.

GROU	GROUND BOX DIMENSIONS							
TYPE	OUTSIDE DIMENSIONS (INCHES) (Width x Length X Depth)							
А	12 X 23 X 11							
В	12 X 23 X 22							
С	16 X 29 X 11							
D	16 X 29 X 22							
E	12 X 23 X 17							

GROUND BOX COVER DIMENSIONS								
TYPE			DIMEN	ISIONS	(INCH	ES)		
1175	Н	Ι	J	К	L	М	N	Р
А, В & Е	23 1/4	23	13 ¾	13 1/2	9 7/8	5 1/8	1 3/8	2
C & D	30 ½	30 1/4	17 ½	17 1/4	13 1/4	6 3/4	1 3/8	2





GROUND BOX COVER

GROUND BOXES

- A. MATERIALS
- Provide polymer concrete ground boxes measuring 16x30x24 in. (WxLxD) or smaller in accordance with Departmental Material Specification (DMS) 11070 "Ground Boxes" and Item 624 "Ground Boxes."
- 2. Provide Type A, B, C, D, and E ground boxes as shown in the plans, and as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 624.
- 3. Ensure ground box cover is correctly labeled in accordance with DMS 11070.
- 4. Provide larger ground boxes in accordance with Item 624 and as shown in the plans.
- B. CONSTRUCTION METHODS
- 1. Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure aggregate bed is in place and at least 9 inches deep, prior to setting the ground box. Install ground box on top of aggregate.
- 2. Cast ground box aprons in place. Reinforcing steel may be field bent. Ensure the depth of concrete for the apron extends from finished grade to the top of the aggregate bed under the box. Ground box aprons, including concrete and reinforcing steel, are subsidiary to ground boxes when called for by descriptive code.
- 3. Keep bolt holes in the box clear of dirt. Bolt covers down when not working in ground boxes.
- 4. Install all conduits and ells in a neat and workmanlike manner. Uniformly space conduits so grounding bushings and bell end fittings can easily be installed.
- 5. Temporarily seal all conduits in the ground box until conductors are installed.
- 6. Permanently seal conduits immediately after the completion of conductor installation and pull tests. Permanently seal the ends of all conduits with duct seal, expandable foam, or other method as approved. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a sealant.
- 7. When a ground rod is present in a ground box, bond all equipment grounding conductors together and to the ground rod with listed connectors.
- 8. When a type B or D ground box is stacked to meet volume requirements, it is allowable to cut an appropriately sized hole for conduit entry in the side wall at least 18 inches below grade.
- 9. If an existing ground box in the contract has a metal cover, bond the cover to the equipment grounding conductor with a 3 ft. long stranded bonding jumper the same size as the grounding conductor. The bonding jumper is subsidiary to various bid items. Verify existing ground boxes with metal covers are shown on the plans, with notes fully describing the work required.
- 10. If other ground boxes with metal covers are within the project limits but are not part of the contract, the Engineer may direct the Contractor to bond the metal covers, identifying the specific boxes in writing. This work will be paid for separately.
- 11. Bond metal ground box covers to the grounding conductor with a tank ground type lug.



Traffic Operations Division Standard

ELECTRICAL DETAILS GROUND BOXES

ED(4)-14

LE:	ed4-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxD01	Ск:	: TxDOT
)TxDOT	October 2014	CONT	SECT	JOB			H [GHWA	·Υ
	REVISIONS	0924	06	644		DAR	RIN	GTON
		DIST		COUNTY			SHEE	T NO.
		FIP		FI PA	SO.		-	36

10:

ELECTRICAL SERVICES NOTES

- 1.Provide new materials. Ensure installation and materials comply with the applicable provisions of the National Electrical Code (NEC) and National Electrical Manufacturers Association (NEMA) standards. Ensure material is Underwriters Laboratories (UL) listed. Provide and install electrical service conduits, conductors, disconnects, contactors, circuit breaker panels, and branch circuit breakers as shown on the Electrical Service Data chart in the plans. Faulty fabrication or poor workmanship in material, equipment, installation is justification for rejection. Where manufacturers provide warranties and guarantees as a customary trade practice, furnish these to the State.
- 2. Provide electrical services in accordance with Electrical Details standard sheets, "Electrical Services-Type A," DMS 11082 "Electrical Services, "DMS 11081 "Electrical Services-Type A," DMS 11082 "Electrical Services-Type C," DMS 11083 "Electrical Services-Type D," DMS 11084 "Electrical Services-Type T," DMS 11085 "Electrical Services-Pedestal (PS)", and Item 628 "Electrical Services" of the Standard Specifications. Provide electrical service types A, C, and D, as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 628. Provide other service types as
- 3. Provide all work, materials, services, and any incidentals needed to install a complete electrical service as specified in the plans.
- 4.Coordinate with the Engineer and the utility provider for meterina and compliance with utility requirements. Primary line extensions, connection charges, meter charges, and other charges by the utility company to provide power to the location are paid for in accordance with Item 628. Get approval for the costs associated with these charges prior to engaging the utility company to do the work. Consult with the utility provider to determine costs and requirements, and coordinate the work as approved.
- 5. The enclosure manufacturer will provide Master Lock Type 2 with brass tumblers keyed #2195 for all custom electrical enclosures. Installing Contractor is to provide Master Lock #2195 Type 2 with brass tumblers for "off the shelf" enclosures. Master Lock #2195 keys and locks become property of the State. Unless otherwise approved, do not energize electrical service equipment until
- 6.Enclosures with external disconnects that de-energize all equipment inside the enclosure do not need a dead front trim. Protect incoming line terminations from incidental contact as required by the NEC.
- 7. When galvanized is specified for nuts, screws, bolts or miscellaneous hardware, stainless steel may be used.
- 8. Provide wiring and electrical components rated for 75°C. Provide red. black. and white colored XHHW service entrance conductors of minimum size 6 American Wire Gauge (AWG). Identify size 6 AWG conductors by continuous color jacket. Identify electrical conductors sized 4 AWG and larger by continuous color jacket or by colored tape. Mark at least 6 inches of the conductor's insulation with half laps of colored tape, when identifying conductors. Ensure each service entrance conductor exits through a separately bushed non-metallic opening in the weatherhead. The lengths of the conductors outside the weatherhead are to be 12 inches minimum, 18 inches maximum, or as required by utility.
- 9.All electrical service conduit and conductors attached to the electrical service including the riser or the elbow below ground are subsidiary to the electrical service. For an underground utility feed, all service conduit and conductors after the elbow, including service conduit and conductors for the utility pole riser when furnished by the Contractor, will be paid for separately
- 10.Provide rigid metal conduit (RMC) for all conduits on service, except for the $\frac{1}{2}$ in. PVC conduit containing the electrical service grounding electrode conductor. Size the service entrance conduit as shown in the plans. Ensure conduit for branch circuit entry to enclosure is the same size as that shown on the layout sheets for branch circuit conduit. Extend all rigid metal conduits a minimum of 6 inches underground and then couple to the type and schedule of the conduit shown on the layout for that particular branch circuit. Install a grounding bushing on the RMC where it terminates in the service enclosure.
- 1.Use of liquidtight flexible metal conduit (LFMC) is allowed between the meter and service enclosure when they are mounted 90 to 180 degrees to each other. Size the LFMC the same size as service entrance conduit. LFMC must not exceed 3 feet in length. Strap LFMC within 1 foot of each end. LFMC less than 12 inches in length need not be strapped. Each end of LFMC must have a grounding bushing or be terminated with a grounding fitting. The LFMC must contain a grounded (neutral) conductor. Ensure any bend in LFMC never exceeds 180 degrees. A pull test is required on all installed conductors, with at least six inches of free conductor movement demonstrated to the satisfaction of the Engineer.
- 12.Ensure all mounting hardware and installation details of services conform to utility company specifications.
- 13.For all electrical service enclosures listed under Item 628 on the MPL, the UL 508 enclosure manufacturers will prepare and submit a schematic drawing unique to each service. Before shipment to the job site, place the applicable laminated schematic service. Before snipment to the job site, place the applicable laminated schematic drawings and the laminated plan sheet showing the electrical service data chart used to build the enclosure in the enclosure's data pocket. The installing contractor will copy and laminate the actual project plan sheets detailing all equipment and branch circuits supplied by that service. The laminated plan sheets are to be placed in the service enclosure's document pocket. Reduce 11 in. x 17 in. plan sheets to $8 \frac{1}{2}$ in. x 11 in. before laminating. If the installation differs from the plan sheets, the installing contractor is to redline plan sheets before laminating.
- 4.When providing an "Off The Shelf" Type D or Type T service, provide laminated plan sheets detailing equipment and branch circuits supplied by that service. Reduce 11 in. x 17 in. plan sheets to 8 $\frac{1}{2}$ in. x 11 in before laminating. Deliver these drawings before completion of the work to the Engineer, instead of placing in enclosure that has no door pocket.
- 5.Do not install conduit in the back wall of a service enclosure where it would penetrate the equipment mounting panel inside the enclosure. Provide grounding bushings on all metal conduits, and terminate bonding jumpers to grounding bus. Grounding bushings are not required when the end of the metal conduit is fitted with a conduit sealing hub or threaded boss, such as a meter base hub.

SERVICE ASSEMBLY ENCLOSURE

- 1. Provide threaded hub for all conduit entries into the top of enclosure.
- 2. Type galvanized steel (GS) enclosures may be used for Type C panelboards and for Type D and T services that do not use an enclosure mounted photocell or lighting contactor. Provide GS enclosures in accordance with DMS 11080, 11082, 11083, and 11084.
- 3. Provide aluminum (AL) and stainless steel (SS) enclosures for Types A, C, and D in accordance with DMS 11080, 11081, 11082, 11083, and 11084. Do not paint stainless steel.
- 4. Provide pedestal service (PS) enclosures in accordance with ED(9) and DMS 11080 and 11085. Do not provide GS pedestal services. If GS is shown in the PS descriptive code, provide an AL enclosure.

MAIN DISCONNECT & BRANCH CIRCUIT BREAKERS


- 1. Field drill flange-mounted remote operator handle if needed, to ensure handle is lockable in both the "On" and "Off" positions.
- 2. When the utility company provides a transformer larger than 50 KVA. verify that the available fault current is less than the circuit breaker's ampere interrupting capacity (AIC) rating and provide documentation from the electric utility provider to the Engineer.


PHOTOELECTRIC CONTROL

1. Provide photocell as listed on the MPL. Move, adjust, or shield the photocell from stray or ambient night time light to ensure proper operation. Mount photocell facing north when practical. Mount top of pole photocells as shown on Top Mounted Photocell Detail.

			* ELE	CTRICAL	SERV	ICE DATA	4					
Elec. Service ID	Plan Sheet Number		Service Conduit **Size	Service Conductors No./Size	Safety Switch Amps	Main Ckt. Bkr. Pole/Amps	Two-Pole Contractor Amps	Panelbd/ Loadcenter Amp Rating	Branch Circuit ID	Branch Ckt. Bkr. Pole/Amps	Branch Circuit Amps	KVA Load
SB 183	289	ELC SRV TY A 240/480 100(SS)AL(E)SF(U)	2"	3/#2	100	2P/100	100	N/A	Lighting NB	2P/40	26	28.1
		1	J	<u> </u>		<u> </u>	<u> </u>		Lighting SB	2P/40	25	
			Į į	<u> </u>	<u> </u>	<u> </u>	<u> </u>		Underpass	1P/20	15	
				'		<u> </u>	'					
NB Access	30	ELC SRV TY D 120/240 060(NS)SS(E)TS(0)	1 1/4"	3/#6	N/A	2P/60	'	100	Sig. Controller	1P/30	23	5.3
				,		'	30		Luminaires	2P/20	9	,
		1							CCTV	1P/20	3	
				1			1					,
2nd & Main	58	ELC SRV TY T 120/240 000(NS)GS(N)SP(O)	1 1/4"	3/#6	N/A	N/A	N/A	70	Flashing Beacon 1	1P/20	4	1.0
				<u> </u>			<u> </u>		Flashing Beacon 2	1P/20	4	

- * Example only, not for construction. All new electrical services must have electrical service data chart specific to that service as shown in the plans.
- ** Verify service conduit size with utility. Size may change due to utility meter requirements. Ensure conduit size meets the National Electrical Code.





TOP MOUNTED PHOTOCELL


Install conduit strap maximum 3 feet from box. 5 foot maximum spacing between straps supporting conduit.




Operation

ED(5)-14


FILE: ed5-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT October 2014	CONT	SECT	JOB		H [GHWAY	
REVISIONS	0924	06	644		DARRINGTO	
	DIST	COUNTY			SHEET NO.	
	ELP		EL PA	SO		37






SCHEMATIC TYPE A THREE WIRE

SCHEMATIC TYPE C THREE WIRE



	WIRING LEGEND						
	Power Wiring						
	Control Wiring						
—N—	Neutral Conductor						
—-G—	Equipment grounding conductor-always required						

	SCHEMATIC LEGEND
1	Safety Switch (when required)
2	Meter (when required-verify with electric utility provider)
3	Service Assembly Enclosure
4	Main Disconnect Breaker (See Electrical Service Data)
5	Circuit Breaker, 15 Amp (Control Circuit)
6	Auxiliary Enclosure
7	Control Station ("H-O-A" Switch)
8	Photo Electric Control (enclosure- mounted shown)
9	Lighting Contactor
10	Power Distribution Terminal Blocks
11	Neutral Bus
12	Branch Circuit Breaker (See Electrical Service Data)
13	Separate Circuit Breaker Panelboard
14	Load Center
15	Ground Bus



SCHEMATIC TYPE T

120/240 VOLTS - THREE WIRE

Galvanized steel-"Buy Off The Shelf" only. When required install photocell top of the pole or on luminaire only, no lighting contractor will be installed.



Traffic Operations Division Standard


ELECTRICAL DETAILS SERVICE ENCLOSURE AND NOTES

ED(6)-14

.E:	ed6-14.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	ı	
TxDOT	October 2014	CONT	SECT	JOB		H	HIGHWAY	ı	
	REVISIONS	0924	06	644		644 DARRING		RINGTON	ı
		DIST		COUNTY			SHEET NO.	ı	
		ELP		EL PAS	SO		38	ı	

TIMBER POLE (TP) SERVICE SUPPORT NOTES

- 1. Ensure electrical service support is a class 5 treated timber pole as per Item 627 "Treated Timber Poles." Embed timber pole to depth required in Item 627.
- 2. Conduit and electrical conductors attached to the electrical service pole and underground within 12 in. of service pole are not paid for directly but are subsidiary to the electrial service.
- 3. Install pole-top mounted photocell (T) on north side of pole, or in service enclosure
 (E) as required. See Electrical Service Data chart in plan set.
- 4. Gain pole as required to provide flat surface for each channel. Gain timber pole to $\frac{5}{8}$ in. max. depth and 1 $\frac{7}{8}$ in. max. height. Gain pole in a neat and workmanlike manner.
- 5. Mount meter and service equipment on stainless steel or galvanized channel (Unistrut, Kindorf, or equal). Provide channel sized 1 in. to 3 $\frac{3}{4}$ maximum depth, and $1\frac{1}{2}$ in. to $1\frac{5}{8}$ in. maximum width. File smooth the cut ends of galvanized channel and paint with zinc rich paint before installing on pole. Secure each channel section to timber pole with two galvanized or SS lag bolts, $\frac{1}{4}$ in. minimum diameter by $\frac{1}{2}$ in. minimum length. Use a galvanized or SS flat washer on each lag bolt. Do not stack channel.
- 6. When excess length must be trimmed from poles, trim from the top end only.
- (1) Class 5 pole, height as required
- (2) Service drop from utility company (attached below weatherhead)
- (3) Service conduit (RMC) and service entrance conductors - One Red, One Black, One White (See Electrical Service Data)
- (4) Safety switch (when required)
- (5) Meter (when required)
- (6) Service enclosure
- (7) 6 AWG bare grounding electrode conductor in $\frac{1}{2}$ in. PVC to ground rod - extend 1/2 in. PVC 6 in. underground.
- (8) % in. x 8 ft. Copper clad ground rod - drive ground rod to a depth of 2 in. to 4 in. below grade.
- (9) RMC same size as branch circuit conduit.
- (10) See pole-top mounted photocell detail on ED(5).
- (11) When required by the serving utility provide bare 6 AWG copper conductor. Run wire from pole top to butt wrap or copper butt plate. Protect conductor with non-conductive material to a height of 8 ft. above finished grade.
- (12) When required by utility, cut top of pole at an angle to enhance rain run off.




SERVICE SUPPORT TYPE TP (0)

Ensure electrical service support structures bid as type Granite Concrete (GC) or Other Concrete (OC) meet the following requirements.

1. Provide GC and OC poles that meet the requirements of DMS 11080 "Electrical Services.


GRANITE CONCRETE (GC) & OTHER CONCRETE (OC) NOTES

- 2. Provide prestressed concrete poles suitable for direct embedment into the ground without special foundations.
- 3. Verify poles are marked as required on DMS 11080. Location of marking should be approximately 4' above final grade. Use the two-point pickup locations when handling pole in horizontal position, and one-point pickup location for use in raising the pole to a vertical position. These marks are small but conspicuous.
- 4. Embed poles 42 in. or 10% of the length plus 2 ft., whichever is greater.
- 5. Ensure all installation details of services are in accordance with utility company specifications.
- 6. Install a one point rack or eye bolt bracket 6 inches to 12 inches below the weatherhead as an overhead service drop anchoring point for the electric utility.
- 7. Furnish and install galvanized or stainless steel channel strut 1 $\frac{1}{2}$ in. or 1 $\frac{5}{8}$ in. wide by 1 in. up to 3 $\frac{3}{4}$ in. deep (Unistrut, Kindorf, B-line or equal). Attach channel strut with stainless steel concrete anchors (max. depth), square U-bolts or back to back channel strut with long bolts, or other secure mounting as approved by the Engineer. Ensure bolts are galvanized in accordance with ASTM A153. Do not stack channel struts.
- 8. Backfill the holes thoroughly by tamping in 6 in. lifts. After tamping to grade, place additional backfill material in a 6 inch high cone around the pole to allow for settling. Use material equal in composition and density to the surrounding area. Backfilling will not be paid for directly but is subsidiary to various bid items.




CONCRETE SERVICE SUPPORT

Overhead(0)




CONCRETE SERVICE SUPPORT

Underground (U)



DETAIL A

See Note 7. Before installing channel that has been cut, file sharp edges and paint with zinc-rich paint. Ensure there is no paint splatter on the pole.



DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO ed10-14.dgn CTxDOT October 2014 JOB 644 DARRINGTON 0924 06 EL PASO

10:51:43

ROADWAY ILLUMINATION ASSEMBLY NOTES

- 1. Details apply to roadway lighting installations bid or referenced under Item 610, "Roadway Illumination Assemblies." Provide, furnish, and install all other materials not shown on the plans which may be necessary for complete and proper construction. Where manufacturers provide warranties or guarantees as a customary trade practice, furnish to the State such warranties or augrantees.
- 2. The locations of poles and fixtures may be shifted by the Engineer to accommodate local conditions. Install or remove poles and luminaires located near overhead electrical lines using established industry and utility safety practices and in accordance with laws governing such work. Consult with the appropriate utility company prior to beginning such work.
- 3. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TXDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association, Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection.
- 4. Provide Roadway Illumination Light Fixtures as per TxDOT Departmental Material Specification (DMS) 11010, Item 610, and as shown on the Material Producers List (MPL) for Roadway Illumination and Electrical Supplies.
- 5. Fabricate steel roadway illumination poles in accordance with Roadway Illumination Poles (RIP) standards and Item 610. Poles fabricated according to RIP standards do not require shop drawing submittals.
 - a. Alternate designs to RIP standards or the use of aluminum to fabricate poles will require the submission of shop drawings electronically. For instructions on submitting shop drawings electronically see "Guide to Electronic Shop Drawing Submittal" on the TxDOT web site.
 - b. Limitations on use of the RIP standard: The RIP standard details were developed for installations in locations where the 3-second gust basic maximum wind speed is 110 mph, and where the elevation of the base of the pole is less than (i.e. not more than) 25' above the elevation of the surrounding terrain, in accordance with the "AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals," 6th Edition (2013) of the AASHTO Design Specifications. For poles to be installed in regions where the maximum basic wind speed exceeds 110 mph or to be mounted more than 25' above the surrounding terrain, provide poles meeting the following requirements:
 - i. Submittals. Following the electronic shop drawing submittal process (see Guide to Electronic Shop Drawing Submittal on the TxDOT web site), submit to the Engineer for approval fabrication drawings and calculations for the poles, sealed by a Texas licensed professional engineer (P.E.).
 - ii. Luminaire Structural Support Requirements. Provide light poles, arms, and anchor bolt assemblies with a 25 year design life to safely resist dead loads, ice loads and the required basic wind speeds at the location of installation in accordance with the 6th edition (2013) of the AASHTO Design Specifications. For transformer base poles, include transformer base and connecting hardware in calculations and shop drawing submittals. Structurally test all transformer bases to resist the theoretical plastic moment capacity of the pole. Submit certification of the plastic moment load test and FHWA breakaway requirement test of the model of base being furnished with the shop drawings. Show breakaway base model number, manufacturer's name, and logo on shop drawings. Include on manufacturer's shop drawings the ASTM designations for all materials to be used.
- 6. For both transformer and shoe-base type illumination poles, provide and install double-pole breakaway fuse holders as specified by DMS-11040. Breakaway fuse holders are listed on the MPL for Roadway Illumination and Electrical Supplies under Items 610 & 620. Provide 10 amp time delay fuses for breakaway connectors in light poles, or inside the light fixture for underpass luminaires. In each pole, connect luminaires to the breakaway connector with continuous stranded 12 AWG copper conductors as listed on the MPL. Bond all equipment grounding conductors together and to the ground lug in the transformer base or hand hole.
- 7. Tighten anchor bolts for shoe base, concrete traffic barrier base, and bridge mount roadway illumination poles, in accordance with Item 449.
- 8. Install T-Base with following procedure:
 - a. Anchor Bolt Tightening.
 - i. Coat the threads of the anchor bolts with electrically conductive lubricant.
 - ii. Place the T-base over the anchor bolts. Foundation must be level and flat. The maximum permissible gap under any one corner of the t-base is 1/8" before nuts are tightened.
 - iii.Coat the bearing surfaces of the nuts and washers with electrically conductive lubricant. Install (1) 1/2" hold down washer, (1) lock washer, and (1) nut on each anchor bolt. Turn the nuts onto the bolts so that each is hand-tight against the washer.
 - iv. Using a torque wrench, tighten each nut to 150 ft-lb. Uniform contact is required between the foundation and the T-base in the corner regions of the T-base, and all corner gaps must be closed after applying torque. If a gap still exists after torquing to 150 ft-lbs, continue torquing each bolt incrementally until gap is closed or maximum allowable torque of 250 ft. pound is reached, whichever comes first. If 250 ft-lbs is not enough to close the gap the foundation must be leveled. Gaps along the straight sides of the T-bases and the foundation are permissible. Ensure that no high point of contact occurs between the straight sides of the T-base and the
 - v. Check top of T-base for level. If not level then foundation must be leveled.
 - b. Top Bolt Procedure
 - i. Erect pole over T-base with crane. Coat bolts, nuts, washers, and lock washers with electrically conductive


- ii. Install bolts and 1/2" connecting washers from the inside of the T-base, thread up through the pole base. Install flat washers, lock washers and nuts snug tight according to Item 447, "Structural Bolting."
- iii. Tighten each nut to 150 ft-lb. using a torque wrench.
- c. Level and Plumb
 - i. Ensure pole is plumb and mast arm is perpendicular to the roadway according to plans to within 5
- 9. Construct luminaire pole foundations in accordance with Item 416, "Drilled Shaft Foundations," and TxDOT standard sheet RID(2).
- 10. Provide and install underpass luminaires in accordance with Item 610, DMS-11010, and TxDOT standard sheet RID(3). Typical luminaire size for underpass luminaires is 150W HPS or 150W EQ LED.
- 11. Mount luminaires on arms level as shown by the luminaire level indicator.
- 12. Orient luminaires perpendicular to the roadway intended to be lit unless otherwise shown on the plans.

Wiring Diagram Notes:


- Use 1/2 in.-13 UNC threaded, copper or tin-plated copper, pole bonding connector, sized appropriately for conductors, bonded to T-base, or use ground lug in handhole as available.
- Use pre-qualified two-pole breakaway connectors for all luminaire pole installations. For luminaires fed by a circuit with a neutral conductor, use double pole breakaway connectors with the neutral side unfused and marked white.
- (3) Split Bolt or other connector.

Decorative LED Lighting Notes:

- 1. LED Drivers in Remote Outdoor enclosures (for drivers that do not include an enclosure as part of a factory assembly):
 - a. Provide NEMA 3R outdoor enclosure or as approved.
 - b. Install enclosure at least 12" above ground or other horizontal surface. Mount vertically or on ceiling, and avoid direct sun where possible.
 - c. Install drivers with at least 2 inches of space from enclosure walls.
 - d. For multiple drivers in an enclosure, provide at least 4 inches side to side and 1 inch end to end from other drivers or electronic equipment
 - e. For drivers mounted on back wall of enclosure, mount enclosure on 1 5/8" strut or other standoff to dissipate heat, or mount driver to side of the enclosure or to the metal cover.
 - f. Provide remote drivers with a maximum of 100 watts
 - g. Provide drivers with documentation of 100,000 hr lifetime at Tcase of 65C or higher.



Driver Spacing In Remote Enclosure



L1, L2 = Hot Conductors G = Grounding Conductor

TYPICAL WIRING DIAGRAM

LUMINAIRES SERVED AT 480V ON 240/480 VOLT SERVICE OR LUMINAIRES SERVED AT 240V FOR 120/240 VOLT SERVICE.



Traffic Safety Division Standard

ROADWAY ILLUMINATION **DETAILS**


RID	(1)	-20
dgn	DN:	CK:

E: rid1-20.dgn	DN:		CK:	DW:		CK:
C)TxD0T January 2007	CONT	SECT	JOB		ніс	HWAY
REVISIONS	0924	06	644		DARR	INGTON
17	DIST		COUNTY			SHEET NO.
20	ELP		EL PAS	SO.		40

No warranty of any for the conversion

is governed by the "Texas Engineering Practice Act". purpose whatseever. TXDT assumes no responsibility nats or for incorrect results or damages resulting from

-AIMER: The use of this standard is made by TXDOT for any



SECTION A-A

SHOWING CONSTANT GRADE

TABLE 1							
ANCHOR BOLTS							
POLE MOUNTING	BOLT C	ANCHOR BOLT					
HEIGHT	Shoe Base	T-Base	SIZE				
<40 ft.	13 in.	14 in.	1in.x 30in.				
40-50 ft.	15 in.	17 ¼in.	1 ¼in. × 30in.				

TABLE 2						
RECOMMENDED FOUNDATION LENGTHS (See note 1)						
MOUNTING HEIGHT	TEXAS CONE PENETROMETER N Blows/ft					
HEIGHT	10	15	40			
<20 ft.	6′	6′	6′			
>20 ft. to 30 ft.	8′	6′	6′			
>30 ft. to 40 ft.	8′	8′	6′			
>40 ft. to 50 ft.	10′	8′	6′			

TABLE 3							
PAY QUANTITY OF RIPRAP PER FOUNDATION (Install only when shown on the plans)							
Foundation Diameter	RIPRAP DIAMETER	RIPRAP (CONC) (CL B)					
30 in.	78 in.	0.35 CY					

POLE MOUNTING	BOLT C	ANCHOR BOLT		
HEIGHT	Shoe Base	T-Base	SIZE	
<40 ft.	13 in.	14 in.	1in.x 30in.	
40-50 ft.	15 in.	17 ¼in.	1 ¼in. x 30in.	

sheets for locations of foundations with more than 2 conduits. Cap unused conduits in foundations on both ends. 9. Conduit location in foundations is critical for breakaway devices. Place

8. Install a minimum of 2 conduits in each foundation. See lighting layout

7. Use 4 hold down and 4 connecting washers on transformer base poles as

recommended by the manufacturer and supplied with base.

1. "Recommended Foundation Lengths" table is for information purposes only. Foundation lengths shall be as shown on the plans, or as directed by the Engineer. Foundations will be paid for under Item 416, "Drilled Shaft

2. Erect roadway illumination assembly poles plumb and true. Form and level

the top 6" of the foundation so the pole will be plumb. Use leveling

transformer bases. Do not grout between baseplate and the foundation.

3. Ensure Class 2A and 2B fit for anchor bolts and nuts. Tap and chase nuts

Concrete for riprap may be upgraded to Class C at no extra cost to the

5. Place riprap around the foundation when called for elsewhere in the plans.

6. Locate breakaway roadway illumination assemblies as shown in the placement

table, unless otherwise dimensioned on the plans. Protect non-breakaway

illumination assemblies from vehicular impact (i.e. 2.5 ft. behind guard rail or mounted on traffic barrier), or located outside the clear zone,

except that 2.5 ft. from curb face is minimum desired for light poles on city streets, 45 mph or less. See Roadway Design Manual for further

4. Use appropriate class of concrete as specified in Items 416 and 432.

after galvanizing. Anchor bolt body with rolled threads need not be full

nuts to plumb shoe base poles. Do not use shims or leveling nuts under

Foundations." unless otherwise shown on the plans.

Riprap will be paid for under Item 432.

electrode which replaces the ground rod.

conduits 2 in. apart on centerline as shown. Bond anchor bolt to rebar cage with #6 bare stranded copper conductor. Use listed mechanical connectors rated for embedment in concrete. The

bonded steel in the foundation creates a concrete encased grounding

Grade earthwork around T-base foundations even with the finished grade as shown in Section A-A to ensure proper function of the breakaway device. Use riprap on T-base foundations that are located on sloped grades, and as shown on the plans for level grades.


TABLE 4 BREAKAWAY POLE PLACEMENT (See note 6) ROADWAY FUNCTIONAL CLASSIFICATION ** POLE OFFSET (DISTANCE TO FACE OF TRANSFORMER BASE) Freeway Mainlanes 15 ft. (minimum and (roadway with full control of access) typical) from lane edge All curbed, 45 mph or less design speed 2.5 ft. minimum (15 ft. desirable) from curb face 10 ft. minimum*(15 ft. desirable) from lane edge All others

GENERAL NOTES:

Department.

information.

- * or as close to ROW line as is practical
- ** provide 2/5 of the luminaire mounting height behind the pole for "falling area" to prevent encroachment on the other travel lanes. See design auidelines.




TETET

- #4 Bars

Template

FOUNDATION DETAIL



ANCHOR BOLT DETAIL

Texas Department of Transportation

Traffic Safety Division Standard

ROADWAY ILLUMINATION **DETAILS** (RDWY ILLUM FOUNDATIONS) RID(2) - 20

FILE: rid2-20.dgn	DN:		CK:	DW:	CK:
© TxDOT January 2007	CONT	SECT	JOB		HIGHWAY
REVISIONS	0924	06	644	DAI	RRINGTON
7-17	DIST		COUNTY		SHEET NO.
12-20	FIP		FI PA	SO.	41

10:51:49

SHIPPING PARTS LIST - POLES AND LUMINAIRE ARMS									
Nominal	Shoe B	ase		T-Bas	е		CSB/SSCB Mounted		
Mounting Ht.	Designation		Ought: tv	Designation		Ought: 4v		Designation	Ought: tv
(f+)	Pole A1 A2	Luminaire	Quantity	Pole A1 A2	Luminaire	Quantity	Pole	A1 A2 Luminaire	Quantity
20	(Type SA 20 S - 4)	(150W EQ) LED		(Type SA 20 T - 4)	(150W EQ) LED	32			
	(Type SA 20 S - 4 - 4)	(150W EQ) LED		(Type SA 20 T - 4 - 4)	(150W EQ) LED				
30	(Type SA 30 S - 4)	(250W EQ) LED		(Type SA 30 T - 4)	(250W EQ) LED		(Type SP 28	S - 4) (250W EQ) LED	
	(Type SA 30 S - 4 - 4)	(250W EQ) LED		(Type SA 30 T - 4 - 4)	(250W EQ) LED		(Type SP 28	S - 4 - 4) (250W EQ) LED	
	(Type SA 30 S - 8)	(250W EQ) LED		(Type SA 30 T - 8)	(250W EQ) LED		(Type SP 28	S - 8) (250W EQ) LED	
	(Type SA 30 S - 8 - 8)	(250W EQ) LED		(Type SA 30 T - 8 - 8)	(250W EQ) LED		(Type SP 28	S - 8 - 8) (250W EQ) LED	
40	(Type SA 40 S - 4)	(250W EQ) LED		(Type SA 40 T - 4)	(250W EQ) LED		(Type SP 38	S - 4) (250W EQ) LED	
	(Type SA 40 S - 4 - 4)	(250W EQ) LED		(Type SA 40 T - 4 - 4)	(250W EQ) LED		(Type SP 38	S - 4 - 4) (250W EQ) LED	
	(Type SA 40 S - 8)	(250W EQ) LED		(Type SA 40 T - 8)	(250W EQ) LED		(Type SP 38	S - 8) (250W EQ) LED	
	(Type SA 40 S - 8 - 8)	(250W EQ) LED		(Type SA 40 T - 8 - 8)	(250W EQ) LED		(Type SP 38	S - 8 - 8) (250W EQ) LED	
	(Type SA 40 S - 10)	(250W EQ) LED		(Type SA 40 T - 10)	(250W EQ) LED		(Type SP 38	S - 10) (250W EQ) LED	
	(Type SA 40 S - 10 - 10)	(250W EQ) LED		(Type SA 40 T - 10 - 10)	(250W EQ) LED		(Type SP 38	S - 10 - 10) (250W EQ) LED	
	(Type SA 40 S - 12)	(250W EQ) LED		(Type SA 40 T - 12)	(250W EQ) LED		(Type SP 38	S - 12) (250W EQ) LED	
	(Type SA 40 S - 12 - 12)	(250W EQ) LED		(Type SA 40 T - 12 - 12)	(250W EQ) LED		(Type SP 38	S - 12 - 12) (250W EQ) LED	
50	(Type SA 50 S - 4)	(400W EQ) LED		(Type SA 50 T - 4)	(400W EQ) LED		(Type SP 48	S - 4) (400W EQ) LED	
	(Type SA 50 S - 4 - 4)	(400W EQ) LED		(Type SA 50 T - 4 - 4)	(400W EQ) LED		(Type SP 48	S - 4 - 4) (400W EQ) LED	
	(Type SA 50 S - 8)	(400W EQ) LED		(Type SA 50 T - 8)	(400W EQ) LED		(Type SP 48	S - 8) (400W EQ) LED	
	(Type SA 50 S - 8 - 8)	(400W EQ) LED	·	(Type SA 50 T - 8 - 8)	(400W EQ) LED		(Type SP 48	S - 8 - 8) (400W EQ) LED	
	(Type SA 50 S - 10)	(400W EQ) LED	·	(Type SA 50 T - 10)	(400W EQ) LED		(Type SP 48	S - 10) (400W EQ) LED	
	(Type SA 50 S - 10 - 10)	(400W EQ) LED	·	(Type SA 50 T - 10 - 10)	(400W EQ) LED		(Type SP 48	S - 10 - 10) (400W EQ) LED	
	(Type SA 50 S - 12)	(400W EQ) LED	·	(Type SA 50 T - 12)	(400W EQ) LED		(Type SP 48	S - 12) (400W EQ) LED	
	(Type SA 50 S - 12 - 12)	(400W EQ) LED		(Type SA 50 T - 12 - 12)	(400W EQ) LED		(Type SP 48	S - 12 - 12) (400W EQ) LED	

		OTH					
	Designation						
Pole	A 1	A2	Luminaire	Quantity			

GENERAL NOTES:

- 1. All work, materials and services not shown on the plans which may be necessary for complete and proper construction shall be performed, furnished and installed by the Contractor. Faulty fabrication or poor workmanship in any material, equipment or installation will be considered justification for rejection. Where manufacturers provide warranties or guarantees as a customary trade practice, furnish to the Department such warranties or guarantees.
- 2. The location of poles and fixtures are diagrammatic only and may be shifted by the Engineer to accommodate local conditions. Install or remove poles and luminaires located near overhead electrical lines using established industry and utility safety practices and in accordance with laws governing such work. Consult with the appropriate utility company prior to beginning such work.
- 3. Standard Steel Pole Designs. Steel poles fabricated in accordance with the details and dimensions shown herein, shall be considered standard designs. Submission of shop drawings and design calculations for standard designs is not required.
- 4. Optional Steel Pole Designs. Multi-sided steel poles may be allowed as optional designs, if steel poles are permitted or required, pending approval by the Department as outlined below.
 - a. Shop Drawings. Optional designs require submission of shop drawings and design calculations bearing the seal of an engineer licensed in the State of Texas, in accordance with Item 441, "Steel Structures."

 The Department may elect to pre-approve some shop drawings for optionally designed poles. Submission of shop drawings and design calculations is not required for structures fabricated in accordance with the details of shop drawings on the pre-approved list maintained by the TxDOT Traffic Operations Division. Any deviation from the pre-approved shop drawings will require submission of shop drawings of the complete assembly and design calculations as described above.
 - design life in accordance with the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals, 6th Edition (2013) and Interim Revisions thereto. All poles shall be designed for 110 mph 3-second gust wind speeds. The Gust Factor, G, and Wind Importance Factor, Ir, shall be applied as per the AASHTO Specifications assuming a 25-year design life. The design wind pressure for hurricane wind velocities greater than 100 mph shall not be less than the design wind pressure using 100 mph with the non-hurricane Wind Importance Factor, Ir, value. For transformer base poles, fabricator shall include transformer base and connecting hardware in design calculations and shop drawing submittals. All transformer bases shall have been structurally tested to resist the theoretical plastic moment capacity of the pole. Certification of the plastic moment load test and FHWA breakaway requirement test of the model of base being furnished shall be submitted with the shop drawings. Shop drawings shall show breakaway base model number, and manufacturer's name and logo. Manufacturer's shop drawings shall include the ASTM designations for all materials to be used.
 - c. Mast Arm Attachments. All poles and attachments shall be structurally designed to support two 12-foot mast arms and luminaires. Poles shall be supplied with mast arm combinations as shown in the plans. Al
 - mast arms shall be designed for a 60-pound luminaire having an effective projected area of 1.6 square feet. d. Anchor Bolt Assembly. Anchor bolt assemblies for optionally designed poles shall be the same as those shown herein.
- 5. Aluminum Pole Designs. Aluminum pole designs may be allowed, if aluminum poles are permitted or required, pending approval by the Department as outlined below.
 - a. Meet all of the requirements stated above for optional steel pole designs and the following:
 1. Aluminum poles shall be fabricated in accordance with "Structural Welding Code-Aluminum" AWS D1.2.

 - Aluminum pole designs shall use the same anchor bolt assembly and be subject to the same geometric restraints and other requirements for steel poles specified herein.
 Aluminum poles shall be equipped with vibration mitigation devices, as approved by the engineer.

 - Pole components shall be constructed using the following material: Shaft: ASTM B221 or B241 Alloy 6063-T6, ASTM B209 Alloy 5086-H34, ASTM B221 Alloy 6005-T5.

 Base Flange: ASTM B26 Alloy 356.0-T6 or ASTM B108 Alloy 356.0-T6 (Yield strength test required).

 Mast Arm Fitting: ASTM B209 Alloy 6061-T6 or ASTM B221 Alloy 6005-T5.

 Mast Arms: ASTM B241 Alloy 6061-T6 or AIIoy 6063-T6.

 Pole Cap: ASTM B209 Alloy 5086-H32 or ASTM B108 or B26 Alloy 356.0-T6.

 Bolts: Stainless Steel AISI 300 series. Bolts threading into aluminum threads shall be treated with
 - anti-seize compound, Never-Seez Compound, Permatex 133K or equal.
- 6. Special Designs. Poles with architectural treatments shall meet the requirements shown elsewhere in the plans.
- 7. Luminaire Mounting Height. Actual luminaire mounting height shall be the nominal mounting height given on RIP(2) for all pole-arm combinations except for poles with 4 ft. luminaire arms, which shall be 3^7-0 " lower than the nominal height, unless otherwise shown or directed.

EXPLANATION OF ROADWAY ILLUMINATION ASSEMBLY DESIGNATIONS

(TYPE SA 50 T - X - X) (400W EQ) LED Pole and mast arm may be steel or-aluminum. ST: Pole and mast arm must be steel AL: Pole and mast arm must be aluminum. Special (ovalized) steel or aluminum pole for installing on CSB or SSCB. See standard sheet CSB (4), or SSCB (4). Two numerical digits denote nominal mounting height in feet. Next letter denotes type of base, (S-Shoe Base, -T-Transformer Base, or B-Bridge/Ret.Wall Mount) First number denotes length of mast arm Use of second mast arm is indicated by second dashed number which denotes length in feet. Luminaire ratina in watts (i.e. 400W). Equivalent wattage LED fixtures will include EQ (i.e. 400W EQ) Last letters indicate light source (S - High Pressure Sodium; LED - LED luminaire)

> ZAHIDUL Q. SIDDIQU 98635

> > CENSE



12/20/2022


ROADWAY ILLUMINATION

C)TxDOT January 2007 JOB HIGHWAY 0924 06 644 DARRINGTON 12-19

SHEET 1 OF 4

Traffic Safety Division Standard

POLES RIP(1) - 19



SHOE BASE POLE

SHOE BASE POLE						
Luminaire Mounting Height (Nominal)(ft)	Base Diameter (in)	Top Diameter (in)	Length (ft)	Pole Thickness (in)	Design Moment (K-ft)	
20.00	7.00	4.90	15.00	0.1196	7.1	
30.00	7.50	4.00	25.00	0.1196	13.2	
31.00-39.00	8.00	4.36-3.24	26,00-34,00	0.1196	20.7	
40.00	8.50	3,60	35,00	0.1196	20.7	
50.00	10.50	4.20	45.00	0.1196	30.3	

See Pole Top Detail, Sheet 3 of 4 1 Simplex Arm Connection 60% of \(\)LP-3 Pole Thickness See Transformer Base Baseplate Detail, Sheet 4 of 4 See Transformer Base Details. Sheet 4 of 4 See Transformer Base Anchor Bolt Assembly Detail,

TRANSFORMER BASE POLE

TRANSFORMER BASE POLE							
Luminaire Mounting Height (Nominal)(ft)	Base Diameter (in)	Top Diameter (in)	Length (ft)	Pole Thickness (in)	Design Moment (K-ft)		
20.00	7.00	5.11	13.50	0.1196	7.1		
30.00	7.50	4.21	23.50	0.1196	13.2		
31.00-39.00	8.00	4.57-3.45	24.50-32.50	0.1196	20.7		
40.00	8.50	3,81	33,50	0.1196	20.7		
50.00	10.00	3.91	43.50	0.1196	30.3		

Top Detail, ~ 1 Simplex Arm Connection Seam Weld located 45° from mast arm axis 60% of Thickness See Handhole Detail, Sheet 3 of 4-Max. , -0" , -6" Oval Sect See Concrete Traffic Barrier 10) Base Baseplate Detail. Sheet 4 of 4 See Concrete Traffic Barrier Base Anchor Bolt Assembly Detail, Sheet 4 of 4

See Pole

CONCRETE TRAFFIC BARRIER BASE POLE

l	CONCRETE TRAFFIC BARRIER BASE POLE (CSB/SSCB)							
I	Luminaire Mountina	Base② Diameter	ter Diameter Length		' Top Longth Pole (K-		Design (K-1	
I	Height (Nominal)(ft)	(in)	(in)	(f+)	(in)	About & of Rail	Perp. to Rail	
I	28.00	9.00	5.78	23.00	0.1196	10.3	13.2	
I	38.00	9.00	4.38	33.00	0.1196	16.6	20.8	
	48.00	10.50	4.48	43.00	0.1345	25.1	30.5	

GENERAL NOTES:

- 1. Designs conform to AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 6th Edition (2013) and Interim Revisions thereto. Design 3-Second Gust Wind Speed equals 110 mph with a 1.14 gust factor. A wind importance factor of 0.80 is applied to adjust the wind speed to a 25 year recurrence interval. Design moments listed in tables assume base of pole is 25' above natural ground level.
- Structures are designed to support two 12' luminaire mast arms and luminaires. Mast arms are designed to support a 60-pound luminaire having an effective projected area of 1.6 square feet.
- 3. Fabrication shall be in accordance with the Specifications and with the details, dimensions, and weld procedures shown herein. Do not submit shop drawings for roadway illumination pole assemblies fabricated in accordance with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of these sheets and the Specifications. In the absence of specified fabrication tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.

- 4. For mounting heights between values shown in the tables, use base diameter and thickness values for the larger height.
- 5. Unless otherwise noted, all steel parts shall be galvanized in accordance with Item 445, "Galvanizing."
- 6. Steel poles shall be fabricated in accordance with Item 441, "Steel Structures." Longitudinal seam welds for pole sections shall have 60% minimum penetration. All welding shall be in accordance with AWS D1.1, Structural Welding Code-Steel.
- 7. Two-section poles joined by circumferential welds will not be permitted, unless otherwise shown on the plans. Poles may be fabricated in two sections and field-assembled by the lap-joint method. The two sections shall telescope together with a lap length of not less than 1-1/2 times the shaft diameter at the lap joint.
- Alternate material equal to or better than material specified may be substituted with the approval of the Engineer.
- Lubricate and tighten anchor bolts, when erecting shoe base poles and concrete traffic barrier base poles, in accordance with Item 449, "Anchor Bolts."

- 10. All poles, except Transformer Base Poles, shall have hand holes with reinforcing frames and covers. For ground mounted shoe base poles, hand holes shall be placed 90 degrees to mast arm unless otherwise noted on the plans. For poles mounted on a concrete traffic barrier with one luminaire arm, hand holes shall be located 180 degrees from luminaire arm. For poles mounted on a concrete traffic barrier with two luminaire arms, all hand holes shall be on the same side of the barrier. For poles mounted on a bridge lighting bracket or a retaining wall lighting bracket, hand hole shall be on traffic side of the pole, at a height that will clear the barrier.
- 11. The finished pole shall have a smooth, uniform finish free of pits, blisters, or other defects. Scratched, chipped, and other damaged galvanized areas on poles and mast arms shall be repaired in accordance with Item 445, "Galvanizing."
- 12. Pole length is based on a 5'-6" luminaire arm rise. 4 ft. luminaire arms have a 2'-6" rise. A pole with 4 ft. luminaire arms will have an actual mounting height 3'-0" less than the nominal mounting height. Increasing the pole length to meet the nominal mounting height is allowed, but unnecessary unless otherwise directed by the engineer.
- 13. Erect transformer base poles in accordance with sheet RID(1).

MATERIAL	DATA	
COMPONENT	ASTM DESIGNATION	MIN. YIELD (ksi)
Pole Shaft (0.14"/ft. Taper)	A572 Gr 50, A595 Gr A, A1011 HSLAS Gr 50 Cl 2 ③, or A1008 HSLAS Gr 50 Cl 2	50
Base Plate and Handhole Frame	A572 Gr.50, or A36	36
T-Base Connecting Bolts	F3125 Gr A325	92
Anchor Bolts	F1554 Gr 55, A193-B7 or A321	55 105
Anchor Bolt Templates	A36	36
Heavy Hex (H.H.) Nuts	A194 Gr 2H,or A563 Gr DH	
Flat Washers	F436	

NOTES:

- (1)2'-6" rise for 4 ft. Luminaire arms.
- ② Before ovalized as shown on Concrete Traffic Barrier Base Baseplate details, Sheet 4 of 4.
- ③ A1011 SS Gr 50 may be used instead of HSLAS, provided the material meets the elongation requirements for HSLAS.

POLE ASSEMBLY FABRICATION TOLERANCES TABLE

IOLERANCES	IADLE
DIMENSION	TOLERANCE
Shaft length	+1"
I.D. of outside piece of slip fitting pieces	+1/8", -1/16"
O.D. of inside piece of slip fitting pieces	+1/32", -1/8"
Shaft diameter: other	+3/16"
Out of "round"	1/4"
Straightness of shaft	±1/4" in 10 ft
Twist in multi-sided shaft	4° in 50 ft
Perpendicular to baseplate	1/8" in 24"
Pole centered on baseplate	±1/4"
Location of Attachments	±1/4"
Bolt hole spacing	±1/16"

SHEET 2 OF 4




Traffic Safety Division Standard

ROADWAY ILLUMINATION POLES

RIP(2)-19

FILE: rip-19.dgn	DN:		CK:	DW:	CK:
© TxDOT January 2007	CONT	SECT	JOB		HIGHWAY
REVISIONS	0924	06	644	D/	ARRINGTON
7-17 12-19	DIST		COUNTY		SHEET NO.
12 13	ELP		EL PA	SO.	43


738



LUMINAIRE ARM

LUMINAIRE ARM DIMENSIONS						
Nominal Arm Length	Arm Length	Rise				
4′-0"	3′-6"	2'-6"				
6'-0"	5′-6"	5′-6"				
8'-0"	7′-6"	5′-6"				
10'-0"	9′-6"	5′-6"				
12'-0"	11′-6"	5′-6"				

ARM ASSEMBLY FABRICATION TOLERANCES TABLE						
DIMENSION	TOLERANCE					
Arm Length	±1"					
Arm Rise	±1"					
Deviation from flat	1/8" in 12"					
Spacing between holes	±1/32"					



-½" Dia. x 1½" A325 Bol+®

-Lock Washer®

 $\sqrt{2}$ LA-3

Тур

Gusset Plate

Arm Simplex Pole Simplex

UPPER SIMPLEX FITTING


LOWER SIMPLEX FITTING (Gusset not shown for clarity)

SECTION B-B

(Gusset not shown for clarity)

Lip

Тур




ARM SIMPLEX DETAIL 9


5" Approx.

NOTES:

- (4) Any of the materials listed for plates may be used where the drawings do not specify a particular ASTM designation.
- (5) A576 must be suitable for forging and also meet minimum tensile strength of 65 ksi, minimum yield of 35 ksi, and elongation in 2 inches of 22 percent.
- (6) A572, A1008 HSLAS-F, and A1011 HSLAS-F materials may have higher yield strengths but shall not have less elongation than the grade indicated.
- (7) Dimensional limits are given to show acceptable variation in design. All of a Fabricator's production of a particular arm length shall have the same dimensions within specified tolerances.
- 8 Each pole simplex fitting shall be supplied with 2 bolts and 2 lock washers of the size specified. The bolts and lock washers shall be secured to the pole with the other hardware items called for in the plans.
- Proposed deviations in arm simplex dimensions or materials must be submitted to the Department for approval.
- (10) A welded handhole frame is permissible. Maximum of two (2) CJP weld splices is allowed.


MATERIALS				
Pole or Arm Simplex	ASTM A27 Gr 65-35 or Gr 70-36, A148 Gr 80-50, A576 Gr 1021⑤,or A36 (Arm only)			
Arm Pipes	ASTM A53 Gr A or B,A500 Gr B, A501, A 1008 HSLAS-F Gr 50 (6), or A1011 HSLAS-F Gr 50 (6)			
arm Struts and Gusset Plates (4)	ASTM A36,A572 Gr 50 ⑥, or A588			
Misc.	ASTM designations as noted			







SECTION C-C

SIMPLEX ATTACHMENT DETAIL



SIDE





SHEET 3 OF 4



ROADWAY ILLUMINATION POLES


RIP(3)-19

Traffic Safety Division Standard

ı	FILE: rip-19.dgn	DN:		CK:	DW:		CK:
ı	© TxDOT January 2007	CONT	SECT	JOB		HIC	SHWAY
4	REVISIONS	0924	06	644	D	ARR:	INGTON
ı	7-17 12-19	DIST		COUNTY			SHEET NO.
	12 13	ELP		EL PA:	SO		44


POLE TOP

HANDHOLE




SHOE BASE BASEPLATE

SHOE BASE BASEPLATE TABLE								
MOUNTING HEIGHTS (nominal)	BOLT CIRCLE	SQUARE	THICK	BOLT HOLE DIAMETER				
20'- 39'	13"	13"	1 1/4"	1 1/4"				
40′	15"	15"	1 1/4"	1 1/2"				
50′	15"	15"	1 1/2 "	1 1/2"				




SHOE BASE ANCHOR BOLT ASSEMBLY

SHOE BASE ANCHOR BOLT ASSEMBLY TABLE						
MOUNTING HEIGHTS (nominal)	A.B. Dia.	BOLT CIRCLE DIAMETER	CTR. HOLE DIAMETER	BOLT HOLE DIAMETER		
20′-39′	1 "	13"	11"	1 1/16 "		
40'-50'	1 1/4"	15"	12 1/2"	1 1/6 "		




CONCRETE TRAFFIC BARRIER BASE BASEPLATE

	NCRETE TRA BASE BASEP		
MOUNTING HEIGHTS (nominal)	POLE DIA.	DIM. A	DIM. B
28'- 38'	9"	7"± 1/4"	10"± 1/4"
48′	13"± 1/4"		




CONCRETE TRAFFIC BARRIER BASE ANCHOR BOLT ASSEMBLY

TRANSFORM	ER BA	SE ANCHO	OR BOLT AS	SEMBLY TABLE
MOUNTING HEIGHTS (nominal)	A.B. Dia.	BOLT CIRCLE DIAMETER	CTR. HOLE DIAMETER	BOLT HOLE DIAMETER
20' - 39'	1 "	14"	12"	1 1/16 "
40' - 50'	1 1/4"	17 1/4"	14 ¾"	1 % "





$\frac{TRANSFORMER}{BASE\ BASEPLATE}$


	TRANSFORMER BASE BASEPLATE TABLE							
MOUNTING HEIGHTS (nominal)	BOLT CIRCLE	SQUARE	THICK	CONNECTING BOLT DIA.	BOLT HOLE DIAMETER	TRANSFOMER BASE TYPE		
20' - 39'	13"	13"	1 1/4"	1"	1 1/4"	Α		
40′	15"	15"	1 1/4"	1 1/4"	1 1/2"	В		
50′	15"	15"	1 1/2"	1 1/4"	1 1/2"	В		




TRANSFORMER BASE ANCHOR BOLT ASSEMBLY












TOP PLAN



ANCHOR BOLT FABRICATION

TOLERANCES TABLE

DIMENSION TOLERANCE

Length ± 1/2 "

Threaded length ± 1/2 "

Galvanized length (if required) - 1/4 "

Access Door
Approx. 9"x 11"

Door Fastener

/4"-20UNC x 1"
Lg. S. S. Hex
Head Bolt
W/ Clip

Transformer
Base

I/2"-13UNC
Tapped thru
hole for
grounding

See
Detail A

ELEVATION

TRANSFORMER BASE DETAILS


For mounting heights between those shown in the table, use the values in the table for the larger mounting height. All breakaway bases shall meet the breakaway.

GENERAL NOTES:

- 2. All breakaway bases shall meet the breakaway requirements of the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals, 6th Edition (2013) and Interim Revisions thereto, and shall have been tested by FHWA-approved methods. All bases shall have been structurally tested to resist 150% of the design moment.
- 3. Transformer bases shall be cast from aluminum, ASTM B108 or B26 Alloy 356.0-T6, or other material approved by the Engineer. Four Hex Head (H.H.) bolts with four H.H. nuts, four lock washers, four flat washers, and connecting and hold-down washers as recommended by the manufacturer, galvanized to ASTM A153 Class C or D, or B695 Class 50, shall be provided with each transformer base for connecting the pole. Bolts shall be ASTM A325 or approved equal. Nuts shall be ASTM A563 grade DH galvanized.
- 4. Bases shall be stamped, incised or by other approved permanent means, marked to show fabricator's name or logo, and model number. Such information shall be placed in a readily seen location, inside or outside the base, but shall not be placed on the door.
- 5. Doors for transformer bases shall be made of plastic, fiberglass or other non-metallic material approved by the Engineer and shall be attached with stainless steel screws or bolts. Transformer bases shall be cleaned by grit blast cleaning after heat treatment. Certification by the manufacturer of heat treatment shall be furnished with transformer bases. The certification shall show the metal alloy and temper and that the base meets those requirements, chemical and physical. The certification shall also show the material ASTM specification. Transformer bases shall be cast with a removable tab bar for material testing. Some bars may have been removed by the manufacturer for testing.

NOTES:

- Anchor Bolt Templates do not need to be galvanized.
- 12 Pole diameter before ovalized.



ROADWAY
ILLUMINATION
POLES

Traffic Safety Division Standard

RIP(4)-19

	FILE: rip-19.dgn	DN:		CK:	DW:		CK:
	© TxDOT January 2007	CONT	SECT	JOB		HIC	CHWAY
	REVISIONS	0924	06	644	D	ARR:	INGTON
ı	7-17 12-19	DIST		COUNTY			SHEET NO.
	12 13	ELP		EL PA:	SO		45

73D

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

0924-06-644

1.2 PROJECT LIMITS:

From: ALBERTON AVE

To: 0.04 MI S OF LTV RD/CLARET CUP PL

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 31.6687419 ,(Long) -106.1896384

,(Long) 1001100

END: (Lat) 31.6533687 ,(Long) -106.1781140

1.4 TOTAL PROJECT AREA (Acres): 18.9

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.89

1.6 NATURE OF CONSTRUCTION ACTIVITY:

INSTALL DRILLED SHAFTS FOR ILLUMINATION POLES INSTALL CONDUIT BY BORE OR TRENCH

1.7 MAJOR SOIL TYPES:

Soil Type	Description
SAND	FINE TO MEDIUM, GRAVELY, SILTY, CLAYEY

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

PSLs determined during preconstruction meeting

□ PSLs determined during construction

X No PSLs planned for construction

Туре	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

X Mobilization

X Install sediment and erosion controls

☐ Blade existing topsoil into windrows, prep ROW, clear and grub

Remove existing pavement

Grading operations, excavation, and embankment

☐ Excavate and prepare subgrade for proposed pavement widening

☐ Remove existing culverts, safety end treatments (SETs)

□ Remove existing metal beam guard fence (MBGF), bridge rail

☐ Install proposed pavement per plans

☐ Install culverts, culvert extensions, SETs

☐ Install mow strip, MBGF, bridge rail

☐ Place flex base

☐ Rework slopes, grade ditches

☐ Blade windrowed material back across slopes

☐ Revegetation of unpaved areas

☐ Achieve site stabilization and remove sediment and erosion control measures

□ Other:

□ Other:

Other:

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- □ Sediment laden stormwater from stormwater conveyance over disturbed area
- X Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- □ Solvents, paints, adhesives, etc. from various construction
- ☐ Transported soils from offsite vehicle tracking
- ★ Construction debris and waste from various construction activities
- □ Contaminated water from excavation or dewatering pump-out water
- X Sanitary waste from onsite restroom facilities
- X Trash from various construction activities/receptacles
- ☐ Long-term stockpiles of material and waste

□ Other:	i	

Other:			

Othor		
Other:		

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
RUNOFF PLUS SURROUNDING WATERSHED TO BE HANDLED PRIMARILY BY SURFACE FLOWS DISCHARGING IN TO CATCH BASINS CONVEYED BY CULVERTS	RIO GRANDE, LOCATED APPROX. 6 MILES SW OF THE PROJECT
* Add (*) for impaired waterhodies	with pollutant in ()

1.12 ROLES AND RESPONSIBILITIES: TxDOT

X Development of plans and specifications

X Perform SWP3 inspections

X Maintain SWP3 records and update to reflect daily operations

∪ Otner:			

□ Other:	

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

X Day To Day Operational Control

□ Other:

X Maintain schedule of major construction activities

X Install, maintain and modify BMPs

□ Other:	•



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)



Sheet 1 of 2

Texas Department of Transportation

FED. RD. DIV. NO.		SHEET NO.					
STATE		STATE DIST.	COUNTY				
TEXA	S	ELP	EL PASO				
CONT.		SECT.	JOB	HIGHWAY NO.			
0924		06	644	DARRINGTON			

^{*} Add (*) for impaired waterbodies with pollutant in ().

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:
T / P Protection of Existing Vegetation Vegetated Buffer Zones Soil Retention Blankets Geotextiles Mulching/ Hydromulching Soil Surface Treatments Temporary Seeding Permanent Planting, Sodding or Seeding
 Biodegradable Erosion Control Logs Rock Filter Dams/ Rock Check Dams Vertical Tracking
 □ Interceptor Swale □ Riprap □ Diversion Dike □ Temporary Pipe Slope Drain
 Embankment for Erosion Control Paved Flumes Other:
□ Other: □ Other: □ Other:
2.2 SEDIMENT CONTROL BMPs:
 □ Sandbag Berms □ Sediment Control Fence □ Stabilized Construction Exit □ Floating Turbidity Barrier
□ Vegetated Buffer Zones□ Vegetated Filter Strips□ Other:
Other:
Refer to the Environmental Layout Sheets/ SWP3 Layout Shee

located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Typo	Stat	tioning
Туре	From	То
NONE		
Refer to the Environmental Layo		3 Layout Sheets

located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

Excess dirt/mud on road removed daily

☐ Haul roads dampened for dust control
□ Loaded haul trucks to be covered with tarpaulin
□ Stabilized construction exit
□ Other:
□ Other:
Other:
□ Othor:

2.5 POLLUTION PREVENTION MEASURES:

Chemical Management	
Concrete and Materials Waste Management	
Debris and Trash Management	
Dust Control	
Sanitary Facilities	
Other:	
Other:	

2.6 VEGETATED BUFFER ZONES:

☐ Other:

□ Other:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Turna	Stati	oning
Туре	From	То
NONE		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



STORMWATER POLLUTION **PREVENTION PLAN (SWP3)** (Less Than 1 Acre)



Sheet 2 of 2

Texas Department of Transportation

FED. RD. DIV. NO.		SHEET NO.					
STATE		STATE DIST.	COUNTY				
TEXA	S	ELP	EL PASO				
CONT.		SECT.	JOB	HIGHWAY NO.			
0924		06	644	DARRINGTON			



FLOW ADDITIONAL UPSTREAM -STAKES FOR HEAVY RUNOFF EVENTS SECURE END_ OF LOG TO STAKE AS DIRECTED TEMP. EROSION-CONTROL LOG MIN (TYP. COMPOST CRADLE UNDER EROSION CONTROL LOG SECTION A-A

TEMP. EROSION CONTROL LOG STAKE LOG ON DOWNHILL SIDE AT THE CENTER, AT EACH END, AND AT ADDITIONAL POINTS AS NEEDED TO SECURE LOG (4' MAX. SPACING), OR AS DIRECTED BY THE ENGINEER. PLAN VIEW

STAKE LOG ON DOWNHILL

R.O.W.

SIDE AT THE CENTER.

AT EACH END, AND AT

ADDITIONAL POINTS AS

NEEDED TO SECURE LOG

AS DIRECTED BY THE

ENGINEER.

(4' MAX. SPACING), OR

ADDITIONAL UPSTREAM

STAKES FOR HEAVY

RUNOFF EVENTS

FLOW ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE AS DISTURBED AREA DIRECTED BACK OF CURB -LIP OF GUTTER STAKE ON DOWNHILL SIDE OF TEMP. EROSION LOG AT 8' (ON CENTER) MAX. CONTROL LOG AS NEEDED TO SECURE LOG, OR AS DIRECTED BY THE ENGINEER.

PLAN VIEW


-TEMP. EROSION

COMPOST CRADIT


UNDER EROSION


CONTROL LOG

CONTROL LOG



PLAN VIEW





GENERAL NOTES: 1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S

2. LENGTHS OF EROSION CONTROL LOGS SHALL

UNLESS OTHERWISE DIRECTED, USE

BIODEGRADABLE OR PHOTODEGRADABLE

USE RECYCLABLE CONTAINMENT MESH.

STAKES SHALL BE 2" X 2" WOOD OR

THE PURPOSE INTENDED.

ENGINEER.

DEFORMATION.

THE ENGINEER.

MESH.

MINIMUM

COMPACTED

DIAMETER

RECOMMENDATIONS, OR AS DIRECTED BY THE

BE IN ACCORDANCE WITH MANUFACTURER'S

RECOMMENDATIONS AND AS REQUIRED FOR

CONTAINMENT MESH ONLY WHERE LOG WILL

REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS.

FILL LOGS WITH SUFFICIENT FILTER MATERIAL

TO ACHIEVE THE MINIMUM COMPACTED DIAMETER

SPECIFIED IN THE PLANS WITHOUT EXCESSIVE

#3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT

SANDBAGS USED AS ANCHORS SHALL BE PLACED

ON TOP OF LOGS & SHALL BE OF SUFFICIENT

6. DO NOT PLACE STAKES THROUGH CONTAINMENT

7. COMPOST CRADLE MATERIAL IS INCIDENTAL &

WILL NOT BE PAID FOR SEPARATELY.

2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY




EROSION CONTROL LOG DAM



LEGEND

- CL-D - EROSION CONTROL LOG DAM
- —(cl-boc)— Erosion control log at back of curb
- EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY (CL-ROW)
- EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING -(CL-SST
- EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING -(CL-SSL
- CL-DI - EROSION CONTROL LOG AT DROP INLET
- (CL-CI -EROSION CONTROL LOG AT CURB INLET
- EROSION CONTROL LOG AT CURB & GRATE INLET CL-GI)



SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB

. CL - BOC

REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

The drainage area for a sediment trap should not exceed Log Traps: 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets
- 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.



SHEET 1 OF 3



MINIMUM

COMPACTED DIAMETER


TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

EROSION CONTROL LOG

EC(9) - 16

FILE: ec916	DN:TxDOT CK: KM DW: LS/PT CK: [ck: LS			
C TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0924	06	644		DARRINGTO	
	DIST		COUNTY			SHEET NO.
	FLP		FI PAS	SO.		48






EL PASO

SECURE END OF LOG TO STAKE AS

TEMP. EROSION-

FLOW

CONTROL LOG



TEMPORARY EROSION CONTROL LOG USE STAKES ON DOWNSTREAM SIDE OF LOGS, AT ENDS, MIDPOINT, & AS NEEDED OR SANDBAGS TO HOLD IN PLACE. SANDBAG EROSION CONTROL LOG AT CURB & GRADE INLET

EROSION CONTROL LOG AT DROP INLET


CURB AND GRATE INLET

OVERLAP ENDS TIGHTLY 24" MINIMUM

---- FLOW

-STAKE OR USE SANDBAGS ON DOWNHILL SIDE OF LOG AS NEEDED TO HOLD IN PLACE (TYPICAL)


COMPLETELY SURROUND
DRAINAGE ACCESS TO
AREA DRAIN INLETS WITH
EROSION CONTROL LOG




EROSION CONTROL LOG AT CURB INLET

EROSION CONTROL LOG AT CURB INLET





NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



SANDBAG DETAIL



-CURB INLET

_INLET EXTENSION

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

> **EROSION CONTROL LOG** EC(9)-16

FILE: ec916	DN: TxDOT		ck: KM	DW: L	.S/PT	ck: LS
C TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0924	06	644		DARR	INGTON
	DIST		COUNTY			SHEET NO.
	L L		EL DAG			- F A