

DESIGN SPEED = REFER TO PROJECT LAYOUT SHEET
 A. D. T. (2021) = REFER TO PROJECT LAYOUT SHEET
 A. D. T. (2041) = REFER TO PROJECT LAYOUT SHEET

CONT	SECT	JOB	HIGHWAY
0014	06	045, ETC	SH 81, ETC
DIST	COUNTY		SHEET NO.
WAC	HILL, ETC		1

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT: BR 2023(500), ETC

HILL COUNTY, ETC SH 81, ETC

LIMITS: FROM AT LITTLE HACKBERRY CREEK TO (STR #077), ETC.

LOCATION	HIGHWAY	ROADWAY	BRIDGE	TOTAL
CSJ: 0014-06-045	SH 81	400.00 FT. = 0.076 MI.	150.00 FT. = 0.028 MI.	550.00 FT. = 0.104 MI.
CSJ: 0014-06-046	SH 81	400.00 FT. = 0.076 MI.	110.00 FT. = 0.021 MI.	510.00 FT. = 0.097 MI.
CSJ: 0162-01-104	US 84	400.00 FT. = 0.076 MI.	397.50 FT. = 0.075 MI.	797.50 FT. = 0.151 MI.

FOR THE CONSTRUCTION OF BRIDGE MAINTENANCE CONSISTING OF BRIDGE MAINTENANCE

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS

SUBMITTED FOR LETTING 12/20/2022

Gregg A. Hostetler

REGG A. HOSTETLER, P.E.
 CONSOR ENGINEERS
 TBPE FIRM NO. F-12040

LOCATION 02


HWY: SH 81
 BEGIN PROJECT
 CSJ 0014-06-046
 STA. 587+85.00
 RM 524+59.00
 END PROJECT
 CSJ 0014-06-046
 STA. 592+95.00
 RM 634+64.00

LOCATION 03

HWY: SH 81
 BEGIN PROJECT
 CSJ 0014-06-045
 STA. 712+60.00
 RM 630+07.00
 END PROJECT
 CSJ 0014-06-045
 STA. 718+10.00
 RM 741+64.00

LOCATION 01

HWY: US 84
 BEGIN PROJECT
 CSJ 0162-01-104
 STA. 317+03.15
 RM 228+33.15
 END PROJECT
 CSJ 0162-01-104
 STA. 325+00.65
 RM 345+24.65



EXCEPTIONS: N/A
 EQUATIONS: N/A
 RAILROAD CROSSINGS: N/A



RECOMMENDED FOR LETTING 12/21/2022

DocuSigned by:
Josh Voiles
 AC8604F84EC2483...
 AREA ENGINEER

RECOMMENDED FOR LETTING 12/29/2022

Uita Yankel, P.E.

DIRECTOR OF TRANSPORTATION PLANNING & DEVELOPMENT

APPROVED FOR LETTING 12/29/2022

DocuSigned by:
Stanley Swiatek
 B69BD796DD564C9...
 DISTRICT ENGINEER

DATE: 12/20/2022 2:19:34 PM
 FILE: P:_v-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\dgn\02_Plan Files\01_genera\I+I+le_Sheet.dgn
 COUNTY: HILL PROJ. NO.:
 HWY. NO.: SH 81 LETTING DATE:
 DATE ACCEPTED:

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHMA 1273, JULY 2022)

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
<u>GENERAL</u>	
1	TITLE SHEET
2	INDEX OF SHEETS
3	PROJECT LAYOUT
4-7	TYPICAL SECTIONS
8, 8A-8F	GENERAL NOTES
9, 9A	ESTIMATE & QUANTITY SHEETS
10-11	SUMMARY OF QUANTITIES
<u>TRAFFIC CONTROL PLAN</u>	
12-14	TRAFFIC CONTROL PLAN TYPICAL SECTIONS
15-17	TRAFFIC CONTROL PLAN NARRATIVE
18-21	PHASE 1 TRAFFIC CONTROL PLAN LAYOUT
22-26	PHASE 2 TRAFFIC CONTROL PLAN LAYOUT
27	CRASH CUSHION SUMMARY SHEET
<u>TRAFFIC CONTROL PLAN STANDARDS</u>	
## 28-39	BC (1)-21 THRU BC (12)-21
## 40	ABSORB (M) -19
## 41	SLED-19
## 42	SLEDMINI-19
## 43	TCP (1-1)-18
## 44	TCP (1-5)-18
## 45	TCP (2-1)-18
## 46	TCP (2-2)-18
## 47	TCP (2-6)-18
## 48	TCP (2-8)-18
## 49	TCP (3-1)-13
## 50	TCP (3-2)-13
## 51	TCP (3-3)-14
## 52	TCP (7-1)-13
## 53	WZ (STPM) -13
## 54	WZ (UL) -13
## 55	WZ (RS) -22
<u>ROADWAY STANDARDS</u>	
## 56	BED-14
## 57-58	GF (31) TR TL3-20
## 59	GF (31) -19
## 60	GF (31) MS-19
## 61	SGT (15) 31-20
## 62	SGT (11S) 31-18
## 63	SGT (12S) 31-18
<u>BRIDGE</u>	
64-65	BRIDGE REPAIR LAYOUT
66	SUBSTRUCTURE REPAIR
67-68	BRIDGE REPAIR LAYOUT
69	SUBSTRUCTURE REPAIR
70-71	BRIDGE REPAIR LAYOUT
72	SUBSTRUCTURE REPAIR
<u>BRIDGE DETAILS</u>	
73	BRIDGE SPALL REPAIR DETAILS
74	CLEANING AND SEALING EXISTING BRIDGE JOINTS
75	RETROFIT TRAFFIC RAIL T552 (MOD)
76	BRIDGE APPROACH SLAB (MOD)
<u>BRIDGE STANDARDS</u>	
## 77	BAS-A
## 78-79	CSAB
## 80-81	SRR
## 82-83	TYPE T552
<u>PAVEMENT MARKING</u>	
84-89	PAVEMENT MARKING LAYOUT
<u>PAVEMENT MARKING STANDARDS</u>	
## 90-95	D&OM (1)-20 THRU D&OM (6)-20
## 96	D&OM (VIA) -20
## 97-98	PM (1)-20 THRU PM (2)-20

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
99-104	STORMWATER POLLUTION PREVENTION PLAN (SWP3) (LESS THAN 1 ACRE)
105-107	SW3P LAYOUT
108	EPIC
<u>ENVIRONMENTAL ISSUES STANDARDS</u>	
** 109	EC (1)-16
** 110	EC (2)-16
** 111-120	TA-BMP (WACO DISTRICT STANDARDS)



Alfonso D. Perez
12/20/2022

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET ** HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

ALFONSO D. PEREZ 12/20/2022
NAME DATE



Kenneth E. Gottleaber
12/20/2022

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET ** HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

KENNETH E. GOTTLAEBER 12/20/2022
NAME DATE

NO.	DATE	REVISION	APPROV.



INDEX OF SHEETS

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT			SHEET NO.
6	TEXAS	BR 2023(500), etc.			2
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILL, ETC	0014	06	045, ETC	SH 81, ETC

LOCATION 02


HWY: SH 81
 BEGIN PROJECT
 CSJ 0014-06-046
 STA. 587+85.00
 RM 524+59.00
 END PROJECT
 CSJ 0014-06-046
 STA. 592+95.00
 RM 634+64.00

LOCATION 03

HWY: SH 81
 BEGIN PROJECT
 CSJ 0014-06-045
 STA. 712+60.00
 RM 630+07.00
 END PROJECT
 CSJ 0014-06-045
 STA. 718+10.00
 RM 741+64.00

LOCATION 01

HWY: US 84
 BEGIN PROJECT
 CSJ 0162-01-104
 STA. 317+03.15
 RM 228+33.15
 END PROJECT
 CSJ 0162-01-104
 STA. 325+00.65
 RM 345+24.65



SCALE: NTS



Alfonso D. Perez 12/20/2022

NO.	DATE	REVISION	APPROV.



F-12040



PROJECT LAYOUT





SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	3		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

LOCATION	STRUCTURE ID	FACILITY CARRIED	FACILITY CROSSED	LOCATION	LATTITUDE	LONGITUDE	DESIGN SPEED	ADT (2021)	ADT (2041)
01	09-161-0-0162-01-008	US 84	TEHUACANA CREEK RELIEF	US 84 WB LANES	31.6245	-97.0356	75 MPH	16,060	22,484
02	09-110-0-0014-06-075	SH 81	LOVELACE CREEK	SH 81 NB & SB LANES	32.09223	-97.12821	75 MPH	1,722	2,411
03	09-110-0-0014-06-077	SH 81	LITTLE HACKBERRY CREEK	SH 81 NB & SB LANES	32.05849	-97.12169	70 MPH	1,853	2,594

LEGEND

➔ TRAFFIC ARROW



SCALE: NTS



12/20/2022




TYPICAL SECTIONS
TEHUACANA CREEK
09-161-0162-01-008

SHEET 1 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		4
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ETC


LEGEND

→ TRAFFIC ARROW




PROPOSED TYPICAL SECTION
US 84
CSJ: 0162-01-104
STA. 317+03.15 TO STA. 318+63.15
&
STA. 323+40.00 TO STA. 325+00.65

PROPOSED
2" HMAC
OVERLAY



PROPOSED TYPICAL SECTION
US 84
CSJ: 0162-01-104
STA. 318+63.15 TO STA. 318+82.13
&
STA. 323+20.88 TO STA. 323+40.00

PROPOSED
2" HMAC
OVERLAY




PROPOSED TYPICAL SECTION
US 84
CSJ: 0162-01-104
STA. 318+82.13 TO STA. 319+03.15
&
STA. 323+00.65 TO STA. 323+20.88

EXISTING T-BEAMS
EXISTING ABUTMENT WALL

PROPOSED
UNDERSEAL
COURSE

PROPOSED
2" HMAC
OVERLAY



PROPOSED BRIDGE TYPICAL SECTION
US 84
CSJ: 0162-01-104
STA. 319+03.15 TO STA. 323+00.65

EXISTING T-BEAMS

PROPOSED
2" HMAC
OVERLAY

SCALE: NTS



12/20/2022



TYPICAL SECTIONS
TEHUACANA CREEK
09-161-0162-01-008





SHEET 2 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	5
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO.	JOB NO. HIGHWAY NO.
WAC	HILLETC	0014 06	045.ETC SH 81, ETC

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\CADD\dgn\01_Master_Design_Files\Prime\TYPTYP01-1.dgn
 2:58:35 PM
 12/20/2022

LEGEND

→ TRAFFIC ARROW



SCALE: NTS



Alfonso D. Perez 12/20/2022

NO.	DATE	REVISION	APPROV.







TYPICAL SECTIONS
 LOVELACE CREEK
 09-110-0-014-06-075

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		6	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

LEGEND

→ TRAFFIC ARROW



SCALE: NTS



Alfonso D. Perez
 12/20/2022

NO.	DATE	REVISION	APPROV.



F-12040



© 2023

TYPICAL SECTIONS
 LITTLE HACKBERRY CREEK
 09-110-0-0014-06-077

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		7	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

BASIS OF ESTIMATE TABLES

Table 6: Basis of Estimate for Asphalt Pavements				
Item	Description	Rate	Basis	Quantities
3076	DENSE-GRADED HOT MIX ASPHALT			
	TY-C PG 70-22 (EXEMPT)	110 LB / SY / IN	8,901 SY	979 TON

Table 7: Basis of Estimate for Interlayer Material				
Item	Description	Rate	Basis	Quantities
3085	UNDERSEAL COURSE	0.25 GAL / SY	8,901 SY	2,226 GAL
	FOR CONTRACTORS INFORMATION			
	SPRAY APPLIED MEMBRANE	0.20 GAL / SY	8,901 SY	1,780 GAL
	TRAIL	0.20 GAL / SY	8,901 SY	1,780 GAL
	ASPH (AC-15P, AC-20XP, AC10-2TR, AC-12-5TR)	0.25 GAL / SY	8,901 SY	2,226 GAL
AGGR (TY-PD GR-5 OR TY-PL GR-5) (SAC-B)	1 CY / 150 SY	8,901 SY	60 CY	

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 0.0 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The Contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the Engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

Contractor questions on this project are to be emailed to the Waco District at the following address:

Bill Compton - Wacoprebid@txdot.gov, 254-867-2770, 100 S. Loop Dr., Waco, TX
 Carmen Chau - Wacoprebid@txdot.gov, 254-867-2794, 100 S. Loop Dr., Waco, TX

Or Via phone or in person to the following individual(s):
 Area Engineer's: Josh Voiles, P.E. (254) 582-5432
 Assistant Area Engineer's: Anel Rivera, P.E. (254) 582-5432

All Contractor questions will be reviewed by the Area Engineer or Assistant Area Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:
[https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20 Responses/](https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/)

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

For Q&A's on Proposals navigate to:
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>.
 Use the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

GENERAL NOTES

The following standard detail sheets have been modified:

Bridge Approach Slab (MOD)

Retrofit Traffic Rail T552 (MOD)

ITEM 5: CONTROL OF THE WORK

Provide the Engineer with a weekly work schedule of planned activities including anticipated quantities of materials to be placed daily (CY of each concrete placement, tons of HMAC to be placed daily, etc.). Schedules will be provided for the following week as part of each week's project meetings or by 5PM on Thursday as approved by the Engineer. Failure to provide notifications are required here may be deemed as insufficient notice per item 5.10.

Provide the Engineer Daily by 3PM the planned activities for the following day including location, quantities of materials to be placed, etc. in a format acceptable to the Engineer.

Submit all fabrication and shop drawings per TxDOT's online shop drawing submittal system and copy the Area Engineer on the email submittal, unless otherwise directed.

Where a precast or cast-in-place concrete element is shown in the plans, Contractor may submit a precast concrete alternate in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at:

<https://www.txdot.gov/inside-txdot/forms-publications/consultants-Contractors/publications/bridge.html#design>.

Acceptance or denial of an alternate is at the sole discretion of the Department. Contractor is responsible for impacts to the project schedule and cost resulting from the use of alternates.

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (254)867-2808 for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (254)867-2726 for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

ITEM 6: CONTROL OF MATERIALS

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

References to manufacturer's trade name or catalog numbers are for the purpose of identification only and the Contractor will be permitted to furnish like materials of other manufacturers provided they are of equal quality and comply with specifications for this project.

This project has a structures with surface coatings which contain hazardous constituent which is asbestos concrete coating. Contractor is responsible for the health and safety of his employees and compliance with all OSHA standards and regulations.

ITEM 7: LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

If utilizing private property for waste disposal sites, field office sites, equipment storage sites or for any other purpose involved with this project, provide to the Engineer written proof of the property owner's approval of the use of this property. This proof may be in the form of a letter or agreement signed by the property owner or other documents acceptable to the Engineer. Provide such proof prior to occupying the site.

Personal vehicles of the Contractor's employees will not be parked within the right of way at any time including any section closed to public traffic, unless the vehicle is being utilized for construction procedures. However, the Contractor's employees may park on the right of way at the sites where the Contractor has his office, equipment and materials storage yard.

The Contractor is alerted to the possible presence of swallows under the existing bridges or culverts. Because the migratory bird treaty act prohibits harm to swallows, their eggs or their nestlings, the Contractor will not begin potentially disturbing activities on or near the bridge until the birds have abandoned any occupied nests (approximately September 1). Active nests may not be removed regardless of the date.

Prior to the swallows returning to the nests (approximately March 1), abandoned nests will be removed from the bridge. The Contractor will prevent the establishment of new nests on any portion of the structure. Methods for preventing the establishment of new nests must be approved by the Engineer. Examples of acceptable nest prevention methods are bird-deterrent netting and bird-repelling sprays and/or gels to be applied to the structure. This work will not be paid for directly, but will be subsidiary to the various bid items. No relief or compensation will be considered for project delays due the Contractors in attention / in action to preventing nesting or for nesting already underway at the commencement of work.

Notify the Engineer in writing a minimum of 7 days in advance of opening any bridge structure to public use, to allow the Engineer an opportunity to conduct a safety assessment prior to opening.

The Contractor will submit detailed site-specific plans for work in each “water of the United States” designated on the EPIC sheet. These plans must be approved by the Engineer prior to starting any work in these areas. The plans must also describe facilities and work activities adjacent the Ordinary High-Water Marks. The plan must show actual dimensions and materials for:

- Proposed construction roads and work areas leading to or in close proximity to the Ordinary High-Water Marks
- Temporary material or equipment storage areas in close proximity to the Ordinary High-Water Marks
- Locations of proposed sediment and erosion control devices
- Identification of construction equipment and construction techniques to accomplish the work

Once this drawing and supporting information is reviewed and approved by TxDOT, all construction workers should be made aware of the limits designated on the drawings by the Contractor’s supervision. Work in all waters of the US will be limited to the minimum necessary required to construct the bridge, culvert or roadway fills. Work will also include all activities needed for bridge and culvert demolitions. Working or disturbing soil in the stream channel outside the limits of the work plan will not be allowed. Orange fencing will be provided and maintained to establish the TxDOT approved boundaries in which work may be conducted between the Ordinary High-Water Marks. Orange fencing will not be paid for but will be considered subsidiary to Item 502, “Barricades, Signs and Traffic Handling”.

ITEM 8: PROSECUTION AND PROGRESS

This Project will be a Standard Workweek in accordance with Article 8.3.1.4.

Meet bi-weekly or at intervals as agreed upon with the Engineer to notify him or her of planned work for the upcoming 3-week period.

For this project, provide a Bar Chart progress schedule.

ITEM 100: PREPARING RIGHT OF WAY

The limits of preparing right of way will be measured at the following locations:

From Sta. 589+40 to Sta. 591+40
 From Sta. 714+35 to Sta. 716+35

along the centerline of construction.

Remove all trees within the right of way within station limits designated for Preparing Right of Way unless designated for preservation or as directed by the Engineer.

Trees to be removed near gas lines shall be cut and ground 1’ below grade.

Preserve trees within temporary construction easements in accordance with Article 100.2., unless otherwise directed.

Prune trees designated for preservation as directed. All work required in preserving and pruning trees will be included in the price bid for Item 100, “Preparing Right Of Way”.

The removal of any existing fence will not be paid for directly, but will be considered subsidiary to the bid Item 100, “Preparing Right Of Way”.

All trees and brush removed each day will be disposed of within the same day of removal unless otherwise approved. If removed vegetation is burned, ashes from burned vegetation will not be placed or allowed to be transported by storm water into any stream. Burn locations, if approved, will be no closer than 300 feet from a stream. Earth berms must be used around burn areas to keep ash in place.

The Contractor is prohibited from removing grass vegetation throughout the entire project limits and then ceasing construction for long periods, typically over three weeks. The Contractor schedule will be developed based on staged vegetation removal, limiting disturbed soil to no more than 25 percent at one time, unless otherwise approved. Should the Contractor not be able to adequately control sediment and erosion for areas disturbed, TxDOT will substantially reduce the size of areas that the Contractor may disturb soil. Should the project be evaluated to have sediment control problems as a result of the Contractor disturbing excessive amounts of soil, the Contractor will be required to immediately re-vegetate (seed and water) those disturbed areas at no cost to TxDOT.

The Contractor will be responsible for leaving the project site clean and neat in appearance upon completion and before final acceptance by the Engineer.

Wood chips may be left on the right of way no deeper than two (2) inches outside of city limits. Do not trespass on private property while performing work on this contract. Do not cut or damage timber outside the right-of-way lines.

Remove all fallen parts of trees, damaged limbs, and dead limbs. This work will not be paid for directly but will be considered subsidiary to this item.

ITEMS 105 & 354: REMOVING TREATED AND UNTREATED BASE AND ASPHALT PAVEMENT & PLANING AND TEXTURING PAVEMENT

Saw existing asphalt along neat lines where portions are to be left in place temporarily or permanently. Sawing is not paid for directly but is subsidiary to this item.

Take possession of recycled asphalt pavement from the project and recycle the material.

Properly dispose of unsalvageable material at Contractor’s expense.

Remove the loose material from the roadway before opening to traffic.

To remove dirt and debris, and assure reclaimable material is not contaminated per the specification, blade or otherwise make a neat cut along the existing pavement edge to a depth approx. 1" below the milling limits. This work will be required prior to milling operation and is subsidiary to this item.

Patch pavement cut to excessive depth by equipment failure with an approved epoxy material. Re-plane patched area to an acceptable approved ride quality. Payment for these corrections is subsidiary to this item

ITEM 150: BLADING

The limits of blading and grading operations will be to the minimum width and length necessary to accomplish the required work. The Contractor will limit the removal of permanent grass that is already established at the proper lines and grades.

ITEM 164: SEEDING FOR EROSION CONTROL

Temporary seeding mixtures (cool and warm) will also include three (3) lbs of Bermuda grass seed per acre, with all seeds being planted concurrently.

Contractor will mow or disc wheat and or oats in spring prior to vegetation going to seed.

Permanent seed mixes for both urban and rural projects including sand or clay soils in the Waco District will be bid and installed to include a minimum of one & one-half (1.5) pounds per acre Green Sprangletop seed and four (4) pounds per acre Bermudagrass seed, with other seed types also being included and quantities remaining unchanged.

ITEM 320: EQUIPMENT FOR ASPHALT CONCRETE PAVEMENT

Use a self-propelled wheel mounted MTV capable of receiving mix from the haul trucks, separate from the paver. It will have a minimum storage capacity of approximately 25 tons. It will be equipped with a pivoting discharge conveyor and will completely and thoroughly remix the material prior to placement. The effectiveness of the MTV's remixing ability is subject to the approval of the Engineer. In addition, the paver will have a surge storage insert with a minimum capacity of 20 tons.

The use of windrow pick-up equipment is allowed with the exception of windrows to be placed on seal coat surface placed as part of this contract or instances when trackless tacks are used as optional bonding or sealing courses.

ITEM 354: PLANING AND TEXTURING PAVEMENT

Saw existing asphalt along neat lines where portions are to be left in place temporarily or permanently. Sawing is not paid for directly but is subsidiary to this item.

ITEM 400: EXCAVATION AND BACKFILL OF STRUCTURES

Aggregate for cement stabilized backfill will be coarse aggregates, GRADE 3, 4 or 5 and fine aggregate, as shown in Item 421, "Hydraulic Cement Concrete". The ratio of coarse aggregate to sand should not contain more than sixty percent (60%) sand unless otherwise approved.

ITEM 420 CONCRETE SUBSTRUCTURES

BENT NUMBERING:

For bridges with four or more spans, number every third bent (counting the abutments) on the up-station and down-station faces of the outside column(s) at approximately the mid height of the column. For structures with three columns or less per bent, place numbers on column A. Where there are four or more columns per bent, place numbers on both outside columns. Bent numbers will be as shown on the bridge layout.

Provide block numbers with a height of 6". Place numbers using appropriate die cut stencils and black paint. All materials, labor and incidentals associated with placing bent numbers are subsidiary to the various bid items.

NATIONAL BRIDGE INVENTORY NUMBERS:

Provide National Bridge Inventory (NBI) numbers on all bridge structures and bridge class culverts.

Where beam types allow access to the face of abutment backwall, place NBI numbers on the face of each abutment backwall using 3" block numbers. Locate NBI numbers between the outside beams at opposite corners of the bridge.

Where beam types do not allow access to the face of abutment backwall, place NBI numbers on the face of each abutment cap using 3" block numbers. Locate NBI numbers below the outside beams at opposite corners of the bridge.

Where a bridge begins, ends or contains a bent common to multiple structures, place NBI numbers on both faces near both ends of the common bent cap. The number placed at each of the four locations will correspond to the NBI number assigned to the bridge immediately above the number. Locate NBI numbers below the outside beam. Place using 3" Block Numbers.

For all conditions, use appropriate die cut stencils and black paint for placement. All materials, labor and incidentals associated with placing NBI numbers are subsidiary to the various bid items.

ITEM 421: HYDRAULIC CEMENT CONCRETE

Furnish mix designs to the Engineer in a format compatible to the latest version of the Department's Construction Management System (Site Manager). Mix Design templates will be provided by the Engineer.

Supply the Engineer with a list of certified personnel and copies of their current ACI certificates before beginning production and when personnel changes are made. Supply hard copies of calibration reports for testing equipment when required by the Engineer.

ITEM 427: SURFACE FINISHES FOR CONCRETE

Apply a rub finish to all Surface Area I within 30 days after form removal unless otherwise shown on a plan Aesthetic Detail Sheets.

ITEM 440: REINFORCEMENT FOR CONCRETE

Fiber Reinforced Concrete (FRC) can be used as a substitute for Non-Structural Class Reinforced Concrete in Mow-Strips for MBGF and Sidewalks. FRC may also be used for other Non-Structural Class Reinforced Concrete Items as approved by the Engineer.

For rip rap slope protection wire mesh will not be allowed. Rebar reinforcing will be required per the Standard Details.

ITEM 451: RETROFIT RAILING

Refinish the outside face of the concrete slabs and curbs on the underpasses where railing is removed in such a manner as to leave a neat surface. Grind existing anchor bolts flush with the concrete. Paint the ends of the anchor bolts with two coats of zinc dust-zinc rich oxide paint as described under Item 450, "Railing". This work will not be paid for directly, but will be subsidiary to Item 451, "Retrofit Railing".

ITEM 500: MOBILIZATION

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

ITEM 502: BARRICADES, SIGNS, AND TRAFFIC HANDLING

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times. Where turning radii are limited during phased construction at intersections, provide all weather surfaces such as RAP or base in turning movements to accommodate and to protect the traffic from edge drop-offs. Materials, labor, maintenance and removal for these temporary accesses and radii will not be paid for directly but will be considered subsidiary to the various bid items.

A meeting between the Contractor and Engineer to discuss upcoming changes in construction phasing and traffic switches is required at least fourteen (14) days prior to the phase change. Items to be discussed at this meeting include temporary signing, traffic control, pavement markings, the processes necessary for the phase change and subcontractor scheduling.

When excavation is required next to a pavement lane carrying traffic and the widening is not completed by the end of the workday, backfill against the edge of the pavement with at least a 3:1

slope using an acceptable material to support vehicular traffic. Carefully remove and dispose of this material when work resumes. Backfilling pavement edges, and the materials required for the work will be subsidiary to this item.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

The Contractor Responsible Person(s) (CRP) for Work Zone Traffic Controls will inspect and ensure any deficiencies are corrected each and every day throughout the duration of this contract. Any misaligned or damaged traffic control devices will be repaired as soon as practical after deficiency is discovered.

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee(s) available to respond on the project for emergencies and for taking corrective measures within One (1) Hour.

ITEM 504: FIELD OFFICE

Furnish one Asphalt Mix Control Laboratory (Type D) for this project.

ITEM 506: TEMPORARY EROSION, SEDIMENTATION AND ENVIRONMENTAL CONTROLS

Take all practicable precautions to prevent debris from being discharged into the Waters of Texas or a designated wetland. Install Best Management Practices before demolition begins and maintain them during the demolition. Remove any debris or construction material that escapes containment devices and are discharged into the restricted areas before the next rain event or within 24 hours of the discharge.

If temporary construction stream crossings are allowed under a Nationwide Permit, submit in writing for approval the type and location of each temporary stream crossing. Use temporary bridges, timber mats, or other structurally sound and non-eroding material for temporary stream crossings. A temporary culvert crossing will consist of storm sewer pipes and 4- to 8-inch nominal size rock. Temporary stream crossings must not cause more than minimal changes to the hydraulic flow characteristics of the stream, increase flooding, or cause more than minimal degradation of water quality. Remove the temporary stream crossings in their entirety and return the affected areas to their pre-existing elevation. All work and materials use for temporary construction stream crossings will not be paid for directly but are subsidiary to pertinent Items.

Provide SW3P Signs. Obtain from the Engineer a copy of the project's completed TPDES Storm Water Program Construction Site Notice and Contractor Site Notice. Laminate the sheets and bond with adhesive to 36" X 36" sign blanks. Ensure the sheets remain dry. Apply Type C Blue reflective sheeting as the background and add the text "SW3P" in 5" white lettering, centered at the top. Attach the signs to approved temporary mounts and locate at each of the project limits just inside the right of way line at a readable height or as directed by the Engineer. If the sign cannot be placed outside the clear zone, it must adhere to the TMUTCD. SW3P signs, maintenance, and reposting (for replacement or as needed to ensure readability) will be subsidiary to Item 502.

Leave all right of way areas undisturbed until actual construction is to be performed in said areas.

No soil disturbing activities will begin on any section of TxDOT ROW without adequate sedimentation controls first being installed and functioning at adjacent drainage outfalls. Begin and continuously prosecute the repairs, additions and maintenance of erosion and sedimentation control devices within seven days after the Contractor receives each Form 2118, Field Inspection and Maintenance Report, from the Engineer. Failure of the Contractor to fulfill either of the above requirements places TxDOT in potential non-compliance with permit requirements and may result in withholding estimates or stopping work or both until all environmental permit requirements are fulfilled.

Concrete Washouts are required per the CGP. The Concrete Washout Area(s) structural controls must consist of temporary berms, temporary shallow pits, and/or temporary storage tanks to prevent contaminated runoff and must be lined as to prevent contamination of underlying soil. Ensure pits properly maintained including removal of concrete as not to allow overflow. The location(s) of washout area will be approved by the Engineer. When washout pits are no longer needed, they will be removed, and area will be restored to original condition. This work, materials and labor will not be measured or paid for directly but will be subsidiary to Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls."

Cleaning and sweeping of open roadways due to material spillage or loss from Contractor equipment or tires will be the responsibility of the Contractor at no cost to TxDOT. This work will not be charged as Item 738, "Cleaning and Sweeping Highways". Cleaning and sweeping of roadways will be completed as directed, including multiple times per day, if necessary, to maintain acceptable roadways for the traveling public and to meet environmental regulations. Construction activities will cease when material deposited on the roadway is not properly removed or when equipment is not available as needed. Adequate construction exits will be planned, constructed, and maintained by the Contractor per Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls".

ITEM 510: ONE-WAY TRAFFIC CONTROL

Provide portable signals from pre-qualified manufactures on the TxDOT Work Zone Compliant List.

ITEM 512: PORTABLE TRAFFIC BARRIER

Department-furnished concrete traffic barrier units are at a TxDOT yard near the project location or other locations within fifty (50) miles of the project as directed. Barrier provided by TxDOT will be single slope barrier. The Contractor will furnish equipment necessary to load the units at the stockpile locations.

The current locations for barrier are:

North of Hillsboro at the SH 810/SP579 Split.

For designated source portable barrier, the Department will provide the connection hardware. Should adequate hardware not be available, the Contractor will acquire the hardware, provide to the Department and be reimbursed via force account.

Upon completion of the project, all barrier deemed still acceptable by the Engineer will remain property of the Department and stockpiled at a TxDOT yard near the project location or other locations within fifty (50) miles of the project as directed. The Contractor will furnish equipment necessary to load and unload the units at the stockpile locations. Stockpiled portable concrete traffic barriers will not be permitted to be stacked more than three (3) barriers high in any direction.

When stockpiling, separate unacceptable barriers from acceptable barriers as directed. This work will not be paid for directly but will be considered subsidiary to the stockpile item.

All hardware will become the property of the Department and will be returned to the TxDOT Maintenance yard within fifty (50) miles of the project as directed. Place hardware in fifty-five (55) gallon barrels or other acceptable storage totes with holes in bottom to allow drainage. All barrels or totes must be on pallets.

ITEM 540: METAL BEAM GUARD FENCE

Furnish steel posts throughout the project except as specifically noted in the plans.

Wooden block out will not be allowed.

ITEMS 542 & 544: REMOVING METAL BEAM GUARD FENCE & GUARDRAIL END TREATMENTS

W-Beam elements, steel posts and composite material block-outs will become the property of the Contractor.

ITEM 544: GUARDRAIL END TREATMENTS

The use of wooden block-outs will not be allowed.

COUNTY: HILL,ETC.

SHEET

HIGHWAY: SH 81,ETC.

CSJ: 0014-06-045,ETC.

ITEM 585: RIDE QUALITY FOR PAVEMENT SURFACES

Use Surface Test Type B pay adjustment schedule 2 on the travel lanes.

Milling will not be allowed as a corrective action for excessive deviations in the surface layer.

ITEM 658: DELINEATOR AND OBJECT MARKER ASSEMBLIES

All flexible and GF2 delineators will have a tubular body.

The delineator assembly BRF Class A (D-SW) and (D-SY) are to be single delineators (Class I) attached to a flat, plastic bracket to facilitate the mounting of the delineator on top of the bridge rail at the locations shown on the plans. Submit a sample for approval before ordering materials.

ITEM 666: RETROREFLECTORIZED PAVEMENT MARKINGS

The Contractor will layout the proposed striping in accordance with TxDOT Traffic Control Plan Standards and latest version Texas Manual on Uniform Traffic Control Devices (TMUTCD) and project striping layout sheets. The Engineer will verify proposed striping layout prior to the beginning of striping operations.

The Contractor will locate the beginning and ending points of No Pass Zones.

ITEM 672: RAISED PAVEMENT MARKERS

Existing raised pavement markers to be replaced will be removed at the same time that the new markers are placed (i.e., remove and replace in one operation). Existing raised pavement markers replaced by new markers will be removed in accordance with Item 677, "Eliminating Existing Pavement Markings and Markers". Immediately fill the damaged area in the pavement due to the removal of existing markers with an approved bituminous material. This removal and backfill work will not be paid for directly, but will be subsidiary to Item 672, "Raised Pavement Markers".

ITEM 3076: DENSE-GRADED HOT-MIX ASPHALT

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class A.

For SAC-A, blending SAC-B Aggregate with an RSSM greater than the SAC-A rating or 10, whichever is greater, is prohibited.

Maximum stripping of 0% is required.

Dense-Graded Hot-Mix Asphalt used as concrete pavement underlayment is deemed as "Exempt Production".

RAP from Contractor owned sources may be used if the RAP is fractionated.

COUNTY: HILL,ETC.

SHEET 8F

HIGHWAY: SH 81,ETC.

CSJ: 0014-06-045,ETC.

ITEM 3096: ASPHALTS, OILS, AND EMULSIONS

Latex additives or modifiers will not be allowed on this project.

ITEM 6001: PORTABLE CHANGEABLE MESSAGE SIGN

This project will require "full matrix" type portable changeable message signs.

Ensure that the Contractor's Responsible Person for traffic control can revise messages within thirty (30) minutes of notification.

Furnish two (2) portable changeable message signs. The portable changeable message sign(s) will be used for all lane closures and freeway closures as shown on the traffic control plan standard sheets.

Supply portable changeable message sign(s) in accordance with the Traffic Control Plan standard sheets and Article 6f.55 of the Texas Manual on Uniform Traffic Control Devices for Streets and Highways Part VI.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0014-06-045

DISTRICT Waco
HIGHWAY SH 81, US 84

COUNTY Hill, McLennan

CONTROL SECTION JOB				0014-06-045		0014-06-046		0162-01-104		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00188602		A00188604		A00188605			
COUNTY				Hill		Hill		McLennan			
HIGHWAY				SH 81		SH 81		US 84			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	100-6002	PREPARING ROW	STA	2.000		2.000				4.000	
	104-6009	REMOVING CONC (RIPRAP)	SY	244.000		244.000				488.000	
	105-6022	REMOVING STAB BASE AND ASPH PAV (13")	SY	196.000		196.000		308.000		700.000	
	150-6001	BLADING	STA					1.000		1.000	
	164-6003	BROADCAST SEED (PERM) (RURAL) (CLAY)	SY	187.000		187.000				374.000	
	168-6001	VEGETATIVE WATERING	MG	15.000		15.000				30.000	
	354-6024	PLANE ASPH CONC PAV(2" TO 4")	SY	2,689.000		2,493.000		3,719.000		8,901.000	
	400-6005	CEM STABIL BKFL	CY	94.000		94.000		100.000		288.000	
	403-6001	TEMPORARY SPL SHORING	SF	200.000		200.000		400.000		800.000	
	422-6015	APPROACH SLAB	CY	70.000		70.000		92.000		232.000	
	429-6002	CONC STR REPAIR (EPOXY MORTAR)	SF					34.000		34.000	
	429-6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	361.000		594.000		121.000		1,076.000	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	80.000		80.000				160.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	25.000		25.000				50.000	
	438-6006	CLEANING AND SEALING JOINTS (CL 3)	LF	176.000		88.000		672.000		936.000	
	451-6017	RETROFIT RAIL (TY T552)	LF	316.000		236.000				552.000	
	500-6001	MOBILIZATION	LS	0.350		0.350		0.300		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	9.000						9.000	
	506-6001	ROCK FILTER DAMS (INSTALL) (TY 1)	LF					40.000		40.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF					40.000		40.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	1,180.000		1,180.000		680.000		3,040.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	1,180.000		1,180.000		680.000		3,040.000	
	510-6003	ONE-WAY TRAF CONT (PORT TRAF SIG)	MO	2.000		2.000				4.000	
	512-6013	PORT CTB (DES SOURCE)(SGL SLP)(TY 1)	LF	690.000		690.000		1,620.000		3,000.000	
	512-6025	PORT CTB (MOVE)(SGL SLP)(TY 1)	LF	690.000		690.000		1,620.000		3,000.000	
	512-6037	PORT CTB (STKPL)(SGL SLP)(TY 1)	LF	690.000		690.000		1,620.000		3,000.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	250.000		250.000				500.000	
	540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	4.000		4.000				8.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	250.000		250.000				500.000	
	542-6005	RM MTL BM GD FEN TRANS (T101)	EA	4.000		4.000				8.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000				8.000	
	544-6003	GUARDRAIL END TREATMENT (REMOVE)	EA	4.000		4.000				8.000	
	545-6003	CRASH CUSH ATTEN (MOVE & RESET)	EA	2.000		2.000		1.000		5.000	
	545-6005	CRASH CUSH ATTEN (REMOVE)	EA	2.000		2.000		1.000		5.000	
	545-6019	CRASH CUSH ATTEN (INSTL)(S)(N)(TL3)	EA	2.000		2.000		1.000		5.000	
	658-6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	7.000		5.000		24.000		36.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	15.000		15.000				30.000	

DISTRICT	COUNTY	CCSJ	SHEET
Waco	Hill	0014-06-045	9



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0014-06-045

DISTRICT Waco
HIGHWAY SH 81, US 84

COUNTY Hill, McLennan



CONTROL SECTION JOB				0014-06-045		0014-06-046		0162-01-104		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00188602		A00188604		A00188605			
COUNTY				Hill		Hill		McLennan			
HIGHWAY				SH 81		SH 81		US 84			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	662-6050	WK ZN PAV MRK REMOV (REFL) TY II-A-A	EA	120.000		120.000				240.000	
	662-6063	WK ZN PAV MRK REMOV (W)4"(SLD)	LF					1,500.000		1,500.000	
	662-6095	WK ZN PAV MRK REMOV (Y)4"(SLD)	LF	4,800.000		4,800.000				9,600.000	
	666-6300	RE PM W/RET REQ TY I (W)4"(BRK)(100MIL)	LF					798.000		798.000	
	666-6303	RE PM W/RET REQ TY I (W)4"(SLD)(100MIL)	LF	1,100.000		1,020.000		798.000		2,918.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF	550.000		510.000				1,060.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	118.000		510.000		798.000		1,426.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	14.000		14.000				28.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA					22.000		22.000	
	3076-6026	D-GR HMA TY-C SAC-A PG70-22 (EXEMPT)	TON	296.000		274.000		409.000		979.000	
	3085-6001	UNDERSEAL COURSE	GAL	672.000		623.000		930.000		2,225.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA					2.000		2.000	
18		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000						1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000						1.000	

LOCATION	SUMMARY OF TCP ITEMS							
	510 6003	512 6013	512 6025	512 6037	545 6003	545 6005	545 6019	6001 6002
	ONE-WAY TRAF CONT (PORT TRAF SIG)	PORT CTB (DES SOURCE) (SGL SLP) (TY 1)	PORT CTB (MOVE) (SGL SLP) (TY 1)	PORT CTB (STKPL) (SGL SLP) (TY 1)	CRASH CUSH ATTEN (MOVE & RESET)	CRASH CUSH ATTEN (REMOVE)	CRASH CUSH ATTEN (IN STL) (S) (N) (TL3)	PORTABLE CHANGEABLE MESSAGE SIGN
	MO	LF	LF	LF	EA	EA	EA	EA
CSJ: 0162-01-104	0	1620	1620	1620	1	1	1	2
CSJ: 0014-06-046	2	690	690	690	2	2	2	0
CSJ: 0014-06-045	2	690	690	690	2	2	2	0
PROJECT TOTALS	4	3000	3000	3000	5	5	5	2

LOCATION	SUMMARY OF REMOVAL ITEMS				
	104 6009	105 6022	542 6001	542 6005	544 6003
	REMOVING CONC (RIPRAP)	REMOVING STAB BASE AND ASPH PAV (13")	REMOVE METAL BEAM GUARD FENCE	RM MTL BM GD FEN TRANS (T101)	GUARDRAIL END TREATMENT (REMOVE)
	SY	SY	LF	EA	EA
CSJ: 0162-01-104	0	308	0	0	0
CSJ: 0014-06-046	244	196	250	4	4
CSJ: 0014-06-045	244	196	250	4	4
PROJECT TOTALS	488	700	500	8	8

LOCATION	SUMMARY OF ROADWAY ITEMS										
	100 6002	150 6001	164 6003	168 6001	354 6024	432 6045	540 6002	540 6006	544 6001	3076 6026	3085 6001
	PREPARING ROW	BLADING	BROADCAST SEED (PERM) (RURAL) (CLAY)	VEGETATIVE WATERING	PLANE ASPH CONC PAV (2" TO 4")	RIPRAP (MOW STRIP) (4 IN)	MTL W-BEAM GD FEN (STEEL POST)	MTL BEAM GD FEN TRANS (THRIE-BEAM)	GUARDRAIL END TREATMENT (INSTALL)	D-GR HMA TY-C SAC-A PG 70-22 (EXEMPT)	UNDERSEAL COURSE
	STA	STA	SY	MG	SY	CY	LF	EA	EA	TON	GAL
CSJ: 0162-01-104	0	1	0	0	3719	0	0	0	0	409	930
CSJ: 0014-06-046	2	0	187	15	2493	25	250	4	4	274	623
CSJ: 0014-06-045	2	0	187	15	2689	25	250	4	4	296	672
PROJECT TOTALS	4	1	374	30	8901	50	500	8	8	979	2225



LOCATION	SUMMARY OF BRIDGE ITEMS							
	400 6005	403 6001	422 6015	429 6002	429 6007	432 6033	438 6006	451 6017
	CEM STABIL BKFL	TEMPORARY SPL SHORING	APPROACH SLAB	CONC STR REPAIR (EPOXY MORTAR)	CONC STR REPAIR (VERTICAL & OVERHEAD)	RIPRAP (STONE PROTECTION) (18 IN)	CLEANING AND SEALING JOINTS (CL 3)	RETROFIT RAIL (TY T552)
	CY	SF	CY	SF	SF	CY	LF	LF
CSJ: 0162-01-104	100	400	92	34	121	0	672	0
CSJ: 0014-06-046	94	200	70	0	594	80	88	236
CSJ: 0014-06-045	94	200	70	0	361	80	176	316
PROJECT TOTALS	288	800	232	34	1076	160	936	552

NO.	DATE	REVISION	APPROV.
 F-12040 © 2023 			
SUMMARY OF QUANTITIES			
SHEET 1 OF 2			
FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	10
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.
WAC	HILLETC	0014	06
		JOB NO.	HIGHWAY NO.
		045.ETC	SH 81, ETC



SUMMARY OF PAVEMENT MARKING ITEMS								
LOCATION	658	658	666	666	666	666	672	672
	6014	6062	6300	6303	6312	6315	6009	6010
	INSTL DEL ASSM (D-SW) SZ (BRF) CTB (BI)	INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)	RE PM W/RET REQ TY I (W) 4" (BRK) (10 OMIL)	RE PM W/RET REQ TY I (W) 4" (SLD) (100 MIL)	RE PM W/RET REQ TY I (Y) 4" (BRK) (10 OMIL)	RE PM W/RET REQ TY I (Y) 4" (SLD) (10 OMIL)	REFL PAV MRKR TY II-A-A	REFL PAV MRKR TY II-C-R
	EA	EA	LF	LF	LF	LF	EA	EA
CSJ: 0162-01-104	24	0	798	798	0	798	0	22
CSJ: 0014-06-046	5	15	0	1020	510	510	14	0
CSJ: 0014-06-045	7	15	0	1100	550	118	14	0
PROJECT TOTALS	36	30	798	2918	1060	1426	28	22

SUMMARY OF WORK ZONE ITEMS			
LOCATION	662	662	662
	6050	6063	6095
	WK ZN PAV MRK REMOV (REFL) TY II-A-A	WK ZN PAV MRK REMOV (W) 4" (SLD)	WK ZN PAV MRK REMOV (Y) 4" (SLD)
	EA	LF	LF
CSJ: 0162-01-104	0	1500	0
CSJ: 0014-06-046	120	0	4800
CSJ: 0014-06-045	120	0	4800
PROJECT TOTALS	240	1500	9600

SUMMARY OF EROSION CONTROL ITEMS				
LOCATION	506	506	506	506
	6001	6011	6038	6039
	ROCK FILTER DAMS (INSTALL) (TY 1)	ROCK FILTER DAMS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	LF	LF	LF	LF
CSJ: 0162-01-104	40	40	680	680
CSJ: 0014-06-046	0	0	1180	1180
CSJ: 0014-06-045	0	0	1180	1180
PROJECT TOTALS	40	40	3040	3040

NO.	DATE	REVISION	APPROV.
 			
SUMMARY OF QUANTITIES			
SHEET 2 OF 2			
FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	11
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO. JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014 06 045, ETC	SH 81, ETC


LEGEND

-  WORK ZONE
-  PROPOSED TRAFFIC

NOTES


1. CONTRACTOR SHALL EXERCISE CAUTION WHEN REMOVING THE EXISTING 2" OVERLAY OVER THE EXISTING BRIDGE DECK.
2. ANY DAMAGE TO THE BRIDGE DECK DUE TO CONTRACTOR NEGLIGENCE DURING MILLING OPERATIONS, WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

PHASE 1



INSTALL 2" ASPHALT OVERLAY, CRCP, CLEAN AND SEAL JOINTS
STA 318+63.15 TO 319+03.65

PHASE 2



INSTALL 2" ASPHALT OVERLAY, CRCP, CLEAN AND SEAL JOINTS
STA 318+63.15 TO 319+03.65

SCALE: NTS



Alfonso D. Perez 12/20/2022

LOCATION	DIRECTION	FACILITY CROSSED	CSJ	NBI #	LAT/LONG	PROPOSED WORK
01	US 84 WB	TEHUACANA CREEK RELIEF	0162-01-104	09-161-0-0162-01-008	LAT: 31.62436 LONG: -97.03604	-CLEAN AND SEAL JT, INSTALL APP SLAB, INSTALL ASPHALT OVERLAY. -CONCRETE REPAIRS.




**TRAFFIC CONTROL PLAN
TYPICAL SECTIONS**

TEHUACANA CREEK
09-161-0162-01-008

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		12
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ETC

PHASE 1



INSTALL 2" ASPHALT OVERLAY, APP SLAB, CLEAN AND SEAL JOINTS, INSTALL RAILING, REPLACE MBGF
STA 587+85.00 TO 592+95.00

LEGEND


WORK ZONE

PROPOSED TRAFFIC

NOTES


1. APPLY TRAFFIC CONTROL PLAN SETUP AS DESCRIBED IN THE TCP TABLE UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
2. PROVIDE AND MAINTAIN ALL BARRICADES, WARNING SIGNS AND TRAFFIC CONTROL DEVICES IN CONFORMANCE WITH TXDOT BC AND TCP STANDARDS, AND PART VI OF THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
3. CONTRACTOR SHALL EXERCISE CAUTION WHEN REMOVING THE EXISTING 2" OVERLAY OVER THE EXISTING BRIDGE DECK.
4. ANY DAMAGE TO THE BRIDGE DECK DUE TO CONTRACTOR NEGLIGENCE DURING MILLING OPERATIONS, WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE

PHASE 2



INSTALL 2" ASPHALT OVERLAY, APP SLAB, CLEAN AND SEAL JOINTS, INSTALL RAILING, REPLACE MBGF
STA 587+85.00 TO 592+95.00

SCALE: NTS





**TRAFFIC CONTROL PLAN
TYPICAL SECTIONS**

LOVELACE CREEK
09-110-0014-06-075
SHEET 1 OF 1

LOCATION	DIRECTION	FACILITY CROSSED	CSJ	NBI #	LAT/LONG	PROPOSED WORK	TCP NARRATIVE	PROPOSED TCP STANDARD
02	SH 81	LOVELACE CREEK	0014-06-046	09-110-0-0014-06-075	LAT: 32.09209 LONG: -97.12813	-CLEAN AND SEAL JT, INSTALL APP SLAB, INSTALL ASPHALT OVERLAY. REPLACE RAIL.	-COMPLETE WORK AS SHOWN ALONG THE ROADWAY. USE PCB AT THIS LOCATION AS SHOWN FOR LANE CLOSURE.	TCP (2-8)-18 TRAFFIC CONTROL PLAN LONG TERM ONE-LANE TWO WAY CONTROL.


FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		13
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ETC

LEGEND


-  WORK ZONE
-  PROPOSED TRAFFIC

NOTES

1. APPLY TRAFFIC CONTROL PLAN SETUP AS DESCRIBED IN THE TCP TABLE UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
2. PROVIDE AND MAINTAIN ALL BARRICADES, WARNING SIGNS AND TRAFFIC CONTROL DEVICES IN CONFORMANCE WITH TXDOT BC AND TCP STANDARDS, AND PART VI OF THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
3. CONTRACTOR SHALL EXERCISE CAUTION WHEN REMOVING THE EXISTING 2" OVERLAY OVER THE EXISTING BRIDGE DECK.
4. ANY DAMAGE TO THE BRIDGE DECK DUE TO CONTRACTOR NEGLIGENCE DURING MILLING OPERATIONS, WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE



INSTALL 2" ASPHALT OVERLAY, APP SLAB, CLEAN AND SEAL JOINTS, INSTALL RAILING, REPLACE MBGF
STA 712+60.00 TO 718+10.00



INSTALL 2" ASPHALT OVERLAY, APP SLAB, CLEAN AND SEAL JOINTS, INSTALL RAILING, REPLACE MBGF
STA 712+60.00 TO 718+10.00

SCALE: NTS



Alfonso D. Perez 12/20/2022

NO.	DATE	REVISION	APPROV.



F-12040

© 2023



**TRAFFIC CONTROL PLAN
TYPICAL SECTIONS**

LITTLE HACKBERRY CREEK
09-110-0014-06-077

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		14	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETG	0014	06	045.ETC	SH 81, ETC

LOCATION	DIRECTION	FACILITY CROSSED	CSJ	NBI #	LAT/LONG	PROPOSED WORK	TCP NARRATIVE	PROPOSED TCP STANDARD
03	SH 81	LITTLE HACKBERRY CREEK	0014-06-045	09-110-0-0014-06-077	LAT: 32.05835 LONG: -97.12158	-CLEAN AND SEAL JT, INSTALL APP SLAB, INSTALL ASPHALT OVERLAY, REPLACE RAIL.	-COMPLETE WORK AS SHOWN ALONG THE ROADWAY. USE PCB AT THIS LOCATION AS SHOWN FOR LANE CLOSURE.	TCP (2-8)-18 TRAFFIC CONTROL PLAN LONG TERM ONE-LANE TWO WAY CONTROL.

TRAFFIC CONTROL PLAN NARRATIVE:

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE REQUIREMENTS OF ITEM 7, "LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC", OF THE TXDOT STANDARD SPECIFICATIONS. IN ADDITION TO THESE REQUIREMENTS, THE FOLLOWING PROVISIONS SHALL ALSO GOVERN ON THIS CONTRACT:

GENERAL:

1. TRAFFIC MUST BE HANDLED THROUGHOUT THE PROJECT DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SAFE AND COMFORTABLE PASSAGE FOR VEHICULAR TRAFFIC WITH MINIMAL INCONVENIENCE TO THE PUBLIC, AS SHOWN IN THE PLANS OR AS DIRECTED AND APPROVED BY THE ENGINEER.
2. THE CONTRACTOR MAY PROPOSE OR RECOMMEND MODIFICATIONS TO THE SEQUENCE OF CONSTRUCTION FOR CONSIDERATION BY THE ENGINEER. ANY MAJOR RECOMMENDED MODIFICATION BY THE CONTRACTOR SHALL INCLUDE ANY CHANGES TO THE VARIOUS BID ITEMS, IMPACT TO TRAFFIC, AND EFFECT OF OVERALL PROJECT IN TIME AND COST. IF THIS PROPOSAL IS IMPLEMENTED, THE CONTRACTOR WILL BE RESPONSIBLE FOR DEVELOPING DETAILED PLAN SHEETS TO BE SEALED BY A LICENSED PROFESSIONAL ENGINEER FOR INCLUSION WITH THE CHANGE ORDER. THE CONTRACTOR CANNOT PROCEED WITH ANY CONSTRUCTION OPERATIONS BASED ON A REVISED PHASE OR SEQUENCE UNTIL WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER. IF AT ANY TIME, DURING CONSTRUCTION, THE CONTRACTOR'S PROPOSED PLAN OF OPERATION FOR HANDLING TRAFFIC DOES NOT PROVIDE FOR SAFE AND COMFORTABLE MOVEMENT, THE CONTRACTOR WILL IMMEDIATELY CHANGE THEIR OPERATION TO CORRECT THE UNSATISFACTORY CONDITION.
3. TEMPORARY DRAINAGE IS THE RESPONSIBILITY OF THE CONTRACTOR. ENSURE ADEQUATE POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.
4. DO NOT STORE ANY CONSTRUCTION MATERIAL OR EQUIPMENT AT ANY LOCATION THAT WILL CONSTITUTE A HAZARD AND WILL ENDANGER TRAFFIC.
5. PROVIDE WRITTEN PROPOSED LANE CLOSURE INFORMATION BY 1:00 PM ON THE BUSINESS DAY PRIOR TO THE PROPOSED CLOSURES. DO NOT CLOSE LANES WHEN THIS REQUIREMENT IS NOT MET.
6. ACCESS TO ADJOINING PROPERTY MUST BE MAINTAINED AT ALL TIMES.
7. NO EQUIPMENT WILL BE LEFT WITHIN 30 FEET OF TRAVEL WAY AFTER WORKING HOURS UNLESS LOCATED BEHIND TRAFFIC BARRIER.
8. COVER PERMANENT SIGNS IF NOT USED. PAYMENT WILL BE CONSIDERED SUBSIDIARY TO ITEM 502.
9. SEE BC STANDARDS AND THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) FOR SIGN SPACING AND LOCATION REQUIREMENTS NOT SHOWN IN THE PLANS.
10. SEE THE DEPARTMENT'S COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICE LIST (CWZTCDL) FOR CHANNELIZING DEVICE SPACING REQUIREMENTS NOT SHOWN IN THE PLANS.
11. THE CONTRACTOR WILL PROVIDE, CONSTRUCT, AND MAINTAIN ALL BARRICADES AND SIGNS IN ACCORDANCE WITH THE DEPARTMENT'S COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICE LIST (CWZTCDL). ANY SIGNS REQUIRED THAT ARE NOT DETAILED IN THE STANDARD SHEETS SHALL BE IN CONFORMANCE WITH THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) AND THE STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS.
12. BARRICADES AND WARNING SIGNS SHALL BE PLACED AS SHOWN ON THE PLANS. THIS SHALL BE CONSIDERED THE MINIMUM REQUIRED TO PROVIDE FOR THE SAFETY OF TRAFFIC DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN OTHER SUCH BARRICADES AND SIGNS DEEMED NECESSARY BY THE ENGINEER OR AS DIRECTED BY FIELD CONDITIONS TO PROVIDE FOR THE SAFE PASSAGE OF TRAFFIC AT ALL TIMES.
13. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN FLAGGERS AS DIRECTED AND APPROVED BY THE ENGINEER, AT SUCH POINTS, AND FOR SUCH PERIODS OR TIME AS MAY BE REQUIRED, TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC AND THE CONTRACTOR'S PERSONNEL.
14. THE CONTRACTOR SHALL KEEP THE ROADWAY CLEAN AND FREE OF DIRT OR OTHER MATERIALS DURING HAULING OPERATIONS. IF THE CONTRACTOR DOES NOT MAINTAIN A CLEAN ROADWAY, THEY SHALL CEASE ALL CONSTRUCTION OPERATIONS, WHEN DIRECTED BY THE ENGINEER, TO CLEAN THE ROADWAY TO THE SATISFACTION OF THE ENGINEER.
15. THE USE OF RUBBER-TIRED EQUIPMENT WILL BE REQUIRED FOR MOVING DIRT OR OTHER MATERIALS ALONG OR ACROSS PAVEMENT SURFACES. WHERE THE CONTRACTOR DESIRES TO MOVE ANY EQUIPMENT NOT LICENSED FOR OPERATION ON PUBLIC HIGHWAYS, ON OR ACROSS PAVEMENT, THEY SHALL PROTECT THE PAVEMENT FROM DAMAGE AS DIRECTED AND APPROVED BY THE ENGINEER.
16. THROUGHOUT CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL BE REQUIRED TO CONDUCT THEIR HAULING OPERATIONS IN A MANNER SUCH THAT VEHICLES WILL NOT HAUL OVER PERVIOUSLY RE-COMPACTED SUBGRADE OR COMPACTED BASE MATERIAL, EXCEPT IN SHORT SECTIONS FOR DUMPING MANIPULATIONS.
17. UPON COMPLETION OF THE WORK AND BEFORE FINAL ACCEPTANCE AND FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL CLEAR AND REMOVE FROM THE SITE ALL SURPLUS AND DISCARDED MATERIALS AND DEBRIS OF EVERY KIND LEAVING THE ENTIRE PROJECT IN A SMOOTH, NEAT, AND SIGHTLY CONDITION.
18. ALL BARRICADES, SIGNS, AND FLAGGERS WILL BE PAID UNDER ITEM 502 "BARRICADES, SIGNS, AND TRAFFIC HANDLING". ALL EROSION AND SEDIMENT CONTROL DEVICES WILL BE PAID UNDER ITEM 506 "TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS". ALL WORK ZONE PAVEMENT MARKINGS WILL BE PAID UNDER ITEM 662 "WORK ZONE PAVEMENT MARKINGS" UNLESS OTHERWISE NOTED. ALL OTHER WORK AND MATERIALS WILL BE CONSIDERED SUBSIDIARY TO THE VARIOUS BID ITEMS UNLESS OTHERWISE INDICATED IN THE PLANS.

SEQUENCE OF CONSTRUCTION:

1. REMOVAL OF EXISTING ITEMS TO BE DONE ONLY IN AREAS WHERE CONSTRUCTION IS OCCURRING, AS PER THE PHASES NOTED BELOW.
2. OVERLAYS WILL BE PERFORMED IN THE DIRECTION OF TRAFFIC.

PHASE 1:

1. INSTALL ADVANCE WARNING SIGNS ACCORDING TO THE BC STANDARDS AND THE LATEST TMUTCD.
2. PLACE PCMS IN AN UNOBSURED LOCATION AT PROJECT LIMITS TO ALERT MOTORISTS OF UPCOMING CHANGES IN TRAFFIC PATTERN.
3. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS OR AS DIRECTED.
4. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TRAFFIC CONTROL PLAN TYPICAL SECTIONS, AND APPLICABLE TCP STANDARDS.
5. REMOVE EXISTING PAVEMENT AS PER PLANS AND TCP TYPICALS ALONG THE BRIDGE DECK AND APPROACHES. INSTALL TEMPORARY SPECIAL SHORING.
6. INSTALL CEMENT STABILIZED BACKFILL.
7. PERFORM SURFACING OPERATIONS, CLEAN JOINTS ALONG THE BRIDGE DECK. INSTALL REINFORCED FABRIC JOINT UNDERSEALS. INSTALL BRIDGE APPROACH SLAB. INSTALL 2" ASPHALT OVERLAY ALONG THE BRIDGE AND APPROACHES. PLACE SIGNING AND PAVEMENT MARKINGS FOR THE TOTAL LIMITS OF THE PROJECT ON RIGHT SIDE. PERFORM BRIDGE SUBSTRUCTURE REPAIRS. CONSTRUCT THE PAVEMENT STRUCTURE IN ACCORDANCE WITH THE PLANS.

PHASE 2:

1. RELOCATE PCMS IN AN UNOBSURED LOCATION AT PROJECT LIMITS TO ALERT MOTORISTS OF UPCOMING CHANGES IN TRAFFIC PATTERN.
2. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS OR AS DIRECTED.
3. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TRAFFIC CONTROL PLAN TYPICAL SECTIONS, AND APPLICABLE TCP STANDARDS.
4. REMOVE EXISTING PAVEMENT AND ELEMENTS AS PER PLANS AND TCP TYPICALS. INSTALL TEMPORARY SPECIAL SHORING.
5. INTALL CEMENT STABILIZED BACKFILL
6. PERFORM SURFACING OPERATIONS, CLEAN JOINTS ALONG THE BRIDGE DECK. INSTALL REINFORCED FABRIC JOINT UNDERSEALS. INSTALL APPROACH SLAB. INSTALL 2" ASPHALT OVERLAY ALONG THE BRIDGE AND APPROACHES. PERFORM BRIDGE SUBSTRUCTURE REPAIRS. PLACE SIGNING AND PAVEMENT MARKINGS FOR THE TOTAL LIMITS OF THE PROJECT ON RIGHT SIDE. CONSTRUCT THE PAVEMENT STRUCTURE IN ACCORDANCE WITH THE PLANS.
7. REMOVE ANY TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THE PLANS.
8. COMPLETE ALL WORK ON THE PLANS AND AS DIRECTED.

SCALE: NTS



12/20/2022



F-12040



© 2023

TRAFFIC CONTROL PLAN
NARRATIVE
TEHUACANA CREEK
09-161-0162-01-008

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT			SHEET NO.
6	TEXAS	BR 2023(500), etc.			15
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

TRAFFIC CONTROL PLAN NARRATIVE:

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE REQUIREMENTS OF ITEM 7, "LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC", OF THE TxDOT STANDARD SPECIFICATIONS. IN ADDITION TO THESE REQUIREMENTS, THE FOLLOWING PROVISIONS SHALL ALSO GOVERN ON THIS CONTRACT:

GENERAL:

1. TRAFFIC MUST BE HANDLED THROUGHOUT THE PROJECT DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SAFE AND COMFORTABLE PASSAGE FOR VEHICULAR TRAFFIC WITH MINIMAL INCONVENIENCE TO THE PUBLIC, AS SHOWN IN THE PLANS OR AS DIRECTED AND APPROVED BY THE ENGINEER.
2. THE CONTRACTOR MAY PROPOSE OR RECOMMEND MODIFICATIONS TO THE SEQUENCE OF CONSTRUCTION FOR CONSIDERATION BY THE ENGINEER. ANY MAJOR RECOMMENDED MODIFICATION BY THE CONTRACTOR SHALL INCLUDE ANY CHANGES TO THE VARIOUS BID ITEMS, IMPACT TO TRAFFIC, AND EFFECT OF OVERALL PROJECT IN TIME AND COST. IF THIS PROPOSAL IS IMPLEMENTED, THE CONTRACTOR WILL BE RESPONSIBLE FOR DEVELOPING DETAILED PLAN SHEETS TO BE SEALED BY A LICENSED PROFESSIONAL ENGINEER FOR INCLUSION WITH THE CHANGE ORDER. THE CONTRACTOR CANNOT PROCEED WITH ANY CONSTRUCTION OPERATIONS BASED ON A REVISED PHASE OR SEQUENCE UNTIL WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER. IF AT ANY TIME, DURING CONSTRUCTION, THE CONTRACTOR'S PROPOSED PLAN OF OPERATION FOR HANDLING TRAFFIC DOES NOT PROVIDE FOR SAFE AND COMFORTABLE MOVEMENT, THE CONTRACTOR WILL IMMEDIATELY CHANGE THEIR OPERATION TO CORRECT THE UNSATISFACTORY CONDITION.
3. TEMPORARY DRAINAGE IS THE RESPONSIBILITY OF THE CONTRACTOR. ENSURE ADEQUATE POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.
4. DO NOT STORE ANY CONSTRUCTION MATERIAL OR EQUIPMENT AT ANY LOCATION THAT WILL CONSTITUTE A HAZARD AND WILL ENDANGER TRAFFIC.
5. PROVIDE WRITTEN PROPOSED LANE CLOSURE INFORMATION BY 1:00 PM ON THE BUSINESS DAY PRIOR TO THE PROPOSED CLOSURES. DO NOT CLOSE LANES WHEN THIS REQUIREMENT IS NOT MET.
6. ACCESS TO ADJOINING PROPERTY MUST BE MAINTAINED AT ALL TIMES.
7. NO EQUIPMENT WILL BE LEFT WITHIN 30 FEET OF TRAVEL WAY AFTER WORKING HOURS UNLESS LOCATED BEHIND TRAFFIC BARRIER.
8. COVER PERMANENT SIGNS IF NOT USED. PAYMENT WILL BE CONSIDERED SUBSIDIARY TO ITEM 502.
9. SEE BC STANDARDS AND THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) FOR SIGN SPACING AND LOCATION REQUIREMENTS NOT SHOWN IN THE PLANS.
10. SEE THE DEPARTMENT'S COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICE LIST (CWZTCDL) FOR CHANNELIZING DEVICE SPACING REQUIREMENTS NOT SHOWN IN THE PLANS.
11. THE CONTRACTOR WILL PROVIDE, CONSTRUCT, AND MAINTAIN ALL BARRICADES AND SIGNS IN ACCORDANCE WITH THE DEPARTMENT'S COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICE LIST (CWZTCDL). ANY SIGNS REQUIRED THAT ARE NOT DETAILED IN THE STANDARD SHEETS SHALL BE IN CONFORMANCE WITH THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) AND THE STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS.
12. BARRICADES AND WARNING SIGNS SHALL BE PLACED AS SHOWN ON THE PLANS. THIS SHALL BE CONSIDERED THE MINIMUM REQUIRED TO PROVIDE FOR THE SAFETY OF TRAFFIC DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN OTHER SUCH BARRICADES AND SIGNS DEEMED NECESSARY BY THE ENGINEER OR AS DIRECTED BY FIELD CONDITIONS TO PROVIDE FOR THE SAFE PASSAGE OF TRAFFIC AT ALL TIMES.
13. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN FLAGGERS AS DIRECTED AND APPROVED BY THE ENGINEER, AT SUCH POINTS, AND FOR SUCH PERIODS OR TIME AS MAY BE REQUIRED, TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC AND THE CONTRACTOR'S PERSONNEL.
14. THE CONTRACTOR SHALL KEEP THE ROADWAY CLEAN AND FREE OF DIRT OR OTHER MATERIALS DURING HAULING OPERATIONS. IF THE CONTRACTOR DOES NOT MAINTAIN A CLEAN ROADWAY, THEY SHALL CEASE ALL CONSTRUCTION OPERATIONS, WHEN DIRECTED BY THE ENGINEER, TO CLEAN THE ROADWAY TO THE SATISFACTION OF THE ENGINEER.
15. THE USE OF RUBBER-TIRED EQUIPMENT WILL BE REQUIRED FOR MOVING DIRT OR OTHER MATERIALS ALONG OR ACROSS PAVEMENT SURFACES. WHERE THE CONTRACTOR DESIRES TO MOVE ANY EQUIPMENT NOT LICENSED FOR OPERATION ON PUBLIC HIGHWAYS, ON OR ACROSS PAVEMENT, THEY SHALL PROTECT THE PAVEMENT FROM DAMAGE AS DIRECTED AND APPROVED BY THE ENGINEER.
16. THROUGHOUT CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL BE REQUIRED TO CONDUCT THEIR HAULING OPERATIONS IN A MANNER SUCH THAT VEHICLES WILL NOT HAUL OVER PREVIOUSLY RE-COMPACTED SUBGRADE OR COMPACTED BASE MATERIAL, EXCEPT IN SHORT SECTIONS FOR DUMPING MANIPULATIONS.
17. UPON COMPLETION OF THE WORK AND BEFORE FINAL ACCEPTANCE AND FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL CLEAR AND REMOVE FROM THE SITE ALL SURPLUS AND DISCARDED MATERIALS AND DEBRIS OF EVERY KIND LEAVING THE ENTIRE PROJECT IN A SMOOTH, NEAT, AND SLIGHTLY CONDITION.
18. ALL BARRICADES, SIGNS, AND FLAGGERS WILL BE PAID UNDER ITEM 502 "BARRICADES, SIGNS, AND TRAFFIC HANDLING". ALL EROSION AND SEDIMENT CONTROL DEVICES WILL BE PAID UNDER ITEM 506 "TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS". ALL WORK ZONE PAVEMENT MARKINGS WILL BE PAID UNDER ITEM 662 "WORK ZONE PAVEMENT MARKINGS" UNLESS OTHERWISE NOTED. ALL OTHER WORK AND MATERIALS WILL BE CONSIDERED SUBSIDIARY TO THE VARIOUS BID ITEMS UNLESS OTHERWISE INDICATED IN THE PLANS.

SEQUENCE OF CONSTRUCTION:

1. REMOVAL OF EXISTING ITEMS TO BE DONE ONLY IN AREAS WHERE CONSTRUCTION IS OCCURRING, AS PER THE PHASES NOTED BELOW.
2. OVERLAYS WILL BE PERFORMED IN THE DIRECTION OF TRAFFIC.

PHASE 1:

1. INSTALL ADVANCE WARNING SIGNS ACCORDING TO THE BC STANDARDS AND THE LATEST TMUTCD.
2. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS, OR AS DIRECTED.
3. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TRAFFIC CONTROL PLAN TYPICAL SECTIONS, AND TCP(2-8)-18 TCP STANDARDS.
4. REMOVE EXISTING PAVEMENT AS PER PLANS AND TCP TYPICALS ALONG THE BRIDGE DECK AND APPROACHES. INSTALL TEMPORARY SPECIAL SHORING.
5. INSTALL CEMENT STABILIZED BACKFILL.
6. PERFORM SURFACING OPERATIONS, CLEAN JOINTS ALONG THE BRIDGE DECK. INSTALL REINFORCED FABRIC JOINT UNDERSEALS. INSTALL APPROACH SLAB. INSTALL 2" ASPHALT OVERLAY ALONG THE BRIDGE AND APPROACHES. PERFORM BRIDGE SUBSTRUCTURE REPAIRS. RETROFIT RAIL. PLACE SIGNING AND PAVEMENT MARKINGS FOR THE TOTAL LIMITS OF THE PROJECT ON RIGHT SIDE. CONSTRUCT THE PAVEMENT STRUCTURE IN ACCORDANCE WITH THE PLANS.

PHASE 2:

1. RELOCATE PCMS IN AN UNOBSERVED LOCATION AT PROJECT LIMITS TO ALERT MOTORISTS OF UPCOMING CHANGES IN TRAFFIC PATTERN.
2. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS OR AS DIRECTED.
3. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TRAFFIC CONTROL PLAN TYPICAL SECTIONS, AND APPLICABLE TCP STANDARDS.
4. REMOVE EXISTING PAVEMENT AND ELEMENTS AS PER PLANS AND TCP TYPICALS. INSTALL TEMPORARY SPECIAL SHORING.
5. INSTALL CEMENT STABILIZED BACKFILL.
6. PERFORM SURFACING OPERATIONS, CLEAN JOINTS ALONG THE BRIDGE DECK. INSTALL REINFORCED FABRIC JOINT UNDERSEALS. INSTALL APPROACH SLAB. INSTALL 2" ASPHALT OVERLAY ALONG THE BRIDGE AND APPROACHES. PERFORM BRIDGE SUBSTRUCTURE REPAIRS. RETROFIT RAIL. PLACE SIGNING AND PAVEMENT MARKINGS FOR THE TOTAL LIMITS OF THE PROJECT ON RIGHT SIDE. CONSTRUCT THE PAVEMENT STRUCTURE IN ACCORDANCE WITH THE PLANS.
7. REMOVE ANY TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THE PLANS.
8. COMPLETE ALL WORK ON THE PLANS AND AS DIRECTED.

SCALE: NTS



12/20/2022



F-12040



© 2023

TRAFFIC CONTROL PLAN
NARRATIVE
LOVELACE CREEK
09-110-0-014-06-075

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	16		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

TRAFFIC CONTROL PLAN NARRATIVE:

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE REQUIREMENTS OF ITEM 7, "LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC", OF THE TXDOT STANDARD SPECIFICATIONS. IN ADDITION TO THESE REQUIREMENTS, THE FOLLOWING PROVISIONS SHALL ALSO GOVERN ON THIS CONTRACT:

GENERAL:

1. TRAFFIC MUST BE HANDLED THROUGHOUT THE PROJECT DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SAFE AND COMFORTABLE PASSAGE FOR VEHICULAR TRAFFIC WITH MINIMAL INCONVENIENCE TO THE PUBLIC, AS SHOWN IN THE PLANS OR AS DIRECTED AND APPROVED BY THE ENGINEER.
2. THE CONTRACTOR MAY PROPOSE OR RECOMMEND MODIFICATIONS TO THE SEQUENCE OF CONSTRUCTION FOR CONSIDERATION BY THE ENGINEER. ANY MAJOR RECOMMENDED MODIFICATION BY THE CONTRACTOR SHALL INCLUDE ANY CHANGES TO THE VARIOUS BID ITEMS, IMPACT TO TRAFFIC, AND EFFECT OF OVERALL PROJECT IN TIME AND COST. IF THIS PROPOSAL IS IMPLEMENTED, THE CONTRACTOR WILL BE RESPONSIBLE FOR DEVELOPING DETAILED PLAN SHEETS TO BE SEALED BY A LICENSED PROFESSIONAL ENGINEER FOR INCLUSION WITH THE CHANGE ORDER. THE CONTRACTOR CANNOT PROCEED WITH ANY CONSTRUCTION OPERATIONS BASED ON A REVISED PHASE OR SEQUENCE UNTIL WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER. IF AT ANY TIME, DURING CONSTRUCTION, THE CONTRACTOR'S PROPOSED PLAN OF OPERATION FOR HANDLING TRAFFIC DOES NOT PROVIDE FOR SAFE AND COMFORTABLE MOVEMENT, THE CONTRACTOR WILL IMMEDIATELY CHANGE THEIR OPERATION TO CORRECT THE UNSATISFACTORY CONDITION.
3. TEMPORARY DRAINAGE IS THE RESPONSIBILITY OF THE CONTRACTOR. ENSURE ADEQUATE POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.
4. DO NOT STORE ANY CONSTRUCTION MATERIAL OR EQUIPMENT AT ANY LOCATION THAT WILL CONSTITUTE A HAZARD AND WILL ENDANGER TRAFFIC.
5. PROVIDE WRITTEN PROPOSED LANE CLOSURE INFORMATION BY 1:00 PM ON THE BUSINESS DAY PRIOR TO THE PROPOSED CLOSURES. DO NOT CLOSE LANES WHEN THIS REQUIREMENT IS NOT MET.
6. ACCESS TO ADJOINING PROPERTY MUST BE MAINTAINED AT ALL TIMES.
7. NO EQUIPMENT WILL BE LEFT WITHIN 30 FEET OF TRAVEL WAY AFTER WORKING HOURS UNLESS LOCATED BEHIND TRAFFIC BARRIER.
8. COVER PERMANENT SIGNS IF NOT USED. PAYMENT WILL BE CONSIDERED SUBSIDIARY TO ITEM 502.
9. SEE BC STANDARDS AND THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) FOR SIGN SPACING AND LOCATION REQUIREMENTS NOT SHOWN IN THE PLANS.
10. SEE THE DEPARTMENT'S COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICE LIST (CWZTCDL) FOR CHANNELIZING DEVICE SPACING REQUIREMENTS NOT SHOWN IN THE PLANS.
11. THE CONTRACTOR WILL PROVIDE, CONSTRUCT, AND MAINTAIN ALL BARRICADES AND SIGNS IN ACCORDANCE WITH THE DEPARTMENT'S COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICE LIST (CWZTCDL). ANY SIGNS REQUIRED THAT ARE NOT DETAILED IN THE STANDARD SHEETS SHALL BE IN CONFORMANCE WITH THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) AND THE STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS.
12. BARRICADES AND WARNING SIGNS SHALL BE PLACED AS SHOWN ON THE PLANS. THIS SHALL BE CONSIDERED THE MINIMUM REQUIRED TO PROVIDE FOR THE SAFETY OF TRAFFIC DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN OTHER SUCH BARRICADES AND SIGNS DEEMED NECESSARY BY THE ENGINEER OR AS DIRECTED BY FIELD CONDITIONS TO PROVIDE FOR THE SAFE PASSAGE OF TRAFFIC AT ALL TIMES.
13. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN FLAGGERS AS DIRECTED AND APPROVED BY THE ENGINEER, AT SUCH POINTS, AND FOR SUCH PERIODS OR TIME AS MAY BE REQUIRED, TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC AND THE CONTRACTOR'S PERSONNEL.
14. THE CONTRACTOR SHALL KEEP THE ROADWAY CLEAN AND FREE OF DIRT OR OTHER MATERIALS DURING HAULING OPERATIONS. IF THE CONTRACTOR DOES NOT MAINTAIN A CLEAN ROADWAY, THEY SHALL CEASE ALL CONSTRUCTION OPERATIONS, WHEN DIRECTED BY THE ENGINEER, TO CLEAN THE ROADWAY TO THE SATISFACTION OF THE ENGINEER.
15. THE USE OF RUBBER-TIRED EQUIPMENT WILL BE REQUIRED FOR MOVING DIRT OR OTHER MATERIALS ALONG OR ACROSS PAVEMENT SURFACES. WHERE THE CONTRACTOR DESIRES TO MOVE ANY EQUIPMENT NOT LICENSED FOR OPERATION ON PUBLIC HIGHWAYS, ON OR ACROSS PAVEMENT, THEY SHALL PROTECT THE PAVEMENT FROM DAMAGE AS DIRECTED AND APPROVED BY THE ENGINEER.
16. THROUGHOUT CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL BE REQUIRED TO CONDUCT THEIR HAULING OPERATIONS IN A MANNER SUCH THAT VEHICLES WILL NOT HAUL OVER PREVIOUSLY RE-COMPACTED SUBGRADE OR COMPACTED BASE MATERIAL, EXCEPT IN SHORT SECTIONS FOR DUMPING MANIPULATIONS.
17. UPON COMPLETION OF THE WORK AND BEFORE FINAL ACCEPTANCE AND FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL CLEAR AND REMOVE FROM THE SITE ALL SURPLUS AND DISCARDED MATERIALS AND DEBRIS OF EVERY KIND LEAVING THE ENTIRE PROJECT IN A SMOOTH, NEAT, AND SIGHTLY CONDITION.
18. ALL BARRICADES, SIGNS, AND FLAGGERS WILL BE PAID UNDER ITEM 502 "BARRICADES, SIGNS, AND TRAFFIC HANDLING". ALL EROSION AND SEDIMENT CONTROL DEVICES WILL BE PAID UNDER ITEM 506 "TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS". ALL WORK ZONE PAVEMENT MARKINGS WILL BE PAID UNDER ITEM 662 "WORK ZONE PAVEMENT MARKINGS" UNLESS OTHERWISE NOTED. ALL OTHER WORK AND MATERIALS WILL BE CONSIDERED SUBSIDIARY TO THE VARIOUS BID ITEMS UNLESS OTHERWISE INDICATED IN THE PLANS.

SEQUENCE OF CONSTRUCTION:

1. REMOVAL OF EXISTING ITEMS TO BE DONE ONLY IN AREAS WHERE CONSTRUCTION IS OCCURING, AS PER THE PHASES NOTED BELOW.
2. OVERLAYS WILL BE PERFORMED IN THE DIRECTION OF TRAFFIC.

PHASE 1:

1. INSTALL ADVANCE WARNING SIGNS ACCORDING TO THE BC STANDARDS AND THE LATEST TMUTCD.
2. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS OR AS DIRECTED.
3. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TRAFFIC CONTROL PLAN TYPICAL SECTIONS, AND TCP(2-8)-18 TCP STANDARDS.
4. REMOVE EXISTING PAVEMENT AS PER PLANS AND TCP TYPICALS ALONG THE BRIDGE DECK AND APPROACHES. INSTALL TEMPORARY SPECIAL SHORING.
5. INSTALL CEMENT STABILIZED BACKFILL.
6. PERFORM SURFACING OPERATIONS, CLEAN JOINTS ALONG THE BRIDGE DECK. INSTALL REINFORCED FABRIC JOINT UNDERSEALS. INSTALL APPROACH SLAB. INSTALL 2" ASPHALT OVERLAY ALONG THE BRIDGE AND APPROACHES. PERFORM BRIDGE SUBSTRUCTURE REPAIRS, RETROFIT RAIL. PLACE SIGNING AND PAVEMENT MARKINGS FOR THE TOTAL LIMITS OF THE PROJECT ON RIGHT SIDE. CONSTRUCT THE PAVEMENT STRUCTURE IN ACCORDANCE WITH THE PLANS.

PHASE 2:

1. RELOCATE PCMS IN AN UNOBSURED LOCATION AT PROJECT LIMITS TO ALERT MOTORISTS OF UPCOMING CHANGES IN TRAFFIC PATTERN.
2. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS OR AS DIRECTED.
3. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TRAFFIC CONTROL PLAN TYPICAL SECTIONS, AND APPLICABLE TCP STANDARDS.
4. REMOVE EXISTING PAVEMENT AND ELEMENTS AS PER PLANS AND TCP TYPICALS. INSTALL TEMPORARY SPECIAL SHORING.
5. INSTALL CEMENT STABILIZED BACKFILL.
6. PERFORM SURFACING OPERATIONS, CLEAN JOINTS ALONG THE BRIDGE DECK. INSTALL REINFORCED FABRIC JOINT UNDERSEALS. INSTALL APPROACH SLAB. INSTALL 2" ASPHALT OVERLAY ALONG THE BRIDGE AND APPROACHES. PERFORM BRIDGE SUBSTRUCTURE REPAIRS, RETROFIT RAIL. PLACE SIGNING AND PAVEMENT MARKINGS FOR THE TOTAL LIMITS OF THE PROJECT ON RIGHT SIDE. CONSTRUCT THE PAVEMENT STRUCTURE IN ACCORDANCE WITH THE PLANS.
7. REMOVE ANY TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THE PLANS.
8. COMPLETE ALL WORK ON THE PLANS AND AS DIRECTED.

SCALE: NTS



12/20/2022



F-12040





© 2023

TRAFFIC CONTROL PLAN
NARRATIVE
LITTLE HACKBERRY CREEK
09-110-014-0-06-077

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		17	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC





LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA

NOTES:

1. PORTBLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.




APD 12/20/2022



**PHASE 1
TRAFFIC CONTROL PLAN
LAYOUT**
TEHUACANA CREEK
09-161-0-0162-01-008
SHEET 1 OF 4

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		18
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ETC

V:\Projects\TX\2019\01902477X.05\1_Design\CADD\qgn\01_Master_Design_Files\Prime\TCP\TCP_LAYOUT_01_PHASE_1-1.dgn





LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA


NOTES:

1. PORTABLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.





**PHASE 1
TRAFFIC CONTROL PLAN
LAYOUT**
TEHUACANA CREEK
09-161-0-0162-01-008
SHEET 2 OF 4

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	19
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO.	JOB NO. HIGHWAY NO.
WAC	HILLETC	0014 06	045, ETC SH 81, ETC





\Projects\TX\2019\01902477X.05\1_Design\500_CADD\qgn\01_Master_Design_Files\Prime\TCP_LAYOUT_01_PHASE 1-2.dgn
 12/20/2022 2:58:48 PM



- LEGEND**
- TRAFFIC DIRECTION
 - PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
 - DRUMS
 - CONSTRUCTION SIGN
 - WORK THIS PHASE
 - WORK PREVIOUS PHASE
 - TYPE 3 BARRICADE
 - PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
 - CRASH CUSHION
 - TMA
 - TEMPORARY OR PORTABLE TRAFFIC SIGNAL

- NOTES:**
1. PORTBLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.



12/20/2022



**PHASE 1
TRAFFIC CONTROL PLAN
LAYOUT**
LOVELACE CREEK
09-110-0-014-06-075
SHEET 3 OF 4

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	20
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO.	JOB NO. HIGHWAY NO.
WAC	HILLETC	0014 06	045.ETC SH 81, ETC

P:_V_TPD\Projects\TX\2019\01902477X.05\1_Design\500_CADD\ggn\01_Master_Design_Files\Prime\TCP\TCP_LAYOUT_02_PHASE_1.dgn
 2:58:50 PM
 12/20/2022


12/20/2022 2:58:50 PM

P:_V_TPD\Projects\TX\2019\01902477X.05\1_Design\500_CADD\ggn\01_Master_Design_Files\Prime\TCP\TCP_LAYOUT_02_PHASE_1.dgn
 D:\902477X.05


If applicable
R4-2
24" X 30"



R4-1
24" X 30"



CW3-3
48" X 48"
(Red Ball on Top)



G20-2
48" X 24"



CW20-4D
48" X 48"
(See note 2)

Temporary
24" Stop Line

50'

100'

STA 712+60.00
BEGIN WORK

MATCHLINE STA 714+60



CW20-1D
48" X 48"

800'

800'

800'

800'



R10-6L
24" X 36"




LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA
- TEMPORARY OR PORTABLE TRAFFIC SIGNAL

NOTES:

1. PORTABLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.



12/20/2022



PHASE 1
TRAFFIC CONTROL PLAN
LAYOUT
LITTLE HACKBERRY CREEK
09-110-0-014-06-077

SHEET 4 OF 4


FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	21
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO.	JOB NO. HIGHWAY NO.
WAC	HILLETC	0014 06	045.ETC SH 81, ETC

P:_V-TPD\Projects\TX\2019\01902477X.05_V1_Design\500_CADD\ggn01_Master_Design_Files\Prime\TCP\TCP_LAYOUT_03_PHASE_1.dgn
2:58:52 PM
12/20/2022

12/20/2022 2:58:52 PM

P:_V-TPD\Projects\TX\2019\01902477X.05_V1_Design\500_CADD\ggn01_Master_Design_Files\Prime\TCP\TCP_LAYOUT_03_PHASE_1.dgn

END ROAD WORK
G20-2
48" x 24"




LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA

WORK ZONE PAVEMENT MARKING QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
662	6063	WK ZN PAV MRK REMOV (W) 4" (SLD)	LF	884	610	1494

NOTES:

- PORTBLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.



0 25' 50'

SCALE: 1" = 50' HORZ
1" = 50' VERT

STATE OF TEXAS
ALFONSO D. PEREZ
120369
LICENSED PROFESSIONAL ENGINEER

12/20/2022

NO.	DATE	REVISION	APPROV.

consor
F-12040
© 2023



Texas Department of Transportation

PHASE 2
TRAFFIC CONTROL PLAN
LAYOUT
TEHUACANA CREEK
09-161-0-0162-01-008
SHEET 1 OF 5

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500),etc.	22		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81,ETC

\Projects\TX\2019\01902477X.05\1_Design\500_CADD\qgn\01_Master_Design_Files\Prime\TCP_LAYOUT_01_PHASE_2-1.dgn

\Projects\TX\2019\01902477X.05\1_Design\500_CADD\qgn\01_Master_Design_Files\Prime\TCP_LAYOUT_01_PHASE_2-2.dgn





LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA

NOTES:

1. PORTABLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.





Alfonso D. Perez 12/20/2022



**PHASE 2
TRAFFIC CONTROL PLAN
LAYOUT**
 TEHUACANA CREEK
 09-161-0-0162-01-008
 SHEET 2 OF 5

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		23
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045, ETC SH 81, ETC




LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA

NOTES:

1. PORTBLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.



Alfonso D. Perez
12/20/2022


NO.	DATE	REVISION	APPROV.



**PHASE 2
TRAFFIC CONTROL PLAN
LAYOUT**
TEHUACANA CREEK
09-161-0-0162-01-008
SHEET 3 OF 5

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		24	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045, ETC	SH 81, ETC

\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\ dgn\01_Master_Design_Files\Prime\TCP_LAYOUT_01_PHASE_2-3.dgn





LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA
- TEMPORARY OR PORTABLE TRAFFIC SIGNAL

NOTES:

1. PORTABLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.



12/20/2022





**PHASE 2
TRAFFIC CONTROL PLAN
LAYOUT**
LOVELACE CREEK
09-110-0-014-06-075
SHEET 4 OF 5

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		25
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ETC

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\dgn\01_Master_Design_Files\Prime\TCP_LAYOUT_02_PHASE_2.dgn
 2:58:59 PM
 12/20/2022

12/20/2022 2:58:59 PM

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\dgn\01_Master_Design_Files\Prime\TCP_LAYOUT_02_PHASE_2.dgn





LEGEND

- TRAFFIC DIRECTION
- PORTABLE CONCRETE TRAFFIC BARRIER (PCTB) W/TYPE C DELINEATORS
- DRUMS
- CONSTRUCTION SIGN
- WORK THIS PHASE
- WORK PREVIOUS PHASE
- TYPE 3 BARRICADE
- PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- CRASH CUSHION
- TMA
- TEMPORARY OR PORTABLE TRAFFIC SIGNAL

NOTES:

1. PORTABLE CHANGEABLE MESSAGE SIGNS TO BE INSTALLED IN LOCATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.



[Signature] 12/20/2022

NO.	DATE	REVISION	APPROV.



**PHASE 2
TRAFFIC CONTROL PLAN
LAYOUT**
LITTLE HACKBERRY CREEK
09-110-0-014-06-077
SHEET 5 OF 5

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	26		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC.

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\dgn\01_Master_Design_Files\Prime\TCP\TCP_LAYOUT_03_PHASE_2.dgn
2:59:00 PM
12/20/2022


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

LOC NO.	TCP PHASE	PLAN SHEET NUMBER	LOCATION	STA	TEST LEVEL	DIRECTION OF TRAFFIC (UNI/BI)	FOUNDATION PAD		BACKUP SUPPORT			AVAILABLE SITE LENGTH	CRASH CUSHION										
							PROPOSED MATERIAL	PROPOSED THICKNESS	DESCRIPTION	WIDTH	HEIGHT		INSTALL	REMOVE	MOVE / RESET		L	L	R	R	S	S	
															MOVE / RESET	FROM LOC. #							N
1	1		US84 WB	331+04.00	TL-3	UNI	EXIST PVMNT	EXIST THICKNESS	TEMPORARY PCTB	24"	32"	50'	1								X		
2	2		US84 WB	334+19.00	TL-3	UNI	PROP PVMNT	PROP THICKNESS	TEMPORARY PCTB	24"	32"	50'		1	1						X		
3	1		US81 NB	586+85.00	TL-3	UNI	EXIST PVMNT	EXIST THICKNESS	TEMPORARY PCTB	24"	32"	50'	1								X		
4	1		US81 NB	593+05.00	TL-3	UNI	EXIST PVMNT	EXIST THICKNESS	TEMPORARY PCTB	24"	32"	50'	1								X		
5	2		US81 NB	586+85.00	TL-3	UNI	PROP PVMNT	PROP THICKNESS	TEMPORARY PCTB	24"	32"	50'		1	1						X		
6	2		US81 NB	593+05.00	TL-3	UNI	PROP PVMNT	PROP THICKNESS	TEMPORARY PCTB	24"	32"	50'		1	1						X		
7	1		US81 NB	711+60.00	TL-3	UNI	EXIST PVMNT	EXIST THICKNESS	TEMPORARY PCTB	24"	32"	50'	1								X		
8	1		US81 NB	719+10.00	TL-3	UNI	EXIST PVMNT	EXIST THICKNESS	TEMPORARY PCTB	24"	32"	50'	1								X		
9	2		US81 NB	711+60.00	TL-3	UNI	PROP PVMNT	PROP THICKNESS	TEMPORARY PCTB	24"	32"	50'		1	1						X		
10	2		US81 NB	719+10.00	TL-3	UNI	PROP PVMNT	PROP THICKNESS	TEMPORARY PCTB	24"	32"	50'		1	1						X		
												TOTALS	5	5	5								

LEGEND:
 L=LOW MAINTENANCE
 R=REUSABLE
 S=SACRIFICIAL
 N=NARROW
 W=WIDE

FOR DEFINITIONS SEE THE "CRASH CUSHION CATEGORIZATION CHART.PDF" AT THE DESIGN DIVISION (ROADWAY STANDARDS) WEBSITE. USE QUICK LINKS TO ACCESS ATTENUATORS / CRASH CUSHIONS SECTION.
<http://www.dot.state.tx.us/insdtdot/orgchart/cmd/cserve/standard/rdwylse.htm>

CRASH CUSHION SUMMARY SHEET



FILE: CCSS.dgn	DN: TxDOT	CK:	CK:
© TxDOT	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC SH 81, ETC
	DIST	COUNTY	
	WAC	HILL, ETC	
	FEDERAL AID PROJECT		SHEET NO.
	BR 2023(500), etc.		27

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other file formats. TxDOT standards\bc-21.dgn

DATE: 12/20/2022 2:59:01 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\agn\01_Master_Design_Files\Time_TCP\Txdot_standards\bc-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

BC (1) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC		SH 81, ETC			
4-03	7-13								
9-07	8-14								
5-10	5-21	DIST	COUNTY		SHEET NO.				
		WAC	HILL, ETC		28				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard. The user of this standard shall be responsible for any damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			80	1000 ²
*			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	WAC	HILL, ETC		29				

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard. BC-21-21-01 damages resulting from its use.

DATE: 12/20/2022 2:59:02 PM
FILE: P:_V-TPD\Projects\TX\2019\190247TX.05\1_Design\500_CADD\agn\01_Master\Barricade\BC-21-21-01.dgn

SHEET 3 OF 12



BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC(3)-21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	WAC	HILL, ETC	30					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/20/2022 2:59:02 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.051_Design\500_CADD\dgn\01_Master_Design_Files\Time\TCP\txdot_standards\bc-21_04.dgn

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.


SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12


Texas Department of Transportation
 Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
9-07	8-14	DIST		COUNTY		SHEET NO.			
7-13	5-21	WAC		HILL, ETC		31			

DATE: 12/20/2022 2:59:03 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master_Design_Files\Prime\Txdot_standards\bc-21_05.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	WAC	HILL, ETC		32				

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/20/2022 2:59:04 PM
FILE: P:_V-TPD\Projects\TX\2019\190247TX_0511_Design\500_CADD\agn\01_Master_Design_Files\Time\TCD\txdot_standards\bc-21_06.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT


Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
REVISIONS	0014	DW:	TxDOT
	06	CK:	TxDOT
9-07	8-14	JOB	
7-13	5-21	O45, ETC	
		SH 81, ETC	
		DIST	COUNTY
		WAC	HILL, ETC
		SHEET NO.	
		33	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/20/2022 2:59:05 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_051_Design\500_CADD\dgn\01_Master_Design Files\Prime\TCP\txdot_standards\bc-21_07.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	November 2002	CONT	SECT	JOB		HIGHWAY			
REVISIONS		0014	06	045, ETC		SH 81, ETC			
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	WAC	HILL, ETC		34				

DATE: 12/20/2022 2:59:05 PM
 FILE: P:\V-TPD\Projects\TX\2019\190247TX.05\1_Design\500_CADD\agn\01_Master_Design_Files\Time\TCP\txdot_standards\bc-21_08.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS




- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC		SH 81, ETC			
4-03	8-14	DIST	COUNTY		SHEET NO.				
9-07	5-21	WAC	HILL, ETC		35				
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/20/2022 2:59:06 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_0511_Design\500_CADD\dgn\01_Master_Design_Files\Time\TCP\txdot_standards\bc-21_09.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * X			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

*X Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	WAC	HILL, ETC		36				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 12/20/2022 2:59:07 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master_Design_Files\Prime\TCP\txdot_standards\bc-21_10.dgn


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	WAC	HILL, ETC	37	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		0014	06	045, ETC
2-98	9-07	5-21		
1-02	7-13			
11-02	8-14			
	DIST	COUNTY		SHEET NO.
	WAC	HILL, ETC		38


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/20/2022 2:59:07 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\dgn\01_Master_Design\Time\TCP\txdot_standards\bc-21_11.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.






RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS



BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	WAC	HILL, ETC	39	
11-02 8-14				

DATE: 12/20/2022 2:59:08 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_051_Design\500_CADD\agn\01_Master_Design\Files\Prime\TCP\txdot_standards\bc-21_12.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."



DATE: 12/20/2022 2:59:08 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\dgn\01_Master\Drawings\Systems\absorb\absorb.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of drawings to other formats or for any errors or omissions that may result from its use.



THE ABSORB-M IS A NON-REDIRECTIVE, GATING, CRASH CUSHION DESIGNED TO MEET THE LATEST TL-3 & TL-2 MASH REQUIREMENTS.
 THE SYSTEM IS DESIGNED TO ACCOMMODATE A VARIETY OF F-SHAPE AND SINGLE SLOPE CONCRETE BARRIERS. CONTACT THE MANUFACTURER FOR GUIDANCE REGARDING OTHER ALLOWABLE SHAPES.

TEST LEVEL	NUMBER OF ELEMENTS	EFFECTIVE LENGTH	MAXIMUM LENGTH
TL-2	2	14' - 7 3/4"	17' - 4"
TL-3	3	20' - 11 3/4"	23' - 8"

NOTE:
 CROSS SLOPES OF UP TO 8% (OR 1:12 SLOPE) CAN BE ACCOMMODATED WITH STANDARD HARDWARE SHOWN WITHIN THE INSTRUCTIONS MANUAL. FOR SLOPES WITH EXCESS OF 8% (OR 1:12) CONTACT, LINDSAY TRANSPORTATION SOLUTIONS.



NOTE:
 APPLY A HIGH REFLECTIVE DECAL TO THE NOSE PLATE. DELINEATION DECAL ORIENTATION IS SHOWN ON THE CONSTRUCTION PLAN SET AND SHALL BE IN ACCORDANCE WITH THE TEXAS MUTCD FOR (TRAFFIC CONTROL DEVICES). DECALS ARE AVAILABLE FOR TRAFFIC FLOW ON THE LEFT-SIDE, BOTH -SIDES AND RIGHT-SIDE.

- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING THE INSTALLATION AND TECHNICAL GUIDANCE, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800. 180 RIVER ROAD, RIO VISTA, CA 94571
 - THE ABSORB-M SYSTEM IS ONLY APPROVED FOR USE IN (TEMPORARY WORK ZONE) LOCATIONS.
 - THE ABSORB-M IS A WATER FILLED NON-REDIRECTIVE, GATING CRASH CUSHION THAT DOES NOT NEED TO BE ATTACHED TO A FOUNDATION AND CAN BE INSTALLED ON TOP OF CONCRETE, ASPHALT, OR ANY SURFACE CAPABLE OF BEARING THE WEIGHT OF THE SYSTEM.
 - MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
 - THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
 - THE ABSORB-M SHOULD BE LOCATED APPROXIMATELY PARALLEL WITH THE BARRIER.
 - THE USE OF THE ABSORB-M IS RESTRICTED TO A BARRIER HEIGHT OF UP TO 42 INCHES.
 - DO NOT ADD WATER TO FRONT ELEMENT (TL-2 OR TL-3 UNIT).

BILL OF MATERIALS (BOM) ABSORB-M TL-3 & TL-2 SYSTEMS			QTY	QTY
ITEM #	PART NUMBER	PART DESCRIPTION	TL-2 SYSTEM	TL-3 SYSTEM
1	BSI-1809036-00	TRANSITION-(GALV)	1	1
2	BSI-1808002-00	PRE-ASSEMBLED ABSORBING (ELEMENTS)	2	3
3	BSI-4004598	FILL CAPS	8	12
4	BSI-4004599	DRAIN PLUGS	2	3
5	BSI-1809053-00	TENSION STRAP-(GALV)	8	12
6	BSI-2001998	C-SCR FH 3/8-16 X 1 1/2 GR5 PLT	8	12
7	BSI-2001999	C-SCR FH 3/8-16 X 1 GR5 PLT	8	12
8	BSI-1809035-00	MIDNOSE-(GALV)	1	1
9	BSI-1808014-00	NOSE PLATE	1	1
10	BSI-1809037-00	TRANSITION STRAP (LEFT-HAND)-(GALV)	1	1
11	BSI-1809038-00	TRANSITION STRAP (RIGHT-HAND)-(GALV)	1	1
12	BSI-1808005-00	PIN ASSEMBLY	8	10
13	BSI-2002001	ANC MECH 5/8-11X5 (GALV)	6	6
14	ABSORB-M	INSTALLATION AND INSTRUCTIONS MANUAL	1	1

* COMPONENTS PRE-ASSEMBLED WITH ELEMENT ASSEMBLY

NOTE:
 THIS STANDARD IS A BASIC REPRESENTATION OF THE ABSORB-M, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.


SACRIFICIAL

Traffic Safety Division Standard


LINDSAY TRANSPORTATION SOLUTIONS
 CRASH CUSHION
 (MASH TL-3 & TL-2)
 TEMPORARY - WORK ZONE
 ABSORB (M) - 19

FILE: tcpsc-3-21.dgn	DN:	CK:	DW:	CK:
© TxDOT	REVISIONS	CONT	SECT	JOB
	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY		SHEET NO.
	WAC	HILL, ETC		40

DATE: 12/20/2022 2:59:09 PM
 FILE: P:\V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\dgn\01_Material\01_01_01.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions.




PLAN VIEW




ELEVATION VIEW

GENERAL NOTES

1. REFER TO THE INSTALLATION MANUAL FOR SPECIFIC SYSTEM ASSEMBLY AND MODULE ORIENTATION. FOR ADDITIONAL INFORMATION, CONTACT TRAFFIX, INC. AT (949) 361-5663.
2. THE SLED SYSTEM IS A MASH APPROVED TEST LEVEL 3 (TL-3) CRASH CUSHION APPROVED FOR USE IN TEMPORARY WORK ZONES. THE SLED SYSTEM IS A NON-REDIRECTIVE, GATING CRASH CUSHION THAT DOES NOT NEED TO BE ATTACHED TO THE GROUND AND CAN BE INSTALLED ON CONCRETE, ASPHALT, GRAVEL OR COMPACTED SOIL.
3. MAXIMUM PERMISSIBLE CROSS SLOPE IS 8° (DEGREES) (14%).
4. THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
5. THE SLED SYSTEM CAN BE ATTACHED TO:
 - CONCRETE BARRIER, TEMPORARY OR PERMANENT, 45" MAXIMUM HEIGHT
 - STEEL BARRIER
 - PLASTIC BARRIER
 - CONCRETE BRIDGE ABUTMENTS
 - W-BEAM GUARD RAIL
 - THRIE BEAM GUARD RAIL




SECTION A-A



NOTE:
SEE INSTALLATION MANUAL FOR CUSTOMIZED DELINEATION NOSE SHEETING FOR DECAL PLACEMENT.

TEST LEVEL	NUMBER OF SECONDARY MODULES	SYSTEM LENGTH
TL-3	3	25' 3"

BILL OF MATERIAL		
PART NUMBER	DESCRIPTION	QTY: TL-3
45131	TRANSITION FRAME, GALVANIZED	1
45150	TRANSITION PANEL, GALVANIZED	2
45147-CP	TRANSITION SHORT DROP PIN W/ KEEPER PIN, GALVANIZED	2
45148-CP	TRANSITION LONG DROP PIN W/ KEEPER PIN, GALVANIZED	1
45050	ANCHOR BOLTS	9
12060	WASHER, 3/4" ID X 2" OD	9
45044-Y	SLED YELLOW WATER FILLED MODULE	3
45044-YH	SLED YELLOW "NO FILL" MODULE	1
45044-S	CIS (CONTAINMENT IMPACT SLED), GALVANIZED	1
45043-CP	T-PIN W/ KEEPER PIN	4
18009-B-I	FILL CAP W/ "DRIVE BY" FLOAT INDICATOR	3
45033-RC-B	DRAIN PLUG	3
45032-DPT	DRAIN PLUG REMOVAL TOOL	1



SLED TRANSITION COMPONENTS FOR ATTACHMENT TO CMB

NOTE:
SEE MANUFACTURER'S INSTALLATION MANUAL FOR FURTHER DETAILS.

TRANSITION OPTIONS
SLED TRANSITION TO CONCRETE TRAFFIC BARRIER (TEMPORARY OR PERMANENT)
SLED TRANSITION TO STEEL TRAFFIC BARRIER (CONTACT MFGR FOR PROPER TRANSITION)
SLED TRANSITION TO PLASTIC TRAFFIC BARRIER (CONTACT MFGR FOR PROPER TRANSITION)
SLED TRANSITION TO W-BEAM OR THRIE BEAM GUARD RAIL (CONTACT MFGR FOR PROPER TRANSITION)
SLED TRANSITION TO CONCRETE BRIDGE ABUTMENT

NOTE:
THIS STANDARD IS A BASIC REPRESENTATION OF THE SLED, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.





SACRIFICIAL

Texas Department of Transportation
Bridge Division Standard

SLED
 CRASH CUSHION
 TL-3 MASH COMPLIANT
 (TEMPORARY, WORK ZONE)
 SLED-19

FILE: r1std005-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: AES
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DIST	COUNTY		SHEET NO.	
WAC	HILL, ETC		41	

DATE: 12/20/2022 2:59:10 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\agn\01_Mas...
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format.




* NOTE: ENGINEER OR CONTRACTOR SHALL COORDINATE WITH THE MANUFACTURER FOR THE CORRECT DECAL PER TRAFFIC FLOW, LEFT, RIGHT OR BOTH-SIDES.

 NOTE: APPLY A HIGH REFLECTIVE DECAL TO THE NOSE PLATE. DELINEATION DECAL ORIENTATION IS SHOWN ON THE CONSTRUCTION PLAN SET AND SHALL BE IN ACCORDANCE WITH THE TEXAS MUTCD FOR TRAFFIC CONTROL DEVICES. DECALS ARE AVAILABLE FOR TRAFFIC FLOW ON THE LEFT-SIDE, BOTH -SIDES AND RIGHT-SIDE. THE ORIENTATION BETWEEN THE LEFT-SIDE AND RIGHT-SIDE TRAFFIC IS CHANGED BY ROTATING THE DECAL 90 DEGREES AND REINSTALLING.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT Traffix Devices, Inc. AT 1(949)361-5663
 - THE SLED MINI IS A MASH APPROVED TEST LEVEL 2 (TL-2) CRASH CUSHION APPROVED FOR USE WITHIN TEMPORARY WORK ZONE LOCATIONS. TL-2 IS APPROVED FOR SPEEDS OF 45 MPH OR LESS.
 - THE SLED MINI IS A GATING, NON-REDIRECTIVE CRASH CUSHION THAT DOES NOT NEED TO BE BOLTED TO THE GROUND AND CAN BE INSTALLED ON CONCRETE, ASPHALT, GRAVEL OR COMPACTED SOIL.
 - THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, AND DEPRESSIONS.
 - THE SLED MINI CAN BE ATTACHED TO CONCRETE BRIDGE ABUTMENTS, CONCRETE BARRIER, STEEL BARRIER AND PLASTIC BARRIER.

SLED MINI TL-2 - BILL OF MATERIALS		
QTY:	PART #	PART DESCRIPTIONS
2	45332-MY	WATER FILLED MODULE
2	45032-CPGAL	T-PINS - LENGTH 26" WITH KEEPER PINS - FOR MODULES
2	18009-B-I	WATER LEVEL INDICATOR FLOAT LID
1	45032-S	CONTAINMENT IMPACT SLED (CIS)
2	45151	UNIVERSAL TRANSITION PANELS
1	45132	TRANSITION FRAME
1	45141	DROP PIN - LENGTH 26.50" WITH KEEPER PIN
2	45142	DROP PINS - LENGTH 18.50" WITH KEEPER PINS
8	45050	TRANSITION PANEL ANCHOR BOLTS 3/4" X 4 1/2" (4 EA. SIDE)

MODULE SPECIFICATIONS	(CIS) SPECIFICATIONS
LENGTH: 73" (PIN TO PIN)	LENGTH: 87 7/8"
HEIGHT: 32"	HEIGHT: 32"
WIDTH: 18"	WIDTH: 23"
EMPTY WEIGHT: 110 lbs.	APPROX. WEIGHT: 1250 lbs.
FILLED WEIGHT: 1100 lbs.	
FILL CAPACITY: 118.5 Gal	



NOTES:
 * SEE DELINEATION GUIDE FOR DECAL PLACEMENT.
 SEE INSTALLATION MANUAL FOR CUSTOMIZED DELINEATION NOSE SHEETING FOR DECAL PLACEMENT.

NOTE:
 THIS STANDARD IS A BASIC REPRESENTATION OF THE SLED MINI, IT IS NOT INTENDED TO REPLACE THE INSTALLATION INSTRUCTIONS MANUAL.


SACRIFICIAL

Bridge Division Standard
SLED MINI END TREATMENT TL-2 MASH COMPLIANT (TEMPORARY, WORK ZONE) SLEDMINI-19

FILE: r1std005-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: AES
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	42	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions that may appear in this standard or for any damages resulting from its use.

DATE: 12/20/2022 2:59:11 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\TPD\WorkSpaceNearShoulder.dgn




TCP (1-1a)

WORK SPACE NEAR SHOULDER
 Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
 Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.




TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK


TCP (1-1) - 18

FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	WAC	HILL, ETC	43	
1-97 2-18				


DATE: 12/20/2022
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\agn\01_Master\Drawings\Traffic\Traffic Control Plans\Traffic Control Plans.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this drawing. The user of this drawing shall be responsible for its use.



ONE LANE CLOSURE



LANE CLOSURE NEAR EXIT RAMP



LANE CLOSURE NEAR ENTRANCE RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation
 Traffic Operations Division Standard




**TRAFFIC CONTROL PLAN
 LANE CLOSURES FOR
 DIVIDED HIGHWAYS**

TCP (1-5) - 18

FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	44	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units or for any damages resulting from its use.

DATE: 12/20/2022 2:59:13 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\Traffic\CP\CP-18.dgn



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
 - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation
 Traffic Operations Division Standard



TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	0014	06	045, ETC	SH 81, ETC
2-94 4-98	DIST:	COUNTY:	SHEET NO.	
8-95 2-12	WAC:	HILL, ETC	45	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard on projects not intended for its use.

DATE: 12/20/2022 2:59:13 PM
 FILE: P:\V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\agn\01_Master\Txdot\Traffic\Traffic Control\TCP (2-2) - 18.dgn



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	575'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.


Texas Department of Transportation Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL


TCP (2-2) - 18

FILE:	tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT	December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS		0014	06	045, ETC	SH 81, ETC
8-95	3-03	DIST	COUNTY	SHEET NO.	
1-97	2-12	WAC	HILL, ETC	46	
4-98	2-18				


DATE: 12/20/2022 2:59:14 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\dgn\01_Master\TDCS\TrafficControlPlan\TCP(2-6).dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units or for any damages resulting from its use.



TCP (2-6a)
ONE LANE CLOSURE



TCP (2-6b)
LANE CLOSURE NEAR EXIT RAMP



TCP (2-6c)
LANE CLOSURE NEAR ENTRANCE RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
 - The placement of pavement markings may be omitted on Intermediate-term stationary work zones with the approval of the Engineer.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
LANE CLOSURES ON
DIVIDED HIGHWAYS
TCP (2-6) - 18

FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	WAC	HILL, ETC	47	
1-97 2-18				


166

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard or for any damages resulting from its use.

DATE: 12/20/2022 2:59:15 PM
 FILE: P:\V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\dgn\01_Master\TrafficControlStandards\TCPS\TCPS.dgn



TCP (2-8a)
ONE LANE TWO-WAY
TRAFFIC CONTROL WITH YIELD SIGNS
 (Less Than 2000 ADT-See Note 5)



TCP (2-8b)
ONE LANE TWO-WAY
TRAFFIC CONTROL WITH TRAFFIC SIGNAL

LEGEND

	Type 3 Barricade		Channelizing Devices
	Sign		Traffic Flow
	Flag		Flagger
	Raised Pavement Markers Ty II-AA		Temporary or Portable Traffic Signal

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

	MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
				✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - When this TCP is used at a location which does not involve a bridge, a 48" x 48" CW20-4D "ONE LANE ROAD AHEAD" signs should be used in lieu of the CW5-3 "ONE LANE BRIDGE" signs. The CW13-1P Advisory Speed Plaque is required with either warning sign.
 - Raised pavement markers shall be placed 40 feet c-c on centerline between DO NOT PASS signs and stop or yield lines.
 - For intermediate term situations, when it is not feasible to remove and restore pavement markings, the channelization must be made dominant by using a very close spacing. This is especially important in locations of conflicting information, such as where traffic is directed over a double yellow centerline. In such locations a maximum channelizing device spacing of 20 feet is recommended. The 20 foot channelizing device spacing recommendation is intended for the area of conflicting information and not the entire work zone.
- TCP (2-8a)**
- Traffic control by CW3-2 "YIELD AHEAD" symbol signs for one lane two-way traffic control operations should be limited to work spaces less than 400 feet long and roadways with less than 2000 ADT. Otherwise, portable traffic signals should be used.
 - If power is available, a flashing beacon should be attached to the CW3-2 "YIELD AHEAD" symbol sign for emphasis.
 - The R1-2 "YIELD" and R1-2aP "TO ONCOMING TRAFFIC" signs and other regulatory signs shall be installed at 7 foot minimum mounting height.
- TCP (2-8b)**
- A list of approved Portable Traffic Signals can be found in the "Compliant Work Zone Traffic Control Devices" list.
 - Portable traffic signals should be located to provide adequate stopping sight distance for approaching motorist (See table above).

Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
LONG TERM ONE-LANE
TWO-WAY CONTROL


TCP (2-8) - 18

FILE: tcp2-8-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	WAC	HILL, ETC	48	
4-98 2-18				


168

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other standards or damages resulting from its use.

DATE: 12/20/2022 2:59:16 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\TrafficControlPlan\TCP3-1.dgn



TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY




TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display Flashing Arrow Board

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)


TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES


- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.




TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board in CAUTION display



STRIPING FOR TMA



Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS
 UNDIVIDED HIGHWAYS**



TCP (3-1) - 13

FILE:	tcp3-1.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	December 1985	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
2-94	4-98	DIST	COUNTY		SHEET NO.				
8-95	7-13	WAC	HILL, ETC		49				
1-97									

DATE: 12/20/2022 2:59:17 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\agn\01_Master\Drawings\TrafficControlPlan\3-2b.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or damages resulting from its use.



RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)




INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle	→	RIGHT Directional
☐	Heavy Work Vehicle	←	LEFT Directional
▲	Truck Mounted Attenuator (TMA)	↔	Double Arrow
↶	Traffic Flow	⊙	CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

- ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
- For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
- Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
- The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
- Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
- The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.



Texas Department of Transportation









Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
DIVIDED HIGHWAYS

TCP(3-2)-13

FILE: tcp3-2.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	WAC	HILL, ETC	50	
1-97	176			

DATE: 12/20/2022 2:59:17 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\dgn\01_Masf...
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to a digital format or for any errors or damages resulting from its use.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.


Texas Department of Transportation
Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/
REMOVAL
TCP (3-3) - 14**

FILE: fcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	WAC	HILL, ETC	51	
1-97 7-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein or for any damages resulting from its use.

DATE: 12/20/2022 2:59:18 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\agn\01_Master\Drawings\TrafficControl\Signage\TCD\TCD-13.dwg



NOTE
 Signing shown for one direction of travel only.

NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS



"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- A. Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- B. At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- D. R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- A. Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- B. At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- C. The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- A. When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- A. Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- B. Tabs shall not be used to simulate edge lines.
- C. Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- A. The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- B. Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

1. The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
2. The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
3. Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
4. When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
5. Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.



TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS


TCP (7-1) - 13

FILE:	tcp7-1.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	March 1991	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS	0014 06			045, ETC	SH 81, ETC				
4-92 4-98			DIST:	COUNTY:	SHEET NO.				
1-97 7-13			WAC:	HILL, ETC	52				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided. This is a standard for the use of temporary flexible-reflective roadway marker tabs and does not constitute a contract.

DATE: 12/20/2022 2:59:18 PM
 FILE: P:\V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\STPM\WZ\WZ-STPM-13.dgn

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS




NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.


TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.


WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS




CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS




LANE LINES FOR DIVIDED HIGHWAY



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



TWO-WAY LEFT TURN LANE



PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm







WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	0014	SECT:	06	JOB:	045, ETC	SH:	81, ETC
1-97	3-03	DIST:	WAC	COUNTY:	HILL, ETC	SHEET NO.		53	
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units. This standard is not intended to be used for any purpose other than that for which it was developed. TxDOT assumes no responsibility for damages resulting from its use.

DATE: 12/20/2022 2:59:19 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\WZ\UL\WZ_UL_13.dgn



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1		
Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"



SIGNING FOR UNEVEN LANES


WZ (UL) - 13

FILE:	WZUL-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0014	06	045, ETC	SH 81, ETC				
8-95	2-98	7-13	DIST		COUNTY	SHEET NO.			
1-97	3-03	WAC		HILL, ETC	54				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. This standard is not intended to be used for any purpose other than that for which it was developed. DATE: 12/20/2022 2:59:20 PM FILE: P:_V-TPD\Projects\TX\2019\ND190247TX.05\1_Design\500_CADD\dgn\01_Master\Drawings\Standard\WZ-RS-22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation Traffic Safety Division Standard




TEMPORARY RUMBLE STRIPS

WZ (RS) - 22



FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	WAC	HILL, ETC	55	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/20/2022 2:59:21 PM
 FILE: P:_V-TPD\Projects\TX\2019\ND190247TX.05\1_Design\500_CADD\agn\01_Master_Design_Files\Prime\TxDOT_Standards\Roadway\bed14.dgn



- GENERAL NOTES**
- For more detail: See GF(31), SGT()31, GF(31)TR, and GF(31)TL2 standard sheets.
 - Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
 - Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
 - MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
 - Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
 - Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal, See Detail A)
 - The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
 - For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge location(s) shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
 - Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
 - A minimum 25' length of MBGF will be required.



Note: All rail elements shall be lapped in the direction of adjacent traffic.


Texas Department of Transportation Design Division Standard

BRIDGE END DETAILS
(METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)

BED-14

FILE: bed14.dgn	DN: TxDOT	CK: AM	DW: BD/VP	CK: CGL
© TxDOT: December 2011	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
REVISED APRIL 2014 SEE (MEMO 0414)	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	56	





DATE: 12/20/2022
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\gn\01_Master_Design Files\Time\TXDOT_Standards\Roadway\gf31tr+1320-1.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- (5) 1" DIA. HOLES.
- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (FACING TRAFFIC SIDE) (ASTM F3125 GR A325 OR A449).
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 7/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563).


NOTE: HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE: CURB IS A REQUIRED COMPONENT FOR THE TRANSITION TO FUNCTION PROPERLY. SEE GENERAL NOTES: 2-4 AND 16-17.




BRIDGE APPROACH - UPSTREAM: THE NESTED RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.

BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.



THRIE-BEAM TERMINAL - CURB TABLE	
PRECAST CURB FULL LENGTH EQUALS 12'-2" THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS.	
CURB (1) LENGTH 5'-8"	CURB (2) LENGTH 6'-6"
TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7	
CONNECTING PRECAST CURB SECTIONS (1) & (2):	
FORM OR CORE 1" DIA. HOLE 9" LONG INTO EACH CURB END. USE (1) #5 GR.60 REBAR 18" LONG TO CONNECT BOTH CURBS.	
SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE *:	
FORM OR CORE (4) 1" DIA. HOLES, SEE PLAN AND ELEVATION VIEWS FOR HOLE LOCATIONS. DRIVE (4) #5 GR.60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB.	
FILL HOLES WITH APPROVED GROUT MIXTURE.	



* NOTES: NOT NEEDED FOR CAST-IN-PLACE. SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS. PERCUSSION DRILLING IS NOT PERMITTED WITH: TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.

GENERAL NOTES


1. CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
2. CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5-3/4" HEIGHT); SEE CURRENT CCG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE:17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
3. CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
4. UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
5. FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
6. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF (31) STANDARD SHEET.
7. THE POST LENGTH SHALL BE MARKED ON ALL 7'-0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 5/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
8. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
9. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
10. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
11. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
12. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
13. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
14. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TXDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
15. REFER TO GF (31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
16. THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
17. IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION, (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED) (TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED) (STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT.2 FOR ADDITIONAL INFORMATION.

HIGH-SPEED TRANSITION
SHEET 1 OF 2


		Design Division Standard	
METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT			
GF (31) TR TL3-20			
FILE: gf31tr+1320.dgn	DN: TxDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2020	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC
	DIST	COUNTY	SH 81, ETC
	WAC	HILL, ETC	SHEET NO. 57

DATE: 12/20/2022
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_DesIgn\500_CADD\dgn\01_Master_Design_Files\Time\TXDOT_Standards\Roadway\gf31tr+1320-2.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)



ELEVATION VIEW



SECTION D-D



THREE BEAM TRANSITION BLOCKOUT DETAILS

HIGH-SPEED TRANSITION


SHEET 2 OF 2




METAL BEAM GUARD FENCE
 THREE-BEAM TRANSITION
 TL-3 MASH COMPLIANT
 GF (31) TR TL3-20

FILE: gf31tr+1320.dgn	DN: TXDOT	CK: KM	DW: KM	CK: CGL/AG
©TXDOT: NOVEMBER 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY		SHEET NO.
	WAC	HILL, ETC		58


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




TYPICAL POST PLACEMENT



WOOD BLOCK TO ROUND WOOD POST




WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST


- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



ELEVATION MID-SPAN RAIL SPLICE


SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.

SPLICE BOLT LENGTH VARIES

FBB01 = 1 1/4"


FBB02 = 2"

POST & BLOCK LENGTH

FBB03 = 10"

FBB04 = 18"

BUTTON HEAD BOLT



MID-SPAN RAIL SPLICE DETAIL

(8) 5/8" X 1 1/4" BUTTON HEAD SPLICE BOLTS WITH RECESSED NUTS.


NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.

DATE: FILE:


				Design Division Standard	
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19					
FILE: gf3119.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CGL/AG	
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0014	06	045, ETC	SH 81, ETC	
	DIST	COUNTY	SHEET NO.		
	WAC	HILL, ETC	59		

DATE: 12/20/2022
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX.05\1_Design\500_CADD\gn\01_Master_Design Files\Time\TXDOT_Standards\Roadway\gf31ms19.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)



SECTION A-A


Typical



MOW STRIP DETAIL


Reinforced Concrete Mow Strip with 18\"/>

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
 2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
 3. The leave-out behind the post shall be a minimum of 7".
 4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
 5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
 6. Thickness of the mow strip will be 4".
 7. The limits of payment for reinforced concrete will include leave-outs for the posts.
 8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)







Curb shown on top of mow strip



CURB OPTION (3)

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF(31)MS-19			
FILE: gf31ms19.dgn	DN:TxDOT	CK: KM	DW: VP
©TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC
	DIST	COUNTY	SHEET NO.
	WAC	HILL, ETC	60

DATE: 12/20/2022
 FILE: P:_v-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\dgn\01_Master_Design Files\TXDOT_Standards\Roadway\sgt153120.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CBO8
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WB08
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/16"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GR17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81

ITEM	QTY	SMALL HARDWARE	ITEM #
a	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPLICE BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M







SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15) 31-20

FILE: sgt153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT: 0014	SECT: 06	JOB: 045, ETC	HIGHWAY: SH 81, ETC
REVISIONS	DIST: WAC	COUNTY: HILL, ETC	SHEET NO. 61	

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
 - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL. P/N MANMAX REV D (ECN 3516).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
 - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
 - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
 - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
 - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
 - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM#	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	5/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	5/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN. ITEM(26) 8" WOOD-BLOCKOUTS ITEM(27) 25' GUARD FENCE PANELS


Texas Department of Transportation
Design Division Standard

MAX-TENSION END TERMINAL
MASH - TL-3
SGT (11S) 31-18

FILE: sg+11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	62	

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.



DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- NOTES:
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/16" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/16" O.D. x 3/16" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard

SINGLE GUARDRAIL TERMINAL

MSKT-MASH-TL-3



SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT: SECT	JOB: HIGHWAY		
REVISIONS				
0014	06	045, ETC	SH 81, ETC	
DIST: WAC	COUNTY: HILL, ETC	SHEET NO. 63		

DATE: FILE:

BRIDGE QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
150	6001	BLADING	STA	1	-	1
105	6022	REMOVING STAB BASE AND ASPH PAV (13")	SY	154	154	308
354	6024	PLANE ASPH CONC PAV (2"-4")	SY	1993	1727	3719
400	6005	CEM STABIL BKFL (G)	CY	50	50	100
403	6001	TEMPORARY SPL SHORING	SF	200	200	400
422	6015	APPROACH SLAB (H)	CY	46	46	92
429	6002	CONC STR REPAIR (EPOXY MORTAR) (A1)	SF	26	6	32
438	6006	CLEANING AND SEALING JOINTS (CL 3) (E)	LF	378	294	672
3076	6026	D-GR HMA TY-C SAC-B PG 70-22 (EXEMPT)	TON	219	190	409
3085	6001	UNDERSEAL COURSE	GAL	498	432	930

BEGIN PROJECT
BEGIN HMAC
OVERLAY
STA 317+03.15





PLAN

- LEGEND**
- BRIDGE APPROACH SLAB (MOD)
 - CLEANING AND SEALING EXISTING JOINT SEE DETAIL
 - PLANE ASPH CONC PAV UNDERSEAL COURSE 2" HMA OVERLAY
 - SOFFIT UNDER DECK
 - LIMITS OF CSAB
 - TEMP SPL SHORING
- REPAIR CALL-OUT LEGEND**
- REPAIR QUANTITY UNIT
 - ESTIMATED REPAIR QUANTITY
 - REPAIR TYPE DESIGNATION - SEE BELOW

- REPAIR TYPE DESCRIPTION**
- (E) CLEANING AND SEALING JOINTS (CL 3)
 - (A1) MINOR SPALL
 - (G) CSAB OPT 2
 - (H) SLAB TRANSITION

- NOTES:**
- SEE "BRIDGE SPALL REPAIR DETAILS," "BRIDGE APPROACH SLAB (MOD)" AND "CLEANING AND SEALING EXISTING JOINTS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.
 - CONTRACTOR TO ENSURE MINIMUM HEIGHT OF MBGF AS PER STANDARD DURING PAVEMENT INSTALLATION.
 - REPLACING WINDROW TOPSOIL ALONG PAVEMENT EDGES WILL BE SUBSIDIARY TO ITEM 150-6001.
 - FOR TYPICAL SECTION REFER TO "TYPICAL SECTIONS" SHEETS 4 & 5.



12/20/2022

NO.	DATE	REVISION	APPROV.





BRIDGE REPAIR LAYOUT
TEHUACANA CREEK
09-161-0-0162-01-008

SHEET 1 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	64		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045, ETC	SH 81, ETC

\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\gn\01_Master_Design_Files\Prime\BRIDGE_LAYOUTS\Teahuacana\LOCATION_01.dgn

\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\ dgn\01_Master_Design_Files\Prime\BRIDGE_LAYOUTS\Tehuacana\LOCATION_01-2.dgn




PLAN

- LEGEND**
- BRIDGE APPROACH SLAB (MOD)
 - CLEANING AND SEALING EXISTING JOINT SEE DETAIL
 - PLANE ASPH CONC PAV UNDERSEAL COURSE 2" HMAC OVERLAY
 - SOFFIT UNDER DECK
 - LIMITS OF CSAB
 - TEMP SPL SHORING

- REPAIR CALL-OUT LEGEND**
- E1 XX XX REPAIR QUANTITY UNIT
 - A1 XX XX ESTIMATED REPAIR QUANTITY
 - G1 XX XX REPAIR TYPE DESIGNATION - SEE BELOW

- REPAIR TYPE DESCRIPTION**
- (E1)** CLEANING AND SEALING JOINTS (CL 3)
 - (A1)** MINOR SPALL
 - (G1)** CSAB OPT 2
 - (H1)** SLAB TRANSITION

- NOTES:**
1. SEE "BRIDGE SPALL REPAIR DETAILS," "BRIDGE APPROACH SLAB (MOD)" AND "CLEANING AND SEALING EXISTING JOINTS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.
 2. CONTRACTOR TO ENSURE MINIMUM HEIGHT OF MBGF AS PER STANDARD DURING PAVEMENT INSTALLATION.
 3. REPLACING WINDROW TOPSOIL ALONG PAVEMENT EDGES WILL BE SUBSIDIARY TO ITEM 150-6001.
 4. FOR TYPICAL SECTION REFER TO "TYPICAL SECTIONS" SHEETS 4 & 5.



12/20/2022

NO.	DATE	REVISION	APPROV.



BRIDGE REPAIR LAYOUT
 TEHUACANA CREEK
 09-161-0-0162-01-008
 SHEET 2 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	65		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045, ETC	SH 81, ETC



REPAIR TYPE DESCRIPTION

- (A1) MINOR SPALL
- (A2) INTERMEDIATE SPALL (STANDARD)
- (J2) BENT CAP BEARING REPAIR

NOTES:
SEE "BRIDGE SPALL REPAIR DETAILS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.

TYPICAL DAMAGE CONDITION AT VARIOUS LOCATIONS

SPALL TYPE	LOCATION	UNIT	QTY
A2	BENT 4 NORTH & SOUTH FACE	SF	5
J2	BENT 4 NORTH FACE AT ORIGINAL SECTION ABOVE COLUMN 4 FROM WEST	SF	6
A2	BENT 5 SOUTH FACE	SF	6
A2	BENT 6 NORTH & SOUTH FACE	SF	8
J2	BENT 6 NORTH FACE AT SOUTHWEST END ABOVE COLUMN 2 FROM WEST	SF	6
A2	BENT 7 NORTH & SOUTH FACE	SF	12
A2	BENT 8 NORTH FACE	SF	8
A2	BENT 9 SOUTH FACE	SF	10
A2	BENT 10 NORTH & SOUTH FACE	SF	8
A2	BENT 11 SOUTH FACE	SF	10
A2	BENT 12 SOUTH FACE	SF	6
A2	BENT 13 SOUTH FACE	SF	10
A2	BENT 14 NORTH & SOUTH FACE	SF	16
A2	BENT 15 NORTH & SOUTH FACE	SF	4
A2	BENT 16 NORTH & SOUTH FACE	SF	6
A1	BENT 17 SOUTH FACE	SF	2
	TOTAL	SF	123

BRIDGE QUANTITIES				
ITEM	CODE	DESCRIPTION	UNIT	QTY
429	6002	CONC STR REPAIR (EPOXY MORTAR) (A1)	SF	2
429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD) (A2) (J2)	SF	121

SCALE: NTS




Alfonso D. Perez
12/20/2022



SUBSTRUCTURE REPAIR
TEHUACANA CREEK
09-161-0-0162-01-008


FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	66
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO. JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014 06 045.ETC	SH 81, ETC



- LEGEND**
- APPROACH SLAB
 - CLEANING AND SEALING EXISTING JOINTS SEE DETAIL
 - PLANE ASPH CONC PAV UNDERSEAL COURSE 2" HMAC OVERLAY
 - SOFFIT UNDER DECK
 - PROPOSED STONE RIPRAP SRR (18 IN)
 - LIMITS OF CSAB
 - TEMP SPL SHORING
- REPAIR CALL-OUT LEGEND**
- REPAIR QUANTITY UNIT
 - ESTIMATED REPAIR QUANTITY
 - REPAIR TYPE DESIGNATION - SEE BELOW

- REPAIR TYPE DESCRIPTION**
- (E1) CLEANING AND SEALING EXISTING JOINTS
 - (A2) INTERMEDIATE SPALL
 - (G1) CSAB OPT 2
 - (C1) PROPOSED RAIL RETROFIT (TY T552)

- NOTES:**
- SEE "BRIDGE SPALL REPAIR DETAILS," AND "CLEANING AND SEALING EXISTING JOINTS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE ON EXISTING SIGN.
 - PLACE SEEDING 3 FEET AWAY FROM PROPOSED MOWSTRIP.
 - FOR TYPICAL SECTION REFER TO "TYPICAL SECTIONS" SHEET 6.



0 10' 20'
SCALE: 1" = 20' HORZ
1" = 20' VERT

STATE OF TEXAS
ALFONSO D. PEREZ
120369
LICENSED PROFESSIONAL ENGINEER

12/20/2022

NO.	DATE	REVISION	APPROV.

consor
F-12040
© 2023

Texas Department of Transportation


BRIDGE REPAIR LAYOUT
LOVELACE CREEK
09-110-0-014-06-075
SHEET 1 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	67		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\dgn\01_Master_Design_Files\Prime\BRIDGE_LAYOUTS\Lowlace_Creek\LOCATION_02.dgn
2:59:40 PM
12/20/2022

12/20/2022 2:59:40 PM

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\dgn\01_Master_Design_Files\Prime\BRIDGE_LAYOUTS\Lowlace_Creek\LOCATION_02.dgn



PLAN

LEGEND

- APPROACH SLAB
- CLEANING AND SEALING EXISTING JOINTS SEE DETAIL
- PLANE ASPH CONC PAV UNDERSEAL COURSE 2" HMAC OVERLAY
- SOFFIT UNDER DECK
- PROPOSED STONE RIPRAP SRR (18 IN)
- LIMITS OF CSAB
- TEMP SPL SHORING

REPAIR CALL-OUT LEGEND

- REPAIR QUANTITY UNIT
- ESTIMATED REPAIR QUANTITY
- REPAIR TYPE DESIGNATION - SEE BELOW


REPAIR TYPE DESCRIPTION

- (E1) CLEANING AND SEALING EXISTING JOINTS
- (A2) INTERMEDIATE SPALL
- (G1) CSAB OPT 2
- (C1) PROPOSED RAIL RETROFIT (TY T552)

NOTES:

1. SEE "BRIDGE SPALL REPAIR DETAILS," AND "CLEANING AND SEALING EXISTING JOINTS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE ON EXISTING SIGN.
3. PLACE SEEDING 3 FEET AWAY FROM PROPOSED MOWSTRIP.
4. FOR TYPICAL SECTION REFER TO "TYPICAL SECTIONS" SHEET 6.

BRIDGE QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
100	6002	PREPARING ROW	STA	2	-	2
104	6009	REMOVING CONC (RIPRAP)	SY	244	-	244
105	6022	REMOVING STAB BASE AND ASPH PAVE (13")	SY	196	-	196
164	6003	BROADCAST SEED (PERM) (RURAL) (CLAY)	SY	134	53	187
168	6001	VEGETATIVE WATERING	MG	11	4	15
354	6024	PLANE ASPH CONC PAV (2"-4")	SY	1975	518	2493
400	6005	CEM STABIL BKFL (G1)	CY	94	-	94
403	6001	TEMPORARY SPL SHORING	SF	200	-	200
422	6015	APPROACH SLAB	CY	70	-	70
429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD) (A2)	SF	562	-	562
432	6033	RIPRAP (STONE PROTECTION) (18IN)	CY	80	-	80
432	6045	RIPRAP (MOW STRIP) (4IN)	CY	20	5	25
438	6006	CLEANING AND SEALING JOINTS (CL 3) (E1)	LF	88	-	88
451	6017	RETROFIT RAIL (TY T552) (C1)	LF	236	-	236
540	6002	MTL W-BEAM GD FEN (STEEL POST)	LF	221	29	250
540	6006	MTL BEAM GD FEN TRANS (THRIE BEAM)	EA	4	-	4
542	6001	REMOVE METAL BEAM GUARD FENCE	LF	221	29	250
542	6005	RM MTL BM GD FEN TRANS (T101)	LF	4	-	4
544	6001	GUARDRAIL END TREATMENT (INSTALL)	EA	2	2	4
544	6003	GUARDRAIL END TREATMENT (REMOVE)	EA	3	1	4
3076	6026	D-GR HMA TY-C SAC-B PG 70-22 (EXEMPT)	TON	217	57	274
3085	6001	UNDERSEAL COURSE	GAL	494	130	623



12/20/2022



BRIDGE REPAIR LAYOUT

LOVELACE CREEK
09-110-0-014-06-075

SHEET 2 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		68
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ETC

P:_V-TPD\Projects\TX\2019\01902471X.05\1_Design\500_CADD\ dgn\01_Master_Design_Files\Prime\BRIDGE_LAYOUTS\ Lovelace_Creek\LOCATION_02-2.dgn
 1:37:58 PM
 12/20/2022

SPALL TYPE	LOCATION	UNIT	QTY
A2	BENT 2 NORTH FACE	SF	8
A2	BENT 3 NORTH & SOUTH FACE	SF	8
A2	BENT 4 NORTH & SOUTH FACE	SF	16
TOTAL		SF	32



REPAIR TYPE DESCRIPTION

- (A1) MINOR SPALL
- (A2) INTERMEDIATE SPALL (STANDARD)

NOTES:
SEE "BRIDGE SPALL REPAIR DETAILS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.



TYPICAL DAMAGE CONDITION AT VARIOUS LOCATIONS

SCALE: NTS

12/20/2022

NO.	DATE	REVISION	APPROV.


F-12040
 © 2023

SUBSTRUCTURE REPAIR
LOVELACE CREEK
09-110-0-014-06-075

SHEET 1 OF 1

BRIDGE QUANTITIES				
ITEM	CODE	DESCRIPTION	UNIT	QTY
429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD) (A2)	SF	32

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	69		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC




- LEGEND**
- APPROACH SLAB
 - CLEANING AND SEALING EXISTING JOINTS SEE DETAIL
 - PLANE ASPH CONC PAV UNDERSEAL COURSE 2" HMAC OVERLAY
 - SOFFIT UNDER DECK
 - PROPOSED STONE RIPRAP SRR (18 IN)
 - LIMITS OF CSAB
 - END MBGF & BEGIN RAIL T552
 - TEMP SPL SHORING


- REPAIR CALL-OUT LEGEND**
- XX XX REPAIR QUANTITY UNIT
 - XX XX ESTIMATED REPAIR QUANTITY
 - REPAIR TYPE DESIGNATION - SEE BELOW

- REPAIR TYPE DESCRIPTION**
- (E1) CLEANING AND SEALING EXISTING JOINTS
 - (A2) INTERMEDIATE SPALL
 - (G1) CSAB OPT 2
 - (C1) PROPOSED RAIL RETROFIT (TY T552)

- NOTES:**
- SEE "BRIDGE SPALL REPAIR DETAILS" AND "CLEANING AND SEALING EXISTING JOINTS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.
 - PLACE SEEDING 3 FEET AWAY FROM PROPOSED MOWSTRIP.
 - FOR TYPICAL SECTION REFER TO "TYPICAL SECTIONS" SHEET 7.



PLAN



STATE OF TEXAS
 ALFONSO D. PEREZ
 120369
 LICENSED PROFESSIONAL ENGINEER
 12/20/2022




BRIDGE REPAIR LAYOUT
 LITTLE HACKBERRY CREEK
 09-110-0-014-06-077

SHEET 1 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	70
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO.	JOB NO. HIGHWAY NO.
WAC	HILLETC	0014 06	045.ETC SH 81, ETC

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\ dgn\01_Master_Design_Files\Prime\BRIDGE_LAYOUTS\Little Hackberry Creek\LOCATION 03.dgn
 2:59:46 PM
 12/20/2022



PLAN

LEGEND

- APPROACH SLAB
- CLEANING AND SEALING EXISTING JOINTS SEE DETAIL
- PLANE ASPH CONC PAV UNDERSEAL COURSE 2" HMAC OVERLAY
- SOFFIT UNDER DECK
- PROPOSED STONE RIPRAP SRR (18 IN)
- LIMITS OF CSAB
- TEMP SPL SHORING

REPAIR CALL-OUT LEGEND

- REPAIR QUANTITY UNIT
- ESTIMATED REPAIR QUANTITY
- REPAIR TYPE DESIGNATION - SEE BELOW



REPAIR TYPE DESCRIPTION

- (E1) CLEANING AND SEALING EXISTING JOINTS
- (A2) INTERMEDIATE SPALL
- (G1) CSAB OPT 2
- (C1) PROPOSED RAIL RETROFIT (TY T552)

NOTES:

1. SEE "BRIDGE SPALL REPAIR DETAILS," AND "CLEANING AND SEALING EXISTING JOINTS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.
2. PLACE SEEDING 3 FEET AWAY FROM PROPOSED MOWSTRIP.
3. FOR TYPICAL SECTION REFER TO "TYPICAL SECTIONS" SHEET 7.

BRIDGE QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
100	6002	PREPARING ROW	STA	2	-	2
104	6009	REMOVING CONC (RIPRAP)	SY	244	-	244
105	6022	REMOVING STAB BASE AND ASPH PAV (13")	SY	196	-	196
164	6003	BROADCAST SEED (PERM) (RURAL) (CLAY)	SY	116	71	187
168	6001	VEGETATIVE WATERING	MG	11	4	15
354	6024	PLANE ASPH CONC PAV (2"-4")	SY	1975	714	2689
400	6005	CEM STABIL BKFL (G1)	CY	94	-	94
403	6001	TEMPORARY SPL SHORING	SF	200	-	200
422	6015	APPROACH SLAB	CY	70	-	70
429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD) (A2)	SF	286	-	286
432	6033	RIPRAP (STONE PROTECTION) (18IN)	CY	80	-	80
432	6045	RIPRAP (MOW STRIP) (4IN)	CY	17	8	25
438	6006	CLEANING AND SEALING JOINTS (CL 3) (E1)	LF	176	-	176
451	6017	RETROFIT RAIL (TY T552) (C1)	LF	316	-	316
540	6002	MTL W-BEAM GD FEN (STEEL POST)	LF	221	29	250
540	6006	MTL BEAM GD FEN TRANS (THRIE BEAM)	EA	4	-	4
542	6001	REMOVE METAL BEAM GUARD FENCE	LF	221	29	250
542	6005	RM MTL BM GD FEN TRANS (T101)	EA	4	-	4
544	6001	GUARDRAIL END TREATMENT (INSTALL)	EA	2	2	4
544	6003	GUARDRAIL END TREATMENT (REMOVE)	EA	2	2	4
3076	6026	D-GR HMA TY-C SAC-B PG 70-22 (EXEMPT)	TON	217	79	296
3085	6001	UNDERSEAL COURSE	GAL	494	178	672



BRIDGE REPAIR LAYOUT

LITTLE HACKBERRY CREEK
09-110-0-014-06-077

SHEET 2 OF 2

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), etc.		71
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILLETC	0014	06	045.ETC SH 81, ET

SPALL TYPE	LOCATION	UNIT	QTY
A2	BENT 2 SOUTH FACE	SF	4
A2	BENT 3 NORTH FACE	SF	15
A2	BENT 5 NORTH FACE	SF	56
TOTAL		SF	75



TYPICAL DAMAGE CONDITION AT VARIOUS LOCATIONS

REPAIR TYPE DESCRIPTION

(A2) INTERMEDIATE SPALL (STANDARD)

NOTES:

SEE "BRIDGE SPALL REPAIR DETAILS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.

SCALE: NTS



NO.	DATE	REVISION	APPROV.




SUBSTRUCTURE REPAIR
LITTLE HACKBERRY CREEK
09-110-0-014-06-077

SHEET 1 OF 1


BRIDGE QUANTITIES				
ITEM	CODE	DESCRIPTION	UNIT	QTY
429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD) (A2)	SF	75

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	72		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC


- (A1) **Minor Spall**
1. Identify and mark all repair locations prior to beginning work. Verify areas and quantities with the Engineer. Provide access for the Engineer to inspect and verify repair areas.
 2. Prepare detailed repair procedure in accordance with Chapter 3, Section 1 of the TxDOT Concrete Repair Manual.
 3. If greater than 1/2 of bar is exposed, proceed as Intermediate Spall Repair.
 4. Repairs are paid as Item 429 6002 Conc Str Repair (Epoxy Mortar).
- (A2) **Intermediate Spall (Vertical & Overhead)**
1. Identify and mark all repair locations prior to beginning work. Verify areas and quantities with the Engineer. Provide access for the Engineer to inspect and verify repair areas.
 2. Prepare detailed repair procedure in accordance with Chapter 3, Section 2 of the TxDOT Concrete Repair Manual and Intermediate Concrete Repair Detail.
 3. Trowel apply repair materials to a maximum depth of 4". Repairs deeper than 4" should be formed and poured in accordance with Chapter 3, Section 2 of the TxDOT Concrete Repair Manual. Bagged concrete (extended) is permissible for formed and poured repairs.
 4. Repairs are paid as Item 429 Concrete Structure Repair (Vertical and Overhead).
 5. Applies to following scenarios.



INTERMEDIATE CONCRETE (A2) REPAIR DETAIL



SECTION (BENT) PLAN (COLUMN/PILE)




PLAN SECTION A-A BENT CAP BEARING REPAIR DETAIL (J2) NTS

BEARING REPAIR NOTES:

Repair as major spall per TxDOT Concrete Repair Manual Chapter 3, Section 3. Form repair area to lines shown. Use of prepackaged repair material is permissible.

Paid for as Item 429 6007, "Conc str repair (vertical & overhead)

Quantity is based on total formed area.



Follow anchor system manufacturer's recommended installation depth, 6" min.

SCALE: NTS

STATE OF TEXAS
ALFONSO D. PEREZ
120369
LICENSED PROFESSIONAL ENGINEER

12/20/2022


NO.	DATE	REVISION	APPROV.

consor F-12040
© 2023
Texas Department of Transportation

BRIDGE SPALL REPAIR DETAILS

SHEET 1 OF 1


FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT			SHEET NO.
6	TEXAS	BR 2023(500), etc.			73
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC



JOINT WITH HOT POURED RUBBER SEAL
(USED WITH ACP OVERLAY)

PROCEDURE FOR CLEANING AND SEALING EXISTING CONCRETE GIRDER JOINT WITH HOT POURED RUBBER SEAL:

- 1) SAW CUT THROUGH THE ASPHALT AT THE CENTERLINE OF JOINT. MAKE MULTIPLE SAW CUTS TO CREATE A 1/2" MINIMUM JOINT OPENING OR MATCH THE EXISTING JOINT OPENING. CLEAN JOINT OPENING OF ALL OLD EXPANSION MATERIALS/DEVICES, BITUMINOUS MATERIALS, DIRT, GREASE AND ALL OTHER DELETERIOUS MATERIALS IN ACCORDANCE WITH ITEM 438, "CLEANING AND SEALING JOINTS."
- 2) OBTAIN APPROVAL OF CLEANED JOINT PRIOR TO PROCEEDING WITH JOINT SEALING OPERATION.
- 3) PLACE BACKER ROD INTO JOINT OPENING 1" BELOW THE TOP OF CONCRETE. BACKER ROD MUST BE OF THE TYPE THAT CAN HANDLE THE HEAT AND BE COMPATIBLE WITH THE HOT POURED RUBBER SEAL. THE BACKER ROD MUST BE 25% LARGER THAN THE JOINT OPENING.
- 4) SEAL THE JOINT OPENING WITH A CLASS 3, "HOT POURED RUBBER." SEAL FLUSH TO THE TOP OF THE ASPHALTIC CONCRETE PAVEMENT.



GENERAL NOTES:

CLEANING EXISTING JOINT OPENING (FULL DEPTH) OF ALL DEBRIS, PROVIDING AND PLACING BACKER ROD, SAW-CUTTING JOINT OPENING, AND SEALING JOINT IS PAID FOR BY AND MEASURED BY THE FOOT OF "CLEANING AND SEALING EXISTING JOINTS."

OBTAIN APPROVAL FOR ALL TOOLS, EQUIPMENT, MATERIALS AND TECHNIQUES PROPOSED FOR USE TO PREPARE THE JOINT.

FOR CLASS 3 HOT POURED RUBBER SEAL, PROVIDE BACKER ROD COMPATIBLE WITH THE HOT POURED RUBBER SEALANT AND RATED FOR A MINIMUM OF 400°F.

PROVIDE CLASS 3 SEALANT IN ACCORDANCE WITH DMS-6310, "JOINT SEALANTS AND FILLERS" FOR JOINTS IN ASPHALT OVERLAY.


- ① BACKER ROD MUST BE 25% LARGER THAN JOINT OPENING AND MUST BE COMPATIBLE WITH THE SEALANT. USE OF MULTIPLE PIECES TO CREATE A BACKER ROD CROSS SECTION IS NOT PERMITTED. TOP OF BACKER ROD MUST BE CONVEX AS SHOWN.
- ② USE CLASS 3 HOT POURED RUBBER SEAL. PREPARE JOINT AND SEAL IN ACCORDANCE WITH ITEM 438 "CLEANING AND SEALING JOINTS."

EXISTING CONCRETE SLAB & GIRDER JOINT REPAIR

E1


PROCEDURES:

- 3) A tack coat must be applied if the surface has been milled.




FABRIC JOINT SEAL WITH HOT POURED RUBBER

- 1) PRIOR TO THE PLACEMENT OF THE FABRIC JOINT UNDERSEAL, CLEAN JOINT OPENING OF ALL OLD EXPANSION MATERIALS/DEVICES, BITUMINOUS MATERIALS, DIRT, GREASE, AND ALL OTHER DELETERIOUS MATERIALS IN ACCORDANCE WITH ITEM 438, "CLEANING AND SEALING JOINTS."
- 2) REPAIR ANY SIGNIFICANT SPALLED OR CRACKED AREAS, AS DETERMINED BY THE ENGINEER, AROUND THE JOINT OPENING WITH TYPE II POLYMER CONCRETE IN ACCORDANCE WITH DMS-6140, "POLYMER CONCRETE FOR JOINT SYSTEMS". THIS WORK WILL BE PAID FOR BY ITEM 429 "CNC STR REP (STANDARD)".
- 3) PLACE TACK COAT OR BINDER AS REQUIRED BY THE FABRIC JOINT UNDERSEAL MANUFACTURER'S INSTALLATION INSTRUCTIONS. PLACE BACKER ROD IN JOINT OPENING PRIOR TO PLACING TACK COAT.
- 4) PLACE REINFORCED FABRIC JOINT UNDERSEAL CENTERED OVER JOINT OPENING. TUCK FABRIC DOWN APPROXIMATELY 1/2" INTO THE JOINT OPENING. INSTALL UNDERSEAL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- 5) WHEN USING THE SELF-ADHESIVE TYPE FABRIC UNDERSEAL, PRESSURE ROLL FABRIC JOINT UNDERSEAL TO IMPROVE ADHESION.
- 6) JUST PRIOR TO PAVING, FILL TUCKED IN PORTION OF UNDERSEAL WITH SAND FLUSH WITH SURFACE. APPLY A TACK COAT TO FABRIC JOINT UNDERSEAL AS REQUIRED BY THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. MARK LOCATION OF CENTERLINE OF JOINT ON CURB OR BARRIER AS APPROVED.
- 7) AFTER THE ASPHALTIC CONCRETE PAVEMENT OPERATIONS ARE COMPLETE, SAW CUT 1" INTO THE ASPHALT AT CENTERLINE OF JOINT. MAKE MULTIPLE SAW CUTS TO CREATE A 3/4" JOINT OPENING OR MATCH THE EXISTING JOINT OPENING, WHICHEVER IS GREATER. DO NOT DAMAGE THE UNDERSEAL.
- 8) SEAL THE JOINT OPENING WITH A CLASS 3, "HOT POURED RUBBER." SEAL FLUSH WITH THE TOP OF THE ASPHALTIC CONCRETE PAVEMENT.



SCALE: NTS




12/20/2022




CLEANING AND SEALING EXISTING BRIDGE JOINTS

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), etc.	74		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC




1) showing location of anchor bars and anchor bolts in a rail retrofit condition. See appropriate rail standard for details and notes not shown.



T552 RAIL

RAIL RETROFIT SECTIONS ON CONCRETE SLABS USING ADHESIVE ANCHORS 5 11



T552 RAIL

RAIL RETROFIT SECTIONS ON WINGWALLS USING ADHESIVE ANCHORS 5

Rail retrofits on existing Traffic Rail Foundations (TRF) are similar.


- 1 Embed (#6) anchor bars with a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 5 1/4". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 20 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing".
- 2 See T552 Rail Sections in "Rail Retrofit Section on Wingwalls using Adhesive Anchors" and/or "Rail Retrofit Section on Concrete Slabs using Adhesive Anchors".
- 3 Showing spacing of (#6) adhesive anchor in a rail retrofit condition. Secondary (#4) adhesive anchor in a rail retrofit not shown for clarity. Reinforcing steel and terminal connections not shown for clarity. See rail standard for details and notes not shown.
- 4 Place side slot drains as shown. See appropriate rail standard for side slot drains, except as noted.
- 5 Showing location or locations of anchor bars in a rail retrofit condition. See appropriate rail standard for details and notes not shown.
- 6 Increase by amount of existing overlay/seal coat thickness, not to exceed 2". If thickness of existing overlay/seal coat is greater than 2" at toe of rail, taper overlay at a 1:10 or flatter slope over shoulder width to a thickness of 2" or less at toe of rail.
- 7 Do not cast rails or parapet walls on top of overlays/seal coats.
- 8 See appropriate rail standard for reinforcing steel. Modify length of vertical reinforcing bars as required to fit existing structure. Longitudinal reinforcing bars may be removed only if their position puts them in conflict with un-removed portions of existing structure.
- 9 Embed secondary (#4) anchor bars 1'-4" in length with a Type III Class C, D, E, or anchor adhesive. Minimum adhesive anchor embedment depth is 4". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 10 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing". (#4) anchor bars spaced longitudinally along rail at 4 ft Max (Spaced 3" longitudinally from outside edge and edge of side slot drains).
- 10 1" Dia Anchor Bolt Spaced longitudinally along rail at 20" Max (Spaced 6" longitudinally from outside edge and edge of side slot drains).



12/20/2022

NO.		DATE		REVISION	APPROV.
F-12040					
© 2023					
RETROFIT TRAFFIC RAIL T552 (MOD)					
SHEET 1 OF 1					
FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		75	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

DATE: 12/20/2022 2:59:58 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\ dgn\01_Master_Design_Files\Prjme\TXDOT_Standards\basasr1-20-1.dgn




SECTIONS DETAIL

- ① Flare Bars B and D in this region (1'-6" Max Spa, 3" Min Spa). Minimum flared bar length = 2'-6". Bend bars as necessary.
- ② Provide longitudinal construction joints that align with longitudinal construction joints in the bridge slab with bridges built in stages. Other longitudinal construction joints must receive approval of the Engineer.
- ③ See details elsewhere in plans for shoulder drain location and details.
- ④ For Contractor's information only. Quantities shown are for one approach slab.
- ⑤ Multiple piece tie bars are acceptable at longitudinal construction joints provided minimum laps shown are achieved.
- ⑥ See details elsewhere in plans for required cross-slope.
- ⑦ Place in accordance with Item 438.
- ⑧ Provide backer rod that is 25% larger than joint opening and compatible with the sealant.
- ⑨ If bridge rail is present at the wingwall or CIP retaining wall, place 1/2" rebonded recycled tire rubber between concrete railing and top of approach slab as shown when concrete railing projects over the approach slab.

BAR TABLE	
BAR	SIZE
A	#8
B	#5
D	#5
T	#5

GENERAL NOTES:
 Construct approach slab in accordance with Item 422. Provide Class "S" concrete with a minimum compressive strength of 4,000 psi. Provide Grade 60 reinforcing steel. Provide longitudinal joints as shown on the Longitudinal Saw Cut Joint Detail at lane lines and shoulders when width between longitudinal construction joints or edges of approach slab exceeds 16 feet. Saw cut joints within 24 hours of concrete placement to a depth of 1 1/2" and seal in accordance with Item 438. Alternately, provide a controlled joint consisting of 1 1/2" vinyl or plastic joint former (Stress Cap, Zip Strip, Stress Lock, or equal as approved by the Engineer.) Provide rebonded recycled tire rubber joint filler that meets the requirements of DMS-6310. "Joint Sealants and Fillers." Construct the subgrade or subbase away from the bridge for a minimum distance of 100 feet prior to the approach slab, unless otherwise indicated on the plans. Compact and finish the subgrade or foundation for the approach slab to the typical cross-section and to the lines and grades shown on the plans. Cure for 4 days using water or membrane curing per Item 422. All details shown herein are subsidiary to bridge approach slab.


Cover dimensions are clear dimensions, unless noted otherwise.




TYPICAL TRANSVERSE SECTION

APPROXIMATE QUANTITIES ④	
Reinf steel weight =	8.5 Lbs/SF of Approach Slab
Volume of Appr Slab Conc (CY) =	0.802W + 0.02W ² Tan S
W =	Width of Approach Slab (ft)
S =	Skew Angle (deg)


SCALE: NTS




SECTION A-A




SECTION B-B




SECTION C-C ⑤




SECTION D-D




SECTION E-E



SEALED CONSTRUCTION JOINT DETAIL



ISOLATION JOINT DETAIL



LONGITUDINAL SAW CUT JOINT DETAIL

NO.	DATE	REVISION	APPROV.



F-12040

© 2023



BRIDGE APPROACH SLAB (MOD)


TEHUACANA CREEK
 09-161-0-0162-01-008

SHEET 1 OF 1

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		76	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILL, ETC	0014	06	045, ETC	SH 81, ETC

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any project not intended by TxDOT.

DATE: 12/20/2022 2:59:59 PM
 FILE: P:_V-TPD\Projects\TX2019\190247TX_05\1_Design\500_CADD\dgn\01_Material\Basaste1-20.dgn







BAR TABLE	
BAR	SIZE
A	#8
B	#5
D	#5
T	#5

APPROXIMATE QUANTITIES ⁽⁴⁾	
Reinf steel weight = 8.5 Lbs/SF of Approach Slab	
Volume of Appr Slab Conc (CY) = 0.802W + 0.02W ² Tan S	
W = Width of Approach Slab (ft)	
S = Skew Angle (deg)	

- Flare Bars B and D in this region (1'-6" Max Spa, 3" Min Spa). Minimum flared bar length = 2'-6". Bend bars as necessary.
- Provide longitudinal construction joints that align with longitudinal construction joints in the bridge slab with bridges built in stages. Other longitudinal construction joints must receive approval of the Engineer.
- See details elsewhere in plans for shoulder drain location and details.
- For Contractor's information only. Quantities shown are for one approach slab.
- Multiple piece tie bars are acceptable at longitudinal construction joints provided minimum laps shown are achieved.
- See details elsewhere in plans for required cross-slope.
- Place in accordance with Item 438.
- Provide backer rod that is 25% larger than joint opening and compatible with the sealant.
- If bridge rail is present at the wingwall or CIP retaining wall, place 1/2" rebonded recycled tire rubber between concrete railing and top of approach slab as shown when concrete railing projects over the approach slab.

LONGITUDINAL SAW CUT JOINT DETAIL




GENERAL NOTES:
 Construct approach slab in accordance with Item 422. Provide Class "S" concrete with a minimum compressive strength of 4,000 psi. Provide Grade 60 reinforcing steel. Provide longitudinal joints as shown on the Longitudinal Saw Cut Joint Detail at lane lines and shoulders when width between longitudinal construction joints or edges of approach slab exceeds 16 feet. Saw cut joints within 24 hours of concrete placement to a depth of 1 1/2" and seal in accordance with Item 438. Alternately, provide a controlled joint consisting of 1 1/2" vinyl or plastic joint former (Stress Cap, Zip Strip, Stress Lock, or equal as approved by the Engineer.) Provide rebonded recycled tire rubber joint filler that meets the requirements of DMS-6310. "Joint Sealants and Fillers." Construct the subgrade or subbase away from the bridge for a minimum distance of 100 feet prior to the approach slab, unless otherwise indicated on the plans. Compact and finish the subgrade or foundation for the approach slab to the typical cross-section and to the lines and grades shown on the plans. Cure for 4 days using water or membrane curing per Item 422. All details shown herein are subsidiary to bridge approach slab. Cover dimensions are clear dimensions, unless noted otherwise.

		Bridge Division Standard	
BRIDGE APPROACH SLAB ASPHALTIC CONCRETE PAVEMENT			
BAS-A			
FILE: basaste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT April 2019	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC
02-20: Removed stress relieving pad.	DIST	COUNTY	SHEET NO.
	WAC	HILL, ETC	77


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

DATE: 12/20/2022 3:00:00 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_051_Design\500_CADD\agn\01_Master\190247TX_051.dgn



OPTION 1 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.




OPTION 1 ~ PLAN WITH MSE RETAINING WALLS


- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a) If flowable backfill is to be placed over MSE backfill then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b) Place flowable fill in lifts not exceeding 2 feet in height, place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).

GENERAL NOTES:

See the Bridge Layout for selected Option. Option 2 is intended for new construction requiring high plasticity embankment fill with a plasticity index (PI) greater than 30 or pavement built in poor native soil. Poor soils are defined as high plasticity clays or expansive clays. Option 1 is intended for construction only requiring PI controlled embankment fill or excavation in competent soils/rocks in order to construct the abutment. Provide Cement Stabilized Backfill (CSB) meeting the requirements of Item 400, "Excavation and Backfill for Structures", to the limits shown at bridge abutments. If required elsewhere in the plans, provide Flowable Backfill meeting the requirements of Item 401, "Flowable Backfill", to the limits shown at bridge abutments. Details are drawn showing left forward skew. See Bridge Layout for actual skew direction. These details do not apply when Concrete Block retaining walls are used in lieu of wingwalls.



WITHOUT APPROACH SLAB



WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)

SECTION A-A

SHEET 1 OF 2




CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT

CSAB

FILE: csabste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
02-20: Added Option 2.	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	78	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein. For more information, contact TxDOT at 1-800-392-2111 or www.txdot.gov.

DATE: 12/20/2022 3:00:01 PM
 FILE: P:\V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\dgn\01_Material\01_01_01_01_01_01_01_01.dgn




OPTION 2 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.




OPTION 2 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a). If flowable backfill is to be placed over MSE backfill then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b). Place flowable fill in lifts not exceeding 2 feet in height, place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).



WITHOUT APPROACH SLAB



SECTION B-B

WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)

SHEET 2 OF 2




**CEMENT STABILIZED
 ABUTMENT BACKFILL
 BRIDGE ABUTMENT**

CSAB


FILE: csabste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT	APRIL 2019	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC	SH 81, ETC
02-20: Added Option 2.	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	79	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from its use.


DATE: 12/20/2022 3:00:01 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\dgn\01_Master\Bridges\Bridges.dgn




PLAN



ELEVATION




SECTION A-A AT CAP




SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A



CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2

		Bridge Division Standard	
<h1>STONE RIPRAP</h1>			
<h2>SRR</h2>			
FILE: srrstd1-19.dgn	DN: AES	CK: JGD	DW: BWH
©TxDOT April 2019	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC
	DIST	COUNTY	SHEET NO.
	WAC	HILL, ETC	80

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project not intended by the original author.

DATE: 12/20/2022 3:00:03 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX.05\1_Design\500_CADD\dgn\01_Master\190247TX.dgn




FIGURE 1 ~ TYPE R STONE RIPRAP
dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP
dry or mortared




FIGURE 3 ~ TYPE F STONE RIPRAP
grouted




FIGURE 4 ~ COMMON STONE RIPRAP
dry or grouted





FIGURE 5 ~ PROTECTION STONE RIPRAP (5)

- (2) Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- (3) Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- (4) "Y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- (5) List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



PROTECTION STONE RIPRAP TOE OPTIONS (5)


STONE RIPRAP

SRR


FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	81	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any project not intended by TxDOT.


DATE: 12/20/2022 3:00:03 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\dgn\01_Masthead.dgn




ROADWAY ELEVATION OF RAIL




INTERMEDIATE WALL JOINT DETAIL
 Provide at all interior bents without slab expansion joints.



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT



SECTION
ELEVATION
TERMINAL CONNECTION DETAILS



PLAN OF RAIL AT EXPANSION JOINTS
 Example showing Slab Expansion Joints without breakbacks.


- 1 Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- 2 Increase 2" for structures with overlay.
- 3 Place 4 additional Bars R(#4) 3'-8" in length inside Bars S(#4) and centered 2'-0" from end of rail when Terminal Connections are required.
- 4 Back of rail offset may, with Engineer's approval, be continued to the end of the railing.

SHEET 1 OF 2

		Bridge Division Standard	
<h1>TRAFFIC RAIL</h1>			
<h2>TYPE T552</h2>			
FILE: r1std010-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONT	SECT	HIGHWAY
REVISIONS	0014	06	045, ETC SH 81, ETC
DIST	COUNTY		SHEET NO.
WAC	HILL, ETC		82

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. This standard is not to be construed as a contract.

DATE: 12/20/2022 3:00:04 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\dgn\01_Masthead.dgn





ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS

ON BRIDGE SLAB


ON BRIDGE SLAB AT SIDE SLOT DRAIN

SECTION THRU RAIL


- ② Increase 2" for structures with overlay.
- ⑤ 5/4" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑥ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars will be furnished at the Contractor's expense.
- ⑦ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑧ Bend or cut as required to clear drain slots.
- ⑨ No longitudinal wires may be in top center of cage.




BARS S (#4)



BARS U (#4)




BARS WU (#4)




OPTIONAL WELDED WIRE REINFORCEMENT (WWR)

DESCRIPTION	LONGITUDINAL WIRES	VERTICAL WIRES
Minimum (Cumulative Total) Wire Area	1.067 Sq In.	0.267 Sq In. per Ft
Minimum	No. of Wires	Spacing
Maximum	8	4"
	10	8"
Maximum Wire Size Differential	The smaller wire must have an area of 40% or more of the larger wire.	



CAST-IN-PLACE WATER BARRIER



PRECAST WATER BARRIER

OPTIONAL WATER BARRIERS

CONSTRUCTION NOTES:
 This railing may be constructed by the slipform process when approved by the Engineer, with equipment approved by the Engineer. Provide sensor control for both line and grade. Tack welding to provide bracing for slipform operations is acceptable. Welding may be performed at a minimum spacing of 3 ft between the cage and the anchorage. It is permissible to weld to bars U, WU and S at any location on the cage. If increased bracing is needed, provide additional anchorage devices and weld in the upper two thirds of the cage. Paint welded areas on epoxy coated and/or galvanized reinforcing with an organic zinc rich paint in accordance with Item 445 "Galvanizing".
 If rail is slipformed, apply an heavy epoxy bead 1" behind toe of traffic side of rail to concrete deck just prior to slip forming. Provide a 3/8" width x 1/4" tall heavy epoxy bead with Type III, Class C or a Type V epoxy.
 The back of railing must be vertical unless otherwise shown on the plans or approved by the Engineer.
 Water barriers must be provided at openings draining onto railroad tracks, undercrossing roadways and sidewalks. They may be cast in place or precast in convenient length and bonded to the bridge deck with an approved epoxy cement.

MATERIAL NOTES:
 Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.
 Provide Grade 60 reinforcing steel.
 Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized.
 Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars U and WU unless noted otherwise. Deformed WWR (ASTM A1064) may be substituted for Bars R and S, as shown. Combinations of reinforcing steel and WWR or configurations of WWR other than shown are permitted if conditions in the table are satisfied. Provide the same laps as required for reinforcing bars.
 Provide bar laps, where required, as follows:
 Uncoated or galvanized ~ #4 = 1'-7"
 Epoxy coated ~ #4 = 2'-5"

GENERAL NOTES:
 This rail has been evaluated and accepted to be of equal strength to railings with like geometry, which have been crash tested to meet MASH TL-3 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.
 Do not use this railing on bridges with expansion joints providing more than 5" movement.
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
 Shop drawings will not be required for this rail.
 Average weight of railing with no overlay is 370 plf.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.




TRAFFIC RAIL


TYPE T552

FILE: r1std010-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: TxDOT
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	83	

PAVEMENT MARKING QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
658	6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	14	10	24
666	6300	RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)	LF	427	371	798
666	6303	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	LF	427	371	798
666	6315	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	LF	427	371	798
672	6010	REFL PAV MRKR TY II-C-R	EA	12	10	22






BEGIN PAVEMENT MARKING
STA 317+03.15
MATCH EXIST PAV MARKING



LEGEND

- A RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)
- B RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
- C RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
- D RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)
- E REFL PAV MRKR TY II-A-A
- F REFL PAV MRKR TY II-C-R
- △ DEL ASSM (D-SW)SZ (BRF)CTB (BI)
- ⇨ TRAFFIC DIRECTION






12/20/2022



PAVEMENT MARKING LAYOUT
TEHUACANA CREEK RELIEF
09-161-0-0162-01-008
SHEET 1 OF 6



FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	84
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO. JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014 06 045, ETC	SH 81, ETC

\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\dm\01_Master_Design_Files\Prime\SPM\Teahuacana\SPM_01.dgn



LEGEND

- A RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)
- B RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
- C RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
- D RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)
- E REFL PAV MRKR TY II-A-A
- F REFL PAV MRKR TY II-C-R
- ⇨ TRAFFIC DIRECTION



Alfonso D. Perez 12/20/2022

NO.	DATE	REVISION	APPROV.




PAVEMENT MARKING LAYOUT
 TEHUACANA CREEK RELIEF
 09-161-0-0162-01-008
 SHEET 2 OF 6

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		85	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC



BEGIN PAVEMENT MARKING
STA 587+85.00
MATCH EXIST PAV MARKING




MATCHLINE STA 589+85


PAVEMENT MARKING QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
658	6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	5	-	5
658	6062	INSTL DEL ASSM (D-SW)SZ 1 (BRF)GF2 (BI)	EA	13	2	15
666	6303	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	LF	808	212	1020
666	6312	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)	LF	404	106	510
666	6315	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	LF	404	106	510
672	6009	REFL PAV MRKR TY II-A-A	EA	10	4	14

- LEGEND**
- A RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)
 - B RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
 - C RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
 - D RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)
 - E REFL PAV MRKR TY II-A-A
 - F REFL PAV MRKR TY II-C-R
 - △ DEL ASSM (D-SW)SZ (BRF)CTB (BI)
 - △ DEL ASSM (D-SW)SZ 1 (BRF)GF2 (BI)
 - ⇨ TRAFFIC DIRECTION

MATCHLINE STA 589+85



MATCHLINE STA 591+89




12/20/2022




PAVEMENT MARKING LAYOUT
LOVELACE CREEK
09-110-0-014-06-075
SHEET 3 OF 6

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.
6	TEXAS	BR 2023(500), etc.	86
STATE DISTRICT	COUNTY	CONTROL NO. SECTION NO. JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014 06 045.ETC SH 81, ETC	



LEGEND

- A RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)
- B RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
- C RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
- D RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)
- E REFL PAV MRKR TY II-A-A
- F REFL PAV MRKR TY II-C-R
- ◁ DEL ASSM (D-SW) SZ (BRF) CTB (BI)
- ◁ DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)
- ⇒ TRAFFIC DIRECTION



Alfonso D. Perez 12/20/2022

NO.	DATE	REVISION	APPROV.




PAVEMENT MARKING LAYOUT
 LOVELACE CREEK
 09-110-0-014-06-075
 SHEET 4 OF 6

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		87	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

P:_V-TPD\Projects\TX\2019\0190247TX.05\1_Design\500_CADD\qgn\01_Master_Design_Files\Prime\SPM\Lovlace\SPM 02-2.dgn
 3:00:12 PM
 12/20/2022



BEGIN PAVEMENT MARKING
STA 712+60.00
MATCH EXIST PAV MARKING




MATCHLINE STA 714+60

LEGEND


- A RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)
- B RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
- C RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
- D RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)
- E REFL PAV MRKR TY II-A-A
- F REFL PAV MRKR TY II-C-R
- △ DEL ASSM (D-SW)SZ (BRF)CTB (BI)
- △ DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)
- ⇄ TRAFFIC DIRECTION

PAVEMENT MARKING QUANTITIES						
ITEM	CODE	DESCRIPTION	UNIT	SHEET 1 QTY	SHEET 2 QTY	TOTAL QTY
658	6014	IN STL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	7	-	7
658	6062	IN STL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	11	4	15
666	6303	RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)	LF	808	292	1100
666	6312	RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)	LF	404	146	550
666	6315	RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)	LF	118	-	118
672	6009	REFL PAV MRKR TY II-A-A	EA	10	4	14



MATCHLINE STA 714+60

MATCHLINE STA 716+64




Alfonso D. Perez 12/20/2022

NO.	DATE	REVISION	APPROV.

PAVEMENT MARKING LAYOUT
LITTLE HACKBERRY CREEK
09-110-0-014-06-077
SHEET 5 OF 6


FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		88	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC.



END PAVEMENT MARKING
 STA 718+10.00
 MATCH EXIST PAV MARKING

LEGEND

- A RE PM W/RET REQ TY I (W) 4" (BRK) (100MIL)
- B RE PM W/RET REQ TY I (W) 4" (SLD) (100MIL)
- C RE PM W/RET REQ TY I (Y) 4" (BRK) (100MIL)
- D RE PM W/RET REQ TY I (Y) 4" (SLD) (100MIL)
- E REFL PAV MRKR TY II-A-A
- F REFL PAV MRKR TY II-C-R
- ◁ DEL ASSM (D-SW)SZ (BRF)CTB (BI)
- ◁ DEL ASSM (D-SW)SZ 1 (BRF)GF2 (BI)
- ⇒ TRAFFIC DIRECTION



Alfonso D. Perez
 12/20/2022

NO.	DATE	REVISION	APPROV.

PAVEMENT MARKING LAYOUT
 LITTLE HACKBERRY CREEK
 09-110-0-014-06-077
 SHEET 6 OF 6

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.	
6	TEXAS	BR 2023(500), etc.		89	
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILLETC	0014	06	045.ETC	SH 81, ETC

DATE: 12/20/2022 3:00:14 PM
 FILE: P:\V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\REFLECTOR AND OBJECT MARKERS.dwg
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES		
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE			
									INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back	
SHEETING	Yellow, White or Red Type B or C reflective sheeting				Yellow, White or Red Type B or C Reflective Sheeting				INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional	
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				SHEETING	Yellow, White or Red Type B or C Reflective Sheeting				
					POST TYPE	WC	YFLX, WFLX	WC		YFLX, WFLX
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF	

OBJECT MARKERS								
DEVICE	Type 1 (OM-1)		Type 2 (OM-2)			Type 3 (OM-3)		Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4
SHEETING	Yellow-Type B _{FL} or C _{FL} Sheeting		Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting		Red -Type B _{FL} or C _{FL} Sheeting
POST TYPE	TWT		WC	WC	WFLX	TWT		TWT
MOUNT TYPE	WAS, WAP		GND	GND	GND, SRF	WAS, WAP		WAS, WAP

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		
DEVICE	GF1	GF2	W1-8	W1-8	W1-8	W1-8	W1-6	W1-6	
SHEETING	Yellow, White, Red								
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).					

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600













NOTE:
 Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.



DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION					
D & OM(1)-20					
FILE: dcm1-20.dgn	DN: TXDOT	CK: TXDOT	DN: TXDOT	CK: TXDOT	
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0014	06	045, ETC	SH 81, ETC	
10-09 3-15	DIST	COUNTY	SHEET NO.		
4-10 7-20	WAC	HILL, ETC	90		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT is not responsible for damages resulting from its use.

DATE: 12/20/2022 3:00:15 PM
 FILE: P:_V-TPD\Projects\TX\2019\ND190247TX_05\1_Design\500_CADD\dgn\01_Master\Delin\Delin.dgn

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS			
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT		
GND	GND	SRF	WAS	WAP	GF 1		
							
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC	GF 2	
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.			NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.		CONCRETE TRAFFIC BARRIER (CTB) 
TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS			
							
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		See general notes 1, 2 and 3.			
GENERAL NOTES						<ol style="list-style-type: none"> Place delineators on a section of roadway at a consistent distance from the edge of pavement. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane. 	
						Texas Department of Transportation Traffic Safety Division Standard	
DELINEATOR & OBJECT MARKER INSTALLATION D & OM(2)-20							
FILE: dom2-20.dgn © TxDOT August 2004 10-09 3-15 4-10 7-20		DNE: TxDOT CONT SECT 0014 06 DIST COUNTY WAC HILL, ETC		CK: TxDOT JOB 045, ETC SHEET NO. 91			


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein.

DATE: 12/20/2022 3:00:21 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\TrafficSafety\Standard\del_om(3)-20.dwg

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS


Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons

SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE
 ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE
 At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3) -20


FILE: dom3-20.dgn	DW: TxDOT	CK: TxDOT	DN: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS				
0014	06	045, ETC		SH 81, ETC
3-15	8-15	DIST	COUNTY	SHEET NO.
8-15	7-20	WAC	HILL, ETC	92

20C

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another. TxDOT assumes no responsibility for damages resulting from its use.


DATE: 12/20/2022 3:00:21 PM
 FILE: P:_V-TPD\Projects\TX\2019\ND190247TX.05\1_Design\500_CADD\agn\01_Master\Delineator\Delineator.dwg

CROSSOVERS




DETAIL 1

FOR CULVERTS WITHOUT MBGF




DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES




DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4) -20

FILE: dom4-20.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
3-15	DIST	COUNTY	SHEET NO.	
7-20	WAC	HILL, ETC	93	


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**

D & OM(5) - 20


FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
7-20	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	94	

DATE: 12/20/2022 3:00:22 PM
 FILE: P:_V-TPD\Projects\TX\2019\ND190247TX.05\1_Design\500_CADD\agn\01_Master\Delineator and Object Marker\Delineator and Object Marker.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into a digital format.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another or for any errors or omissions resulting from its use.

DATE: 12/20/2022 3:00:22 PM
 FILE: P:_V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\TxDOT\Standard\Delin\6-20\delin6-20.dwg


CONTINUOUS CONCRETE OR STEEL BARRIER




MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



EMERGENCY CROSSOVER



NOTES

1. Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delineators. On Continuous Barrier, equal spacing (100' max.)
2. Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delineators.
3. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow







DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(6) - 20




FILE: dom6-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
7-20	DIST	COUNTY	SHEET NO.	
	WAC	HILL, ETC	95	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the drawings or the results of any construction resulting from its use.


DATE: 12/20/2022 3:00:23 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_0511_Design_500_CADD\agn\01_Master\Delin\Delin_VIA_20.dwg







Object marker installed per manufacturer's recommendations.



* Adjust to fit attenuator per manufacturer's recommendation, or as directed by the Engineer



OBJECT MARKERS SMALLER THAN 3 FT²



- NOTES**
1. Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
 2. Mounting should be flush with top of attenuator. Minimum size 96" x 24".


NOTES

1. Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
2. Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
3. Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
4. Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
5. Object Marker at nose of attenuator is subsidiary to the attenuator.
6. See D & OM (1-4) for required barrier reflectors.


			Traffic Safety Division Standard		
DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS D & OM(VIA) - 20					
FILE: domvia20.dgn	DW: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT	
© TxDOT December 1989	CONT	SECT	JOB	HIGHWAY	
REVISIONS			0014	06	045, ETC
4-92	8-04				
8-95	3-15				SH 81, ETC
4-98	7-20				
	DIST	COUNTY			SHEET NO.
	WAC	HILL, ETC			96
20G					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in the original drawings or for any damages resulting from its use.


DATE: 12/20/2022 3:00:24 PM
 FILE: P:_V-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\agn\01_Markings\Standard\PM(1)-20.dgn




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




For posted speed on road being marked equal to or less than 40 MPH.



For posted speed on road being marked equal to or greater than 45 MPH.

YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES

- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop bars/yield triangles) when a 50' or greater median centerline can be placed. Stop bars shall only be used with stop signs. Yield triangles shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


GENERAL NOTES

- Edgeline striping shall be as shown in the plans or as directed by the Engineer. The edgeline should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edgelines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the inside of edgeline to the inside of edgeline of a two lane roadway.

MATERIAL SPECIFICATIONS

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Highways




**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1)-20


FILE: pm1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT November 1978	CONT	SECT	JOB	HIGHWAY
8-95 3-03 REVISIONS	0014	06	045, ETC	SH 81, ETC
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	WAC	HILL, ETC	97	

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units. This standard is for informational purposes only and does not constitute a contract. DATE: 12/20/2022 3:00:24 PM FILE: P:\V-TPD\Projects\TX\2019\N190247TX_05\1_Design\500_CADD\agn\01_Master\Drawings\REFLECTIVE RAISED PAVEMENT MARKERS.dwg



CENTERLINE FOR ALL TWO LANE ROADWAYS




**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY HIGHWAYS**




DETAIL "A"

DETAIL "B"

DETAIL "C"




CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.



**REFLECTORIZED PROFILE
PATTERN DETAIL**

USING REFLECTIVE PROFILE PAVEMENT MARKINGS



**4" EDGE LINE,
CENTER LINE
OR LANE LINE**


**OPTIONAL 6" EDGE
LINE, CENTER LINE
OR LANE LINE**

NOTE


Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



RAISED PAVEMENT MARKERS

GENERAL NOTES

1. All raised pavement markers placed in broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.



**POSITION GUIDANCE USING
RAISED MARKERS
REFLECTORIZED PROFILE
MARKINGS
PM(2) - 20**

FILE: pm2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT April 1977	CONT	SECT	JOB	HIGHWAY
4-92 2-10	0014	06	045, ETC	SH 81, ETC
5-00 2-12	DIST	COUNTY	SHEET NO.	
8-00 6-20	WAC	HILL, ETC	98	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

CSJ 0162-01-104: US 84 @ Tehuacana Creek Relief

1.2 PROJECT LIMITS:

From: at Tehuacana Creek Relief

To: (str #008)

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 31°37'9.53"N, (Long) 97° 2'51.07"W

END: (Lat) 31°37'11.36"N, (Long) 97° 2'46.90"W

1.4 TOTAL PROJECT AREA (Acres): 1.00 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.00 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:

Construction of bridge maintenance consisting of bridge maintenance

1.7 MAJOR SOIL TYPES:

Soil Type	Description
Tinn clay	Vegetative cover is in good condition with 90-95% coverage

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- X Mobilization
- X Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- X Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- X Remove existing metal beam guard fence (MBGF), bridge rail
- X Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- X Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: _____
 Other: _____
 Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- X Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- X Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- X Sanitary waste from onsite restroom facilities
- X Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Tehuacana Creek Relief	Tehuacana Creek (1242N)

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- X Development of plans and specifications
- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- X Day To Day Operational Control
- X Maintain schedule of major construction activities
- X Install, maintain and modify BMPs
- Other: _____
- Other: _____



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	BR 2023(500), ETC.		99
STATE	STATE DIST.	COUNTY	
TEXAS	WAC	HILL, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0014	06	045, ETC	SH 81, ETC

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- X Protection of Existing Vegetation
- X Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- X Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- X Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- X Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- X Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- X Chemical Management
- Concrete and Materials Waste Management
- X Debris and Trash Management
- X Dust Control
- X Sanitary Facilities
- X Other: Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	BR 2023(500), ETC.		100
STATE	STATE DIST.	COUNTY	
TEXAS	WAC	HILL, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0014	06	045, ETC	SH 81, ETC

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

CSJ 0014-06-046: SH 81 @ Lovelace Creek

1.2 PROJECT LIMITS:

From: at Lovelace Creek

To: (str #075)

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 32° 5'32.33"N, (Long) 97° 7'41.37"W

END: (Lat) 32° 5'30.40"N, (Long) 97° 7'41.23"W

1.4 TOTAL PROJECT AREA (Acres): 0.70 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.00 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:

Construction of bridge maintenance consisting of bridge maintenance

1.7 MAJOR SOIL TYPES:

Soil Type	Description
Tinn clay	Vegetative cover is in good condition with 90-95% coverage

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- X Mobilization
- X Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- X Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- X Remove existing metal beam guard fence (MBGF), bridge rail
- X Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- X Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- X Revegetation of unpaved areas
- X Achieve site stabilization and remove sediment and erosion control measures

Other: _____

Other: _____

Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- X Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- X Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- X Sanitary waste from onsite restroom facilities
- X Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Lovelace Creek	Hackberry Creek (1254A)

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- X Development of plans and specifications
- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- X Day To Day Operational Control
- X Maintain schedule of major construction activities
- X Install, maintain and modify BMPs
- Other: _____
- Other: _____



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	BR 2023(500), ETC.		101
STATE	STATE DIST.	COUNTY	
TEXAS	WAC	HILL, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0014	06	045, ETC	SH 81, ETC

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- X Protection of Existing Vegetation
- X Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- X Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- X Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- X Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.5 POLLUTION PREVENTION MEASURES:

- X Chemical Management
- Concrete and Materials Waste Management
- X Debris and Trash Management
- X Dust Control
- X Sanitary Facilities
- X Other: Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	BR 2023(500), ETC.		102
STATE	STATE DIST.	COUNTY	
TEXAS	WAC	HILL, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0014	06	045, ETC	SH 81, ETC

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

CSJ 0014-06-045: SH 81 @ Little Hackberry Creek

1.2 PROJECT LIMITS: REFER TO TITLE SHEET

From: _____

To: _____

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 32° 6'27.50"N, (Long) 97° 7'51.81"W

END: (Lat) 32° 6'25.21"N, (Long) 97° 7'51.32"W

1.4 TOTAL PROJECT AREA (Acres): 0.70 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.00 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:

Construction of bridge maintenance consisting of bridge maintenance

1.7 MAJOR SOIL TYPES:

Soil Type	Description
Tinn clay	Vegetative cover is in good condition with 90-95% coverage

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- X Mobilization
- X Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- X Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- X Remove existing metal beam guard fence (MBGF), bridge rail
- X Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- X Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- X Revegetation of unpaved areas
- X Achieve site stabilization and remove sediment and erosion control measures

Other: _____

Other: _____

Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- X Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- X Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- X Sanitary waste from onsite restroom facilities
- X Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Little Hackberry Creek	Hackberry Creek (1254A)

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- X Development of plans and specifications
- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- X Day To Day Operational Control
- X Maintain schedule of major construction activities
- X Install, maintain and modify BMPs
- Other: _____
- Other: _____



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	BR 2023(500), ETC.		103
STATE	STATE DIST.	COUNTY	
TEXAS	WAC	HILL, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0014	06	045, ETC	SH 81, ETC

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- X Protection of Existing Vegetation
- X Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- X Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- X Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- X Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- X Chemical Management
- Concrete and Materials Waste Management
- X Debris and Trash Management
- X Dust Control
- X Sanitary Facilities
- X Other: Sanitary waste from portable units will be collected by a licensed sanitary waste management contractor
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.




12/6/2022

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	BR 2023(500), ETC.		104
STATE	STATE DIST.	COUNTY	
TEXAS	WAC	HILL, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0014	06	045, ETC	SH 81, ETC

BID ITEM NO.	506 6001	506 6011	506 6038	506 6039
DESCRIPTION	ROCK FILTER DAMS (INSTALL) (TY 1)	ROCK FILTER DAMS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
UNIT	LF	LF	LF	LF
	40	40	680	680
PROJECT TOTAL	40	40	680	680



LEGEND

○ SCF — TEMPORARY SEDIMENT CONTROL FENCE

○ RFD — ROCK FILTER DAM

- NOTES**
- LOCATIONS OF EROSION CONTROL DEVICES ARE APPROXIMATIONS. ACTUAL LOCATIONS TO BE DETERMINED IN THE FIELD AND APPROVED BY THE ENGINEER IN THE FIELD.
 - EROSION CONTROL DEVICE INSTALLATION, MAINTENANCE AND REMOVAL SHALL IN BE ACCORDANCE WITH THE TxDOT STANDARDS FOR EROSION CONTROL.



NO.	DATE	REVISION	APPROV.

Civil Associates, Inc.
 9330 LBJ Frwy, Ste. 1150
 Dallas, Texas 75243
 TBPE Firm Registration No. 6981
A Bortlett & West Company

© 2023

Texas Department of Transportation

US 84
SW3P LAYOUT
 TEHUACANA CREEK RELIEF
 09-161-0-0162-01-008
SHEET 1 OF 3

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), ETC.		105
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILL, ETC	0014	06	045, ETC
				SH 81, ETC

c:\projectwise\bartwest-pw\bartwest-pw-03\adeel.saleh@bartwest.com\dms01719\US84_EC_01.dgn
 3:27:30 PM
 12/6/2022



BID ITEM NO.	506	6038	506	6039
DESCRIPTION	TEMP SEDMT CONT FENCE (INSTALL)		TEMP SEDMT CONT FENCE (REMOVE)	
UNIT	LF		LF	
	1180		1180	
PROJECT TOTAL	1180		1180	

LEGEND

—(SCF)— TEMPORARY SEDIMENT CONTROL FENCE

NOTES

1. LOCATIONS OF EROSION CONTROL DEVICES ARE APPROXIMATIONS. ACTUAL LOCATIONS TO BE DETERMINED IN THE FIELD AND APPROVED BY THE ENGINEER IN THE FIELD.
2. EROSION CONTROL DEVICE INSTALLATION, MAINTENANCE AND REMOVAL SHALL IN BE ACCORDANCE WITH THE TxDOT STANDARDS FOR EROSION CONTROL.



STATE OF TEXAS
 ENGINEER
 61759
 12/6/2022

Civil Associates, Inc.
 9330 LBJ Frwy, Ste. 1150
 Dallas, Texas 75243
 TBPE Firm Registration No. 6981
 A Bortlett & West Company

© 2023
 Texas Department of Transportation

SH 81
 SW3P LAYOUT
 LOVELACE CREEK
 09-110-0-0014-06-075
 SHEET 2 OF 3

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT	SHEET NO.		
6	TEXAS	BR 2023(500), ETC.	106		
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.
WAC	HILL, ETC	0014	06	045, ETC	SH 81, ETC

c:\projectwise\bartwest-pw\adeel.saleh@bartwest.com\dms01719\USB1_EC_02.dgn
 3:27:46 PM
 12/6/2022



BID ITEM NO.	506	6038	506	6039
DESCRIPTION	TEMP SEDMT CONT FENCE (INSTALL)		TEMP SEDMT CONT FENCE (REMOVE)	
UNIT	LF		LF	
	1180		1180	
PROJECT TOTAL	1180		1180	

LEGEND

○ SCF — TEMPORARY SEDIMENT CONTROL FENCE

NOTES

1. LOCATIONS OF EROSION CONTROL DEVICES ARE APPROXIMATIONS. ACTUAL LOCATIONS TO BE DETERMINED IN THE FIELD AND APPROVED BY THE ENGINEER IN THE FIELD.
2. EROSION CONTROL DEVICE INSTALLATION, MAINTENANCE AND REMOVAL SHALL IN BE ACCORDANCE WITH THE TxDOT STANDARDS FOR EROSION CONTROL.



12/6/2022

NO.	DATE	REVISION	APPROV.

9330 LBJ Frwy, Ste. 1150
 Dallas, Texas 75243
 TBPE Firm Registration No. 6981

© 2023

SH 81
SW3P LAYOUT
 LITTLE HACKBERRY CREEK
 09-110-0-0014-06-077
SHEET 3 OF 3

FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT		SHEET NO.
6	TEXAS	BR 2023(500), ETC.		107
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
WAC	HILL, ETC	0014	06	045, ETC

c:\projectwise\bartwest-pw\adeel.saleh@bartwest.com\dms01719\USB1_EC_03.dgn
 3:28:02 PM
 12/6/2022

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.
2.
- No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# 3

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- All bridge locations are over Waters of the US;
- NWP 3 would be used if work occurs in water.
-
-
-
-
-
-

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input checked="" type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action No.

- SEE STATEMENT ABOVE
-

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

Action No.

- SEE STATEMENT ABOVE
-
-
-

- No Action Required Required Action

Action No.

- Comply with Migratory Bird Treaty Act (MBTA)
-
-
-

5. SEE STATEMENT BELOW

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

-


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)


- No Action Required Required Action

Action No.

-
-
-


		Design Division Standard		
<h2 style="margin: 0;">ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</h2> <h1 style="margin: 0;">EPIC</h1>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DN: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0014	06	045, etc.	SH 81, etc.
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.	
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	WAC	HILL, etc.	108	

10/28/2022
 P:\1118-TPD\Projects\TX\2019\190247TX_05\1_Design\500_CADD\dgn\01_Master_Design_Files\ENV\ec116.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES


1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING


				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1) - 16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0014	06	045, ETC	SH 81, ETC	
	DIST	COUNTY	SHEET NO.		
	WAC	HILL, ETC	109		

DATE: 12/20/2022
 FILE: P:_V-TPD\Projects\TX\2019\ND190247TX_05\1_Design\500_CADD\dgn\01 Master Design Files\Prime\ENV\ec216.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




FILTER DAM AT TOE OF SLOPE

RFD1




FILTER DAM AT SEDIMENT TRAP

RFD1 OR RFD2




FILTER DAM AT CHANNEL SECTIONS


RFD1 OR RFD2 OR RFD3




PLAN VIEW




"V" SHAPE PLAN VIEW



SECTION B-B



PROFILE



SECTION C-C

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.


Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam — RFD1 —
- Type 2 Rock Filter Dam — RFD2 —
- Type 3 Rock Filter Dam — RFD3 —
- Type 4 Rock Filter Dam — RFD4 —



TYPE 4 (SACK GABIONS)

RFD4



SECTION A-A

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES			
ROCK FILTER DAMS			
EC (2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DN: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0014	06	045, ETC
	DIST	COUNTY	SHEET NO.
	WAC	HILL, ETC	110

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

1. Prior to TxDOT allowing the Contractor to start construction, the Contractor will provide the required storm water and 404 permit documentation and support activities, including but not limited to the following:
 - Provide a list of all chemicals, construction and waste products that will be generated, stored or brought upon TxDOT ROW. The list includes expected construction debris, sanitary wastes, construction chemicals and petroleum products used or generated by the Contractor and sub-contractors. Along with the list, the Contractor will supply a spill prevention plan and clean up procedures that will include each of these chemical products or generated waste.
 - Provide in the construction schedule the necessary line items that will comply with the schedule and planning requirements of the storm water permit.
 - Post the TxDOT storm water permit and any Contractor permits, per permit requirements.
 - Provide copies of storm water permits for Contractor PSL(s). As new PSL(s) may be obtained for the project, provide copies of new or amended permits to TxDOT. The Contractor will not disturb soil without the proper permits.
 - Provide scale drawings of off ROW PSL's within one mile of the project, for field offices, borrow sources, plant sites or other uses.
 - Provide permit information on any Contractor batch plants or concrete crushing plants to be located at a Contractor PSL(s) within one mile of the project limits or boundaries. Copies of the air and water permits are to be provided to TxDOT before materials will be used on the project. No asphalt or concrete batch plants or concrete crushing plants will be located on TxDOT ROW.
 - Provide a letter indicating a Contractor Responsible Person for environmental compliance (CRP) for the project, and maintain a CRP throughout the project duration.
 - Provide all environmental documentation including certification of compliance and EMS training documents/certificates prior to starting work. The Contractor is to provide daily BMP inspection reports that document all field BMPs needing repair or replacement. The Contractor is to clearly document specific BMPs needing repair and location each work day. The Contractor is encouraged to be proactive in fixing BMPs without TxDOT direction.
 - Provide documentation required for Waters of the US, Note #3 and submittals for Item 496 bridge removal. Bridge removal methods submitted will follow all Waters of the US note requirements. The Contractor is not to start construction within the Ordinary High Water Marks of any stream until receiving approval for stream channel construction methods from TxDOT.
 - Provide a written procedure for managing all chemicals and construction items placed in vertical containment structures. Also, provide methods to be used for the treatment, disposal, collection or release of storm water.
 - Provide an estimated date by letter, for the submittal of marked up bridge drawings, indicating cut locations for any structural steel requiring cutting or torching of steel, coated with lead containing paints.
2. Place and maintain trash cans and portable sanitary facilities at locations where there is active construction. Worker generated trash and construction debris will be kept from being transported by storm water and will be collected daily from the ground and routinely hauled from the work area.
3. Contractor will provide TxDOT copies of all correspondence with MS4s, TCEQ, EPA, DSHS and Corps of Engineers regarding activities on this project.
4. Contractor to conduct storm water inspections and develop SWPPP documents to support Contractor permits obtained for the project including PSL(s).
5. Contractor will maintain written documentation of locations of all portable sanitary facilities. The Contractor is required to document the location and disposition of all spills and cleanups from portable sanitary facilities.
6. Contractor will not store chemicals on TxDOT ROW, unless chemicals are stored following all environmental and safety regulations. Fuels for construction equipment will not be stored on TxDOT ROW.
7. The Contractor will store fuels and bulk chemicals on Contractor PSL(s) using a secondary containment method, such as double lined tanks and/or free standing containment reservoirs made of plastic or steel designed to hold bulk chemicals or drums.
8. The Contractor will not remove sediment controls without the prior approval of TxDOT, except for a sediment control that may back up water and cause safety or traffic problems.

SCALE = NTS SHEET 1 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

FILE: BMPLAYOUTS.dgn	DN:	CK:	DW:	CK:
© TxDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	111	

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

9. Any sediment controls removed by the Contractor must be re-installed before the next rainfall event or by the end of day, as approved in advance.
10. Vegetative buffer strips may be used in place of temporary sediment controls such as silt fences and rock filter dams. The amount of disturbed soil area will be limited to 1/3 of an acre or less for a minimum of 50 feet of grassed ditch and 2/3 of an acre of disturbed soil for a minimum of 100 feet of grassed ditch.
11. Construction equipment found to be leaking oil, fuel or coolant will be immediately stopped, the leaking fluid collected and the equipment fixed. Equipment continuing to leak will be removed from the project at no cost to TxDOT. Leaking fluids from equipment will be collected and removed from the project or PSL.
12. Earth berms or mounds typically used to stockpile topsoil and used in place of boundary silt fence will be seeded upon being constructed. Long term use of earth berms or mounds will not be continued without establishing grass on the control.
13. The Contractor will inform TxDOT of new areas where soil will be disturbed to facilitate planning for new sediment controls. Areas of vegetated soil will not be disturbed by the Contractor, unless adequate sediment controls can be installed before the next rainfall event. The Contractor will assist TxDOT in keeping an accurate set of working SWPPP drawings that show the locations of all temporary sediment and erosion controls.
14. The Contractor will maintain an adequate amount of temporary sediment controls on hand at the field office or project staging area for critical SWPPP maintenance, including silt fence (minimum of 200 feet) and rock / fabric for rock filter dams (minimum for 100 feet of Type III dams).

The requirement for BMP rock quantities on hand is waived for small projects for on and off system bridge installations. The Contractor having a BMP Subcontractor does not eliminate the requirement for the Contractor to have the required silt fence and rock on hand, typically stored at the Contractor PSL.
15. Failure of a sub-contractor to complete storm water work on time will require the Contractor to start storm water sediment control work immediately and complete the work with high priority, or be subject to stop work on the entire project.
16. Earth materials on roads as a result of soil tracking will not be allowed to be transported off ROW in storm water. Soil or rock material found on roadways deposited from Contractor equipment will be removed daily.
17. Unless approved, completed concrete curb inlets will not be blocked by sediment controls. The contractor will frequently sweep the completed or partially completed roadway to keep sediment out of drainage pipes.
18. The Contractor will be responsible for proper dust control and will route construction traffic in a manner that minimizes dust generation.
19. Water for dust control will contain no pollutants, but may be non-potable from upland stock ponds. No quantity of water to be used for construction purposes may be taken from a 404 stream, prior to the proper authorizations or permits being obtained by the Contractor.
20. Contractor is to direct workers and sub-contractors to use portable sanitary facilities provided by the Contractor and not to trespass off ROW.
21. Contractor will provide written verification to TxDOT that earth borrow pits and disposal sources meet environmental and regulatory requirements, prior to use. Excavations will meet all OSHA requirements and the current safety guidelines established for TxDOT Quarries and Pits.
22. Boundary silt fences that are terminated down slope, with one end being at the lowest elevation, will be installed with an L - hook to contain sediment. Boundary silt fences that are installed on flat ground will have L-hooks on both ends.
23. Rock filter dams across ditches will be constructed where the rock filter dam ends are embedded within the ditch side slopes and ditch bottom. The top center elevation of the rock filter dam will be at least 6 inches lower than the elevations on the rock filter dam ends.
24. Silt fence will be constructed in a U or V pattern across ditch lines and up the ditch side slope to keep storm water from flowing around the ends of the silt fence. Small silt fences that do not adequately span the ditch and allows storm water around the end(s) will not be used. Where there is adequate space, large U pattern silt fences are preferred to facilitate sediment collection and sediment removal with equipment.
25. Sediment controls (RFDs or silt fences) will be located along road ditches as marked on the SWPPP drawings. Modifications to the sediment control spacing will be adjusted during the project based on sediment control effectiveness. The installation and maintenance of sediment controls at or near outfalls, where storm water leaves TxDOT ROW, takes persistent over ditch line sediment controls.

SCALE = NTS SHEET 2 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

FILE: BMPLAYOUTS.dgn	DN:	CK:	DW:	CK:
© TxDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	112	

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

26. Storm water draining sheet flow over disturbed soil sloped towards the ROW property line, will be intercepted by a boundary silt fence typically installed with L-shaped ends.
27. For ditch grading and shoulder up work, the Contractor is limited during good weather to remove up to one mile (limited to five acres of disturbed soil) of ditch line sediment controls; on one side of the roadway. Outfall controls cannot be removed during this activity. Ditch line controls must be replaced upon completion of work and before the next rain event.
28. Sediment controls damaged by the Contractor, as defined by permit, must be fixed or replaced immediately upon discovery.
29. Notches in silt fences are not typically allowed. Specific silt fences that back up water onto lanes of traffic may be notched if approved.
30. For silt fence maintenance, the Contractor will leave approximately 4 inches of deposited sediment up stream of silt fences and not over excavate around silt fences or rock filter dams.
31. The Contractor will inform TxDOT of new construction areas and where soil is planned to be disturbed. Sediment controls will be installed at outfalls prior to the Contractor beginning soil disturbing activities up slope from the outfall.
32. Water from concrete saw cutting, concrete grinding and concrete coring activities; or fine materials from concrete chipping and salvage will not be allowed to enter storm drains or enter streams.
33. Storm water containing suspended sediment and turbidity needing to be removed from excavations or low areas will be pumped or gravity drained through vegetated buffer strips (50 foot minimum) or placed in ditches with temporary sediment controls, prior to the water being discharged into a stream.
34. Uncontaminated water from natural groundwater seepage, springs, foundations and drains that does not contain suspended sediment or any pollutants may be discharged without storm water controls.
35. Lime or cement if spilled in ditches or outside the defined limits of application is considered a pollutant and will be excavated and removed the same day, to avoid contaminating streams.
36. If located along the project ROW, RAP stockpiles will be located where there is a minimum 100 feet of vegetative buffer strip before storm water will reach a stream. RAP will not be used as a construction material within the Ordinary High Water Marks of a stream channel of a 404 designated stream.
37. If allowed on the project, concrete truck wash out areas will have adequate volume to allow 12 inch freeboard for rain and will be lined with 6 mils of plastic. No concrete will be stored higher than the 12 inch freeboard. Cleaning of truck chutes and equipment does not constitute concrete truck wash out and this activity may be completed at the concrete placement location. Wash out areas will not be located closer than 50 ft from down slope inlets or stream channels.
38. For outfalls near stock ponds closer than 50 foot from disturbed soil at the ROW line, redundant sediment controls will be provided, typically a combination of rock filter dam and a silt fence constructed in line of the flow.
39. Earth stockpiles will utilize silt fence sediment controls, positioned on the low end of the stockpile drainage area with L-hooks or silt fence installed around the entire stockpile.
40. Sediment controls including rock filter dams and silt fences will not be installed across any 404 streams. Sediment controls at 404 streams will be positioned to limit sediment entering the stream from the banks and around structures/culverts, and will allow free flow of storm water to pass through the ROW without being dammed by any sediment controls. Remove loose materials from stream channels prior to each rain event.
41. Sediment controls for non-404 streams may be constructed across the drainage channel in unlimited locations. It is appropriate to use sediment control details typically used for 404 streams for non-404 streams when flow velocities are high. Remove loose material from stream channels prior to each rain event.
42. Incomplete drainage pipe installation across the roadway does not remove the requirement for having sediment controls around the ends of the pipe. To stay within permit requirements, sediment controls should be installed over and around the terminated end and along each side of the banks as soon as construction on the pipe has been completed. Remove loose material from stream channels prior to each rain event.
43. Safety end / headwall construction temporarily will require the removal of part of the sediment control placed over and around the pipe end. Retain in place as much functioning sediment control as possible. Replace the silt fence over and around the top of the pipe, immediately upon concrete placement and form removal. Do not remove culvert sediment controls that cannot be replaced before the next rain event. Sediment control at the ends of culverts must be in place and available for any rain event until the disturbed soil areas are re-vegetated.

SCALE = NTS SHEET 3 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

FILE: BMPLAYOUTS.dgn	DN:	CK:	DW:	CK:
© TxDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	113	

BEST MANAGEMENT PRACTICE (BMP) GENERAL NOTES

44. Between the Ordinary High Water Marks of a 404 stream channel, the Contractor will disturb only the minimum amount of stream channel that is necessary to complete the work.
45. Rock riprap for erosion control does not replace the requirements to maintain sediment control until vegetation is re-established. Replace sediment controls immediately after installing erosion rock.
46. At the direction of TxDOT, sediment deposited into existing and new culverts will be removed subsidiary to Item 506. Sediment to be removed is either pre-existing material before construction starts or sediment generated as a part of this project.
47. Provide treated 2X4 cross bracing for rectangular inlet silt fence, subsidiary to Item 506.
48. Loose or granular earth materials will not be used to repair silt fence undercuts. Silt fence undercut repairs will be conducted with well compacted soils or the silt fence will be reset in a nearby location.
49. Silt fence steel T posts of approximately 1.25 pounds per foot are allowed at a spacing of 8 feet or less. Silt fence steel T posts between approximately 1.25 pounds per foot and 0.85 pounds per foot are allowed for T post spacing of 5 feet or less.
50. Silt fence to be used to slow the flow of storm water down slopes will be positioned approximately horizontal (on the contour) with L hooks on the ends and limited to approximately 200 feet in length. Multiple sections and levels of silt fence may be required in addition to temporary / permanent erosion control flumes.
51. Soil retention blankets will be installed rolled down the slope with the small dimension side embedded at the top of slope, unless recommended otherwise by the manufacturer. Excess grass, rocks, trash, debris or clods will be removed before seeding and installing soil retention blankets. All installations will be by the manufacturer recommendations. Contractor equipment, including tractor mowers will be kept off areas with soil retention blankets until the grass is established.





SCALE = NTS SHEET 4 OF 10

 **Texas Department of Transportation**
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

FILE: BMPLAYOUTS.dgn	DN:	CK:	DW:	CK:
© TxDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY		SHEET NO.
FEB 2015	WAC	HILL, ETC		114



	SEDIMENT CONTROL FENCE
	ROCK FILTER DAM (TY 2)
	ROCK FILTER DAM (TY 3)
	DIRECTION OF FLOW

- NOTES:
- ① EXTEND SILT FENCE SO STORM WATER DOES NOT GO AROUND THE ENDS. USE L-HOOKS ON ENDS AS REQUIRED.
 - ② EXTEND ROCK FILTER DAM SO STORM WATER DOES NOT GO AROUND THE ENDS.





SCALE = NTS SHEET 5 OF 10



**TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES**

TA-BMP

FILE: BMAPLAYOUTS.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	115	



	SEDIMENT CONTROL FENCE
	ROCK FILTER DAM (TY 2)
	ROCK FILTER DAM (TY 3)
	DIRECTION OF FLOW

- NOTES:
- ① PROVIDE OVERLAP OF SILT FENCE WITH ROCK FILTER DAM.
 - ② USE SILT FENCE L-HOOKS ON ENDS TO BLOCK STORM WATER SEDIMENT


SCALE = NTS SHEET 6 OF 10




**TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES**

TA-BMP

FILE: BMPLAYOUTS.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	116	



BEST MANAGEMENT PRACTICE (BMP) #9
STOCKPILE SEDIMENT CONTROL




BEST MANAGEMENT PRACTICE (BMP) #10
FOR 404 OR NON-404 STREAMS ONLY ~
SEDIMENT CONTROL AT PHASED CONSTRUCTION OF BRIDGE CLASS CULVERTS


	SEDIMENT CONTROL FENCE
	ROCK FILTER DAM (TY 2)
	ROCK FILTER DAM (TY 3)
	DIRECTION OF FLOW

NOTES:

- ① START SEDIMENT CONTROL AT LOCATION SO ALL STORM WATER WITH SEDIMENT IS COLLECTED
- ② ROCK FILTER DAMS OR EARTH/GRASSED EMBANKMENTS CAN BE SUBSTITUTED AS DIRECTED.
- ③ PROVIDE A SMOOTH TRANSITION FROM THE INVERT ELEVATIONS BETWEEN CULVERTS. REMOVE LOOSE SOIL FROM EXCAVATED AREA BETWEEN CULVERTS.
- ④ PROVIDE AND INSTALL PNEUMATICALLY PLACED CONCRETE ON THE DITCH BOTTOM AND SIDE SLOPES BETWEEN TEMPORARY TERMINATIONS BETWEEN OLD AND NEW CULVERTS. PNEUMATICALLY PLACED CONCRETE WILL BE PLACED TO THE HEIGHT OF THE LARGEST CULVERT ON THE DITCH SIDE SLOPES; AND TO A LIMIT 10 FEET OUTSIDE THE LOCATION OF BMPS ALONG THE DITCH BOTTOM. CEMENT STABILIZED SAND MAY BE SUBSTITUTED FOR PNEUMATICALLY PLACED CONCRETE, IN AREAS WHERE INSTALLATION WORKS AND AT THE OPTION OF TXDOT.



BEST MANAGEMENT PRACTICE (BMP) #11
BOUNDRY SEDIMENT CONTROL ~ BOTH ENDS OF CONTROL TERMINATED UP SLOPE



BEST MANAGEMENT PRACTICE (BMP) #12
BOUNDRY SEDIMENT CONTROL ~ BOTH ENDS OF CONTROL TERMINATED DOWN SLOPE


SCALE = NTS SHEET 7 OF 10

Texas Department of Transportation
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

FILE: BMLAYOUTS.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	117	




BEST MANAGEMENT PRACTICE (BMP) #13

USE OF VEGETATIVE BUFFERS IN PLACE OF TEMPORARY SEDIMENT CONTROLS SUCH AS SILT FENCE AND ROCK FILTER DAMS

	FULLY GRASSED DITCH
	DISTURBED AREA
	DIRECTION OF FLOW
	SEDIMENT CONTROL FENCE

- ① FOR H DIMENSIONS LESS THAN 1.5' SILT FENCE MAY NEED TO BE NOTCHED AS SHOWN IN VIEW A-A. ADD EXTRA POSTS AT NOTCH.
- ② BMP #14 MAY BE USED AT CROSS DRAINAGE STRUCTURES AS DIRECTED.



BEST MANAGEMENT PRACTICE (BMP) #14

NON-404 STREAMS AND DITCHES ONLY ~ SEDIMENT CONTROL AT PARALLEL DRAINAGE STRUCTURE ENTRANCE ②


SCALE = NTS SHEET 8 OF 10




TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES

TA-BMP

FILE: BMPLAYOUTS.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	118	




BEST MANAGEMENT PRACTICE (BMP) #15
CONCRETE TRUCK WASHOUT AREA




BEST MANAGEMENT PRACTICE (BMP) #16
PUMPED STORM WATER SEDIMENT CONTROLS ①

	FULLY GRASSED DITCH
	DIRECTION OF FLOW
	SEDIMENT CONTROL FENCE
	ROCK FILTER DAM (TY 2)
	ROCK FILTER DAM (TY 3)

- ① PUMPED STORM WATER FROM AN EXCAVATION AREA SHOULD BE DISCHARGED IN A 50' VEGETATIVE BARRIER OR THROUGH TWO TEMPORARY SEDIMENT CONTROLS BEFORE ENTERING A 404 STREAM.
- ② FOR LANDOWNER STOCKPONDS WITHIN 50' OF THE RIGHT OF WAY LINE, PROVIDE REDUNDANT SEDIMENT CONTROLS AT THE CONVEYANCE OF THE POND. MINIMUM OF TWO SEDIMENT CONTROLS.
- ③ WHEN CONTAINMENT AREA REACHES 1' FREEBOARD, DISCONTINUE WASHOUT PLACEMENT AND REMOVE MATERIAL UPON SOLIDIFICATION.
- ④ EACH TIME SOLIDIFIED MATERIAL IS REMOVED REPLACE PLASTIC SHEETING.



BEST MANAGEMENT PRACTICE (BMP) #17
HORIZONTAL INLET SEDIMENT CONTROL



BEST MANAGEMENT PRACTICE (BMP) #18
LANDOWNER STOCKPOND SEDIMENT CONTROL ②


SCALE = NTS SHEET 9 OF 10

Texas Department of Transportation
Waco District Standard

TYPICAL APPLICATIONS FOR BEST MANAGEMENT PRACTICES


TA-BMP

FILE: BMPLAYOUTS.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	119	



	DIRECTION OF FLOW
	SEDIMENT CONTROL FENCE
	ROCK FILTER DAM
	SECURITY FENCING

- ① HAY BALES MAY BE SUBSTITUTED FOR SILT FENCE OVER THE STREAM CROSSING.
- ② CROSSING WILL BE AS PER REQUIREMENTS OF THE WATERS OF THE US GENERAL NOTES.
- ③ INSTALL SILT FENCE SLIGHTLY UP FROM OHW MARK FROM R.O.W. TO R.O.W.
- ④ USE SILT FENCE L-HOOKS ON LEVEL OR DOWN SLOPING ENDS TO BLOCK STORM WATER SEDIMENT
- ⑤ INSTALL LARGE V OR U SHAPED BMP'S FROM ABUTMENT AS SHOWN. IF THERE IS STEEP DITCH CONDITIONS DECREASE SPACING AND CONSIDER RFD'S. ADD ADDITIONAL BMP'S IF GRADE IS STEEP OR IF FLOW IS HIGH.



SCALE = NTS SHEET 10 OF 10

Texas Department of Transportation
Waco District Standard

**TYPICAL APPLICATIONS
FOR
BEST MANAGEMENT
PRACTICES**

TA-BMP

FILE: BMPLAYOUTS.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT 2009	CONT	SECT	JOB	HIGHWAY
REVISIONS	0014	06	045, ETC	SH 81, ETC
DEC 2013	DIST	COUNTY	SHEET NO.	
FEB 2015	WAC	HILL, ETC	120	