

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT
F 2023(609)
CSJ 3090-01-012


FM 3041 NAVARRO COUNTY

NET LENGTH OF ROADWAY = 15555.80 FT. = 2.946 MI.
NET LENGTH OF BRIDGE = 31.17 FT. = 0.006 MI.
NET LENGTH OF PROJECT = 15586.97 FT. = 2.952 MI.

LIMITS: FROM CHAMBERS CREEK TO FM 1129

FOR THE CONSTRUCTION OF : REHABILITATION OF EXISTING ROAD

CONSISTING OF : REHABILITATION OF EXISTING PAVEMENT AND ADD SHOULDERS



FEDERAL AID PROJECT NO.			
F 2023(609)			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	NAVARRO		1

DESIGN SPEED = 50 MPH
A.D.T. (2022)= 1220
A.D.T. (2042)= 1620

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014, AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 5, 2022)

FINAL PLANS

LETTING DATE: _____
DATE CONTRACTOR BEGAN WORK: _____
DATE WORK WAS COMPLETED & ACCEPTED: _____
FINAL CONTRACT COST: \$ _____
CONTRACTOR : _____

DATE: 1/25/2023 9:35:00 AM
FILE: c:\tdot\pw_on\in\tdot\5\craig_parker\1046395\4\TITLE SHEET.dgn

WORK WAS COMPLETED ACCORDING TO THE PLANS AND CONTRACT.

_____, P.E.
Signature of Registrant & Date

EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE



SUBMITTED FOR REVIEW: 2/1/2023
Morgan Neill, P.E.
D0DE095C8... ENGINEER

RECOMMENDED FOR LETTING: 2/1/2023
Juan A. Paredes, P.E., P.E.
4A97FFA3D... ENGINEER

RECOMMENDED FOR REVIEW: 2/1/2023
James P. Campbell, P.E.
98671... DIRECTOR OF TRANSPORTATION PLANNING & DEVELOPMENT

APPROVED FOR LETTING: 2/1/2023
Casson Clemens, P.E.
A879E0D... DISTRICT ENGINEER

INDEX OF SHEETS

SHEET DESCRIPTION

GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3 PROJECT LAYOUT AND ADVANCE WARNING SIGNS
- 4-7 TYPICAL SECTIONS
- 8, 8A-8F GENERAL NOTES
- 9, 9A-9B ESTIMATE & QUANTITY
- 10-14 QUANTITY SUMMARY
- 15 DRIVEWAY SUMMARY

TRAFFIC CONTROL PLAN

- 16 TRAFFIC CONTROL PLAN - NARRATIVE
- 17 TRAFFIC CONTROL PLAN - TYPICAL SECTIONS
- 18 TRAFFIC CONTROL PLAN - TYPICAL SECTIONS CULVERT REPLACEMENT
- 19 PAVEMENT CUT & RESTORE DETAILS

TRAFFIC CONTROL PLAN STANDARDS

- ## 20-31 BC (1) - 21 THRU BC (12) - 21
- ## 32 TCP (1-1) - 18
- ## 33 TCP (1-2) - 18
- ## 34 TCP (1-3) - 18
- ## 35 TCP (1-6) - 18
- ## 36 TCP (2-1) - 18
- ## 37 TCP (2-2) - 18
- ## 38 TCP (2-3) - 18
- ## 39 TCP (2-6) - 18
- ## 40 TCP (3-1) - 13
- ## 41 TCP (3-3) - 14
- ## 42 TCP (3-4) - 13
- ## 43 TCP (7-1) - 13
- ## 44 WZ (RS) - 22
- ## 45 WZ (STPM) - 13
- ## 46 WZ (TD) - 17
- ## 47 WZ (UL) - 13

ROADWAY DETAILS

- 48-50 CORE BORING DATA
- 51-58 ALIGNMENT DATA
- 59 SUPERELEVATION DATA
- 60-66 ROADWAY PLAN
- 67 DRIVEWAY DETAILS
- 68 TRANSITION & MAILBOX DETAILS

SHEET DESCRIPTION

ROADWAY DETAILS STANDARDS

- ## 69 GF (31) - 19
- ## 70 GF (31) MS - 19
- ## 71-74 MB (1) - 21 THRU MB (4) - 21
- ## 75 SGT (10S) 31 - 16
- ## 76 SGT (11S) 31 - 18
- ## 77 SGT (12S) 31 - 18
- ## 78 SGT (15) 31 - 20
- ## 79 TE (HMAC) - 11
- ## 80 TREATMENT FOR VARIOUS EDGE CONDITION
- ## 81 LJD(1-1)-07(DAL)
- ## 82 TRB-15(1)(DAL)

RETAINING WALL DETAILS

NONE

DRAINAGE DETAILS

- 83 DRAINAGE AREA MAP
- 84 RUNOFF COMPUTATIONS
- 85 CULVERT CALCULATIONS
- 86-93 CULVERT LAYOUT

DRAINAGE DETAILS STANDARDS

- ## 94 CH - PW - 0
- ## 95 CH - PW - S
- ## 96 CRR
- ## 97 PAZD
- ## 98 PB
- ## 99 PDD
- ## 100 PSET - RR
- ## 101 PSET - RP
- ## 102-103 PSL
- ## 104-105 SRR

UTILITIES

NONE

BRIDGE

- 106 BRIDGE CLASS DRAINAGE AREA MAP
- 107 CROSS SECTIONS MAP
- 108-110 HYDRAULIC DATA
- 111 EXISTING & PROPOSED TYPICAL SECTIONS
- 112 TCP TYPICAL SECTIONS BRIDGE CLASS CULVERT
- 113 BRIDGE CLASS CULVERT

BRIDGE STANDARDS

- ## 114 BCS
- ## 115 ECD
- ## 116 PW
- ## 117 SCP-10
- ## 118 SCP-MD

TRAFFIC DETAILS

- 119-126 SUMMARY OF SMALL SIGNS
- 127-133 PAVEMENT MARKINGS & SIGNING LAYOUT
- 134 GUIDE SIGN DETAILS

TRAFFIC STANDARDS

- ## 135 D&OM (1) - 20
- ## 136 D&OM (2) - 20
- ## 137 D&OM (3) - 20
- ## 138 D&OM (4) - 20
- ## 139 D&OM (5) - 20
- ## 140 D&OM (VIA) - 20
- ## 141 PM (1) - 22
- ## 142 PM (2) - 22
- ## 143 RS (3) - 13
- ## 144 RS (4) - 13
- ## 145 SMD (GEN) - 08
- ## 146 SMD (SLIP - 1) - 08 (DAL)
- ## 147 SMD (SLIP - 2) - 08
- ## 148 SMD (SLIP - 3) - 08
- ## 149 TSR (3) - 13
- ## 150 TSR (4) - 13
- ## 151 TSR (5) - 13

ENVIRONMENTAL ISSUES

- 152-153 STORMWATER POLLUTION PREVENTION PLAN (SW3P)
- 154 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)
- 155-161 SW(3)P LAYOUT

ENVIRONMENTAL ISSUES STANDARDS


- ## 162-164 EC (1) - 16 THRU EC (3) - 16
- ## 165-167 EC (9) - 16
- ## 168 SW3P SIGN SHEET (DAL)
- ## 169 VEGETATIVE ESTABLISHMENT SHEET (DAL)

MISCELLANEOUS ITEMS

NONE

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Morgan Neill, P.E. 2/1/2023
SIGNATURE OF REGISTRANT DATE




FM 3041
INDEX OF SHEETS


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		Navarro	2


CK: DW: CK: DW:




INTERSECTION A




INTERSECTION E AND C



END OF PROJECT




INTERSECTION D AND B



BEGIN PROJECT
FM 3041
CSJ: 3090-01-012
STA: 00+60



- ① END ROAD WORK
G20-2
- ② BEGIN ROAD WORK
NEXT X MILES
NAME
ADDRESS
CITY
STATE
CONTRACTOR
G20-5T
G20-6T
- ③ ROAD WORK AHEAD
CW20-1D
- ④ OBEY WARNING SIGNS
STATE LAW
R20-3T
- ⑤ WORK ZONE
TRAFFIC FINES DOUBLE
WHEN WORKERS ARE PRESENT
G20-5aP
R20-5T
R20-5aTP
- ⑥ END WORK ZONE
G20-2bT
- ⑦ ROAD WORK NEXT X MILES
G20-1bTR
- ⑧ ROAD WORK NEXT X MILES
G20-1bTL
- ⑨ SPEED LIMIT XX
R2-1
- ⑩ BEGIN WORK ZONE
TRAFFIC FINES DOUBLE
WHEN WORKERS ARE PRESENT
G20-9TP
R20-5T
R20-5aTP
- ⑪ STAY ALERT
TALK OR TEXT LATER
G20-10T
- ⑫ ROAD WORK NEXT X MILES
G20-1aT



Morgan Neill, P.E. 1/31/2023

- NOTES:
1. THE CONTRACTOR SHALL PLACE & MAINTAIN ALL PROJECT LIMIT TRAFFIC CONTROL DEVICES AS SHOWN ON THE CURRENT BC (2)-21 STANDARD IN CURRENT TEXAS MUTCD GUIDELINES, AND AS DIRECTED BY THE ENGINEER.
 2. "X" - SPACING OF OTHER ADVANCE WARNING SIGNS SHALL BE ACCORDING TO THE CURRENT BC(2)-21 STANDARD, TEXAS MUTCD GUIDELINES, AND AS DIRECTED BY THE ENGINEER.




FM 3041
PROJECT LAYOUT AND
ADVANCE WARNING SIGNS

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 3


DATE: 1/27/2023 11:13:48 AM
FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\0463954\FM 3041_PROJECT LAYOUT.dgn

CK: DW: CK: DW: CK: DW: CK: DW:



EXISTING TYPICAL SECTION

- STA 28+00 - STA 32+00
- STA 36+00 - STA 41+00
- STA 50+20 - STA 56+00
- STA 62+00 - STA 65+00
- STA 77+00 - STA 78+50
- STA 99+00 - STA 102+50
- STA 108+00 - STA 115+60
- STA 120+50 - STA 127+60
- STA 137+40 - STA 139+70
- STA 151+30 - STA 152+00
- INTERSECTION RT. 154+15



Morgan Neill, P.E. 1/31/2023




FM 3041
TYPICAL SECTIONS
(EXISTING)

SHEET 1 OF 4

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	4	


DATE: 1/25/2023 9:35:44 AM
FILE: c:\tdot\ipw_onlinetx\d05\craig_parker\04639541\TYPICAL SECTIONS.dgn

CK:
DW:
CK:
DW:



EXISTING TYPICAL SECTION

- STA 0+60 - STA 28+00
- STA 32+00 - STA 36+00
- STA 41+00 - STA 50+20
- STA 56+00 - STA 62+00
- STA 65+00 - STA 77+00
- STA 78+50 - STA 99+00
- STA 102+50 - STA 108+00
- STA 115+60 - STA 120+50
- STA 127+60 - STA 137+40
- STA 139+70 - STA 151+30
- STA 152+00 - INTERSECTION RT 154+15



Morgan Neill, P.E. 1/31/2023



FM 3041


TYPICAL SECTIONS
(EXISTING)

SHEET 2 OF 4

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	5	

DATE: 1/25/2023 9:35:46 AM
FILE: c:\tdot\ipw_onlinetx\dtd5\craig_parker\04639541\TYPICAL SECTIONS.dgn


CK
DW
CK
DW



- NOTE:
1. NEW FLEXBASE - TY D GR 1-2
 2. SUPERELEVATION & PAVEMENT TRANSITION ARE SHOWN IN PLANS
 3. SIDE SLOPES AT CULVERT WILL BE AS SHOWN IN CULVERT PLAN & PROFILE.
 4. PROPOSED FRONT SLOPE WILL MEET AT OR BEFORE DITCHLINE EXCEPT CROSS CULVERT AREA.
 5. LIMITS OF EXIST PAVEMENT & BASE DEPTHS WERE ESTIMATED BY INTERPOLATING BETWEEN CORE DATA LOCATIONS. CONTRACTOR SHALL FIELD VERIFY TO ENSURE MAX 50% RAP FOR REWORKED BASE.
 6. CONTRACTOR TO VERIFY IF BASE & SUBGRADE MATERIAL IS STABLE FOR MOVEMENT OF CONSTRUCTION EQUIPMENT. ANY NECESSARY STABILIZATION OF MATERIAL SHALL BE RESPONSIBILITY OF THE CONTRACTOR.
 7. MINIMIZE VEGETATION AND SOIL DISTURBANCE TO EXTENT PRACTICABLE (WHILE STILL ACCOMPLISHING REQUIRED CONSTRUCTION). RE-VEGETATE DISTURBED SOIL.
 8. DITCH GRADING WILL BE PAID UNDER ITEM 152.

1. REMOVE 2" OF EXISTING HMA (20' WIDE) (ITEM 354)
2. REWORK 8" OF EXISTING MATERIALS (22 FT WIDE) WITH 3.0" NEW ROADWAY DELIVERY FLEXIBLE BASE (ITEM 251), AND SPREAD OUT OVER 30 FT SECTION.
3. FILL 5'X0.5' NOTCHES ON EACH SIDE OF SECTION USING REWORKED MATERIALS.
4. CEMENT TREAT 6" OF EXISTING BASE MATERIALS & NEW FLEXIBLE BASE WITH 2% CEMENT (30' WIDE) (ITEM 275).
5. PLACE 10" OF NEW FLEXIBLE BASE MATERIAL (TY D GR 1 OR 2) (ITEM 247)
6. APPLY PRIME (ITEM 314) & ONE COURSE SURFACE TREATMENT (ITEM 316)
7. PLACE 2" OF SUPERPAVE-C SAC-B PG 64-22 (28' WIDE) (ITEM 3077)
8. PGL WILL BE 8" HIGHER THAN EXISTING


PROPOSED TYPICAL SECTION
 STA 02+20.00 TO STA 94+09.18
 STA 111+09.18 TO STA 146+22.00



1. REMOVE 10"-18" OF EXISTING MATERIAL (ITEM 105)
2. PLACE 6" NEW FLEXIBLE BASE MATERIAL (ITEM 247) OVER 30' SECTION AND MIX WITH 2% CEMENT (ITEM 275)
3. PLACE 10" OF NEW FLEXIBLE BASE MATERIAL (TY D GR 1 OR 2) (ITEM 247)
4. APPLY PRIME (ITEM 314) & ONE COURSE SURFACE TREATMENT (ITEM 316)
5. PLACE 2" OF SUPERPAVE-C SAC-B PG 64-22 (ITEM 3077)
6. PGL WILL BE 0-8" HIGHER THAN EXISTING

PROPOSED TYPICAL SECTION
 STA 00+60.00 TO STA 02+20.00
 STA 94+09.18 TO STA 95+69.18
 STA 109+49.18 TO STA 111+09.18
 *STA 146+22.00 TO STA 147+82.00

*LANE WIDTH TAPERS SHOWN ONLY APPLY TO SELECTED STATION RANGE. ALL OTHER TAPERS ARE VERTICAL.



Morgan Neill, P.E. 1/31/2032



FM 3041


TYPICAL SECTIONS
(PROPOSED)

SHEET 30F 4

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	NAVARRO	6	

DATE: 1/25/2023 9:35:49 AM
 FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\04639541\TYPICAL SECTIONS.dgn


CK:
DW:
CK:
DW:



- NOTE:
1. NEW FLEXBASE - TY D GR 1-2
 2. SUPERELEVATION & PAVEMENT TRANSITION ARE SHOWN IN PLANS
 3. SIDE SLOPES AT CULVERT WILL BE AS SHOWN IN CULVERT PLAN & PROFILE.
 4. PROPOSED FRONT SLOPE WILL MEET AT OR BEFORE DITCHLINE EXCEPT CROSS CULVERT AREA.
 5. LIMITS OF EXIST PAVEMENT & BASE DEPTHS WERE ESTIMATED BY INTERPOLATING BETWEEN CORE DATA LOCATIONS. CONTRACTOR SHALL FIELD VERIFY TO ENSURE MAX 50% RAP FOR REWORKED BASE.
 6. CONTRACTOR TO VERIFY IF BASE & SUBGRADE MATERIAL IS STABLE FOR MOVEMENT OF CONSTRUCTION EQUIPMENT. ANY NECESSARY STABILIZATION OF MATERIAL SHALL BE RESPONSIBILITY OF THE CONTRACTOR.
 7. MINIMIZE VEGETATION AND SOIL DISTURBANCE TO EXTENT PRACTICABLE (WHILE STILL ACCOMPLISHING REQUIRED CONSTRUCTION). RE-VEGETATE DISTURBED SOIL.


1. REMOVE 10-18" OF EXISTING MATERIAL (ITEM 105)
2. PLACE 6" NEW FLEXIBLE BASE MATERIAL (ITEM 247) OVER 30' SECTION AND MIX WITH 2% CEMENT (ITEM 275)
3. PLACE 10" OF NEW FLEXIBLE BASE MATERIAL (TY D GR 1 OR 2) (ITEM 247)
4. APPLY PRIME (ITEM 314) & ONE COURSE SURFACE TREATMENT (ITEM 316)
5. PLACE 2" OF SUPERPAVE-C SAC-B PG 64-22 (28' WIDE) (ITEM 3077)
6. PGL WILL MATCH THE EXISTING

PROPOSED TYPICAL SECTION
STA 95+69.18 TO STA 109+49.18



1. REMOVE 10-18" OF EXISTING MATERIAL (ITEM 105)
2. PLACE 6" OF NEW FLEXIBLE BASE MATERIAL (ITEM) OVER EXISTING 20' SECTION AND MIX WITH 2% CEMENT (ITEM 275)
3. PLACE 8"-10" OF NEW FLEXIBLE BASE MATERIAL (TY D GR 1 OR 2) (ITEM 247)
4. APPLY PRIME (ITEM 314) & ONE COURSE SURFACE TREATMENT (ITEM 316)
5. PLACE 2" OF SUPERPAVE-C SAC-B PG 64-22 (28' WIDE) (ITEM 3077)
6. PGL WILL MATCH THE EXISTING

PROPOSED TYPICAL SECTION
STA 147+82.00 TO STA 156+46.97



Morgan Neill, P.E. 1/31/2023



FM 3041
TYPICAL SECTIONS (PROPOSED)

SHEET 4 OF 4

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	7	

DATE: 1/25/2023 9:35:53 AM
FILE: c:\tdot\ipw_online\tdot5\craig_parker\104639541\TYPICAL SECTIONS.dgn

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

or Contractor questions on this project are to be addressed to the following individual(s):

Juan Paredes, P.E.

Juan.Paredes@txdot.gov

Amanda McKittrick, P.E.

Amanda.McKittrick@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Paper copies of cross-sections may be produced by using the provided .pdf file located on the above FTP Website at the bidders' expense and at copying companies. This data is for non-construction purposes only and it is the responsibility of the prospective bidder to validate the enclosed data with appropriate plans, specifications and estimate for the project(s).

Item 5:

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (214-320-6682) for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (214-320-6205) for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

For the project to be deemed complete, permanently stabilize all unpaved disturbed areas of the project with a vegetative cover at a minimum of 70% density for the control of erosion.

Place construction stakes/station markings at intervals of no more than 100 feet or as directed by the Engineer. Place stakes and markings so as not to interfere with normal construction operations.

Item 6:

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Item 7:

Repair or replace any structures and utilities that might have been damaged by negligence or a failure to have utility locates performed.

Holiday restrictions – The Engineer may decide that no lane closures or construction operations shall be allowed during the restricted periods listed in the following holiday schedule. TxDOT has the right to lengthen, shorten, or otherwise modify these restricted periods as actual, or expected, traffic conditions may warrant. Working days will not be charged for these restricted periods. No additional compensation will be allowed for these closures (i.e., overhead, delays, stand-by, barricades or any other associated cost impacts).

- New Year's Eve and Day (5 am on December 31 thru 10:00 pm January 1)
- Easter Holiday weekend (5 am on Friday thru 10:00 pm Sunday)
- Memorial Day weekend (5 am on Friday thru 10:00pm Monday)
- Independence Day (5 am on July 3 thru 10:00 pm on July 5)
- Labor Day weekend (5 am on Friday thru 10:00 pm Monday)
- Thanksgiving Holiday (5 am on Wednesday thru 10:00 pm Sunday)
- Christmas Holiday (5 am on December 23 thru 10:00 pm December 26)

No significant traffic generator events identified.

Item 8:

This Project will be a Standard Workweek.

Meet weekly with the engineer to notify him or her of planned work for the upcoming week.

Provide the engineer with a daily work schedule of planned work.

Critical Path Method (CPM) schedule in P6 format will be required for this project. Submit baseline schedule and obtain approval prior to beginning construction. The Estimate will be held if monthly schedule update is not submitted.

County: NAVARRO

Highway: FM 3041

Item 100:

Remove the existing roadway small signs, delineators and object markers as shown on the plans, or as directed, during construction within the right of way. Small sign, delineator and object marker removals are subsidiary to this Item.

The limits of preparing right of way will be measured from Sta. 0+60 to Sta. 156+46.97 along the centerline of construction.

Tree trimming and tree and brush removal shall be performed in accordance to details shown on TRB-15(1)DAL. This work is not paid for directly but is subsidiary to this item. Any tree that interferes with the work shown in the plans shall be removed.

Avoid pruning oak trees between March 15 and the end of June to limit the potential spread of Oak Wilt disease.

Department will mark any trees to be removed with florescent orange pain

Do not use a telescopic side boom rotary mower.

Tree Removal – Cut designated trees as close to the ground as possible but no higher than 6 in. above the ground level until the stump can be removed according to the plans.

Brush Removal – Remove brush as directed at culverts, headwalls, wingwalls, guardrail, cable barrier, and riprap.

Neatly trim trees, overhanging branches and all underbrush to produce an 18-foot vertical clear area within the MUTCD roadway safety Clear Zone. Minimize any unnecessary vegetation disturbance outside of the Clear Zone. Do not disturb any vegetation beyond the TxDOT ROW line or its authorized easement.

Remove and dispose of all dead fall (trees and/or limbs already fallen to the ground) from within the roadway Clear Zone and where otherwise directed. Any limbs that are less than 4 in. in diameter will be paid for in the same manner as trees that are to be felled and removed.

Do not use any chemical agents to aid in the deterioration or removal of the stump.

Do not prune the canopy to less than half of the overall height of the tree.

Trees blocking signs shall be trimmed as directed.

Burning of brush will not be permitted. Cleanup shall be continuous and concurrent with pruning, trimming, and removal operations.

Item 104:

In those areas where the pavement is not to be overlaid, provide a smooth surface after the curb removal. Planing or grinding is considered an acceptable method at these locations. Measurement and payment is in accordance with this item.

Sawing of concrete is not paid for directly, but is considered subsidiary to this item.

County: NAVARRO

Highway: FM 3041

Items 105, 251, and 354:

Saw existing asphalt along neat lines where portions are to be left in place temporarily or permanently. Sawing is not paid for directly, but is subsidiary to this item.

Item 105:

Take possession of recycled asphalt pavement from the project and recycle the material.

Properly dispose of unsalvageable material at your own expense.

Item 110:

Excavated shale is not an acceptable material for embankment.

Items 110 and 132:

Scarify and loosen the excavated areas, unpaved surface areas, except rock, to a depth of at least 8 inches and compact in accordance with the specifications.

Excavation and embankment for driveways, sleeper slabs, alleys and intersections will not be paid for directly, but will be considered subsidiary to these items.

Item 132:

Excavated material from the project site has not been determined to be suitable for embankment. The bidder assumes all risk for the use of excavated materials for embankment and is expected to meet all material requirements for embankment regardless of the source.

Perform Tex-106-E (Plasticity Index) by an approved laboratory on excavated soils from sources outside right of way when used in roadway embankment. Provide the test results at no expense to the department. The engineer will sample and test soils produced by the construction project for specification requirements or material sources specified in the plans.

Earth embankment Type C, is mainly composed of material other than shale. Furnish material that is free from vegetation or other objectionable material and that conforms to the requirements of Table 1 (Sheet A). If necessary, treat material with lime slurry in accordance with Item 260, "Lime Treatment (Road-Mixed)" in order to meet these requirements. Use Tex-121-E, figure 1, page 4 to calculate the amount of lime required. When lime treated subgrade is specified, 3000 PPM is the maximum allowed sulfate content in the top 3 feet when material comes from borrow source. Follow recommendations of 260.4.4 for mixing and mellowing. The engineer will test material placed or excavated to a depth of one foot below and laterally to one foot outside the proposed treatment limit. Lime treatment of this material will not be paid for directly, but will be considered subsidiary to this item.

Do not use shaley clays in embankment unless approved in writing.

Item 134:

Start backfilling pavement edges as soon as possible after the surface course is started.

Backfill and compact the pavement edges to produce a smooth surface adjacent to the pavement with no vertical edges.

Use Type "A" or "B" material to backfill pavement edges as shown in plans. Type "A" or "B" material shall consist of suitable material that when compacted will support the pavement edge. Rap is considered suitable Type "A" or "B" material.

Blade the existing vegetation into a neat wind-row prior to overlay. After placing Ty A or Ty B backfill and placing seeding, the material from the wind-row shall be replaced on the completed slopes. Emulsion shall be placed at a 50/50 solution of water to emulsion over disturbed area. Emulsion rate=0.15 Gal/SY residual. This work, materials and equipment shall be subsidiary to Item 134.

Item 160:

Sequence construction operations to salvage topsoil from one location and spread on areas ready to receive topsoil. Keep stockpiling of topsoil to a minimum.

Use fertile clay or loam from the project site not more than six inches below natural grade as topsoil.

Item 161:

Provide tickets representing quantity of compost delivered to site.

Item 247:

Construct uniform layer thickness of 12 inches, or less with the required density and moisture content. Minimum PI is equal to three (3) for all grades.

Flexible Base shall not contain more than 1% by weight of clay balls.

Roadway delivery flexbase measured by the Ton shall be used as additional base material to construct superelevation sections to rates shown in the plans. Processing of this material will not be paid for directly, but will be considered subsidiary to the various bid items. Place blue top hubs for alignment and elevations of new base at centerline and edge of pavement.

Measure roadway profile smoothness with a high speed or lightweight inertial profiler that is certified by the Texas Transportation Institute. Acceptance for locations constructed under traffic will be based on no 0.10-mile section having an average IRI value greater than 125 inches per mile. Acceptance for locations not constructed under traffic will be based on no 0.10 mile section having an average IRI value greater than 95 inches per mile and no individual wheel path spike greater than 105. Following corrections, re-profile the roadway to verify that corrective actions were successful.

Item 301:

Provide liquid antistripping agents unless otherwise directed. Add the minimum dosage determined by the manufacturer or higher dosage determined by design requirement and try subsequent trials at 0.25% increments.

Item 314:

Apply MS-2 or SS-1 as a prime, dilute the asphalt with base finish water, distribute in successive applications, and work into the top 1/4" of flex base. Residual asphalt 0.20 Gal/SY.

Item 316:

	AC20-5TR, AC20-XP AC15-P	CRS-2P	RC-250
JANUARY			REQUIRES INTERMEDIATE COURSE TO BE PLACED
FEBRUARY			
MARCH		REFER TO STANDARD SPECIFICATIONS ITEM 316 FOR TEMPERATURE REQUIREMENTS	
APRIL			
MAY			
JUNE	REFER TO STANDARD SPECIFICATIONS ITEM 316 FOR TEMPERATURE REQUIREMENTS		
JULY			
AUGUST			
SEPTEMBER		REFER TO STANDARD SPECIFICATIONS ITEM 316 FOR TEMPERATURE REQUIREMENTS	
OCTOBER			
NOVEMBER			REQUIRES INTERMEDIATE COURSE TO BE PLACED
DECEMBER			

RC-250 is only allowed as a first course in accordance with table above.

Utilize an asphalt distributor capable of providing a transversely varied asphalt rate. The Engineer will select the pavements where the transversely varied asphalt rate is required. When a transversely varied rate is required, the asphalt rate outside of the wheel paths will be between 22 and 32% higher than the asphalt rate applied in the wheel paths. Provide calibration documents to the Engineer that include a description of the spray bar(s) and nozzles that will be used and the percentage difference in asphalt rate achieved by each tested spray bar and nozzle arrangement. The nozzles proposed for use shall be clearly stamped or marked from the factory identifying the manufacturer.

First Course				
ITEM	APPLICATION			
	Emul. Asphalt Treatment	1 st Course		
*Asphalt Type	MS-2 or SS-1	CRS-2P	AC20-5TR, AC20-XP, AC15-P	RC-250 #
*Asph. Rate (Gal/SY)	0.20	0.50	0.42	0.28
Aggregate Type		B or L	B or L	B or L
Aggregate Grade		3	3	5
Aggr. Rate (CY/SY)		1:105	1:105	1:125
Min. Cure Time	24 hrs	14 days (Emulsion)		

When RC-250 is used as the 1st course, an intermediate course will be required and will be placed as soon as temperature allows which will be before 2nd Course is placed.

Intermediate Seal	
ITEM	APPLICATION
	Intermediate Course
*Asphalt Type	CRS-2P
*Asph. Rate (Gal/SY)	0.44
Aggregate Type	B or L
Aggregate Grade	4
Aggr. Rate (CY/SY)	1:120

* The information above is intended to provide general guidance and as a basis of estimate. Based on the season and weather conditions at the time, the engineer will determine the asphalt type and rates to be used at the time of application.

In addition to the temperature requirements of this Item, AC Asphalts used in Surface Treatments and Sealcoats must be placed between May 15 and August 31. Emulsions may be substituted for AC Asphalts outside this timeframe only with the approval of the Engineer.

Item 320:

Use a self-propelled wheel mounted MTV capable of receiving mix from the haul trucks, separate from the paver. It shall have a minimum storage capacity of approximately 25 tons. It shall be equipped with a pivoting discharge conveyor and shall completely and thoroughly remix the material prior to placement. The effectiveness of the MTV's remixing ability is subject to the approval of the Engineer. In addition, the paver shall have a surge storage insert with a minimum capacity of 20 tons.

The use of windrow pick-up equipment is allowed except on the first course of roadway material placed over the subgrade.

Item 354:

Remove the loose material from the roadway before opening to traffic.

Take possession of recycled asphalt pavement from the project and recycle the material.

Properly dispose of unsalvageable material at your own expense.

Slope longitudinal faces greater than 1 ¼" to a minimum of 1:1 slope at the end of the work period if traffic is able to traverse the joint. Slope transverse tapers to a minimum of 36:1 at the end of the workday. Remove the taper prior to continuing the milling.

For open shoulder sections, plane the asphalt so the flow of water is not impeded at the shoulder edge or across the surface. Added planing up to three feet in width outside the lines and grades of the plans, necessary to provide proper drainage, will be subsidiary to the bid item.

Patch pavement cut to excessive depth by equipment failure with an approved epoxy material. Re-plane patched area to an acceptable approved ride quality. Payment for these corrections is subsidiary to this item.

Item 400:

Structural Excavation is not paid for directly but is considered subsidiary to pertinent Items.

When placing concrete storm drain pipe on slopes of greater than 10 percent, provide cement stabilized backfill to a depth shown on the plans.

Item 421:

Furnish mix designs to the Engineer in a format compatible to the latest version of the Department's Construction Management System (Site Manager). Mix Design templates will be provided by the Engineer.

Supply the Engineer with a list of certified personnel and copies of their current ACI certificates before beginning production and when personnel changes are made. Supply hard copies of calibration reports for testing equipment when required by the Engineer.

Item 440:

Fiber Reinforced Concrete (FRC) can be used as a substitute for Non-Structural Class Reinforced Concrete in Mow-Strip and Rip Rap Items as approved. FRC may also be used for other Non-Structural Class Reinforced Concrete Items as approved.

Item 464:

The concrete collars and the connections of pipes to existing or proposed concrete boxes or pipe will not be paid for directly but will be considered subsidiary to the various bid items.

Item 465:

All manholes, junction boxes and inlets will require inverts unless otherwise directed.

Item 496:

Use earth embankment TY C which conforms to the requirements of Table 1 as backfill material for excavation and voids resulting from the removal of existing structures. The materials

County: NAVARRO

Highway: FM 3041

required for this work will be subsidiary to this item.

Item 500:

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

Item 502:

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times. Where turning radii are limited during phased construction at intersections, provide all weather surfaces such as RAP or base in turning movements to accommodate and to protect the traffic from edge drop-offs. Materials, labor, maintenance and removal for these temporary accesses and radii will not be paid for directly but will be considered subsidiary to the various bid items.

Provide written proposed lane closure information by 1:00 pm on the business day prior to the proposed closures. Do not close lanes when this requirement is not met.

When excavation is required next to a pavement lane carrying traffic and the widening is not completed by the end of the work day, backfill against the edge of the pavement with at least a 3:1 slope using an acceptable material to support vehicular traffic. Carefully remove and dispose of this material when work resumes. Backfilling pavement edges, and the materials required for the work will be subsidiary to this item.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

Do not commence work on the road before sunrise.

Do not operate or park any equipment/machinery closer than 30 feet from the traveled roadway after sunset unless authorized by the engineer.

When moving unlicensed equipment on or across any pavement or public highways, protect the pavement from all damage using an acceptable method.

As approved by the Engineer, provide uniformed off duty police officers and squad cars during lane or ramp closures, night time work or other situations that indicate a need for additional traffic control to protect the traveling public or the construction workforce. Provide documentation such as payroll, log sheets with signatures and badge number, or invoices from the government entity providing the officers for reimbursement. Complete the weekly tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Reimbursement will not be made for coordination fees charged by any party.

County: NAVARRO

Highway: FM 3041

Limit lane closures along FM 3041 to the hours between 9:00 am and 3:30 pm. Work in other areas of the project is not restricted to this time frame.

Item 506:

Take all practicable precautions to prevent debris from being discharged into the Waters of Texas or a designated wetland. Install Best Management Practices before demolition begins and maintain them during the demolition. Remove any debris or construction material that escapes containment devices and are discharged into the restricted areas, before the next rain event or within 24 hours of the discharge.

If temporary construction stream crossings are allowed under a Nationwide Permit, submit in writing for approval the type and location of each temporary stream crossing. Use temporary bridges, timber mats, or other structurally sound and non-eroding material for temporary stream crossings. A temporary culvert crossing will consist of storm sewer pipes and 4- to 8-inch nominal size rock. Temporary stream crossings must not cause more than minimal changes to the hydraulic flow characteristics of the stream, increase flooding, or cause more than minimal degradation of water quality. Remove the temporary stream crossings in their entirety and return the affected areas to their pre-existing elevation. All work and materials use for temporary construction stream crossings will not be paid for directly but are subsidiary to pertinent items.

Provide SW3P Signs. Obtain from the Engineer a copy of the project's completed TPDES Storm Water Program Construction Site Notice and Contractor Site Notice. Laminate the sheets and bond with adhesive to 36" X 36" plywood sign blanks. Ensure the sheets remain dry. Apply Type C Blue reflective sheeting as the background and add the text "SW3P" in 5" white lettering, centered at the top. Attach the signs to approved temporary mounts and locate at each of the project limits just inside the right of way line at a readable height or as directed by the Engineer. If the sign cannot be placed outside the clear zone, it must adhere to the TMUTCD. SW3P signs, maintenance, and reposting (for replacement or as needed to ensure readability) will be subsidiary to Item 502.

Concrete Washouts are required per the CGP. The Concrete Washout Area(s) structural controls must consist of temporary berms, temporary shallow pits, and/or temporary storage tanks to prevent contaminated runoff and must be lined as to prevent contamination of underlying soil. Ensure pits properly maintained including removal of concrete as not to allow over flow. The location(s) of washout area will be approved by the Engineer. When washout pits are no longer needed, they will be removed and area will be restored to original condition. This work, materials and labor will not be measured or paid for directly but will be subsidiary to Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls."

Item 530:

Provide Class "HES" concrete for concrete intersections and driveways listed or shown on the plans.

Item 585:

Use Surface Test Type A on all intersections and driveways.

Use Surface Test Type B pay adjustment schedule 3 on the travel lanes.

Attach sheeting applied to extruded aluminum panels to each individual extrusion.

Items 644:

Prior to taking elevations to determine lengths for fabrication of sign posts and/or sign support towers, obtain verification of all proposed locations.

All sign mounts shall have a clamp base system for all small roadside sign assemblies.

Provide two (2) sets of shop drawings for signs. The shop drawings shall conform to the details shown on the plans. The shop drawings shall show the details of the panels, wind beams, stiffeners, joint backing plates, splices, fasteners, brackets, and sign support connections. The shop drawings shall show letter types and sizes, interline spacing and message arrangements.

Affix a sign identification decal to the back of all signs and mark out the installation date in accordance with Item 643.

Item 666:

Place pavement markings according to the "Texas Manual on Uniform Traffic Control Devices" and the applicable plan sheets.

No contract stripe will be placed unless the striping inspector is present and at least 24 hours advance notice has been given by the Contractor.

Lay out pilot lines for approval to all final pavement marking applications.

Use equipment with footage counters capable of measuring the linear footage placed. Calibrate counters prior to the beginning of striping operations.

Use a double-drop bead system with an application rate of 7.0 lbs/gal Type II and 7.0 lbs/gal Type III beads. Apply the Type II beads before applying Type III beads. Use a gravity flow applicator to funnel beads onto the stripe. Reduce truck speed enough that the beads drop onto the stripe and do not roll in the paint film.

Apply all stripes in one coat.

A portable retro reflectometer may be used in accordance to the specifications for this project if total quantity of striping is less than 200,000 linear foot.

Due to problems in traffic handling, do not place a dash center stripe and edge line at the same time.

Item 672:

Black adhesive will be used on asphalt pavements and white adhesive will be used on concrete pavement.

Item 730:

At the discretion of the Engineer, mow non-paved areas within the project prior to placement of permanent vegetation. Mow up to three (3) cycles per growing season.

Item 3077:

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class B.

Provide PG binder 64-22 in Type SP-C mixture.

Item 6185:

The total number of truck mounted attenuators (TMAs) or trailer attenuators (TAs) required when utilizing the traffic control standards are shown in the tables below.

TCP 1 Series	Scenario		Required TMA/TA	
(1-1)-18 / (1-2)-18			1	
(1-3)-18	A	B	1	2

TCP 2 Series	Scenario		Required TMA/TA	
(2-1)-18 / (2-2)-18	All		1	
(2-3)-18	A	B	1	2

TCP 3 Series	Scenario			Required TMA/TA
(3-1)-13	All			2
(3-3)-14	A	B	D	2
	C			3

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed for the project. Additional TMAs/TAs used that are not specified in the plans in which the contractor expects compensation will require prior approval from the Engineer.

SPECIFICATION DATA

Table 1: Soil Constants Requirements				
Item	Description	Plasticity Index		Note
		Max	Min	
132	EMBANKMENT (ORD COMP)(TY C)	40	8	1

Note 1: Material excavated from the project must meet the PI requirements when used in the top 10 feet of embankment that supports the pavement structure or other locations shown in the plans. Do not use shale and obtain approval to incorporate shaley clay produced by the construction project.

Table 2: Basis of Estimate for Permanent Construction					
Item	Description	Thickness	Rate		Quantity
164	Drill Seed (Perm) (R) (C)	N/A	See Specifications		125,831 SY
166 *	Fertilizer (12-6-6)	N/A	500	Lbs./Ac	6.5 Ton
168	Vegetative Watering (Warm)**	N/A	12	MG/Ac/Day	18,719 MG
314	Emuls Asph	N/A	0.20	Gal/SY	9,583 Gal
3077	SP MIXES	See Plans	110	Lbs./SY/ln	5,274 Ton
3077	Tack Coat (Undiluted Application Rate)	New HMA	0.06	Gal/SY	2,875 Gal
		Milled HMA	0.11		
*For contractor's information only					
**Use Summer rate for calculation, adjust for actual field conditions/temperatures as necessary. See Vegetation Establishment Plan Sheet for estimated daily rates.					
***Portland Concrete Cement					
Note: (1) Base material weight based on 1.50 Ton/CY (dry- compacted)					
(2) Asphalt weight based on 110 Lbs./SY/ln					
(3) Subgrade weight based on 1.75 Ton/CY (dry-compacted)					
(4) Item 314 Residual Asphalt 0.20 Gal/SY					

Table 3: Basis of Estimate for Temporary Erosion Control Items				
Item	Description	Rate		Quantity
164	Drill Seeding (Temp) (Warm or Cool)	See Specifications		18,874 SY
166*	Fertilizer (12-6-6)	500	Lb/Ac	1.0 Ton
168	Vegetative Watering (Warm)**	12	MG/Ac/Day	2,809 MG
*For Contractor's Information Only.				
**Use Summer rate for calculation, adjust for Actual Field Conditions/Temperatures as Necessary. See Vegetation Establishment Sheet for estimated daily rates.				

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 26.0 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

This project required permits with environmental resources agencies. There is a high probability that an environmentally sensitive area could be encountered on the contractor designated Project-Specific Locations (PSL) for this project (haul roads, equipment staging areas, borrow pits, disposal sites, field offices, storage areas, parking areas, etc.). Item 7.6 "Project-Specific Locations", provides a listing of regulatory agencies that may need to be contacted regarding this project.

Install traffic marking signs prior to sealcoat application and remove within three days after placement of traffic markings.

Leave all right of way areas undisturbed until actual construction is to be performed in said areas.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 3090-01-012

DISTRICT Dallas
HIGHWAY FM 3041

COUNTY Navarro

CONTROL SECTION JOB				3090-01-012		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00066994			
COUNTY				Navarro			
HIGHWAY				FM 3041			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	464-6007	RC PIPE (CL III)(30 IN)	LF	30.000		30.000	
	464-6008	RC PIPE (CL III)(36 IN)	LF	286.000		286.000	
	464-6009	RC PIPE (CL III)(42 IN)	LF	100.000		100.000	
	464-6010	RC PIPE (CL III)(48 IN)	LF	111.000		111.000	
	464-6013	RC PIPE (CL III)(66 IN)	LF	387.000		387.000	
	465-6158	INLET(COMPL)(PAZD)(FG)(3FTX3FT-3FTX3FT)	EA	2.000		2.000	
	465-6162	INLET(COMPL)(PAZD)(FG)(5FTX5FT-4FTX4FT)	EA	2.000		2.000	
	466-6097	HEADWALL (CH - PW - 0) (DIA= 24 IN)	EA	2.000		2.000	
	466-6101	HEADWALL (CH - PW - 0) (DIA= 36 IN)	EA	4.000		4.000	
	466-6106	HEADWALL (CH - PW - 0) (DIA= 66 IN)	EA	2.000		2.000	
	466-6135	HEADWALL (CH - PW - S) (DIA= 42 IN)	EA	1.000		1.000	
	466-6136	HEADWALL (CH - PW - S) (DIA= 48 IN)	EA	1.000		1.000	
	466-6139	HEADWALL (CH - PW - S) (DIA= 66 IN)	EA	2.000		2.000	
	466-6188	WINGWALL (PW - 2) (HW=13 FT)	EA	2.000		2.000	
	467-6363	SET (TY II) (18 IN) (RCP) (6: 1) (P)	EA	72.000		72.000	
	467-6395	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA	6.000		6.000	
	467-6423	SET (TY II) (30 IN) (RCP) (6: 1) (P)	EA	2.000		2.000	
	496-6005	REMOV STR (WINGWALL)	EA	2.000		2.000	
	496-6006	REMOV STR (HEADWALL)	EA	12.000		12.000	
	496-6007	REMOV STR (PIPE)	LF	1,782.000		1,782.000	
	496-6008	REMOV STR (BOX CULVERT)	LF	166.000		166.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	12.000		12.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	208.000		208.000	
	506-6003	ROCK FILTER DAMS (INSTALL) (TY 3)	LF	529.000		529.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	737.000		737.000	
	506-6020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	111.000		111.000	
	506-6024	CONSTRUCTION EXITS (REMOVE)	SY	111.000		111.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	10,364.000		10,364.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	10,364.000		10,364.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	1,449.000		1,449.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,449.000		1,449.000	
	530-6005	DRIVEWAYS (ACP)	SY	3,082.000		3,082.000	
	530-6017	DRIVEWAYS (CONC) (HES)	SY	53.000		53.000	
	533-6003	RUMBLE STRIPS (SHOULDER) ASPHALT	LF	30,950.000		30,950.000	
	533-6004	RUMBLE STRIPS (CENTERLINE) ASPHALT	LF	15,587.000		15,587.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	1,450.000		1,450.000	



DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Navarro	3090-01-012	9A



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 3090-01-012

DISTRICT Dallas
HIGHWAY FM 3041

COUNTY Navarro

CONTROL SECTION JOB				3090-01-012		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00066994			
COUNTY				Navarro			
HIGHWAY				FM 3041			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	1,116.000		1,116.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	10.000		10.000	
	560-6011	MAILBOX INSTALL-S (TWW-POST) TY 4	EA	13.000		13.000	
	560-6012	MAILBOX INSTALL-D (TWW-POST) TY 4	EA	2.000		2.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	34.000		34.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	1.000		1.000	
	658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	36.000		36.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,169.000		1,169.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF	32.000		32.000	
	666-6309	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL)	LF	30,950.000		30,950.000	
	666-6312	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	LF	11,494.000		11,494.000	
	666-6315	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	LF	16,289.000		16,289.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	390.000		390.000	
	730-6107	FULL - WIDTH MOWING	CYC	3.000		3.000	
	3077-6013	SP MIXESSP-CSAC-B PG64-22	TON	5,274.000		5,274.000	
	3077-6075	TACK COAT	GAL	2,875.000		2,875.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY	10.000		10.000	
	6185-6003	TMA (MOBILE OPERATION)	HR	120.000		120.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 3090-01-012

DISTRICT Dallas
HIGHWAY FM 3041

COUNTY Navarro

CONTROL SECTION JOB				3090-01-012		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00066994			
COUNTY				Navarro			
HIGHWAY				FM 3041			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6002	PREPARING ROW	STA	156.000		156.000	
	104-6001	REMOVING CONC (PAV)	SY	11,305.000		11,305.000	
	104-6017	REMOVING CONC (DRIVEWAYS)	SY	47.000		47.000	
	105-6011	REMOVING STAB BASE AND ASPH PAV (2"-6")	SY	219.000		219.000	
	105-6075	REMOV STAB BASE AND ASPH PAV (10"-18")	SY	8,399.000		8,399.000	
	112-6001	SUBGRADE WIDENING (ORD COMP)	STA	147.000		147.000	
	132-6005	EMBANKMENT (FINAL)(ORD COMP)(TY C)	CY	8,489.000		8,489.000	
	134-6004	BACKFILL (TY A OR B)	STA	156.000		156.000	
	152-6001	ROAD GRADER WORK (ORD COMP)	STA	156.000		156.000	
	161-6017	COMPOST MANUF TOPSOIL (4")	SY	125,831.000		125,831.000	
	164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	125,831.000		125,831.000	
	164-6051	DRILL SEED (TEMP)(WARM OR COOL)	SY	18,874.000		18,874.000	
	168-6001	VEGETATIVE WATERING	MG	21,528.000		21,528.000	
	247-6073	FL BS (CMP IN PLC)(TY D GR 1-2) (6")	SY	8,848.000		8,848.000	
	247-6133	FL BS (RDWY DEL) (TY D GR 1-2)	TON	6,175.000		6,175.000	
	247-6304	FL BS (CMP IN PLACE) (TY D GR 1-2)(10")	SY	47,916.000		47,916.000	
	251-6034	REWORK BS MTL (TY C) (8") (ORD COMP)	SY	31,049.000		31,049.000	
	275-6001	CEMENT	TON	299.000		299.000	
	275-6003	CEMENT TREAT (NEW BASE) (6")	SY	8,848.000		8,848.000	
	275-6004	CEMENT TREAT (MX EXST MTL & NW BS) (6")	SY	42,340.000		42,340.000	
	314-6021	EMULS ASPH (PRIME)(MS-2 OR SS-1)	GAL	9,583.000		9,583.000	
	316-6024	ASPH (CRS-2P)	GAL	7,986.000		7,986.000	
	316-6029	ASPH (RC-250)	GAL	4,472.000		4,472.000	
	316-6403	AGGR (TY-B GR-5 OR TY-L GR-5)	CY	128.000		128.000	
	316-6419	ASPH (AC-15P, AC-20-5TR OR AC-20XP)	GAL	23,958.000		23,958.000	
	316-6435	AGGR (TY-B GR-4 OR TY-L GR-4 SAC-B)	CY	133.000		133.000	
	316-6440	AGGR (TY-B GR-3 OR TY-L GR-3)(SAC-B)	CY	152.000		152.000	
	354-6045	PLANE ASPH CONC PAV (2")	SY	28,227.000		28,227.000	
	400-6006	CUT & RESTORING PAV	SY	385.000		385.000	
	402-6001	TRENCH EXCAVATION PROTECTION	LF	568.000		568.000	
	403-6001	TEMPORARY SPL SHORING	SF	3,329.000		3,329.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY	52.000		52.000	
	432-6026	RIPRAP (STONE COMMON)(DRY)(18 IN)	CY	943.000		943.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	100.000		100.000	
	462-6034	CONC BOX CULV (10 FT X 10 FT)	LF	192.000		192.000	
	464-6003	RC PIPE (CL III)(18 IN)	LF	1,102.000		1,102.000	
	464-6005	RC PIPE (CL III)(24 IN)	LF	236.000		236.000	




DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Navarro	3090-01-012	9

DATE: 1/27/2023 11:14:01 AM
 FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\0815297\QUANTITY SUMMARY.dgn

SUMMARY OF ROADWAY ITEMS		
LOCATION		104
		6001
STA	STA	SY
0+60.00	28+00.00	2740
32+00.00	36+00.00	400
41+00.00	50+20.00	920
56+00.00	62+00.00	600
65+00.00	77+00.00	1200
78+50.00	99+00.00	2050
102+50.00	108+00.00	550
115+60.00	120+50.00	490
127+60.00	137+40.00	980
139+70.00	151+30.00	1160
152+00.00	154+15.00	215
PROJECT TOTALS		11305

SUMMARY OF ROADWAY ITEMS			
LOCATION		560	560
		6011	6012
STA	STA	MAILBOX INSTALL-S (TWW-POST) TY 4	MAILBOX INSTALL-D (TWW-POS T) TY 4
STA	STA	EA	EA
0+60.00	24+10.00	2	2
24+10.00	48+10.00	5	
48+10.00	72+10.00	1	
72+10.00	96+10.00	1	
96+10.00	120+10.00	3	
120+10.00	144+10.00	1	
144+10.00	156+46.97		
PROJECT TOTALS		13	2



Texas Department of Transportation

FM 3041

QUANTITY SUMMARY

SHEET 10 OF 5

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	10	

CK: DW: CK: DW:

SUMMARY OF ROADWAY ITEMS																		
LOCATION			LENGTH			100	105	112	132	134	152	247	247	247	251	275	275	275
						6002	6075	6001	6006	6004	6001	6073	6133	6304	6034	6001	6003	6004
STA	STA	LF	STA	SY	STA	CY	STA	STA	SY	TON	SY	SY	TON	SY	SY	SY		
0+60.00	2+20.00	160.00	1.60	498	2	15	2	2	533		498		3	533				
2+20.00	94+09.18	9189.18	91.89		92	5125	92	92		4467	28589	22462	179			30631		
94+09.18	95+69.18	160.00	1.60	498	2	44	2	2	533		498		3	533				
95+69.18	109+49.18	1380.00	13.80	4293	14	1575	14	14	4600		4293		27	4600				
109+49.18	111+09.18	160.00	1.60	498	2	28	2	2	533		498		3	533				
111+09.18	146+22.00	3512.82	35.13		35	1650	35	35		1708	10929	8587	68			11709		
146+22.00	147+82.00	160.00	1.60	498	2	52	2	2	533		498		3	533				
147+82.00	156+46.97	864.97	8.65	2114			9	9	2114		2114		12	2114				
PROJECT TOTALS					156	8399	147	8489	156	156	8848	6175	47916	31049	299	8848	42340	

SUMMARY OF ROADWAY ITEMS														
LOCATION			LENGTH			314	316	316	316	316	316	354	3077	3077
						6021	6024	6029	6403	6419	6435	6440	6045	6013
STA	STA	LF	GAL	GAL	GAL	CY	GAL	CY	CY	SY	TON	GAL		
0+60.00	2+20.00	160.00	100	83	46	1	249	1	2		55	30		
2+20.00	94+09.18	9189.18	5718	4765	2668	76	14294	79	91	20420	3145	1715		
94+09.18	95+69.18	160.00	100	83	46	1	249	1	2		55	30		
95+69.18	109+49.18	1380.00	859	716	401	11	2147	12	14		472	258		
109+49.18	111+09.18	160.00	100	83	46	1	249	1	2		55	30		
111+09.18	146+22.00	3512.82	2186	1821	1020	29	5464	30	35	7806	1202	656		
146+22.00	147+82.00	160.00	100	83	46	1	249	1	2		55	30		
147+82.00	156+46.97	864.97	423	352	197	6	1057	6	7		236	127		
PROJECT TOTALS					9583	7986	4472	128	23958	133	152	28227	5274	2875



FM 3041

QUANTITY SUMMARY

SHEET 20F 5

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	11	


DATE: 1/31/2023 8:40:52 AM
 FILE: c:\tdot\ipw_onlinetx\d051\craig_parker\d0815297\QUANTITY SUMMARY.dgn

DATE: 1/27/2023 2:34:13 PM
 FILE: c:\tdot\ipw_online\tdot5\craig_parker\0815297\QUANTITY SUMMARY.dgn

SUMMARY OF DRAINAGE ITEMS												
CULVERT NO.	STATION	400 6006	402 6001	403 6001	432 6001	432 6026	464 6005	464 6008	464 6009	464 6010	464 6013	465 6158
		CUT & RESTORING PAV	TRENCH EXCAVATI ON PROTECTI ON	TEMPORARY SPL SHORING	RIPRAP (CONC)(4 IN)	RIPRAP (STONE COMMON)(DRY)(18 IN)	RC PIPE (CL III)(24 IN)	RC PIPE (CL III)(36 IN)	RC PIPE (CL III)(42 IN)	RC PIPE (CL III)(48 IN)	RC PIPE (CL III)(66 IN)	INLET(COM PL)(PAZD) (FG)(3FTX 3FT-3FTX3 FT)
		SY	LF	SF	CY	CY	LF	LF	LF	LF	LF	EA
1	35+34.92	41	102		2	34				111		
2	43+55.65	87	94	901		81					330	
3	57+10.18	18	57		1	11	68					1
4	97+35.40	21	39			44		58				
5	107+24.51	18	58		1	11	76					1
6	117+60.45	26	87		1	22			100			
7	142+29.94	62	37			85		228				
8	147+57.96	26	40		3	70					57	
PROJECT TOTALS		299	513	901	8	357	144	286	100	111	387	2

SUMMARY OF DRAINAGE ITEMS												
CULVERT NO.	STATION	465 6162	466 6097	466 6101	466 6106	466 6135	466 6136	466 6139	496 6006	496 6007	658 6100	
		INLET(COM PL)(PAZD) (FG)(5FTX 5FT-4FTX4 FT)	HEADWALL (CH - PW - 0)(DIA= 24 IN)	HEADWALL (CH - PW - 0)(DIA= 36 IN)	HEADWALL (CH - PW - 0)(DIA= 66 IN)	HEADWALL (CH - PW - S)(DIA= 42 IN)	HEADWALL (CH - PW - S)(DIA= 48 IN)	HEADWALL (CH - PW - S)(DIA= 66 IN)	REMOV STR (HEADWAL L)	REMOV STR (PIPE)	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	
		EA	EA	EA	EA	EA	EA	EA	EA	LF	EA	
1	35+34.92	1						1	1	111	4	
2	43+55.65							2	2	276	4	
3	57+10.18		1						1	59	4	
4	97+35.40			2					2	48	4	
5	107+24.51		1						1	80	4	
6	117+60.45	1				1			1	100	4	
7	142+29.94			2					2	163	4	
8	147+57.96				2				2	40	4	
PROJECT TOTALS		2	2	4	2	1	1	2	12	877	32	

SUMMARY OF BRIDGE CLASS CULVERT AT TUPELO BRANCH ITEMS												NBI: 181750309001005
BRDGE NO.	STATION	400 6006	402 6001	403 6001	432 6001	432 6026	462 6034	466 6188	496 6005	496 6008	658 6100	
		CUT & RESTORING PAV	TRENCH EXCAVATI ON PROTECTI ON	TEMPORARY SPL SHORING	RIPRAP (CONC)(4 IN)	RIPRAP (STONE COMMON)(DRY)(18 IN)	CONC BOX CULV (10 FT X 10 FT)	WINGWALL (PW - 2) (HW=13 FT)	REMOV STR (WINGWAL L)	REMOV STR (BOX CULVERT)	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	
		SY	LF	SF	CY	CY	LF	EA	EA	LF	EA	
BCC AT TUPELO BRANCH	102+59.18	86	55	2428	44	586	192	2	2	166	4	
PROJECT TOTALS		86	55	2428	44	586	192	2	2	166	4	



FM 3041

QUANTITY SUMMARY


SHEET 3 OF 5

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		Navarro	12

CK: DW: CK: DW:

SUMMARY OF PAVEMENT MARKING ITEMS								
LOCATION		533	533	666	666	666	666	672
		6003	6004	6048	6309	6312	6315	6009
		RUMBLE STRIPS (SHOULDER) ASPHALT	RUMBLE STRIPS (CENTERLINE) ASPHALT	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL)	RE PM W/RET REQ TY I (Y)4"(BRK)(100MIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL)	REFL PAV MRKR TY II-A-A
STA	STA	LF	LF	LF	LF	LF	LF	EA
0+60.00	12+10.00	2300	1150		2300	860	775	29
12+10.00	24+10.00	2400	1200	7	2400	1200	510	30
24+10.00	36+10.00	2400	1200		2400	1200	1200	30
36+10.00	48+10.00	2400	1200		2400	1200	350	30
48+10.00	60+10.00	2400	1200		2400	560	1820	30
60+10.00	72+10.00	2333	1200	25	2333		2400	30
72+10.00	84+1.00	2393	1200		2393	860	1540	30
84+10.00	96+10.00	2400	1200		2400	1200	600	30
96+10.00	108+10.00	2400	1200		2400	1190	1220	30
108+10.00	120+10.00	2400	1200		2400	400	2000	30
120+10.00	132+10.00	2400	1200		2400	910	1490	30
132+10.00	144+10.00	2400	1200		2400	1200	550	30
144+10.00	156+10.00	2250	1200		2250	640	1760	30
156+10.00	156+46.97	74	37		74	74	74	1
PROJECT TOTALS		30950	15587	32	30950	11494	16289	390

SUMMARY OF SIGNING ITEMS			
LOCATION		644	644
		6001	6004
		IN SM RD SN SUP&AM TY10BWG(1)SA(P)	IN SM RD SN SUP&AM TY10BWG(1)SA(T)
SAT	STA	EA	EA
0+60.00	24+10.00	4	1
24+10.00	48+10.00	1	
48+10.00	72+10.00	15	
72+10.00	96+10.00	6	
96+10.00	120+10.00		
120+10.00	144+10.00		
144+10.00	156+46.97	8	
PROJECT TOTALS		34	1


Texas Department of Transportation
FM 3041
QUANTITY SUMMARY

SHEET 4 OF 5

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		13

DATE: 1/27/2023 11:14:09 AM
 FILE: c:\tdot\ipw_onlinetx\d051\craig_parker\d0815297\QUANTITY SUMMARY.dgn

CK
DW
CK
DW

SUMMARY OF EROSION CONTROL ITEMS																
LOCATION		161	164	164	*166	168	506	506	506	506	506	506	506	506	730	
		6017	6035	6051	6002	6001	6002	6003	6011	6020	6024	6038	6039	6041	6043	6107
		COMPOST MANUF TOPSOIL (4")	DRILL SEEDING (PERM) (RURAL) (CLAY)	DRILL SEED (TEMP)(W ARM OR COOL)	FERTILIZE R	VEGETATIV E WATERING	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (INSTALL) (TY 3)	ROCK FILTER DAMS (REMOVE)	CONSTRUCT ION EXITS (INSTALL) (TY 1)	CONSTRUCT ION EXITS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)	BIODEG EROSN CONT LOGS (INSTL) (12")	BIODEG EROSN CONT LOGS (REMOVE)	FULL - WIDTH MOWING
STA	STA	SY	SY	SY	TON	MG	LF	LF	LF	SY	SY	LF	LF	LF	LF	CYC
0+60.00	24+10.00	16769	16769	2515	0.996	2869								300	300	3
24+10.00	48+10.00	18307	18307	2746	1.087	3132		203	203		1601	1601	180	180		
48+10.00	72+10.00	20255	20255	3038	1.203	3465	54		54		624	624	210	210		
72+10.00	96+10.00	20415	20415	3062	1.213	3493					1533	1533	210	210		
96+10.00	120+10.00	20855	20855	3128	1.239	3568	77	249	326		2877	2877	75	75		
120+10.00	144+10.00	19639	19639	2946	1.167	3360		77	77	111	111	594	594	210	210	
144+10.00	156+46.97	9591	9591	1439	0.57	1641	77		77		2225	2225	120	120		
10% ADDITIONAL QUANTITY											910	910	144	144		
PROJECT TOTALS		125831	125831	18874	7.5	21528	208	529	737	111	111	10364	10364	1449	1449	3


ADDITIONAL 10% QUANTITY FOR BMP'S ITEMS PROVIDED TO ALLOW FOR VARYING SITE CONDITION AND PERIODIC REPLACEMENT DUE TO NORMAL WEAR.

SUMMARY OF MGF ITEMS					
LOCATION		432	540	542	544
		6045	6001	6001	6001
		RIPRAP (MOW STRIP)(4 IN)	MTL W-BEAM GD FEN (TIM POST)	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL END TREATMENT (INSTALL)
STA	STA	CY	LF	LF	EA
24+10.00	48+10.00	51	600	222	4
96+10.00	120+10.00	48	850	894	6
PROJECT TOTALS		100	1450	1116	10

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS					
LOCATION		662	6001	6185	6185
		6111	6002	6002	6003
		WK ZN PAV MRK SHT TERM (TAB)TY Y-2	PORTABLE CHANGEAB LE MESSAGE SIGN	TMA (STATION ARY)	TMA (MOBILE OPERATIO N)
		EA	EA	DAY	HR
STA 0+60 to STA 156+46.97		1169	2	10	120
PROJECT TOTALS		1169	2	10	120

*FOR CONTRACTOR'S INFO ONLY


DATE: 1/27/2023 11:14:11 AM
FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0815297\QUANTITY SUMMARY.dgn

 Texas Department of Transportation			
FM 3041			
QUANTITY SUMMARY			
SHEET 5 OF 5			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		14

DW: CK DW: CK CK:

SUMMARY OF DRIVEWAY AND INTERSECTIONS																		
DW #	STATION (LT/RT)	Type	EXISTING MATERIAL	PROPOSED LENGTH (FT)	PROPOSED THROAT WIDTH (FT)	PROPOSED RADIUS (R1)	PROPOSED RADIUS (R2)	104	105	530	530	464	464	464	467	467	496	
								6017	6011	6005	6017	6003	6005	6007	6363	6395	6423	6007
								REMOVING CONC DRIVEWAYS	REMOVING STAB BASE & ASPH PAV (2"-6")	DRIVEWAY (ACP)	DRIVEWAY (CONC) (HES)	RC PIPE (CL III) (18 IN)	RC PIPE (CL III) (24 IN)	RC PIPE (CL III) (30 IN)	SET (TY II) (18IN)(RCP) (6:1)(P)	SET(TY II) (24IN)(RCP) (6:1)(P)	SET(TY II) (30 IN)(RCP) (6:1)(P)	REMOVE STR (PIPE)
				LF	LF	LF	LF	SY	SY	SY	SY	LF	LF	LF	EA	EA	EA	LF
DW-1	1+29.85 RT	DRIVEWAY	GRASS	31	14	15	15			63		30			2			19
DW-2	1+38.51 LT	DRIVEWAY	GRAVEL	33	14	15	15			66		40			2			40
DW-3	1+98.70 LT	DRIVEWAY	GRASS	31	12	15	15			53		28			2			17
DW-4	2+27.48 RT	DRIVEWAY	GRASS	31	14	15	15			60		30			2			19
DW-5	5+10.10 RT	DRIVEWAY	GRAVEL	31	10	15	15			46		30			2			22
DW-6	6+32.29 RT	DRIVEWAY	GRAVEL	32	10	15	15			50		28			2			22
DW-7	8+54.16 LT	DRIVEWAY	ASPHALT	31	18	15	15		68	73		34			2			31
DW-8	8+81.88 RT	DRIVEWAY	GRAVEL	31	12	15	15			52		28			2			21
DW-9	9+84.09 LT	DRIVEWAY	GRASS	31	18	15	15			73		34			2			22
DW-10	9+89.85 RT	DRIVEWAY	GRASS	31	16	15	15			66		32			2			
DW-11	11+75.18 RT	DRIVEWAY	GRASS	31	12	15	15			52		28			2			19
DW-12	12+44.63 RT	DRIVEWAY	GRAVEL	31	12	15	15			50		28			2			18
DW-13	23+18.13 LT (NE 0150)	INTERSECTION	GRAVEL	31	14	15	15			59		30			2			30
DW-14	24+57.69 LT	DRIVEWAY	GRAVEL	31	12	15	15			52		28			2			19
DW-15	25+90.33 LT	DRIVEWAY	ASPHALT	31	18	15	15		58	73		34			2			24
DW-16	27+22.93 RT	DRIVEWAY	GRAVEL	31	10	15	15			45				30			2	29
DW-17	27+93.76 LT	DRIVEWAY	GRASS	31	16	15	15			66			32			2		20
DW-18	28+71.96 RT	DRIVEWAY	GRASS	31	16	20	25			80		74			4			51
DW-19	31+23.14 LT	DRIVEWAY	GRAVEL	31	14	15	15			59		60			4			40
DW-20	32+50.26 LT	DRIVEWAY	GRAVEL	31	14	15	15			59		30			2			19
DW-21	37+43.50 LT	DRIVEWAY	GRAVEL	42	14	15	15			78		32			2			20
DW-22	52+26.21 RT	DRIVEWAY	GRASS	41	10	30	30			87		32			2			31
DW-23	52+27.91 LT	DRIVEWAY	GRASS	41	12	20	20			74		32			2			31
DW-24	54+32.19 LT	DRIVEWAY	GRASS	41	16	15	15			84								
DW-25	54+64.45 RT	DRIVEWAY	GRASS	41	16	15	15			84								
DW-26	55+63.30 RT	DRIVEWAY	GRASS	42	32	15	25			165								
DW-27	59+87.76 LT	DRIVEWAY	GRAVEL	41	10	15	20			62			28			2		17
DW-28	61+81.25 RT (NE 0130)	INTERSECTION	GRAVEL	42	16	40	25			113		38			2			31
DW-29	62+55.23 LT (NE 0120)	INTERSECTION	GRAVEL	44	18	40	25			121								
DW-30	74+91.46 LT	DRIVEWAY	GRAVEL	36	8	15	15			43		24			2			24
DW-31	80+62.47 LT	DRIVEWAY	ASPHALT	36	10	15	15		41	51		26			2			19
DW-32	94+04.25 RT	DRIVEWAY	GRASS	61	14	15	15			106								
DW-33	96+96.99 LT	DRIVEWAY	GRASS	37	14	15	15			68		30			2			18
DW-34	103+78.83 LT	DRIVEWAY	GRASS	37	14	15	15			68		30			2			19
DW-35	104+90.63 RT	DRIVEWAY	GRASS	36	14	15	15			67								
DW-36	109+19.74 RT	DRIVEWAY	CONCRETE	38	10	15	15	47			53	28			2			20
DW-37	112+36.00 LT	DRIVEWAY	GRAVEL	51	10	15	20			71		32			2			31
DW-38	113+36.19 RT	DRIVEWAY	GRASS	49	14	30	20			107		32			2			32
DW-39	115+19.63 RT	DRIVEWAY	GRASS	36	14	25	20			80		30			2			19
DW-40	115+31.10 LT	DRIVEWAY	GRASS	37	14	15	20			71		30			2			19
DW-41	119+73.06 RT	DRIVEWAY	GRAVEL	36	10	15	15			52		26			2			25
DW-42	122+21.67 RT	DRIVEWAY	GRAVEL	42	12	15	15			67			32			2		32
DW-43	127+71.25 RT	DRIVEWAY	GRAVEL	38	12	15	15			65		28			2		2	21
DW-44	141+43.29 LT	DRIVEWAY	GRAVEL	37	10	15	15			51		26			2			19
DW-45	143+46.46 RT	DRIVEWAY	ASPHALT	37	10	15	15			52								
DRIVEWAY AND INTERSECTION SHEET TOTAL								47	219	3082	53	1102	92	30	72	6	2	905

DATE: 2/1/2023 10:25:45 AM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0815297\DRIVEWAY_SUMMARY.dgn



FM 3041

DRIVEWAY SUMMARY

SHEET 10F 1

COUNT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		15

CK: DW: CK: DW:

SUGGESTED SEQUENCE OF WORK

PHASE I

1. INSTALL PROJECT SIGNS & ADVANCE WARNING SIGNS AS SPECIFIED IN BC STANDARDS, TCP STANDARDS OR AS DIRECTED BY ENGINEER.
2. PLACE SW3P DEVICES AS PER STANDARD AND DIRECTED BY THE ENGINEER.
3. SET CHANNELIZATION DEVICES AND CONSTRUCT CULVERT EXTENSIONS/REPLACEMENT. DURING CONSTRUCTION MAINTAIN POSITIVE DRAINAGE. "SEE CULVERT DETAIL SHEET FOR MORE INFORMATION."
4. CONSTRUCT UPSTREAM OR DOWNSTREAM CULVERT EXTENSIONS ONE SIDE AT A TIME WITHOUT INTERRUPTION OF TRAFFIC FLOW. FOLLOW TCP(2-1)-18 AND TCP(2-2)-18 FOR THIS WORK

PHASE II


1. DELINEATE PAVEMENT EDGE AND CENTERLINE WITH VERTICAL PANELS. SALVAGE EXISTING TOPSOIL FROM WORK AREA.
2. REMOVE EXISTING HMAC AS SHOWN IN TYPICAL SECTIONS AND AS DETAILED IN THE PLAN SHEET. REMIX EXISTING MATERIAL WITH NEW FLEXIBLE BASE AND SPREAD OUT OVER 30' WIDTH AND NOTCHES. THIS WORK WILL BE PERFORMED IN ACCORDANCE WITH TCP(2-2)-18.
3. REWORK EACH SEGMENT FULL WIDTH EACH DAY TO WHERE NO GRADE DIFFERENCE IS PRESENT AT CENTERLINE.
4. CEMENT TREAT SUBGRADE MATERIAL IN HALF WIDTH.
5. PLACE NEW BASE SECTION IN HALF WIDTH. SEQUENCE OPERATIONS TO CONSTRUCT FULL WIDTH BASE SECTION WHERE NO GRADE DIFFERENCE IS PRESENT AT COMPLETION OF DAILY OPERATIONS.
6. APPLY PRIME COAT, PLACE ONE COURSE SURFACE TREATMENT, 2" SP-C SAC-B PER PLANS AND TEMPORARY PAVEMENT MARKINGS.
7. FILL SIDE SLOPE AND BACKFILL EDGES AS SHOWN IN TYPICAL SECTION OR AS DIRECTED BY THE ENGINEER.
8. CONSTRUCT DRIVEWAYS AND DRIVEWAY CULVERTS FOLLOWING TCP(2-1)-18.

PHASE III

1. INSTALL NEW SIGNS.
2. PLACE PERMANENT PAVEMENT MARKINGS FOLLOWING TCP(3-1)-13 AND TCP(3-3)-14 WITHIN 14 CALENDAR DAYS OF PLACEMENT OF FINAL SURFACE.
3. INSTALL MAILBOXES.
4. RE-VEGETATE DISTURBED SOILS IN COMPLETED PROJECT AREA AS SOON AS PRACTICABLE OR AS DIRECTED BY THE ENGINEER.
5. PERFORM FINAL CLEANUP AS DIRECTED BY ENGINEER.

TCP GENERAL NOTES

1. SUBMIT FOR APPROVAL A TRAFFIC CONTROL PLAN (TCP), FOLLOWING THE SUGGESTED SEQUENCE OF WORK, OUTLINING IN DETAIL, THE METHOD OF HANDLING TRAFFIC WITHIN AND ADJACENT TO THE WORK ZONE BEFORE BEGINING WORK ON THE PROJECT. THE CONTRACTOR MAY SUGGEST AN ALTERNATE SEQUENCE OF WORK TO THE CONSTRUCTION ENGINEER OF THE TRAFFIC CONTROL PLAN FOR APPROVAL. IF THE ALTERNATE TCP IS ACCEPTED, THE CONTRACTOR WILL BE RESPONSIBLE FOR DEVELOPING DETAILED PLANS TO BE SEALED BY A LICENSED PROFESSIONAL ENGINEER FOR INCLUSION WITH THE CHANGE ORDER. THE CONTRACTOR CANNOT PROCEED WITH ANY CONSTRUCTION OPERATIONS BASED ON REVISED PHASE/STAGE UNTIL WRITTEN APPROVAL OF THE ENGINEER IS OBTAINED.
2. OVERNIGHT LANE CLOSURES WILL NOT BE PERMITTED.
3. LIMIT THE LENGTH OF DAILY WORK TO THAT AREA OF OPERATION THAT CAN BE COMPLETED IN ONE WORKDAY IN ORDER TO ALLOW FOR TWO-WAY TRAFFIC AT NIGHT. SUCH AREAS MUST NOT EXCEED ONE (1) MILE, UNLESS APPROVED BY THE ENGINEER. WITHIN THE 1 MILE SECTION, ONLY CLOSE OFF THE AREA WHERE ACTUAL WORK IS BEING PERFORMED. COMPLETE ONE (1) MILE SECTION TO ONE COURSE TREATMENT BEFORE PROCEEDING TO THE NEXT SECTION UNLESS APPROVED BY THE ENGINEER.
4. INTERMITTENT ONE-WAY TRAFFIC CONTROL (LANE CLOSURES) WILL BE IN ACCORDANCE WITH TCP & WZ STANDARD AND AS DIRECTED BY THE ENGINEER.
5. THE CONTRACTOR WILL PROVIDE WRITTEN NOTICE TO THE ENGINEER BEFORE 1:00 PM ON THE BUSINESS DAY PRECEDING PROPOSED LANE CLOSURES. LANE CLOSURES WILL NOT BE PERMITTED WITHOUT THIS NOTIFICATION.
6. PAVEMENT EDGE DROP-OFFS WILL NOT BE ALLOWED TO REMAIN OVER NIGHT. AT THE END OF EACH WORKDAY ALL PAVEMENT EDGE DROP-OFFS SHALL BE BACK FILLED BY A SUITABLE MATERIAL TO FORM A STABLE 3:1 SLOPE OR FLATTER.
7. COMPLY WITH TCP (7-1)-13, WHICH INCLUDES PROVISIONS FOR CERTAIN SIGNS TO BE INSTALLED AND TO REMAIN UNTIL PERMANENT PAVEMENT MARKINGS ARE IN PLACE. THESE SIGNS ARE IN ADDITION TO SIGNS THAT MAY BE REQUIRED BY THE VARIOUS TCP AND BC STANDARDS.
8. THE CONTRACTOR SHALL COVER OR REMOVE ANY CONFLICTING SIGNS OR PAVEMENT MARKINGS DURING CONSTRUCTION AS DIRECTED BY ENGINEER AND THIS WORK SHALL BE SUBSIDIARY TO ITEM 502. LOCATION OF CONSTRUCTION EXIT WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
9. THE CONTRACTOR WILL PROVIDE AND MAINTAIN SKILLED FLAGGERS EQUIPPED WITH TWO-WAY RADIOS TO HANDLE TRAFFIC THROUGH THE WORK AREAS FOR THE SAFETY AND CONVENIENCE OF THE TRAVELING PUBLIC AND CONTRACTOR PERSONNEL.
10. PAY ATTENTION FOR OVERHEAD UTILITIES.
11. MAINTAIN DRIVEWAY AND SIDE STREET ACCESS AT ALL TIMES WITH AN ALL WEATHER SURFACE CONSISTING OF RAP OR BASE.
12. TEMPORARY SW3P EROSION CONTROL MEASURES SHALL ONLY BE PLACED IN AREAS WHERE SOIL DISTURBANCE IS EXPECTED TO OCCUR WITHIN TWO WEEKS. TEMPORARY SW3P EROSION CONTROL MEASURES SHALL BE REMOVED IN EACH AREA WITHIN TWO WEEKS OF VEGETATION ESTABLISHMENT OR AS DIRECTED BY THE ENGINEER.
13. MINIMIZE THE USE OF EQUIPMENT IN THE STREAMS AND RIPARIAN AREAS DURING CONSTRUCTION. WHEN POSSIBLE, EQUIPMENT ACCESS SHOULD BE REMOVED FROM BANKS OR BRIDGE DECKS. WHEN TEMPORARY STREAM CROSSINGS ARE UNAVOIDABLE, REMOVE STREAM CROSSINGS ONCE THEY ARE NO LONGER NEEDED, AND STABILIZE BANKS AND SOILS AROUND THE CROSSING.
14. KEEP ALL DRIVEWAYS OPEN DURING CONSTRUCTION IN ALL PHASES.
15. MAINTAIN POSITIVE DRAINAGE AT ALL TIME.
16. ALL TRAFFIC CONTROL SHALL CONFORM TO THE TEXAS ANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, ALL APPLICABLE TXDOT STANDARDS AND AS DIRECTED BY ENGINEER.
17. ALL TCP DEVICES AND SIGNS SHOWN ON TCP PLAN ARE CONSIDERED MINIMUM. ADDITIONAL DEVICES AND SIGNS MAY BE NECESSARY AND SUBSIDIARY TO ITEM 502.



Morgan Neill, P.E. 1/31/2023




FM 3041

TCP NARRATIVE


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	16	

CK: DW: CK: DW:



PHASE II
CONSTRUCTION OPERATION PRESENT




PHASE II
CONSTRUCTION OPERATION NOT PRESENT

NOTES:

1. INSTALL ADVANCE WARNING SIGNS. SEE BC & TCP STANDARDS AND TCP NARRATIVE FOR ADDITIONAL INFORMATION.
2. SEE CULVERT LAYOUTS FOR ADDITIONAL INFORMATION.
3. USE FLAGGERS AND PILOT VEHICLE TO HANDLE TRAFFIC FLOW.
4. CENTERLINE CHANNELIZATION DEVICES MAY BE OMITTED WHEN A PILOT CAR IS LEADING TRAFFIC IN ACCORDANCE WITH TCP(2-2)-18.
5. AT ANY REMOVAL OF EXISTING PAVEMENT AREA, CONTRACTOR SHALL SEQUENCE OPERATIONS TO PLACE FIRST LIFT OF NEW FLEXBASE THE SAME DAY AS REMOVAL.
6. CONTRACTORS RESPONSIBILITY TO DETERMINE IF THE EXISTING SUBGRADE IS SUITABLE FOR DIRECT TRAFFIC
7. COMPLETE EACH CULVERT REPLACEMENT OR EXTENSION WITHOUT INTERRUPTION.
8. IF NEEDED, PROVIDE TEMPORARY DETOUR WITH APPROVAL OF THE ENGINEER.
9. PROVIDE AND MAINTAIN A SMOOTH SURFACE AND PAVEMENT MARKINGS AS NEEDED AFTER CULVERT REPLACEMENT/EXTENSION.

LEGEND



Morgan Neill, P.E. 1/31/2023



FM 3041


TRAFFIC CONTROL PLAN
TYPICAL SECTIONS

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	NAVARRO	17	

DATE: 1/27/2023 1:18:41 PM
 FILE: c:\tdot\ipw_onlinet\mneil\tdot5\craig_parker\0463958\TRAFFIC CONTROL PLAN - TYPICAL SECTIONS CULVERT REPLACEMENT.dgn

CK:
 DW:
 CK:
 DW:



TYPICAL TCP FOR CULVERT REPLACEMENT-STEP 1





TYPICAL TCP FOR CULVERT REPLACEMENT-STEP 2

NOTES:

1. INSTALL ADVANCE WARNING SIGNS. SEE BC & TCP STANDARDS AND TCP NARRATIVE FOR ADDITIONAL INFORMATION.
2. SEE CULVERT LAYOUTS FOR ADDITIONAL INFORMATION.
3. USE FLAGGERS AND PILOT VEHICLE TO HANDLE TRAFFIC FLOW.
4. CENTERLINE CHANNELIZATION DEVICES MAY BE OMITTED WHEN A PILOT CAR IS LEADING TRAFFIC IN ACCORDANCE WITH TCP(2-2)-18.
5. COMPLETE EACH CULVERT REPLACEMENT OR EXTENSION WITHOUT INTERRUPTION.
6. IF NEEDED, PROVIDE TEMPORARY DETOUR WITH APPROVAL OF THE ENGINEER.
7. PROVIDE AND MAINTAIN A SMOOTH SURFACE AND PAVEMENT MARKINGS AS NEEDED AFTER CULVERT REPLACEMENT/EXTENSION.

LEGEND



Morgan Neill, P.E. 1/31/2023




FM 3041

TRAFFIC CONTROL PLAN
 TYPICAL SECTIONS
 CULVERT REPLACEMENT


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		NAVARRO	18

CK:
DW:
CK:
DW:



PLAN VIEW (NTS)
EXISTING CULVERT TO BE REMOVED




PROFILE VIEW (NTS)
EXISTING CULVERT TO BE REMOVED

ITEM 400- CUT & RESTORE PAVEMENT

CULVERT	LOCATION		AREA SY
	SAT	STA	
1	35+28.52	35+41.30	41
2	43+38.76	43+72.53	87
3	57+05.93	57+14.43	19
4	97+30.57	97+40.23	22
5	107+20.26	107+28.76	19
6	117+55.02	117+65.9	28
7	142+17.48	142+42.40	56
8	147+51.67	147+64.25	28
BCC	102+40.01	102+78.34	86

NOTE: EXISTING CULVERT AT THE INDICATED LOCATION WILL BE REMOVED AND REPLACED



Morgan Neill, P.E. 1/31/2023



FM 3041
PAVEMENT
CUT & RESTORE
DETAILS

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	19	

DATE: 1/25/23 10:32:24 9:39:36 AM
FILE: C:\DOCUMENTS\DRAWING\PAVEMENT CUT & RESTORE DETAILS.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/08
 FILE: DOCUMENT NAME

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) - 21			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
		DW:	TxDOT
		CR:	TxDOT
		HW:	TxDOT
		REVISIONS	
4-03	7-13	3090 01	012
9-07	8-14		FM 3041
5-10	5-21	DIST	COUNTY
		DAL	Navarro
			SHEET NO.
			20

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL LOCATION OF CROSSROAD SIGNS



May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	48" x 48"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12			60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	DAL	Navarro		21

DATE: 2022/09/08 FILE: DOCUMENT NAME

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 - 40 mph and greater 0.2 to 2 miles
 - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/08
FILE: DOCUMENT NAME

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		3090	01	012	FM 3041				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	DAL	Navarro		22				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	Navarro	23	


DATE: 2022/09/08
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- * See BC(4) for definition of "Work Duration."
- ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		3090 01		012		FM 3041			
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	DAL	Navarro	24					

DATE: 2022/09/08
FILE: DOCUMENT NAME

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	Hwy	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM	3041
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	Navarro	25	

DATE: 2022/09/08
FILE: DOCUMENT NAME


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE: 2022/09/08
 FILE: DOCUMENT NAME

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	Navarro	26	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/08
 FILE: DOCUMENT NAME

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS




- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
 (Maximum Sign Dimension)
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
 mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21


FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		3090 01		012	FM 3041				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	DAL	Navarro	27					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	Navarro	28	

DATE: 2022/09/08
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM	3041
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	DAL	Navarro	29	

DATE: 2022/09/08
FILE: DOCUMENT NAME

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	DAL	Navarro	30	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/08
FILE: DOCUMENT NAME

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.






RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	DAL	Navarro	31	
11-02 8-14				


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/08
FILE: DOCUMENT NAME


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME




TCP (1-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.



TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (1-1) - 18

FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
2-94 4-98				
8-95 2-12				
1-97 2-18	DAL	Navarro		SHEET NO. 32

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = WS ² / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40	L = WS	265'	295'	320'	40'	80'	240'	155'	305'
45		450'	495'	540'	45'	90'	320'	195'	360'
50	L = WS	500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60	L = WS	600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70	L = WS	700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

TCP (1-2b)

- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.




TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP (1-2) - 18


FILE: tcp1-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
4-90 4-98	DIST	COUNTY	SHEET NO.	
2-94 2-12	DAL	Navarro	33	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



BE PREPARED TO STOP
CW3-4 48" X 48"▲
CW20-7 48" X 48"▲
For either TCP(1-3a) or TCP(1-3b)
USE ONLY WHEN FLAGGERS CONTROL TRAFFIC
(See Notes 2 & 3)



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Additional flaggers may be positioned in advance of traffic queues to alert traffic to reduce speed.
 - DO NOT PASS, PASS WITH CARE and construction regulatory speed zone signs may be installed downstream of the ROAD WORK AHEAD signs.
 - When the work zone is made up of several work spaces, channelizing devices should be placed laterally across the closed lane to re-emphasize closure. Laterally placed channelizing devices should be repeated every 500 to 1000 feet in urban areas and every 1/4 to 1/2 mile in rural areas.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20', or 15' if posted speed are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the area of conflicting markings not the entire work zone.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO LANE ROADS
TCP (1-3) - 18


FILE: tcp1-3-18.dgn
CONT: 3090 01
REV: 8-95 2-12
1-97 2-18

DATE: 2-94 4-98
8-95 2-12
1-97 2-18


COUNTY: Navarro
SHEET NO.: 34

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



TCP (1-6a)
ONE LANE TWO-WAY CONTROL WITH STOP/SLOW AFADs



TCP (1-6b)
ONE LANE TWO-WAY CONTROL WITH RED/YELLOW LENS AFADs

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Automated Flagger Assistance Device (AFAD)		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- AFADs shall only be used in situations where there is one lane of approaching traffic in the direction to be controlled.
- Adequate stopping sight distance must be provided to each AFAD location for approaching traffic. (See table above).
- Each AFAD shall be operated by a qualified/certified flagger. Flaggers operating AFADs shall not leave them unattended while they are in use.
- One flagger may operate two AFADs only when the flagger has an unobstructed view of both AFADs and of the approaching traffic in both directions.
- When pilot cars are used, a flagger controlling traffic shall be located on each approach. AFADs shall not be operated by the pilot car operator.
- All AFADs shall be equipped with gate arms with an orange or fluorescent red-orange flag attached to the end of the gate arm. The flag shall be a minimum of 16" square.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the AFAD.
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- The R1-7aT "WAIT ON STOP" sign and the R1-8aT "GO ON SLOW" sign shall be installed at the AFAD location on separate supports or they may be fabricated as one 48" x 30" sign. They shall not obscure the face of the STOP/SLOW AFAD.
- The R10-6 "STOP HERE ON RED" arrow sign shall be offset so as not to obscure the lenses of the AFAD.

Texas Department of Transportation
Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
AUTOMATED FLAGGER ASSISTANCE DEVICES (AFADs)**

TCP (1-6) - 18

FILE: tcp1-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	3090 01	012	FM 3041
	DIST	COUNTY	SHEET NO.	
	DAL	Navarro	35	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME




TCP (2-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.





TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	DAL	Navarro	36	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

	MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation
Traffic Operations Division Standard



**TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL**

TCP (2-2) - 18

FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT	CON: 1985	SECT:	JOB:	HIGHWAY:
REVISIONS	3090	01	012	FM 3041
8-95 3-03				
1-97 2-12				
4-98 2-18	DAL		Navarro	SHEET NO. 37

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	70'	120'	90'
35		205'	225'	245'	35'	80'	160'	120'
40		265'	295'	320'	40'	90'	240'	155'
45	L = WS	450'	495'	540'	45'	100'	320'	195'
50		500'	550'	600'	50'	110'	400'	240'
55		550'	605'	660'	55'	120'	500'	295'
60		600'	660'	720'	60'	130'	600'	350'
65		650'	715'	780'	65'	140'	700'	410'
70		700'	770'	840'	70'	150'	800'	475'
75		750'	825'	900'	75'	160'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓
				TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Traffic Operations Division Standard

TEXAS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS




TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	DAL	Navarro	38	
4-98 2-18				

163

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
 - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

TCP (2-6) - 18


FILE: tcp2-6-18.dgn	DW: _____	CK: _____	DW: _____	CK: _____
© TxDOT December 1985	CONT: _____	SECT: _____	JOB: _____	HIGHWAY: _____
REVISIONS: _____	309001	012	FM 3041	
2-94 4-98				
8-95 2-12				
1-97 2-18	DAL	Navarro		SHEET NO. 30

166

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY




TRAIL/SHADOW VEHICLE A
with RIGHT Directional display Flashing Arrow Board

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)


TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES


1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.




TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



TRAIL/SHADOW VEHICLE B
with Flashing Arrow Board in CAUTION display



STRIPING FOR TMA


**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
UNDIVIDED HIGHWAYS**

TCP (3-1) - 13


FILE:	tcp3-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	December 1985	CONT:		SECT:		JOB:		HIGHWAY:	
REVISIONS		3090 01		012		FM 3041			
2-94	4-98	DIST:		COUNTY:		SHEET NO.:			
8-95	7-13	DAL		Navarro		40			
1-97									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/09/07
 FILE: DOCUMENT NAME




TCP (3-3a)
TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3b)
TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3c)
DIVIDED MULTILANE HIGHWAY




TCP (3-3d)
UNDIVIDED MULTILANE HIGHWAY




TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display
 Flashing Arrow Board



TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board
 in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				




GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

 Texas Department of Transportation		Traffic Operations Division Standard
TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL TCP (3-3) - 14		
FILE: tcp3-3.dgn © TxDOT September 1987	D#: TxDOT CONT: 3090 01 REVISIONS: 2-94 4-98 8-95 7-13 1-97 7-14	CK: TxDOT DW: TxDOT JOB: 012 COUNTY: Navarro HIGHWAY: FM 3041 SHEET NO.: 41

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



LEGEND		
*	Trail Vehicle	ARROW BOARD DISPLAY
**	Shadow Vehicle	
***	Work Vehicle	RIGHT Directional
	Heavy Work Vehicle	LEFT Directional
	Truck Mounted Attenuator (TMA)	Double Arrow
	Traffic Flow	Channelizing Devices


Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. This traffic control plan is for use on conventional roads posted at 45 mph or less and is intended for mobile operations that move continuously or intermittently (stopping up to approximately 15 minutes) such as short-line striping and in-lane rumble strips. When activities are anticipated to take longer amounts of time or traffic conditions warrant, a short duration or short-term stationary traffic control plan should be used.
2. A Truck Mounted Attenuator shall be used on Shadow Vehicle. Striping on the back panel of all truck mounted attenuators shall be 8" red and white reflective sheeting placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental material specification DMS-8300, Type A.
3. All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.
4. The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the drivers side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
5. Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C as per BC Standards. The arrow board operation shall be controlled from inside the truck.



STRIPING FOR TMA

Texas Department of Transportation
Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS FOR
ISOLATED WORK AREAS
UNDIVIDED HIGHWAYS**

TCP(3-4)-13


FILE: tcp3-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT July, 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
	DIST	COUNTY	SHEET NO.	
	DAL	Navarro	42	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS



TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS

For seal coat, micro-surface or similar operations

"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- Tabs shall not be used to simulate edge lines.
- Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
- Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
- Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.



TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS


TCP (7-1) - 13

FILE: tcp7-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT March 1991	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
4-92 4-98	DIST	COUNTY	SHEET NO.	
1-97 7-13	DAL	Navarro	43	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



WZ (RS-1a)

RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



WZ (RS-1b)

RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/2 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
 * For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation
 Traffic Safety Division Standard


TEMPORARY RUMBLE STRIPS

WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	DAL	Navarro	44	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:
http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS


WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	3090 01	SECT:	012	JOB:	FM 3041	HIGHWAY	
REVISIONS	1-97	DIST:	DAL	COUNTY:	Navarro	SHEET NO.		45	
	3-03								
	7-13								

DATE: 2022/09/07
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



LEGEND	
	Type 3 Barricade
	Channelizing Devices
	Trailer Mounted Flashing Arrow Board
	Sign
	Safety glare screen

DEPARTMENTAL MATERIAL SPECIFICATIONS	
SIGN FACE MATERIALS	DMS-8300
DELINEATORS AND OBJECT MARKERS	DMS-8600
MODULAR GLARE SCREENS FOR HEADLIGHT BARRIER	DMS-8610


Only pre-qualified products shall be used. A copy of the Compliant Work Zone Traffic Control Devices List (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:

<http://www.txdot.gov/business/resources/producer-list.html>

NOTES:

- Length of Safety Glare screen will be specified elsewhere in the plans.
- The cumulative nominal length of the modular safety glare screen units shall equal the length of the individual sections of temporary concrete traffic barrier on which they are installed so the joint between barrier sections will not be spanned by any one safety glare screen unit.
- Screen Panel/blades will be designed such that reflective sheeting conforming with Departmental Material Specification DMS-8300, Sign Face Materials, Type B or C Yellow, minimum size of 2 inches by 12 inches can be attached to the edge of the panel/blade. The sheeting shall be attached to one glare screen panel/blade per section of concrete barrier not to exceed a spacing of 30 feet. Barrier reflectors are not necessary when panel/blades are installed with reflective sheeting as described.
- Payment for these devices will be under statewide Special Specification "Modular Glare Screens for Headlight Barrier."
- This detail is only intended to show types of locations where Glare Screens would be appropriate. Required signing and other devices shall be as shown elsewhere in the plans.

BARRIER DELINEATION WITH MODULAR GLARE SCREENS



NOTES:

- When two-lane, two way traffic control must be maintained on one roadway of a normally divided highway, opposing traffic shall be separated with either temporary traffic barriers, channelizing devices, or a temporary raised island throughout the length of the two way operation. The above Typical Application is intended to show the appropriate application of channelizing devices when they are used for this purpose. This is not a traffic control plan. If this detail is to be used for other types of roads or applications, those locations should be stated elsewhere in the plans.
- Space devices according to the Tangent Spacing shown on the Device Spacing table on BC(9) but not exceeding 100'.
- Every fifth device should be an OTLD except when spaced closer to accommodate an intersection. An OTLD should be the first device on each side of intersecting streets or roads.
- Locations where surface mount bases with adhesives or self-righting devices will be required in order to maintain them in their proper position should be noted elsewhere in the plans.
- Channelizing devices are to be vertical panels, 42" cones or tubular markers that are at least 36" tall. Tubular markers used to separate traffic should have a rubber base weighing at least 30 pounds. Tubular markers that are 42" tall or more shall have four bands of reflective material as detailed for 42" cones on BC(10). Tubular markers less than 42" but at least 36" tall shall have three bands of 3" wide white reflective material spaced 2" apart. Reflective material shall meet DMS-8300, Type A.

VERTICAL PANELS & OPPOSING TRAFFIC LANE DIVIDERS (OTLD) SEPARATING TWO-WAY TRAFFIC ON NORMALLY DIVIDED HIGHWAYS







TRAFFIC CONTROL PLAN TYPICAL DETAILS

WZ(TD) - 17

FILE:	wz1d-17.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
4-98	2-17	3090	01	012	FM 3041				
3-03		DIST	COUNTY		SHEET NO.				
7-13		DAL	Navarro		46				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"



SIGNING FOR UNEVEN LANES


WZ (UL) - 13

FILE: wzu1-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
8-95 2-98 7-13	DIST	COUNTY		SHEET NO.
1-97 3-03	DAL	Navarro		47

DW: CK DW: CK DW: CK

EXISTING ROADWAY INVESTIGATION							
Texas Department of Transportation							
FM 3041 Cores, Navarro County							
CSJ #s 3090-01-012 & 0719-03-004							
Coring No.	Coordinates		Nominal Location	Roadway Direction	Total Pavement Thickness (Inches)	Layer Profile	
	Latitude	Longitude				(Inches)	(Inches)
C-1	32° 8'56.11"N	96°25'25.92"W	Approximately 122 ft N. of NE 1040	Northbound	16.25	0-4.25	Hot Mix Asphalt Concrete
						4.25-16.25	Cement Treated Base
						16.25-40.25	Light Brown Clay
C-2	32° 9'4.67"N	96°25'11.72"W	Approximately 0.31 miles E. of NE 1040	Westbound	20.25	0-5.75	Hot Mix Asphalt Concrete
						5.75-14.25	Cement Treated Base
						14.25-20.25	Lightly Cement Treated Soil
						20.25-44.25	Dark Gray Clay
C-3	32° 9'12.42"N	96°24'56.79"W	Approximately 0.59 miles E. of NE 1040	Eastbound	20.50	0-5.5	Hot Mix Asphalt Concrete
						5.5-12.5	Cement Treated Base
						12.5-20.5	Lightly Cement Treated Soil
						20.5-44.5	Brown Clay
C-4	32° 9'20.06"N	96°24'41.83"W	Approximately 0.88 miles E. of NE 1040	Westbound	16.75	0-4.75	Hot Mix Asphalt Concrete
						4.75-16.75	Cement Treated Base
						16.75-40.75	Dark Brown Clay
C-5	32° 9'27.05"N	96°24'26.37"W	Approximately 1.16 miles E. of NE 1040	Eastbound	12.50	0-4.25	Hot Mix Asphalt Concrete
						4.25-10.75	Cement Treated Base
						10.75-12.5	Lightly Cement Treated Soil
						12.5-36.5	Dark Gray Clay
C-6	32° 9'34.68"N	96°24'11.44"W	Approximately 1.45 miles E. of NE 1040	Westbound	18.25	0-7.25	Hot Mix Asphalt Concrete
						7.25-14.25	Cement Treated Base
						14.25-18.25	Lightly Cement Treated Soil
						18.25-42.25	Dark Brown Clay

DATE: 1/31/2023 11:29:27 AM
 FILE: c:\tdot\pw_onlinetx\d05\craig_parker\0463959\CORE BORING DATA.dgn



Texas Department of Transportation
FM 3041
CORE BORING DATA


SHEET 1 OF 3

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		48

DATE: 1/31/2023 11:29:35 AM
 FILE: c:\tdot\pw_onlinetx\dot5\craig_parker\0463959\CORE BORING DATA.dgn

DW: CK DW: CK

EXISTING ROADWAY INVESTIGATION							
Texas Department of Transportation							
FM 3041 Cores, Navarro County							
CSJ #s 3090-01-012 & 0719-03-004							
Coring No.	Coordinates Latitude Longitude		Nominal Location	Roadway Direction	Total	Layer	Layer Description
					Pavement Thickness (Inches)	Profile (Inches)	
C-7	32° 9'45.83"N	96° 24'0.61"W	Intersection of NE 0120 and FM 3041	Northbound	10.00	0-3.0	Hot Mix Asphalt Concrete
						3.0-10.0	Cement Treated Base
						10.0-34.0	Dark Brown Clay
C-8	32° 9'56.24"N	96° 23'49.13"W	Approx. 0.47 miles W. of NE 0150	Westbound	20.25	0-4.75	Hot Mix Asphalt Concrete
						4.75-14.25	Cement Treated Base
						14.25-20.25	Lightly Cement Treated Soil
						20.25-44.25	Brown Clay
C-9	32° 10'3.58"N	96° 23'33.91"W	Approx. 0.19 miles W. of NE 0150	Eastbound	15.50	0-7.0	Hot Mix Asphalt Concrete
						7.0-12.5	Cement Treated Base
						12.5-15.5	Lightly Cement Treated Soil
						15.5-39.5	Dark Brown Clay
C-10	32° 10'11.27"N	96° 23'18.98"W	Approx. 0.10 miles E. of NE 0150	Westbound	18.50	0-4.0	Hot Mix Asphalt Concrete
						4.0-11.0	Cement Treated Base
						11.0-13.0	Gravelly Clay Layer
						13.0-18.5	Concrete
						18.5-42.5	Dark Gray Clay
C-11	32° 10'18.80"N	96° 23'3.88"W	Approx. 272 ft W. of FM 1129	Eastbound	13.50	0-2.25	Hot Mix Asphalt Concrete
						2.25-9.5	Cement Treated Base
						9.5-13.5	Lightly Cement Treated Soil
						13.5-37.5	Dark Gray Clay
C-12	32° 10'26.49"N	96° 22'48.91"W	Approx. 0.22 miles E. of FM 1129	Westbound	6.25	0-1.0	Hot Mix Asphalt Concrete
						1.0-6.25	Concrete
						6.25-30.25	Dark Brown Clay

 Texas Department of Transportation

FM 3041

CORE BORING DATA

SHEET 2 OF 3

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		49

CK
DW
CK
DW

ALLIANCE GEOTECHNICAL GROUP LABORATORY TEST SUMMARY

Project: FM 3041								PROJECT NO.: DC20-465				Date: 10/2/2020			
SAMPLE NO.	SAMPLE ID	DEPTH, FEET	% MOISTURE	DRY DENSITY (pcf)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	-200 SIEVE	Sulfate ppm	UNC. STRESS (ksf)	% STRAIN	Pocket Penetrometer (tsf)	CONFINING PRESSURE (psi)	UU. STRESS (ksf)	% STRAIN
C-1		0-1			46	15	31		100						
C-2		1-2			52	19	33		120						
C-3		0-1			47	17	30		>100						
C-4		1-2			44	15	29		120						
C-5		0-1			50	20	30		>100						
C-6		1-2			46	15	31		120						
C-7		0-1			55	19	36		>100						
C-8		1-2			53	18	35		>100						
C-9		0-1			53	18	35		120						
C-10		1-2			49	20	29		100						
C-11		0-1			49	18	31		>100						
C-12		1-2			46	16	30		>100						

DATE: 1/31/2023 11:29:43 AM
FILE: c:\tdot\pw_onlinetx\d05\craig_parker\0463959\CORE BORING DATA.dgn

FM 3041
CORE BORING DATA

SHEET 3 OF 3


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		Navarro	50

CK: DW: CK: DW: CK: DW:

FM 3041 HORIZONTAL ALIGNMENT DATA

	STATION	EASTING	NORTHING		STATION	EASTING	NORTHING
POT	0+10.000 R1	2623443.339	6752497.389	PI	24+77.167 R1	2621350.093	6751191.578
PI	0+48.264 R1	2623410.717	6752477.391	Tangential Direction:	S58°09'04.980"W		
Tangential Direction:	S58°29'26.703"W			Tangential Length:	201.084		
Tangential Length:	38.264			PI	24+77.167 R1	2621350.093	6751191.577
PI	0+48.264 R1	2623410.715	6752477.39	PI	26+20.939 R1	2621228.621	6751114.67
PI	5+50.878 R1	2622984.572	6752210.89	Tangential Direction:	S57°39'39.117"W		
Tangential Direction:	S57°58'44.931"W			Tangential Length:	143.771		
Tangential Length:	502.614			PI	26+20.939 R1	2621228.62	6751114.669
PI	5+50.878 R1	2622984.573	6752210.891	PI	28+09.740 R1	2621068.172	6751015.159
PI	8+99.888 R1	2622689.234	6752024.925	Tangential Direction:	S58°11'34.044"W		
Tangential Direction:	S57°48'09.861"W			Tangential Length:	188.801		
Tangential Length:	349.01			PI	28+09.740 R1	2621068.172	6751015.159
PI	8+99.888 R1	2622689.233	6752024.925	PI	29+06.356 R1	2620986.808	6750963.058
PI	10+54.748 R1	2622557.218	6751943.97	Tangential Direction:	S57°21'59.622"W		
Tangential Direction:	S58°28'56.436"W			Tangential Length:	96.616		
Tangential Length:	154.86			PI	29+06.356 R1	2620986.812	6750963.06
PI	10+54.748 R1	2622557.221	6751943.972	PI	32+98.550 R1	2620652.918	6750757.314
PI	13+58.043 R1	2622300.277	6751782.829	Tangential Direction:	S58°21'30.881"W		
Tangential Direction:	S57°54'21.584"W			Tangential Length:	392.194		
Tangential Length:	303.295			PI	32+98.550 R1	2620652.93	6750757.321
PI	13+58.043 R1	2622300.273	6751782.826	PI	36+89.786 R1	2620318.161	6750554.849
PIBL CL-60	15+59.603 R1	2622128.883	6751676.752	Tangential Direction:	S58°50'01.903"W		
Tangential Direction:	S58°14'46.961"W			Tangential Length:	391.236		
Tangential Length:	201.56			PI	36+89.786 R1	2620318.161	6750554.849
PI	15+59.603 R1	2622128.883	6751676.752	PI	38+42.956 R1	2620186.478	6750476.613
PI	16+11.647 R1	2622084.472	6751649.618	Tangential Direction:	S59°17'04.522"W		
Tangential Direction:	S58°34'35.573"W			Tangential Length:	153.17		
Tangential Length:	52.044			PI	38+42.956 R1	2620186.478	6750476.613
PI	16+11.647 R1	2622084.472	6751649.618	PI	41+37.669 R1	2619933.971	6750324.641
PI	21+21.134 R1	2621651.862	6751380.497	Tangential Direction:	S58°57'29.951"W		
Tangential Direction:	S58°06'53.308"W			Tangential Length:	294.713		
Tangential Length:	509.488			PI	41+37.669 R1	2619933.971	6750324.641
PI	21+21.134 R1	2621651.861	6751380.497	PI	44+25.278 R1	2619688.656	6750174.513
PI	22+76.083 R1	2621520.9	6751297.683	Tangential Direction:	S58°32'02.409"W		
Tangential Direction:	S57°41'33.149"W			Tangential Length:	287.607		
Tangential Length:	154.949			PI	44+25.276 R1	2619688.658	6750174.514
PI	22+76.083 R1	2621520.903	6751297.685	PI	50+77.312 R1	2619129.553	6749839.025

NOTES:
 1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
 2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.



Texas Department of Transportation

FM 3041

ALIGNMENT DATA

SHEET 1 OF 8

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		51


DATE: 1/25/2023 9:44:12 AM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463959\fm_3041_Verical & Horizontal Alignment & Superelevation Data.dgn

DW: CK: DW: CK: DW: CK:

FM 3041 HORIZONTAL ALIGNMENT DATA

	STATION	EASTING	NORTHING		STATION	EASTING	NORTHING
Tangential Direction:	S59°02'03.466"W			PI	64+74.377 R1	2618312.4	6748748.925
Tangential Length:	652.036			PI	65+72.868 R1	2618274.529	6748658.006
PI	50+77.287 R1	2619129.574	6749839.037	Tangential Direction:	S22°36'48.608"W		
PI	51+80.124 R1	2619042.35	6749784.609	Tangential Length:	98.491		
Tangential Direction:	S58°02'07.508"W			PI	65+72.868 R1	2618274.521	6748657.987
Tangential Length:	102.812			PC	67+35.463 R1	2618210.02	6748508.733
PI	51+80.124 R1	2619042.353	6749784.611	Tangential Direction:	S23°22'18.479"W		
PC	52+20.427 R1	2619008.499	6749762.744	Tangential Length:	162.595		
Tangential Direction:	S57°08'31.383"W			PC	67+35.463 R1	2618210.02	6748508.733
Tangential Length:	40.302			PI	71+85.988 R1	2618031.298	6748095.173
PC	52+20.427 R1	2619008.499	6749762.744	CC		2616894.598	6749077.199
PI	56+47.689 R1	2618649.591	6749530.93	PT	76+08.471 R1	2617648.08	6747858.284
CC		2619771.982	6748580.677	Radius:	1433		
PT	60+50.054 R1	2618480.16	6749138.698	Delta:	34°54'20.090" Right		
Radius:	1407.193			Degree of Curvature(Arc):	03°59'53.915"		
Delta:	33°46'45.869" Left			Length:	873.008		
Degree of Curvature(Arc):	04°04'17.890"			Tangent:	450.525		
Length:	829.627			Chord:	859.57		
Tangent:	427.262			Middle Ordinate:	65.969		
Chord:	817.664			External:	69.152		
Middle Ordinate:	60.698			Tangent Back Direction:	S23°22'18.479"W		
External:	63.434			Radial Direction:	N66°37'41.521"W		
Tangent Back Direction:	S57°08'31.383"W			Chord Direction:	S40°49'28.524"W		
Radial Direction:	N32°51'28.617"W			Radial Direction:	N31°43'21.431"W		
Chord Direction:	S40°15'08.449"W			Tangent Ahead Direction:	S58°16'38.569"W		
Radial Direction:	N66°38'14.485"W			PT	76+08.471 R1	2617648.08	6747858.284
Tangent Ahead Direction:	S23°21'45.515"W			PI	78+21.581 R1	2617466.808	6747746.229
PT	60+50.054 R1	2618480.16	6749138.698	Tangential Direction:	S58°16'38.569"W		
PI	62+21.835 R1	2618412.041	6748981.002	Tangential Length:	213.11		
Tangential Direction:	S23°21'45.515"W			PI	78+21.581 R1	2617466.808	6747746.229
Tangential Length:	171.78			PI	78+73.890 R1	2617421.89	6747719.422
PIBL CL-46	62+21.835 R1	2618412.041	6748981.002	Tangential Direction:	S59°10'15.630"W		
PI	62+72.712 R1	2618392.445	6748934.049	Tangential Length:	52.309		
Tangential Direction:	S22°39'11.567"W			PI	78+73.890 R1	2617421.886	6747719.419
Tangential Length:	50.878			PI	81+82.897 R1	2617158.637	6747557.601
PI	62+72.712 R1	2618392.445	6748934.049	Tangential Direction:	S58°25'16.098"W		
PI	64+74.377 R1	2618312.409	6748748.946	Tangential Length:	309.007		
Tangential Direction:	S23°22'59.072"W			PI	81+82.897 R1	2617158.634	6747557.599
Tangential Length:	201.665			PI	85+79.770 R1	2616821.365	6747348.416
				Tangential Direction:	S58°11'30.036"W		

- NOTES:**
1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
 2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.



Morgan Neill, P.E. 1/31/2023

Texas Department of Transportation

FM 3041

ALIGNMENT DATA

SHEET 2 OF 8

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	52	


DATE: 1/25/2023 9:44:22 AM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463959\ALIGNMENT DATA.dgn

CK: DW: CK: DW:


FM 3041 HORIZONTAL ALIGNMENT DATA

	STATION	EASTING	NORTHING		STATION	EASTING	NORTHING
Tangential Length:	396.873			PI	95+53.921 R1	2615992.786	6746836.254
PI	85+79.770 R1	2616821.365	6747348.416	PI	97+05.674 R1	2615863.856	6746756.217
Tangential Direction:	S58°31'33.382"W			Tangential Direction:	S58°10'08.233"W		
Tangential Length:	147.494			Tangential Length:	151.753		
PI	87+27.265 R1	2616695.571	6747271.407	PI	97+05.674 R1	2615863.856	6746756.217
Tangential Direction:	S57°51'23.027"W			PI	97+91.315 R1	2615790.309	6746712.34
Tangential Length:	148.15			Tangential Direction:	S59°10'48.906"W		
PI	87+27.265 R1	2616695.571	6747271.407	Tangential Length:	85.641		
PI	88+75.414 R1	2616570.13	6747192.585	PI	97+91.315 R1	2615790.309	6746712.34
Tangential Direction:	S58°28'11.073"W			PI	98+70.509 R1	2615721.117	6746673.815
Tangential Length:	151.868			Tangential Direction:	S60°53'30.248"W		
PI	88+75.414 R1	2616570.136	6747192.589	Tangential Length:	79.194		
PI	90+27.282 R1	2616440.689	6747113.17	PI	98+70.509 R1	2615721.12	6746673.817
Tangential Direction:	S58°11'43.131"W			PI	99+96.957 R1	2615609.716	6746613.999
Tangential Length:	50.975			Tangential Direction:	S61°46'00.898"W		
PI	90+27.282 R1	2616440.693	6747113.172	Tangential Length:	126.448		
PI	90+78.257 R1	2616397.372	6747086.307	PI	99+96.957 R1	2615609.716	6746613.999
Tangential Direction:	S58°45'46.112"W			PI	100+96.835 R1	2615521.296	6746567.55
Tangential Length:	72.78			Tangential Direction:	S62°17'09.978"W		
PI	90+78.257 R1	2616397.372	6747086.307	Tangential Length:	99.878		
PI	91+51.037 R1	2616335.143	6747048.565	PI	99+96.957 R1	2615609.716	6746613.999
Tangential Direction:	S57°50'52.845"W			PI	100+96.835 R1	2615521.288	6746567.547
Tangential Length:	79.743			PI	102+22.134 R1	2615410.66	6746508.715
PI	91+51.037 R1	2616335.173	6747048.583	Tangential Direction:	S61°59'45.934"W		
PI	92+30.780 R1	2616267.659	6747006.146	Tangential Length:	125.299		
Tangential Direction:	S58°06'37.757"W			PI	102+22.134 R1	2615410.66	6746508.715
Tangential Length:	195.086			PI	102+60.324 R1	2615376.857	6746490.944
PI	92+30.780 R1	2616267.659	6747006.146	Tangential Direction:	S62°16'04.483"W		
PI	94+25.866 R1	2616102.017	6746903.085	Tangential Length:	38.19		
Tangential Direction:	S58°38'49.815"W			PI	102+60.324 R1	2615376.857	6746490.944
Tangential Length:	50.864			PI	104+57.646 R1	2615201.915	6746399.666
PI	94+25.866 R1	2616102.017	6746903.085	Tangential Direction:	S62°26'46.829"W		
PI	94+76.730 R1	2616058.581	6746876.621	Tangential Length:	197.323		
Tangential Direction:	S58°28'11.883"W			PI	104+57.646 R1	2615201.915	6746399.666
Tangential Length:	77.191			PI	105+05.637 R1	2615159.572	6746377.079
PI	94+76.730 R1	2616058.581	6746876.62	Tangential Direction:	S61°55'21.832"W		
PI	95+53.921 R1	2615992.786	6746836.254	Tangential Length:	47.991		

- NOTES:**
- ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
 - CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.



Morgan Neill, P.E. 1/31/2023



FM 3041
ALIGNMENT DATA

SHEET 3 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		Navarro	53

DATE: 1/25/2023 9:44:27 AM
FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463959\ALIGNMENT DATA.dgn


CK: DW: CK: DW:

FM 3041 HORIZONTAL ALIGNMENT DATA

	STATION	EASTING	NORTHING		STATION	EASTING	NORTHING
PI	105+05.637 R1	2615159.572	6746377.079	PI	118+53.244 R1	2614008.08	6745677.358
PI	105+54.919 R1	2615116.093	6746353.879	PIBL CL-6	122+36.596 R1	2613681.697	6745476.28
Tangential Direction:	S61°54'56.252"W			Tangential Direction:	S58°21'48.562"W		
Tangential Length:	49.281			Tangential Length:	383.352		
PI	105+54.919 R1	2615116.091	6746353.877	PI	122+36.596 R1	2613681.697	6745476.28
PIBL CL-84	106+99.310 R1	2614990.407	6746282.796	PI	123+83.905 R1	2613557.529	6745397.018
Tangential Direction:	S60°30'34.101"W			Tangential Direction:	S57°26'53.650"W		
Tangential Length:	144.392			Tangential Length:	147.309		
PI	106+99.310 R1	2614990.407	6746282.796	PI	123+83.905 R1	2613557.529	6745397.018
PI	107+99.422 R1	2614904.404	6746231.56	PI	127+47.266 R1	2613252.378	6745199.751
Tangential Direction:	S59°12'57.469"W			Tangential Direction:	S57°07'08.603"W		
Tangential Length:	100.109			Tangential Length:	363.361		
PI	107+99.419 R1	2614904.406	6746231.562	PI	127+47.266 R1	2613252.379	6745199.751
PI	110+42.339 R1	2614697.599	6746104.122	PI	128+51.009 R1	2613165.742	6745142.684
Tangential Direction:	S58°21'27.509"W			Tangential Direction:	S56°37'38.980"W		
Tangential Length:	242.92			Tangential Length:	103.743		
PI	110+42.339 R1	2614697.599	6746104.122	PI	128+51.009 R1	2613165.742	6745142.684
PI	111+42.942 R1	2614612.295	6746050.793	PI	129+03.326 R1	2613121.854	6745114.207
Tangential Direction:	S57°59'16.520"W			Tangential Direction:	S57°01'19.031"W		
Tangential Length:	100.602			Tangential Length:	52.317		
PI	111+42.941 R1	2614612.295	6746050.793	PI	129+03.326 R1	2613121.854	6745114.207
PI	111+93.100 R1	2614569.546	6746024.614	PIBL CL-23	129+56.422 R1	2613077.584	6745084.893
Tangential Direction:	S58°31'00.996"W			Tangential Direction:	S56°29'19.019"W		
Tangential Length:	50.128			Tangential Length:	53.095		
PI	111+93.069 R1	2614569.573	6746024.631	PI	129+56.422 R1	2613077.584	6745084.893
PI	112+43.569 R1	2614526.851	6745997.704	PI	130+06.443 R1	2613035.982	6745057.12
Tangential Direction:	S57°46'40.260"W			Tangential Direction:	S56°16'23.746"W		
Tangential Length:	50.5			Tangential Length:	50.021		
PI	112+43.569 R1	2614526.838	6745997.697	PI	130+06.443 R1	2613035.981	6745057.119
PI	113+95.276 R1	2614397.511	6745918.391	PI	131+50.923 R1	2612914.335	6744979.165
Tangential Direction:	S58°28'57.279"W			Tangential Direction:	S57°20'49.671"W		
Tangential Length:	151.708			Tangential Length:	144.48		
PI	113+95.276 R1	2614397.493	6745918.38	PI	131+50.923 R1	2612914.335	6744979.165
PI	118+53.244 R1	2614008.08	6745677.358	PI	131+98.570 R1	2612874.62	6744952.841
Tangential Direction:	S58°14'42.722"W			Tangential Direction:	S56°27'44.340"W		
Tangential Length:	457.967			Tangential Length:	47.647		

NOTES:

1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.



Morgan Neill, P.E. 1/31/2023

FM 3041			
ALIGNMENT DATA			
SHEET 4 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		54

DATE: 1/25/2023 9:44:31 AM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463959\ALIGNMENT DATA.dgn


DW: CK: DW: CK:

FM 3041 HORIZONTAL ALIGNMENT DATA

NOTES:

1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.

	STATION	EASTING	NORTHING		STATION	EASTING	NORTHING
PI	131+98.570 R1	2612874.62	6744952.841	PC	149+67.034 R1	2611389.619	6743992.547
PI	134+40.162 R1	2612671.787	6744821.595	PI	152+91.385 R1	2611120.749	6743811.13
Tangential Direction:	S57°05'40.592"W			CC	2611843.791	6743319.441	
Tangential Length:	241.592			PT	155+84.202 R1	2611050.863	6743494.398
				Radius:	812		
PI	134+40.162 R1	2612671.787	6744821.595	Delta:	43°32'53.382" Left		
PI	135+37.059 R1	2612590.32	6744769.134	Degree of Curvature(Arc):	07°03'22.070"		
Tangential Direction:	S57°13'12.456"W			Length:	617.168		
Tangential Length:	96.897			Tangent:	324.351		
				Chord:	602.419		
PI	135+37.059 R1	2612590.32	6744769.134	Middle Ordinate:	57.933		
PI	135+84.233 R1	2612550.409	6744743.987	External:	62.384		
Tangential Direction:	S57°47'11.196"W			Tangent Back Direction:	S55°59'27.216"W		
Tangential Length:	47.172			Radial Direction:	N34°00'32.784"W		
				Chord Direction:	S34°13'00.525"W		
PI	135+84.232 R1	2612550.41	6744743.988	Radial Direction:	N77°33'26.166"W		
PI	138+77.196 R1	2612305.107	6744583.817	Tangent Ahead Direction:	S12°26'33.834"W		
Tangential Direction:	S56°51'26.850"W						
Tangential Length:	292.964			PT	155+84.202 R1	2611050.863	6743494.398
				POT	156+46.973 R1	2611037.338	6743433.101
PI	138+77.196 R1	2612305.102	6744583.814	Tangential Direction:	S12°26'33.834"W		
PI	140+41.547 R1	2612166.506	6744495.483	Tangential Length:	62.771		
Tangential Direction:	S57°29'22.064"W						
Tangential Length:	164.351						
PI	140+41.547 R1	2612166.508	6744495.484				
PI	149+01.386 R1	2611444.038	6744029.266				
Tangential Direction:	S57°09'55.424"W						
Tangential Length:	859.839						
PI	149+01.386 R1	2611444.038	6744029.266				
PC	149+67.034 R1	2611389.619	6743992.547				
Tangential Direction:	S55°59'27.216"W						
Tangential Length:	65.648						



Morgan Neill, P.E. 1/31/2023

Texas Department of Transportation

FM 3041

ALIGNMENT DATA

SHEET 5 OF 8

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	55	


DW: CK: DW: CK: DW: CK:

FM 3041 VERTICAL ALIGNMENT DATA

	STATION	ELEVATION		STATION	ELEVATION
POT	0+59.999 R1	429.965	VPT	46+20.860 R1	393.365
VPC	11+59.975 R1	426.228	VPC	52+61.831 R1	403.206
Tangent Grade:	-0.003		Tangent Grade:	0.015	
Tangent Length:	1099.976		Tangent Length:	640.97	
VPC	11+59.975 R1	426.228	VPC	52+61.831 R1	403.206
VPI	15+24.242 R1	424.991	VPI	56+92.031 R1	409.811
VPT	18+88.510 R1	424.961	VPT	61+22.231 R1	407.599
			VHP	59+06.331 R1	408.154
Length:	728.536		Length:	860.4	
Entrance Grade:	-0.003		Entrance Grade:	0.015	
Exit Grade:	0		Exit Grade:	-0.005	
K Value =:	2196.341		K Value =:	419.784	
Middle Ordinate (E):	0.302		Middle Ordinate (E):	-2.204	
VPT	18+88.510 R1	424.961	VPT	61+22.231 R1	407.599
VPC	25+95.350 R1	424.905	VPC	68+32.836 R1	403.944
Tangent Grade:	0		Tangent Grade:	-0.005	
Tangent Length:	706.84		Tangent Length:	710.605	
VPC	25+95.350 R1	424.905	VPC	68+32.836 R1	403.944
VPI	28+42.649 R1	424.885	VPI	70+08.889 R1	403.038
VPT	30+89.949 R1	419.07	VPT	71+84.943 R1	398.871
Length:	494.599		Length:	352.107	
Entrance Grade:	0		Entrance Grade:	-0.005	
Exit Grade:	-0.024		Exit Grade:	-0.024	
K Value =:	211.094		K Value =:	190.021	
Middle Ordinate (E):	-1.449		Middle Ordinate (E):	-0.816	
VPT	30+89.949 R1	419.07	VPT	71+84.943 R1	398.871
VPC	40+91.445 R1	395.525	VPC	78+11.646 R1	384.035
Tangent Grade:	-0.024		Tangent Grade:	-0.024	
Tangent Length:	1001.496		Tangent Length:	626.703	
VPC	40+91.445 R1	395.525	VPC	78+11.646 R1	384.035
VPI	43+56.153 R1	389.301	VPI	78+97.774 R1	381.996
VPT	46+20.860 R1	393.365	VPT	79+83.902 R1	378.191
VLP	44+11.715 R1	391.76			
Length:	529.416		Length:	172.256	
Entrance Grade:	-0.024		Entrance Grade:	-0.024	
Exit Grade:	0.015		Exit Grade:	-0.044	
K Value =:	136.223		K Value =:	84	
Middle Ordinate (E):	2.572		Middle Ordinate (E):	-0.442	

NOTES:

1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.



Morgan Neill, P.E. 1/31/2023

FM 3041 ALIGNMENT DATA			
SHEET 6 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		56

DATE: 1/25/2023 9:44:38 AM
 FILE: c:\tdot\pw_onlinetx\d051\craig_parker\0463959\ALIGNMENT DATA.dgn

DW: CK: DW: CK: DW: CK:


FM 3041 VERTICAL ALIGNMENT DATA

	STATION	ELEVATION		STATION	ELEVATION
VPT	79+83.902 R1	378.191	VPT	104+79.572 R1	357.807
VPC	83+28.079 R1	362.985	VPC	105+98.910 R1	363.069
Tangent Grade:	-0.044		Tangent Grade:	0.044	
Tangent Length:	344.177		Tangent Length:	119.338	
VPC	83+28.079 R1	362.985	VPC	105+98.910 R1	363.069
VPI	85+96.536 R1	351.125	VPI	107+80.353 R1	371.069
VPT	88+64.993 R1	349.612	VPT	109+61.795 R1	373.683
Length:	536.914		Length:	362.885	
Entrance Grade:	-0.044		Entrance Grade:	0.044	
Exit Grade:	-0.006		Exit Grade:	0.014	
K Value =:	139.296		K Value =:	122.258	
Middle Ordinate (E):	2.587		Middle Ordinate (E):	-1.346	
VPT	88+64.993 R1	349.612	VPT	109+61.795 R1	373.683
VPC	91+86.575 R1	347.8	VPC	109+85.587 R1	374.026
Tangent Grade:	-0.006		Tangent Grade:	0.014	
Tangent Length:	321.582		Tangent Length:	23.791	
VPC	91+86.575 R1	347.8	VPC	109+85.587 R1	374.026
VPI	94+77.086 R1	346.163	VPI	111+67.665 R1	376.649
VPT	97+67.597 R1	347.287	VPT	113+49.744 R1	376.688
VLP	95+31.062 R1	346.829			
Length:	581.022		Length:	364.157	
Entrance Grade:	-0.006		Entrance Grade:	0.014	
Exit Grade:	0.004		Exit Grade:	0	
K Value =:	611.348		K Value =:	256.562	
Middle Ordinate (E):	0.69		Middle Ordinate (E):	-0.646	
VPT	97+67.597 R1	347.287	VPT	113+49.744 R1	376.688
VPC	100+93.444 R1	348.548	VPC	122+02.368 R1	376.872
Tangent Grade:	0.004		Tangent Grade:	0	
Tangent Length:	325.847		Tangent Length:	852.625	
VPC	100+93.444 R1	348.548	VPC	122+02.368 R1	376.872
VPI	102+86.508 R1	349.295	VPI	124+86.425 R1	376.933
VPT	104+79.572 R1	357.807	VPT	127+70.481 R1	364.884
			VHP	122+05.234 R1	376.872
Length:	386.128		Length:	568.113	
Entrance Grade:	0.004		Entrance Grade:	0	
Exit Grade:	0.044		Exit Grade:	-0.042	
K Value =:	96		K Value =:	133.263	
Middle Ordinate (E):	1.941		Middle Ordinate (E):	-3.027	

NOTES:

1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.

DATE: 1/25/2023 9:44:41 AM
 FILE: c:\tdot\pw_online\tdot5\craig_parker\0463959\ALIGNMENT DATA.dgn



Morgan Neill, P.E. 1/31/2023



FM 3041

ALIGNMENT DATA

SHEET 7 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		57


DW: CK: DW: CK:

FM 3041 VERTICAL ALIGNMENT DATA

	STATION	ELEVATION
VPT	127+70.481 R1	364.884
VPC	129+90.508 R1	355.552
Tangent Grade:	-0.042	
Tangent Length:	220.027	
VPC	129+90.508 R1	355.552
VPI	131+86.498 R1	347.239
VPT	133+82.488 R1	346.008
Length:	391.98	
Entrance Grade:	-0.042	
Exit Grade:	-0.006	
K Value =:	108.477	
Middle Ordinate (E):	1.771	
VPT	133+82.488 R1	346.008
VPC	139+85.344 R1	342.221
Tangent Grade:	-0.006	
Tangent Length:	602.856	
VPC	139+85.344 R1	342.221
VPI	141+58.924 R1	341.131
VPT	143+32.505 R1	341.261
VLP	142+95.510 R1	341.247
Length:	347.16	
Entrance Grade:	-0.006	
Exit Grade:	0.001	
K Value =:	493.828	
Middle Ordinate (E):	0.305	

NOTES:

1. ALIGNMENT DATA PROVIDED FOR CONTRACTOR'S INFORMATION ONLY.
2. CONSTRUCT ACCORDING TO EXISTING ROADWAY ALIGNMENT AND VERTICAL OFFSET AS NOTED IN TYPICAL SECTIONS AND PLAN SHEETS.



Morgan Neill, P.E. 1/31/2023

 Texas Department of Transportation			
FM 3041			
ALIGNMENT DATA			
SHEET 8 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		58

DATE: 1/25/2023 9:44:45 AM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463959\ALIGNMENT DATA.dgn

CK: DW: CK: DW:

FM 3041 SUPERELEVATION DATA REPORT


Design Speed: 50
 Pivot Method: Crown
 E Selection: 6%
 L Selection: Relative Gradient

Superelevation: LT


Station	Cross	Point Type	Transition
0+10.000 R1	-2.00%	Normal Crown	
50+48.619 R1	-2.00%	Normal Crown	Parabolic Curve
52+49.379 R1	-5.17%	Full Super	Parabolic Curve
60+21.102 R1	-5.17%	Full Super	Parabolic Curve
62+21.862 R1	-2.00%	Normal Crown	Parabolic Curve
65+64.551 R1	-2.00%	Normal Crown	Parabolic Curve
66+20.551 R1	0.00%	Level Crown	Parabolic Curve
66+76.551 R1	2.00%	Reverse Crown	Parabolic Curve
67+64.191 R1	5.13%	Full Super	Parabolic Curve
75+79.743 R1	5.13%	Full Super	Parabolic Curve
76+67.383 R1	2.00%	Reverse Crown	Parabolic Curve
77+23.383 R1	0.00%	Level Crown	Parabolic Curve
77+79.383 R1	-2.00%	Normal Crown	Parabolic Curve

Superelevation: RT

Station	Cross	Point Type	Transition
0+10.000 R1	-2.00%	Normal Crown	
50+48.619 R1	-2.00%	Normal Crown	Parabolic Curve
51+04.619 R1	0.00%	Level Crown	Parabolic Curve
51+60.619 R1	2.00%	Reverse Crown	Parabolic Curve
52+49.379 R1	5.17%	Full Super	Parabolic Curve
60+21.102 R1	5.17%	Full Super	Parabolic Curve
61+09.862 R1	2.00%	Reverse Crown	Parabolic Curve
61+65.862 R1	0.00%	Level Crown	Parabolic Curve
62+21.862 R1	-2.00%	Normal Crown	Parabolic Curve
65+64.551 R1	-2.00%	Normal Crown	Parabolic Curve
67+64.191 R1	-5.13%	Full Super	Parabolic Curve
75+79.743 R1	-5.13%	Full Super	Parabolic Curve
77+79.383 R1	-2.00%	Normal Crown	Parabolic Curve



Morgan Neill, P.E. 01/31/2023





FM 3041
 SUPERELEVATION DATA

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	59	


DATE: 1/25/2023 9:44:48 AM
 FILE: c:\tdot\pw_online\m\tdot5\craig_parker\0463959\ALIGNMENT DATA.dgn

DW: CK: DW: CK: DW: CK:




- LEGEND:**
- TRAVEL LANE & DIRECTION
 - MAILBOXES
 - DRIVEWAY

- NOTE:**
1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
 2. SEE DRIVEWAY DETAILS FOR RADIUS.
 3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
 4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
 5. DITCH GRADING SHOULD BE GRADED TO DRAIN, CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
 6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
 7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



Morgan Neill, P.E. 1/31/2023





FM 3041
ROADWAY PLAN

SHEET 1 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 60



DATE: 1/31/2023 8:41:13 AM
FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\10463959\ROADWAY PLAN.dgn

DW: CK: DW: CK: DW: CK:



- LEGEND:**
- TRAVEL LANE & DIRECTION
 - MAILBOXES
 - DRIVEWAY

- NOTE:**
1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
 2. SEE DRIVEWAY DETAILS FOR RADIUS.
 3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
 4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
 5. DITCH GRADING SHOULD BE GRADED TO DRAIN CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
 6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
 7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



Morgan Neill, P.E. 1/31/2023



FM 3041



PLAN LAYOUT

SHEET 2 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	61	

DATE: 1/25/2023 9:45:15 AM
 FILE: c:\tdot\pw_online\txdot\5\craig_parker\0463959\FM 3041 ROADWAY PLAN-2.dgn


CK:
DW:
CK:
DW:



PI 56+47.69
 Δ 33°46'45.9" (LT)
 D 04°04'17.9"
 T 427.26'
 L 829.63'
 R 1407.19'
 PC 52+20.43
 PT 60+50.05

- LEGEND:
- TRAVEL LANE & DIRECTION
 - MAILBOXES
 - DRIVEWAY

- NOTE:
1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
 2. SEE DRIVEWAY DETAILS FOR RADIUS.
 3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
 4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
 5. DITCH GRADING SHOULD BE GRADED TO DRAIN, CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
 6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
 7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



PI 71+85.99
 Δ 34°54'20.1" (RT)
 D 03°59'53.9"
 T 450.53'
 L 873.01'
 R 1433.00'
 PC 67+35.46
 PT 76+08.47

Morgan Neill, P.E. 1/31/2023

Texas Department of Transportation

FM 3041
ROADWAY PLAN


SHEET 3 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		Navarro	62

DATE: 1/25/2023 9:45:29 AM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463959\fm_3041_roadway_plan_3.dgn



NE 0130

DW:
 CK:
 DW:
 CK:



- LEGEND:**
- TRAVEL LANE & DIRECTION
 - MAILBOXES
 - DRIVEWAY

- NOTE:**
1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
 2. SEE DRIVEWAY DETAILS FOR RADIUS.
 3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
 4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
 5. DITCH GRADING SHOULD BE GRADED TO DRAIN CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
 6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
 7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



Morgan Neill, P.E. 1/31/2023

Texas Department of Transportation



FM 3041
ROADWAY PLAN

SHEET 4 OF 7



CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 63

DATE: 1/25/2023 9:45:41 AM
 FILE: c:\tdot\ipw_onlinetx\d05\craig_parker\10463959\FM_3041_ROADWAY_PLAN-4.dgn

CK:
DW:
CK:
DW:



- NOTE:
1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
 2. SEE DRIVEWAY DETAILS FOR RADIUS.
 3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
 4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
 5. DITCH GRADING SHOULD BE GRADED TO DRAIN, CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
 6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
 7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



Morgan Neill, P.E. 1/31/2023

Texas Department of Transportation

FM 3041



ROADWAY PLAN

SHEET 5 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 64



DATE: 1/25/2023 9:45:53 AM
FILE: c:\tdot\ipw_onlinetx\dot5\craig_parker\0463959\fm_3041_roadway_plan-5.dgn

DW: CK: DW: CK: DW: CK:



- LEGEND:**
- TRAVEL LANE & DIRECTION
 - MAILBOXES
 - DRIVEWAY

- NOTE:**
1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
 2. SEE DRIVEWAY DETAILS FOR RADIUS.
 3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
 4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
 5. DITCH GRADING SHOULD BE GRADED TO DRAIN, CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
 6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
 7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



Morgan Neill, P.E. 1/31/2023

Texas Department of Transportation

FM 3041



ROADWAY PLAN

SHEET 6 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 65

DATE: 1/25/2023 9:46:06 AM
 FILE: c:\tdot\ipw_onlinetx\d05\craig_parker\0463959\FM_3041_ROADWAY_PLAN-6.dgn

DW: CK: DW: CK: CK:





LEGEND:

- ← TRAVEL LANE & DIRECTION
- (MB) MAILBOXES
- (DW) DRIVEWAY

NOTE:

1. PROPOSED GRADE LINE IS CONTROLLED BY THE TYPICAL SECTIONS.
2. SEE DRIVEWAY DETAILS FOR RADIUS.
3. RIPRAP SHALL MAINTAIN POSITIVE DRAINAGE.
4. DITCH GRADING WILL BE PAID UNDER ITEM 152.
5. DITCH GRADING SHOULD BE GRADED TO DRAIN CONTINUOUS TO NEAREST STRUCTURE AS SHOWN IN THE PLANS.
6. SEE ROADWAY MISC. DETAILS SHEETS FOR PROFILE TRANSITION DETAILS.
7. SEE HORIZONTAL ALIGNMENT DATA FOR DETAILED CURVE INFORMATION.



Morgan Neill, P.E. 1/31/2023




FM 3041
ROADWAY PLAN





SHEET 7 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	66	

CK:
DW:
CK:
DW:



- NOTES:
1. DRIVEWAY RETURN RADIUS IS 15' FOR RESIDENTIAL DRIVEWAY OR 30' FOR CROSS STREET INTERSECTIONS UNLESS OTHERWISE NOTED IN THE PLAN SHEETS.
 2. DRIVEWAY LOCATIONS MAY BE SHIFTED AT TIME OF CONSTRUCTION AS DIRECTED BY THE ENGINEER TO MATCH EXISTING CONDITIONS.
 3. SEE DRIVEWAY SUMMARY SHEET FOR THROAT WIDTHS AND ADDITIONAL INFORMATION



Morgan Neill, P.E. 2/1/2023

Texas Department of Transportation


FM 3041
DRIVEWAY DETAILS

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	67	

DATE: 1/31/2023 1:09:02 PM
 FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\0463959\DRIVEWAY DETAILS.dgn


CK: DW: CK: DW:



PAVEMENT TRANSITION DETAIL

NOTE:


1. PROPOSED PAVEMENT TRANSITIONS ARE SHOWN IN PROPOSED TYPICAL SECTIONS.
2. PGL CHANGE / H IS SHOWN IN PROPOSED TYPICAL SECTIONS.



MAILBOX PLACEMENT

NOTE:

- * WHEN THE PAVED SHOULDER IS 8 FEET OR LESS, PLACE THE FACE OF THE MAILBOX APPROXIMATELY 2 FEET FROM THE EDGE OF PAVEMENT.
- ** WHEN THE PAVED SHOULDER IS 8 FEET OR MORE, PLACE THE FACE OF THE MAILBOX APPROXIMATELY 1 FEET FROM THE EDGE OF PAVEMENT.



Morgan Neill, P.E. 1/31/2023



FM 3041
TRANSITION & MAILBOX
DETAILS


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	68	


DATE: 1/25/2023 9:46:41 AM
FILE: c:\tdot\ipw_onlinetx\dtd5\craig_parker\0463959\FM_3041_TRANSITION_DETAIL.dgn

GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.




TYPICAL POST PLACEMENT




WOOD BLOCK TO ROUND WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.

12" X 12" X 1/4" (ASTM A36) STEEL BOTTOM PLATE WITH 1" DIA. HOLES REQUIRED WITH BOLT-THROUGH INSTALLATION.

LOW FILL CULVERT POST




NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.


NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.



BUTTON HEAD BOLT




MID-SPAN RAIL SPLICE DETAIL

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

		Design Division Standard	
<h2>METAL BEAM GUARD FENCE</h2> <h3>TL-3 MASH COMPLIANT</h3> <h3>GF(31)-19</h3>			
FILE: gf3119.dgn	DN: TxDOT	CK: KM	DW: VP
© TxDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	3090	01	012
	DIST	COUNTY	SHEET NO.
	DAL	NAVARRO	69


DATE: FILE:



Note: See SGT standard sheets for proper installation and length of need requirements.

GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)


GENERAL NOTES

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type I or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




SECTION A-A

Typical




MOW STRIP DETAIL

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)

Curb shown on top of mow strip




CURB OPTION (3)


		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF(31)MS-19			
FILE: gf31ms19.dgn	DN: TxDOT	CK: KM	DW: VP
©TxDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	3090	01	012
	DIST	COUNTY	SHEET NO.
	DAL	NAVARRO	70

DATE:
FILE:

TYPE 1 - MULTIPLE



TYPE 4 - MULTIPLE



MAILBOX SIZES


MAILBOX SIZE	TYPICAL DIMENSIONS			MAX **
	LENGTH	WIDTH	HEIGHT	
SMALL	19 1/2"	6"	7"	6 LBS
MEDIUM	22 1/2" *	8" *	11 1/2" *	8 LBS
LARGE	23 1/2"	11 1/2"	13 1/2"	11 LBS
EXTRA LARGE	18"	14"	12"	13 LBS
LOCKABLE	18"	11 1/2"	15"	23 LBS

GENERAL NOTES:

- Dimensions shown (length, width, and height) are typical, not maximums. However, anytime a medium size mailbox is mounted on a single/double mount or on the outside position on a multi mount, the dimensions shown are maximums.
- Mailboxes shall be made of light weight sheet metal or light weight plastic. Heavy steel, cast iron or decorative mailboxes shall not be used on the state highway system.

* See Note 1.
** Excluding Molded Plastic on 4 X 4 Post


TYPICAL INSTALLATION MEASUREMENTS




NOTE:

Mailbox installations in sidewalk areas shall be in accordance with the latest TxDOT Design Standard sheets PED-Pedestrian Facilities Curb Ramps.


TYPE 2 and 4 - SINGLE/DOUBLE



TYPE 3 - SINGLE/DOUBLE





PLACEMENT OF EMERGENCY LOCATION NUMBER




NOTES:

- Location numbers are provided by homeowner. Minimum size 1" height.
- Location number is typically placed on the mailbox in a contrasting color.
- Black numbers may be placed on the Type 2 object marker if the numbers cannot be placed on the mailbox.
- Alternatively, a green or blue plate with white numbers attached may be mounted below the object marker. Other contrasting color configuration, as approved, may be used.
- See 3 of 4 for Foundation details.
- See 4 of 4 for Hardware details.

SHEET 1 OF 4



TYPE 5




MAILBOX MOUNTING AND ASSEMBLY

MB(1)-21

FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT March 2004	CON: 3090	SECT: 01	JOB: 012	HIGHWAY: FM 3041
2/2005	11/2009	4/2015	DIST: COUNTY	SHEET NO. 71
6/2005	1/2011		DAL	Navarro
11/2006	7/2014			

TYPE 1 - MULTI LOCKABLE AND XL MAILBOX



Multiple Mailbox Post
NIGP#: 45057255254
For 12 gauge steel

TYPE 2/4 - SINGLE LOCKABLE MAILBOX





Plate Washer (X2)
NIGP: 45057250255

Single Mailbox Bracket
NIGP: 45057252350

Bolt, 3/8" x 3 1/2" hex (X2)
NIGP: 32020561117

Bolt, 5/16" x 1 1/4" hex (X4)
NIGP: 32020681246

TYPE 2/4 - SINGLE XL MAILBOX



L-bracket (X4)
NIGP#: 45057250263

Bolt, 3/8" x 3 1/2" hex (X2)
NIGP: 32020561117

Bolt, 5/16" x 1 1/2" hex (X4)
NIGP: 32020560507

Single Mailbox Bracket
NIGP: 45057252350


Bolt, 1/4" x 3/4" hex (2 each side)
NIGP: 45057521002
Field Drill Holes as Needed

Plate Washer (X2)
NIGP: 45057250255

Bolt, 3/8" x 3 1/2" hex (X2)
NIGP: 32020561117

NOTE:
Follow same configuration when mounting an XL mailbox on a Type 4 multi post.

TYPE 1 MULTI - LOCKABLE ARCHITECTURAL (LA)



Bolt, 3/8" x 3/4" hex (X6)
NIGP: 45057521028
Typical at Each Angle Bracket and plate washer


Mailbox Bracket
NIGP: 45057252251 (Inverted)

Bolt, 3/8" x 4 1/2" hex
NIGP: 32020561133
Drill 1/16" hole in Post

Plate Washer (X2)
NIGP: 45057250255

Angle Bracket Part A (X2)
NIGP: 45057258001

TYPE 1 MULTI - XL MAILBOX



L-bracket (X4)
NIGP# 45057250263

Bolt, 3/8" x 3/4" hex (X6)
NIGP: 45057521028
Typical at Each Angle Bracket and plate washer

Angle Bracket Part A (X2)
NIGP: 45057258001

Bolt, 1/4" x 3/4" hex (2 each side)
NIGP: 45057521002
Field Drill Holes as Needed


Mailbox Bracket
NIGP#: 45057252251 (Inverted)

Bolt, 5/16" x 2 1/2" hex (X4)
NIGP: 32020220938
Use existing hole in mailbox

Plate Washer (X2)
NIGP#: 45057250255

Bolt, 3/8" x 4 1/2" hex
NIGP: 32020561133
Drill 1/16" hole in Post

TYPE 3 - XL MAILBOX MOUNTING



Bolt, 5/16" x 1- 1/2" hex (X4)
NIGP: 32020560507

L-bracket (X4)
NIGP: 45057250263

Plate Washer (X2)
NIGP: 45057250255

Angle Bracket Part B
NIGP: 45057258027

Angle Bracket Part A
NIGP: 45057258001

Bolt, 1/4" x 3/4" hex (2 each side)
NIGP: 45057521002
Field Drill Holes as Needed

Mailbox Bracket
NIGP: 45057252251 (Inverted)

Bolt, 3/8" x 3/4" hex (X2)
NIGP: 45057521028
Typical at Each Angle Bracket

Bolt, 5/16" x 3" (X2)
NIGP: 32020743004

SHEET 2 OF 4




XL AND LOCKABLE ARCHITECTURAL MAILBOX ASSEMBLY MB (2) - 21

FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
2/2005	11/2009	4/2015		
6/2005	1/2011			
11/2006	7/2014			
DIST	COUNTY	SHEET NO.		
DAL	Navarro	72		


DATE:
FILE:

TYPE 1 - SUPPORT/FOUNDATION

Thin Wall Tube w/ V-LOC Anchorage




TYPE 3 - SUPPORT/FOUNDATION




NOTES:

1. Attach Object Marker (OM) facing direction of traffic.
2. OM will also be required on opposite side if installed on a 2-Lane, 2-Way roadway.

TYPE 5 - SUPPORT/FOUNDATION



TYPE 6 - TEMPORARY MAILBOX SUPPORT




NOTES:

1. Place on approved plastic drum as shown in the Compliant Work Zone Traffic Control Devices (CWZTCD).
2. Existing attachment hardware shall be used unless damaged. Damaged hardware shall be replaced.


TYPE 2 - SUPPORT/FOUNDATION

Thin Wall Steel Tube w/Wedge Anchor System



TYPE 4 - SUPPORT/FOUNDATION

Whitecoated steel post NIGP: 45057561107
Multiple post NIGP: 45057257409
Recycled Rubber post (RR) NIGP: 45057561057



GENERAL NOTES:

1. Erect post plumb or vertical.
2. When galvanized part is required galvanize in accordance with Item 445.
3. Use a concrete footing as shown or when directed. Concrete footing will be required when soils do not hold the support/foundations in a stable condition, only on Type 1, Type 2, and Type 4

SHEET 3 OF 4



















MAILBOX SUPPORT AND FOUNDATION

MB (3) - 21

FILE: MB-21.dgn	DN:	CK:	DW:	CK:
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
2/2005	11/2009	4/2015		
6/2005	1/2011			
11/2006	7/2014			
	DIST	COUNTY		SHEET NO.
	DAL	NAVARRO		73

TYPE	TYPE 1	TYPE 2	TYPE 3	TYPE 4	TYPE 5	TYPE 6
Configuration	Multiple	Single or Double	Single or Double	Single	Double	Multiple
Mailbox Size NIGP #	Outside Position: S or M Inside Position: S, M, L, XL, or LA	Single: S, M, L, XL, or LA Double: SS, SM, MM	Single: S, M, L, or XL Double: SS, SM, MM	S, M, L, XL, or LA	SS, SM, or MM	Outside Position: S or M Inside Position: S, M, L, or XL
Mailbox Post NIGP #	45057255254 (Galvanized Multiple)	45057561404 (Thin Walled Govanize)	57044325108 (Wing Channel Post)	45057561107 (Thin walled white powder coated) 45057561057 (Recycled Rubber Post: S or M only)	45057561107 (Thin Walled White Powder Coated)	45057257409 (White Powder Coated Multiple)
Post and Mailbox Hardware NIGP #	45057259009 (Wedge) 45057256500 (V-Wing Socket) 45057253002 (Bracket Extension) 45057252251 (Mailbox Bracket) 45057258001 (Part A Angle Bracket x2) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	80130598701 (Wedge) 80130238407 (Wedge Anchor) 45057253002 (Bracket Extension) 45057252343 (Double MB Bracket) 45057252350 (S. Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	45057541653 (Type 3 Double Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057253002 (Bracket Extension) 45057258001 (Part A Angle Bracket) 45057258027 (Part B Angle Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057252350 (Single Mailbox Bracket) 45057253002 (Bracket Extension) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252343 (Double Mount Bracket) 45057252251 (Mailbox Bracket x2)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252350 (Single Mount Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)
Foundation Used	Class B Concrete (Required for LA Mailboxes)	Class B Concrete (Required for LA Mailboxes)	None	Class B Concrete (not used with recycled rubber post, required for LA Mailboxes)	Class B Concrete (not required)	Class B Concrete

 NIGP: 45057250263 L-Bracket x4 for XL sized mailboxes	 NIGP: 45057252343 Double Mailbox Bracket For Type 2 and Type 4 double mount	 NIGP: 45057252350 Single Mailbox Bracket For Type 2 single and for Type 4 single and multi mount	 NIGP: 45057258001 Part "A" Angle Bracket For Type 1 multi (2 per mailbox) and Type 3 single and double
 NIGP: 45057251055 Type 6 Angle Bracket (2 per mailbox)	 NIGP: 45057252251 Mailbox Bracket For Type 1 multi and any double mount (use 2)	 NIGP: 45057253002 Bracket Extension Use 1 for a medium Mailbox Use 2 for a Large Mailbox	 NIGP: 45057258027 Part "B" Angle Bracket For Type 3 single and double
 NIGP: 80130598701 Wedge for Type 2	 NIGP: 45057250255 Plate Washer for Architecural and XL Mailboxes	 NIGP: 45057541653 Type 3 double mailbox bracket	 NIGP: 55083571053 Type 4 Mailbox Wedge
 NIGP: 55083571004 Type 4 Mailbox Socket	 NIGP: 80130238407 Type 2 Wedge Anchor	 NIGP: 45057259009 Wedge for Type 1 V-wing Socket	 NIGP: 45057256500 V-wing Socket for Type 1 Foundation

NIGP #	OBJECT MARKERS AND CONFORMABLE SHEETING
55008311759	Type 2 OM 4"x4" (3 Needed) for Type 3 Wing Channel Post
55008312906	Type 2 OM 6"x12" (1 needed) for Type 3 Wing Channel Post
80149872006	12" Conformable Reflective Yellow Sheeting for Flexible Posts

NOTES:

- Type 2 object marker in accordance with Traffic Engineering Standard Delineators & Object Markers.
- A light weight receptacle for newspaper delivery can be attached to mailbox posts if the receptacle does not touch the mailbox, present a hazard to traffic or delivery of the mail, extend beyond the front of the mailbox, or display advertising, except the publication title.

BID CODES FOR CONTRACTS

MB-(X) ASSM TY (XXX) (X)

Type of Mailbox _____

S = Single
D = Double
M = Multiple
MP = Molded Plastic


Type of Post _____

WC = Winged Channel Post
RR = Recycled Rubber
TWW = Thin Walled White Tubing
TWG = Thin Walled Galvanized Tubing
TIM = Timber







Type of Foundation _____

Ty 1 = V-Loc
Ty 2 = Wedge Anchor Steel System
Ty 3 = Winged Channel post
Ty 4 = Wedge Anchor Plastic System
Ty 5 = 4 X 4 Post

SHEET 4 OF 4

 Texas Department of Transportation				<i>Maintenance Division Standard</i>	
NIGP PARTS LIST AND COMPATIBILITY					
MB(4)-21					
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY	
2/2005	3090	01	012	FM 3041	
6/2005	DIST	COUNTY		SHEET NO.	
11/2006	DAL	NAVARRO		74	

DATE: FILE:



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; Soft+Stop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MGBF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IT IS ACCEPTABLE TO INSTALL THE Soft+Stop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
 - DO NOT ATTACH THE Soft+Stop SYSTEM DIRECTLY TO A RIGID BARRIER.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE Soft+Stop SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTE: A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE: B PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

NOTE: C W-BEAM SPLICE LOCATED BETWEEN LINE POST(4) AND LINE POST(5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	Soft+Stop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	Soft+Stop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	Soft+Stop DOWNSTREAM W-BEAM RAIL (12GA) (25' - 0")
15205A	1	POST #0 - ANCHOR POST (6' - 5 3/8")
15203G	1	POST #1 - (SYTP) (4' - 9 1/2")
15000G	1	POST #2 - (SYTP) (6' - 0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6' - 0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	3/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B


Texas Department of Transportation
Design Division Standard

**TRINITY HIGHWAY
SOFTSTOP END TERMINAL
MASH - TL-3
SGT (10S) 31-16**

FILE: sgt10s3116	DW: TXDOT	CK: KM	DW: VP	CK: MB/VP
© TXDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
	DIST	COUNTY	SHEET NO.	
	DAL	NAVARRO	75	






DATE: FILE:

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE Soft+Stop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.





NOTES:
 1. ITEM (2) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (9) THRU LINE POST (2).
 2. DO NOT INSTALL A BLOCKOUT AT LINE POST (1).

NOTE: RECESSED HEX NUTS FACING TRAFFIC-SIDE SEE DETAIL (C)
 NOTE: SECURE THE (TSS) PANEL TO OUTSIDE OF RAIL 2 WITH THE PANEL ARROWS POINTING TOWARDS THE HEAD.




- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
 - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
 - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
 - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
 - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
 - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
 - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.


ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST - GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	3/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	3/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev- (D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.



NOTE: DELINEATION MARKER IN ACCORDANCE WITH TEXAS MUTCD.



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.


* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS

Texas Department of Transportation

MAX-TENSION END TERMINAL
MASH - TL-3
SGT (11S) 31-18

FILE: sg11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TXDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.	
DAL	NAVARRO		76	



DATE:
FILE:




- * NOTES:
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
o	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. * *
 * ITEM (P) 8" WOOD-BLOCKOUT
 * * ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.



SINGLE GUARDRAIL TERMINAL MSKT-MASH-TL-3 SGT (12S) 31-18






FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT SECT	JOB	HIGHWAY	
REVISIONS	3090	01	012	FM 3041
	DIST	COUNTY	SHEET NO.	
	DAL	NAVARRO		77

DATE:
FILE:



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CBO8
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WBO8
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/8"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GR17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81
SMALL HARDWARE			
o	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPlice BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563DH HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

Texas Department of Transportation
Design Division Standard


SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15) 31-20

FILE: sg153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT: 3090	SECT: 01	JOB: 012	HIGHWAY: FM 3041
REVISIONS	DIST: DAL	COUNTY: NAVARRO	SHEET NO. 78	

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS


CONDITION - 1
THIN HMAC SURFACES OR HMAC OVERLAY
WITH THICKNESS OF 2.5" OR LESS



** EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 2
OVERLAY OF EXISTING PAVEMENT
HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 3
NEW OR RECONSTRUCTED PAVEMENT
HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 4
NEW OR RECONSTRUCTED PAVEMENT
HMAC THICKNESS 5" OR GREATER

GENERAL NOTES







1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

(NOT TO SCALE)

					Design Division Standard
TAPERED EDGE DETAILS HMAC PAVEMENT					
TE (HMAC) - 11					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS			3090 01	012	FM 3041
DIST	COUNTY		SHEET NO.		
DAL	NAVARRO				79

DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS

Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet




Zone	Treatment Types Guidelines:
①	No treatment
②	CW 8-11 "Uneven Lanes" signs.
③	CW 8-9a Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.
④	CW8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge slope to that of the proferred Edge Condition I.
⑤	Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone-4 may be used after consideration of other applicable factors.

Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ([Cross-hatched])



- $E = ADT \times T$
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within the clear zone.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.


FACTORS CONSIDERED IN THE GUIDELINES:

- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

				Traffic Safety Division Standard	
<h2>TREATMENT FOR VARIOUS EDGE CONDITIONS</h2>					
FILE:	edgecon.dgn	DN:		CK:	
© TxDOT	August 2000	CONT	SECT	JOB	HIGHWAY
REVISIONS		3090 01	012	FM 3041	
03-01	08-01	DIST	COUNTY	SHEET NO.	
	9-21	DAL	Navarro	80	




@ IF BACKFILLED SLOPE IS LESS THAN 3:1, COVER WEDGE WITH APPROVED BACKFILL.

* SEE TYPICAL SECTION FOR DEPTH AND TYPE OF HMA.
 # NOTCH DEPTH SHALL NOT BE LESS THAN NOMINAL AGGREGATE SIZE.

NOTES:


1. THE ABOVE DETAILS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LANE WIDTH AND BE LAID MONOLITHICALLY WITH ADJOINING MAT. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED STRIKE-OFF DEVICE THAT WILL PROVIDE A UNIFORM SLOPE AND WILL NOT RESTRICT THE MAIN SCREED. CLEAN WEDGE PRIOR TO PLACEMENT OF TACK COAT. TACK COAT SHALL BE APPLIED UNIFORMLY TO THE IN-PLACE TAPER WITH A DISTRIBUTOR BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED. COMPACTION OF THE INITIAL TAPER SECTION WILL BE REQUIRED AS NEAR TO FINAL DENSITY AS POSSIBLE. ROLL ADJACENT MAT FROM HOT SIDE TO COLD.
2. THE TYPE OF DEVICE TO PRODUCE ABOVE REFERENCED DETAILS SHALL PROVIDE INITIAL COMPACTION EQUIVALENT TO LAYDOWN MACHINE, WITH FINAL DENSITY ADHERING TO NOTE 1, AND BE APPROVED BY THE ENGINEER.
3. HOT MIX MATERIAL AND PLACEMENT SHALL BE PAID FOR UNDER THE PERTINENT ITEM. ANY ADDITIONAL SURFACE PREPARATION, TACK COAT, TACK COAT PLACEMENT, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS TO PRODUCE TAPERED EDGE AND JOINTS AS DESCRIBED ABOVE SHALL BE CONSIDERED SUBSIDIARY TO THE HOT MIX ITEM.
4. THE TAPERED JOINT DETAIL IS NOT INTENDED FOR USE ON 2 WAY 2 LANE ROADBED CENTERLINE WITH LESS THAN 22' OVERALL WIDTH.
5. FULL PAVING OF ALL LANES AND SHOULDERS BY THE END OF EACH DAY PRODUCTION WILL NOT REQUIRE A TAPERED JOINT.


Texas Department of Transportation

HOT MIX EDGE AND LONGITUDINAL JOINT DETAILS
DALLAS DISTRICT STANDARD
LJD(1-1)-07

FED. RD. DIV. NO.	PROJECT NUMBER	SHEET NUMBER
18		81
STATE	DISTRICT	COUNTY
TEXAS	DALLAS	DALLAS
CONTROL	SECTION	HIGHWAY NUMBER
0000	00	000 IH/SH/FM

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





TREE REMOVAL

STEP 1:
CUT 1/3 WAY THROUGH BOTTOM OF LIMB 8" TO 12" ABOVE MAIN STEM (OR TRUNK).


STEP 2:
REMOVE LIMB 4" TO 6" BEYOND THE FIRST CUT

STEP 3:
REMOVE STUB WITH A SMOOTH CUT SO THAT TRACE COLLAR OF THE REMOVED LIMB PROTRUDES APPROXIMATELY 1/2" FROM THE MAIN STEM




REMOVE ALL LIMBS ON PAVEMENT SIDE TO 18' AS MEASURED FROM THE EDGE OF PAVEMENT. TREES MAY OR MAY NOT OVERHANG PVMT.


TREE TRIMMING



STEPS 1, 2 AND 3 APPLY WHEN REMOVING LIMBS 2" IN DIAMETER OR LARGER.



REMOVE ALL LIMBS ON PAVEMENT SIDE TO 18' ABOVE SURROUNDING NATURAL GROUND WHEN TREE IS AT R.O.W.



BRUSH REMOVAL


GENERAL NOTES:

TREE TRIMMING

1. TRIM AND REMOVE ALL TREE LIMBS ON THE PAVEMENT SIDE OF THE TRUNK 18' ABOVE THE PAVEMENT OR BRIDGE DECK ELEVATION, OVER HANGING THE ROADWAY OR NOT, UNLESS OTHERWISE SHOWN ON THE PLANS.
2. TRIM AND REMOVE ALL TREE LIMBS BETWEEN THE TRUNK AND R.O.W. LINE 14' ABOVE NATURAL GROUND, TERRAIN OR OTHER STRUCTURE ELEVATION, UNLESS OTHERWISE SHOWN ON THE PLANS.

TREE REMOVAL

3. FOR TREES MARKED FOR REMOVAL, THE DIAMETER OF TREES ARE DETERMINED BY MEASUREMENT OF THE TRUNK CIRCUMFERENCE 3' ABOVE THE GROUND. TREES WITH TRUNKS OF LESS THAN 4" DIAMETER ARE CONSIDERED TO BE BRUSH. TREES WITH MULTIPLE TRUNKS AT THE POINT OF MEASUREMENT ARE MEASURED AND PAID FOR SEPARATELY.
4. MEASUREMENTS FOR PAYMENT ARE PRESENTED IN TABLE 1: RANGE FOR PAY ITEMS.



BRUSH REMOVAL UNDER BRIDGE AND IN CHANNEL

TABLE 1 TREE TRUNK SIZE FOR TREE REMOVAL PAYMENT				
PAY ITEM	RANGE FOR PAY ITEMS			
	TRUNK DIAMETER *		TRUNK CIRCUMFERENCE	
	LOWER LIMIT IS GREATER THAN	UPPER LIMIT IS LESS THAN OR EQUAL TO	LOWER LIMIT IS GREATER THAN	UPPER LIMIT IS LESS THAN OR EQUAL TO
752 6005	4	12	12 1/2	37 1/2
752 6006	12	18	37 1/2	56 1/2
752 6007	18	24	56 1/2	75 1/2
752 6008	24	30	75 1/2	94
752 6009	30	36	94	113
752 6010	36	42	113	132
752 6011	42	48	132	151
752 6012	48	60	151	188 1/2
752 6013	60	72	188 1/2	226
752 6019	72	84	226	264
	84	GREATER THAN 84	264	NOT APPLICABLE

*SEE GENERAL NOTE #3.

Maintenance Division Standard


TREE AND BRUSH REMOVAL

TRB-15(1) (DAL)

FILE:	DN: JEO	CK: LJB	DW: JEO	CK:
© TxDOT MARCH 2017	CONT	SECT	JOB	HIGHWAY
REVISED TO CLARIFY WORK AT THE R.O.W. AND GENERAL NOTE 1.	3090	01	012	FM 3041
	DIST	COUNTY	SHEET NO.	
	DAL	Navarro	82	


CK: DW: CK: DN:

DATE: 1/27/23 1:09:52 PM
 FILE: c:\pwworking\morgane\15\craig_parker\10463961\1\DRAINAGE AREA MAP.dwg



- LEGEND**
- DRAINAGE AREA BOUNDARY
 - DRAINAGE AREA ID & SIZE
 - FLOW DIRECTION

SCALE 1:20000



Morgan Neill, P.E. 2/1/2023



FM 3041
DRAINAGE AREA MAP

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	83	

DW: CK: DW: CK: DW: CK:

DRAINAGE AREA RUNOFF COMPUTATIONS

DRAINAGE AREA	HYDROLOGIC METHOD	TIME OF CONCENTRATION METHOD	RURAL WATERSHED RUNOFF COEFFICIENT COMPONENTS				TOTAL RUNOFF COEFFICIENT "C"	DRAINAGE AREA SIZE "A" (AC)	TIME OF CONCENTRATION "Tc" (MIN)	INTENSITY "I" (IN/HR)		DRAINAGE AREA DISCHARGE "Q" (CFS)	
			CR	CI	CV	CS				10-YR	100-YR	10-YR	100-YR
1	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	29.5	57	2.79	4.32	27.19	42.05
3	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	10.5	21	5.14	7.90	17.8	27.38
4	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	55.0	63	2.61	4.04	47.35	73.27
5	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	5.5	12	6.72	10.31	12.19	18.70
6	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	19.5	31	4.12	6.35	26.53	40.88
7	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	95.0	43	3.36	5.19	105.49	162.85
8	RATIONAL	NRCS	0.1	0.08	0.07	0.08	0.33	26.0	17	5.72	8.80	49.12	75.48

NOTES:


1. TXDOT HYDRAULIC DESIGN MANUAL REVISED SEPT. 2019 WAS UTILIZED FOR THE DESIGN OF THIS PROJECT.
2. DESIGN STORM FREQUENCY FOR RUNOFF COMPUTATIONS IS 10-YR WITH 100-YR PERFORMED AS A CHECK.

RUNOFF COMPUTATIONS (NRCS METHOD)

DA ID	Culvert Station	Area (Sq Mi)	Tc (Hr)	Lag Time (Hr)	Lag Time (min)	Base RCN	Adjusted RCN	24-Hour Precipitation (in)						Peak Discharge (cfs @ 1)					
								2-yr	5-yr	10-yr	25-yr	50-yr	100-yr	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
2	43+55.65	0.97	1.70	1.02	61	84	80	3.66	5.07	6.20	7.84	9.18	10.70	317	554	753	1253	4739	1495

NOTES:

1. NRCS HYDROGRACPH METHOD WAS MODELED IN HEC-HMS VERSION 4.10.
2. PRECIPITATION DATA WAS OBTAINED FROM NOAA ATLAS -14 FOR THIS PROJECT LOCATION.
3. SOILS DATA WAS OBTAINED FROM NRCS WEB SOIL SURVEY UTILITY.
4. LAND USE DATA WAS OBTAINED FROM AERIAL PHOTOGRAMMETRY.
5. RUNOFF CURVE NUMBER (RCN) WAS BASED ON TXDOT HYDRAULIC DESIGN MANUAL, TABLE 4-20 AND FIGURE 4-22.
6. LAG TIME CALCULATIONS BASED ON $LAGTIME = 0.6 Tc$. Tc IS TIME OF CONCENTRATION.



Morgan Neill, P.E. 2/11/2023

Texas Department of Transportation

FM 3041


RUNOFF COMPUTATIONS

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	84	

DATE: 1/31/2023 1:10:09 PM
 FILE: c:\txdot\ipw_onlinetx\dot5\craig_parker\0463961\CULVERT_CALCULATIONS.dgn

CK:
DW:
CK:
DW:





LEGEND
 DELINEATOR
 FLOW DIRECTION
 PROPOSED PAVEMENT



HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	27.19	6.46	396.53	394.07
100	42.05	7.24	397.21	394.10

ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	102
432-6001	RIPRAP (CONC) (4 IN)	CY	0.756
432-6026	RIPRAP (STONE COMMON)(DRY)(18 IN)	CY	33.5
464-6010	RC PIPE (CL III)(48 IN)	LF	111
465-6162	INLET (COMPL)(PAZD)(FG)(5FTX5FT-4FTX4FT)	EA	1
466-6136	HEADWALL (CH - PW - S) (DIA=48 IN)	EA	1
496-6006	REMOV STR (HEADWALL)	EA	1
496-6007	REMOV STR (PIPE)	LF	116
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4



Morgan Neill, P.E. 2/1/2023






FM 3041
CULVERT LAYOUT NO. 1
STA. 35+34.92

SHEET 1 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		86

DATE: 1/31/2023 1:10:27 PM
 FILE: c:\tdot\ipw\onlinet\tdot5\craig_parker\10463961\Culvert_1_LAYOUT.dgn

CK
DW
CK
DW




- LEGEND**
- DELINEATOR
 - FLOW DIRECTION
 - PROPOSED PAVEMENT

SHORING	DIMENSIONS (FT)				QUANTITY (SF)
	A	B	C	D	
1	2.18	10.85	27.75	7.60	263.96
2	2.83	9.55	18.00	7.60	186.60
3	2.83	9.55	18.00	7.60	186.60
4	2.18	10.85	27.75	7.60	263.96
TOTAL					901.12

RIPRAP (STONE COMMON DRY)
(18" (36 IN) THICKNESS (34.08 CY)

ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	94
403-6001	TEMPORARY SPL SHORING	SF	901.12
432-6026	RIPRAP (STONE COMMON)(DRY)(18IN)	CY	81.45
464-6013	RC PIPE (CL III)(66 IN)	LF	330
466-6139	HEADWALL (CH - PW - S) (DIA=66 IN)	EA	2
496-6006	REMOV STR (HEADWALL)	EA	2
496-6007	REMOV STR (PIPE)	LF	276
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4

HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	753	13.70	383.31	374.18
100	1495	20.54	393.89	374.54



Morgan Neill, P.E. 2/1/2023

FM 3041


CULVERT LAYOUT NO. 2

STA. 43+55.65

SHEET 2 OF 8

COVT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	NMARRCO		87



DATE: 1/31/2023 1:10:40 PM
FILE: c:\tdot\ipw\onlinetx\d05\craig_parker\d0463961\Culvert 2_LAYOUT.dgn



- LEGEND**
- DELINEATOR
 - FLOW DIRECTION
 - PROPOSED PAVEMENT

HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q CFS	V FPS	HW EL. FT	TW EL. FT
10	17.8	10.83	402.37	398.36
100	27.38	12.01	404.09	398.41

ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	57
432-6001	RIPRAP (CONC) (4 IN)	CY	1.58
432-6026	RIPRAP (STONE COMMON)(DRY) (18 IN)	CY	11.17
464-6005	RC PIPE (CL III)(24 IN)	LF	68
465-6158	INLET (COMPL)(PAZD)(FG)(3FTX3FT-3FTX3FT)	EA	1
466-6097	HEADWALL (CH - PW - 0) (DIA=24")	EA	1
496-6006	REMOV STR (HEADWALL)	EA	1
496-6007	REMOV STR (PIPE)	LF	59
658-6100	INSTL OM ASSM (OM-22)(WFLX)GND(BI)	EA	4



Morgan Neill, P.E. 2/1/2023



FM 3041
CULVERT LAYOUT NO. 3
STA 57+10.18


SHEET 3 OF 8

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	88	

CK:
DW:
CK:
DW:





- LEGEND**
- DELINEATOR
 - FLOW DIRECTION
 - PROPOSED PAVEMENT



ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	38.5
432-6026	RIPRAP (STONE COMMON)(DRY) (18 IN)	CY	43.5
464-6008	RC PIPE (CL III)(36 IN)	LF	58
466-6101	HEADWALL (CH - PW - 0) (DIA=36")	EA	2
496-6006	REMOV STR (HEADWALL)	EA	2
496-6007	REMOV STR (PIPE)	LF	48
658-6100	IN STL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4

HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	47.35	8.36	343.79	340.04
100	73.27	10.94	346.22	340.12



Morgan Neill, P.E. 2/1/2023




FM 3041
CULVERT LAYOUT NO. 4
STA 97+35.4

SHEET 4 OF 8

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		89

DATE: 1/31/2023 1:11:06 PM
FILE: c:\tdot\pw\onlinet\tdot5\craig_parker\0463961\Culvert_4_LAYOUT.dgn



CK:
DW:
CK:
DW:



- LEGEND
- DELINEATOR
 - FLOW DIRECTION
 - PROPOSED PAVEMENT

ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	58
432-6001	RIPRAP (CONC) (4 IN)	CY	1.0
432-6026	RIPRAP (STONE COMMON)(DRY) (18 IN)	CY	10.80
464-6005	RC PIPE (CL III)(24 IN)	LF	76
465-6158	INLET (COMPL)(PAZD)(FG)(3FTX3FT-3FTX3FT)	EA	1
466-6097	HEADWALL (CH - PW - 0) (DIA=24*)	EA	1
496-6006	REMOV STR (HEADWALL)	EA	1
496-6007	REMOV STR (PIPE)	LF	80.0
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4

HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	12.19	15.50	362.36	354.37
100	18.70	17.27	363.16	354.41



Morgan Neill, P.E. 2/1/2023



FM 3041
CULVERT LAYOUT NO. 5
STA 107+24.51

SHEET 5 OF 8


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	90	

DATE: 1/31/2023 1:11:22 PM
FILE: c:\tdot\ipw\onlinet\tdot5\craig_parker\0463961\Culvert_5_LAYOUT.dgn

CK: DW: CK: DW:





- LEGEND
- DELINEATOR
 - FLOW DIRECTION
 - PROPOSED PAVEMENT



ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	87
432-6001	RIPRAP (CONC) (4 IN)	CY	1.02
432-6026	RIPRAP (STONE COMMON)(DRY) (18 IN)	CY	21.5
464-6009	RC PIPE (CL III)(42 IN)	LF	100
465-6162	INLET (COMPL)(PAZD)(FG)(5FTX5FT-4FTX4FT)	EA	1
466-6135	HEADWALL (CH - PW - S) (DIA=42")	EA	1
496-6006	REMOV STR (HEADWALL)	EA	1
496-6007	REMOV STR (PIPE)	LF	100
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4

HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	26.53	6.38	366.68	362.27
100	40.88	7.69	367.38	362.31



Morgan Neill, P.E. 2/1/2023



FM 3041
CULVERT LAYOUT NO. 6
STA 117+60.45

SHEET 6 OF 8

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		91

DATE: 1/31/2023 1:11:37 PM
FILE: c:\tdot\ipw\onlinet\tdot5\craig_parker\0463961\Culvert 6_LAYOUT.dgn



CK: DW: CK: DW:



LEGEND
 DELINEATOR
 FLOW DIRECTION
 PROPOSED PAVEMENT

ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	36.7
432-6026	RIPRAP (STONE COMMON)(DRY) (18 IN)	CY	84.53
464-6008	RC PIPE (CL III)(36 IN)	LF	228
466-6101	HEADWALL (CH - PW - 0) (DIA=36")	EA	2
496-6006	REMOV STR (HEADWALL)	EA	2
496-6007	REMOV STR (PIPE)	LF	163.2
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4

HYDRAULIC DATA				
PROPOSED STRUCTURE				
YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	105.49	8.08	336.41	334.24
100	162.85	8.94	336.70	334.29



STATE OF TEXAS
 MORGAN A. NEILL
 115916
 LICENSED PROFESSIONAL ENGINEER
 Morgan Neill, P.E. 2/1/2023


Texas Department of Transportation

FM 3041
 CULVERT LAYOUT NO. 7
 STA 142+29.94


SHEET 7 OF 8			
CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		92

DATE: 1/31/2023 1:11:51 PM
 FILE: c:\tdot\pw\onlinet\tdot5\craig_parker\0463961\Culvert 7_LAYOUT.dgn

CK: DW: CK: DW: CK: DW: CK: DW:



LEGEND
X DELINEATOR
→ FLOW DIRECTION
— PROPOSED PAVEMENT




ESTIMATED QUANTITIES


ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	39.5
432-6026	RIPRAP (STONE COMMON)(DRY) (18 IN)	CY	70.1
464-6013	RC PIPE (CL III)(66 IN)	LF	57
466-6106	HEADWALL (CH - PW - 0) (DIA=66")	EA	2
496-6006	REMOV STR (HEADWALL)	EA	2
496-6007	REMOV STR (PIPE)	LF	39.2
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4

HYDRAULIC DATA
PROPOSED STRUCTURE

YEAR	Q	V	HW EL.	TW EL.
	CFS	FPS	FT	FT
10	49.12	6.79	335.55	332.95
100	75.48	7.64	336.66	333.01



CULVERT # 8
STA 147+57.96
EXIST.: 66" X 39.2' RCP W/ HEADWALLS TO BE REMOVED
PROP.: 66" X 57' RCP W/ CH-PW-0 STANDARDS: CH-PW-0



Morgan Neill, P.E. 2/11/2023



FM 3041
CULVERT LAYOUT NO. 8
STA 147+57.96

SHEET 8 OF 8


COUNT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	93	

DATE: 1/31/2023 1:12:05 PM
FILE: c:\tdot\p\online\tdot5\craig_parker\0463961\Culvert 8_LAYOUT.dgn


TABLE OF VARIABLE DIMENSIONS AND QUANTITIES FOR ONE HEADWALL (5)

Slope	Dia of Pipe (D)	Values for One Pipe		Values To Be Added for Each Add'l Pipe			
		W	Reinf (Lbs) (1)	Conc (CY) (2)	W	Reinf (Lbs) (1)	Conc (CY) (2)
2:1	12"	9' - 0"	122	1.1	1' - 9"	15	0.2
	15"	10' - 3"	136	1.3	2' - 2"	16	0.2
	18"	11' - 6"	163	1.5	2' - 8"	19	0.3
	21"	12' - 9"	200	1.8	3' - 1"	31	0.4
	24"	14' - 0"	217	2.1	3' - 7"	34	0.4
	27"	15' - 3"	254	2.4	3' - 11"	37	0.5
	30"	16' - 6"	272	2.7	4' - 4"	40	0.6
	33"	17' - 9"	314	3.1	4' - 8"	43	0.6
	36"	19' - 0"	371	3.9	5' - 1"	46	0.8
	42"	21' - 6"	442	4.9	5' - 10"	52	1.0
	48"	25' - 0"	569	6.4	6' - 7"	59	1.3
	54"	27' - 6"	701	7.5	7' - 6"	82	1.6
	60"	30' - 0"	794	8.8	8' - 3"	90	1.8
	66"	32' - 6"	894	10.2	8' - 9"	96	2.0
72"	35' - 0"	1,055	11.7	9' - 4"	103	2.3	
3:1	12"	13' - 0"	175	1.6	1' - 9"	14	0.2
	15"	14' - 9"	193	1.9	2' - 2"	17	0.2
	18"	16' - 6"	228	2.2	2' - 8"	19	0.3
	21"	18' - 3"	299	2.6	3' - 1"	31	0.4
	24"	20' - 0"	323	3.0	3' - 7"	33	0.4
	27"	21' - 9"	371	3.5	3' - 11"	37	0.5
	30"	23' - 6"	415	4.0	4' - 4"	40	0.5
	33"	25' - 3"	469	4.6	4' - 8"	43	0.6
	36"	27' - 0"	556	5.7	5' - 1"	46	0.8
	42"	30' - 6"	675	7.1	5' - 10"	52	1.0
	48"	35' - 6"	837	9.2	6' - 7"	59	1.3
	54"	39' - 0"	1,015	11.0	7' - 6"	84	1.6
	60"	42' - 6"	1,171	12.9	8' - 3"	91	1.8
	66"	46' - 0"	1,298	14.9	8' - 9"	98	2.0
72"	49' - 6"	1,561	17.1	9' - 4"	103	2.3	
4:1	12"	17' - 0"	229	2.0	1' - 9"	15	0.2
	15"	19' - 3"	266	2.4	2' - 2"	17	0.2
	18"	21' - 6"	308	2.9	2' - 8"	19	0.3
	21"	23' - 9"	382	3.5	3' - 1"	31	0.3
	24"	26' - 0"	430	3.9	3' - 7"	34	0.4
	27"	28' - 3"	486	4.7	3' - 11"	37	0.5
	30"	30' - 6"	539	5.2	4' - 4"	40	0.6
	33"	32' - 9"	603	6.0	4' - 8"	42	0.6
	36"	35' - 0"	738	7.5	5' - 1"	47	0.8
	42"	39' - 6"	881	9.3	5' - 10"	52	1.0
	48"	46' - 0"	1,102	12.1	6' - 7"	61	1.3
	54"	50' - 6"	1,364	14.4	7' - 6"	84	1.6
	60"	55' - 0"	1,547	16.9	8' - 3"	91	1.8
	66"	59' - 6"	1,741	19.5	8' - 9"	98	2.0
72"	64' - 0"	2,077	22.4	9' - 4"	102	2.3	
6:1	12"	25' - 0"	336	3.0	1' - 9"	14	0.2
	15"	28' - 3"	384	3.6	2' - 2"	17	0.2
	18"	31' - 6"	452	4.2	2' - 8"	19	0.3
	21"	34' - 9"	581	5.1	3' - 1"	31	0.4
	24"	38' - 0"	644	5.8	3' - 7"	34	0.4
	27"	41' - 3"	737	6.9	3' - 11"	37	0.5
	30"	44' - 6"	807	7.7	4' - 4"	39	0.6
	33"	47' - 9"	912	8.9	4' - 8"	44	0.6
	36"	51' - 0"	1,108	11.0	5' - 1"	48	0.8
	42"	57' - 6"	1,318	13.7	5' - 10"	54	1.0
	48"	67' - 0"	1,682	17.9	6' - 7"	59	1.3
	54"	73' - 6"	2,072	21.3	7' - 6"	83	1.6
	60"	80' - 0"	2,351	24.9	8' - 3"	89	1.8
	66"	86' - 6"	2,643	28.9	8' - 9"	96	2.0
72"	93' - 0"	3,121	33.1	9' - 4"	101	2.3	


DATE: FILE:




- Total quantities include one 3'-1" lap for bars over 60' in length.
- Quantities shown are for concrete pipe and will increase slightly for metal pipe installations.
- Indicated slope is perpendicular to centerline pipe or pipes.
- For vehicle safety, construct curbs no more than 3" above finished grade. Reduce curb heights, if necessary, to meet these requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- Dimensions shown are usual and maximum.
- Quantities shown are for one structure end only (one headwall).



ELEVATION



PLAN OF NON-SKEWED PIPES



SECTION AT CENTER OF PIPE

TABLE OF CONSTANT DIMENSIONS

Dia of Pipe (D)	G	K (5)	H	T	E
12"	0' - 9"	1' - 0"	2' - 8"	0' - 9"	1' - 9"
15"	0' - 11"	1' - 0"	2' - 11"	0' - 9"	1' - 9"
18"	1' - 2"	1' - 0"	3' - 2"	0' - 9"	1' - 9"
21"	1' - 4"	1' - 0"	3' - 5"	0' - 9"	2' - 0"
24"	1' - 7"	1' - 0"	3' - 8"	0' - 9"	2' - 0"
27"	1' - 8"	1' - 0"	3' - 11"	0' - 9"	2' - 3"
30"	1' - 10"	1' - 0"	4' - 2"	0' - 9"	2' - 3"
33"	1' - 11"	1' - 0"	4' - 5"	0' - 9"	2' - 6"
36"	2' - 1"	1' - 0"	4' - 8"	1' - 0"	2' - 6"
42"	2' - 4"	1' - 0"	5' - 2"	1' - 0"	2' - 9"
48"	2' - 7"	1' - 3"	5' - 11"	1' - 0"	3' - 0"
54"	3' - 0"	1' - 3"	6' - 5"	1' - 0"	3' - 3"
60"	3' - 3"	1' - 3"	6' - 11"	1' - 0"	3' - 6"
66"	3' - 3"	1' - 3"	7' - 5"	1' - 0"	3' - 9"
72"	3' - 4"	1' - 3"	7' - 11"	1' - 0"	4' - 0"

TABLE OF REINFORCING STEEL (6)

Bar	Size	Spa	No.
A1	#5	~	2
A2	#5	1' - 6"	~
E	#5	~	2
F	#5	1' - 0"	~

MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide Class C concrete (f_c = 3,600 psi).


GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications.
Do not mount bridge rails of any type directly to these culvert headwalls.
This standard may not be used for wall heights, H, exceeding the values shown.

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing dimensions are out-to-out of bars.

		Bridge Division Standard	
CONCRETE HEADWALLS WITH PARALLEL WINGS FOR NON-SKEWED PIPE CULVERTS			
CH-PW-0			
FILE: chpw0ste-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT	SECT	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	94	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME




INTERMEDIATE TOEWALL


PLAN




ELEVATION




SEC A-A




SEC B-B
(No drain)



SEC B-B
(Shoulder drain integral with riprap)



SEC D-D
(Shoulder drain)




RIPRAP DETAIL AT COLUMNS


(As directed by the Engineer)

- 1 When riprap is shown extended around header on layout, extend slab and toewall as shown and eliminate 4" curb.
- 2 Limits and configuration of drains and depressions are as shown elsewhere in plans or as directed by the Engineer.
- 3 Location of shoulder drain must consider limitations imposed by rail transition. Do not locate shoulder drains at expansion joints between approach slab and concrete pavement.
- 4 See details elsewhere in plans for installation of guard fence posts through concrete riprap.
- 5 Provide intermediate toewall only when designated elsewhere in the plans or included in the specifications.
- 6 Provide lower level of 2" Dia weep holes at 10' c-c backed by 1 CF packet of gravel and galvanized hardware cloth at all locations unless directed by the Engineer to eliminate.
- 7 Use wider or other drain configurations if shown elsewhere in plans or if directed by the Engineer.
- 8 Wall extension may be reduced or modified if approved by the Engineer. Increase wall extension to 1'-6" whenever the optional intermediate toewall is called for in the plans.
- 9 Top of cap to top of riprap dimension varies as directed by the Engineer. Should be 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.
- 10 #5 bars shown are required even when synthetic fiber reinforcing option is selected.
- 11 Provide sealing option for joint between the face of cap and riprap as designated by the Engineer or as shown elsewhere on plans.
- 12 Flashing (shown in Cap Option A) may be used at wingwall in addition to Exp Jt Mat'l if shown on plans or directed by the Engineer.
- 13 Provide #3 reinforcing bars at 18" Spa c-c. Provide Welded Wire Reinforcement (WWR) as 6x6-D2.9xD2.9 or D3xD3. Combinations of WWR and reinforcing bars may be used if both are permitted. Use lap splices of a minimum 6 inches, measured from the transverse wire of WWR, and the ends of reinforcing bars.
- 14 If granular material is specified, provide upper level of 2" Dia weep holes at 10' c-c backed by galvanized hardware cloth.
- 15 8" x 18 Gage Galv Sheet Metal
- 16 Provide WWR or #3 bars, with 1'-0" extension into slope.
- 17 WWR or reinforcing steel is continuous through riprap construction joints. Provide WWR or reinforcing steel that extends 1'-1" minimum into adjacent riprap on each side of construction joint even if synthetic reinforcing fiber is utilized.


FOR CONTRACTOR'S INFORMATION ONLY:
 5" of RR8 = 0.015 CY/SF
 4" of RR9 = 0.012 CY/SF
 #3 Reinf at 18" c-c = 0.501 Lbs/SF
 6x6-D3xD3 = 0.408 Lbs/SF



SHOWING KEYWAY OPTION



SECTIONS THRU RIPRAP AT CAP




REINFORCEMENT DETAILS

See General Notes for optional synthetic fiber reinforcement.


GENERAL NOTES:
 Provide Class "B" concrete (f_c = 2,000 psi) unless noted elsewhere in plans.
 Provide Grade 60 reinforcing steel.
 Provide deformed welded wire reinforcement (WWR) meeting ASTM A1064, unless otherwise shown.
 Provide reinforcing bars, deformed WWR, or any suitable combination of both types for riprap reinforcing, unless specified elsewhere in the plans.
 Optionally synthetic fibers may be used if approved by the Engineer. Provide synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) in lieu of steel reinforcing in riprap concrete. Install construction joints or grooved joints extending the full slant slope height at intervals of approximately 20 feet unless otherwise directed by the Engineer.
 Hardware cloth, loose grade stone behind weep holes, flashing, or other sealing material are subsidiary to the bid item "Riprap". See Layout for limits of riprap.
 RR8 is to be used on stream crossings.
 RR9 is to be used on other embankments.

		Bridge Division Standard	
CONCRETE RIPRAP AND SHOULDER DRAINS EMBANKMENTS AT BRIDGE ENDS (TYPES RR8 & RR9)			
CRR			
FILE: crstdet1-19.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT April 2019	CONT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	96	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




ELEVATION VIEW




ELEVATION VIEW



ELEVATION VIEW




ELEVATION VIEW



PLAN VIEW
NO OPENINGS


STYLE 'SL'



PLAN VIEW

32" DIA CAST-IN RING & COVER


STYLE 'RC'



PLAN VIEW

32" DIA CAST-IN RING & GRATE

STYLE 'RG'



PLAN VIEW

CAST-IN FRAME & GRATE

STYLE 'FG'

① Matches inside face of wall of precast base or riser below inlet.

FABRICATION NOTES:

1. Provide Class "H" concrete in accordance with Item 421 and having a minimum compressive strength of 5,000 psi.
2. Provide Grade 60 reinforcing steel or equivalent area of WWR.
3. Provide clear cover of 3/4" to reinforcing from bottom of slab for structural reinforcement. Place short span reinforcing closest to surface.
4. No substitution is allowed for diagonal #4 bars around openings.
5. Design tongue and groove joints for full closure on both shoulders. Minimum spigot depth is 3/4".
6. Provide lifting devices in conformance with Manufacturer's recommendations.


INSTALLATION NOTES:

1. PAZD is for use in ditches and medians outside of the horizontal clearance (clear zone). Precast Area Zone Drain is not intended for direct traffic and may not be placed in roadway.
2. Seal tongue and groove joints with preformed or bulk mastic in conformance with Manufacturer's recommendations. Tongue and groove joints may be grouted no more than 1" between each section, or 1/2 the joint depth, whichever is greater.
3. Do not grout rubber gasket joints without Manufacturer's recommendation.

GENERAL NOTES:

1. Designed according to ASTM C913.
2. Payment for inlet is per Item 465, "Junction Boxes, Manholes, and Inlets" by type, style, size, and opening size (when applicable).

Construct cast-in-place reinforced concrete apron when shown elsewhere in plans. Use Class "A" concrete. Apron is subsidiary to PAZD. Apron is 1'-6" Min width around precast zone drain.



DETAIL "A"

(Reinforcing not shown for clarity)

When an apron is to be cast around PAZD, use detail above to create an apron ledge on all 4 sides.

Style	Size (X x Y)	A x A *	B x B	Short Span Reinf Steel Area	Long Span Reinf Steel Area
SL	3'x3'	n/a	n/a	0.37 in ² /ft	0.37 in ² /ft
RC, RG	3'x3'	32" Dia	1.5'x1.5'	0.37 in ² /ft	0.37 in ² /ft
FG	3'x3'	3'x3'	1.5'x1.5'	0.37 in ² /ft	0.37 in ² /ft
SL	4'x4'	n/a	n/a	0.34 in ² /ft	0.34 in ² /ft
RC, RG	4'x4'	32" Dia	2'x2'	0.34 in ² /ft	0.34 in ² /ft
FG	4'x4'	3'x3'	2'x2'	0.34 in ² /ft	0.34 in ² /ft
FG	4'x4'	4'x4'	2'x2'	0.34 in ² /ft	0.34 in ² /ft
SL	5'x5'	n/a	n/a	0.43 in ² /ft	0.43 in ² /ft
RC, RG	5'x5'	32" Dia	2.5'x2.5'	0.68 in ² /ft	0.68 in ² /ft
FG	5'x5'	3'x3'	2.5'x2.5'	0.43 in ² /ft	0.43 in ² /ft
FG	5'x5'	4'x4'	2.5'x2.5'	0.43 in ² /ft	0.43 in ² /ft

* Nominal frame/grate or ring/cover size.

Bridge Division Standard

PRECAST AREA ZONE DRAIN






PAZD

FILE: prest08-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
DIST	COUNTY	SHEET NO.		
DAL	Navarro			97

DATE: 2022/09/07
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/13
FILE: DOCUMENT NAME



Cover dimensions are clear dimensions, unless noted otherwise.

FABRICATION NOTES:

1. Provide Class "H" concrete in accordance with Item 421 and having a minimum compressive strength of 5,000 psi.
2. Provide Grade 60 reinforcing steel or equivalent area of WWR.
3. Provide typical clear cover of 1 1/2" to reinforcing steel at interior or exterior walls.
4. Walls or slabs with a thickness of 8" or greater require shrinkage and temperature reinforcing steel. Provide steel area = 0.11 in²/ft each way.
5. No substitution is allowed for vertical and horizontal #4 bars in corners.
6. Manufacture base and risers to nearest 3" increment.
7. Design tongue and groove joints for full closure on both shoulders. Minimum spigot depth is 3/4".
8. Provide lifting devices in conformance with Manufacturer's recommendations.
9. See sheet PDD for sizes, dimensions, and reinforcing steel not shown.

INSTALLATION NOTES:

1. If required elsewhere. Inverts (benching) to be provided by Contractor. Concrete or mortar used for invert is subsidiary to specified inlet or manhole.
2. Seal tongue and groove joints with preformed or bulk mastic in conformance with Manufacturer's recommendations. Tongue and groove joints may be grouted no more than 1" between each section, or 1/2 the joint depth, whichever is greater.
3. Do not grout rubber gasket joints without Manufacturer's recommendation.
4. For rigid pipe, cut hole in thin wall panel (KO) 4" Max, 2" Min larger than pipe OD.
5. For flexible pipe, consult boot/seal Manufacturer's specification for placement tolerance and hole size. Center pipe in hole and install boot/seal per Manufacturer's specification.

GENERAL NOTES:

1. Precast Base consists of base slab, base unit, risers (as required), reducing slab (as required), and reduced risers (as required). See sheet PDD for sizes.
2. Designed according to ASTM C913.
3. Payment for precast base is subsidiary to the specified inlet, per Item 465, "Junction Boxes, Manholes, and Inlets."

HL93 LOADING



PRECAST BASE

PB

FILE: prest01-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM	3041
DIST	COUNTY	SHEET NO.		
DAL	Navarro	98		

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME

Size	MAXDEPTH = 15 ft. to top of BASE SLAB											MAXDEPTH = 25 ft. to top of BASE SLAB											Min Height (See Gen Note 3)	Max HOLE DIA (See Fab Note 2)	Max KO DIA (See Fab Note 2)
	Base Slab			Base Unit or Riser Walls			Below Grade Slab (w/PJB) Reducing Slab (w/PB)					Base Slab			Base Unit or Riser Walls			Below Grade Slab (w/PJB) Reducing Slab (w/PB)							
	Short Span Reinf Steel Area	Long Span Reinf Steel Area	Thickness	Short Span Reinf Steel Area	Long Span Reinf Steel Area	Thickness	Reduced Riser Size	Short Span Reinf Steel Area	Long Span Reinf Steel Area	Thickness	Short Span Reinf Steel Area	Long Span Reinf Steel Area	Thickness	Short Span Reinf Steel Area	Long Span Reinf Steel Area	Thickness	Reduced Riser Size	Short Span Reinf Steel Area	Long Span Reinf Steel Area	Thickness					
	Ashort	Along	BS	Bshort	Blong	W	RWSxRWL or ID	Dshort	Dlong	TS	Ashort	Along	BS	Bshort	Blong	W	RWSxRWL or ID	Dshort	Dlong	TS	BH MIN	HOLE DIA			
X x Y	in ² /ft	in ² /ft	in.	in ² /ft	in ² /ft	in.	ft. **	in ² /ft	in ² /ft	in.	in ² /ft	in ² /ft	in.	in ² /ft	in ² /ft	in.	ft. **	in ² /ft	in ² /ft	in.	ft.	in.	in.		
Precast Junction Box (PJB)	3x3	0.23	0.23	6	0.19	0.19	6	N/A	0.37	0.37	9	0.29	0.29	6	0.24	0.24	6	N/A	0.37	0.37	9	3.5	36	36	
	4x4	0.29	0.29	6	0.24	0.24	6	N/A	0.41	0.41	9	0.47	0.47	6	0.38	0.38	6	N/A	0.41	0.41	9	4.5	48	48	
	3x5	0.29	0.18	6	0.19	0.35	6	N/A	0.48	0.48	9	0.39	0.18	6	0.23	0.59	6	N/A	0.48	0.48	9	3.5	36/60	36/60	
	4x5	0.36	0.18	6	0.22	0.34	6	N/A	0.42	0.42	9	0.53	0.26	6	0.39	0.59	6	N/A	0.42	0.42	9	4.5	48/60	48/60	
	5x5	0.36	0.36	6	0.34	0.34	6	N/A	0.43	0.43	9	0.62	0.62	6	0.59	0.59	6	N/A	0.43	0.43	9	5.5	60	60	
	5x6	0.27	0.27	9	0.34	0.45	6	N/A	0.48	0.48	9	0.47	0.45	9	0.38	0.54	8	N/A	0.48	0.48	9	5.5	60/72	60/72	
	6x6	0.27	0.27	9	0.45	0.45	6	N/A	0.56	0.56	9	0.52	0.52	9	0.54	0.54	8	N/A	0.56	0.56	9	6.5	72	72	
	8x8	0.46	0.46	9	0.51	0.51	8	N/A	0.45	0.45	12	0.87	0.87	9	0.59	0.59	10	N/A	0.45	0.45	12	8.5	96	72	
Precast Base (PB)	3x3	0.23	0.23	6	0.19	0.19	6	N/A	N/A	N/A	N/A	0.29	0.29	6	0.24	0.24	6	N/A	N/A	N/A	N/A	3.5	36	36	
	4x4	0.29	0.29	6	0.24	0.24	6	N/A	N/A	N/A	N/A	0.47	0.47	6	0.38	0.38	6	N/A	N/A	N/A	N/A	4.5	48	48	
	3x5	0.29	0.18	6	0.19	0.35	6	3x3	0.30	0.34	9	0.39	0.18	6	0.23	0.59	6	3x3	0.40	0.40	9	3.5	36/60	36/60	
	4x5	0.36	0.18	6	0.22	0.34	6	3x3	0.30	0.30	9	0.53	0.26	6	0.39	0.59	6	3x3	0.46	0.37	9	4.5	48/60	48/60	
	4x5	0.36	0.18	6	0.22	0.34	6	4x4	0.30	0.30	9	0.53	0.26	6	0.39	0.59	6	4x4	0.39	0.39	9	4.5	48/60	48/60	
	4x5	0.36	0.18	6	0.22	0.34	6	48"	0.39	0.39	9	0.53	0.26	6	0.39	0.59	6	48"	0.47	0.47	9	4.5	48/60	48/60	
	4x5	0.36	0.18	6	0.22	0.34	6	3x5	0.33	0.40	9	0.53	0.26	6	0.39	0.59	6	3x5	0.48	0.48	9	4.5	48/60	48/60	
	5x5	0.36	0.36	6	0.34	0.34	6	3x3	0.34	0.34	9	0.62	0.62	6	0.59	0.59	6	3x3	0.53	0.53	9	5.5	60	60	
	5x5	0.36	0.36	6	0.34	0.34	6	4x4	0.36	0.36	9	0.62	0.62	6	0.59	0.59	6	4x4	0.64	0.64	9	5.5	60	60	
	5x5	0.38	0.38	6	0.34	0.34	6	48"	0.36	0.36	9	0.62	0.62	6	0.59	0.59	6	48"	0.64	0.64	9	5.5	60	60	
	5x5	0.36	0.36	6	0.34	0.34	6	3x5	0.34	0.40	9	0.62	0.62	6	0.59	0.59	6	3x5	0.53	0.53	9	5.5	60	60	
	5x6	0.31	0.31	9	0.34	0.45	6	3x3	0.34	0.34	9	0.47	0.45	9	0.38	0.54	8	3x3	0.61	0.50	9	5.5	60/72	60/72	
	5x6	0.27	0.27	9	0.34	0.45	6	4x4	0.36	0.45	9	0.47	0.45	9	0.38	0.54	8	4x4	0.74	0.57	9	5.5	60/72	60/72	
	5x6	0.29	0.29	9	0.34	0.45	6	48"	0.36	0.45	9	0.47	0.45	9	0.38	0.54	8	48"	0.74	0.57	9	5.5	60/72	60/72	
	5x6	0.29	0.29	9	0.34	0.45	6	3x5	0.45	0.45	9	0.47	0.45	9	0.38	0.54	8	3x5	0.61	0.61	9	5.5	60/72	60/72	
	6x6	0.29	0.29	9	0.45	0.45	6	3x3	0.41	0.41	9	0.52	0.52	9	0.54	0.54	8	3x3	0.74	0.74	9	6.5	72	72	
	6x6	0.27	0.27	9	0.45	0.45	6	4x4	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	4x4	0.87	0.87	9	6.5	72	72	
	6x6	0.29	0.29	9	0.45	0.45	6	48"	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	48"	0.87	0.87	9	6.5	72	72	
	6x6	0.29	0.29	9	0.45	0.45	6	3x5	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	3x5	0.87	0.87	9	6.5	72	72	
	8x8	0.52	0.52	9	0.51	0.51	8	3x3	0.61	0.61	12	0.91	0.91	9	0.70	0.70	10	3x3	0.85	0.85	12	8.5	96	72	
8x8	0.52	0.52	9	0.51	0.51	8	4x4	0.70	0.70	12	0.87	0.87	9	0.70	0.70	10	4x4	1.01	1.01	12	8.5	96	72		
8x8	0.52	0.52	9	0.51	0.51	8	48"	0.70	0.70	12	0.87	0.87	9	0.70	0.70	10	48"	1.01	1.01	12	8.5	96	72		
8x8	0.52	0.52	9	0.51	0.51	8	3x5	0.70	0.85	12	0.87	0.87	9	0.70	0.70	10	3x5	1.01	1.01	12	8.5	96	72		

** Unless otherwise indicated.



FABRICATION NOTES:

- Maximum spacing of reinforcement is 8".
- At manufacturer's option, provide cast or cored holes or thin wall panels (KO) to the maximum diameter shown for each. When no penetration is required, it is acceptable to provide a wall with no sectional reduction.

GENERAL NOTES:


- Precast Junction Box consists of base slab, base unit, risers (as required), and below grade slab. See sheet PJB for details.
- Precast Base consists of base slab, base unit, risers (as required), reducing slab (as required), and reduced risers (as required). See sheet PB for details.
- Min Height shown is for stock base units. Use stock base units whenever practical. Smaller height base units can be used in special installation circumstances, when noted elsewhere in the plans. Absolute minimum height of base units is 2'-6".

HL93 LOADING


			
<p>DESIGN DATA FOR PRECAST BASE AND JUNCTION BOX</p>			
<p>PDD</p>			
FILE: prest10-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT	SECT	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		99

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY)



Nominal Culvert (Pipe) I.D.	PSET-SC and PSET-SP Standards					PSET-RC and PSET-RP Standards		
	Unit Width "W"	Side Slope			Unit Width "W"	Side Slope		
		3:1	4:1	6:1		3:1	4:1	6:1
12"	23.0"	0.1	0.2	0.2	16.0"	0.1	0.1	0.2
15"	26.5"	0.2	0.2	0.3	19.5"	0.1	0.2	0.2
18"	30.0"	0.2	0.2	0.3	23.0"	0.2	0.2	0.3
24"	37.0"	0.3	0.3	0.5	30.0"	0.2	0.3	0.4
30"	44.5"	0.3	0.4	0.6	37.0"	0.3	0.3	0.5
36"	51.5"	0.4	0.5	0.7	44.0"	0.3	0.4	0.6
42"	58.5"	0.5	0.6	0.8	51.0"	0.4	0.5	0.7




PLAN



LONGITUDINAL ELEVATION



MULTIPLE PIPE INSTALLATION



SINGLE PIPE INSTALLATION

SECTION A-A

- Riprap placed beyond the limits shown will be paid as concrete riprap in accordance with Item 432, "Riprap". When riprap is cast integrally with the precast safety end treatment, this dimension is 1'-0" minimum.
- 1#2" Dia ASTM A307 Gr A threaded anchor rod with 2 nuts and 2 washers. Galvanize all components in accordance with Item 445, "Galvanizing". Repair galvanizing that is damaged during transport or construction in accordance with the specifications.
- 3/4" through holes in walls of safety end treatment for riprap anchor rods may be drilled with rotary (coring or masonry) type drilling equipment or may be formed. Do not use percussive (star) type drilling equipment. If holes are drilled, patch spalls in the inside face of the wall exceeding 1#2" from the holes.
- Provide riprap toe wall when dimension is shown elsewhere in the plans or when field conditions require a toe wall.
- Quantities shown are for one end of one reinforced concrete pipe culvert. For multiple pipe culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only. Quantities are based on the minimum unit lengths shown on the Precast Safety End Treatment (SET) standard sheets.

MATERIAL NOTES:

Provide Class "B" riprap in accordance with Item 432, "Riprap". Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. The anchor rods shown are always required.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment". Refer to PSET-SC or PSET-SP standard sheets for details of square safety end treatments not shown. Refer to PSET-RC or PSET-RP standard sheets for details of round safety end treatments not shown. For precast units with integrally cast riprap, substitute reinforcing steel in the amount on 0.26 in./ft. minimum for the threaded anchor rods shown. When requested, submit sealed engineering drawings for approval prior to construction. Shop drawings will not be required. Note that a proprietary precast unit with integral riprap is available from L&R Precast Concrete Works, Inc. (956) 583-6293 or www.lrpccast.com. Payment for riprap and toewalls is included in the price bid for each safety end treatment.

These riprap details are only applicable when notes that require placement of riprap with precast safety end treatments are shown elsewhere in the plans.

Precast units with integrally cast riprap are permitted unless noted otherwise on the plans.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME


		Bridge Division Standard	
PRECAST SAFETY END TREATMENT TYPE II RIPRAP DETAILS PSET-RR			
FILE: psetrrse-20.dgn	DN: GAF	CK: TxDOT	DW: JRP
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	100	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/09/07
FILE: DOCUMENT NAME




PLAN VIEW - 12" THRU 24"
(Showing spigot end connection.)



LONGITUDINAL ELEVATION - 12" THRU 24"
(Showing spigot end connection.)




SECTION A-A




MULTIPLE PIPE INSTALLATION


- ① Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- ② Provide cement stabilized bedding and backfill in accordance with the Item, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- ③ Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- ④ Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- ⑤ Safety pipe runners are required for multiple pipe culverts with more than two pipes.



INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS
(If required)



OPTION A



OPTION B

END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS
(If required)

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. per ft. of Pipe)	Max Slope	Min Length of Unit	Pipe Runner Requirements		Required Pipe Runner Sizes		
							Single Pipe	Multiple Pipe	Nominal Dia	O.D.	I.D.
12"	2"	16"	16"	0.07 Circ.	6:1	4' - 0"	No	⑤	3" STD	3.500"	3.068"
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	6:1	5' - 8"	No	⑤	3" STD	3.500"	3.068"
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	6:1	7' - 3"	No	⑤	3" STD	3.500"	3.068"
24"	3"	30"	27"	0.07 Circ.	6:1	10' - 6"	No	⑤	3" STD	3.500"	3.068"
30"	3 1/2"	37"	31"	0.18 Circ.	6:1	12' - 1"	No	Yes	4" STD	4.500"	4.026"
36"	4"	44"	36"	0.19 Ellip.	6:1	15' - 4"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	6:1	18' - 7"	Yes	Yes	4" STD	4.500"	4.026"

MATERIAL NOTES:

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.
Galvanize steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (RCP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".
When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.
Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.
Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.
Methods of lifting shall be provided by the manufacturer for ease of loading, unloading and installation.
Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.




PRECAST SAFETY END TREATMENT TYPE II ~ PARALLEL DRAINAGE

PSET-RP


FILE: psetrpss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
DIST	COUNTY	SHEET NO.		
DAL	Navarro	101		

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/09/07
 FILE: DOCUMENT NAME




ELEVATION VIEW




ELEVATION VIEW




ELEVATION VIEW




ELEVATION VIEW




PLAN VIEW
 NO OPENINGS
STYLE 'SL'




PLAN VIEW
 SHIP LOOSE RING & COVER
STYLE 'RH'



PLAN VIEW
 32" DIA CAST-IN RING & COVER
STYLE 'RC'




PLAN VIEW
 32" DIA CAST-IN RING & GRATE
STYLE 'RG'




STYLE 'FG'


ORIENT TAPER TO CORRESPOND WITH ROADWAY CROSS-SLOPE.




STYLE 'SFG'
ELEVATION VIEW




ELEVATION VIEW




ELEVATION VIEW



PLAN VIEW
 CAST-IN FRAME & GRATE
STYLES 'FG' & 'SFG'



PLAN VIEW
 SHIP LOOSE FRAME & GRATE
STYLE 'SH'



PLAN VIEW
 EXPOSED REBAR
STYLE 'S1'

① Matches inside face of wall of precast base or riser below inlet.

HL93 LOADING SHEET 1 OF 2



PRECAST SLAB LID

PSL


FILE: presto05-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.	
DAL	Navarro		102	

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Style	Size (X x Y)	W ⁽²⁾	A x B (nominal)	Short Span Reinf Steel Area	Long Span Reinf Steel Area
SL	3'x3'	6"	n/a	0.37 in ² /ft	0.37 in ² /ft
RH,RC,RG,SH,S1,FG	3'x3'	6"	3'x3' or 32" Dia	0.37 in ² /ft	0.37 in ² /ft
SFG	3'x3'	6"	3'x3'	0.32 in ² /ft	0.32 in ² /ft
SL	4'x4'	6"	n/a	0.34 in ² /ft	0.34 in ² /ft
RH,RC,RG,SH,S1,FG	4'x4'	6"	3'x3' or 32" Dia	0.41 in ² /ft	0.41 in ² /ft
SH,S1,FG	4'x4'	6"	4'x4'	0.41 in ² /ft	0.41 in ² /ft
SFG	4'x4'	6"	4'x4'	0.32 in ² /ft	0.32 in ² /ft
SL	3'x5'	6"	n/a	0.39 in ² /ft	0.39 in ² /ft
RH,RC,RG,SH,S1,FG	3'x5'	6"	3'x3' or 32" Dia	0.48 in ² /ft	0.48 in ² /ft
SH,S1,FG	3'x5'	6"	3'x5'	0.48 in ² /ft	0.48 in ² /ft
SFG	3'x5'	6"	3'x5'	0.32 in ² /ft	0.32 in ² /ft
SL	4'x5'	6"	n/a	0.42 in ² /ft	0.42 in ² /ft
RH,RC,RG,SH,S1,FG	4'x5'	6"	3'x3' or 32" Dia	0.42 in ² /ft	0.42 in ² /ft
SH,S1,FG	4'x5'	6"	4'x4'	0.63 in ² /ft	0.63 in ² /ft
SH,S1,FG	4'x5'	6"	3'x5'	0.66 in ² /ft	0.66 in ² /ft
SL	5'x5'	6"	n/a	0.36 in ² /ft	0.36 in ² /ft
RH,RC,RG,SH,S1,FG	5'x5'	6"	3'x3' or 32" Dia	0.43 in ² /ft	0.43 in ² /ft
SH,S1,FG	5'x5'	6"	4'x4'	0.63 in ² /ft	0.63 in ² /ft
SH,S1,FG	5'x5'	6"	3'x5'	0.63 in ² /ft	0.63 in ² /ft
SL	5'x6'	6"/8"	n/a	0.48 in ² /ft	0.48 in ² /ft
RH,RC,RG,SH,S1,FG	5'x6'	6"/8"	3'x3' or 32" Dia	0.48 in ² /ft	0.48 in ² /ft
SH,S1,FG	5'x6'	6"/8"	4'x4'	0.60 in ² /ft	0.60 in ² /ft
SH,S1,FG	5'x6'	6"/8"	3'x5'	0.60 in ² /ft	0.60 in ² /ft
SL	6'x6'	6"/8"	n/a	0.43 in ² /ft	0.43 in ² /ft
RH,RC,RG,SH,S1,FG	6'x6'	6"/8"	3'x3' or 32" Dia	0.56 in ² /ft	0.56 in ² /ft
SH,S1,FG	6'x6'	6"/8"	4'x4'	0.56 in ² /ft	0.56 in ² /ft
SH,S1,FG	6'x6'	6"/8"	3'x5'	0.59 in ² /ft	0.59 in ² /ft
SL	8'x8'	8"/10"	n/a	0.45 in ² /ft	0.45 in ² /ft
RH,RC,RG,SH,S1,FG	8'x8'	8"/10"	3'x3' or 32" Dia	0.45 in ² /ft	0.45 in ² /ft
SH,S1,FG	8'x8'	8"/10"	4'x4'	0.45 in ² /ft	0.45 in ² /ft
SH,S1,FG	8'x8'	8"/10"	3'x5'	0.45 in ² /ft	0.45 in ² /ft

⁽²⁾ See sheet PDD for corresponding wall thickness (W) of base unit or riser.

Construct cast-in-place reinforced concrete apron, when shown elsewhere in plans. Use Class "A" concrete. Apron is subsidiary to PSL. Apron is 1'-6" Min width around precast zone drain.



DETAIL "A"

(Reinforcing not shown for clarity)
When an apron is to be cast around PSL, use detail above to create an apron ledge on all 4 sides.

FABRICATION NOTES:

1. Locate penetration (Style 'RH'), ring and cover (Style 'RC'), ring and grate (Style 'RG'), and frame and grate (Style 'FG') in a corner. Only one penetration is allowed per slab lid.
2. Provide Class "H" concrete in accordance with Item 421 and having a minimum compressive strength of 5,000 psi.
3. Provide Grade 60 reinforcing steel or equivalent area of WWR.
4. Provide clear cover of 3/4" to reinforcing from lower outside shoulder of slab for structural reinforcement, and 2" from top of slab for shrinkage and temperature reinforcement. Place short span reinforcing closest to surface.
5. Slabs with a thickness of 8" or greater require shrinkage and temperature reinforcing. Provide steel area = 0.11 in²/ft each way.
6. No substitution is allowed for diagonal #4 bars around openings.
7. Design tongue and groove joints for full closure on both shoulders. Minimum spigot depth is 3/4".
8. Provide lifting devices in conformance with Manufacturer's recommendations.

INSTALLATION NOTES:

1. Precast slab lids are intended for direct traffic and may be placed in roadway.
2. Seal tongue and groove joints with preformed or bulk mastic in conformance with Manufacturer's recommendations. Tongue and groove joints may be grouted no more than 1" between each section, or 1/2 the joint depth, whichever is greater.
3. Do not grout rubber gasket joints without Manufacturer's recommendation.
4. Initial installation of grade adjustment rings for Styles 'RH' and 'SH' is limited to 1'-0" Max as shown.
5. Grade adjustment rings for Styles 'RH' and 'SH' may be increased to 2'-0" Max when future construction affects final grade of structure. Make adjustments greater than 2'-0" with additional risers. Adjustments can be made up to Max depth shown on sheet PDD. Structure must be evaluated if Max depth will be exceeded.
6. Orient long dimension of grate slots perpendicular to traffic, unless noted otherwise on plans.

GENERAL NOTES:

1. Designed according to ASTM C913.
2. Payment for lid is per Item 465, "Junction Boxes, Manholes, and Inlets" by type, style, size, and opening size (when applicable).

Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING SHEET 2 OF 2



PRECAST SLAB LID


PSL

FILE: prest05-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.	
DAL	Navarro		103	


DATE: 2022/09/07
FILE: DOCUMENT NAME

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/09/07
 FILE: DOCUMENT NAME




PLAN



ELEVATION




SECTION A-A AT CAP



SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".


8"X 18 Gage galvanized flashing full length of cap



CAP OPTION A

Nail flashing to cap or wingwall and seal with joint sealer

Plug ends and seal joint along ends of cap and side of wingwalls with joint sealer



CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:

Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2

		Bridge Division Standard	
<h2>STONE RIPRAP</h2>			
<h3>SRR</h3>			
FILE: srrstd1-19.dgn	DN: AES	CK: JGD	DW: BWH
©TxDOT April 2019	CONTRACT NO. 3090	SECTION 01	HIGHWAY 012
REVISIONS	DIST. DAL	COUNTY. Navarro	SHEET NO. 104

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME




FIGURE 1 ~ TYPE R STONE RIPRAP

dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP

dry or mortared





FIGURE 3 ~ TYPE F STONE RIPRAP

grouted

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "Y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



PROTECTION STONE RIPRAP TOE OPTIONS




FIGURE 4 ~ COMMON STONE RIPRAP

dry or grouted






FIGURE 5 ~ PROTECTION STONE RIPRAP

SHEET 2 OF 2

		Bridge Division Standard	
<h2>STONE RIPRAP</h2>			
<h3>SRR</h3>			
FILE: srrstd1-19.dgn	DN: AES	CK: JGD	DW: BWH
©TxDOT	APR 2019	CONT SECT	JOB HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	105	

CK
DW
CK
DW



LEGEND
 ——— DRAINAGE AREA BOUNDARY
 (XXX) DRAINAGE AREA ID
 (XXX) DRAINAGE AREA (SQ MI)
 → FLOW DIRECTION

STATE OF TEXAS
 ★
 AMIR M. SHAMMET
 95892
 LICENSED PROFESSIONAL ENGINEER
Amir M. Shammet
 01/27/2023

CULVERT @ TUPELO BRANCH
 FM 3041 STA 102+59.18

RUNOFF COMPUTATIONS (NRCS METHOD)																			
DA ID	Culvert Station	Area (Sq Mi)	Tc (Hr)	Log Time (Hr)	Log Time (min)	Base RCN	Adjusted RCN	24-Hour Precipitation (in)					Peak Discharge (cfs@*)						
								2-yr	5-yr	10-yr	25-yr	50-yr	100-yr	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
DA #5-1		8.26	5.36	3.22	193	84	80	3.65	5.05	6.19	7.81	9.14	10.60	1179	1980	2649	3685	4739	5877
DA #5-3		0.62	1.97	1.18	71.0	85	81	3.66	5.06	6.20	7.83	9.16	10.70	256	412	537	707	839	979
DA #5	102+59.18	8.88	-	-	-	-	-	-	-	-	-	-	-	1240	2083	2788	3868	4966	6163

(*) The peak discharge at the culvert is controlled by the storage capacity of soil conservation service (SCS) site #131 within DA #5-1.

1. NRCS Hydrograph Method was modeled in HEC-HMS version 4.10.
2. Precipitation data was obtained from NOAA Atlas-14 for this project location.
3. Soils data was obtained from NRCS Web Soil Survey Utility.
4. Land use data was obtained from aerial photogrammetry.
5. Runoff Curve Number (RCN) was based on TxDOT Hydraulic Design Manual, Table 4-19, Table 4-20 and Figure 4-22.
6. Lag time calculations based on lagtime=0.6 Tc. Tc is time of concentration.

Texas Department of Transportation


FM 3041
 BRIDGE CLASS
 DRAINAGE AREA MAP
 TUPELO BRANCH
 STA 102+59.18

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	106	

DATE: 1/25/2023 9:54:15 AM
 FILE: c:\tdot\p\onlinet\tdot5\craig_parker\0463963\BRIDGE CLASS DRAINAGE AREA MAP.dgn

DN: DW: CC: CK:



CULVERT @ TUPLEO BRANCH
FM 3041 STA 102+59.18



Texas Department of Transportation

FM 3041
CROSS-SECTIONS MAP
TUPLEO BRANCH
STA 102+59.18

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	107	

DATE: 1/26/2023 9:01:28 AM
FILE: c:\txdot\pw_onlinetxdot5\craig_parker\10463963\CROSS_SECTIONS_MAP.dgn

DATE: 1/25/2023 9:54:45 AM
 FILE: c:\tdot\ipw_onlinetxdot5\craig_parker\0463963\HYDRAULIC DATA.dgn

HEC-RAS														
River	Reach	River Sta	Profile	Plan	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Tupelo Branch	Upper	4153.264	10-YR	EX	2648.60	334.14	346.59		346.69	0.001303	3.12	1184.29	481.51	0.21
Tupelo Branch	Upper	4153.264	10-YR	PROP	2648.60	334.14	346.59		346.69	0.001302	3.12	1184.57	481.52	0.21
Tupelo Branch	Upper	4153.264	100-YR	EX	5876.80	334.14	351.74		351.78	0.000174	1.64	3831.46	549.50	0.08
Tupelo Branch	Upper	4153.264	100-YR	PROP	5876.80	334.14	351.77		351.80	0.000172	1.63	3846.42	549.85	0.08
Tupelo Branch	Upper	3957.516	10-YR	EX	2648.60	333.81	345.49	345.49	346.08	0.012865	7.06	510.55	390.93	0.59
Tupelo Branch	Upper	3957.516	10-YR	PROP	2648.60	333.81	345.49	345.49	346.08	0.012865	7.06	510.55	390.93	0.59
Tupelo Branch	Upper	3957.516	100-YR	EX	5876.80	333.81	351.68		351.74	0.000272	1.85	3177.68	471.22	0.10
Tupelo Branch	Upper	3957.516	100-YR	PROP	5876.80	333.81	351.71		351.76	0.000269	1.84	3190.80	471.84	0.10
Tupelo Branch	Upper	3622.302	10-YR	EX	2648.60	333.93	345.17		345.23	0.000606	1.95	1366.71	340.17	0.14
Tupelo Branch	Upper	3622.302	10-YR	PROP	2648.60	333.93	344.90		344.97	0.000755	2.12	1276.66	338.74	0.15
Tupelo Branch	Upper	3622.302	100-YR	EX	5876.80	333.93	351.63		351.67	0.000125	1.43	3744.39	418.14	0.07
Tupelo Branch	Upper	3622.302	100-YR	PROP	5876.80	333.93	351.66		351.70	0.000124	1.43	3756.24	418.80	0.07
Tupelo Branch	Lower	3603.85	10-YR	EX	2787.90	333.93	345.07	342.19	345.14	0.000725	2.12	1334.68	338.66	0.15
Tupelo Branch	Lower	3603.85	10-YR	PROP	2787.90	333.93	344.78	342.19	344.86	0.000928	2.32	1236.29	338.10	0.17
Tupelo Branch	Lower	3603.85	100-YR	EX	6162.70	333.93	351.61	343.28	351.66	0.000138	1.50	3735.28	417.64	0.07
Tupelo Branch	Lower	3603.85	100-YR	PROP	6162.70	333.93	351.64	343.27	351.68	0.000137	1.50	3747.18	418.30	0.07
Tupelo Branch	Lower	3560.0			Culvert									
Tupelo Branch	Lower	3498.850	10-YR	EX	2787.90	333.18	343.13		343.25	0.003438	3.66	1128.03	863.29	0.31
Tupelo Branch	Lower	3498.850	10-YR	PROP	2787.90	333.18	343.13		343.25	0.003438	3.66	1128.03	863.29	0.31
Tupelo Branch	Lower	3498.850	100-YR	EX	6162.70	333.18	344.17		344.30	0.003002	3.73	2271.85	1251.10	0.30
Tupelo Branch	Lower	3498.850	100-YR	PROP	6162.70	333.18	344.17		344.30	0.003002	3.73	2271.93	1251.11	0.30
Tupelo Branch	Lower	3208.713	10-YR	EX	2787.90	332.35	342.58		342.63	0.001519	2.57	1574.69	991.20	0.21
Tupelo Branch	Lower	3208.713	10-YR	PROP	2787.90	332.35	342.58		342.63	0.001519	2.57	1574.69	991.20	0.21
Tupelo Branch	Lower	3208.713	100-YR	EX	6162.70	332.35	343.61		343.69	0.001695	2.23	2725.24	1209.35	0.21
Tupelo Branch	Lower	3208.713	100-YR	PROP	6162.70	332.35	343.61		343.69	0.001695	2.23	2725.35	1209.35	0.21
Tupelo Branch	Lower	2735.257	10-YR	EX	2787.90	332.58	342.05		342.11	0.001287	2.61	1599.69	984.06	0.20
Tupelo Branch	Lower	2735.257	10-YR	PROP	2787.90	332.58	342.05		342.11	0.001287	2.61	1599.69	984.06	0.20
Tupelo Branch	Lower	2735.257	100-YR	EX	6162.70	332.58	343.00		343.09	0.001557	3.17	2665.99	1175.90	0.22
Tupelo Branch	Lower	2735.257	100-YR	PROP	6162.70	332.58	343.00		343.09	0.001557	3.17	2666.24	1175.95	0.22
Tupelo Branch	Lower	2605.566	10-YR	EX	2787.90	332.02	341.41		341.45	0.001447	2.06	1674.80	1164.79	0.20
Tupelo Branch	Lower	2605.566	10-YR	PROP	2787.90	332.02	341.41		341.45	0.001447	2.06	1674.80	1164.79	0.20
Tupelo Branch	Lower	2605.566	100-YR	EX	6162.70	332.02	342.25		342.33	0.001759	2.63	2693.01	1257.02	0.23
Tupelo Branch	Lower	2605.566	100-YR	PROP	6162.70	332.02	342.25		342.33	0.001757	2.63	2694.01	1257.06	0.23

Plan: PROP Tupelo Branch Lower RS: 3560.0 Culv Group: Culvert #1 Profile: 10-YR

Q Culv Group (cfs)	2787.90	Culv Full Len (ft)	63.00
# Barrels	3	Culv Vel US (ft/s)	9.29
Q Barrel (cfs)	929.30	Culv Vel DS (ft/s)	9.29
E.G. US. (ft)	344.86	Culv Inv El Up (ft)	333.08
W.S. US. (ft)	344.78	Culv Inv El Dn (ft)	333.05
E.G. DS (ft)	343.25	Culv Frctn Ls (ft)	0.12
W.S. DS (ft)	343.13	Culv Exit Loss (ft)	1.22
Delta EG (ft)	1.61	Culv Entr Loss (ft)	0.27
Delta WS (ft)	1.65	Q Weir (cfs)	
E.G. IC (ft)	343.52	Weir Sta Lft (ft)	
E.G. OC (ft)	344.86	Weir Sta Rgt (ft)	
Culvert Control	Outlet	Weir Submerg	
Culv WS Inlet (ft)	343.08	Weir Max Depth (ft)	
Culv WS Outlet (ft)	343.05	Weir Avg Depth (ft)	
Culv Nml Depth (ft)		Weir Flow Area (sq ft)	
Culv Crt Depth (ft)	6.45	Min El Weir Flow (ft)	350.15

Plan: PROP Tupelo Branch Lower RS: 3560.0 Culv Group: Culvert #1 Profile: 100-YR

Q Culv Group (cfs)	5804.41	Culv Full Len (ft)	63.00
# Barrels	3	Culv Vel US (ft/s)	19.35
Q Barrel (cfs)	1934.80	Culv Vel DS (ft/s)	19.35
E.G. US. (ft)	351.68	Culv Inv El Up (ft)	333.08
W.S. US. (ft)	351.64	Culv Inv El Dn (ft)	333.05
E.G. DS (ft)	344.30	Culv Frctn Ls (ft)	0.53
W.S. DS (ft)	344.17	Culv Exit Loss (ft)	5.69
Delta EG (ft)	7.39	Culv Entr Loss (ft)	1.16
Delta WS (ft)	7.47	Q Weir (cfs)	358.29
E.G. IC (ft)	352.47	Weir Sta Lft (ft)	277.36
E.G. OC (ft)	351.68	Weir Sta Rgt (ft)	419.22
Culvert Control	Outlet	Weir Submerg	0.00
Culv WS Inlet (ft)	343.08	Weir Max Depth (ft)	1.59
Culv WS Outlet (ft)	343.05	Weir Avg Depth (ft)	0.95
Culv Nml Depth (ft)	10.00	Weir Flow Area (sq ft)	134.25
Culv Crt Depth (ft)	10.00	Min El Weir Flow (ft)	350.15

NOTES:

- 1) HYDRAULIC ANALYSIS WAS BASED ON TxDOT'S HYDRAULIC DESIGN MANUAL (SEPTEMBER 2019).
- 2) USACE HEC-RAS VERSION 5.0.7 WAS USED FOR THE ANALYSIS.
- 3) THIS SITE IS DESIGNATED AS FEMA ZONE "A" WITH FLOODPLAIN AS SHOWN ON PANEL 48349C0200D, EFFECTIVE DATE JUNE 5, 2012.
- 4) ALL ELEVATIONS ARE BASED ON THE NAVD 88 VERTICAL DATUM.
- 5) THE DOWNSTREAM BOUNDARY CONDITION WAS ESTABLISHED USING CHANNEL SLOPE FOR NORMAL DEPTH CALCULATIONS.



Texas Department of Transportation

FM 3041



HYDRAULIC DATA

TUPELO BRANCH
STA 102+59.18

SHEET 1 OF 3

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	108	

CK: DW: CK: DW:



DATE: 1/25/2023 9:55:01 AM
 FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\0463963\3041_HDS_BCC_SHEET_04.dgn

NOTES:

- 1) HYDRAULIC ANALYSIS WAS BASED ON TxDOT'S HYDRAULIC DESIGN MANUAL (SEPTEMBER 2019).
- 2) USACE HEC-RAS VERSION 5.0.7 WAS USED FOR THE ANALYSIS.
- 3) THIS SITE IS DESIGNATED AS FEMA ZONE "A" WITH FLOODPLAIN AS SHOWN ON PANEL 48349C0200D, EFFECTIVE DATE JUNE 5, 2012.
- 4) ALL ELEVATIONS ARE BASED ON THE NAVD 88 VERTICAL DATUM.
- 5) THE DOWNSTREAM BOUNDARY CONDITION WAS ESTABLISHED USING CHANNEL SLOPE FOR NORMAL DEPTH CALCULATIONS.



Texas Department of Transportation



FM 3041

HYDRAULIC DATA
 TUPELO BRANCH
 STA 102+59.18

SHEET 2 OF 3

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	109	

CK:
DW:
CK:
DW:



NOTES:

- 1) HYDRAULIC ANALYSIS WAS BASED ON TxDOT'S HYDRAULIC DESIGN MANUAL (SEPTEMBER 2019).
- 2) USACE HEC-RAS VERSION 5.0.7 WAS USED FOR THE ANALYSIS.
- 3) THIS SITE IS DESIGNATED AS FEMA ZONE "A" WITH FLOODPLAIN AS SHOWN ON PANEL 48349C0200D, EFFECTIVE DATE JUNE 5, 2012.
- 4) ALL ELEVATIONS ARE BASED ON THE NAVD 88 VERTICAL DATUM.
- 5) THE DOWNSTREAM BOUNDARY CONDITION WAS ESTABLISHED USING CHANNEL SLOPE FOR NORMAL DEPTH CALCULATIONS.



Texas Department of Transportation

FM 3041


HYDRAULIC DATA
 TUPELO BRANCH
 STA 102+59.18

SHEET 3 OF 3


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	110	

DATE: 1/25/2023 9:55:17 AM
 FILE: c:\tdot\ipw_online\tdot5\craig_parker\0463963\3041_HDS_BCC_SHEET_05.dgn


CK: DW: CK: DW:



EXISTING TYPICAL SECTION
 STA 102+43.01 TO STA 102+75.34
 BRIDGE CLASS CULVERT ON TUPELO BRANCH AT STA 102+59.18
 EXISTING: 3-10' X10' X55.2 LF MBC W/ WINGWALLS



PROPOSED TYPICAL SECTION
 STA 102+43.01 TO STA 102+75.34
 BRIDGE CLASS CULVERT TUPELO BRANCH AT STA 102+59.18
 PROP.: 3-10' X10' X63.2 LF MBC W/ PW-1 (US & DS)



Morgan Neill, P.C. 2/1/2023




FM 3041
 EXISTING & PROPOSED
 TYPICAL SECTIONS
 BRIDGE CLASS CULVERT
 TUPELO BRANCH

SHEET 1 OF 1



CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	111	

DATE: 1/31/2023 1:15:53 PM
 FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\10463963\EXISTING & PROPOSED TYPICAL SECTIONS.dgn


CK: DW: CK: DW:



- PHASE 1
- 1.SETUP TRAFFIC CONTROL PLAN FOLLOWING TCP AND BC STANDARDS.
 - 2.REMOVE EXISTING WINGWALL AND BOX CULVERT.
 - 3.PLACE PROPOSED CULVERT.
 - 4.REGRADE UPSTREAM TO FLOW.




- PHASE 2
- 1.SETUP TRAFFIC CONTROL PLAN FOLLOWING TCP AND BC STANDARDS.
 - 2.REMOVE EXISTING WINGWALL AND BOX CULVERT.
 - 3.PLACE PROPOSED CULVERT.
 - 4.REGRADE DOWNSTREAM TO FLOW



PROPOSED TYPICAL SECTION
 STA 102+43.01 TO STA 102+75.34
 BRIDGE CLASS CULV TUPELO BRANCH STA 102+59.18
 PROP.: 3-10' X 10' X 63.2 LF MBC W/ PW-1 (US & DS)

- NOTES:
1. TWO-WAY TRAFFIC SHALL BE ESTABLISHED AT THE END OF EACH WORK DAY.
 2. IF LANE CLOSING IS NEEDED, WITH THE ENGINEER'S APPROVAL, USE FLAGGERS & PILOT VEHICLE TO HANDLE THE TRAFFIC FLOW
 3. IF NEEDED, PROVIDE TEMPORARY DETOUR WITH APPROVAL OF THE ENGINEER.
 4. PROVIDE & MAINTAIN SMOOTH SURFACE & PAVEMENT MARKINGS AS NEEDED AFTER THE COMPLETION OF THE CULVERT EXTENSIONS.
 5. SEE CULVERT LAYOUTS FOR ADDITION DETAIL.



Morgan Neill, P.E. 2/1/2023



FM 3041




TCP TYPICAL SECTIONS
 BRIDGE CLASS CULVERT
 TUPELO BRANCH

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	112	

DATE: 1/31/2023 1:16:05 PM
 FILE: c:\tdot\ipw_on\in\m\tdot5\craig_parker\0463963\TCP TYPICAL SECTIONS BRIDGE CLASS CULVERT.dgn

CK
DWF
CK
DWF





ESTIMATED QUANTITIES			
ITEM CODE	DESCRIPTION	UNIT	QUANTITY
402-6001	TRENCH EXCAVATION PROTECTION	LF	55.2
403-6001	TEMPORARY SPL SHORING	SF	2427.6
432-6001	RIPRAP (CONC) (4 IN)	CY	44.39
432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	585.78
462-6034	CONC BOX CULV (10FTX10FT)	LF	192
466-6188	WINGWALL (PW-1) (HW= 13 FT)	EA	2
496-6005	REMOVE STR (WINGWALLS)	EA	2
496-6008	REMOVE STR (BOX CULVERT)	LF	165.6
658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	4



- GENERAL NOTES:
- DESIGNED ACCORDING TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 9TH EDITION (2020) AND TXDOT BRIDGE DESIGN MANUAL (NOV 2021).
 - SEE MC-MD STD FOR CULVERT DETAIL.
 - FOR ANY DAMAGE OF CULVERTS DUE TO CONTRACTOR'S OPERATIONS, CONTRACTOR SHALL REPAIR BY THEIR OWN EXPENSES.
 - SEE PLAN LAYOUT SHEETS FOR MORE INFORMATION REGARDING METAL BEAM GUARD FENCE (MBGF).
 - DESIGN SPEED : 50 MPH (2R)
FUNCTIONAL CLASSIFICATION : RURAL MAJOR COLLECTOR
ADT = 1220(2022)
ADT = 1620(2042)

HL93 LOADING
INV-OPR RATINGS: 1.00/1.30* ~ *ASSUMED RATING

EXISTING NBI: 18-175-0-3090-01-001
PROPOSED NBI: 18-175-0-3090-01-005



Morgan Neill, P.E. 2/1/2023



FM 3041
BRIDGE CLASS CULVERT
TUPELO BRANCH
STA 102+59.18

H & V SCALE: 1" = 25' SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		113

DATE: 1/31/2023 1:16:21 PM
FILE: c:\tdot\p\onlinetx\d05\craiz_parker\0463963\FM 3041_BCC_LAYOUT_SHEET.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert No. Spans ~ Span X Height	Max Fill Height (Ft)	Applicable Box Culvert Standard (4)	Applicable Wingwall or End Treatment Standard	Skew Angle (0°, 15°, 30° or 45°)	Side Slope or Channel Slope Ratio (SL:1)	T Culvert Top Slab Thickness (In)	U Culvert Wall Thickness (In)	C Estimated Curb Height (Ft)	Hw Height of Wingwall (Ft)	A Curb to End of Wingwall (Ft)	B Offset of End of Wingwall (Ft)	Lw Length of Longest Wingwall (Ft)	Ltw Culvert Toewall Length (Ft)	Atw Anchor Toewall Length (Ft)	Riprap Apron (CY)	Class "C" Conc (Curb) (CY) (2)	Class "C" Conc (Wingwall) (CY) (3)	Total Wingwall Area (SF)
102+59.18 (LT)	3 - 10' X 10'	5.4'	MC - 10-7	PW - 1	0°	3:1	8"	7"	2.000'	12.667'	N/A	N/A	38.00'	32.333	N/A	0.0	2.4	74.6	963
102+59.18 (RT)	3 - 10' X 10'	5.4'	MC - 10-7	PW - 1	0°	3:1	8"	7"	2.000'	12.667'	N/A	N/A	38.00'	32.333	N/A	0.0	2.4	74.6	963

NOTES:

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets; 30° maximum for safety end treatment

SL:1 = Horizontal : 1 Vertical

- Side slope at culvert for flared or straight wingwalls.
- Channel slope for parallel wingwalls.
- Slope must be 3:1 or flatter for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)


B = Offset of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)

Atw = Length of anchor toewall (applicable to safety end treatment only)
 Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt.
 Area for four wingwalls (two structure ends) if Both.

- 1 Round the wall heights shown to the nearest foot for bidding purposes.
- 2 Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class S concrete is required for the top slab of the culvert, also provide Class S concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.
- 3 Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.
- 4 Regardless of the type of culvert shown on this sheet, the Contractor has the option of furnishing cast-in-place or precast culverts unless otherwise shown elsewhere on the plans. If the Contractor elects to provide culverts of a different type than those shown on this sheet, it is the Contractor's responsibility to make the necessary adjustments to the dimensions and quantities shown.




Morgan Neill, P.E. 2/11/2023

												Bridge Division Standard	
<h2>BOX CULVERT SUPPLEMENT WINGS AND END TREATMENTS</h2>													
<h3>BCS</h3>													
FILE:	bcsstde1-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT								
©TxDOT	February 2020	CONT	SECT	JOB		HIGHWAY							
REVISIONS		3090	01	012		FM 3041							
		DIST	COUNTY			SHEET NO.							
		DAL	Navarro			114							


DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/11/18
FILE: DOCUMENT NAME




TYPICAL SECTION


Used for curbs over 1'-0" to 5'-0"




BARS V (#5)
Spaced at 12" Max



BARS L (#5)
Spaced at 12" Max



OPTIONAL BARS L (#5)
Spaced at 12" Max



BARS U (#4)
Spaced at 12" Max

- ① "C" is equal to the culvert top slab thickness. For precast boxes with slabs less than 8" thick, see SCP-MD standard for additional details.
- ② Adjust normal culvert slab bars as necessary to clear obstructions.
- ③ Place bars L as shown. Tilt hook as necessary to maintain cover.
- ④ Place normal culvert curb bars H(#4) as shown. Adjust as necessary to clear obstructions.
- ⑤ Additional bars H(#4) as required to maintain 12" Max spacing.
- ⑥ Replace normal culvert curb bars K with one bar U and two bars V as shown spaced at 12" Max. Adjust length of bars V as necessary to maintain clear cover.
- ⑦ Optional bars L are to be used only for precast box culverts with 3'-0" closure pour.
- ⑧ Quantities shown are for Contractor's information only. Quantities are per linear foot of curb length. The value in table can be interpolated for intermediate values of curb height, "C". Quantity includes bars K (when applicable).

TABLE OF ESTIMATED CURB QUANTITIES ⑧		
Curb Height "C"	Conc (CY/LF)	Reinf Steel (Lb/LF)
1'-0"	0.037	10.4
1'-6"	0.056	14.5
2'-0"	0.074	15.6
2'-6"	0.093	18.0
3'-0"	0.111	19.0
3'-6"	0.130	21.3
4'-0"	0.148	22.4
4'-6"	0.167	24.8
5'-0"	0.185	25.9

CONSTRUCTION NOTES:
Adjust reinforcing steel as necessary to provide 1/4" cover.
For vehicle safety, top of the curb must not project more than 3" above the finished grade.

MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide galvanized reinforcing steel if required elsewhere in the plans.
Provide Class "C" concrete (f'c = 3,600 psi) minimum for curbs.
Provide bar laps, where required, as follows:
· Uncoated or galvanized ~ #4 = 1'-8" Min

GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications.
These extended curb details have sufficient strength to allow for future retrofit of Type T631 or T631LS railing. These details are suitable for use with PR11, PR22 and PR3 type rails. These details are not suitable for the mounting of other rail types. For new construction using T631 or T631LS railing, use the T631-CM standard.
This Curb is considered as part of the Box Culvert for payment.

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bar dimensions shown are out-to-out of bar.

Bridge Division Standard

EXTENDED CURB DETAILS

FOR BOX CULVERTS WITH CURBS OVER 1'-0" TO 5'-0" TALL

ECD

FILE: ecdstd1-20.dgn	DN: GAF	CK: TxDOT	DW: TxDOT	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
DIST	COUNTY		SHEET NO.	
DAL	Navarro		115	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME

TABLE OF DIMENSIONS AND REINFORCING STEEL
(Wings for one structure end)




Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings)		Estimated Quantities per ft of Toewall (1-toewall)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

TABLE OF WINGWALL REINFORCING
(2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

TABLE OF TOEWALL REINFORCING

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



WING DIMENSION FORMULAS:
(All values are in feet.)

Hw = H + T + C
 Lw = (Hw) (SL) + cosine (θ) for Type PW-1
 = (Hw - 1') (SL) + cosine (θ) for Type PW-2 and Hw 4'
 = (Hw - 0.5') (SL) + cosine (θ) for Type PW-2 and Hw 4'








For cast-in-place culverts:
 Ltw = [(N) (S) + (N + 1) (U)] + cosine (θ)

For precast culverts:
 Ltw = [(N) (2U + S) + (N - 1) (0.5')] + cosine (θ)
 Total Wingwall Area (two wings ~ SF)
 = (2)(Hw)(Lw) for Type PW-1
 = (2)(Hw)(Lw) - 6 SF for Type PW-2 and Hw 4'
 = (2)(Hw)(Lw) - 1.5 SF for Type PW-2 and Hw 4'

Hw = Height of wingwall
 Lw = Length of wingwall
 Ltw = Culvert toewall length
 N = Number of culvert spans
 SL:1 = Channel slope ratio. (horizontal: 1 vertical, usual value is 2:1)
 θ = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.

- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"
For 30° skew ~ 2"
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.



DESIGNER NOTES:
 Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall. Type PW-2 can only be used for applications without a railing mounted to the wingwall.

MATERIAL NOTES:
 Provide Class C concrete (f'c=3,600 psi).
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel if required elsewhere in the plans.

GENERAL NOTES:
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information. Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.

Texas Department of Transportation Bridge Division Standard

CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2

PW

FILE: pwstd01-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
REVISIONS	CONTRACT	SECTION	JOB	HIGHWAY
	3090 01	012	FM 3041	
DIST	COUNTY	SHEET NO.		
DAL	Navarro	116		

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/4
FILE: DOCUMENT NAME

BOX DATA

SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) ^②							① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8	
10	4	10	10	10	< 2	-	0.33	0.34	0.27	0.24	0.24	0.24	0.24	16.5
10	4	10	10	10	2 < 3	58	0.38	0.35	0.30	0.24	-	-	-	16.5
10	4	10	10	10	3 - 5	53	0.31	0.28	0.27	0.24	-	-	-	16.5
10	4	10	10	10	10	52	0.36	0.32	0.33	0.24	-	-	-	16.5
10	4	10	10	10	15	52	0.47	0.42	0.43	0.24	-	-	-	16.5
10	4	10	10	10	20	52	0.61	0.54	0.55	0.24	-	-	-	16.5
10	4	10	10	10	25	52	0.75	0.67	0.68	0.24	-	-	-	16.5
10	5	10	10	10	< 2	-	0.30	0.36	0.30	0.24	0.24	0.24	0.24	17.5
10	5	10	10	10	2 < 3	58	0.35	0.39	0.34	0.24	-	-	-	17.5
10	5	10	10	10	3 - 5	52	0.28	0.31	0.30	0.24	-	-	-	17.5
10	5	10	10	10	10	52	0.33	0.35	0.36	0.24	-	-	-	17.5
10	5	10	10	10	15	47	0.42	0.46	0.47	0.24	-	-	-	17.5
10	5	10	10	10	20	47	0.55	0.59	0.61	0.24	-	-	-	17.5
10	5	10	10	10	25	47	0.68	0.73	0.75	0.24	-	-	-	17.5
10	6	10	10	10	< 2	-	0.28	0.38	0.33	0.24	0.24	0.24	0.24	18.5
10	6	10	10	10	2 < 3	58	0.32	0.42	0.37	0.24	-	-	-	18.5
10	6	10	10	10	3 - 5	53	0.26	0.34	0.33	0.24	-	-	-	18.5
10	6	10	10	10	10	52	0.30	0.38	0.39	0.24	-	-	-	18.5
10	6	10	10	10	15	47	0.39	0.49	0.51	0.24	-	-	-	18.5
10	6	10	10	10	20	47	0.50	0.63	0.65	0.24	-	-	-	18.5
10	6	10	10	10	25	47	0.61	0.78	0.80	0.24	-	-	-	18.5
10	7	10	10	10	< 2	-	0.25	0.40	0.36	0.24	0.24	0.24	0.24	19.5
10	7	10	10	10	2 < 3	58	0.30	0.45	0.40	0.24	-	-	-	19.5
10	7	10	10	10	3 - 5	58	0.24	0.36	0.35	0.24	-	-	-	19.5
10	7	10	10	10	10	52	0.28	0.40	0.42	0.24	-	-	-	19.5
10	7	10	10	10	15	47	0.36	0.52	0.54	0.24	-	-	-	19.5
10	7	10	10	10	20	47	0.46	0.67	0.69	0.24	-	-	-	19.5
10	7	10	10	10	25	47	0.56	0.82	0.85	0.24	-	-	-	19.5
10	8	10	10	10	< 2	-	0.24	0.41	0.38	0.24	0.24	0.24	0.24	20.5
10	8	10	10	10	2 < 3	64	0.27	0.47	0.43	0.24	-	-	-	20.5
10	8	10	10	10	3 - 5	58	0.24	0.38	0.38	0.24	-	-	-	20.5
10	8	10	10	10	10	52	0.26	0.42	0.44	0.24	-	-	-	20.5
10	8	10	10	10	15	47	0.34	0.54	0.57	0.24	-	-	-	20.5
10	8	10	10	10	20	47	0.43	0.69	0.72	0.24	-	-	-	20.5
10	9	10	10	10	< 2	-	0.24	0.42	0.41	0.24	0.24	0.24	0.24	21.5
10	9	10	10	10	2 < 3	70	0.26	0.50	0.46	0.24	-	-	-	21.5
10	9	10	10	10	3 - 5	64	0.24	0.40	0.40	0.24	-	-	-	21.5
10	9	10	10	10	10	58	0.25	0.43	0.46	0.24	-	-	-	21.5
10	9	10	10	10	15	52	0.32	0.56	0.59	0.24	-	-	-	21.5
10	9	10	10	10	20	47	0.40	0.71	0.75	0.24	-	-	-	21.5
10	10	10	10	10	< 2	-	0.24	0.44	0.44	0.24	0.24	0.24	0.24	22.5
10	10	10	10	10	2 < 3	79	0.25	0.52	0.48	0.24	-	-	-	22.5
10	10	10	10	10	3 - 5	70	0.24	0.42	0.43	0.24	-	-	-	22.5
10	10	10	10	10	10	64	0.24	0.44	0.48	0.24	-	-	-	22.5
10	10	10	10	10	15	52	0.30	0.57	0.61	0.24	-	-	-	22.5
10	10	10	10	10	20	52	0.38	0.73	0.77	0.24	-	-	-	22.5

① For box length = 8'-0"


② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.



CORNER OPTION "A"


CORNER OPTION "B"

FILL HEIGHT 2 FT AND GREATER



SECTION A-A

(Showing top and bottom slab joint reinforcement.)



CORNER OPTION "A"

CORNER OPTION "B"

FILL HEIGHT LESS THAN 2 FT

④ Length is equal to spacing of longitudinal reinforcing plus 2". (10" Min) (Typ)

MATERIAL NOTES:

Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.
Provide Class H concrete ($f'c = 5,000$ psi).

GENERAL NOTES:


Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.
See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.
In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

HL93 LOADING


		Bridge Division Standard	
<h2>SINGLE BOX CULVERTS PRECAST 10'-0" SPAN</h2>			
<h3>SCP-10</h3>			
FILE: scp10sts-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT	SECT	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY		SHEET NO.
DAL	Navarro		117

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/12/19
FILE: DOCUMENT NAME




MULTIPLE UNIT PLACEMENT



SECTION B-B




DETAIL "A" (13)




WINGWALL CONNECTION

(Also applies to safety end treatment.)




SECTION THRU TOP SLABS LESS THAN 8"




SECTION THRU CURB

QUANTITIES PER FOOT OF CURB (10)	
Reinforcing Steel	4.12 Lb
Concrete	0.037 CY



BARS C (#4)
(Spa = 1'-0" Max)




BARS K (#4)
(Spa = 1'-0" Max)
(Length = 4'-2")

- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail, bicycle rail, or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- Extend curb, wingwall, or safety end treatment reinforcing into concrete closure. Bend or trim, as necessary, any reinforcing that does not fit into closure area.
- Provide a 3'-0" Min cast-in-place concrete closure. Break back boxes in the field or cast boxes short. Provide bands of reinforcing in the closure that are the same size and spacing as in the precast box section. Provide #4 longitudinal reinforcement spaced at 12 inches Max within the closure. Except where shown otherwise, construct the cast-in-place closure flush with the inside and outside faces of the precast box section.
- For multiple unit placements, adjust the length of the closure for the interior walls as necessary. Provide a 3'-0" Min cast-in-place closure in the top slab, bottom slab, and exterior wall. See Section B-B detail when interior walls are cast full length.
- Extend precast box reinforcing a minimum of 1'-0" into concrete closure (Typ).
- Place bands of reinforcing matching the inside and outside face reinforcing in the gaps of the top and bottom slabs. Place a band matching the outside face reinforcing of the wall in the gaps of the walls (placed in the outside face only). Tack weld the bands to the exposed reinforcing at each point of contact.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- Cement stabilized backfill between boxes is considered part of the box culvert for payment.
- All curb concrete and reinforcing is considered part of the box culvert for payment.
- Any additional concrete and reinforcing required for the closures will be considered subsidiary to the box culvert for payment.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- For multiple unit placement with overlay, with 1 to 2 course surface treatment, or with the top slab as the final riding surface, provide wall closure as shown in Detail "A".
- This dimension may be increased with approval of the Engineer to allow the precast boxes to be tunneled or jacked in accordance with Item 476, "Jacking, Boring, or Tunneling Pipe or Box". No payment will be made for any additional material in the gap between adjacent boxes.


MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide ASTM A1064 welded wire reinforcement.
Provide Class C concrete (f_c = 3,600 psi) for the closures.
Provide cement stabilized backfill meeting the requirements of Item 400, "Excavation and Backfill for Structures."
Any additional concrete required for the closures will be considered subsidiary to the box culvert.

GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications.
Refer to the Single Box Culverts Precast (SCP) standard sheets for details and notes not shown.
Chamfer the bottom edge of the top slab closure 3 inches at culvert closure ends.


Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bars dimensions are out-to-out of bars.



ANGLE DETAIL



SECTION A-A



PLAN OF SKEWED ENDS









(Showing multi-box placement.)

HL93 LOADING

		Bridge Division Standard	
BOX CULVERTS PRECAST MISCELLANEOUS DETAILS			
SCP-MD			
FILE: scpmdsts-20.dgn	DN: GAF	CK: LMW	DW: BWH/TXDOT
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	113	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
129	1	M3-4 M1-6R	 	24x12 24x24	x		10BWG	1	SA	P	
	2	R2-1		24x30	x		10BWG	1	SA	P	
	3	D1-1		84x18	x		10BWG	1	SA	T	
	4	M2-1 M1-6R	 	21x15 24x24	x		10BWG	1	SA	P	
	5	R1-1		36x36	x		10BWG	1	SA	P	
130	1	W1-2L		36x36	x		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).

SHEET 1 OF 8



SUMMARY OF SMALL SIGNS









SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	119	

DATE: 2023/01/18
 FILE: DOCUMENT NAME

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
131	1	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	2	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	3	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	4	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS









SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	120	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2023/01/18
 FILE: DOCUMENT NAME

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
131	5	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	6	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	7	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	8	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



Traffic Operations Division Standard

SUMMARY OF SMALL SIGNS







SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	121	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2023/01/18
 FILE: DOCUMENT NAME

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
131	9	W1-2R		36x36	x		10BWG	1	SA	P	
	10	R1-1		36x36	x		10BWG	1	SA	P	
	11	R1-1		36x36	x		10BWG	1	SA	P	
	12	W1-2R		36x36	x		10BWG	1	SA	P	
	13	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS









SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	122	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2023/01/18
 FILE: DOCUMENT NAME

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
131	14	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	15	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
132	1	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	2	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).











SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	123	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
132	3	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	4	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
5		W1-2L		36x36	x		10BWG	1	SA	P	
6		M3-2		24x24	x		10BWG	1	SA	P	
		M1-6R									
		D10-7oT D10-7oT									

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS









SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	124	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2023/01/18
 FILE: DOCUMENT NAME

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
135	1	W1-2L		36x36	x		10BWG	1	SA	P	
		W13-1P		18x18	x						
	2	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	3	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						
	4	W1-8L		24x30	x		10BWG	1	SA	P	
		W1-8R		24x30	x						

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS









SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01		012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	125	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2023/01/18
 FILE: DOCUMENT NAME

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
135	5	W1-8L		24X30	x		10BWG	1	SA	P	
		W1-8R		24X30	x						
	6	W1-8L		24X30	x		10BWG	1	SA	P	
		W1-8R		24X30	x						
	7	W1-8L		24X30	x		10BWG	1	SA	P	
		W1-8R		24X30	x						
	8	W1-8L		24X30	x		10BWG	1	SA	P	
		W1-8R		24X30	x						

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS




SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
4-16	DIST	COUNTY	SHEET NO.	
8-16	DAL	Navarro	126	

CK: DW: CK: DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/11/2023




FM 3041
PAVEMENT MARKINGS & SIGNING LAYOUT

SHEET 1 OF 7




CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 127

DATE: 1/31/2023 1:17:59 PM
FILE: c:\tdot\ipw_onlinetx\dot5\craig_parker\0463964\FM 3041_PM & S_PLAN 1.dgn

CK: DW: CK: DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/1/2023

Texas Department of Transportation


FM 3041
PAVEMENT MARKINGS & SIGNING LAYOUT

SHEET 2 OF 7



CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 128

DATE: 1/31/2023 1:18:14 PM
FILE: c:\tdot\ipw_onlinetx\dot5\craig_parker\0463964\FM 3041_PM & S_PLAN 2.dgn

CK:
DW:
CK:
DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/11/2023




FM 3041
PAVEMENT MARKINGS & SIGNING LAYOUT

SHEET 3 OF 7




CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		NAVARRO	SHEET NO. 129

DATE: 1/31/2023 1:18:27 PM
FILE: c:\tdot\ipw_onlinetx\d05\craig_parker\00463964\FM_3041_PM & S_PLAN_3.dgn

CK: DW: CK: DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/1/2023




FM 3041
PAVEMENT MARKINGS & SIGNING LAYOUT

SHEET 4 OF 7




CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 130

DATE: 1/31/2023 1:18:41 PM
FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\0463964\FM_3041_PM & S_PLAN 4.dgn

CK: DW: CK: DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/1/2023



FM 3041
PAVEMENT MARKINGS & SIGNING LAYOUT

SHEET 5 OF 7




CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 131

DATE: 1/31/2023 1:18:53 PM
FILE: c:\tdot\ipw_onlinet\m\neill\tdot5\craig_parker\0463964\FM 3041_PM & S_PLAN 5.dgn

CK: DW: CK: DW: CK: DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/1/2023




FM 3041
PAVEMENT MARKINGS & SIGNING

SHEET 6 OF 7




CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST		COUNTY	SHEET NO.
DAL		Navarro	132

DATE: 1/31/2023 1:19:06 PM
FILE: c:\tdot\pw_onlinetx\dot5\craig_parker\0463964\FM_3041_PM & S_PLAN 6.dgn

CK:
DW:
CK:
DW:



- LEGEND:
- SIGN POST
 - NEW SIGN TO BE INSTALLED
 - TRAVEL LANE & DIRECTION



Morgan Neill, P.E. 2/1/2023




FM 3041
PAVEMENT MARKINGS & SIGNING

SHEET 7 OF 7


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DAL		Navarro	SHEET NO. 133

DATE: 1/31/2023 1:19:20 PM
FILE: c:\tdot\ipw_onlinetx\dot5\craig_parker\0463964\FM_3041_PMGSS_PLAN.7.dgn




D1-1 8in LT;
 1.5" Radius, 0.5" Border, White on Green;
 Standard Arrow Custom 12.0" X 7.1" 180°; "Chatfield", ClearviewHwy-3-W;

SHEET 1 SIGN 3



No border, White on Green;
 [6] ClearviewHwy-4-W;
 [1] ClearviewHwy-4-W;
 [0] ClearviewHwy-4-W;

SHEET 4 SIGN 6



Mark A. Aboso, P.E. 01/18/2023
 Signature of Registrant Date

 © 2023			
<h2>GUIDE SIGN DETAILS</h2>			
SCALE: NTS		SHEET 1 OF 1	
DESIGN/CK	FED. RD. DIV. NO.	FEDERAL-AID PROJECT NUMBER	HIGHWAY NO.
CHECK MAA	6	SEE TITLE SHEET	FM 3041
CHECK MA	STATE	DISTRICT	COUNTY
CHECK MM	TEXAS	DAL	NAVARRO
CHECK BA	CONTROL	SECTION	JOB
	3090	01	012
			134

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	DEVICE	SINGLE	DOUBLE	INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX)	
								NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back	
SHEETING: Yellow, White or Red Type B or C reflective sheeting				SHEETING: Yellow, White or Red Type B or C Reflective Sheeting				INSTL OM ASSM (OM-XX) (XXXX)XXX (XX)	
NOTE: 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE: WC, YFLX, WFLX, GND				TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional	

OBJECT MARKERS									
DEVICE	Type 1 (OM-1)		Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4	
SHEETING	Yellow-Type B _{FL} or C _{FL} Sheeting		Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			Red -Type B _{FL} or C _{FL} Sheeting
POST TYPE	TWT		WC	WC	WFLX	TWT			TWT
MOUNT TYPE	WAS, WAP		GND	GND	GND, SRF	WAS, WAP			WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.
DEVICE	GF1	GF2	CTB	W1-8				W1-6	
SHEETING: Yellow, White, Red			MOUNTING HEIGHT: 4'-0" or 7'-0"				MOUNTING HEIGHT: 7'-0"		
NOTE: 1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			NOTE: 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).				NOTE: 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.		

Texas Department of Transportation
 Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION


D & OM(1)-20

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	012	FM 3041
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	DAL	Navarro	135	

DATE: 2022/09/07
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS	
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT
GND	GND	SRF	WAS	WAP	GF 1
<p>Ground Line</p> <p>2'-0" Usual</p>	<p>Reflective material</p> <p>Post</p> <p>Stub</p>	<p>Reflective material</p> <p>Post</p> <p>Base</p>	<p>12" Dia.</p> <p>12" 27" 30"</p>	<p>3" (Approx.)</p> <p>15" 17" 20"</p> <p>12" Dia.</p>	<p>Centerline of MBCF rail element</p>
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.	NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.		<p>Place Barrier Reflector on top or on side(s) of CTB.</p>



- GENERAL NOTES**
- Place delineators on a section of roadway at a consistent distance from the edge of pavement.
 - Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
 - When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
 - Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
 - Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
 - Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS

4'-0"

Pavement surface

Ground Line

NOTE
 Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN

7'-0"

Pavement surface

Ground Line

NOTE
 Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

DELINEATORS AND TYPE 2 OBJECT MARKERS

Approximately 4'-0"

Pavement surface

Ground Line

2'-0" to 8'-0" or in front of object being marked

See general notes 1, 2 and 3.

Texas Department of Transportation
 Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	012	FM 3041
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	DAL	Navarro	136	

20B


DATE: 2022/09/07
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND

	Bi-directional Delineator
	Delineator
	Sign



DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20


FILE: dom3-20.dgn	DW: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	012	FM 3041
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	DAL	Navarro	137	

DATE: 2022/09/07
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2022/09/07
FILE: DOCUMENT NAME

CROSSOVERS




DETAIL 1

FOR CULVERTS WITHOUT MBGF




DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES




DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4) -20

FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM	3041
3-15	DIST	COUNTY	SHEET NO.	
7-20	DAL	Navarro	138	


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**





D & OM(5) - 20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
7-20	DIST	COUNTY	SHEET NO.	
	DAL	Navarro	139	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




Object marker installed per manufacturer's recommendations.





BACK PANEL (OPTIONAL)



* Adjust to fit attenuator per manufacturer's recommendation, or as directed by the Engineer



OBJECT MARKERS SMALLER THAN 3 FT²




NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

NOTES

- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- Mounting should be flush with top of attenuator. Minimum size 96" x 24".




DATE: 2022/09/07
FILE: DOCUMENT NAME


		Traffic Safety Division Standard	
DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS D & OM(VIA) -20			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT	SECT	HIGHWAY
REVISIONS		3090 01	012
4-92 8-04		JOB	FM 3041
8-95 3-15		DIST	COUNTY
4-98 7-20		DAL	Navarro
			SHEET NO. 140
20G			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:





**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**





**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



YIELD LINES



**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**
 Based on Traveled Way and Pavement Widths
 for Undivided Roadways



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES

- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

GENERAL NOTES

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.


**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1)-22


FILE:	pm1-22.dgn	DN:	CK:	DW:	CK:
© TxDOT	REVISIONS	CONT	SECT	JOB	HIGHWAY
11-78	8-00 6-20				
8-95	3-03 12-22				
5-00	2-12	DIST	COUNTY	SHEET NO.	
					141

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS




**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY ROADWAYS**




DETAIL "A"

DETAIL "B"

DETAIL "C"





CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.
See Note 3.



**REFLECTORIZED PROFILE
PATTERN DETAIL**

USING REFLECTIVE PROFILE PAVEMENT MARKINGS

6" EDGE LINE, 6" CENTERLINE
OR 6" LANE LINE




NOTES


- Edge lines should typically be 6" wide and the materials shall be specified in the plans.
- Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS




**POSITION GUIDANCE USING
RAISED MARKERS
REFLECTORIZED PROFILE
MARKINGS
PM(2) - 22**

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS				
4-77	8-00	6-20		
4-92	2-10	12-22		
5-00	2-12			
DIST			COUNTY	SHEET NO.
				142

DATE: FILE:





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME




TWO LANE TWO-WAY ROADWAYS

CENTERLINE RUMBLE STRIPS




PROFILE VIEW




PLAN VIEW
OPTION 1

MILLED CENTERLINE RUMBLE STRIPS




PLAN VIEW
OPTION 2

RAISED CENTERLINE RUMBLE STRIPS



PLAN VIEW
OPTION 3

RAISED CENTERLINE RUMBLE STRIPS AND PREFORMED THERMOPLASTIC STRIPS



PLAN VIEW
OPTION 4

PROFILE CENTERLINE MARKINGS AND PREFORMED THERMOPLASTIC STRIPS

GENERAL NOTES

- This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
- Centerline and edgeline rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
- Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks.
- Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, and dimensions pavement markings and profile markings.
- Consideration should be given to noise levels when centerline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inch depth of milled rumble strip may be considered in these areas.
- Pavement markings must be applied over milled centerline rumble strips.

WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
- When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.

WHEN INSTALLING EDGELINE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

- See standard sheet RS(4).





CENTERLINE RUMBLE STRIPS ON TWO LANE TWO-WAY HIGHWAYS

RS(3) - 13

FILE: r's(3)-13.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041	
DIST	COUNTY	SHEET NO.		
DAL	Navarro	143		



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
FILE: DOCUMENT NAME




PROFILE VIEW
OPTION 1

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PROFILE VIEW
OPTION 2

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)





* This distance may vary based on width of shoulder




PROFILE VIEW
OPTION 3

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PROFILE VIEW
OPTION 4

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)



PLAN VIEW
OPTION 5

RAISED EDGELINE RUMBLE STRIPS



PLAN VIEW
OPTION 6

PROFILE EDGELINE MARKINGS

SHOULDER WIDTH TABLE		
EQUAL TO OR LESS THAN 2 FEET	GREATER THAN 2 FEET LESS THAN 4 FEET	EQUAL TO OR GREATER THAN 4 FEET
Option 1, 5 OR 6	Option 1, 2, 3 5 OR 6	Option 2, 4, 5 OR 6

GENERAL NOTES

- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
- See the table below for determining what options may be used for edgeline rumble strips.

WHEN INSTALLING MILLED DEPRESSION EDGELINE RUMBLE STRIPS:

- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Operations Division.
- Pavement markings can be applied over milled shoulder rumble strips to create an edgeline rumble stripe.
- Breaks in edgeline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections and driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are installed near residential areas, schools, churches, etc. A minimum of 3/8 inches depth of milled rumble strip may be considered in these areas.

- On roadways with high bicycle activity, consideration should be given before the installation of edgeline rumble strips. Things to consider include size of rumble strips, rumble strip material and location of rumble strips on the shoulder. If the designer determines that gaps are needed in the rumble strips due to bicycle use of the road, then follow the requirement shown in FHWA Technical Advisory T5040.39, or latest version. A detail of the spacing shall be included in the plans.

WHEN INSTALLING RAISED OR PROFILE EDGELINE RUMBLE STRIPS:

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edgeline when used as a rumble strip. The color of the button should match the color of the adjacent edgeline marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- Breaks in edgeline rumble strips using raised traffic buttons shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections and driveways with high usage of large trucks when installed on conventional highways.
- The minimum distance between the edgeline and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edgelines may substitute for buttons.

<p>EDGELINE RUMBLE STRIPS ON UNDIVIDED OR TWO LANE HIGHWAYS RS(4)-13</p>			
FILE: rs(4)-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT October 2013	CONT	SECT	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	144	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


Post Type
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)

Anchor Type
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))



Sign Mounting Designation
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))

REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT






To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION



No more than 2 sign posts should be located within a 7 ft. circle.



TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES



When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)




Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

CURB & GUTTER OR RAISED ISLAND



* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>




SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD(GEN) -08



© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		3090	01	012	FM 3041
		DIST	COUNTY		SHEET NO.
		DAL	NAVARRO		145

DATE: 1/31/2023 1:21:50 PM
 FILE: c:\txdot\pwworking\online\txdot5\craig.parker\0797839\SMD(GEN)-08.dgn


TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE
The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.



CONCRETE ANCHOR



Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE

- Foundation**
- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
 - The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
 - Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
 - Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
 - The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

ADDED DETAIL A FOR CLAMP BASE
10-2010

Texas Department of Transportation
Dallas District Standard

**SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM**

SMD(SLIP-1)-08(DAL)















© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
12-10 (DISTRICT)		3090	01	012	FM 3041
ADDED CLAMP BASE DETAIL FOR SLIP BASE INSTALLATION		DIST	COUNTY	SHEET NO.	
		DAL	Navarro	146	

26B

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023 1:22:13 PM
 FILE: c:\t\dot\p\online\txdot5\craig_parker\40797839\SMD(SLIP-2)-08.dgn



All dimensions are in english unless detailed otherwise.

SM RD SGN ASSM TY XXXX(1)XX(T) (* - See Note 12)

GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.











Texas Department of Transportation
 Traffic Operations Division

SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-2)-08

© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		3090	01	012	FM 3041
		DIST	COUNTY	SHEET NO.	
		DAL	NAVARRO	147	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023 1:22:25 PM
 FILE: c:\txdot\pww\online\txdot5\craig_parker\d07978339\SMD(SLIP-3)-08.dgn



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT

	SIGN DESCRIPTION		SUPPORT
	Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
60-inch YIELD sign (R1-2)		TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)	
48x16-inch ONE-WAY sign (R6-1)		TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)	
36x48, 48x36, and 48x48-inch signs		TY 10BWG(1)XX(T)	
48x60-inch signs		TY S80(1)XX(T)	
Warning	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)	
	48x60-inch signs	TY S80(1)XX(T)	
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)	
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	



SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM
 SMD(SLIP-3)-08



© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		3090	01	012	FM 3041
		DIST	COUNTY		SHEET NO.
		DAL	NAVARRO		148

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
 FILE: DOCUMENT NAME

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>


		<i>Traffic Operations Division Standard</i>	
<h2 style="margin: 0;">TYPICAL SIGN REQUIREMENTS</h2>			
<h3 style="margin: 0;">TSR(3) - 13</h3>			
FILE:	tsr3-13.dgn	DN:	TxDOT
© TxDOT	October 2003	CK:	TxDOT
REVISIONS	CONT	SECT	JOB
12-03 7-13	3090 01	012	FM 3041
9-08	DIST	COUNTY	SHEET NO.
	DAL	Navarro	149

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2022/09/07
 FILE: DOCUMENT NAME

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



TYPICAL SIGN REQUIREMENTS


TSR(4) - 13

FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		3090 01	012	FM	3041				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		DAL	Navarro	150					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	


CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT

NOTE

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.


The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5




EXIT ONLY PANEL


MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)



DIRECT APPLIED ATTACHMENT



SCREW ATTACHMENT




NUT/BOLT ATTACHMENT


NOTE:

- Sheeting for legend, symbols, and borders must be cut at panel joints.
- Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".

ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.



TYPICAL SIGN REQUIREMENTS

TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM	3041
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	DAL	Navarro	151	

DATE: 2022/09/07
 FILE: DOCUMENT NAME

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

3090-01-012 (FM 3041)

1.2 PROJECT LIMITS:

From: CHAMBERS CREEK

To: FM 1129

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 32.1478927, (Long) -96.4242339

END: (Lat) 32.1723613, (Long) -96.3835930

1.4 TOTAL PROJECT AREA (Acres): 36.02 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 26.0 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:

REHABILITATION OF EXISTING PAVEMENT AND
ADD SHOULDERS

1.7 MAJOR SOIL TYPES:

Soil Type	Description
LAMAR CLAY LOAM 3% TO 8% SLOPES	100% LAMAR CLAY, WELL DRAINED, MEDIUM RATE OF RUNOFF, HIGH EROSION POTENTIAL
BONHAM LOAM 1% TO 3% SLOPES	100% BONHAM LOAM, MODERATELY WELL DRAINED, HIGH RATE OF RUNOFF, MEDIUM EROSION POTENTIAL
BLUM LOAM 0% TO 1% SLOPES	100% BLUM LOAM, MODERATELY WELL DRAINED, MEDIUM RATE OF RUNOFF, LOW EROSION POTENTIAL
EXISTING VEGETATION IS GRASS WITH APPROXIMATELY 95% COVER.	

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

- Other: _____
- Other: _____
- Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: Sediment from placement of embankment material
- Other: _____
- Other: Concrete saw-cutting
- Other: _____
- Other: Concrete pouring and concrete washout
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
TUPELO BRANCH POST OAK BRANCH BURKE BRANCH AND ITS TRIBUTARY, AND TRIBUTARIES TO CHAMBERS CREEK (0814)	CHAMBERS CREEK ABOVE RICHLAND-CHAMBERS RESERVOIR (0814) [IMPAIRED BY BACTERIA IN WATER (RECREATION USE)]
No TMDLs or I-PLANS were identified.	

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT


- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:

MS4 Entity



Morgan Neill, P.E. 2/1/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3)

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
	3090-01-012			152
STATE	STATE DIST.	COUNTY		
TEXAS	DALLAS	NAVARRO		
CONT.	SECT.	JOB	HIGHWAY NO.	
3090	01	012	FM 3041	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

T / P

- Sediment Trap
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
 - Not required (<10 acres disturbed)
 - Required (>10 acres) and implemented.
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
- Required (>10 acres), but not feasible due to:
 - Available area/Site geometry
 - Site slope/Drainage patterns
 - Site soils/Geotechnical factors
 - Public safety
 - Other: _____

Alternate BMPs are provided in the SWP3 for equivalent sedimentation control.

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To
No BMPs will be left in place post construction.		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: Dampen areas of disturbed soil as needed to control dust

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: Avoid storing portable sanitary units or chemicals within 50 feet upgradient of a receiving water or drainage conveyance without adequate pollution controls.
- Other: Maintain roadways and adjacent properties free of project sedimentation and loose materials.

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Vegetated buffer will be protected for as long as feasible. However, construction vehicles will need to operate on the earthen ground next to the surface waters to replace/extend the culverts that carry those waters. See below for a list of sediment control measures that will be implemented in lieu of a buffer zone. Upon completion, disturbed stream banks will be re-stabilized with vegetation (where not otherwise hardscaped), as applicable to pre-construction conditions.

Type	Stationing	
	From	To
Unnamed Tributary to Burke Branch Rock Filter Dam Type 3 Silt Fence Silt Fence	35+45 RT 33+93 RT 33+61 LT	36+06 RT 37+31 RT 36+46 LT
Burke Branch Rock Filter Dam Type 3 Silt Fence Silt Fence	43+42 LT 41+73 RT 41+99 LT	44+30 LT 44+98 RT 47+42 LT
Post Oak Branch Rock Filter Dam Type 2 Silt Fence Silt Fence	97+18 LT 96+17 RT 97+21 LT	97+54 LT 98+69 RT 99+21 LT
Tupelo Branch Rock Filter Dam Type 3 Silt Fence Silt Fence	102+03 LT 100+60 RT 99+70 LT	103+17 LT 104+41 RT 103+44 LT
Unnamed Tributary to Chambers Creek Rock Filter Dam Type 2 Silt Fence Silt Fence	107+06 RT 105+39 RT 105+91 LT	107+41 RT 108+98 RT 108+93 LT
Unnamed Tributary to Chambers Creek Rock Filter Dam Type 3 Silt Fence Silt Fence	142+06 LT 140+66 RT 141+55 LT	142+55 LT 143+29 RT 147+15 LT

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:


- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.



Morgan Neill, P.E. 2/11/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3)



Sheet 2 of 2

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
	3090-01-012		153
STATE	STATE DIST.	COUNTY	
TEXAS	DALLAS	NAVARRO	
CONT.	SECT.	JOB	HIGHWAY NO.
3090	01	012	FM 3041

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act".
 No warranty of any kind is made by TxDOT for any purpose whatsoever.
 TxDOT assumes no responsibility for the conversion of this standard to other
 formats or for incorrect results or damage resulting from its use.

Notes To Designer:
 1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
 2. If additional space is needed for a numbered section, fence and adjust sections up or down
 as needed for proportioning and readability but do not relocate from its relative position.
 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to
 support actions needed.

Filled Out: XX/XX/XXXX
 Prepared By: Name/Section

I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.
 List adjacent MS 4 Operator(s) that receive discharges from this project. They need to be notified prior to construction activities.
 (Note: Leave blank only if no adjacent MS 4 Operator(s) are affected.)

No Action Required Required Action

Action Number:

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the ordinary High Water Mark except on approved temporary stream crossings or drill pads.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# 3(a)

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- Non-reportable crossings authorized under NWP 14:
- Culvert 1 - STA 35+34.92 - Unnamed Tributary to Burke Branch - Pond / Stream Impacts
 - Culvert 2 - STA 43+55.65 - Burke Branch - Stream Impacts
 - Culvert 4 - STA 97+35.4 - Post Oak Branch overflow - Stream Impacts
 - Bridge - STA 102+59.18 - Tupelo Branch - Stream Impacts
 - Culvert 6 - STA 117+60.45 - Unnamed Tributary to Chambers Creek - Stream Impacts
 - Culvert 7 - STA 142+29.94 - Unnamed Tributary to Chambers Creek - Stream Impacts

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices for applicable 401 General Conditions:
 (Note: If CORP Permit not required, do not check boxes.)

Erosion	Sedimentation	Post-Construction TSS
<input checked="" type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required Required Action

Action Number:

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751 & 752 in order to comply with requirements for invasive species, beneficial landscaping and tree/brush removal commitments.

No Action Required Required Action

Action Number:

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT.

No Action Required Required Action

Action Number:

1. The following species could occur in the project area:
 Monarch butterfly, southern crawfish frog, Woodhouse's toad, Sprague's Pipit, Western Burrowing Owl, American bumblebee, eastern spotted skunk, long-tailed weasel, swamp rabbit, eastern box turtle, and western box turtle. Follow the special note on the EPIC sheet and the BMPs listed below to protect these species.

2. Contractor to implement the following BMPs from Beneficial Management Practices: Avoiding, Minimizing, and Mitigating Impacts of Transportation Projects on State Natural Resources available at <https://ftp.txdot.gov/pub/txdot-info/env/toolkit/300-01-bmp.pdf>.
- Minimize impacts to wetland habitats and isolated ephemeral pools.
 - Section 2.6.1 Aquatic Amphibian and Reptile BMP (barrier fencing not required)
 - Section 2.6.2 Terrestrial Amphibian and Reptile BMP
 - Section 2.4.4 Insect Pollinator BMP
 - Section 2.2.1 Bird BMP
 - Section 1.4 Water Quality BMP
 - Section 1.2 Vegetation BMP

Follow Special Notes.

Special Notes:

- Avoid harming all wildlife species if encountered and allow them to safely leave the project site. Due diligence should be used to avoid killing or harming any wildlife species in the implementation of transportation projects.
- If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediated area, and contact the Engineer immediately.
- The Migratory Bird Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. The contractor would remove all old migratory bird nests from any structure or trees where work would be done from October 1 to February 15. In addition, the contractor would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, efforts to avoid adverse impacts on protected birds, active nests, eggs and/or young would be observed.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corp of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):
 Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Safety Data Sheets (SDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the SDS. In the event of a spill, take actions to mitigate the spill as indicated in the SDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canisters, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?

Yes No

If "No", then no further action is required.
 If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required Required Action

Action Number:

-
-
-

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required Required Action

Action Number:

-




ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		FM 3041
STATE	DISTRICT	County	
TEXAS	DALLAS	NAVARRO	
CONTROL	SECTION	JOB	SHEET NO.
3090	01	012	154

GENERAL NOTE:
 Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.


CK: DW: CK: DW: CK: DW:



BMP	A1	A2	A3	A4	A5	A6	A7	A8	A9	A10	A11	A12
INSTALL DATE												
REMOVE DATE												


- SW3P LEGEND
- SEDIMENT CONTROL FENCE
 - ROCK FILTER DAM (TY 2)
 - ROCK FILTER DAM (TY 3)
 - EROSION CONTROL LOG
 - CONSTRUCTION EXIT
 - DIRECTION OF FLOW

- NOTES:
- BMPs SHALL NOT BE INSTALLED ANY SOONER THAN TWO WEEKS PRIOR TO SOIL DISTURBING OR POTENTIAL POLLUTANT GENERATING ACTIVITIES IN THEIR CONTROL AREA.
 - PROTECT TREES AND THEIR ROOTS, IF ALL POSSIBLE. PRESERVE CREEKSIDE VEGETATION TO EXTENT PRACTICABLE.
 - REMOVE LITTER & CONSTRUCTION DEBRIS AS NEEDED OR AS DIRECTED BY THE ENGINEER. THIS WORK IS SUBSIDIARY TO VARIOUS EROSION CONTROL ITEMS (ITEM 506).
 - ADJUST BMPs AS NEEDED BASED ON ACTIVITIES AND SITE CONDITIONS, AND AS AUTHORIZED BY ENGINEER.
 - REMOVE SEDIMENT FROM BMP WHEN IT REDUCES BMP'S CAPACITY BY 40%. ALWAYS PROVIDE CONSISTENT DRAINAGE.
 - CONTRACTOR TO PLACE AND MAINTAIN SW3P MEASURES APPLICABLE TO EACH PHASE OF CONSTRUCTION.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - SEE PROPOSED TYPICAL SECTIONS FOR LIMITS OF SOIL DISTURBANCE AND FINAL STABILIZATION PLANS.




BMP	B1	B2	B3	B4	B5	B6	B7	B8
INSTALL DATE								
REMOVE DATE								

DATE DISTURBED: _____
DATE STABILIZED: _____



Morgan Neill, P.E. 2/1/2023




FM 3041
SW(3)P LAYOUT

SHEET 1 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	155	

DATE: 1/31/2023 1:23:44 PM
FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463965\FM_3041_SW3P_SHEETS-1.dgn


CK: DW: CK: DW:



BMP	C1	C2	C3	C4	C5	C6	C7
INSTALL DATE							
REMOVE DATE							
BMP	C8	C9	C10	C11	C12	C13	C14
INSTALL DATE							
REMOVE DATE							


- SW3P LEGEND
- SEDIMENT CONTROL FENCE
 - ROCK FILTER DAM (TY 2)
 - ROCK FILTER DAM (TY 3)
 - EROSION CONTROL LOG
 - CONSTRUCTION EXIT
 - DIRECTION OF FLOW

- NOTES:
- BMPs SHALL NOT BE INSTALLED ANY SOONER THAN TWO WEEKS PRIOR TO SOIL DISTURBING OR POTENTIAL POLLUTANT GENERATING ACTIVITIES IN THEIR CONTROL AREA.
 - PROTECT TREES AND THEIR ROOTS, IF ALL POSSIBLE. PRESERVE CREEKSIDE VEGETATION TO EXTENT PRACTICABLE.
 - REMOVE LITTER & CONSTRUCTION DEBRIS AS NEEDED OR AS DIRECTED BY THE ENGINEER. THIS WORK IS SUBSIDIARY TO VARIOUS EROSION CONTROL ITEMS (ITEM 506).
 - ADJUST BMPs AS NEEDED BASED ON ACTIVITIES AND SITE CONDITIONS, AND AS AUTHORIZED BY ENGINEER.
 - REMOVE SEDIMENT FROM BMP WHEN IT REDUCES BMP'S CAPACITY BY 40%. ALWAYS PROVIDE CONSISTENT DRAINAGE.
 - CONTRACTOR TO PLACE AND MAINTAIN SW3P MEASURES APPLICABLE TO EACH PHASE OF CONSTRUCTION.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - SEE PROPOSED TYPICAL SECTIONS FOR LIMITS OF SOIL DISTURBANCE AND FINAL STABILIZATION PLANS.




BMP	D1	D2	D3	D4	D5	D6	D7
INSTALL DATE							
REMOVE DATE							
BMP	D8	D9	D10	D11	D12	D13	
INSTALL DATE							
REMOVE DATE							

DATE DISTURBED: _____
DATE STABILIZED: _____



Morgan Neill, P.E. 2/1/2023



FM 3041
SW(3)P LAYOUT

SHEET 2 OF 7


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	156	

DATE: 1/31/2023 1:23:59 PM
FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\0463965\FM 3041_SW3P_SHEETS-2.dgn

CK:
DW:
CK:
DW:




- SW3P LEGEND
- SEDIMENT CONTROL FENCE
 - ROCK FILTER DAM (TY 2)
 - ROCK FILTER DAM (TY 3)
 - EROSION CONTROL LOG
 - CONSTRUCTION EXIT
 - DIRECTION OF FLOW




BMP	E1	E2	E3	E4	E5	E6
INSTALL DATE						
REMOVE DATE						
BMP	E7	E8	E9	E10	E11	E12
INSTALL DATE						
REMOVE DATE						

- NOTES:
- BMPs SHALL NOT BE INSTALLED ANY SOONER THAN TWO WEEKS PRIOR TO SOIL DISTURBING OR POTENTIAL POLLUTANT GENERATING ACTIVITIES IN THEIR CONTROL AREA.
 - PROTECT TREES AND THEIR ROOTS, IF ALL POSSIBLE. PRESERVE CREEKSIDE VEGETATION TO EXTENT PRACTICABLE.
 - REMOVE LITTER & CONSTRUCTION DEBRIS AS NEEDED OR AS DIRECTED BY THE ENGINEER. THIS WORK IS SUBSIDIARY TO VARIOUS EROSION CONTROL ITEMS (ITEM 506).
 - ADJUST BMPs AS NEEDED BASED ON ACTIVITIES AND SITE CONDITIONS, AND AS AUTHORIZED BY ENGINEER.
 - REMOVE SEDIMENT FROM BMP WHEN IT REDUCES BMP'S CAPACITY BY 40%. ALWAYS PROVIDE CONSISTENT DRAINAGE.
 - CONTRACTOR TO PLACE AND MAINTAIN SW3P MEASURES APPLICABLE TO EACH PHASE OF CONSTRUCTION.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - SEE PROPOSED TYPICAL SECTIONS FOR LIMITS OF SOIL DISTURBANCE AND FINAL STABILIZATION PLANS.



BMP	F1	F2	F3	F4	F5	F6	F7	F8	F9
INSTALL DATE									
REMOVE DATE									

DATE DISTURBED: _____
DATE STABILIZED: _____



Morgan Neill, P.E. 2/1/2023

Texas Department of Transportation

FM 3041


SW(3)P LAYOUT

SHEET 3 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	157	

DATE: 1/31/2023 1:24:14 PM
FILE: c:\tdot\pw_onlinet\tdot5\craig_parker\10463965\FM 3041_SW3P_SHEETS-3.dgn


CK:
DW:
CK:
DW:



BMP	G1	G2	G3	G4	G5	G6
INSTALL DATE						
REMOVE DATE						
BMP	G7	G8	G9	G10	G11	
INSTALL DATE						
REMOVE DATE						


- SW3P LEGEND
- SEDIMENT CONTROL FENCE
 - ROCK FILTER DAM (TY 2)
 - ROCK FILTER DAM (TY 3)
 - EROSION CONTROL LOG
 - CONSTRUCTION EXIT
 - DIRECTION OF FLOW

- NOTES:
- BMPs SHALL NOT BE INSTALLED ANY SOONER THAN TWO WEEKS PRIOR TO SOIL DISTURBING OR POTENTIAL POLLUTANT GENERATING ACTIVITIES IN THEIR CONTROL AREA.
 - PROTECT TREES AND THEIR ROOTS, IF ALL POSSIBLE. PRESERVE CREEKSIDE VEGETATION TO EXTENT PRACTICABLE.
 - REMOVE LITTER & CONSTRUCTION DEBRIS AS NEEDED OR AS DIRECTED BY THE ENGINEER. THIS WORK IS SUBSIDIARY TO VARIOUS EROSION CONTROL ITEMS (ITEM 506).
 - ADJUST BMPs AS NEEDED BASED ON ACTIVITIES AND SITE CONDITIONS, AND AS AUTHORIZED BY ENGINEER.
 - REMOVE SEDIMENT FROM BMP WHEN IT REDUCES BMP'S CAPACITY BY 40%. ALWAYS PROVIDE CONSISTENT DRAINAGE.
 - CONTRACTOR TO PLACE AND MAINTAIN SW3P MEASURES APPLICABLE TO EACH PHASE OF CONSTRUCTION.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - SEE PROPOSED TYPICAL SECTIONS FOR LIMITS OF SOIL DISTURBANCE AND FINAL STABILIZATION PLANS.




BMP	H1	H2	H3	H4	H5	H6	H7	H8
INSTALL DATE								
REMOVE DATE								

DATE DISTURBED: _____
DATE STABILIZED: _____



Morgan Neill, P.E. 2/11/2023




FM 3041
SW(3)P LAYOUT

SHEET 4 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	158	

DATE: 1/31/2023 1:24:27 PM
FILE: c:\tdot\pw_onlinet\dot5\craig_parker\0463965\FM_3041_SW3P_SHEETS-4.dgn


DW: CK: DW: CK: DW: CK:




BMP	K1	K2	K3	K4	K5	K6	K7	K8
INSTALL DATE								
REMOVE DATE								

- SW3P LEGEND
- SEDIMENT CONTROL FENCE
 - ROCK FILTER DAM (TY 2)
 - ROCK FILTER DAM (TY 3)
 - EROSION CONTROL LOG
 - CONSTRUCTION EXIT
 - DIRECTION OF FLOW

- NOTES:
- BMPs SHALL NOT BE INSTALLED ANY SOONER THAN TWO WEEKS PRIOR TO SOIL DISTURBING OR POTENTIAL POLLUTANT GENERATING ACTIVITIES IN THEIR CONTROL AREA.
 - PROTECT TREES AND THEIR ROOTS, IF ALL POSSIBLE. PRESERVE CREEKSIDE VEGETATION TO EXTENT PRACTICABLE.
 - REMOVE LITTER & CONSTRUCTION DEBRIS AS NEEDED OR AS DIRECTED BY THE ENGINEER. THIS WORK IS SUBSIDIARY TO VARIOUS EROSION CONTROL ITEMS (ITEM 506).
 - ADJUST BMPs AS NEEDED BASED ON ACTIVITIES AND SITE CONDITIONS, AND AS AUTHORIZED BY ENGINEER.
 - REMOVE SEDIMENT FROM BMP WHEN IT REDUCES BMP'S CAPACITY BY 40%. ALWAYS PROVIDE CONSISTENT DRAINAGE.
 - CONTRACTOR TO PLACE AND MAINTAIN SW3P MEASURES APPLICABLE TO EACH PHASE OF CONSTRUCTION.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - SEE PROPOSED TYPICAL SECTIONS FOR LIMITS OF SOIL DISTURBANCE AND FINAL STABILIZATION PLANS.



BMP	L1	L2	L3	L4	L5	L6	L7	L8
INSTALL DATE								
REMOVE DATE								
BMP	L9	L10	L11	L12	L13	L14	L15	
INSTALL DATE								
REMOVE DATE								



Morgan Neill, P.E. 2/1/2023



FM 3041
SW(3)P LAYOUT

SHEET 6 OF 7


CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	160	

DATE: 1/31/2023 1:24:55 PM
FILE: c:\tdot\pw_onlinetx\dot5\craig_parker\0463965\FM_3041_SW3P_SHEETS-6.dgn

CK:
DW:
CK:
DW:




- SW3P LEGEND
- SCF SEDIMENT CONTROL FENCE
 - RFD2 ROCK FILTER DAM (TY 2)
 - RFD3 ROCK FILTER DAM (TY 3)
 - EROSION CONTROL LOG
 - ▨ CONSTRUCTION EXIT
 - DIRECTION OF FLOW




- EROSION CONTROL LOG 15 LF (M10)
- EROSION NOTES:
- BMPs SHALL NOT BE INSTALLED ANY SOONER THAN TWO WEEKS PRIOR TO SOIL DISTURBING OR POTENTIAL POLLUTANT GENERATING ACTIVITIES IN THEIR CONTROL AREA.
 - PROTECT TREES AND THEIR ROOTS, IF ALL POSSIBLE. PRESERVE CREEKSIDE VEGETATION TO EXTENT PRACTICABLE.
 - REMOVE LITTER & CONSTRUCTION DEBRIS AS NEEDED OR AS DIRECTED BY THE ENGINEER. THIS WORK IS SUBSIDIARY TO VARIOUS EROSION CONTROL ITEMS (ITEM 506).
 - ADJUST BMPs AS NEEDED BASED ON ACTIVITIES AND SITE CONDITIONS, AND AS AUTHORIZED BY ENGINEER.
 - REMOVE SEDIMENT FROM BMP WHEN IT REDUCES BMP'S CAPACITY BY 40%. ALWAYS PROVIDE CONSISTENT DRAINAGE.
 - CONTRACTOR TO PLACE AND MAINTAIN SW3P MEASURES APPLICABLE TO EACH PHASE OF CONSTRUCTION.
 - SEE DAILY WORK REPORTS FOR INITIAL STABILIZATION TIME FRAMES.
 - SEE PROPOSED TYPICAL SECTIONS FOR LIMITS OF SOIL DISTURBANCE AND FINAL STABILIZATION PLANS.

BMP	M1	M2	M3	M4	M5	M6	M7	M8	M9
INSTALL DATE									
REMOVE DATE									
BMP	M10	M11	M12	M13	M14	M15	M16	M17	
INSTALL DATE									
REMOVE DATE									



BMP	N1	N2
INSTALL DATE		
REMOVE DATE		



Morgan Neill, P.E. 2/1/2023

Texas Department of Transportation

FM 3041


SW(3)P LAYOUT

SHEET 7 OF 7

CONT	SECT	JOB	HIGHWAY
3090	01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	Navarro	161	


DATE: 1/31/2023 1:25:10 PM
FILE: c:\tdot\ipw_onlinet\tdot5\craig_parker\0463965\FM_3041_SW3P_SHEETS-7.dgn

1/31/2023
 c:\txdot\pw_online\txdot5\craig.parker\d0797840\EC (1) - 16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1) - 16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	3090	01	012	FM 3041	
	DIST	COUNTY		SHEET NO.	
	DAL	NAVARRO		162	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023
 FILE: c:\txdot\pw_online\txdot5\craig.parker\d0797840\EC (2) - 16.dgn




FILTER DAM AT TOE OF SLOPE

(RFD1)




FILTER DAM AT SEDIMENT TRAP

(RFD1) OR (RFD2)




FILTER DAM AT CHANNEL SECTIONS


(RFD1) OR (RFD2) OR (RFD3)




PLAN VIEW




"V" SHAPE PLAN VIEW




PROFILE



SECTION C-C




SECTION B-B



TYPE 4 (SACK GABIONS)

(RFD4)



SECTION A-A

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4"
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC (2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	3090 01	012	FM 3041
	DIST	COUNTY	SHEET NO.
	DAL	NAVARRO	163

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023
 FILE: c:\txdot\pw_online\txdot5\craig_parker\d0797840\EC (3) - 16.dgn



PLAN VIEW




ELEVATION VIEW


CONSTRUCTION EXIT (TYPE 1)
 ROCK CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 1)

- The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
- The coarse aggregate should be open graded with a size of 4" to 8".
- The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other materials approved by the Engineer.
- The construction exit shall be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




ELEVATION VIEW


CONSTRUCTION EXIT (TYPE 2)
 TIMBER CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 2)

- The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50'.
- The treated timber planks shall be attached to the railroad ties with 1/2" x 6" min. lag bolts. Other fasteners may be used as approved by the Engineer.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The approach transitions shall be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- The construction exit should be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW



SECTION A-A
 CONSTRUCTION EXIT (TYPE 3)
 SHORT TERM


GENERAL NOTES (TYPE 3)

- The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
- The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES CONSTRUCTION EXITS EC(3)-16			
FILE: ec316	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041
	DIST	COUNTY	SHEET NO.
	DAL	NAVARRO	164

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023
 FILE: c:\txdot\p_w_online\txdot5\craig.parker\d0797840\EC (9) - 16.dgn



PLAN VIEW




SECTION A-A

EROSION CONTROL LOG DAM


CL-D

LEGEND

- CL-D EROSION CONTROL LOG DAM
- CL-BOC EROSION CONTROL LOG AT BACK OF CURB
- CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
- CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
- CL-DI EROSION CONTROL LOG AT DROP INLET
- CL-CI EROSION CONTROL LOG AT CURB INLET
- CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



REBAR STAKE DETAIL




PLAN VIEW



SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

SHEET 1 OF 3

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

Texas Department of Transportation
 Design Division Standard

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

EROSION CONTROL LOG


EC (9) - 16

FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	3090	01	012	FM 3041
	DIST	COUNTY	SHEET NO.	
	DAL	NAVARRO	165	

- GENERAL NOTES:**
1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
 3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
 4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
 5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
 6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
 7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
 8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
 9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023
 FILE: c:\txdot\pw_online\txdot5\craig.parker\d0797840\EC (9) - 16.dgn



**EROSION CONTROL LOGS ON SLOPES
 STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




**EROSION CONTROL LOGS ON SLOPES
 STAKE AND LASHING ANCHORING**

CL-SSL




STAKE AND TRENCHING ANCHORING DETAIL

CL-SST



STAKE AND LASHING ANCHORING DETAIL

CL-SSL



STAKE NOTCH DETAIL


LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

SHEET 2 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	NAVARRO	166	


DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 1/31/2023
 FILE: c:\txdot\pw_online\txdot5\craig.parker\d0797840\EC (9) - 16.dgn




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI




SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	3090 01	012	FM 3041
DIST	COUNTY	SHEET NO.	
DAL	NAVARRO	167	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

LEVELS DISPLAYED	1
PATH:	




Sign Dimensions

36" X 36"

- Letters - White
- Numbers - White
- Border - White
- Background - Blue

SW3P SIGN

TxDOT & Contractor
Construction Site Note
(CSN)



GENERAL NOTES:

- The alphabets and lateral spacing between letters and numerals shall conform with the "Texas Manual on Uniform Traffic Control Devices for Streets and Highways", (TMUTCD) latest edition, and the "Compliant Work Zone Traffic Control Devices List". Lateral spacing of text shall provide a balanced appearance. All materials shall conform to Department Specifications.
- Legend and border may be applied by reverse screening process with transparent colored ink, cut-out white reflective sheeting applied to colored background or combination thereof. Background shall be reflective sheeting Type C.
- CSN Sheets will be laminated and attached to the sign with an adhesive. Ensure sheets remain dry. (See Figure 1).
- SW3P Signs should be placed just inside the ROW line at the project limits at a readable height. It may be placed perpendicular or parallel to ROW line. If the sign cannot be placed outside the clear zone, it will be mounted per TMUTCD requirements.
- Final location of the signs will be as approved by the Engineer.




Figure 1

DEPARTMENT MATERIAL SPECIFICATIONS	
PLYWOOD SIGN BLANKS	DMS-7100
FLAT SURFACE REFLECTIVE SHEETING	DMS-8300
VINYL NON-REFLECTIVE DECAL SHEETING	DMS-8320

COLOR	USAGE	REFLECTIVE SHEETING OR OTHER MATERIAL
BLUE	BACKGROUND	TYPE C (FLUORESCENT PRISMATIC)
WHITE	LEGEND & BORDERS	VINYL NON-REFLECTIVE DECAL SHEETING

Texas Department of Transportation
DALLAS DISTRICT STANDARD

SW3P SIGN SHEET

FILE:	DW: I&D	CK:	DW:	CK:
©TxDOT 2016	DISTRICT	FEDERAL AID PROJECT		SHEET
	18			168
REVISION DATE: 10-16-15	COUNTY	CONTROL	SECT	JOB
	NAVARRO	3090	01	012

USER ID

SURFACE PREPARATION ITEM 160* TOPSOIL SY / ITEM 161* COMPOST MANUF. TOPSOIL (BOS) (4") SY

SURFACE PREPARATION

Prepare planting area surface BEFORE placing Topsoil, Compost, Fertilizer, Seed and/or Sod. Once project area has been completed to final lines, grade and compaction, remove objectionable materials from planting area surface and cultivate existing surface to a depth of 4 inches, unless otherwise specified or directed.

Refer to Items 160 and 161 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.

TOPSOIL NOTES:

- When Topsoil is specified under Item 160, use suitable material salvaged from the project ROW in accordance with Item 160 specifications, and/or secure additional good material from approved sources.
- Topsoil shall include only the top 6 inches of its native surface, and be easily cultivated, fertile, erosion-resistant and free of objectionable materials.
- Topsoil obtained from sites outside of the ROW must come from approved sources and have a pH between 5.5 and 8.5 su.
- Place Topsoil on pre-cultivated surface, spread to a uniform loose cover at thickness specified, and shape per plans. Water and roll the finished surface with a light roller or other suitable equipment per Item 160.3; do not over-compact.

COMPOST NOTES:

- When Compost Manufactured Topsoil (4") is specified under Item 161, use compost meeting all requirements of Item 161.2 and Table 1. Provide quality control (QC) documentation and obtain Engineer approval prior to compost delivery.
- Contractor shall provide tickets/invoices that document material type, quantity and placement for all compost delivered.
- Additional topsoil may be required to be imported to achieve the compost/topsoil mix ratio. Topsoil must meet Item 160 specifications.

APPLICATION OF COMPOST MANUFACTURED TOPSOIL (4")

AFTER Surface Preparation, uniformly spread a 1-inch layer of compost on-grade with 3 inches topsoil over pre-cultivated planting area. (25% compost and 75% topsoil = 1" compost and 3" topsoil.) Then mix compost and topsoil together by cultivating the compost into the topsoil (by till or disk) to a 4-inch (4") depth. Roll the finished surface with a light corrugated drum; do not over-compact.

FERTILIZER ITEM 166* FERTILIZER AC

SOIL ANALYSIS FOR FERTILIZER APPLICATION RATE

Unless otherwise stated in the plans, Contractor shall perform at least one soil analysis on each project before fertilization, and submit results to Engineer with recommended fertilizer rates based on soil analysis. Engineer may direct sample location(s). Soil analysis may be waived if both compost and sod are used on entire project.

FERTILIZER NOTES:

- Refer to Item 166 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Apply fertilizer BEFORE seeding, or AFTER placing sod.
- Use fertilizer containing nitrogen (N), phosphoric acid (P) and potash (K) nutrients, unless otherwise specified. At least 50% of the Nitrogen component shall be a slow-release sulfur-coated urea as described in Item 166.3. Do not apply more than 60 lbs Nitrogen per acre without Engineer concurrence.
- Deliver fertilizer in bags, clearly labeled to show contents, unless otherwise specified or approved prior to delivery. When non-bagged, loose fertilizer is approved, provide documentation for each load of material delivered, to validate authenticity of the material.
- Apply fertilizer uniformly, as a dry, granular material, essentially dust-free, and do not mix with water for application as a slurry.
- When both temporary and permanent seeding are specified for the same area, apply half of the required fertilizer before the temporary seeding operation and the other half before the permanent seeding operation.

SEEDING FOR EROSION CONTROL ITEM 164* DRILL SEEDING AC

RECOMMENDED PLANTING SEASON	PERMANENT RURAL SEED MIX ITEM 164 - DRILL SEEDING (PERM) (RURAL) (CLAY)	PERMANENT URBAN SEED MIX ITEM 164 - DRILL SEEDING (PERM) (URBAN) (CLAY)	TEMPORARY DRILL SEED MIX ITEM 164 - DRILL SEEDING (TEMP) (WARM OR COOL)
WARM SEASON Mar. 15th, April, May, June, July, August, Sept. 15th	Green Sprangletop (Van Horn) - 1.0 lbs/AC Sideoats Grama (Haskell) - 1.0 lbs/AC Texas Grama (Atascosa) - 1.0 lbs/AC Hairy Grama (Chaparral) - 0.4 lbs/AC Shortspike Windmillgrass (Welder) - 0.2 lbs/AC Little Bluestem (OK Select) - 0.8 lbs/AC Purple Prairie Clover (Cuero) - 0.6 lbs/AC Engelmann Daisy (Eldorado) - 0.75 lbs/AC Illinois Bundlesflower - 1.3 lbs/AC Awnless Bushsunflower (Plateau) - 0.2 lbs/AC	Green Sprangletop (Leptochloa dubia) - 0.3 lbs/AC Sideoats Grama (El Reno) (Bouteloua curtipendula) - 3.6 lbs/AC Buffalograss (Texoka) (Buchloe dactyloides) - 1.6 lbs/AC Bermudagrass (Cynodon dactylon) - 2.4 lbs/AC	Foxtail Millet (Setaria italica) - 34 lbs/AC
COOL SEASON Sept 16th, Oct, Nov, Dec, Jan, Feb, Mar 14th			Tall Fescue (Festuca arundinaceae) - 4.5 lbs/AC Western Wheatgrass (Agropyron smithii) - 5.6 lbs/AC Red Winter Wheat (Triticum aestivum) - 34 lbs/AC Cereal Rye - 34 lbs/AC

SEEDING NOTES:

- When seeding is specified under Item 164, refer to TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown. Materials and construction shall meet specifications.
- Conduct seeding upon completion of each applicable construction stage (dependent upon planting season requirements), without compensation for additional move-ins.
- Place seed AFTER preparing planting area surface. Refer to Surface Preparation detail in this sheet, as well as Topsoil Item 160 and Compost Manufactured Topsoil Item 161 when specified. Apply fertilizer per Item 166 BEFORE seeding, per specifications and this sheet, to help drill the fertilizer into the soil.
- When temporary grasses are well-established and more than 2 inches tall, mow planting area before seeding permanent grasses; mowing for this purpose will be subsidiary. When vegetation is not already well-established, cultivate planting area to a depth as described in Item 164.3, before temporary seeding and before permanent seeding.
- Seed material must be appropriate to the location, soil type and season. Use the seed mix species and pure live seed rates designated in Tables 1-4 of the TxDOT 2014 Standard Specifications* for Item 164, unless otherwise specified.
- All seed shall meet labeling, delivery, analysis, and testing requirements described in Item 164.2.1. Deliver seed in labeled, unopened bags or containers to Engineer prior to planting.
- Uniformly plant seed over the designated planting area, along the contour of slopes, and drill seed to a depth as described in Item 164.3.4.
- Hydroseeding may be allowed, when specified or Engineer concurs.
- Implement and continue Vegetative Watering per the schedule, rate and volume specified under Item 168.

TXDOT REFERENCE MATERIALS:

- "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES" 2014
- "A GUIDANCE TO ROADSIDE VEGETATION ESTABLISHMENT" 2004
- ONLINE TRAINING COURSE: MNT415 REVEGETATION DURING CONSTRUCTION
- DALLAS DISTRICT "VEGETATION ESTABLISHMENT GUIDELINES"

SODDING FOR EROSION CONTROL ITEM 162* BLOCK SOD (BERMUDA) SY

BLOCK OR ROLL SOD	COMMON NAME	BOTANICAL NAME
	Common Bermuda Grass	Cynodon dactylon

SODDING NOTES:

- Refer to Item 162 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Place sod between the average date of the last freeze in the Spring and 6 weeks before the average date of the first freeze in the Fall, per the Texas Almanac for the project area.
- Place sod only AFTER soil surface preparation is complete as detailed in this sheet. Dry soil may require pre-watering.
- Place all sod (blocks or rolls) within 24 hours of delivery to the site, and keep moist from the time it is dug up until it is planted. Sod with dried roots will not be accepted.
- Place sod with joints alternating on each row to prevent all joints from lining up, and place blocks firmly against adjacent blocks. Roll, tamp and trim sod per Item 162.3.
- Place fertilizer promptly AFTER sodding operation is complete in each area.
- Water sod immediately following placement, and continue Vegetative Watering per Item 168.

VEGETATIVE WATERING FOR ESTABLISHING SEED AND SOD ITEM 168* VEGETATIVE WATERING MG

SEASON (Usual Months)	RATE	TIME SCHEDULE	TOTAL WATER ESTIMATE
SPRING & FALL (March, April, May, October)	7,000 gallons/acre per working day	Vegetative watering for seed shall begin on the day after rainfall described below and continue for 60 consecutive working days; vegetative watering for sod shall begin on the day the sod is placed and continue for a minimum of 15 consecutive working days.	420,000 gallons/acre (60 working days)
SUMMER (June, July, August, September)	12,000 gallons/acre per working day		720,000 gallons/acre (60 working days)
WINTER (November through February)	1,000 gallons/acre per working day	Vegetative watering for seed and/or sod shall begin on the day after placement for 15 consecutive working days	15,000 gallons/acre (15 working days)

Notes: Rate and frequency may be adjusted, with the approval of the Engineer, to meet site conditions (especially with sod). For informational purposes only: 1,000 gallons equals 1 MG

VEGETATIVE WATERING NOTES:

- Refer to Item 168 of TxDOT 2014 Standard Specifications* for specifications, dimensions, volumes, and measurements that have been modified or not shown in plans. Materials and construction shall meet all specifications.
- Use clean water free of industrial waste and other substances harmful to vegetation growth, per Item 168.2.
- Use Vegetative Watering to keep the seed bed moist during germination; not to provide initial watering. After drill seeding, postpone watering operations until site receives at least 1/2-inch of natural rainfall in a single day. Delay watering operations for warm season grasses until soil temperature exceeds 70 degrees F.
- For sod, water immediately.
- All water distribution equipment shall be furnished and operated to provide water at a uniform and controllable rate. Use a metering device on all watering equipment.
- Evenly distribute water over entire area designated for seeding and/or sodding, using even spray patterns that do not disturb seed bed and/or dislodge seed from seed bed.
- Do not water between the hours of 12:00 p.m. and 6:00 p.m. when daytime temperatures exceed 95 degrees F.
- After initial establishment period, continue intermittent watering of newly established seed or sod at a rate of approximately 1-inch water/week, during summer months until end of contract.
- If 1/4-inch or more of rainfall occurs on site on any given working day, no vegetative watering will be needed on that working day. (Note: 1/4-inch rain equals 7,000 gallons of water per acre.)
- Should the Contractor fail to apply the specified amount of water within the time allowed, any seed or sod in poor condition shall be replaced, fertilized, and watered at Contractor's expense.

ROADSIDE MOWING ITEM 730* PROJECT MAINTENANCE AC

MOWING NOTES:

- During project construction, once seed is established, use mowing to promote permanent grasses by mowing any remaining temporary grasses.
- Also mow established turf and ROW grasses in designated areas of project limits as specified or directed by Engineer.
- Remove litter and debris prior to mowing.
- Do not mow on wet ground when soil rutting can occur.
- Hand-trim around obstructions and stormwater control devices as needed.
- Maintain paved surfaces free of tracked soils and clipped vegetation.

SEQUENCE OF WORK:

- CULTIVATE SURFACE SOIL.
- PREPARE / PLACE TOPSOIL, OR
- PREPARE / PLACE COMPOST MANUFACTURED TOPSOIL.
- APPLY FERTILIZER AND THEN PLACE SEEDING, OR
- PLACE SOD AND THEN APPLY FERTILIZER.
- CONDUCT VEGETATIVE WATERING.
- CONDUCT ROADSIDE MOWING, AS DIRECTED.



VEGETATION ESTABLISHMENT SHEET
(DALLAS DISTRICT)

TEMPLATE REVISION DATE: 02/21/19

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CPB	6	(See Title Sheet)		FM 3041
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	DALLAS	NAVARRO	
CHECK	CONTROL	SECTION	JOB	169
	3090	01	012	

DATE