STATE OF TEXAS DEPARTMENT OF TRANSPORATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENTS

FEDERAL AID PROJECT NO. F 2023(606)
HIGHWAY SAFETY IMPROVEMENT PROJECT TASK ORDER NO. 3

NUECES COUNTY, TEXAS

NET LENGTH OF PROJECT = 5,900 FT. (1.120 MI)

LIMITS: EVERHART ROAD BETWEEN S. SHEA PARKWAY AND HOLLY ROAD

(CSJ-0916-35-238) 0.30 MILES

GOLLIHAR ROAD BETWEEN HELEN STREET AND DEVON DRIVE


(CSJ-0916-35-241) 0.13 MILES

McARDLE ROAD BETWEEN NILE DRIVE AND CLARE DRIVE

(CSJ-0916-35-242) 0.58 MILES

S. STAPLES STREET BETWEEN DODY STREET AND DRIFTWOOD PLACE

(CSJ-0916-35-246) 0.11 MILES



EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE

NOTE: SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL PROJECTS (FORM FHWA 1273, JULY 2022)

INDEX OF SHEETS

NDLA OI	SHLLIS	DECIGHEDED A COPOCA DIVINERA ODECI A MOR
		REGISTERED ACCESSABILITY SPECIALIST
SHEET NO.	<u>DESCRIPTION</u>	(RAS) INSPECTION REQUIRED
1	TITLE SHEET	TDLR NO. TABS2023011992
2, 2A-2B	GENERAL NOTES	
3	ESTIMATE & QUANTITIES	
4	OMIT	
5	SUMMARY OF QUANTITIES	
6		OUT SHEET EVERHART ROAD
7		RKINGS LAYOUT EVERHART ROAD
8 9	PAVING LAYOUT SHEET EV	OUT SHEET GOLLIHAR ROAD
10		OUT SHEET GOLLIHAR ROAD
11		DLLIHAR ROAD AT DEVON DRIVE
12		OUT SHEET MCARDLE ROAD SHEET 1
13		OUT SHEET MCARDLE ROAD SHEET 2
14		RKINGS LAYOUT McARDLE ROAD
15	PAVING LAYOUT SHEET MO	CARDLE ROAD
16	EXISTING CONDITIONS LAY	OUT SHEET S STAPLES ST
17	SIGN AND PAVEMENT MAR	RKINGS LAYOUT S STAPLES ST
18	PAVING LAYOUT SHEET S	STAPLES ST
19	SUMMARY OF SMALL SIGN	IS SHEET 1 OF 2
20	SUMMARY OF SMALL SIGN	IS SHEET 2 OF 2
21		PREVENTION PLAN 1 OF 2
22		PREVENTION PLAN 2 OF 2
23	*SMD(GEN)-08	
24-26	*SMD(SLIP-1)-08 THROU	GH SMD(SLIP-03)-08
27	*TSR(4)-13	
28	*TS-FD-12	
29	*SPRFBA(1)-13	
30-32	*PM(1)-22 THROUGH PM	(3)–22
33-34	*D&OM(1)-20 THROUGH	D&OM(2)-20
35	*PM(4)-22A	
36-39	*PED-18 (SHEET 1 THRO	OUGH SHEET 4)
40-42	*EC(9)-16 (SHEET 1 THE	ROUGH SHEET 3)
43-54	*BC(1)-21 THROUGH BC(
55	*TCP(2-1)-18	
56	*TCP(2-2)-18	
57	*TCP(2-4)-18	
58	*WZ(TD)-17	
59	*WZ(STPM)-13	
	` '	
60	*WZ(UL)-13	TC 0) 47
61-62	*WZ(BTS-1)-13 & WZ(B	15-2)-13
63	*PM(5)-22	

STATE TEXAS

CONTROL

CRP

SECTION 35

NUECES

JOB HWY. NO

238,ETC. VARIES

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH AN * HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT

*CCCG-22



Texas Department of Transportation
© 2023 BY TEXAS DEPARTMENT OF TRANSPORTATION
ALL RIGHTS RESERVED

Paula Salus-Evans, P.E.
5975450A18CC435...
AND DEVELOPMENT

— DocuSigned by:

10/2023

Valente Olivarez

County: Nueces Control: 0916-35-238, ETC.

Highways: Various

GENERAL NOTES:

Find, for your information and convenience, tools such as forms, software, materials, and various other information provided by the Department at https://www.txdot.gov/business.html. Please note that these tools are updated periodically, and your attention is directed to the latest edition.

In the event of a called evacuation, emergencies, impending adverse weather or as directed, do not perform any work without written authorization. The District reserves the right to suspend all work in support of evacuations or emergencies occurring from other parts of the state. Any work performed, other than work directed by the Department, is unauthorized work in accordance with

Sweep, clean and remove any construction waste, surplus materials or debris from the roadway and right of way at the end of each day unless otherwise approved. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

All payement markings shall be in accordance with the latest edition of Texas MUTCD.

Contractor questions on this project are to be addressed to the following individual(s):

Ernest Longoria, P.E. Ernest.Longoria@txdot.gov Fidencio Lopez Fidencio.Lopez@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals. Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid O&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

ITEM 2

It is recommended that prospective bidders examine the specified work locations with the Engineer to view the nature of the work, the need for close coordination with the various utilities, traffic control considerations, and other factors influencing the prosecution of the work.

County: Nueces Control: 0916-35-238, ETC.

Highways: Various

ITEM 5

Field verify all dimensions and notify Engineer prior to initiating any work.

Verify the locations of utilities, underground or overhead, shown within the limits of the right-ofway. Adhere to OSHA Standards when working within the vicinity of overhead power lines. Coordinate with the utility companies and notify the Engineer of any possible conflicts. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The 811 call services for a utility location does not include TxDOT facilities. Provide notification to the District Traffic Signal Shop by email at CRP Utility Locate@txdot.gov or call 361-739-6044 when planning, drilling, or excavating in areas where existing TxDOT underground utilities exist. Visual evidence of TxDOT underground utilities in the area include illumination poles, ground boxes, flashing beacons, traffic signals, etc. This notification must be provided 48 hours in advance of performing the work, but no earlier than 72 business hours before the work will commence. Drilled shaft locations or excavation areas must be staked prior to the notification so that the underground utilities can be located in relationship to the proposed work.

Notify the Engineer immediately of utility conflicts in accordance with Item 5.6. Refer to Item 4.5 for consideration of differing site conditions.

The responsibility for the construction surveying on this contract will be in accordance with Item 5.9.3, "Method C".

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.


ITEM 6

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. https://www.txdot.gov/business/resources/materials/buy-america-material-classificationsheet.html for clarification on material categorization.

General Notes Sheet A



Sheet B

NUECES

238

Various

2

County: Nueces Control: 0916-35-238, ETC.

Highways: Various

ITEM 7

The work performed for Item 7.2.4, "Public Safety and Convenience" will not be measured or paid for directly, but will be subsidiary to pertinent Items.

When working at street, farm-to-market, state highway, and county road intersections, schedule work to minimize intersection closures. During nonworking hours, all public road intersections will be open to the traveling public.

The total disturbed area for this project is 0.07 acres. The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer.

Establish uniform perennial vegetative coverage with a density of at least 70% of the native background vegetative cover to achieve final stabilization.

Comply with the Texas Aggregate Quarry and Pit Safety Act for waste areas or material source areas resulting from this project.

No significant traffic generator events identified.

ITEM 8

Prepare the progress schedule using the Critical Path Method (CPM). Submit (2) two 11" x 17" hard copies and an electronic file of the original or updated progress schedule. Submit the original progress schedule seven (7) days before the Preconstruction Conference.

Submit an updated progress schedule as directed to show proposed major changes, changes affecting compliance with the contract requirements, or changes affecting the critical path/controlling item of work.

Working days will be computed and charge in accordance with Article 8.3.1.4, "Standard Workweek".

Work above traffic is not allowed.

Lane closures are not permitted Monday through Friday before 9:00 AM or after 4 PM unless approved. Lane closures are not permitted Monday through Friday during school zone hours.

> General Notes Sheet C

County: Nueces Control: 0916-35-238, ETC.

Highways: Various

ITEM 9

Monthly progress payments will be made for items of work completed by the 28th day of each month. Any work completed after the 28th will be included for payment in the subsequent monthly progress estimate.

Submit signed request for compensation of material-on-hand (MOH), including any requests from subcontractors, suppliers, or fabricators for MOH, at least two (2) working days prior to the end of the month on the Departments approved forms.

ITEM 100

Coordinate all right of way preparation activities with the project's Storm Water Pollution Prevention Plan (SWP3) and Environmental Permit Issues, and Commitments Sheet (EPIC) or as approved.

ITEM 500

"Materials on Hand" payments are not considered when determining partial payments.

ITEM 502

Furnish additional barricades, signs, and traffic handling as directed. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Traffic control for daytime lane closures shall be in accordance with applicable standards. Traffic control shall include temporary rumble strips in accordance with WZ (RS)-22.

When advanced warning flashing arrow panels are specified, furnish one (1) standby unit in good condition at the job site for immediate use.

Attach stop/slow paddle to a staff with a minimum length of 6 feet to the bottom of the sign.

Contractors' attention is directed to a construction speed zone, signage is subsidiary to Item 502.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

All items marked as optional on all traffic control standards shall be required unless otherwise approved by an Engineer.



2A

County: Nueces Control: 0916-35-238, ETC.

Highways: Various

Trail vehicle shall be required on all mobile traffic control operations.

ITEM 529

Construct an expansion joint at a depth equal to the depth of the curb, gutter, and combined curb and gutter every 40 feet. Construct a tooled joint every 10 feet. When sidewalks are constructed next to curb or curb and gutter, place sidewalk expansion joints at the same location as the curb and gutter expansion joints

ITEM 531

Reinforce sidewalks with $4 \times 4 - W2.9 \times W2.9$ welded wire fabric or with No. 3 reinforcing bars spaced at a maximum of 12 inch in each direction unless otherwise shown.

Construct an expansion joint at a depth equal to the depth of the sidewalk every 40 feet. Construct a tooled joint every 5 feet. When sidewalks are constructed next to curb or curb and gutter, place sidewalk expansion joints at the same location as the curb and gutter expansion joints.

Mixing of detectable warning materials is not permitted on curb ramps.

ITEM 636

All sign wraps are subsidiary to Item 636.

Field verify vertical clearance as directed by the online Texas Department of Transportation manual, "Sign Guidelines and Applications Manual" chapter 6 section 3. The Engineer's approval will be required prior to fabrication.

Furnish new sign supports when replacing overhead signs. This will be subsidiary to pertinent items.

Disassemble, deliver and neatly stack salvageable materials at Public Works – Traffic Signals 2525 Hygeia St. Bldg. #021, Corpus Christi, TX 78415. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 644

Use crash worthy supports as shown on the BC sheets, the CWZTCD, or as directed for signs relocated using temporary supports. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

All slip bases and hardware including but not limited to nuts, bolts, screws and washers will be galvanized. All sign and housing components will be galvanized. Slip bases shall be clamp-style.

General Notes Sheet E

County: Nueces Control: 0916-35-238, ETC.

Highways: Various

Disassemble, deliver and neatly stack salvageable materials at 2525 Hygeia, Corpus Christi, TX 78415. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 658

Furnish round delineators and object markers.

ITEM 666


Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

ITEM 685

Provide solar powered flasher controller assemblies capable of a 24-hr flash with dual indications.

Provide single-pole breakaway disconnects. Ensure the disconnects have a white colored marking and a permanently installed solid neutral.

This item includes Solar Powered Rectangular Rapid Flashing Beacons back to back with 24 inch drilled shaft foundation.



			Sheet 1		
	FED.RD. DIV.NO.	FEDER/	AL AID PROJECT NO.	Н	IGHWAY NO.
_	6			۷a	rious
tion	STATE	DISTRICT	COUNTY		
-	TEXAS	CRP	NUECES		SHEET
	CONTROL	SECTION	JOB		NO.
	0916	35	238		2B

Sheet F



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0916-35-238

DISTRICT Corpus Christi

COUNTY Nueces

Report Created On: Feb 27, 2023 2:44:53 PM

HIGHWAY EVERHART RD, GOLLIHAR RD, MC CARDLE RD, STAPLES ST

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	104-6001	REMOVING CONC (PAV)	SY	38.000	
	104-6036	REMOVING CONC (SIDEWALK OR RAMP)	SY	61.000	
	105-6005	REMOVING STAB BASE AND ASPH PAV (3")	SY	106.000	
	500-6001	MOBILIZATION	LS	1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	5.000	
	529-6002	CONC CURB (TY II)	LF	324.000	
	529-6008	CONC CURB & GUTTER (TY II)	LF	90.500	
	531-6004	CURB RAMPS (TY 1)	EA	6.000	
	531-6005	CURB RAMPS (TY 2)	EA	2.000	
	531-6010	CURB RAMPS (TY 7)	EA	2.000	
	531-6016	CURB RAMPS (TY 21)	EA	4.000	
	536-6002	CONC MEDIAN	SY	101.000	
	636-6001	ALUMINUM SIGNS (TY A)	SF	340.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	22.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	6.000	
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	460.000	
	677-6005	ELIM EXT PAV MRK & MRKS (12")	LF	329.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	378.000	
	677-6019	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	EA	30.000	
	685-6003	REMOVE RDSD FLASH BEACON ASSEMBLY	EA	2.000	
	685-6004	INSTL RDSD FLSH BCN ASSM (SOLAR PWRD)	EA	8.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	87.000	
	6185-6002	TMA (STATIONARY)	DAY	87.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Corpus Christi	Nueces	0916-35-238	3

EVERHA	ART ROAD B	ETWEEN HOLLY ROAD AND SOUTH SHEA PAR	KWAY	(CSJ 0916-35-238)
ITEM	SPEC NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY
1	104 6036	REMOVING CONC (SIDEWALK OR RAMP)	SY	14
2	105 6005	REMOVING STAB BASE AND ASPH PAVE (3")	SY	38
3	529 6002	CONC CURB (TY II)	LF	82
4	531 6004	CURB RAMPS (TY 1)	EA	2
5	531 6010	CURB RAMPS (TY 7)	EA	1
6	531 6016	CURB RAMPS (TY 21)	EA	1
7	529 6008	CONC CURB & GUTTER (TY II)	LF	20
8	536 6002	CONC MEDIAN	SY	28
9	636 6001	ALUMINUM SIGNS (TY A)	SF	90
10	644 6001	IN SM RD SN SUP&AM TY 10BWG(1)SA(P)	EA	6
11	668 6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	116
12	677 6005	ELIM EXT PAV MRK & MRKS (12")	LF	118
13	677 6007	ELIM EXT PAV MRK & MRKS (24")	LF	99
14	685 6003	REMOVE RDSD FLASH BEACON ASSEMBLY	EA	2
15	685 6004	INSTL RDSD FLSH BCN ASSM (SOLAR PWRD)	EA	2

	MCARDL	E ROAD BETWEEN CLARE DRIVE AND NILE DRIV	VE (CSJ	0916-35-242)
ITEM	SPEC NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY
1	104 6036	REMOVING CONC (SIDEWALK OR RAMP)	SY	5
2	105 6005	REMOVING STAB BASE AND ASPH PAVE (3")	SY	34
3	529 6002	CONC CURB (TY II)	LF	80
4	531 6005	CURB RAMPS (TY 2)	EA	2
5	531 6016	CURB RAMPS (TY 21)	EA	1
6	529 6008	CONC CURB & GUTTER (TY II)	LF	28
7	536 6002	CONC MEDIAN	SY	24
8	636 6001	ALUMINUM SIGNS (TY A)	SF	90
9	644 6001	IN SM RD SN SUP&AM TY 10BWG(1)SA(P)	EA	6
10	668 6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	86
11	677 6019	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	EA	10
12	677 6005	ELIM EXT PAV MRK & MRKS (12")	LF	92
13	677 6007	ELIM EXT PAV MRK & MRKS (24")	LF	72
14	644 6076	REMOVE SM RD SN SUP&AM	EA	2
15	685 6004	INSTL RDSD FLSH BCN ASSM (SOLAR PWRD)	EA	2

GOLLIHAR ROAD BETWEEN HELEN STREET AND GREEN GROVE DRIVE (CSJ 0916-35-241)						
ITEM	SPEC NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY		
1	104 6036	REMOVING CONC (SIDEWALK OR RAMP)	SY	33		
2	105 6005	REMOVING STAB BASE AND ASPH PAVE (3")	SY	34		
3	529 6002	CONC CURB (TY II)	LF	80		
4	531 6004	CURB RAMPS (TY 1)	EA	2		
5	531 6010	CURB RAMPS (TY 7)	EA	1		
6	531 6016	CURB RAMPS (TY 21)	EA	1		
7	529 6008	CONC CURB & GUTTER (TY II)	LF	28.50		
8	536 6002	CONC MEDIAN	SY	24		
9	636 6001	ALUMINUM SIGNS (TY A)	SF	90		
10	644 6001	IN SM RD SN SUP&AM TY 10BWG(1)SA(P)	EA	6		
11	668 6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	116		
12	677 6005	ELIM EXT PAV MRK & MRKS (12")	LF	119		
13	677 6007	ELIM EXT PAV MRK & MRKS (24")	LF	99		
14	644 6076	REMOVE SM RD SN SUP&AM	EA	2		
15	685 6004	INSTL RDSD FLSH BCN ASSM (SOLAR PWRD)	EA	2		

sou	JTH STAPLE	S STREET BETWEEN DODY STREET AND DRIFT	WOOD	PLACE (CSJ 0916-35-246)
ITEM	SPEC NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY
1	104 6036	REMOVING CONC (SIDEWALK OR RAMP)	SY	9
2	104 6001	REMOVING CONC (PAV)	SY	38
3	529 6002	CONC CURB (TY II)	LF	82
4	531 6004	CURB RAMPS (TY 1)	EA	2
5	531 6016	CURB RAMPS (TY 21)	EA	1
6	529 6008	CONC CURB & GUTTER (TY II)	LF	14
7	536 6002	CONC MEDIAN	SY	25
8	636 6001	ALUMINUM SIGNS (TY A)	SF	70
9	644 6001	IN SM RD SN SUP&AM TY 10BWG(1)SA(P)	EA	4
10	668 6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	142
11	677 6019	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	EA	20
12	677 6007	ELIM EXT PAV MRK & MRKS (24")	LF	108
13	644 6076	REMOVE SM RD SN SUP&AM	EA	2
14	685 6004	INSTL RDSD FLSH BCN ASSM (SOLAR PWRD)	EA	2




_			
NO.	REVISIONS	DATE	NAME





CITY of CORPUS CHRISTI TEXAS Department of Public Works

HSIP SAFETY IMPROVEMENTS
SUMMARY OF QUANTITIES

SCALE:					
DWN: JDL		CKD:	DLR		
STATE	DI	STRICT	FED. RD. DIV. NO.	COL	INTY
TEXAS		CRP	6	NUECES	
CONT.		SECT.	JOB	HWY. NO.	SHEET NO.
0916		35	238,241 242,246	VA	5








NOTES:

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES (PUBLIC AND PRIVATE) PRIOR TO COMMENCING WORK. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ANY DAMAGE CAUSED BY HIS FAILURE TO LOCATE AND PRESERVE THESE UTILITIES, WHETHER UNDERGROUND, ABOVE GROUND OR OVERHEAD.
- 2. CONTRACTOR SHALL RESTORE THE CONSTRUCTION AREA TO ORIGINAL CONDITION PRIOR TO FINAL INSPECTION.
- 3. CONTRACTOR SHALL NOT INSTALL CONCRETE RAMPS UNTIL POLE FOUNDATIONS ARE IN PLACE.
- 4. ADA RAMPS SHALL COMPLY TO TDLR REQUIREMENTS.
- CONTRACTOR SHALL CONTACT PUBLIC WORKS SIGNAL DEPARTMENT AT 361.826.1610 72 HOURS IN ADVANCE TO INSPECT DRILLED SHAFT POLE FOUNDATIONS DURING INSTALLATION.



EVERHART ROAD

SCALE: 1" = 10'




	REVISION	ONS	DATE	NAME
	4			
Tre	exas Depart	tment of Tra	nsport	ation

HSIP SAFETY IMPROVEMENTS

PAVING LAYOUT SHEET EVERHART ROAD

SCALE:						
DWN: JDL		CKD: J	DLR			
STATE	DIS	TRICT	FED. RD. DIV. NO.	COUNTY		
TEXAS	С	RP	6	NUECES		CES
CONT.	SE	ECT.	JOB	HWY.	NO.	SHEET NO.
0916	3	35	238	VA	4	8




LEGEND

EXISTING SIGN

PEDESTRIAN POLE



I _	4.			




HSIP SAFETY IMPROVEMENTS
EXISTING CONDITIONS
LAYOUT SHEET
GOLLIHAR RD

SCALE:						
DWN: JDL		CKD: J	DLR			
STATE	DI	STRICT	FED. RD. DIV. NO.	COUNTY		
TEXAS		CRP	6	NUECES		
CONT.		SECT.	JOB	HWY. NO.	SHEET NO.	
0916		35	241	VA	9	



- ___ EXISTING SIGN
- PROPOSED SIGN
- REFL PAV MRK TY C HEAT APPLIED PREFAB PREFORMED THERMOPLASTIC (W) 24" (SLD) (125 MIL)
- B INSTL DEL ASSM (D-SY)SZ 1(YFLX(SRF(BI)
- TRAFFIC FLOW



NOTES:

- CONTRACTOR SHALL REPLACE PAVEMENT MARKINGS FOLLOWING DESIGN STANDARDS PROVIDED ON THIS PACKAGE AND THE 2011 TEXAS MANUAL OF UNIFORM CONTROL DEVICES (TMUTCD).
- FLASHING PEDSTRIAN CROSSING SAFETY SYSTEM SHALL INCLUDE:
 SIGN ASSEMBLIES, 2 DOUBLE RECTANGULAR RAPID FLASHING BEACONS, 2 SOLAR PANELS, 24" DRILLED SHAFT FOUNDATION. COORDINATE WITH PUBLIC WORKS TRAFFIC ENGINEERING DEPARTMENT FOR APPROVAL PRIOR TO ORDERING MATERIALS.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES (PUBLIC AND PRIVATE) PRIOR TO COMMENCING WORK. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ANY DAMAGE CAUSED BY HIS FAILURE TO LOCATE AND PRESERVE THESE UTILITIES, WHETHER UNDERGROUND, ABOVE GROUND OR OVERHEAD.





CITY of CORPUS CHRIST


Department of Public Works

HSIP SAFETY IMPROVEMENTS
SIGN AND PAVEMENT
MARKINGS LAYOUT
GOLLIHAR ROAD

		DWN: JDL	С	KD: J			·
50'	100'	STATE	DISTR	ICT	FED. RD. DIV. NO.	COL	INTY
		TEXAS	CRI	Р	6	NUE	CES
1" = 50'		CONT.	SEC	T.	JOB	HWY. NO.	SHEET NO.
1 - 50		0916	35	,	241	VA	10










- ___ EXISTING SIGN
- PROPOSED SIGN
- REFL PAV MRK TY C HEAT APPLIED PREFAB PREFORMED THERMOPLASTIC (W) 24" (SLD) (125 MIL)
- (B) INSTL DEL ASSM (D-SY)SZ 1(YFLX(SRF(BI)
- TRAFFIC FLOW



NOTES:

- CONTRACTOR SHALL REPLACE PAVEMENT MARKINGS FOLLOWING DESIGN STANDARDS PROVIDED ON THIS PACKAGE AND THE 2011 TEXAS MANUAL OF UNIFORM CONTROL DEVICES (TMUTCD).
- FLASHING PEDSTRIAN CROSSING SAFETY SYSTEM SHALL INCLUDE:
 SIGN ASSEMBLIES, 2 DOUBLE RECTANGULAR RAPID FLASHING BEACONS, 2 SOLAR PANELS, 24" DRILLED SHAFT FOUNDATION. COORDINATE WITH PUBLIC WORKS TRAFFIC ENGINEERING DEPARTMENT FOR APPROVAL PRIOR TO ORDERING MATERIALS.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES (PUBLIC AND PRIVATE) PRIOR TO COMMENCING WORK. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ANY DAMAGE CAUSED BY HIS FAILURE TO LOCATE AND PRESERVE THESE UTILITIES, WHETHER UNDERGROUND, ABOVE GROUND OR OVERHEAD.

4	-		_	




CITY of CORPUS CHRIST TEXAS Department of Public Works

HSIP SAFETY IMPROVEMENTS

SIGN AND PAVEMENT MARKINGS LAYOUT MCARDLE ROAD

		SCALE:				
		DWN: JDL	CKD:	JDLR		
50'	100'	STATE	DISTRICT	FED. RD. DIV. NO.	cou	JNTY
		TEXAS	CRP	6	NUE	CES
SCALE: 1" = 50'		CONT.	SECT.	JOB	HWY. NO.	SHEET NO.
30ALL. 1 = 30		0916	35	242	VA	14





- 1. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES (PUBLIC AND PRIVATE) PRIOR TO COMMENCING WORK. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ANY DAMAGE CAUSED BY HIS FAILURE TO LOCATE AND PRESERVE THESE UTILITIES, WHETHER UNDERGROUND, ABOVE GROUND OR OVERHEAD.
- 2. CONTRACTOR SHALL RESTORE THE CONSTRUCTION AREA TO ORIGINAL CONDITION PRIOR TO FINAL INSPECTION.
- 3. CONTRACTOR SHALL NOT INSTALL CONCRETE RAMPS UNTIL POLE FOUNDATIONS ARE IN PLACE.
- 4. ADA RAMPS SHALL COMPLY TO TDLR REQUIREMENTS.
- 5. CONTRACTOR SHALL CONTACT PUBLIC WORKS SIGNAL DEPARTMENT AT 361.826.1610 72 HOURS IN ADVANCE TO INSPECT DRILLED SHAFT POLE FOUNDATIONS DURING INSTALLATION.




NO.	REVISIONS	DATE	NAME
	NE VIOIONO	DATE	11711112
╻	_4^		



CITY of CORPUS CHRISTI TEXAS Department of Public Works

HSIP SAFETY IMPROVEMENTS **PAVING LAYOUT SHEET** McARDLE ROAD


		SCALE:					
		DWN: JDL	C	KD: J	DLR		
10'	20'	STATE	DISTR	ICT	FED. RD. DIV. NO.	COL	INTY
		TEXAS	CRI	Р	6	NUE	CES
SCALE: 1" = 10'		CONT.	SEC	T.	JOB	HWY. NO.	SHEET NO.
30ALL: 1 - 10		0916	35	,	242	VA	15





LEGEND

- ___ EXISTING SIGN
- PROPOSED SIGN
- REFL PAV MRK TY C HEAT APPLIED PREFAB PREFORMED THERMOPLASTIC (W) 24" (SLD) (125 MIL)
- B INSTL DEL ASSM (D-SY)SZ 1(YFLX(SRF(BI)
- TRAFFIC FLOW



NOTES:

- CONTRACTOR SHALL REPLACE PAVEMENT MARKINGS FOLLOWING DESIGN STANDARDS PROVIDED ON THIS PACKAGE AND THE 2011 TEXAS MANUAL OF UNIFORM CONTROL DEVICES (TMUTCD).
- FLASHING PEDSTRIAN CROSSING SAFETY SYSTEM SHALL INCLUDE:
 SIGN ASSEMBLIES, 2 DOUBLE RECTANGULAR RAPID FLASHING BEACONS, 2 SOLAR PANELS, 24" DRILLED SHAFT FOUNDATION. COORDINATE WITH PUBLIC WORKS TRAFFIC ENGINEERING DEPARTMENT FOR APPROVAL PRIOR TO ORDERING MATERIALS.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES (PUBLIC AND PRIVATE) PRIOR TO COMMENCING WORK. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ANY DAMAGE CAUSED BY HIS FAILURE TO LOCATE AND PRESERVE THESE UTILITIES, WHETHER UNDERGROUND, ABOVE GROUND OR OVERHEAD.



7	Texas Department of Trai	nsperi	ation

REVISIONS

DATE NAME





HSIP SAFETY IMPROVEMENTS
SIGN AND PAVEMENT
MARKINGS LAYOUT

S STAPLES STREET

SCALE:						
DWN: JDL CKD: JDLR						
STATE	DI	STRICT	FED. RD. DIV. NO.	COUNTY		
TEXAS		CRP	6	NUECES		
CONT.		SECT.	JOB	HWY. NO.	SHEET NO.	
0916		35	246	VA	17	









JUSTIN AARON DE LA ROSA

Justin Laren De La Rosas Re


NO. REVISIONS DATE NAME



CITY of CORPUS CHRISTI
TEXAS
Department of Public Works

HSIP SAFETY IMPROVEMENTS
SUMMARY OF SMALL SIGNS
SHEET 1 OF 2

CALE:						
DWN: JDL		CKD: J				
STATE	DI	STRICT	FED. RD. DIV. NO.	COUNTY		
TEXAS		CRP	6	NUECES		
CONT.		SECT.	JOB	HWY. NO.	SHEET NO.	
0916		35	238,241 242,246	VA	19	





NO.	REVISIONS	DATE	NAME



CITY of CORPUS CHRISTI

TEXAS

Department of Public Works

HSIP SAFETY IMPROVEMENTS
SUMMARY OF SMALL SIGNS
SHEET 2 OF 2

SCALE:						
DWN: JDL		CKD: J	DLR			
STATE	DI	STRICT	FED. RD. DIV. NO.	COUNTY		
TEXAS		CRP	6	NUECES		
CONT.		SECT.	JOB	HWY. NO.	SHEET NO.	
0916		35	238,241 242,246	VA	20	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP), The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

CSJ 0916-35-238

1.2 PROJECT LIMITS:

EVERHART ROAD BETWEEN S. SHEA PARKWAY AND HOLLY ROAD (0.30 MILES). From: GOLLIHAR ROAD BETWEEN HELEN STREET AND DEVON DRIVE (0.13 MILES)

MCARDLE ROAD BETWEEN NILE DRIVE AND CLARE DRIVE (0.58 MILES) S. STAPLES STREET BETWEEN DODY DRIVE AND DRIFTWOOD PLACE (0.11 MILES)

1.3 PROJECT COORDINATES:

BEGIN	: (Lat) 27°42' 13.22" N	,(Long)	97° 23' 28.16" W
	(La ^{· 27°} 42' 13.22" N	,(Long)	97° 23' 28.16" W

1.4 TOTAL PROJECT AREA (Acres): 7.05

1.5 TOTAL AREA TO BE DISTURBED (Acres):

1.6 NATURE OF CONSTRUCTION ACTIVITY:

REMOVING EXISTING PEDESTRIAN SIGNS AND INSTALLING PEDESTRIAN SIGNAGE INCLUDING PEDESTRIAN RECTUANULAR RAPID FLASHING BEACONS. INSTALLATION OF PEDESTRIAN ADA RAMPS AND MEDIANS

1.7 MAJOR SOIL TYPES:

		_ □ Excavate and prepare subgrade for proposed pavement
Soil Type	Description	widening
FAT CLAY	EXPANSIVE CLAY THAT IS SOFT TEXTURED CONTAINING MINERLAS THAT UNDERGO CONSIDERABLE VOLUMETRIC CHANGES.	Remove existing culverts, safety end treatments (SETs) Remove existing metal beam guard fence (MBGF), bridge rall Install proposed pavement per plans Install culverts, culvert extensions, SETs Install mow strip, MBGF, bridge rail Place flex base Rework slopes, grade ditches Blade windrowed material back across slopes Revegetation of unpaved areas Achieve site stabilization and remove sediment and erosion control measures Other:

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- ☐ PSLs determined during preconstruction meeting ☐ PSLs determined during construction
- ☑ No DSI e planned for construction

2 No Facs planned for construction		
Туре	Sheet #s	

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- □ Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- □ Grading operations, excavation, and embankment

Other: _			
			-

Sediment laden stormwater from stormwater conveyance over

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- ☑ Solvents, paints, adhesives, etc. from various construction
- Transported soils from offsite vehicle tracking
- ☑ Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out
- Sanitary waste from onsite restroom facilities
- ☑ Trash from various construction activities/receptacles
- ☐ Long-term stockpiles of material and waste

Other:	

Other:		

1.11 RECEIVING WATERS:

☐ Other:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters. Classified Waterbady Tuibutaniaa

Tributaries	Classified Waterbody
CORPUS CHRISTI BAY BASIN	
OSO CREEK BASIN	
OSO BAY BASIN	

Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TXDOT

- X Development of plans and specifications
- X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- X Submit NOI/CSN to local MS4
- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations
- ▼ Maintain SWP3 records for 3 years
- Other:

Other:	

Other:

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- M Day To Day Operational Control
- X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- X Post Construction Site Notice
- X Maintain schedule of major construction activities
- X Install, maintain and modify BMPs
- X Complete and submit Notice of Termination to TCEQ
- X Maintain SWP3 records for 3 years ☐ Other:

	•		
☐ Other:			

1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:

MS4 Entity

CITY OF CORPUS CHRISTI

ADDITIONAL BMP'S


☐ Other:

a. The Federal Migratory Bird Treaty Act (MBTA) states that it is unlawful to pursue, hunt, take, kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit. This project does not have a federal permit; therefore, in accordance with this regulation, the Contractor will avoid disturbing, destroying, removing, or relocating migratory birds and active nests found in trees, culverts, bridges, on the ground, etc. Typical breeding season occurs from March through August; therefore, tree trimming and other vegetation clearing activities that may disturb breeding birds should be done in the non-breeding season (September-February), when possible. If work must be performed during the breeding season, the Contractor shall have a qualified biologist conduct a survey of the right of way to determine if bird nests are present. In the event that active nests are encountered on-site during construction, the Contractor shall notify the Engineer and measures shall be taken to avoid disturbance of these birds, their occupied nest, eggs, and/or young, in accordance with the MBTA. Phasing of work during construction may be necessary to stay in compliance with the MBTA. The Contractor can discuss other preventative measures with the Project Engineer and/or District Environmental Staff

b.If the construction of the project requires the use of open trenches and excavated pits, install escape ramps at an angle of less than 45 degrees (1:1) in areas left uncovered Visually inspect excavation areas for trapped wildlife prior to backfilling.

 Avoid or minimize disturbing or removing downed trees, rotting stumps, and leaf little STORMWATER POLLUTION







NO.	REVISIONS	DATE	NAME



CITY of CORPUS CHRISTI TEXAS

Department of Public Works

HSIP SAFETY IMPROVEMENTS STORMWATER POLLUTION **PREVENTION PLAN NOTES**

SCALE:					
DWN: JDL		CKD: J	DLR		
STATE	DI	STRICT	FED. RD. DIV. NO.	COL	INTY
TEXAS		CRP	6	NUE	CES
CONT.		SECT.	JOB	HWY. NO.	SHEET NO.
0916		35	238,241 242,246	VA	21

AND	EST MANAGEMENT PRACTICES (BMPs) CONTROLS, INSPECTION, AND ITENANCE
the B for co opera SWP	Contractor shall be the responsible party for implementin MPs described herein and for complying with the SWP3 ontrol of erosion and sedimentation during day-to-day ations. The Contractor shall implement changes to this 3 approved by TxDOT within the times specified in this 3 or the CGP.
	ROSION CONTROL AND SOIL STABILIZATION BMPs:
	Protection of Existing Vegetation Vegetated Buffer Zones Soil Retention Blankets Geotextiles
	Mulching/ Hydromulching Soil Surface Treatments Temporary Seeding Permanent Planting, Sodding or Seeding
	Biodegradable Erosion Control Logs Rock Filter Dams/ Rock Check Dams Vertical Tracking Interceptor Swale Riprap
	Diversion Dike Temporary Pipe Slope Drain Embankment for Erosion Control Paved Flumes
	Other: Other: Other: Other:
	EDIMENT CONTROL BMPs:
	Biodegradable Erosion Control Logs Dewatering Controls Inlet Protection
	Rock Filter Dams/ Rock Check Dams Sandbag Berms Sediment Control Fence
	Stabilized Construction Exit Floating Turbidity Barrier Vegetated Buffer Zones Vegetated Filter Strips
	Other: Other: Other:
	Other:

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.): T/P

- □ □ Sediment Trap ☐ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area □ 3,600 cubic feet of storage per acre drained
- □ □ Sedimentation Basin
 - ☑ Not required (<10 acres disturbed)
 </p>
 - □ Required (>10 acres) and implemented.
 - ☐ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - □ 3,600 cubic feet of storage per acre drained
 - ☐ Required (>10 acres), but not feasible due to:
 - □ Available area/Site geometry
 - ☐ Site slope/Drainage patterns
 - ☐ Site soils/Geotechnical factors
 - □ Public safety
 - □ Other:

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing		
Туре	From	То	
	l		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily ☐ Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other:
- Other: Other: _

Other:

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- ☑ Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other:
- Other:
- Other:
- Other:

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stati	oning
Туре	From	То

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- ⋉ Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

ADDITIONAL BMP'S

- a. Minimize the use of equipment in streams and riparian areas during construction. When possible, equipment access should be from banks, bridge decks, or barges.
- b. When temporary stream crossings are unavoidable, remove stream crossings once they are no longer needed and stabilize banks and soils around the crossing.
- c. Minimize the amount of vegetation cleared. Removal of native vegetation, particularly mature native trees and shrubs should be avoided to the greatest extent practicable. Wherever practicable, impacted vegetation should be replaced with in-kind on-site replacement/restoration of native vegetation.
- d. Do not attempt to handle or catch any of these species. Report all sightings and/or impacts to the TxDOT Corpus Christ District Environmental Section.


STORMWATER POLLUTION **PREVENTION PLAN (SWP3)**



Sheet 2 of 2

PROJECT NO. TEXAS SECT.





TEXAS Department of Public Works

HSIP SAFETY IMPROVEMENTS STORMWATER POLLUTION PREVENTION PLAN NOTES

SCALE:					
DWN: JDL		CKD: J	DLR		
STATE	TATE DISTRICT FED. RD. COUNTY			INTY	
TEXAS	CRP		6	NUE	CES
CONT.	CONT. SECT. JOB		JOB	HWY. NO.	SHEET NO.
0916		35	238,241 242,246	VA	22

SIGN SUPPORT DESCRIPTIVE CODES (Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

Post Type

FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP)) TWT = Thin-Walled Tubing (see SMD(TWT))

10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3)) S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2) =

Anchor Type

UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT)) UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))

- WS = Wedge Anchor Steel (see SMD(TWT))
- WP = Wedge Anchor Plastic (see SMD(TWT))
- SA = Slipbase Concreted (see SMD(SLIP-1) to (SLIP-3))
- SB = Slipbose Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Wounting Designation

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))

- T = Prefqb. "T" (see SMD(SLIP-1) to (SLIP-3). (TWT))
- U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))


No more than 2 sign

posts should be located

within a 7 ft. circle.

- 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
- BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3)) WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
- EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))

REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project mare than 4 inches above a 60-inch chard (i.e., typical space between wheel paths).

> 7 ft. diameter

> > circle


Not Acceptable

Not Acceptable

HIGHWAY INTERSECTION AHEAD -0 to 6 ft 7.5 ft max 7.0 ft min Travel Lane Payed Shou I der

LESS THAN 6 FT. WIDE

When the shoulder is 6 ft. or less in width. the sign must be placed at least 12 ft. from the edge of the travel lane.



SIGN LOCATION

GREATER THAN 6 FT. WIDE

When the shoulder is greater than 6 ft in width the sign must be placed at least 6 ft. from the edge of the shoulder.

When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

Paved

Shou I der


T-INTERSECTION

12 ft min:

- 6 ft min⊸

7.5 ft max


7.0 ft min *





Travel

Lane




- * Signs shall be maunted using the following condition that results in the greatest sign elevation:
- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or (2) a minimum of 7 to a maximum of 7.5 feet above the
- grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by


See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is: http://www.txdot.gov/publications/traffic.htm

BEHIND BARRIER



BEHIND GUARDRAIL



**Sign clearance based on distance required for proper guard rail or concrete barrier performance,

RESTRICTED RIGHT-OF-WAY

(When 6 ft min. is not possible.)

7.5 ft max

7.0 ft min *

HIGHWAY

INTERSECTION

AHEAD

Maximum

possible

Travel

Lane


factors.

Paved

TYPICAL SIGN ATTACHMENT DETAIL

diameter

circle



diameter

circle / Not Acceptable

Bolts used to maunt sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp the universal clamp.

Back-to-Back Signs Nylon washer, flat washer. lock washer. -Sign Panel Sign Post ∠_{Sign Panet} Nylon washer, flat washer, lock washer, └ Sign Bolt


diameter

circle


Acceptable

	Approximate	Bolt Length
Pipe Diameter	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES



CURB & GUTTER OR RAISED ISLAND



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme




SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD (GEN) -08

©TxDOT July 2002	DN: TX	то	CK: TXDOT	DW:	TXDOT	CK: TXDOT
9-08 REVISIONS	CONT	SECT	JOB		ніс	HWAY
	0916	35	238,241 242,246		/	VA.
	DIST		COUNTY			SHEET NO.
	CRP		NUECE	S	2	23


TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System, Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

CONCRETE ANCHOR



SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" digmeter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud balt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxies and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchorwhen installed in 4000 psi normalweight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

GENERAL NOTES:

- 1. Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:

10 BWG Tubing (2.875" outside diameter)

0.134" nominal wall thickness

Seamless or electric-resistance welded steel tubing or pipe

Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008

Other steels may be used if they meet the following:

55,000 PSI minimum yield strength 70,000 PSI minimum tensile strength

20% minimum elongation in 2"

Wall thickness (uncoated) shall be within the range of 0.122" to 0.138" Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"

Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat

tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.

Schedule 80 Pipe (2.875" outside diameter)

0.276" nominal wall thickness

Steel tubing per ASTM A500 Gr C

Other seamless or electric-resistance welded steel tubing or pipe with equivalent

outside diameter and wall thickness may be used if they meet the following:

46,000 PSI minimum yield strength 62,000 PSI minimum tensile strength

21% minimum elongation in 2"

Wall thickness (uncoated) shall be within the range of 0.248" to 0.304" Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"

Galvanization per ASTM A123

- 3. See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is:
 - http://www.txdot.gov/publications/traffic.htm
- 4. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE

Foundation

- 1. Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- 2. The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- 3. Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- 4. Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- 5. The triangular slipbase system is multidirectianal and is designed to release when struck from any direction.


- 1. Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and
- 2. Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.



SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD (SL IP-1) -08

© TxDOT July 2002	DN: TX	тос	CK: TXDOT	D₩s	TXDOT	CK:	TXDOT
9-08 REVISIONS	CONT	SECT	JOB		HI	CHWAY	,
	0916	35	238,241 242,246			VA	
	DIST		COUNTY			SHEET	NO.
	CRP		NUECI	ES		2	4



±.05"

Skirt

Variation

Depth

Rolled Crimp to

engage pipe 0, D,

Pipe O.D.

-.025"<u>+</u>.010"

Pipe O.D.

+. 025" ±. 010"

All dimensions are in english

unless detailed otherwise.

SM RD SGN ASSM TY XXXXX(1)XX(T)

(* - See Note 12)

GENERAL NOTES:

1.	SIGN SUPPORT	# OF POSTS	MAX. SIGN AREA
	10 BWG	1	16 SF
	10 BWG	2	32 SF
	Sch 80	1	32 SF
	Sch 80	2	64 SF

The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.

3. Sign supports shall not be spliced except where shown.

Sign support posts shall not be spliced. 4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.

5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.

6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of areater height.

7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.

Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.


9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."

10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.

11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.

12. Post open ends shall be fitted with Friction Caps.

13. Sign blanks shall be the sizes and shapes shown on the plans.



Texas Department of Transportation Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD (SL IP-2) -08

				_		-	
©TxDOT July 2002	DN: TXD	ОТ	CK: TXDOT	DW:	TXDOT	CK:	TXDOT
9-08 REVISIONS	CONT	SECT	JOB		н	CHWAY	
	0916	35	238,241 242,246			VA	
	DIST		COUNTY			SHEET	r NO.
	CRP		NUECE	ES		25	5

thickness shall be 24 gauge for all cap sizes.


The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture.


Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

0.25 H

0.2W


W (max) = 8FT





Detail B

w variable



Splices shall only be allowed behind the sign substrate.

Sign

Clamps

(Specific or

Universal)

3/8" x 4 1/2"


square head bolt, nut, flat washer and lock washer per

ASTM A307 galvanized


per Item 445.

"Galvanizing.


Detail E




SM RD SGN ASSM TY S80(2) XX (P-EXAL) ¥ Additional stiffener placed at approximate center of signs when sign width is greater than 10'.



With T Bracket



for clamp installation



Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details See Detail E for clamp installation

GENERAL NOTES:

1. [SIGN SUPPORT	# OF POSTS	MAX. SIGN AREA
	10 BWG	1	16 SF
	10 BWG	2	32 SF
	Sch 80	1	32 SF
	Sch 80	2	64 SF

- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- 3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- 5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- 6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of
- greater height.
 7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- 9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- 10. Sign blanks shall be the sizes and shapes shown on
- 11. Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- 12. Post open ends shall be fitted with Friction Caps.

	REQUIRED SUPPORT					
	SIGN DESCRIPTION	SUPPORT				
	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)				
٠	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)				
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)				
36x48, 48x36, and 48x48-inch signs		TY 10BWG(1)XX(T)				
	48x60-inch signs	TY \$80(1)XX(T)				
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)				
,	48x60-inch signs	TY \$80(1)XX(T)				
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)				
١	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)				
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)				



SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM


SMD(SLIP-3)-08

©TxDOT July 2002	DN: TXDOT	CK: TXDOT DW:	TXDOT CK: TXDOT		
9-08 REVISIONS	CONT SECT	JOB	H I GHWAY		
	0916 35	238,241 242,246	VA		
	DIST	COUNTY	SHEET NO.		
	CRP	NUECES	26		

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)









REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

	SHEETING REC	UIREMENTS
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

55

SPEED



TYPICAL EXAMPLES

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS

(EXCLUDING STOP, YIELD, DO NOT ENTER AND

WRONG WAY SIGNS)

SHEETING REQUIREMENTS						
USAGE COLOR SIGN FACE MATERIAL						
BACKGROUND	WHITE	TYPE A SHEETING				
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING				
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM				
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING				

REQUIREMENTS FOR WARNING SIGNS





TYPICAL EXAMPLES

*						
SHEETING REQUIREMENTS						
USAGE COLOR SIGN FACE MATERIAL						
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING				
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM				
LEGEND & SYMBOLS	ALL OTHER	ER TYPE B OR C SHEETING				

REQUIREMENTS FOR SCHOOL SIGNS





TYPICAL EXAMPLES

SHEETING REQUIREMENTS						
USAGE COLOR SIGN FACE MATERIAL						
BACKGROUND	WHITE	TYPE A SHEETING				
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING				
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM				
SYMBOLS	RED	TYPE B OR C SHEETING				

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- 4. Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- 5. White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN I	BLANKS THICKNESS
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0,100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPEC	IFICATIONS
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

http://www.txdot.gov/



Traffic Operations Division Standard

TYPICAL SIGN REQUIREMENTS

TSR(4)-13

LE: †S	r4-13.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ск: Тх	DOT
TXDOT OC	ctober 2003	CONT	SECT	JOB	54)	ні	HWAY	ij
	VISIONS							
2-03 7-13 9-08		DIST		COUNTY			SHEET M	10.
		CRP		NUECI	ES	4	_27_	

DATE

	FOUNDATION SELECTION TABLE FOR STANDARD MAST ARM PLUS ILSN SUPPORT ASSEMBLIES (f+)								
		FDN 30-A	FDN 36-A	FDN 36-B	FDN 42-A				
_	MAX SINGLE ARM LENGTH	32′	48′						
DESIGN SPEED		24' X 24'							
띯		28' X 28'							
152	MAXIMUM DOUBLE ARM	32' X 28'	32' X 32'						
80 MPH WIND S	LENGTH COMBINATIONS		36, x 36,						
စ္ကန္			40' X 36'						
"			44' X 28'	44' X 36'					
z	MAX SINGLE ARM LENGTH		36'	44'					
DESIGN SPEED			24' X 24'						
			28' X 28'						
<u> ۲</u>	MAXIMUM DOUBLE ARM		32' X 24'	32' X 32'					
물물	LENGTH COMBINATIONS			36' X 36'					
100 MPH WIND S				40' x24'	40' X 36'				
Ē					44' × 36'				

Traffic Signal Pole

Use average N value over the top third of the

Ignore the top 1' of soil.

embedded shaft.

NOTES:

- Anchor bolt design develops the foundation capacity given under Foundation Design Loads.
- (2) Foundation Design Loads are the allowable moments and shears at the base of the structure,
- 3 Foundations may be listed separately or grouped according to similarity of location and type. Quantities are for the Contractor's information only.
- 4 Field Penetrometer readings at a depth of approximately 3 to 5 feet may be used to adjust shaft lengths.
- (5) If rock is encountered, the Drilled Shaft shall extend a minimum of two diameters into solid rock.
- (6) Decimal lengths in Design Table are to allow interpolation for other penetrometer values. Round to nearest foot for entry into Summary Table.

ANCHOR BOLT & TEMPLATE SIZES								
BOLT DIA IN.	BOLT (7) BOLT TOP POTTOM POLT							
₹4"	1'-6"	3"	_	12 ¾"	7 1/8"	5 % "		
1 1/2"	3′-4"	6"	4"	17"	10"	7"		
1 ¾"	3′ -10"	7"	4 1/2"	19"	11 1/4"	7 ¾"		
2"	4′-3"	8"	5"	21"	12 1/2"	8 1/2"		
2 1/4"	4'-9"	9"	5 ½"	23"	13 ¾"	9 1/4"		

7 Min dimensions given, longer bolts are acceptable.

TOP VIEW


-Spiral

-Vertical

Diometer

Bolt Circle

Bars



GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals and interim revisions thereto.


Reinforcing Steel shall conform to Item 440, "Reinforcing Steel".

Concrete shall be Class "C".

Threads for anchor bolts and nuts shall be rolled or cut threads of 8UN series up to 2" in diameter or UNC series for all sizes. Bolts and nuts shall have Class 2A and 2B fit tolerances. Galvanized nuts shall be tapped after galvanizing.

Anchor bolts that are larger than 1" in diameter shall conform to "alloy steel" or "medium-strength mild steel" per Item 449, "Anchor Bolts". Anchor bolts that are 1" in diameter or less shall conform to ASTM A36. Galvanize a minimum of the top end thread length plus 6" for all anchor boits unless otherwise noted. Exposed washers and exposed nuts shall be galvanized. All galvanizing shall be in accordance with Item 445, "Galvanizing".

Templates and embedded nuts need not be galvanized. Lubricate and tighten anchor bolts when erecting the structure in accordance with Item 449, "Anchor Bolts".






TRAFFIC SIGNAL POLE FOUNDATION

TS-FD-12

C TxDOT August 1995	QN: MS		CK: JSY	DWs	MAO/MMF	CK: JSY/TEB	
REVISIONS	CONT	SECT	108		ню	HLÇHWAY	
	0916	35	35 238,241 242,246		١	VA	
	DIST		COUNTY			SHEET NO.	
	CRP		NUECE:	5		28	



1/4" to 1/2" of bolt shank shall project above concrete Circular Steel Template (Temporary) Conduit (See Layout Sheets for digmeter. Orient as directed by the Engineer. 1 or 2 required) -Anchor Bolt -Circular Vertical Bars (See Design Table for size _ Steel Template Spiral, 3 flat turns top & 1 flat turn Table for size & pitch) Drilled 5 Vertical bars may rest on bottom of drilled hole if material is firm enough ELEVATION

Conduit-

Steel Template with holes 1/16 " greater than bolt diameter —

Bond anchor bolts to

rebar cage, two
locations using #3

jumper. Mechanical

Listed for concrete

connectors shall be UL

bar or #6 copper

ensure that two bolts are in

tension under dead load.

bottom. (See Design

to do so when concrete is placed.


FOUNDATION DETAILS


TYPICAL MAST ARM

ASSEMBLY


GENERAL NOTES:

- Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
- See Item 685, "Roadside Flashing Beacon Assemblies" for further requirements.
- See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- 4. Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered flashing beacon assemblies.
- When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- Use materials specifically designed for attaching cabinets, beacon heads, solar panels, etc., to poles.
- Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on poles.
- 8. Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening on connection.
- 10. Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT'S MPL in the file "Roadway Illumination and Electrical Supplies." Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
- 11. Install the batteries in a battery box. Place the batteries on a $\frac{7}{16}$ " thick plastic sheet and connect together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and $\frac{7}{16}$ " plastic sheet are subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies." When required, install batteries in the flasher cabinet. Wire batteries according to manufacturers recommendations. Provide the number of batteries as required by the manufacturer.
- See standard sheet Electrical Details (ED) for additional requirements regarding the installation of ground boxes/battery boxes, conduit, and cabinets.
- 13. Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
- 14. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- 15. Orient solar panel for optimum exposure to sunlight (face to the south). Prior to installation, check the location to ensure there is no overhead obstruction that would block the solar panel from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- 16. Ensure height of conduit is below top of anchor bolts.





LINE



NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS
EXPLODED VIEW




Traffic Operations Division Standard

SOLAR POWERED ROADSIDE FLASHING BEACON ASSEMBLY DETAILS

SPRFBA(1)-13

FILE: spb1-13.dgn	DN: TxDOT		CK: TXDOT DV	: TxDOT	ck: TxD01	
©TxDOT May 2003	CONT SECT		JOB	н	HIGHWAY	
REVISIONS	0916	5 35 238,241 242,246		Ĭ.	VA	
12-04 3-13	DIST		COUNTY	ľ	SHEET NO.	
2	CRP		NUECES	5	29	

NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS



ΔΔΔΔΔΔ

48" min.

line to

Storage

Deceleration

 \Rightarrow

from edge

stop/yield

FOUR LANE DIVIDED ROADWAY CROSSOVERS

Lines

6" White Lane Line

GENERAL NOTES

 \Diamond

 \Diamond

➪


➾

ف

- 1. Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- 2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

GUIDE FOR PLACEMENT OF STOP LINES. EDGE LINE & CENTERLINE

Based on Traveled Way and Pavement Widths for Undivided Roadways



Texas Department of Transportation

Traffic Safety Division Standard

TYPICAL STANDARD PAVEMENT MARKINGS

PM(1)-22

		•				
ILE: pm1-22.dgn	DN:		CK:	DW:	CK:	
CTxDOT December 2022	CONT	SECT	JOB		HIGHWAY	
REVISIONS 11-78 8-00 6-20	0916	35	238,241 242,246		VA	
8-95 3-03 12-22	DIST		COUNTY		SHEET NO.	
5-00 2-12	CRP		NUECE	S	30	

Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection

control. Stop signs and stop bars are optional as determined by the Engineer.

2. Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines

shall only be used with stop signs. Yield lines shall only be used with yield signs.

3. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

White

Line — Extension

See note 3


6" Solid Yellow-

Edae Line


Edge Line —

6" Solid White


REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS




CENTERLINE & LANE LINES FOR FOUR LANE TWO-WAY ROADWAYS



OR 6" LANE LINE

Center line -Symmetrical around centerline Continuous two-way left turn lane 401 80' Type I-C

CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic. See Note 3.

Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.


CENTER OR EDGE LINE (see note 1) 10' 30' BROKEN LANE LINE -300 to 500 mil in height 18"± 1" A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters. REFLECTORIZED PROFILE 51/2 " ± 1/2 PATTERN DETAIL 2 to 3"--NOTES USING REFLECTIVE PROFILE PAVEMENT MARKINGS 1. Edge lines should typically be 6" wide and the materials shall be specified in the plans. 6" EDGE LINE, 6" CENTERLINE

GENERAL NOTES


- All raised pavement markers placed along broken lines shall be placed in line with and midway between
- 2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal
- Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

١	MATERIAL SPECIFICATIONS	
1	PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
	EPOXY AND ADHESIVES	DMS-6100
	BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
	TRAFFIC PAINT	DMS-8200
١	HOT APPLIED THERMOPLASTIC	DMS-8220
١	PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



RAISED PAVEMENT MARKERS



Traffic Safety Division Standard

POSITION GUIDANCE USING RAISED MARKERS RELECTORIZED PROFILE **MARKINGS** PM(2) - 22

FILE: pm2-22.dgn	DN:		CK:	DW:	CK:	
©TxDOT December 2022	CONT	SECT	JOB		HIGHWAY	
REVISIONS 4-77 8-00 6-20			238,241 242,246			
4-92 2-10 12-22	DIST	COUNTY			SHEET NO.	
5-00 2-12					31	

Pavement

RIGHT

Edge ·

NOTES

- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- 3. Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on englineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- 4. For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

	D WARNING ISTANCE (
Posted Speed	D (ft)	L (f+)
30 MPH	460	_{wc} 2
35 MPH	565	$L = \frac{WS^2}{60}$
40 MPH	670	0
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	L=WS
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

Type III-A-A Morkers 20' \$\frac{20'}{5}\$ 8'-16'

A two-way left-turn (TWLT) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY

GENERAL NOTES


- 1. Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- 2. When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- 4. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS					
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200				
EPOXY AND ADHESIVES	DMS-6100				
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130				
TRAFFIC PAINT	DMS-8200				
HOT APPLIED THERMOPLASTIC	DMS-8220				
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240				

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS






Traffic Safety Division Standard LANES, BAYS,

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3)-22

FILE: pm3-22.dgn	DN:		CK:	DW:	CK:
©TxDOT December 2022	CONT	SECT	JOB		HIGHWAY
REVISIONS 4-98 3-03 6-20 5-00 2-10 12-22			238,241 242,246		
	DIST		COUNTY	COUNTY	
8-00 2-12					32
226		_			

LANE REDUCTION



Lane-Reduction

Arrow

D/4

6" Dotted White

9′,3′,9′ <≻| |<≻|

D/2

Lane Line

D/4

MERGE LEFT


W9-2TL

Paved Shoulder

300'-500'


(Optional)

TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP

i e



be installed per SMD standard sheets and

paid under item 644.

GF2

Traffic Safety Division Standard

VA

34

JOB

10-09 3-15

4-10 7-20

the chevron (sizes 24" x 30" and

smaller)


TxDOI assumes no responsibility


GENERAL NOTES

- Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
- 2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
- For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
- 4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
- 5. Each crosswalk shall be a minimum of 6' wide.
- 6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
- Final placement of Stop Bar and Crosswalk shall be approved by the Engineer in the field.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.





UNSIGNALIZED MIDBLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK

NOTES:

- Use stop bars with Stop Here For Pedestrians (R1-5b) signs at unsignalized midblock cross walks.
- 2. Use stop bars with STOP HERE ON RED (R10-6 or R10-6a) signs at mid block crosswalks controlled by traffic signals or pedestrian hybrid beacons.




CROSSWALK PAVEMENT MARKINGS

Traffic Safety Division Standard

PM(4)-22A

FILE: pm4-22a.dgn	DN:		CK:	DW:		CK:
© TxDOT December 2022	CONT	SECT	JOB		HIGH	HWAY
REVISIONS 6-20	0916	35	238,241 242,246		٧	Ά
6-22	DIST	COUNTY			SHEET NO.	
12-22	CRP		NUECE:	S		35



GENERAL NOTES

CURB RAMPS

- 1. Install a curb ramp or blended transition at each pedestrian street crossing.
- 2. All slopes shown are maximum allowable. Cross slopes of 1.5% and lesser running should be used. Adjust curb ramp length or grade of approach sidewalks as directed.
- 3. Maximum allowable cross slope on sidewalk and curb ramp surfaces is 2%.
- 4. The minimum sidewalk width is 5'. Where the sidewalk is adjacent to the back of curb, a 6' sidewalk width is desirable. Where a 5' sidewalk cannot be provided due to site constraints, sidewalk width may be reduced to 4' for short distances. 5'x 5' passing areas at intervals not to exceed 200' are required.
- 5. Turning Spaces shall be 5'x 5' minimum. Cross slope shall be maximum 2%.
- 6. Clear space at the bottom of curb ramps shall be a minimum of 4'x 4' wholly contained within the crosswalk and wholly outside the parallel vehicular travel path.
- 7. Provide flared sides where the pedestrian circulation path crosses the curb ramp. Flared sides shall be sloped at 10% maximum, measured parallel to the curb. Returned curbs may be used only where pedestrians would not normally walk across the ramp, either because the adjacent surface is planted, substantially obstructed, or otherwise protected.
- 8. Additional information on curb ramp location, design, light reflective value and texture may be found in the latest draft of the Proposed Guidelines for Pedestrian Facilities in the Public Right of Way (PROWAG) as published by the U.S. Architectural and Transportation Barriers Compliance Board (Access Board).
- 9. To serve as a pedestrian refuge area, the median should be a minimum of 6' wide, measured from back of curbs. Medians should be designed to provide accessible passage over or through them.
- 10. Small channelization islands, which do not provide a minimum 5'x 5' landing at the top of curb ramps, shall be cut through level with the surface of the street.
- 11. Crosswalk dimensions, crosswalk markings and stop bar locations shall be as shown elsewhere in the plans. At intersections where crosswalk markings are not required, curb ramps shall align with theoretical crosswalks unless otherwise directed.
- 12. Provide curb ramps to connect the pedestrian access route at each pedestrian street crossing. Handrails are not required on curb ramps.
- 13. Curb ramps and landings shall be constructed and paid for in accordance with Item 531
- 14. Place concrete at a minimum depth of 5" for ramps, flares and landings, unless otherwise directed.
- 15. Furnish and install No. 3 reinforcing steel bars at 18" o.c. both ways, unless otherwise directed.
- 16. Provide a smooth transition where the curb ramps connect to the street.
- 17. Curbs shown on sheet 1 within the limits of payment are considered part of the curb ramp for payment, whether it is concrete curb, gutter, or combined curb and gutter.
- 18. Existing features that comply with applicable standards may remain in place unless otherwise shown on the plans.

DETECTABLE WARNING MATERIAL


- 19. Curb ramps must contain a detectable warning surface that consists of raised truncated domes complying with PROWAG. The surface must contrast visually with adjoining surfaces, including side flares. Furnish and install an approved cast-in-place dark brown or dark red detectable warning surface material adjacent to uncolored concrete, unless specified elsewhere in the plans.
- 20. Detectable Warning Materials must meet TxDOT Departmental Materials Specification DMS 4350 and be listed on the Material Producer List. Install products in accordance with manufacturer's specifications.
- 21. Detectable warning surfaces must be firm, stable and slip resistant.
- 22. Detectable warning surfaces shall be a minimum of 24 inches in depth in the direction of pedestrian travel, and extend the full width of the curb ramp or landing where the pedestrian access route enters the street.
- 23. Detectable warning surfaces shall be located so that the edge nearest the curb line is at the back of curb and neither end of that edge is greater than 5 feet from the back of curb. Detectable warning surfaces may be curved along the corner radius.
- 24. Shaded areas on Sheet 1 of 4 indicate the approximate location for the detectable warning surface for each curb ramp type.

DETECTABLE WARNING PAVERS (IF USED)

- 25. Furnish detectable warning paver units meeting all requirements of ASTM C-936, C-33. Lay in a two by two unit basket weave pattern or as directed.
- 26. Lay full-size units first followed by closure units consisting of at least 25 percent (25%) of a full unit. Cut detectable warning paver units using a power saw.

SIDEWALKS

- 27. Provide clear ground space at operable parts, including pedestrian push buttons. Operable parts shall be placed within unobstructed reach range specified in PROWAG section R406.
- 28. Place traffic signal or illumination poles, ground boxes, controller boxes, signs, drainage facilities and other items so as not to obstruct the pedestrian access route or clear ground space.
- 29. Street grades and cross slopes shall be as shown elsewhere in the plans.
- 30. Changes in level greater than 1/4 inch are not permitted.
- 31. The least possible grade should be used to maximize accessibility. The running slope of sidewalks and crosswalks within the public right of way may follow the grade of the parallel roadway. Where a continuous grade greater than five percent (5%) must be provided, handrails may be desirable to improve accessibility. Handrails may also be needed to protect pedestrians from potentially hazardous conditions. If provided, handrails shall comply with PROWAG R409.
- 32. Handrail extensions shall not protrude into the usable landing area or into intersecting pedestrian routes.
- 33. Driveways and turnouts shall be constructed and paid for in accordance with Item 'Intersections, Driveways and Turnouts". Sidewalks shall be constructed and paid for in accordance with Item. "Sidewalks".
- 34. Sidewalk details are shown elsewhere in the plans.



DETECTABLE WARNING SURFACE DETAILS

PEDESTRIAN TRAVEL

DIRECTION

TURNING

SPACE

PARALLEL CURB RAMP

TYPICAL PLACEMENT OF DETECTABLE WARNING

SURFACE ON LANDING AT STREET EDGE.

RAMP


2' (Min.)

DETECTABLE WARNING


SURFACE

BACK OF


RAMP



PEDESTRIAN TRAVEL



FILE: ped18 C TXDOT: MARCH, 2002



CRP


SHEET 2 OF 4

PED-18 CONT SECT JOB


DN:TxDOT DW:VP CK:KM CK:PK & JG HIGHWAY 238,241 242,246 VA 0916 | 35 | SHEET NO.

NUECES


37



SECTION VIEW DETAIL CURB RAMP AT DETECTIBLE WARNINGS




- * X IF CURB HEIGHT IS GREATER THAN 6 INCHES, USE GRADE LESS THAN OR EQUAL TO 5%. HANDRAIL AND DETECTABLE WARNING ARE NOT REQUIRED.




PROTECTED ZONE


NOTE: IN PEDESTRIAN CIRCULATION AREA, MAXIMUM 4" PROJECTION FOR POST OR WALL MOUNTED OBJECTS BETWEEN 27" AND 80" ABOVE THE SURFACE.



CLEAR SPACE ADJACENT TO PEDESTRIAN PUSH BUTTON



NOTE: ITEMS NOT INTENDED FOR PUBLIC USE. MINIMUM 4' X 4' CLEAR GROUND SPACE REQUIRED AT PUBLIC USE FIXTURES.



27" FROM THE SURFACE WOULD CREATE A PROTRUSION OF MORE THAN 4" INTO THE PEDESTRIAN CIRCULATION AREA, CONSTRUCT ADDITIONAL CURB OR FOUNDATION AT THE BOTTOM TO PROVIDE A MAXIMUM 4" OVERHANG.

PROTRUDING OBJECTS OF A HEIGHT ≤27" ARE DETECTABLE BY CANE AND DO NOT REQUIRE ADDITIONAL TREATMENT.

DETECTION BARRIER FOR **VERTICAL CLEARANCE < 80"**

SHEET 3 OF 4




PEDESTRIAN FACILITIES **CURB RAMPS**

PED-18


FILE: ped18	DN: Tx	DOT	DW: VP	CK:	KM	CK: PK & JG	
© TxDOT: MARCH, 2002	CONT	SECT	JOB			HIGHWAY	
REVISIONS REVISED 08,2005	0916	35	238,24 242,24	1 5	VA		
REVISED 06, 2012 REVISED 01, 2018	DIST		COUNTY	′	SHEET NO.		
	CRP		NUEC	ES		38	

* WHERE DRIVEWAYS CROSS THE PEDESTRIAN ROUTE, SIDES SHALL BE FLARED AT 10% MAX SLOPE.


TYPICAL CROSSING LAYOUTS SEE SHEET 1 OF 4 FOR DETAILS AND DIMENSIONS




SKEWED INTERSECTION WITH "LARGE" RADIUS




SKEWED INTERSECTION WITH "SMALL" RADIUS



NORMAL INTERSECTION WITH "SMALL" RADIUS



AT INTERSECTION W/FREE RIGHT TURN & ISLAND



 \boxtimes

k k K

LEGEND:

SHOWS DOWNWARD SLOPE.

DENOTES PREFERRED LOCATION OF PEDESTRIAN PUSH BUTTON (IF APPLICABLE).

DENOTES PLANTING OR NON-WALKING SURFACE NOT PART OF PEDESTRIAN CIRCULATION PATH. **PED-18**


FILE: ped18	DN: T x	DN: T×DOT DW: VP		CK:	KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB			HIGHWAY
REVISIONS REVISED 08,2005	0916	35	238,241 242,246		VA	
REVISED 06, 2012 REVISED 01, 2018	DIST		COUNTY		SHEET NO.	
	CRP		NUEC	ES		39

SHEET 4 OF 4

PEDESTRIAN FACILITIES

CURB RAMPS

Texas Department of Transportation



PLAN VIEW

NIN.

ENGINEER.

FLOW ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE AS DISTURBED AREA DIRECTED BACK OF CURB LIP OF GUTTER STAKE ON DOWNHILL SIDE OF TEMP. EROSION LOG AT 8' (ON CENTER) MAX. AS NEEDED TO SECURE LOG, CONTROL LOG OR AS DIRECTED BY THE ENGINEER.

STAKE ON DOWNHILL SIDE OF LOG AT 8' (ON CENTER) MAX. AS NEEDED TO SECURE LOG, (TYP.) OR AS DIRECTED BY THE ENGINEER. R. O. W. TEMPORARY EROSION CONTROL LOG FLOW DISTURBED AREA SECURE END BACK OF CURB OF LOG TO STAKE AS DIRECTED LIP OF GUTTER ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS

PLAN VIEW

TEMP. EROSION R. O. W. CONTROL LOG COMPOST CRADLE UNDER EROSION CONTROL LOG STAKE SECTION C-C



PLAN VIEW


TEMP. EROSION

COMPOST CRADLE

UNDER EROSION

CONTROL LOG

CONTROL LOG



RUNOFF EVENTS

SECTION B-B EROSION CONTROL LOG AT BACK OF CURB

CL-BOC

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

SECTION A-A **EROSION CONTROL LOG DAM**



LEGEND

CL-D — EROSION CONTROL LOG DAM

TEMP. EROSION-

CONTROL LOG

(TYP.)

COMPOST CRADLE

UNDER EROSION

CONTROL LOG

⟨CL-BOC⟩— EROSION CONTROL LOG AT BACK OF CURB.

√CL-ROW)— EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY


(CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING

EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING -(CL-SSL)

≺CL-DI \succ EROSION CONTROL LOG AT DROP INLET

(CL-CI) $\!-$ EROSION CONTROL LOG AT CURB INLET

 $\mathsf{CL} ext{-}\mathsf{GI}$ ullet EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over Log Traps: the drainage area).

Control logs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction
- limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.


Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:

- 1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S RECOMMENDATIONS. OR AS DIRECTED BY THE ENGINEER.
- 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
- UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
- FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
- STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
- DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
- COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
- SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
- TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE
- 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.



SHEET 1 OF 3



MINIMUM

COMPACTED

DIAMETER

MINIMUM


COMPACTED DIAMETER

TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES

EROSION CONTROL LOG

EC(9)-16

FILE: ec916	DN: TxD	OT	ск: КМ	DW:	LS/PT	CK: LS
C TxDOT: JULY 2016	CONT	SECT	JOB		ні	GHWAY
REVISIONS	0916	35	238,241 242,246			VA
	DIST		COUNTY			SHEET NO.
	CRP		NUECE	S		40



0916 35

238,241 242,246

NUECES

VA SHEET NO.

41

SECURE ENDO OF LOG TO STAKE AS DIRECTED


TEMP. EROSION-CONTROL LOG

FLOW

(CL-GI)-

EROSION CONTROL LOG AT CURB & GRADE INLET

EROSION CONTROL LOG AT DROP INLET





EROSION CONTROL LOG AT CURB INLET

2 SAND BAGS

(CL-CI



TEMP. EROSION CONTROL LOG



SANDBAG


USE STAKES ON DOWNSTREAM SIDE OF LOGS, AT ENDS, MIDPOINT, & AS NEEDED OR SANDBAGS TO HOLD IN PLACE.

NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.

6" CURB-

2 SAND BAGS

TEMP. EROSION CONTROL LOG



SHEET 3 OF 3


CURB INLET INLET EXTENSION



TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES **EROSION CONTROL LOG**

FC (Q) - 16

	19	, -	10		
FILE: ec916	DN: Tx[OT	ск: КМ	DW: LS/F	PT CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY
REVISIONS	0916	35	238,241 242,246		VA
	DIST		COUNTY		SHEET NO.
l	CRP		NUECE	ES	42



OVERLAP ENDS TIGHTLY 24" MINIMUM

COMPLETELY SURROUND DRAINAGE ACCESS TO AREA DRAIN INLETS WITH EROSION CONTROL LOG

- FLOW

-STAKE OR USE SANDBAGS ON DOWNHILL SIDE OF LOG AS NEEDED TO HOLD IN PLACE (TYPICAL)

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS

BC(1)-21

		-	•	_			
FILE:	bc-21, dgn	DN: T	(DOT	ck: TxDOT	D₩:	TxDOT	ck: TxDOT
© TxD0T	November 2002	CONT	SECT	JOB		HI	GHWAY
4-03	REVISIONS 7-13	0916	35	238,241 242,246			VA
9-07	8-14	DIST		COUNTY			SHEET NO.
5-10	5-21	CRP		NUECE	ES		43



- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- 4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

BEGIN T-INTERSECTION WORK ZONE * * G20-9TP ★ ★ R20-5T FINES DOUBL XX R20-5aTP NORKERS ARE PRESENT END WORK ZONE ★ ★ G20-2bT G20-1bTI INTERSECTED 1000' -1500' Hwy 1 Block - City 1000'-1500' - Hwy 1 Block - City ROADWAY \Rightarrow ROAD WORK G20-16TR NEXT X MILES => WORK ZONE G20-2bT * * Limit BEGI G20-5T * * G20-9TP ZONE G20-6T X X R20-5T FINES IDOUBLI X R20-5aTP NORMERS ROAD WORK G20-2

CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING 1,5,6

SIZE

Posted Speed Spacing MPH 30 35 40 45 50 55 60

SPACING

Sign∆

"X"

Feet

(Apprx.)

120

160

240

320

400

500²

6002

700²

800²

900²

1000 ²

onventional Expressway/ Freeway 48" x 48' 48" x 48' 48" x 48" 36" x 36 65 70 48" x 48' 48" x 48' 75 80

¥ For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

△ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

Sign

Number

or Series

CW201

CW21

CW22

CW23

CW25

CW14

CW1, CW2,

CW7. CW8.

CW9, CW11


CW3, CW4,

CW5, CW6,


CW10, CW12

CW8-3,

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded

to the nearest whole mile with the approval of the Engineer.

The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2b) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.

** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.

Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic

Contractor will install a regulatory speed limit sign at the end of the work zone.

	LEGEND							
ш	Type 3 Barricade							
00	000 Channelizing Devices							
_	Sign							
х	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.							

SHEET 2 OF 12

Texas Department of Transportation

Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

				_			
ILE:	bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>D₩s</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	D₩s	TxDOT	ck: TxDOT
TxD0T	November 2002	CONT	SECT	JOB		HIC	HWAY
	REVISIONS	0916	35	238,241 242,246			VA
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	CRP		NUECE	ES		44

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:

40 mph and greater 0.2 to 2 miles

35 mph and less

0.2 to 2 miles

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only.
 Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

LE:	bc-21.dgn	DN: TX	TOC	ck: TxDOT	D₩:	TxDOT	CK: TXDOT
TxD0T	November 2002	CONT	SECT	JOB		H	HIGHWAY
0.07	REVISIONS	0916	35	238,241 242,246			VA
9-07	8-14 5-21	DIST		COUNTY			SHEET NO.
7-13	3-21	CRP		NUECE	ES		45

ATE:

12' min.

Poved

shou I der

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS ROAD ROAD ROAD ROAD WORK minimum WORK WORK WORK from AHEAD AHEAD AHEAD curb AHEAD min. XX MPH

* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb.


Objects shall NOT be placed under skids as a means of leveling.

7.0' min.

9.0' max.

* X When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane.

Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.



7-0' min.

6' or

greater

Paved

shou I der

9.0' max.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

Attachment to wooden supports
will be by bolts and nuts
or screws. Use TxDOT's or
manufacturer's recommended
procedures for attaching sign
substrates to other types of
sign supports


7.0' min.

9.0' max.

Nails shall NOT
be allowed.
Each sign
shall be attached
directly to the sign
support. Multiple
signs shall not be
joined or spliced by
any means. Wood
supports shall not be
extended or repaired
by splicing or
other means.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectorized when used at night.
 STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING RE	QUIREMENT	S (WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

SIDE ELEVATION

Wood

- Permanent signs are used to give notice of traffic laws or regulations, call
 attention to conditions that are potentially hazardous to traffic operations,
 show route designations, destinations, directions, distances, services, points
 of interest, and other geographical, recreational, specific service (LOGO), or
 cultural information. Drivers proceeding through a work zone need the same,
 if not better route guidance as normally installed on a roadway without
 construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- 4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- 1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- 2. Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- 5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- 6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations, if there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- 9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- b. Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
- c. Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
- d. Short, duration work that occupies a location up to 1 hour.
- e. Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- 1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- 2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- the ground.
 3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
 - Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

6.0' min.

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- 1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- 2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- 3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- 2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- 3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL} , shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

 All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when
 the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any
 intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- 4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
 5. Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- 7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
 The sandbags will be tied shut to keep the sand from spilling and to maintain a
- The sandbags will be fied shuf to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
 Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
 Sandbags shall be made of a durable material that tears upon vehicular
- impoct. Rubber (such as tire inner tubes) shall NOT be used.
 Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured
- with rubber bases may be used when shown on the CWZTCD list.
 7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- 8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

 Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face. SHEET 4 OF 12

Traffic Safety Division Standard




BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) -21

ILE:	bc-21.dgn	DN: T	KDOT	ck: TxDOT	D₩:	TxDOT	ck: TxDOT
TxD0T	November 2002	CONT	SECT	JOB		HIC	SHWAY
	REVISIONS	0916	35	238,241 242,246			VA
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	CRP		NUECE	S		46

DATE




-2" x 2"

12 ga. upright


2"

SINGLE LEG BASE



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



WEDGE ANCHORS

Post

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
 - See BC(4) for definition of "Work Duration."
 - Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE:	bc-21.dgn	DN: T:	xDOT	ck: TxDOT	D₩:	TxDOT	ck: TxD0
© TxDOT	November 2002	CONT	SECT	JOB		ΗI	GHWAY
	REVISIONS	0916	35	238,241 242,246			VA
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	CRP		NUECE	ES		47

SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32'

going in opposite directions. Minimum

back fill puddle.

weld, do not

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit romp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
 Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT"
- on a PCMS. Drivers do not understand the message.

 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
	EMER	Slippery	SL IP
Emergency Vehicle	EMER VEH	South	S
	ENT	Southbound	(route) S
Entrance, Enter	EXP LN	Speed	SPD
Express Lane	EXPWY	Street	ST
Expressway XXXX Feet	XXXX FT	Sunday	SUN
	FOG AHD	Telephone	PHONE
Fog Ahead		Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday		Traffic	TRAF
Hazardous Driving	HAZ DRIVING	Travelers	TRVLRS
Hazardous Material		Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway	UD UDC	Vehicles (s)	VEH, VEHS
Hour (s)	HR, HRS	Warning	WARN
Information	INFO	Wednesday	WED
It Is	ITS	Weight Limit	WT LIMIT
Junction	JCT	West	W
Left	LFT	Westbound	(route) W
Left Lane	LFT LN	Wet Pavement	WET PVMT
Lane Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL		
Maintenance	MAINT		

Roadway

designation # IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp	Closure List	Other Cond	ition List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT
xxxxxxx			

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

A	ction to Take	e/E Lis		ve I	Location List		Warning List		* * Advance Notice List
	MERGE RIGHT		FORM X LINES RIGHT		AT FM XXXX		SPEED LIMIT XX MPH		TUE-FRI XX AM- X PM
	DETOUR NEXT X EXITS		USE XXXXX RD EXIT		BEFORE RAILROAD CROSSING		MAXIMUM SPEED XX MPH		APR XX- XX X PM-X AM
	USE EXIT XXX		USE EXIT I-XX NORTH		NEXT X MILES		MINIMUM SPEED XX MPH		BEGINS MONDAY
	STAY ON US XXX SOUTH		USE I-XX E TO I-XX N		PAST US XXX EXIT		ADVISORY SPEED XX MPH		BEGINS MAY XX
	TRUCKS USE US XXX N		WATCH FOR TRUCKS		XXXXXXX TO XXXXXXX		RIGHT LANE EXIT		MAY X-X XX PM - XX AM
	WATCH FOR TRUCKS		EXPECT DELAYS		US XXX TO FM XXXX		USE CAUTION		NEXT FRI-SUN
	EXPECT DELAYS		PREPARE TO STOP				DRIVE SAFELY		XX AM TO XX PM
	REDUCE SPEED XXX FT		END SHOULDER USE				DRIVE WITH CARE		NEXT TUE AUG XX
	USE OTHER ROUTES		WATCH FOR WORKERS						TONIGHT XX PM- XX AM
se 2.	STAY IN LANE	*			*	X See A	pplication Guide	elines N	Note 6.

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
 FI and MI. MILE and MILES interchanged as appropriate.
- 7. FT and MI, MILE and MILES interchanged as appropriate 8. AT. BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4)

PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


FULL MATRIX PCMS SIGNS

BLVD

CLOSED

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE


Traffic Safety

BC(6)-21

MESSAGE SIGN (PCMS)


FILE:	bc-21.dgn	DN: T	(DOT	ck: TxDOT	D₩:	TxDOT	ck: TxDOT
© TxD0T	November 2002	CONT	SECT	T JOB		HIGHWAY	
REVISIONS		0916	35	35 238,241 242,246		VA	
9-07	8-14	DIST	COUNTY			SHEET NO.	
7-13	5-21	CRP	NUECES				48

- 1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10.Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- 11. Single slope barriers shall be delineated as shown on the above detail.




IN WORK ZONES LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE

BARRIER (LPCB) USED

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)




DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- 5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- 2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- 4. The Flashing Arrow Board should be able to display the following symbols:



- 5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.

 9. The sequential arrow display is NOT ALLOWED.

 10. The flashing arrow display is the TxDOT standard; however, the sequential chevron
- display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
 A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
 A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility,
- flash rate and dimming requirements on this sheet for the same size arrow.
- 14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

	REQUIREMENTS										
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE								
В	30 × 60	13	3/4 mile								
С	48 × 96	15	1 mile								

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimmina devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted in the plans.
- 5. A TMA should be used gnytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- 6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



Traffic Safety Division Standar

BARRICADE AND CONSTRUCTION ARROW PANEL. REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC(7)-21

FILE:	bc-21.dgn	DN: T	xDOT	ck: TxDOT	D₩:	TxDOT	ck: TxDC
© TxDOT	November 2002	CONT SECT		JOB		HIGHWAY	
9-07 8-	REVISIONS	0916	35	238,241 242,246			VA
	8-14	DIST	COUNTY				SHEET NO.
7-13	5-21	CDD	MILIECES				40

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWTTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:


- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs, of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.





DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TIC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CM1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type $B_{\rm FL}$ or Type $C_{\rm FL}$ Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12


Texas Department of Transportation


Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21


	_		_			
ILE: bc-21.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C)TxDOT November 2002	CONT	SECT	JOB		HIC	GHWAY
REVISIONS 4-03 8-14	0916	35	238,241 242,246			VA
4-03 8-14 9-07 5-21	DIST		COUNTY			SHEET NO.
7-13	CRP	NUECES				50






- 1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- 4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- 5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List"
- 6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- 7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42"
- 3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black nonreflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300. unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the out side of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type BFL or Type CFL conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula		esirab er Lend **		Spacing of Channelizing Devices		
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	2	1501	1651	180'	30′	60'	
35	L = WS ²	2051	225′	245'	35'	701	
40	- 60	2651	295′	3201	40'	801	
45		450′	495′	540'	45′	90'	
50		5001	550′	600'	50′	100'	
55	L=WS	550′	605′	660′	55′	110′	
60	L-#3	600'	6601	720'	60′	120'	
65		650'	7151	780'	65′	130'	
70		7001	770′	840'	70′	140′	
75		7501	825′	900'	75′	150'	
80		800'	880'	960'	80'	160′	
	Y Topos I	onothe.	have be	00 5000	ded off		

Suggested Maximum

Traffic Safety Division Standard

*X Taper lengths have been rounded off. L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Texas Department of Transportation


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) -21


ILE:	bc-21.dgn	DN: T	xDOT	ck: TxD0T	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		HIG	HWAY
	REVISIONS	0916	35	238,241 242,246			VA
9-07 8-14	•	DIST		COUNTY		SHEET NO.	
7-13	5-21	CRP		NUECE	S		51

TYPE 3 BARRICADES

- Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- . Warning lights shall NOT be installed on barricades.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION

Two-Piece cones

1. Where positive redirectional capability is provided, drums may be omitted. 2. Plastic construction fencing may be used with drums for safety as required in the plans. 3. Vertical Panels on flexible support may be substituted for drums when the Typical shoulder width is less than 4 feet. Plastic Drum 4. When the shoulder width is greater than 12 feet, steady-burn lights PERSPECTIVE VIEW may be omitted if drums are used. 5. Drums must extend the length These drums are not required of the culvert widening. on one-way roadway **LEGEND** Plastic drum Plastic drum with steady burn light two drums s ss the work or yellow warning reflector Steady burn warning light or yellow warning reflector of S Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums) PLAN VIEW

3"-4"


4" min. orange
2" min.
4" min. white
2" min.
2" min.
4" min. orange
4" min. orange
4" min. orange
4" min. orange
4" min. white

6" min. 2" min. 4" min. 2" mox. 3" min. 2" to 6" 3" min. 28" min.

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

One-Piece cones

Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

LE:	bc-21.dgn	DN: To	KDOT	ck: TxDOT	D₩:	TxDOT	CK: TXDOT
TxDOT	November 2002	CONT	SECT	JOB		H	HIGHWAY
	REVISIONS	0916	35	238,241 242,246			VA
	8-14	DIST	COUNTY				SHEET NO.
7-13	5-21	CRP		NUECE	ES		52

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the IMUTCD and as shown on the plans,
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard povement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised povement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body).
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIO	NS
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12




Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

	-					
bc-21.dgn	DN: T	(DOT	ck: TxDOT	D₩:	TxDOT	CK: TXDOT
TxDOT February 1998	CONT	SECT	JOB		HIG	HWAY
REVISIONS 98 9-07 5-21	0916	35	238,241 242,246			VA
02 7-13	DIST	ST COUNTY			SHEET NO.	
02 8-14	CRP		NUECE	ES		53




EDGE & LANE LINES FOR DIVIDED HIGHWAY


RAISED PAVEMENT MARKERS

REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



TWO-WAY LEFT TURN LANE



Raised pavement markers used as standard

Item 672 "RAISED PAVEMENT MARKERS."


pavement markings shall be from the approved products list and meet the requirements of

STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS

BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

DATE



LEGEND Type 3 Barricade Channelizing Devices Truck Mounted Attenuator (TMA) Heavy Work Vehicle Portable Changeable Message Sign (PCMS) Trailer Mounted Flashing Arrow Board M Traffic Flow Sign Q LO Flagger

	V ,					,		_
Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	2	1501	1651	180'	30′	60′	1201	90'
35	L = WS ²	2051	2251	245'	35'	701	160'	120'
40	80	2651	2951	3201	40'	80'	240'	155′
45		4501	495′	540'	45′	901	3201	195'
50		5001	550′	600'	50'	1001	4001	240'
55	L=WS	5501	6051	660'	55′	110'	5001	295'
60	- "3	600'	660'	720'	60′	120'	600,	350'
65		650′	715′	7801	65'	1301	700′	410′
70		7001	770′	840'	701	140'	8001	475′
75	l	7501	8251	900,	75′	150'	900'	540'

- * Conventional Roads Only
- ** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE							
MOBILE	SHORT DURATION						
	✓	✓	✓	√			

GENERAL NOTES

Line

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer
- 3. Stockpiled material should be placed a minimum of 30 feet from
- nearest traveled way.

 4. Shodow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shodow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 5. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space. 6. See TCP(5-1) for shoulder work on divided highways, expressways and
- 7. Inactive work vehicles or other equipment should be parked near the
- right-of-way line and not parked on the paved shoulder.
- 8. CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.


Texas Department of Transportation


Traffic Operations Division Standard

TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(2-1)-18

	_				
LE: tcp2-1-18.dgn	DN:		CK:	DW#	CK:
TxDOT December 1985	CONT	SECT	J08		HIGHWAY
REVISIONS -94 4-98	0916	35	238,241 242,246		VA
-95 2-12	DIST	COUNTY			SHEET NO.
-97 2-18	CRP		NUECI	ES	55





ONE LANE TWO-WAY

CONTROL WITH FLAGGERS

	LEGEND						
	Type 3 Barricade		Channelizing Devices				
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)				
	Trailer Mounted Flashing Arrow Board	I ^	Portable Changeable Message Sign (PCMS)				
_	Sign	♦	Traffic Flow				
\Diamond	Flag	LO	Flagger				

Posted Speed	Formula	D	Minimum esirab er Leng X X	le gths	Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance
 *		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"	
30	ws ²	150'	165′	180'	30'	60′	120'	90'	200'
35	L = WS	205'	225′	245′	35′	70′	160'	120′	250'
40	60	265′	295′	3201	40′	80'	240'	1551	305′
45		450'	495′	540′	45′	90′	320'	195′	360′
50		500′	550′	600′	50′	100′	400'	240′	425'
55	L=WS	550′	6051	660′	55′	110'	500′	295′	495′
60	L "3	600'	660′	720′	60′	120′	600'	350′	570′
65		650'	715′	780′	65′	130′	700′	410'	645'
70		700′	770′	840′	70'	140′	800'	475′	730′
75		750′	825′	900′	75′	150′	900'	540′	820'

* Conventional Roads Only

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE							
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY			
	1	1	1				

GENERAL NOTES

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
- 4. Flaggers should use two-way radios or other methods of communication to control traffic.

5. Length of work space should be based on the ability of flaggers to communicate.

- 6. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 7. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-2a)

8. The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.

9. The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum

mounting height.

TCP (2-2b)

- 10. Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
- 12.Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situtations.



TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

Traffic Operation Division Standard

TCP(2-2)-18

FILE: tcp2-2-18.dgn	DNs		CK=	DW=	CK:
©⊤xDOT December 1985	CONT	SECT	JOB		HIGHWAY
REVISIONS 8-95 3-03	0916	35	238,241 242,246		VA
1-97 2-12	DIST		COUNTY		SHEET NO.
4-98 2-18	CRP		NUECI	ES	56

Type 3 Barricade Channelizing Devices Truck Mounted Attenuator (TMA) Trailer Mounted Flashing Arrow Board Sign Traffic Flow		LEGEND						
Heavy Work Vehicle Attenuator (TMA) Trailer Mounted Flashing Arrow Board Sign Traffic Flow	~~~	Type 3 Barricade		Channelizing Devices				
Flashing Arrow Board (M) Message Sign (PCMS) Sign Traffic Flow		Heavy Work Vehicle						
			M					
		Sign	\ \ \ \	Traffic Flow				
Triagger — Triagger		Flag		Flagger				

	<u> </u>					, 9 9 .		
Posted Speed	Formula	Minimum Desirable Taper Lengths **			Spacir Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	WS ²	150′	165′	180'	30'	60′	120′	90'
35	L = 7 WS	2051	225′	245'	35′	70′	160′	120′
40	00	265′	295′	3201	40′	80′	240′	155′
45		450′	4951	540'	45′	90'	320'	1951
50		5001	550′	6001	50'	100'	400'	240'
55	L=WS	550′	605′	6601	55′	110'	500′	295'
60] - ""	600′	660′	7201	60′	120'	600′	350′
65		6501	715′	7801	65′	130'	7001	410'
70		700′	7701	840'	70′	140'	800′	475′
75]	750′	825′	900′	75′	150′	900′	540'

- * Conventional Roads Only
- ** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE						
MOBILE	SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY					
		1	1			

GENERAL NOTES

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- 4. For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

7. If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

CP (2-4b)

8. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
LANE CLOSURES ON MULTILANE
CONVENTIONAL ROADS

TCP(2-4)-18

FILE: tcp2-4@18.dgn	DN:		CK: DW:		CK:
©TxDOT December 1985	CONT	SECT	JOB	Н	IGHWAY
8-95 3-03 REVISIONS	0916	35	238,241 242,246		VA
1-97 2-12	DIST		COUNTY		SHEET NO.
4-98 2-18	CRP		NUECE	S	57




LEGEND						
	Type 3 Barricade					
• • •	Channelizing Devices					
Â	Troiler Mounted Flashing Arrow Boord					
4	Sign					
NNN	Safety glare screen					

DEPARTMENTAL MATERIAL SPECIFICA	ATIONS
SIGN FACE MATERIALS	DMS-8300
DELINEATORS AND OBJECT MARKERS	DMS-8600
MODULAR GLARE SCREENS FOR HEADLIGHT BARRIER	DMS-8610

Only pre-qualified products shall be used. A copy of the Compliant Work Zone Traffic Control Devices List" CWZTCD) describes pre-quolified products and their sources and may be found at the following web address:

http://www.txdot.gov/business/resources/producer-list.html



VERTICAL PANELS & OPPOSING TRAFFIC LANE DIVIDERS (OTLD) SEPARATING TWO-WAY TRAFFIC ON NORMALLY DIVIDED HIGHWAYS

sections will not be spanned by any one safety glare screen unit.

4. Payment for these devices will be under statewide Special Specification

This detail is only intended to show types of locations where Glare Screens would be oppropriate. Required signing and other devices shall

ore installed with reflective sheeting as described.

"Modulor Glore Screens for Headlight Borrier."

be as shown elsewhere in the plans.

 Screen Panel/blades will be designed such that reflective sheeting conforming with Departmental Material Specification DMS-8300, Sign Face Materials, Type B or C Yellow, minimum size of 2 inches by 12 inches con be attached to the edge of the panel/blade. The sheeting sholl be attached to one glore screen ponel/blode per section of concrete borrier not to exceed o spacing of 30 feet. Barrier reflectors ore not necessary when panel/blades

₹

4>

➾

When two-lone, two way traffic control must be maintained on one roadway of o normally divided highway, opposing traffic sholl be separated with either temporary traffic barriers, channelizing devices, or a temporary raised island throughout the length of the two way operation. The above Typical Application is intended to show the appropriate opplication of channelizing devices when they are used for this purpose. This is not a traffic control pion. If this detoil is to be used for other types of roods or applications, those locations should be stated elsewhere in the



NOTES:

Space devices according to the Tangent Spacing shown on the Device Spacing table on BC(9) but not exceeding 100'.

- Every fifth device should be on OTLD except when spaced closer to occommodate on intersection. An OTLD should be the first device on each side of intersecting streets or roods.
- 4. Locations where surface mount bases with adhesives or self-righting devices will be required in order to maintain them in their proper position should be noted elsewhere in the plans.
- Channelizing devices are to be vertical panels, 42" cones or tubular markers that are at least 36" toll. Tubular markers used to separate traffic should have a rubber base weighing at least 30 pounds. Tubular markers that ore 42" toll or more shall have four bonds of reflective material as detailed for 42" cones on BC(10). Tubular markers less than 42" but at least 36" toll shall have three bonds of 3" wide white reflective material spaced 2" apart. Reflective material shall meet DMS-8300, Type A.



Traffic Operations Division Standard

TRAFFIC CONTROL PLAN TYPICAL DETAILS

W7 (TD) - 17

	W	_ \	U				
ILE:	wztd-17, dgn	DN: T	×DOT	CK: TXDOT	D#:	TxDOT	CK: TXDOT
C) TxDOT	February 1998	CONT	SECT	JOB		ніс	CHWAY
4-98	REVISIONS 2-17	0916	35	238,241 242,246	ij		VA [
3-03	¢-11	DIST		COUNTY			SHEET NO.
7-13		CRP	Ε.	NUECE	S	1	58

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS DOUBLE TABS NO-PASSING LINE ← 20′±6" SOL ID LINES Type Y-2 or W 20' ±6" SINGLE TABS NO-PASSING LINE or CHANNEL IZATION TAPE LINE 4.5'±6" Yellow or White Type Y-2 or V **BROKEN** TABS 000 →| | 1′±3" LINES TAPE (FOR CENTER LINE OR LANE LINE) → 4.5′±6" Yellow or White Type W — 12′±6" 3'±3" TABS WIDE DOTTED LINES (FOR LANE DROP LINES) TAPE -- 12' ±6" → 3′±3" White 20' ±6" TABS 07 WIDE GORE --12" MARK INGS TAPE 20' ±6"


NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexiblereflective roadway marker tabs unless otherwise specified elsewhere in plans.
- 2. Short term payement markings shall NOT be used to simulate edge lines.
- 3. Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- 4. Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- 5. No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent payement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- 6. For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- 8. For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.


TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.


WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS




CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS



LANE LINES FOR DIVIDED HIGHWAY



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



Removable Raised Short Term Pavement 1 4 1 Pavement Marker Marking (Tape)

If raised payement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

Texas Department of Transportation

Traffic Operations Division Standard

PREFABRICATED PAVEMENT MARKINGS

- 1. Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240
 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Costruction-Grade
 Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

1. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

1. DMSs referenced above can be found along with embedded links to their respective MPLs at the following website: http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm

WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ (STPM) - 13

l	FILE:	wzstpm-13.dgn	DN: T	xDOT	CK: TXDOT DW:	TxDOT	ck: TxDOT
ı	© TxDOT	April 1992	CONT	SECT	JOB	HI	GHWAY
ı	1-97	REVISIONS	0916	35	238,241 242,246	į.	VA
ı	3-03		DIST		COUNTY	8	SHEET NO.
J	7-13		CRP		NUECES	i.	59

UNEVEN LANES *See Table 1 Area where Edge Area where Edge Condition exists Condition exists Table 1 "X" distance "X" distance (See Note 4) (See Note 4) *See Table 1 UNEVEN 4 4 UNEVEN LANES LANES CW8-11 UNEVEN LANES **UNEVEN LANES** CW8-11 FOUR LANE CONVENTIONAL ROAD TWO LANE CONVENTIONAL ROAD NO CENTER LINE CW8-12 "X" distance (See Note 4) Area missing Center Area where Edge Line markings Condition exists * See Table 1 "X" distance (See Note 4) "X" distance (See Note 4) UNEVEN **"UNEVEN**" LANES LANES NO. 4 CENTER CW8-11 LINE UNEVEN LANES NO CENTER LINE

DIVIDED ROADWAY

DEPARTMENTAL MATERIAL SPECIFICATIONS							
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240						
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241						
SIGN FACE MATERIALS	DMS-8300						

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

- If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
- UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
- 3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
- 4. Signs shall be spaced at the distances recommended as per BC standards.
- Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
- Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
- 7. Short term markings shall not be used to simulate edge lines.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1								
Edge Condition	Edge Height (D)	* Warning Devices						
O	Less than or equal to: 11/4" (maximum-planing) 11/2" (typical-overlay)							
	Distance "D" may be a maximum of 1 1/4 " for planing operations and 2" for overlay operations if uneven lanes with edge condition 1 are open to traffic after work operations cease.							
② >3 T D	Less than or equal to 3"	Sign: CW8-11						
0" to 3/4" D	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".							
Notched Wedge Joint		<u> </u>						

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING	SIGN SIZE
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" × 48"

Texas Department of Transportation

SIGNING FOR UNEVEN LANES

WZ (UL) - 13


Traffic Operations Division Standard


DN: TxDC	T CK: TxDOT DW:	TxDOT ck: TxDOT
CONT	CT JOB	HIGHWAY
0916 3	5 238,241 242,246	VA
DIST	COUNTY	SHEET NO.
CRP	NUECES	60
	0916 3	CONT SECT JOB 238,241 242,246 DIST COUNTY

112

ATE:

TWO LANE CONVENTIONAL ROAD





	LEGEND								
	Type 3 Barricade	••	Channelizing Devices						
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)						
_	Sign	♦	Traffic Flow						
	Flag	ПО	Flagger						

Speed	Formula	D	Minimum esirab er Lend **	le	Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	WS ²	1501	1651	1801	30′	60′	120'	90′
35	L= WS	2051	2251	2451	35′	701	160'	120′
40	80	2651	2951	3201	40′	80'	240'	155′
45		4501	4951	5401	45′	90'	320′	195′
50	Ĭ Ì	5001	5501	6001	50′	100'	400'	240′
55	L=WS	5501	6051	6601	55′	110'	500'	295′
60	- "3	6001	6601	7201	60′	120'	600′	350′
65	j j	6501	7151	7801	65′	130′	700′	410′
70		7001	7701	8401	70′	140′	8001	475′
75		7501	8251	9001	75′	150'	9001	540′

* Conventional Roads Only


** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.

GENERAL NOTES

- 1. The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.
- 2. Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- 4. Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- 5. High level warning devices (flag trees) may be used at corners of the vehicle.
- When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P) signs may be implemented when approved by the engineer.
- 7. For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- 8. The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.
- Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.



R4-7 24" × 30"

SIGNAL WORK AHEAD

⇧

SIGNAL WORK AHEAD

CW20SG-1 48" × 48"

SIGNAL WORK AHEAD

OPERATIONS IN THE INTERSECTION

SHEET 1 OF 2




Traffic Operations Division Standard

TRAFFIC SIGNAL WORK TYPICAL DETAILS

WZ (BTS-1)-13

TILE: wzbts-13.dgn	DN: T	KDOT ck: TxDOT DW:	TxDOT CK: TxDOT
C)TxDOT April 1992	CONT	SECT JOB	HIGHWAY
REVISIONS	0916	35 238,241 242,246	VA
2-98 10-99 7-13	DIST	COUNTY	SHEET NO.
4-98 3-03	CRP	NUECES	61



FOR LONG TERM and INTERMEDIATE-TERM STATIONARY WORK OPERATIONS

- Sandbags shall be made of a durable material that tears upon
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD
- 7. Sandbags shall only be placed along or laid over the base supports

LEGEND								
	Sign							
	Channelizing Devices							
	Type 3 Barricade							

DEPARTMENTAL MATERIAL	SPECIFICATIONS
SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL				
ORANGE	BACKGROUND	TYPE BFL OR TYPE CFL SHEETING				
WHITE	BACKGROUND	TYPE A SHEETING				
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING				

Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address: http://www.txdot.gov/txdot_library/publications/construction.htm

See the Table on sheet 1 of 2 for Typical warning sign spacing. REFLECTIVE SHEETING

All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

OBEY

WARNING

SIGNS

STATE LAW

48" x 42"

R20-3T

R20-5T

36" × 36"

 \Diamond <>

SIGN SUPPORT WEIGHTS

- Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- vehicular impact. Rubber, such as tire inner tubes, shall not be used.
- of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fastners. Sandbags shall be placed along the length of the skids to weigh down the
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

1	LEGEND						
	in t						
	Sign						
	Channelizing Devices						
	Chamile 11211ig Devices						
	Type 3 Barricade						
	Trype o ben neede						

Temporary Traffic Barrier

SIDEWALK DIVERSION

10' Min.

SIDEWALK

CLOSED

R9-9 24" x 12"

4' Min. (See Note 7 below

CROSS HERE

R9-11aL 24" x 12"

∟Work Area

SIDEWALK

CLOSED

-Work Area

CROSSWALK CLOSURES

R9-9 24" x 12"

SIDEWALK DETOUR

R9-11aR

CW11-2

See Note 6

CW16-7PL 24" x 12"

CROSS HERE

K

| ♥ | �

♡ | ☆ |

SIDEWALK CLOSE

CROSS HERE

R9-11aR

24" x 12"

|♥||�

♦ ♦

♦

4

♦

♦

♦

♦

CW11-2 36" x 36"

See Note 6

AHEAD

CW16-9P

x 12"

 \Diamond

♦

SIDEWALK CLOSED

USE OTHER SIDE

PEDESTRIAN CONTROL

Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer. "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval

CW20SG-1

SIGNA

AHEAD

prior to installation. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic substrates, they may be mounted on top of a plastic drum at or near the

location shown. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9) and manufacturer's recommendations.

Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.

Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.

The width of existing sidewalk should be maintained if practical. Pavement markings for mid-block crosswalks shall be paid for under the

appropriate bid items.

When crosswalks or other pedestrian facilities are closed or relocated. temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian SHEET 2 OF 2

Texas Department of Transportation

TRAFFIC SIGNAL WORK BARRICADES AND SIGNS

WZ (BTS-2) -13

SIGNAL

WORK

♦

♦

SIGNAL WORK

AHEAD

♦

♦

SIGNA

WORK

AHEAD

CW20SG-1

 \Diamond

♦

Operations Division Standard

48" × 48"

CW20SG-1

48" x 48

| ② | ② |

◇Ⅱ◇Ⅰ

| 쇼 |

₹ħ

R9-11L 24" x 12"

 \Diamond ₩

₽

CROSS HERE

FILE: wzbts-13.dgn	DN: To	kDOT	CK: TXDOT DW:	TxDOT ck: TxD0
©⊺xDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-98 10-99 7-13		35	238,241 242,246	_ VA
			COUNTY	SHEET NO.
4-98 3-03	CRP		NUECES	62

When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs. Duct tape or other adhesive material shall NOT be affixed to a sign face. $\,$

Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

GENERAL NOTES FOR WORK ZONE SIGNS

Wooden sign posts shall be painted white.

directed by the Engineer.

DURATION OF WORK

SIGN MOUNTING HEIGHT

REMOVING OR COVERING

3. Barricades shall NOT be used as sign supports.

Signs shall be installed and maintained in a straight and plumb condition.

All signs shall be installed in accordance with the plans or as directed by the Engineer. $\,$

Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as

Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).

The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.

Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".

Work zone durations are defined in Part 6, Section 66.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

Sign height of Short-term/Short Duration warning signs shall be as shown on Figure 6F-2 of the TMUTCD.

When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.

Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

Nails shall NOT be used to attach signs to any support.

CROSSHATCH LENGTH (L)

L (ft)

300 ft

500 ft

Posted Speed

(MPH)

30

35


40 45

50

55 60

65 70

75



NOTES

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 4 inches from the bridge rail or face of curb or 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions.
- No-passing zone on bridge approach is optional. If used, the no-passing zone shall be a minimum 500 feet long from the beginning of the bridge.
- 3. The crosshatching should be required if the shoulder width in advance of the bridge is 4 feet or wider and a reduction of at least 3 feet in shoulder width across the bridge occurs.
- On divided highways, review both the right and left shoulder widths for the need for narrow bridge pavement markings.

MATERIAL SPECIFICATIONS					
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200				
EPOXY AND ADHESIVES	DMS-6100				
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130				
TRAFFIC PAINT	DMS-8200				
HOT APPLIED THERMOPLASTIC	DMS-8220				
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240				

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

-Solid White Edge Line



Traffic Safety Division Standard

PAVEMENT MARKINGS FOR ROADWAYS WITH REDUCED SHOULDER WIDTHS ACROSS BRIDGE OR CULVERT

PM(5)-22

FILE: pm5-22.dgn	DN: TXDOT		ck: TxDOT	DW:	TxDOT	ck: TxDOT
CTxDOT December 2022	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0916	35	238,241 242,246	ļ	VA	
	DIST	COUNTY			SHEET NO.	
	CRP		NUECE	S		63

