

INDEX OF SHEETS

SEE SHEET 2

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT

STATE PROJECT NO.			
C 3510-6-30			
CONT	SECT	JOB	HIGHWAY
3510	06	030	SH 99
DIST	COUNTY		SHEET NO.
HOU	HARRIS		1

DESIGN SPEED: 70 MPH
ADT(2021): = 62,100
ADT(2041): = 87,000

PROJECT NO: C 3510-6-30

CSJ: 3510-06-030


HIGHWAY: SH 99

COUNTY: HARRIS

LIMITS: NORTH OF US 290 TO SH 249

LENGTH: 11.434 MILES

FOR THE CONSTRUCTION OF INSTALL/UPGRADE ROADWAY LIGHTING



VICINITY MAP
NTS

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION ON NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS FOR ALL STATE CONSTRUCTION CONTRACTS. (SP 000---008)

EXCEPTIONS: NONE
EQUATIONS: NONE
RR CROSSINGS: NONE

© 2023 by Texas Department of Transportation
(512) 416-2055; all rights reserved.



Jacob A. Sessions
3/21/2023



SUBMITTED FOR LETTING: 03/28/2023

For *[Signature]*
DISTRICT TRAFFIC ENGINEER

RECOMMENDED FOR LETTING: 3/30/2023

For *James Koch*, P.E.
DISTRICT ENGINEER

3/21/2023 1:39:33 PM
2022_0062_GEN_TS.dgn

3/21/2023 1:39:34 PM
2022_0062_GEN_INDEX.dgn

GENERAL ITEMS


- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3-8 GENERAL NOTES
- 9 ESTIMATE AND QUANTITIES
- 10-11 SUMMARY OF QUANTITIES

ILLUMINATION PLAN

- 12-60 ILLUMINATION LAYOUTS
- 61-67 UNDERPASS ILLUMINATION LAYOUTS
- 68 ELECTRICAL DETAIL SHEET
- 69-70 ILLUMINATION CIRCUIT DIAGRAMS

STANDARD DETAILS

- 71-82 *BC (1-12) -21
- 83-88 *ED (1-6) -14
- 89 *ED (10) -14
- 90-98 *HMID (1-9) -03
- 99-100 *HMIF (1-2) -98
- 101-102 *HMIP (1-2) -16
- 103 *MOWING PAD (HOU)
- 104-106 *RID (1-3) -20
- 107 *RIP (1) -19 (MOD)
- 108-110 *RIP (2-4) -19
- 111 *TCP (2-1) -18
- 112 *TCP (2-3) -18
- 113 *TCP (2-4) -18
- 114 *TCP (2-7) -18
- 115 *TCP (5-1) -18
- 116 *TCP (6-1) -12
- 117 *TCP (6-2) -12
- 118 *TCP (6-3) -12
- 119 *TCP (6-4) -12
- 120 *TCP (6-5) -12
- 121 *TCP (6-8) -14
- 122 *TCP (6-9) -14
- 123 *WV & IZ-14



*THE STANDARD SHEETS SPECIFICALLY IDENTIFIED HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THE PROJECT.

Jacob A. Sessions 3/21/2023
 JACOB A. SESSIONS DATE

ATG ALLIANCE <small>TRANSPORTATION GROUP</small>				
				© 2023
SH 99				
INDEX OF SHEETS				
(SHEET 1 OF 1)				
		PROJECT NO.		
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	2

County: Harris**Control:** 3510-06-030**Highway:** SH 99**General Notes:****General:**

Area Engineer contact information for this project follows:

Hamoon Bahrami, hamoon.bahrami@txdot.gov

Yannick F. Dwatie, yannick.dwatie@txdot.gov

Submit any questions about this project via the Letting Pre-Bid Q&A web page, located at:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

The Letting Pre-Bid Q&A web page for each project can be accessed by scrolling or filtering the dashboard using the controls on the left side to navigate to the project. Hover over the blue hyperlink of the project to view the Q&A and click on the link in the window that pops up.

Large files with relevant project documentation, such as Geotech reports, As-Built plans, and cross-sections will continue to be provided on the following FTP site:

[Index of /pub/txdot-info/Pre-Letting Responses/Houston District \(state.tx.us\)](Index of /pub/txdot-info/Pre-Letting Responses/Houston District (state.tx.us) or) or

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/Houston%20District/>

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved, except for roadway illumination, electrical, and traffic signal items.

The cost for materials, labor, and incidentals to provide for traffic across the roadway and for ingress and egress to private property in accordance with Section 7.2.4 of the standard specifications is subsidiary to the various bid items. Restore access roadways to their original condition upon completing construction.

If a foundation is to be placed where a riprap surface or an asphalt concrete surface presently exists, use caution in breaking out the existing surface for placement. Break out no greater area than is required to place the foundation. After placing the foundation, wrap the periphery with 0.5 in. pre-molded mastic expansion joint. Then replace the remaining portion of the broken out surface with Class A or Class C concrete or cold mix asphalt concrete to the exact slope, pattern, and thickness of the existing riprap or asphalt. Payment for breaking out the existing surface, wrapping the foundation, and replacing the surface is subsidiary to the various bid items.

County: Harris**Control:** 3510-06-030**Highway:** SH 99

Clearly mark or highlight on the shop drawings, the items being furnished for this project. Submit required shop drawings in accordance with the shop drawing distribution list shown in the note for Item 5 for review and distribution.

Unless otherwise shown on the plans or otherwise directed, commence work after sunrise and ensure construction equipment is off the road by sunset.

Tolls incurred by the Contractor are incidental to the various bid items.

Procure permits and licenses, which are to be issued by the City, County, or Municipal Utility District.

General: Roadway Illumination and Electrical

For roadway illumination and electrical items, use materials from pre-qualified producers as shown on the Construction Division (CST) of the Department's material producers list. Check the latest link on the Department's website for this list. The category/item is "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials found on this list.

Perform electrical work in conformance with the National Electrical Code (NEC) and the Department's standard sheets.

The Contractor may make the electrical grounding connections and permissible splices using the thermal fusion process, Cadweld, ThermOweld, or approved equal, instead of bolted connections and splices.

The Area Engineer will arrange with the Contractor, an inspection of the completed electrical systems for the highway lighting systems before final acceptance for compliance with plans and specifications. The inspection will be made with personnel from the electrical section of the Department's District Transportation Operations Office. The city's electrical division personnel will also inspect lighting systems within the city limits. Portions of the work found to be deficient during this inspection will not be accepted.

General: Site Management

Mow the grass and weeds within the project limits a maximum of 3 times a year as directed. This work is subsidiary to the various bid items.

Do not mix or store materials, or store or repair equipment, on top of concrete pavement or bridge decks unless authorized by the Engineer. Permission will be granted to store materials on surfaces if no damage or discoloration will result.

Assume ownership of debris and dispose of at an approved location. Do not dispose of debris on private property unless approved in writing by the District Engineer.

County: Harris

Control: 3510-06-030

Highway: SH 99

Control the dust caused by construction operations.

General: Utilities

Consider the locations of underground utilities depicted in the plans as approximate and employ responsible care to avoid damaging utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities.

If the Contractor damages or causes damage (breaks, leaks, nicks, dents, gouges, etc.) to the utility, contact the utility facility owner or operator immediately.

Be aware that an operational Computerized Transportation Management System (CTMS) exists within the limits of this project and that the system must remain operational throughout construction. If the Contractor damages or causes damage to this system, repair such damage within 8 hours of occurrence at no cost to the Department. In the event of system damage, notify the Director of Traffic Management Systems at 713-881-3283 within one hour of occurrence. Failure of the Contractor to repair damage to the main fiber optic cable and CCTV cable trunk lines, which convey all corridor information to TranStar, will result in the Contractor being billed for the full cost of emergency repairs.

At least 72 hours before starting work, make arrangements for locating existing Department-owned above ground and underground fiber optic, communications, power, illumination, and traffic signal cabling and conduit. Do this by calling the Department’s Houston District Traffic Signal Operations Office at 713-802-5662, or by e-mailing the Department’s Houston District Traffic Signal Operations Office at HOU-LocateRequest@txdot.gov, to schedule marking of underground lines on the ground. Use caution if working in these areas to avoid damaging or interfering with existing facilities.

Install or remove poles and luminaires located near overhead or underground electrical lines using established industry and utility safety practices. Consult the appropriate utility company before beginning such work.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Costs associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Perform electrical work in conformance with the National Electrical Code (NEC) and Department’s standard sheets.

County: Harris

Control: 3510-06-030

Highway: SH 99

Before beginning any underground work, notify the City of Houston’s Chief Inspector, Public Works and Engineering, to establish the locations of any existing electrical systems for lighting facilities within the limits of this project.

Item 5: Control of Work

Submit shop drawings electronically for the fabrication of items as documented in Table 2 below. Information and requirements for electronic submittals can be viewed in the “Guide to Electronic Shop Drawing Submittal” which can be accessed through the following web link, ftp://ftp.dot.state.tx.us/pub/txdot-info/library/pubs/bus/bridge/e_submit_guide.pdf. References to 11 in. x 17 in. sheets in individual specifications for structural items imply electronic CAD sheets.

Table 2
2014 Construction Specification Required Shop/Working Drawing Submittals - Consultant Generated Plans

Spec Item No.'s	Product	Submittal Required	Approval Required (Y/N)	Contractor/ Fabricator P.E. Seal Required	Reviewing Party	Shop or Working Drawing (Note 1)
7.16.1&.2	Construction Load Analyses	Y	Y	Y	D	WD
400	Excavation and Backfill for Structures (cofferdams)	Y	N	Y	D	WD
403	Temporary Special Shoring	Y	N	Y	D	WD
420	Formwork/Falsework	Y	N	Y	D	WD
423	Retaining Walls, (calcs req'd.)	Y	Y	Y	D	SD
425	Optional Design Calculations (Prstrs Bms)	Y	Y	Y	D	SD
425	Prestr Concr Sheet Piling	Y	Y	N	D	SD
425	Prestr Concr Beams	Y	Y	N	D	SD
425	Prestr Concr Bent	Y	Y	N	D	SD
426	Post Tension Details	Y	Y	N	D	SD
434	Elastomeric Bearing Pads (All)	Y	Y	N	D	SD
441	Bridge Protective Assembly	Y	Y	N	D	SD
441	Misc Steel (various steel assemblies)	Y	Y	N	D	SD
441	Steel Pedestals (bridge raising)	Y	Y	N	D	SD
441	Steel Bearings	Y	Y	N	D	SD
441	Steel Bent	Y	Y	N	D	SD
441	Steel Diaphragms	Y	Y	N	D	SD
441	Steel Finger Joint	Y	Y	N	D	SD
441	Steel Plate Girder	Y	Y	N	D	SD
441	Steel Tub-Girders	Y	Y	N	D	SD
441	Erection Plans, including Falsework	Y	N	Y	D	WD
449	Sign Structure Anchor Bolts	Y	Y	N	D	SD
450	Railing	Y	Y	N	D	SD
462	Concrete Box Culvert	Y	Y	N	D	SD
462	Concrete Box Culvert (Alternate Designs Only, calcs reqd.)	Y	Y	Y	D	SD
464	Reinforced Concrete Pipe (Jack and Bore only; ONLY when requested)	Y	Y	Y	D	SD
465	Pre-cast Junction Boxes, Grates,	Y	Y	N	D	SD

County: Harris

Control: 3510-06-030

Highway: SH 99

	and Inlets					
465	Pre-cast Junction Boxes, Grates, and Inlets (Alternate Designs Only, calcs req'd.)	Y	Y	Y	D	SD
466	Pre-cast Headwalls and Wingwalls	Y	Y	N	D	SD
467	Pre-cast Safety End Treatments	Y	Y	N	D	SD
495	Raising Existing Structure (calcs reqd.)	Y	Y	Y	D	SD
610	Roadway Illumination Supports (Non-Standard only, calcs reqd.)	Y	Y	Y	D	SD
613	High Mast Illumination Poles (Non-standard only, calcs reqd.)	Y	Y	Y	D	SD
627	Treated Timber Poles	Y	Y	N	D	SD
644	Special Non-Standard Supports (Bridge Mounts, Barrier Mounts, Etc.)	Y	Y	Y	D	SD
647	Large Roadside Sign Supports	Y	Y	Y	D	SD
650	Cantilever Sign Structure Supports - Alternate Design Calcs.	Y	Y	Y	D	SD
650	Sign Structures	Y	Y	N	D	SD
680	Installation of Highway Traffic Signals	Y	Y	N	D	SD
682	Vehicle and Pedestrian Signal Heads	Y	Y	N	D	SD
684	Traffic Signal Cables	Y	Y	N	D	SD
685	Roadside Flashing Beacon Assemblies	Y	Y	N	D	SD
686	Traffic Signal Pole Assemblies (Steel) (Non-Standard only)	Y	Y	Y	D	SD
687	Pedestal Pole Assemblies	Y	Y	N	D	SD
688	Detectors	Y	Y	N	D	SD
784	Repairing Steel Bridge Members	Y	Y	Y	D	WD
SS	Prestr Concr Crown Span	Y	Y	N	D	SD
SS	Sound Barrier Walls	Y	Y	Y	D	SD
SS	Camera Poles	Y	Y	Y	TMS	SD
SS	Pedestrian Bridge (Calcs req'd.)	Y	Y	Y	D	SD
SS	Screw-In Type Anchor Foundations	Y	Y	N	D	SD
SS	Fiber Optic/Communication Cable	Y	Y	N	TMS	SD
SS	Spread Spectrum Radios for Signals	Y	Y	N	D	SD
SS	VIVDS System for Signals	Y	Y	N	D	SD
SS	CTMS Equipment	Y	Y	N	TMS	SD

Notes:

1. Document flow for Working Drawings differs from Shop Drawings in that Working Drawings must be submitted to the Engineer rather than the Engineer of Record and they are for the information of the Engineer only; an approval stamp and distribution to all project offices is not required.

Key to Reviewing Party

D – Consultant: Submit to Engineer of Record at JSessions@emailatg.com	
TMS – Traffic Management System	
Computerized Traffic Management Systems (CTMS)	HOU-CTMSShpDrwgs@txdot.gov

County: Harris

Control: 3510-06-030

Highway: SH 99

Item 7: Legal Relations and Responsibilities

This project does not require a U.S. Army Corps of Engineers (USACE) Section 404 Permit before letting, but if a permit is needed during construction, assume responsibility for preparing the permit application. Submit the permit application to the Department's District Environmental Section for approval. Once the permit application is approved, the Department will submit it to the USACE. Assume responsibility for the requested revisions, in coordination with the Department's District Environmental Section.

Maintain the roadway slope stability. Maintaining slope stability is subsidiary to the various bid items.

The nesting / breeding season for migratory birds is February 15 through September 30.

Take measures to prevent the building of nests on any structures or trees within the project limits throughout the duration of the construction if work / removal will be performed during the nesting / breeding season. This can be accomplished by application of bird repellent gel, netting by hand every 3 to 4 days, or any other non-threatening method approved by the Houston District Environmental Section. Obtain this approval well in advance of the planned use. Contact the Houston District Environmental Section at 713-802-5244. The cost of this work is subsidiary to the various bid items.

No significant traffic generator events have been identified.

Item 8: Prosecution and Progress

The Department will not adjust the number of days for the project and milestones, if any, due to differences in opinion regarding any assumptions made in the preparation of the schedule or for errors, omissions, or discrepancies found in the time determination schedule.

Working days will be computed and charged based on a *standard* workweek in accordance with Section 8.3.1.4.

The maximum number of days the time charges on this contract may be suspended due to contractor mobilization, and material fabrication/accumulation or processing delays is 120 days. The Engineer and the Contractor may mutually agree, in writing, to decrease this maximum number of days.

Items 360, 420, and 421: All Concrete Items

For the Department's concrete cylinder split samples, transport the test cylinders to the Houston District Laboratory located at 7600 Washington Avenue in Houston, or to the appropriate Area Laboratory, when applicable. Transporting the test cylinders is subsidiary to the various bid items.

County: Harris

Control: 3510-06-030

Highway: SH 99

Item 416: Drilled Shaft Foundations

Include the cost for furnishing and installing anchor bolts mounted in the drilled shafts in the unit bid price for the various diameter drilled shafts.

The Department may test using ultrasonic methods the anchor bolts for overhead sign supports, light standards, and traffic signal poles after they are installed. Replace faulty anchor bolts as directed. Do not weld the anchor bolts.

Item 420: Concrete Substructures

Unless otherwise noted, use Class C concrete with an ordinary surface finish for signal, lighting, or sign structure foundations.

Item 421: Hydraulic Cement Concrete

Entrained air is required in all slip formed concrete (bridge rail, concrete traffic barrier, pavement, etc.), but is not required for other structural concrete. Adjust the dosage of air entraining agent for low air content as directed or allowed by the Engineer. If entrained air is provided where not required, do not exceed the manufacturer's recommended dosage.

Item 449: Anchor Bolts

Pipe joint compound, as used in this Item, is an electrically conducting protective thread lubricant compound to be used on the foundation anchor bolts for illuminations poles (Crouse-Hinds TL-2, 0z/Gedney Stl, or Thomas & Betts Kopr-Shield).

Item 502: Barricades, Signs, and Traffic Handling

Use a traffic control plan for handling traffic through the various phases of construction. Follow the phasing sequence unless otherwise agreed upon by the Area Engineer and the Project Manager. Ensure this plan conforms to the latest "Texas Manual on Uniform Traffic Control Devices" and the latest Barricade and Construction (BC) Standard Sheets. The latest versions of Work Zone Standard Sheets WZ (BTS-1) and WZ (BTS-2) are the traffic control plan for the signal installations.

Submit changes to the traffic control plan to the Area Engineer. Provide a layout showing the construction phasing, signs, striping, and signalizations for changes to the original traffic control plan.

Furnish and maintain the barricades and warning signs, including the necessary temporary and portable traffic control devices, during the various phases of construction. Place and construct these barricades and warning signs in accordance with the latest "Texas Manual on Uniform Traffic Control Devices" for typical construction layouts.

County: Harris

Control: 3510-06-030

Highway: SH 99

Cover work zone signs when work related to the signs is not in progress, or when any hazard related to the signs no longer exists.

Keep the delineation devices, signs, and pavement markings clean. This work is subsidiary to the Item, "Barricades, Signs, and Traffic Handling."

Cover or remove the permanent signs and construction signs that are incorrect or that do not apply to the current situation for a particular phase.

Do not mount signs on drums or barricades, except those listed in the latest Barricades and Construction standard sheets.

Use traffic cones for daytime work only. Replace the cones with plastic drums during nighttime hours.

Place positive barriers to protect drop-off conditions greater than 2 ft. within the clear zone that remain overnight.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506: Temporary Erosion, Sedimentation and Environmental Controls

The use of hay bales is not permitted as Storm Water Pollution Prevention Plan (SWP3) measures.

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7. Since the disturbed area is less than 5 acres, a "Notice of Intent" (NOI) is not required.

Use appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. Remove and dispose of materials in compliance with State and Federal laws.

Implement temporary and permanent erosion control measures to comply with the National Pollution Discharge Elimination System (NPDES) general permit under the Clean Water Act.

County: Harris

Control: 3510-06-030

Highway: SH 99

Item 610: Roadway Illumination Assemblies

The cost of providing the electrical conductor in the pole foundation or in the pole base to make connections is subsidiary to the roadway illumination assembly. The quantity for payment is the surface distance between locations.

Fabricate steel roadway illumination poles in accordance with the latest Department RIP (Roadway Illumination Poles) Standards. Poles manufactured according to the latest RIP Standards require no shop drawings. Alternate designs to the Department's RIP Standards or the use of aluminum to fabricate poles will require the submission of shop drawings electronically.

For poles to be installed in regions where the maximum basic wind speed exceeds 110 mph or to be mounted more than 25 ft. above the surrounding terrain, provide shop drawings (see ftp://ftp.dot.state.tx.us/pub/txdot-info/library/pubs/bus/bridge/e_submit_guide.pdf) and calculations that are sealed, signed, and dated by a professional engineer registered or licensed in Texas.

Supply anchor bolt assemblies as shown on the RIP standard sheets, unless a larger capacity bolt assembly is required for the 3-second gust wind speed and mounting elevation at the pole installation location.

Item 613: High Mast Illumination Poles

Before erecting the high mast poles, notify the Engineer a minimum of 3 working days in advance for scheduling the inspection of each assembled high mast pole and high mast assembly.

Place high mast illumination poles in locations so that the light mounting and support assembly can be lowered and maintained from ground level without interfering with bridges or retaining walls. Notify the Engineer of any such conflicts.

Provide anchor bolts for high mast illumination poles in accordance with the Item, "Anchor Bolts."

Item 614: High Mast Illumination Assemblies

Erect and place in operation high mast illumination poles before removing existing illumination facilities.

The high mast power cable must meet the latest edition of Department Standard sheets, "High Mast Illumination Details" (HMID) and Department Material Specification (DMS) 11021, "High Mast Assembly Kits."

Furnish stainless steel pulley material for the Wire Rope Pulley as shown on the HMID standard.

County: Harris

Control: 3510-06-030

Highway: SH 99

Provide pre-qualified High-Pressure Sodium (HPS) lamps from the Material Producer List (MPL) of the wattages shown on the plans, shipped and secured within the fixture. No alternatives are allowed.

Item 616: Performance Testing of Lighting Systems

The illumination plans provide for a complete illumination system installed, connected, tested, and ready for operation.

After satisfactory completion of tests, place the new lighting fixtures in operation. Final acceptance will be made after the fixtures operate satisfactorily for a minimum period of 14 days. The 14-day test period is included in the allowed working days.

Assume responsibility for the new lighting fixtures during the test period. Make adjustments or repairs as required and repair defects or damage at no expense to the Department.

Item 618: Conduit

When backfilling bore pits, ensure that the conduit is not damaged during installation or due to settling backfill material. Compact select backfill in 3 equal lifts to the bottom of the conduit; or if using sand, place it 2 in. above the conduit. Ensure backfill density is equal to that of the existing soil. Prevent material from entering the conduit.

Construct bore pits a minimum of 5 ft. from the edge of the base or pavement. Close the bore pit holes overnight.

Unless otherwise shown on the plans, install underground conduit a minimum of 24 in. deep. Install the conduit in accordance with the latest National Electrical Code (NEC) and applicable Department standard sheets. Place conduit under driveways or roadways a minimum of 24 in. below the pavement surface.

If using casing to place bored conduit, the casing is subsidiary to the conduit.

If placing the conduit under existing pavement to reach the service poles, bore the conduit in place and extend it a minimum distance of 5 ft. beyond the edge of shoulder or the back of curb.

Where PVC, duct cable, and HDPE conduit 1 in. and larger is allowed and installed per Department standards, provide a PVC elbow in place of the galvanized rigid metal elbow required by the Electrical Details standards. Ensure the PVC elbow is of the same schedule rating as the conduit to which it is connected. Use only a flat, high tensile strength polyester fiber pull tape to pull conductors through the PVC conduit system.

Remove conductor and conduit to be abandoned to 1 ft. below the ground level. This work is subsidiary to the various bid items.

County: Harris

Control: 3510-06-030

Highway: SH 99

Do not use cast iron junction boxes in concrete traffic barriers and single slope traffic barriers. Use polymer concrete junction boxes as shown on standar sheet ED(4)-14. Mount the junction boxes flush (+ 0 in., - 1/2 in.) with the concrete surface of the concrete barrier.

Use materials from pre-qualified producers as shown on the Department's Construction Division (CST) material producers list. Check the latest links on the Department's website for the list. The category is "Roadway Illumination and Electrical Supplies." The polymer concrete barrier box is subsidiary to Item 618, "Conduit."

Item 620: Electrical Conductors

Test each wire of each cable or conductor after installation. Incomplete circuits or damage to the wire or the cable are cause for immediate rejection of the entire cable being tested. Remove and replace the entire cable at no expense to the Department. Also test the replacement cable after installation.

When pulling cables or conductors through the conduit, do not exceed the manufacturer's recommended pulling tensions. Lubricate the cables or conductors with a lubricant recommended by the cable manufacturer.

For both transformer and shoe-base type illumination poles, provide double-pole breakaway fuse holders as shown on the Department's Construction Division (CST) material producers list. Check the latest link on the Department's website for this list. The category is "Roadway Illumination and Electrical Supplies." The fuse holder is shown on the list under Items 610 and 620. Provide 10 Amp time delay fuses.

Ensure that circuits test clear of faults, grounds, and open circuits.

Split bolt connectors are allowed only for splices on the grounding conductors.

For electrical licensing and electrical certification requirements for this project, see Item 7 of the Standard Specifications and any applicable special provisions to Item 7.

Item 624: Ground Boxes

The ground box locations are approximate. Alternate ground box locations may be used as directed, to avoid placing in sidewalks or driveways.

Ground metal ground box covers. Bond the ground box cover and ground conductors to a ground rod located in the ground box and to the system ground.

Ground the existing metal ground box covers as shown on the latest standard sheet ED (4)-14.

During construction and until project completion, provide personnel and equipment necessary to remove ground box lids for inspection. Provide this assistance within 24 hours of notification.

County: Harris

Control: 3510-06-030

Highway: SH 99

Construct concrete aprons in accordance with the latest standard sheet ED (4)-14. Make the depth of the concrete apron the same as the depth of the ground box, except for Type 1 and Type 2 ground boxes. For Type 1 or Type 2 ground boxes, construct the concrete apron in accordance with details shown on the "Ground Box Details Installations" standard.

Item 628: Electrical Services

Verify and coordinate the electrical service location with the engineering section of the appropriate utility district or company.

Identify the electrical service pole with an address number assigned by the Utility Service Provider. Provide 2-in. numerals visible from the highway. Provide numbers cut out aluminum figures nailed to wood poles or painted figures on steel poles or service cabinets.

Item 656: Foundations for Traffic Control Devices

Excavating and disposing of surplus materials for lighting standard foundations are subsidiary to the roadway illumination assembly foundation. Dispose of surplus excavated material. Use rigid metal conduit (RMC) for stub-outs in foundation and concrete structures. These stub-outs are subsidiary to the drilled shaft foundations.

Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

A shadow vehicle with Truck Mounted Attenuators (TMAs) or Trailer Attenuators (TAs) is required as shown on the appropriate Traffic Control Plan (TCP) sheets. TMAs/TAs must meet the requirements of the Compliant Work Zone Traffic Control Device List.

Level 3 Compliant TMAs/TAs are required for this project.

A total of one (1) shadow vehicle with a TMA/TA is required for the work with the exception of Pavement Marking Operations. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.

A total of three (3) shadow vehicles with a TMA/TA are required for Pavement Marking Operations. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 3510-06-030

DISTRICT Houston
HIGHWAY SH 99


COUNTY Harris

CONTROL SECTION JOB				3510-06-030		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00185907			
COUNTY				Harris			
HIGHWAY				SH 99			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	416-6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	2,852.000		2,852.000	
	416-6027	DRILL SHAFT (HIGH MAST POLE) (66 IN)	LF	130.000		130.000	
	416-6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	88.000		88.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY	332.000		332.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	19.000		19.000	
	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	38.000		38.000	
	610-6218	IN RD IL (TY SA) 40T-12 (250W EQ) LED	EA	6.000		6.000	
	610-6290	IN RD IL (TY SA) 50T-12 (400W EQ) LED	EA	4.000		4.000	
	613-6006	HI MST IL POLE (150 FT)(100 MPH)	EA	61.000		61.000	
	613-6008	HI MST IL POLE (175 FT)(100 MPH)	EA	3.000		3.000	
	614-6014	LED HI MST IL AM(6 FIXT)ASYM(TY A)SHLD	EA	65.000		65.000	
	618-6046	CONDT (PVC) (SCH 80) (2")	LF	55,220.000		55,220.000	
	618-6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	4,625.000		4,625.000	
	618-6070	CONDT (RM) (2")	LF	3,385.000		3,385.000	
	620-6005	ELEC CONDR (NO.10) BARE	LF	16,700.000		16,700.000	
	620-6006	ELEC CONDR (NO.10) INSULATED	LF	33,400.000		33,400.000	
	620-6007	ELEC CONDR (NO.8) BARE	LF	15,200.000		15,200.000	
	620-6008	ELEC CONDR (NO.8) INSULATED	LF	30,400.000		30,400.000	
	620-6009	ELEC CONDR (NO.6) BARE	LF	30,815.000		30,815.000	
	620-6010	ELEC CONDR (NO.6) INSULATED	LF	61,630.000		61,630.000	
	620-6011	ELEC CONDR (NO.4) BARE	LF	10,875.000		10,875.000	
	620-6012	ELEC CONDR (NO.4) INSULATED	LF	21,750.000		21,750.000	
	624-6009	GROUND BOX TY D (162922)	EA	66.000		66.000	
	624-6010	GROUND BOX TY D (162922)W/APRON	EA	162.000		162.000	
	628-6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	24.000		24.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	268.000		268.000	
	6185-6002	TMA (STATIONARY)	DAY	268.000		268.000	
	08	CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS	1.000		1.000	
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS	1.000		1.000	


SUMMARY OF ILLUMINATION ITEMS

LOCATION	416	416	416	432	610	610	610	613	613	614	618	618	618
	6026	6027	6029	6001	6104	6218	6290	6006	6008	6014	6046	6047	6070
	DRILL SHAFT (HIGH MAST POLE) (60 IN)	DRILL SHAFT (HIGH MAST POLE) (66 IN)	DRILL SHAFT (RDWY ILL POLE) (30 IN)	RIPRAP (CONC) (4IN)	IN RD IL (U/P) (TY 1) (150W EQ) LED	IN RD IL (TY SA) (40T-12) (250W EQ) LED	IN RD IL (TY SA) (50T-12) (400W EQ) LED	HI MST IL POLE (150 FT) (100 MPH)	HI MST IL POLE (175 FT) (100 MPH)	LED HI MST IL AM (6 FIXT) AYSM (TY A) SHLD	CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	CONDT (RM) (2")
LF	LF	LF	CY	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF
ILLUMINATION LAYOUT													
SHEET 1 OF 49				0.5							230	50	
SHEET 2 OF 49													
SHEET 3 OF 49													
SHEET 4 OF 49													
SHEET 5 OF 49	92			11			2			2	470	240	
SHEET 6 OF 49	92			11			2			2	650	115	
SHEET 7 OF 49	46			5.5			1			1	1370	130	
SHEET 8 OF 49	46	65		10			1	1		2	2535		
SHEET 9 OF 49		65		5				1		1	550	140	
SHEET 10 OF 49	92			10			2			2	1320		
SHEET 11 OF 49	46			5			1			1	1990	205	
SHEET 12 OF 49	92			10			2			2	1425	240	
SHEET 13 OF 49	46			5.5			1			1	915		
SHEET 14 OF 49	92			10.5			2			2	930	175	
SHEET 15 OF 49	92			10			2			2	900		
SHEET 16 OF 49	46			5			1			1	2850		
SHEET 17 OF 49	92			10.5			2			2	1730	335	
SHEET 18 OF 49	46			5			1			1	590	170	
SHEET 19 OF 49	92			10.5			2			2	500		
SHEET 20 OF 49	46			5.5			1			1	1335	200	
SHEET 21 OF 49	92			10			2			2	405		
SHEET 22 OF 49	46			5.5			1			1	2385	180	
SHEET 23 OF 49	92			10			2			2	2305		
SHEET 24 OF 49	46			5			1			1	540		
SHEET 25 OF 49	92			10.5			2			2	1420	285	
SHEET 26 OF 49	46			5			1			1	360	160	
SHEET 27 OF 49	92			10.5			2			2	2160	185	
SHEET 28 OF 49	92			10			2			2	450		
SHEET 29 OF 49	46			5.5			1			1	1400	490	
SHEET 30 OF 49	92			10			2			2	945	285	
SHEET 31 OF 49	46			5			1			1	545		
SHEET 32 OF 49	92			10.5			2			2	2175	175	
SHEET 33 OF 49	46			5			1			1	730		
SHEET 34 OF 49	92			11			2			2	645	90	
SHEET 35 OF 49	46			5			1			1	660		
SHEET 36 OF 49	46		16	5.5		2	1			2	795	195	
SHEET 37 OF 49			72	0.5		4	4				2600	240	
SHEET 38 OF 49	92			10.5			2			2	1090	55	
SHEET 39 OF 49	46			5				1		1	1340		
SHEET 40 OF 49	92			10			2			2	1620	55	
SHEET 41 OF 49	46			5			1			1	1905		
SHEET 42 OF 49	92			10			2			2	1345		
SHEET 43 OF 49	46			5.5			1			1	1010		
SHEET 44 OF 49	92			10.5			2			2	2185	165	
SHEET 45 OF 49	92			10			2			2	2670		
SHEET 46 OF 49	92			10			2			2	1040		
SHEET 47 OF 49													
SHEET 48 OF 49				0.5							205	65	
SHEET 49 OF 49													
UNDERPASS ILLUMINATION													
SHEET 1 OF 7					12								770
SHEET 2 OF 7					6								435
SHEET 3 OF 7					4								350
SHEET 4 OF 7					4								740
SHEET 5 OF 7					6								420
SHEET 6 OF 7					2								205
SHEET 7 OF 7					4								465
PROJECT TOTALS	2852	130	88	332	38	6	4	61	3	65	55220	4625	3385

3/21/2023 12:15:05 PM 2022_0062_GEN_SUM_QTY_1.dgn



ATG ALLIANCE
TRANSPORTATION GROUP



© 2023
Texas Department of Transportation

SH 99

SUMMARY OF QUANTITIES


(SHEET 1 OF 2)

PROJECT NO.				
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	10

SUMMARY OF ILLUMINATION ITEMS

LOCATION	620	620	620	620	620	620	620	620	620	624	624	628	6001	6185
	6005	6006	6007	6008	6009	6010	6011	6012	6012	6009	6010	6082	6001	6002
	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	ELEC CONDR (NO. 4) BARE	ELEC CONDR (NO. 4) INSULATED	ELEC CONDR (NO. 4) INSULATED	GROUND BOX TY D (162922)	GROUND BOX TY D (162922) W/APRON	ELC SRV TY A 240/480 100(SS)SS (E)GC(O)	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)
LF	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	DAY	DAY	
ILLUMINATION LAYOUT														
SHEET 1 OF 49	280	560									3	1		
SHEET 2 OF 49														
SHEET 3 OF 49														
SHEET 4 OF 49														
SHEET 5 OF 49	880	1760							2	7	2			
SHEET 6 OF 49	795	1590							2	4	2			
SHEET 7 OF 49	70	140			1535	3070			1	6	1			
SHEET 8 OF 49					2535	5070			2	5				
SHEET 9 OF 49					690	1380			1	2				
SHEET 10 OF 49					1320	2640			2	3				
SHEET 11 OF 49					2900	5800			1	5				
SHEET 12 OF 49					3305	6610			2	4				
SHEET 13 OF 49					2745	5490			1	2	1			
SHEET 14 OF 49	1245	2490							2	2	1			
SHEET 15 OF 49					900	1800			2	2				
SHEET 16 OF 49					2850	5700			1	6				
SHEET 17 OF 49					2105	4210			2	5	1			
SHEET 18 OF 49	760	1520							1	2				
SHEET 19 OF 49	500	1000							2	1	1			
SHEET 20 OF 49	2180	4360							1	8	1			
SHEET 21 OF 49	210	420			195	390			2					
SHEET 22 OF 49					3425	6850			1	7	1			
SHEET 23 OF 49					2305	4610			2	5				
SHEET 24 OF 49					540	1080			1	1				
SHEET 25 OF 49			2145	4290					2	4	1			
SHEET 26 OF 49			520	1040					1	1				
SHEET 27 OF 49			2525	5050					2	6	1			
SHEET 28 OF 49			450	900					2					
SHEET 29 OF 49			3150	6300					1	7	1			
SHEET 30 OF 49			1785	3570					2	4				
SHEET 31 OF 49			545	1090					1	1				
SHEET 32 OF 49			2930	5860					2	5	1			
SHEET 33 OF 49			730	1460					1	2				
SHEET 34 OF 49	735	1470							2	5	2			
SHEET 35 OF 49	660	1320							1	1				
SHEET 36 OF 49	990	1980							2	6	1			
SHEET 37 OF 49	3130	6260							1	3	1			
SHEET 38 OF 49	985	1970			160	320			2	3	1			
SHEET 39 OF 49					1340	2680			1	3				
SHEET 40 OF 49					1390	2780			2	4				
SHEET 41 OF 49					575	1150	1330	2660	1	4				
SHEET 42 OF 49							1345	2690	2	3				
SHEET 43 OF 49							1010	2020	1	3	1			
SHEET 44 OF 49							3195	6390	2	7	1			
SHEET 45 OF 49							2670	5340	2	5				
SHEET 46 OF 49							1040	2080	2	2				
SHEET 47 OF 49														
SHEET 48 OF 49	270	540								3	1			
SHEET 49 OF 49														
UNDERPASS ILLUMINATION														
SHEET 1 OF 7	770	1540												
SHEET 2 OF 7	435	870												
SHEET 3 OF 7	350	700												
SHEET 4 OF 7	785	1570												
SHEET 5 OF 7			420	840										
SHEET 6 OF 7	205	410												
SHEET 7 OF 7	465	930												
PROJECT TOTALS	16700	33400	15200	30400	30815	61630	10875	21750	66	162	24	268	268	

3/21/2023 12:15:06 PM 2022_0062_GEN_SUM_QTY_2.dgn



© 2023


Texas Department of Transportation

SH 99

SUMMARY OF QUANTITIES

(SHEET 2 OF 2)

PROJECT NO.				
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	11



- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.





- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW

CONDUIT RUN ID:
XX-XX-XX

— RUN NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER

POLE ID:
X X X

— POLE NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER



J. Sessions
3/21/2023



Texas Department of Transportation
© 2023

SH 99

ILLUMINATION LAYOUT
START TO STA 112+00


(SHEET 1 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO.
3510	06	030	SH 99
			SHEET NO.
			12

CONDUIT			CONDUCTOR							
ITEM-CODE	RUN NO.	CONDUIT STATUS	618-6046		618-6047		620-6005		620-6006	
			COND'T (PVC) (SCH 80) (2")	COND'T (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED				
COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	
1	100	TRENCH	1	100	1	100	2	200	1	100
1	50	BORE			1	50	2	100		
1	130	TRENCH	1	130			2	260		
SHEET TOTALS				230		50		280		560

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
432	6001	RIPRAP (CONC) (4 IN)	CY	0.5
618	6046	COND'T (PVC) (SCH 80) (2")	LF	230
618	6047	COND'T (PVC) (SCH 80) (2") (BORE)	LF	50
620	6005	ELEC CONDR (NO.10) BARE	LF	280
620	6006	ELEC CONDR (NO.10) INSULATED	LF	560
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

3/21/2023 12:18:28 PM 2022_0062_ILM01.dgn





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW

- CONDUIT RUN ID:**
XX-XX-XX
- RUN NUMBER
 - CIRCUIT LETTER
 - SERVICE NUMBER
- POLE ID:**
X X X
- POLE NUMBER
 - CIRCUIT LETTER
 - SERVICE NUMBER



MATCHLINE STA. 125+00

MATCHLINE STA. 112+00

CYPRESSWODD DR




Jacob A. Sessions
3/21/2023



SH 99
ILLUMINATION LAYOUT
STA 112+00 TO STA 125+00

(SHEET 2 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 13





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW

CONDUIT RUN ID:
 XX-XX-XX
 |
 | RUN NUMBER
 | CIRCUIT LETTER
 | SERVICE NUMBER

POLE ID:
 X X X
 |
 | POLE NUMBER
 | CIRCUIT LETTER
 | SERVICE NUMBER



MATCHLINE STA. 125+00

MATCHLINE STA. 138+00




Jacob A. Sessions
 3/21/2023



SH 99
 ILLUMINATION LAYOUT
 STA 125+00 TO STA 138+00

(SHEET 3 OF 49)

SCALE: 1" = 100'		PROJECT NO.		
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	14




- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW


CONDUIT RUN ID:
 XX-XX-XX
 └──┬──┬──
 RUN NUMBER
 CIRCUIT LETTER
 SERVICE NUMBER

POLE ID:
 X X X
 └──┬──┬──
 POLE NUMBER
 CIRCUIT LETTER
 SERVICE NUMBER



MATCHLINE STA. 138+00

MATCHLINE STA. 151+00




Jacob A. Sessions
 3/21/2023



SH 99
ILLUMINATION LAYOUT
 STA 138+00 TO STA 151+00

(SHEET 4 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 15





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
2A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	153+06	91.25' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
3B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	159+99	87.94' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



PROP ELEC SERV #2
TY A 240/480 100(SS)SS(E)GC(O)
CL SH 99 ML STA 151+13.7, 186.6' RT

PROP ELEC SERV #3
TY A 240/480 100(SS)SS(E)GC(O)
CL SH 99 ML STA 159+21.3, 191.5' RT

CONDUIT							CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED				
			COUNT	LENGTH	COUNT	LENGTH	GROUND	POWER	COUNT	LENGTH
2-A-1	20	TRENCH	1	20			1	20	2	40
2-A-2	55	BORE			1	55	1	55	2	110
2-A-3	205	TRENCH	1	205			1	205	2	410
3-A-1	65	TRENCH	1	65			1	65	2	130
3-AB-1	35	TRENCH	1	35			2	70	4	140
3-AB-2	45	BORE				45	2	90	4	180
3-AB-3	90	TRENCH	1	90			2	180	4	360
3-B-1	140	BORE				140	1	140	2	280
3-B-2	55	TRENCH	1	55			1	55	2	110
SHEET TOTALS				470		240		880		1760

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	11
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	470
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	240
620	6005	ELEC CONDR (NO.10) BARE	LF	880
620	6006	ELEC CONDR (NO.10) INSULATED	LF	1760
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	7
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	2




ILLUMINATION LAYOUT
STA 151+00 TO STA 164+00

(SHEET 5 OF 49)

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 16

3/21/2023 12:21:51 PM 2022_0062_ILM05.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
4A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	167+86	88.96' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
5A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	175+26	117.72' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - EXIST HIGH MAST LUMINAIRE
 - PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



PROP ELEC SERV #4
TY A 240/480 100(SS)SS(E)GC(O)
CL SH 99 ML STA 164+15.1, 188.6' RT

CONDUIT						CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED				
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
4-A-1	20	TRENCH	1	20			1	20	2	40
4-A-2	45	BORE			1	45	1	45	2	90
4-A-3	365	TRENCH	1	365			1	365	2	730
5-AB-1	30	TRENCH	1	30			2	60	4	120
5-A-1	70	BORE			1	70	1	70	2	140
5-A-2	135	TRENCH	1	135			1	135	2	270
5-B-1	100	TRENCH	1	100			1	100	2	200
SHEET TOTALS				650		115		795		1590

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	11
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	650
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	115
620	6005	ELEC CONDR (NO. 10) BARE	LF	795
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	1590
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	2




ILLUMINATION LAYOUT
STA 164+00 TO STA 177+00

(SHEET 6 OF 49)

SCALE: 1" = 100'

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 17

3/21/2023 12:22:43 PM 2022_0062_ILM06.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES				
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION
6A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	184+67
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD		



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



PROP ELEC SERV #6
TY A 240/480 100(SS)SS(E)GC(O)
CL SH 99 ML STA 183+87.5, 135.2' RT

Jacob A. Sessions
127122
Licensed Professional Engineer
3/21/2023

CONDUIT		618-6046		618-6047		
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	CONDT (PVC) (SCH 80) (2")		CONDT (PVC) (SCH 80) (2") (BORE)	
			COUNT	LENGTH	COUNT	LENGTH
5-B-1	70	TRENCH	1	70		
6-AB-1	105	TRENCH	1	105		
6-A-1	45	TRENCH	1	45		
6-A-2	370	TRENCH	1	370		
6-A-3	205	TRENCH	1	205		
6-B-1	130	BORE			1	130
6-B-2	145	TRENCH	1	145		
6-B-3	370	TRENCH	1	370		
6-B-4	60	TRENCH	1	60		
SHEET TOTALS				1370		130

CONDUCTOR				CONDUCTOR			
620-6009		620-6010		620-6005		620-6006	
ELEC CONDR (NO. 6) BARE		ELEC CONDR (NO. 6) INSULATED		ELEC CONDR (NO. 10) BARE		ELEC CONDR (NO. 10) INSULATED	
GROUND		POWER		GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
2	210	4	420	1	70	2	140
1	45	2	90				
1	370	2	740				
1	205	2	410				
1	130	2	260				
1	145	2	290				
1	370	2	740				
1	60	2	120				
1535		3070		70		140	


QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1370
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	130
620	6005	ELEC CONDR (NO. 10) BARE	LF	70
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	140
620	6009	ELEC CONDR (NO. 6) BARE	LF	1535
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	3070
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	6
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ILLUMINATION LAYOUT
STA 177+00 TO STA 190+00
(SHEET 7 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 18

3/21/2023 12:23:34 PM 2022_0062_ILM07.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
6A2	613-6008	HI MST IL POLE (175 FT) (100 MPH)	CL SH 99 ML	201+62	90.62' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
6B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	192+72	84.92' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			CONDT (PVC) (SCH 80) (2")		ELEC CONDR (NO. 6) BARE		ELEC CONDR (NO. 6) INSULATED	
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
6-A-3	205	TRENCH	1	205	1	205	2	410
6-A-4	330	TRENCH	1	330	1	330	2	660
6-A-5	330	TRENCH	1	330	1	330	2	660
6-A-6	330	TRENCH	1	330	1	330	2	660
6-B-4	265	TRENCH	1	265	1	265	2	530
6-B-5	400	TRENCH	1	400	1	400	2	800
6-B-6	400	TRENCH	1	400	1	400	2	800
6-B-7	275	TRENCH	1	275	1	275	2	550
SHEET TOTALS				2535		2535		5070

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
416	6027	DRILL SHAFT (HIGH MAST POLE) (66 IN)	LF	65
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
613	6008	HI MST IL POLE (175 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	2535
620	6009	ELEC CONDR (NO. 6) BARE	LF	2535
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	5070
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5




ILLUMINATION LAYOUT
STA 190+00 TO STA 203+00

(SHEET 8 OF 49)

SCALE: 1" = 100'

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 19

3/21/2023 12:24:23 PM 2022_0062_ILM08.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
6B2	613-6008	HI MST IL POLE (175 FT) (100 MPH)	CL SH 99 ML	209+61	83.06' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



MATCHLINE STA. 203+00

MATCHLINE STA. 216+00



CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED
			COUNT	LENGTH	COUNT	LENGTH
6-B-7	85	TRENCH	1	85		
6-B-8	140	BORE			1	140
6-B-9	170	TRENCH	1	170		
6-B-10	295	TRENCH	1	295		
SHEET TOTALS				550		140

GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH
1	85	2	170
1	140	2	280
1	170	2	340
1	295	2	590
	690		1380

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6027	DRILL SHAFT (HIGH MAST POLE) (66 IN)	LF	65
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6008	HI MST IL POLE (175 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	550
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	140
620	6009	ELEC CONDR (NO. 6) BARE	LF	690
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	1380
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2



Jacob A. Sessions
3/21/2023




SH 99

ILLUMINATION LAYOUT
STA 203+00 TO STA 216+00

(SHEET 9 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 20

3/21/2023 12:25:13 PM 2022_0062_ILM09.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
7B2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	226+46	92.80' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



STATE OF TEXAS

 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
J. Sessions
 3/21/2023


ATG ALLIANCE
 TRANSPORTATION GROUP
 © 2023
 Texas Department of Transportation

CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			COND (PVC) (SCH 80) (2")	LENGTH	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	GROUND	POWER
7-B-4	260	TRENCH	1	260	1	260	2	520
7-C-3	55	TRENCH	1	55	1	55	2	110
7-C-4	335	TRENCH	1	335	1	335	2	670
7-C-5	335	TRENCH	1	335	1	335	2	670
7-C-6	335	TRENCH	1	335	1	335	2	670
SHEET TOTALS				1320		1320		2640

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	1320
620	6009	ELEC CONDR (NO. 6) BARE	LF	1320
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	2640
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3

SH 99
ILLUMINATION LAYOUT
 STA 216+00 TO STA 229+00
 (SHEET 10 OF 49)
 SCALE: 1" = 100'
 PROJECT NO. C 3510-6-30
 STATE: TEXAS DISTRICT: HOU DIV. NO.: 6 COUNTY: HARRIS
 CONTROL SECTION: 06 JOB: 030 HWY. NO.: SH 99 SHEET NO.: 21

3/21/2023 12:26:04 PM
 2022_0062_ILM10.dgn




NOTES:
 1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
7C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	235+22	102.5' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			




- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - EXIST HIGH MAST LUMINAIRE
 - PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▼ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - EXIST TRAFFIC FLOW



MATCHLINE STA. 229+00

MATCHLINE STA. 242+00



JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
 3/21/2023

CONDUIT			CONDUCTOR							
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6009		620-6010	
			COND'T (PVC) (SCH 80) (2")	COND'T (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	GROUND	POWER		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
7-BC-4	300	TRENCH	1	300			2	600	4	1200
7-BC-5	405	TRENCH	1	405			2	810	4	1620
7-B-2	305	TRENCH	1	305			1	305	2	610
7-B-3	305	TRENCH	1	305			1	305	2	610
7-B-4	50	TRENCH	1	50			1	50	2	100
7-C-1	205	BORE			1	205	1	205	2	410
7-C-2	335	TRENCH	1	335			1	335	2	670
7-C-3	290	TRENCH	1	290			1	290	2	580
SHEET TOTALS				1990		205		2900		5800

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	COND'T (PVC) (SCH 80) (2")	LF	1990
618	6047	COND'T (PVC) (SCH 80) (2") (BORE)	LF	205
620	6009	ELEC CONDR (NO. 6) BARE	LF	2900
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	5800
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5

ATG ALLIANCE
 TRANSPORTATION GROUP

Texas Department of Transportation

SH 99


ILLUMINATION LAYOUT
 STA 229+00 TO STA 242+00

(SHEET 11 OF 49)

SCALE: 1" = 100'

DWN: ATG	CKD: ATG	C 3510-6-30
STATE	DISTRICT	FED. RD. DIV. NO.
TEXAS	HOU	6
CONTROL	SECTION	JOB
3510	06	030
		HWY. NO.
		SH 99
		SHEET NO.
		22

3/21/2023 12:26:56 PM
 2022_0062_ILM11.dgn



- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.


SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
7A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	252+05	104.36' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
7B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	243+12	105.37' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



MATCHLINE STA. 242+00

MATCHLINE STA. 255+00



CONDUIT RUN ID:
XX-XX-XX
└─┬─┬─┘
└─┬─┘
└─┘
RUN NUMBER
CIRCUIT LETTER
SERVICE NUMBER

POLE ID:
X X X
└─┬─┬─┘
└─┬─┘
└─┘
POLE NUMBER
CIRCUIT LETTER
SERVICE NUMBER



Jacob A. Sessions
3/21/2023



© 2023
Texas Department of Transportation

SH 99
ILLUMINATION LAYOUT
STA 242+00 TO STA 255+00

(SHEET 12 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30


STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 23

CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	COUNT	LENGTH	COUNT
7-ABC-4	300	TRENCH	1	300		
7-A-1	240	BORE			1	240
7-BC-1	310	TRENCH	1	310		
7-BC-2	310	TRENCH	1	310		
7-BC-3	310	TRENCH	1	310		
7-BC-4	110	TRENCH	1	110		
7-B-1	85	TRENCH	1	85		
SHEET TOTALS				1425		240

620-6009		620-6010	
ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED
GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH
3	900	6	1800
1	240	2	480
2	620	4	1240
2	620	4	1240
2	620	4	1240
2	220	4	440
1	85	2	170
3305		6610	

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1425
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	240
620	6009	ELEC CONDR (NO. 6) BARE	LF	3305
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	6610
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4

3/21/2023 12:27:51 PM
2022.0062_ILM12.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
7A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	260+04	102.2' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW



J. Sessions
3/21/2023



© 2023 Texas Department of Transportation

CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			COND'T (PVC) (SCH 80) (2")	CONDUCTOR (NO. 6) BARE	ELEC COND'R (NO. 6) INSULATED	GROUND POWER	ELEC COND'R (NO. 6) INSULATED	
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
7-ABC-1	30	TRENCH	1	30	3	90	6	180
7-ABC-2	365	TRENCH	1	365	3	1095	6	2190
7-ABC-3	405	TRENCH	1	405	3	1215	6	2430
7-ABC-4	115	TRENCH	1	115	3	345	6	690
SHEET TOTALS				915		2745		5490

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	COND'T (PVC) (SCH 80) (2")	LF	915
620	6009	ELEC COND'R (NO. 6) BARE	LF	2745
620	6010	ELEC COND'R (NO. 6) INSULATED	LF	5490
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

SH 99

ILLUMINATION LAYOUT

STA 255+00 TO STA 268+00


(SHEET 13 OF 49)

SCALE: 1" = 100'

PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 24

3/21/2023 12:28:45 PM 2022_0062_ILM13.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
8A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	276+88	104.2' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
8B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	269+11	95.9' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT RUN ID:
XX-XX-XX

— RUN NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER

POLE ID:
X X X

— POLE NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER

0 100
SCALE: 1"=100'



Jacob A. Sessions
3/21/2023



© 2023
Texas Department of Transportation

SH 99
ILLUMINATION LAYOUT
STA 268+00 TO STA 281+00

(SHEET 14 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30


STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 25

CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED
			COUNT	LENGTH	COUNT	LENGTH
8-AB-1	140	TRENCH	1	140		
8-A-1	405	TRENCH	1	405		
8-B-1	385	TRENCH	1	385		
8-B-2	175	BORE			1	175
SHEET TOTALS				930		175

GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH
2	280	4	560
1	405	2	810
1	385	2	770
1	175	2	350
	1245		2490

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	930
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	175
620	6005	ELEC CONDR (NO. 10) BARE	LF	1245
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	2490
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

3/21/2023 12:29:37 PM
2022_0062_ILM14.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
9B2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	285+56	94.45' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
9C2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	293+55	101.32' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



STATE OF TEXAS
 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER

J. Sessions
 3/21/2023

ATG ALLIANCE
 TRANSPORTATION GROUP

Texas Department of Transportation

CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			CONDT (PVC) (SCH 80) (2")	LENGTH	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED
9-B-7	185	TRENCH	1	185	1	185	2	370
9-B-8	335	TRENCH	1	335	1	335	2	670
9-B-9	335	TRENCH	1	335	1	335	2	670
9-C-9	45	TRENCH	1	45	1	45	2	90
SHEET TOTALS				900		900		1800

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	900
620	6009	ELEC CONDR (NO. 6) BARE	LF	900
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	1800
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2

SH 99


ILLUMINATION LAYOUT
 STA 281+00 TO STA 294+00

(SHEET 15 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 26

3/21/2023 12:30:30 PM
 2022_0062_ILM15.dgn




NOTES:
 1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
9B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	302+20	95.86' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW



CONDUIT RUN ID:
 XX-XX-XX
 RUN NUMBER
 CIRCUIT LETTER
 SERVICE NUMBER

POLE ID:
 X X X
 POLE NUMBER
 CIRCUIT LETTER
 SERVICE NUMBER

0 100
 SCALE: 1"=100'



J. Sessions
 3/21/2023




CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			COUNT	LENGTH	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED
9-B-3	165	TRENCH	1	165	1	165	2	330
9-B-4	325	TRENCH	1	325	1	325	2	650
9-B-5	335	TRENCH	1	335	1	335	2	670
9-B-6	335	TRENCH	1	335	1	335	2	670
9-B-7	335	TRENCH	1	335	1	335	2	670
9-C-6	195	TRENCH	1	195	1	195	2	390
9-C-7	400	TRENCH	1	400	1	400	2	800
9-C-8	400	TRENCH	1	400	1	400	2	800
9-C-9	360	TRENCH	1	360	1	360	2	720
SHEET TOTALS				2850		2850		5700

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	CONDT (PVC) (SCH 80) (2")	LF	2850
620	6009	ELEC CONDR (NO. 6) BARE	LF	2850
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	5700
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	6

SH 99
 ILLUMINATION LAYOUT
 STA 294+00 TO STA 307+00
 (SHEET 16 OF 49)
 SCALE: 1" = 100'
 PROJECT NO. C 3510-6-30
 STATE: TEXAS DISTRICT: HOU DIV. NO.: 6 COUNTY: HARRIS
 CONTROL SECTION: 06 JOB: 030 HWY. NO.: SH 99 SHEET NO.: 27

3/21/2023 12:31:25 PM
 2022_0062_ILM16.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
9A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	319+20	107.16' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
9C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	310+73	106.09' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT							CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6009		620-6010	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	GROUND		POWER	
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
9-ABC-1	20	TRENCH	1	20			3	60	6	120
9-A-1	335	TRENCH	1	335			1	335	2	670
9-A-2	335	TRENCH	1	335			1	335	2	670
9-B-1	380	TRENCH	1	380			1	380	2	760
9-B-2	110	BORE			1	110	1	110	2	220
9-B-3	70	TRENCH	1	70			1	70	2	140
9-C-1	220	TRENCH	1	220			1	220	2	440
9-C-2	180	BORE			1	180	1	180	2	360
9-C-3	90	TRENCH	1	90			1	90	2	180
9-C-4	45	BORE			1	45	1	45	2	90
9-C-5	255	TRENCH	1	255			1	255	2	510
9-C-6	25	TRENCH	1	25			1	25	2	50
SHEET TOTALS				1730		335		2105		4210

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1730
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	335
620	6009	ELEC CONDR (NO. 6) BARE	LF	2105
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	4210
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

SH 99

ILLUMINATION LAYOUT
STA 307+00 TO STA 320+00


(SHEET 17 OF 49)

SCALE: 1" = 100'

PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 28

3/21/2023 12:32:22 PM 2022_0062_ILM17.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
10A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	327+28	97.04' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW



Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

Jacob A. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

CONDUIT			CONDUCTOR							
ITEM-CODE	RUN NO.	CONDUIT STATUS	618-6046		618-6047		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED				
COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	
10-A-3	295	TRENCH	1	295			1	295	2	590
10-A-4	295	TRENCH	1	295			1	295	2	590
10-A-5	170	BORE			1	170			2	340
SHEET TOTALS				590		170		760		1520

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	590
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	170
620	6005	ELEC CONDR (NO.10) BARE	LF	760
620	6006	ELEC CONDR (NO.10) INSULATED	LF	1520
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2


ILLUMINATION LAYOUT
STA 320+00 TO STA 333+00

(SHEET 18 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 29

3/21/2023 12:33:14 PM
2022_0062_ILM18.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
10A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	335+94	110.58' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
11A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	344+93	86.25' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



PROP ELEC SERV #10
 TY A 240/480 100(SS)SS(E)GC(O)
 CL SH 99 ML STA 335+95.4, 196.2' RT



CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")		ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
10-A-1	95	TRENCH	1	95	1	95	2	190
10-A-2	295	TRENCH	1	295	1	295	2	590
11-A-2	110	TRENCH	1	110	1	110	2	220
SHEET TOTALS				500		500		1000

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	500
620	6005	ELEC CONDR (NO. 10) BARE	LF	500
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	1000
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	1
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ILLUMINATION LAYOUT
 STA 333+00 TO STA 346+00

(SHEET 19 OF 49)


SCALE: 1" = 100'

PROJECT NO. C 3510-6-30

STATE: TEXAS DISTRICT: HOU FED. RD. DIV. NO.: 6 COUNTY: HARRIS

CONTROL SECTION: 3510 JOB: 06 HWY. NO.: 030 SHEET NO.: 30

3/21/2023 12:34:06 PM 2022_0062_ILM19.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
11B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	351+74	95.58' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⬛ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT RUN ID:
XX-XX-XX
├── RUN NUMBER
├── CIRCUIT LETTER
└── SERVICE NUMBER

POLE ID:
X X X
├── POLE NUMBER
├── CIRCUIT LETTER
└── SERVICE NUMBER

SCALE: 1" = 100'



Jacob A. Sessions
3/21/2023



Texas Department of Transportation
SH 99

ILLUMINATION LAYOUT
STA 346+00 TO STA 359+00


(SHEET 20 OF 49)

SCALE: 1" = 100'	PROJECT NO.
DWN: ATG	CKD: ATG
STATE: TEXAS	DISTRICT: HOU
FED. RD. DIV. NO.: 6	COUNTY: HARRIS
CONTROL: SECTION 06	JOB: 030
	HWY. NO.: SH 99
	SHEET NO.: 31

RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	CONDUIT				CONDUCTOR			
			618-6046		618-6047		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED				
COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH			
11-ABCD-1	60	TRENCH	1	60			4	240	8	480
11-ABCD-2	60	BORE			1	60	4	240	8	480
11-AB-1	180	TRENCH	1	180			2	360	4	720
11-A-1	340	TRENCH	1	340			1	340	2	680
11-A-2	230	TRENCH	1	230			1	230	2	460
11-B-1	140	BORE			1	140	1	140	2	280
11-B-2	45	TRENCH	1	45			1	45	2	90
11-CD-1	105	TRENCH	1	105			2	210	4	420
11-D-3	290	TRENCH	1	290			1	290	2	580
11-D-4	85	TRENCH	1	85			1	85	2	170
SHEET TOTALS				1335		200		2180		4360

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	1335
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	200
620	6005	ELEC CONDR (NO.10) BARE	LF	2180
620	6006	ELEC CONDR (NO.10) INSULATED	LF	4360
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	8
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

3/21/2023 12:34:55 PM 2022_0062_ILM20.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
11D1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	℄ SH 99 ML	361+07	99.21' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
12C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	℄ SH 99 ML	370+04	97.29' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



MATCHLINE STA. 359+00

MATCHLINE STA. 372+00

CONDUIT				CONDUCTOR				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COUNT	LENGTH	ELEC CONDR (NO.6) BARE	ELEC CONDR (NO.6) INSULATED	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED	GROUND	POWER	GROUND
					COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
11-D-4	210	TRENCH	1	210					1	210	2	420
12-C-2	195	TRENCH	1	195	1	195	2	390				
SHEET TOTALS				405		195		390		210		420

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	405
620	6005	ELEC CONDR (NO.10) BARE	LF	210
620	6006	ELEC CONDR (NO.10) INSULATED	LF	420
620	6009	ELEC CONDR (NO.6) BARE	LF	195
620	6010	ELEC CONDR (NO.6) INSULATED	LF	390
624	6009	GROUND BOX TY D (162922)	EA	2

Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

J. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation


SH 99

ILLUMINATION LAYOUT
STA 359+00 TO STA 372+00

(SHEET 21 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 32

3/21/2023 12:35:49 PM 2022_0062_ILM21.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
12A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	378+05	98.06' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



J. Sessions
3/21/2023

CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED
			COUNT	LENGTH	COUNT	LENGTH
12-ABC-1	20	TRENCH	1	20		
12-ABC-2	320	TRENCH	1	320		
12-A-1	330	TRENCH	1	330		
12-A-2	330	TRENCH	1	330		
12-A-3	45	TRENCH	1	45		
12-BC-1	180	BORE			1	180
12-B-1	300	TRENCH	1	300		
12-B-2	300	TRENCH	1	300		
12-B-3	120	TRENCH	1	120		
12-C-1	405	TRENCH	1	405		
12-C-2	215	TRENCH	1	215		
SHEET TOTALS				2385		180

CONDUCTOR			
620-6009		620-6010	
ELEC CONDR (NO. 6) BARE		ELEC CONDR (NO. 6) INSULATED	
GROUND POWER		POWER	
COUNT	LENGTH	COUNT	LENGTH
3	60	6	120
3	960	6	1920
1	330	2	660
1	330	2	660
1	45	2	90
2	360	4	720
1	300	2	600
1	300	2	600
1	120	2	240
1	405	2	810
1	215	2	430
	3425		6850

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	2385
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	180
620	6009	ELEC CONDR (NO. 6) BARE	LF	3425
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	6850
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	7
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1




SH 99

ILLUMINATION LAYOUT
STA 372+00 TO STA 385+00

(SHEET 22 OF 49)

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 33

3/21/2023 12:36:40 PM 2022_0062_ILM22.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
12A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	394+47	98.67' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
12B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	386+76	100.92' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW



CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			COND (PVC) (SCH 80) (2")		ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED		
			COUNT	LENGTH	GROUND		POWER	
					COUNT	LENGTH	COUNT	LENGTH
12-A-3	295	TRENCH	1	295	1	295	2	590
12-A-4	330	TRENCH	1	330	1	330	2	660
12-A-5	330	TRENCH	1	330	1	330	2	660
12-B-3	185	TRENCH	1	185	1	185	2	370
12-B-4	340	TRENCH	1	340	1	340	2	680
12-B-5	340	TRENCH	1	340	1	340	2	680
12-B-6	340	TRENCH	1	340	1	340	2	680
12-B-7	145	TRENCH	1	145	1	145	2	290
SHEET TOTALS				2305		2305		4610

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	2305
620	6009	ELEC CONDR (NO. 6) BARE	LF	2305
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	4610
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5

SH 99

ILLUMINATION LAYOUT


STA 385+00 TO STA 398+00

(SHEET 23 OF 49)

SCALE: 1" = 100'

PROJECT NO.		C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 34

3/21/2023 12:37:34 PM 2022_0062_ILM23.dgn



- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
12B2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	403+24	91.49' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW





CONDUIT RUN ID:
XX-XX-XX

— RUN NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER

POLE ID:
X X X

— POLE NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER



Jacob A. Sessions
3/21/2023



© 2023
Texas Department of Transportation

SH 99
ILLUMINATION LAYOUT
STA 398+00 TO STA 411+00


(SHEET 24 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 35

CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			COND'T (PVC) (SCH 80) (2")		ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
12-B-7	200	TRENCH	1	200	1	200	2	400
12-B-8	340	TRENCH	1	340	1	340	2	680
SHEET TOTALS				540		540		1080

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	COND'T (PVC) (SCH 80) (2")	LF	540
620	6009	ELEC CONDR (NO. 6) BARE	LF	540
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	1080
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	1

3/21/2023 12:38:25 PM 2022_0062_ILM24.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
13A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	420+28	95.24' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
13B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	411+57	99.40' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT RUN ID:
XX-XX-XX

POLE ID:
X X X

Legend for Run ID and Pole ID:
 - RUN NUMBER
 - CIRCUIT LETTER
 - SERVICE NUMBER

Legend for Pole ID:
 - POLE NUMBER
 - CIRCUIT LETTER
 - SERVICE NUMBER

0 100
SCALE: 1"=100'

PROP ELEC SERV #13
TY A 240/480 100(SS)SS(E)GC(O)
CL IH 99 ML STA 419+65.3, 200.4' RT

STATE OF TEXAS
 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
 3/21/2023

CONDUIT						
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)
13-ABC-1	130	TRENCH	1	130		
13-A-1	110	TRENCH	1	110		
13-BC-1	180	BORE			1	180
13-B-1	395	TRENCH	1	395		
13-B-2	395	TRENCH	1	395		
13-C-1	390	TRENCH	1	390		
13-C-2	105	BORE			1	105
SHEET TOTALS				1420		285

CONDUCTOR					
COUNT	LENGTH	620-6007		620-6008	
		ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED
3	390	6	780		
1	110	2	220		
2	360	4	720		
1	395	2	790		
1	395	2	790		
1	390	2	780		
1	105	2	210		
	2145		4290		

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1420
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	285
620	6007	ELEC CONDR (NO. 8) BARE	LF	2145
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	4290
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1


ATG ALLIANCE
 TRANSPORTATION GROUP
 TEXAS Department of Transportation

ILLUMINATION LAYOUT
 STA 411+00 TO STA 424+00

(SHEET 25 OF 49)
 SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 36

3/21/2023 12:39:20 PM
 2022_0062_ILM25.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
13C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	429+01	108.59' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT				CONDUCTOR						
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6007		620-6008	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	GROUND	POWER		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
13-C-2	160	BORE			1	160	1	160	2	320
13-C-3	360	TRENCH	1	360			1	360	2	720
SHEET TOTALS				360		160		520		1040

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	360
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	160
620	6007	ELEC CONDR (NO. 8) BARE	LF	520
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	1040
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	1

SH 99


ILLUMINATION LAYOUT

STA 424+00 TO STA 437+00

(SHEET 26 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 37

3/21/2023 12:40:17 PM 2022_0062_ILM26.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
14A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	437+64	101.32' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
14B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	445+80	107.90' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



STATE OF TEXAS
 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
 3/21/2023

CONDUIT							CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6007		620-6008	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	GROUND	POWER		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
14-ABC-1	90	TRENCH	1	90			3	270	6	540
14-A-1	55	TRENCH	1	55			1	55	2	110
14-B-1	185	BORE				1	185	2	370	
14-B-2	400	TRENCH	1	400			1	400	2	800
14-B-3	400	TRENCH	1	400			1	400	2	800
14-C-1	400	TRENCH	1	400			1	400	2	800
14-C-2	400	TRENCH	1	400			1	400	2	800
14-C-3	400	TRENCH	1	400			1	400	2	800
14-C-4	15	TRENCH	1	15			1	15	2	30
SHEET TOTALS				2160		185		2525		5050

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	2160
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	185
620	6007	ELEC CONDR (NO. 8) BARE	LF	2525
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	5050
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	6
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ATG ALLIANCE
 TRANSPORTATION GROUP

© 2023
 Texas Department of Transportation

SH 99


ILLUMINATION LAYOUT
 STA 437+00 TO STA 450+00

(SHEET 27 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 38

3/21/2023 12:41:11 PM
 2022_0062_ILM27.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
14C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	453+87	102.68' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
15B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	462+34	94.63' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6007		620-6008	
			COND (PVC) (SCH 80) (2")	COUNT	LENGTH	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	COUNT
14-C-4	385	TRENCH	1	385	1	385	2	770
15-B-4	65	TRENCH	1	65	1	65	2	130
SHEET TOTALS				450		450		900

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	450
620	6007	ELEC CONDR (NO. 8) BARE	LF	450
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	900
624	6009	GROUND BOX TY D (162922)	EA	2

Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

Jacob A. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

SH 99


ILLUMINATION LAYOUT
STA 450+00 TO STA 463+00

(SHEET 28 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 39

3/21/2023 12:42:03 PM
 2022_0062_ILM28.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
15A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	469+42	102.57' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇄ EXIST TRAFFIC FLOW



CONDUIT RUN ID:
XX-XX-XX
└─ RUN NUMBER
└─ CIRCUIT LETTER
└─ SERVICE NUMBER

POLE ID:
X X X
└─ POLE NUMBER
└─ CIRCUIT LETTER
└─ SERVICE NUMBER

0 100
SCALE: 1"=100'

CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED
			COUNT	LENGTH	COUNT	LENGTH
15-ABCDE-1	40	TRENCH	1	40		
15-ABCDE-2	90	BORE			1	90
15-AB-1	70	TRENCH	1	70		
15-B-1	45	TRENCH	1	45		
15-B-2	145	BORE			1	145
15-B-3	365	TRENCH	1	365		
15-B-4	300	TRENCH	1	300		
15-C-1	165	TRENCH	1	165		
15-DE-1	75	TRENCH	1	75		
15-DE-2	255	BORE			1	255
15-DE-3	340	TRENCH	1	340		
SHEET TOTALS				1400		490

CONDUCTOR			
620-6007		620-6008	
ELEC CONDR (NO. 8) BARE		ELEC CONDR (NO. 8) INSULATED	
GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH
5	200	10	400
5	450	10	900
2	140	4	280
1	45	2	90
1	145	2	290
1	365	2	730
1	300	2	600
1	165	2	330
2	150	4	300
2	510	4	1020
2	680	4	1360
	3150		6300

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1400
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	490
620	6007	ELEC CONDR (NO. 8) BARE	LF	3150
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	6300
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	7
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

SH 99


ILLUMINATION LAYOUT
STA 463+00 TO STA 476+00

(SHEET 29 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 40

3/21/2023 12:42:56 PM 2022_0062_ILM29.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
15D1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	479+24	86.23' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
15E1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	487+30	104.45' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW



CONDUIT							
ITEM-CODE	RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
				COUNT	LENGTH	COUNT	LENGTH
15-DE-4		340	TRENCH	1	340		
15-D-1		205	BORE			1	205
15-E-1		390	TRENCH	1	390		
15-E-2		80	BORE			1	80
15-E-3		215	TRENCH	1			
15-E-4		215	TRENCH	1	215		
SHEET TOTALS					945		285

CONDUCTOR			
620-6007		620-6008	
ELEC CONDR (NO. 8) BARE		ELEC CONDR (NO. 8) INSULATED	
GROUND POWER		POWER	
COUNT	LENGTH	COUNT	LENGTH
2	680	4	1360
1	205	2	410
1	390	2	780
1	80	2	160
1	215	2	430
1	215	2	430
SHEET TOTALS		1785	

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	945
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	285
620	6007	ELEC CONDR (NO. 8) BARE	LF	1785
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	3570
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4



Jacob A. Sessions
3/21/2023



© 2023
Texas Department of Transportation


SH 99

ILLUMINATION LAYOUT
STA 476+00 TO STA 489+00

(SHEET 30 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 41

3/21/2023 12:43:45 PM
2022_0062_ILM30.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
16B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	496+64	95.73' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - EXIST HIGH MAST LUMINAIRE
 - PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

Jacob A. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6007		620-6008	
			COND (PVC) (SCH 80) (2")		ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
16-B-2	245	TRENCH	1	245	1	245	2	490
16-B-3	300	TRENCH	1	300	1	300	2	600
SHEET TOTALS				545		545		1090

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	545
620	6007	ELEC CONDR (NO. 8) BARE	LF	545
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	1090
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	1

SH 99


ILLUMINATION LAYOUT
STA 489+00 TO STA 502+00

(SHEET 31 OF 49)

SCALE: 1" = 100'

DWN: ATG	STATE DISTRICT	CKD: ATG	FED. RD. DIV. NO.	C 3510-6-30	PROJECT NO.
TEXAS	HOU	6	HARRIS		
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.	
3510	06	030	SH 99	42	

3/21/2023 12:44:37 PM 2022_0062_ILM31.dgn



- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
16A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	505+52	89.04' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
16A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	513+46	99.73' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			




- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - EXIST HIGH MAST LUMINAIRE
 - PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇄ EXIST TRAFFIC FLOW

CONDUIT RUN ID:
XX-XX-XX
└─┬─┬─┘
└─┬─┘ RUN NUMBER
└─┘ CIRCUIT LETTER
SERVICE NUMBER

POLE ID:
X X X
└─┬─┬─┘
└─┬─┘ POLE NUMBER
└─┘ CIRCUIT LETTER
SERVICE NUMBER

0 100
SCALE: 1"=100'



PROP ELEC SERV #16
TY A 240/480 100(SS)SS(E)GC(O)
CL IH 99 ML STA 508+73.5, 103.9' RT


STATE OF TEXAS
JACOB A. SESSIONS
127122
LICENSED PROFESSIONAL ENGINEER
Jacob Sessions
3/21/2023

CONDUIT							CONDUCTOR				
RUN NO.	ITEM-CODE	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6007		620-6008	
				COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED				
				COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
16-ABC-1		35	TRENCH	1	35			3	105	6	210
16-AB-1		335	TRENCH	1	335			2	670	4	1340
16-AB-2		175	BORE			1	175	2	350	4	700
16-A-1		400	TRENCH	1	400			1	400	2	800
16-A-2		400	TRENCH	1	400			1	400	2	800
16-B-1		300	TRENCH	1	300			1	300	2	600
16-B-2		60	TRENCH	1	60			1	60	2	120
16-C-1		400	TRENCH	1	400			1	400	2	800
16-C-2		245	TRENCH	1	245			1	245	2	490
SHEET TOTALS					2175		175		2930		5860

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND (PVC) (SCH 80) (2")	LF	2175
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	175
620	6007	ELEC CONDR (NO. 8) BARE	LF	2930
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	5860
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ATG ALLIANCE
TRANSPORTATION GROUP
Texas Department of Transportation
SH 99
ILLUMINATION LAYOUT
STA 502+00 TO STA 515+00
(SHEET 32 OF 49)
SCALE: 1" = 100' PROJECT NO. C 3510-6-30
STATE: TEXAS DISTRICT: HOU FED. RD. DIV. NO.: 6 COUNTY: HARRIS
CONTROL SECTION: 06 JOB: 030 HWY. NO.: SH 99 SHEET NO.: 43

3/21/2023 12:45:28 PM
2022_0062_ILM32.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
16C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	522+12	57.22' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇄ EXIST TRAFFIC FLOW



CONDUIT					CONDUCTOR			
ITEM-CODE		CONDUIT STATUS	618-6046		620-6007		620-6008	
RUN NO.	RUN LENGTH (FT)		CONDT (PVC) (SCH 80) (2")	COUNT	LENGTH	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	POWER
16-C-2	15	TRENCH	1	15	1	15	2	30
16-C-3	310	TRENCH	1	310	1	310	2	620
16-C-4	405	TRENCH	1	405	1	405	2	810
SHEET TOTALS				730		730		1460

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	CONDT (PVC) (SCH 80) (2")	LF	730
620	6007	ELEC CONDR (NO. 8) BARE	LF	730
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	1460
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2



SH 99


ILLUMINATION LAYOUT

STA 515+00 TO STA 528+00

(SHEET 33 OF 49)

SCALE: 1" = 100'	PROJECT NO.
DWN: ATG	CKD: ATG
STATE	FED. RD. DIST. NO.
TEXAS	6
CONTROL	COUNTY
3510	HARRIS
SECTION	HWY. NO.
06	SH 99
JOB	SHEET NO.
030	44

3/21/2023 12:46:22 PM 2022_0062_ILM33.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
17A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	530+58	77.18' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
18A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	539+24	79.66' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



STATE OF TEXAS

 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
J. Sessions
 3/21/2023


CONDUIT						
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)
			COUNT	LENGTH	COUNT	LENGTH
17-AB-1	25	TRENCH	1	25		
17-AB-2	45	BORE			1	45
17-AB-3	310	TRENCH	1	310		
17-B-1	200	TRENCH	1	200		
18-A-1	30	TRENCH	1	30		
18-A-2	45	BORE			1	45
18-A-3	80	TRENCH	1	80		
SHEET TOTALS				645		90

CONDUCTOR					
ITEM	DESC	620-6005		620-6006	
		ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED
		GROUND POWER		GROUND POWER	
		COUNT	LENGTH	COUNT	LENGTH
1	25	2	50		
1	45	2	90		
1	310	2	620		
1	200	2	400		
1	30	2	60		
1	45	2	90		
1	80	2	160		
		735	1470		

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	11
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	645
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	90
620	6005	ELEC CONDR (NO. 10) BARE	LF	735
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	1470
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	2

ATG ALLIANCE
 TRANSPORTATION GROUP
 TEXAS Department of Transportation
 SH 99
ILLUMINATION LAYOUT
 STA 528+00 TO STA 541+00
 (SHEET 34 OF 49)
 SCALE: 1" = 100'
 PROJECT NO. C 3510-6-30
 STATE: TEXAS DISTRICT: HOU DIV. NO.: 6 COUNTY: HARRIS
 CONTROL SECTION: 06 JOB: 030 HWY. NO.: SH 99 SHEET NO.: 45

3/21/2023 12:47:19 PM 2022_0062_ILM34.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
19A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	547+49	70.56' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			




- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW




MATCHLINE STA. 541+00

MATCHLINE STA. 554+00



CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COUNT	LENGTH	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED	COUNT
19-A-7	300	TRENCH	1	300	1	300	2	600
19-A-8	360	TRENCH	1	360	1	360	2	720
SHEET TOTALS				660		660		1320

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	660
620	6005	ELEC CONDR (NO.10) BARE	LF	660
620	6006	ELEC CONDR (NO.10) INSULATED	LF	1320
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	1



Jacob A. Sessions
3/21/2023




© 2023
Texas Department of Transportation

SH 99
ILLUMINATION LAYOUT
STA 541+00 TO STA 554+00

(SHEET 35 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 46





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
19A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	556+26	95.12' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
20A4	610-6218	TY SA 40T-12 (250W EQ) LED	CL SH 99 ML	565+27	44.13' RT
20A5	610-6218	TY SA 40T-12 (250W EQ) LED	CL SH 99 ML	562+74	49.62' RT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



PROP ELEC SERV #19
TY A 240/480 100(SS)SS(E)GC(O)
CL SH 99 ML STA 555+06.0, 161.4' RT

CONDUIT			CONDUCTOR							
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047		620-6005		620-6006	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	GROUND		POWER	
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
19-A-1	15	TRENCH	1	15			1	15	2	30
19-A-2	40	BORE			1	40	1	40	2	80
19-A-3	130	TRENCH	1	130			1	130	2	260
19-A-4	210	TRENCH	1	210			1	210	2	420
19-A-5	155	BORE			1	155	1	155	2	310
19-A-6	365	TRENCH	1	365			1	365	2	730
19-A-7	75	TRENCH	1	75			1	75	2	150
20-A-5	180	TRENCH	1	180			1	180	2	360
20-A-6	260	TRENCH	1	260			1	260	2	520
SHEET TOTALS				795		195		990		1980

QUANTITY SUMMARY					
ITEM	DESC	DESCRIPTION	UNITS	QTY	
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46	
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	16	
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5	
610	6218	IN RD IL (TY SA) 40T-12 (250W EQ) LED	EA	2	
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1	
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	2	
618	6046	COND (PVC) (SCH 80) (2")	LF	795	
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	195	
620	6005	ELEC CONDR (NO. 10) BARE	LF	990	
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	1980	
624	6009	GROUND BOX TY D (162922)	EA	2	
624	6010	GROUND BOX TY D (162922) W/APRON	EA	6	
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1	

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation


SH 99

ILLUMINATION LAYOUT
STA 554+00 TO STA 567+00

(SHEET 36 OF 49)

SCALE: 1" = 100'

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 47





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
20A1	610-6290	TY SA 50T-12 (400W EQ) LED	CL SH 99 ML	576+17	59.92' RT
20A2	610-6218	TY SA 40T-12 (250W EQ) LED	CL SH 99 ML	570+15	40.72' RT
20A3	610-6218	TY SA 40T-12 (250W EQ) LED	CL SH 99 ML	567+93	43.52' RT
20A6	610-6290	TY SA 50T-12 (400W EQ) LED	CL SH 99 ML	577+54	66.21' LT
20A7	610-6290	TY SA 50T-12 (400W EQ) LED	CL SH 99 ML	575+35	67.38' LT
20A8	610-6290	TY SA 50T-12 (400W EQ) LED	CL SH 99 ML	573+15	104.87' LT
20A9	610-6218	TY SA 40T-12 (250W EQ) LED	CL SH 99 ML	570+97	87.17' LT
20A10	610-6218	TY SA 40T-12 (250W EQ) LED	CL SH 99 ML	568+77	72.09' LT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT			CONDUCTOR			
ITEM-CODE	RUN NO.	CONDUIT STATUS	618-6046		618-6047	
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED
	LENGTH (FT)		COUNT	LENGTH	COUNT	LENGTH
20-AB-1	105	TRENCH	1	105		
20-AB-2	185	BORE			1	185
20-A-1	350	TRENCH	1	350		
20-A-2	310	TRENCH	1	310		
20-A-3	310	TRENCH	1	310		
20-A-4	230	TRENCH	1	230		
20-A-5	100	TRENCH	1	100		
20-A-7	210	TRENCH	1	210		
20-A-8	225	TRENCH	1	225		
20-A-9	30	TRENCH	1	30		
20-A-10	55	BORE			1	55
20-A-11	205	TRENCH	1	205		
20-A-12	250	TRENCH	1	250		
20-A-13	225	TRENCH	1	225		
20-B-1	50	TRENCH	1	50		
SHEET TOTALS				2600		240

GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH
2	210	4	420
2	370	4	740
1	350	2	700
1	310	2	620
1	310	2	620
1	230	2	460
1	100	2	200
1	210	2	420
1	225	2	450
1	30	2	60
1	55	2	110
1	205	2	410
1	250	2	500
1	225	2	450
1	50	2	100
	3130		6260

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	72
432	6001	RIPRAP (CONC) (4 IN)	CY	0.5
610	6218	IN RD IL (TY SA) 40T-12 (250W EQ) LED	EA	4
610	6290	IN RD IL (TY SA) 50T-12 (400W EQ) LED	EA	4
618	6046	COND (PVC) (SCH 80) (2")	LF	2600
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	240
620	6005	ELEC CONDR (NO.10) BARE	LF	3130
620	6006	ELEC CONDR (NO.10) INSULATED	LF	6260
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

SH 99


ILLUMINATION LAYOUT
STA 567+00 TO STA 580+00

(SHEET 37 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 48

3/21/2023 12:50:05 PM 2022_0062_ILM37.dgn




- NOTES:**
- 1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
20B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	581+67	69.62' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
20B2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	589+73	95.71' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			




- LEGEND**
- - - PROP CONDUIT (TRENCH)
 - PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - PROP GROUND BOX TY D W/ APRON
 - PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - EXIST HIGH MAST LUMINAIRE
 - PROP TY A HIGH MAST LUMINAIRE (AYSM)
 - PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - EXIST TRAFFIC FLOW



CONDUIT RUN ID:
 XX-XX-XX
 RUN NUMBER
 CIRCUIT LETTER
 SERVICE NUMBER

POLE ID:
 X X X
 POLE NUMBER
 CIRCUIT LETTER
 SERVICE NUMBER



STATE OF TEXAS
 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
 3/21/2023

		CONDUIT		CONDUCTOR		CONDUCTOR	
ITEM-CODE	RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
				COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED
20-B-1	175	175	TRENCH	1	175		
20-B-2	405	405	TRENCH	1	405		
20-B-3	405	405	TRENCH	1	405		
21-A-1	25	25	TRENCH	1	25		
21-A-2	55	55	BORE			1	55
21-A-3	80	80	TRENCH	1	80		
SHEET TOTALS					1090		55

		CONDUCTOR		CONDUCTOR		CONDUCTOR					
ITEM-CODE	RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	620-6009		620-6010		620-6005		620-6006	
				ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED		
				GROUND	POWER	GROUND	POWER	GROUND	POWER	GROUND	POWER
				COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
				1	25	2	50	1	175	2	350
				1	55	2	110	1	405	2	810
				1	80	2	160	1	405	2	810
				1	160	2	320	1	405	2	810
				1	160	2	320	1	405	2	810
				1	160	2	320	1	405	2	810

		QUANTITY SUMMARY		QUANTITY SUMMARY	
ITEM	DESC	DESCRIPTION	UNITS	QTY	
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92	
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5	
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2	
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2	
618	6046	COND (PVC) (SCH 80) (2")	LF	1090	
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	55	
620	6005	ELEC CONDR (NO.10) BARE	LF	985	
620	6006	ELEC CONDR (NO.10) INSULATED	LF	1970	
620	6009	ELEC CONDR (NO.6) BARE	LF	160	
620	6010	ELEC CONDR (NO.6) INSULATED	LF	320	
624	6009	GROUND BOX TY D (162922)	EA	2	
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3	
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1	


ILLUMINATION LAYOUT
 STA 580+00 TO STA 593+00

(SHEET 38 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 49

3/21/2023 12:51:00 PM 2022_0062_ILM38.dgn





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
21A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	598+37	73.86' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6009		620-6010	
			CONDT (PVC) (SCH 80) (2")		ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED		
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
21-A-3	240	TRENCH	1	240	1	240	2	480
21-A-4	310	TRENCH	1	310	1	310	2	620
21-A-5	310	TRENCH	1	310	1	310	2	620
21-A-6	310	TRENCH	1	310	1	310	2	620
21-A-7	170	TRENCH	1	170	1	170	2	340
SHEET TOTALS				1340		1340		2680


QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6008	HI MST IL POLE (175 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1340
620	6009	ELEC CONDR (NO. 6) BARE	LF	1340
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	2680
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3

STATE OF TEXAS
 JACOB A. SESSIONS
 127122
 LICENSED PROFESSIONAL ENGINEER
 3/21/2023

ATG ALLIANCE
 TRANSPORTATION GROUP
 © 2023
 Texas Department of Transportation

SH 99
ILLUMINATION LAYOUT
 STA 593+00 TO STA 606+00
 (SHEET 39 OF 49)
 SCALE: 1" = 100'
 PROJECT NO. C 3510-6-30
 STATE: TEXAS DISTRICT: HOU DIV. NO.: 6 COUNTY: HARRIS
 CONTROL SECTION: 06 JOB: 030 HWY. NO.: SH 99 SHEET NO.: 50

3/21/2023 12:51:53 PM 2022_0062_ILM39.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
21A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	607+37	84.18' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
22A4	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	616+84	94.97' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT						
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	COUNT	LENGTH
21-A-7	145	TRENCH	1	145		
21-A-8	335	TRENCH	1	335		
21-A-9	55	BORE			1	55
21-A-10	355	TRENCH	1	355		
21-A-11	355	TRENCH	1	355		
21-A-12	145	TRENCH	1	145		
22-A-13	285	TRENCH	1	285		
SHEET TOTALS				1620		55

CONDUCTOR				CONDUCTOR			
620-6011		620-6012		620-6009		620-6010	
ELEC CONDR (NO. 4) BARE		ELEC CONDR (NO. 4) INSULATED		ELEC CONDR (NO. 6) BARE		ELEC CONDR (NO. 6) INSULATED	
GROUND		POWER		GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
				1	145	2	290
				1	335	2	670
				1	55	2	110
				1	355	2	710
				1	355	2	710
				1	145	2	290
1	285	2	570				
	285		570		1390		2780

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1620
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	55
620	6009	ELEC CONDR (NO. 6) BARE	LF	1390
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	2780
620	6011	ELEC CONDR (NO. 4) BARE	LF	285
620	6012	ELEC CONDR (NO. 4) INSULATED	LF	570
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4



Jacob A. Sessions
3/21/2023




Texas Department of Transportation

SH 99

ILLUMINATION LAYOUT
STA 606+00 TO STA 619+00

(SHEET 40 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 51





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
21A3	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	624+61	92.95' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊗ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046	
			COND (PVC) (SCH 80) (2")	
			COUNT	LENGTH
21-A-12	220	TRENCH	1	220
21-A-13	355	TRENCH	1	355
22-A-10	400	TRENCH	1	400
22-A-11	405	TRENCH	1	405
22-A-12	405	TRENCH	1	405
22-A-13	120	TRENCH	1	120
SHEET TOTALS				1905

CONDUCTOR				CONDUCTOR			
620-6011		620-6012		620-6009		620-6010	
ELEC CONDR (NO. 4) BARE		ELEC CONDR (NO. 4) INSULATED		ELEC CONDR (NO. 6) BARE		ELEC CONDR (NO. 6) INSULATED	
GROUND		POWER		GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
				1	220	2	440
				1	355	2	710
1	400	2	800				
1	405	2	810				
1	405	2	810				
1	120	2	240				
SHEET TOTALS		1330		2660		575	

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	1
618	6046	COND (PVC) (SCH 80) (2")	LF	1905
620	6009	ELEC CONDR (NO. 6) BARE	LF	575
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	1150
620	6011	ELEC CONDR (NO. 4) BARE	LF	1330
620	6012	ELEC CONDR (NO. 4) INSULATED	LF	2660
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4



Jacob A. Sessions
3/21/2023



Texas Department of Transportation

SH 99

ILLUMINATION LAYOUT


STA 619+00 TO STA 632+00

(SHEET 41 OF 49)

SCALE: 1" = 100'

PROJECT NO.		C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 52

3/21/2023 12:53:36 PM
2022_0062_ILM41.dgn



- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
22A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	640+74	87.43' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
22A3	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	632+03	99.35' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW

CONDUIT RUN ID:
XX-XX-XX

— RUN NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER

POLE ID:
X X X

— POLE NUMBER
— CIRCUIT LETTER
— SERVICE NUMBER

0 100
SCALE: 1" = 100'



CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6011		620-6012	
			CONDT (PVC) (SCH 80) (2")		ELEC CONDR (NO. 4) BARE		ELEC CONDR (NO. 4) INSULATED	
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
22-A-5	145	TRENCH	1	145	1	145	2	290
22-A-6	295	TRENCH	1	295	1	295	2	590
22-A-7	345	TRENCH	1	345	1	345	2	690
22-A-8	250	TRENCH	1	250	1	250	2	500
22-A-9	300	TRENCH	1	300	1	300	2	600
22-A-10	10	TRENCH	1	10	1	10	2	20
SHEET TOTALS				1345		1345		2690

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1345
620	6011	ELEC CONDR (NO. 4) BARE	LF	1345
620	6012	ELEC CONDR (NO. 4) INSULATED	LF	2690
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3

STATE OF TEXAS
JACOB A. SESSIONS
127122
LICENSED PROFESSIONAL ENGINEER

J. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

SH 99


ILLUMINATION LAYOUT
STA 632+00 TO STA 645+00

(SHEET 42 OF 49)

SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 53

3/21/2023 12:54:25 PM
2022_0062_ILM42.dgn







- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
22A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	649+37	99.13' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT					CONDUCTOR			
ITEM-CODE		618-6046			620-6011		620-6012	
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	CONDT (PVC) (SCH 80) (2")		ELEC CONDR (NO. 4) BARE		ELEC CONDR (NO. 4) INSULATED	
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
22-A-1	25	TRENCH	1	25	1	25	2	50
22-A-2	260	TRENCH	1	260	1	260	2	520
22-A-3	275	TRENCH	1	275	1	275	2	550
22-A-4	295	TRENCH	1	295	1	295	2	590
22-A-5	155	TRENCH	1	155	1	155	2	310
SHEET TOTALS				1010		1010		2020

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	46
432	6001	RIPRAP (CONC) (4 IN)	CY	5.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	1
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A) SHLD	EA	1
618	6046	CONDT (PVC) (SCH 80) (2")	LF	1010
620	6011	ELEC CONDR (NO. 4) BARE	LF	1010
620	6012	ELEC CONDR (NO. 4) INSULATED	LF	2020
624	6009	GROUND BOX TY D (162922)	EA	1
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

SH 99


ILLUMINATION LAYOUT

STA 645+00 TO STA 658+00

(SHEET 43 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 54

3/21/2023 12:55:14 PM 2022_0062_ILM43.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
23A1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	666+72	118.66' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
23B1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	658+32	85.9' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW



CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		618-6047	
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 4) BARE	ELEC CONDR (NO. 4) INSULATED
			COUNT	LENGTH	COUNT	LENGTH
23-ABC-1	20	TRENCH	1	20		
23-ABC-2	320	TRENCH	1	320		
23-A-1	70	TRENCH	1	70		
23-A-2	370	TRENCH	1	370		
23-A-3	70	TRENCH	1	70		
23-BC-1	165	BORE			1	165
23-B-1	265	TRENCH	1	265		
23-B-2	210	TRENCH	1	210		
23-B-3	355	TRENCH	1	355		
23-C-1	310	TRENCH	1	310		
23-C-2	195	TRENCH	1	195		
SHEET TOTALS				2185		165

GROUND		POWER	
COUNT	LENGTH	COUNT	LENGTH
3	60	6	120
3	960	6	1920
1	70	2	140
1	370	2	740
1	70	2	140
2	330	4	660
1	265	2	530
1	210	2	420
1	355	2	710
1	310	2	620
1	195	2	390
	3195		6390

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10.5
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	2185
618	6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	165
620	6011	ELEC CONDR (NO. 4) BARE	LF	3195
620	6012	ELEC CONDR (NO. 4) INSULATED	LF	6390
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	7
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1



Jacob A. Sessions
3/21/2023




SH 99

ILLUMINATION LAYOUT
STA 658+00 TO STA 671+00

(SHEET 44 OF 49)

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 55

3/21/2023 12:56:05 PM 2022_0062_ILM44.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
23A2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	681+21	140.37' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
23C1	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	675+19	108.82' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW




STATE OF TEXAS
JACOB A. SESSIONS
127122
LICENSED PROFESSIONAL ENGINEER
Jacob Sessions
3/21/2023

CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6011		620-6012	
			COUNT	LENGTH	ELEC CONDR (NO. 4) BARE	ELEC CONDR (NO. 4) INSULATED	GROUND	POWER
23-A-3	310	TRENCH	1	310	1	310	2	620
23-A-4	370	TRENCH	1	370	1	370	2	740
23-A-5	370	TRENCH	1	370	1	370	2	740
23-A-6	290	TRENCH	1	290	1	290	2	580
23-C-2	120	TRENCH	1	120	1	120	2	240
23-C-3	310	TRENCH	1	310	1	310	2	620
23-C-4	375	TRENCH	1	375	1	375	2	750
23-C-5	375	TRENCH	1	375	1	375	2	750
23-C-6	150	TRENCH	1	150	1	150	2	300
SHEET TOTALS				2670		2670		5340

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	CONDT (PVC) (SCH 80) (2")	LF	2670
620	6011	ELEC CONDR (NO.4) BARE	LF	2670
620	6012	ELEC CONDR (NO.4) INSULATED	LF	5340
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	5

ATG ALLIANCE
TRANSPORTATION GROUP
Texas Department of Transportation
SH 99
ILLUMINATION LAYOUT
STA 671+00 TO STA 684+00
(SHEET 45 OF 49)
SCALE: 1" = 100'
PROJECT NO. C 3510-6-30
STATE: TEXAS DISTRICT: HOU DIV. NO.: 6 COUNTY: HARRIS
CONTROL SECTION: 3510 06 JOB: 030 HWY. NO.: SH 99 SHEET NO.: 56

3/21/2023 12:56:59 PM 2022_0062_ILM45.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
23A3	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	691+87	149.32' LT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			
23C2	613-6006	HI MST IL POLE (150 FT) (100 MPH)	CL SH 99 ML	686+31	138.38' RT
	614-6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD			



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT				CONDUCTOR				
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6046		620-6011		620-6012	
			COND'T (PVC) (SCH 80) (2")	COND'T (PVC) (SCH 80) (2")	ELEC CONDR (NO. 4) BARE	ELEC CONDR (NO. 4) INSULATED	ELEC CONDR (NO. 4) BARE	ELEC CONDR (NO. 4) INSULATED
23-A-6	85	TRENCH	1	85	1	85	2	170
23-A-7	365	TRENCH	1	365	1	365	2	730
23-A-8	360	TRENCH	1	360	1	360	2	720
23-C-6	230	TRENCH	1	230	1	230	2	460
SHEET TOTALS				1040		1040		2080

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
416	6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	92
432	6001	RIPRAP (CONC) (4 IN)	CY	10
613	6006	HI MST IL POLE (150 FT) (100 MPH)	EA	2
614	6014	LED HI MST IL AM(6 FIXT) AYSM(TY A)SHLD	EA	2
618	6046	COND'T (PVC) (SCH 80) (2")	LF	1040
620	6011	ELEC CONDR (NO.4) BARE	LF	1040
620	6012	ELEC CONDR (NO.4) INSULATED	LF	2080
624	6009	GROUND BOX TY D (162922)	EA	2
624	6010	GROUND BOX TY D (162922) W/APRON	EA	2



SH 99

ILLUMINATION LAYOUT


STA 684+00 TO STA 697+00

(SHEET 46 OF 49)

SCALE: 1" = 100'

DWN: ATG	CKD: ATG	C 3510-6-30
STATE	DISTRICT	FED. RD. DIV. NO.
TEXAS	HOU	6
CONTROL	SECTION	JOB
3510	06	030
		HWY. NO.
		SH 99
		SHEET NO.
		57

3/21/2023 12:57:57 PM 2022_0062_ILM46.dgn




- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW

CONDUIT RUN ID:
 XX-XX-XX
 |
 | RUN NUMBER
 | CIRCUIT LETTER
 | SERVICE NUMBER

POLE ID:
 X X X
 |
 | POLE NUMBER
 | CIRCUIT LETTER
 | SERVICE NUMBER



Jacob A. Sessions
 3/21/2023




SH 99
 ILLUMINATION LAYOUT
 STA 697+00 TO STA 710+00

(SHEET 47 OF 49)

SCALE: 1" = 100'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 58



3/21/2023 12:58:47 PM
 2022_0062_ILM47.dgn



- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



MATCHLINE STA. 710+00

MATCHLINE STA. 723+00



J. Sessions
3/21/2023



© 2023
Texas Department of Transportation

SH 99

ILLUMINATION LAYOUT
STA 710+00 TO STA 723+00

(SHEET 48 OF 49)


SCALE: 1" = 100' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 59

CONDUIT			CONDUCTOR						
ITEM-CODE	CONDUIT STATUS	618-6046		618-6047		620-6005		620-6006	
		COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED	GROUND POWER			
RUN NO.	RUN LENGTH (FT)	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
24-A-1	70	1	70			1	70	2	140
24-A-2	65			1	65	1	65	2	130
24-A-3	135	1	135			1	135	2	270
SHEET TOTALS			205		65		270		540

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
432	6001	RIPRAP (CONC) (4 IN)	CY	0.5
618	6046	COND (PVC) (SCH 80) (2")	LF	205
618	6047	COND (PVC) (SCH 80) (2") (BORE)	LF	65
620	6005	ELEC CONDR (NO.10) BARE	LF	270
620	6006	ELEC CONDR (NO.10) INSULATED	LF	540
624	6010	GROUND BOX TY D (162922) W/APRON	EA	3
628	6082	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	EA	1

3/21/2023 12:59:46 PM
2022.0062_ILM48.dgn





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇨ EXIST TRAFFIC FLOW

- CONDUIT RUN ID:**
XX-XX-XX
- RUN NUMBER
 - CIRCUIT LETTER
 - SERVICE NUMBER
- POLE ID:**
X X X
- POLE NUMBER
 - CIRCUIT LETTER
 - SERVICE NUMBER



Jacob A. Sessions
3/21/2023




SH 99
ILLUMINATION LAYOUT
STA 723+00 TO END

(SHEET 49 OF 49)

SCALE: 1" = 100'		PROJECT NO.		
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	60

3/21/2023 1:00:47 PM
2022_0062_ILM49.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
1A1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	111+49	45.8' LT
1A2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	111+95	45.8' LT
1A3	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	112+16	45.8' LT
1A4	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	112+66	45.8' LT
1A5	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	112+66	46.5' RT
1A6	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	112+16	46.5' RT
1A7	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	111+95	46.5' RT
1A8	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	111+49	46.5' RT
1A9	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	112+66	92.7' RT
1A10	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	112+16	95.1' RT
1A11	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	111+95	95.6' RT
1A12	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	CL SH 99 ML	111+49	97.8' RT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT			CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6070		620-6005	620-6006
			COUNT	LENGTH	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED
1-A-4	25	RM	1	25	1	2
1-A-5	65	RM	1	65	1	2
1-A-6	55	RM	1	55	1	2
1-A-7	20	RM	1	20	1	2
1-A-8	55	RM	1	55	1	2
1-A-9	45	RM	1	45	1	2
1-A-10	100	RM	1	100	1	2
1-A-11	45	RM	1	45	1	2
1-A-12	55	RM	1	55	1	2
1-A-13	20	RM	1	20	1	2
1-A-14	55	RM	1	55	1	2
1-A-15	50	RM	1	50	1	2
1-A-16	45	RM	1	45	1	2
1-A-17	60	RM	1	60	1	2
1-A-18	20	RM	1	20	1	2
1-A-19	55	RM	1	55	1	2
SHEET TOTALS			770		770	1540

SEE ILLUMINATION LAYOUT SHEET 1 OF 49 FOR DETAILS

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	12
618	6070	CONDT (RM) (2")	LF	770
620	6005	ELEC CONDR (NO. 10) BARE	LF	770
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	1540

3/21/2023 1:01:57 PM 2022_0062_ILMUP01.dgn

Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

J. Sessions
3/21/2023


ATG ALLIANCE
TRANSPORTATION GROUP

Texas Department of Transportation

SH 99
UNDERPASS
ILLUMINATION LAYOUT
CYPRESSWOOD DR BRIDGE

(SHEET 1 OF 7)

SCALE: 1" = 40'		PROJECT NO.	
DWN: ATG	CKD: ATG	C 3510-6-30	
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 61





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
3A1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	158+16	46.49' RT
3A2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	158+07	41.49' RT
3A3	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	157+60	41.51' RT
3A4	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	158+14	31.34' LT
3A5	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	158+05	36.34' LT
3A6	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	157+55	36.35' LT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



Jacob A. Sessions
3/21/2023



SH 99
UNDERPASS
ILLUMINATION LAYOUT
CUMBERLAND RIDGE DR BRIDGE

(SHEET 2 OF 7)


SCALE: 1" = 40' PROJECT NO. C 3510-6-30

STATE	CKD: ATG	FED. RD. DIST. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 62

CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6070		620-6005		620-6006	
			COUNT	LENGTH	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	GROUND	POWER
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
3-A-2	30	RM	1	30	1	30	2	60
3-A-3	30	RM	1	30	1	30	2	60
3-A-4	75	RM	1	75	1	75	2	150
3-A-5	10	RM	1	10	1	10	2	20
3-A-6	55	RM	1	55	1	55	2	110
3-A-7	85	RM	1	85	1	85	2	170
3-A-8	80	RM	1	80	1	80	2	160
3-A-9	10	RM	1	10	1	10	2	20
3-A-10	60	RM	1	60	1	60	2	120
SHEET TOTALS			435		435		870	

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	6
618	6070	COND (RM) (2")	LF	435
620	6005	ELEC CONDR (NO. 10) BARE	LF	435
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	870

3/21/2023 1:02:35 PM
2022_0062_ILMUP02.dgn





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES						
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET	
5B1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	176+97	41.29' LT	
5B2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	176+29	43.69' LT	
5B3	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	177+19	36.09' RT	
5B4	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	176+49	33.69' RT	



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

Jacob A. Sessions
3/21/2023

CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	COND'T (RM) (2")		620-6005		620-6006	
			COUNT	LENGTH	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	GROUND	POWER
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
5-B-2	20	RM	1	20	1	20	2	40
5-B-3	30	RM	1	30	1	30	2	60
5-B-4	20	RM	1	20	1	20	2	40
5-B-5	85	RM	1	85	1	85	2	170
5-B-6	90	RM	1	90	1	90	2	180
5-B-7	20	RM	1	20	1	20	2	40
5-B-8	85	RM	1	85	1	85	2	170
SHEET TOTALS				350		350		700

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	4
618	6070	COND'T (RM) (2")	LF	350
620	6005	ELEC CONDR (NO. 10) BARE	LF	350
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	700

ATG ALLIANCE
TRANSPORTATION GROUP


© 2023
Texas Department of Transportation

SH 99
UNDERPASS
ILLUMINATION LAYOUT
SCHIEL RD BRIDGE

(SHEET 3 OF 7)

SCALE: 1" = 40'	PROJECT NO.		
DWN: ATG	CKD: ATG		
C 3510-6-30			
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 63

3/21/2023 1:03:31 PM 2022_0062_ILMUP03.dgn




- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
11C1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	☉ SH 99 ML	354+32	39.66' LT
11C2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	☉ SH 99 ML	355+32	37.71' LT
11C3	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	☉ SH 99 ML	354+49	35.24' RT
11C4	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	☉ SH 99 ML	355+50	37.19' RT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



CONDUIT RUN ID:
XX-XX-XX
└─ RUN NUMBER
└─ CIRCUIT LETTER
└─ SERVICE NUMBER

POLE ID:
X X X
└─ POLE NUMBER
└─ CIRCUIT LETTER
└─ SERVICE NUMBER

0 40
SCALE: 1" = 40'

STATE OF TEXAS
JACOB A. SESSIONS
127122
LICENSED PROFESSIONAL ENGINEER
J. Sessions
3/21/2023


ATG ALLIANCE
TRANSPORTATION GROUP
© 2023
Texas Department of Transportation

SH 99
UNDERPASS ILLUMINATION LAYOUT
MUESCHKE RD BRIDGE
(SHEET 4 OF 7)
SCALE: 1" = 40' PROJECT NO. C 3510-6-30
DWN: ATG CKD: ATG
STATE DISTRICT FED. RD. DIV. NO. COUNTY
TEXAS HOU 6 HARRIS
CONTROL SECTION JOB HWY. NO. SHEET NO.
3510 06 030 SH 99 64

CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	618-6070		620-6005		620-6006	
			COUNT	LENGTH	ELEC CONDR (NO. 10) BARE	ELEC CONDR (NO. 10) INSULATED	GROUND	POWER
					COUNT	LENGTH	COUNT	LENGTH
11-CD-2	45	RM	1	45	2	90	4	180
11-C-1	20	RM	1	20	1	20	2	40
11-C-2	65	RM	1	65	1	65	2	130
11-C-3	115	RM	1	115	1	115	2	230
11-C-4	80	RM	1	80	1	80	2	160
11-C-5	80	RM	1	80	1	80	2	160
11-C-6	120	RM	1	120	1	120	2	240
11-D-1	170	RM	1	170	1	170	2	340
11-D-2	45	RM	1	45	1	45	2	90
SHEET TOTALS				740		785		1570

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	4
618	6070	COND (RM) (2")	LF	740
620	6005	ELEC CONDR (NO.10) BARE	LF	785
620	6006	ELEC CONDR (NO.10) INSULATED	LF	1570

3/21/2023 1:04:19 PM 2022_0062_ILMUP04.dgn





- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
15C1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	470+83	37.92' RT
15C2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	471+24	37.92' RT
15C3	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	471+89	39.62' RT
15C4	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	470+70	38.10' LT
15C5	610-6105	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	471+10	38.10' LT
15C6	610-6106	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	471+77	36.39' LT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

J. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

SH 99
UNDERPASS
ILLUMINATION LAYOUT
CYPRESS ROSEHILL RD BRIDGE

(SHEET 5 OF 7)


SCALE: 1" = 40' PROJECT NO. C 3510-6-30

STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO. SHEET NO.
3510	06	030	SH 99 65

CONDUIT					CONDUCTOR			
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	COND'T (RM) (2")		620-6007		620-6008	
			COUNT	LENGTH	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	GROUND	POWER
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
15-C-2	45	RM	1	45	1	45	2	90
15-C-3	25	RM	1	25	1	25	2	50
15-C-4	50	RM	1	50	1	50	2	100
15-C-5	80	RM	1	80	1	80	2	160
15-C-6	85	RM	1	85	1	85	2	170
15-C-7	50	RM	1	50	1	50	2	100
15-C-8	85	RM	1	85	1	85	2	170
SHEET TOTALS				420		420		840


QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	6
618	6070	COND'T (RM) (2")	LF	420
620	6007	ELEC CONDR (NO. 8) BARE	LF	420
620	6008	ELEC CONDR (NO. 8) INSULATED	LF	840

3/21/2023 1:05:10 PM
 2022_0062_ILMUP05.dgn




- NOTES:**
1. CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 2. ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 3. COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 4. JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESCR.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
17B1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	528+45	2.70' RT
17B2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	527+32	2.69' RT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - ≡≡≡ PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



ATG ALLIANCE
TRANSPORTATION GROUP

Texas Department of Transportation

SH 99
UNDERPASS
ILLUMINATION LAYOUT
CEDAR LN BRIDGES

(SHEET 6 OF 7)


SCALE: 1" = 40' PROJECT NO. C 3510-6-30

DWN: ATG	STATE DISTRICT	CKD: ATG	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6		HARRIS
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	66

CONDUIT					CONDUCTOR			
ITEM-CODE		618-6070			620-6006		620-6007	
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	CONDT (RM) (2")		ELEC CONDR (NO.10) BARE	ELEC CONDR (NO.10) INSULATED		
			COUNT	LENGTH			GROUND	POWER
			COUNT	LENGTH	COUNT	LENGTH	COUNT	LENGTH
17-B-2	50	RM	1	50	1	50	2	100
17-B-3	50	RM	1	50	1	50	2	100
17-B-4	105	RM	1	105	1	105	2	210
SHEET TOTALS				205		205		410

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	2
618	6070	CONDT (RM) (2")	LF	205
620	6005	ELEC CONDR (NO.10) BARE	LF	205
620	6006	ELEC CONDR (NO.10) INSULATED	LF	410

3/21/2023 1:05:54 PM 2022_0062_ILMUP06.dgn





- NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF ALL UTILITIES IN FIELD PRIOR TO LIGHTING INSTALLATION.
 - ALL ELECTRICAL WORK SHALL MEET NEC REQUIREMENTS.
 - COORDINATE AND VERIFY ALL SERVICE POLE LOCATIONS AND SERVICE DROPS WITH RESPECTIVE ELECTRICAL COMPANY REPRESENTATIVES.
 - JUNCTION BOXES SHALL NOT BE PAID FOR DIRECTLY BUT CONSIDERED SUBSIDIARY TO VARIOUS CONTRACT ITEMS.

SCHEDULE OF ROADWAY ILLUMINATION ASSEMBLIES					
POLE NO.	ITEM DESC.	ILLUMINATION ASSEMBLY DESCRIPTION	CHAIN	STATION	OFFSET
24A1	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	715+88	35.63' RT
24A2	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	717+10	34.26' RT
24A3	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	715+86	27.76' LT
24A4	610-6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	℄ SH 99 ML	717+09	29.12' LT



- LEGEND**
- PROP CONDUIT (TRENCH)
 - === PROP CONDUIT (BORE)
 - PROP CONDUIT (RM)
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - ⊞ PROP DISCONNECT BOX
 - EXIST RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ EXIST HIGH MAST LUMINAIRE
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)
 - ⇒ EXIST TRAFFIC FLOW



Jacob A. Sessions
127122
LICENSED PROFESSIONAL ENGINEER

J. Sessions
3/21/2023

ATG ALLIANCE
TRANSPORTATION GROUP

© 2023
Texas Department of Transportation

CONDUIT					CONDUCTOR			
ITEM-CODE		618-6070			620-6005		620-6006	
RUN NO.	RUN LENGTH (FT)	CONDUIT STATUS	CONDT (RM) (2")		ELEC CONDR (NO. 10) BARE		ELEC CONDR (NO. 10) INSULATED	
			COUNT	LENGTH	GROUND	POWER	COUNT	LENGTH
24-A-4	80	RM	1	80	1	80	2	160
24-A-5	35	RM	1	35	1	35	2	70
24-A-6	140	RM	1	140	1	140	2	280
24-A-7	70	RM	1	70	1	70	2	140
24-A-8	140	RM	1	140	1	140	2	280
SHEET TOTALS				465		465		930

QUANTITY SUMMARY				
ITEM	DESC	DESCRIPTION	UNITS	QTY
610	6104	IN RD IL (U/P) (TY 1) (150W EQ) LED	EA	4
618	6070	CONDT (RM) (2")	LF	465
620	6005	ELEC CONDR (NO. 10) BARE	LF	465
620	6006	ELEC CONDR (NO. 10) INSULATED	LF	930

SH 99
UNDERPASS
ILLUMINATION LAYOUT
ROCKY RD BRIDGE

(SHEET 7 OF 7)

SCALE: 1" = 40' PROJECT NO. C 3510-6-30

DWN: ATG	STATE DISTRICT	CKD: ATG	FED. RD. DIV. NO.	COUNTY
TEXAS	HOU	6	6	HARRIS
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	67

3/21/2023 1:06:16 PM 2022_0062_ILMUP07.dgn

3/21/2023 1:42:13 PM
2022_0062_ILM_CIR.dgn

SERVICE NUMBER	SHEET NUMBER	ELECTRICAL SERVICE DESCRIPTION	SERVICE CONDUIT SIZE	SERVICE CONDUCTOR NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK. POLE/AMP	TWO-POLE CONTACTOR AMPS	PANELBD./LOADCENTER AMP RATING (MIN)	CIRCUIT NO.	BRANCH CKT. BRK. POLE/AMPS	BRANCH CIRCUIT AMPS	KVA LOAD
1	ILM-01	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/15	5.04	2.4
2	ILM-05	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	7.2
3	ILM-05	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/15	2.52	8.4
4	ILM-06	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
5	ILM-06	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	8.0
6	ILM-07	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/15	1.68	
7	ILM-13	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/40	30	28.8
8	ILM-14	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/40	30	
9	ILM-17	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	30	43.2
10	ILM-19	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/40	30	
11	ILM-20	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/40	30	
12	ILM-22	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	14.4
13	ILM-25	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
14	ILM-27	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	36.0
15	ILM-29	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/40	30	
16	ILM-32	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/40	30	
17	ILM-20	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/40	30	22.4
18	ILM-22	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
19	ILM-25	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/15	1.68	
20	ILM-27	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	D	1P/20	15	
21	ILM-22	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/40	30	36.0
22	ILM-25	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/40	30	
23	ILM-27	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/20	15	
24	ILM-25	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	21.6
25	ILM-27	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
26	ILM-29	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/20	15	
27	ILM-29	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	30.0
28	ILM-32	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
29	ILM-34	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/15	2.52	
30	ILM-34	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	D	1P/20	15	
31	ILM-36	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	E	1P/20	15	
32	ILM-32	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/40	30	28.8
33	ILM-34	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
34	ILM-34	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/15	0.84	7.6
35	ILM-36	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
36	ILM-37	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	15	7.2
37	ILM-36	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/40	30	
38	ILM-37	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/20	8.09	18.3
39	ILM-38	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/40	30	
40	ILM-43	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/60	45	21.6
41	ILM-44	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/80	60	
42	ILM-44	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/60	45	43.2
43	ILM-44	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	B	1P/20	15	
44	ILM-48	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	C	1P/40	30	
45	ILM-48	ELC SRV TY A 240/480 100(SS)SS(E)GC(O)	1 1/4"	3/#6	100	2P/100	2P/100	N/A	A	1P/15	1.68	0.8



Jacob A. Sessions
3/21/2023




SH 99

**ELECTRICAL
DETAILS**



(SHEET 1 OF 1)

SCALE:		PROJECT NO.			
DWN: ATG	CKD: ATG	C 3510-6-30			
STATE	DISTRICT	FED. RD. DIV. NO.	COUNTY		
TEXAS	HOU	6	HARRIS		
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.	
3510	06	030	SH 99	68	



3/21/2023 1:42:18 PM
 2022_0062_ILM_CIR_DIA1.dgn





ELECTRICAL SERVICE NO. 8





ELECTRICAL SERVICE NO. 9





ELECTRICAL SERVICE NO. 10



ELECTRICAL SERVICE NO. 11



ELECTRICAL SERVICE NO. 12



- LEGEND**
- PROP CONDUIT
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊗ PROP JUNCTION BOX
 - ⊗-○ PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊗ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)

Jacob A. Sessions
 127122
 LICENSED PROFESSIONAL ENGINEER

Jacob A. Sessions
 3/21/2023



ATG ALLIANCE
 TRANSPORTATION GROUP

Texas Department of Transportation
 SH 99

ILLUMINATION CIRCUIT DIAGRAM
 (SHEET 1 OF 2)

SCALE:		PROJECT NO.		
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	69

3/21/2023 1:42:19 PM
 2022_0062_ILM_CIR_DIA2.dgn



- LEGEND**
- PROP CONDUIT
 - PROP ELECTRICAL SERVICE
 - PROP GROUND BOX TY D
 - ▣ PROP GROUND BOX TY D W/ APRON
 - ⊠ PROP JUNCTION BOX
 - PROP RDWY ILL ASSEMBLY (TRANSFORMER BASE)
 - ⊙ PROP TY A HIGH MAST LUMINAIRE (ASYM)
 - ▶ PROP RDWY ILL ASSEMBLY (UNDERPASS)



SH 99

**ILLUMINATION
CIRCUIT DIAGRAM**

(SHEET 2 OF 2)

SCALE:		PROJECT NO.		
DWN: ATG	CKD: ATG	C 3510-6-30		
STATE	STATE DISTRICT	FED. RD. DIV. NO.	COUNTY	
TEXAS	HOU	6	HARRIS	
CONTROL	SECTION	JOB	HWY. NO.	SHEET NO.
3510	06	030	SH 99	70

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

<p>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov</p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

DATE: 3/21/2023 1:42:20 PM
 FILE: BC(1)-21.dgn

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

BC (1) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
	3510	06	030	SH 99
REVISIONS	DIST	COUNTY	SHEET NO.	
4-03 7-13	HOU	HARRIS	71	
9-07 8-14				
5-10 5-21				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
	Type 3 Barricade
	Channelizing Devices
	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	72	

DATE: 3/21/2023 1:42:20 PM
 FILE: BC(2)-21.dgn

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/21/2023 1:42:21 PM
FILE: BC(3)-21.dgn

SHEET 3 OF 12

Texas Department of Transportation		Traffic Safety Division Standard
<h2 style="margin: 0;">BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>		
<h3 style="margin: 0;">BC (3) - 21</h3>		
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT SECT	JOB HIGHWAY
REVISIONS	3510 06	030 SH 99
9-07 8-14	DIST	COUNTY SHEET NO.
7-13 5-21	HOU	HARRIS 73

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	74	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- * See BC(4) for definition of "Work Duration."
- ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	75	

DATE: 3/21/2023 1:42:23 PM
FILE: BC(5) - 21.dgn

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM - X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	76	

DATE: 3/21/2023 1:42:24 PM
FILE: BC(6)-21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE: 3/21/2023 1:42:24 PM
 FILE: BC(7)-21.dgn

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	77	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:25 PM
 FILE: BC(8)-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign
substrates shall NOT be used on
plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		3510	06	030	SH 99				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	HOU	HARRIS	78					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)


- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	79	


DATE: 3/21/2023 1:42:26 PM
FILE: BC(9)-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES


Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




PLAN VIEW

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	80	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS





BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		3510	06	030
2-98	9-07	5-21		SH 99
1-02	7-13			
11-02	8-14			
	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	81	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



DATE: 3/21/2023 1:42:34 PM
FILE: BC(11)-21.dgn

PAVEMENT MARKING PATTERNS





Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS





Prefabricated markings may be substituted for reflectorized pavement markings.

EDGE & LANE LINES FOR DIVIDED HIGHWAY



Prefabricated markings may be substituted for reflectorized pavement markings.


LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS





Prefabricated markings may be substituted for reflectorized pavement markings.

TWO-WAY LEFT TURN LANE



STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
1-97 9-07 5-21				
2-98 7-13				
11-02 8-14				
	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	82	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:35 PM
FILE: BC(12)-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:36 PM
 FILE: ED(1)-14.dgn

GENERAL NOTES FOR ALL ELECTRICAL WORK

- The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
- Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
- Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is 1/2 in. or less in diameter.
- Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
- Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
- When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

CONDUIT

A. MATERIALS

- Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
- Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
- Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.


AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" x 8" x 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" x 8" x 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" x 8" x 4"	8" x 8" x 4"	10" x 10" x 4"
#8	8" x 8" x 4"	8" x 8" x 4"	8" x 8" x 4"

- Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
- Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
- Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
- Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

- Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
- When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
- Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.


B. CONSTRUCTION METHODS

- Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
- Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
- Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
- Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
- When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
- Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
- During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
- Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
- Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
- Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
- At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
- Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
- Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
- File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.

				Traffic Operations Division Standard	
<h1>ELECTRICAL DETAILS CONDUITS & NOTES</h1>					
<h2>ED(1) - 14</h2>					
FILE:	ed1-14.dgn	DN:	CK:	DW:	CK:
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		3510	06	030	SH 99
		DIST	COUNTY		SHEET NO.
		HOU	HARRIS		83

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



DATE: 3/21/2023 1:42:37 PM
FILE: ED(2)-14.dgn



CONDUIT HANGING DETAIL


CONDUIT MOUNTING CHANNEL		
"SPAN"	"W" x "H"	"T"
less than 2'	1 5/8" x 1 3/8"	12 Ga.
2'-0" to 2'-6"	1 5/8" x 1 5/8"	12 Ga.
>2'-6" to 3'-0"	1 5/8" x 2 7/16"	12 Ga.

Channels with round or short slotted hole patterns are allowed, if the load carrying capacity is not reduced by more than 15%.




HANGER ASSEMBLY DETAIL

ELECTRIC CONDUIT TO BRIDGE DECK ATTACHMENT



CONDUIT MOUNTING OPTIONS

Attachment to concrete surfaces
See ED(1)B.2



TYPICAL CONDUIT ENTRY TO BRIDGE STRUCTURE DETAIL

EXPANSION ANCHOR NOTES FOR BRIDGE DECK ATTACHMENT

1. Use torque controlled mechanical expansion anchors that are approved for use in cracked concrete by the International Code Council, Evaluation Service (ICC-ES). The chosen anchor product shall have a designated ICC-ES Evaluation Report number, and its approval status shall be maintained on the ICC-ES website under Division 031600 for Concrete Anchors.
2. Unless otherwise approved by the Engineer: do not use adhesive anchors; do not use expansion anchors that are not included in the ICC-ES approval list; and do not use expansion anchors that are only approved for use in uncracked concrete.
3. Use anchors manufactured with stainless steel expansion wedges. Anchors manufactured with carbon steel expansion wedges are not allowed. Anchor bodies can be either zinc-plated carbon steel or stainless steel. For application in marine environment, both the anchor body and expansion wedge shall be stainless steel.
4. Install anchors as shown on the plans and in accordance with the anchor manufacturer's published installation instructions. Arrange a field demonstration test to evaluate the procedures and tools. The test shall be witnessed and approved by the Engineer prior to furnishing anchors on the structure.
5. Prior to hole drilling, use rebar locator to ensure clearing of existing deck strands or reinforcement. Install anchors to ensure a minimum effective embedment depth, (h_{ef}), as shown. Increase (h_{ef}) as needed to ensure sufficient thread length for proper torqueing and tightening of anchors.
6. Use anchors of minimum 1600 Lbs tensile capacity (minimum of steel, concrete breakout, and concrete pullout strengths as determined by ACI 318 Appendix D) at the required minimum embedment depth (h_{ef}). No lateral loads shall be introduced after conduit installation.



ELECTRICAL DETAILS
CONDUIT SUPPORTS

ED(2)-14

FILE: ed2-14.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	84	

ELECTRICAL CONDUCTORS

A. MATERIAL INFORMATION

1. Provide Type XHHW insulated conductors in accordance with Departmental Material Specification (DMS) 11040 "Conductors" and Item 620 "Electrical Conductors." Provide conductors as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 620. Color code insulated conductors in conformance with the NEC. Identify grounded (neutral) conductors with white insulation. Identify grounding conductors (ground wires) with green insulation or bare conductors. Identify ungrounded (hot) conductors with any color insulation except green, white, or gray. Keep color scheme consistent throughout the wiring system. Identify conductors 6 American Wire Gauge (AWG) and smaller by continuous color jacket. Identify electrical conductors 4 AWG and larger by continuous color jacket or by colored tape. When identifying conductors with colored tape, mark at least 6 in. of the conductor's insulation with half laps of tape.
2. Provide a solid copper 6 AWG grounding electrode conductor to bond the electrical service equipment to the concrete encased grounding electrode or the ground rod at the service location. Connect the grounding electrode conductor to the ground rod with a UL listed connector in accordance with DMS 11040. Connect the grounding electrode conductor to the concrete encased grounding electrode as shown in the plans.
3. Where two or more circuits are present in one conduit or enclosure, permanently identify the conductors of each branch circuit by attaching a non-metallic tag around both circuit conductors at each accessible location. Provide tags with two straps, large enough to indicate circuit number, letter, or other identification as shown in the plans. Print circuit identification on the tag with a permanent marker.
4. Use listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors for splicing as specified in DMS 11040. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Provide UL listed gel-filled insulating splice covers. Splicing materials, insulating materials, breakaway disconnects, splice covers, and fuse holders are subsidiary to various bid items.

B. CONSTRUCTION METHODS

1. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the conduit system. After installing conductors in conduit, perform conductor pull test. If a conductor cannot be freely pulled, make any needed alterations or repairs at no additional cost to the department. Perform insulation resistance tests in accordance with Item 620. Coordinate with the Engineer to witness the tests.
2. Leave 2 ft. minimum, 3 ft. maximum length for each conductor up to the splice in ground boxes. Leave 3 ft. minimum, 4 ft. maximum length of conductor in ground boxes when pulled through with no splice. Leave 1 ft. minimum, 1.5 ft. maximum length of conductor at enclosures, weatherheads and pole bases.
3. Make splices only in junction boxes, ground boxes, pole bases, or electrical enclosures and use only listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors. Insulate splices with heavy wall heat shrink tubing or gel-filled insulating splice covers to provide a watertight seal. Overlap conductor insulation with heat shrink tubing a minimum of 2 in. past both sides of the splice. Where heat shrink tubing may not shrink sufficiently to provide a watertight seal around the individual conductors, prior to heating the tubing, increase the diameter of the conductor insulation using hot melt adhesive tape to provide a watertight seal between the individual conductors and the heat shrink tubing. Ensure the tape extends past the heat shrink tubing. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Heat shrink tubing that appears to have been burned, or overheated, is considered defective and must be replaced.
4. Size and install gel-filled insulating splice covers according to manufacturer's specifications when used in place of heat shrink tubing.
5. Wire nuts with factory applied waterproof sealant may be used for 8 AWG or smaller conductors in above ground junction boxes, but not in pole bases or ground boxes. Install wire nuts in an upright position to prevent the accumulation of water.
6. Support conductors in illumination poles with a J-hook at the top of the pole.
7. When terminating conductors, remove the insulation and jacketing material without nicking the individual strands of the conductor. Conductors with nicked individual conductor strands or removed strands will be considered damaged.
8. Replace conductors and cables that are damaged beyond repair or that fail an insulation resistance test at no additional cost to the department.
9. Do not repair damaged conductors with duct tape, electrical tape, or wire nuts. Use only approved splicing methods.
10. Do not terminate more than one conductor under a single connector, unless the connector is rated for multiple conductors. Do not exceed the pressure connector's listing for maximum number and size of conductors allowed.
11. Install breakaway connectors on conductors bid under Item 620 whenever those conductors pass through a breakaway support device. Follow manufacturer's instructions when terminating conductors to breakaway connectors. Properly torque threaded connections. Proper terminations are critical to the safe operation of breakaway devices. Trim waterproofing boots on breakaway connectors to fit snugly around the conductor to ensure waterproof connection. Only one conductor may enter a single opening in a boot. Provide waterproof boots with the correct number of openings. Leave unused openings factory sealed. Use prequalified breakaway connectors as shown on the MPL.

12. Provide and install a separate stranded equipment grounding conductor (EGC) in all conduits that contain circuit wiring of 50 volts or more. Unless shown elsewhere, size the EGC to be the same size as the largest current carrying conductor contained in the conduit. Ensure all EGCs are bonded together at every accessible location. For traffic signal installations, provide a minimum size 8 AWG EGC. The EGC is paid for under Item 620.

C. TEMPORARY WIRING

1. Install temporary conductors and electrical equipment in accordance with the NEC article "Temporary Installations" and Department standard sheets.
2. Provide a ground fault circuit interrupter (GFCI) for power outlets for portable electrical equipment, power tools, ice machines, ice storage bins and refrigerators located outdoors at grade. GFCI may be any one of the following: molded cord and plug set, receptacle, or circuit breaker type.
3. Use listed wire nuts with factory applied sealant for temporary wiring where approved.
4. Enclose conductor splices within a listed enclosure or ground box, or ensure the splices are more than 10 ft. above grade vertically and more than 5 ft. horizontally from any metal structure. Where installing temporary conductors in areas subject to vehicle traffic or mobile construction equipment, ensure the vertical clearance to ground is at least 18 ft. when measured at the lowest point. Ground messenger wires that support power conductors in conformance with the NEC.
5. Protect and when necessary repair any existing electrical conduits uncovered during the construction process in a timely manner and in conformance with the NEC.


GROUND RODS & GROUNDING ELECTRODES

A. MATERIAL INFORMATION


1. Provide and install a grounding electrode at electrical services. Provide ground rods according to DMS 11040 and the plans. Larger diameter or longer length rods may be called for in some specific locations, see the individual plans sheets. Concrete encased grounding electrodes may be called for in specific locations including electrical service, see individual plan sheets.

B. CONSTRUCTION METHODS


1. Furnish auxiliary ground rods for lightning protection and install in soil, concrete, or both, as called for in the plans. For ground rods installed in concrete, ensure the connection of the conductor to the ground rod is readily accessible for inspection or repairs. For ground rods installed in soil, ensure that the upper end is between 2 to 4 in. below finished grade.
2. Do not place ground rods in the same drilled hole as a timber pole.
3. Install ground rods so the imprinted part number is at the upper end of the rod.
4. Remove all non-conductive coatings such as concrete splatter from the rod at the clamp location.
5. Route all conductors as short and straight as possible for connection to lightning protection ground rods. When a bend is required, ensure a minimum radius bend of four inches for these conductors.
6. Unless otherwise called for in the plans, protect grounding electrode conductors with non-metallic conduit. When protecting grounding electrode conductors with metal conduit, provide and install a grounding type bushing and properly sized bonding jumper on each end of the metal conduit.
7. Written authorization is required before installing a ground rod in a horizontal trench for rocky soil or a solid rock bottom.



**SPLICE OPTION 1
Compression Type**



**SPLICE OPTION 2
Split Bolt Type**




**SPLICE OPTION 3
Listed Screw Type**

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:39 PM
FILE: ED(3)-14.dgn

				Traffic Operations Division Standard	
<h1>ELECTRICAL DETAILS CONDUCTORS</h1>					
<h2>ED(3)-14</h2>					
FILE: ed3-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
© TxDOT October 2014	CONT	SECT	JOB	HIGHWAY	
REVISIONS	3510	06	030	SH	99
	DIST	COUNTY		SHEET NO.	
	HOU	HARRIS			85

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




APRON FOR GROUND BOX

- (1) Uniformly space ends of conduits within the ground box. Position ends of conduits so that ground box walls do not interfere with the installation of grounding bushings or bell end fittings.
- (2) Maintain sufficient space between conduits to allow for proper installation of bushing.
- (3) Place aggregate under the box, not in the box. Aggregate should not encroach on the interior volume of the box.
- (4) Install a grounding bushing on the upper end of all RMC terminating in a ground box. Ground RMC elbows when any part of the elbow is less than 18 in. below the bottom of the ground box. Install a PVC bushing or bell end fitting on the upper end of all PVC conduits terminating in a ground box.

GROUND BOX DIMENSIONS	
TYPE	OUTSIDE DIMENSIONS (INCHES) (Width x Length X Depth)
A	12 X 23 X 11
B	12 X 23 X 22
C	16 X 29 X 11
D	16 X 29 X 22
E	12 X 23 X 17

GROUND BOX COVER DIMENSIONS								
TYPE	DIMENSIONS (INCHES)							
	H	I	J	K	L	M	N	P
A, B & E	23 1/4	23	13 3/4	13 1/2	9 7/8	5 1/8	1 3/8	2
C & D	30 1/2	30 1/4	17 1/2	17 1/4	13 1/4	6 3/4	1 3/8	2



GROUND BOX COVER

GROUND BOXES

A. MATERIALS

1. Provide polymer concrete ground boxes measuring 16x30x24 in. (WxLxD) or smaller in accordance with Departmental Material Specification (DMS) 11070 "Ground Boxes" and Item 624 "Ground Boxes."
2. Provide Type A, B, C, D, and E ground boxes as shown in the plans, and as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 624.
3. Ensure ground box cover is correctly labeled in accordance with DMS 11070.
4. Provide larger ground boxes in accordance with Item 624 and as shown in the plans.

B. CONSTRUCTION METHODS

1. Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure aggregate bed is in place and at least 9 inches deep, prior to setting the ground box. Install ground box on top of aggregate.
2. Cast ground box aprons in place. Reinforcing steel may be field bent. Ensure the depth of concrete for the apron extends from finished grade to the top of the aggregate bed under the box. Ground box aprons, including concrete and reinforcing steel, are subsidiary to ground boxes when called for by descriptive code.
3. Keep bolt holes in the box clear of dirt. Bolt covers down when not working in ground boxes.
4. Install all conduits and ells in a neat and workmanlike manner. Uniformly space conduits so grounding bushings and bell end fittings can easily be installed.
5. Temporarily seal all conduits in the ground box until conductors are installed.
6. Permanently seal conduits immediately after the completion of conductor installation and pull tests. Permanently seal the ends of all conduits with duct seal, expandable foam, or other method as approved. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a sealant.
7. When a ground rod is present in a ground box, bond all equipment grounding conductors together and to the ground rod with listed connectors.
8. When a type B or D ground box is stacked to meet volume requirements, it is allowable to cut an appropriately sized hole for conduit entry in the side wall at least 18 inches below grade.
9. If an existing ground box in the contract has a metal cover, bond the cover to the equipment grounding conductor with a 3 ft. long stranded bonding jumper the same size as the grounding conductor. The bonding jumper is subsidiary to various bid items. Verify existing ground boxes with metal covers are shown on the plans, with notes fully describing the work required.
10. If other ground boxes with metal covers are within the project limits but are not part of the contract, the Engineer may direct the Contractor to bond the metal covers, identifying the specific boxes in writing. This work will be paid for separately.
11. Bond metal ground box covers to the grounding conductor with a tank ground type lug.

DATE: 3/21/2023 1:42:40 PM
 FILE: ED(4)-14.dgn

				Traffic Operations Division Standard	
<h2>ELECTRICAL DETAILS GROUND BOXES</h2> <h3>ED(4) - 14</h3>					
FILE:	ed4-14.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2014	CONT:	3510	SECT:	06
REVISIONS:		JOB:	030	HIGHWAY:	SH 99
		DIST:	HOU	COUNTY:	HARRIS
				SHEET NO.:	86

ELECTRICAL SERVICES NOTES

- Provide new materials. Ensure installation and materials comply with the applicable provisions of the National Electrical Code (NEC) and National Electrical Manufacturers Association (NEMA) standards. Ensure material is Underwriters Laboratories (UL) listed. Provide and install electrical service conduits, conductors, disconnects, contactors, circuit breaker panels, and branch circuit breakers as shown on the Electrical Service Data chart in the plans. Faulty fabrication or poor workmanship in material, equipment, or installation is justification for rejection. Where manufacturers provide warranties and guarantees as a customary trade practice, furnish these to the State.
- Provide electrical services in accordance with Electrical Details standard sheets, Departmental Material Specification (DMS) 11080 "Electrical Services," DMS 11081 "Electrical Services-Type A," DMS 11082 "Electrical Services-Type C," DMS 11083 "Electrical Services-Type D," DMS 11084 "Electrical Services-Type T," DMS 11085 "Electrical Services-Pedestal (PS)", and Item 628 "Electrical Services" of the Standard Specifications. Provide electrical service types A, C, and D, as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 628. Provide other service types as detailed on the plans.
- Provide all work, materials, services, and any incidentals needed to install a complete electrical service as specified in the plans.
- Coordinate with the Engineer and the utility provider for metering and compliance with utility requirements. Primary line extensions, connection charges, meter charges, and other charges by the utility company to provide power to the location are paid for in accordance with Item 628. Get approval for the costs associated with these charges prior to engaging the utility company to do the work. Consult with the utility provider to determine costs and requirements, and coordinate the work as approved.
- The enclosure manufacturer will provide Master Lock Type 2 with brass tumblers keyed #2195 for all custom electrical enclosures. Installing Contractor is to provide Master Lock #2195 Type 2 with brass tumblers for "off the shelf" enclosures. Master Lock #2195 keys and locks become property of the State. Unless otherwise approved, do not energize electrical service equipment until locks are installed.
- Enclosures with external disconnects that de-energize all equipment inside the enclosure do not need a dead front trim. Protect incoming line terminations from incidental contact as required by the NEC.
- When galvanized is specified for nuts, screws, bolts or miscellaneous hardware, stainless steel may be used.
- Provide wiring and electrical components rated for 75°C. Provide red, black, and white colored XHHW service entrance conductors of minimum size 6 American Wire Gauge (AWG). Identify size 6 AWG conductors by continuous color jacket. Identify electrical conductors sized 4 AWG and larger by continuous color jacket or by colored tape. Mark at least 6 inches of the conductor's insulation with half laps of colored tape, when identifying conductors. Ensure each service entrance conductor exits through a separately bushed non-metallic opening in the weatherhead. The lengths of the conductors outside the weatherhead are to be 12 inches minimum, 18 inches maximum, or as required by utility.
- All electrical service conduit and conductors attached to the electrical service including the riser or the elbow below ground are subsidiary to the electrical service. For an underground utility feed, all service conduit and conductors after the elbow, including service conduit and conductors for the utility pole riser when furnished by the Contractor, will be paid for separately.
- Provide rigid metal conduit (RMC) for all conduits on service, except for the 1/2 in. PVC conduit containing the electrical service grounding electrode conductor. Size the service entrance conduit as shown in the plans. Ensure conduit for branch circuit entry to enclosure is the same size as that shown on the layout sheets for branch circuit conduit. Extend all rigid metal conduits a minimum of 6 inches underground and then couple to the type and schedule of the conduit shown on the layout for that particular branch circuit. Install a grounding bushing on the RMC where it terminates in the service enclosure.
- Use of liquidtight flexible metal conduit (LFMC) is allowed between the meter and service enclosure when they are mounted 90 to 180 degrees to each other. Size the LFMC the same size as service entrance conduit. LFMC must not exceed 3 feet in length. Strap LFMC within 1 foot of each end. LFMC less than 12 inches in length need not be strapped. Each end of LFMC must have a grounding bushing or be terminated with a grounding fitting. The LFMC must contain a grounded (neutral) conductor. Ensure any bend in LFMC never exceeds 180 degrees. A pull test is required on all installed conductors, with at least six inches of free conductor movement demonstrated to the satisfaction of the Engineer.
- Ensure all mounting hardware and installation details of services conform to utility company specifications.
- For all electrical service enclosures listed under Item 628 on the MPL, the UL 508 enclosure manufacturers will prepare and submit a schematic drawing unique to each service. Before shipment to the job site, place the applicable laminated schematic drawings and the laminated plan sheet showing the electrical service data chart used to build the enclosure in the enclosure's data pocket. The installing contractor will copy and laminate the actual project plan sheets detailing all equipment and branch circuits supplied by that service. The laminated plan sheets are to be placed in the service enclosure's document pocket. Reduce 11 in. x 17 in. plan sheets to 8 1/2 in. x 11 in. before laminating. If the installation differs from the plan sheets, the installing contractor is to redline plan sheets before laminating.
- When providing an "Off The Shelf" Type D or Type T service, provide laminated plan sheets detailing equipment and branch circuits supplied by that service. Reduce 11 in. x 17 in. plan sheets to 8 1/2 in. x 11 in. before laminating. Deliver these drawings before completion of the work to the Engineer, instead of placing in enclosure that has no door pocket.
- Do not install conduit in the back wall of a service enclosure where it would penetrate the equipment mounting panel inside the enclosure. Provide grounding bushings on all metal conduits, and terminate bonding jumpers to grounding bus. Grounding bushings are not required when the end of the metal conduit is fitted with a conduit sealing hub or threaded boss, such as a meter base hub.

SERVICE ASSEMBLY ENCLOSURE

- Provide threaded hub for all conduit entries into the top of enclosure.
- Type galvanized steel (GS) enclosures may be used for Type C panelboards and for Type D and T services that do not use an enclosure mounted photoceII or lighting contactor. Provide GS enclosures in accordance with DMS 11080, 11082, 11083, and 11084.
- Provide aluminum (AL) and stainless steel (SS) enclosures for Types A, C, and D in accordance with DMS 11080, 11081, 11082, 11083, and 11084. Do not paint stainless steel.
- Provide pedestal service (PS) enclosures in accordance with ED(9) and DMS 11080 and 11085. Do not provide GS pedestal services. If GS is shown in the PS descriptive code, provide an AL enclosure.

MAIN DISCONNECT & BRANCH CIRCUIT BREAKERS

- Field drill flange-mounted remote operator handle if needed, to ensure handle is lockable in both the "On" and "Off" positions.
- When the utility company provides a transformer larger than 50 KVA, verify that the available fault current is less than the circuit breaker's ampere interrupting capacity (AIC) rating and provide documentation from the electric utility provider to the Engineer.



PHOTOELECTRIC CONTROL

- Provide photocell as listed on the MPL. Move, adjust, or shield the photocell from stray or ambient night time light to ensure proper operation. Mount photocell facing north when practical. Mount top of pole photocells as shown on Top Mounted Photocell Detail.

* ELECTRICAL SERVICE DATA												
Elec. Service ID	Plan Sheet Number	Electrical Service Description	Service Conduit *xSize	Service Conductors No./Size	Safety Switch Amps	Main Ckt. Bkr. Pole/Amps	Two-Pole Contractor Amps	Panelbd/ Loadcenter Amp Rating	Branch Circuit ID	Branch Ckt. Bkr. Pole/Amps	Branch Circuit Amps	KVA Load
SB 183	289	ELC SRV TY A 240/480 100(SS)AL(E)SF(U)	2"	3/#2	100	2P/100	100	N/A	Lighting NB	2P/40	26	28.1
									Lighting SB	2P/40	25	
									Underpass	1P/20	15	
NB Access	30	ELC SRV TY D 120/240 060(NS)SS(E)TS(O)	1 1/4"	3/#6	N/A	2P/60		100	Sig. Controller	1P/30	23	5.3
							30		Luminaires	2P/20	9	
									CCTV	1P/20	3	
2nd & Main	58	ELC SRV TY T 120/240 000(NS)GS(N)SP(O)	1 1/4"	3/#6	N/A	N/A	N/A	70	Flashing Beacon 1	1P/20	4	1.0
									Flashing Beacon 2	1P/20	4	

* Example only, not for construction. All new electrical services must have electrical service data chart specific to that service as shown in the plans.
 ** Verify service conduit size with utility. Size may change due to utility meter requirements. Ensure conduit size meets the National Electrical Code.

EXPLANATION OF ELECTRICAL SERVICE DESCRIPTIVE CODE



TOP MOUNTED PHOTOCELL

Install conduit strap maximum 3 feet from box. 5 foot maximum spacing between straps supporting conduit.

Texas Department of Transportation Traffic Operations Division Standard


ELECTRICAL DETAILS SERVICE NOTES & DATA

ED(5) - 14

FILE: ed5-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
DIST	COUNTY		SHEET NO.	
HOU	HARRIS		87	

DATE: 3/21/2023 1:42:41 PM
 FILE: ED(5)-14.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**SCHEMATIC TYPE A
THREE WIRE**


Red insulation or color code 6" length of Line 1 or Line 2 conductors' insulation with red tape where conductor exits the weatherhead.

White insulation or color code 6" length of neutral conductors' insulation with white tape where conductor exits the weatherhead.


⑧ Two Photocell viewing windows not shown but required when photocell is listed as enclosure mounted. Windows not required when photocell is listed as pole top mounted.

Do not bond this bus to the enclosure

WIRING LEGEND	
————	Power Wiring
- - - -	Control Wiring
—N—	Neutral Conductor
—G—	Equipment grounding conductor-always required




**SCHEMATIC TYPE C
THREE WIRE**



**SCHEMATIC TYPE D - CUSTOM
120/240 VOLTS - THREE WIRE**

Red insulation or color code 6" length of Line 1 or Line 2 conductors' insulation with red tape where conductor exits the weatherhead.

White insulation or color code 6" length of neutral conductors' insulation with white tape where conductor exits the weatherhead.



**SCHEMATIC TYPE T
120/240 VOLTS - THREE WIRE**
Galvanized steel-"Buy Off The Shelf" only. When required install photocell top of the pole or on luminaire only, no lighting contractor will be installed.

SCHEMATIC LEGEND	
1	Safety Switch (when required)
2	Meter (when required-verify with electric utility provider)
3	Service Assembly Enclosure
4	Main Disconnect Breaker (See Electrical Service Data)
5	Circuit Breaker, 15 Amp (Control Circuit)
6	Auxiliary Enclosure
7	Control Station ("H-O-A" Switch)
8	Photo Electric Control (enclosure-mounted shown)
9	Lighting Contactor
10	Power Distribution Terminal Blocks
11	Neutral Bus
12	Branch Circuit Breaker (See Electrical Service Data)
13	Separate Circuit Breaker Panelboard
14	Load Center
15	Ground Bus

				Traffic Operations Division Standard	
ELECTRICAL DETAILS SERVICE ENCLOSURE AND NOTES					
ED(6) - 14					
FILE:	ed6-14.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2014	CONT:	3510	SECT:	06
REVISIONS		JOB:	030	HIGHWAY:	SH 99
DIST:	HOU	COUNTY:	HARRIS	SHEET NO.:	88


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:43 PM
FILE: ED(10)-14.dgn

TIMBER POLE (TP) SERVICE SUPPORT NOTES

1. Ensure electrical service support is a class 5 treated timber pole as per Item 627 "Treated Timber Poles." Embed timber pole to depth required in Item 627.
2. Conduit and electrical conductors attached to the electrical service pole and underground within 12 in. of service pole are not paid for directly but are subsidiary to the electrical service.
3. Install pole-top mounted photocell (T) on north side of pole, or in service enclosure (E) as required. See Electrical Service Data chart in plan set.
4. Gain pole as required to provide flat surface for each channel. Gain timber pole to 3/8 in. max. depth and 1 7/8 in. max. height. Gain pole in a neat and workmanlike manner.
5. Mount meter and service equipment on stainless steel or galvanized channel (Unistrut, Kindorf, or equal). Provide channel sized 1 in. to 3 3/4 in. maximum depth, and 1 1/2 in. to 1 5/8 in. maximum width. File smooth the cut ends of galvanized channel and paint with zinc rich paint before installing on pole. Secure each channel section to timber pole with two galvanized or SS lag bolts, 1/4 in. minimum diameter by 1 1/2 in. minimum length. Use a galvanized or SS flat washer on each lag bolt. Do not stack channel.
6. When excess length must be trimmed from poles, trim from the top end only.

- ① Class 5 pole, height as required
- ② Service drop from utility company (attached below weatherhead)
- ③ Service conduit (RMC) and service entrance conductors - One Red, One Black, One White (See Electrical Service Data)
- ④ Safety switch (when required)
- ⑤ Meter (when required)
- ⑥ Service enclosure
- ⑦ 6 AWG bare grounding electrode conductor in 1/2 in. PVC to ground rod - extend 1/2 in. PVC 6 in. underground.
- ⑧ 5/8 in. x 8 ft. Copper clad ground rod - drive ground rod to a depth of 2 in. to 4 in. below grade.
- ⑨ RMC same size as branch circuit conduit.
- ⑩ See pole-top mounted photocell detail on ED(5).
- ⑪ When required by the serving utility provide bare 6 AWG copper conductor. Run wire from pole top to butt wrap or copper butt plate. Protect conductor with non-conductive material to a height of 8 ft. above finished grade.
- ⑫ When required by utility, cut top of pole at an angle to enhance rain run off.




SERVICE SUPPORT TYPE TP (O)


GRANITE CONCRETE (GC) & OTHER CONCRETE (OC) NOTES

Ensure electrical service support structures bid as type Granite Concrete (GC) or Other Concrete (OC) meet the following requirements.


1. Provide GC and OC poles that meet the requirements of DMS 11080 "Electrical Services."
2. Provide prestressed concrete poles suitable for direct embedment into the ground without special foundations.
3. Verify poles are marked as required on DMS 11080. Location of marking should be approximately 4' above final grade. Use the two-point pickup locations when handling pole in horizontal position, and one-point pickup location for use in raising the pole to a vertical position. These marks are small but conspicuous.
4. Embed poles 42 in. or 10% of the length plus 2 ft., whichever is greater.
5. Ensure all installation details of services are in accordance with utility company specifications.
6. Install a one point rack or eye bolt bracket 6 inches to 12 inches below the weatherhead as an overhead service drop anchoring point for the electric utility.
7. Furnish and install galvanized or stainless steel channel strut 1 1/2 in. or 1 5/8 in. wide by 1 in. up to 3 3/4 in. deep (Unistrut, Kindorf, B-line or equal). Attach channel strut with stainless steel concrete anchors (max. 1" depth), square U-bolts or back to back channel strut with long bolts, or other secure mounting as approved by the Engineer. Ensure bolts are galvanized in accordance with ASTM A153. Do not stack channel struts.
8. Backfill the holes thoroughly by tamping in 6 in. lifts. After tamping to grade, place additional backfill material in a 6 inch high cone around the pole to allow for settling. Use material equal in composition and density to the surrounding area. Backfilling will not be paid for directly but is subsidiary to various bid items.



CONCRETE SERVICE SUPPORT Overhead (O)



CONCRETE SERVICE SUPPORT Underground (U)



DETAIL A

See Note 7. Before installing channel that has been cut, file sharp edges and paint with zinc-rich paint. Ensure there is no paint splatter on the pole.


		Texas Department of Transportation		Traffic Operations Division Standard	
ELECTRICAL DETAILS SERVICE SUPPORT TYPES GC, OC, & TP					
ED(10)-14					
FILE:	ed10-14.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		3510	06	030	SH 99
		DIST	COUNTY	SHEET NO.	
		HOU	HARRIS	89	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/21/2023 1:42:45 PM
 FILE: HMID(1)-03.dgn

NOTES:


1. Pole, Ring, and Ring Support shall be assembled and erected so that Reference Line is parallel to center line of roadway or as shown on "Lighting Layouts" sheets.
2. Fixture Placement on ring shall provide a min. Clearance of 7" between Fixtures.




LIGHT MOUNTING RING & SUPPORT ASSEMBLY




SECTION B-B




Handhole Located on Reference Line. See Lighting Layout.
 Reference Line (See Light Setting Diagrams)



PLAN





DETAIL "C" INNER RING SPLICE




SECTION C-C (FOR AREALIGHTS)

As required by Trunnion Adapter supplied.




SECTION C-C (FOR TRUNNION MOUNT)

NOTE: Provide S.S. or galv. cable safety lanyard for Light Fixture when Trunnion Mount is used.




SECTION C-C (FOR FLOODLIGHTS)




DETAIL "E"

(CONDUIT ATTACHMENT FOR OBSTRUCTION LIGHTS. TYPICAL (3) PLACES)



SECTION D-D

NOTE: COVER CORD WITH HEAT SHRINK TUBING FROM CABLE GRIP TO WITHIN ONE INCH OF GRIP TO CONNECTOR TRANSITION PRIOR TO INSTALLING CABLE GRIP.



Note: Confirm Connector Size. Use 1" All Thread Nipple & (2) 1" Jam Nuts to Connect Grip to Cord Connector

Texas Department of Transportation
 Traffic Operations Division


HIGH MAST ILLUMINATION DETAILS

HMID(1)-03


© TxDOT January 1986		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
5-86	REVISIONS	CONT	SECT	JOB	HIGHWAY
4-87	10-14-87	3510	06	030	SH 99
5-87	4-96	DIST	COUNTY		SHEET NO.
10-1-87		HOU	HARRIS		90

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/21/2023 1:42:46 PM
 FILE: HMID(2)-03.dgn




PLAN VIEW




DETAIL "G"
 TOP PLATE CONNECTION
 (LESS ELECT. CABLE PULLEY SUPPORT)
 (SEE DETAIL "L")




PLAN VIEW




SECTION "H-H"
 PULLEY MOUNTING FOR
 RING SUPPORT ARMS




DETAIL "L"
 ELECT. CABLE PULLEY SUPPORT
 (RING SUPPORT ARMS NOT SHOWN FOR CLARITY)



DETAIL "F"
 RING SUPPORT ASSEMBLY
 (NEAR SIDE SUPPORT ARM & ELECT. CABLE
 PULLEY COVER NOT SHOWN FOR CLARITY)



SECTION "E - E"



DETAIL "N"

Texas Department of Transportation
 Traffic Operations Division


HIGH MAST
 ILLUMINATION
 DETAILS

HMID(2)-03


© TxDOT January 1986		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
4-86	REVISIONS	CONT	SECT	JOB	HIGHWAY
5-86	4-96	3510	06	030	SH 99
5-87		DIST	COUNTY		SHEET NO.
12-87		HOU	HARRIS		91

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:46 PM
 FILE: HMID(3)-03.dgn




DETAIL "J"




DETAIL "K"
 MOUNTING RING CONNECTION & STABILIZER

* EXTRA 2'-0" of wire cable to be attached to ring with SS Bands as directed by Engineer.




DETAIL "V"
 WINCH MOUNTING PLATE

NOTE: Dimensions may vary-Verify with winch manufacturer.




PLAN


NOTE: Cover to be 14 ga. galv. sht. metal or 0.10" anodized aluminum sheet.



DETAIL "M"
 COVER CAP ASSEMBLY




SAFETY LANYARD DETAIL




SECTION F-F
 ELECTRICAL CABLE PULLEY

(Pulley material to be aluminum alloy, Type 356-T6 or equal)




SECTION G-G
 WIRE ROPE PULLEY


(Pulley material to be plated steel or Stainless Steel)



SECTION L-L
 ELECTRICAL CABLE PULLEY MOUNTING



PLAN



DETAIL "H"
 MOUNTING RING SPLICE PLATE

Texas Department of Transportation
 Traffic Operations Division


HIGH MAST ILLUMINATION DETAILS

HMID (3) - 03





© TxDOT January 1986		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
5-5-86	REVISIONS	CONT	SECT	JOB	HIGHWAY
5-10-86	4-96	3510	06	030	SH 99
10-87		DIST	COUNTY		SHEET NO.
10-88		HOU	HARRIS		92

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:47 PM
 FILE: HMID(4)-03.dgn




50 A 480V. Circuit Breaker, NEMA 4 for total lamp watts exceeding 9000, 30A, 480V. Circuit Breaker, NEMA 4 for 9000 or less total lamp watts. Enclosure shall be stainless steel, 14 ga., weatherproof with full length vertical door hinge, welded hasp, lock and two sets of keys. Hinge pin shall be tack-welded to prevent removal. Lock (Master # 2195) and keys shall be furnished by the contractor and shall be the same type as used for the service enclosures. Enclosure dimensions shall be approx. 20" high x 9" wide x 5" deep. Attach enclosure with (4) 1/4" S.S. Bolts & Nuts w/ 1/4" Spacers. Breakers are to be mounted on a dielectric mounting board or high voltage insulating paper.




DETAIL "Q"
 (CABLE ATTACHING PLATE)


NOTE: 3/8" Cable for this Project shall be 19x7 Rotation Resistant per Sheet 9.




DETAIL "R"
 ENCLOSURE ENTRANCES



DETAIL "S"
 (WINCH DRIVE ACCESS COVER)



POWER DRIVE ASSEMBLY



SECTION K-K
 (DRILL MOTOR MOUNTING PLATE)
 * Make from 6061-T6 Aluminum

Texas Department of Transportation
 Traffic Operations Division





HIGH MAST
 ILLUMINATION
 DETAILS

HMID(4)-03



© TxDOT January 1986		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
4-86	REVISIONS	5-86	12-87	4-96	
12-3-86		3510	06	030	SH 99
12-8-86		DIST	COUNTY		SHEET NO.
		HOU	HARRIS		93

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:49 PM
FILE: HMID(5)-03.dgn



- NOTES:
1. OBSTRUCTION LIGHTS COLOR CODE: FROM SECONDARY SIDE OF TRANSFORMER THROUGH-OUT-CIRCUIT TO SOCKET, WHITE-NEUTRAL, BLACK-LOAD.
 2. POWER SUPPLY CORD TO FLANGED INLET: GREEN-GROUND, WHITE LINE, BLACK LINE. FROM FLANGED INLET (A) TO TERMINAL BLOCKS: GREEN-GROUND, RED LINE, BLUE-LINE. FROM THERE ON ALL 480V. CIRCUIT WIRES TO BE RED AND BLUE TO JUNCTION BOXES.
 3. WIRE SIZE FROM POWER SUPPLY TO TERMINAL BLOCKS SHALL BE #8 AWG-SEE (B).
 4. WIRE SIZE FROM TERMINAL BLOCKS TO JUNCTION BOXES SHALL BE #12 AWG.
 5. MOUNT TERMINAL BLOCKS ON 3/4" EXTERIOR GRADE PLYWOOD.
 6. FOR 2-WIRE, 480V. SERVICE, OMIT FUSE IN GROUNDED CONDUCTOR IN LEADS TO TRANSFORMER.



- NOTES:
1. PLUGS, CONNECTOR BODIES AND FLANGED INLETS AT CORD TO RING CONNECTION SHALL BE "TWIST LOCK" TYPE, 3-PRONG, RATED 50 AMPS AT 600V, AND 20 AMPS FOR 120 V. 50 AMP CONNECTORS SHALL BE 3 WIRE CASE GROUNDED, ARMORED, WITH CORD GRIP, 20 AMP CONNECTOR SHALL BE 3 WIRE GROUNDING WITH CORD GRIP, NEMA TYPE L5-20.
 2. PROVIDE HANDLE ON 1.5KVA TRANSFORMER FOR PORTABILITY. (SEE ONE-LINE SCHEMATIC)
 3. CIRCUIT BREAKERS SHALL BE ITE #E43B030 OR #E43B050, SQUARE "D" #FAL24030 S/N OR #FAL24050 S/N, OR EQUAL.
 4. CONDUIT ENTRIES INTO TERMINAL BOX SHALL BE INTO THE SIDE OF THE BOX.
 5. A MINIMUM OF ONE (1) MAINTENANCE JUMPER CABLE SHALL BE SUPPLIED FOR EACH PROJECT. SUPPLY ONE (1) PORTABLE TRANSFORMER FOR EACH POWER DRIVE UNIT REQUIRED FOR PROJECT.

Texas Department of Transportation
Traffic Operations Division


HIGH MAST ILLUMINATION DETAILS

HMID (5) -03

© TxDOT January 1986		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
6-87	REVISIONS	CONT	SECT	JOB	HIGHWAY
11-87	4-96	3510	06	030	SH 99
10-88		DIST	COUNTY		SHEET NO.
10-93		HOU	HARRIS		94

76E


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



12-LIGHT SETTING


LUMINAIRE LOCATIONS

NOTE: AIRCRAFT OBSTRUCTION LIGHT LOCATIONS NOT SHOWN. THREE ARE REQUIRED LOCATED APPROX. 120° APART. LOCATIONS WILL VARY DEPENDENT ON THE LIGHT SETTING USED.




AREALIGHT MOUNTING ASSEMBLY
(SYMMETRIC AND ASYMMETRIC)

NOTES: IF ASYMMETRIC FIXTURES ARE USED, THE REFRACTORS SHALL BE ORIENTED TO PROPERLY ILLUMINATE THE ADJACENT ROADWAYS. ORIENTATION SHALL BE AS SHOWN IN PLANS.



TERMINAL FOR 3/8" WIRE ROPE
MATERIAL: STAINLESS STEEL, TYPE 303SE OR 304
WITH 115,000 P. S. I. MAX. ULTIMATE TENSILE STRENGTH.



TERMINAL FOR 3/8" WIRE ROPE
MATERIAL: STAINLESS STEEL, TYPE 303SE OR 304
WITH 115,000 P. S. I. MAX. ULTIMATE TENSILE STRENGTH.

GENERAL NOTES:

1. AFTER FINAL AIMING HAS BEEN COMPLETED AND APPROVED BY THE ENGINEER, FIXTURES MUST BE LOCKED IN POSITION. CONTRACTOR MUST SUBMIT PROPOSED LOCKING SCHEME WITH THE FIXTURE SUBMITTAL. (FLOODLIGHTS ONLY).

3/03 Revision

Removed obsolete diagrams and updated drawings.

Texas Department of Transportation
Traffic Operations Division

HIGH MAST ILLUMINATION DETAILS

HMID (6) -03

© TxDOT January 1986		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
10-93	REVISIONS	CONT	SECT	JOB	HIGHWAY
10-95		3510	06	030	SH 99
4-96		DIST		COUNTY	SHEET NO.
3-03		HOU		HARRIS	95

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:50 PM
 FILE: HMID(7)-03.dgn



1. AREA LIGHTING (Bid under Item 614, "High Mast Illumination Assemblies")

- A. Area lighting shall be symmetric or asymmetric, as shown on the descriptive code. The number and wattage of the fixtures on each pole shall be as shown on the lighting layouts. The lighting pattern for symmetric fixtures shall be IES Type V; for asymmetric fixtures, it shall be IES Type II, III, or IV.
- B. All luminaires shall be pre-qualified before installation. A sample of each type of luminaire to be considered for pre-qualification shall be submitted to TxDOT's Traffic Operations Division - Traffic Engineering Section (TRF-TE).

Traffic Operations Division - TE
 Texas Department of Transportation
 125 East 11th Street
 Austin, TX 78701-2483

Sample luminaires are non-returnable. A list of pre-qualified luminaires may be obtained by contacting TRF-TE. In addition, luminaires will be sampled and tested in accordance with Item 614. Luminaires that inconsistently pass testing or that are inconsistent with published photometric information will be removed from the pre-qualified list at the discretion of the Engineer. Once a fixture has been approved, no changes shall be made in any material or manufacturing methods without prior approval of the Department. Unapproved changes will result in rejection of all fixtures.

- C. Symmetric and Asymmetric fixtures shall meet the following requirements unless otherwise approved by the Engineer:

1. Luminaire Construction

- a) The luminaire housing shall be formed, cast or drawn from low copper aluminum and shall be free of cracks and excessive porosity. Formed aluminum shall have a minimum thickness of 0.090, and shall have all seams welded. The minimum thickness of cast parts shall be as approved by the Engineer. Nuts, screws, and washers shall be made of Type 316 stainless steel. The housing shall be marked with minimum 2" letters to indicate the photometric type as being either A, B, C, or S as specified. Marking shall be permanent and shall be by stencil or stick on labels similar to "wattage" label on cobra heads. Wattage label will not be required on high mast fixtures. The fixture housing shall be constructed separate from the fixture reflector.
- b) Fixtures shall be natural aluminum in color or shall be painted gray.
- c) The slipfitter shall securely attach the luminaire to the tenon on the ring assembly with a minimum of 2 bolts and clamp. A positive means of vertical adjustment shall be provided.
- d) For optical assemblies with lenses, reflectors shall be polished aluminum with Alzak or equal coating and shall not be painted. The optic assembly shall be sealed. The lens shall be tempered glass or prismatic glass, either flat or sag. The optic assembly shall be provided with a resilient seamless or sonically welded silicone rubber gasket, and constructed so that a positive seal against weather and other contaminants will be maintained. The latches shall be stainless steel, spring loaded, and hand operated (2 latches minimum, 3 attachment points), and shall provide a positive means of maintaining closure of the luminaire.
- e) For optical assemblies without lenses, optical assembly shall consist of an open ventilated borosilicate glass reflector. The reflecting prisms shall be protected from dirt depreciation by a spun on hermetically sealed aluminum cover. There shall be no glass lens/refractor on this optical assembly.
- f) Asymmetric fixtures shall have field rotatable optics with accurate degree of rotation markings. Reflector shall have "house side" and "street side" markings.
- g) The socket shell shall be nickel plated and shall be rigidly attached to a high grade porcelain mogul base, which shall extend and enclose the metal shell. A locking means shall be incorporated in the shell of the socket to positively resist the removal of the lamp. This locking means shall be a spring loaded center tip. Lamp socket shall be non-adjustable and shall be riveted, welded, or otherwise permanently installed. Lamps shall be held securely in the proper position with a lamp support.
- h) The terminal block shall use nickel plated brass connectors.
- i) Fixture weight including ballast shall not exceed 80 pounds, and effective projected area (EPA) shall not exceed 2.62 square feet.
- j) The Contractor may be responsible for fixture testing costs. See TxDOT's "Manual of Testing Procedures," Chapter 11 - "Traffic Systems and Illumination," TEX-1110-T - "Sampling Lighting Assemblies," at <http://manuals.dot.state.tx.us/dynaweb/>.

2. Photometrics

- a) The Contractor shall submit a computer generated light level array of the area to be lighted by high mast poles. All computer generated arrays shall have 400 watt fixtures derated to 40,000 lumens per lamp.
- b) The Type "A" 400 watt asymmetric fixture shall be IES cutoff. The Department will use the measured photometric data of sampled fixtures to run the following tests on a computer simulation:

- (1) When mounted in the level position, 50 ft. above the midpoint and 20 ft outside of either long side of a rectangular area measuring 340 ft. by 50 ft., the fixture shall pass the following tests:

- (a) The fixture shall provide a measured minimum intensity of 0.15 horizontal foot-candles at any point on the surface of this area.
- (b) The fixture shall provide a measured maximum to minimum light ratio, based on horizontal foot-candles, of less than 25.
- (c) The fixture shall provide an average measured intensity of 0.6 horizontal foot-candles on the surface area.

- (2) When mounted in the level position, 50 ft. above the midpoint and 20 ft outside of either long side of a rectangular area measuring 260 ft. by 30 ft., the fixture shall provide a measured minimum intensity of 0.30 horizontal foot-candles at any point on the surface of this area.

- c) The Type "B" 400 watt asymmetric fixture shall be IES cutoff. The Department will use the measured photometric data of sampled fixtures to run the following tests on a computer simulation:

- (1) When mounted in the level position, 50 ft. above the midpoint and 20 ft outside of either long side of a rectangular area measuring 260 ft. by 65 ft., the fixture shall pass the following tests:

- (a) The fixture shall provide a measured minimum intensity of 0.15 horizontal foot-candles at any point on the surface of this area.
- (b) The fixture shall provide a measured maximum to minimum light ratio, based on horizontal foot-candles, of less than 25.
- (c) The fixture shall provide an average measured intensity of 0.6 horizontal foot-candles on the surface area.

- (2) When mounted in the level position, 50 ft. above the midpoint and 20 ft outside of either long side of a rectangular area measuring 200 ft. by 40 ft., the fixture shall provide a measured minimum intensity of 0.30 horizontal foot-candles at any point on the surface of this area.

- d) The Type "C" 400 watt asymmetric fixture shall be IES cutoff. The Department will use the measured photometric data of sampled fixtures to run the following tests on a computer simulation:

- (1) When mounted in the level position, 50 ft. above the midpoint and 20 ft. outside of either long side of a rectangular area measuring 220 ft. by 80 ft., the fixture shall pass the following tests:

- (a) The fixture shall provide a measured minimum intensity of 0.15 horizontal foot-candles at any point on the surface of this area.
- (b) The fixture shall provide a measured maximum to minimum light ratio, based on horizontal foot-candles, of less than 25.
- (c) The fixture shall provide an average measured intensity of 0.6 horizontal foot-candles on the surface area.

- (2) When mounted in the level position, 50 ft. above the midpoint and 20 ft. outside of either long side of a rectangular area measuring 160 ft. by 50 ft., the fixture shall provide a measured minimum intensity of 0.30 horizontal foot-candles at any point on the surface of this area.

- e) The Type "S" 400 watt Symmetric fixture shall be IES cutoff. The Department will use the measured photometric data of sampled fixtures to run the following tests on a computer simulation:

- (1) When mounted in the level position at 50 foot mounting height, the fixture shall provide the minimum light levels as shown below:

- (a) 0.15 horizontal foot-candles within a 130 foot radius.
- (b) 0.30 horizontal foot-candles within a 100 foot radius.
- (c) 0.50 horizontal foot-candles within a 60 foot radius.

3. Ballasts

- a) All ballasts shall be isolated-winding lag-type magnetic regulators designed to operate 400 watt high pressure sodium lamps rated 480 volts. Ballasts shall be capable of starting lamps at an ambient temperature of -20 degrees F. Ballast wiring shall include a grounding terminal bonded to metal housing. Ballasts shall be fused with a 5 amp time-delay fuse in an insulated fuse holder. Fuse holders shall be internal to the housing. Ballast wiring to the terminal board shall be through a quick-disconnect plug. Windings shall be made from copper wire.
- b) When the circuit voltage indicated on the plans is applied, the ballast input wattage during fluctuations of the test voltage of +10% and -10% shall not exceed 552 watts for a 400 watt HPS lamp.

3/03 Revision



Revised Area Lighting Requirements



HIGH MAST ILLUMINATION DETAILS

HMID(7)-03

© TxDOT January 1986		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-91	10-93	3510	06	030	SH 99
4-96	3-03	DIST COUNTY		SHEET NO.	
		HOU		HARRIS	
				96	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:52 PM
FILE: HMID(8)-03.dgn

- c) During fluctuation of the line voltage of +10% or -10%, the lamp wattage fluctuation shall not exceed a total of 20%. Ballast shall maintain lamp wattage between 280 and 475 watts for a 400 watt HPS lamp.
- d) The power factor of any ballast when tested at the circuit voltage indicated in the plans shall not be less than 90% at any point in life. Ballast factor shall be between .95 and 1.0.
- e) The electronic starting aid shall provide a starting pulse with an amplitude of 2500 volts minimum, 4000 volts maximum. The pulse width shall be a minimum of 0.8 microseconds at 2250 volts. The pulse shall occur when the open-circuit voltage is equal to or greater than 90 percent of peak open-circuit voltage. Pulse repetition rate shall be a minimum of one per cycle and pulse current shall be a minimum of 0.18 amperes. Electronic starting aids shall be replaceable without the use of tools. The starting aid shall discontinue to pulse when the lamp starts. Starter shall sense an inoperative or missing HPS lamp and automatically shut down luminaire to protect ballast after 10 minutes.
- f) Ballasts shall permanently and clearly indicate the following: lamp type, catalog number, voltage rating, connection diagram, and manufacturer. Capacitors in all luminaires shall be non-PCB type.

4. Lamps

- a) All lamps shall be new and of recent manufacture.
- b) Lamps shall be high pressure sodium and shall meet ANSI C78 requirements. Lamps shall be the type that extinguish at the end of usable lamp life and remain extinguished without cycling. 400 watt lamps shall contain less than 4.0 mg of mercury. Lamps shall be lead free and shall pass the Federal Toxic Characteristic Leachate Procedure (TCLP). Lamp shall be Osram-Sylvania LU400/Eco Plus. No alternatives will be approved.
- c) 400 watt high pressure sodium lamps shall have average initial lumens of 50000 and average rated life of 24000 hours.

2. GENERAL

- A. All material shall be in accordance with the applicable sections of the NEC. All conduit and conductors shall be in accordance with the materials and construction methods requirements of Items 618 and 620. Heat shrink tubing for use with cable grips and cable splicing shall meet the requirements of Item 620.
- B. Where stainless steel bands are called for on the HMID sheets, stainless steel hose clamps may be provided. Stainless steel bands and stainless steel hose clamps shall be provided with stainless steel clips or stainless steel screws.
- C. Obstruction Lights
 - 1. When obstruction lights are required by layout sheets, summary sheets or general notes, the entire high mast assembly shall be controlled by an FAA approved photocell mounted inside the service enclosure. Ring mounted luminaires shall be controlled by up to 4 additional ring mounted photocells, with each photocell controlling up to 3 fixtures. Photocells shall meet the following requirements:
 - a) All photocells shall consist of a photoelectric cell, an internal lightning arrester, and a relay or bimetallic switch mounted inside a weather proof enclosure with standard 3-prong twist lock photocell plug and receptacle. The enclosure shall be made of poly-acrylic with clear acrylic window. Enclosure chassis shall be molded thermosetting plastic. The photocell shall have an arrester rated 2.0kV sparkover with 5000 amps follow-through. Relay or switch shall be time delay type with normally closed contacts. Photocell shall be rated a minimum of 1800 VA.
 - b) Service enclosure mounted photocell (FAA photocell) shall turn on at light levels below 35 foot-candles and off at levels above 58 foot-candles, in accordance with FAA requirements. This photocell shall be rated for operation at 240 volts. A permanent placard shall be installed on the inside of the service enclosure door to indicate that an FAA approved photocell is required.
 - c) High mast assembly ring mounted photocells (one foot-candle photocells) shall turn on at light levels below 1.0 (plus or minus 0.5) foot-candle, and shall turn off at 2 foot-candles higher than this level. These photocells shall be rated for operation at 480 volts. Photocells shall be mounted upright on the terminal box or on various junction boxes around the ring as approved by the Engineer. Conduit entries shall not be made into the top of the terminal box or junction boxes. The Contractor shall submit mounting details to the Engineer for approval.
 - 2. When obstruction lights are not required, eliminate the 3 obstruction light fixtures, 3 mounting posts, 480/120 volt transformer, 120 volt wiring, and 3 mounting post support connections shown on detail "E", sheet 1.
- D. The male cord connector on the lower end of the Type W cord running up the pole, the female cord connector for the Type W cord running to the circuit breaker enclosure and the male connector on the maintenance jumper shall meet the following or approved equal specifications:

- 1. Arrow Hart pin and sleeve watertight connectors UL listed, catalog numbers AH330C7W and AH330P6W.
- 2. Bryant watertight pin and sleeve connectors UL listed, catalog numbers 330C6W and 330P6W.

- 3. Hubble pin and sleeve connectors UL listed, catalog numbers HBL330C7W and HBL 330P7W.
- 4. The male connector for use with the Type W maintenance jumper shall be a pin and sleeve connector of one of the above types. The Contractor shall attach a 50 amp twist lock receptacle to the opposite end of the maintenance jumper to match the flange mounted plug on the ring and the portable transformer.
- 5. The Contractor shall make a brochure submittal on the cord connectors.
- E. When shown on the plans, spill light shall be restricted to less than 0.15 horizontal footcandles.
- F. The Contractor shall provide shop drawings for high mast illumination assemblies in accordance with this Item and Item 441. An Engineer licensed in the State of Texas shall seal the shop drawings.

3. TESTING

- A. Fixtures, lamps and ballasts will be sampled and tested in accordance with the Department "Manual of Testing Procedures" except as noted in these specifications.
- B. Ballasts and fixtures will be tested using a reference lamp.
- C. The Department will bear the cost of all testing of equipment that complies with the specification requirements. However, the source of supply of fixtures and ballasts must be approved as required in Article 6.1 of the Standard Specifications. Such approval will be contingent on the supplier agreeing to bear the cost of testing any equipment that fails to comply with the specification requirements listed in this specification.
- D. All other equipment will be tested in accordance with Item 614 of the Standard Specifications and Materials and Test Division Test Standards.
- E. After High Mast Assembly has been completely assembled, the Engineer may require Contractor to fully lower and raise each high mast ring one time to demonstrate proper operation of the lowering mechanism, or may require the ring to be lowered for ring or fixture inspection. If any malfunction occurs, the problem shall be corrected at the Contractor's expense and the lowering test will be repeated.

4. MOUNTING RING AND SUPPORT ASSEMBLY


- A. Ring and support assembly shall be fabricated from steel having a minimum yield strength of 36 KSI.
- B. Cover assemblies, fittings and miscellaneous parts shall be as outlined on the plans.
- C. All hardware shall be hot-dipped galvanized per ASTM A153 or shall be stainless steel, unless noted otherwise on the plans.

5. WINCH

- A. Housing shall be high tensile strength die-cast silicon aluminum. Cable drum shall be fabricated from seamless steel tubing with stamped steel flanges and shall be hot-dipped galvanized. Drum shall have a minimum diameter of 4.5 inches. Drum shall be keyed to drum shaft. Drum and flanges shall be sized so that, when the fixture mounting ring is in the raised position, the cable including one full layer will fill the drum to no more than two-thirds of full capacity. Drum shaft shall be ground from stainless steel and mounted on lubricated bronze bearings with seals. Wormgear shall be made of nickel-bronze and worm shaft shall be high-strength stress-proofed steel, ground and polished and supported by tapered roller bearings.
- B. Gear ratio shall be 36:1 with safe hoisting capacity of not less than 4000 pounds.
- C. Winch shall incorporate adjustable automatic brake to assure positive load suspension. Brake shall be multiple disc with friction plates running in oil bath and one-direction clutch which operates only when load is suspended or lowered. Winch shall not have throw-out clutch.
- D. Any winch that is operated without oil shall be considered damaged and shall be replaced by the contractor at the contractor's expense.

6. WIRE ROPE AND TERMINALS

- A. 5/16 and 3/8 wire rope shall be 19x7 Rotation Resistant IWRC stainless steel. 19x7 rotation resistant wire rope shall meet the construction requirements of Fed. Spec. RR-W-410D, Type IV, class 2, modified for stainless steel with a nominal breaking strength of 11,100 lbs. All wire rope shall be pre-formed and factory lubricated. Wire rope shall meet the requirements of the applicable specification except where modified by this specification. Quality Assurance testing shall be the responsibility of the manufacturer and shall meet recognized wire rope industry standards. No special tensile or torsion testing will be required. Mill Test Reports shall be furnished.
- B. Winch cable shall be of sufficient length to leave a minimum of one full layer of cable on the drum when the fixture mounting ring is in the full down position.
- C. Wire rope terminals shall be stainless steel, solid stud type as shown on Sheet 7. All terminals shall be drilled for cotter pin. Material to be 303 SE or 304 stainless steel with a maximum tensile strength of 115,000 p.s.i. Mill Test Reports shall be furnished.



One foot-candle photocell keeps High Mast fixtures off when FAA photocell energizes circuit at 35 foot-candles. Fixtures come on when sun goes down at 1 foot-candle.

One Foot-candle PhotoCell Schematic

Use on ring when obstruction lights are installed and FAA photocell is installed in electrical service.

3/03 Revision

- ⚠ Revised General requirements; add diagram
- ⚠ Revised Wire Rope and Terminals

Texas Department of Transportation
Traffic Operations Division

HIGH MAST ILLUMINATION DETAILS

HMID (8) -03

© TxDOT January 1986		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
4-89	10-93	CONT	SECT	JOB	HIGHWAY
4-96	3-03	3510	06	030	SH 99
		DIST		COUNTY	SHEET NO.
		HOU		HARRIS	97

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:53 PM
 FILE: HMID(9)-03.dgn

D. All terminals shall be proof-tested by the manufacturer to 40% of rated strength of the wire rope. Each terminal shall be identified by manufacturer's logo permanently incised on terminal. Manufacturer shall furnish certification of tests. Contractor shall also furnish one sample of each size of terminal with 5 ft. of wire rope for load tests by the State. Samples tested must withstand test load not less than 100% of rated breaking strength of wire rope. If sample fails test, all terminals of same size will be rejected.

E. Wire rope shall be delivered from the manufacturer on a reel.

7. SPRINGS

- A. Provide three steel springs as shown on plans.
- B. Springs shall have an uncompressed length of approximately 8 inches and shall compress 3 inches under 700-pound load.
- C. Springs shall contain approximately 19 total coils with ID of 0.875 and OD of 1.375 inches. Ends shall be closed and ground. Springs shall be zinc-plated.
- D. Springs shall be made from 1/4" diameter oil-tempered MB Steel treated for overstress. Springs shall not develop permanent set from 3-inch compression.

8. ELECTRICAL POWER CABLE

- A. Power cable shall be No. 8 AWG three-conductor round Type W, rated 90 degrees C, 600 volt or 2000 volt. Each conductor shall be tinned copper and shall consist of 133 strands. Insulation shall be ethylene propylene rubber. Jacket shall be chlorosulfonated polyethylene (CSPE), with glass fiber or nylon reinforcing mesh between two layers of CSPE. Nominal diameter shall be 0.91". Filler shall be rubber compound or other approved non-hygroscopic compound. Jacket shall be Hypalon Power Flex 90, with no substitutions allowed.

9. POWER DRIVE ASSEMBLY (ONE ONLY THIS CONTRACT UNLESS OTHERWISE SHOWN ELSEWHERE ON THE PLANS)

A. Drive Motor

- 1. Drive motor shall be 1-1/4" heavy-duty reversible portable electric drill modified as shown on plans.
- 2. Shall have a minimum of 6 radial ball bearings, one thrust bearing, and one needle bearing.
- 3. Shall have No. 3 Morse Taper socket.
- 4. Shall be designed for 115 volt 60 Hertz single phase operation 250 RPM at no load.
- 5. Shall be designed for continuous rated duty of 160 RPM and 15 amperes at 115 volts with delivery of 33-pound-feet of torque. Drill motor to be operated only at low speed range. (i.e. 150 to 160 RPM)
- 6. Shall develop 240 pound-feet of torque at stalled rotor condition.

B. Torque Limiter Coupling

- 1. Torque limiter coupling shall consist of standard torque limiter with Type A sprocket center member coupled to a Type B sprocket by an ASA double strand roller chain. Type A sprocket shall be chrome-plated.
- 2. Coupling shall have torque capacity minimum of 15 pound-feet and a maximum of 55 pound-feet.
- 3. Limiter section of coupling shall consist of integral hub and pressure plate, two friction facings, sintered iron bushing, pilot plate, disk spring, lock washer and hex adjustment nut. All major components except spring and friction facings shall be cadmium-plated with dichromate treatment.
- 4. Type A center sprocket shall have ground face (63 micro-inch) and shall be run-in for 4 minutes at approximately 60 RPM at a torque setting 70% to 80% of spring rating. Contractor shall provide written certification that run-in has been accomplished.
- 5. The torque limiter coupling shall, after run-in, be set to a torque limit of 35 pound-feet or as directed by the Engineer. The proper setting of the coupling shall be demonstrated to the Engineer.

C. Universal Joints

- 1. Shall be slip-type with 4-inch barrel. A grease fitting shall be so located in the spider that all caps and needle bearings may be adequately serviced. The assembly shall be disassembled and zinc-plated, then reassembled and properly lubricated.
- 2. Shall have a minimum torque rating of 1270 inch-pounds at 200 RPM.
- 3. Shall have set screw and keyed coupling as shown on plans.



10. CONSTRUCTION METHODS

A. Fabrication

- 1. Fabrication and welding shall be in accordance with Item 441, "Steel Structures".
- 2. All holes supporting pulley shafts shall be drilled (not punched) prior to galvanizing.
- 3. All component parts shall be galvanized where galvanizing is applicable, after fabrication.
- 4. Galvanizing on all parts which have become scratched, chipped or otherwise damaged shall be thoroughly cleaned and the cleaned area painted with two coats of zinc dust-zinc oxide paint conforming to the requirements of repair compounds meeting Federal Specification TT-P-641 b.
- 5. Mounting rings and ring support assemblies shall be fabricated with the use of jigs that have been inspected and approved by Material and Test Division personnel prior to their usage.
- 6. The fabricator shall submit his proposed welding procedures in accordance with Item 441, "Steel Structures".

B. Installing Wire Rope

- 1. Extreme care shall be used to prevent wire rope from kinking, nicking, or from sustaining other damage during installation. Rope shall not be installed by pulling from flat coil, but shall be carefully unrolled its full length or placed on a horizontal axis and unreel according to wire rope industry standards.
- 2. For right lay rope, the rope shall be attached to the drum on the end opposite the winch gear train, and wound on drum so that the free end of the rope comes off the backside of the drum during normal operation of the winch. Rope must be unreel carefully as stated above. Care must be taken to insure that all layers lay full and tight on drum.
- 3. Installation of all wire rope shall be accomplished only under direct supervision of the Engineer or his authorized representative. Contractor shall not remove wire rope from manufacturer's reel until authorized by the Engineer. Installation of wire rope on winch shall be in accordance with the above and accepted industry practice. Installation of the three hoist cables shall be made from the top end of the pole and as directed by the Engineer or his representative.

C. Installing Wire Rope Clips

- 1. Turn back approx. 2' 3" of rope, measured from the top of thimble. Apply seizing to pigtail end of wire rope prior to cutting to length. See detail "K", Sheet 3. Apply first clip approx. 3" from the dead end of the wire rope with U-bolt over dead end and live end in clip saddle. Tighten nuts evenly to 30 pound-feet of torque, or as recommended by manufacturer.
- 2. Install second clip as near loop as possible, take out slack and torque nuts evenly to 30 pound-feet or as recommended by manufacturer.
- 3. After final erection and assembly of the pole and high mast assembly, retighten nuts to required torque.

D. Installing Light Ring and Luminaires

- 1. Prior to mounting luminaires to the light ring, Contractor shall ensure the ring is level. Luminaires shall be mounted level on the light ring. Luminaires shall be oriented as shown on plans.

3/03 Revision



Revised Construction Methods.


Texas Department of Transportation
Traffic Operations Division

HIGH MAST
ILLUMINATION
DETAILS


HMID(9)-03

© TxDOT January 1986		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
10-93	REVISIONS	CONT	SECT	JOB	HIGHWAY
10-95		3510	06	030	SH 99
4-96		DIST		COUNTY	SHEET NO.
3-03		HOU		HARRIS	98


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




ANCHOR BOLT TEMPLATES



RIPRAP ON SLOPES



- ⑤ Match slope of finished ground if slope is less than approx 4 to 1. For steeper slopes, bench to provide work area with approx 2% slope around pole base. Other configurations may be shown elsewhere on the plans.
- ④ If rock is encountered, the Drilled Shaft shall extend a minimum of two diameters into solid rock.



LIGHTNING PROTECTION SYSTEM




TABLE 5	
Shaft Dia (inches)	Min Spiral Length (feet)
48	19
54	21
60	23
66	26


Drilled Shaft Length (See Chart)

Equally spaced Bands at 4'-0" Max spacing or Spiral at 9" pitch

Spiral (see Table S) with Bands or Spiral to within 1 ft of bottom. Spiral not to be welded within Table S length


Vertical bars may be supported on bottom of drilled hole if material is firm enough to do so when concrete is placed

DRILLED SHAFT FOUNDATION DETAIL




ANCHOR BOLT ASSEMBLY

(See Anchor Bolt Table for number of bolts required)



- ② Place ground box cover flush with riprap.
- ⑩ If, due to tolerances in fabrication, the anchor bolt hole to ground sleeve weld is less than approx 1/8", clipped 1/2" thick washers shall be supplied at those



Texas Department of Transportation
Traffic Operations Division

HIGH MAST ILLUMINATION POLE FOUNDATIONS

SHEET 1 OF 2 HMIF (1) - 98


© TxDOT August 1995		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
11-97	REVISIONS	CONT	SECT	JOB	HIGHWAY
5-98	Anchor Bolt Circle Dia	3510	06	030	SH 99
		DIST	COUNTY		SHEET NO.
		HOU	HARRIS		99

DATE: 3/21/2023 1:42:54 PM
FILE: HMIF (1) - 98.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:55 PM
 FILE: HMIF (2) -98.dgn

⑥ Includes normal 3 Ft exposure. Shafts with more than 3 Ft exposure must have additional length.



Do not extrapolate below 5 Blows/Ft. A special design will be required for soil less than 5 Blows/Ft.



Do not extrapolate below 5 Blows/Ft. A special design will be required for soil less than 5 Blows/Ft.

TEXAS CONE PENETROMETER TEST TABLES

NOTE: Use average "N" value over the top third of the embedded shaft. Ignore the top 2' of soil.

ANCHOR BOLT TABLE						
Pole Height (feet)	Bolt Diameter (inches)	Bolt Length (feet)	Bolt Templates		No. of Bolts	Bolt Cir Dia (inches)
			O D (inches)	I D (inches)		
80 MPH DESIGNS						
8 SIDED POLE						
175	2.25	4.83	45.5	36.5	16	41
150	2.25	4.83	42.5	33.5	12	38
125	2.25	4.83	39.5	30.5	8	35
100	2.25	4.83	35.5	26.5	6	31
12 SIDED POLE						
175	2.25	4.83	48.5	39.5	12	44
150	2.25	4.83	45.5	36.5	10	41
125	2.25	4.83	40.5	31.5	8	36
100	2.25	4.83	36.5	27.5	6	32
100 MPH DESIGNS						
8 SIDED POLE						
175	2.25	4.83	50.5	41.5	20	46
150	2.25	4.83	47.5	38.5	16	43
125	2.25	4.83	43.5	34.5	12	39
100	2.25	4.83	38.5	29.5	10	34
12 SIDED POLE						
175	2.25	4.83	50.5	41.5	16	46
150	2.25	4.83	48.5	39.5	12	44
125	2.25	4.83	44.5	35.5	10	40
100	2.25	4.83	40.5	31.5	6	36

MISCELLANEOUS QUANTITIES - ONE HMIF			
Shaft Diameter (in) ⑦	48	54	60
Concrete Riprap (CY)	2.33	2.44	2.56
Reinforcing (Lbs) ⑧	94	99	103
Ground Box (ea)	1	1	1
R O W Marker (ea) ⑨	1	1	1

- ⑦ See elsewhere on plans for length of Drilled Shaft required.
- ⑧ For Contractors information only.
- ⑨ Designated elsewhere on plans if required.

GENERAL NOTES:

- Unless otherwise noted, the welded steel bands may be replaced with spiral as shown on the foundation details.
- Anchor bolts shall be placed in foundation so there are always two bolts on reference line.
- Drilled shaft lengths as determined from the foundation design chart or other acceptable methods are to be as shown elsewhere on the plans.
- ODSR may not be used for HMIF drilled shafts.
- Concrete for drilled shafts shall be Class C.
- Repair welded areas with zinc-rich paint.
- All Anchor Bolts, Nuts and Washers shall be galvanized in accordance with Item 445, "Galvanizing".














HIGH MAST ILLUMINATION POLE FOUNDATIONS

SHEET 2 OF 2 HMIF (2) -98

© TxDOT August 1995		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY	
5-98 - Anchor Bolt Circle Dia	3510	06	030	SH 99	
	DIST	COUNTY		SHEET NO.	
	HOU	HARRIS		100	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:56 PM
 FILE: HMIP(1)-16.dgn



SHEET 1 OF 2

Texas Department of Transportation		Traffic Operations Division Standard	
HIGH MAST ILLUMINATION POLES			
100' - 125' - 150' - 175'			
HMIP(1)-16			
FILE: hmip-16.dgn	DN:	CK:	DW:
© TxDOT August 1995	CON:	SECT:	JOB:
REVISIONS	3510	06	030
5-98	DIST:	COUNTY:	SHEET NO.
8-16	HOU	HARRIS	101

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:42:57 PM
FILE: HMIP(2)-16.dgn

TABLE OF VARIABLE POLE DIMENSIONS												
8 SIDED POLE							12 SIDED POLE					
Ht (ft)	Section	Diameter (Inches)		Thickness (inches)	Length (feet)	Splice (inches)	Diameter (Inches)		Thickness (inches)	Length (feet)	Splice (inches)	
		Bottom	Top				Bottom	Top				
80 MPH DESIGNS	175	A	13.083	7.750	.250	33.33	19	16.792	7.750	.250	51.67	24
		B	17.792	12.205	.375	34.92	25	24.858	15.817	.313	51.67	36
		C	22.250	16.583	.375	35.42	32	32.625	23.583	.313	51.67	48
		D	25.375	20.948	.438	27.67	36	36.250	31.175	.375	29.00	~
		E	28.375	23.895	.500	28.00	41					
		F	31.250	26.703	.500	28.42	~					
150	A	13.083	7.750	.250	33.33	19	16.792	7.750	.250	51.67	24	
	B	17.792	12.205	.375	34.92	25	24.858	15.817	.313	51.67	36	
	C	22.250	16.583	.375	35.42	32	32.625	23.583	.313	51.67	~	
	D	25.375	20.948	.438	27.67	36						
	E	28.375	23.895	.500	28.00	~						
125	A	13.083	7.750	.250	33.33	19	16.792	7.750	.250	51.67	24	
	B	17.792	12.205	.375	34.92	25	24.858	15.817	.313	51.67	36	
	C	22.250	16.583	.375	35.67	32	28.250	23.583	.313	26.67	~	
	D	25.375	20.948	.438	27.67	~						
100	A	13.083	7.750	.250	33.33	19	16.792	7.750	.250	51.67	24	
	B	17.792	12.205	.375	34.67	25	24.625	15.817	.313	50.33	~	
	C	22.250	16.583	.375	35.67	~						
100 MPH DESIGNS	175	A	14.208	7.875	.313	33.33	20	17.433	7.875	.375	51.67	25
		B	19.792	13.142	.375	35.00	28	25.747	16.173	.438	51.75	37
		C	25.250	18.473	.438	35.67	36	33.750	24.176	.438	51.75	49
		D	29.000	23.680	.500	28.00	42	37.375	31.995	.500	29.08	~
		E	32.625	27.210	.563	28.50	47					
		F	36.125	30.631	.563	28.92	~					
150	A	14.208	7.875	.313	33.33	20	17.433	7.875	.375	51.67	25	
	B	19.792	13.142	.375	35.00	28	25.747	16.173	.438	51.75	37	
	C	25.250	18.473	.438	35.67	36	33.750	24.176	.438	51.75	~	
	D	29.00	23.680	.500	28.00	42						
	E	32.625	27.210	.563	28.50	~						
125	A	14.208	7.875	.313	33.33	20	17.433	7.875	.375	51.67	25	
	B	19.792	13.142	.375	35.00	28	25.747	16.173	.438	51.75	37	
	C	25.250	18.473	.438	35.67	36	29.125	24.176	.438	26.75	~	
	D	29.00	23.680	.500	28.00	~						
100	A	14.208	7.875	.313	33.33	20	17.433	7.875	.375	51.67	25	
	B	19.792	13.142	.375	35.00	28	25.500	16.173	.375	50.42	~	
	C	25.250	18.473	.438	35.67	~						

Diameters are measured across the flats.

MATERIALS	
Polygonal Shafts Ground Sleeves	ASTM A709 Grade 50 A572 Grade 50 ① ②
Base Plate and Handhole Frame	ASTM A709 Grade 50 A572 Grade 50 ① A633 Grade C ①
Miscellaneous Steel	ASTM A36 or equal

- ① ASTM A572 and A633 may have higher yield strength but shall not have less elongation than the grade indicated.
- ② The silicon content of all steel shall be controlled to ensure high quality galvanizing and to avoid discoloration.

TABLE OF VARIABLE BASE DIMENSIONS							
Ht (ft)	O.D. (inches)	I.D. (inches)	Bolt Cir (inches)	No. Bolts	S (inches)	T (inches)	U (inches)
80 MPH DESIGNS							
8 SIDED POLE							
175'	47	22	41	16	2.00	3.75	4.50
150'	44	18	38	12	2.00	4.00	3.50
125'	41	16	35	8	2.00	4.50	3.50
100'	37	14	31	6	2.00	5.00	3.50
12 SIDED POLE							
175'	50	24	44	12	1.75	3.50	3.50
150'	47	22	41	10	1.75	3.50	2.50
125'	42	18	36	8	1.75	3.75	2.50
100'	38	13	32	6	1.75	4.00	2.50
100 MPH DESIGNS							
8 SIDED POLE							
175'	52	27	46	20	1.75	3.50	4.50
150'	49	23	43	16	1.75	4.00	3.50
125'	45	21	39	12	1.75	4.50	3.50
100'	40	17	34	10	1.75	4.50	3.50
12 SIDED POLE							
175'	52	27	46	16	1.75	3.25	3.50
150'	50	25	44	12	1.75	3.50	2.50
125'	46	22	40	10	1.75	3.75	2.50
100'	42	19	36	6	1.75	4.00	2.50

NOTE: Base Plate may be round or with 8 or 12 equal segments matching the pole.

GENERAL NOTES:

- Design conforms to AASHTO 1994 Standard Specifications for Structural Supports for Highway Signs, Luminaries, and Traffic Signals and Interim Revisions thereto. The Design Wind Speed is 80 mph or 100 mph.
- The required design height and wind speed shall be as shown elsewhere in the plans.
- Each pole section, top flange plate and base plate shall be permanently marked on the reference line. The required mark locations are shown on the baseplate, top plate, and foundation plan details. These marks shall be used in pole assembly and erection alignment. The reference line and anchor bolt orientation shall be parallel to roadway centerline unless otherwise shown on Lighting Layouts.

SHEET 2 OF 2



**HIGH MAST
ILLUMINATION POLES
100' - 125' - 150' - 175'**

HMIP(2)-16

FILE: hmip-16.dgn	DN:	CK:	DW:	CK:
© TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
5-98	DIST	COUNTY	SHEET NO.	
8-16	HOU	HARRIS	102	


NOTES:

1. BLOCK-OUT SHALL BE LARGE ENOUGH TO ACCOMMODATE THE SERVICE POLE, CONDUITS AND GROUND ROD OR AS DIRECTED BY THE ENGINEER.

2. CONCRETE RIPRAP WILL NOT BE PAID DIRECTLY BUT WILL BE SUBSIDIARY TO ITEM 628.

3. CONCRETE FOR RIPRAP SHALL BE CLASS "B" IN ACCORDANCE WITH THE ITEM 421, "HYDRAULIC CEMENT CONCRETE".


4. FOR ELECTRICAL SERVICE AND CONCRETE SUPPORT DETAILS SEE TXDOT ELECTRICAL DETAIL STANDARDS.



CONCRETE SERVICE SUPPORT WITH RIPRAP MOWING PAD


(OVERHEAD) ELEVATION

4' x 8' x 4" RIPRAP MOWING PAD WITH NO. 3 REBARS @ 18" C-C OR WWF 6x6-W2.9xW2.9



CONCRETE SERVICE SUPPORT WITH RIPRAP MOWING PAD

(UNDERGROUND) ELEVATION



CONCRETE SERVICE SUPPORT WITH RIPRAP MOWING PAD

PLAN

MOWING PAD
SH 146

DATE:		REVISIONS		PROJECT NO.		SHEET	
DN:	STATE DISTRICT	FEDERAL REGION					
CR:	HOU	6	C 3510-6-30				103
DN:	COUNTY		CONTROL	SECTION	JOB	HIGHWAY	
CR:	HARRIS		3510	06	030	SH 99	

SHEET 1 OF 1

SCALE: N. T. S.

ROADWAY ILLUMINATION ASSEMBLY NOTES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:08 PM
FILE: RID(1)-20.dgn

1. Details apply to roadway lighting installations bid or referenced under Item 610, "Roadway Illumination Assemblies." Provide, furnish, and install all other materials not shown on the plans which may be necessary for complete and proper construction. Where manufacturers provide warranties or guarantees as a customary trade practice, furnish to the State such warranties or guarantees.
2. The locations of poles and fixtures may be shifted by the Engineer to accommodate local conditions. Install or remove poles and luminaires located near overhead electrical lines using established industry and utility safety practices and in accordance with laws governing such work. Consult with the appropriate utility company prior to beginning such work.
3. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association, Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection.
4. Provide Roadway Illumination Light Fixtures as per TxDOT Departmental Material Specification (DMS) 11010, Item 610, and as shown on the Material Producers List (MPL) for Roadway Illumination and Electrical Supplies.
5. Fabricate steel roadway illumination poles in accordance with Roadway Illumination Poles (RIP) standards and Item 610. Poles fabricated according to RIP standards do not require shop drawing submittals.
 - a. Alternate designs to RIP standards or the use of aluminum to fabricate poles will require the submission of shop drawings electronically. For instructions on submitting shop drawings electronically see "Guide to Electronic Shop Drawing Submittal" on the TxDOT web site.
 - b. Limitations on use of the RIP standard: The RIP standard details were developed for installations in locations where the 3-second gust basic maximum wind speed is 110 mph, and where the elevation of the base of the pole is less than (i.e. not more than) 25' above the elevation of the surrounding terrain, in accordance with the "AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals," 6th Edition (2013) of the AASHTO Design Specifications. For poles to be installed in regions where the maximum basic wind speed exceeds 110 mph or to be mounted more than 25' above the surrounding terrain, provide poles meeting the following requirements:
 - i. Submittals. Following the electronic shop drawing submittal process (see Guide to Electronic Shop Drawing Submittal on the TxDOT web site), submit to the Engineer for approval fabrication drawings and calculations for the poles, sealed by a Texas licensed professional engineer (P.E.).
 - ii. Luminaire Structural Support Requirements. Provide light poles, arms, and anchor bolt assemblies with a 25 year design life to safely resist dead loads, ice loads and the required basic wind speeds at the location of installation in accordance with the 6th edition (2013) of the AASHTO Design Specifications. For transformer base poles, include transformer base and connecting hardware in calculations and shop drawing submittals. Structurally test all transformer bases to resist the theoretical plastic moment capacity of the pole. Submit certification of the plastic moment load test and FHWA breakaway requirement test of the model of base being furnished with the shop drawings. Show breakaway base model number, manufacturer's name, and logo on shop drawings. Include on manufacturer's shop drawings the ASTM designations for all materials to be used.
6. For both transformer and shoe-base type illumination poles, provide and install double-pole breakaway fuse holders as specified by DMS-11040. Breakaway fuse holders are listed on the MPL for Roadway Illumination and Electrical Supplies under Items 610 & 620. Provide 10 amp time delay fuses for breakaway connectors in light poles, or inside the light fixture for underpass luminaires. In each pole, connect luminaires to the breakaway connector with continuous stranded 12 AWG copper conductors as listed on the MPL. Bond all equipment grounding conductors together and to the ground lug in the transformer base or hand hole.
7. Tighten anchor bolts for shoe base, concrete traffic barrier base, and bridge mount roadway illumination poles, in accordance with Item 449.
8. Install T-Base with following procedure:
 - a. Anchor Bolt Tightening.
 - i. Coat the threads of the anchor bolts with electrically conductive lubricant.
 - ii. Place the T-base over the anchor bolts. Foundation must be level and flat. The maximum permissible gap under any one corner of the t-base is 1/8" before nuts are tightened.
 - iii. Coat the bearing surfaces of the nuts and washers with electrically conductive lubricant. Install (1) 1/2" hold down washer, (1) lock washer, and (1) nut on each anchor bolt. Turn the nuts onto the bolts so that each is hand-tight against the washer.
 - iv. Using a torque wrench, tighten each nut to 150 ft-lb. Uniform contact is required between the foundation and the T-base in the corner regions of the T-base, and all corner gaps must be closed after applying torque. If a gap still exists after torquing to 150 ft-lbs, continue torquing each bolt incrementally until gap is closed or maximum allowable torque of 250 ft. pound is reached, whichever comes first. If 250 ft-lbs is not enough to close the gap the foundation must be leveled. Gaps along the straight sides of the T-bases and the foundation are permissible. Ensure that no high point of contact occurs between the straight sides of the T-base and the foundation.
 - v. Check top of T-base for level. If not level then foundation must be leveled.
 - b. Top Bolt Procedure
 - i. Erect pole over T-base with crane. Coat bolts, nuts, washers, and lock washers with electrically conductive lubricant.


- ii. Install bolts and 1/2" connecting washers from the inside of the T-base, thread up through the pole base. Install flat washers, lock washers and nuts snug tight according to Item 447, "Structural Bolting."
 - iii. Tighten each nut to 150 ft-lb. using a torque wrench.
- c. Level and Plumb
- i. Ensure pole is plumb and mast arm is perpendicular to the roadway according to plans to within 5 degrees.
9. Construct luminaire pole foundations in accordance with Item 416, "Drilled Shaft Foundations," and TxDOT standard sheet RID(2).
 10. Provide and install underpass luminaires in accordance with Item 610, DMS-11010, and TxDOT standard sheet RID(3). Typical luminaire size for underpass luminaires is 150W HPS or 150W EQ LED.
 11. Mount luminaires on arms level as shown by the luminaire level indicator.
 12. Orient luminaires perpendicular to the roadway intended to be lit unless otherwise shown on the plans.

Wiring Diagram Notes:

- ① Use 1/2 in. -13 UNC threaded, copper or tin-plated copper, pole bonding connector, sized appropriately for conductors, bonded to T-base, or use ground lug in handhole as available.
- ② Use pre-qualified two-pole breakaway connectors for all luminaire pole installations. For luminaires fed by a circuit with a neutral conductor, use double pole breakaway connectors with the neutral side unfused and marked white.
- ③ Split Bolt or other connector.


Decorative LED Lighting Notes:

1. LED Drivers in Remote Outdoor enclosures (for drivers that do not include an enclosure as part of a factory assembly):
 - a. Provide NEMA 3R outdoor enclosure or as approved.
 - b. Install enclosure at least 12" above ground or other horizontal surface. Mount vertically or on ceiling, and avoid direct sun where possible.
 - c. Install drivers with at least 2 inches of space from enclosure walls.
 - d. For multiple drivers in an enclosure, provide at least 4 inches side to side and 1 inch end to end from other drivers or electronic equipment
 - e. For drivers mounted on back wall of enclosure, mount enclosure on 1 5/8" strut or other standoff to dissipate heat, or mount driver to side of the enclosure or to the metal cover.
 - f. Provide remote drivers with a maximum of 100 watts
 - g. Provide drivers with documentation of 100,000 hr lifetime at Tcase of 65C or higher.



TYPICAL WIRING DIAGRAM

LUMINAIRES SERVED AT 480V ON 240/480 VOLT SERVICE OR LUMINAIRES SERVED AT 240V FOR 120/240 VOLT SERVICE.




Driver Spacing In Remote Enclosure


				Traffic Safety Division Standard	
<h1>ROADWAY ILLUMINATION DETAILS</h1> <h2>RID(1)-20</h2>					
FILE:	rid1-20.dgn	DN:	CK:	DW:	CK:
© TxDOT	January 2007	CONT	SECT	JOB	HIGHWAY
REVISIONS		3510	06	030	SH 99
7-17		DIST	COUNTY	SHEET NO.	
12-20		HOU	HARRIS	104	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:10 PM
FILE: RID(2)-20.dgn



SECTION A-A
SHOWING SLOPED GRADE



SECTION A-A
SHOWING CONSTANT GRADE

TABLE 1

ANCHOR BOLTS

POLE MOUNTING HEIGHT	BOLT CIRCLE		ANCHOR BOLT SIZE
	Shoe Base	T-Base	
<40 ft.	13 in.	14 in.	1 in. x 30 in.
40-50 ft.	15 in.	17 1/4 in.	1 1/4 in. x 30 in.

TABLE 2

RECOMMENDED FOUNDATION LENGTHS
(See note 1)

MOUNTING HEIGHT	TEXAS CONE PENETROMETER N Blows/ft		
	10	15	40
≤20 ft.	6'	6'	6'
>20 ft. to 30 ft.	8'	6'	6'
>30 ft. to 40 ft.	8'	8'	6'
>40 ft. to 50 ft.	10'	8'	6'

TABLE 3

PAY QUANTITY OF RIPRAP PER FOUNDATION
(Install only when shown on the plans)

Foundation Diameter	RIPRAP DIAMETER	RIPRAP (CONC) (CL B)
30 in.	78 in.	0.35 CY

GENERAL NOTES:

1. "Recommended Foundation Lengths" table is for information purposes only. Foundation lengths shall be as shown on the plans, or as directed by the Engineer. Foundations will be paid for under Item 416, "Drilled Shaft Foundations," unless otherwise shown on the plans.
2. Erect roadway illumination assembly poles plumb and true. Form and level the top 6" of the foundation so the pole will be plumb. Use leveling nuts to plumb shoe base poles. Do not use shims or leveling nuts under transformer bases. Do not grout between baseplate and the foundation.
3. Ensure Class 2A and 2B fit for anchor bolts and nuts. Tap and chase nuts after galvanizing. Anchor bolt body with rolled threads need not be full size.
4. Use appropriate class of concrete as specified in Items 416 and 432. Concrete for riprap may be upgraded to Class C at no extra cost to the Department.
5. Place riprap around the foundation when called for elsewhere in the plans. Riprap will be paid for under Item 432.
6. Locate breakaway roadway illumination assemblies as shown in the placement table, unless otherwise dimensioned on the plans. Protect non-breakaway illumination assemblies from vehicular impact (i.e. 2.5 ft. behind guard rail or mounted on traffic barrier), or located outside the clear zone, except that 2.5 ft. from curb face is minimum desired for light poles on city streets, 45 mph or less. See Roadway Design Manual for further information.
7. Use 4 hold down and 4 connecting washers on transformer base poles as recommended by the manufacturer and supplied with base.
8. Install a minimum of 2 conduits in each foundation. See lighting layout sheets for locations of foundations with more than 2 conduits. Cap unused conduits in foundations on both ends.
9. Conduit location in foundations is critical for breakaway devices. Place conduits 2 in. apart on centerline as shown.
10. Bond anchor bolt to rebar cage with #6 bare stranded copper conductor. Use listed mechanical connectors rated for embedment in concrete. The bonded steel in the foundation creates a concrete encased grounding electrode which replaces the ground rod.
11. Grade earthwork around T-base foundations even with the finished grade as shown in Section A-A to ensure proper function of the breakaway device. Use riprap on T-base foundations that are located on sloped grades, and as shown on the plans for level grades.


TABLE 4

BREAKAWAY POLE PLACEMENT (See note 6)


ROADWAY FUNCTIONAL CLASSIFICATION	** POLE OFFSET (DISTANCE TO FACE OF TRANSFORMER BASE)
Freeway Mainlanes (roadway with full control of access)	15 ft. (minimum and typical) from lane edge
All curbed, 45 mph or less design speed	2.5 ft. minimum (15 ft. desirable) from curb face
All others	10 ft. minimum*(15 ft. desirable) from lane edge

* or as close to ROW line as is practical

** provide 2/5 of the luminaire mounting height behind the pole for "falling area" to prevent encroachment on the other travel lanes. See design guidelines.



FOUNDATION DETAIL



ANCHOR BOLT DETAIL







Texas Department of Transportation
Traffic Safety Division Standard

ROADWAY ILLUMINATION DETAILS
(RDWY ILLUM FOUNDATIONS)
RID(2)-20







FILE: rid2-20.dgn	DN:	CK:	DW:	CK:
© TxDOT January 2007	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
1-11	DIST	COUNTY	SHEET NO.	
7-17	HOU	HARRIS	105	
12-20				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:11 PM
 FILE: RID(3)-20.dgn



- GENERAL NOTES:**
- A. ALL 150 watt HPS and 150 watt equivalent LED Luminaires**
- Luminaire locations, conduit and conductor sizes and routing are typical and diagrammatic only. See project layout sheets for specific details.
 - Conduit will be paid for under Item 618, "Conduit" and conductors will be paid for under Item 620, "Electrical Conductors," unless otherwise shown on the plans.
 - Adjust conduit in saddles to place fixture height and orientation as required. See fixture orientation detail and plans. Where practicable, place luminaires so the bottom of luminaire is above the bottom of the beam, maximum of 3 in. (See detail UNDERPASS LIGHTING ARM TYPE 2)
 - Except as noted, galvanize all structural steel and exposed bolts, nuts, and washers in accordance with Item 445 "Galvanizing".
 - Fabrication of brackets and support arms will not be paid for directly but is subsidiary to Item 610, "Roadway Illumination Assemblies."
 - Install a heavy duty NEMA 3R fused disconnect or breaker enclosure rated at 30 amps and 480 volts to switch underpass luminaires as shown on plans, with at least one per bridge circuit. Install 20 amp time-delay fuses or inverse-time circuit breakers. Mount disconnect or breaker enclosure 10 ft. (min) above grade on columns or bent caps as approved by the Department. Modify disconnect to allow padlocking in the "ON" and "OFF" positions. Padlocks and disconnect switches or circuit breakers for underpass fixtures will not be paid for directly but are subsidiary to the various bid items of the contract.
 - Conduit on columns, caps, and slab is shown surface mounted. For new columns and caps, embed PVC conduit in concrete. Bond and ground metal junction boxes and conduit.



- B. TYPE 1**
- Provide 2 in. rigid metal conduit (2.375" O.D., 0.146" wall) for Type 1 arm shaft.
 - Use 3/8 in. stainless steel bolt or stud non-epoxy type expansion anchors for concrete for Type 1 mounting. Except as noted, provide an allowable 2650 lbs minimum pull-out force (after consideration of adjustment factors for edge distance and bolt spacing) for each anchor. Install each anchor to the embedment depth recommended by the manufacturer.
 - Attach conduit to plate with 4 saddles, four - 3/8 in. diameter bolts, nylon throat lock nuts, and lock washers.
- C. TYPE 2**
- Provide 2 in. rigid metal conduit (2.375" O.D., 0.146" wall) or provide a combination of 2 1/2 in. (2.875" O.D., 0.193" wall) and 2 in. (2.375" O.D., 0.146" wall) rigid metal conduits with a reducing bushing as beam height stipulated for Type 2 arm shaft. Field cutting and threading will be permitted. Paint cut and threaded areas with zinc rich paint after conduit is connected to adjacent fitting.
 - Connecting conduit may be strapped to tapered section of precast beams as shown. Anchor as approved by the Engineer. Maximum anchor depth is 1 in.
 - Indiscriminate drilling into precast concrete beams may result in reduced beam strength. Use drilling location and method as directed by the Engineer. See Location of Underpass Lighting Mounting Bracket detail. The locations shown in the table are such that reinforcing strands will not be damaged.









TABLE 5 LOCATION OF UNDERPASS LIGHT MOUNTING BRACKET	
SPAN LENGTH	MINIMUM DISTANCE
≤ 50'	10'-0"
50' - 70'	15'-0"
70' - 90'	20'-0"
> 90'	25'-0"

IN RD IL AM (U/P) (TY 1)
 If bridge has pre-cast panels under deck, run circuit under deck edge.
UNDERPASS LIGHTING TYPE 1

IN RD IL AM (U/P) (TY 2)
UNDERPASS LIGHTING TYPE 2

LOCATION OF UNDERPASS LIGHT MOUNTING BRACKET

Texas Department of Transportation
 Traffic Safety Division Standard


ROADWAY ILLUMINATION DETAILS (UNDERPASS LIGHT FIXTURES)

RID(3)-20

FILE: rid3-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
2-14	DIST	COUNTY	SHEET NO.	
7-17	HOU	HARRIS	106	
12-20				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:14 PM
FILE: RIP(2)-19.dgn




SHOE BASE POLE

SHOE BASE POLE					
Luminaire Mounting Height (Nominal) (ft)	Base Diameter (in)	Top Diameter (in)	Length (ft)	Pole Thickness (in)	Design Moment (K-ft)
20.00	7.00	4.90	15.00	0.1196	7.1
30.00	7.50	4.00	25.00	0.1196	13.2
31.00-39.00	8.00	4.36-3.24	26.00-34.00	0.1196	20.7
40.00	8.50	3.60	35.00	0.1196	20.7
50.00	10.50	4.20	45.00	0.1196	30.3



TRANSFORMER BASE POLE

TRANSFORMER BASE POLE					
Luminaire Mounting Height (Nominal) (ft)	Base Diameter (in)	Top Diameter (in)	Length (ft)	Pole Thickness (in)	Design Moment (K-ft)
20.00	7.00	5.11	13.50	0.1196	7.1
30.00	7.50	4.21	23.50	0.1196	13.2
31.00-39.00	8.00	4.57-3.45	24.50-32.50	0.1196	20.7
40.00	8.50	3.81	33.50	0.1196	20.7
50.00	10.00	3.91	43.50	0.1196	30.3



CONCRETE TRAFFIC BARRIER BASE POLE

CONCRETE TRAFFIC BARRIER BASE POLE (CSB/SSCB)						
Luminaire Mounting Height (Nominal) (ft)	Base Diameter (in)	Top Diameter (in)	Length (ft)	Pole Thickness (in)	Design Moment (K-ft)	
					About C of Rail	Perp. to Rail
28.00	9.00	5.78	23.00	0.1196	10.3	13.2
38.00	9.00	4.38	33.00	0.1196	16.6	20.8
48.00	10.50	4.48	43.00	0.1345	25.1	30.5

GENERAL NOTES:

- Designs conform to AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 6th Edition (2013) and Interim Revisions thereto. Design 3-Second Gust Wind Speed equals 110 mph with a 1.14 gust factor. A wind importance factor of 0.80 is applied to adjust the wind speed to a 25 year recurrence interval. Design moments listed in tables assume base of pole is 25' above natural ground level.
- Structures are designed to support two 12' luminaire mast arms and luminaires. Mast arms are designed to support a 60-pound luminaire having an effective projected area of 1.6 square feet.
- Fabrication shall be in accordance with the Specifications and with the details, dimensions, and weld procedures shown herein. Do not submit shop drawings for roadway illumination pole assemblies fabricated in accordance with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of these sheets and the Specifications. In the absence of specified fabrication tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.
- For mounting heights between values shown in the tables, use base diameter and thickness values for the larger height.
- Unless otherwise noted, all steel parts shall be galvanized in accordance with Item 445, "Galvanizing."
- Steel poles shall be fabricated in accordance with Item 441, "Steel Structures." Longitudinal seam welds for pole sections shall have 60% minimum penetration. All welding shall be in accordance with AWS D1.1, Structural Welding Code-Steel.
- Two-section poles joined by circumferential welds will not be permitted, unless otherwise shown on the plans. Poles may be fabricated in two sections and field-assembled by the lap-joint method. The two sections shall telescope together with a lap length of not less than 1-1/2 times the shaft diameter at the lap joint.
- Alternate material equal to or better than material specified may be substituted with the approval of the Engineer.
- Lubricate and tighten anchor bolts, when erecting shoe base poles and concrete traffic barrier base poles, in accordance with Item 449, "Anchor Bolts."
- All poles, except Transformer Base Poles, shall have hand holes with reinforcing frames and covers. For ground mounted shoe base poles, hand holes shall be placed 90 degrees to mast arm unless otherwise noted on the plans. For poles mounted on a concrete traffic barrier with one luminaire arm, hand holes shall be located 180 degrees from luminaire arm. For poles mounted on a concrete traffic barrier with two luminaire arms, all hand holes shall be on the same side of the barrier. For poles mounted on a bridge lighting bracket or a retaining wall lighting bracket, hand hole shall be on traffic side of the pole, at a height that will clear the barrier.
- The finished pole shall have a smooth, uniform finish free of pits, blisters, or other defects. Scratched, chipped, and other damaged galvanized areas on poles and mast arms shall be repaired in accordance with Item 445, "Galvanizing."
- Pole length is based on a 5'-6" luminaire arm rise. 4 ft. luminaire arms have a 2'-6" rise. A pole with 4 ft. luminaire arms will have an actual mounting height 3'-0" less than the nominal mounting height. Increasing the pole length to meet the nominal mounting height is allowed, but unnecessary unless otherwise directed by the engineer.
- Erect transformer base poles in accordance with sheet RID(1).

MATERIAL DATA

COMPONENT	ASTM DESIGNATION	MIN. YIELD (ksi)
Pole Shaft (0.14"/ft. Taper)	A572 Gr 50, A595 Gr A, A1011 HSLAS Gr 50 Cl 2 ③, or A1008 HSLAS Gr 50 Cl 2	50
Base Plate and Handhole Frame	A572 Gr.50, or A36	36
T-Base Connecting Bolts	F3125 Gr A325	92
Anchor Bolts	F1554 Gr 55, A193-B7 or A321	55 105
Anchor Bolt Templates	A36	36
Heavy Hex (H.H.) Nuts	A194 Gr 2H, or A563 Gr DH	
Flat Washers	F436	

NOTES:

- 2'-6" rise for 4 ft. luminaire arms.
- Before ovalized as shown on Concrete Traffic Barrier Base Baseplate details, Sheet 4 of 4.
- A1011 SS Gr 50 may be used instead of HSLAS, provided the material meets the elongation requirements for HSLAS.

POLE ASSEMBLY FABRICATION TOLERANCES TABLE

DIMENSION	TOLERANCE
Shaft length	+1"
I.D. of outside piece of slip fitting pieces	+1/8", -1/16"
O.D. of inside piece of slip fitting pieces	+1/32", -1/8"
Shaft diameter: other	+3/16"
Out of "round"	1/4"
Straightness of shaft	±1/4" in 10 ft
Twist in multi-sided shaft	4° in 50 ft
Perpendicular to baseplate	1/8" in 24"
Pole centered on baseplate	±1/4"
Location of Attachments	±1/4"
Bolt hole spacing	±1/16"




**ROADWAY ILLUMINATION POLES
RIP(2)-19**

FILE: rip-19.dgn	DN:	CK:	DW:	CK:
© TxDOT January 2007	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
7-17	DIST	COUNTY	SHEET NO.	
12-19	HOU	HARRIS	108	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/21/2023 1:43:16 PM
FILE: RIP(3)-19.dgn




LUMINAIRE ARM

LUMINAIRE ARM DIMENSIONS		
Nominal Arm Length	Arm Length	Rise
4'-0"	3'-6"	2'-6"
6'-0"	5'-6"	5'-6"
8'-0"	7'-6"	5'-6"
10'-0"	9'-6"	5'-6"
12'-0"	11'-6"	5'-6"


ARM ASSEMBLY FABRICATION TOLERANCES TABLE	
DIMENSION	TOLERANCE
Arm Length	±1"
Arm Rise	±1"
Deviation from flat	1/8" in 12"
Spacing between holes	±1/32"




UPPER SIMPLEX FITTING
(Gusset not shown for clarity)






LOWER SIMPLEX FITTING
(Gusset not shown for clarity)
SECTION B-B




POLE SIMPLEX DETAIL




ARM SIMPLEX DETAIL




SIMPLEX ATTACHMENT DETAIL



POLE TOP



ELEVATION



SECTION A-A

HANDHOLE

NOTES:

- ④ Any of the materials listed for plates may be used where the drawings do not specify a particular ASTM designation.
- ⑤ A576 must be suitable for forging and also meet minimum tensile strength of 65 ksi, minimum yield of 35 ksi, and elongation in 2 inches of 22 percent.
- ⑥ A572, A1008 HSLAS-F, and A1011 HSLAS-F materials may have higher yield strengths but shall not have less elongation than the grade indicated.
- ⑦ Dimensional limits are given to show acceptable variation in design. All of a Fabricator's production of a particular arm length shall have the same dimensions within specified tolerances.
- ⑧ Each pole simplex fitting shall be supplied with 2 bolts and 2 lock washers of the size specified. The bolts and lock washers shall be secured to the pole with the other hardware items called for in the plans.
- ⑨ Proposed deviations in arm simplex dimensions or materials must be submitted to the Department for approval.
- ⑩ A welded handhole frame is permissible. Maximum of two (2) CJP weld splices is allowed.

MATERIALS

Pole or Arm Simplex	ASTM A27 Gr 65-35 or Gr 70-36, A148 Gr 80-50, A576 Gr 1021 ⑤, or A36 (Arm only)
Arm Pipes	ASTM A53 Gr A or B, A500 Gr B, A501, A 1008 HSLAS-F Gr 50 ⑥, or A1011 HSLAS-F Gr 50 ⑥
Arm Struts and Gusset Plates ④	ASTM A36, A572 Gr 50 ⑥, or A588
Misc.	ASTM designations as noted

SHEET 3 OF 4




ROADWAY ILLUMINATION POLES

RIP(3)-19

FILE: rip-19.dgn	DN:	CK:	DW:	CK:
© TxDOT January 2007	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
7-17	DIST	COUNTY	SHEET NO.	
12-19	HOU	HARRIS	109	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:17 PM
FILE: RIP(4)-19.dgn




SHOE BASE BASEPLATE

SHOE BASE BASEPLATE TABLE				
MOUNTING HEIGHTS (nominal)	BOLT CIRCLE	SQUARE	THICK	BOLT HOLE DIAMETER
20' - 39'	13"	13"	1 1/4"	1 1/4"
40'	15"	15"	1 1/4"	1 1/2"
50'	15"	15"	1 1/2"	1 1/2"




CONCRETE TRAFFIC BARRIER BASE BASEPLATE

CONCRETE TRAFFIC BARRIER BASE BASEPLATE TABLE			
MOUNTING HEIGHTS (nominal)	POLE DIA. (12)	DIM. A	DIM. B
28' - 38'	9"	7" ± 1/4"	10" ± 1/4"
48'	10 1/2"	7" ± 1/4"	13" ± 1/4"




TRANSFORMER BASE BASEPLATE

TRANSFORMER BASE BASEPLATE TABLE						
MOUNTING HEIGHTS (nominal)	BOLT CIRCLE	SQUARE	THICK	CONNECTING BOLT DIA.	BOLT HOLE DIAMETER	TRANSFORMER BASE TYPE
20' - 39'	13"	13"	1 1/4"	1"	1 1/4"	A
40'	15"	15"	1 1/4"	1 1/4"	1 1/2"	B
50'	15"	15"	1 1/2"	1 1/4"	1 1/2"	B




SHOE BASE ANCHOR BOLT ASSEMBLY

SHOE BASE ANCHOR BOLT ASSEMBLY TABLE				
MOUNTING HEIGHTS (nominal)	A.B. Dia.	BOLT CIRCLE DIAMETER	CTR. HOLE DIAMETER	BOLT HOLE DIAMETER
20' - 39'	1"	13"	11"	1 1/16"
40' - 50'	1 1/4"	15"	12 1/2"	1 5/16"




CONCRETE TRAFFIC BARRIER BASE ANCHOR BOLT ASSEMBLY

TRANSFORMER BASE ANCHOR BOLT ASSEMBLY TABLE				
MOUNTING HEIGHTS (nominal)	A.B. Dia.	BOLT CIRCLE DIAMETER	CTR. HOLE DIAMETER	BOLT HOLE DIAMETER
20' - 39'	1"	14"	12"	1 1/16"
40' - 50'	1 1/4"	17 1/4"	14 3/4"	1 5/16"




TRANSFORMER BASE ANCHOR BOLT ASSEMBLY


TRANSFORMER BASE TABLE		
TYPE	TOP B.C.	BTM. B.C.
A	13"	14"
B	15"	17 1/4"




DETAIL A




DETAIL B



TOP PLAN



BOTTOM PLAN



ELEVATION

TRANSFORMER BASE DETAILS

GENERAL NOTES:

- For mounting heights between those shown in the table, use the values in the table for the larger mounting height.
- All breakaway bases shall meet the breakaway requirements of the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals, 6th Edition (2013) and Interim Revisions thereto, and shall have been tested by FHWA-approved methods. All bases shall have been structurally tested to resist 150% of the design moment.
- Transformer bases shall be cast from aluminum, ASTM B108 or B26 Alloy 356.0-T6, or other material approved by the Engineer. Four Hex Head (H.H.) bolts with four H.H. nuts, four lock washers, four flat washers, and connecting and hold-down washers as recommended by the manufacturer, galvanized to ASTM A153 Class C or D, or B695 Class 50, shall be provided with each transformer base for connecting the pole. Bolts shall be ASTM A325 or approved equal. Nuts shall be ASTM A563 grade DH galvanized.
- Bases shall be stamped, incised or by other approved permanent means, marked to show fabricator's name or logo, and model number. Such information shall be placed in a readily seen location, inside or outside the base, but shall not be placed on the door.
- Doors for transformer bases shall be made of plastic, fiberglass or other non-metallic material approved by the Engineer and shall be attached with stainless steel screws or bolts. Transformer bases shall be cleaned by grit blast cleaning after heat treatment. Certification by the manufacturer of heat treatment shall be furnished with transformer bases. The certification shall show the metal alloy and temper and that the base meets those requirements, chemical and physical. The certification shall also show the material ASTM specification. Transformer bases shall be cast with a removable tab bar for material testing. Some bars may have been removed by the manufacturer for testing.

NOTES:

- Anchor Bolt Templates do not need to be galvanized.
- Pole diameter before ovalized.

ANCHOR BOLT FABRICATION TOLERANCES TABLE	
DIMENSION	TOLERANCE
Length	± 1/2"
Threaded length	± 1/2"
Galvanized length (if required)	- 1/4"

SHEET 4 OF 4

Texas Department of Transportation
Traffic Safety Division Standard


ROADWAY ILLUMINATION POLES

RIP(4)-19

FILE: rip-19.dgn	DN:	CK:	DW:	CK:
©TxDOT January 2007	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	3510	06	030	SH 99
7-17	DIST:	COUNTY:	SHEET NO.:	
12-19	HOU	HARRIS	110	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:22 PM
FILE: TCP(2-1)-18.dgn




TCP (2-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.





TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK

TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	3510	06	030	SH 99
2-94 4-98	DIST:	COUNTY:	SHEET NO.	
8-95 2-12	HOU	HARRIS	111	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:23 PM
FILE: TCP(2-3)-18.dgn



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓
				TCP(2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Traffic Operations Division Standard

TEXAS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS


TCP (2-3) - 18

FILE: tcp(2-3)-18.dgn	DWG: CK:	DW: CK:	CK:
© TxDOT December 1985	CONT: 3510	SECT: 06	JOB: 030
REVISIONS: 8-95 3-03			HIGHWAY: SH 99
1-97 2-12			DIST: COUNTY
4-98 2-18			SHEET NO.: HARRIS 112


163

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:24 PM
 FILE: TCP (2-4) -18.dgn



TCP (2-4a)
ONE LANE CLOSED



TCP (2-4b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

TCP (2-4b)

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.



**TRAFFIC CONTROL PLAN
 LANE CLOSURES ON MULTILANE
 CONVENTIONAL ROADS**

TCP (2-4) - 18

FILE: tcp2-4-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	HOU	HARRIS	113	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:25 PM
FILE: TCP (2-7) -18.dgn

Traffic Control Devices shown for one direction

New pavement surface should extend to this point. (See note 2)

CW1-6
48" X 24"
(See note 2) ▲

OM-3 Object Markers

Type II-A-A Raised Pavement Markers on 40' C-C.

New pavement surface should extend to this point. (See note 5)

END ROAD WORK
G20-2
48" X 24"

← CW1-6
48" X 24"
(See note 2) ▲

Warning Reflectors may be added on top of channelizing devices for additional conspicuity at night. Warning Reflectors, chevrons or steady-burn warning lights may be added if drums or longitudinal channelizing devices are used. (Both directions)

Barricades may be offset to permit workers and equipment to enter and exit work space.

CW1-4R
48" X 48"

XX MPH
CW13-1P
24" X 24"

ROAD CLOSED
R11-2
48" X 30"

← CW1-6
48" X 24"

↘ CW1-4L
48" X 48"

XX MPH
CW13-1P
24" X 24"
(See note 2) ▲

ROAD WORK XXX FT
CW20-1A, B or C
48" X 48"

ROAD WORK AHEAD
CW20-1D
48" X 48"
(Flags - See note 1)

TCP (2-7a)

ROADWAY DIVERSION

Traffic Control Devices shown for one direction

END ROAD WORK
G20-2
48" X 24"

PASS WITH CARE
R4-2
24" X 30"
If applicable

CTB with safety end treatment, or other barrier system as detailed elsewhere in the plans.

4" Solid White Edgeline

4" Double Yellow Line
1"-2"
Type II-A-A Raised Pavement Markers on 40' C-C.
+4"

NARROW BRIDGE
CW5-2
48" X 48"
(See note 6)

DO NOT PASS
R4-1
24" X 30"

ROAD WORK AHEAD
CW20-1D
48" X 48"
(Flags - See note 1)

TCP (2-7b)

BRIDGE WIDENING

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.

- TCP (2-7a)**
- Raised pavement markers shall be placed 40 feet c-c on centerline throughout project.
 - Roadway diversion design requirements should be based on posted speed limit or prevailing speed.
 - New pavement surface should be extended across existing roadway edge to a point where existing pavement markings left in place during project do not conflict with construction area pavement marking.

- TCP (2-7b)**
- The CW5-2 "Narrow Bridge" sign may be omitted if lane and shoulder widths are maintained.




**TRAFFIC CONTROL PLAN
DIVERSIONS AND
NARROW BRIDGES**

TCP (2-7) - 18

FILE: tcp2-7-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	HOU	HARRIS	114	
4-98 2-18				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:25 PM
FILE: TCP (5-1) -18.dgn



TCP (5-1a)

WORK AREA ON SHOULDER



TCP (5-1b)

WORK AREA ON SHOULDER

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55	L = WS	550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65	L = WS	650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75	L = WS	750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

GENERAL NOTES

1. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
2. 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.




**TRAFFIC CONTROL PLAN
SHOULDER WORK FOR
FREEWAYS / EXPRESSWAYS**

TCP (5-1) - 18


FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
2-18	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	115	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:26 PM
FILE: TCP (6-1) -12.dgn



TCP (6-1a)
TYPICAL FREEWAY ONE LANE CLOSURE



TCP (6-1b)
TYPICAL FREEWAY TWO LANE CLOSURE

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.




**TRAFFIC CONTROL PLAN
FREEWAY LANE CLOSURES**

TCP (6-1) - 12


FILE:	tcp6-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
8-12	REVISIONS	3510	06	030	SH 99				
	DIST	COUNTY		SHEET NO.					
	HOU	HARRIS		116					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:27 PM
 FILE: TCP (6-2) -12.dgn



TCP (6-2a)
ENTRANCE RAMP OPEN
WORK WITHIN 500' OF RAMP



TCP (6-2b)
ENTRANCE RAMP CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainlane can be seen from both roadways.
- See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA NEAR RAMP

TCP (6-2) - 12


FILE:	tcp6-2.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	February 1994	CONT	SECT	JOB	HIGHWAY				
REVISIONS		3510	06	030	SH 99				
1-97	8-98			DIST	COUNTY	SHEET NO.			
4-98	8-12			HOU	HARRIS	117			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:27 PM
FILE: TCP(6-3)-12.dgn



TCP (6-3a)
ENTRANCE RAMP OPEN



TCP (6-3b)
EXIT RAMP CLOSED
TRAFFIC EXITS PRIOR TO CLOSED RAMP

STREET B
EXIT
CLOSED

USE
STREET A
EXIT

EXIT XY
CLOSED

USE
EXIT XX

Or, as an option when exits are numbered

Place 1 mile (approx.) in advance of Street A exit.

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES:
1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
WORK AREA BEYOND RAMP

TCP (6-3) - 12


FILE: tcp6-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	HOU	HARRIS	118	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:28 PM
FILE: TCP (6-4) -12.dgn



TCP (6-4a)
EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP



TCP (6-4b)
EXIT RAMP OPEN

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

**Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
 - See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP (6-4) - 12


FILE: tcp6-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	HOU	HARRIS	119	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:28 PM
 FILE: TCP(6-5)-12.dgn



TCP (6-5a)
EXIT RAMP OPEN



TCP (6-5b)
**EXIT RAMP OPEN
 TWO LANE CLOSURE WITHIN
 1500' PAST EXIT RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC standards for sign details.
- If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN
 WORK AREA BEYOND EXIT RAMP**

TCP (6-5) - 12


FILE: tcp6-5.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	HOU	HARRIS	120	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/21/2023 1:43:29 PM
 FILE: TCP (6-8) -14.dgn



TCP (6-8a)



TCP (6-8b)



TCP (6-8c)

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Place channelizing devices in the gore at 20' spacing.
 - See the Standard Highway Sign Design for Texas (SHSD) for sign details.
 - The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
 - When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP (6-4) for traffic control details.
 - Truck mounted attenuator is required.
 - The PCMS may be omitted if replaced with a "RAMP CLOSED" AHEAD (CW20RP-3D) Sign.
 - Roadway ADT should be greater than 10,000.




WORK IN EXIT GORE FOR ADT GREATER THAN 10,000

TCP (6-8) - 14


FILE: tcp6-8.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	121	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:29 PM
 FILE: TCP (6-9) -14.dgn



TCP (6-9a)



TCP (6-9b)

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Place channelizing devices in the gore at 20' spacing.
 - See the Standard Highway Sign Design for Texas (SHSD) for sign details.
 - The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
 - When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP (6-4) and TCP (6-8) for traffic control details.
 - Truck mounted attenuators are required.
 - The PCMS may be omitted if replaced with a "ROAD WORK 1/2 MILE" (CW20-1E).
 - Roadway ADT should be less than 10,000.



**WORK IN EXIT GORE
 FOR ADT LESS THAN 10,000**

TCP (6-9) - 14


FILE: tcp6-9.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	3510	06	030	SH 99
DIST	COUNTY	SHEET NO.		
HOU	HARRIS	122		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/21/2023 1:43:35 PM
FILE: WV&IZ-14.dgn

APPLICABLE STANDARDS SHEETS

- OVERHEAD SIGN BRIDGE STANDARDS:
 OSB-SE
 OSB-Z#
 OSB-Z#1
 HOSB-Z#
 HOSB-Z1L
 HOSB-Z#1
 OSBT
 OSBC
 OSBC-SC-Z#
 OSBS-SC
 OSB-FD
 OSB-FD-SC
- HIGH MAST ILLUMINATION POLE STANDARDS:
 HMIP-98
 HMIF-98
- WALKWAYS AND BRACKETS STANDARDS:
 SWW
 SB(SWL-1)
- TRAFFIC SIGNAL POLE STANDARDS:
 SP-80
 SP-100
 SMA-80
 SMA-100
 DMA-80
 DMA-100
 MA-C
 MAC (ILSN)
 MAD-D
 TS-FD
 LUM-A
 CFA
 LMA
 TS-C
 MA-DPD
- CANTILEVER OVERHEAD SIGN SUPPORT STANDARDS:
 COSS-SE
 COSS-Z#-10
 HCOSS-Z#-10
 COSS-Z21-10
 COSS-Z#&Z#1-10
 COSSD
 COSSF
 COSS-FD
- Note: # = Wind Zone number 1, 2, 3 or 4



NOTE: Structures north of ice line to be designed for ice.

LEGEND

- ZONE 1 - [diagonal lines] = (100 MPH WIND)
- ZONE 2 - [diagonal lines] = (90 MPH WIND)
- ZONE 3 - [white box] = (80 MPH WIND)
- ZONE 4 - [diagonal lines] = (70 MPH WIND)
- [dashed line with circles] = (ICE LINE)
- [solid black line] = (DISTRICT LINES)

WIND VELOCITY & ICE ZONES FOR APPLICABLE OVERHEAD SIGN SUPPORTS, HIGH MAST POLES, AND TRAFFIC SIGNAL POLES

Based on 50 Year Mean Recurrence Interval of Fastest Mile Wind Velocity at 33 feet height.

THIS SHEET TO BE INCLUDED IN ALL P.S.&E. PACKAGES CONTAINING ONE OR MORE OF THE APPLICABLE STANDARD SHEETS LISTED HEREON

FOR HARRIS CO. ONLY
 Zone line is just North of US 90, around the North, West and South sides of IH 610 and down the West side of SH 288.

FOR JACKSON CO. ONLY
 Zone line is just North of SH 616.

		Traffic Operations Division Standard	
<h2>WIND VELOCITY AND ICE ZONES</h2> <h3>WV & IZ-14</h3>			
FILE:	windice.dgn	DN: TxDOT	CK: TxDOT
© TxDOT	April 1996	CONT SECT	JOB
REVISIONS	3510	06	030
8-14-Added list of applicable standards, restricting use to structures designed for Fastest Mile wind speeds.	DIST	COUNTY	SHEET NO.
	HOU	HARRIS	123