

FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO. <b>STP 2023 (889) VRU</b>	SHEET NO. <b>1</b>	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	ORANGE	
CONTROL	SECTION	JOB	HIGHWAY NO.
0883	02	091	FM408

**INDEX OF SHEETS**

SHEET NO.      DESCRIPTION

SEE SHEET 2 FOR INDEX OF SHEETS

**STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT No. STP 2023 (889) VRU

**FM 408  
ORANGE COUNTY  
CJS: 0883-02-091**

NET LENGTH OF ROADWAY = 16,694.00 FT. = 3.162 MI.  
NET LENGTH OF BRIDGE = 23.00 FT. = 0.004 MI.  
NET LENGTH OF PROJECT = 16,717.00 FT. = 3.166 MI.

LIMITS: FROM FM 105, SOUTH TO FM 1442

FOR THE CONSTRUCTION OF A SAFETY IMPROVEMENT PROJECT

CONSISTING OF WIDENING SHOULDERS AND SAFETY TREAT FIXED OBJECTS

DESIGN SPEED = 30 MPH MAIN LANES  
A.D.T.(2022)= 5,700  
A.D.T.(2052)=9,000

**FINAL PLANS**

LETTING DATE: \_\_\_\_\_

DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_


DATE WORK WAS COMPLETED & ACCEPTED: \_\_\_\_\_

FINAL CONTRACT COST: \$ \_\_\_\_\_

CONTRACTOR : \_\_\_\_\_

**START PROJECT**  
CSJ: 0883-02-091  
STA: 0.00  
REF MRK: 770-0.0335

**END PROJECT**  
CSJ: 0883-02-091  
STA: 167.17  
REF MRK: 772-1.181



EXCEPTIONS: N/A  
EQUATIONS: N/A  
RAILROAD CROSSINGS: N/A

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)-21 THRU BC (12)-21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

© 2023  
BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED.




SUBMITTED FOR LETTING: 3/30/2023  
Designed by: *[Signature]*  
5023 DISTRICT DESIGN ENGINEER

APPROVED FOR LETTING: 3/30/2023  
Designed by: *[Signature]*  
578CD749 DISTRICT ENGINEER

FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DCN\001 T1+1e.dgn  
DATE: 3/16/2023 7:21:13 PM

# INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>	<u>SHEET NO.</u>	<u>DESCRIPTION</u>
	<b><u>GENERAL</u></b>		<b><u>UTILITIES</u></b>
1	TITLE SHEET	63	UTILITY LAYOUTS DETAIL
2	INDEX OF SHEETS	64-77	UTILITY LAYOUTS
3	TYPICAL SECTIONS		
4-8	GENERAL NOTES		
9-10	ESTIMATE & QUANTITY SHEET		
11-13	QUANTITY SUMMARY		
	<b><u>TRAFFIC CONTROL PLAN</u></b>		<b><u>TRAFFIC DETAILS</u></b>
14	SEQUENCE OF WORK	** 78-91	PAVEMENT MARKINGS & SIGN LAYOUTS
** 15-26	BC (1)-21 THRU BC (12)-21	** 92-95	MB-(1)-21 THRU MB-(4)-21
** 27	TCP (1-2)-18	** 96-97	MBP(1)-22 & MBP(2)-22
** 28	TCP (2-2)-18	** 98	D&OM (1)-20
** 29	TCP (3-1)-13	** 99	D&OM (2)-20
** 30	TCP (3-3)-14	** 100	D&OM (3)-20
** 31	WZ (STPM)-23	** 101	D&OM (4)-20
** 32	WZ (UL)-13	** 102	D&OM (5)-20
** 33	WZ (RS)-22	** 103	D&OM (VIA)-20
	<b><u>ROADWAY DETAILS</u></b>	** 104	PM (1)-22
34-47	ROADWAY LAYOUT	** 105	PM (2)-22
48-49	TYPICAL DRIVEWAY & SIDE ROAD DETAILS	** 106	PM (3)-22
50	TREATMENT FOR VARIOUS EDGE CONDITIONS	107-108	SOSS
51	HOT MIX LONGITUDINAL AND PAVEMENT EDGE JOINT DETAILS	109	SMALL SIGN DETAILS
** 52	RS (3)-23	** 110	SMD (GEN)-08
** 53	RS (4)-23	** 111	SMD (SLIP-1)-08
	<b><u>RAIL STANDARDS</u></b>	** 112	SMD (SLIP-2)-08
** 54	BED-14	** 113	SMD (SLIP-3)-08
** 55	GF (31)-19	** 114	TSR (3)-13
** 56	GF (31)MS-19	** 115	TSR (4)-13
** 57	SGT (10S)31-16	** 116	TSR (5)-13
** 58	SGT (11S)31-18		
** 59	SGT (12S)31-18		
	<b><u>DRAINAGE STANDARDS</u></b>		<b><u>ENVIRONMENTAL ISSUES</u></b>
** 60	PSET-SP	117-118	SWP3
** 61	PSET-RP	119	SW3P-B
** 62	SETP-PD	** 120-122	EC (9)-16
		123	EPIC



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A "\*\*\*\*" HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.



NAME \_\_\_\_\_ DATE 03/17/2023

## INDEX OF SHEETS




FHWA TEXAS DIVISION		SHEET NO. 2	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	ORANGE	
CONTROL	SECTION	JOB	HIGHWAY NO.
0883	02	091	FM408

DATE: 3/16/2023 7:39:45 PM  
 FILE: c:\t\dot\pw\_online\tdot5\d\omar\_qui\lenzuni\q\0818274\03\_Typical\_SectionsFM408.dgn



**NOTES:**  
 ① BASE REPAIRS TO BE CONSTRUCTED WILL BE MARKED AND CALLED OUT IN THE FIELD BY THE ENGINEER.



**TYPICAL SECTIONS**  
 N. T. S.

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY		SHEET NO.
BMT	ORANGE		3

County: Orange

Sheet:

Highway: FM 408

Control: 0883-02-091

#### GENERAL NOTES:

Contractor questions on this project are to be addressed to the following individual(s):

Name Bryce A Broussard, P.E.  
Email Bryce.Broussard@txdot.gov

Name Jim B Grissom, P.E.  
Email [Jim.Grissom@txdot.gov](mailto:Jim.Grissom@txdot.gov)

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:  
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

#### Item 000 Utilities

Consider the locations of underground utilities depicted on the plans as approximate and employ responsible care to avoid damaging or accommodate utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities. If utility damage (breaks, leaks, nicks, dents, gouges, etc.) occurs, contact the utility facility owner or operator immediately. In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others.

Overhead utility is present throughout the limits. The contractor is to be familiar with the locations and take care to not damage or disturb the utility while work occurs.

#### Item 4 Scope of Work

Remove all vegetation from pavement edges, intersections and driveways before planing or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

It is the contractor's responsibility to mark the location of all existing striping and place proposed striping back in the same location or as shown in the plans.

General Notes

Sheet A

County: Orange

Sheet: 4

Highway: FM 408

Control: 0883-02-091

#### Item 5 Control of the Work

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

When a precast or cast in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at <https://www.tdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.htmls#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impact to the project schedule and any additional cost resulting from the use of alternates are the sole responsibility of the Contractor.

#### Item 6 Control of Materials

Flammable/combustible materials must be stored at a designated location as approved.

Do not store or mix flammable/combustible materials or equipment under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

#### Item 7 Legal Relations and Responsibilities

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Maintain ingress and egress to the adjacent property at all times. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

General Notes

Sheet B



County: Orange

Sheet:

Highway: FM 408

Control: 0883-02-091

No significant traffic generator events have been identified in the project limits

**Item 8 Prosecution and Progress**

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Submit monthly progress schedules in accordance with 8.5.5.2.3. Failure to supply updated project schedule may result in the Engineer withholding progress (monthly) payments.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Maintain one lane open to traffic during construction, unless otherwise approved.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

Limit lane closures to 1 mile unless otherwise approved.

The Contractor will be expected to schedule this work so that the base placement operations will follow the subgrade work as closely as practical in order to reduce the hazard to the traveling public and prevent undue delay from wet weather.

All edges must be backfilled by the end of the day with a 3:1 or flatter slope. No drop offs will be left overnight.

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

Working days will be charged during the observed curing times, even if no other work is being performed.

**HURRICANE**

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

**Item 112 Subgrade Widening**

Remove excess material daily unless otherwise directed. Fill all excavated areas by the end of the workday.

Provide a clean vertical edge by milling or saw cutting full depth. Consider this work to be subsidiary to the various bid items of the contract.

General Notes

Sheet C

County: Orange

Sheet: 5

Highway: FM 408

Control: 0883-02-091

Subgrade widening will be used to excavate material from earth shoulders and to correct minor deficiencies, such as adding embankment on high sides of horizontal curves. It is not expected that additional embankment will be required.

No buildup of material that impedes drainage from the roadway will be allowed.

**Item 134 Backfilling Pavement Edges**

As base is placed, backfill the pavement edges daily so that no drop-off conditions exist.

Retain ownership of planed materials.

Type A or B material will meet one of the following requirements:

1. Use material from subgrade widening for backfilling pavement edges.
2. Item 132, TY C – Liquid Limit = 40 max, Plasticity Index 8-25, and cohesionless sand will not be permitted.

**Item 164 Seeding for Erosion Control**

Final grading and stabilization (seeding) will be achieved as soon as possible and not scheduled only for the end of the project. Final grading and stabilization should be initiated as the overall work progresses.

Multiple mobilizations of the seeding crews will be expected to comply with the Construction General Permit of the Texas Pollution Elimination Discharge System requirements for re-vegetating disturbed soils.

Eliminate seeding in areas of natural growth determined to have enough cover.

**Item 168 Vegetative Watering**

Equip water trucks with sprinkler systems capable of covering the entire area to be seeded or sodded from the roadway.

Water all newly placed sod or seeded areas the same day of installation. Thereafter, maintain the sod or seeded areas in a well-watered condition and at no time allow the areas to dry to the condition that water stress is evident.

Mechanical watering may not be required during periods of adequate moisture as determined.

Furnish and apply water at a rate of 6.788 Mega gallons per acre per cycle or as directed on the plans.

Comply with stabilization requirements for 70% grass coverage; uniform vegetative coverage is required. During this period, meter and operate water equipment under pumping pressure capable of delivering the required quantities of water necessary. For Permanent seeding each cycle will be

General Notes

Sheet D

executed weekly for 12 weeks, unless directed otherwise. For Temporary seeding each cycle will be executed weekly for 6 weeks, unless directed otherwise.

Provide a logbook showing daily water usage and receipts of water applied, in addition to metering the water equipment.

**Item 247 Flexible Base**

Use Type A, Grade 1-2 flexible base

The minimum plasticity index for this material will be 4.

Do not damage existing or proposed structures during base operations.

**Item 351 Flexible Pavement Structure Repair**

The repair areas will require full depth saw-cut when milling is not used. Consider this work to be subsidiary to the various bid items of the contract.

Provide Flexible Pavement Repair with Item 3076, Type B (PG 64-22) unless approved otherwise. Place Hot Mix with a constant longitudinal surface grade and tie in flush with the existing surface at each end and both sides of the repair area.

Unless otherwise directed, place new ASB with maximum 4” lifts. The minimum patch sizes will be 6’ in width and 10’ in length.

Match the existing cross slope in the repair areas, unless directed otherwise.

All repair locations must be filled the same day they are excavated. No open cut areas will be allowed overnight.

All excavated materials will be removed from the project daily.

Ordinary compaction will be used on this project.

Station limits may be adjusted as directed to meet varying field conditions

For repair locations located in areas to be planed, perform flexible pavement repairs after planing operations.

Seal the perimeter of the repair areas with hot poured rubber in accordance with Item 712. Consider this work to be subsidiary to the various bid items of the contract.

**Item 467 Safety End Treatment**

At driveway locations where the contract requires modifying pipe installations, provide a 6:1 maximum embankment slope from the edge of the driveway to the top of the SET.

Grading required for shaping driveways and side road turnouts, including embankment for pipe culverts at these access locations, will be considered subsidiary to various bid items.

Provide precast Type II SETs. Riprap aprons will not be required.

**Item 502 Barricades, Signs, and Traffic Handling**

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

<u>Square Feet</u>	<u>Minimum Thickness</u>
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Arrange asphalt laydown schedule to meet plan striping requirements.

Use drums as channelizing devices.

Remove all traffic control devices from the right of way when they are not in use. Devices scheduled to be used within 3 days may be placed along the shoulder of the roadway or along the right of way when not in use or stored in other approved areas on the project. Cover any construction signs that are not in effect and are installed in a fashion that will not allow them to be removed from the right of way easily.

Arrange construction operations to prevent the hauling of materials through the completed pavement sections unless otherwise approved.

Provide all flaggers and pilot vehicle drivers with two-way radio communication capability. Provide flaggers at each side road intersection.

**Item 506 Temporary Erosion, Sedimentation, and Environmental Controls**

Should the project be evaluated to have sediment control problems as a result of the Contractor disturbing excessive amounts of soil, the Contractor will be required to immediately re-vegetate (seed and water) those disturbed areas at no cost to the Department.

County: Orange

Sheet:

Highway: FM 408

Control: 0883-02-091

The Contractor will designate a clean out area for concrete trucks. No other area will be allowed without approval of the Engineer.

**Item 540 Metal Beam Guard Fence**

Provide Type II galvanization metal beam rail elements.

Provide round timber posts.

At the close of work each day, protect the ends of metal beam guard fence in an approved manner, so that no blunt ends are exposed to approaching traffic.

**Item 542 Removing Metal Beam Guard Fence**

Accept ownership of removed metal beam guard fence and terminal anchors.

**Item 560 Mailbox Assemblies**

Retain and reuse or, if necessary, replace newspaper holders removed, relocated, or damaged by construction operations for placement on new mailbox assemblies in accordance with mailbox standard sheets. Consider this work subsidiary to this Item.

Repair and, if necessary, replace mailboxes damaged by construction operations. Consider this work subsidiary to this Item.

Coordinate and verify temporary and final mailbox locations with the Department and the US Postmaster.

**Item 585 Ride Quality for Pavement Surfaces**

Use Surface Test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

**Item 644 Small Roadside Sign Assemblies**

Erect Reference Marker signs at the same station as they were located before removal.

Contractor will be responsible to confirm sign, post and connection types and location prior to removing and replacing the existing signs.

State will maintain ownership of sign blanks.

**Item 658 Delineator and Object Marker Assemblies**

Use bolt-on attachment for delineator assemblies attached to guard fence.

Install delineators when directed. This may require installation of delineators on portions of guardrail and bridge rail that is not being repaired in order to maintain consistency with adjacent sections.

MBGF will receive GF2 delineators installed on 100' maximum spacing.

General Notes

Sheet G

County: Orange

Sheet: 7

Highway: FM 408

Control: 0883-02-091

Type C delineators will be installed using Adhesive 795A manufactured by Davidson Traffic Control Products or an equivalent approved in writing.

**Item 666 Retro reflectorized Pavement Markings**

Furnish Type II drop-on glass beads.

**Item 672 Raised Pavement Markers**

Remove all existing traffic buttons before the application of overlay operations. Consider this work to be subsidiary to the various bid items of the contract. Location and details of the existing buttons are available at the Area Engineer 's office.

**Item 3076 Dense-Graded Hot Mix Asphalt**

Prepare Mix Designs and QC testing using the Superpave Gyratory compactor.

**Item 3077 Superpave Mixtures**

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC" Superpave Gyratory Compactor" and TGC "Texas Gyratory Compactor". All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68°F through 72°F).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Provide mix designs. Mix designs must be verified and approved.

General Notes

Sheet H

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

1. A 10 lb. ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
2. Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
3. Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
4. An operational telephone system.
5. Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
6. Water (for testing purposes) from an approved source
7. Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.
8. A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment
9. A laboratory sink measuring 24 x 30 in. and 12 in. deep
10. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facilities, then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.
11. Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17.

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes. RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders are required to meet SAC requirements. Provide mix designs. Mix designs must be verified and approved.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

A material transfer device (MTD) will be required for all surface courses of HMA on this project. An MTD is defined as a self-propelled, wheel-mounted vehicle capable of receiving HMA from the haul trucks separate from the paver. The MTD will have a minimum storage capacity of approximately 25 tons and will be equipped with a pivoting discharge conveyor and a means of completely remixing the HMA before placement. The Engineer may approve an alternative device on a trial basis for the surface course. This device will be capable of receiving HMA separate from the paver and must have remixing capabilities. For all other courses of HMA, other than the surface, an alternative device may be used as long as it is capable of receiving HMA separate from the paver.

#### **Item 3096 Asphalts, Oils, and Emulsions**

Furnish non-tracking tack coat meeting the requirements of SS 3096.

#### **Item 6185 TMA (Mobile and Stationary)**

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMAs for mobile operations.

Consider all shadow vehicles with Truck Mounted Attenuators (TMA) shown in the various TCP's to be required. Submit requests for exceptions to the Engineer for approval.

Therefore, 3 total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.





# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0883-02-091

DISTRICT Beaumont  
HIGHWAY FM 408

COUNTY Orange

CONTROL SECTION JOB				0883-02-091		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00180219			
COUNTY				Orange			
HIGHWAY				FM 408			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	104-6017	REMOVING CONC (DRIVEWAYS)	SY	760.000		760.000	
	112-6001	SUBGRADE WIDENING (ORD COMP)	STA	168.000		168.000	
	134-6004	BACKFILL (TY A OR B)	STA	168.000		168.000	
	164-6025	CELL FBR MLCH SEED(PERM)(URBAN)(SANDY)	SY	18,582.000		18,582.000	
	168-6001	VEGETATIVE WATERING	MG	157.000		157.000	
	247-6001	FL BS (CMP IN PLACE)(TYA GR1-2)(IN VEH)	CY	80.000		80.000	
	351-6004	FLEXIBLE PAVEMENT STRUCTURE REPAIR(8")	SY	2,397.000		2,397.000	
	354-6002	PLAN & TEXT ASPH CONC PAV(0" TO 2")	SY	1,340.000		1,340.000	
	400-6012	CUT AND RESTORE PAV (FLEX BASE)	SY	18.000		18.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	45.000		45.000	
	464-6003	RC PIPE (CL III)(18 IN)	LF	110.000		110.000	
	467-6363	SET (TY II) (18 IN) (RCP) (6: 1) (P)	EA	32.000		32.000	
	467-6374	SET (TY II) (21 IN) (RCP) (6: 1) (P)	EA	17.000		17.000	
	467-6395	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA	3.000		3.000	
	467-6423	SET (TY II) (30 IN) (RCP) (6: 1) (P)	EA	2.000		2.000	
	496-6007	REMOV STR (PIPE)	LF	110.000		110.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	6.000		6.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	1,000.000		1,000.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,000.000		1,000.000	
	530-6010	INTRSCT, DRVWAYS, & TURNOUT (CONC)	SY	760.000		760.000	
	530-6011	INTRSCT, DRVWAYS, & TURNOUT (ACP)	SY	1,937.000		1,937.000	
	533-6001	RUMBLE STRIPS (SHOULDER)	LF	27,838.000		27,838.000	
	533-6002	RUMBLE STRIPS (CENTERLINE)	LF	13,948.000		13,948.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	525.000		525.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	525.000		525.000	
	542-6002	REMOVE TERMINAL ANCHOR SECTION	EA	8.000		8.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	8.000		8.000	
	560-6011	MAILBOX INSTALL-S (TWW-POST) TY 4	EA	49.000		49.000	
	560-6013	MAILBOX INSTALL-M (TWW-POST) TY 4	EA	3.000		3.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	35.000		35.000	
	644-6030	IN SM RD SN SUP&AM TYS80(1)SA(T)	EA	6.000		6.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	41.000		41.000	
	658-6017	INSTL DEL ASSM (D-SW)SZ (BRF)GF1 (BR)	EA	20.000		20.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	2,518.000		2,518.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	85.000		85.000	
	666-6308	RE PM W/RET REQ TY I (W)6"(SLD)(090MIL)	LF	31,868.000		31,868.000	



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0883-02-091

DISTRICT Beaumont

COUNTY Orange

HIGHWAY FM 408

CONTROL SECTION JOB				0883-02-091		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00180219			
COUNTY				Orange			
HIGHWAY				FM 408			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	666-6317	RE PM W/RET REQ TY I (Y)6"(BRK)(090MIL)	LF	2,930.000		2,930.000	
	666-6320	RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL)	LF	15,866.000		15,866.000	
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	340.000		340.000	
	668-6092	PREFAB PAV MRK TY C (W) (36")(YLD TRI)	EA	4.000		4.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	380.000		380.000	
	712-6009	JT / CRCK SEAL (HOT - POURED RUBBER)	LF	33,314.000		33,314.000	
	3076-6001	D-GR HMA TY-B PG64-22	TON	6,542.000		6,542.000	
	3076-6066	TACK COAT	GAL	892.000		892.000	
	3077-6033	SP MIXESSP-CSAC-A PG76-22	TON	6,131.000		6,131.000	
	3077-6075	TACK COAT	GAL	3,344.000		3,344.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY	52.000		52.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	26.000		26.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	



**SUMMARY OF ROADWAY ITEMS**

STATION	STATION	LENGTH	WIDTH	AREA	104	112	134	247	351	354	400
					6017	6001	6004	6001	6004	6002	6012
					REMOVING CONC (DRIVEWAYS)	SUBGRADE WIDENING (ORD COMP)	BACKFILL (TY A OR B)	FL BS (CMP IN PLACE)TYA GRI-2X(IN VEH)	FLEXIBLE PAVEMENT STRUCTURE REPAIR (8")	PLAN & TEXT ASPH CONC PAV (0" TO 2")	CUT AND RESTORE PAV(FLEX BASE)
					SY	STA	STA	CY	SY	SY	SY
0+00	1+35	135	30	4050	-	-	-	-	-	670	-
1+35	6+50	515	30	15450	-	-	-	-	-	-	-
6+50	35+10	2860	30	85800	104	-	-	-	-	-	6
35+10	44+28	918	30	27540	-	-	-	-	-	-	-
44+28	55+00	1072	30	32160	-	-	-	-	-	-	-
55+00	65+52	1052	30	31560	-	-	-	-	-	-	-
65+52	71+80	628	30	18840	-	-	-	-	-	-	-
71+80	82+88	1108	30	33240	-	-	-	-	-	-	-
82+88	108+55	2567	30	77010	-	168	168	80	2397	-	-
108+55	118+28	973	30	29190	-	-	-	-	-	-	-
118+28	119+64	136	30	4080	-	-	-	-	-	-	-
119+64	132+20	1256	30	37680	-	-	-	-	-	-	-
132+20	137+98	578	30	17340	-	-	-	-	-	-	-
137+98	151+90	1392	30	41760	-	-	-	-	-	-	13
151+90	159+80	790	30	23700	-	-	-	-	-	-	-
159+80	167+17	737	30	22110	-	-	-	-	-	670	-
<b>TOTAL</b>					<b>760</b>	<b>168</b>	<b>168</b>	<b>80</b>	<b>2397</b>	<b>1340</b>	<b>18</b>

**CONT. OF ROADWAY ITEMS**

STATION	STATION	LENGTH	WIDTH	AREA	530	530	712	3076	3076	3077	3077
					6010	6011	6009	6001	6066	6033	6075
					INTRSCT, DRVWAYS, TURNOUT (CONC)	INTRSCT, DRVWAYS, & TURNOUT (ACP)	JT/CRACK SEAL (HOT-POURED RUBBER)	D-GR HMA TY-B PG64-22	TACK COAT	SP MIXES SP-C SAC-A PG76-22	TACK COAT
					SY	SY	LF	SY	SY	SY	SY
0+00	1+35	135	30	450	-	-	150	120	120	450	450
1+35	6+50	515	30	1717	-	-	1030	458	458	1717	1717
6+50	35+10	2860	30	9534	104	291	5720	2543	2543	9534	9534
35+10	44+28	918	30	3060	-	84	1836	816	816	3060	3060
44+28	55+00	1072	30	3574	-	185	2144	953	953	3574	3574
55+00	65+52	1052	30	3507	62	232	2104	936	936	3507	3507
65+52	71+80	628	30	2094	97	-	1256	559	559	2094	2094
71+80	82+88	1108	30	3694	-	233	2216	985	985	3694	3694
82+88	108+55	2567	30	8557	-	382	5134	2282	2282	8557	8557
108+55	118+28	973	30	3244	-	84	1946	865	865	3244	3244
118+28	119+64	136	30	454	-	-	272	121	121	454	454
119+64	132+20	1256	30	4187	-	226	2512	1117	1117	4187	4187
132+20	137+98	578	30	1927	-	-	1156	514	514	1927	1927
137+98	151+90	1392	30	4640	152	130	2784	1238	1238	4640	4640
151+90	159+80	790	30	2634	77	77	1580	703	703	2634	2634
159+80	167+17	737	30	2457	268	13	1474	656	656	2457	2457
<b>TOTAL</b>					<b>760</b>	<b>1937</b>	<b>33314</b>	<b>14866</b>	<b>14866</b>	<b>55730</b>	<b>55730</b>

**SUMMARY OF DRAINAGE ITEMS**

STATION	STATION	LENGTH	464	467				496
			6003	6363	6374	6395	6423	6007
			RC PIPE (CL III)(18 IN)	SET (TY II) (18 IN)(RCP) (6:1)(P)	SET (TY II) (21 IN)(RCP) (6:1)(P)	SET (TY II) (24 IN)(RCP) (6:1)(P)	SET (TY II) (30 IN)(RCP) (6:1)(P)	REMOV STR (PIPE)
			LF	EA	EA	EA	EA	LF
0+00	1+35	135	-	-	-	-	-	-
1+35	6+50	515	-	-	-	-	-	-
6+50	35+10	2860	35	12	-	-	-	35
35+10	44+28	918	-	-	-	-	-	-
44+28	55+00	1072	-	-	-	-	-	-
55+00	65+52	1052	-	-	-	-	-	-
65+52	71+80	628	-	-	-	2	-	-
71+80	82+88	1108	-	-	-	-	-	-
82+88	108+55	2567	-	-	-	-	-	-
108+55	118+28	973	-	-	-	-	-	-
118+28	119+64	136	-	-	-	-	-	-
119+64	132+20	1256	-	-	10	-	-	-
132+20	137+98	578	-	-	4	-	2	-
137+98	151+90	1392	75	12	2	-	-	75
151+90	159+80	790	-	8	-	-	-	-
159+80	167+17	737	-	-	1	1	-	-
<b>TOTAL</b>			<b>110</b>	<b>32</b>	<b>17</b>	<b>3</b>	<b>2</b>	<b>110</b>

\*SEE LAYOUT SHEETS FOR SPECIFIC STATIONING

**BASIS OF ESTIMATE**

ITEM	DESCRIPTION	RATE	NO. OF UNITS	UNIT	QUANTITY	UNIT
168-6001	VEGETATIVE WATERING	6.788 MG/AC/CYCLE X 6 CYCLES	3.84	AC	157	MG
3076-6001	D-GR HMA TY-B PG64-22	880 LBS/SY	14866	SY	6542	TON
3076-6066	TACK COAT	0.06 GAL/SY	14866	SY	892	GAL
3077-6033	SP MIXES SP-C SAC-A PG76-22	220 LBS/SY	55730	SY	6131	TON
3077-6075	TACK COAT	0.06 GAL/SY	55730	SY	3344	GAL

**QUANTITY SUMMARY**

©2025 Texas Department of Transportation  
SHEET 1 OF 3

STATE	DISTRICT	COUNTY
TEXAS	BMT	ORANGE
CONTROL	SECTION	JOB
0883	02	091
HIGHWAY NO.		FM408

FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DN\011-013 QuantitySummary.dgn  
DATE: 3/17/2023 3:24:01 PM

**SUMMARY OF TRAFFIC ITEMS**

STATION	STATION	LENGTH	533		666			
			6001	6002	6035	6308	6317	6320
			RUMBLE STRIPS (SHOULDER)	RUMBLE STRIPS (CENTERLINE)	REFL PAV MRK TY 1 (W)8"(SLD) (090MIL)	RE PM W/RET REQ TY 1 (W)6"(SLD) (090MIL)	RE PM W/RET REQ TY 1 (Y)6"(BRK) (090MIL)	RE PM W/RET REQ TY 1 (Y)6"(SLD) (090MIL)
FT	LF	LF	LF	LF	LF	LF		
0+00	1+35	135	-	-	85	380	-	220
1+35	6+50	515	-	-	-	1030	130	515
6+50	35+10	2860	4420	2210	-	5458	715	-
35+10	44+28	918	1836	918	-	1716	220	891
44+28	55+00	1072	2144	1072	-	2030	-	2094
55+00	65+52	1052	2104	1052	-	1939	235	941
65+52	71+80	628	1256	628	-	1256	160	-
71+80	82+88	1108	2216	1108	-	2032	255	1013
82+88	108+55	2567	5134	2567	-	4891	-	4702
108+55	118+28	973	1946	973	-	1866	230	931
118+28	119+64	136	272	136	-	272	-	272
119+64	132+20	1256	2512	1256	-	2333	280	1129
132+20	137+98	578	1156	578	-	1156	-	1156
137+98	151+90	1392	2784	1392	-	2609	320	1265
151+90	159+80	790	58	58	-	1426	200	-
159+80	167+17	737	-	-	-	1474	185	737
<b>TOTAL</b>			<b>27838</b>	<b>13948</b>	<b>85</b>	<b>31868</b>	<b>2930</b>	<b>15866</b>

**SUMMARY OF TRAFFIC ITEMS**

STATION	STATION	LENGTH	668		672
			6076	6092	6009
			PREFAB PAV MRK TY C (W)24"(SLD)	PREFAB PAV MRK TY C (W)36"(Y)LD TRI	REFL PAV MRKR TY II-A-A
FT	LF	EA	EA	EA	
0+00	1+35	135	10	4	4
1+35	6+50	515	-	-	14
6+50	35+10	2860	48	-	36
35+10	44+28	918	24	-	24
44+28	55+00	1072	12	-	28
55+00	65+52	1052	36	-	28
65+52	71+80	628	12	-	8
71+80	82+88	1108	24	-	28
82+88	108+55	2567	24	-	66
108+55	118+28	973	12	-	26
118+28	119+64	136	12	-	4
119+64	132+20	1256	36	-	32
132+20	137+98	578	-	-	16
137+98	151+90	1392	36	-	36
151+90	159+80	790	24	-	10
159+80	167+17	737	30	-	20
<b>TOTAL</b>			<b>340</b>	<b>4</b>	<b>380</b>

**SUMMARY OF WORK ZONE ITEMS**

STATION	STATION	LENGTH	662	6001	6185	
			6111	6002	6002	6005
			WK ZN PAV MRK SHT TERM (TAB) TY Y-2	PORTABLE CHANGEABLE MESSAGE SIGNS	TMA (STATIONARY)	TMA (MOBILE OPS)
FT	EA	EA	DAY	DAY		
0+00	1+35	135	20	-	-	-
1+35	6+50	515	78	-	-	-
6+50	35+10	2860	430	-	-	-
35+10	44+28	918	138	-	-	-
44+28	55+00	1072	160	-	-	-
55+00	65+52	1052	158	-	-	-
65+52	71+80	628	96	-	-	-
71+80	82+88	1108	168	-	-	-
82+88	108+55	2567	386	2	52	26
108+55	118+28	973	146	-	-	-
118+28	119+64	136	20	-	-	-
119+64	132+20	1256	190	-	-	-
132+20	137+98	578	88	-	-	-
137+98	151+90	1392	210	-	-	-
151+90	159+80	790	120	-	-	-
159+80	167+17	737	110	-	-	-
<b>TOTAL</b>			<b>2518</b>	<b>2</b>	<b>52</b>	<b>26</b>

FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DGN\011-013 QuantitySummary.dgn  
DATE: 3/17/2023 3:24:01 PM

**QUANTITY  
SUMMARY**

**SUMMARY OF SIGNING ITEMS**

STATION	STATION	LENGTH	560		6001	644	6076
			6011	6013	IN SM RD SN	IN SM RD SN	REMOVE SM RD SN
			MAILBOX INSTALL-S (TWW-POST) TY 4	MAILBOX INSTALL-M (TWW-POST) TY 4	SUP&AM TY10BWG (1)(SA)(P)	SUP&AM TYS80 (1)(SA)(T)	SUP&AM
		EA	EA	EA	EA	EA	
0+00	1+35	135	-	-	1	1	2
1+35	6+50	515	3	-	3	2	5
6+50	35+10	2860	16	-	2	1	3
35+10	44+28	918	4	-	1	-	1
44+28	55+00	1072	-	-	-	-	-
55+00	65+52	1052	1	1	2	-	2
65+52	71+80	628	5	-	-	-	-
71+80	82+88	1108	4	-	4	-	4
82+88	108+55	2567	5	1	6	-	6
108+55	118+28	973	4	1	4	-	4
118+28	119+64	136	-	-	-	-	-
119+64	132+20	1256	3	-	2	-	2
132+20	137+98	578	2	-	-	-	-
137+98	151+90	1392	-	-	3	-	3
151+90	159+80	790	-	-	3	1	4
159+80	167+17	737	2	-	4	1	5
<b>TOTAL</b>			<b>49</b>	<b>3</b>	<b>35</b>	<b>6</b>	<b>41</b>

**SUMMARY OF MGBF ITEMS**

STATION	STATION	LENGTH	432	540	542		544	658
			6045	6001	6001	6002	6001	6017
			RIPRAP (MOW STRIP) (4 IN)	MTL W-BEAM GD FEN (TIM POST)	REMOVE METAL BEAM GUARD FENCE	REMOVE TERMINAL ANCHOR SECTION	GUARDRAIL END TREATMENT (INSTALL)	INSTL DEL ASSM (D-SW)SZ (BRF)GF1 (BR)
		FT	CY	LF	LF	EA	EA	EA
0+00	1+35	135	-	-	-	-	-	-
1+35	6+50	515	-	-	-	-	-	-
6+50	35+10	2860	-	-	-	-	-	-
35+10	44+28	918	-	-	-	-	-	-
44+28	55+00	1072	-	-	-	-	-	-
55+00	65+52	1052	-	-	-	-	-	-
65+52	71+80	628	-	-	-	-	-	-
71+80	82+88	1108	19	225	225	4	4	10
82+88	108+55	2567	26	300	300	4	4	10
108+55	118+28	973	-	-	-	-	-	-
118+28	119+64	136	-	-	-	-	-	-
119+64	132+20	1256	-	-	-	-	-	-
132+20	137+98	578	-	-	-	-	-	-
137+98	151+90	1392	-	-	-	-	-	-
151+90	159+80	790	-	-	-	-	-	-
159+80	167+17	737	-	-	-	-	-	-
<b>TOTAL</b>			<b>45</b>	<b>525</b>	<b>525</b>	<b>8</b>	<b>8</b>	<b>20</b>


**SUMMARY OF SW3P ITEMS**

STATION	STATION	LENGTH	WIDTH	AREA	164	168	506	
					6025	6001	6041	6043
					CELL FBR MLCH SEED(PERM) (URBAN)(SANDY)	VEGETATIVE WATERING	BIODEG EROSN CONT LOGS (INSTL)(12')	BIODEG EROSN CONT LOGS (REMOVE)
		FT	FT	SY	SY	SY	LF	LF
0+00	1+35	135	30	4050	150	150		
1+35	6+50	515	30	15450	573	573		
6+50	35+10	2860	30	85800	3178	3178		
35+10	44+28	918	30	27540	1020	1020		
44+28	55+00	1072	30	32160	1192	1192		
55+00	65+52	1052	30	31560	1169	1169		
65+52	71+80	628	30	18840	698	698		
71+80	82+88	1108	30	33240	1232	1232		
82+88	108+55	2567	30	77010	2853	2853	1000	1000
108+55	118+28	973	30	29190	1082	1082		
118+28	119+64	136	30	4080	152	152		
119+64	132+20	1256	30	37680	1396	1396		
132+20	137+98	578	30	17340	643	643		
137+98	151+90	1392	30	41760	1547	1547		
151+90	159+80	790	30	23700	878	878		
159+80	167+17	737	30	22110	819	819		
<b>TOTAL</b>				<b>18582</b>	<b>18582</b>	<b>18582</b>	<b>1000</b>	<b>1000</b>

**QUANTITY SUMMARY**

SEQUENCE OF WORK:

1. INSTALL CONSTRUCTION BARRICADES, SIGNS AND SW3P ITEMS. MAINTAN THESE ITEMS THROUGHOUT THE CONSTRUCTION OF THIS PROJECT.
2. CUT AND RESTORE DRIVEWAYS AS SHOWN IN PLANS. COORDINATE WITH PROPERTY OWNERS TO MAINTAIN ACCESS AT ALL TIMES.
  - 2A. INSTALL RCP & SETS AT DRIVEWAYS AS SHOWN IN PLANS.
3. CONSTRUCT FULL DEPTH BASE REPAIRS AS MARKED IN THE FIELD IN ACCORDANCE WITH METHODS SHOWN.
4. CONSTRUCT ROADWAY WIDENING (5A-5C) IN 1 MILE SEGMENTS ON ONE SIDE OF THE ROAD AT A TIME, OR AS APPROVED BY THE ENGINEER. BACKFILL PAVEMENT EDGE DROP-OFFS DAILY DURING THESE OPERATIONS.
  - 4A. MOVE MAILBOXES AND SIGNS TO TEMPORARY LOCATIONS AS NEEDED.
  - 4B. PERFORM SUBGRADE WIDENING.
  - 4C. INSTALL 8" D-GR TY-B HMA ALONG WIDENED SECTIONS IN 4" LIFTS. PLACE HOT Poured RUBBER IN THE LONGITUDINAL CONSTRUCTION JOINT.
5. PLACE SUPERPAVE SURFACE & SHORT TERM PAVEMENT MARKINGS AS NEEDED.
  - 5A. PLACE PERMENANT PAVEMENT MARKINGS WITHIN 14 DAYS OF PLACING SUPERPAVE.
  - 5B. CONSTRUCT DRIVEWAY AND SIDEROAD TAPERS ACCORDING TO DRIVEWAY SUMMARY & DETAILS.
6. INSTALL RUMBLE STRIPS, PERMANENT MARKINGS AND PERMENANT SEEDING. REPLACE SIGNS, MAILBOXES, DELINIATORS AND MBGF AS SHOWN IN PLANS.
7. CLEAN UP SITE AND REMOVE BARRICADES AND SW3P ITEMS UPON FINAL ACCEPTANCE.



*J. Horne*

03/17/2023

**SEQUENCE OF WORK**



NOTES:

- I. REFER TO THE GENERAL NOTES & PLAN SHEETS FOR ADDITIONAL DIRECTION
- II. PREPARE THE BID FOLLOWING THE PROPOSED SEQUENCE OF WORK. THE ENGINEER MAY APPROVE ADJUSTMENTS TO THE SEQUENCE OF WORK AFTER LETTING.

FHWA		SHEET	
TEXAS		NO.	
DIVISION		14	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	ORANGE	
CONTROL	SECTION	JOB	HIGHWAY NO.
0883	02	091	FM408

DATE: 3/16/2023 7:21:58 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\015-026\_BC(1)2-THRU\_BC(1)2-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b> <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
<b>BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS</b>			
<b>BC (1) - 21</b>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
		DW:	TxDOT
		CK:	TxDOT
REVISIONS	CONT	SECT	JOB
4-03 7-13	0883	02	091
9-07 8-14			FM408
5-10 5-21			
	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	15


DATE: 3/16/2023 7:21:58 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DN\Standards\015-026\_BC(1)2.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard into other formats or for incorrect results or damages resulting from its use.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - Contractor will install a regulatory speed limit sign at the end of the work zone.

**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation  
Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-21**


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	16	



# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present.

Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12



## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 21


FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0883	02	091	FM408				
9-07	8-14								
7-13	5-21	DIST	COUNTY	SHEET NO.					
		BMT	ORANGE	17					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any other errors or omissions. This standard is subject to change without notice. DATE: 3/16/2023 7:21:59 PM FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\015-026\_BC(1)2\_Plan\0883-02-091\_FM\_408.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:21:59 PM  
 FILE: T:\BMTDESIGN\Projects\0883-02-091\_FM\_408\GNVStandards\015-026\_BC(1)21\_THRU\_BC(12)-21.dgn


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.




**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0883	02	091	FM408				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	BMT	ORANGE		18				



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:21:59 PM  
 FILE: T:\BMTDESIGN\Projects\0883-02-091\_FM\_408\DN\Standards\015-026\_BC(1)2\_THRU\_BC(1)2-21.dgn




### SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS





### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



### SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



### WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

### GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- \* See BC(4) for definition of "Work Duration."
- \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



## BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	0883	SECT:	02	JOB:	091	HIGHWAY:	FM408
REVISIONS									
9-07	8-14	DIST:	BMT	COUNTY:	ORANGE	SHEET NO.:	19		
7-13	5-21								

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

### Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:22:00 PM  
FILE: T:\BMT\DESIGN\Projects\0883-02-091 FM 408\DGN\Standards\015-026 BC(1)2\_THRU\_BC(1)2-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number



## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC(6)-21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	0883	SECT:	02	JOB:	091	HIGHWAY:	FM408
REVISIONS									
9-07	8-14	DIST:		COUNTY:		SHEET NO.:			
7-13	5-21	BMT:		ORANGE		20			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/16/2023 7:22:00 PM  
 FILE: T:\BMTDESIGN\Projects\0883-02-091\_FM\_408\DNVStandards\015-026\_BC(1)21\_THRU\_BC(12)-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**  
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0883	02	091	FM408				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	ORANGE	21					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 3/16/2023 7:22:01 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNVStandards\015-026\_BC(1)21\_THRU\_BC(12)-21.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**




- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
  - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
  - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
  - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
  - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
  - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
  - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
  - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
  - Drum body shall have a maximum unballasted weight of 11 lbs.
  - Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**


**BC (8) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0883	02	091	FM408				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	BMT	ORANGE	22					
7-13									



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:22:01 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\015-026\_BC(1)21\_THRU\_BC(12)-21.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
2. The OTLD may be used in combination with 42" cones or VPs.
3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
4. To be effective, the chevron should be visible for at least 500 feet.
5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
2. LCDs may be used instead of a line of cones or drums.
3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

1. Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\* \* \* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	23	

DATE: 3/16/2023 7:22:01 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNVStandards\015-026\_BC(11)21\_THRU\_BC(12)-21.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

Each roadway of a divided highway shall be barricaded in the same manner.



**PERSPECTIVE VIEW**


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




**PLAN VIEW**

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



**PERSPECTIVE VIEW**




**PLAN VIEW**

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



**Two-Piece cones**

**One-Piece cones**

**Tubular Marker**

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	24	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	ORANGE	25	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 3/16/2023 7:22:02 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\015-026\_BC(11)21\_THRU\_BC(12)-21.dgn

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A



RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	BMT	ORANGE	26	
11-02 8-14				

DATE: 3/16/2023 7:22:02 PM  
 FILE: I:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\015-026\_BC(12)\_THRU\_BC(12)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:22:03 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DN\Standards\027\_tcp1-2-18.dgn

Warning Sign Sequence in Opposite Direction Same as Below




Channelizing devices separate work space from traveled way



**TCP (1-2a)**  
**ONE LANE TWO-WAY CONTROL WITH YIELD SIGNS**  
 (Less than 2000 ADT - See note 7)

END ROAD WORK  
 G20-2  
 48" X 24"



**TCP (1-2b)**  
**ONE LANE TWO-WAY CONTROL WITH FLAGGERS**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = WS <sup>2</sup> / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30		150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45		450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

**GENERAL NOTES**

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

**TCP (1-2a)**

- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

**TCP (1-2b)**

- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.




**TRAFFIC CONTROL PLAN**  
**ONE-LANE TWO-WAY**  
**TRAFFIC CONTROL**

**TCP (1-2) - 18**


FILE: tcp1-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
4-90 4-98	DIST	COUNTY	SHEET NO.	
2-94 2-12	BMT	ORANGE	27	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:22:03 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\tcp2-2-18.dgn



TCP (2-2a)  
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS  
 ONE LANE TWO-WAY  
 CONTROL WITH YIELD SIGNS  
 (Less than 2000 ADT - See Note 9)



TCP (2-2b)  
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS  
 ONE LANE TWO-WAY  
 CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
  - Flaggers should use two-way radios or other methods of communication to control traffic.
  - Length of work space should be based on the ability of flaggers to communicate.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
  - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
  - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
  - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation  
 Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN  
 ONE-LANE TWO-WAY  
 TRAFFIC CONTROL**

**TCP (2-2) - 18**


FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT	CON: 0883	SECT: 02	JOB: 091	HIGHWAY: FM408
REVISIONS				
8-95 3-03				
1-97 2-12				
4-98 2-18				
	DIST: BMT	COUNTY: ORANGE	SHEET NO.: 28	




DATE: 3/16/2023 7:22:04 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNVStandards\029\_tcp3-1.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**TCP (3-1a)**  
**UNDIVIDED MULTILANE ROADWAY**




**TCP (3-1b)**  
**TWO-WAY ROADWAY WITH PAVED SHOULDERS**



**TCP (3-1c)**  
**TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS**



**TRAIL/SHADOW VEHICLE A**  
with RIGHT Directional display Flashing Arrow Board




**TRAIL/SHADOW VEHICLE B**  
with Flashing Arrow Board in CAUTION display

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.











**STRIPING FOR TMA**

Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS**  
**UNDIVIDED HIGHWAYS**  
  
**TCP(3-1)-13**

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	ORANGE	29	
1-97				

DATE: 3/16/2023 7:22:05 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNV\Standards\030\_tcp3-3.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

**GENERAL NOTES**

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation

Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**

**MOBILE OPERATIONS**

**RAISED PAVEMENT**

**MARKER INSTALLATION/REMOVAL**


**TCP (3-3) - 14**

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	ORANGE	30	
1-97 7-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/17/2023 3:24:04 PM  
 FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DGN\Standards\031 wz(stpm)-23.dgn

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.

- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)







## WORK ZONE SHORT TERM PAVEMENT MARKINGS

### WZ(STPM)-23

FILE: wzstpm-23.dgn	DWG:	CK:	DW:	CK:
© TxDOT February 2023	CONT: 0883	SECT: 02	JOB: 091	HIGHWAY: FM408
4-92 7-13 1-97 2-23 3-03	REVISIONS:	DIST: BMT	COUNTY: ORANGE	SHEET NO.: 31

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:22:05 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\032\_wz11-13.dgn



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

**GENERAL NOTES**

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

TABLE 1		
Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

**TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.**

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"



**SIGNING FOR UNEVEN LANES**


**WZ (UL) - 13**

FILE: wz11-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT	APR 1992	CONT	SECT	JOB
REVISIONS	0883	02	091	FM408
8-95	2-98	7-13	DIST	COUNTY
1-97	3-03		BMT	ORANGE
				SHEET NO.
				32


DATE: 3/16/2023 7:22:06 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNVStandards\033\_wzrs22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



**RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION**



**RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY**

**GENERAL NOTES**

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT)  
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.  
 \* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation  
 Traffic Safety Division Standard



## TEMPORARY RUMBLE STRIPS

### WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	BMT	ORANGE	33	

CK: DW: CK: DW: CK: DW:

- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - 
  -



STATE OF TEXAS  
 JAMES D. HORNE  
 141323  
 REGISTERED PROFESSIONAL ENGINEER  
 John  
 03/17/2023

N.T.S

**Texas Department of Transportation**

**FM408  
 ROADWAY LAYOUT**


SHEET 1 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	34	





CK: DW: CK: DW: CK: DW:

- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - DRIVEWAY TAPER AREA (ACP/CONC)
  - ROADWAY WIDENING



PI 12+45.47  
 Δ 04°37'34.7" (RT)  
 D 02°02'46.6"  
 T 113.10'  
 L 226.08'  
 R 2800.00'  
 PC 11+32.36  
 PT 13+58.45



*J. Horne*  
 03/17/2023

N.T.S



**FM 408  
 ROADWAY LAYOUT**

SHEET 2 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	35

DATE: 3/17/2023 2:48:55 PM  
 FILE: c:\pwworkspace\10677285\035 FM408 Roadway Layout-2.dgn






CK: DW: CK: DW:



LEGEND

EXIST - EXISTING  
 PROP - PROPOSED  
 EOP - EDGE OF PAVEMENT  
 ROW - RIGHT OF WAY  
 # - DRIVEWAY NUMBER

- DRIVEWAY TAPER AREA (ACP/CONC)  
 - ROADWAY WIDENING



PI 54+74.68  
 Δ 40°06'10.3" (LT)  
 D 08°48'53.0"  
 T 237.24'  
 L 454.95'  
 R 650.00'  
 PC 52+37.44  
 PT 56+92.39



*J. Horne*  
 03/17/2023

N.T.S



FM 408  
 ROADWAY LAYOUT

SHEET 5 OF 14




CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	38	

DATE: 3/17/2023 2:49:53 PM  
 FILE: C:\CGW\BENTON\WMA\06772851038\_FM408\_RoadwayLayout-5.dgn

DW: CK: DW: CK: CK:



- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - DRIVEWAY TAPER AREA (ACP/CONC)
  - ROADWAY WIDENING



*J. Horne*

03/17/2023

N.T.S



**FM 408  
ROADWAY LAYOUT**

SHEET 6 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	39


DATE: 3/17/2023 2:50:12 PM  
 FILE: c:\pwworking\tdot5\diomarc\quillenzuniga\0677285\039 FM408 RoadwayLayout-6.dgn





CK: DW: CK: DW:



- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - DRIVEWAY TAPER AREA (ACP/CONC)
  - ROADWAY WIDENING



PI 73+53.60  
 Δ 03°25'55.6" (RT)  
 D 01°08'44.8"  
 T 149.82'  
 L 299.54'  
 R 5000.58'  
 PC 72+03.78  
 PT 75+03.32



*John*  
 03/17/2023

N.T.S



**FM 408  
ROADWAY LAYOUT**

SHEET 7 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	40


DATE: 3/17/2023 2:50:31 PM  
 FILE: c:\pwworkspace\dwg\72851040 FM408 Roadway Layout-7.dgn





- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - [Cross-hatched box] - DRIVEWAY TAPER AREA (ACP/CONC)
  - [Dashed line] - ROADWAY WIDENING

PI 86+83.10  
 Δ 94°05'18.0" (LT)  
 D 11°41'34.9"  
 T 526.27'  
 L 804.65'  
 R 490.00'  
 PC 81+56.83  
 PT 89+61.48



*J. Horne*

03/17/2023

N.T.S




**FM 408  
 ROADWAY LAYOUT**

SHEET 8 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY		SHEET NO.
BMT	ORANGE		41



PI 95+07.60  
 Δ 16°49'53.7" (RT)  
 D 04°46'28.7"  
 T 177.54'  
 L 352.52'  
 R 1200.00'  
 PC 93+30.06  
 PT 96+82.58




CK: DW: CK: DW:



- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - ▨ - DRIVEWAY TAPER AREA (ACP/CONC)
  - ▧ - ROADWAY WIDENING



PI 106+69.64  
 Δ 73°14'25.3" (RT)  
 D 08°44'50.8"  
 T 486.80'  
 L 837.28'  
 R 655.00'  
 PC 101+82.83  
 PT 110+20.11



John  
 03/17/2023  
 N.T.S



**FM 408  
 ROADWAY LAYOUT**




SHEET 9 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
BMT		ORANGE	42

DATE: 3/17/2023 2:51:11 PM  
 FILE: c:\p\0817\0817.dwg

LEGEND

- EXIST - EXISTING
- PROP - PROPOSED
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- # - DRIVEWAY NUMBER
- [Hatched Box] - DRIVEWAY TAPER AREA (ACP/CONC)
- [Dashed Box] - ROADWAY WIDENING



John  
03/17/2023

N.T.S



**FM 408  
ROADWAY LAYOUT**



SHEET 10 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	43	


DW: CK: DW: CK: DW: CK:



- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - DRIVEWAY TAPER AREA (ACP/CONC)
  - ROADWAY WIDENING



PI 131+80.97  
 Δ 18°15'06.8" (RT)  
 D 04°56'21.4"  
 T 186.34'  
 L 369.52'  
 R 1160.00'  
 PC 129+94.63  
 PT 133+64.15



*John*  
 03/17/2023

N.T.S



**FM 408  
ROADWAY LAYOUT**

SHEET 11 OF 14



CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
BMT		COUNTY	SHEET NO.
		ORANGE	44

DATE: 3/17/2023 2:51:49 PM  
 FILE: c:\pwworking\tdot\10677285\044 FM408 RoadwayLayout-11.dgn




LEGEND

- EXIST - EXISTING
- PROP - PROPOSED
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- # - DRIVEWAY NUMBER
- DRIVEWAY TAPER AREA (ACP/CONC)
- ROADWAY WIDENING



PI 138+61.65  
 $\Delta$  18°41'25.0" (LT)  
 D 05°12'31.3"  
 T 181.02'  
 L 358.83'  
 R 1100.00'  
 PC 136+80.63  
 PT 140+39.46



*John*

03/17/2023

N.T.S



### FM 408 ROADWAY LAYOUT

SHEET 12 OF 14




CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	45

DATE: 3/17/23 10:39:16 2:52:09 PM  
 FILE: c:\p02\022916\022916\022916.dwg

DW: CK: DW: CK: DW: CK:



- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - DRIVEWAY TAPER AREA (ACP/CONC)
  - ROADWAY WIDENING



*John*  
 03/17/2023

N.T.S



**FM 408**  
**ROADWAY LAYOUT**

SHEET 13 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	46



DATE: 3/17/2023 2:52:28 PM  
 FILE: c:\pwworking\tdotcom\quillenzuniga\0677285\046 FM408 Roadway Layout-13.dgn



DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_



- LEGEND**
- EXIST - EXISTING
  - PROP - PROPOSED
  - EOP - EDGE OF PAVEMENT
  - ROW - RIGHT OF WAY
  - # - DRIVEWAY NUMBER
  - DRIVEWAY TAPER AREA (ACP/CONC)
  - ROADWAY WIDENING



*John*  
03/17/2023

N.T.S




**FM 408  
ROADWAY LAYOUT**

SHEET 14 OF 14


CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	47	

DATE: 3/17/2023 2:52:47 PM  
 FILE: c:\p08\p08\0883\02\091\047 FM408 RoadwayLayout-14.dgn


FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\Drawings\FM408Driveway\_Detail.dgn  
 DATE: 3/17/2023 4:16:59 PM



**SECTION "A-A"**




**SECTION "B-B"**



**PROFILE VIEW**

PROPOSED CONCRETE DRIVEWAYS


 PROPOSED HMA DRIVEWAY TAPER



**TYPICAL PLAN**

EXISTING GRAVEL, GRASS, & DIRT DRIVEWAYS

 PROPOSED HMA COUNTY ROAD TAPER




**TYPICAL PLAN**

ACP & CONCRETE DRIVEWAYS & SIDEROADS

**NOTES:**

- MATERIAL SPECIFICATIONS, TYPES AND RATES SHALL CONFORM TO ITEM 3076. HMA FOR INTERSECTIONS AND PUBLIC DRIVEWAYS WILL MATCH THE MATERIAL REQUIREMENTS OF THE HMA USED DURING SURFACING OPERATIONS.
- PROPOSED OVERLAY IS CALCULATED AS 5' FROM EOP OR TO EXTEND TO THE RADIUS OF THE DRIVEWAY, WHICHEVER COMES FIRST.
- ALL CR WITH EXISTING ASPHALT OVERLAYS ARE CALCULATED AS EOP TO ROW LINE.
- USE ITEM 247 TO REBUILD RADIUS OF DRIVEWAYS AS NEEDED.



*J. Horne*

03/17/2023

**TYPICAL DRIVEWAY & SIDE ROAD DETAILS**

N.T.S.




STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	BMT	ORANGE	48
CONTROL	SECTION	JOB	HIGHWAY NO.
0883	02	091	FM408

FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\Drawings\FM408Driveway\_Detail2.dgn  
 DATE: 3/17/2023 4:17:00 PM

INTERSECTIONS & DRIVEWAY SUMMARY					
#	LOCATION		TYPE		SURFACE
			INTRSCT, DRVWAYS, & TURNOUT	USE	
1	1+22	LT	-	PVT DRIVEWAY	GRAVEL
2	1+29	RT	-	PVT DRIVEWAY	GRAVEL
3	1+98	LT	-	PVT DRIVEWAY	GRAVEL
4	2+13	RT	-	PVT DRIVEWAY	GRAVEL
5	2+42	LT	-	PVT DRIVEWAY	GRAVEL
6	2+90	RT	-	PVT DRIVEWAY	GRAVEL
7	3+35	RT	-	PVT DRIVEWAY	GRAVEL
8	3+62	RT	-	PVT DRIVEWAY	GRAVEL
9	4+24	LT	-	PVT DRIVEWAY	GRAVEL
10	5+77	RT	-	PVT DRIVEWAY	GRAVEL
11	7+32	RT	69	MC GILL RD	ACP
12	8+81	RT	47	PARKING LOT	CONC
13	9+85	LT	-	PVT DRIVEWAY	GRAVEL
14	10+00	RT	57	PVT DRIVEWAY	CONC
15	10+89	RT	-	PVT DRIVEWAY	GRAVEL
16	11+64	LT	103	CORMIER RD	ACP
17	12+75	LT	-	PARKING LOT	ACP
18	13+30	RT	-	PVT DRIVEWAY	GRAVEL
19	13+72	RT	-	PVT DRIVEWAY	GRAVEL
20	14+08	LT	-	PVT DRIVEWAY	GRAVEL
21	15+20	RT	-	PVT DRIVEWAY	GRAVEL
22	15+23	LT	-	PVT DRIVEWAY	GRAVEL
23	15+90	RT	-	PVT DRIVEWAY	GRAVEL
24	16+52	LT	-	PVT DRIVEWAY	GRAVEL
25	16+95	RT	11	PVT DRIVEWAY	ACP
26	18+04	RT	-	PVT DRIVEWAY	GRAVEL
27	19+14	RT	-	PVT DRIVEWAY	GRAVEL
28	20+63	RT	-	PVT DRIVEWAY	GRAVEL
29	21+32	LT	-	PVT DRIVEWAY	GRAVEL
30	21+57	RT	63	NORWODD	ACP
31	22+41	LT	-	PVT DRIVEWAY	GRAVEL
32	24+96	RT	-	PVT DRIVEWAY	GRAVEL
33	25+97	LT	-	PVT DRIVEWAY	GRAVEL
34	26+17	RT	-	PVT DRIVEWAY	GRAVEL
35	27+13	LT	-	PVT DRIVEWAY	GRAVEL
36	27+78	RT	-	PVT DRIVEWAY	GRAVEL
37	28+66	RT	45	LA FLEUR	ACP
38	32+43	RT	-	PVT DRIVEWAY	GRAVEL
39	32+74	LT	-	PVT DRIVEWAY	GRAVEL
40	33+29	RT	-	PVT DRIVEWAY	GRAVEL
41	34+04	LT	-	PVT DRIVEWAY	GRAVEL
42	34+43	RT	-	PVT DRIVEWAY	GRAVEL
43	34+48	LT	-	PVT DRIVEWAY	GRAVEL
44	35+04	LT	-	PVT DRIVEWAY	GRAVEL
45	35+60	RT	-	PVT DRIVEWAY	GRAVEL
46	37+04	RT	-	PVT DRIVEWAY	GRAVEL
47	37+40	LT	-	PVT DRIVEWAY	GRAVEL
48	38+05	RT	-	PVT DRIVEWAY	GRAVEL
49	38+06	LT	-	PVT DRIVEWAY	GRAVEL
50	39+27	RT	-	PVT DRIVEWAY	GRAVEL

INTERSECTIONS & DRIVEWAY SUMMARY					
#	LOCATION		TYPE		SURFACE
			INTRSCT, DRVWAYS, & TURNOUT	USE	
51	40+09	RT	-	PVT DRIVEWAY	GRAVEL
52	40+96	RT	-	PVT DRIVEWAY	GRAVEL
53	41+49	LT	-	SINCLAIR RD	GRAVEL
54	42+46	RT	-	PVT DRIVEWAY	GRAVEL
55	43+55	RT	84	DUHON ST	ACP
56	44+47	LT	185	GULF RD	ACP
57	44+93	RT	-	PVT DRIVEWAY	GRAVEL
58	51+53	LT	-	PVT DRIVEWAY	GRAVEL
59	51+57	RT	-	PVT DRIVEWAY	GRAVEL
60	52+42	RT	-	PVT DRIVEWAY	GRAVEL
61	54+91	LT	-	PVT DRIVEWAY	GRAVEL
62	55+28	RT	223	BESSIE HEIGHTS RD	ACP
63	56+74	RT	-	PVT DRIVEWAY	GRAVEL
64	57+62	LT	62	PVT DRIVEWAY	CONC
65	59+06	LT	-	PVT DRIVEWAY	GRAVEL
66	61+71	LT	-	PVT DRIVEWAY	GRAVEL
67	62+54	LT	9	CRATER RD	ACP
68	64+55	LT	-	PVT DRIVEWAY	GRAVEL
69	65+08	RT	-	PVT DRIVEWAY	GRAVEL
70	65+81	LT	-	PVT DRIVEWAY	GRAVEL
71	66+51	LT	55	PARKING LOT	CONC
72	66+79	RT	-	PVT DRIVEWAY	GRAVEL
73	67+51	LT	42	PARKING LOT	CONC
74	67+51	RT	-	PVT DRIVEWAY	GRAVEL
75	69+60	LT	-	PVT DRIVEWAY	GRAVEL
76	70+25	RT	-	PVT DRIVEWAY	GRAVEL
77	70+25	LT	-	PVT DRIVEWAY	GRAVEL
78	72+69	RT	-	PVT DRIVEWAY	GRAVEL
79	74+34	LT	-	PVT DRIVEWAY	GRAVEL
80	74+44	RT	-	PVT DRIVEWAY	GRAVEL
81	75+37	LT	-	PVT DRIVEWAY	GRAVEL
82	75+77	RT	-	PVT DRIVEWAY	GRAVEL
83	76+92	RT	-	PVT DRIVEWAY	GRAVEL
84	77+44	LT	-	PVT DRIVEWAY	GRAVEL
85	77+47	RT	87	GARRISON DR	ACP
86	78+00	RT	9	PVT DRIVEWAY	ACP
87	79+14	LT	137	SCALES LN	ACP
88	79+77	RT	-	PVT DRIVEWAY	GRAVEL
89	80+50	RT	-	PVT DRIVEWAY	GRAVEL
90	81+89	LT	-	PVT DRIVEWAY	GRAVEL
91	83+34	LT	-	PVT DRIVEWAY	GRAVEL
92	84+32	RT	15	PVT DRIVEWAY	ACP
93	84+48	RT	161	HUMBLE ST	ACP
94	85+71	LT	-	PVT DRIVEWAY	GRAVEL
95	87+18	LT	-	PVT DRIVEWAY	GRAVEL
96	87+95	RT	206	HUMBLE ST	ACP
97	88+06	RT	-	PVT DRIVEWAY	GRAVEL
98	88+68	LT	-	PVT DRIVEWAY	GRAVEL
99	89+00	RT	-	PVT DRIVEWAY	GRAVEL
100	90+05	LT	-	PVT DRIVEWAY	GRAVEL
101	91+12	LT	-	PVT DRIVEWAY	GRAVEL
102	92+28	LT	-	PVT DRIVEWAY	GRAVEL
103	95+00	RT	-	PVT DRIVEWAY	GRAVEL
104	108+16	RT	-	PVT DRIVEWAY	GRAVEL
105	108+86	RT	-	PVT DRIVEWAY	GRAVEL

INTERSECTIONS & DRIVEWAY SUMMARY					
#	LOCATION		TYPE		SURFACE
			INTRSCT, DRVWAYS, & TURNOUT	USE	
106	110+62	RT	84	INEZ AVE	ACP
107	111+89	RT	-	PVT DRIVEWAY	GRAVEL
108	112+28	RT	-	PVT DRIVEWAY	GRAVEL
109	113+16	LT	-	PVT DRIVEWAY	GRAVEL
110	113+25	RT	-	PVT DRIVEWAY	GRAVEL
111	113+86	RT	-	PVT DRIVEWAY	GRAVEL
112	114+78	RT	-	PVT DRIVEWAY	GRAVEL
113	116+65	RT	-	PVT DRIVEWAY	GRAVEL
114	119+77	RT	81	LEBLANC ST	ACP
115	120+62	RT	-	PVT DRIVEWAY	GRAVEL
116	121+61	RT	-	PVT DRIVEWAY	GRAVEL
117	122+05	RT	-	PVT DRIVEWAY	GRAVEL
118	123+07	RT	-	PVT DRIVEWAY	GRAVEL
119	124+26	RT	73	VINCENT ST	ACP
120	125+57	RT	-	PVT DRIVEWAY	GRAVEL
121	128+16	RT	72	CLARK	ACP
122	129+90	RT	-	PARKING LOT	GRAVEL
123	130+59	LT	-	PVT DRIVEWAY	GRAVEL
124	130+61	RT	-	PARKING LOT	GRAVEL
125	132+00	RT	-	PVT DRIVEWAY	GRAVEL
126	132+52	LT	-	PVT DRIVEWAY	GRAVEL
127	133+25	LT	-	PVT DRIVEWAY	GRAVEL
128	134+76	LT	-	PVT DRIVEWAY	GRAVEL
129	135+20	RT	-	PVT DRIVEWAY	GRAVEL
130	138+16	LT	64	WARBLER RD	ACP
131	142+50	LT	62	QUAIL DR	ACP
132	144+02	RT	42	PVT DRIVEWAY	CONC
133	144+32	LT	-	PVT DRIVEWAY	GRAVEL
134	144+90	RT	54	PVT DRIVEWAY	CONC
135	145+13	LT	-	PVT DRIVEWAY	GRAVEL
136	146+77	LT	66	OAK VISTA DR	ACP
137	147+64	RT	-	PVT DRIVEWAY	GRAVEL
138	148+06	RT	-	PVT DRIVEWAY	GRAVEL
139	149+35	RT	-	PVT DRIVEWAY	GRAVEL
140	150+87	LT	56	PVT DRIVEWAY	CONC
141	152+19	RT	50	ARTHUR ST	ACP
142	153+70	RT	-	PVT DRIVEWAY	GRAVEL
143	154+53	RT	-	PVT DRIVEWAY	GRAVEL
144	154+85	LT	-	PVT DRIVEWAY	GRAVEL
145	155+63	RT	-	PVT DRIVEWAY	GRAVEL
146	155+90	LT	-	PVT DRIVEWAY	GRAVEL
147	156+28	RT	31	PVT DRIVEWAY	CONC
148	156+82	LT	-	PVT DRIVEWAY	GRAVEL
149	158+47	LT	77	ARIZONA	ACP
150	159+40	RT	46	PVT DRIVEWAY	CONC
151	159+72	RT	13	PVT DRIVEWAY	ACP
152	159+92	LT	-	PVT DRIVEWAY	GRAVEL
153	160+24	RT	40	PVT DRIVEWAY	CONC
154	160+62	LT	-	PVT DRIVEWAY	GRAVEL
155	161+11	LT	-	PVT DRIVEWAY	GRAVEL
156	161+65	RT	63	PVT DRIVEWAY	CONC
157	163+69	RT	77	PVT DRIVEWAY	CONC
158	164+95	RT	43	PVT DRIVEWAY	CONC
159	165+76	LT	45	PVT DRIVEWAY	CONC



*J. Horne*  
03/17/2023

**CONT.**  
**TYPICAL DRIVEWAY &**  
**SIDE ROAD DETAILS**  
 N.T.S.



STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	BMT	ORANGE	49
CONTROL	SECTION	JOB	ROADWAY NO.
0883	02	091	FM408




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



DATE: 3/16/2023 7:21:56 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNV050\_Treatment For Various Edge Conditions.dgn

### DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS


Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet





Edge Condition I  
 $S = (3:1)$  (or flatter)



Edge Condition II  
 $S = ((2.99):1)$  to  $(1:1)$



Edge Condition III  
 $S$  is steeper than  $(1:1)$



#### FACTORS CONSIDERED IN THE GUIDELINES:

- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.


#### Zone Treatment Types Guidelines:

- | Zone | Treatment Types Guidelines:   |
|------|---|
| ①    | No treatment.   |
| ②    | CW 8-11 "Uneven Lanes" signs.   |
| ③    | CW 8-9a "Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.  |
| ④    | CW 8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge fill may be provided to change the edge slope to that of the preferable Edge Condition I. |
| ⑤    | Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone- 4 may be used after consideration of other applicable factors.                  |

#### Edge Condition Notes:


- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ( [Cross-hatched symbol] )



- $E = ADT \times T$   
 Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within a lateral offset of 20 feet from the edge of the travel lane.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.








03/17/2023

Texas Department of Transportation  
 Traffic Operations Division

### TREATMENT FOR VARIOUS EDGE CONDITIONS

© TxDOT August 2000		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS					
03-01	0883	02	091	FM408	
08-01 correct typos		BMT	ORANGE		50




\*\* SEE TYPICAL SECTION FOR DEPTH.

**NOTES:**

LONGITUDINAL JOINTS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LANE WIDTH. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. TACK COAT SHALL BE APPLIED TO THE IN-PLACE TAPER BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED.

PAVEMENT EDGES SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL BE PLACED WITHIN THE NORMAL LANE WIDTH UNLESS OTHERWISE SHOWN ON THE PLANS. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. COMPACTION OF THE PAVEMENT EDGE TAPER WILL BE REQUIRED TO AS NEAR TO FINAL DENSITY AS POSSIBLE.



*J. Horne*



03/17/2023

**HOT MIX  
LONGITUDINAL  
AND  
PAVEMENT EDGE  
JOINT DETAILS**



STATE	DISTRICT	COUNTY		SHEET NO.
TEXAS	BMT	ORANGE		51
CONTROL	SECTION	JOB	HIGHWAY NO.	
0883	02	091	FM408	

# CENTERLINE RUMBLE STRIPS



**PLAN VIEW OPTION 1**  
**MILLED CENTERLINE RUMBLE STRIPS**

**PLAN VIEW OPTION 2**  
**RAISED CENTERLINE RUMBLE STRIPS**

**PLAN VIEW OPTION 3**  
**PREFORMED THERMOPLASTIC RUMBLE STRIPS**

**PLAN VIEW OPTION 4**  
**PROFILE CENTERLINE MARKINGS**

### GENERAL NOTES

1. This standard sheet provides guidelines for installing centerline rumble strips on multilane undivided highways.
2. Centerline and edge line rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossing, intersections or driveways with high usage of large trucks.
6. Use standard sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips for normal centerline spacing. For wider medians, specify in the plans the exact placement of the rumble strips. Place the rumble strips under each centerline marking or centered in the middle of the median.

### WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The color of the button should be yellow for a continuous no passing roadway. The button will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
11. Consideration shall be given to bicyclists. See RS(6).

### WHEN INSTALLING EDGE LINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

12. See standard sheet RS(2).

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:22:06 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standard\052\_rs(3)-23-.dgn

**MULTILANE UNDIVIDED HIGHWAY WITH SHOULDER**

Texas Department of Transportation

## CENTERLINE RUMBLE STRIPS ON MULTILANE UNDIVIDED HIGHWAYS


### RS(3)-23

FILE: rs(3)-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	January 2023	CONT	SECT	JOB
		0883	02	091
10-13		DIST	COUNTY	SHEET NO.
1-23		BMT	ORANGE	52




DATE: 3/16/2023 7:22:07 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standard\rs(4)-23.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TWO LANE TWO-WAY HIGHWAYS**




**CENTERLINE RUMBLE STRIPS**




PROFILE VIEW




PROFILE VIEW



PROFILE VIEW




PROFILE VIEW




PLAN VIEW  
OPTION 1

**MILLED CENTERLINE RUMBLE STRIPS**




PLAN VIEW  
OPTION 2

**RAISED CENTERLINE RUMBLE STRIPS**



PLAN VIEW  
OPTION 3

**PREFORMED THERMOPLASTIC RUMBLE STRIPS**



PLAN VIEW  
OPTION 4

**PROFILE CENTERLINE MARKINGS AND PREFORMED THERMOPLASTIC RUMBLE STRIPS**

**GENERAL NOTES**

1. This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
2. Centerline and edge line rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections or driveways with high usage of large trucks.
6. Use standard sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips.

**WHEN INSTALLING CENTERLINE RUMBLE STRIPS:**

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
11. The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.
12. Consideration shall be given to bicyclists. See RS(6).




**WHEN INSTALLING EDGE LINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:**

13. See standard sheet RS(2).

<p><b>CENTERLINE RUMBLE STRIPS ON TWO LANE TWO-WAY HIGHWAYS RS(4)-23</b></p>			
FILE: rs(4)-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT	January 2023	COM: 0883	SECT: 02
REVISIONS		JOB: 091	HIGHWAY: FM408
10-13		DIST: BMT	COUNTY: ORANGE
1-23			SHEET NO.: 53



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/17/2023 10:07:28 AM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\054\_bed14.dgn



**GENERAL NOTES**


- For more detail: See GF(31), SGT( )31, GF(31)TR, and GF(31)TL2 standard sheets.
- Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
- Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
- MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
- Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
- Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal, See Detail A)
- The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
- For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge locations shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
- Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
- A minimum 25' length of MBGF will be required.



Note: All rail elements shall be lapped in the direction of adjacent traffic.


		Design Division Standard	
<b>BRIDGE END DETAILS</b> <b>(METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)</b>			
<b>BED-14</b>			
FILE: bed14.dgn	DN: TxDOT	CK: AM	DW: BD/VP
© TxDOT: December 2011	CONT	SECT	JOB
REVISIONS	0883	02	091
REVISED APRIL 2014 SEE MEMO 04141	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	54

DATE: 3/17/2023  
 FILE: I:\BMT\DESIGN\Projects\0883-02-091 FM 408\GNVStandard\055\_gf3119.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




**TYPICAL POST PLACEMENT**

NOTE: \*\* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




**ELEVATION MID-SPAN RAIL SPLICE**

SHOWING A 25' - 0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




**ELEVATION 25' - 0" (NOM.) W-BEAM SECTION**

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




**BUTTON HEAD BOLT**

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



**MID-SPAN RAIL SPLICE DETAIL**

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.




**WOOD BLOCK TO ROUND WOOD POST**      **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**

**GENERAL NOTES**

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

\* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



**LOW FILL CULVERT POST**


NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.


		Design Division Standard	
<b>METAL BEAM GUARD FENCE</b> <b>TL-3 MASH COMPLIANT</b> <b>GF(31)-19</b>			
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0883	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	55	

DATE: 3/16/2023  
 FILE: T:\BMTDESIGN\Projects\0883-02-091\_FM 408\GN\Standards\056\_gf31ms19.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



**GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS**


Note: Site Condition(s)  
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.  
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.



**PLAN**


**GENERAL NOTES**

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type I or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




**SECTION A-A**

Typical




**MOW STRIP DETAIL**

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




**CURB OPTION (1)**

This option will increase the post embedment throughout the system.



**CURB OPTION (2)**


Curb shown on top of mow strip



**CURB OPTION (3)**

		Design Division Standard	
<b>METAL BEAM GUARD FENCE (MOW STRIP)</b> <b>TL-3 MASH COMPLIANT</b> <b>GF(31)MS-19</b>			
FILE: gf31ms19.dgn	DN: TxDOT	CK: KM	DW: VP
©TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0883	02	091
	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	56

DATE: 3/16/2023  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DN\Standards\057\_sgt10s3116.dgn



PART		MAIN SYSTEM COMPONENTS	
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)	
15208A	1	SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)	
15215G	1	SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS	
61G	1	SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25' - 0")	
15205A	1	POST #0 - ANCHOR POST (6' - 5 3/8")	
15203G	1	POST #1 - (SYTP) (4' - 9 1/2")	
15000G	1	POST #2 - (SYTP) (6' - 0")	
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6' - 0")	
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")	
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")	
15204A	1	ANCHOR PADDLE	
15207G	1	ANCHOR KEEPER PLATE (24 GA)	
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)	
15201G	2	ANCHOR POST ANGLE (10" LONG)	
15202G	1	ANGLE STRUT	

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B

REVISIONS		DESIGN			HIGHWAY		
NO.	DATE	BY	CHECKED	DATE	COUNTY	DISTRICT	SHEET NO.
0883	JULY 2016	02		091			FM408
					BMT	ORANGE	57


**TRINITY HIGHWAY  
 SOFTSTOP END TERMINAL  
 MASH - TL-3  
 SGT (10S) 31-16**

FILE: sgt10s3116  
 DNE: TxDOT  
 CR: KM  
 DW: VP  
 CR: MB/VP  
 ©TxDOT: JULY 2016  
 REVISIONS  
 CONT SECT JOB COUNTY DISTRICT SHEET NO.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023  
 FILE: I:\BMT\DESIGN\Projects\0883-02-091.FM 408.DGN\Standards\058\_sgt11s3118.dgn




NOTES:  
 1. ITEM 2 COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (9) THRU LINE POST (2).  
 2. DO NOT INSTALL A BLOCKOUT AT LINE POST (1).

NOTE: SECURE THE (TSS) PANEL TO OUTSIDE OF RAIL 2 WITH THE PANEL ARROWS POINTING TOWARDS THE HEAD.




SECTION VIEW A-A  
 SOIL ANCHOR, POST 1 & LINE POST 2 THRU 9



\* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.  
 \*\* ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
  - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
  - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
  - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
  - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
  - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
  - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
  - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	3/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	3/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1



APPROACH GRADING AT GUARDRAIL END TREATMENTS

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.




**Texas Department of Transportation**  
 Design Division Standard

**MAX-TENSION END TERMINAL  
 MASH - TL-3  
 SGT (11S) 31-18**

FILE: sgt11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883 02	091	FM408	
DIST	COUNTY	SHEET NO.		
BMT	ORANGE	58		




DATE: 3/16/2023  
 FILE: T:\BMT\ESGN\Projects\0883-02-091\_FM\_408\DGN\Standard\059\_sgt12s3118.dgn  
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
  - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MOW STRIP STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN ITS PLACE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard


## SINGLE GUARDRAIL TERMINAL

### MSKT-MASH-TL-3

### SGT (12S) 31-18


FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
DIST	COUNTY		SHEET NO.	
BMT	ORANGE		59	

DATE: 3/16/2023 7:34:31 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standard\060\_pset-spss-2.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**PLAN**

(Showing bell end connection.)




**LONGITUDINAL ELEVATION**

(Showing bell end connection.)




**INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS**

(If required)




**OPTION A**




**OPTION B**

**END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS**

(If required)




**MULTIPLE PIPE INSTALLATION**




**OPTION WITH SQUARE BOTTOM**

**SECTION A-A**



**OPTION WITH INVERT BOTTOM**



**OPTIONAL JOINT FOR RCP**

(Showing joint between RCP and precast safety end treatment.)

**REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS**

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness	"D"	Slope	Min Length	Pipe Runners Required		Required Pipe Runner Size		
						Single Pipe	Multiple Pipe	Nominal Dia.	O.D.	I.D.
12"	2"	1.15"	17.00"	6:1	4' - 9"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
15"	2 1/4"	1.30"	20.50"	6:1	6' - 5"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
18"	2 1/2"	1.60"	24.00"	6:1	8' - 0"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
24"	3"	1.95"	31.00"	6:1	11' - 3"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
30"	3 1/2"	2.65"	38.50"	6:1	14' - 8"	No	Yes	4" STD	4.500"	4.026"
36"	4"	2.75"	45.50"	6:1	17' - 11"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	2.7"	52.50"	6:1	21' - 2"	Yes	Yes	4" STD	4.500"	4.026"

- Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- Toewall to be used only when dimension is shown elsewhere in the plans.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

**GENERAL NOTES:**


Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".  
 When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.  
 Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:  
 A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).  
 B. For precast (steel formed) sections, provide Class "C" concrete (f'c = 3,600 psi).  
 At the option and expense of the Contractor the next larger size of safety end treatment may be furnished; as long as the "D" dimension cast is that of the required size of pipe.  
 Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.  
 Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.  
 Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.  
 Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464, "Reinforced Concrete Pipe". Connect TP by grouting. See Pipe and Box Grouted Connections (PBGC) standard for grouted connections with TP and precast safety end treatment.

**Texas Department of Transportation**  
 PRECAST SAFETY END TREATMENT  
 TYPE II ~ PARALLEL DRAINAGE  
 PSET-SP

FILE: psetspss-21.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
12-21: Added 42" TP	DIST	COUNTY	SHEET NO.	
BMT	ORANGE	60		


*Bridge Division Standard*

DATE: 3/16/2023 7:34:31 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\061\_psetrpss-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**PLAN VIEW - 12" THRU 24"**

(Showing spigot end connection.)




**LONGITUDINAL ELEVATION - 12" THRU 24"**

(Showing spigot end connection.)




**SECTION A-A**




**MULTIPLE PIPE INSTALLATION**

- ① Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- ② Provide cement stabilized bedding and backfill in accordance with the Item, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- ③ Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- ④ Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- ⑤ Safety pipe runners are required for multiple pipe culverts with more than two pipes.




**INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS**

(If required)



**OPTION A**



**OPTION B**

**END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS**

(If required)

**REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS**

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. per ft. of Pipe)	Max Slope	Min Length of Unit	Pipe Runner Requirements		Required Pipe Runner Sizes		
							Single Pipe	Multiple Pipe	Nominal Dia	O.D.	I.D.
12"	2"	16"	16"	0.07 Circ.	6:1	4' - 0"	No	⑤	3" STD	3.500"	3.068"
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	6:1	5' - 8"	No	⑤	3" STD	3.500"	3.068"
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	6:1	7' - 3"	No	⑤	3" STD	3.500"	3.068"
24"	3"	30"	27"	0.07 Circ.	6:1	10' - 6"	No	⑤	3" STD	3.500"	3.068"
30"	3 1/2"	37"	31"	0.18 Circ.	6:1	12' - 1"	No	Yes	4" STD	4.500"	4.026"
36"	4"	44"	36"	0.19 Ellip.	6:1	15' - 4"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	6:1	18' - 7"	Yes	Yes	4" STD	4.500"	4.026"

**MATERIAL NOTES:**

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
 Galvanize steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**


Precast safety end treatment for reinforced concrete pipe (RCP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".  
 When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.  
 Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.  
 Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.  
 Methods of lifting shall be provided by the manufacturer for ease of loading, unloading and installation.  
 Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.

Texas Department of Transportation  
Bridge Division Standard

PRECAST SAFETY END TREATMENT  
 TYPE II ~ PARALLEL DRAINAGE  
 PSET-RP

FILE: psetrpss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0883</b>	<b>02</b>	<b>091</b>	<b>FM408</b>
DIST	COUNTY		SHEET NO.	
<b>BMT</b>	<b>ORANGE</b>		<b>61</b>	


DATE: 3/16/2023 7:34:32 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\062\_setpdse-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




NOTE: All cross pipes, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

### SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER


(Showing corrugated metal pipe (CMP) culvert. Details at reinforced concrete pipe (RCP) culvert are similar.)




### ISOMETRIC VIEW OF TYPICAL INSTALLATION



### PIPE WITH BOLTED ANCHOR




### PIPE WITH ANCHOR BARS




### SECTION C-C

### CROSS PIPE DETAILS



### DETAIL "A"


(Showing invert with corrugated metal pipe (CMP) culvert. Reinforced concrete pipe (RCP) culvert details are similar. Cross pipes not shown for clarity.)




### SECTION B-B

(Cross pipes not shown for clarity.)


Limits of riprap (to be included with SET for payment)



### SHOWING TYPICAL PIPE CULVERT AND RIPRAP



### SHOWING CROSS PIPE WITH ANCHOR BAR



### SHOWING CROSS PIPE WITH BOLTED ANCHOR

### SECTION A-A

## CROSS PIPE LENGTHS, REQUIRED PIPE SIZES, AND RIPRAP QUANTITIES

Nominal Culvert I.D.	Conc Riprap (CY) (6)	Pipe Culvert Spa ~ G	Single Barrel ~ Q1	Multi-Barrel ~ Q1	Q2	Conditions for Use of Cross Pipes	Cross Pipe Sizes
12"	0.6	0' - 9"	N/A	2' - 1"	1' - 9"	3 or more pipe culverts	3" Std (3.500" O.D.)
15"	0.7	0' - 11"	N/A	2' - 5"	2' - 2"		
18"	0.8	1' - 2"	N/A	2' - 10"	2' - 8"		
21"	0.9	1' - 4"	N/A	3' - 2"	3' - 1"	3 or more pipe culverts	3 1/2" Std (4.000" O.D.)
24"	0.9	1' - 7"	N/A	3' - 6"	3' - 7"		
27"	1.0	1' - 8"	N/A	3' - 10"	3' - 11"		
30"	1.1	1' - 10"	N/A	4' - 2"	4' - 4"	2 or more pipe culverts	3 1/2" Std (4.000" O.D.)
33"	1.2	1' - 11"	4' - 2"	4' - 5"	4' - 8"	All pipe culverts	
36"	1.3	2' - 1"	4' - 5"	4' - 9"	5' - 1"	All pipe culverts	4" Std (4.500" O.D.)
42"	1.5	2' - 4"	4' - 11"	5' - 5"	5' - 10"		
48"	1.7	2' - 7"	5' - 5"	6' - 0"	6' - 7"	All pipe culverts	5" Std (5.563" O.D.)
54"	2.0	3' - 0"	5' - 11"	6' - 9"	7' - 6"		
60"	2.2	3' - 3"	6' - 5"	7' - 4"	8' - 3"		
66"	2.4	3' - 3"	6' - 11"	7' - 10"	8' - 9"	All pipe culverts	5" Std (5.563" O.D.)
72"	2.7	3' - 4"	7' - 5"	8' - 5"	9' - 4"		


- The proper installation of the first cross pipe is critical for vehicle safety. Place the top of the first cross pipe no more than 6" above the flow line.
- Provide cross pipes, except the first bottom pipe, of the size shown in the table. Provide a 3 1/2" standard pipe (4" O.D.) for the first bottom pipe.
- Install the third cross pipe from the bottom of the culvert using a bolted connection. Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access. At the Contractor's option, install all other cross pipes using the bolted connection details.
- Match cross slope as shown elsewhere in the plans. Cross slope of 6:1 or flatter is required for vehicle safety.
- Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for contractor's information only.

#### MATERIAL NOTES:

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. Provide cross pipes that meet the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 (Gr B), or API 5LX52. Provide ASTM A307 bolts and nuts. Galvanize all steel components, except concrete reinforcing, after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

#### GENERAL NOTES:

Cross pipes are designed for a traversing load of 10,000 pounds at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981. Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the cross pipes. Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap". Payment for riprap and toewall is included in the Price Bid for each Safety End Treatment.



### SIDE ELEVATION OF CAST-IN-PLACE CONCRETE

(Showing reinforced concrete pipe (RCP) culvert. Details at corrugated metal pipe (CMP) culvert are similar.)

**Bridge Division Standard**

**SAFETY END TREATMENT**  
FOR 12" DIA TO 72" DIA  
PIPE CULVERTS  
TYPE II ~ PARALLEL DRAINAGE

**SETP-PD**

FILE: setpdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT	February 2020	CONT	SECT	HIGHWAY
REVISIONS	0883	02	091	FM408
DIST	COUNTY		SHEET NO.	
BMT	ORANGE		62	

# LEGEND

GAS ——— G1 ——— CENTERPOINT ENERGY  
 GAS -- G1 (D) ----- G1 (D) -- CENTERPOINT ENERGY  
 PIPELINE ——— PL1 ——— SUNOCO  
 PIPELINE -- PL1 (D) ----- PL1 (D) -- SUNOCO  
 PIPELINE ——— PL2 ——— CHEVRON  
 PIPELINE -- PL2 (D) ----- PL2 (D) -- CHEVRON  
 PIPELINE ——— PL3 ——— ENTERPRISE  
 PIPELINE -- PL3 (D) ----- PL3 (D) -- ENTERPRISE  
 PIPELINE ——— PL4 ——— KINDER MORGAN  
 PIPELINE -- PL4 (D) ----- PL4 (D) -- KINDER MORGAN  
 PIPELINE ——— PL5 ——— BCKY  
 PIPELINE -- PL5 (D) ----- PL5 (D) -- BCKY  
 PIPELINE ——— PL6 ——— SHELL  
 PIPELINE -- PL6 (D) ----- PL6 (D) -- SHELL  
 PIPELINE ——— PL7 ——— COLONIAL  
 PIPELINE -- PL7 (D) ----- PL7 (D) -- COLONIAL  
 PIPELINE ——— PL8 ——— CENTANA INTRASTATE  
 PIPELINE -- PL8 (D) ----- PL8 (D) -- CENTANA INTRASTATE  
 PIPELINE ——— PL9 ——— FLINT HILLS  
 PIPELINE -- PL9 (D) ----- PL9 (D) -- FLINT HILLS  
 PIPELINE ——— PL10 ——— DOW  
 PIPELINE -- PL10 (D) ----- PL10 (D) -- DOW  
 PIPELINE ——— PL11 ——— EASTON ENERGY  
 PIPELINE -- PL11 (D) ----- PL11 (D) -- EASTON ENERGY  
 PIPELINE ——— PL12 ——— AIR PRODUCTS  
 PIPELINE -- PL12 (D) ----- PL12 (D) -- AIR PRODUCTS  
 PIPELINE ——— PL13 ——— UCAR  
 PIPELINE -- PL13 (D) ----- PL13 (D) -- UCAR  
 PIPELINE ——— PL14 ——— UNKNOWN  
 PIPELINE -- PL14 (D) ----- PL14 (D) -- UNKNOWN  
 TELEPHONE ——— T1 ——— ATT  
 TELEPHONE ----T1 (D)-----T1 (D)--- ATT  
 FIBER OPTIC ——— FOC1 ——— ATT  
 FIBER OPTIC - FOC1 (D)----- FOC1 (D)- ATT  
 FIBER OPTIC ——— FOC2 ——— SPECTRUM  
 FIBER OPTIC - FOC2 (D)----- FOC2 (D)- SPECTRUM  
 WATER ——— CITY OF BRIDGE CITY  
 WATER ——— CITY OF BRIDGE CITY  
 WASTE WATER ——— CITY OF BRIDGE CITY  
 WASTE WATER ——— CITY OF BRIDGE CITY  
 WASTE WATER ——— CITY OF BRIDGE CITY  
 OVERHEAD ——— OH ——— (SEE OVERHEAD LEGEND)

OVERHEAD LEGEND	
1	ENTERGY ELECTRIC
2	AT&T TELEPHONE
3	CATV CATV
4	CATV FIBER OPTIC

□ ELECTRICAL TRANSFORMER BOX  
 ⊙ TELEPHONE MANHOLE  
 □ TELEPHONE VAULT  
 □ TELEPHONE PEDESTAL  
 □ TELEPHONE HAND HOLE  
 □ FIBER OPTIC VAULT  
 ⊙ FIBER OPTIC MANHOLE  
 □ FIBER OPTIC HANDHOLE  
 □ ELECTRICAL POWER BOX  
 ⊙ HYDRANT  
 ⊙ WATER MANHOLE  
 ∞ WATER VALVE  
 □ WATER METER  
 ⊙ WATER VAULT  
 □ TRANSMISSION TOWER  
 ⊙ ELECTRIC MANHOLE  
 ■ TRAFFIC SIGNAL POWER BOX  
 ⊙ POWER POLE  
 □ LIGHT POLE  
 ⊙ WASTE WATER MANHOLE  
 ⊙ CLEAN OUT  
 ⊙ GAS MANHOLE  
 ⊙ GAS VENT  
 □ GAS METER  
 ~ OUT OF SCOPE  
 - END OF LINE

## MATERIAL

AC= ABESTOS CEMENT  
 PVC=POLYVINYL CHLORIDE  
 MW=MILL WRAPPED  
 DI=DUCTILE IRON  
 STL=STEEL  
 PE=POLYETHYLENE

## UTILITIES

WW=WASTE WATER  
 WL=WATER LINE  
 FOC=FIBER OPTIC  
 TELE=TELEPHONE  
 CTV=CABLE TV  
 GAS=GAS  
 PL=PIPELINE  
 ELECT-ELECTRIC

## GENERAL

ED-ELECTRONIC DEPTH  
 TH-TESTHOLE  
 FL-FLOW LINE  
 ELEV-ELEVATION  
 EXIST-EXISTING  
 PROP-PROPOSED

QUALITY LEVEL "D": INFORMATION DERIVED FROM EXISTING RECORDS AND/OR ORAL RECOLLECTIONS,

QUALITY LEVEL "C": INFORMATION OBTAINED BY SURVEYING AND PLOTTING VISIBLE ABOVE-GROUND UTILITY FEATURES AND BY USING PROFESSIONAL JUDGMENT IN CORRELATING THIS INFORMATION TO QUALITY LEVEL D INFORMATION.

QUALITY LEVEL "B": INFORMATION OBTAINED THROUGH THE APPLICATION OF APPROPRIATE SURFACE GEOPHYSICAL METHODS TO DETERMINE THE EXISTENCE AND APPROXIMATE HORIZONTAL POSITION OF SUBSURFACE UTILITIES (AKA DESIGNATING).

QUALITY LEVEL "A": PRECISE HORIZONTAL AND VERTICAL LOCATION OF UTILITIES OBTAINED BY THE ACTUAL EXPOSURE AND SUBSEQUENT MEASUREMENT OF SUBSURFACE UTILITIES, USUALLY AT A SPECIFIC POINT (AKA LOCATING).




FM 408


UTILITY LAYOUTS DETAIL

SHEET 1 OF 15

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	63	




MATCHLINE STA. 6+60.00



MATCHLINE STA. 6+60.00

MATCHLINE STA. 12+60.00



*John*  
03/17/2023

N.T.S



**FM 408**  
**UTILITY LAYOUTS**


SHEET 2 OF 14

CONTRACT	SECTION	JOB	HIGHWAY
0883	02	091	FM408
DISTRICT	COUNTY	SHEET NO.	
BMT	ORANGE	64	



DATE: 3/17/2023 2:53:25 PM  
FILE: c:\projects\100\10016\10016.dwg



DW: CK: DW: CK: CK:



PI 12+45.47  
 $\Delta$  04°37'34.7" (RT)  
 D 02°02'46.6"  
 T 113.10'  
 L 226.08'  
 R 2800.00'  
 PC 11+32.36  
 PT 13+58.45



*John*

N.T.S






**FM 408**  
  
**UTILITY LAYOUTS**

SHEET 3 OF 15

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
BMT		COUNTY	SHEET NO.
		ORANGE	65

DATE: 3/17/2023 2:53:44 PM  
 FILE: c:\pwworking\adamarc\quillen\julia\08691461065 FM408 Ut-3.dgn

CK: DW: CK: DW:



03/17/2023

N.T.S





FM 408  
UTILITY LAYOUTS

SHEET 4 OF 15


CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST			COUNTY
BMT			ORANGE
			SHEET NO.
			66

DATE: 3/17/2023 2:54:04 PM  
FILE: C:\CGI\BENTON\NAMES\cdot5\diomar.quillen\unlga\0869146\066 FM408 Ut-4.dgn

DW: CK: DW: CK: DW: CK:



PI 45+12.71  
 Δ 40°57'34.2" (RT)  
 D 08°25'05.5"  
 T 254.20'  
 L 486.56'  
 R 680.62'  
 PC 42+58.51  
 PT 47+45.07



*John*

03/17/2023

N.T.S



FM 408


UTILITY LAYOUTS

SHEET 5 OF 15



CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	67

DATE: 3/17/23 02:31:16 2:54:23 PM  
 FILE: C:\DOCUMENTS\NAMES\cd05\diomarc\quillen\zuni\ga\0869146\067 FM408 Ut-5.dgn

CK: DW: CK: DW:



PI 54+74.68  
 Δ 40°06'10.3" (LT)  
 D 08°48'53.0"  
 T 237.24'  
 L 454.95'  
 R 650.00'  
 PC 52+37.44  
 PT 56+92.39



*J. Horne*  
 03/17/2023

N.T.S

Texas Department of Transportation

FM 408

UTILITY LAYOUTS




SHEET 6 OF 15

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	68

DATE: 3/17/2023 2:54:44 PM  
 FILE: C:\GUNTEN\DRAWING\0883\02\091\FM408 Ut-6.dgn



CK: DW: CK: DW: CK: DW:



*J. Horne*  
03/17/2023

N.T.S



FM 408


UTILITY LAYOUTS

SHEET 7 OF 15


CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	69

DATE: 3/17/2023 2:55:02 PM  
FILE: c:\pwworkspace\1461069\FM408 Ut-7.dgn

CK: DW: CK: DW: CK: DW:



PI 73+53.60  
 Δ 03°25'55.6" (RT)  
 D 01°08'44.8"  
 T 149.82'  
 L 299.54'  
 R 5000.58'  
 PC 72+03.78  
 PT 75+03.32



*J. Horne*  
 03/17/2023

N.T.S

Texas Department of Transportation

FM 408

UTILITY LAYOUTS



SHEET 8 OF 15

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	70


DATE: 3/17/2023 2:55:20 PM  
 FILE: C:\G:\BENTON\WMA\0883\02\091\461070\_FM408\_Ut-8.dgn



PI 86+83.10  
 Δ 94°05'18.0" (LT)  
 D 11°41'34.9"  
 T 526.27'  
 L 804.65'  
 R 490.00'  
 PC 81+56.83  
 PT 89+61.48



PI 95+07.60  
 Δ 16°49'53.7" (RT)  
 D 04°46'28.7"  
 T 177.54'  
 L 352.52'  
 R 1200.00'  
 PC 93+30.06  
 PT 96+82.58



*J. Horne*

03/17/2023

N.T.S



FM 408




UTILITY LAYOUTS

SHEET 9 OF 15

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	71

DATE: 3/17/2023 2:55:41 PM  
 FILE: C:\DOCUMENTS\NAMES\cd5\diomar.quillen\zuniqa\0869146\071 FM408 Ut-9.dgn

CK:  
DW:  
CK:  
DW:



*J. Horne*  
03/17/2023

N.T.S



FM 408

UTILITY LAYOUTS

SHEET 10 OF 15

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	72

DATE: 3/17/2023 2:56:00 PM  
FILE: c:\pwworking\dwg\10869146\1072 FM408 Ut-10.dwg


















CK: DW: CK: DW:

- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



John  
03/17/2023

N.T.S



**FM408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**


SHEET 1 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	78



DATE: 3/17/2023 2:58:01 PM  
FILE: c:\tdot\pw\_onlinetxdot5\diomar.quillen\zuniqa\0853876\078 FM408 PvmMk Sign-1.dgn

DW: CK: DW: CK: DW: CK:

- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



PI 12+45.47  
 Δ 04°37'34.7" (RT)  
 D 02°02'46.6"  
 T 113.10'  
 L 226.08'  
 R 2800.00'  
 PC 11+32.36  
 PT 13+58.45



*J. Horne*

03/17/2023

N.T.S



**FM 408  
 PAVEMENT MARKINGS  
 AND SIGN LAYOUT**

SHEET 2 OF 14




CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	79

DATE: 3/17/2023 2:58:21 PM  
 FILE: c:\tdot\pw\onlinetx\dot5\dlomar\quillenzuniga\0853876\079 FM408 PvmTrk\_Sign-2.dgn

DW: CK: DW: CK: DW: CK: DW: CK:



- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



*J. Horne*

03/17/2023

N.T.S



**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**

SHEET 3 OF 14



CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	80

DATE: 3/17/2023 2:58:40 PM  
FILE: c:\tdot\pw\onlinetxdot5\diomar.quillen\zuntiga\0853876\080 FM408 Pvm\Mrk\_Sign-3.dgn

CK: DW: CK: DW:



- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



*J. Horne*  
03/17/2023

N.T.S




**FM408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**

SHEET 4 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	81

DATE: 3/17/2023 2:59:00 PM  
FILE: c:\tdot\pw\onlinetxdot5\diomar.quillen\zuniqa\0853876\081 FM408 PvmrMk\_Sign-4.dgn




PI 45+12.71  
Δ 40°57'34.2" (RT)  
D 08°25'05.5"  
T 254.20'  
L 486.56'  
R 680.62'  
PC 42+58.51  
PT 47+45.07




DW: CK: DW: CK: DW: CK:

LEGEND

- WS - 6" WHITE SOLID
- YB - 6" YELLOW BROKEN
- YS - 6" YELLOW SOLID
- DYS - 6" DOUBLE YELLOW SOLID
- 8WS - 8" WHITE SOLID
- 12WS - 12" WHITE SOLID
- 24WS - 24" WHITE SOLID
- ROW - RIGHT OF WAY
- MBGF - METAL BEAM GUARDFENCE



PI 54+74.68  
 Δ 40°06'10.3" (LT)  
 D 08°48'53.0"  
 T 237.24'  
 L 454.95'  
 R 650.00'  
 PC 52+37.44  
 PT 56+92.39



*J. Horne*  
 03/17/2023

N.T.S



**FM 408**  
**PAVEMENT MARKINGS**  
**AND SIGN LAYOUT**

SHEET 5 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	82




DATE: 3/17/2023 2:59:19 PM  
 FILE: c:\tdot\pw\onlinetxdot5\diomar.quillenzuniga\0853876\082 FM408 PvmMk\_Sign-5.dgn



DW: CK: DW: CK: DW: CK:



- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW SOLID
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



*John*  
 03/17/2023

N.T.S



**FM 408**  
**PAVEMENT MARKINGS**  
**AND SIGN LAYOUT**

SHEET 6 OF 14


CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	83

DATE: 3/17/2023 2:59:40 PM  
 FILE: c:\tdot\pw\onlinetxdot5\diomar.quillenzuniga\0853876\083 FM408 PvmMk\_Sign-6.dgn

CK: DW: CK: DW:




- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



REPLACE  
STA 73+50

W1-4L  
35  
M.P.H.  
W13-1

PI 73+53.60  
Δ 03°25'55.6" (RT)  
D 01°08'44.8"  
T 149.82'  
L 299.54'  
R 5000.58'  
PC 72+03.78  
PT 75+03.32



REPLACE  
STA 80+27

W1-8L

REPLACE  
STA 81+17


W1-8L  
W1-8R

REPLACE  
STA 82+55

W1-8L  
W1-8R

REPLACE  
STA 81+17

W1-8L  
W1-8R



*J. Horne*  
03/17/2023

N.T.S



**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**

SHEET 7 OF 14


CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	84

DATE: 3/17/2023 3:00:01 PM  
FILE: c:\tdot\pw\onlinetxdot5\diomar.quillen\zuniqa\0853876\084 FM408 PvmMk\_Sign-7.dgn



PI 86+83.10  
 Δ 94°05'18.0" (LT)  
 D 11°41'34.9"  
 T 526.27'  
 L 804.65'  
 R 490.00'  
 PC 81+56.83  
 PT 89+61.48

LEGEND

WS - 6"	WHITE SOLID
YB - 6"	YELLOW BROKEN
YS - 6"	YELLOW SOLID
DYS - 6"	DOUBLE YELLOW SOLID
8WS - 8"	WHITE SOLID
12WS - 12"	WHITE SOLID
24WS - 24"	WHITE SOLID
ROW -	RIGHT OF WAY
MBGF -	METAL BEAM GUARDFENCE



PI 95+07.60  
 Δ 16°49'53.7" (RT)  
 D 04°46'28.7"  
 T 177.54'  
 L 352.52'  
 R 1200.00'  
 PC 93+30.06  
 PT 96+82.58



John  
 03/17/2023

N.T.S



**FM 408**  
**PAVEMENT MARKINGS**  
**AND SIGN LAYOUT**

SHEET 8 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	85	




DATE: 3/17/2023 3:00:22 PM  
 FILE: c:\tdot\pw\onlinetxdot5\diomar.quillenzuniga\0853876\085 FM408 PvmTrk\_Sign-8.dgn

CK: DW: CK: DW:



LEGEND

WS -	6" WHITE SOLID
YB -	6" YELLOW BROKEN
YS -	6" YELLOW SOLID
DYS -	6" DOUBLE YELLOW SOLID
8WS -	8" WHITE SOLID
12WS -	12" WHITE SOLID
24WS -	24" WHITE SOLID
ROW -	RIGHT OF WAY
MBGF -	METAL BEAM GUARDFENCE



*J. Horne*  
03/17/2023

N.T.S



**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**




SHEET 9 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	86	

DATE: 3/17/2023 3:00:42 PM  
FILE: c:\tdot\pw\onlinetxdot5\diomar.quillenzuniga\0853876\086 FM408 PvrmtMk\_Sign-9.dgn

CK: DW: CK: DW: CK: DW: CK: DW:

- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



*J. Horne*  
03/17/2023

N.T.S



**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**

SHEET 10 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	87




DATE: 3/17/2023 3:01:02 PM  
FILE: c:\tdot\pw\_onlinetxdot5\diomar.quillenzuniga\0853876\087 FM408 PvmTmk\_Sign-10.dgn




DW: CK: DW: CK: DW: CK:



- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



PI 131+80.97  
 Δ 18°15'06.8" (RT)  
 D 04°56'21.4"  
 T 186.34'  
 L 369.52'  
 R 1160.00'  
 PC 129+94.63  
 PT 133+64.15



*John*  
 03/17/2023

N.T.S



**FM 408  
 PAVEMENT MARKINGS  
 AND SIGN LAYOUT**

SHEET 11 OF 14




CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	88

DATE: 3/17/23 02:31:17 3:01:22 PM  
 FILE: c:\pwworking\tdotcom\quillenzuniga\0853876\088 FM408 PvmMk\_Sign-11.dgn



DW: CK: DW: CK: DW: CK:

- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



*John*  
03/17/2023

N.T.S



**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUTS**

SHEET 12 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	89




DATE: 3/17/23 10:29:17 3:01:43 PM  
FILE: c:\p\c\dw\pvt\mkt\sign\12.dgn

PI 138+61.65  
Δ 18°41'25.0" (LT)  
D 05°12'31.3"  
T 181.02'  
L 358.83'  
R 1100.00'  
PC 136+80.63  
PT 140+39.46

DW: CK: DW: CK: DW: CK:



- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



*J. Horne*  
03/17/2023

N.T.S



**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**

SHEET 13 OF 14




CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	90	

DATE: 3/17/23 10:59:17 3:02:03 PM  
 FILE: c:\pwworking\tdm\external\quillenzuniga\0853876\090 FM408 PvmMk\_Sign-13.dgn

DW: CK: DW: CK: DW: CK: DW: CK: DW: CK: DW: CK:



- LEGEND**
- WS - 6" WHITE SOLID
  - YB - 6" YELLOW BROKEN
  - YS - 6" YELLOW SOLID
  - DYS - 6" DOUBLE YELLOW SOLID
  - 8WS - 8" WHITE SOLID
  - 12WS - 12" WHITE SOLID
  - 24WS - 24" WHITE SOLID
  - ROW - RIGHT OF WAY
  - MBGF - METAL BEAM GUARDFENCE



**N.T.S**

**Texas Department of Transportation**

**FM 408  
PAVEMENT MARKINGS  
AND SIGN LAYOUT**


SHEET 14 OF 14

CONT	SECT	JOB	HIGHWAY
0883	02	091	FM408
DIST		COUNTY	SHEET NO.
BMT		ORANGE	91


DATE: 3/21/2017 3:02:23 PM  
 FILE: c:\pwworkspace\141323\141323.dwg

DATE: 3/16/2023 7:34:33 PM  
 FILE: T:\BMTDESIGN\Projects\0883-02-091\_FM\_408\GNSStandards\092-95\_mb-21.dwg  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any kind to other formats or for incorrect results or damages resulting from its use.

### TYPE 1 - MULTIPLE



### TYPE 4 - MULTIPLE




### MAILBOX SIZES

MAILBOX SIZE	TYPICAL DIMENSIONS			MAX **
	LENGTH	WIDTH	HEIGHT	
SMALL	19 1/2"	6"	7"	6 LBS
MEDIUM	22 1/2" *	8" *	11 1/2" *	8 LBS
LARGE	23 1/2"	11 1/2"	13 1/2"	11 LBS
EXTRA LARGE	18"	14"	12"	13 LBS
LOCKABLE	18"	11 1/2"	15"	23 LBS

- GENERAL NOTES:**
- Dimensions shown (length, width, and height) are typical, not maximums. However, anytime a medium size mailbox is mounted on a single/double mount or on the outside position on a multi mount, the dimensions shown are maximums.
  - Mailboxes shall be made of light weight sheet metal or light weight plastic. Heavy steel, cast iron or decorative mailboxes shall not be used on the state highway system.


\* See Note 1.  
 \*\* Excluding Molded Plastic on 4 X 4 Post

### TYPICAL INSTALLATION MEASUREMENTS




**NOTE:**  
 Mailbox installations in sidewalk areas shall be in accordance with the latest TxDOT Design Standard sheets PED-Pedestrian Facilities Curb Ramps.


### TYPE 2 and 4 - SINGLE/DOUBLE





### TYPE 3 - SINGLE/DOUBLE




### PLACEMENT OF EMERGENCY LOCATION NUMBER



- NOTES:**
- Location numbers are provided by homeowner. Minimum size 1" height.
  - Location number is typically placed on the mailbox in a contrasting color.
  - Black numbers may be placed on the Type 2 object marker if the numbers cannot be placed on the mailbox.
  - Alternatively, a green or blue plate with white numbers attached may be mounted below the object marker. Other contrasting color configuration, as approved, may be used.
  - See 3 of 4 for Foundation details.
  - See 4 of 4 for Hardware details.



### TYPE 5



Typical Molded Plastic Mailbox

SHEET 1 OF 4




## MAILBOX MOUNTING AND ASSEMBLY

### MB(1)-21


FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
2/2005	0883	02	091	FM408
6/2005	DIST	COUNTY	SHEET NO.	
11/2006	BMT	ORANGE	92	

DATE: 3/16/2023 7:34:34 PM  
 FILE: I:\BMTDESIGN\Projects\0883-02-091\_FM\_408\DNVStandards\0883-02-091\_fm-21(1)0883.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 1 - MULTI LOCKABLE AND XL MAILBOX**



**TYPE 2/4 - SINGLE LOCKABLE MAILBOX**




**TYPE 2/4 - SINGLE XL MAILBOX**




**NOTE:**  
Follow same configuration when mounting an XL mailbox on a Type 4 multi post.


**TYPE 1 MULTI - LOCKABLE ARCHITECTURAL (LA)**



**TYPE 1 MULTI - XL MAILBOX**



**TYPE 3 - XL MAILBOX MOUNTING**



SHEET 2 OF 4

















		Maintenance Division Standard	
<h2>XL AND LOCKABLE ARCHITECTURAL MAILBOX ASSEMBLY</h2> <h3>MB (2) - 21</h3>			
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT March 2004	CONT	SECT	JOB
2/2005	0883	02	091
6/2005			FM408
11/2006			
REVISIONS	DIST	COUNTY	SHEET NO.
4/2015	BMT	ORANGE	93





DATE: 3/16/2023 7:34:34 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNV\Standards\092-95\_mb-21(1)12.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPE	TYPE 1	TYPE 2	TYPE 3	TYPE 4	TYPE 5	TYPE 6
Configuration	Multiple	Single or Double	Single or Double	Single	Double	Multiple
Mailbox Size NIGP #	Outside Position: S or M Inside Position: S, M, L, XL, or LA	Single: S, M, L, XL, or LA Double: SS, SM, MM	Single: S, M, L, or XL Double: SS, SM, MM	S, M, L, XL, or LA	SS, SM, or MM	Outside Position: S or M Inside Position: S, M, L, or XL
Mailbox Post NIGP #	45057255254 (Galvanized Multiple)	45057561404 (Thin Walled Govanize)	57044325108 (Wing Channel Post)	45057561107 (Thin walled white powder coated) 45057561057 (Recycled Rubber Post: S or M only)	45057561107 (Thin Walled White Powder Coated)	45057257409 (White Powder Coated Multiple)
Post and Mailbox Hardware NIGP #	45057259009 (Wedge) 45057256500 (V-Wing Socket) 45057253002 (Bracket Extension) 45057252251 (Mailbox Bracket) 45057258001 (Part A Angle Bracket x2) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	80130598701 (Wedge) 80130238407 (Wedge Anchor) 45057253002 (Bracket Extension) 45057252343 (Double MB Bracket) 45057252350 (S. Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	45057541653 (Type 3 Double Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057253002 (Bracket Extension) 45057258001 (Part A Angle Bracket) 45057258027 (Part B Angle Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057252350 (Single Mailbox Bracket) 45057253002 (Bracket Extension) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252343 (Double Mount Bracket) 45057252251 (Mailbox Bracket x2)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252350 (Single Mount Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)
Foundation Used	Class B Concrete (Required for LA Mailboxes)	Class B Concrete (Required for LA Mailboxes)	None	Class B Concrete (not used with recycled rubber post, required for LA Mailboxes)	Class B Concrete (not required)	Class B Concrete


 NIGP: 45057250263 L-Bracket x4 for XL sized mailboxes	 NIGP: 45057252343 Double Mailbox Bracket For Type 2 and Type 4 double mount	 NIGP: 45057252350 Single Mailbox Bracket For Type 2 single and for Type 4 single and multi mount	 NIGP: 45057258001 Part "A" Angle Bracket For Type 1 multi (2 per mailbox) and Type 3 single and double
 NIGP: 45057251055 Type 6 Angle Bracket (2 per mailbox)	 NIGP: 45057252251 Mailbox Bracket For Type 1 multi and any double mount (use 2)	 NIGP: 45057253002 Bracket Extension Use 1 for a medium Mailbox Use 2 for a Large Mailbox	 NIGP: 45057258027 Part "B" Angle Bracket For Type 3 single and double
 NIGP: 80130598701 Wedge for Type 2	 NIGP: 45057250255 Plate Washer for Architecural and XL Mailboxes	 NIGP: 45057541653 Type 3 double mailbox bracket	 NIGP: 55083571053 Type 4 Mailbox Wedge
 NIGP: 55083571004 Type 4 Mailbox Socket	 NIGP: 80130238407 Type 2 Wedge Anchor	 NIGP: 45057259009 Wedge for Type 1 V-wing Socket	 NIGP: 45057256500 V-wing Socket for Type 1 Foundation

NIGP #	OBJECT MARKERS AND CONFORMABLE SHEETING
55008311759	Type 2 OM 4"x4" (3 Needed) for Type 3 Wing Channel Post
55008312906	Type 2 OM 6"x12" (1 needed) for Type 3 Wing Channel Post
80149872006	12" Conformable Reflective Yellow Sheeting for Flexible Posts


**NOTES:**

- Type 2 object marker in accordance with Traffic Engineering Standard Delineators & Object Markers.
- A light weight receptacle for newspaper delivery can be attached to mailbox posts if the receptacle does not touch the mailbox, present a hazard to traffic or delivery of the mail, extend beyond the front of the mailbox, or display advertising, except the publication title.

**BID CODES FOR CONTRACTS**




SHEET 4 OF 4


 Texas Department of Transportation		Maintenance Division Standard
<h2>NIGP PARTS LIST AND COMPATIBILITY</h2> <h3>MB(4)-21</h3>		
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT March 2004	CONT	SECT
REVISIONS	0883	02
2/2005 11/2009 4/2015		091
6/2005 1/2011	DIST	COUNTY
11/2006 7/2014	BMT	ORANGE
		SHEET NO.
		95

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.


DATE: 3/16/2023 7:34:35 PM  
 FILE: \\BMT\DESIGN\Projects\0883-02-091 FM 408\DGN\Standards\096-097.mbp(1).dgn




CASE 1. OFF TRAVEL WAY DELIVERY



CASE 2. BACK SIDE DELIVERY




CASE 3. DELIVERY NEAR RIGHT OF WAY LINE



TYPICAL PLAN

**GENERAL NOTES:**

- CASE 1 IS THE MOST COMMON METHOD.
- TURN OUT BEHIND MAILBOX FOR CASE 2 WILL NORMALLY BE ALLOWED FOR NATURAL TERRAIN THAT WILL SERVE AS AN ALL WEATHER SURFACE.
- ALL WEATHER DRIVEWAYS FOR CASE 3 MAILBOXES LOCATED AT THE RIGHT OF WAY LINE SHOULD NORMALLY BE PLACED IN CONJUNCTION WITH COUNTY ROADS OR OTHER CONNECTING COMMUNITY ROADS OR STREETS. WHEN 3 OR MORE MULTI-RACKS ARE ANTICIPATED, THE USE OF AN NDCBU IS RECOMMENDED. ONLY RURAL PATRONS LOCATED ON STATE MAINTAINED HIGHWAYS MAY HAVE A MAILBOX OR NDCBU SLOT ON TxDOT RIGHT OF WAY.



TYPICAL SECTION CASE 1

↑ MAIL DELIVERY VEHICLE TRAVEL DIRECTION

\* NDCBU MAY BE INSTALLED ON COUNTY ROAD ROW WITH APPROVAL OF COUNTY.



Guideline  
**MAILBOX SIDE ROAD PLACEMENT AND TURNOUTS**


**MBP(1)-22**

FILE: MBP-22.DGN	DN: VS	CK:	DW: VS	CK:
© TxDOT OCTOBER 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
12/2012 5/2014	DIST	COUNTY	SHEET NO.	
BMT	ORANGE		96	


DATE: 5/16/2023 7:34:35 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091 FM 408\DN\Standard\096-097.mbp(1) - 22.mbp  
 T:\BMT\DESIGN\Projects\0883-02-091 FM 408\DN\Standard\096-097.mbp(1) - 22.mbp

DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into other formats or for incorrect results or damages resulting from its use.


**MAILBOX PLACEMENT AT RURAL LOCATIONS**  
 THROUGH HIGHWAY SPEEDS  
 LESS THAN 55 MPH



**MAILBOX PLACEMENT AT RURAL LOCATIONS**  
 THROUGH HIGHWAY SPEEDS  
 GREATER THAN OR EQUAL TO 55 MPH



**CURB AND GUTTER MAILBOX INSTALLATION**



- NOTES:
1. A NON-TRAVERSABLE SURFACE MUST BE INSTALLED NEAR THE MAILBOX (NATURAL VEGETATION OR OTHER) IN THE BUFFER ZONE. ALTERNATIVELY, A BASE WITH A MINIMUM HEIGHT OF 2.5 INCHES MAY BE INSTALLED SO THAT THE EDGE OF THE MAILBOX DOES NOT EXTEND OUT MORE THAN 4 INCHES HORIZONTALLY BEYOND THE BASE.
  2. THE SIDEWALK WIDTH MAY BE REDUCED TO 4 FOOT FOR SHORT DISTANCES AROUND THE MAILBOX IF NEEDED.
  3. MAINTAIN A MINIMUM OF 5 FEET BETWEEN OBSTRUCTIONS IN THE PEDESTRIAN ACCESS ROUTE.

SHEET 2 OF 2



**MAILBOX PLACEMENT  
 CURBS & INTERSECTIONS**

**MBP(2)-22**

FILE: MBP-22.DGN	DN: VS	CK:	DW: VS	CK:
© TxDOT OCTOBER 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
12/2012	DIST	COUNTY	SHEET NO.	
5/2014	BMT	ORANGE		97

DATE: 3/16/2023 7:34:36 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNV\Standards\098\_dom1-20.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES		
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE			
									<b>INSTL DEL ASSM</b> (D-XX)SZ X (XXXX)XXX (XX) <b>NUMBER OF REFLECTORS</b> S = Single D = Double <b>COLOR OF REFLECTORS</b> W = White Y = Yellow R = Red <b>REFLECTOR UNIT SIZE</b> 1 or 2 <b>TYPE OF POST OR DELINEATOR</b> WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector <b>TYPE OF MOUNT</b> GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount	
<b>SHEETING</b>	Yellow, White or Red Type B or C reflective sheeting				<b>SHEETING</b>		Yellow, White or Red Type B or C Reflective Sheeting		<b>DIRECTION</b> If Required BI = Bi-Directional BR = Bi-Directional with red on back <b>INSTL OM ASSM</b> (OM-XX) (XXXX)XXX (XX) <b>TYPE OF OBJECT MARKER</b> 1, 2, 3, or 4 <b>NUMBER OF REFLECTORS OR DIRECTION</b> X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) <b>TYPE OF POST</b> WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing <b>TYPE OF MOUNT</b> GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic <b>DIRECTION</b> If Required BI = Bi-Directional	
<b>NOTE</b>	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				<b>POST TYPE</b>	WC	YFLX, WFLX	WC		YFLX, WFLX
					<b>MOUNT TYPE</b>	GND	GND, SRF	GND		GND, SRF

OBJECT MARKERS								
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4
<b>SHEETING</b>	Yellow-Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting			Red -Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting
<b>POST TYPE</b>	TWT	WC	WC	WFLX	TWT			TWT
<b>MOUNT TYPE</b>	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.	
DEVICE	GF1	GF2	CTB	W1-8		W1-6				
<b>SHEETING</b>	Yellow, White, Red			18"x 24" (Conventional)		24"x 30" (Conventional Oversize)	30"x 36" (Expressway)	36" x 48" (Freeway)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
<b>NOTE</b>	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			4'-0" or 7'-0"		7'-0" Only		7'-0"		
								1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).		

Texas Department of Transportation  
 Traffic Safety Division Standard

### DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION











#### D & OM(1)-20


FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	BMT	ORANGE	98	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:36 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\099\_dom2-20.dgn

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS		
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT	
GND	GND	SRF	WAS	WAP	GF 1	
						
	EMBEDDED	SURFACE MOUNT	STEEL	PLASTIC	CONCRETE TRAFFIC BARRIER (CTB)	
<b>NOTES</b> 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.			<b>NOTES</b> 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		<b>GENERAL NOTES</b> 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.	
TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS		
						
<b>NOTE</b> Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		<b>NOTE</b> Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		<b>NOTE</b> See general notes 1, 2 and 3.		



Texas Department of Transportation  
Traffic Safety Division Standard

## DELINEATOR & OBJECT MARKER INSTALLATION

### D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	BMT	ORANGE	99	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:42 PM  
 FILE: I:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\100\_dom3-20.dgn

### MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


### SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



**NOTE**

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

### SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



**NOTE**

At least one chevron pair is installed beyond the point of tangent in tangent section.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

### DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

**NOTES**

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation  
Traffic Safety Division Standard


## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

### D & OM(3)-20

FILE: dom3-20.dgn	DW: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	BMT	ORANGE	100	


DATE: 3/16/2023 7:34:42 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\101\_dom4-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**CROSSOVERS**




**DETAIL 1**

**FOR CULVERTS WITHOUT MBGF**




**DETAIL 2**

**FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES**




**DETAIL 3**

**TYPICAL APPLICATION OF DEAD END BARRICADE**



**DETAIL 4**

**TYPICAL DEAD END BARRICADE INSTALLATION**



**NOTES**

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

**DETAIL 5**

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(4) -20**

FILE: dom4-20.dgn	DW: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
3-15	DIST	COUNTY	SHEET NO.	
7-20	BMT	ORANGE	101	


**TWO-WAY, TWO LANE ROADWAY  
WITH REDUCED WIDTH APPROACH RAIL**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY  
WITH METAL BEAM GUARD FENCE (MBGF)**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY  
BRIDGE WITH NO APPROACH RAIL**



**LEGEND**

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &  
OBJECT MARKER  
PLACEMENT DETAILS**








**D & OM(5)-20**

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
7-20	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	102	


DATE: 3/16/2023 7:34:43 PM  
 FILE: T:\BMTDESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\102\_dom5-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:43 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\103\_domvia-20.dgn



OBJECT MARKERS SMALLER THAN 3 FT<sup>2</sup>



- NOTES**
- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
  - Mounting should be flush with top of attenuator. Minimum size 96" x 24".


**NOTES**

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.


<b>DELINEATOR &amp;          OBJECT MARKER          FOR VEHICLE IMPACT          ATTENUATORS          D &amp; OM(VIA) -20</b>			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT
© TXDOT December 1989	CONT	SECT	HIGHWAY
REVISIONS	0883	02	091 FM408
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	BMT	ORANGE	103
4-98 7-20			
20G			




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.  
 DATE: 3/16/2023 7:34:44 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GNVStandards\104\_pml-22.dgn





**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**



**DETAIL "B"**



**YIELD LINES**



**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

**NOTES**


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

**GENERAL NOTES**

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**  
Based on Traveled Way and Pavement Widths for Undivided Roadways

Traffic Safety Division Standard

**Texas Department of Transportation**

**TYPICAL STANDARD PAVEMENT MARKINGS**


**PM(1) - 22**

FILE:	pml-22.dgn	DN:	CK:	DW:	CK:
© TxDOT	December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS		0883	02	091	FM408
11-78	8-00 6-20	DIST	COUNTY	SHEET NO.	
8-95	3-03 12-22	BMT	ORANGE	104	
5-00	2-12				


22A

# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS**




**CENTERLINE & LANE LINES  
FOR FOUR LANE TWO-WAY ROADWAYS**




**DETAIL "A"**

**DETAIL "B"**

**DETAIL "C"**




**CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE**



**LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)**


Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.  
 See Note 3.



**REFLECTORIZED PROFILE  
PATTERN DETAIL**

USING REFLECTIVE PROFILE PAVEMENT MARKINGS

6" EDGE LINE, 6" CENTERLINE  
 OR 6" LANE LINE



**NOTES**


1. Edge lines should typically be 6" wide and the materials shall be specified in the plans.
2. Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

**GENERAL NOTES**


1. All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
3. Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**Type I (Top View)**



**Type II (Top View)**



**SECTION A**

**RAISED PAVEMENT MARKERS**




**POSITION GUIDANCE USING  
RAISED MARKERS  
REFLECTORIZED PROFILE  
MARKINGS  
PM(2) - 22**

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
4-77 8-00 6-20	DIST	COUNTY	SHEET NO.	
4-92 2-10 12-22	BMT	ORANGE	105	
5-00 2-12				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:45 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\106\_pm3-22.dgn



**LANE REDUCTION**

**NOTES**

- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.


ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	
45 MPH	775	L=WS
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

**GENERAL NOTES**


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




**TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE**




**TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY**



**TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP**



**TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS**



**DETAIL A**

**DETAIL B**

Texas Department of Transportation  
 Traffic Safety Division Standard

**TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 22**

FILE: pm3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
4-98 3-03 6-20	DIST	COUNTY	SHEET NO.	
5-00 2-10 12-22	BMT	ORANGE	106	
8-00 2-12				

# SUMMARY OF SMALL SIGNS

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		TEXT or 2EXT - • of Ext
							FRP - Fiberglass	1 or 2	UA-Universal Conc	P	TEXT or 2EXT - • of Ext	
							TWT - Thin-Wall		UB-Universal Bolt	P	BM - Extruded Wind Beam	
							10BWG - 10 BWG	SA-Slipbase-Conc	P	WC - 1.12 "/ft Wing		
							S80 - Sch 80	SB-Slipbase-Bolt	T - "T"	Channel		
								WS-Wedge Steel	U - "U"	EXAL- Extruded Alum Sign		
								WP-Wedge Plastic		Panels		
											TY - TYPE	
											TY N	
											TY S	
1	1	R1-1	STOP	36 x 36	X		10BWG	1	SA	P		
1	2	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X		S80	1	SA	P		
	2.1	M3-2	EAST <AUXILIARY SIGN>	24 x 12	X							
	2.2	D10-3	<3 DIGIT MILE MARKER>	10 x 36	X							
1	3	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
1	4	D1-2	(DESTINATION - 2 LINE)	66 x 30	X		S80	1	SA	U		
1	5	W3-1	SYMBOL - STOP AHEAD	30 x 30	X		10BWG	1	SA	P		
1	6	D1-1	(DESTINATION - 1 LINE)	54 x 12	X		S80	1	SA	T		
2	7	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
2	8	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
3	9	W1-4R	SYMBOL - REVERSE CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
	9.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
5	10	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
5	11	W1-4R	SYMBOL - REVERSE CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
	11.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
7	12	W1-4L	SYMBOL - REVERSE CURVE LEFT	36 x 36	X		10BWG	1	SA	P		
	12.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
7	13	W1-4R	SYMBOL - REVERSE CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
	13.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
7	14	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
7	15	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
	15.1	W1-8R	<CHEVRON RIGHT>	18 x 24	X							
7	16	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
	16.1	W1-8R	<CHEVRON RIGHT>	18 x 24	X							
7	17	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
	17.1	W1-8R	<CHEVRON RIGHT>	18 x 24	X							
8	18	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
	18.1	W1-8R	<CHEVRON RIGHT>	18 x 24	X							
8	19	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
	19.1	W1-8R	<CHEVRON RIGHT>	18 x 24	X							
8	20	W1-8L	<CHEVRON LEFT>	18 x 24	X		10BWG	1	SA	P		
	20.1	W1-8R	<CHEVRON RIGHT>	18 x 24	X							
9	21	W1-2R	SYMBOL - HORIZ CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
	21.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
9	22	W1-8R	<CHEVRON RIGHT>	18 x 24	X		10BWG	1	SA	P		
	22.1	W1-8L	<CHEVRON LEFT>	18 x 24	X							
9	23	W1-8R	<CHEVRON RIGHT>	18 x 24	X		10BWG	1	SA	P		
	23.1	W1-8L	<CHEVRON LEFT>	18 x 24	X							
9	24	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X		10BWG	1	SA	P		
	24.1	M3-4	WEST <AUXILIARY SIGN>	24 x 12	X							
	24.2	D10-3	<3 DIGIT MILE MARKER>	10 x 36	X							
9	25	W1-8R	<CHEVRON RIGHT>	18 x 24	X		10BWG	1	SA	P		
	25.1	W1-8L	<CHEVRON LEFT>	18 x 24	X							
9	26	W1-8R	<CHEVRON RIGHT>	18 x 24	X		10BWG	1	SA	P		
	26.1	W1-8L	<CHEVRON LEFT>	18 x 24	X							
10	27	W1-8R	<CHEVRON RIGHT>	18 x 24	X		10BWG	1	SA	P		
	27.1	W1-8L	<CHEVRON LEFT>	18 x 24	X							
10	28	W1-8R	<CHEVRON RIGHT>	18 x 24	X		10BWG	1	SA	P		
	28.1	W1-8L	<CHEVRON LEFT>	18 x 24	X							
10	29	I-2AT	(CITY NAME) CITY LIMIT	48 x 24	X		S80	1	SA	U		
10	30	I-2AT	(CITY NAME) CITY LIMIT	48 x 24	X		S80	1	SA	U		
10	31	W1-2L	SYMBOL - HORIZ CURVE LEFT	36 x 36	X		10BWG	1	SA	P		
	31.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
11	32	W1-4R	SYMBOL - REVERSE CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
	32.1	W13-1P	(SPEED) MPH <ADVISORY SPEED PLAQUE>	18 x 18	X							
12	33	W1-4R	SYMBOL - REVERSE CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
13	34	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
13	35	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
13	36	W2-1aTL	HIGHWAY INTERSECTION AHEAD	48 x 48	X		S80	1	SA	P		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 3/17/2023 3:24:03 PM  
 FILE: I:\BMT\DESIGN\Projects\0883-02-091 FM 408\DCGN\107-109\_SOSS.dgn

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:  
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
  - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
  - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



## SUMMARY OF SMALL SIGNS

### SOSS

FILE: sums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT: 0883	SECT: 02	JOB: 091	HIGHWAY: FM408
4-16	DIST: BMT	COUNTY: ORANGE	SHEET NO.: 107	

# SUMMARY OF SMALL SIGNS

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		TEXT or 2EXT - • of Ext
							FRP - Fiberglass TWT - Thin-Wall 10BWG - 10 BWG S80 - Sch 80	1 or 2	UA-Universal Conc UB-Universal Bolt SA-Slipbase-Conc SB-Slipbase-Bolt WS-Wedge Steel WP-Wedge Plastic	P = "Plain" T = "T" U = "U"	BM - Extruded Wind Beam WC - 1.12 "/ft Wing Channel EXAL - Extruded Alum Sign Panels	TY - TYPE TY N TY S
13	37	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X		10BWG	1	SA	P		
	37.1	M2-1	JCT <AUXILIARY SIGN>	21x 15	X							
14	38	D1-1	(DESTINATION - 1LINE)	54 x 12	X		S80	1	SA	T		
14	39	R2-1	SPEED LIMIT (SPEED)	30 x 36	X		10BWG	1	SA	P		
14	40	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X		10BWG	1	SA	P		
	40.1	M3-4	WEST <AUXILIARY SIGN>	24 x 12	X							
14	41	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X		10BWG	1	SA	U	2EXT	
	41.1	M3-3	SOUTH <AUXILIARY SIGN>	24 x 12	X							
	41.2	M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21x 15	X							
	41.3	M1-6F	<FM SHIELD> FARM ROAD (ROUTE #)	24 x 24	X							
	41.4	M3-1	NORTH <AUXILIARY SIGN>	24 x 12	X							
	41.5	M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21x 15	X							

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/17/2023 3:24:03 PM  
 FILE: I:\BMT\DESIGN\Projects\0883-02-091 FM 408\VDGN\107-109\_SOSS.dgn

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.  
<http://www.txdot.gov/>

**NOTE:**


1. Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
2. For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
3. For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



## SUMMARY OF SMALL SIGNS

### SOSS


FILE: sumsf6.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	ORANGE	<b>108</b>	



D1-2 8in LT-RT;


1.9" Radius, 0.8" Border, White on, Green;  
Standard Arrow Custom 12.0" X 7.1" 180°;  
"Vidor", ClearviewHwy-3-W;

1.9" Radius, 0.8" Border, White on, Green;  
"Orange", ClearviewHwy-3-W;  
Standard Arrow Custom 12.0" X 7.1" 0°;




I-2aT 6in;

1.5" Radius, 0.8" Border, White on, Green;  
"Bridge City", ClearviewHwy-5-W-R;  
"CITY LIMIT", ClearviewHwy-3-W;  
"POP 9546", ClearviewHwy-3-W;




I-2cT 6in;

1.5" Radius, 0.5" Border, White on, Green;  
"Bridge City 4", ClearviewHwy-5-W-R;



I-2cT 6in;

1.5" Radius, 0.5" Border, White on, Green;  
"Orangefield 3", ClearviewHwy-5-W-R;



*J. Horne*

03/17/2023

**SMALL  
SIGN  
DETAILS**



FHWA TEXAS DIVISION		SHEET NO. 109	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	ORANGE	
CONTROL	SECTION	JOB	HIGHWAY NO.
0883	02	091	FM408



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:46 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\110\_smdgen.dgn

### SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


**Post Type**  
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))  
 TWT = Thin-Walled Tubing (see SMD(TWT))  
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))  
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

**Number of Posts (1 or 2)**

**Anchor Type**  
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))  
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))  
 WS = Wedge Anchor Steel - (see SMD(TWT))  
 WP = Wedge Anchor Plastic (see SMD(TWT))  
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))  
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))



**Sign Mounting Designation**  
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))  
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))  
 IF REQUIRED  
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))  
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))  
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))

### REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT






To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


### SIGN LOCATION



No more than 2 sign posts should be located within a 7 ft. circle.



### TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.


Sign clamps may be either the specific size clamp or the universal clamp.

Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"


### SIGNS WITH PLAQUES



### CURB & GUTTER OR RAISED ISLAND



### RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



\* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:  
<http://www.txdot.gov/publications/traffic.htm>




## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS SMD(GEN)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0883	02	091	FM408
		DIST	COUNTY		SHEET NO.
		BMT	ORANGE		110

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:46 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091.FM.408.DGN\Standards\111.smds1.dgn

## TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



### NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. [http://www.txdot.gov/business/producer\\_list.htm](http://www.txdot.gov/business/producer_list.htm) The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

### GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
  - 10 BWG Tubing (2.875" outside diameter)
    - 0.134" nominal wall thickness
    - Seamless or electric-resistance welded steel tubing or pipe
    - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
    - Other steels may be used if they meet the following:
      - 55,000 PSI minimum yield strength
      - 70,000 PSI minimum tensile strength
      - 20% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
    - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
    - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
  - Schedule 80 Pipe (2.875" outside diameter)
    - 0.276" nominal wall thickness
    - Steel tubing per ASTM A500 Gr C
    - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
      - 46,000 PSI minimum yield strength
      - 62,000 PSI minimum tensile strength
      - 21% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
    - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
    - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

### ASSEMBLY PROCEDURE


#### Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

#### Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

### CONCRETE ANCHOR



Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.















 Texas Department of Transportation  
Traffic Operations Division

## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS		CONT	SECT	JOB
			0883	02	091
			DIST	COUNTY	SHEET NO.
		BMT	ORANGE	111	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:47 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\112\_smds2.dgn



All dimensions are in english unless detailed otherwise.

GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA
 

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.




**Texas Department of Transportation**  
 Traffic Operations Division

**SIGN MOUNTING DETAILS**  
**SMALL ROADSIDE SIGNS**  
**TRIANGULAR SLIPBASE SYSTEM**  
**SMD(SLIP-2)-08**



© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0883	02	091	FM408
		DIST	COUNTY	SHEET NO.	
		BMT	ORANGE	112	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/16/2023 7:34:47 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\GN\Standards\113\_smds3.dgn




Splices shall only be allowed behind the sign substrate.




\* Additional stiffener placed at approximate center of signs when sign width is greater than 10'.



Detail E




Detail A




Detail D

EXTRUDED ALUMINUM SIGN WITH T BRACKET



EXTRUDED ALUMINUM SIGN With T Bracket



Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details  
 See Detail E for clamp installation

GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG       | 1          | 16 SF          |
| 10 BWG       | 2          | 32 SF          |
| Sch 80       | 1          | 32 SF          |
| Sch 80       | 2          | 64 SF          |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)



**SIGN MOUNTING DETAILS  
 SMALL ROADSIDE SIGNS  
 TRIANGULAR SLIPBASE SYSTEM  
 SMD (SLIP-3) - 08**




© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0883	02	091	FM408
		DIST	COUNTY	SHEET NO.	
		BMT	ORANGE	113	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023 7:34:48 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\114\_tsr3-13.dgn

## REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

## REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

## GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.


<http://www.txdot.gov/>

				Traffic Operations Division Standard	
<h3>TYPICAL SIGN REQUIREMENTS</h3>					
<h3>TSR(3) - 13</h3>					
FILE:	tsr3-13.dgn	DN:	TxDOT	CK:	TxDOT
©TxDOT	October 2003	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS		0883	02	091	FM408
12-03	7-13	DIST:	COUNTY:	SHEET NO.	
9-08		BMT	ORANGE	114	

DATE: 3/16/2023 7:34:48 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\115\_tsr4-13.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

### REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

### REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR WARNING SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR SCHOOL SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

### GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

#### ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

#### DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS

### TSR(4) - 13


FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0883	02	091	FM408				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		BMT	ORANGE	115					




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 3/16/2023 7:34:49 PM  
 FILE: T:\BMT\DESIGN\Projects\0883-02-091\_FM\_408\DGN\Standards\116\_tsr5-13.dgn

### ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	


CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT

**NOTE**

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.


The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:  
<http://www.txdot.gov/>

### SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5




EXIT ONLY PANEL

### MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

- NOTE:**
- Sheeting for legend, symbols, and borders must be cut at panel joints.
  - Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".




SCREW ATTACHMENT




NUT/BOLT ATTACHMENT

- NOTE:**
- Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

### ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.



## TYPICAL SIGN REQUIREMENTS

### TSR (5) - 13

FILE: tsr5-13.dgn	DW: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	BMT	ORANGE	116	

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**  
0883-02-091

**1.2 PROJECT LIMITS:**

From: FM 105, SOUTH

To: FM 1442

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 30.0757995, (Long) -93.8555077

END: (Lat) 30.0346979, (Long) -93.8508415

**1.4 TOTAL PROJECT AREA (Acres):** ~11.5

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** ~1.6

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

SAFETY TREAT FIXED OBJECTS, & WIDEN  
PAVED SHOULDERS TO 5 FT OR LESS

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
0511 Cow Bayou Tidal	
0511B Coon Bayou	

\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**



Sheet 1 of 2

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				119
STATE	STATE DIST.	COUNTY		
TEXAS		ORANGE		
CONT.	SECT.	JOB	HIGHWAY NO.	
0883	02	091	FM 408	

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

**T / P**

- Sediment Trap
  - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
  - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
  - Not required (<10 acres disturbed)
  - Required (>10 acres) and implemented.
    - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
    - 3,600 cubic feet of storage per acre drained
  - Required (>10 acres), but not feasible due to:
    - Available area/Site geometry
    - Site slope/Drainage patterns
    - Site soils/Geotechnical factors
    - Public safety
    - Other: \_\_\_\_\_

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

**2.9 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				120
STATE	STATE DIST.	COUNTY		
TEXAS		ORANGE		
CONT.	SECT.	JOB	HIGHWAY NO.	
0883	02	091	FM 408	

**NOTES:**

For projects disturbing 5 or more acres, place laminated copies of the TxDOT and Contractor Construction Site Notices and the TxDOT and Contractor Notices of Intent on the SW3P Notification Board.


For projects disturbing between 1 and 5 acres, place laminated copies of the TxDOT and Contractor Construction Site Notices on the SW3P Notification Board.

For projects with an Individual Permit with the US Army Corp of Engineer, place a laminated copy of the Permit Certificate on the Notification Board.

Center all postings.

Notification Boards are to be constructed from chloroplast and placed at a location within the right-of-way but outside the clear zone as directed by the Engineer. This work will not be paid for directly, but will be considered subsidiary to other items.

CSN - Construction Site Notice, Large for projects greater than 5 acres, Small for projects greater than 1 and less than 5 acres.




2.3" Radius, 0.9" Border, White on Blue;  
 [TxDOT PROJECT] E Mod; [SW3P] E Mod; [INFORMATION] E Mod;




**BEAUMONT DISTRICT  
 SW3P  
 NOTIFICATION BOARD  
 DETAIL  
 (SW3P-B)**

REVISIONS © 2022	FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.		SHEET NO. 119
	STATE	DISTRICT	COUNTY	
	TEXAS	BMT	ORANGE	
	CONTROL	SECTION	JOB	HIGHWAY NO.
	0883	02	091	FM408

DATE: 3/17/2023  
 FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DGN\Standards\120-122 ec916.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PLAN VIEW




SECTION A-A  
EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B  
EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW



SECTION C-C


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
  - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
  - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
  - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
  - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
  - CL-DI EROSION CONTROL LOG AT DROP INLET
  - CL-CI EROSION CONTROL LOG AT CURB INLET
  - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

**SEDIMENT BASIN & TRAP USAGE GUIDELINES**

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

**Log Traps:** The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

**GENERAL NOTES:**


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<i>Design Division Standard</i>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DW: TxDOT	CK: KM	DS: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0883	02	091
	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	120


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/17/2023  
 FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DGN\Standards\120-122 ec916.dgn



**EROSION CONTROL LOGS ON SLOPES  
 STAKE AND TRENCHING ANCHORING**


CL-SST



**END SECTION RAP DETAIL**


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

\* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:  
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;  
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART





**EROSION CONTROL LOGS ON SLOPES  
 STAKE AND LASHING ANCHORING**

CL-SSL




**STAKE AND TRENCHING ANCHORING DETAIL**

CL-SST




**STAKE AND LASHING ANCHORING DETAIL**

CL-SSL



LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

**TRENCH DEPTH TABLE**



**STAKE NOTCH DETAIL**


Texas Department of Transportation  
 Design Division Standard

**TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES  
 EROSION CONTROL LOG  
 EC(9) - 16**

FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0883	02	091	FM408
DIST	COUNTY		SHEET NO.	
BMT	ORANGE		121	




DATE: 3/17/2023  
 FILE: T:\BMTDESIGN\Projects\0883-02-091 FM 408\DGN\Standards\120-122 ec916.dgn  
 DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**EROSION CONTROL LOG AT DROP INLET**

CL-DI



**EROSION CONTROL LOG AT CURB INLET**


CL-CI



**EROSION CONTROL LOG AT CURB INLET**


CL-CI

NOTE:  
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



**EROSION CONTROL LOG AT CURB & GRADE INLET**

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0883	02	091
	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	122

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- 1. TxDOT - Beaumont District

- 2. City of Bridge City

No Action Required       Required Action  
Action No.

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
2. Comply with the SW3P and revise when necessary to control pollution or as required by the Engineer.
3. This project disturbs more than one but less than five acres. The Contractor is required to post a Construction Site Notice in a manner which meets TCEQ Permit 150000 requirements and conforms to TxDOT standards. Contractor shall provide a copy of the Construction Site Notice to any adjacent non-TxDOT MS4 Operator. Contractor is responsible for acquiring permits from any adjacent non-TxDOT MS4 Operator. Contact the Beaumont District Construction Office with questions regarding TCEQ Permit 150000.
4. Take measures to prevent construction materials and debris including, but not limited to wastewater (i.e., cooling liquid, etc.) associated with concrete removal from entering any inlets, ditches, or waterways.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions, including Regional conditions for the State of Texas, associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required: Permit # \_\_\_\_\_
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1. Maintain a neat and clean worksite next to the water and do not allow any debris to fall into the water.
2. Comply with "Work In or Near Waters/Wetlands Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

<b>Erosion</b>	<b>Sedimentation</b>	<b>Post-Construction TSS</b>
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	

**III. CULTURAL RESOURCES**

No Action Required       Required Action

Action No.

1. Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

**IV. VEGETATION RESOURCES**

No Action Required       Required Action

Action No.

1. Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.
2. Comply with "Vegetation and Habitat Impacts: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

No Action Required       Required Action

Action No.

1. If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own. Do not impact dens of animals if found.
2. If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEQC for guidance.
3. Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
4. Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and (TPW) Code Section 64.002. For compliance with MBTA and TPW Code, bridge demolition, clearing of vegetation, and tree trimming activities are to be scheduled from October 1 to February 14 (outside of migratory bird nesting season). Contractor is responsible for securing a qualified biologist to conduct a nest survey for any bridge demolition, tree trimming, or vegetation clearing that occurs during migratory bird nesting season. The qualified biologist must submit a survey protocol for approval by District environmental staff prior to construction. A nesting survey will remain valid up to five days. Any activity not completed within 5 days of a nesting survey will require another survey. Migratory bird nesting season is from February 15 to September 30. No removal of active nests is allowed during migratory bird nesting season; therefore, any structure or vegetation containing an active nest may not be disturbed, cleared, or trimmed. No removal of inactive nests is allowed during migratory bird nesting season except by an approved, qualified biologist. Contractor is responsible for ensuring all nests on bridge structures are removed prior to the start of nesting season. The full TxDOT MBTA guidance may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/toolkit/350-01-gui.pdf>
5. Resource specific BMPs (Section I) and Pavement BMPs (Section II, F) from the 'Updated Best Management Practices (BMPs) for TxDOT Maintenance Activities' guidance under the TxDOT Maintenance Program EA shall be reviewed and implemented where appropriate. The maintenance EA BMPs may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/080-01-bmp.pdf>

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

No Action Required       Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances
- \* Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
None				

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

Action No.

1. Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous materials or contamination is noted during construction.
2. Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.

**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required       Required Action

Action No.

1. Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.

*Carol Crapanzano*  
APPROVED BY  
03/23/2023  
DATE  
DISTRICT ENVIRONMENTAL DEPARTMENT



**ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC**

FILE: epic.dgn	DN: TxDOT	CK: AM	DW: VP	CK: AR
© TxDOT February 2019	CONT	SECT	JOB	HIGHWAY
	0883	02	091	FM 408
	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	123	