GENERAL TITLE SHEET GENERAL NOTES

ESTIMATE & QUANTITY BRIDGE REPAIR LAYOUT (NBI: 160130010008098) SUMMARY OF REPAIRS (NBI: 160130010008098) BRIDGE REPAIR LAYOUT (NBI: 160130010008099)
SUMMARY OF REPAIRS (NBI: 160130010008099) QUANTITY SUMMARY

\* BC (1)-21 THRU BC (12)-21 23 \* TCP (1-1)-18 24 \* TCP (1-2)-18 \* TCP (1-3)-18 25 \* TCP (2-1)-18 26 \* TCP (2-2)-18 28 \* TCP (2-3)-18 \* WZ (RS)-22 30-31 \* SRR

BRIDGE DETAILS STONE RIPRAP DETAILS

32 CLEANING AND SEALING EXISTING BRIDGE JOINTS

ENVIRONMENTAL ISSUES STANDARDS

34-35 ENVIRONMENTAL PERMITS, ISSUES, AND COMMITMENTS \* FC (1)-16

> RMANDO BOSQUEZ 91354 SS JONAL ENGINE

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A " \* " HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

4/27/2023 Armando Bosquez DATE NAMEB23CC13362472...

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY2022)

0100 08 105 US 181 SHEET NO.

DESIGN SPEED - 55 MPH

NO RAS REVIEW REQUIRED RURAL PRINCIPAL ARTERIAL

PM- PREVENTATIVE MAINTENANCE

#### PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO. BR 2B23 (115)

US 181 BEE COUNTY


CSJ: 0100-08-105

NET LENGTH OF ROADWAY: 0.00 FT.= 0.000 MI. NET LENGTH OF BRIDGE 120.00 FT.= 0.023 MI. NET LENGTH OF PROJECT: 120.00 FT.= 0.023 MI.

LIMITS: US 181 AT POESTA CREEK

FOR THE CONSTRUCTION OF BRIDGE MAINTENANCE

CONSISTING OF CONCRETE RIPRAP REPAIR, REGRADING, CLEANING AND SEALING EXISTING BRIDGE JOINTS, SEALING CONCRETE CRACKS, AND STONE RIPRAP PROTECTION



EQUATIONS: NONE
RAILROAD CROSSINGS: NONE

4/28/2023

Valente Olivarez EER

-303F64E8A9B44E0...

RECOMMENDED FOR LETTING: 4/28/2023

-5975450A18CC435...

PROJ. NO. LET DATE:

KARNES 181 COUNTY: HWY: US

Paula Sales-Evans, P.E. (TION

County: BEE Control: 0100-08-105

Highway: US 181

#### **GENERAL NOTES:**

Find, for your information and convenience, tools such as forms, software, materials, and various other information provided by the Department at <a href="https://www.txdot.gov/business.html">https://www.txdot.gov/business.html</a>. Please note that these tools are updated periodically, and your attention is directed to the latest edition.

In the event of a called evacuation, emergencies, impending adverse weather or as directed, do not perform any work without written authorization. The District reserves the right to suspend all work in support of evacuations or emergencies occurring from other parts of the state. Any work performed, other than work directed by the Department, is unauthorized work in accordance with Item 5

Sweep, clean and remove any construction waste, surplus materials or debris from the roadway and right of way at the end of each day unless otherwise approved. The work performed will not be measured or paid for directly but will be subsidiary to pertinent Items.

Contractor questions on this project are to be addressed to the following individual(s):

Nick Novosad, P.E. Nick.Novosad@txdot.gov
Roberto Jimenez, P.E. Roberto.A.Jimenez@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

#### ITEM 2

It is recommended that prospective bidders examine the specified work locations with the Engineer to view the nature of the work, the need for close coordination with the various utilities, traffic control considerations, and other factors influencing the prosecution of the work.

#### ITEM 5

Field verify all dimensions and notify Engineer prior to initiating any work.

General Notes

**County: BEE Control:** 0100-08-105

Highway: US 181

Verify the locations of utilities, underground or overhead, shown within the limits of the right-of-way. Adhere to OSHA Standards when working within the vicinity of overhead power lines. Coordinate with the utility companies and notify the Engineer of any possible conflicts. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The 811 call services for a utility location does not include TxDOT facilities. Contact the Corpus Christi District Traffic Signal Supervisor (Juan Marfil 361-808-2501 or 361-336-7851) or email (<u>CRP\_Utility\_Locate@txdot.gov</u>) for coordination with TxDOT underground lines.

Notify the Engineer immediately of utility conflicts in accordance with Item 5.6. Refer to Item 4.5 for consideration of differing site conditions.

The responsibility for the construction surveying on this contract will be in accordance with Item 5.9.3, "Method C".

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

#### ITEM 6

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.


Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. <a href="https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html">https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html</a> for clarification on material categorization.

#### ITEM 7

The work performed for Item 7.2.4, "Public Safety and Convenience" will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The total disturbed area for this project is less than 1 acres. The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities



General Notes

FED.RD. DIV.NO.	FEDER	AL AID PROJECT NO.	H:	IGHWAY NO.
6			U:	5 181
STATE	DISTRICT	COUNTY		
TEXAS	CRP	BEE		SHEET
CONTROL	SECTION	JOB		NO.
0100	08	105		2

County: BEE Control: 0100-08-105

Highway: US 181

shown on the plans. The Contractor is to obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer.

Comply with the Texas Aggregate Quarry and Pit Safety Act for waste areas or material source areas resulting from this project.

No significant traffic generator events identified.

#### ITEM 8

Prepare the progress schedule using the Critical Path Method (CPM). Submit (2) two 11" x 17" hard copies and an electronic file of the original or updated progress schedule. Submit the original progress schedule seven (7) days before the Preconstruction Conference.

Submit an updated progress schedule as directed to show proposed major changes, changes affecting compliance with the contract requirements, or changes affecting the critical path/controlling item of work.

Working days will be computed and charge in accordance with Article 8.3.1.4, "Standard Workweek".

Work above traffic is not allowed.

Nighttime work is allowable.

Notify the Engineer at least 48 hours in advance of weekend or nighttime work.

#### ITEM 9

Monthly progress payments will be made for items of work completed by the 28th day of each month. Any work completed after the 28th will be included for payment in the subsequent monthly progress estimate.

Submit signed request for compensation of material-on-hand (MOH), including any requests from subcontractors, suppliers, or fabricators for MOH, at least two (2) working days prior to the end of the month on the Departments approved forms.

#### **ITEM 354**

Any RAP remaining from the contract is to remain with the Contractor.

General Notes

County: BEE Control: 0100-08-105

Highway: US 181

#### **ITEM 429**

Areas to be repaired at each location shall be repaired in accordance with the Department's Concrete Repair Manual. The Contractor must prepare and submit formal procedures outlining repair plans and which proprietary implementation, so the Engineer has sufficient time to review. The Engineer must approve in writing any procedures that differ form those in the Concrete Repair Manual or materials that are not include in one of TxDOT's MPLS materials they plan to utilize. Submit the package a minimum of two weeks prior to performing repair.

A hard copy of the Department's Concrete Repair Manual shall be on-hand whenever concrete repairs are being performed.

For Vertical and Overhead repairs use preapproved Type C Repair Material.

Provide containment for repair materials to prevent materials from falling into the water.

Remove any repair materials that do fall into the water.

#### **ITEM 438**

Provide for approval a method of cleaning and sealing joints to prevent any materials from falling through the joint when working over water or traffic. The method used and work performed will not be measured or paid for directly but will be subsidiary to pertinent Items.

Saw cut of asphalt concrete pavement and concrete approach slabs shall be subsidiary regardless of the depth.

Submit installation instructions for "Foam Compression Seal" expansion joint seal for review.


#### **ITEM 500**

"Materials on Hand" payments are not considered when determining partial payments.

#### **ITEM 502**

Furnish additional barricades, signs, and traffic handling as directed. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Traffic control for daytime lane closures shall be in accordance with applicable standards. Traffic control shall include temporary rumble strips in accordance with WZ (RS)-16.



FED.RD. DIV.NO.	FEDER/	AL AID PROJECT NO.	HIGHWAY NO.		
6			U:	S 181	
STATE	DISTRICT	COUNTY			
TEXAS	CRP	BEE		SHEET	
CONTROL	SECTION	JOB		NO.	
0100	08	105		3	

County: BEE Control: 0100-08-105

Highway: US 181

When advanced warning flashing arrow panels are specified, furnish one (1) standby unit in good condition at the job site for immediate use.

Attach stop/slow paddle to a staff with a minimum length of 6 feet to the bottom of the sign.

The use of a pilot vehicle in conjunction with flaggers will be permitted. If used, provide positive and unrestricted communication between the driver of the pilot vehicle and the flaggers. The work performed will not be measured or paid for directly but will be subsidiary to pertinent Items.

Contractors attention is directed to a construction speed zone, signage is subsidiary to Item 502.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

All items marked as optional on all traffic control standards shall be required unless otherwise approved by an Engineer.

Trail vehicle shall be required on all mobile traffic control operations.

#### **ITEM 504**

No field office will be required for this project.

#### **ITEM 506**

Designate in writing a Contractor Responsible Person (CRP) for implementing, maintaining, and reviewing environmental requirements.

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7.

#### **ITEM 780**

Repair cracks in concrete structures by epoxy injection.

General Notes

County: BEE Control: 0100-08-105

Highway: US 181

#### ITEM 6001

Furnish the portable changeable message signs displaying the correct message at least seven (7) days prior to beginning work or as directed.

The Contractor's Responsible Person (CRP) will maintain full control of messages at all times.

The Engineer will provide the sign message text to use at each sign.

A minimum of 2 PCMS will be required. However, additional units may be necessary depending on the work in progress.

Standby time will not be measured or paid for directly but will be subsidiary to pertinent Items.

Portable changeable message signs may be moved, and message changed at any time as deemed necessary by the Engineer. This will be considered subsidiary to Item 6001.

#### **ITEM 6038**

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

Place pavement markings no later than 14 calendar days after the placement of the surface. When inclement weather prohibits placement of the markings, the 14-day period may be extended until weather permits proper application.

Place pavement markings under these items in accordance with details shown on the plans, the latest "Texas Manual on Uniform Traffic Control Devices", or as directed.


#### **ITEM 6185**

A minimum of 2 TMAS will be required. However, additional units may be necessary depending on the work in progress

Provide manufacturer's curb weight or certified scales weight ticket to the Engineer for approval.

TMAs paid by the each shall be available for the duration of the project. Relocation of TMAs will be as directed by the Engineer, and will be considered subsidiary to this Item.





	FED.RD. DIV.NO.	FEDER/	AL AID PROJECT NO.	H.	IGHWAY NO.
	6			U:	S 181
n	STATE	DISTRICT	COUNTY		
	TEXAS	CRP	BEE		SHEET
	CONTROL	SECTION	JOB		NO.
	0100	08	105		4



### **Estimate & Quantity Sheet**

**CONTROLLING PROJECT ID** 0100-08-105

**DISTRICT** Corpus Christi **HIGHWAY** US 181


**COUNTY** Bee

Report Created On: May 18, 2023 11:47:43

		CONTROL SECTIO	N JOB	0100-0	8-105		
		PROJE	CT ID	A0019	1067		
		со	UNTY	Bee		TOTAL EST.	TOTAL FINAL
		HIG	HWAY	US 1	.81		1
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	104-6010	REMOVING CONC (RIPRAP)	CY	16.000		16.000	
	132-6005	EMBANKMENT (FINAL)(ORD COMP)(TY C)	CY	115.000		115.000	
	401-6001	FLOWABLE BACKFILL	CY	30.000		30.000	
	429-6011	CONC STR REPR(REMOV AND REPL WINGWALL)	CY	20.000		20.000	
	432-6008	RIPRAP (CONC)(CL B)(RR8&RR9)	CY	24.000		24.000	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	125.000		125.000	
	438-6001	CLEANING AND SEALING EXISTING JOINTS	LF	159.000		159.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	3.000		3.000	
	752-6015	TREE AND BRUSH REMOVAL	AC	0.600		0.600	
	760-6002	DITCH CLEAN / RESHAPING(CU YD IN PLACE)	CY	60.000		60.000	
	780-6002	CNC CRACK REPAIR (DISCRETE)(INJECT)	LF	10.000		10.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	41.000		41.000	
	6185-6002	TMA (STATIONARY)	DAY	34.000		34.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Corpus Christi	Bee	0100-08-105	5





	SUMMARY OF REPAIRS (US 181 NB FR)										
REPAIR NO.	ITEM	BID ITEM DESCRIPTION	UNIT	QUANTITY	REPAIR DESCRIPTION/ LOCATOR	DETAILS/ NOTES					
0)	0104 6010	REMOVING CONC (RIPRAP)	CY	16	REMOVE FAILED RIPRAP SW BANK						
02	0132 6005	EMBANKMENT (FINAL) (ORD COMP) (TY C)	CY	115	BUILD UP ERODED SW BANK						
03	0401 6001	FLOWABLE BACKFILL	CY	10	FILL VOIDS OF ROADWAY AND ABUTMENT						
<b>Ø</b>	0429 6011	CONC STR REPR (REMOV AND REPL WINGWALL)	CY	20	REMOVE AND REPLACE SW WINGWALL						
<b>©</b> 5	0432 6008	RIPRAP (CONC) (CL B) (RR8&RR9)	CY	24	REPLACE CONC RR8						
66	0432 6033	RIPRAP (STONE PROTECION) (18 IN)	CY	100	PLACE ALONG BANKS						
07	0438 6001	CLEANING AND SEALING EXISTING JOINTS	LF	84	CLEAN AND SEAL ALL EXPANSION JOINTS	SEE CLEANING AND SEALING EXISTING BRIDGE JOINTS SHEET					
<b>®</b>	0752 6015	TREE AND BRUSH REMOVAL	AC	0.3	BOTH SIDES OF CHANNEL						
<b>9</b>	0780 6003	CNC CRACK REPAIR (DISCRETE) (INJECT)	LF	4	BEAMS 2 & 6						

SUMMARY OF REPAIRS

US 181 NB FR


POESTA CREEK 160130010008098





- Layout, stations, and elevations shown are based on as-built plans. Copies of available portions of as-built plans may be provided upon request.
- Repair locations and quantities are based on Field Survey dated (06/2022). Current conditions may vary. Field verify locations and extent of repairs in the presence of the Engineer prior to ordering materials.
- 3. See stone riprap detail sheet for repair @2

REPAIR CALL-OUT LEGEND






US 181 SB FR

LAYOUT

POESTA CREEK 160130010008099




	SUMMARY OF REPAIRS (US 181 SB FR)											
REPAIR NO.	ITEM	BID ITEM DESCRIPTION	UNIT	QUANTITY	REPAIR DESCRIPTION/ LOCATOR	DETAILS/ NOTES						
<b>(</b> )	0401 6001	FLOWABLE BACKFILL	CY	20	FILL VOIDS IN NW & SE CORNER RIPRAP							
<b>@</b>	0432 6033	RIPRAP (STONE PROTECION) (18 IN)	CY	25	NORTH BANK & NW EDGE OF RIPRAP	SEE STONE RIP RAP DETAIL SHEET						
03	0438 6001	CLEANING AND SEALING EXISTING JOINTS	LF	75	CLEAN AND SEAL ALL EXPANSION JOINTS	SEE CLEANING AND SEALING EXISTING BRIDGE JOINTS SHEET						
<b>@</b>	0752 6015	TREE AND BRUSH REMOVAL	AC	0.3	BOTH SIDES OF CHANNEL							
<b>©</b> 5	0760 6002	DITCH CLEAN / RESHAPING (CU YD IN PLACE)	CY	60	CLEAN AND RESHAPE BOTH SIDES OF CHANNEL							
69	0780 6002	CNC CRACK REPAIR (DISCRETE) (INJECT)	LF	6	BEAMS 2 & 3 FROM EAST							

SUMMARY OF REPAIRS


US 181 SB FR

POESTA CREEK 160130010008099



		PROJECT QUANTITY SUMMARY		
ITEM ID.	ITEM	BID ITEM DESCRIPTION	UNIT	QUANTITY
01	0104 6010	REMOVING CONC (RIPRAP)	CY	16
02	0132 6005	EMBANKMENT (FINAL) (ORD COMP) (TY C)	CY	115
03	0401 6001	FLOWABLE BACKFILL	CY	30
04	0429 6011	CONC STR REPR (REMOV AND REPL WINGWALL)	CY	20
05	0432 6008	RIPRAP (CONC)(CL B)(RR8&RR9)	CY	24
06	0432 6033	RIPRAP (STONE PROTECION) (18 IN)	CY	125
07	0438 6001	CLEANING AND SEALING EXISTING JOINTS	LF	159
08	0752 6015	TREE AND BRUSH REMOVAL	AC	0.6
09	0760 6002	DITCH CLEAN / RESHAPING (CU YD IN PLACE)	CY	60
10	0780 6002	CNC CRACK REPAIR (DISCRETE) (INJECT)	LF	10

#### QUANTITY SUMMARY



#### BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

#### WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

#### COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

# THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




Safety Division Standard

# BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC(1)-21

				_			
ILE:	bc-21.dgn	DN:	TxDOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CON	SECT	JOB		HIO	GHWAY
4-03	REVISIONS 7-13	010	0 08	105		US	181
9-07	8-14	DIS	r	COUNTY			SHEET NO.
5-10	5-21	CR	>	BEE			11



 $\sharp$  May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

#### BEGIN T-INTERSECTION WORK ZONE ★ ★ G20-9TP ★ ★ R20-5T FINES DOUBL X R20-5aTP MORKERS ARE PRESENT ROAD WORK ← NEXT X WILES X X G20-2bT WORK ZONE G20-1bTI INTERSECTED 1000' - 1500' - Hwy 1 Block - City 1000'-1500' - Hwy 1 Block - City ROADWAY $\Rightarrow$ ROAD WORK G20-1bTR NEXT X MILES => WORK ZONE G20-2bT \* \* Limit BEGIN \* \* G20-9TP ZONE TRAFFI G20-6T \* \* R20-5T FINES DOUBLE X X R20-5aTP WHEN WORKERS ROAD WORK G20-2

#### CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

#### TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING 1,5,6

#### SIZE

#### Posted Expressway/ Speed Freeway MPH 30 48" × 48' 35

80

SPACING

Sign△

Spacing

"X"

1000 <sup>2</sup>

Sign onventional Number or Series CW20' CW21 CW22 48" x 48" CW23 CW25 CW1, CW2, CW7. CW8. 48" x 48' 36" x 36' CW9, CW11 CW14 CW3, CW4, CW5, CW6, 48" x 48' 48" x 48' CW8-3, CW10, CW12

\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

 $\triangle$  Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

#### GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design

#### SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS X X G20-9TP SPEED STAY ALERT ROAD LIMIT R4-1 DO NOT PASS appropriate: OBEY TRAFFIC **X X** R20-5T WORK WARNING \* \* G20-5 ROAD WORK CW1-4L AHEAD DOUBLE SIGNS € ★ R20-5aTP ME PRESENT CW20-1D ROAD STATE LAW TALK OR TEXT LATER CW13-1P ROAD ★ ★ G20-6T R2-1 X > WORK WORK G20-10T \* \* R20-3T \* \* AHEAD AHEAD Type 3 Barricade or WPH CW13-1P CW20-1D channelizing devices $\Diamond$ $\Diamond$ $\Diamond$ $\Leftrightarrow$ $\Rightarrow$ $\Leftrightarrow$ $\Rightarrow$ $\Rightarrow$ Beginning of NO-PASSING SPEED END G20-2bT \* R2-1 LIMIT line should $\langle \rangle \times \times$ coordinate ROAD WORK then extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional with sign ROAD WORK AHEAD"(CW20-1D)signs are placed in advance of these work areas to remind drivers they are still G20-2 X X location NOTES within the project limits. See the applicable TCP sheets for exact location and spacing of signs and

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS

★ ★G20-9TP ZONE STAY ALERT BEGIN ROAD WORK NEXT X MILES OBEY SPEED TRAFFI × + G20-5T ROAD LIMIT ROAD ROAD ¥ ¥R20-5T FINES SIGNS WORK CLOSED R11-2 WORK DOUBLE STATE LAW √2 MILE TALK OR TEXT LATER AHEAD X X R20-5aTP SHEN SHEEN ARE PRESENT \* \*G20-6T Type 3 R20-3T R2-1 G20-10 CW20-1D Barricade or CW13-1P CW20-1E channelizina devices -CSJ Limi Channelizing Devices  $\Rightarrow$ SPEED R2-1 END LIMIT END | ROAD WORK WORK ZONE G20-26T \* \* G20-2 \* \*

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer.

- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2b1 shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at the end of the work zone.

		LEGEND
	I	Type 3 Barricade
c	0	Channelizing Devices
	<b>h</b>	Sign
	x	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

#### SHEET 2 OF 12

Texas Department of Transportation

Traffic Safety Division Standard


#### BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

				_			
ILE:	bc-21.dgn	DN: T	×DOT	ck: TxDOT	DW:	TxDOT	ск: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		н	SHWAY
REVISIONS		0100	08	105		US	181
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	CRP	BEE			12	

#### TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



#### GUIDANCE FOR USE:

#### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

#### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

#### GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:

40 mph and greater 0.2 to 2 miles

35 mph and less

0.2 to 2 miles

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to:
  A. Law enforcement.
  - B. Flagger stationed next to sign.
- C. Portable changeable message sign (PCMS).
- D. Low-power (drone) radar transmitter.
- E. Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only.
   Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12



Traffic Safety Division Standard


## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

:	bc-21.dgn	DN: Tx[	T00	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		н	GHWAY
		0100	08	105		US	181
9-07	8-14 5-21	DIST		COUNTY			SHEET NO.
7-13	3-21	CRP		BEE			13


97

#### TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\* \* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.




Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

#### STOP/SLOW PADDLES

- 1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24". STOP/SLOW paddles shall be retroreflectorized when used at night.
- 3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)							
USAGE	USAGE COLOR SIGN FACE MATERIAL						
BACKGROUND	RED	TYPE B OR C SHEETING					
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING					
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING					
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM					

#### CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

SIDE ELEVATION

Wood

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports. the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CW7TCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

#### GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question reaardina installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

#### <u>DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)</u>

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary work that occupies a location more than 3 days.
  - Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration work that occupies a location up to 1 hour. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

#### SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plagues mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

#### SIZE OF SIGNS

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

#### SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

#### REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- 3. Orange sheeting, meeting the requirements of DMS-8300 Type  $B_{FL}$  or Type  $C_{FL}$ , shall be used for rigid signs with orange backgrounds.

#### SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

#### REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting. Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

#### SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular
- impact. Rubber (such as tire inner tubes) shall NOT be used. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured
- with rubber bases may be used when shown on the CWZTCD list. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

#### FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12

Traffic Safety Division Standard



#### BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21

ILE:	bc-21.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		н	IGHWAY
9-07 8-14 7-13 5-21	0100	08	08 105			S 181	
	•	DIST		COUNTY			SHEET NO.
	5-21	CRP		BEE			14



Welds to start on

opposite sides going in opposite directions. Minimum

weld, do not

back fill puddle.

weld starts here

¥ Maximum 12 sq. ft. of ★ Maximum wood 21 sq. ft. of sign face post sign face 4×4 block block 72" Length of skids may be increased for wood additional stability. for sign Top 2x4 x 40" height 2x4 brace for sign requirement height 3/8" bolts w/nuts requiremen or 3/8" x 3 1/2" (min.) lag screws Front 4x4 block 40" 4x4 block 36" Side Front SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

-2" x 2"

12 ga. upright

2"

SINGLE LEG BASE

Pos Post Post desirable 34" min. in Optional strong soils, reinforcing 48" 55" min. in minimum sleeve -34" min, in weak soils. (1/2" larger strong soils, than sian 55" min, in post) x 18' weak soils. Anchor Stub Anchor Stub (1/4" larger (1/4" larger than sign than sign post) post) -OPTION 2 OPTION 1 OPTION 3 (Anchor Stub) (Direct Embedment) (Anchor Stub and Reinforcing Sleeve)) PERFORATED SQUARE METAL TUBING


# See the CWZTCD for embedment. WING CHANNEL Lap-splice/base bolted anchor

#### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support.

The maximum sign square footage shall adhere to the manufacturer's recommendation.

Two post installations can be used for larger signs.



#### **WEDGE ANCHORS**

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

#### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE
AND SHORT TERM SUPPORTS CAN BE FOUND ON THE
CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

#### GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- . No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
  - imes See BC(4) for definition of "Work Duration."
  - \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

#### SHEET 5 OF 12



Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC (5) -21

FILE:	bc-21.dgn	DN: T	(DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C TxD0T	November 2002	CONT	SECT	JOB		H	IGHWAY
REVISIONS		0100	08	105		US 181	
	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	CRP		BEE			15

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32′

aa I

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

#### PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message.
- 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	мі
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SL IP
Emergency Vehicle		South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY. FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving		Traffic	TRAF
Hazardous Material		Travelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour (s)	HR, HRS	Vehicles (s)	VEH, VEHS
Information	INFO	Warning	WARN
It Is	ITS	Wednesday	WED
Junction	JCT	Weight Limit	WT LIMIT
Left	LFT	West	W
Left Lane	LFT LN	Westbound	(route) W
Lane Closed	LN CLOSED	Wet Pavement	WET PVMT
Lower Level	LWR LEVEL	Will Not	WONT
Maintenance	MAINT		
mo il il el lulice	Mrs 11/1		

designation # IH-number, US-number, SH-number, FM-number

#### RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

#### Phase 1: Condition Lists

Road/Lane/Ramp Closure List Other Condition List										
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT							
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT							
ROAD	RIGHT LN	RIGHT LN	TWO-WAY							
CLSD AT	CLOSED	NARROWS	TRAFFIC							
FM XXXX	XXX FT	XXXX FT	XX MILE							
RIGHT X	RIGHT X	MERGING	CONST							
LANES	LANES	TRAFFIC	TRAFFIC							
CLOSED	OPEN	XXXX FT	XXX FT							
CENTER	DAYTIME	LOOSE	UNEVEN							
LANE	LANE	GRAVEL	LANES							
CLOSED	CLOSURES	XXXX FT	XXXX FT							
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT							
VARIOUS	EXIT XXX	ROADWORK	ROADWORK							
LANES	CLOSED	PAST	NEXT							
CLOSED	X MILE	SH XXXX	FRI-SUN							

EXIT RIGHT LN CLOSED TO BE CLOSED X LANES MALL DRIVEWAY

CLOSED

XXXXXXX BLVD

CLOSED

CLOSED TUE - FRI

TRAFFIC SIGNAL XXXX FT

**BUMP** 

XXXX FT

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase

#### Phase 2: Possible Component Lists

Г		Lis	ffect on Trave st	ет	Location List		Warning List		* * Advance Notice List
	MERGE RIGHT		FORM X LINES RIGHT		AT FM XXXX		SPEED LIMIT XX MPH		TUE-FRI XX AM- X PM
	DETOUR NEXT X EXITS		USE XXXXX RD EXIT		BEFORE RAILROAD CROSSING		MAXIMUM SPEED XX MPH		APR XX- XX X PM-X AM
	USE EXIT XXX		USE EXIT I-XX NORTH		NEXT X MILES		MINIMUM SPEED XX MPH		BEGINS MONDAY
	STAY ON US XXX SOUTH		USE I-XX E TO I-XX N		PAST US XXX EXIT		ADVISORY SPEED XX MPH		BEGINS MAY XX
	TRUCKS USE US XXX N		WATCH FOR TRUCKS		XXXXXXX TO XXXXXXX		RIGHT LANE EXIT		MAY X-X XX PM - XX AM
	WATCH FOR TRUCKS		EXPECT DELAYS		US XXX TO FM XXXX		USE CAUTION		NEXT FRI-SUN
	EXPECT DELAYS		PREPARE TO STOP				DRIVE SAFELY		XX AM TO XX PM
	REDUCE SPEED XXX FT		END SHOULDER USE				DRIVE WITH CARE		NEXT TUE AUG XX
	USE OTHER ROUTES		WATCH FOR WORKERS						TONIGHT XX PM- XX AM
. [	STAY IN LANE	<b>*</b>			* >	€ See Ap	oplication Guide	elines N	Note 6.

#### APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

#### WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- 2. Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- 7. FI and MI. MILE and MILES interchanged as appropriate.
- 8. AT. BEFORE and PAST interchanged as needed.

9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

US XXX

EXIT

X MILES


LANES

SHIFT

#### FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

#### SHEET 6 OF 12




Traffic Safety Division Standard

#### BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21


FILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDO</th><th>T CK: TXDOT</th></dot<>	ck: TxDOT	DW:	TxDO	T CK: TXDOT
C TxD0T	November 2002	CONT	SECT	JOB			HIGHWAY
	REVISIONS	0100	08	105		l	JS 181
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	CRP		BEE			16

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of pregualified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




#### CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- 4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10. Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer
- 11. Single slope barriers shall be delineated as shown on the above detail.



#### LOW PROFILE CONCRETE BARRIER (LPCB)

Attach the delineators as per manufacturer's recommendations.




#### DELINEATION OF END TREATMENTS

#### END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

#### BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

#### WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type  $B_{FL}$  or  $C_{FL}$  Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control
- devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB". 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

#### WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- 5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.


#### WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.

  2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions
- or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- 4. The Flashing Arrow Board should be able to display the following symbols:



- 5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage.
   The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
   Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal
- intervals of 25 percent for each sequential phase of the flashing chevron.

  9. The sequential arrow display is NOT ALLOWED.

  10. The flashing arrow display is the TxDOT standard; however, the sequential chevron
- display may be used during daylight operations.
- 11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
  12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
  13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility,
- flash rate and dimming requirements on this sheet for the same size arrow.
- 14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

	REQUIREMENTS									
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE							
В	30 × 60	13	3/4 mile							
С	48 × 96	15	1 mile							

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE
TRAFFIC BARRIER OR GUARDRAIL.

#### FLASHING ARROW BOARDS

SHEET 7 OF 12

#### TRUCK-MOUNTED ATTENUATORS

- 1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted in the plans.
- 5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL. REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC(7)-21

FILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ск: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ск: TxDOT	
C TxD0T	November 2002	CONT	SECT	JOB		н	CHWAY	
REVISIONS		0100	08 105			US	181	
9-07	8-14	DIST	IST COUNTY			SHEET NO.		
7-13	5-21	CDD	DEE			17		



#### GENERAL NOTES

- 1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

#### GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:


- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- 3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange,
- high-density polyethylene (HDPE) or other approved material. 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Drum and base shall be marked with manufacturer's name and model number.


#### RETROREFLECTIVE SHEETING

- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting

#### BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.






#### DETECTABLE PEDESTRIAN BARRICADES

- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- 2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian
- 5. Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24" Vertical Panel mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- 1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type  $B_{\text{FL}}$  or Type  $C_{\text{FL}}$  Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- 3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- 5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each
- 6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum, A minimum of three (3) should be used at each location called for in the plans.
- 8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12





Traffic Safety

#### BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21


E: bc-21.dgn	DN: Tx	DOT	CK: TXDOT DW:		TxDOT CK: TxDOT		
TxDOT November 2002	CONT	SECT	JOB		HIGHWAY		
REVISIONS -03 8-14	0100	80	105		US 181		
-03 8-14 -07 5-21	DIST	ST COUNTY			SHEET NO.		
-13	CRP BEE						






- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base.
   See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

#### VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>E</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

#### CHEVRONS

#### **GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



#### LONGITUDINAL CHANNELIZING DEVICES (LCD)

36'

Fixed Base w/ Approved Adhesive

(Driveable Base, or Flexible

Support can be used)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

#### WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the
  work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on
  roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	-	esirab er Lend **	-	Spacing of Channelizing Devices			
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	2	150′	1651	180′	30'	60′		
35	L= WS <sup>2</sup>	2051	2251	2451	35′	70′		
40	80	265′	295′	3201	40′	80′		
45		450′	495′	540′	45′	90′		
50		5001	550′	600,	50′	100′		
55	L=WS	550′	6051	6601	55′	110′		
60	L - 11 3	600'	660′	720′	60′	120′		
65		650′	715′	7801	65 <i>°</i>	130′		
70		700′	770′	840′	70′	140′		
75		750′	8251	900'	75′	150′		
80		800'	880′	960′	80,	160′		
	V T 1							

\*\*X\*Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

# SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Traffic Safety Division Standard

Suggested Maximum


# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) -21


		_		_			
ILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		HI	GHWAY
		0100	08	105		US	181
9-07 7-13	8-14 5-21	DIST	DIST COUNTY		SHEET NO.		
		CRP	BEE				19

#### TYPE 3 BARRICADES

- Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- 7. Warning lights shall NOT be installed on barricades.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solld objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




#### TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

#### TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



3"-4"

4" min. orange

2" min.

4" min. white

4" min. orange

4" min. white

6" min. 2" min. 4" min. 2" max. 3" min. 2" to 6" 3" min. 28" min.


CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

Two-Piece cones

One-Piece cones

PLAN VIEW

Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12

Texas Department of Transportation

Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

.E:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th><th></th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
TxDOT	November 2002	CONT	SECT	JOB		HIC	SHWAY	
		0100	08	105		US	181	
9-07			DIST COUNTY		COUNTY SHEET NO.		SHEET NO.	
7-13	5-21	CRP		BEE			20	

# :34:10 Aw | Iencl\Desktop\BMIP's\BMIP 0100-08-105\Standards\bc-21.dgn

#### WORK ZONE PAVEMENT MARKINGS

#### **GENERAL**

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard povement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

#### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on RC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

#### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


#### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per

#### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

#### Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

#### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body).
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIO	NS
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


E: bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT February 1998	CONT SECT		JOB		HIGHWAY	
REVISIONS -98 9-07 5-21	0100	00 08 105		US 181		
-96 9-07 5-21 -02 7-13	DIST	DIST COUNTY			SHEET NO.	
-02 8-14	CRP		BEE			21

105


Prefabricated markings may be substituted for reflectorized pavement markings.

#### PAVEMENT MARKING PATTERNS 10 to 12" Type II-A-An 1 Q O O O O O O O O O ₹> Yellow -Type Y buttons RAISED PAVEMENT MARKERS - PATTERN A REFLECTORIZED PAVEMENT MARKINGS - PATTERN A Type II-A-A <>> □وہ/ہ□ہہہ \$\frac{1}{4 \tau 8"} Type Y Type II-A-Abuttons-REFLECTORIZED PAVEMENT MARKINGS - PATTERN B RAISED PAVEMENT MARKERS - PATTERN B Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings. CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE. TWO-WAY HIGHWAYS Type I-C Type W buttons-Type I-C or II-C-R 0000 0000 0000 Type I-A Type Y buttons ₹> Yellow White 0000 ─Type I-C or II-C-R Type W buttons-REFLECTORIZED PAVEMENT MARKINGS RAISED PAVEMENT MARKERS


#### EDGE & LANE LINES FOR DIVIDED HIGHWAY



#### LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



TWO-WAY LEFT TURN LANE



STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS

BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS


BC(12)-21

DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO ©⊺xDOT February 1998 JOB HIGHWAY 0100 08 105 US 181 1-97 9-07 5-21 2-98 7-13 11-02 8-14 22

Raised pavement markers used as standard

Item 672 "RAISED PAVEMENT MARKERS,"

pavement markings shall be from the approved products list and meet the requirements of



Channelizing

(See note 2)

ROAD

WORK

AHEAD

Work vehicles or

other equipment necessary for the work operation, such

as trucks, moveable cranes, etc., shall remain in areas

devices at all times.

separated from lanes of traffic by channelization

Shadow Vehicle with TMA and

Channelizing

(See note 2) ▲

END

ROAD WORK

(See note 2)▲

48" X 24"

G20-2

Devices


rotating, flashing, oscillating or strobe lights. (See notes 4 & 5)—

Devices

CW20-1D

48" X 48" (Flags-

See note 1)



Posted Speed	Formula	D	Desirable Spacing of Channelizing X X Devices		Channelizing Devices		Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	2	150′	165′	180'	30′	60′	120′	90'
35	L = WS <sup>2</sup>	2051	2251	245′	35′	70′	160′	120′
40	6	265′	2951	3201	40′	80′	240′	155′
45		4501	4951	540′	45′	90′	320′	195′
50		500'	550′	6001	50′	100′	400′	240′
55	L=WS	550′	6051	660′	55′	110′	500′	295′
60	L-113	600'	660′	7201	60′	120'	600′	350′
65		650′	715′	780′	65′	130′	700′	410′
70		7001	770′	840'	70′	140′	800′	475′
75		750′	8251	900'	75′	150′	900'	540′

\* Conventional Roads Only

END

ROAD WORK

 $\triangle$ 

 $\Diamond$ 

G20-2

48" X 24"

(See note 2)▲

Inactive

work vehicle

(See Note 3)

ROAD

WORK

AHEAD

CW20-1D

48" X 48" (Flags-

See notes 1 & 7)

- XX Taper lengths have been rounded off.
- L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE										
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY						
<b>√ √</b>										

#### GENERAL NOTES

- 1. Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- . A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- Surface, next to those shown in order to protect where work spaces.

  6. See TCP (5-1) for shoulder work on divided highways, expressways and freeways.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(1-1)-18


			-		
ILE: tcp1-1-18.dgn	DN:		CK:	DW:	CK:
CTxDOT December 1985	CONT	SECT	JOB		H]GHWAY
REVISIONS 1-94 4-98	0100	08	105	l l	JS 181
3-95 2-12	DIST		COUNTY		SHEET NO.
-97 2-18	CRP		BEE		23

WORK VEHICLES ON SHOULDER
Conventional Roads

TCP (1-1c)

分

1151



	LEGEND									
~~~	Type 3 Barricade		Channelizing Devices							
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
<b>₽</b>	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)							
•	Sign	♡	Traffic Flow							
$\Diamond$	Flag	Ц	Flagger							

Posted Speed	Formula	**		le	Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"	
30	<u>ws²</u>	150′	1651	1801	30'	60′	1201	90′	200'
35	L = WS	2051	225'	245′	35′	70′	160′	120′	250′
40	60	2651	2951	3201	40'	80′	240′	155′	3051
45		450′	4951	540′	45′	90′	320′	195′	360′
50		5001	550′	600,	50′	100′	4001	240′	425′
55	L=WS	550′	605′	660'	55′	110'	500′	295′	495′
60	L-#3	600'	660′	7201	60′	120'	600′	350′	570′
65		650′	715′	7801	65′	130′	700′	410′	645′
70		700′	770′	8401	701	140′	800′	475′	730′
75		750'	825′	900′	75′	150′	900′	540′	820′

\* Conventional Roads Only

\*\* Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY					
	1	1							

#### GENERAL NOTES

ROAD

WORK

AHEAD

- 1. Flags attached to signs where shown are REQUIRED.
- 2, All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- 4. Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 6. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

#### TCP (1-2a)

- 7. R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- 8. R1-2 "YIELD" sign with "R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

- 9. Flaggers should use two-way radios or other methods of communication to control traffic.
- 10. Length of work space should be based on the ability of flaggers to communicate.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above)
- 12. Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- 3. Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP(1-2)-18

FILE: tcp1-2-18.dgn	DN:		CK:	DW:	CK:
ℂTxDOT December 1985	CONT	SECT	JOB		HIGHWAY
4-90 4-98 REVISIONS	0100	08	08 105		US 181
2-94 2-12	DIST	COUNTY			SHEET NO.
1-97 2-18	CRP		BEE		24



	LEGEND									
~~~	Type 3 Barricade		Channelizing Devices							
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)							
•	Sign	♦	Traffic Flow							
$\Diamond$	Flag	ПО	Flagger							

Speed	Formula	Taper Lengths Channelizing  ** Destructe Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space			
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	2	150′	165′	180′	30′	60′	1201	90'
35	L = WS <sup>2</sup>	2051	2251	245'	35′	70′	160′	120′
40	60	265′	295′	3201	40'	80′	240′	155′
45		450'	4951	540′	45′	90′	320′	195′
50		500'	550′	600′	50′	1001	400′	240′
55	L=WS	550′	605′	660′	55′	110'	500′	295′
60	- "3	600′	660′	720′	60′	120'	600′	350′
65		650′	715′	780′	65′	130′	700′	410′
70		700′	770′	840′	70'	140′	800'	475′
75		750′	825′	900′	75′	150′	900′	540′

- \* Conventional Roads Only
- \*\* Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE							
MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM STATIONARY STATIONARY STATIONARY							
	✓	1					

#### **GENERAL NOTES**

- 1. Flags attached to signs where shown are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- 3. Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Additional flaggers may be positioned in advance of traffic queues to alert traffic to reduce speed.
- 4. DO NOT PASS, PASS WITH CARE and construction regulatory speed zone signs may be installed downstream of the ROAD WORK AHEAD signs.
- 5. When the work zone is made up of several work spaces, channelizing devices should be placed laterally across the closed lane to re-emphasize closure. Laterally placed channelizing devices should be repeated every 500 to 1000 feet in urban areas and every 1/4 to 1/2 mile in rural areas.
- 6. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of  $% \left( 1\right) =\left( 1\right) \left( 1\right)$  the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 7. Additional Shadow Vehicles with TMAs may be positioned off the paved
- surface, next to those shown in order to protect wider work spaces. 8. Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20', or 15' if posted speed are 35 mph or slower, and for tangent sections, at 1/2Swhere S is the speed in mph. This tighter device spacing is intended for the area of conflicting markings not the entire work zone.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN TRAFFIC SHIFTS ON TWO LANE ROADS

TCP(1-3)-18

FILE: tcp1-3-18,dgn	DN:		CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB		HIGHWAY
REVISIONS 2-94 4-98	0100	08	105		US 181
8-95 2-12	DIST		COUNTY		SHEET NO.
1-97 2-18	CRP		BEE		25



	LEGEND							
~~~	Type 3 Barricade		Channelizing Devices					
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)					
<b>E</b>	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)					
-	Sign	♡	Traffic Flow					
$\Diamond$	Flag Flagger							

Posted Speed	* *		le gths	Spacii Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	2	1501	1651	1801	30′	60′	120′	90,
35	L = WS <sup>2</sup>	2051	225′	245'	35′	70′	160′	120'
40	80	265'	2951	3201	40′	80′	240′	155′
45		4501	4951	540′	45′	90′	320′	195′
50		500'	550′	6001	50′	100′	400′	240'
55	L=WS	550′	605′	660′	55′	110′	500′	295′
60	- "3	600'	660′	720′	60′	120′	600′	350′
65		650'	715′	7801	65′	130′	700′	410′
70		7001	770′	840′	701	140′	800′	475′
75	1	750′	825′	900'	75′	150′	900'	540′

- \* Conventional Roads Only
- \*\* Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY							
	✓	✓	<b>√</b>	<b>√</b>				

#### **GENERAL NOTES**

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer
- 3. Stockpiled material should be placed a minimum of 30 feet from
- nearest traveled way.

  4. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 5. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- 6. See TCP(5-1) for shoulder work on divided highways, expressways and
- 7. Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- 8. CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(2-1)-18

	_		-	-	
tcp2-1-18.dgn	DN:		CK:	DW:	CK:
TxDOT December 1985	CONT	SECT	JOB		HIGHWAY
REVISIONS 94 4-98	0100	08	105	ı	US 181
94 4-96 95 2-12	DIST		COUNTY		SHEET NO.
97 2-18	CRP		BEE		26

END

ROAD WORK

G20-2

48" X 24"

Temporary Yield Line

(See Note 2)▲

ΤO

ONE LANE

AHEAD

ONCOMING R1-2aP TRAFFIC 48" X 36" (See note

48" X 48"

CW20-4D

48" X 48"

↔

ŏ riñ Š

Warning Sign Sequence in Opposite Direction

YIELD.

ΤO

ONCOMING

TRAFFIC R1-2aP 48" X 36" (See note 9)

R1-2

42" X 42

Devices at 20'

spacing on the Taper

Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe

Devices at 20°

Temporary Yield Line

(See Note 2)▲


END

ROAD WORK

spacing on the Taper

lights. (See notes 6 & 7)

♡□公



CONTROL WITH FLAGGERS

**LEGEND** . . Type 3 Barricade Channelizing Devices Truck Mounted Heavy Work Vehicle Attenuator (TMA) Portable Changeable Message Sign (PCMS) railer Mounted M Flashing Arrow Board Traffic Flow Flag Flagger

Speed	Formula	D	Minimur esirab er Len **	le	Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance "B"		
30	2	150′	165′	180′	30'	60′	120'	90′	2001
35	L = WS <sup>2</sup>	2051	225′	2451	35′	70′	160′	120′	250′
40	80	265′	295′	3201	40'	80′	240'	1551	305′
45		450′	495′	540′	45′	90′	320′	195′	360′
50		5001	550′	600,	50′	100′	400'	240'	425′
55	L=WS	550′	605′	660′	55′	110'	500′	295′	495′
60		600′	660′	720′	60'	120'	600'	350'	570′
65		650′	715′	7801	65′	130'	700′	410′	645′
70		700′	770′	840′	70′	140′	800′	475′	730′
75		750′	825′	900'	75′	150′	900'	540′	820′

\* Conventional Roads Only

\*\* Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE							
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY						
	1	_/					

#### GENERAL NOTES

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
- 4. Flaggers should use two-way radios or other methods of communication to control traffic.
- 5. Length of work space should be based on the ability of flaggers to communicate.
- 6. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 7. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

#### TCP (2-2a)

- 8. The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
- 9. The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.

#### TCP (2-2b)

- 10.Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles.
- 12.Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situtations.





TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

Traffic Operations Division Standard

TCP (2-2) -18

FILE: tcp2-2-18.dgn	DN:		CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB		H]GHWAY
REVISIONS 8-95 3-03	0100	08	105		JS 181
1-97 2-12	DIST		COUNTY		SHEET NO.
4-98 2-18	CRP		BEE		27





Speed	•		Minimum Desirable Taper Lengths **			d Maximum ng of lizing ices	Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	WS <sup>2</sup>	150′	165′	180′	30′	60′	120′	90′
35	L= WS	2051	225′	245'	35′	70′	160′	120′
40	80	265′	295′	3201	40′	80′	240'	155′
45		4501	4951	540′	45′	90′	320′	195′
50		500′	550′	6001	50′	100′	400′	240′
55	L=WS	550′	6051	660′	55′	110′	500′	295′
60	L - W 3	600'	660′	7201	60′	120'	600′	350′
65		650′	715′	7801	65′	130'	700′	410′
70		7001	770′	840′	70′	140′	800′	475′
75		750′	8251	900′	75′	150′	900'	540′

\* Conventional Roads Only

\*\* Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
				TCP (2-3b) ONLY				
			<b>√</b>	<b>√</b>				

#### GENERAL NOTES

If applicable

R4-2

24" X 30'

48" X 48"

CW13-1P

CW1-4L

CW13-1P

DO

24" X 24"

24" X 30"

CW20-1D

(Flags-

48" X 48"


See note 1)

48" X 48"

- 1. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
- Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue. The R4-1 "DO NOT PASS," R4-2 " PASS WITH CARE" and construction
- regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
- Conflicting pavement marking shall be removed for long term projects.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned  $30\ \text{to}\ 100\ \text{feet}$  in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place. Type 3 Barricades or other channelizing devices may be substituted.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

#### TCP (2-3a)

Conflicting pavement markings shall be removed for long-term projects.For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN TRAFFIC SHIFTS ON TWO-LANE ROADS

TCP (2-3) -18

FILE: tcp(2-3)-18.dgn	DN:		CK:	DW:	CK:
ℂTxDOT December 1985	CONT	SECT	JOB		HIGHWAY
REVISIONS 8-95 3-03	0100	08	105		US 181
1-97 2-12	DIST		COUNTY		SHEET NO.
4-98 2-18	CRP		BEE		28

TABLE 1 Warning sign and rumble strip # of Rumble sequence in Flagger Strip opposite direction (Length of Work Area) Arrays is some as below. < 4,500 1/8 Mile > 4,500 2 3,500 1/4 Mile > 3,500 2 < 2,600 1 1/2 Mile <u>></u> 2,600 2 < 1,600 1 1 Mile 2 <u>></u> 1,600 N/A > 1 Mile See note 8 Rumble Strip Array (See note 1) Rumble Strip Array (See note 1) The second Rumble Strip Array is required when the ADT thresholds in Table 1 indicate the need for 2 Arrays. RUMBLE  $\Diamond$ AHEAD, CW17-2T 48" X 48" (See note 2) ROAD WORK AHEAD CW20-1D 48" X 48" WZ (RS-1a) RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



#### GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- 2. The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- 4. Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- B. The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- 10. Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

	LEGEND									
	Type 3 Barricade		Channelizing Devices							
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
<b>E</b>	Trailer Mounted Flashing Arrow Panel	(M	Portable Changeable Message Sign (PCMS)							
_	Sign	Ŷ	Traffic Flow							
$\Diamond$	Flag	T)	Flagger							

Posted Formula Speed		Desirable Taper Lengths <del>X X</del>			Spacir Channe		Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space	
*	*		11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"В"	
30	ws <sup>2</sup>	150′	165′	180′	30′	60′	120'	90′	
35	L = WS	2051	2251	2451	35′	701	160′	120′	
40	80	265′	2951	3201	40′	80'	240'	155′	
45		450′	495′	540'	45′	90′	320'	195′	
50		500′	550′	6001	50°	100′	4001	240′	
55	L=WS	550′	605′	660′	55′	110′	500′	295′	
60	L - # 3	600'	660′	720′	60′	120′	600'	350′	
65		6501	715′	7801	65′	130′	700′	410'	
70		700′	770′	840′	70′	140′	800'	475′	
75		750′	825′	900′	75′	150′	900′	540′	

- \* Conventional Roads Only
- \*\* Taper lengths have been rounded off.
   L=Length of Taper(FT) W=Width of Offset(FT)
   S=Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY					
	✓	✓							

- Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
- For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

T.	ABLE 2
Speed	Approximate distance between strips in an array
<u>&lt;</u> 40 MPH	10′
> 40 MPH & <u>&lt;</u> 55 MPH	15′
= 60 MPH	20′
<u>&gt;</u> 65 MPH	<b>*</b> 35′+




TEMPORARY RUMBLE STRIPS

WZ (RS) -22

FILE: \	vzrs22.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
C TxDOT 1	November 2012	CONT	ONT SECT JOB		HIGHWAY			
REVISIONS 2-14 1-22 4-16		0100	08	105		U:	US 181	
		DIST		COUNTY			SHEET NO.	
4-16		CRP		BEE			29	


11



See elsewhere in plans for rail transition

ELEVATION

Showing conc traffic rail -




# Type R, Type F, Common 1'-0" Thickness

#### SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".

#### SECTION A-A AT CAP



#### CAP OPTION A

#### CAP OPTION B


#### DETAIL C


#### GENERAL NOTES:


Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.


See elsewhere in plans for locations and details of


shoulder drains.











#### TOEWALL STONE RIPRAP DETAIL

Scale: N.T.S.

#### BENT STONE RIPRAP DETAIL

Scale: N.T.S.

#### ABUTMENT STONE RIPRAP DETAIL

Scale: N.T.S.

1) Stone riprap thickness should be a minimum thickness of 1.5 times the nominal stone riprap size.



#### STONE RIPRAP DETAILS


Bridge Division

ILE:	X X . dgn	DN:		CK:	DW:		CK:	
C)T x D0T	June 2020	CONT	SECT	JOB		HIG	HIGHWAY	
	REVISIONS	0100	08	105		US	181	
		DIST		COUNTY			SHEET NO.	
		CRP		BEE			32	

)ATE:

Grind 1/4" R Sealant (1 Backer Rod (2) Concrete Slab and Girder (Pan Form) Field Verify

DETAIL "A"



SILICONE SEAL (used without ACP Overlay)

JOINT WITH HOT POURED RUBBER SEAL (used with ACP Overlay)

-Joint Sealant

EXISTING CONCRETE SLAB & GIRDER JOINT REPAIR

1) Clean joint opening of all old expansion materials/devices, dirt, and all other deleterious materials in accordance with Item 438, "Cleaning and Sealing Joints and Cracks." Clean joint out full depth

PROCEDURE FOR CLEANING AND SEALING

SILICONE SEAL:

EXISTING CONCRETE GIRDER JOINT WITH

Obtain approval of cleaned joint prior to proceeding with joint sealing operation.


- 3) Place backer rod into joint opening 1" below the top of concrete. The backer rod must be 25% larger than the joint opening.
- 4) Seal the joint opening with a Class 7 Silicone. Recess seal ½" below top of concrete in travel lanes and 1/8" below top of concrete in shoulders.

#### PROCEDURE FOR CLEANING AND SEALING EXISTING CONCRETE GIRDER JOINT WITH HOT POURED RUBBER SEAL:

- 1) Saw cut through the asphalt at the centerline of joint. Make multiple saw cuts to create a ½" minimum joint opening or match the existing joint opening. Clean joint opening of all old expansion materials/devices, bituminous materials, dirt, grease and all other deleterious materials in accordance with Item 438, "Cleaning and Sealing Joints and Cracks.
- Obtain approval of cleaned joint prior to proceeding with joint sealing operation.
- 3) Place backer rod into joint opening 1" below the top of concrete. Backer rod must be of the type that can handle the heat and be compatible with the hot poured rubber seal. The backer rod must be 25% larger than the joint opening.
- 4) Seal the joint opening with a Class 3, "Hot Poured Rubber." Seal flush to the top of the asphaltic concrete pavement.

#### PROCEDURE FOR CLEANING AND SEALING EXISTING ARMOR JOINTS:

- 1) Remove existing seal.
- 2) Abrasive blast clean existing steel surface where silicone seal is to be placed.
- 3) Obtain approval of cleaned joint prior to proceeding with joint sealing operation.
- 4) Place backer rod into joint opening 1" below the top of concrete. The backer rod must be 25% larger than the joint opening.
- 5) Seal the joint opening with a Class 7 Silicone. Recess seal  $\frac{\pi}{2}$ " below top of concrete in travel lanes and  $\frac{\pi}{8}$ " below top of concrete in shoulders.



#### larger than joint opening) CLEANING AND SEALING EXISTING ARMOR JOINTS

#### **GENERAL NOTES:**

Cleaning existing joint opening (full depth) of all debris, providing and placing backer rod, saw-cutting joint opening, and sealing joint is paid for by Item 438, "Cleaning and Sealing Joints and Cracks" and measured by the foot of "Cleaning and Sealing of Existing Joints.

(1) Use Class 7 silicone sealant. Prepare joint and seal in accordance with Item 438 "Cleaning and Sealing Joints and

compatible with the sealant.

(2) Backer rod must be 25% larger than joint opening and must be

(3)Use Class 3 hot poured rubber seal. Prepare joint and seal in

accordance with Item 438 "Cleaning and Sealing Joints and Cracks."

Obtain approval for all tools, equipment, materials and techniques proposed for use to prepare the joint. For Class 3 Hot Poured Rubber Seal, provide backer rod compatible with the hot poured rubber sealant and rated for a minimum of 400°F.

Provide Class 3 sealant in accordance with DMS-6310, "Joint Sealants and Fillers" for joints in asphalt

overlay.

Provide Class 7 silicone sealant in accordance with DMS-6310, "Joint Sealants and Fillers" for joints in

concrete. Extend sealant up into rail or curb 3 inches on low side or sides of deck. If the Class 7 Sealant cannot be effectively placed in the vertical position, a Class 4 Sealant compatible with the Class 7 sealant is allowed for the extension of the seal into the curb or rail. Prepare surfaces where sealant is to be placed in accordance with manufacturer's specifications.

(Showing Armor Joint Section)

# Joint Sealant Backer Rod

SHOWN AT STEEL RAIL

AM

SHOWN AT BARRIER RAIL

Backer Rod


SHOWN AT CURB

Backer Rod -

#### JOINT SEALANT TERMINATION DETAILS

Joint Sealant

#### CLEANING AND SEALING BRIDGE JOINT DETAILS



0100 08 105 US 181 33

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide Post-Construction TSS Vegetative Filter Strips ☐ Blankets/Matting Rock Berm Retention/Irrigation Systems Mulch Extended Detention Basin ☐ Triangular Filter Dike Sodding Sand Bag Berm Constructed Wetlands ☐ Interceptor Swale Straw Bale Dike Wet Basin ☐ Diversion Dike ☐ Brush Berms Erosion Control Compost Erosion Control Compost Erosion Control Compost Mulch Filter Berm and Socks

☐ Mulch Filter Berm and Socks ☐ Mulch Filter Berm and Socks ☐ Compost Filter Berm and Socks

Stone Outlet Sediment Traps Sand Filter Systems

Grassy Swales

Compost Filter Berm and Socks Compost Filter Berm and Socks Vegetation Lined Ditches

Sediment Basins

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

Required Action No Action Required

Action No. 1.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required

Required Action

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required

Required Action

- 1. Be advised of the potential occurrence of sheep frog in the project area. This species prefers subterranean burrows, such as those of pack rats. They will also burrow under fallen tree limbs. Although this species will remain in its burrow for most of the year, they may emerge with heavy rains in the late summer season. Breeding takes place in August and September. Ensure that SW3P and 401 BMPs are implemented and maintained during construction. Avoid harming this species if encountered.
- 2. Be advised of the potential occurrence of sheep frog in the project area. This species prefers subterranean burrows, such as those of pack rats. They will also burrow under fallen tree limbs. Although this species will remain in its burrow for most of the year, they may emerge with heavy rains in the late summer season. Breeding takes place in August and September. Ensure that SW3P and 401 BMPs are implemented and maintained during construction. Avoid harming this species if encountered.
- 3. Be advised of the potential occurrence of the South Texas siren in the project area. This species usually burrows in mud within marshes and streams. It will occasionally venture onto dry land. The South Texas siren has a characteristic eel-like body with a large head and small lidless eyes. This amphibian has an olive to dark gray or brown coloration with small black spots on the top of its body with light colored spots on the underside of its body. The siren has two reduced limbs behind a large set of external gills. Avoid harming this species if encountered.

- 4. Minimize impacts to wetland, temporary and permanent open water features, including depressions, and riverine habitats. Maintain hydrologic regime and connections between wetlands and other aquatic features. Use silt fencing (barrier) to direct animal movements away from construction activities and areas of potential wildlife-vehicle collisions in construction areas directly adjacent, or that may directly impact, potential habitat for the target species.
- 5. Consider applying hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas where feasible. If hydromulching and/or hydroseeding are not feasible due to site conditions, using erosion control blankets or mats that contain no netting, or only contain loosely woven natural fiber netting is preferred. Plastic netting should be avoided to the extent practicable.
- 6. Project Specific Locations (PSLs) proposed within state-owned ROW should be located in uplands away from aquatic features. When work is directly adjacent to the water, minimize impacts to shoreline basking sites (e.g., downed trees, sand bars, exposed bedrock) and overwinter sites (e.g., brush and debris piles, crawfish burrows), where feasible. Avoid or minimize disturbing or removing downed trees, rotting stumps, and leaf litter, which may be refugia for terrestrial amphibians, where feasible.

7. The Federal Migratory Bird Treaty Act (MBTA) states that it is unlawful to pursue, hunt, take, kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit. This project does not have a federal permit; therefore, in accordance with this regulation, the Contractor will avoid disturbing, destroying, removing, or relocating migratory birds and active nests found in trees, culverts, bridges, on the ground, etc. Typical breeding season occurs from March through August; therefore, tree trimming and other vegetation clearing activities that may disturb breeding birds should be done in the non-breeding season (September-February), when possible. If work must be performed during the breeding season, the Contractor  $\ensuremath{\mathsf{Contractor}}$ shall have a qualified biologist conduct a survey of the right of way to determine if bird nests are present. In the event that active nests are encountered on-site during construction, the Contractor shall notify the Engineer and measures shall be taken to avoid disturbance of these birds, their occupied nest, eggs, and/or young, in accordance with the MBTA. Phasing of work during construction may be necessary to stay in compliance with the MBTA. The Contractor can discuss other preventative measures with the Project Engineer and/or District Environmental Staff.

LIST OF ABBREVIATIONS

BMP: Best Management Practice CGP: Construction General Permit DSHS: Texas Department of State Health Services FHWA: Federal Highway Administration MOA: Memorandum of Agreement MOU: Memorandum of Understanding Municipal Separate Stormwater Sewer System MBTA: Migratory Bird Treaty Act

NOT: Notice of Termination

NWP: Nationwide Permit

NOI: Notice of Intent

SPCC: Spill Prevention Control and Countermeasure SW3P: Storm Water Pollution Prevention Plan PCN: Pre-Construction Notification Project Specific Location TCFQ: Texas Commission on Environmental Quality TPDES: Texas Pollutant Discharge Elimination System

TPWD: Texas Parks and Wildlife Department TxDOT: Texas Department of Transportation Threatened and Endangered Species USACE: U.S. Army Corps of Engineer:

USFWS: U.S. Fish and Wildlife Service

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

Texas Department of Transportation

FPIC

LE: epic.dgn	DN: Tx[	TOC	ck: RG	DW: VP		ck: AR
TxDOT: February 2015	CONT	SECT	JOB		HIC	SHWAY
REVISIONS 12-2011 (DS)	0100	08	105	US 18		181
07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO		
23-2015 SECTION I (CHANGED ITEM 1122 ITEM 506, ADDED GRASSY SWALES.	CRP		BEE		3	34

- 8. If the construction of the project requires the use of open trenches and excavated pits, install escape ramps at an angle of less than 45 degrees (1:1) in areas left uncovered. Visually inspect excavation areas for trapped wildlife prior to backfilling.
- 9. I. Avoid or minimize disturbing or removing downed trees, rotting stumps, and leaf litter where feasible.

#### WATER QUALITY

- 10. Minimize the use of equipment in streams and riparian areas during construction. When possible, equipment access should be from banks, bridge decks, or barges.
- 11. When temporary stream crossings are unavoidable, remove stream crossings once they are no longer needed and stabilize banks and soils around the crossing.

12. Do not attempt to handle or catch any of these species. Report all sightings and/or impacts to the TxDOT Corpus Christ District Environmental Section.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

#### VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS. in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

☐ Yes No.

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

☐ No Action Required

Required Action

Action No.

1.Cleaning and sealing existing bridge joints and bridge rail (concrete and steel) work may include potential exposure to lead-based paint (LBP) and/or asbestos containing material (ACM). Surveys for LBP and ACM are being completed for this project and results are pending. Copies of LBP and ACM survey reports will be made available by the Engineer upon completion.

#### VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

☐ No Action Required

Required Action

Action No.

1.


2.



ENVIRONMENTAL PERMITS. ISSUES AND COMMITMENTS


FPIC

ILE: epic.dgn	DN: Tx[	TO	ck: RG	DW:	VP	ck: AR
TxDOT: February 2015	CONT	SECT	JOB		HIC	SHWAY
REVISIONS -12-2011 (DS)	0100	08	105		US 181	
-07-14 ADDED NOTE SECTION IV.	DIST		COUNTY			SHEET NO.
-23-2015 SECTION I (CHANGED ITEM 1122 ITEM 506, ADDED GRASSY SWALES.	CRP BEE		3	55		



#### TEMPORARY SEDIMENT CONTROL FENCE





#### HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA.SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

#### SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.


Sediment control fence should be sized to filter a maximum flow through rate of 100  ${\sf GPM/FT}^2$ . Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.

#### LEGEND


Sediment Control Fence

#### GENERAL NOTES

- Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
- 2. Perform vertical tracking on slopes to temporarily stabilize soil.
- 3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
- 4. Do not exceed 12" between track impressions.
- 5. Install continous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING



Design Division Standard

TEMPORARY EROSION,
SEDIMENT AND WATER
POLLUTION CONTROL MEASURES
FENCE & VERTICAL TRACKING

EC(1)-16

FILE: ec116	DN: TxD	OT	ck: KM	1		DN/CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB			HIGHWAY
REVISIONS	0100	08	105		US 181	
	DIST	COUNTY		SHEET NO		
	CRP		RFF			36