

SEE SHEET 2 FOR
INDEX OF SHEETS

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

STATE AID PROJECT NO. C 2121-4-124

IH 10 EL PASO COUNTY

| CSJ | LIMITS FROM | LIMITS TO | LINEAR FEET | MILES |
|--------------|---------------------|---------------------|-------------|-------|
| 2121-04-124 | 1.04 MI W OF FM 793 | 0.54 MI W OF FM 793 | 2, 671.68 | 0.506 |
| 2121-05-054 | 0.47 MI E OF FM 793 | FM 3380 | 29, 166.72 | 5.524 |
| TOTAL LENGTH | | | 31, 838.40 | 6.030 |

| STATE AID PROJECT NO. | | | |
|-----------------------|--------|----------|-----------|
| C 2121-4-124 | | | |
| CONT | SECT | JOB | HIGHWAY |
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | COUNTY | | SHEET NO. |
| ELP | ELP | | 1 |

DESIGN SPEED = VARIES
A.D.T. (2021)= 21,067
A.D.T. (2041)=29,494



FINAL PLANS

CONTRACTOR: _____
 TIME CHARGES BEGAN: _____
 DATE CONTRACTOR BEGAN WORK: _____
 DATE WORK WAS COMPLETED: _____
 DATE WORK WAS ACCEPTED: _____
 TOTAL DAYS CHARGED: _____
 ORIGINAL CONTRACT AMOUNT: \$ _____
 AMOUNT OF CONTRACT AMENDMENTS: \$ _____
 FINAL CONTRACT COST: \$ _____

20

AREA ENGINEER

FOR THE REHABILITATION OF EXISTING ROAD CONSISTING OF
DIAMOND GRINDING AND NEXT GENERATION CONCRETE
SURFACE GRINDING AND PAVEMENT MARKINGS



KEY TO COUNTIES

EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE
TDLR INSPECTION NOT REQUIRED

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH
BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS
MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".



RECOMMENDED FOR LETTING: 4/27/2023
 Signed by: *Eduardo Perales, P.E.*
 SAFETY REVIEW COMMITTEE CHAIRMAN

RECOMMENDED FOR LETTING: 4/27/2023
 Signed by: *L. Raul Ortega Jr., P.E.*
 DISTRICT DIRECTOR OF TRANSPORTATION
 PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 4/27/2023
 Signed by: *Tommy Chaves, P.E.*
 DISTRICT ENGINEER

DATE: 2023/03/23 4:15:29 PM
FILE: DOCUMENT NAME

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS FOR ALL STATE CONSTRUCTION PROJECTS. (SP000--008)

CK: DW: CK: DW:

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|--|--|
| <u>GENERAL</u> | |
| 1 | TITLE SHEET |
| 2 | INDEX OF SHEETS |
| 3 | DIAMOND GRINDING PROJECT LAYOUT |
| 4-5 | TYPICAL SECTIONS |
| 6,6A-6D | GENERAL NOTES |
| 7 | QUANTITY SUMMARY |
| 8,8A | ESTIMATE & QUANTITY |
| 9 | ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC) |
| <u>TRAFFIC CONTROL PLAN</u> | |
| 10 | TRAFFIC CONTROL PLAN NARRATIVE |
| <u>TRAFFIC CONTROL PLAN STANDARDS</u> | |
| 11-22 | #BC (1)-21 THRU BC (12)-21 |
| 23 | #TCP (3-2)-13 |
| 24 | #TCP (3-3)-14 |
| 25 | #TCP (6-1)-12 |
| 26 | #TCP (6-2)-12 |
| 27 | #TCP (6-3)-12 |
| 28 | #TCP (6-4)-12 |
| 29 | #TCP (6-8)-14 |
| 30 | #WZ (STPM)-23 |
| 31 | #WZ (BRK)-13 |
| <u>PAVEMENT MARKINGS</u> | |
| 32-34 | PAVEMENT MARKINGS LAYOUT |
| <u>PAVEMENT MARKINGS & DELINEATION STANDARDS</u> | |
| 35 | #FPM (1)-22 |
| 36 | #FPM (2)-22 |
| 37 | #FPM (5)-22 |
| 38 | #CPM (1)-23 |
| <u>ENVIRONMENTAL ISSUES</u> | |
| 39-40 | STORMWATER POLLUTION PREVENTION PLAN (SWP3) |

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET BY A # HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.




Karla Rios, PE.

04/27/2023

DATE: 4/14/2023 11:20:51 AM
 FILE: pw://txdot.projectwiseonline.com/TxDOT5/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/1 - General/IH10_2D_INDEX.dgn

| | | | |
|-----------------|--------|----------|-----------|
| | | | |
| IH 10 | | | |
| INDEX OF SHEETS | | | |
| SHEET 1 OF 1 | | | |
| CONT | SECT | JOB | HIGHWAY |
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | COUNTY | | SHEET NO. |
| ELP | ELP | | 2 |

DATE: 4/13/2023 4:16:16 PM
 FILE: pw://txdot.projectwiseonline.com/TxDOT5/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/1 - General/IH10_PLANLYT.dgn



Karla Rios, P.E.
 04/14/2023

N.T.S.

© 2023 Texas Department of Transportation

IH 10


DIAMOND GRINDING PROJECT LAYOUT

SHEET 1 OF 1

| CONT | SECT | JOB | HIGHWAY |
|------|------|----------|-----------|
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | | COUNTY | SHEET NO. |
| ELP | | ELP | 3 |

CK: DW: CK: DW:

DATE: 4/13/2023 4:16:41 PM
 FILE: p:\w\txdot\projectwiseonline.com\TxDOT5\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\1. General\IH10_2D_TYPSEC.dgn



EXISTING TYPICAL SECTION IH 10

CSJ: 2121-04-124
 RM 48+0.50 TO RM 49+0.00
 CSJ: 2121-05-054
 RM 50+0.00 TO RM 55+0.518

LEGEND

- (A) PROPOSED 6" WHT SLD
- (B) PROPOSED 6" YEL SLD
- (C) PROPOSED 6" WHT BRK & 6" BLACK SHADOW
- (D) PROPOSED REFL PAV MRKR TY II-C-R SPACING AT 80'
- (E) EXISTING 4" WHT PROF PAV MRK
- (F) EXISTING CONCRETE PAVEMENT
- (G) EXISTING 6" WHT BRK & 6" BLACK SHADOW
- (H) EXISTING REFL PAV MARK TY II-C-R
- (I) EXISTING 4" YEL PROF PAV MRK


NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY. DO NOT USE FOR QUANTITY CALCULATIONS OR AS A CONSTRUCTION DETAIL.
2. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS. REFERENCE MARKER ARE FOR LOCATIONS PURPOSES ONLY.
3. DIAMOND GRINDING AND NEXT GENERATION CONCRETE SURFACE GRINDING SHALL BE PERFORMED ON MAINLANE ONLY. IT IS NOT TO BE PERFORMED ON BRIDGE DECKS AND ANY PAVEMENT ON FRONTAGE ROADS OR SHOULDERS.
4. REFER TO FPM(1)-22, FPM(2)-22, FPM(5)-22 AND CPM(1)-23 FOR PAVEMENT MARKINGS INFORMATION.
5. REMOVE EXISTING PAVEMENT MARKINGS PRIOR TO INSTALLING PROPOSED PAVEMENT MARKINGS. REFER TO "PAVEMENT MARKINGS LAYOUT SHEETS FOR ADDITIONAL INFORMATION ON PAVEMENT MARKINGS LIMITS.
6. NO RUMBLE STRIPS SHALL BE INSTALLED ON BRIDGE STRUCTURES.



Karla Rios, P.E.

04/14/2023



PROPOSED 3/16" TO 1/4" DIAMOND GRINDING AND PROPOSED NEXT GENERATION CONCRETE SURFACE GRINDING

PROPOSED TYPICAL SECTION IH 10


CSJ: 2121-05-054
 RM 50+0.35 TO RM 55+0.50 EASTBOUND

N.T.S.

| | | | |
|---|------|----------|-----------|
| © 2023 Texas Department of Transportation | | | |
| IH 10 | | | |
| TYPICAL SECTIONS | | | |
| SHEET 1 OF 2 | | | |
| CONT | SECT | JOB | HIGHWAY |
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | | COUNTY | SHEET NO. |
| ELP | | ELP | 4 |

DATE: 4/13/2023 4:17:05 PM
 FILE: pw://txdot.projectwiseonline.com/TxDOT5/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/1 - General/IH10_2D_TYPSEC_2.dgn

CK:
 DW:
 CK:
 DW:



PROPOSED TYPICAL SECTION IH 10
 CSJ: 2121-04-124
 RM 48+0.50 TO RM 49+0.00
 CSJ: 2121-05-054
 RM 50+0.00 TO RM 50+0.35

LEGEND

- (A) PROPOSED 6" PROF WHT SLD
- (B) PROPOSED 6" PROF YEL SLD
- (C) PROPOSED 6" WHT BRK & 6" BLACK SHADOW
- (D) PROPOSED REFL PAV MRKR TY II-C-R SPACING AT 80'
- (E) PROPOSED RUMBLE STRIPS

NOTES:

1. TYPICAL SECTIONS ARE FOR GENERAL INFORMATION ONLY. DO NOT USE FOR QUANTITY CALCULATIONS OR AS A CONSTRUCTION DETAIL.
2. FIELD VERIFY ACTUAL LOCATIONS AND PAVEMENT DIMENSIONS. REFERENCE MARKER ARE FOR LOCATIONS PURPOSES ONLY.
3. DIAMOND GRINDING AND NEXT GENERATION CONCRETE SURFACE GRINDING SHALL BE PERFORMED ON MAINLANE ONLY. IT IS NOT TO BE PERFORMED ON BRIDGE DECKS AND ANY PAVEMENT ON FRONTAGE ROADS OR SHOULDERS.
4. REFER TO FPM(1)-22, FPM(2)-22, FPM(5)-22 AND CPM(1)-23 FOR PAVEMENT MARKINGS INFORMATION.
5. REMOVE EXISTING PAVEMENT MARKINGS PRIOR TO INSTALLING PROPOSED PAVEMENT MARKINGS. REFER TO "PAVEMENT MARKINGS LAYOUT" SHEETS FOR ADDITIONAL INFORMATION ON PAVEMENT MARKINGS LIMITS.
6. NO RUMBLE STRIPS SHALL BE INSTALLED ON BRIDGE STRUCTURES.



Karla Rios, P.E.
 04/14/2023

N.T.S.

© 2023
Texas Department of Transportation

IH 10

TYPICAL SECTIONS

SHEET 2 OF 2

| CONT | SECT | JOB | HIGHWAY |
|------|------|----------|-----------|
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | | COUNTY | SHEET NO. |
| ELP | | ELP | 5 |

CONTROL: 2121-04-124, ETC

COUNTY: EL PASO

HIGHWAY: IH 10

General Requirements

Maintain the entire project area in a neat and orderly manner throughout the duration of the work. Remove all construction litter and undesirable vegetation within the right of way inside the project limits. This work will be subsidiary to the various bid items.

General Project Description – This project consists of rehabilitation of existing road consisting of Diamond Grinding and Next Generation Concrete Surface Grinding (NGCS) and Pavement Markings on Interstate Highway 10 in El Paso County, Texas.

Traffic

Contact the Engineer or the City when construction operations are within 400 feet of a signalized intersection to determine/verify the location of loop detectors, conduit, ground-boxes, etc. Repair or replace any signal equipment damaged by construction operations. The method of repair or replacement shall be pre-approved and inspected. This work shall be completed at the Contractor's expense.

Contractor questions on this project are to be addressed to the following individual(s):

| | | |
|--|--|--|
| Rene Romero, P.E. East El Paso Area Engineer Rene.Romero@txdot.gov | Aldo Madrid, P.E. Director of Construction Aldo.Madrid@txdot.gov | Monica Ruiz, P.E. District Construction Engineer Monica.Ruiz@txdot.gov |
|--|--|--|

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>.

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 4 – Scope of Work

Schedule and perform all work to ensure proper drainage during the course of construction or maintenance operations. All labor, tools, equipment, and supervision required, to ensure drainage, removal, and handling of water shall be considered incidental work.

Item 7 – Legal Relations and Responsibilities

Comply with all requirements of the Environmental Permits Issues and Commitments (EPIC)

CONTROL: 2121-04-124, ETC

SHEET 6

COUNTY: EL PASO

HIGHWAY: IH 10

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

Occupational Safety & Health Administration (OSHA) regulations prohibit operations that bring people or equipment within 10 ft. of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all

No significant traffic generator events identified.

Law Enforcement Personnel

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site.

Item 8 – Prosecution and Progress

Working days will be calculated in accordance with Section 8.3.1., "Standard Workweek."

Create and maintain a Bar Chart schedule.

Submit baseline schedule and obtain approval prior to beginning construction. The monthly progress payment will be held if the monthly update is not submitted.

Provide a Project Schedule Summary Report on a monthly basis along with the monthly progress schedule.

Item 9 – Measurement and Payment

Monthly progress payments will be made for items of work completed by the 27th day of each month. Any work completed after the 27th will be included for payment in the subsequent monthly progress payment.

Submit Material on Hand (MOH) payment requests at least two (2) working days before the end of the month for payment consideration on that month's estimate.

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

CONTROL: 2121-04-124, ETC

COUNTY: EL PASO

HIGHWAY: IH 10

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" WEB-BASED (Course #133119) which can be found online at the following site: <https://www.nhi.fhwa.dot.gov/>

Certificates of completion should be available to all who finish the course. These should be kept by the officers in order to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case by case basis.

Item 502 – Barricades, Signs, and Traffic Handling

Prior to beginning construction, the Engineer will approve the routing of traffic and sequence of work.

Additional signs and barricades, placed as directed, will be considered subsidiary to this Item.

In accordance with Section 7.2.6.1, designate, in writing, a Contractor Responsible Person (CRP) and a CRP alternate to take full responsibility for the set-up, maintenance, and necessary corrective measures of the traffic control plan. The CRP or CRP alternate must be present at site and implement the initial set up of every traffic control phase/stage, at each location, and/or each call out, for the entire duration of the project.

At the written request of the Engineer, immediately remove the CRP or CRP alternate from the project if, in the opinion of the Engineer, is not competent, not present at initial TCP set-ups, or does not perform in a proper, skillful, or safe manner. These individuals shall not be reinstated without written consent of the Engineer.

CRP and CRP alternate must be trained using Department approved training. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 1 for Department approved Training.

CONTROL: 2121-04-124, ETC

SHEET 6A

COUNTY: EL PASO

HIGHWAY: IH 10

Table 1

Contractor Responsible Person and Alternate

| Provider | Course Number | Course Title | Duration | Notes |
|---|---------------|--|----------|--|
| American Traffic Safety Services Association | TCS | Traffic Control Supervisor | 2 days | |
| National Highway Institute | 133112 | Design and Operation of Work Zone Traffic Control | 1 day | Both courses are required to meet minimum required training. |
| | 133113 | Work Zone Traffic Control for Maintenance Operations | 1 day | |
| Texas Engineering Extension Services | 133112A | Design and Operation of Work Zone Traffic Control | 3 days | |
| University of Texas Arlington Division for Enterprise Development | WKZ421 | Traffic Control Supervisor | 16 hours | Contact UTA for training needs. |

All contractor workers involved with the traffic control implementation and maintenance must participate and complete a Department approved training course. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 2 for Department approved training.

CONTROL: 2121-04-124, ETC

COUNTY: EL PASO

HIGHWAY: IH 10

Table 2
Other Work Zone Personnel

| Provider | Course Number | Course Title | Duration | Notes |
|---|---------------|--|------------|--|
| American Traffic Safety Services Association | TCT | Traffic Control Technician | 1 day | |
| Texas Engineering Extension Services | HWS002 | Work Zone Traffic Control | 16 hours | Identical to HWS-410. Counts for 3 year CRP requirement. |
| National Highway Institute | 133116 | Maintenance of Traffic for Technicians | 5 hours | Web based |
| National Highway Institute | 134109-I | Maintenance Training Series: Basics of Work Zone Traffic Control | 1 hour | Free, Web based |
| University of Texas at Arlington, Division for Enterprise Development | WKZ100 | Work Zone Safety: Temporary Traffic Control | 4 hours | Note name change. Free, Web based |
| TxDOT/AGC Joint Development | N/A | Safe Workers Awareness | 16 minutes | Videos available through AGC of Texas offices. English & Spanish |
| | | Highway Construction Work Zone Hazards | 18 minutes | |
| AGC America | N/A | Highway Work Zone Safety Training | 1 day | |
| Texas Engineering Extension Service | HWS400 | Temporary Traffic Control Worker | 4 hours | Contact TEEX, if interested in course |
| TxDOT/AGC Joint Development | N/A | Work Zone Fundamentals | 10 minutes | Videos available through ACT of Texas offices. English & Spanish |

CONTROL: 2121-04-124, ETC

SHEET 6B

COUNTY: EL PASO

HIGHWAY: IH 10

Contractor may choose to train workers involved with the traffic control implementation and maintenance with a contractor developed training in lieu of Department approved training. Contractor developed training must be equivalent to the Department approved training shown in Table 2. Provide the Engineer a copy of the course curriculum for pre-approval, prior to conducting the contractor developed training. Provide the Engineer a copy of the log of attendees after training completion for project records.

Existing regulatory signs, route marker auxiliaries, guide signs, and warning signs that must be removed due to widening shall be relocated temporarily and erected on approved supports at locations shown in the plans, or as directed. This work will not be paid for directly but considered subsidiary to this item.

Notify the Department officials when major traffic changes are to be made, such as detours. Coordinate with the Department on all traffic changes. Advance notification for the following week's work must be made by 5 P.M. on Wednesdays.

If Law Enforcement Personnel is required by the Engineer, coordinate with local law enforcement as directed or agreed. Complete the weekly tracking form provided by the Department and submit invoices with 5% allowance for Law Enforcement payments by Contractor that agree with the tracking form for payment at the end of each month where approved services were provided.

Provide access to intersecting side roads and driveways at all times, unless otherwise directed.

Any approved change to the sequence of work or TCP, must be signed and sealed by a Contractor's Licensed Professional Engineer assuming full responsibility for any additional barricade signs and devices needed.

Use striping operations to channelize traffic into the newly completed roadway, as directed. Maintain shoulders and median areas in a condition capable of serving as emergency paths, as approved. This work will be subsidiary to this item.

Use portable changeable message signs (PCMS) to alert public of construction two weeks prior to construction.

Use flaggers when directed. Provide two-way radio communication for all flaggers.

Place and maintain sufficient additional warning signs, beacons, delineators, and barricades to warn and guide the public of all hazards through the construction zone at all times, and as directed.

Use flashing arrow boards on all tapers for each lane closure.

Some signs, barricades, and channelization devices may not be shown at the precise or measured position. Place the barricades, devices, or signs, with approval, in positions to meet field conditions.

Fill any holes left by barricade or sign supports and restore the area to its original condition.

Use Type A flashing warning lights or delineators to mark open excavation, footings, foundations, or other obstructions near lanes that may be open to traffic, as directed.

CONTROL: 2121-04-124, ETC

COUNTY: EL PASO

HIGHWAY: IH 10

For additional information pertaining to channelization, signing, spacing details, and flagging procedures required to regulate, warn, and guide traffic through project, refer to the "Barricade and Construction Standards," BC(1)-21 and to the current *Texas Manual on Uniform Traffic Control Devices(TMUTCD)*.

Remove or cover signs that do not apply to current conditions at the end of each day's work.

Repair and/or replace all signs damaged by the public or due to weather events.

Safety Contingency

The contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancement, to improve the effectiveness of the TCP that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506 – Temporary Erosion, Sedimentation, and Environmental Controls

It is not anticipated that any erosion, sedimentation, or environmental control devices will be needed on this project. However, in the event that such controls are necessary, the Storm Water Pollution Prevention Plan (SWP3) for this project shall consist of the use of any temporary erosion control measures deemed necessary by the Engineer and as provided under this Item. Payment for the work will be determined in accordance with Article 9.7, "Payment for Extra Work and Force Account Method."

Item 662 – Work Zone Pavement Markings

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engineer as directed. Place final striping on these locations.

Remove and properly dispose of tabs upon completion of the final striping. This work is considered subsidiary to various bid items.

Place tabs as per the Department's Standard sheet TCP (7-1)-13. Place raised pavement markers in accordance with applicable standards and as directed.

Item 666 –Retroreflectorized Pavement Markings

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required as pavement surface.

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engineer as directed. Place final striping on these locations.

CONTROL: 2121-04-124, ETC

SHEET 6C

COUNTY: EL PASO

HIGHWAY: IH 10

Item 672 – Raised Pavement Markers

Use a pilot line for final pavement markers and remove pilot line after all striping is complete. Remove pilot line in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required for pavement surface preparation.

Do not place raised pavement markers when the pavement surface temperature is below 60°F.

Completely remove all existing raised pavement markers from pavement where raised pavement markers are proposed as shown in the plans. This will include all RPMs in the surrounding area of the proposed RPM. Removal of raised pavement markers is subsidiary to various bid items

Raised pavement marking spacing must be in compliance with the requirements as shown on the plans.

Item 677 – Eliminating Existing Pavement Markings and Markers

Use water blasting as the method for removal of existing pavement markings, unless otherwise approved by the engineer.

Item 3004 – Diamond Grinding and Grooving Pavement

Diamond grinding will be performed with a minimum of 3 pavement grinding machines to ensure the work is maximized within a shift and to complete all work in the required contract time. This method will be performed on travel lanes only omitting shoulder, bridges, and ramps. The whole lane width shall be completed in one workday. After completion of the surface grinding operation, measure the ride quality and correct areas not within tolerance in accordance with Item 585 "Ride Quality for Pavement Surfaces". Ride Quality will be subsidiary to Item 3004.

Item 3012 – Next Generation Concrete Surface Grinding

NGCS Grinding will be performed with at least 6 pavement grinding machines. Provide a two-pass operation to ensure the work is maximized within a shift, an entire lane width (12') is covered at once and to complete all work in the required contract time. The first pass will be to provide a flush surface, second pass will be to provide longitudinal grooves. Both steps will have to be performed during the same lane closure for a given length. The whole lane width shall be completed at once within the same pass and in one workday. Pavement shall not be opened to traffic prior to completing the two-pass operation. Before opening to traffic, verify that the full lane width has been grinded and grooved to avoid irregularities on either of the wheel paths. Perform diamond grinding on the traveled lanes only. Omit shoulders, bridges, and ramps. Cleaning and sealing existing joints and cracks will be subsidiary to this item.

Coordinate with the Engineer any necessary concrete spall repairs before performing any NGCS grinding.

CONTROL: 2121-04-124, ETC

COUNTY: EL PASO

HIGHWAY: IH 10

Item 6001 – Portable Changeable Message Sign

Provide messages as directed by the Engineer.

Provide two Portable Changeable Message Signs (PCMS) as advanced notification for two weeks prior to beginning project and throughout duration of project as directed.

Item 6185 – Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

All TMA Operators must participate in a TMA workshop to be conducted by the El Paso District Safety Office, on the proper use of TMAs, prior to working on Department Right of Way (ROW). A certificate of

completion will be issued to TMA Operators that successfully complete the TMA workshop. The certificate of completion must be carried by TMA Operators at all times while working on Department right of way.

Acquire the TCP and TMA Operator’s certificates of completion prior to the authorization to begin work. No time suspension will be granted and no traffic control work will be allowed without certificates of completion.

Up to three (3) total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA’s needed for the project.

The supporting vehicle for the TMA shall have a minimum gross (i.e., ballasted) vehicular weight of 19,000 pounds.

| Basis of Estimate for Stationary TMAs | | | | | |
|---------------------------------------|---------------------|----------|------------|-------|------|
| Phase | Standard | Required | Additional | Total | Days |
| Diamond Grinding | TCP (6-1) – 12 thru | 1 | 0 | 1 | 13 |
| NGCS | TCP (6-4)-12 | 1 | 0 | 1 | 13 |

| Basis of Estimate for Mobile TMAs | | | | | |
|-----------------------------------|--------------|----------|------------|-------|------|
| Phase | Standard | Required | Additional | Total | Days |
| Pavement Markers | TCP (3-2)-13 | 3 | 0 | 3 | 1 |
| Pavement Markings | | 3 | 0 | 3 | 7 |

DATE: 4/13/2023 4:17:56 PM
 FILE: \\txdot-projectwiseonline.com\TxDOT5\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\1 - General\IH10_2D_SUMMARY-01.dgn

DW: _____
 CK: _____
 DW: _____
 CK: _____

| SUMMARY OF MOBILIZATION ITEMS | | |
|-------------------------------|--------------|--|
| LOCATION | 500 | 502 |
| | 6001 | 6001 |
| | MOBILIZATION | BARRICADES, SIGNS AND TRAFFIC HANDLING |
| | LS | MO |
| 2121-04-124 | | |
| 2121-05-054 | 1 | 2 |
| PROJECT TOTALS | 1 | 2 |

| SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS | | | | | |
|---|------------------------------------|----------------------------------|----------------------------------|------------------|------------------------|
| LOCATION | 662 | 6001 | 6158 | 6185 | 6185 |
| | 6005 | 6002 | 6001 | 6002 | 6005 |
| | WK ZN PAV MRK NON-REMOV (W)6*(BRK) | PORTABLE CHANGEABLE MESSAGE SIGN | TMSP RADAR SPEED CONTROL MONITOR | TMA (STATIONARY) | TMA (MOBILE OPERATION) |
| | LF | EA | EA | DAY | DAY |
| 2121-04-124 | 1,320 | | | | |
| 2121-05-054 | 8,184 | 2 | 1 | 36 | 8 |
| PROJECT TOTALS | 9,504 | 2 | 1 | 36 | 8 |

| SUMMARY OF ROADWAY ITEMS | | |
|--------------------------|---------------------------------------|--------------------------------------|
| LOCATION | 3004 | 3012 |
| | 6001 | 6002 |
| | CONTINUOUS DIAMOND GRINDING CONC PVMT | NEXT GEN CONC SURF GRIND OF CONC PAV |
| | SY | SY |
| 2121-04-124 | 7,040 | 7040 |
| 2121-05-054 | 77,440 | 77440 |
| PROJECT TOTALS | 84,480 | 84,480 |

| SUMMARY OF PAVEMENT MARKING ITEMS | | | | | | | | | | | | | | | |
|-----------------------------------|-----------------------------------|---------------------------------------|--|---|---|---|---------------------------------|---------------------------------|----------------------------------|------------------------------------|------------------------------------|---------------------------------|---------------------------------------|--|--|
| LOCATION | 533 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 | 666 |
| | 6005 | 6017 | 6047 | 6080 | 6083 | 6161 | 6172 | 6174 | 6182 | 6193 | 6194 | 6210 | 6219 | 6285 | 6289 |
| | RUMBLE STRIPS (SHOULDER) CONCRETE | REFL PAV MRK TY I (W)6*(DOT)(09 0MIL) | REFL PAV MRK TY I (W)24*(SLD)(090 MIL) | REFL PAV MRK TY I(W)(ENTR GORE)(090MIL) | REFL PAV MRK TY I(W)(EXIT GORE)(090MIL) | RE PV MRK TY I(BLACK)6*(SHADOW)(090MIL) | REFL PAV MRK TY II (W) 6" (DOT) | REFL PAV MRK TY II (W) 6" (SLD) | REFL PAV MRK TY II (W) 24" (SLD) | REFL PAV MRK TY II (W) (ENTR GORE) | REFL PAV MRK TY II (W) (EXIT GORE) | REFL PAV MRK TY II (Y) 6" (SLD) | REFL PAV MRK TY II (BLACK) 6*(SHADOW) | REF PROF PAV MRK TY I(W)6*(SLD)(0 90MIL) | REF PROF PAV MRK TY I(Y)6*(SLD)(0 90MIL) |
| | LF | LF | LF | EA | EA | LF | LF | LF | LF | EA | EA | LF | LF | LF | LF |
| 2121-04-124 | | | | | | | | | | | | | | | |
| SHEET 1 OF 3 | 9,401 | 160 | | | 1 | 1,395 | 160 | 5,856 | | | 1 | 5,782 | 1395 | | |
| SHEET 2 OF 3 | 3,256 | | 35 | 1 | | 480 | | 4073 | 35 | 1 | | 4426 | 480 | | |
| CSJ TOTAL | 12,657 | 160 | 35 | 1 | 1 | 1,875 | 160 | 9,929 | 35 | 1 | 1 | 10,208 | 1,875 | | |
| 2121-05-054 | | | | | | | | | | | | | | | |
| SHEET 2 OF 3 | 1,900 | | 35 | | | 220 | | 1410 | 35 | | | 1370 | 220 | | |
| SHEET 3 OF 3 | 8,553 | 105 | | 2 | 2 | 11,065 | 105 | 30761 | | 2 | 2 | 32457 | 11065 | 300 | 300 |
| CSJ TOTAL | 10,453 | 105 | 35 | 2 | 2 | 11,285 | 105 | 32,171 | 35 | 2 | 2 | 33,827 | 11,285 | 300 | 300 |
| PROJECT TOTALS | 23,110 | 265 | 70 | 3 | 3 | 13,160 | 265 | 42,100 | 70 | 3 | 3 | 44,035 | 13,160 | 300 | 300 |

| SUMMARY OF PAVEMENT MARKING ITEMS CONT'D | | | | | | | | | | | | |
|--|--|--|--|------------------------|------------------------------|-------------------------------|-------------------------------------|-------------------------------------|----------------------------|-----------------------------|-----------------------------------|-----------------------------------|
| LOCATION | 666 | 666 | 666 | 672 | 677 | 677 | 677 | 677 | 678 | 678 | 678 | 678 |
| | 6305 | 6308 | 6320 | 6010 | 6001 | 6007 | 6013 | 6014 | 6002 | 6008 | 6017 | 6018 |
| | RE PM W/RET REQ TY I (W)6*(BRK)(0 90MIL) | RE PM W/RET REQ TY I (W)6*(SLD)(09 0MIL) | RE PM W/RET REQ TY I (Y)6*(SLD)(09 0MIL) | REFL PAV MRK TY II-C-R | ELIM EXT PAV MRK & MRKS (4") | ELIM EXT PAV MRK & MRKS (24") | ELIM EXT PAV MRK & MRKS (ENTR GORE) | ELIM EXT PAV MRK & MRKS (EXIT GORE) | PAV SURF PREP FOR MRK (6") | PAV SURF PREP FOR MRK (24") | PAV SURF PREP FOR MRK (ENTR GORE) | PAV SURF PREP FOR MRK (EXIT GORE) |
| | LF | LF | LF | EA | LF | LF | EA | EA | LF | LF | EA | EA |
| 2121-04-124 | | | | | | | | | | | | |
| SHEET 1 OF 3 | 1395 | 5856 | 5782 | 82 | 11638 | | | 1 | 14588 | | | 1 |
| SHEET 2 OF 3 | 480 | 4073 | 4426 | 24 | 8499 | 35 | 1 | | 9459 | 35 | 1 | |
| CSJ TOTAL | 1,875 | 9,929 | 10,208 | 106 | 20,137 | 35 | 1 | 1 | 24,047 | 35 | 1 | 1 |
| 2121-05-054 | | | | | | | | | | | | |
| SHEET 2 OF 3 | 220 | 1410 | 1370 | 20 | 2780 | 35 | | | 3220 | 35 | | |
| SHEET 3 OF 3 | 11065 | 30761 | 32457 | 454 | 63813 | | 2 | 2 | 89003 | | 2 | 2 |
| CSJ TOTAL | 11,285 | 32,171 | 33,827 | 474 | 66,593 | 35 | 2 | 2 | 92,223 | 35 | 2 | 2 |
| PROJECT TOTALS | 13,160 | 42,100 | 44,035 | 580 | 86,730 | 70 | 3 | 3 | 116,270 | 70 | 3 | 3 |


Texas Department of Transportation

IH 10

QUANTITY SUMMARY

SHEET 1 OF 1

| CONT | SECT | JOB | HIGHWAY |
|------|--------|-----------|---------|
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | COUNTY | SHEET NO. | |
| ELP | ELP | 7 | |



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 2121-04-124

DISTRICT El Paso
HIGHWAY IH 10

COUNTY El Paso

| CONTROL SECTION JOB | | | | 2121-04-124 | | 2121-05-054 | | TOTAL EST. | TOTAL FINAL |
|---------------------|-----------|--|------|-------------|-------|-------------|-------|-------------|-------------|
| PROJECT ID | | | | A00191781 | | A00191782 | | | |
| COUNTY | | | | El Paso | | El Paso | | | |
| HIGHWAY | | | | IH 10 | | IH 10 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | EST. | FINAL | | |
| | 500-6001 | MOBILIZATION | LS | | | 1.000 | | 1.000 | |
| | 502-6001 | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO | | | 2.000 | | 2.000 | |
| | 533-6005 | RUMBLE STRIPS (SHOULDER) CONCRETE | LF | 12,657.000 | | 10,453.000 | | 23,110.000 | |
| | 662-6005 | WK ZN PAV MRK NON-REMOV (W)6"(BRK) | LF | 1,320.000 | | 8,184.000 | | 9,504.000 | |
| | 666-6017 | REFL PAV MRK TY I (W)6"(DOT)(090MIL) | LF | 160.000 | | 105.000 | | 265.000 | |
| | 666-6047 | REFL PAV MRK TY I (W)24"(SLD)(090MIL) | LF | 35.000 | | 35.000 | | 70.000 | |
| | 666-6080 | REFL PAV MRK TY I(W)(ENTR GORE)(090MIL) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 666-6083 | REFL PAV MRK TY I(W)(EXIT GORE)(090MIL) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 666-6161 | RE PV MRK TY I(BLACK)6"(SHADOW)(090MIL) | LF | 1,875.000 | | 11,285.000 | | 13,160.000 | |
| | 666-6172 | REFL PAV MRK TY II (W) 6" (DOT) | LF | 160.000 | | 105.000 | | 265.000 | |
| | 666-6174 | REFL PAV MRK TY II (W) 6" (SLD) | LF | 9,929.000 | | 32,171.000 | | 42,100.000 | |
| | 666-6182 | REFL PAV MRK TY II (W) 24" (SLD) | LF | 35.000 | | 35.000 | | 70.000 | |
| | 666-6193 | REFL PAV MRK TY II (W) (ENTR GORE) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 666-6194 | REFL PAV MRK TY II (W) (EXIT GORE) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 666-6210 | REFL PAV MRK TY II (Y) 6" (SLD) | LF | 10,208.000 | | 33,827.000 | | 44,035.000 | |
| | 666-6219 | REFL PAV MRK TY II (BLACK) 6"(SHADOW) | LF | 1,875.000 | | 11,285.000 | | 13,160.000 | |
| | 666-6285 | REF PROF PAV MRK TY I(W)6"(SLD)(090MIL) | LF | | | 300.000 | | 300.000 | |
| | 666-6289 | REF PROF PAV MRK TY I(Y)6"(SLD)(090MIL) | LF | | | 300.000 | | 300.000 | |
| | 666-6305 | RE PM W/RET REQ TY I (W)6"(BRK)(090MIL) | LF | 1,875.000 | | 11,285.000 | | 13,160.000 | |
| | 666-6308 | RE PM W/RET REQ TY I (W)6"(SLD)(090MIL) | LF | 9,929.000 | | 32,171.000 | | 42,100.000 | |
| | 666-6320 | RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL) | LF | 10,208.000 | | 33,827.000 | | 44,035.000 | |
| | 672-6010 | REFL PAV MRKR TY II-C-R | EA | 106.000 | | 474.000 | | 580.000 | |
| | 677-6001 | ELIM EXT PAV MRK & MRKS (4") | LF | 20,137.000 | | 66,593.000 | | 86,730.000 | |
| | 677-6007 | ELIM EXT PAV MRK & MRKS (24") | LF | 35.000 | | 35.000 | | 70.000 | |
| | 677-6013 | ELIM EXT PAV MRK & MRKS (ENTR GORE) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 677-6014 | ELIM EXT PAV MRK & MRKS (EXIT GORE) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 678-6002 | PAV SURF PREP FOR MRK (6") | LF | 24,047.000 | | 92,223.000 | | 116,270.000 | |
| | 678-6008 | PAV SURF PREP FOR MRK (24") | LF | 35.000 | | 35.000 | | 70.000 | |
| | 678-6017 | PAV SURF PREP FOR MRK (ENTR GORE) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 678-6018 | PAV SURF PREP FOR MRK (EXIT GORE) | EA | 1.000 | | 2.000 | | 3.000 | |
| | 3004-6001 | CONTINUOUS DIAMOND GRINDING CONC PVMT | SY | 7,040.000 | | 77,440.000 | | 84,480.000 | |
| | 3012-6002 | NEXT GEN CONC SURF GRIND OF CONC PAV | SY | 7,040.000 | | 77,440.000 | | 84,480.000 | |
| | 6001-6002 | PORTABLE CHANGEABLE MESSAGE SIGN | EA | | | 2.000 | | 2.000 | |
| | 6158-6001 | TMSP RADAR SPEED CONTROL MONITOR | EA | | | 1.000 | | 1.000 | |
| | 6185-6002 | TMA (STATIONARY) | DAY | | | 36.000 | | 36.000 | |
| | 6185-6005 | TMA (MOBILE OPERATION) | DAY | | | 8.000 | | 8.000 | |
| | 08 | CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING) | LS | | | 1.000 | | 1.000 | |



| | | | |
|----------|---------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| El Paso | El Paso | 2121-04-124 | 8 |



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 2121-04-124

DISTRICT El Paso

COUNTY El Paso

HIGHWAY IH 10

| CONTROL SECTION JOB | | | | 2121-04-124 | | 2121-05-054 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|---|------|-------------|-------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00191781 | | A00191782 | | | |
| COUNTY | | | | El Paso | | El Paso | | | |
| HIGHWAY | | | | IH 10 | | IH 10 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | EST. | FINAL | | |
| | 08 | CONTRACTOR FORCE ACCOUNT LAW ENFORCEMENT (NON-PARTICIPATING) | LS | | | 1.000 | | 1.000 | |
| | | CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING) | LS | | | 1.000 | | 1.000 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.
2.
 No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SWP3 and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
 Individual 404 Permit Required
 Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.
2.
3.
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

| | | |
|--|--|--|
| Erosion | Sedimentation | Post-Construction TSS |
| <input type="checkbox"/> Temporary Vegetation | <input type="checkbox"/> Silt Fence | <input type="checkbox"/> Vegetative Filter Strips |
| <input type="checkbox"/> Blankets/Matting | <input type="checkbox"/> Rock Berm | <input type="checkbox"/> Retention/Irrigation Systems |
| <input type="checkbox"/> Mulch | <input type="checkbox"/> Triangular Filter Dike | <input type="checkbox"/> Extended Detention Basin |
| <input type="checkbox"/> Sodding | <input type="checkbox"/> Sand Bag Berm | <input type="checkbox"/> Constructed Wetlands |
| <input type="checkbox"/> Interceptor Swale | <input type="checkbox"/> Straw Bale Dike | <input type="checkbox"/> Wet Basin |
| <input type="checkbox"/> Diversion Dike | <input type="checkbox"/> Brush Berms | <input type="checkbox"/> Erosion Control Compost |
| <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Mulch Filter Berm and Socks |
| <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks |
| <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Vegetation Lined Ditches |
| | <input type="checkbox"/> Stone Outlet Sediment Traps | <input type="checkbox"/> Sand Filter Systems |
| | <input type="checkbox"/> Sediment Basins | <input type="checkbox"/> Grassy Swales |

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

| | |
|---|---|
| BMP: Best Management Practice | SPCC: Spill Prevention Control and Countermeasure |
| CGP: Construction General Permit | SW3P: Storm Water Pollution Prevention Plan |
| DSHS: Texas Department of State Health Services | PCN: Pre-Construction Notification |
| FHWA: Federal Highway Administration | PSL: Project Specific Location |
| MOA: Memorandum of Agreement | TCEQ: Texas Commission on Environmental Quality |
| MOU: Memorandum of Understanding | TPDES: Texas Pollutant Discharge Elimination System |
| MS4: Municipal Separate Stormwater Sewer System | TPWD: Texas Parks and Wildlife Department |
| MBTA: Migratory Bird Treaty Act | TxDOT: Texas Department of Transportation |
| NOT: Notice of Termination | T&E: Threatened and Endangered Species |
| NWP: Nationwide Permit | USACE: U.S. Army Corps of Engineers |
| NOI: Notice of Intent | USFWS: U.S. Fish and Wildlife Service |

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

1.
2.
3.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action No.

1.
2.
3.

| | | | |
|---|-----------|---------------------------------|-------------|
|  Texas Department of Transportation | | <i>Design Division Standard</i> | |
| ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS | | | |
| EPIC | | | |
| FILE: epic.dgn | DN: TxDOT | CK: RG | DW: VP |
| ©TxDOT: February 2015 | CONT | SECT | JOB |
| 12-12-2011 (DS) REVISIONS | 2121 | 04 | 124, ETC |
| 05-07-14 ADDED NOTE SECTION IV. | DIST | COUNTY | IH 10 |
| 01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES. | ELP | ELP | SHEET NO. 9 |

NOTES:

1. THE CONTRACTOR SHALL FOLLOW ALL TXDOT STANDARDS FOR TRAFFIC CONTROL AND FOLLOW THE TRAFFIC CONTROL PLAN (TCP) AT ALL TIMES. ANY DEVIATION FROM THE ADOPTED TCP SHALL BE REVIEWED AND APPROVED BY THE ENGINEER.
2. DO NOT STORE ANY CONSTRUCTION MATERIAL OR EQUIPMENT AT ANY LOCATION THAT WILL CONSTITUTE A HAZARD AND ENDANGER TRAFFIC.
3. AT NO TIME TWO CONSECUTIVE RAMPS SHALL BE CLOSED AT ONE TIME DURING CONSTRUCTION. REFER TO TCP (6-2)-12, TCP (6-4)-12, AND TCP (6-8)-14 FOR WORK AREA ON GORES, NEAR RAMP, AND WORK AREA RAMP.
4. ENSURE TO PROTECT EXISTING RUMBLE STRIPS THAT ARE ADJACENT TO THE GRINDING OPERATIONS.
5. DIAMOND GRINDING AND NGCS SHALL NOT BE PERFORMED ON ANY BRIDGES, RAMPS, OR SHOULDERS.

SEQUENCE OF CONSTRUCTION:

1. THE PROJECT SHALL BE CONSTRUCTED IN 2 PHASES. BEFORE THE COMMENCEMENT OF EACH PHASE, INSTALL THE RADAR SPEED CONTROL MONITOR, ADVANCE WARNING SIGNS, TEMPORARY SIGNS AND BARRICADES AS SHOWN ON THE TXDOT STANDARDS OR AS DIRECTED BY THE ENGINEER.
2. DAILY LANE CLOSURES WILL BE IN ACCORDANCE WITH TXDOT TCP STANDARDS.

PHASE 1 STEP 1: IH 10 EASTBOUND MAINLANES DIAMOND GRINDING AND NEXT GENERATION CONCRETE SURFACE (NGCS) GRINDING.

1. IMPLEMENT TRAFFIC CONTROL.
2. CONCRETE SPALL REPAIRS TO BE PERFORMED BY OTHERS PRIOR TO DIAMOND GRINDING AND NGCS OPERATIONS. COORDINATE ACCORDINGLY WITH THE ENGINEER.
3. PERFORM DIAMOND GRINDING UTILIZING TXDOT STANDARD TCP (6-1)-12 AND APPLICABLE TCP STANDARDS FOR WORK AREA NEAR RAMP AND WORK AREA AT RAMP. THIS OPERATION MUST BE LIMITED TO WHAT CAN BE COMPLETED DURING ONE WORKDAY ON ONE FULL LANE WIDTH.
4. PLACE WORK ZONE PAVEMENT MARKINGS AND PERFORM CLEAN-UP OPERATION PRIOR TO MOVING TO A NEW REFERENCE OR PRIOR TO OPENING TO TRAFFIC AT THE END OF THE DAY.
6. PERFORM NGCS GRINDING UTILIZING TXDOT STANDARD TCP (6-1)-12 AND APPLICABLE TCP STANDARDS FOR WORK AREA NEAR RAMP AND WORK AREA AT RAMP. THE TWO PASS NGCS OPERATION MUST BE PERFORMED WITHIN THE SAME LANE CLOSURE. THIS OPERATION MUST BE LIMITED TO WHAT CAN BE COMPLETED DURING ONE WORKDAY ON ONE FULL LANE WIDTH.
7. PLACE WORK ZONE PAVEMENT MARKINGS AND PERFORM CLEAN-UP OPERATION PRIOR TO MOVING TO A NEW REFERENCE OR PRIOR TO OPENING TO TRAFFIC AT THE END OF THE DAY.

PHASE 1 STEP 2: IH 10 WESTBOUND MAINLANES DIAMOND GRINDING AND NEXT GENERATION CONCRETE SURFACE (NGCS) GRINDING.

1. REPEAT PHASE 1 STEP 1 FOR IH 10 WESTBOUND MAINLANES GRINDING OPERATIONS.

PHASE 2: STRIPING AND RPM INSTALLATION

1. IMPLEMENT TRAFFIC CONTROL.
2. REMOVE PAVEMENT MARKINGS.
3. PLACE NEW PAVEMENT MARKINGS AND RAISED PAVEMENT MARKINGS UTILIZING TXDOT STANDARDS TCP(3-2)-13, TCP(3-3)-14, AND TCP (6-8)-14.
4. PERFORM CLEAN-UP AND REMOVAL OF TEMPORARY TRAFFIC CONTROL ITEMS.

| TCP SELECTION TABLE | | | | |
|----------------------|--|------------------------------|--|---|
| PHASE | TYPE OF WORK | STANDARD | SHEET DESCRIPTION | SUGGESTED SHEET DIAGRAM |
| 1, STEP 1 AND STEP 2 | WESTBOUND AND EASTBOUND MAINLANES DIAMOND GRINDING AND NEXT GENERATION CONCRETE SURFACE (NGCS) GRINDING, WORK ZONE PAVEMENT MARKINGS | TCP (6-1)-12 | TRAFFIC CONTROL PLAN FREEWAY LANE CLOSURES | TCP (6-1a): ONE LANE CLOSURE ADDITIONAL PORTABLE CHANGEABLE MESSAGE SIGN (PCMS) SHALL BE USED AS REQUIRED, AT THE DISCRETION OF THE ENGINEER. |
| 2 | PAVEMENT MARKINGS | TCP (3-2)-13 TCP (6-8)-14 | MOBILE OPERATIONS - DIVIDED HIGHWAYS | TCP (3-2a) & TCP (3-2b): MOBILE OPERATION TCP (6-8): WORK ON EXIT GORE |
| | RPM INSTALLATION | TCP (3-3)-14 TCP (6-8)-14 | MOBILE OPERATIONS - RPM INSTALLATION/REMOVAL | TCP (3-3c): DIVIDED MULTILANE HIGHWAY TCP (6-8): WORK ON EXIT GORE |



Karla Rios, P.E.

04/14/2023

| | | | |
|---|--------|----------|-----------|
| | | | |
| <h2>IH 10</h2> | | | |
| <h3>TRAFFIC CONTROL PLAN NARRATIVE</h3> | | | |
| SHEET 1 OF 1 | | | |
| CONT | SECT | JOB | HIGHWAY |
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | COUNTY | | SHEET NO. |
| ELP | ELP | | 10 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions resulting from its use.

DATE: 4/14/2023 10:40:33 AM
 FILE: //txdot.projectwiseonline.com:txdot15/Documents/24 - ELP/Design Projects/24 - Design/Sign Set/24 - BC(1)-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


| |
|---|
| THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov |
| COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) |
| DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) |
| MATERIAL PRODUCER LIST (MPL) |
| ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS) " |
| STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) |
| TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) |
| TRAFFIC ENGINEERING STANDARD SHEETS |

SHEET 1 OF 12

| | | | |
|---|---------------|----------------------------------|-----------|
|  Texas Department of Transportation | | Traffic Safety Division Standard | |
| BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS | | | |
| BC (1) - 21 | | | |
| FILE: | bc-21.dgn | DN: | TxDOT |
| © TxDOT | November 2002 | CK: | TxDOT |
| | | DW: | TxDOT |
| | | CK: | TxDOT |
| CONT | SECT | JOB | HIGHWAY |
| 2121 | 04 | 124, ETC | IH 10 |
| REVISIONS | | DIST | COUNTY |
| 4-03 | 7-13 | | |
| 9-07 | 8-14 | | |
| 5-10 | 5-21 | ELP | ELP |
| | | | SHEET NO. |
| | | | 11 |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

| Sign Number or Series | SIZE | | SPACING | |
|---------------------------------------|-------------------|--------------------|------------------|----------------------------------|
| | Conventional Road | Expressway/Freeway | Posted Speed MPH | Sign Δ Spacing "x" Feet (Apprx.) |
| CW20 ⁴ | 48" x 48" | 48" x 48" | 30 | 120 |
| CW21 | | | 35 | 160 |
| CW22 | | | 40 | 240 |
| CW23 | | | 45 | 320 |
| CW25 | | | 50 | 400 |
| CW1, CW2, CW7, CW8, CW9, CW11, CW14 | 36" x 36" | 48" x 48" | 55 | 500 ² |
| CW3, CW4, CW5, CW6, CW8-3, CW10, CW12 | 48" x 48" | 48" x 48" | 60 | 600 ² |
| | | | 65 | 700 ² |
| | | | 70 | 800 ² |
| | | | 75 | 900 ² |
| | | | 80 | 1000 ² |
| | | | * | * ³ |


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

| LEGEND | |
|--------|---|
| | Type 3 Barricade |
| | Channelizing Devices |
| | Sign |
| | See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements. |

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 9-07 8-14 | DIST | COUNTY | | SHEET NO. |
| 7-13 5-21 | ELP | ELP | | 12 |

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

| | |
|--------------------|----------------|
| 40 mph and greater | 0.2 to 2 miles |
| 35 mph and less | 0.2 to 1 mile |
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided herein.

DATE: 4/14/2023 10:40:44 AM
FILE: \\txdot.projectwiseonline.com:txdot\Documents\24 - ELP\Design Projects\24-0472\BC(3)-21.dgn


SHEET 3 OF 12

| | | | |
|---|---------------|-----------|-----------|
| | | | |
| <h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2> | | | |
| <h3>BC (3) - 21</h3> | | | |
| FILE: | bc-21.dgn | DN: TxDOT | CK: TxDOT |
| © TxDOT | November 2002 | CONT | SECT |
| REVISIONS | | JOB | HIGHWAY |
| 9-07 | 8-14 | 2121 04 | 124, ETC |
| 7-13 | 5-21 | DIST | COUNTY |
| | | ELP | ELP |
| | | | SHEET NO. |
| | | | 13 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/14/2023 10:40:50 AM
 FILE: pw://txdot.projectwiseonline.com:ELP/Design Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/bc-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



| SHEETING REQUIREMENTS (WHEN USED AT NIGHT) | | |
|--|--------|--|
| USAGE | COLOR | SIGN FACE MATERIAL |
| BACKGROUND | RED | TYPE B OR C SHEETING |
| BACKGROUND | ORANGE | TYPE B _{FL} OR C _{FL} SHEETING |
| LEGEND & BORDER | WHITE | TYPE B OR C SHEETING |
| LEGEND & BORDER | BLACK | ACRYLIC NON-REFLECTIVE FILM |

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

Texas Department of Transportation
 Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ELP | ELP | 14 | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/14/2023 10:40:55 AM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\24 - ELP\Design Projects\21210412474 - Design\Plan Set\2 - TSP\Standards\bc-21.dgn




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- * See BC(4) for definition of "Work Duration."
- ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

| | | | | | | | | | |
|-----------|---------------|------|----------|-----------|---------|-----|-------|-----|-------|
| FILE: | bc-21.dgn | DN: | TxDOT | CK: | TxDOT | DW: | TxDOT | CR: | TxDOT |
| © TxDOT | November 2002 | CONT | SECT | JOB | HIGHWAY | | | | |
| REVISIONS | 2121 | 04 | 124, ETC | IH | 10 | | | | |
| 9-07 | 8-14 | DIST | COUNTY | SHEET NO. | | | | | |
| 7-13 | 5-21 | ELP | ELP | 15 | | | | | |

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

| | |
|-----------------------|--------------------------|
| FREEWAY CLOSED X MILE | FRONTAGE ROAD CLOSED |
| ROAD CLOSED AT SH XXX | SHOULDER CLOSED XXX FT |
| ROAD CLSD AT FM XXXX | RIGHT LN CLOSED XXX FT |
| RIGHT X LANES CLOSED | RIGHT X LANES OPEN |
| CENTER LANE CLOSED | DAYTIME LANE CLOSURES |
| NIGHT LANE CLOSURES | I-XX SOUTH EXIT CLOSED |
| VARIOUS LANES CLOSED | EXIT XXX CLOSED X MILE |
| EXIT CLOSED | RIGHT LN TO BE CLOSED |
| MALL DRIVEWAY CLOSED | X LANES CLOSED TUE - FRI |
| XXXXXXXX BLVD CLOSED | |

Other Condition List

| | |
|--------------------------|-------------------------|
| ROADWORK XXX FT | ROAD REPAIRS XXXX FT |
| FLAGGER XXXX FT | LANE NARROWS XXXX FT |
| RIGHT LN NARROWS XXXX FT | TWO-WAY TRAFFIC XX MILE |
| MERGING TRAFFIC XXXX FT | CONST TRAFFIC XXX FT |
| LOOSE GRAVEL XXXX FT | UNEVEN LANES XXXX FT |
| DETOUR X MILE | ROUGH ROAD XXXX FT |
| ROADWORK PAST SH XXXX | ROADWORK NEXT FRI-SUN |
| BUMP XXXX FT | US XXX EXIT X MILES |
| TRAFFIC SIGNAL XXXX FT | LANES SHIFT * |

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

| | |
|----------------------|----------------------|
| MERGE RIGHT | FORM X LINES RIGHT |
| DETOUR NEXT X EXITS | USE XXXXX RD EXIT |
| USE EXIT XXX | USE EXIT I-XX NORTH |
| STAY ON US XXX SOUTH | USE I-XX E TO I-XX N |
| TRUCKS USE US XXX N | WATCH FOR TRUCKS |
| WATCH FOR TRUCKS | EXPECT DELAYS |
| EXPECT DELAYS | PREPARE TO STOP |
| REDUCE SPEED XXX FT | END SHOULDER USE |
| USE OTHER ROUTES | WATCH FOR WORKERS |
| STAY IN LANE * | |

Location List

| |
|--------------------------|
| AT FM XXXX |
| BEFORE RAILROAD CROSSING |
| NEXT X MILES |
| PAST US XXX EXIT |
| XXXXXXXX TO XXXXXXX |
| US XXX TO FM XXXX |

Warning List

| |
|-----------------------|
| SPEED LIMIT XX MPH |
| MAXIMUM SPEED XX MPH |
| MINIMUM SPEED XX MPH |
| ADVISORY SPEED XX MPH |
| RIGHT LANE EXIT |
| USE CAUTION |
| DRIVE SAFELY |
| DRIVE WITH CARE |

** Advance Notice List

| |
|-----------------------|
| TUE-FRI XX AM-X PM |
| APR XX-XX X PM-X AM |
| BEGINS MONDAY |
| BEGINS MAY XX |
| MAY X-X XX PM - XX AM |
| NEXT FRI-SUN |
| XX AM TO XX PM |
| NEXT TUE AUG XX |
| TONIGHT XX PM-XX AM |

** See Application Guidelines Note 6.

| WORD OR PHRASE | ABBREVIATION | WORD OR PHRASE | ABBREVIATION |
|------------------------|--------------|----------------|--------------|
| Access Road | ACCS RD | Major | MAJ |
| Alternate | ALT | Miles | MI |
| Avenue | AVE | Miles Per Hour | MPH |
| Best Route | BEST RTE | Minor | MNR |
| Boulevard | BLVD | Monday | MON |
| Bridge | BRDG | Normal | NORM |
| Canot | CANT | North | N |
| Center | CTR | Northbound | (route) N |
| Construction Ahead | CONST AHD | Parking | PKING |
| CROSSING | XING | Road | RD |
| Detour Route | DETOUR RTE | Right Lane | RT LN |
| Do Not | DONT | Saturday | SAT |
| East | E | Service Road | SERV RD |
| Eastbound | (route) E | Shoulder | SHLDR |
| Emergency | EMER | Slippery | SLIP |
| Emergency Vehicle | EMER VEH | South | S |
| Entrance, Enter | ENT | Southbound | (route) S |
| Express Lane | EXP LN | Speed | SPD |
| Expressway | EXPWY | Street | ST |
| XXXX Feet | XXXX FT | Sunday | SUN |
| Fog Ahead | FOG AHD | Telephone | PHONE |
| Freeway | FRWY, FWY | Temporary | TEMP |
| Freeway Blocked | FWY BLKD | Thursday | THURS |
| Friday | FRI | To Downtown | TO DWNTN |
| Hazardous Driving | HAZ DRIVING | Traffic | TRAF |
| Hazardous Material | HAZMAT | Travelers | TRVLR |
| High-Occupancy Vehicle | HOV | Tuesday | TUES |
| Highway | HWY | Time Minutes | TIME MIN |
| Hour(s) | HR, HRS | Upper Level | UPR LEVEL |
| Information | INFO | Vehicles (s) | VEH, VEHS |
| It Is | ITS | Warning | WARN |
| Junction | JCT | Wednesday | WED |
| Left | LFT | Weight Limit | WT LIMIT |
| Left Lane | LFT LN | West | W |
| Lane Closed | LN CLOSED | Westbound | (route) W |
| Lower Level | LWR LEVEL | Wet Pavement | WET PVMT |
| Maintenance | MAINT | Will Not | WONT |

Roadway designation # IH-number, US-number, SH-number, FM-number

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

SHEET 6 OF 12

| | | | |
|---|---------------|-----------|-------|
| | | | |
| <h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3> | | | |
| <h2>BC (6) - 21</h2> | | | |
| FILE: | bc-21.dgn | DN: | TxDOT |
| © TxDOT | November 2002 | CONT: | SECT: |
| REVISIONS | | 2121 | 04 |
| 9-07 | 8-14 | 124, ETC | |
| 7-13 | 5-21 | IH 10 | |
| DIST: | COUNTY: | SHEET NO. | |
| ELP | ELP | 16 | |


DATE: 4/14/2023 10:41:01 AM

FILE: p:\t\dot\project\wiseonline.com\txdot\Documents\24 - ELP\Design Projects\2121012474 - Design\Plan Set\2 - PCMSStandards\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/14/2023 10:41:06 AM
 FILE: \\txdot.projectwiseonline.com:ELP/Design/Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)


- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

| REQUIREMENTS | | | |
|--------------|--------------|-------------------------------|-----------------------------|
| TYPE | MINIMUM SIZE | MINIMUM NUMBER OF PANEL LAMPS | MINIMUM VISIBILITY DISTANCE |
| B | 30 x 60 | 13 | 3/4 mile |
| C | 48 x 96 | 15 | 1 mile |

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

| | | | | | | | | | |
|-----------|---------------|------|--------|-----------|---------|-----|-------|-----|-------|
| FILE: | bc-21.dgn | DN: | TxDOT | CR: | TxDOT | OW: | TxDOT | CK: | TxDOT |
| © TxDOT | November 2002 | CONT | SECT | JOB | HIGHWAY | | | | |
| REVISIONS | | 2121 | 04 | 124, ETC | IH 10 | | | | |
| 9-07 | 8-14 | DIST | COUNTY | SHEET NO. | | | | | |
| 7-13 | 5-21 | ELP | ELP | 17 | | | | | |

DATE: 4/14/2023 10:41:13 AM
 FILE: pw://txdot.projectwiseonline.com:TxDOT15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS



- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS


- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12

| | | | |
|---|---------------|----------------------------------|--------------|
| | | Traffic Safety Division Standard | |
| BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES | | | |
| BC (8) - 21 | | | |
| FILE: | bc-21.dgn | DWG: | TxDOT |
| © TxDOT | November 2002 | CONT: | 2121 |
| REVISIONS | | SECT: | 04 |
| 4-03 | 8-14 | JOB: | 124, ETC |
| 9-07 | 5-21 | HIGHWAY: | IH 10 |
| 7-13 | | DIST: | COUNTY |
| | | ELP: | ELP |
| | | | SHEET NO. 18 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/14/2023 10:41:18 AM
 FILE: pw://txdot.projectwiseonline.com:txdot15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/bc-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




PORTABLE

VERTICAL PANELS (VPs)




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

| Posted Speed | Formula | Minimum Desirable Taper Lengths * * | | | Suggested Maximum Spacing of Channelizing Devices | |
|--------------|--------------------------|-------------------------------------|------------|------------|---|--------------|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' |
| 35 | | 205' | 225' | 245' | 35' | 70' |
| 40 | | 265' | 295' | 320' | 40' | 80' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' |
| 50 | | 500' | 550' | 600' | 50' | 100' |
| 55 | | 550' | 605' | 660' | 55' | 110' |
| 60 | | 600' | 660' | 720' | 60' | 120' |
| 65 | | 650' | 715' | 780' | 65' | 130' |
| 70 | | 700' | 770' | 840' | 70' | 140' |
| 75 | | 750' | 825' | 900' | 75' | 150' |
| 80 | | 800' | 880' | 960' | 80' | 160' |

* * *Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 9-07 8-14 | DIST | COUNTY | | SHEET NO. |
| 7-13 5-21 | ELP | ELP | | 19 |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/14/2023 10:41:24 AM
 FILE: \\txdot.projectwiseonline.com:txdot15\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\2 - TCP\Standards\bc-21.dgn


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

| LEGEND | |
|--------|---|
| | Plastic drum |
| | Plastic drum with steady burn light or yellow warning reflector |
| | Steady burn warning light or yellow warning reflector |



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 5-21 | ELP | ELP | 20 | |

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS


- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

| DEPARTMENTAL MATERIAL SPECIFICATIONS | |
|--|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| TRAFFIC BUTTONS | DMS-4300 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |
| TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS | DMS-8242 |

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CR: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT February 1998 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 2-98 9-07 5-21 | DIST | COUNTY | SHEET NO. | |
| 1-02 7-13 | ELP | ELP | 21 | |
| 11-02 8-14 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/14/2023 10:41:29 AM
 FILE: pw://txdot.projectwiseonline.com:txdot15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS



BC(12)-21

| | | | | |
|----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-21.dgn | DN: TxDOT | CK: TxDOT | OW: TxDOT | CR: TxDOT |
| ©TxDOT February 1998 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 1-97 9-07 5-21 | DIST | COUNTY | | SHEET NO. |
| 2-98 7-13 | ELP | ELP | | 22 |
| 11-02 8-14 | | | | |



Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DATE: 4/14/2023 10:41:35 AM
 FILE: D:\txdot\project\wiseonline.com\txdot\Documents\24 - ELP\Design Projects\2121041244 - Design\Plan Set\2 - TCP\Standards\bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/13/2023 4:20:34 PM
 FILE: pw://txdot.projectwiseonline.com:txdot15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/tcp3-2.dgn



RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)




INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)

| LEGEND | | | |
|--------|--------------------------------|---------------------|---|
| * | Trail Vehicle | ARROW BOARD DISPLAY | |
| ** | Shadow Vehicle | | |
| *** | Work Vehicle | | RIGHT Directional |
| | Heavy Work Vehicle | | LEFT Directional |
| | Truck Mounted Attenuator (TMA) | | Double Arrow |
| | Traffic Flow | | CAUTION (Alternating Diamond or 4 Corner Flash) |

| TYPICAL USAGE | | | | |
|-------------------------------------|--------------------------|--------------------------|------------------------------|--------------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

GENERAL NOTES

- ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
- For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
- Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
- The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
- Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
- The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.











STRIPING FOR TMA

| | | | |
|--|---------------|---|--------------|
| | | Traffic Operations Division Standard | |
| TRAFFIC CONTROL PLAN MOBILE OPERATIONS DIVIDED HIGHWAYS | | | |
| TCP(3-2)-13 | | | |
| FILE: | tcp3-2.dgn | DN: | TxDOT |
| © TxDOT | December 1985 | CONT: | SECT |
| REVISIONS | 2121 | 04 | 124, ETC |
| 2-94 | 4-98 | | IH 10 |
| 8-95 | 7-13 | DIST: | COUNTY |
| 1-97 | | ELP: | ELP |
| | | | SHEET NO. 23 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/13/2023 4:20:56 PM
 FILE: \\txdot.projectwiseonline.com:TXDOT\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\2 - TCP\Standards\tcp3-3.dgn



| LEGEND | | |
|-------------------|---------------------|---|
| * Trail Vehicle | ARROW BOARD DISPLAY | |
| ** Shadow Vehicle | | |
| *** Work Vehicle | | RIGHT Directional |
| | | LEFT Directional |
| | | Double Arrow |
| | | CAUTION (Alternating Diamond or 4 Corner Flash) |

| TYPICAL USAGE | | | | |
|-------------------------------------|--------------------------|--------------------------|------------------------------|--------------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
12. For divided highways with three or four lanes in each direction, use TCP(3-2).
13. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
14. The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
15. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation


Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS
 RAISED PAVEMENT
 MARKER INSTALLATION/
 REMOVAL
 TCP (3-3) - 14**


| | | | | |
|------------------------|-----------|-----------|-----------|-----------|
| FILE: tcp3-3.dgn | DN: TxDOT | CK: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT September 1987 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 2-94 4-98 | DIST | COUNTY | | SHEET NO. |
| 8-95 7-13 | ELP | ELP | | 24 |
| 1-97 7-14 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/13/2023 4:21:18 PM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\2 - TCP\Standards\tcp6-1.dgn



TCP (6-1a)
TYPICAL FREEWAY ONE LANE CLOSURE



TCP (6-1b)
TYPICAL FREEWAY TWO LANE CLOSURE

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 540' |
| 80 | 800' | 880' | 960' | 80' | 160' | 615' | |

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.




**TRAFFIC CONTROL PLAN
 FREEWAY LANE CLOSURES**

TCP (6-1) - 12


| | | | | | | | | | |
|---------|---------------|--------|-------|-----------|---------|-----|-------|-----|-------|
| FILE: | tcp6-1.dgn | DN: | TxDOT | CK: | TxDOT | DW: | TxDOT | CK: | TxDOT |
| © TxDOT | February 1998 | CONT | SECT | JOB | HIGHWAY | | | | |
| 8-12 | REVISIONS | 2121 | 04 | 124, ETC | IH 10 | | | | |
| | DIST | COUNTY | | SHEET NO. | | | | | |
| | ELP | ELP | | 25 | | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/13/2023 4:21:42 PM
 FILE: pw://txdot.projectwiseonline.com:txdot/Design/Projects/212104124/4 - ELP/Design/Plan Set/2 - TCP/Standards/tcp6-2.dgn



TCP (6-2a)
ENTRANCE RAMP OPEN
WORK WITHIN 500' OF RAMP



TCP (6-2b)
ENTRANCE RAMP CLOSED

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 540' |
| 80 | | 800' | 880' | 960' | 80' | 160' | 615' |

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset(FT) S=Posted Speed(MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainlane can be seen from both roadways.
- See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA NEAR RAMP

TCP (6-2) - 12


| | | | | | | | | | |
|-----------|---------------|------|----------|-----------|---------|-----|-------|-----|-------|
| FILE: | tcp6-2.dgn | DN: | TxDOT | CK: | TxDOT | DW: | TxDOT | CK: | TxDOT |
| ©TxDOT | February 1994 | CONT | SECT | JOB | HIGHWAY | | | | |
| REVISIONS | 2121 | 04 | 124, ETC | IH | 10 | | | | |
| 1-97 | 8-98 | DIST | COUNTY | SHEET NO. | | | | | |
| 4-98 | 8-12 | ELP | ELP | 26 | | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/13/2023 4:22:05 PM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\2 - TCP\Standards\tcp6-3.dgn



TCP (6-3a)
ENTRANCE RAMP OPEN



TCP (6-3b)
EXIT RAMP CLOSED
TRAFFIC EXITS PRIOR TO CLOSED RAMP

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" ** | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|--|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 540' |
| 80 | | 800' | 880' | 960' | 80' | 160' | 615' |

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | |

GENERAL NOTES:

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA BEYOND RAMP

TCP (6-3) - 12

| | | | | |
|----------------------|-----------|-----------|-----------|-----------|
| FILE: tcp6-3.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| ©TxDOT February 1994 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 1-97 8-98 | DIST | COUNTY | SHEET NO. | |
| 4-98 8-12 | ELP | ELP | 27 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/13/2023 4:22:27 PM
 FILE: \\txdot.projectwiseonline.com:txdot\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\2 - TCP\Standards\tcp6-4.dgn




TCP (6-4a)
EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP

| | |
|----------------------------|-------------------------|
| STREET A EXIT CLOSED | USE STREET B EXIT |
| EXIT XX CLOSED | USE EXIT XY |

Or, as an option when exits are numbered

Place 1 mile (approx.) in advance of closed ramp.



TCP (6-4b)
EXIT RAMP OPEN

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices (CDs) |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 540' |
| 80 | | 800' | 880' | 960' | 80' | 160' | 615' |

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP (6-4) - 12


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: tcp6-4.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT February 1994 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 1-97 8-98 | DIST | COUNTY | SHEET NO. | |
| 4-98 8-12 | ELP | ELP | 28 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 1/14/2023
 FILE: \\txdotprojectwiseonline.com\txdot\Documents\24 - ELP\Design Projects\212104124\4 - Design\Plan Set\2 - TCP\Standards\tcp6-8.dgn



TCP (6-8a)



TCP (6-8b)



TCP (6-8c)

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices (CDs) |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" ** | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|--|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 540' |
| 80 | | 800' | 880' | 960' | 80' | 160' | 615' |

** Taper lengths have been rounded off.
 L = Length of Taper (FT) W = Width of Offset (FT)
 S = Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | | |

- GENERAL NOTES**
- Place channelizing devices in the gore at 20' spacing.
 - See the Standard Highway Sign Design for Texas (SHSD) for sign details.
 - The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
 - When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) for traffic control details.
 - Truck mounted attenuator is required.
 - The PCMS may be omitted if replaced with a "RAMP CLOSED" AHEAD (CW20RP-3D) Sign.
 - Roadway ADT should be greater than 10,000.

Texas Department of Transportation
 Traffic Operations Division Standard


WORK IN EXIT GORE FOR ADT GREATER THAN 10,000

TCP (6-8) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: tcp6-8.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CR: TxDOT |
| © TxDOT February 2014 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| | DIST | COUNTY | | SHEET NO. |
| ELP | EL PASO | | | 29 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS




NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm


Texas Department of Transportation
Traffic Safety Division Standard

WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ(STPM)-23

| | | | | |
|-----------------------|------|--------|----------|-----------|
| FILE: wzstpm-23.dgn | DN: | CK: | DW: | CK: |
| © TxDOT February 2023 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 4-92 7-13 | DIST | COUNTY | | SHEET NO. |
| 1-97 2-23 | ELP | ELP | | 30 |
| 3-03 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/13/2023 4:23:46 PM
 FILE: pw://txdot.projectwiseonline.com:txdot15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/2 - TCP/Standards/WZbrk-13.dgn



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

| BACKGROUND COLOR | SIGN DESIGNATION | SIGN | SIGN DIMENSIONS | REFLECTIVE SHEETING | SQ FT | GALVANIZED STRUCTURAL STEEL | | DRILLED SHAFT |
|------------------|------------------|------|-----------------|---|-------|-----------------------------|-------|---------------|
| | | | | | | Size | (LF) | |
| | | | | | | | ① ② | 24" DIA. (LF) |
| Orange | G20-7T | | 96" X 48" | Type B _{FL} or C _{FL} | 32 | ▲ | ▲ ▲ | ▲ |
| Orange | G20-7T | | 192" X 96" | Type B _{FL} or C _{FL} | 128 | W8x18 | 16 17 | 12 |

▲ See Note 6 Below

LEGEND

| | |
|--|--------------|
| | Sign |
| | Large Sign |
| | Traffic Flow |

DEPARTMENTAL MATERIAL SPECIFICATIONS

| | |
|----------------------|----------|
| PLYWOOD SIGN BLANKS | DMS-7100 |
| ALUMINUM SIGN BLANKS | DMS-7110 |
| SIGN FACE MATERIALS | DMS-8300 |

| COLOR | USAGE | SHEETING MATERIAL |
|--------|------------------|--|
| ORANGE | BACKGROUND | TYPE B _{FL} OR TYPE C _{FL} |
| BLACK | LEGEND & BORDERS | NON-REFLECTIVE ACRYLIC FILM |

GENERAL NOTES

- See BC and SMD sheets for additional sign support details.
- Sign locations shall be approved by the Engineer.
- For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
- Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
- Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
- The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
- The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:
 Item 636 - Aluminum Signs
 Item 647 - Large Roadside Sign Supports and Assemblies.
 Item 416 - Drilled Shaft Foundations
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.


| | | | | | |
|--|--------------|------|-------|--------------------------------------|--------------|
| | | | | Traffic Operations Division Standard | |
| WORK ZONE "GIVE US A BRAKE" SIGNS | | | | | |
| WZ (BRK) - 13 | | | | | |
| FILE: | wzbrk-13.dgn | DN: | TxDOT | CK: | TxDOT |
| © TxDOT | August 1995 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | | 2121 | 04 | 124, ETC | IH 10 |
| 6-96 | 5-98 | 7-13 | DIST | | COUNTY |
| 8-96 | 3-03 | ELP | | ELP | SHEET NO. 31 |

DATE: 4/14/2023 10:45:45 AM
 FILE: p:\t\dot\projectwiseonline.com\TxDOT5\Documents\24 - ELP\Design Projects\212104124\4 - Design\Master Design Files\IH10 STRIPING CONTAINER.dgn


| PAVEMENT MARKINGS QUANTITIES (SHEET 1 OF 3)(2121-04-124) | | | | |
|--|------|---|------|-------|
| ITEM | CODE | DESCRIPTION | UNIT | QTY |
| 533 | 6005 | RUMBLE STRIPS(SHOULDER) CONCRETE | LF | 9401 |
| 666 | 6017 | REFL PAV MRK TY I (W) 6" (DOT) (90MIL) | LF | 160 |
| 666 | 6083 | REFL PAV MRK TY I(W)(EXIT GORE)(090MIL) | EA | 1 |
| 666 | 6161 | RE PV MRK TY I(BLACK)6"(SHADOW)(090MIL) | LF | 1395 |
| 666 | 6172 | REFL PAV MRK TY II (W) 6" (DOT) | LF | 160 |
| 666 | 6174 | REFL PAV MRK TY II (W) 6" (SLD) | LF | 5856 |
| 666 | 6194 | REFL PAV MRK TY II (W) (EXIT GORE) | EA | 1 |
| 666 | 6210 | REFL PAV MRK TY II (Y) 6" (SLD) | LF | 5782 |
| 666 | 6219 | REFL PAV MRK TY II (BLACK) 6"(SHADOW) | LF | 1395 |
| 666 | 6305 | RE PM W/RET REQ TY I (W)6"(BRK)(090MIL) | LF | 1395 |
| 666 | 6308 | RE PM W/RET REQ TY I (W)6"(SLD)(090MIL) | LF | 5856 |
| 666 | 6320 | RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL) | LF | 5782 |
| 672 | 6010 | REFL PAV MRKR TY II-C-R | EA | 82 |
| 677 | 6001 | ELIM EXT PAV MRK & MRKS (4") | LF | 11638 |
| 677 | 6014 | ELIM EXT PAV MRK & MRKS (EXIT GORE) | EA | 1 |
| 678 | 6002 | PAV SURF PREP FOR MRK (6") | LF | 14588 |
| 678 | 6018 | PAV SURF PREP FOR MRK (EXIT GORE) | EA | 1 |

LEGEND

- (A) PROPOSED RUMBLE STRIPS
- (B) REFL PAV MARK TY I (W) 6" (DOT)
- (C) REFL PAV MARK TY I (W)(EXIT GORE)
- (D) RE PM W/RET REQ TY I (W)6"(BRK)
- (E) RE PM W/RET REQ TY I (W)6"(SLD)
- (F) RE PM W/RET REQ TY I (Y)6"(SLD)
- (G) REFL PAV MARK TY I (W)24"(SLD)
- (H) REFL PAV MARK TY I (ENTR GORE)
- (I) REF PROF PAV MRK TY I (W)6"(SLD)
- (J) REF PROF PAV MRK TY I (Y)6"(SLD)



Karla Rios, P.E.
 04/14/2023



© 2023
 Texas Department of Transportation

IH 10
 PAVEMENT MARKINGS LAYOUT
 RM 48+0.50 TO
 RM 49+0.35

SHEET 1 OF 3

| | | | |
|------|--------|-----------|---------|
| CONT | SECT | JOB | HIGHWAY |
| 2121 | 04 | 124, ETC | IH 10 |
| DIST | COUNTY | SHEET NO. | |
| ELP | ELP | 32 | |

DATE: 4/14/2023 10:45:57 AM
 FILE: p:\w\projectwiseonline.com\TXDOT5\Documents\24 - ELP\Design Projects\212104124\4 - Design\Master Design Files\I10_STRIPING_CONTAINER.dgn

PAVEMENT MARKINGS QUANTITIES (SHEET 2 OF 3)(CSJ 2121-04-124)

| ITEM | CODE | DESCRIPTION | UNIT | QTY |
|------|------|---|------|------|
| 533 | 6005 | RUMBLE STRIPS(SHOULDER) CONCRETE | LF | 3256 |
| 666 | 6047 | REFL PAV MRK TY I (W)24"(SLD)(090MIL) | LF | 35 |
| 666 | 6080 | REFL PAV MRK TY I(W)(ENTR GORE)(090MIL) | EA | 1 |
| 666 | 6161 | RE PV MRK TY I(BLACK)6"(SHADOW)(090MIL) | LF | 480 |
| 666 | 6174 | REFL PAV MRK TY II (W) 6" (SLD) | LF | 4073 |
| 666 | 6182 | REFL PAV MRK TY II (W) 24" (SLD) | LF | 35 |
| 666 | 6193 | REFL PAV MRK TY II (W) (ENTR GORE) | EA | 1 |
| 666 | 6210 | REFL PAV MRK TY II (Y) 6" (SLD) | LF | 4426 |
| 666 | 6219 | REFL PAV MRK TY II (BLACK) 6" (SHADOW) | LF | 480 |
| 666 | 6305 | RE PM W/RET REQ TY I (W)6"(BRK)(090MIL) | LF | 480 |
| 666 | 6308 | RE PM W/RET REQ TY I (W)6"(SLD)(090MIL) | LF | 4073 |
| 666 | 6320 | RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL) | LF | 4426 |
| 672 | 6010 | REFL PAV MRKR TY II-C-R | EA | 24 |
| 677 | 6001 | ELIM EXT PAV MRK & MRKS (4") | LF | 8499 |
| 677 | 6007 | ELIM EXT PAV MRK & MARKS (24") | LF | 35 |
| 677 | 6013 | ELIM EXT PAV MRK & MRKS (ENTR GORE) | EA | 1 |
| 678 | 6002 | PAV SURF PREP FOR MRK (6") | LF | 9459 |
| 678 | 6008 | PAV SURF PREP FOR MRK (24") | LF | 35 |
| 678 | 6017 | PAV SURF PREP FOR MRK (ENTR GORE) | EA | 1 |


PAVEMENT MARKINGS QUANTITIES (SHEET 2 OF 3)(CSJ 2121-05-054)

| ITEM | CODE | DESCRIPTION | UNIT | QTY |
|------|------|---|------|------|
| 533 | 6005 | RUMBLE STRIPS(SHOULDER) CONCRETE | LF | 1900 |
| 666 | 6047 | REFL PAV MRK TY I (W)24"(SLD)(090MIL) | LF | 35 |
| 666 | 6161 | RE PV MRK TY I(BLACK)6"(SHADOW)(090MIL) | LF | 220 |
| 666 | 6174 | REFL PAV MRK TY II (W) 6" (SLD) | LF | 1410 |
| 666 | 6182 | REFL PAV MRK TY II (W) 24" (SLD) | LF | 35 |
| 666 | 6210 | REFL PAV MRK TY II (Y) 6" (SLD) | LF | 1370 |
| 666 | 6219 | REFL PAV MRK TY II (BLACK) 6" (SHADOW) | LF | 220 |
| 666 | 6305 | RE PM W/RET REQ TY I (W)6"(BRK)(090MIL) | LF | 220 |
| 666 | 6308 | RE PM W/RET REQ TY I (W)6"(SLD)(090MIL) | LF | 1410 |
| 666 | 6320 | RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL) | LF | 1370 |
| 672 | 6010 | REFL PAV MRKR TY II-C-R | EA | 20 |
| 677 | 6001 | ELIM EXT PAV MRK & MRKS (4") | LF | 2780 |
| 677 | 6007 | ELIM EXT PAV MRK & MARKS (24") | LF | 35 |
| 678 | 6002 | PAV SURF PREP FOR MRK (6") | LF | 3220 |
| 678 | 6008 | PAV SURF PREP FOR MRK (24") | LF | 35 |

- LEGEND**
- (A) PROPOSED RUMBLE STRIPS
 - (B) REFL PAV MARK TY I (W) 6" (DOT)
 - (C) REFL PAV MARK TY I (W)(EXIT GORE)
 - (D) RE PM W/RET REQ TY I (W)6"(BRK)
 - (E) RE PM W/RET REQ TY I (W)6"(SLD)
 - (F) RE PM W/RET REQ TY I (Y)6"(SLD)
 - (G) REFL PAV MARK TY I (W)24"(SLD)
 - (H) REFL PAV MARK TY I (ENTR GORE)
 - (I) REF PROF PAV MRK TY I (W)6"(SLD)
 - (J) REF PROF PAV MRK TY I (Y)6"(SLD)

MATCHLINE A

MATCHLINE B



Karla Rios, PE
 04/14/2023



Texas Department of Transportation


IH 10
PAVEMENT MARKINGS
LAYOUT
 RM 48+0.50 TO
 RM 49+0.623

2022 SHEET 2 OF 3

| CONT | SECT | JOB | HIGHWAY |
|-------------|------|----------|-----------|
| 2121 | 04 | 124, ETC | IH 10 |
| DIST COUNTY | | | SHEET NO. |
| ELP ELP | | | 33 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2023/01/25
FILE: DOCUMENT NAME



NOTE

Reflectorized raised pavement markers Type II-C-R shall be spaced on 80' centers with the clear face toward normal traffic and the red face toward wrong way traffic. All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.


TRAFFIC LANE LINES PAVEMENT MARKING



NOTE

Edge lines should typically be 6" wide and the materials shall be as specified in the plans. See details above if reflective profile pavement markings are to be used.


EDGE LINE PAVEMENT MARKINGS




NOTES

1. Reflectorized raised pavement markers Type-II-C-R in the wrong way arrow shall have the clear face toward normal traffic and the red face toward the wrong way traffic.
2. Red reflectorized wrong way arrows, not to exceed two, may be placed on exit ramps. Locations of the arrows shall be as shown in the plans or as directed by the engineer.

WRONG WAY ARROW




TYPICAL ENTRANCE RAMP GORE MARKING



NOTE

See the Roadway Design Manual Chapter 3 to determine if a tapered acceleration lane may be used.

TAPERED ACCELERATION LANE



NOTE

See the Roadway Design Manual Chapter 3 to determine lengths of the acceleration lane and taper.

PARALLEL ACCELERATION LANE


| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.


| LEGEND | |
|--------|--|
| ← | Traffic flow |
| ↩ | Pavement marking arrows (white) |
| □ | Reflectorized Raised Markers (RPM) Type II-C-R |

GENERAL NOTE

On concrete pavements the raised pavement markers shall be placed to one side of the longitudinal joints.



Type II (Top View)



SECTION A


REFLECTORIZED RAISED PAVEMENT MARKER (RPM)

Texas Department of Transportation
Traffic Safety Division Standard

TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS WITH RAISED PAVEMENT MARKERS FPM(1)-22


| | | | | |
|---------------------|------|--------|-----------|---------|
| FILE: fpm(1)-22.dgn | DN: | CK: | DW: | CK: |
| ©TxDOT October 2022 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 5-74 8-00 2-12 | DIST | COUNTY | SHEET NO. | |
| 4-92 2-08 10-22 | ELP | ELP | 35 | |
| 5-00 2-10 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 4/13/2023 4:25:32 PM
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/8 - Traffic/Standards/fpm(2)-22.dgn




SINGLE LANE EXIT WITH AUXILIARY LANE

(See Note 2)




TAPERED DECELERATION LANE

NOTE
 Reference Roadway Design Manual Chapter 3 to determine if tapered deceleration lane may be used.




PARALLEL DECELERATION LANE


NOTE
 Reference Roadway Design Manual Chapter 3 to determine length of deceleration lane and taper.




DETAIL A



DETAIL B



DETAIL C



DETAIL D

GENERAL NOTES

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") dotted lane line (see Detail B) is used to separate a through lane that continues beyond the interchange from an adjacent mandatory exit lane.
4. Normal (6") dotted lane line (see Detail C) is used at parallel acceleration and deceleration lanes.
5. See FPM(1) for traffic lane line pavement marking details.

| LEGEND | |
|--------|--|
| ← | Traffic flow |
| ↩ | Pavement marking arrows (white) |
| □ | Reflectorized Raised Markers (RPM) Type II-C-R |
| ✱ | Arrow markings are optional, however "ONLY" is required if arrow is used |

| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS ENTRANCE AND EXIT RAMP

FPM(2)-22


| | | | | | |
|----------------------|------------------|----------|--------|--------------|-----------|
| FILE: fpm(2)-22.dgn | DN: October 2022 | CK: 2121 | DW: 04 | CK: 124, ETC | CK: IH 10 |
| © TxDOT October 2022 | | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | | DIST | | COUNTY | SHEET NO. |
| 2-77 | 5-00 | 2-12 | ELP | ELP | 36 |
| 4-92 | 8-00 | 10-22 | | | |
| 8-95 | 2-10 | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/13/2023 4:25:53 PM
 FILE: pw://txdot.projectwiseonline.com:txdot15/Documents/24 - ELP/Design Projects/212104124/4 - Design/Plan Set/8 - Traffic/Standards/fpm(5)-22.dgn

EXIT NUMBER PAVEMENT MARKING NOTES

1. Minimum 8 foot white exit number pavement markings should be used, unless otherwise noted.
2. Spacing between letters and numbers should be approximately 4 inches.
3. Pavement markings are to be located as specified elsewhere in the plans.
4. Numbers and Letters details can be found in the Standard Highway Design for Texas (SHSD) Section 12 at <http://www.txdot.gov>



MARKINGS WITH EXIT NUMBER



NOTES


1. Raised pavement markers shall be centered between each chevron or neutral area line.
2. For more information, see ReflectORIZED Raised Pavement Marker Detail.

DETAIL A


| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

| LEGEND | |
|--------|--|
| ← | Traffic flow |
| □ | ReflectORIZED Raised Markers (RPM) Type II-C-R |



Type II (Top View)



SECTION A


REFLECTORIZED RAISED PAVEMENT MARKER (RPM)



EXIT GORE PAVEMENT MARKINGS

FPM(5) - 22




| | | | | |
|---------------------|------|--------|----------|-----------|
| FILE: fpm(5)-22.dgn | DN: | CK: | DW: | CK: |
| ©TxDOT October 2022 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 9-19 | DIST | COUNTY | | SHEET NO. |
| 10-22 | ELP | ELP | | 37 |



MARKINGS WITHOUT EXIT NUMBER

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
 FILE:



- GENERAL NOTES**
1. Contrast and Shadow markings may only be used on concrete pavements.
 2. Contrast and Shadow markings shall not be used on edge lines.
 3. Contrast lane lines shall be permanent prefabricated pavement markings meeting DMS 8240.
 4. Shadow lane line designs shall be a liquid markings system approved by TxDOT.
 5. All raised reflective pavement markers placed in broken lines shall be placed in line with and midway between the white stripes.
 6. See PM(2) for raised reflective pavement markings installation details.

| MATERIAL SPECIFICATIONS | |
|---|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| TRAFFIC PAINT | DMS-8200 |
| HOT APPLIED THERMOPLASTIC | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



CONTRAST AND SHADOW PAVEMENT MARKINGS

CPM(1)-23

| | | | | |
|-----------------------|------|--------|-----------|---------|
| FILE: CPM(1)-23.dgn | DN: | CK: | DW: | CK: |
| © TxDOT February 2023 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 2121 | 04 | 124, ETC | IH 10 |
| 5-14 | DIST | COUNTY | SHEET NO. | |
| 2-23 | ELP | ELP | 38 | |

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):
2121-04-124, ETC.

1.2 PROJECT LIMITS:

From: CSJ:2121-04-124 1.04 MI W OF FM 793
CSJ:2121-05-054 0.47 MI E OF FM 793
To: CSJ: 2121-04-124 0.54 MI W OF FM 793
CSJ: 2121-05-054 FM 3380

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 31.5319670, (Long) -106.1408490
END: (Lat) 31.4653143, (Long) -106.0530404

1.4 TOTAL PROJECT AREA (Acres): 20.36

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0

1.6 NATURE OF CONSTRUCTION ACTIVITY:

PROJECT CONSISTS OF DIAMOND GRINDING: NO SOIL TO BE DISTURBED.

1.7 MAJOR SOIL TYPES:

| Soil Type | Description |
|---|---|
| Bluepoint association, rolling, 5 to 15% slopes | Loamy fine sand to very fine sand, somewhat excessively drained, low rate of runoff |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

| Type | Sheet #s |
|------|----------|
| N/A | |
| | |
| | |
| | |
| | |

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: _____
 Other: _____
 Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

| Tributaries | Classified Waterbody |
|--|--|
| Rio Grande Below Riverside Diversion Dam | Rio Grande Basin (2307); Impaired for bacteria |
| | |
| | |
| | |
| | |
| | |

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: _____
- Other: _____



Karla Rios, P.E.
04/27/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

| | | | |
|-------------------|--------------|-----------|-------------|
| FED. RD. DIV. NO. | PROJECT NO. | | SHEET NO. |
| | C 2121-4-124 | | 39 |
| STATE | STATE DIST. | COUNTY | |
| TEXAS | ELP | EL PASO | |
| CONT. | SECT. | JOB | HIGHWAY NO. |
| 2121 | 04 | 124, ETC. | IH 10 |

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

| Type | Stationing | |
|------|------------|----|
| | From | To |
| N/A | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

| Type | Stationing | |
|------|------------|----|
| | From | To |
| N/A | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



Karla Rios, P.E.
04/27/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

| | | | |
|-------------------|--------------|-----------|-------------|
| FED. RD. DIV. NO. | PROJECT NO. | | SHEET NO. |
| | C 2121-4-124 | | 40 |
| STATE | STATE DIST. | COUNTY | |
| TEXAS | ELP | EL PASO | |
| CONT. | SECT. | JOB | HIGHWAY NO. |
| 2121 | 04 | 124, ETC. | IH 10 |