

**INDEX OF SHEETS**

SEE SHEET NO. 2

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY		SHEET NO.
CRP	NUECES		1

**STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT**

**FEDERAL AID PROJECT NO. F 2B23 (116)  
SH 358 WB FRONTAGE RD  
NUECES COUNTY**

NET LENGTH OF ROADWAY = 20,978.00 FT. = 3.970 MI.  
NET LENGTH OF BRIDGE = 0.00 FT. = 0.000 MI.  
NET LENGTH OF PROJECT = 23,652.00 FT. = 4.480 MI.

LIMITS: FROM: AIRLINE RD  
TO: AYERS ST

DESIGN SPEED = 45 MPH  
A. D. T. (2020) = 23,830  
A. D. T. (2040) = 33,362

PM DESIGN GUIDELINES  
NO RAS REVIEW REQUIRED  
PRINCIPAL ARTERIAL

FINAL PLANS

LETTING DATE: \_\_\_\_\_  
DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_  
DATE WORK WAS COMPLETED & ACCEPTED: \_\_\_\_\_  
FINAL CONTRACT COST: \$ \_\_\_\_\_  
CONTRACTOR : \_\_\_\_\_

FOR THE REHABILITATION OF EXISTING ROADWAY  
CONSISTING OF PLANING, PAVEMENT INLAY, PAVEMENT REPAIRS, AND PAVEMENT MARKINGS



END PROJECT  
CSJ: 0617-01-207  
STA: 574+61  
REF MRK: 562+0.09

BEGIN PROJECT  
CSJ: 0617-01-207  
STA: 338+09  
REF MRK: 566+0.6

EXCEPTIONS: NONE  
EQUATIONS: NONE  
RAILROAD CROSSINGS: NONE



SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

DocuSigned by: Valente Olivaréz 303F64E8A9B44E0... 3/22/2023  
DocuSigned by: Paula Sales-Evans, P.E. 5975450A18CC435... 3/22/2023

DATE: \$DATE\$3/16/2023 11:06 PM  
FILE: \$FILE\$\\txdot\projectwiseonline.com\TXDOT4\Documents\16 - CRP\Design Projects\06170120714 - Design\Plan Set1 - General\TITLE SHEET.dgn

# INDEX OF SHEETS

SHEET NO.	DESCRIPTION
<b>GENERAL</b>	
1	TITLE SHEET
2	INDEX OF SHEETS
3-5	TYPICAL SECTIONS
6, 6A-6D	GENERAL NOTES
7-7A	ESTIMATE & QUANTITY
8	ROADWAY SUMMARY
9	SURFACE DETAILS SUMMARY
10	SW3P SUMMARY
11-13	SMALL SIGNS DETAILS AND SUMMARY

**TRAFFIC CONTROL PLAN**

14	SUGGESTED SEQUENCE OF CONSTRUCTION
----	------------------------------------

**TRAFFIC CONTROL PLAN STANDARDS**

15-26	* BC (1)-21 THRU BC (12)-21
27	* TCP ( 2-6)-18
28	* TCP (3-2)-13
29	* TCP (3-3)-14
30	* TCP (6-1)-12
31	* TCP (6-2)-12
32	* TCP (6-3)-12
33	* TCP (6-4)-12
34	* TCP (6-5)-12
35	* TCP (6-6)-12
36	* TCP (6-7)-12
37	* TCP (6-8)-14
38	* TCP (7-1)-13
39	* TCP (S-1)-08A
40	* TCP (S-2)-08A
41	* TCP (S-3)-08
42	* WZ (BRK)-13
43	* WZ (RCD)-13
44	* WZ (STPM)-13
45	* WZ (UL)-13
46	* WZ (BTS-2)-13

**ROADWAY DETAILS**

47	FLEX PAVEMENT STRUCTURE REPAIR AIRLINE TO STAPLES
48-57	ROADWAY LAYOUT SHEETS
58	MISCELLANEOUS DETAILS

**ROADWAY DETAILS STANDARDS**

59	* OGELITE (M10) (N) -20
60	* REACT (M) -21
61	* SMTC (N) -16
62-63	* SSTR
64	* TRF

**TRAFFIC DETAILS**

65-74	SURFACE DETAILS LAYOUT SHEETS
-------	-------------------------------

**PAVEMENT MARKINGS STANDARDS**

75	* FPM (1)-22
76	* FPM (2)-22
77	* FPM (6)-22
78	* PM (1)-22
79	* PM (2)-22
80	* PM (3)-22
81	* PM (4)-22A

**SIGNING STANDARDS**


82-84	* TSR (3)-13 THRU TSR (5)-13
85	* SMD (GEN)
86-88	* SMD (SLIP 1) THRU SMD (SLIP 3)

**ENVIRONMENTAL ISSUES**

89-90	STORMWATER POLLUTION PREVENTION PLAN (SWP3)
91-92	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

**ENVIRONMENTAL ISSUES STANDARDS**

93-94	* CRP-BECL
95-97	* EC(9) - 16



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A " \* " HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

*E. Martinez*

03/14/2023

NAME

DATE




SH 358 WB FRTG RD

INDEX OF SHEETS


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	2	


DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_



EXISTING SH 358 WESTBOUND FRONTAGE RD TYPICAL SECTION



EXISTING TYPICAL SECTION INTERSECTION



*Eric R. Martinez*

03/22/2023



SH 358 WB FRTG RD


TYPICAL SECTION

SHEET 1 OF 3

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	3	


DATE: 03/10/2023 02:56 PM  
 FILE: \$FILES

CK: DW: CK: DN:




PROPOSED SH 358 WESTBOUND FRONTAGE RD

STA 364+93 TO STA 413+82  
 STA 416+58 TO STA 466+53  
 STA 469+15 TO STA 492+88  
 STA 495+24 TO STA 519+40  
 STA 521+80 TO STA 571+15




PROPOSED SH 358 WESTBOUND FRONTAGE RD RAMP/TURNAROUND

STA 415+62 EVERHART EB TURNAROUND 22'  
 STA 448+87 TO STA 452+96 WEBER ENTR RAMP 11' - 25'



PROPOSED SH 358 WESTBOUND FRONTAGE RD 5" REHAB

STA 390+52 TO STA 409+94  
 STA 425+71 TO STA 462+21



*Eric R. Martinez*

03/14/2023



SH 358 WB FRTG RD


TYPICAL SECTIONS

SHEET 2 OF 3

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH 358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	4	


DATE: PM  
 FILE: \\txdot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\1 - General\SH358\_TYPICAL SECTIONS(1).dgn

CK:  
DW:  
CK:  
DN:




PROPOSED TYPICAL SECTION INTERSECTION

EVERHART RD  
WEBER RD  
CARROLL LN  
KOSTORYZ RD



PROPOSED TYPICAL SECTION - AYERS ST INTERSECTION



*E. Martinez*

03/14/2023

NOTES: CONTRACTOR SHALL MAINTAIN EXISTING BRIDGE CLEARANCE HEIGHT DURING AND AFTER CONSTRUCTION.  
CONTRACTOR SHALL VERIFY/MEASURE THIS IN THE FIELD

**Texas Department of Transportation**

**SH 358 WB FRTG RD**

**TYPICAL SECTIONS**

SHEET 3 OF 3

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST		COUNTY	SHEET NO.
CRP		NUECES	5

◆ - MATCH EXIST CROSS SLOPES

DATE: 01/25/2023 11:55 AM PM  
FILE: pw://txdot-projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/1 - General/SH358\_TYPICAL SECTIONS(2).dgn

County: Nueces

Control: 0617-01-207

Highway: SH 358

**GENERAL NOTES:**

Find, for your information and convenience, tools such as forms, software, materials, and various other information provided by the Department at <https://www.txdot.gov/business.html>. Please note that these tools are updated periodically and your attention is directed to the latest edition.

In the event of a called evacuation, emergencies, impending adverse weather or as directed, do not perform any work without written authorization. The District reserves the right to suspend all work in support of evacuations or emergencies occurring from other parts of the state. Any work performed, other than work directed by the Department, is unauthorized work in accordance with Item 5.

Sweep, clean and remove any construction waste, surplus materials or debris from the roadway and right of way at the end of each day unless otherwise approved. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Asphalt application season will be established in accordance with Item 316.4.4 Adverse Weather Conditions or as directed by the Engineer.

Cut existing pavement using a saw or other approved method to ensure a neat transverse and/or longitudinal line to assure a smooth tie-in with new pavement. Cut to a minimum depth of the final lift thickness. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Promptly pick up and properly dispose of paper and other materials used for pavement joints.

All pavement markings shall be in accordance with the latest edition of Texas MUTCD.

Contractor questions on this project are to be addressed to the following individual(s):

Ernest Longoria, P.E. [Ernest.Longoria@txdot.gov](mailto:Ernest.Longoria@txdot.gov)  
Fidencio Lopez, P.E. [Fidencio.Lopez@txdot.gov](mailto:Fidencio.Lopez@txdot.gov)

Contractor questions will be accepted through email, phone, and in person by the above individuals. Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

County: Nueces

Control: 0617-01-207

Highway: SH 358

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

**ITEM 2**

It is recommended that prospective bidders examine the specified work locations with the Engineer to view the nature of the work, the need for close coordination with the various utilities, traffic control considerations, and other factors influencing the prosecution of the work.

**ITEM 5**

Field verify all dimensions and notify Engineer prior to initiating any work.

Verify the locations of utilities, underground or overhead, shown within the limits of the right-of-way. Adhere to OSHA Standards when working within the vicinity of overhead power lines. Coordinate with the utility companies and notify the Engineer of any possible conflicts. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The 811 call services for a utility location does not include TxDOT facilities. Provide notification to the District Traffic Signal Shop by email at [CRP\\_Utility\\_Locate@txdot.gov](mailto:CRP_Utility_Locate@txdot.gov) or call 361-739-6044 when planning, drilling, or excavating in areas where existing TxDOT underground utilities exist. Visual evidence of TxDOT underground utilities in the area include illumination poles, ground boxes, flashing beacons, traffic signals, etc. This notification must be provided 48 hours in advance of performing the work, but no earlier than 72 business hours before the work will commence. Drilled shaft locations or excavation areas must be staked prior to the notification so that the underground utilities can be located in relationship to the proposed work.


Notify the Engineer immediately of utility conflicts in accordance with Item 5.6. Refer to Item 4.5 for consideration of differing site conditions.

The responsibility for the construction surveying on this contract will be in accordance with Item 5.9.3, "Method C".

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

**ITEM 6**

Inspection at Precast Concrete Fabrication Plants is as follows: TxDOT's Materials and Pavements Section will inspect any precast units at commercial fabrication yards and staging areas. The Area Engineer will inspect all other precast units.

 © 2023 <b>GENERAL NOTES</b>	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
	6			SH 358
	STATE	DISTRICT	COUNTY	
	TEXAS	CRP	NUECES	
	CONTROL	SECTION	JOB	
	0617	01	207	
				SHEET NO.
				6

County: Nueces

Control: 0617-01-207

Highway: SH 358

For Department-furnished material, contact the Engineer or his designated representative to request material a minimum of one workday prior to pick up. Load material with contract personnel. Materials are to be stored in a safe location outside TXDOT property or right-of-way, {unless otherwise approved.} Use material furnished by the Department only on the project(s) intended. Return any unused material as soon as possible.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. <https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

**ITEM 7**

The work performed for Item 7.2.4, "Public Safety and Convenience" will not be measured or paid for directly, but will be subsidiary to pertinent Items.

When working at street, farm-to-market, state highway, and county road intersections, schedule work to minimize intersection closures. During nonworking hours, all public road intersections will be open to the traveling public.

The total disturbed area for this project is less than 1 acres. The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer.

Comply with the Texas Aggregate Quarry and Pit Safety Act for waste areas or material source areas resulting from this project.

No significant traffic generator events identified.

Submit charge summary and invoices for Law Enforcement Personnel using the Department forms.

General Notes

Sheet C

County: Nueces

Control: 0617-01-207

Highway: SH 358

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles. No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site.

A maximum combined rate of \$70 per hour for the law enforcement personnel and the patrol vehicle will be allowed. Any scheduling fee is subsidiary per Standard Specification 502.4.2.

Cancel law enforcement personnel when the event is canceled. Cancellation, minimums or "show up" fees will not be paid when cancellation is made 12 hours prior to beginning of the event. Failure to cancel within 12 hours will not be cause for payment for cancellation, minimums, or "show up" time. Payment of actual "show up" time to the event site due to cancellation will be on a case by case basis at a maximum of 2 hours per officer.

Alterations to the cancellation and maximum rate must be approved by the Engineer or pre-determined by official policy of the officers governing authority.

**ITEM 8**

Prepare the progress schedule using the Critical Path Method (CPM). Submit (2) two 11" x 17" hard copies and an electronic file of the original or updated progress schedule. Submit the original progress schedule seven (7) days before the Preconstruction Conference.

Asphalt application season will be considered to be May 1 to Sept 30, except as established in Item 316.4.4 Adverse Weather Conditions or as directed by the Engineer.

Submit an updated progress schedule as directed to show proposed major changes, changes affecting compliance with the contract requirements, or changes affecting the critical path/controlling item of work.

Working days will be computed and charge in accordance with Article 8.3.1.4, "Standard Workweek".

Lane closures are not permitted Monday through Friday between 6 AM and 9 PM unless approved.


Any lane closed or obstructed beyond the period permitted will be assessed a lane rental charge. The following lane rental charges will apply:

Weekdays/Weekends = \$5,340/hr/lane

Nighttime work will be required.

General Notes

Sheet D

 © 2023 <b>GENERAL NOTES</b>	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
	6			SH 358
	STATE	DISTRICT	COUNTY	SHEET NO.
	TEXAS	CRP	NUECES	
CONTROL	SECTION	JOB		
0617	01	207	6A	

County: Nueces

Control: 0617-01-207

Highway: SH 358

Notify the Engineer at least 48 hours in advance of weekend work.

**ITEM 9**

Monthly progress payments will be made for items of work completed by the 28th day of each month. Any work completed after the 28th will be included for payment in the subsequent monthly progress estimate.

Submit signed request for compensation of material-on-hand (MOH), including any requests from subcontractors, suppliers, or fabricators for MOH, at least two (2) working days prior to the end of the pay cycle on the Department's approved forms.

**ITEM 134**

Backfill pavement edges with reclaimable asphalt material (R.A.P.).

Use backfill material with a plasticity index (PI) ranging from 10 to 40. Notify the Engineer of the proposed material sources and of changes to material sources. The Engineer may sample and test project materials at any time before compaction throughout the duration of the project to assure specification compliance.

If Contractor elects to use R.A.P. material for backfill pavement edges, the R.A.P. material must pass a 2" sieve. All material not passing sieve will be removed and disposed of properly. This shall be considered subsidiary to Item 134.

Windrow the existing topsoil and grass along the edge of the grading operations or as directed. After grading operations are completed, spread the topsoil and grass uniformly on all slopes and ditch lines. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Manipulate and compact backfill material in accordance with Item 132.3.4.1, "Ordinary Compaction". The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Apply SS-1 at a rate of application of 0.15 gallon per square yard. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

**ITEM 302**

Provide aggregates with a minimum surface aggregate classification (SAC) of "B" unless otherwise shown. The SAC for sources on the Department's Aggregate Quality Monitoring Program (AQMP) is listed in the Department's Bituminous Rated Source Quality Catalogue (BRSQC). SAC requirements apply to aggregates used on all final roadway surfaces, including shoulders.

General Notes

Sheet E

County: Nueces

Control: 0617-01-207

Highway: SH 358

For precoated aggregate Type PB crushed gravel will not be used.

**ITEM 316**

Do not place surface treatment on exposed concrete structures unless directed.

Furnish a distributor equipped with a working hand hose.

Material rates shown are for estimating purposes only. Adjust actual rates based on the material used, the existing condition and type of roadway surface, and as approved.

When using asphalt emulsion, a minimum 24-hour curing period is required before placing any subsequent asphalt courses.

Remove vegetation and blade pavement edges prior to surfacing operations. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Broom and clean sealed sections of roadway and all adjacent paved surfaces, including the gutter line, of any surplus aggregate before opening to traffic or as directed.

A vacuum sweeper will be required for this project. This shall be considered subsidiary to Item 316. Vacuum sweeper must perform a test strip before use.

**ITEM 351**

Use of motor grader will not be permitted unless approved.

Saw cut and remove the full depth of pavement repair at all transverse joints.

**ITEM 354**

Reclaimable asphalt material (RAP) may be retained only if incorporated into the project. Incorporate the RAP into the pavement mix design, into the backfill for pavement edges, into temporary structures, or as approved.


Any RAP remaining from the contract is to remain with the Contractor.

**ITEM 500**

"Materials on Hand" payments are not considered when determining partial payments.

General Notes

Sheet F

 © 2023 <b>GENERAL NOTES</b>	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
	6			SH 358
	STATE	DISTRICT	COUNTY	
	TEXAS	CRP	NUECES	
CONTROL	SECTION	JOB		SHEET NO.
0617	01	207		6B



County: Nueces

Control: 0617-01-207

Highway: SH 358

**ITEM 502**

Furnish additional barricades, signs, and traffic handling as directed. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

When advanced warning flashing arrow panels are specified, furnish one (1) standby unit in good condition at the job site for immediate use.

Attach stop/slow paddle to a staff with a minimum length of 6 feet to the bottom of the sign.

The use of a pilot vehicle in conjunction with flaggers will be permitted. If used, provide positive and unrestricted communication between the driver of the pilot vehicle and the flaggers. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

All items marked as optional on all traffic control standards shall be required unless otherwise approved by an Engineer.

Trail vehicle shall be required on all mobile traffic control operations.

**ITEM 504**

No field office will be required for this project.

Asphalt content will be measured by Ignition Method.

**ITEM 506**

Designate in writing a Contractor Responsible Person (CRP) for implementing, maintaining, and reviewing environmental requirements.

**ITEM 585**

Use Surface Test Type B and Pay Adjustment Schedule 2 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

General Notes

Sheet G

County: Nueces

Control: 0617-01-207

Highway: SH 358

**ITEM 662**

Use temporary flexible-reflective roadway marker tabs at the beginning and end of no passing zones as shown on the TCP (7-1)-13 for seal coats and WZ(STPM)-13 for hot mix overlays.

**ITEM 666**

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

Place pavement markings no later than 14 calendar days after the placement of the surface. When inclement weather prohibits placement of the markings, the 14-day period may be extended until weather permits proper application.

**ITEM 3076**

SAC requirements apply to aggregates used on all surfaces.

Construct longitudinal joints with a joint marker providing a maximum one (1) inch vertical edge (1/2 inch desirable) with an adjacent 6:1 taper. Backfill edges within the same day.

The Engineer reserves the right to test all sources even if the source is listed in the Bituminous Source Rated Quality Catalog.

Provide the testing lab samples to calibrate the ignition oven no later than five (5) working days prior to mix the design verification.

Place HMA utilizing an automatic, dual, longitudinal-grade control system and automatic transverse-grade control system as specified under Item 320, unless otherwise approved by the Engineer.

Contractor shall temporarily cover all inlets during the milling and paving operations. Inlets shall be uncovered when milling and paving operations are complete. This shall be subsidiary to Item 3076 and not paid for directly.

**ITEM 3082**


Use asphalt with a PG binder of 76-22

Lime shall be used as an antistripping agent at a rate of 1% in accordance with Item 301, "Asphalt Antistripping Agents."

Provide aggregates with a minimum surface aggregate classification (SAC) of "A" unless otherwise shown. SAC requirements apply to aggregates used on all final roadway surfaces, including shoulders.

General Notes

Sheet H

 © 2023 <b>GENERAL NOTES</b>	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
	6			SH 358
	STATE	DISTRICT	COUNTY	
	TEXAS	CRP	NUECES	
	CONTROL	SECTION	JOB	
	0617	01	207	
				SHEET NO. 6C

County: Nueces

Control: 0617-01-207

Highway: SH 358

Class B virgin (non-recycled) aggregate will not be allowed.

The use of Reclaimed Asphalt Pavement (RAP) or Recycled Asphalt Shingles (RAS) will not be allowed on surface mixtures.

The contractor will not be compensated for excess thin bonded wearing course material placed and removed from irregular areas due to contractor placement methods.

**ITEM 6001**

Furnish the portable changeable message signs displaying the correct message at least seven (7) days prior to beginning work or as directed.

The Contractor's Responsible Person (CRP) will maintain full control of messages at all times.

The Engineer will provide the sign message text to use at each sign.

A minimum of 2 PCMS will be required. However, additional units may be necessary depending on the work in progress.

Standby time will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Portable changeable message signs may be moved and message changed at any time as deemed necessary by the Engineer. This will be considered subsidiary to Item 6001.

**ITEM 6185**

A minimum of 2 TMAS will be required. However, additional units may be necessary depending on the work in progress

Provide manufacturer's curb weight or certified scales weight ticket to the Engineer for approval.

TMA's paid by the each shall be available for the duration of the project. Relocation of TMA's will be as directed by the Engineer, and will be considered subsidiary to this Item.

General Notes

Sheet I

County: Nueces

Control: 0617-01-207

Highway: SH 358

**SPECIFICATION DATA**

**UNIT WEIGHT ESTIMATES**


ITEM 3082 – 3/4" TBWC PG76-22 SAC-A TY-C ----- 100 (LBS/SY)  
ITEM 3076 – 2.5" D-GR HMA (TY-B) SAC-B PG 70-22 ----- 275 (LBS/SY)  
ITEM 3076 – 5" D-GR HMA (TY-B) SAC-B PG 70-22 ----- 550 (LBS/SY)

**UNDERSEAL**

ASPHALT TYPE ----- ASPH (AC-10, CRS-2, OR HFRS-2)  
ASPHALT RATE ----- 0.39 (GAL/SY)  
AGGREGATE TYPE ----- PB  
AGGREGATE GRADE ----- 4/4S SAB-B  
AGGREGATE RATE ----- 1/110 (CY/SY)

General Notes

Sheet J

 © 2023 <b>GENERAL NOTES</b>	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
	6		SH 358
	STATE	DISTRICT	COUNTY
	TEXAS	CRP	NUECES
	CONTROL	SECTION	JOB
	0617	01	207
			SHEET NO.
			60



CONTROLLING PROJECT ID 0617-01-207

DISTRICT Corpus Christi  
HIGHWAY SH 358

# Estimate & Quantity Sheet

COUNTY Nueces

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	104-6010	REMOVING CONC (RIPRAP)	CY	42.000	
	104-6011	REMOVING CONC (MEDIANS)	SY	156.000	
	316-6001	ASPH (MULTI OPTION)	GAL	39,028.000	
	316-6427	AGGR(TY-PB GR-4S OR TY-PB GR-4)(SAC-B)	CY	919.000	
	351-6027	FLEX PAVEMENT STRUCTURE REPAIR (2.5")	SY	7,857.000	
	354-6088	PLANE ASPH CONC PAV (0" TO 5")	SY	100,053.000	
	420-6066	CL C CONC (RAIL FOUNDATION)	CY	64.000	
	450-6023	RAIL (TY SSTR)	LF	400.000	
	500-6001	MOBILIZATION	LS	1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	1,149.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,149.000	
	512-6001	PORT CTB (FUR & INST)(SGL SLOPE)(TY 1)	LF	400.000	
	512-6049	PORT CTB (REMOVE)(SGL SLP)(TY 1)	LF	400.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	400.000	
	544-6003	GUARDRAIL END TREATMENT (REMOVE)	EA	3.000	
	545-6005	CRASH CUSH ATTEN (REMOVE)	EA	3.000	
	545-6007	CRASH CUSH ATTEN (INSTL)(L)(N)(TL3)	EA	3.000	
	545-6019	CRASH CUSH ATTEN (INSTL)(S)(N)(TL3)	EA	3.000	
	636-6001	ALUMINUM SIGNS (TY A)	SF	41.250	
	644-6027	IN SM RD SN SUP&AM TYS80(1)SA(P)	EA	3.000	
	644-6033	IN SM RD SN SUP&AM TYS80(1)SA(U)	EA	6.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	6,702.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	469.000	
	666-6005	REFL PAV MRK TY I (W)4"(DOT)(090MIL)	LF	339.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	9,144.000	
	666-6038	REFL PAV MRK TY I (W)12"(LNDP)(090MIL)	LF	739.000	
	666-6041	REFL PAV MRK TY I (W)12"(SLD)(090MIL)	LF	2,118.000	
	666-6168	REFL PAV MRK TY II (W) 4" (DOT)	LF	339.000	
	666-6171	REFL PAV MRK TY II (W) 6" (BRK)	LF	6,551.000	
	666-6174	REFL PAV MRK TY II (W) 6" (SLD)	LF	1,580.000	
	666-6178	REFL PAV MRK TY II (W) 8" (SLD)	LF	9,144.000	
	666-6179	REFL PAV MRK TY II (W) 12" (LNDP)	LF	739.000	
	666-6180	REFL PAV MRK TY II (W) 12" (SLD)	LF	2,118.000	
	666-6210	REFL PAV MRK TY II (Y) 6" (SLD)	LF	4,647.000	
	666-6305	RE PM W/RET REQ TY I (W)6"(BRK)(090MIL)	LF	6,551.000	
	666-6308	RE PM W/RET REQ TY I (W)6"(SLD)(090MIL)	LF	1,580.000	
	666-6320	RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL)	LF	4,647.000	
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	3,809.000	
	668-6077	PREFAB PAV MRK TY C (W) (ARROW)	EA	47.000	
	668-6078	PREFAB PAV MRK TY C (W) (DBL ARROW)	EA	29.000	

DISTRICT	COUNTY	CCSJ	SHEET
Corpus Christi	Nueces	0617-01-207	7



CONTROLLING PROJECT ID 0617-01-207

DISTRICT Corpus Christi  
HIGHWAY SH 358

COUNTY Nueces

# Estimate & Quantity Sheet

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	668-6080	PREFAB PAV MRK TY C (W) (UTURN ARROW)	EA	10.000	
	668-6085	PREFAB PAV MRK TY C (W) (WORD)	EA	55.000	
	668-6092	PREFAB PAV MRK TY C (W) (36")(YLD TRI)	EA	20.000	
	672-6007	REFL PAV MRKR TY I-C	EA	125.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	112.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA	860.000	
	764-6001	DRAIN INLET CLEANING	EA	80.000	
	3076-6006	D-GR HMA TY-B PG70-22	TON	15,197.000	
	3082-6004	TBWC (MEMBRANE)	GAL	20,017.000	
	3082-6005	TBWC PG76-22 SAC-A TY C	TON	5,011.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	118.000	
	6185-6002	TMA (STATIONARY)	DAY	59.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	
		LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	

DW:   
 CK:   
 CK:   
 DW:   
 CK:

DATE: 2/23/2023 4:31:43 PM   
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/1 - General/ROADWAY\_SUMMARY.dgn

SH 358 WB FR ROADWAY SUMMARY													
LOCATION			AREA		104	104	316	316	351	354	3076	3082	3082
					6010	6011	6001	6427	6027	6088	6006	6004	6005
			REMOVING CONC (RIPRAP)	REMOVING CONC (MEDIANS)	ASPH (MULTI OPTION)	AGGR (TY-PB GR-4S OR TY-PB GR-4) (SAC-B)	FLEX PAVEMENT STRUCTURE REPAIR (2.5")	PLANE ASPH CONC PAV (0" TO 5")	D-GR HMA TY B SAC-B PG 70-22	TBWC (MEMBRANE)	TBWC PG76-22 SAC-A TY C		
WESTBOUND FRONTAGE RD			SY	CY	SY	GAL	CY	SY	SY	TON	GAL	TON	
SHEET	BEGIN STA	END STA											
1	364+83	381+00	6383			2490	59		6383	878	1277	320	
2	381+00	405+00	9724			3793	89		9724	1603	1945	487	
3	405+00	429+00	8472			3305	78		8472	1484	1695	424	
4	429+00	453+00	9623			3753	88		9623	1882	1925	482	
5	453+00	477+00	8984			3504	82		8984	1484	1797	450	
6	477+00	501+00	7262			2833	67		7262	999	1453	364	
7	501+00	525+00	9255			3610	85		9255	1273	1851	463	
8	525+00	549+00	8350	12		3257	76		8350	1149	1670	418	
9	549+00	573+00	8147	30		3178	75		8147	1121	1630	408	
10	573+00	574+61											
INTERSECTION													
EVERHART RD			4826		40	1883	44		4826	706	966	242	
WEBER RD			4746		41	1851	44		4746	653	950	238	
CARROLL LN			3754		39	1465	35		3754	517	751	188	
KOSTORYZ RD			3656		36	1426	34		3656	503	732	183	
AYERS ST			6871			2680	63		6871	945	1375	344	
								7857					
CSJ 0617-01-207 TOTAL:				<b>42</b>	<b>156</b>	<b>39028</b>	<b>919</b>	<b>7857</b>	<b>100053</b>	<b>15197</b>	<b>20017</b>	<b>5011</b>	

SH 358 WB MAIN LANE SUMMARY													
LOCATION			AREA		420	450	512	512	542	544	545	545	545
					6066	6023	6001	6049	6001	6003	6005	6007	6019
			CL C CONC (RAIL FOUNDATION)	RAIL (TY SSTR)	PORT CTB (FUR & INST) (SGL SLOPE) (TY 1)	PORT CTB (REMOVE) (SGL SLP) (TY 1)	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL END TREATMENT (REMOVE)	CRASH CUSH ATTEN (REMOVE)	CRASH CUSH ATTEN (INSTL) (L) (N) (TL3)	CRASH CUSH ATTEN (INST) (L) (N) (TL3)		
			SY	CY	LF	LF	LF	LF	EA	EA	EA	EA	
BEGIN STA	BEGIN STA												
539+58	540+58	9255	16	100	100	100	100	1	1	1	1		
549+67	550+67	8350	16	100	100	100	100	1	1	1	1		
557+15	559+15	8147	32	200	200	200	200	1	1	1	1		
CSJ 0617-01-207 TOTAL:			<b>64</b>	<b>400</b>	<b>400</b>	<b>400</b>	<b>400</b>	<b>3</b>	<b>3</b>	<b>3</b>	<b>3</b>		

**SH 358 WB FRTG RD**  
  
**ROADWAY SUMMARY**

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY		SHEET NO.
CRP	NUECES		8

CK: DW: CK: DN:

DATE: 01/09/2023 02:50 PM PM  
 FILE: p:\t\dot\project\seonline.com\TXDOT14\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\1 - General\SURFACE DETAIL\_SUMMARY.dgn

SH 358 WB FRTG RD SURFACE DETAILS QUANTITY SUMMARY																
LOCATION				662	662	666	666	666	666	666	666	666	666	666	666	666
				6109	6111	6005	6035	6038	6041	6168	6171	6174	6178	6179	6180	6210
SHEET	BEGIN STA	END STA	LENGTH FT	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	REFL PAV MRK TY I (W) 4" (DOT) (090 MIL)	REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)	REFL PAV MRK TY I (W) 12" (LNDP) (090 MIL)	REFL PAV MRK TY I (W) 12" (SLD) (090 MIL)	REFL PAV MRK TY II (W) 4" (DOT)	REFL PAV MRK TY II (W) 6" (BRK)	REFL PAV MRK TY II (W) 6" (SLD)	REFL PAV MRK TY II (W) 8" (SLD)	REFL PAV MRK TY II (W) 12" (LNDP)	REFL PAV MRK TY II (W) 12" (SLD)	REFL PAV MRK TY II (Y) 6" (SLD)
				EA	EA	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF
1	364+94	381+00	1606	314	82		363		113		402		363		113	816
2	381+00	405+00	2400	1258	65		372	309	518		600	233	372	309	518	645
3	405+00	429+00	2400	625	26		1168				652	250	1168			257
4	429+00	453+00	2400	1378	43		352	355	570		600	226	352	355	570	425
5	453+00	477+00	2400	695	27		1500		237		659	170	1500		237	262
6	477+00	501+00	2400	476	5		399				659	48	399			48
7	501+00	525+00	2400	695			1375		170		699	210	1375		170	
8	525+00	549+00	2400	469			544				600	220	544			
9	549+00	573+00	2400	509			653		275		631	2	653		275	
10	573+00	574+61	161	10							16					
INTERSECTION																
EVERHART RD				51	55	62	345			62	106		345			550
WEBER RD				55	65	62	372			62	118		372			644
CARROLL LN				46	45	44	390			44	43	221	390			444
KOSTORYZ RD				43	34	59	302			59	80		302			340
AYERS ST				78	22	112	538			112	156		538			216
338+09 357+00 1891							471	75	235		530		471	75	235	
<b>CSJ 0617-01-207 TOTAL:</b>				<b>6702</b>	<b>469</b>	<b>339</b>	<b>9144</b>	<b>739</b>	<b>2118</b>	<b>339</b>	<b>6551</b>	<b>1580</b>	<b>9144</b>	<b>739</b>	<b>2118</b>	<b>4647</b>

SH 358 WB FRTG RD SURFACE DETAILS QUANTITY SUMMARY																
LOCATION				666	666	666	668	668	668	668	668	668	672	672	672	
				6305	6308	6320	6076	6077	6078	6080	6085	6092	6007	6009	6010	
SHEET	BEGIN STA	END STA	LENGTH FT	RE PM W/ RET REQ TY I (W) 6" (BRK) (090 MIL)	RE PM W/ RET REQ TY I (W) 6" (SLD) (090 MIL)	RE PM W/ RET REQ TY I (Y) 6" (SLD) (090 MIL)	PREFAB PAV MRK TY C (W) (24") (SLD)	PREFAB PAV MRK TY C (W) (ARROW)	PREFAB PAV MRK TY C (W) (DBL ARROW)	PREFAB PAV MRK TY C (W) (UTURN ARROW)	PREFAB PAV MRK TY C (W) (WORD)	(36") (YLD TRI)	TY I-C	TY II-A-A	TY II-C-R	
				LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA
1	364+94	381+00	1606	402		816									50	
2	381+00	405+00	2400	600	233	645									127	
3	405+00	429+00	2400	652	250	257		6	2	2	8				91	
4	429+00	453+00	2400	600	226	425									135	
5	453+00	477+00	2400	659	170	262		4	4	2	6				132	
6	477+00	501+00	2400	659	48	48		4	2	2	6				53	
7	501+00	525+00	2400	699	210			6	2	2	8				121	
8	525+00	549+00	2400	600	220										58	
9	549+00	573+00	2400	631	2			2	4	2	4				92	
10	573+00	574+61	161	16											1	
INTERSECTION																
EVERHART RD				106		550	798	4	2		4	5	23	28		
WEBER RD				118		644	883	4	2		4	10	25	33		
CARROLL LN				43	221	444	610	3	4		3	22	23			
KOSTORYZ RD				80		340	708	4	2		4	5	20	17		
AYERS ST				156		216	810	10	5		8		35	11		
338+09 357+00 1891							530									
<b>CSJ 0617-01-207 TOTAL:</b>				<b>6551</b>	<b>1580</b>	<b>4647</b>	<b>3809</b>	<b>47</b>	<b>29</b>	<b>10</b>	<b>55</b>	<b>20</b>	<b>125</b>	<b>112</b>	<b>860</b>	

 Texas Department of Transportation

**SH 358 WB FRTG RD**


**SURFACE  
DETAILS  
SUMMARY**

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	9	

SH 358 WB FR RD SW3P QUANTITY SUMMARY							
STATION	FEATURE	STRUCTURE	DATE INSTALLED	DATE REMOVED	506	506	764
					6041	6043	6001
					BIODEG EROSN CONT LOGS (INSL) (12")	BIODEG EROSN CONT LOGS (REMOV)	DRAIN INLET CLEANING
					LF	LF	EA
368+50 RT	FR	CURB INLET			9	9	1
372+00 LT	MEDIAN	CURB INLET			9	9	1
374+52 LT	MEDIAN	SWALE			9	9	1
375+00 LT	MEDIAN	DROP INLET			30	30	1
375+00 RT	FR	CURB INLET			9	9	1
381+25 RT	FR	CURB INLET			9	9	1
383+85 RT	FR	CURB INLET			15	15	1
393+00 RT	FR	CURB INLET			13	13	1
396+00 RT	FR	CURB INLET			13	13	1
400+50 LT	FR	CURB INLET			15	15	1
403+00 LT	FR	CURB INLET			15	15	1
403+00 RT	FR	CURB INLET			13	13	1
409+75 LT	MEDIAN	DROP INLET			20	20	1
409+75 RT	FR	CURB INLET			13	13	1
414+60	INTERSECTION	CURB INLET			9	9	1
414+60	INTERSECTION	CURB INLET			9	9	1
415+27	INTERSECTION	CURB INLET			9	9	1
415+27	INTERSECTION	CURB INLET			9	9	1
421+80 LT	MEDIAN	DROP INLET			20	20	1
427+50 LT	FR	CURB INLET			15	15	1
433+15 LT	MEDIAN	DROP INLET			60	60	1
433+15 RT	FR	CURB INLET			9	9	1
440+25 LT	MEDIAN	DROP INLET			20	20	1
440+25 RT	FR	CURB INLET			9	9	1
441+50 RT	FR	CURB INLET			13	13	1
448+85 LT	MEDIAN	DROP INLET			20	20	1
448+85 RT	FR	CURB INLET			9	9	1
449+50 RT	FR	CURB INLET			9	9	1
454+50 RT	FR	CURB INLET			13	13	1
462+13 LT	MEDIAN	DROP INLET			24	24	1
463+15 RT	FR	CURB INLET			13	13	1
467+34	INTERSECTION	CURB INLET			9	9	1
467+34	INTERSECTION	CURB INLET			9	9	1
468+00	INTERSECTION	CURB INLET			9	9	1
468+00	INTERSECTION	CURB INLET			9	9	1
471+00 LT	MEDIAN	DROP INLET			20	20	1
471+00 RT	FR	CURB INLET			13	13	1
476+50 LT	FR	CURB INLET			9	9	1
477+35 RT	FR	CURB INLET			9	9	1
478+00 RT	FR	CURB INLET			9	9	1
487+23 RT	FR	CURB INLET			15	15	1
480+40 RT	FR	CURB INLET			13	13	1
487+80 LT	FR	CURB INLET			13	13	1
487+80 RT	MEDIAN	DROP INLET			30	30	1
490+45 RT	FR	CURB INLET			13	13	1
490+80 LT	MEDIAN	DROP INLET			20	20	1
493+76	INTERSECTION	CURB INLET			9	9	1
493+76	INTERSECTION	CURB INLET			9	9	1
494+44	INTERSECTION	CURB INLET			9	9	1
494+44	INTERSECTION	CURB INLET			9	9	1
498+05 LT	MEDIAN	DROP INLET			20	20	1
498+05 RT	FR	CURB INLET			9	9	1
500+95 RT	FR	CURB INLET			13	13	1
501+00 LT	MEDIAN	DROP INLET			20	20	1
504+60	MEDIAN	DROP INLET			30	30	1
512+25 LT	FR	CURB INLET			9	9	1
513+50 RT	FR	CURB INLET			9	9	1
520+18	INTERSECTION	CURB INLET			9	9	1

SH 358 WB FR RD SW3P QUANTITY SUMMARY							
STATION	FEATURE	STRUCTURE	DATE INSTALLE	DATE REMOVED	506	506	
					6041	6043	
					BIODEG EROSN CONT LOGS (INSL) (12")	BIODEG EROSN CONT LOGS (REMOV)	DRAIN INLET CLEANING
					LF	LF	EA
520+18	INTERSECTION	CURB INLET			9	9	1
520+87	INTERSECTION	CURB INLET			9	9	1
520+87	INTERSECTION	CURB INLET			9	9	1
523+05 LT	MEDIAN	DROP INLET			20	20	1
526+80 RT'	DRIVEWAY	GRATE INLET			25	25	1
534+05 LT	MEDIAN	DROP INLET			20	20	1
534+05 RT'	DRIVEWAY	GRATE INLET			30	30	1
542+05 LT	MEDIAN	DROP INLET			20	20	1
542+05 RT	FR	CURB INLET			13	13	1
548+80 LT	MEDIAN	DROP INLET			20	20	1
548+80 RT	FR	CURB INLET			13	13	1
557+05 LT	MEDIAN	DROP INLET			20	20	1
557+05 RT	FR	CURB INLET			13	13	1
565+00 RT	FR	CURB INLET			13	13	1
567+75 LT	MEDIAN	DROP INLET			20	20	1
567+75 RT	FR	CURB INLET			9	9	1
569+50 LT	MEDIAN	DROP INLET			20	20	1
570+70 RT	FR	CURB INLET			13	13	1
572+96	INTERSECTION	CURB INLET			9	9	1
572+96	INTERSECTION	CURB INLET			9	9	1
573+75	INTERSECTION	CURB INLET			9	9	1
573+75	INTERSECTION	CURB INLET			9	9	1
				<b>TOTAL</b>	1149	1149	80




**SH 358 WB FRTG RD**

**SW3P  
SUMMARY**

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY		SHEET NO.
CRP	NUECES		10

SH 358 WB SMALL SIGN SUMMARY		
LOCATION	644	644
	6027	6033
	IN SM RD SN SUP&AM TYS80 (1) SA (P)	IN SM RD SN SUP&AM TYS80 (1) SA (U)
	EA	EA
D3-2		6
M2-1	2	
M4-3	1	
<b>CSJ 0617-01-207 TOTAL:</b>	<b>3</b>	<b>6</b>



**SH 358 WB FRTG RD**

**SMALL SIGNS  
DETAILS AND SUMMARY**





SHEET 1 OF 3


CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	11	



DATE: 01/17/2023 09:50 AM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/1 - General/SMALL\_SIGN\_SUMMARY


## SUMMARY OF SMALL SIGNS

PLAN SHEET NO.	SIGN NO.	SIGN DESIGNATION	SIGN CONTENT	SIGN DIMENSIONS (See above Note)	ALUMINUM TYPE A	ALUMINUM TYPE G
46	S2	R3-8LMS		48 x 30	X	
46	S3	R3-8SPL		60 x 30	X	
48	S1	R10-12		30 x 36	X	
48	S2	R3-8LMS		48 x 30	X	




R3-8LMS\*48x30;  
 1.875" Radius, 0.750" Border, 0.500" Indent, Black on White;  
 L ir=4.25, s=2.5; "ONLY", D 50% spacing;  
 M ir=13.25, s=2.5; S h=19.125, s=2.5;  
 "ONLY", D 50% spacing;

NOTE:  
 1. SIGNS TO BE MOUNTED ON HIGH MAST ARMS



1.875" Radius, 0.750" Border, 0.500" Indent, LaneMarker height: 12.000 LaneMarker width: 0.750 Black on White;  
 EL ir=5.813, s=2.5; "ONLY", D 50% spacing;  
 1.875" Radius, 0.750" Border, 0.500" Indent, LaneMarker height: 12.000 LaneMarker width: 0.750 Black on White;  
 "ONLY", D 50% spacing;  
 1.875" Radius, 0.750" Border, 0.500" Indent, LaneMarker height: 12.000 LaneMarker width: 0.750 Black on White;  
 C h=19.125, s=2.5; "ONLY", D 50% spacing;  
 1.875" Radius, 0.750" Border, 0.500" Indent, Black on White;  
 BR ir=13.25, s=2.5;



*Eric R. Martinez*

03/14/2023



SH 358 WB FRTG RD


SMALL SIGNS  
 DETAILS AND SUMMARY

SHEET 2 OF 3


CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	12	

DATE: 01/17/2023 10:41 AM  
 FILE: pw://twdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/1 - General/SMALL\_SIGN\_SUMMARY2.DGN


SUMMARY OF SMALL SIGNS						SMA RD SGN ASSM TY XXXXX (X) XX (X-XXXX)						
PLAN SHEET NO.	SIGN NO.	SIGN DESIGNATION	SIGN CONTENT	SIGN DIMENSIONS (See above Note)	ALUMINUM TYPE A	ALUMINUM TYPE G	Post Type		Anchor Type		Mounting Designation	
							FRP = Fiberglass TWT = Thin-wall 10BWG = 10 BWG S80 = Sched 80	Posts (1 or 2)	UA = Univer-Conc UB = Univer-Bolt SA = Slip-Conc SB = Slip-Bolt WS = Wedge Steel WP = Wedge Pistic	P = Prefab. "Plain" T = Prefab. "T" U = Prefab. "U"	1EXT or 2EXT = # of Ext. BM = Extruded Beam WC = 1.12 #/ft Wing Chan. EXAL = Extruded Alum. Signs	
345+00	S4	M2-1	JCT <AUXILIARY SIGN>	21 x 15	X		S80	1	SA	P		
		M1-6F	2444	24 x 24	X							
348+50	S5	D3-2	STAPLES ST NEXT SIGNAL	48 x 30	X		S80	1	SA	U		
		S6	EVERHART RD NEXT SIGNAL	54 x 30	X		S80	1	SA	U		
49	S7	M2-1	JCT <AUXILIARY SIGN>	21 x 15	X		S80	1	SA	P		
		M1-6F	2444	24 x 24	X							
50	S8	D3-2	WEBER RD NEXT SIGNAL	48 x 30	X		S80	1	SA	U		
51	S9	D3-2	CARROL LN NEXT SIGNAL	54 x 30	X		S80	1	SA	U		
52	S10	D3-2	KOSTORYZ RD NEXT SIGNAL	54 x 30	X		S80	1	SA	U		
54	S11	M4-3	BUSINESS <AUXILIARY SIGN>	24 x 12	X		S80	1	SA	P		
		M1-6TB	286	24 x 24	X							
		M6-1	LEFT ARROW	21 x 15	X							
54	S12	D3-2	AYERS ST NEXT SIGNAL	48 x 30	X		S80	1	SA	U		




D3-2(1)\_VARx30;  
 1.875" Radius, 0.750" Border, White on Green;  
 "Staples St", ClearviewHwy-3-W 75% spacing;  
 "NEXT SIGNAL", ClearviewHwy-3-W 78% spacing;




D3-2(1)\_VARx30;  
 1.875" Radius, 0.750" Border, White on Green;  
 "Everhart Rd", ClearviewHwy-3-W 75% spacing;  
 "NEXT SIGNAL", ClearviewHwy-3-W 75% spacing;




D3-2(1)\_VARx30;  
 1.875" Radius, 0.750" Border, White on Green;  
 "Weber Rd", ClearviewHwy-3-W 75% spacing;  
 "NEXT SIGNAL", ClearviewHwy-3-W 75% spacing;




D3-2(1)\_VARx30;  
 1.875" Radius, 0.750" Border, White on Green;  
 "Carroll Ln", ClearviewHwy-3-W; "NEXT SIGNAL", ClearviewHwy-3-W;



D3-2(1)\_VARx30;  
 1.875" Radius, 0.750" Border, White on Green;  
 "Kostoryz Rd", ClearviewHwy-3-W 75% spacing;  
 "NEXT SIGNAL", ClearviewHwy-3-W 75% spacing;



D3-2(1)\_VARx30;  
 1.875" Radius, 0.750" Border, White on Green;  
 "Ayers St", ClearviewHwy-3-W 75% spacing;  
 "NEXT SIGNAL", ClearviewHwy-3-W 75% spacing;



*Eric R. Martinez*

03/14/2023

**SH 358 WB FRTG RD**  
 SMALL SIGNS  
 DETAILS AND SUMMARY

SHEET 3 OF 3

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST		COUNTY	SHEET NO.
CRP		NUECES	13

CK: DW: CK: DN:

DATE: 2/23/2023 4:33:20 PM  
 FILE: p:\w\l\ob\p\project\wse\al\iee\com\TX\0074\0\Documents\166-CRRP\Design\Projects\0104\700\200744-Design\Plan\866\86602-TCP\FSE\01\HUE\06\FCONS\55\88\0074\00\0104.dgn

GENERAL NOTES FOR THE CONSTRUCTION SEQUENCE

1. ALL BEGINNING AND ENDING BARRICADES AND SIGNS ARE TO REMAIN IN PLACE FOR THE DURATION OF THE PROJECT.
2. ALL SIGNS, BARRICADES AND PAVEMENT MARKINGS SHALL CONFORM WITH THE BC STANDARD SHEETS, TCP SHEETS, AND THE LATEST EDITION OF THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".
3. CW20-1D, G20-2A & EITHER G20-1bL or G20-1bR SIGNS WILL BE REQUIRED AT ALL PUBLIC ROADS, AND INTERSECTIONS WITHIN LIMITS. (G20-2A) SIGNS MAY BE MOUNTED ON BACK OF CW20-1D, SEE BC(2)-14.
4. THE CONTRACTOR SHALL PROVIDE FOR SAFE AND CONVENIENT INGRESS AND EGRESS TO ABUTTING PROPERTY HIGHWAY, PUBLIC ROAD, AND STREET CROSSING FOR ALL VEHICLES. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN ALL CROSSINGS IN A SAFE AND PASSABLE CONDITION.
5. REFER TO THE BARRICADE AND CONSTRUCTION STANDARD SHEETS FOR REQUIRED SPACING OF SIGNS AND BARRICADES.
6. THE CONTRACTOR MAY BE REQUIRED TO FURNISH ADDITIONAL BARRICADES, SIGNS, AND WARNING LIGHTS TO MAINTAIN TRAFFIC AND PROMOTE MOTORISTS SAFETY. ANY SUCH ADDITIONAL SIGNS AND BARRICADES SHALL BE CONSIDERED SUBSIDIARY TO ITEM 502.
7. ALL SIGNS SHALL BE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
8. ALL TRAFFIC BARRELS & EDGE LINE CHANNELIZERS SHALL BE USED IN ACCORDANCE WITH THE PLANS AND MANUFACTURER'S RECOMMENDATIONS AND SHALL HAVE A 7" PRISMATIC REFLECTOR UNIT, AS APPROVED BY THE ENGINEER. ALL MATERIALS SHALL BE CONSIDERED SUBSIDIARY TO ITEM 502.
9. SIGNS, PAVEMENT MARKINGS, CHANNELIZING DEVICES, AND OTHER TRAFFIC CONTROL DEVICES THAT ARE INCONSISTENT WITH INTENDED TRAVEL PATHS THROUGH THE PROJECT AREA SHALL BE REMOVED IMMEDIATELY.
10. ALL TRAFFIC CONTROL DEVICES SHALL BE REMOVED WHEN NO LONGER NEEDED. WHEN WORK IS SUSPENDED FOR SHORT TIME PERIOD, ADVANCED WARNING SIGNS THAT ARE NO LONGER APPROPRIATE SHALL BE REMOVED FROM THE PROJECT AREA.
11. THE CONTRACTOR WILL BE RESPONSIBLE FOR MARKING THE LOCATION OF ALL TRAFFIC CONTROL STRIPING AND PERMANENT STRIPING AS DIRECTED BY THE ENGINEER.
12. SHORT TERM FLEXIBLE REFLECTIVE ROADWAY TABS SHALL BE USED TO DELINEATE THE CENTERLINE AND TURNING LANES FOR A MAXIMUM OF 14 DAYS. PERMANENT STRIPING SHALL THEN BE PLACED. PERMANENT STRIPING SHALL BE DONE IN ACCORDANCE WILL ALL APPLICABLE STANDARDS. THE CONTRACTOR SHOULD BE AWARE, DEPENDING ON THE SEQUENCE OF CONSTRUCTION, THE STRIPING CREW MAY HAVE SEVERAL MOVE-INS. ALL SHORT TERM FLEXIBLE REFLECTIVE ROADWAY TABS SHALL BE REPLACED AS NEEDED WITHIN THAT 14 DAY PERIOD AT THE CONTRACTOR'S EXPENSE.
13. THE CONTRACTOR MAY SUBMIT AN ALTERNATE TRAFFIC CONTROL PLAN AND/OR AN ALTERNATE SEQUENCE OF CONSTRUCTION, IN ADVANCE AND IN WRITING, SUBJECT TO THE APPROVAL OF THE ENGINEER. REFER TO ITEM 502.2 - CONSTRUCTION.

UNEVEN LANES


1. ANY VERTICAL OR NEAR VERTICAL LONGITUDINAL FACE EXCEEDING 2 INCHES IN HEIGHT IN THE PAVEMENT SURFACE OPEN TO TRAFFIC AT THE END OF THE WORK DAY SHALL BE SLOPED A MINIMUM OF 3:1. TRANSVERSE FACES THAT ARE PRESENT AT THE END OF THE WORK DAY SHALL BE TAPERED IN A MANNER ACCEPTABLE TO THE ENGINEER.
2. SIGNING FOR UNEVEN LANES (CW8-11) SHALL BE INSTALLED IN ADVANCE TO THE CONDITION AND REPEATED EVERY 1 MILE. SIGNS INSTALLED ALONG THE UNEVEN LANE CONDITION SHOULD BE SUPPLEMENTED WITH THE "NEXT XX MILES" MILES SIGN (CW21-16) OR ADVISORY SPEED SIGN (SCW13-1). SEE WZ(UL)-03 FOR ADDITIONAL DETAILS.
3. UNEVEN LANE SIGNS (CW8-11) SHALL BE ERECTED ON BOTH ENDS ON THE AREA WHERE THERE IS A DIFFERENCE IN ELEVATION BETWEEN ADJACENT LANES GREATER THAN ONE INCH

PAVEMENT DROP-OFF

1. MAXIMUM ELEVATION DROP-OFF ON PAVEMENT EDGE SHALL NOT EXCEED 1 INCH WHEN TRAFFIC IS ALLOWED ADJACENT TO THE DROP-OFF. THE SLOPE MUST BE COMPACTED MATERIAL CAPABLE OF SUPPORTING VEHICLES. THIS WORK WILL NOT BE PAID FOR DIRECTLY BUT SHALL BE CONSIDERED SUBSIDIARY TO THE VARIOUS BID ITEMS.
2. SIGNING FOR PAVEMENT DROP-OFF (CW8-9a) SHOULD BE INSTALLED IN ADVANCE OF THE CONDITION AND REPEATED EVERY 1 MILE. SIGNS INSTALLED ALONG THE PAVEMENT EDGE SHOULD BE SUPPLEMENTED WITH THE NEXT XX MILES SIGN (CW21-16) OR ADVISORY SPEED SIGN (SCW13-1).

SUGGESTED SEQUENCE OF CONSTRUCTION

1. PLACE THE FOLLOWING ADVANCE WARNING SIGNS IN ACCORDANCE WITH BC(2)-14; R20-3T, G20-10T, G20-9TP, R20-5T, R20-5aTP, CW 20-1D, G20-5T, G20-6T, G20-2bT, G20-2, G20-5ap, G20-1bTR, AND G20-1bTL.
2. PLACE EROSION CONTROL DEVICES AS SHOWN ON SW3P SUMMARY AND IN ACCORDANCE WITH ALL APPLICABLE STANDARD SHEETS.
3. ALL WORK TO BE COMPLETED AT NIGHT BETWEEN 9 PM AND 6 AM. CONTRACTOR WILL PLAN DAILY WORK LIMITS THAT ALLOW FOR THE COMPLETION OF MILL, SEAL, AND INLAY OPERATIONS UP TO THE PLACEMENT OF THE TY-B HOTMIX LAYER AT THE END OF EACH NIGHT.
  - A. PLANE EXISTING PAVEMENT TO THE DEPTH DESIGNATED IN THE PLANS FOR THE SECTION OF THE ROADWAY TO BE COMPLETED EACH NIGHT.
  - B. PLACE UNDERSEAL AND TY-B HMA IN THE PLANNED SECTION.
  - C. PLACE WORK ZONE PAVEMENT MARKINGS.
4. REPEAT STEPS 1A-1C FOR EACH LANE OF THE ROADWAY AND THE PROPOSED INTERSECTION WORK.
  - A. CONCRETE BARRIER WORK ON WESTBOUND MAIN LANES AND SMALL SIGN INSTALLATION CAN BE COMPLETED CONCURRENTLY WITH PAVING WORK
5. ONCE ALL MILL AND INLAY WORK IS COMPLETE, BEGIN TBWC OVERLAY THROUGHOUT PROJECT LIMITS. PLACE WORK ZONE TABS PRIOR TO OPENING SECTION TO TRAFFIC.
6. PLACE FINAL PAVEMENT MARKINGS.
7. CLEAN UP PROJECT LIMITS AND REMOVE SW3P ITEMS.



*E. R. Martinez*

03/14/2023



**SUGGESTED SEQUENCE OF CONSTRUCTION**

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	14	

DATE: 2/23/2023 4:33:37 PM  
 FILE: //txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/06102074 - Design/Plan Set/13 - Standards/BC(1)-21.dgn  
 No. warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for the accuracy of the information contained herein.

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

<b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b> <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS) "
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION  
GENERAL NOTES  
AND REQUIREMENTS**

**BC (1) -21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
4-03	7-13	0617	01	207	SH 358				
9-07	8-14	DIST	COUNTY		SHEET NO.				
5-10	5-21	CRP	NUECES		15				


DATE: 2/23/2023 4:33:40 PM  
 FILE: D:\txdot\project\wisonline.com\TXDOT4\Documents\16 - CRP\Design Projects\0617020720\BC(2)-21.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of any data.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - Contractor will install a regulatory speed limit sign at the end of the work zone.

**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**


**BC(2)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	CRP	NUECES	16	



DATE: 2/23/2023 4:33:46 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\0617012074 - Design\Plan Set\13\_Standards\TCP\_Standards\BC (11)-21 THRU BC (12)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for its use, of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

**Nails shall NOT be allowed.**  
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflective when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTC list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTC) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short, duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTC lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTC list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12




**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**


FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0617	01	207	SH 358				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	CRP	NUECES	18					

DATE: 2/23/2023 4:33:48 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\061702074 - Design\Plan Set\13 - Standards\BC (5)-21.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results. Standards/BC (5)-21.dgn




**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS




**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**GENERAL NOTES**

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

\* See BC(4) for definition of "Work Duration."  
 \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.  
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12

Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC (5) - 21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	CRP	NUECES	19	



WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results obtained from its use. (1) 21 THRU BC (12) -21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

### Other Condition List

FRONTAGE ROAD CLOSED
SHOULDER CLOSED XXX FT
RIGHT LN CLOSED XXX FT
RIGHT X LANES OPEN
DAYTIME LANE CLOSURES
I-XX SOUTH EXIT CLOSED
EXIT XXX CLOSED X MILE
RIGHT LN TO BE CLOSED
X LANES CLOSED TUE - FRI

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) -21


FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		0617	01	207	SH 358				
9-07	8-14	DIST:	COUNTY:	SHEET NO.:					
7-13	5-21	CRP:	NUECES	20					

DATE: 2/23/2023 4:33:51 PM

FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/06170207/4 - Design/Plan Set/13 - Standards/PCMS Standards/BC (12) -21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 2/23/2023 4:33:54 PM  
 FILE: D:\t\dot\project\wiseonline.com\CRP\Design Projects\061701207\4 - Design\Plan Set\13\_Standards\TCP\_Standards\BC (1)-21 THRU BC (12)-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**  
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation  
 Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0617	01	207	SH 358				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	CRP	NUECES	21					

DATE: 2/23/2023 4:33:59 PM  
 FILE: D:\txdot\project\wiseonline.com\TXDOT4\Documents\16 - CRP\Design Projects\0617012074 - Design\Plan Set\13\_Standards\TCP\_Standards\BC (11)-21\_THRU BC (12)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
 (Maximum Sign Dimension)  
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
 mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0617	01	207	SH 358				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	CRP	NUECES	22					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 2/23/2023 4:34:01 PM  
 FILE: pw://tcdot.projectwiseonline.com: TXDOT4/ Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13\_ Standards/BC (11)-21 THRU BC (12)-21.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**PORTABLE**

**VERTICAL PANELS (VPs)**




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\*\*Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	SH	358			
REVISIONS		0617	01	207					
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	CRP	NUECES	23					

DATE: 2/23/2023 4:34:04 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\0617012074 - Design\Plan Set\13 - Standards\TCP\_Standards\BC (11)-21 THRU BC (12)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) -21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	CRP	NUECES	24	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	CRP	NUECES	25	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/23/2023 4:34:08 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/0617012074 - Design/Plan Set/13 - Standards/TCP\_Standards/BC(11)-21\_THRU BC(12)-21.dgn

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS


BC (12) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	CRP	NUECES	26	
11-02 8-14				


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DATE: 2/23/2023 4:34:11 PM  
 FILE: D:\txdot\projectwiseonline.com\TXDOT4\Documents\16 - CRP\Design Projects\0617012074 - Design\Plan Set\13 - Standards\TCP\_Standards\BC (12)-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/23/2023 4:34:27 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\061701\061701.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions that may appear hereon.



TCP (2-6a)  
**ONE LANE CLOSURE**



TCP (2-6b)  
**LANE CLOSURE NEAR EXIT RAMP**



TCP (2-6c)  
**LANE CLOSURE NEAR ENTRANCE RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
  - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
  - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
  - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation  
 Traffic Operations Division Standard

## TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS

### TCP (2-6) - 18









FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	CRP	NUECES		27
1-97 2-18				

166





DATE: 2/23/2023 4:34:59 PM  
 FILE: D:\projects\project\wisonline.com\TXDOT4\Documents\16 - CRP\Design\Project\16-010000\16-010000.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

**GENERAL NOTES**


- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation  
Traffic Operations Division Standard


## TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	CRP	NUECES		
1-97 7-14				

DATE: 2/23/2023 4:35:13 PM  
 FILE: D:\projects\projectwiseonline.com\TXDOT4\Documents\16 - CRP\Design\Project\16-12.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any units or the use of any equipment or materials for any purpose whatsoever.



TCP (6-1a)  
**TYPICAL FREEWAY ONE LANE CLOSURE**



TCP (6-1b)  
**TYPICAL FREEWAY TWO LANE CLOSURE**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

\* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.



**TRAFFIC CONTROL PLAN  
 FREEWAY LANE CLOSURES**

**TCP (6-1) - 12**


FILE:	tcp6-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
8-12	REVISIONS	0617	01	207	SH 358				
	DIST	COUNTY	SHEET NO.						
	CRP	NUECES	30						






DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard for any purpose other than that intended by the original author.

DATE: 2/23/2023 4:36:00 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\CP6-4\Documents\16 - CRP\Design Projects\CP6-4\Documents\16 - CRP\Design Projects\CP6-4.dgn



TCP (6-4a)  
**EXIT RAMP CLOSED**  
**TRAFFIC EXITS PAST CLOSED RAMP**



TCP (6-4b)  
**EXIT RAMP OPEN**

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC Standards for sign details.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.



**TRAFFIC CONTROL PLAN**  
**WORK AREA AT EXIT RAMP**

**TCP (6-4) - 12**

FILE: tcp6-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	CRP	NUECES	33	















DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/23/2023 4:37:33 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/TCP (S-1)-08A.dgn



TCP (S-1a)  
 WORK OFF SHOULDER  
 OR PAVED SURFACE



TCP (S-1b)  
 WORK ON SHOULDER

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision  
 Corrected misspelling.

LEGEND

	Type III Barricade		Channelizing Devices		Flag
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)		
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)		
	Flagger		Sign Post		

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Device		Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60' - 75'	120'	90'
35		205'	225'	245'	35'	70' - 90'	160'	120'
40		265'	295'	320'	40'	80' - 100'	240'	155'
45		450'	495'	540'	45'	90' - 110'	320'	195'
50		500'	550'	600'	50'	100' - 125'	400'	240'
55		550'	605'	660'	55'	110' - 140'	500'	295'
60		600'	660'	720'	60'	120' - 150'	600'	350'
65	650'	715'	780'	65'	130' - 165'	700'	410'	
70	700'	770'	840'	70'	140' - 175'	800'	475'	
75	750'	825'	900'	75'	150' - 185'	900'	540'	

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:  
 SHORT DURATION - work that occupies a location up to 1 hour.  
 SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

- GENERAL NOTES:
- The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
  - Channelizing devices on the shoulder taper and tangent section may be omitted for short duration (less than 1 hour) work.
  - If line-of-sight requirements for surveying operations will preclude the placement of the Work Vehicle to protect workers, the channelizing devices mentioned in Note 2 are required.
  - A Shadow Vehicle with a Truck Mounted Attenuator and flashing warning lights/arrow panel in caution mode may be used in lieu of the Work Vehicle to protect the work space.
  - The CW20-1D "ROAD WORK AHEAD" sign may be substituted for the CW21-6D "SURVEY CREW AHEAD" sign.
  - This plan may also be used for shoulder work or off shoulder work for multilane undivided roadways.
  - The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

TCP (S-1a)  
 8. Cones may be placed at edge of pavement adjacent to the work space to enhance safety.

Texas Department of Transportation  
 Traffic Operations Division


**TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS**

TCP (S-1) - 08A


© TxDOT August 2008		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
8-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0617	01	207	SH 358
		DIST	COUNTY		SHEET NO.
		CRP	NUECES		39

DATE: 2/23/2023 4:37:48 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13\_ Standards/Plan Set/13\_ Standards/TCP (S-2)-08A.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (S-2a)  
 ROAD CLOSED FOR LESS THAN 20 MINUTES -  
 OFF PEAK TRAFFIC HOURS  
 WITH OR WITHOUT SHOULDERS



TCP (S-2b)  
 WORK IN ROADWAY  
 OFF PEAK TRAFFIC HOURS  
 WITH OR WITHOUT SHOULDERS

Posted Speed (mph)	Distance (ft)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820
80	910

LEGEND

- Type III Barricade
- Channelizing Devices
- Flag
- Heavy Work Vehicle
- Truck Mounted Attenuator (TMA)
- Trailer Mounted Flashing Arrow Panel
- Portable Changeable Message Sign (PCMS)
- Flagger
- Sign Post

Posted Speed $\times$	Formula	Minimum Desirable Taper Lengths $\times$			Suggested Maximum Spacing of Device		Min. Sign Spacing "x" Distance	Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60' - 75'	120'	90'
35		205'	225'	245'	35'	70' - 90'	160'	120'
40	L = WS	265'	295'	320'	40'	80' - 100'	240'	155'
45		450'	495'	540'	45'	90' - 110'	320'	195'
50	L = WS	500'	550'	600'	50'	100' - 125'	400'	240'
55		550'	605'	660'	55'	110' - 140'	500'	295'
60	L = WS	600'	660'	720'	60'	120' - 150'	600'	350'
65		650'	715'	780'	65'	130' - 165'	700'	410'
70	L = WS	700'	770'	840'	70'	140' - 175'	800'	475'
75		750'	825'	900'	75'	150' - 185'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

TYPICAL USAGE:				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

DEFINITIONS:  
 SHORT DURATION - work that occupies a location up to 1 hour.  
 SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

- GENERAL NOTES:
- The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
  - Adequate Stopping Sight Distance (see Stopping Sight Distance table) should be maintained from approaching traffic to the flagger or a queue of stopped vehicles. The Buffer Space "B" should be extended around curves or other obstacles, when necessary, to have adequate Stopping Sight Distance to the flagger station.
  - Flaggers should use two-way radios or other means of communication while flagging.
  - The length of the work space should be based on the ability of the flaggers to communicate.
  - CW20-1D "ROAD WORK AHEAD" signs may be substituted for CW21-6D "SURVEY CREW AHEAD" signs.
  - The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

- TCP (S-2a)
- Road closures shall be less than 20 minutes. Closures less than 5 minutes are desirable.
  - Sign spacing should be increased if traffic repeatedly queues past the CW20-7b "BE PREPARED TO STOP" sign.
  - The surveying instrument should not be located on the paved surface.
- TCP (S-2b)
- For short duration work the Shadow Vehicle with a TMA may be replaced by another Work Vehicle with high intensity rotating, flashing or strobe lights.
  - Shadow Vehicles with a TMA are desirable when workers or equipment are in the work space. When approved by the engineer, Type III barricades or other channelizing devices may be substituted for the Shadow Vehicle.
  - The CW20-7b "BE PREPARED TO STOP" sign is optional. When used, it should be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign.

WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECESSARY PERIODS OF TIME ON THE ROAD SURFACE.

8-18-08 Revision  
 Corrected reference to notes.

Texas Department of Transportation  
 Traffic Operations Division



## TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS

### TCP (S-2) -08A

© TxDOT August 2008	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
8-08	REVISONS	CONT	SECT	JOB
		0617	01	207
		DIST	COUNTY	SHEET NO.
		CRP	NUECES	40

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/23/2023 4:38:02 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/TCP (S-3)-08.dgn



WHENEVER POSSIBLE, SURVEY PARTIES SHOULD AVOID, BY THE USE OF OFFSET LINES, ANY UNNECESSARY PERIODS OF TIME ON THE ROAD SURFACE.

**LEGEND**

	Type III Barricade		Channelizing Devices		Flag
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)		
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)		
	Flagger		Sign Post		

Posted Speed * S	Formula	Minimum Desirable Taper Lengths ** L			Suggested Maximum Spacing of Device On a Tangent		Min. Sign Spacing "X" Distance	Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Tangent	On a Curve		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60' - 75'	120'	90'
35		205'	225'	245'	35'	70' - 90'	160'	120'
40		265'	295'	320'	40'	80' - 100'	240'	155'
45		450'	495'	540'	45'	90' - 110'	320'	195'
50		500'	550'	600'	50'	100' - 125'	400'	240'
55		550'	605'	660'	55'	110' - 140'	500'	295'
60		600'	660'	720'	60'	120' - 150'	600'	350'
65	650'	715'	780'	65'	130' - 165'	700'	410'	
70	700'	770'	840'	70'	140' - 175'	800'	475'	
75	750'	825'	900'	75'	150' - 185'	900'	540'	

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)

**TYPICAL USAGE:**

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

**DEFINITIONS:**  
 SHORT DURATION - work that occupies a location up to 1 hour.  
 SHORT TERM STATIONARY - daytime work that occupies a location for more than 1 hour within a single daylight period.

- GENERAL NOTES:**
- The G20-2a "END ROAD WORK" sign may be placed on the back of the CW21-6D "SURVEY CREW AHEAD" sign or may be omitted for short duration (less than 1 hour) work.
  - For short duration work the Shadow Vehicle with TMA may be replaced by another Work Vehicle with high intensity rotating, flashing or strobe lights.
  - Shadow Vehicles with a TMA are desirable when workers or equipment are in the work space. When approved by the engineer, Type III barricades or other channelizing devices may be substituted for the Shadow Vehicle.
  - CW20-1D "ROAD WORK AHEAD" signs may be substituted for CW21-6D "SURVEY CREW AHEAD" signs.
  - The CW21-6D "SURVEY CREW AHEAD" sign for low volume intersecting side roads is desirable, but is not required when working less than 15 minutes in area of the side road, as determined by the Engineer.

**TCP (S-3a)**  
 6. If shoulders are not present, the 1/3L shoulder taper is to be omitted and four channelizing devices shall be placed in front of the arrow panel, perpendicular to traffic.

**TCP (S-3b)**  
 7. One CW20-5L "LEFT LANE CLOSED" sign in each direction may be omitted when the posted speed is less than 45mph and volume is less than 2000 ADT.

**Texas Department of Transportation**  
 Traffic Operations Division

**TRAFFIC CONTROL PLAN FOR SURVEYING OPERATIONS**


**TCP (S-3) -08**

© TxDOT August 2008		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
REVISIONS		CONT	SECT	JOB	HIGHWAY
		0617	01	207	SH 358
		DIST	COUNTY	SHEET NO.	
		CRP	NUECES	41	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project. For more information, please contact the Texas Department of Transportation, 12000 North Loop West, P.O. Box 21087, Houston, Texas 77210-0877, or call 1-800-392-0050.

DATE: 2/23/2023 4:38:33 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\160727\160727.dgn



**ROAD CLOSURE BEYOND THE INTERSECTION**  
 Signing for a Numbered Route with an Off-Site Detour



**ROAD CLOSURE AT THE INTERSECTION**  
 Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "x" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

\* Conventional Roads Only

**GENERAL NOTES**

1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.


		Traffic Operations Division Standard	
<b>WORK ZONE ROAD CLOSURE DETAILS</b>			
<b>WZ (RCD) - 13</b>			
FILE: wzrcd-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT August 1995	CONT	SECT	JOB
REVISIONS	0617	01	207
1-97 4-98 7-13	DIST	COUNTY	SHEET NO.
2-98 3-03	CRP	NUECES	43



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein.

DATE: 2/23/2023 4:38:48 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\061701\061701\_013.dwg

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible-reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:  
[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)



## WORK ZONE SHORT TERM PAVEMENT MARKINGS


### WZ (STPM) - 13

FILE:	wzstpm-13.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	April 1992	CONT:	0617	SECT:	01	JOB:	207	SH:	358
REVISIONS		DIST:		COUNTY:		SHEET NO.:			
1-97		CRP:		NUECES					44
3-03									
7-13									



No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect use of this standard.

DATE: 09/20/2022 09:59 AM  
 FILE: DOCUMENT NAME



- NOTES**
1. Project signing as shown shall be in place whenever signal contract work is in progress.
  2. For closely adjoining projects, advance signing may not be required in advance of each intersection, but only in advance of the intersections at the project limits. Actual locations will be as directed by the Engineer.
  3. Advance signs shall be removed when signal construction operations are no longer under way, as directed by the Engineer.
  4. Warning sign spacing shown is typical for both directions.
  5. See the Table on sheet 1 of 2 for Typical warning sign spacing.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Signs shall be installed and maintained in a straight and plumb condition.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. Nails shall NOT be used to attach signs to any support.
5. All signs shall be installed in accordance with the plans or as directed by the Engineer.
6. The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).
7. The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.
8. Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as directed by the Engineer.
9. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".
10. Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

**DURATION OF WORK**

1. Work zone durations are defined in Part 6, Section 60.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

**SIGN MOUNTING HEIGHT**

1. Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.
2. Sign height of Short-term/Short Duration warning signs shall be as shown on Figure 6F-2 of the TMUTCD.
3. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.
2. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs.
3. Duct tape or other adhesive material shall NOT be affixed to a sign face.
4. Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

**SIGN SUPPORT WEIGHTS**

1. Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber, such as tire inner tubes, shall not be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**LEGEND**




	Sign
	Channelizing Devices
	Type 3 Barricade

**DEPARTMENTAL MATERIAL SPECIFICATIONS**

SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
WHITE	BACKGROUND	TYPE A SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:  
[http://www.txdot.gov/txdot\\_library/publications/construction.htm](http://www.txdot.gov/txdot_library/publications/construction.htm)



**PEDESTRIAN CONTROL**

1. Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.
2. "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation.
3. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic substrates, they may be mounted on top of a plastic drum at or near the location shown.
4. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9) and manufacturer's recommendations.
5. Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.
6. Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.
7. The width of existing sidewalk should be maintained if practical.
8. Pavement markings for mid-block crosswalks shall be paid for under the appropriate bid items.
9. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.

SHEET 2 OF 2

Traffic Operations Division Standard



TRAFFIC SIGNAL WORK  
 BARRICADES AND SIGNS



WZ (BTS-2) - 13

FILE: wzbts-13.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	061701		207	SH358
2-98 10-99 7-13	DIST	COUNTY		SHEET NO.
4-98 3-03	CRP	NUECES		46

CK:  
DW:  
CK:  
DN:

DATE: 2/27/2023 04:18:00 PM  
FILE: p:\C\CL\BENTON\BENTON\online.com\TXDOT4\Documents\16 - CRP\Design Projects\0617012074 - Design\Plan\_Set\3 - Roadway\SH358 - PVMT RPR AIRLINE TO STAPLES.dgn

**LEGEND**  
 DIRECTION OF TRAFFIC  
 PAVEMENT REPAIR 2.5"



*Eric R. Martinez*

03/14/2023



SH 358 WB FRTG RD





FLEX PAVEMENT  
STRUCTURE REPAIR  
AIRLINE TO STAPLES

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	47	

CK: DW: CK: DN:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ⊕ ROADWAY SECTION
  - ➔ DIRECTION OF TRAFFIC



*E. Martinez, P.E.*

03/14/2023

Texas Department of Transportation

SH 358 WB FRTG RD

ROADWAY LAYOUTS




SHEET 1 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	48	

DATE: 01/13/2023 10:20 AM TM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/3 - Roadway/SH358\_ROADWAY\_LAYOUTS1.dgn


CK:  
DW:  
CK:  
DN:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ⊙ ROADWAY SECTION
  - ➔ DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023



SH 358 WB FRTG RD



ROADWAY LAYOUTS

SHEET 2 OF 10


CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	49	

DATE: 01/10/2023 04:34 PM  
FILE: p:\txdot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\3 - Roadway\SH358\_ROADWAY\_LAYOUTS2.dgn

CK:  
DW:  
CK:  
DN:



- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ① ROADWAY SECTION
  - EXISTING MAST ARM AND POLE
  - DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023

Texas Department of Transportation

SH 358 WB FRTG RD

ROADWAY LAYOUTS




SHEET 3 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	50	

DATE: 01/10/2023 04:33 PM  
FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/3 - Roadway/SH358 - ROADWAY LAYOUTS3.dgn

CK:  
DW:  
CK:  
DN:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ③ ROADWAY SECTION
  - ➔ DIRECTION OF TRAFFIC



*E. Martinez, P.E.*

03/14/2023

Texas Department of Transportation

**SH 358 WB FRTG RD**  
**ROADWAY LAYOUTS**

SHEET 4 OF 10




CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	51	

DATE: 01/10/2023 04:32 PM  
FILE: p:\txdot\project\isonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan\_Set\3 - Roadway\SH358\_ROADWAY\_LAYOUTS4.dgn



CK: DW: CK: DN:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ⊙ ROADWAY SECTION
  - EXIST MAST ARM AND POLE
  - DIRECTION OF TRAFFIC



*Eric R. Martinez*

03/14/2023

Texas Department of Transportation

SH 358 WB FRTG RD

ROADWAY LAYOUTS

SHEET 5 OF 10




CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	52	

DATE: 01/10/2023 04:31 PM  
 FILE: p:\txdot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\3 - Roadway\SH358 - ROADWAY LAYOUTS5.dgn



CK: DW: CK: DN:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ⊠ PAVEMENT REPAIR
  - ⊙ ROADWAY SECTION
  - ➔ DIRECTION OF TRAFFIC



*Eric R. Martinez*

03/14/2023

Texas Department of Transportation

SH 358 WB FRTG RD

ROADWAY LAYOUTS

SHEET 7 OF 10





CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	54	

DATE: 01/10/2023 04:29 PM  
FILE: p:\txdot\project\online.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\3 - Roadway\SH358 - ROADWAY LAYOUTS7.dgn

DATE: 01/10/2023 04:28 PM  
 FILE: \\txdot-project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\3 - Roadway\SH358\_Roadway\_LAYOUTS8.dgn

DN:  
 CK:  
 DW:  
 CK:  
 CK:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ⊠ PAVEMENT REPAIR
  - ⊕ ROADWAY SECTION
  - ➔ DIRECTION OF TRAFFIC



*Eric R. Martinez*  
 E.R.M., P.E.

03/14/2023






**SH 358 WB FRTG RD**  
 ROADWAY LAYOUTS

SHEET 8 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	55	

CK:  
DW:  
CK:  
DN:

- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ⊙ ROADWAY SECTION
  - ➔ DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023



Texas Department of Transportation

SH 358 WB FRTG RD

ROADWAY LAYOUTS


SHEET 9 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	56	


DATE: 01/10/2023 04:27 PM  
FILE: p:\txdot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\3 - Roadway\SH358\_ROADWAY\_LAYOUTS9.dgn

DATE: 01/10/2023 04:35 PM 'M  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/3 - Roadway/SH358 - ROADWAY\_LAYOUTS10.dgn

DN:  
 CC:  
 DW:  
 CC:  
 CC:



- LEGEND**
- ▭ LIMITS OF ROADWAY WORK
  - ▨ LIMITS OF INTERSECTION WORK
  - ▩ PAVEMENT REPAIR
  - ⊕ ROADWAY SECTION



*E. Martinez*

03/14/2023




**SH 358 WB FRTG RD**

**ROADWAY LAYOUTS**


SHEET 10 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	57	


CK:  
DW:  
CK:  
DN:




TEMPORARY PLANING DETAILS AT EXISTING MANHOLES SECTION



FINAL PAVING DETAIL AT EXISTING MANHOLES SECTION




WEDGE MILL DETAIL  
STA 567+00 TO STA 571+00  
AYERS ST INTERSECTION




FLEXIBLE PAVEMENT STRUCTURE REPAIR DETAIL (2.5")

STA 338+09 TO STA 340+35	35'
STA 340+35 TO STA 342+00	35' - 30'
STA 342+00 TO STA 344+91	30'
STA 344+91 TO STA 348+79	52' - 40'
STA 348+79 TO STA 352+67	40' - 52'
STA 352+67 TO STA 357+00	30'



CONC MEDIAN REPLACEMENT DETAIL

REMOVAL TO BE PAID THROUGH ITEM 104 REMOVE CONC (MEDIAN)  
HOT MIX TO BE PAID THROUGH ITEM 3076 TY-B HMA  
ENTIRE INTERSECTION OVERLAYED W/ TBWC PER TYPICAL SECTION



*E. Martinez*

03/22/2023

NOTES:

1. LOCATIONS AND DIMENSIONS OF FLEXIBLE PAVEMENT STRUCTURE REPAIR ARE APPROXIMATE. EXACT LOCATIONS MUST BE VERIFIED WITH THE ENGINEER. THE ENGINEER MAY ADD ADDITIONAL LOCATIONS AS NEEDED AND QUANTITIES WILL BE ADJUSTED. PROVIDE MATERIALS OF THE TYPE AND GRADE AND IN ACCORDANCE WITH ITEM 3076, "DENSE-GRADED HOT-MIX ASPHALT" AND ITEM 316 "SEAL COAT". THE FOLLOWING DATA IS FOR CONTRACTOR'S INFORMATION ONLY AND WILL BE SUBSIDIARY TO ITEM 351, "FLEXIBLE PAVEMENT STRUCTURE REPAIR."
2. PAVEMENT REPAIR WIDTHS WILL BE 7' TO 12' TYP AS DETERMINED BY THE ENGINEER AND A MINIMUM OF 50' IN LENGTH.
3. SEE GENERAL NOTES FOR MATERIALS AND MATERIAL RATES.



SH 358 WB FRTG RD

MISCELLANEOUS  
DETAILS

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	58	

DATE: 03/16/2023 03:00 PM  
FILE: SFILES

DATE: 2/23/2023  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP\Design Projects\0617012074 - Design\Plan Set\13. Standards\Roadway Standards\OGELITE (M10) (N) -20.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

NOTE:  
A TRANSITION MAY BE REQUIRED TO INSTALL THE QUADGUARD ELITE M10 TO THE OBJECT BEING SHIELDED.

**QUADGUARD ELITE M10 24" WIDE (8 BAY) SYSTEM**




KEY	KEY
① ME3 CYLINDER ASSEMBLIES	⑥ DIAPHRAGMS
② ME2 CYLINDER ASSEMBLIES	⑦ FENDER PANELS
③ ME1 CYLINDER ASSEMBLY	⑧ MONORAILS
④ QEN CYLINDER	⑨ TYPE OF BACKUP
⑤ NOSE BELT ASSEMBLY	⑩ HIT INDICATOR

⑨ SHOWN WITH TENSION STRUT BACKUP ASSEMBLY

NOTE: PROVISION SHALL BE MADE FOR REAR FENDER SIDE PANELS TO SLIDE REARWARD UPON IMPACT, 25" MIN.

NOTE: HIT INDICATOR WILL RAISE UPON IMPACT.

④ QEN CYLINDER INSTALLED INSIDE OF NOSE BELT ASSEMBLY ⑤



NOTES:  
CONTACT THE MANUFACTURER WITH SITE SPECIFIC DATA (SSD) FOR CONCRETE PAD AND ANCHOR BLOCK INSTALLATION REQUIREMENTS.

A MANUFACTURER'S DRAWING PACKAGE UNIQUE AND SPECIFIC FOR THE QUADGUARD ELITE M10 FIELD INSTALLATION AND INFORMATION REGARDING THE TYPE OF BACKUP ASSEMBLY REQUIRED FOR THE TRANSITION WILL BE PROVIDED BY THE MANUFACTURER TO THE ENGINEER AND INSTALLER.

6" REINFORCED CONCRETE PAD REQUIRES THE INSTALLATION OF AN ANCHOR BLOCK AS SHOWN ON THE MANUFACTURER'S DRAWING PACKAGE.

8" NON-REINFORCED CONCRETE PAD MAY NOT REQUIRE AN ANCHOR BLOCK, IF THE PAD IS INSTALLED AGAINST AN IMMOVABLE CONCRETE BACKUP.

CONCRETE PAD AND ANCHOR BLOCK COMBINATIONS SHALL BE CONFIRMED WITH THE MANUFACTURER BASED UPON SITE SPECIFIC DATA (SSD).

NOTE:  
THE QUADGUARD ELITE M10 8-BAY, 24" WIDE - NARROW SYSTEM TESTED TO MASH TEST LEVEL 3.

TL-3 MODEL #	QM10024E	CYLINDER TYPES IN BAYS			
BAYS	8	TYPE-ME3	TYPE-ME2	TYPE-ME1	TYPE-QEN
DIAPHRAGMS	8	4	3	1	1
WIDTH	24"	REAR	FRONT	NOSE	

**BACKUP ASSEMBLY TYPES FOR SYSTEM TRANSITIONS**

SEE GENERAL NOTE 10 FOR CLEARANCE LIMITATIONS

⑨ TENSION STRUT BACKUP

⑨ CONCRETE BACKUP

SYSTEM TRANSITIONS TYPES	
1	QUAD-BEAM TO CONCRETE SAFETY BARRIER
2	QUAD-BEAM TO CONCRETE BRIDGE RAIL
3	QUAD-BEAM TO CONCRETE END SHOE
4	QUAD-BEAM TO THRIE-BEAM RAIL
5	QUAD-BEAM TO W-BEAM RAIL

NOTE:  
TRANSITION ASSEMBLIES FOR THE QUADGUARD ELITE M10 TO THRIE-BEAM OR W-BEAM FENCE REQUIRES I-BEAM POSTS:  
ALL POSTS W6X8.5/9 I-BEAMS (78" LONG).

NOTES:  
CONTACT THE MANUFACTURER WITH SITE SPECIFIC DATA (SSD) FOR THE CORRECT BACKUP ASSEMBLY AND TRANSITION PANELS OR SIDE PANELS USED FOR STANDARD AND BI-DIRECTIONAL INSTALLATIONS: AT DIVIDED-HIGHWAY MEDIANS OR UNDIVIDED ROADWAYS WHERE THE SYSTEM IS EXPOSED TO IMPACTS FROM ONE OR TWO DIFFERENT DIRECTIONS OF TRAFFIC FLOW.

NOTE:  
THIS STANDARD IS A BASIC REPRESENTATION OF THE QUADGUARD ELITE M10 SYSTEM AND IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

**GENERAL NOTES**

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY - ENERGY ABSORPTION INC. AT 1 (888) 323-6374.
- SEE THE RECENT QUADGUARD ELITE M10 PRODUCT DESCRIPTION ASSEMBLY MANUAL FOR IMPACT PERFORMANCE CHARACTERISTICS AND DESIGN LIMITATIONS AND THE DRAWING PACKAGE FOR THE NARROW 24" SYSTEM BEFORE INSTALLING THE QUADGUARD ELITE M10 AT ANY GIVEN LOCATION.
- FOR BI-DIRECTIONAL TRAFFIC: THE LOCATION AND OR WIDTH OF THE QUADGUARD ELITE M10 IS RESTRICTED. AS BI-DIRECTIONAL TRAFFIC APPROACHES THE REAR OF THE QUADGUARD ELITE M10, THE QUADGUARD ELITE M10 SHOULD NOT EXTEND FURTHER INTO THE TRAFFIC-SIDE OF THE BARRIER THAN THE OBSTACLE. ANY TRANSITION INSTALLED MUST EITHER BE TANGENT TO BOTH QUADGUARD ELITE M10 AND OBSTACLE OR MUST ANGLE TOWARD FIELD SIDE OF THE BARRIER.
- SYSTEM TRANSITION: APPROPRIATE TRANSITION PANELS OR SIDE PANELS WILL BE REQUIRED FOR PROPER IMPACT PERFORMANCE. THE CORRECT PANEL(S) TO USE WILL DEPEND ON THE DIRECTION OF TRAFFIC FLOW AND WHAT TYPE OF BARRIER OR ROAD FEATURE THE QUADGUARD ELITE M10 SYSTEM IS SHIELDING. SEE THE QUADGUARD ELITE M10 PRODUCT DESCRIPTION & ASSEMBLY MANUAL FOR FURTHER DETAILS.
- COMPONENTS FOR THE QUADGUARD ELITE (M10) BACKUP AND REINFORCING DETAILS ARE SHOWN ON THE QUADGUARD ELITE M10 PRODUCT DESCRIPTION & ASSEMBLY MANUAL.
- CONCRETE PAD SHALL BE 6" MIN. REINFORCED 28MPa [4,000 PSI] (P.C.) OR 8" MIN. NON-REINFORCED 28MPa [4,000 PSI] CONCRETE ROADWAY MEASURING AT LEAST 12'-0" WIDE BY 50'-0" LONG. ANCHOR BLOCK IS NOT REQUIRED WHEN USING 8" CONCRETE PAD INSTALLED AGAINST AN IMMOVABLE STRUCTURE, E.G. CONCRETE WALL.
- IF THE CROSS-SLOPE VARIES MORE THAN 2% OVER THE LENGTH OF THE SYSTEM, THE CONCRETE PAD WILL REQUIRE LEVELING. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
- THE INSTALLATION AREA SHOULD BE FREE OF CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
- THE QUADGUARD ELITE M10 SYSTEM SHOULD BE INSTALLED APPROXIMATELY PARALLEL WITH THE BARRIER.
- FOR THE TENSION STRUT BACKUP THE DISTANCE BETWEEN THE BACK OF BACKUP AND THE BARRIER WALL SHOULD NOT EXCEED 7" IN ANY CASE.
- TXDOT HAS ONLY APPROVED THE 24" WIDE QUADGUARD ELITE M10 SYSTEM. THE QUADGUARD ELITE M10 PRODUCT DESCRIPTION AND ASSEMBLY MANUAL INCLUDES SYSTEM WIDTH OF 24". ONLY THE 24" SYSTEM IS ALLOWED TO BE INSTALLED ON TEXAS ROADWAYS.

FOUNDATION & ANCHORING REQUIREMENTS	
FOUNDATION TYPES: A, B, C, & D	
FOUNDATION TYPE: A	REINFORCED CONCRETE PAD OR ROADWAY
FOUNDATION:	6" MINIMUM DEPTH (P.C.C.)
ANCHORAGE:	7" STUDS EMBEDDED 5 1/2" - APPROVED ADHESIVE
FOUNDATION TYPE: B	ASPHALT OVER P.C.C.
FOUNDATION:	3" MIN. (A.C.) OVER 3" MIN. (P.C.C.)
ANCHORAGE:	18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE
FOUNDATION TYPE: C	ASPHALT OVER SUBBASE
FOUNDATION:	6" MIN. (A.C.) OVER 6" MIN. (C.S.)
ANCHORAGE:	18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE
FOUNDATION TYPE: D	ASPHALT ONLY
FOUNDATION:	8" MIN. (A.C.)
ANCHORAGE:	18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE

KEY:  
ASPHALT CONCRETE (A.C.)  
COMPACTED SUBBASE (C.S.)  
PORTLAND CEMENT CONCRETE (P.C.C.)

NOTE: SEE TRINITY'S PRODUCT DESCRIPTION ASSEMBLY MANUAL FOR THE APPROVED ADHESIVE.

IF THE UNIT IS ANCHORED TO ASPHALTIC CONCRETE, IT SHOULD BE RELOCATED TO FRESH, UNDISTURBED ASPHALT AND RE-ANCHORED AFTER EACH IMPACT TO ENSURE ADEQUATE FUTURE PERFORMANCE.

TENSION STRUT BACKUP MAY BE USED IN CONSTRUCTION ZONES ON ASPHALT CONCRETE (A.C.) FOR TEMPORARY USE ONLY.

Texas Department of Transportation  
Design Division Standard






**TRINITY HIGHWAY  
ENERGY ABSORPTION  
QUADGUARD ELITE M10  
(MASH TL-3)  
OGELITE (M10) (N) -20**

FILE: qgelite1em10n20.dgn	DN: TXDOT	CK: KM	DW: VP	CK: AG
© TXDOT: NOVEMBER 2020	CONT SECT	JOB	HIGHWAY	
REVISIONS	0617 01	207	SH 358	
	DIST	COUNTY	SHEET NO.	
	CRP	NUECES	59	

**LOW MAINTENANCE**



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



NOTES:  
CONTACT THE MANUFACTURER WITH SITE SPECIFIC DATA (SSD) FOR THE CORRECT BACKUP ASSEMBLY AND TRANSITION PANELS OR SIDE PANELS USED FOR STANDARD AND BI-DIRECTIONAL INSTALLATIONS: AT DIVIDED-HIGHWAY MEDIANS OR UNDIVIDED ROADWAYS WHERE THE SYSTEM IS EXPOSED TO IMPACTS FROM ONE OR TWO DIFFERENT DIRECTIONS OF TRAFFIC FLOW.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY - ENERGY ABSORPTION AT 1(888)323-6374 OR WEBSITE: [www.trinityhighway.com](http://www.trinityhighway.com).
  - THE NOSE OF THE REACT M SHALL BE CLAD WITH A PLASTIC WRAP WITH STANDARD DELINEATION ADHERED TO THE WRAP AND SHALL HAVE A SERIES OF SIDE MARKER REFLECTORS ON BOTH SIDES OF THE UNIT. SEE SITE PLAN VIEWS FOR MARKER AND PLASTIC WRAP COLOR ORIENTATION.
  - FOR BI-DIRECTIONAL TRAFFIC, APPROPRIATE TRANSITION DETAILS WILL BE AS SHOWN ON THE MANUFACTURER'S SHOP DRAWINGS.
  - DETAILS OF COMPONENTS FOR THE REACT M, BACKUPS AND REINFORCING DETAILS WILL BE SHOWN ON THE MANUFACTURER'S SHOP DRAWINGS FURNISHED TO THE ENGINEER.
  - IF THE CROSS-SLOPE VARIES MORE THAN 2% OVER THE LENGTH OF THE SYSTEM, THE CONCRETE PAD WILL REQUIRE LEVELING. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
  - THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
  - THE REACT M SYSTEM SHOULD BE APPROXIMATELY PARALLEL WITH THE BARRIER OR CENTERLINE OF MERGING BARRIERS.
  - ALL STEEL COMPONENTS TO BE HOT DIPPED GALVANIZED EXCEPT STAKES, DRIVE SPIKES, THREADED BOLTS IN BACKUP UNIT, AND WEDGE FITTINGS ON CABLES.
  - THIS DRAWING REPRESENTS THE REACT M TL-3 SYSTEM, RE-DIRECTIVE, NON-GATING CRASH CUSHION THAT CAN PROTECT HAZARDS UP TO 30-INCHES IN WIDTH.

**DESIGN DATA TABLE FOR REACT M**

TEST NUMBER	TEST LEVEL	OVERALL LENGTH	TRANSITION LENGTH	SYSTEM WIDTH
3-30 to 3-36	TL-3	22'-2 3/4"	-	3'-5 3/4"
3-37A	TL-3	22'-2 3/4"	9'-10 3/4"	3'-5 3/4"
3-38	TL-3	22'-2 3/4"	-	3'-5 3/4"

**ANCHOR SYSTEM TYPE**

APPROVED ADHESIVE, 7" STUDS, 5.5" EMBEDMENT

**FOUNDATION TYPES**

MINIMUM 8" REINFORCED PORTLAND CEMENT CONCRETE PAD (REQUIRED REINFORCING STEEL FOR CONCRETE PAD SHALL BE SHOWN ON THE MANUFACTURER'S SHOP DRAWINGS.)

MINIMUM 8" NON-REINFORCED PORTLAND CEMENT CONCRETE ROADWAY MEASURING AT LEAST 12' WIDE BY 50' LONG)

MINIMUM 7" CONCRETE DECK STRUCTURE, OR MINIMUM 6" REINFORCED CONCRETE ROADWAY

NOTE:  
THIS STANDARD IS A BASIC REPRESENTATION OF THE REACT M SYSTEM AND IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Texas Department of Transportation *Design Division Standard*


**TRINITY HIGHWAY ENERGY ABSORPTION CRASH CUSHION REACT M (NARROW) (MASH TL-3) REACT (M) -21**

FILE: reactm21.dgn	DN: TxDOT	CK: KM	DW: SS	CK: CL
©TxDOT: JULY 2021	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
	DIST	COUNTY		SHEET NO.
	CRP	NUECES		60


**LOW MAINTENANCE**

DATE: 2/23/2023  
FILE: \$FILEL\$.s

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 2/23/2023  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/Roadway Standards/SMTc(N) - 16.dgn



**PLAN VIEW**



**ELEVATION VIEW**

6" REINFORCED PAD SHOWN  
(SEE FOUNDATION OPTIONS)

**GENERAL NOTES**

1. FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: WORK AREA PROTECTION, CORP. AT (800) 327-4417, OR (630) 377-9100.
2. FOR BI-DIRECTIONAL TRAFFIC, APPROPRIATE TRANSITION PANELS WILL BE REQUIRED.
3. ADDITIONAL DETAILS FOR THE TRANSITION OPTION AND FOUNDATION OPTION WILL BE SHOWN ON THE MANUFACTURER'S SHOP DRAWINGS FURNISHED TO THE ENGINEER.
4. CONCRETE SHALL BE CLASS "S" WITH A MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI.
5. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
6. THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
7. THE SCI100GM & SCI70GM SYSTEMS SHOULD BE APPROXIMATELY PARALLEL WITH THE BARRIER OR CENTERLINE OF MERGING BARRIERS.

NOTE:  
FOR ATTACHMENT AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BI-DIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

NOTE:  
SIDE PANELS CAN TRAVEL 30" BEYOND THE LAST TERMINAL BRACE AT THE REAR OF THE CUSHION. ALL OBJECTS THAT MAY INTERFERE WITH THIS MOTION CAN AFFECT PERFORMANCE OF AND MAY CAUSE UNDUE DAMAGE TO THE CRASH CUSHION.

MODEL	TEST LEVEL	UNIT LENGTH (approx.)	UNIT WIDTH	FOUNDATION LENGTH	OBSTACLE WIDTH
SCI70GM	TL-2	13'-6"	2'-10 5/8"	15'- 6 1/4"	24" to 36"
SCI100GM	TL-3	21'-6"	3'-1 1/2"	23'- 0"	24" to 36"

SYSTEM AND PAD LENGTHS VARY DEPENDING ON BACKUP TYPE.

FOUNDATION OPTIONS
6" REINFORCED CONCRETE (5 1/2" ANCHOR EMBEDMENT)
8" UNREINFORCED CONCRETE (5 1/2" ANCHOR EMBEDMENT)
3" MIN. ASPHALT OVER 3" MIN. CONCRETE (16 1/2" ANCHOR EMBED.)
6" ASPHALT OVER 6" COMPACT SUBBASE (16 1/2" ANCHOR EMBED.)
8" MINIMUM ASPHALT (16 1/2" ANCHOR EMBEDMENT)

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

TRANSITION OPTIONS
CONCRETE VERTICAL WALL
CONCRETE TRAFFIC BARRIERS
GUARDRAIL (W-BEAM)
GUARDRAIL (THRIE-BEAM)

TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS (I.E. ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES).

FOR BI-DIRECTIONAL TRANSITION PANEL AND END SHOE DETAILS, SEE MANUFACTURER'S PRODUCT MANUAL.




**WORK AREA PROTECTION  
CORP  
(SMART-NARROW)  
SMTc(N) - 16**

FILE: smtcn16.dgn	DN: TxDOT	CK: KM	DW: VP	CK: VP
©TxDOT: February 2006	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
REVISED 06, 2013 (VP)	DIST	COUNTY	SHEET NO.	
REVISED 03, 2016 (VP)	CRP	NUECES	61	


**LOW MAINTENANCE**

DATE: 2/23/2023 4:43:39 PM  
 FILE: \\txdot.projectwiseonline.com\TXDOT14\Documents\16 - CRP\Design\Project\16190101\16190101.dgn  
 PROJECT: 16190101 - CRP Design  
 DRAWING: 16190101.dgn  
 STANDARD: Standard.dwg/RLSTD014-19.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy or completeness of the information provided.




**ROADWAY ELEVATION OF RAIL**




**INTERMEDIATE WALL JOINT DETAIL**


Provide at all interior bents without slab expansion joints.



**ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT**



**SECTION**  
**ELEVATION**  
**TERMINAL CONNECTION DETAILS**



**PLAN OF RAIL AT EXPANSION JOINTS**

Example showing Slab Expansion Joints without breakbacks.


- 1 Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- 2 Increase 2" for structures with Overlay.
- 3 Back of rail offset may, with Engineer's approval, be continued to the end of the railing.
- 4 Place 4 additional Bars R(#4) 3'-8" in length inside Bars S(#4) and centered 2'-0" from end of rail when Terminal Connections are required.

SHEET 1 OF 2


		<b>Bridge Division Standard</b>	
<b>TRAFFIC RAIL SINGLE SLOPE</b>			
<b>TYPE SSTR</b>			
FILE: rlst014-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONT	SECT	HIGHWAY
REVISIONS	0617	01	207 SH 358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	62	

DATE: 2/23/2023 4:43:42 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT4\Documents\16 - CRP/Design Projects\Railroad Separators\Roadway Standard\RLSTD014-19.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.




**SECTIONS THRU RAIL**




BARS S (#4)



BARS U (#4)



BARS WU (#4)



OPTIONAL WELDED WIRE REINFORCEMENT (WWR)


- ② Increase 2" for structures with Overlay.
- ⑤ 5 1/4" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑥ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars must be furnished at the Contractor's expense.
- ⑦ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑧ No longitudinal wires may be within upper bend.
- ⑨ Bend or cut as required to clear drain slots.
- ⑩ Space U(#4) bars at 4" Max when end region of panel length is less than 6'-0" to side slot drain. Space U(#4) bars at 6" Max when end region of panel length is 6'-0" and greater to side slot drain.

**CONSTRUCTION NOTES:**  
 This railing may be constructed by the slipform process when approved by the Engineer, with equipment approved by the Engineer. Provide sensor control for both line and grade. Tack welding to provide bracing for slipform operations is acceptable. Welding may be performed at a minimum spacing of 3 ft between the cage and the anchorage. It is permissible to weld to bars U, WU and S at any location on the cage. If increased bracing is needed, provide additional anchorage devices and weld in the upper two thirds of the cage. Paint welded areas on epoxy coated and/or galvanized reinforcing with an organic zinc rich paint in accordance with Item 445 "Galvanizing".  
 If rail is slipformed, apply an heavy epoxy bead 1" behind toe of traffic side of rail to concrete deck just prior to slip forming. Provide a 3/8" width x 1/4" tall heavy epoxy bead with Type III, Class C or a Type V epoxy.  
 The back of railing must be vertical unless otherwise shown in the plans or approved by the Engineer.

**MATERIAL NOTES:**  
 Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.  
 Provide Grade 60 reinforcing steel.  
 Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized.  
 Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars U and WU unless noted otherwise. Deformed WWR (ASTM A1064) may be substituted for Bars R and S, as shown. Combinations of reinforcing steel and WWR or configurations of WWR other than shown are permitted if conditions in the table are satisfied. Provide the same laps as required for reinforcing bars.  
 Provide bar laps, where required, as follows:  
 Uncoated or galvanized ~ #4 = 1'-7"  
 Epoxy coated ~ #4 = 2'-5"


**GENERAL NOTES:**  
 This rail has been successfully evaluated by full-scale crash test to meet MASH TL-4 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.  
 Do not use this railing on bridges with expansion joints providing more than 5" movement.  
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.  
 Shop drawings will not be required for this rail.  
 Average weight of railing with no overlay is 376 plf.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bar dimensions shown are out-to-out of bar.



**OPTIONAL SIDE SLOT DRAIN DETAIL**

Note: Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. Drains should not be placed over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.



**SECTION THRU OPTIONAL SIDE SLOT DRAIN**

DESCRIPTION	LONGITUDINAL WIRES	VERTICAL WIRES
Minimum (Cumulative Total) Wire Area	1.067 Sq In.	0.267 Sq In. per Ft
Minimum	No. of Wires	Spacing
Maximum	8	4"
Maximum Wire Size Differential	10	8"
	The smaller wire must have an area of 40% or more of the larger wire.	

Texas Department of Transportation  
 Bridge Division Standard

**TRAFFIC RAIL SINGLE SLOPE**

**TYPE SSTR**

FILE: rlstd014-19.dgn	DN: TXDOT	CK: TXDOT	DW: JTR	CK: TXDOT
©TXDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH 358
DIST	COUNTY	SHEET NO.		
CRP	NUECES			63




DATE: 01/10/2023 04:12 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/8 - Traffic/SH358\_SURFACE\_DETAILS.dgn

CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_



- LEGEND**
- ▣ PREFAB PAV MRK TY C (W) (WORD)
  - ↖ PREFAB PAV MRK TY C (W) (ARROW)
  - ↗ PREFAB PAV MRK TY C (W) (DBL ARROW)
  - ↻ PREFAB PAV MRK TY C (W) (UTURN ARROW)
  - ↑↑ DIRECTION OF TRAFFIC



MATCHLINE STA. 369+00.00



MATCHLINE STA. 381+00.00



*Eric R. Martinez*

03/14/2023

**Texas Department of Transportation**

**SH 358 WB FRTG RD**




**SURFACE DETAIL LAYOUTS**

SHEET 1 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST		COUNTY	SHEET NO.
CRP		NUECES	65

DATE: 01/10/2023 04:13 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/8 - Traffic/SH358\_SURFACE\_DETAILS2.dgn

- LEGEND**
- ▣ PREFAB PAV MRK  
TY C (W) (WORD)
  - ↵ PREFAB PAV MRK  
TY C (W) (ARROW)
  - ↵↵ PREFAB PAV MRK  
TY C (W) (DBL ARROW)
  - ↵↵↵ PREFAB PAV MRK  
TY C (W) (UTURN ARROW)
  - ↑↑ DIRECTION  
OF TRAFFIC



*E. Martinez*

03/14/2023

**Texas Department of Transportation**

**SH 358 WB FRTG RD**

**SURFACE DETAIL LAYOUTS**

SHEET 2 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	66	



DATE: 01/10/2023 04:15 PM  
 FILE: p:\t\dot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\8 - Traffic\SH358\_SURFACE\_DETAILS3.dgn

MATCHLINE STA. 405+00.00


MATCHLINE STA. 417+00.00

MATCHLINE STA. 417+00.00

MATCHLINE STA. 429+00.00



- LEGEND**
- ▬ PREFAB PAV MRK TY C (W) (WORD)
  - ↖ PREFAB PAV MRK TY C (W) (ARROW)
  - ↔ PREFAB PAV MRK TY C (W) (DBL ARROW)
  - ↻ PREFAB PAV MRK TY C (W) (UTURN ARROW)
  - ↑ DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023

Texas Department of Transportation

**SH 358 WB FRTG RD**



**SURFACE DETAIL LAYOUTS**

SHEET 3 OF 10


CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	67	



DATE: 01/10/2023 04:16 PM 'M  
 FILE: p:\txdot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\8 - Traffic\SH358\_SURFACE\_DETAILS4.dgn



- LEGEND**
- ▬ PREFAB PAV MRK TY C (W) (WORD)
  - ↖ PREFAB PAV MRK TY C (W) (ARROW)
  - ↗ PREFAB PAV MRK TY C (W) (DBL ARROW)
  - ↻ PREFAB PAV MRK TY C (W) (UTURN ARROW)
  - ↑↓ DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023






**SH 358 WB FRTG RD**  
**SURFACE DETAIL LAYOUTS**

SHEET 4 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	68	

DATE: 01/10/2023 04:17 PM M  
 FILE: p:\txdot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\8 - Traffic\SH358\_SURFACE\_DETAIL\SS.dgn

- LEGEND**
- ▬ PREFAB PAV MRK TY C (W) (WORD)
  - ▬ PREFAB PAV MRK TY C (W) (ARROW)
  - ↔ PREFAB PAV MRK TY C (W) (DBL ARROW)
  - ↻ PREFAB PAV MRK TY C (W) (UTURN ARROW)
  - ↑↓ DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023



SH 358 WB FRTG RD




SURFACE DETAIL LAYOUTS

SHEET 5 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	69	

DATE: 01/10/2023 04:19 PM TM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/8 - Traffic/SH358\_SURFACE\_DETAIL/SH358.dgn

- LEGEND**
- ▣ PREFAB PAV MRK  
TY C (W) (WORD)
  - ↖ PREFAB PAV MRK  
TY C (W) (ARROW)
  - ↗ PREFAB PAV MRK  
TY C (W) (DBL ARROW)
  - ↻ PREFAB PAV MRK  
TY C (W) (TURN ARROW)
  - ↑↓ DIRECTION  
OF TRAFFIC



*E. Martinez*

03/14/2023





SH 358 WB FRTG RD

SURFACE DETAIL  
LAYOUTS


SHEET 6 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	70	

DATE: 01/10/2023 04:20 PM TM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/8 - Traffic/SH358\_SURFACE\_DETAILS7.dgn



- LEGEND**
- ▣ PREFAB PAV MRK TY C (W) (WORD)
  - ▤ PREFAB PAV MRK TY C (W) (ARROW)
  - ▥ PREFAB PAV MRK TY C (W) (DBL ARROW)
  - ▧ PREFAB PAV MRK TY C (W) (UTURN ARROW)
  - ↑↓ DIRECTION OF TRAFFIC



*E. R. Martinez*

03/14/2023

Texas Department of Transportation

SH 358 WB FRTG RD

SURFACE DETAIL LAYOUTS

SHEET 7 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	71	



DATE: 01/10/2023 04:24 PM PM  
 FILE: p:\t\dot\project\seonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan\_Set\8 - Traffic\SH358\_SURFACE\_DETAIL\8.dgn

MATCHLINE STA. 525+00.00


MATCHLINE STA. 537+00.00

MATCHLINE STA. 537+00.00

MATCHLINE STA. 549+00.00



- LEGEND**
- ▣ PREFAB PAV MRK TY C (W) (WORD)
  - ↖ PREFAB PAV MRK TY C (W) (ARROW)
  - ↗ PREFAB PAV MRK TY C (W) (DBL ARROW)
  - ↻ PREFAB PAV MRK TY C (W) (UTURN ARROW)
  - ↑↓ DIRECTION OF TRAFFIC



*E. Martinez*

03/14/2023



**SH 358 WB FRTG RD**  
**SURFACE DETAILS LAYOUTS**

SHEET 8 OF 10

CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY		SHEET NO.
CRP	NUECES		72

DATE: 01/10/2023 04:23 PM V  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/8 - Traffic/SH358\_SURFACE\_DETAILS9.dgn

MATCHLINE STA. 549+00.00




MATCHLINE STA. 561+00.00

MATCHLINE STA. 561+00.00

MATCHLINE STA. 573+00.00

**LEGEND**

- ▬ PREFAB PAV MRK  
TY C (W) (WORD)
- ↖ PREFAB PAV MRK  
TY C (W) (ARROW)
- ↔ PREFAB PAV MRK  
TY C (W) (DBL ARROW)
- ↻ PREFAB PAV MRK  
TY C (W) (UTURN ARROW)
- ↑↓ DIRECTION  
OF TRAFFIC



*E. Martinez, P.E.*

03/14/2023

Texas Department of Transportation


SH 358 WB FRTG RD

SURFACE DETAIL LAYOUTS

SHEET 9 OF 10



CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	73	

DATE: 01/10/2023 04:11 PM PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/8 - Traffic/SH358 SURFACE DETAILS10.dgn



**LEGEND**

- PREFAB PAV MRK TY C (W) (WORD)
- PREFAB PAV MRK TY C (W) (ARROW)
- PREFAB PAV MRK TY C (W) (DBL ARROW)
- PREFAB PAV MRK TY C (W) (UTURN ARROW)
- DIRECTION OF TRAFFIC




*E. R. Martinez, P.E.*

03/14/2023

<b>SH 358 WB FRTG RD</b>			
<b>SURFACE DETAIL LAYOUTS</b>			
SHEET 10 OF 10			
CONT	SECT	JOB	HIGHWAY
0617	01	207	SH358
DIST	COUNTY	SHEET NO.	
CRP	NUECES	74	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/20/2022 09:34 AM  
FILE: DOCUMENT NAME




**NOTE**  
Reflectorized raised pavement markers Type II-C-R shall be spaced on 80' centers with the clear face toward normal traffic and the red face toward wrong way traffic. All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.

**TRAFFIC LANE LINES PAVEMENT MARKING**




**NOTE**  
Edge lines should typically be 6" wide and the materials shall be as specified in the plans. See details above if reflective profile pavement markings are to be used.

**EDGE LINE PAVEMENT MARKINGS**




**NOTES**  
1. Reflectorized raised pavement markers Type-II-C-R in the wrong way arrow shall have the clear face toward normal traffic and the red face toward the wrong way traffic.  
2. Red reflectorized wrong way arrows, not to exceed two, may be placed on exit ramps. Locations of the arrows shall be as shown in the plans or as directed by the engineer.

**WRONG WAY ARROW**




**TYPICAL ENTRANCE RAMP GORE MARKING**



**NOTE**  
See the Roadway Design Manual Chapter 3 to determine if a tapered acceleration lane may be used.

**TAPERED ACCELERATION LANE**



**NOTE**  
See the Roadway Design Manual Chapter 3 to determine lengths of the acceleration lane and taper.


**PARALLEL ACCELERATION LANE**

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

LEGEND	
←	Traffic flow
↩	Pavement marking arrows (white)
□	Reflectorized Raised Markers (RPM) Type II-C-R

**GENERAL NOTE**  
On concrete pavements the raised pavement markers shall be placed to one side of the longitudinal joints.



Type II (Top View)



SECTION A

**REFLECTORIZED RAISED PAVEMENT MARKER (RPM)**


Texas Department of Transportation  
Traffic Safety Division Standard

**TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS WITH RAISED PAVEMENT MARKERS FPM(1)-22**

FILE: fpm(1)-22.dgn	DN:	CK:	DW:	CK:
©TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH358
5-74 8-00 2-12	DIST	COUNTY	SHEET NO.	
4-92 2-08 10-22	CRP	NUECES	75	
5-00 2-10				




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




### SINGLE LANE EXIT WITH AUXILIARY LANE

(See Note 2)




### TAPERED DECELERATION LANE

**NOTE**  
Reference Roadway Design Manual Chapter 3 to determine if tapered deceleration lane may be used.




### PARALLEL DECELERATION LANE


**NOTE**  
Reference Roadway Design Manual Chapter 3 to determine length of deceleration lane and taper.




**DETAIL A**



**DETAIL B**



**DETAIL C**



**DETAIL D**

#### GENERAL NOTES

- Pavement markings shall be white except as otherwise noted.
- Length of 12" white line may vary depending on location.
- Wide (12") dotted lane line (see Detail B) is used to separate a through lane that continues beyond the interchange from an adjacent mandatory exit lane.
- Normal (6") dotted lane line (see Detail C) is used at parallel acceleration and deceleration lanes.
- See FPM(1) for traffic lane line pavement marking details.

#### LEGEND

←	Traffic flow
↶	Pavement marking arrows (white)
□	Reflectorized Raised Markers (RPM) Type II-C-R
✱	Arrow markings are optional, however "ONLY" is required if arrow is used

#### MATERIAL SPECIFICATIONS

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.






## TYPICAL STANDARD FREEWAY PAVEMENT MARKINGS ENTRANCE AND EXIT RAMP

### FPM(2) - 22

FILE: fpm(2)-22.dgn	DN:	CK:	DW:	CK:
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH358
2-77 5-00 2-12	DIST	COUNTY	SHEET NO.	
4-92 8-00 10-22	CRP	NUECES	76	
8-95 2-10				

DATE: 12/20/2022 09:37 AM  
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.

**GENERAL NOTES**

1. Pavement markings shall be white except as otherwise noted.
2. Length of 12" white line may vary depending on location.
3. Wide (12") dotted lane line (see FPM(2) Detail B) is used to separate a through lane that continues beyond the interchange from an adjacent mandatory exit lane.
4. Edge lines are not required in curb and gutter sections of frontage roads.
5. See FPM(1) for traffic lane line pavement marking details.

LEGEND	
↔	Traffic flow
↶	Pavement marking arrows (white)
□	ReflectORIZED Raised Markers (RPM) Type II-C-R
*	Arrow markings are optional, however "ONLY" is required if arrow is used



**TYPICAL STANDARD  
FREEWAY AND FRONTAGE  
ROAD PAVEMENT MARKINGS**


**FPM(6) -22**

FILE: fpm(6)-22.dgn	DN:	CK:	DW:	CK:
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
10-22	REVISIONS	0617 01	207	SH358
	DIST	COUNTY	SHEET NO.	
	CRP	NUECES	77	


DATE: 01/09/2023 10:03 AM  
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/20/2022 09:43 AM  
 FILE: DOCUMENT NAME





**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**





**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**YIELD LINES**



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**  
Based on Traveled Way and Pavement Widths  
for Undivided Roadways



**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

**NOTES**

- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

**GENERAL NOTES**

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




**TYPICAL STANDARD  
PAVEMENT MARKINGS**

**PM(1) - 22**


FILE:	pml-22.dgn	DN:	CK:	DW:	CK:
© TxDOT	December 2022	CONT	SECT	JOB	HIGHWAY
11-78	8-00 6-20	0617	01	207	SH358
8-95	3-03 12-22	DIST	COUNTY	SHEET NO.	
5-00	2-12	CRP	NUECES	78	

# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS**



**CENTERLINE & LANE LINES  
FOR FOUR LANE TWO-WAY ROADWAYS**





**CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE**




**LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)**

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.  
See Note 3.



**REFLECTORIZED PROFILE  
PATTERN DETAIL**

USING REFLECTIVE PROFILE PAVEMENT MARKINGS



**NOTES**


1. Edge lines should typically be 6" wide and the materials shall be specified in the plans.
2. Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

**GENERAL NOTES**


1. All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
3. Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**Type I (Top View)**



**Type II (Top View)**



**SECTION A**

**RAISED PAVEMENT MARKERS**




**POSITION GUIDANCE USING  
RAISED MARKERS  
REFLECTORIZED PROFILE  
MARKINGS  
PM(2) - 22**

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH358
4-77 8-00 6-20	DIST	COUNTY	SHEET NO.	
4-92 2-10 12-22	CRP	NUECES	79	
5-00 2-12				

DATE: 12/20/2022 09:45 AM  
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 01/09/2023 10:09 AM  
FILE: DOCUMENT NAME



LANE REDUCTION

NOTES

- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.


ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	
45 MPH	775	L=WS
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

GENERAL NOTES


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE




TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY



TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A

DETAIL B


\* 2" minimum allowed for restripe projects when approved by the Engineer.

Texas Department of Transportation  
Traffic Safety Division Standard

### TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 22

FILE: pm3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH358
4-98 3-03 6-20	DIST	COUNTY	SHEET NO.	
5-00 2-10 12-22	CRP	NUECES	80	
8-00 2-12				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**HIGH-VISIBILITY LONGITUDINAL CROSSWALK AT CONTROLLED APPROACH**

**GENERAL NOTES**

1. Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
3. For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
5. Each crosswalk shall be a minimum of 6' wide.
6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
7. Final placement of Stop Bar and Crosswalk shall be approved by the Engineer in the field.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**UNSIGNALIZED MIDBLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK**

**NOTES:**

1. Use stop bars with Stop Here For Pedestrians (R1-5b) signs at unsignalized midblock crosswalks.
2. Use stop bars with STOP HERE ON RED (R10-6 or R10-6a) signs at mid block crosswalks controlled by traffic signals or pedestrian hybrid beacons.

DATE: 12/20/2022 10:01 AM  
FILE: DOCUMENT NAME




<p><b>CROSSWALK PAVEMENT MARKINGS</b></p> <p><b>PM(4) - 22A</b></p>			
FILE: pm4-22a.dgn	DN:	CK:	DW:
© TxDOT December 2022	CONT	SECT	JOB
REVISIONS	0617	01	207
6-20	DIST	COUNTY	SHEET NO.
6-22	CRP	NUECES	81
12-22			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 01/17/2023 08:08 AM  
FILE: DOCUMENT NAME

## REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

## REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

## GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS

### TSR(3) - 13


FILE:	tsr3-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
©TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0617	01	207	SH358				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		CRP	NUECES	82					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 01/17/2023 08:16 AM  
 FILE: DOCUMENT NAME

### REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

### REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR WARNING SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR SCHOOL SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

### GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:  
<http://www.txdot.gov/>


				<i>Traffic Operations Division Standard</i>	
<h2>TYPICAL SIGN REQUIREMENTS</h2>					
<h3>TSR(4) - 13</h3>					
FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT:	SECT:	JOB:	HIGHWAY:
REVISIONS		061701	207		SH358
12-03	7-13	DIST:	COUNTY:	SHEET NO.	
9-08		CRP	NUECES	83	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

### ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	

CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT


**NOTE**

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.


<http://www.txdot.gov/>

### SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5



EXIT ONLY PANEL


### MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

**NOTE:**

- Sheeting for legend, symbols, and borders must be cut at panel joints.
- Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".



SCREW ATTACHMENT




NUT/BOLT ATTACHMENT


**NOTE:**

Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

### ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.



## TYPICAL SIGN REQUIREMENTS

### TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0617	01	207	SH358
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	CRP	NUECES	84	

DATE: 01/17/2023 08:19 AM  
 FILE: DOCUMENT NAME

DATE: 2/23/2023 4:49:43 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/Traffic Standards/smdgen.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conveyance of this standard to other formats or for incorrect results or damages resulting from its use.

## SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)


SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

**Post Type**  
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))  
 TWT = Thin-Walled Tubing (see SMD(TWT))  
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))  
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

**Number of Posts (1 or 2)**  
**Anchor Type**  
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))  
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))  
 WS = Wedge Anchor Steel - (see SMD(TWT))  
 WP = Wedge Anchor Plastic (see SMD(TWT))  
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))  
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))



**Sign Mounting Designation**  
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))  
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))  
 IF REQUIRED  
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))  
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))  
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))

## REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT






To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


## SIGN LOCATION



No more than 2 sign posts should be located within a 7 ft. circle.



## TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.


Sign clamps may be either the specific size clamp or the universal clamp.

Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"


## SIGNS WITH PLAQUES



## CURB & GUTTER OR RAISED ISLAND



## RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

\*\*\* Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

\* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:  
<http://www.txdot.gov/publications/traffic.htm>




## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS SMD (GEN) - 08

© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0617	01	207	SH 358
		DIST	COUNTY		SHEET NO.
		CRP	NUECES		85

DATE: 2/23/2023 4:50:00 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/Traffic Standards/smdsl.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

## TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



### NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. [http://www.txdot.gov/business/producer\\_list.htm](http://www.txdot.gov/business/producer_list.htm)  
 The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

### GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
  - 10 BWG Tubing (2.875" outside diameter)
    - 0.134" nominal wall thickness
    - Seamless or electric-resistance welded steel tubing or pipe
    - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
    - Other steels may be used if they meet the following:
      - 55,000 PSI minimum yield strength
      - 70,000 PSI minimum tensile strength
      - 20% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
    - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
    - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
  - Schedule 80 Pipe (2.875" outside diameter)
    - 0.276" nominal wall thickness
    - Steel tubing per ASTM A500 Gr C
    - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
      - 46,000 PSI minimum yield strength
      - 62,000 PSI minimum tensile strength
      - 21% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
    - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
    - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

### ASSEMBLY PROCEDURE


#### Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

#### Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

### CONCRETE ANCHOR



5/8" diameter Concrete Anchor -  
 8 places (embed a minimum of  
 5 1/2" and torque to min. of  
 50 ft-lbs). Anchor may be  
 expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.







## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08











© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
9-08	REVISIONS		CONT	SECT	JOB	HIGHWAY
			0617	01	207	SH 358
			DIST	COUNTY	SHEET NO.	
		CRP	NUECES		86	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/23/2023 4:50:17 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/Traffic Standards/smds2.dgn



All dimensions are in english unless detailed otherwise.



Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes.

The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture.

Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	












SIGN MOUNTING DETAILS  
 SMALL ROADSIDE SIGNS  
 TRIANGULAR SLIPBASE SYSTEM  
 SMD(SLIP-2)-08

© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0617	01	207	SH 358
		DIST	COUNTY		SHEET NO.
		CRP	NUECES		87

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/23/2023 4:50:31 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/Traffic Standards/smds3.dgn



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG       | 1          | 16 SF          |
| 10 BWG       | 2          | 32 SF          |
| Sch 80       | 1          | 32 SF          |
| Sch 80       | 2          | 64 SF          |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)



**SIGN MOUNTING DETAILS  
 SMALL ROADSIDE SIGNS  
 TRIANGULAR SLIPBASE SYSTEM  
 SMD(SLIP-3)-08**

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0617	01	207	SH 358
		DIST	COUNTY		SHEET NO.
		CRP	NUECES		88

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**

0617-01-207

**1.2 PROJECT LIMITS:**

From: West of Staples St

To: West of Ayers St

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 27.7355216° (N), (Long) -97.4273134° (W)

END: (Lat) 27.7040396° (N), (Long) -97.3628206° (W)

**1.4 TOTAL PROJECT AREA: 20.67 Acres**

**1.5 TOTAL AREA TO BE DISTURBED: 0 Acres**

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

Rehabilitation of existing roadway consisting of planing, pavement inlay, pavement repairs, and pavement markings.

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
Victoria Clay 0 to 1 percent slopes	97% clay, well drained, medium rate of runoff
Orellia fine sandy loam 0 to 1 percent slopes	90% loam, well drained, low rate of runoff

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
	Oso Bay (segment 2485)

\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)**



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				89
STATE	STATE DIST.	COUNTY		
TEXAS	CRP	NUECES		
CONT.	SECT.	JOB	HIGHWAY NO.	
0617	01	207	SH 358	

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- X   Biodegradable Erosion Control Logs
- Dewatering Controls
- X   Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

No surface waters present, vegetated buffer zones are not planned.

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

**2.9 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)**



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				90
STATE	STATE DIST.	COUNTY		
TEXAS	CRP	NUECES		
CONT.	SECT.	JOB	HIGHWAY NO.	
0617	01	207	SH 358	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/23/2023  
FILE: p:\t\dot\projectwiseonline.com\TXDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\9. Environmental\ENVIRONMENTAL PERMITS, ISSUES, AND COMMITMENTS

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- 1.
- 2.  No Action Required  Required Action

Action No.

- 1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- 2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- 3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- 4. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 1.
- 2.
- 3.
- 4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input checked="" type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required  Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required  Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

- No Action Required  Required Action

Action No.

- 1.
- 2.
- 3.
- 4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes  No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes  No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required  Required Action

Action No.

- 1.
- 2.
- 3.

**VII. OTHER ENVIRONMENTAL ISSUES**


(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required  Required Action

Action No.

- 1.
- 2.
- 3.

SHEET 1 OF 2

		<b>Design Division Standard</b>	
<b>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</b> <b>EPIC</b>			
FILE: epic.dgn	DN: TxDOT	CR: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (DS) REVISIONS	0617	01	207
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	CRP	NUECES	91



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
 FILE:

**Amphibians**

a. Be advised of the potential occurrence of the black-spotted newt in the project area. This species prefers warm shallow watered areas with vegetative cover such as arroyos, canals, ditches, or even shallow depressions. During dry seasons, the newt lays dormant underground. Ensure that SW3P and 401 BMPs are implemented and maintained during construction. Avoid harming this species if encountered.

b. Be advised of the potential occurrence of sheep frog in the project area. This species prefers subterranean burrows, such as those of pack rats. They will also burrow under fallen tree limbs. Although this species will remain in its burrow for most of the year, they may emerge with heavy rains in the late summer season. Breeding takes place in August and September. Ensure that SW3P and 401 BMPs are implemented and maintained during construction. Avoid harming this species if encountered.

c. Be advised of the potential occurrence of South Texas siren in the project area. This species usually burrows in mud within marshes and streams. It will occasionally venture onto dry land. The South Texas siren has a characteristic eel-like body with a large head and small lidless eyes. This amphibian has an olive to dark gray or brown coloration with small black spots on the top of its body with light colored spots on the underside of its body. The siren has two reduced limbs behind a large set of external gills. Ensure that SWPPP and 401 BMPs are implemented and maintained during construction. Avoid harming this species if encountered.

d. Minimize impacts to wetland, temporary and permanent open water features, including depressions, and riverine habitats. Maintain hydrologic regime and connections between wetlands and other aquatic features. Use barrier fencing to direct animal movements away from construction activities and areas of potential wildlife-vehicle collisions in construction areas directly adjacent, or that may directly impact, potential habitat for the target species.

e. Consider applying hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas where feasible. If hydromulching and/or hydroseeding are not feasible due to site conditions, using erosion control blankets or mats that contain no netting, or only contain loosely woven natural fiber netting is preferred. Plastic netting should be avoided to the extent practicable.

f. Project Specific Locations (PSLs) proposed within state-owned ROW should be located in uplands away from aquatic features. When work is directly adjacent to the water, minimize impacts to shoreline basking sites (e.g., downed trees, sand bars, exposed bedrock) and overwinter sites (e.g., brush and debris piles, crawfish burrows), where feasible. Avoid or minimize disturbing or removing downed trees, rotting stumps, and leaf litter, which may be refugia for terrestrial amphibians, where feasible.

**Birds**

g. The Federal Migratory Bird Treaty Act (MBTA) states that it is unlawful to pursue, hunt, take, kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit. This project does not have a federal permit; therefore, in accordance with this regulation, the Contractor will avoid disturbing, destroying, removing, or relocating migratory birds and active nests found in trees, culverts, bridges, on the ground, etc. Typical breeding season occurs from March through August; therefore, tree trimming and other vegetation clearing activities that may disturb breeding birds should be done in the non-breeding season (September-February), when possible. If work must be performed during the breeding season, the Contractor shall have a qualified biologist conduct a survey of the right of way to determine if bird nests are present. In the event that active nests are encountered on-site during construction, the Contractor shall notify the Engineer and measures shall be taken to avoid disturbance of these birds, their occupied nest, eggs, and/or young, in accordance with the MBTA. Phasing of work during construction may be necessary to stay in compliance with the MBTA. The Contractor can discuss other preventative measures with the Project Engineer and/or District Environmental Staff.

**Mammals**

h. Be advised of the potential occurrence of white-nosed coati (Coatimundis) in the project area. This species prefers wooded areas near creeks. The species spends most of its day searching for food. Sleeps and raises young in crudely made nests in the treetops. It becomes more active during the mating season, January-March. Avoid unnecessary impacts to dens if encountered. Avoid harming this species if encountered.


**Water Quality**

i. Minimize the use of equipment in streams and riparian areas during construction. When possible, equipment access should be from banks, bridge decks, or barges.

j. When temporary stream crossings are unavoidable, remove stream crossing once they are no longer needed and stabilize banks and soil around the crossings.

**Other**


k. Do not attempt to handle or catch any of these species. Report all sightings and/or impacts to the TxDOT-Corpus Christ District Environmental Section.

 Texas Department of Transportation		Design Division Standard		
<b>ENVIRONMENTAL PERMITS,          ISSUES AND COMMITMENTS          EPIC</b>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
© TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12-12-2011 (DS) REVISIONS	0617	01	207	SH 358
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	CRP	NUECES		92




**DISCLAIMER**  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


LEVELS DISPLAYED	
1	2
3	4
5	6
7	8
9	10
11	12
13	14
15	16
17	18
19	20
21	22
23	24
25	26
27	28
29	30
31	32
33	34
35	36
37	38
39	40
41	42
43	44
45	46
47	48
49	50
51	52




**AT CULVERT ENDS**  
NTS




**AT BRIDGE MEDIAN**  
NTS




**AT DROP INLETS**  
NTS




**LAP DETAIL**  
NTS



**EROSION CONTROL LOG ELEVATION**  
NTS



**REBAR STAKE DETAIL**  
NTS



**AT MEDIAN DRAINS**  
NTS

**LEGEND**

	DISTURBED AREA
	EXISTING VEGETATION

© 2008 by Texas Department of Transportation  
 All rights reserved

**Texas Department of Transportation**


**BIODEGRADABLE EROSION CONTROL LOGS**

**CRP-BECL**


**CORPUS CHRISTI DISTRICT STANDARD** SHEET 2 OF 2

FILE: crp-becl.dgn	DN: TxDOT	CK: CAF	CK: PWS	STD:
ORIG DATE: MAY 2008	DIST: CRP	FED REG: 6	FEDERAL AID PROJECT: NH 1902 (108)	SHEET: 94
REVISIONS		COUNTY: NUECES	CONTROL SECT: 0617	JOB: 01
		HIGHWAY: 207	SH: 358	

DATE: 3/16/2023  
 FILE: p:\t\dot\projectwiseonline.com\TxDOT4\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\13. Standards\Environmental Standards\ec916.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PLAN VIEW




SECTION A-A  
EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B  
EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW



SECTION C-C


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
  - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
  - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
  - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
  - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
  - CL-DI EROSION CONTROL LOG AT DROP INLET
  - CL-CI EROSION CONTROL LOG AT CURB INLET
  - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

**SEDIMENT BASIN & TRAP USAGE GUIDELINES**

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

**Log Traps:** The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

**GENERAL NOTES:**


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		Design Division Standard	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0617	01	207
	DIST	COUNTY	SHEET NO.
	CRP	NUECES	95


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023  
 FILE: pw://txdot.projectwiseonline.com/TxDOT4/Documents/16 - CRP/Design Projects/061701207/4 - Design/Plan Set/13. Standards/Environmental Standards/ec916.dgn



**EROSION CONTROL LOGS ON SLOPES  
 STAKE AND TRENCHING ANCHORING**


CL-SST



**END SECTION RAP DETAIL**


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

\* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:  
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;  
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART





**EROSION CONTROL LOGS ON SLOPES  
 STAKE AND LASHING ANCHORING**

CL-SSL




**STAKE AND TRENCHING ANCHORING DETAIL**

CL-SST




**STAKE AND LASHING ANCHORING DETAIL**

CL-SSL



LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

**TRENCH DEPTH TABLE**




**STAKE NOTCH DETAIL**

SHEET 2 OF 3

		Design Division Standard	
<b>TEMPORARY EROSION,          SEDIMENT AND WATER          POLLUTION CONTROL MEASURES          EROSION CONTROL LOG          EC (9) - 16</b>			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0617	01	207
DIST	COUNTY	SHEET NO.	
CRP	NUECES	96	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/16/2023  
 FILE: p:\t\projectwise\online.com\txdot\Documents\16 - CRP\Design Projects\061701207\4 - Design\Plan Set\13. Standards\Environmental Standards\ec916.dgn




**EROSION CONTROL LOG AT DROP INLET**

CL-DI



**EROSION CONTROL LOG AT CURB INLET**


CL-CI



**EROSION CONTROL LOG AT CURB INLET**


CL-CI

NOTE:  
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



**EROSION CONTROL LOG AT CURB & GRADE INLET**

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0617	01	207
DIST	COUNTY	SHEET NO.	
CRP	NUECES	<b>97</b>	