

FINAL PLANS

NAME OF CONTRACTOR: \_\_\_\_\_  
 DATE OF LETTING: \_\_\_\_\_  
 DATE WORK BEGAN: \_\_\_\_\_  
 DATE WORK COMPLETED: \_\_\_\_\_  
 DATE WORK ACCEPTED: \_\_\_\_\_  
 SUMMARY OF CHANGE ORDERS:

# STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

## PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO.: F 2B23(174)

### FM 731 TARRANT COUNTY

LIMITS: FROM: SOUTH HAMPTON RD. TO: DEER CREEK DR.  
 LENGTH OF PROJECT = 1800.00 FT = 0.341 MI  
 FOR THE CONSTRUCTION OF LANDSCAPE & SCENIC ENHANCEMENT  
 CONSISTING OF PLANTING & IRRIGATION IMPROVEMENTS


DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS	6	F 2B23(174)		FM 731
CHECK	STATE	DISTRICT	COUNTY	001
CHECK	TEXAS	FTW	TARRANT	
CHECK	CONTROL	SECTION	JOB	
	1094	02	017	

DESIGN SPEED = 40 MPH  
 #02-Crowley-LMA-0001

END PROJECT  
 FM 731 STA 18+00  
 CSJ: 1094-02-017  
 TRM: 280+1.073

TARRANT COUNTY  
 FORT WORTH DISTRICT

BEGIN PROJECT  
 FM 731 STA 00+00  
 CSJ: 1094-02-017  
 TRM: 280+1.358



EXCEPTIONS: NONE  
 EQUATIONS: NONE  
 RAILROADS: NONE

**Pacheco Koch** a Westwood company  
 4060 BRYANT IRVIN RD. ■ FORT WORTH, TX 76109 ■ 817.412.7155  
 TX REG. ENGINEERING FIRM F-469  
 TX REG. SURVEYING FIRM LS-10008001

SUBMITTED FOR LETTING: 08/02/2023  
 \_\_\_\_\_, R.L.A.  
 CONSULTANT DESIGN ENGINEER OR PROJECT MANAGER

NOTE:  
 SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014, AND THE CONTRACT PROVISIONS LISTED AND DATED AS FOLLOWS SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 5, 2022)

**Pacheco Koch** a Westwood company  
 4060 BRYANT IRVIN RD. ■ FORT WORTH, TX 76109 ■ 817.412.7155  
 TX REG. ENGINEERING FIRM F-469  
 TX REG. SURVEYING FIRM LS-10008001

WORK WAS COMPLETED ACCORDING TO THE PLANS AND CONTRACT.

Final Plans Only \_\_\_\_\_, P.E.  
 Signature of Registrant & Date

© 2023 by Texas Department of Transportation; all rights reserved



CONCURRENCE FOR LETTING: 4/21/2023  
 \_\_\_\_\_, P.E.  
 CITY OF CROWLEY

RECOMMENDED FOR LETTING: 5/17/2023  
 \_\_\_\_\_, P.E.  
 DIRECTOR OF TP&D

SUBMITTED FOR LETTING: 5/15/2023  
 \_\_\_\_\_, P.E.  
 AREA ENGINEER

APPROVED FOR LETTING: 5/17/2023  
 \_\_\_\_\_, P.E.  
 DISTRICT ENGINEER

INDEX OF SHEETS

SHEET NO.    DESCRIPTION

I. GENERAL

001    TITLE SHEET  
 002    INDEX OF SHEETS  
 003    GENERAL LAYOUT OVERVIEW  
 004,4A-4C    GENERAL NOTES  
 005    ESTIMATES AND QUANTITIES  
 006    QUANTITY SUMMARY

II. BARRICADE AND TRAFFIC CONTROL PLAN STANDARDS

007    \* BC (1)-21  
 008    \* BC (2)-21  
 009    \* BC (3)-21  
 010    \* BC (4)-21  
 011    \* BC (5)-21  
 012    \* BC (7)-21  
 013    \* BC (8)-21  
 014    \* BC (9)-21  
 015    \* BC (10)-21  
 016    \* BC (11)-21  
 017    \* BC (12)-21  
 018    \* TCP (1-4)-18  
 019    \* TCP (1-5)-18  
 020    \* TCP (2-4)-18  
 021    \* TCP (2-5)-18  
 022    \* TCP (2-6)-18

SHEET NO.    DESCRIPTION

III. ENVIRONMENTAL ISSUES STANDARDS

023    EPIC  
 024    SW3P  
 025    SW3P  
 026    \* CURB INLET PROTECTION

IV. MISCELLANEOUS ITEMS

027 -028    EROSION CONTROL PLAN  
 029 -032    PLANTING PLAN  
 033    PLANT DETAILS  
 034 -037    IRRIGATION PLAN  
 038    IRRIGATION DETAILS


THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS PAGE (\*) HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

*Mark C. Schluter*  
 MARK SCHLUTER, P.E.

06/28/2023

DATE



WFRIEDER  
 06/28/2023 - 8:38AM  
 M:\DWG-36\36986-22.645\DWG\LANDSCAPE\FX 2018\SHEETS\TITLE SHEET.DWG



INDEX OF SHEETS

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	002	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO.
1094	02	017	FM 731

APRIL 2023 1 95% PLAN SET



OPENING DATE: 03/17/2023 - 2:23PM  
M:\DWG-36\3666-22\645\DWG\LANDSCAPE.FX 2018\SHEETS\TITLE SHEET.DWG

**INTERIM REVIEW**  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
BENJAMIN J. WINTER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-10008001  
4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155



### GENERAL LAYOUT OVERVIEW

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	003	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO
1094	02	017	FM 731

MARCH 2023 - 90% PLAN SET

Project Number: F 2B23(174)

County: TARRANT

Control: 1094-02-017

Highway: FM 731

**Special Notes**

Electronic files containing answered pre-letting questions and other project related design information will be placed in the following FTP site periodically.

Check this site for new information. Notices of new postings will not be sent out by the Engineer.

The data located in these files is for non-construction purposes only and can be found at

TxDOT's public FTP site at <https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>.

Access is read-only.

All files in the FTP site are subject to the License Agreement shown on the FTP site.

To obtain a copy of the project plans free of charge, submit a request from the following site: <http://www.txdot.gov/business/letting-bids/plans-online.html>

Contractor questions on this project are to be addressed to the following individual(s):

Area Engineer's Email: [David.Neeley@txdot.gov](mailto:David.Neeley@txdot.gov)  
Area Engineer's Email: [Maribel.Rangel@txdot.gov](mailto:Maribel.Rangel@txdot.gov)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: <https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20 Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Single lane closures, except as otherwise shown in the plans, will be restricted to off-peak hours as defined in the following table:

Project Number: F 2B23(174)

County: TARRANT

Control: 1094-02-017

Highway: FM 731

Peak Hours		Off-Peak Hours	
6 to 9 AM Monday through Friday	3 to 7 PM Monday through Friday	9 AM to 3 PM and 7 PM to 6 AM Monday through Friday	All day Saturday and Sunday

Work that requires closure of multiple travel lanes in the same direction, except as otherwise shown in the plans, are restricted to night hours between 9 PM and 6 AM.

Existing storm sewers and utilities are shown from the best available information. Verify the location of all underground facilities prior to starting work.

For dimensions of right-of-way not shown on the plans, see right-of-way map on file at the TxDOT District Office.

Provide temporary drain opening at all low points or other drainage structures, as required, at the contractor's expense.

Remove any obstructions to existing drainage due to the contractors' operations, as required, at the contractor's expense.

**Modifications to Lane Closure / Work Restrictions:**

Submit a request in writing for approval by the Engineer a minimum of 10 days in advance of implementing a change to lane closure restrictions.

When deemed necessary, the Engineer will lengthen, shorten, or otherwise modify lane closure restrictions as traffic conditions warrant.

Special Events/ Special Situations will be handled on a case-by-case basis. No work restricting lane closures is allowed from 3 PM a day before to 9 AM the day after the Special Event or Special Situation.

**Item 2. Instructions to Bidders**

Mailbox manipulation made necessary because of construction will be in accordance with Item 560 "Mailbox Assemblies," except that this work will not be paid for directly but will subsidiary to the pertinent bid items.

Proposals with a bid of more than 60 working days for the substantial completion of the project will be considered non-responsive.

**Project Number:** F 2B23(174)

**County:** TARRANT

**Control:** 1094-02-017

**Highway:** FM 731

**Item 4 – Scope of Work**

Reimbursement for project overhead will not be considered until project completion has extended beyond the original Contract Time.

**Item 6. Control of Materials**

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

**Item 5. Control of the Work**

When supplementary shop drawings, shop details, erection drawings, working drawings, forming plans, or other drawings are required, prepare and submit drawings on sheets 8-1/2 by 11 inches, 17 by 22 inches, or full size drawings reduced to half scale if completely legible. If, in the opinion of the Engineer, the drawings are not completely legible, prepare and submit on sheets 22 by 34 inches, with a 1-1/2 inch left margin, and 1/2 inch top, right, and bottom margins.

Submit all sheets with a title in the lower right hand corner. The title must include the sheet index data shown on the lower right corner of the project plans, name of the structure or element or stream, sheet numbering for the shop drawings, name of the fabricator and the name of the Contractor.

Standard Operating Procedure for Alternate Precast Proposal Submission” found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

**Item 7. Legal Relations and Responsibilities**

**Project Number:** F 2B23(174)

**County:** TARRANT

**Control:** 1094-02-017

**Highway:** FM 731

The total area disturbed for this project is 1.30 acres. The disturbed area in this project, all project locations in the Contract, and the Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the right of way. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the right of way to the Engineer and to the local government that operates a separate storm sewer system.

Prevention of Migratory Bird Nesting

It is anticipated that migratory birds, a protected group of species, may try to nest on bridges, culverts, vegetation, or gravel substrate, at any time of the year. The preferred nesting season for migratory birds is from February 15 through October 1. When practicable, schedule construction operations outside of the preferred nesting season. Otherwise, avoid nests containing migratory birds and perform no work in the nesting areas until the young birds have fledged.

No extension of time or compensation payment will be granted for a delay or suspension of work caused by nesting swallows. This work is subsidiary to the various bid items.

The following Holiday/Event lane closure restriction requirements apply to this project: No work that restricts or interferes with traffic shall be allowed between 3 PM on the day preceding a Holiday or Event and 9 AM on the day after the Holiday or Event.

<b>Holiday Lane Closure Restrictions</b>	
<b>New Year’s Eve and New Year’s Day</b> (December 31 through January 1)	3 PM December 30 through 9 AM January 2
<b>Easter Holiday Weekend</b> (Friday through Sunday)	3PM Thursday through 9 AM Monday
<b>Memorial Day Weekend</b> (Friday through Monday)	3 PM Thursday through 9 AM Tuesday
<b>Independence Day</b> (July 3 through July 5)	3 PM July 2 through 9 AM July 6
<b>Labor Day Weekend</b> (Friday through Monday)	3 PM Thursday through 9 AM Tuesday
<b>Thanksgiving Holiday</b> (Wednesday through Sunday)	3 PM Tuesday through 9 AM Monday
<b>Christmas Holiday</b> (December 23 through	3 PM December 22 through 9 AM December

**Project Number:** F 2B23(174)

**County:** TARRANT

**Control:** 1094-02-017

**Highway:** FM 731

December 26)	27
--------------	----

Plan work schedules around the appropriate dates above to ensure productive work is performed without lane closures.

**Item 8. Prosecution and Progress**

Working days will be computed and charged in accordance with Section 8.3.1.1, 'Five-Day Workweek.'

Construction will begin 90 days after authorization in accordance to Special provision (SP008-003), due to Item 180-6001 "Wildflower seeding" being planted in spring.

**Item 100. Preparing Right of Way**

Work under this item to include, weed removal and continued maintenance in all existing medians work area and the following:

Mow all existing vegetation in the work area to a height of no more than 6". One to two weeks following this mowing, apply general non-selective herbicide to all vegetation within the work area per manufacturer's recommendations. When vegetation has died, drag or otherwise strip and remove the dead surface vegetation without removing topsoils in place. Following dead vegetation removal, wait a minimum of two weeks, then re-apply non-selective herbicide to all new vegetation. Following visible die off, work may begin in the area to be improved per the plans.

**Item 161. Compost**

Place approximately 4" of compost manufactured topsoil (CMT) in areas indicated, then till into a minimum of 6" existing soil to create a 10" minimum profile.

Salvage suitable topsoil from areas shown on plans. Maximum salvage depth is 4-in. Place approximately 4 inches of topsoil on areas shown to compost if existing soil is not suitable for 10" minimum profile.

Where "blended on-site" CMT is specified, produce the compost manufactured topsoil by incorporating 4" of compost with 6" of furnished topsoil as shown on the plans.

**Project Number:** F 2B23(174)

**County:** TARRANT

**Control:** 1094-02-017

**Highway:** FM 731

**Item 170. Irrigation System**

Contact Matt Elgin @ 817-297-2201 with the City of Crowley for installation of the water meter for the project. The Contractor is to pay for the installation & fees. Irrigation system under this pay item is defined as the total system from the outlet of the water meter. The contractor is to pay for the installation of the water meter & associated fees. City of Crowley fees will be waived, but impact fees for the City of Fort Worth are subsidiary to this item.

**Item 192. Landscape Planting**

No planting shall occur between June 1st and September 15th without written approval from the Landscape Architect. Per special provision 192.001 plant material requiring replacement will be at the cost of the contractor.

All plant material to be full and matching per species.

**Item 502. Barricades, Signs, and Traffic Handling**

The contractor force account 'safety contingency' that has been established for this project is intended to be utilized for work zone enhancements to improve the effectiveness of the traffic control plan that could typically not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's responsible person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Permanent signs may be installed when construction in an area is complete, and they will not conflict with the traffic control plan for the remainder of the job.

Existing signs are to remain as long as they do not interfere with construction, and they do not conflict with the traffic control plan.

Any sign not detailed in the plans but called for in the layout will be as shown in the current "Standard Highway Sign Designs for Texas".

When traffic is obstructed, arrange warning devices in accordance with the latest edition of the "Texas Manual on Uniform Traffic Control Devices".

Cover or remove any work zone signs when work or condition referenced is not occurring.

Do not place barricades, signs, or any other traffic control devices where they interfere with sight distance at driveways or side streets. Provide access to all driveways during all phases of construction unless otherwise noted in the plans or as directed.

**Project Number:** F 2B23(174)

**County:** TARRANT

**Control:** 1094-02-017

**Highway:** FM 731

**Item 506. Temporary Erosion, Sedimentation, and Environmental Controls**

The SW3P for this project will consist of using the following items as directed:

- 7012 Curb Inlet Sediment Protection

Remove accumulated sediment or replace SW3P controls when the capacity has been reduced by 50% or when the depth of sediment at the control structure exceeds one foot. Install and removal is subsidiary to this bid item.

**Item 6001. Portable Changeable Message Signs**

Provide all portable changeable message signs and arrow panels with a photoelectric device to allow for automatic dimming of operations to approximately 50% of their normal brightness when ambient light drops to approximately five footcandles, and then increase back again for daytime operations.

(2) electronic portable changeable message sign unit(s) will be required. Individual or collective use of signs will be required by the Engineer when deemed necessary to supplement the traffic control plan.

Each sign must have programmed in its permanent memory the following 15 messages:

1. Exit Closed Ahead
2. Use Other Routes
3. Right Lane
4. Left Lane
5. Closed Ahead
6. Two Lane
7. Detour Ahead
8. Thru Traffic
9. Prepare To Stop
10. Merging Traffic
11. Expect 15 Minute Delay
12. Max Speed \*\* MPH
13. Merge Right
14. Merge Left
15. No Exit Next \*\* Miles

**Item 1005. Loose Aggr for Groundcover**

Geotextile fabric is subsidiary to this item.



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 1094-02-017

DISTRICT Fort Worth  
HIGHWAY FM 731

COUNTY Tarrant

CONTROL SECTION JOB				1094-02-017		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00194941			
COUNTY				Tarrant			
HIGHWAY				FM 731			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6001	PREPARING ROW	AC	1.300		1.300	
	161-6008	EROSION CONTROL COMPOST (2")	SY	3,192.000		3,192.000	
	161-6022	GENERAL USE COMPOST (4")	SY	1,868.000		1,868.000	
	170-6001	IRRIGATION SYSTEM	LS	1.000		1.000	
	180-6001	WILDFLOWER SEEDING	AC	0.660		0.660	
	192-6003	PLANT MATERIAL (3-GAL)	EA	1,465.000		1,465.000	
	192-6004	PLANT MATERIAL (5-GAL)	EA	131.000		131.000	
	192-6013	MULCH	SY	1,289.000		1,289.000	
	192-6025	PLANT MATERIAL (45 GAL) (TREE)	EA	21.000		21.000	
	192-6026	PLANT MATERIAL (65 GAL) (TREE)	EA	23.000		23.000	
	192-6097	CONC LNDSCP EDG (12 IN WIDTH)	LF	1,902.000		1,902.000	
	193-6001	PLANT MAINTENANCE	MO	9.000		9.000	
	193-6014	IRRIG SYS OPER AND MAINT (SCH A)	MO	9.000		9.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	3.000		3.000	
	618-6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	114.000		114.000	
	618-6034	CONDT (PVC) (SCH 40) (4") (BORE)	LF	114.000		114.000	
	1005-6001	LOOSE AGGR FOR GROUNDCOVER (TYPE I)	CY	78.000		78.000	
	1005-6002	LOOSE AGGR FOR GROUNDCOVER (TYPE II)	CY	85.000		85.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	60.000		60.000	
	7012-6001	CURB INLET SEDIMENT PROTECTION	LF	236.000		236.000	
18		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	



SUMMARY OF ITEMS				
LOCATION	100-6001	500-6001	502-6001	6001-6001
	PREPARING ROW	MOBILIZATION	BARRICADES, SIGNS AND TRAFFIC HANDLING	PORTABLE CHANGEABLE MESSAGE SIGN
	AC	LS	MO	DAY
GENERAL	1.3	1	3	60

SUMMARY OF ITEMS	
LOCATION	7012-6001
	CURB INLET SEDIMENT PROTECTION
	LF
EROSION CONTROL PLAN (1 OF 1)	119
EROSION CONTROL PLAN (1 OF 2)	117
<b>TOTAL</b>	<b>236</b>

SUMMARY OF ITEMS												
LOCATION	161-6022	161-6008	180-6001	192-6003	192-6004	192-6013	192-6025	192-6026	192-6028	193-6001	1005-6001	1005-6002
	GENERAL USE COMPOST (4")	EROSION CONTROL COMPOST (2")	WILDFLOWER SEEDING (NATIVE SUN TURF)	LANDSCAPE PLANTING (3 GAL)	LANDSCAPE PLANTING (5 GAL)	LANDSCAPE PLANTING (MULCH) (BARK)	PLANT MATERIAL (45 GAL) (TREE)	PLANT MATERIAL (65 GAL) (TREE)	CONCRETE LANDSCAPE EDGE (12" WIDTH)	PLANT MAINTENANCE	LOOSE AGGR FOR GROUND COVER (TYP 1)	LOOSE AGGR FOR GROUND COVER (TYP 11)
	SY	SY	AC	EA	EA	SY	EA	EA	LF	MO	CY	CY
PLANTING (1 OF 4)	627	742	0.15	486	59	393	6	5	591		16	36
PLANTING (2 OF 4)	450	1,455	0.29	335	36	279	5	8	714		15	22
PLANTING (3 OF 4)	580	721	0.16	501		497	5	8	339		27	17
PLANTING (4 OF 4)	211	274	0.06	143	36	120	5	2	258		20	10
<b>TOTAL</b>	<b>1,868</b>	<b>3,192</b>	<b>0.66</b>	<b>1,465</b>	<b>131</b>	<b>1,289</b>	<b>21</b>	<b>23</b>	<b>1,902</b>	<b>9</b>	<b>78</b>	<b>85</b>

SUMMARY OF ITEMS				
LOCATION	170-6001	193-6007	618-6024	618-6034
	IRRIGATION SYSTEM	IRRIG SYS OPER AND MAINT	COND (PVC) (SCH 40) (2") (BORE)	COND (PVC) (SCH 40) (4") (BORE)
	LS	MO	LF	LF
IRRIGATION (1 OF 4)				
IRRIGATION (2 OF 4)				
IRRIGATION (3 OF 4)				
IRRIGATION (4 OF 4)			114	114
<b>TOTAL</b>	<b>1</b>	<b>9</b>	<b>114</b>	<b>114</b>

**INTERIM REVIEW**  
 THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
 REGISTERED LANDSCAPE ARCHITECT  
 SENGUPTA J. BHIMBEN  
 TEXAS REGISTRATION NUMBER 3159



## QUANTITY SUMMARY

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	006	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO
1094	02	017	FM 731

D:\BENTLEY\BENTLEY\DWG\LANDSCAPE\FX 2018\SHEETS\TITLE SHEET.DWG  
 M:\DWG-36\3666-22\645\DWG\LANDSCAPE\FX 2018\SHEETS\TITLE SHEET.DWG  
 1:32PM

APRIL 2023 - 95% PLAN SET

DISCLAIMER: Use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
 FILE:

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<p><b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b>  <a href="http://www.txdot.gov">http://www.txdot.gov</a></p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard		
<p><b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b></p> <p><b>BC (1) -21</b></p>				
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
4-03 7-13	1094	02	XXX	FM 731
9-07 8-14	DIST	COUNTY		SHEET NO.
5-10 5-21	FTW	TARRANT		007


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "X" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW23			40	240
CW25			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14			50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - \*\* CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
— —	Type 3 Barricade
○ ○ ○	Channelizing Devices
—	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-21**

FILE: bc-21.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT SECT	JOB	HIGHWAY	
REVISIONS	1094 02	XXX	FM 731	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	FTW	TARRANT	008	


DATE: FILE:

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project.

Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

### GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
  - 40 mph and greater 0.2 to 2 miles
  - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - A. Law enforcement.
  - B. Flagger stationed next to sign.
  - C. Portable changeable message sign (PCMS).
  - D. Low-power (drone) radar transmitter.
  - E. Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:  
FILE:

SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC(3)-21</h3>			
FILE:	bc-21.dgn	DN:	TxDOT
CONT:	November 2002	CK:	TxDOT
REVISIONS:		DW:	TxDOT
9-07	8-14	1094	02
7-13	5-21	XXX	FM 731
		DIST:	COUNTY
		FTW:	TARRANT
			SHEET NO. 009

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

- All sign letters and numbers shall be clear, and standard rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectized when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12

Traffic Safety Division Standard



**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) -21**


FILE: bc-21.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT SECT	JOB	HIGHWAY	
REVISIONS		1094 02	XXX	FM 731
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	FTW	TARRANT	010	

DATE: FILE:

DISCLAIMER: Use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





**SKID MOUNTED WOOD SIGN SUPPORTS**  
 \* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support.  
 The maximum sign square footage shall adhere to the manufacturer's recommendation.  
 Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**  
 \* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

**WEDGE ANCHORS**

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

**GENERAL NOTES**

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."
  - \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION  
 TYPICAL SIGN SUPPORT**


**BC(5)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1094	02	XXX	FM 731
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	FTW	TARRANT	011	


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**




**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**  
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

**LOW PROFILE CONCRETE BARRIER (LPCB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.

See D & OM (VIA)



Install a minimum of 3 Barrier Reflectors as per manufacturer's recommendations.


**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**

- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC(7)-21**

FILE:	bc-21.dgn	DATE:	TxDOT	DATE:	TxDOT	DATE:	TxDOT	DATE:	TxDOT
REVISED:	November 2002	CONT:	SECT	JOB:	XXX	HIGHWAY:	FM 731		
REVISED:	1094	REVISED:	02	REVISED:	XXX	REVISED:	FM 731		
DATE:	9-07	DATE:	8-14	DATE:	7-13	DATE:	5-21		
DIST:	FTW	COUNTY:	TARRANT	SHEET NO.:	012				

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelizing devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**



- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12

		Traffic Safety Division Standard	
<b>BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES</b>			
<b>BC (8) -21</b>			
FILE:	bc-21.dgn	DN:	TxDOT
REV:	November 2002	CR:	TxDOT
COM:	1094	SECT:	02
JOB:	XXX	HWY:	FM 731
DIST:	FTW	COUNTY:	TARRANT
SHEET NO.:	013		




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



**CHEVRONS**

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\*\*Taper lengths have been rounded off.  
L=Length of Taper (FT.) W=Width of Offset (FT.)  
S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©	TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY			
		REVISIONS	1094	02	XXX	FM 731			
9-07	8-14		DIST	COUNTY		SHEET NO.			
7-13	5-21		FTW	TARRANT		014			


DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined in BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(10)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1094	02	XXX	FM 731
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	FTW	TARRANT	015	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ (STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ (STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242





A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12

<span style="font-size: small; vertical-align: middle;">           Texas Department of Transportation            Traffic Safety Division Standard         </span>																														
BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS																														
BC(11) - 21																														
<table border="0" style="width: 100%;"> <tr> <td>FILE: bc-21.dgn</td> <td>DN: TxDOT</td> <td>CK: TxDOT</td> <td>DW: TxDOT</td> <td>CK: TxDOT</td> </tr> <tr> <td>© TxDOT February 1998</td> <td>CONT SECT</td> <td>JOB</td> <td colspan="2">HIGHWAY</td> </tr> <tr> <td>REVISIONS</td> <td>1094 02</td> <td>XXX</td> <td colspan="2">FM 731</td> </tr> <tr> <td>2-98 9-07 5-21</td> <td>DIST</td> <td>COUNTY</td> <td colspan="2">SHEET NO.</td> </tr> <tr> <td>1-02 7-13</td> <td>FTW</td> <td>TARRANT</td> <td colspan="2">016</td> </tr> <tr> <td>11-02 8-14</td> <td></td> <td></td> <td colspan="2"></td> </tr> </table>	FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	© TxDOT February 1998	CONT SECT	JOB	HIGHWAY		REVISIONS	1094 02	XXX	FM 731		2-98 9-07 5-21	DIST	COUNTY	SHEET NO.		1-02 7-13	FTW	TARRANT	016		11-02 8-14				
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT																										
© TxDOT February 1998	CONT SECT	JOB	HIGHWAY																											
REVISIONS	1094 02	XXX	FM 731																											
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.																											
1-02 7-13	FTW	TARRANT	016																											
11-02 8-14																														



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

## PAVEMENT MARKING PATTERNS





Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.

### CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS





Prefabricated markings may be substituted for reflectORIZED pavement markings.

### EDGE & LANE LINES FOR DIVIDED HIGHWAY



Prefabricated markings may be substituted for reflectORIZED pavement markings.







### LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



Prefabricated markings may be substituted for reflectORIZED pavement markings.

### TWO-WAY LEFT TURN LANE

## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS


### BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	1094	02	XXX	FM 731
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	FTW	TARRANT	017	
11-02 8-14				

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (1-4a)

**ONE LANE CLOSED**



TCP (1-4b)

**TWO LANES CLOSED**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

**GENERAL NOTES**

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

**TCP (1-4a)**

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

**TCP (1-4b)**

- Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

**Texas Department of Transportation**  
Traffic Operations Division Standard




**TRAFFIC CONTROL PLAN  
 LANE CLOSURES ON MULTILANE  
 CONVENTIONAL ROADS**

**TCP (1-4) - 18**

FILE: tcp1-4-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	1094	02	XXX	FM 731
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	FTW	TARRANT	018	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = WS <sup>2</sup> / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
  - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

**Texas Department of Transportation**  
 Traffic Operations Division Standard



**TRAFFIC CONTROL PLAN  
 LANE CLOSURES FOR  
 DIVIDED HIGHWAYS**

**TCP (1-5) - 18**

FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	1094 02	XXX	FM 731
	DIST	COUNTY	SHEET NO.	
	FTW	TARRANT	019	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = $\frac{WS^2}{60}$	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = $\frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40	L = WS	265'	295'	320'	40'	80'	240'	155'
45		450'	495'	540'	45'	90'	320'	195'
50	L = WS	500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60	L = WS	600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	L = WS	700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
  - For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-4a)**
- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.
- TCP (2-4b)**
- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.

**Texas Department of Transportation**  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**LANE CLOSURES ON MULTILANE**  
**CONVENTIONAL ROADS**



**TCP (2-4) - 18**

FILE: tcp2-4-18.dgn	DW:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	1094	02	XXX	FM 731
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	FTW	TARRANT	020	
4-98 2-18				

164

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.
  - The downstream taper is optional. When used, it should be 100 feet approximately per lane, with channelizing devices spaced at 20 feet.

- TCP (2-5a)**
- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic, with the arrow board placed in the closed lane near the end of the merging taper.
- TCP (2-5b)**
- Conflicting pavement markings shall be removed for long-term projects.

**Texas Department of Transportation**  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
 LONG TERM LANE CLOSURES  
 MULTILANE CONVENTIONAL RDS.**




**TCP (2-5) - 18**

FILE: tcp2-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	COMT	SECT	JOB	HIGHWAY
8-95 2-12 REVISIONS	1094	02	XXX	FM 731
1-97 3-03	DIST	COUNTY	SHEET NO.	
4-98 2-18	FTW	TARRANT	021	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula	Minimum Desirable Taper Lengths * X			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
- The placement of pavement markings may be omitted on Intermediate-term stationary work zones with the approval of the Engineer.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.



**TRAFFIC CONTROL PLAN  
LANE CLOSURES ON  
DIVIDED HIGHWAYS**

**TCP (2-6) - 18**

FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	COMT	SECT	JOB	HIGHWAY
REVISIONS	1094	02	XXX	FM 731
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	FTW	TARRANT	022	
1-97 2-18				

I. STORMWATER POLLUTION PREVENTION—CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. CITY OF CROWLEY

2.

No Action Required  Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 – PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 – PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 
- 
- 
- 

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion

- Temporary Vegetation
- Blankets/Matting
- Mulch
- Sodding
- Interceptor Swale
- Diversion Dike
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks

Sedimentation

- Erosion Control Logs
- Rock Berm
- Triangular Filter Dike
- Sand Bag Berm
- Straw Bale Dike
- Brush Berms
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Stone Outlet Sediment Traps
- Sediment Basins

Post-Construction TSS

- Vegetative Filter Strips
- Retention/Irrigation Systems
- Extended Detention Basin
- Constructed Wetlands
- Wet Basin
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Vegetation Lined Ditches
- Sand Filter Systems
- Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required  Required Action

Action No.

1.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required  Required Action

Action No.

- Executive Order 13112 on Invasive Species and Environmentally and Economically Beneficial Practices on Federal Landscaped Grounds. No landscaping would be a part of the proposed project. Disturbed areas would be re-vegetated according to TxDOT5/32s standard practices for rural area, which to the extent practical, is in compliance with EO 13112 on Invasive Species and the Executive Memorandum on Beneficial Landscaping (04/26/94).
- Vegetation Disturbance. During construction, efforts would be taken to avoid and minimizing disturbance of vegetation and soils. Areas within the existing ROW, but outside the limits of construction, would not be disturbed. Every effort would be made to preserve trees where they would neither compromise safety nor substantially interfere with the proposed projects.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required  Required Action

Action No.

- Migratory Bird Treaty Act (MBTA). Between October 1 and February 15, the contractor would remove all old migratory bird nests from any structure that would be affected by the proposed project, and complete any bridge work/demolition and /or vegetation clearing. In addition, the contractor would be prepared to prevent migratory birds from building nests by utilizing nest prevention methods, such as bird-deterrent netting and bird-repelling sprays and/or gels, between February 15 and October 1. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young would be avoided.
- Bird BMP and Bald & Golden Eagle Protection Act. The contractor would be prepared to take appropriate measures to avoid disturbing, destroying, or removing active nests, including ground nesting birds, during the nesting season. Avoid the removal of unoccupied, inactive nests, as practicable. As necessary, take appropriate measures to prevent the establishment of active nests during the nesting season on facilities and structures proposed for replacement or repair. Collecting, capturing, relocation, or transporting birds, eggs, young, or active nests without a permit is prohibited. The Bald and Golden Eagle Protection Act prohibits the taking or possession of and commerce in eagles, parts, feathers, nests, or eggs with limited exceptions. The definition of take includes pursue, shoot, shoot at, poison, wound, kill, capture, trap, collect, molest or disturb. Eagles may not be taken for any purpose unless a permit is issued prior to the taking.
- Threatened and Endangered Species: Whooping Crane. The contractor and/or TxDOT personnel would be advised of potential for Whooping Cranes to occur within the project limits. Construction personnel will be advised to avoid adverse impacts to this species and to report any sightings to TxDOT District Environmental staff. Drainage modifications will be limited to the extent practical to accommodate the additional paved surface needed to bring the roadway up to current TxDOT safety standards. The construction personnel will report all sightings to TxDOT Fort Worth District Environmental staff. Reports should include the time, date and location and any available photos.

*If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.*

LIST OF ABBREVIATIONS

BMP: Best Management Practice  
 CGP: Construction General Permit  
 DSHS: Texas Department of State Health Services  
 FHWA: Federal Highway Administration  
 MOA: Memorandum of Agreement  
 MS4: Municipal Separate Stormwater Sewer System  
 MBTA: Migratory Bird Treaty Act  
 NOI: Notice of Intent

SPCC: Spill Prevention Control and Countermeasure  
 SW3P: Storm Water Pollution Prevention Plan  
 PCN: Pre-Construction Notification  
 TCEQ: Texas Commission on Environmental Quality  
 TPDES: Texas Pollutant Discharge Elimination System  
 TPWD: Texas Parks and Wildlife Department  
 T&E: Texas Department of Transportation  
 USACE: U.S. Army Corps of Engineers  
 USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes  No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes  No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required  Required Action

Action No.

- 
- 
- 

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)


No Action Required  Required Action

Action No.

1.

GENERAL NOTE:

Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities as additional environmental clearance may be required.

		<i>Design Division Standard</i>		
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS  EPIC				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY
12--12--2011 (DS) REVISIONS	1094	02	XXX	FM 731
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	FTW	TARRANT		023

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

https://www.dot.state.tx.us/ftw/specinfo/standard.htm  
 9/3/2019 5:50:13 PM  
 T:\CENTERS\District Hydraulics\Inlet Standards Update\100% website\roadway\sw3p-ftw.dgn

## A. GENERAL SITE DATA

- PROJECT LIMITS:** Highway: FM 731  
 From: S HAMPTON ROAD  
 To: DEER CREEK DRIVE  
 LATTITUDE: START: 32°33'29" N END: 32°33'38" N LONGITUDE: START: 97°21'28" W END: 97°21'13" W
- PROJECT SITE MAPS:**
  - Project Location Map: Title Sheet (Sheet I)
  - Drainage Patterns: Drainage Area Maps (027-028 EROSION CONTROL PLANS)
  - Approx. Slopes Anticipated After Major Graddings and Areas of Soil Disturbance: (N/A)
  - Major Controls and Locations of Stabilization Practices: (Sheets X-Y) SW3P Site Map Sheets
  - Project Specific Locations: To be specified by Project Field Office and located in the Project SW3P File
  - Surface Waters and Discharge Locations: Drainage and Culvert Layout Sheets (N/A)
- PROJECT DESCRIPTION:** FM 731 ROAD MEDIAN PLANTING AND IRRIGATION ENHANCEMENTS
- MAJOR SOIL DISTURBING ACTIVITIES:** TREE AND SHRUB PLANTING AND TRENCHING FOR IRRIGATION
- EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:** (Provide description of soil condition, vegetative cover and percentage)
- TOTAL PROJECT AREA:** 1.3 ACRES
- TOTAL AREA TO BE DISTURBED:** 1.3 ACRES (100% OF TOTAL PROJECT AREA)
- WEIGHTED RUNOFF COEFFICIENT**

BEFORE CONSTRUCTION:	0.33
AFTER CONSTRUCTION:	0.33
- NAME OF RECEIVING WATERS:** N/A
- ENDANGERED SPECIES, DESIGNATED CRITICAL HABITAT AND HISTORIC PROPERTY:** No Endangered Species, Designated Critical Habitat or Historic Property has been found on this project site.

The documentation satisfying TPDES Construction General Permit eligibility pertaining to the existence of or any protective action taken with regards to endangered species or designated critical habitat or historical property in this project area is contained in the project's Environmental document (EA or EIS) and can be viewed under the State Open Records Act at the address shown below:

TEXAS DEPARTMENT OF TRANSPORTATION  
 FORT WORTH DISTRICT HEADQUARTERS  
 DISTRICT DESIGN SECTION  
 2501 SW LOOP  
 FORT WORTH, TX 76133  
 PHONE: 817-370-6500

## B. EROSION AND SEDIMENT CONTROLS

- SOIL STABILIZATION PRACTICES:** (Select T = Temporary or P = Permanent, as applicable)
 

<input type="checkbox"/> TEMPORARY SEEDING	<input type="checkbox"/> PRESERVATION OF NATURAL RESOURCES
<input type="checkbox"/> MULCHING (Hay or Straw)	<input type="checkbox"/> FLEXIBLE CHANNEL LINER
<input type="checkbox"/> BUFFER ZONES	<input type="checkbox"/> RIGID CHANNEL LINER
<input type="checkbox"/> PLANTING	<input type="checkbox"/> SOIL RETENTION BLANKET
<input type="checkbox"/> SEEDING	<input type="checkbox"/> COMPOST MANUFACTURED TOPSOIL
<input type="checkbox"/> SODDING	<input type="checkbox"/> OTHER: (Specify Practice)
- STRUCTURAL PRACTICES:** (Select T = Temporary or P = Permanent, as applicable)
 

<input type="checkbox"/> SILT FENCES	<input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
<input type="checkbox"/> HAY BALES	<input type="checkbox"/> DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
<input type="checkbox"/> ROCK FILTER DAMS	<input type="checkbox"/> DIVERSION DIKE AND SWALE COMBINATIONS
<input type="checkbox"/> PIPE SLOPE DRAINS	<input type="checkbox"/> ROCK BEDDING AT CONSTRUCTION EXIT
<input type="checkbox"/> PAVED FLUMES	<input type="checkbox"/> TIMBER MATTING AT CONSTRUCTION EXIT
<input type="checkbox"/> CHANNEL LINERS	<input type="checkbox"/> STONE OUTLET STRUCTURES
<input type="checkbox"/> SEDIMENT TRAPS	<input type="checkbox"/> VELOCITY CONTROL DEVICES
<input type="checkbox"/> SEDIMENT BASINS	<input type="checkbox"/> CURBS AND GUTTERS
<input type="checkbox"/> STORM SEWERS	<input type="checkbox"/> STORM INLET SEDIMENT TRAP
<input type="checkbox"/> OTHER: (CURB INLET SEDIMENT PROTECTION)	
- STORM WATER MANAGEMENT:** (Example Below - May be used as applicable, revised or expanded)
  - Storm water drainage will be provided by the ditches, inlets and storm water systems that will carry drainage within the R.O.W. to the low points within the roadway and project site which drain to natural facilities.
  - Other permanent erosion controls include hydraulic design to limit structure outlet velocities and grading design generally consisting of 4:1 or flatter slopes with permanent vegetative cover.
- STORM WATER MANAGEMENT ACTIVITIES:** (Sequence of Construction) (Describe Storm Water Management Activities by Phases)
- NON-STORM WATER DISCHARGES:** Non-storm water discharges should be filtered, or held in retention basins, before being allowed to mix with storm water. These discharges consist of non-polluted ground water, spring water, foundation and/or footing drain water, and water used for dust control, pavement washing and vehicle washwater containing no detergents.

INTERIM REVIEW  
 THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL/PERMITTING, OR CONSTRUCTION.  
 REGISTERED LANDSCAPE ARCHITECT  
 DOROTHY J. WITMCKER  
 TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** 4060 BRYANT IRVIN ROAD  
 FORT WORTH, TX 76109 817.412.7155  
 TX REG. ENGINEERING FIRM F-469  
 TX REG. SURVEYING FIRM LS-10008001

**Texas Department of Transportation** Fort Worth District Standard

## STORM WATER POLLUTION PREVENTION PLAN (SW3P)

SHEET 1 OF 2 SHEETS

ORIGINAL DRAWING: 09/2002	sw3p-ftw.dgn	FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.
DATE	REVISIONS	6	SEE TITLE SHEET	024
09/2008	HPDES TO TPDES	STATE	STATE	COUNTY
01/2012	CLARIFY NOTE C. 2.	TEXAS	FTW	TARRANT
08/2013	ADDED SIGN	CONT.	SECT.	JOB
05/2019	2-SHEET FORMAT	1094	02	XXX
				HIGHWAY NO.
				FM 731

https://www.dot.state.tx.us/ftw/spec/info/standard.htm  
 9/3/2019 5:51:02 PM  
 T:\CENTRES\District Hydraulics\Inlet Standards Update\100% website\roadway\sw3p-ftw.dgn

## C. OTHER REQUIREMENTS & PRACTICES

### 1. MAINTENANCE:

All erosion and sediment controls shall be maintained in good working order. If a repair is necessary, it shall be performed at the earliest date possible but no later than 7 calendar days after the surrounding exposed ground has dried sufficiently to prevent further damage from heavy equipment. Disturbed areas on which construction activities have ceased, temporarily or permanently, shall be stabilized within 14 calendar days unless they are scheduled to and do resume within 21 calendar days. The areas adjacent to creeks and drainageways shall have priority followed by devices protecting storm sewer inlets.

### 2. INSPECTION:

An inspection shall be performed by a TxDOT Inspector every 14 calendar days as well as within 24 hours after any rainfall of one-half inch or more is recorded on a non-freezing rain gauge to be located at the project site, or every 7 calendar days. An Inspection and Maintenance Report shall be filed for each inspection. Based on the inspection results, the controls shall be revised in accordance with the inspection report.

### 3. WASTE MATERIALS:

Except as noted below, all waste materials shall be collected in a metal dumpster having a secure cover. The dumpster shall meet all state and local solid waste management regulations. All trash and debris from construction shall be deposited in the dumpster. The dumpster shall be emptied, as necessary or as required by local regulation, and hauled to a local approved land fill site. The burying of construction waste on the project site shall not be permitted.

Concrete washout areas shall be required and shall consist of a pit, lined with an impervious material, of sufficient size to contain, until evaporation, all water used and washout material produced during concrete washout operations. The concrete washout locations shall be as directed by the engineer.

Lime slaking tanks shall be surrounded by an earthen berm, capable of containing any overflow.

### 4. HAZARDOUS WASTE (INCLUDING SPILL REPORTING):

As a minimum, any products in the following categories are considered to be hazardous: paints, acids, solvents, asphalt products, chemical additives for soil stabilization, and concrete curing compounds or additives. In the event of a spill which may be hazardous, the spill coordinator shall be contacted immediately.

### 5. SANITARY WASTE:

All sanitary waste shall be collected from the portable units, as necessary or as required by local regulation, by a licensed sanitary waste management contractor.

### 6. OFFSITE VEHICLE TRACKING:

The Contractor shall be required, on a regular basis or as may be directed by the Engineer, to dampen haul roads for dust control, stabilize construction entrances and to remove excess dirt from the roadway.


### 7. MANAGEMENT PRACTICES: (Example Below - May be used as applicable, revised or expanded)

1. Disposal areas, stockpiles and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, waterbody or streambed.
2. Construction staging areas and vehicle maintenance areas shall be constructed by the Contractor in a manner to minimize the runoff of pollutants.
3. All temporary fills placed in waterways shall be built of erosion resistant material. (NWP 14)
4. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.

### 8. OTHER:

1. Listing of construction materials stored on site to be provided by Project Field Office.
2. The Project SW3P File located at the project field office shall contain the N.O.I., CGP Coverage Notice, TCEQ TPDES Form, Signature Authorization, Certification/Qualification Statements, Inspection Reports, Required Maps, and a copy of the TPDES General Permit No. TXR150000.

## STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING



No Permanent Installation Allowed.  
Sign to be Removed After Project Completion.

INTERIM REVIEW

THESE DOCUMENTS ARE INTENDED FOR  
 INTERIM REVIEW ONLY AND NOT FOR  
 REGULATORY APPROVAL, PERMITTING, OR  
 CONSTRUCTION.  
 REGISTERED LANDSCAPE ARCHITECT  
 DOROTHY J. WITMEYER  
 TEXAS REGISTRATION NUMBER 3159


**Pacheco Koch**  
 4060 BRYANT IRVIN ROAD  
 FORT WORTH, TX 76109 817.412.7155  
 TX REG. ENGINEERING FIRM F-469  
 TX REG. SURVEYING FIRM LS-10008001

**Texas Department of Transportation**
Fort Worth District Standard


## STORM WATER POLLUTION PREVENTION PLAN (SW3P)

SHEET 2 OF 2 SHEETS

ORIGINAL DRAWING: 09/2002 sw3p-ftw.dgn		FED. NO. 6	PROJECT NO.	SHEET NO. 025
DATE	REVISIONS	STATE	STATE DIST. NO.	COUNTY
09/2008	TPDES TO TPDES	TEXAS	FTW	TARRANT
01/2012	CLARIFY NOTE C. 2.	CONT.	SECT.	JOB
08/2013	ADDED SIGN	1094	02	XXX
05/2019	2-SHEET FORMAT			FM 731



PLASTIC MESH L-SHAPE  
CROSS SECTION




**NOTES:**

1. The device shall be a molded L-Shaped plastic mesh material that will cover the entire curb opening with a minimum 6" vertical face height by 6" horizontal plane width by 6' long with approximately .25" openings.
2. The device must have filter fabric material that will allow water flow but stop sediment. It will extend from bottom up vertical plane a minimum of 2" and full width of horizontal bottom plane. The filter fabric shall be attached to the back of the plastic mesh. It shall not cover more than 1/3 of the height of the vertical plane opening to allow overflow in larger storm events to prevent flooding of travel lanes.

Filter Fabric Physical Requirements Table

Apparent Opening Size (AOS)	400 to 600 microns
Percent Open Area (POA)	>10%
Flow Rate	130 gallons per SF per minute with clean water or greater.


3. Place with horizontal plane pointing away from curb.
4. For high openings, the device or attachment should extend above opening.
5. For long curb openings, overlap the segments 6". Tie together with 4 zip ties in 4 places, 2 at the top and 2 at the bottom.
6. Install gravel, not sand, bags at each end, at overlaps pass the inlet opening and in the middle of each section. Use 1/3 full bags for low profile and best traffic avoidance.
7. Overlap the fabric material pass the inlet opening 8" to 12".
8. Use bags that will have long-term resistance to UV exposure.
9. Sediment should be removed and device cleaned when sediment reaches 1" in depth.


 Texas Department of Transportation  
 FORT WORTH DISTRICT STANDARD  
 TEMPORARY EROSION,  
 SEDIMENT AND WATER  
 POLLUTION CONTROL MEASURES  
 CURB INLET SEDIMENT  
 PROTECTION

FED. RD. DIV. NO.	PROJECT NUMBER	SHEET NUMBER	
6	SEE TITLE SHEET	026	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NUMBER
1094	02	XXX	FM 731

REVISED ON 8/7/15

CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 DK: \_\_\_\_\_  
 DN: \_\_\_\_\_  
 DATE: \$DATE\$  
 FILE: \$FILE\$




### REFERENCE NOTES SCHEDULE 1


SYMBOL	DESCRIPTION	QTY
(7)	7012-6001 CURB INLET SEDIMENT PROTECTION	119 LF

### GENERAL NOTES

1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINEWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.



1 STA 00+00 - STA 09+00  
1" = 30'-0"



**INTERIM REVIEW**  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
 REGISTERED LANDSCAPE ARCHITECT  
 DOROTHY J. WINTER  
 TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** a Westwood company  
 4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155  
 TX REG. ENGINEERING FIRM F-469  
 TX REG. SURVEYING FIRM LS-1008001


©2023  
 Texas Department of Transportation

**EROSION CONTROL PLAN**  
 STA 00+00 - STA 09+00

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 027
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT
CONTROL 1094	SECTION 02	JOB 017
		HIGHWAY NO FM 731

OPEN FILE: M:\DWG-36\3666-22\DWG\LANDSCAPE.FX.2018\SHEETS\EROSION CONTROL PLAN.DWG  
 DATE: 03/20/2023 - 2:26PM  
 USER: M\DWG-36\3666-22\DWG\LANDSCAPE.FX.2018\SHEETS\EROSION CONTROL PLAN.DWG

MARCH 2023 - 90% PLAN SET




### REFERENCE NOTES SCHEDULE 2


SYMBOL	DESCRIPTION	QTY
7	7012-6001 CURB INLET SEDIMENT PROTECTION	117 LF

### GENERAL NOTES

1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINEWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.



1 STA 09+00 - STA 18+00  
1" = 30'-0"



**INTERIM REVIEW**  
 THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
 REGISTERED LANDSCAPE ARCHITECT  
 DOROTHY J. WINTER  
 TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
 a Westwood company TX REG. SURVEYING FIRM LS-1008001  
 4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155  
 ©2023  
 Texas Department of Transportation

### EROSION CONTROL PLAN STA 09+00 - STA 18+00


FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 028
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT
CONTROL 1094	SECTION 02	JOB 017
		HIGHWAY NO FM 731

OPEN FILE: C:\WORK\2023 - 2195PM.MXD  
 M:\DWG-36\3666-22\645\DWG\LANDSCAPE.FX 2018\SHEETS\EROSION CONTROL PLAN.DWG

MARCH 2023 - 90% PLAN SET


PLANT SCHEDULE I			
TREES	QTY	BOTANICAL / COMMON NAME	REMARKS
CL	3	CHILOPSIS LINEARIS 'BUBBA' DESERT WILLOW	192 6025 LANDSCAPE PLANTING (45 GAL)
QT	3	QUERCUS TEXANA TEXAS RED OAK	192 6026 LANDSCAPE PLANTING (65 GAL)
QH	2	QUERCUS VIRGINIANA 'HIGH RISE' HIGH RISE LIVE OAK	192 6026 LANDSCAPE PLANTING (65 GAL)
VC	3	VITEX AGNIUS-CASTUS 'SHOAL CREEK' CHASTE TREE	192 6025 LANDSCAPE PLANTING (45 GAL)
SHRUBS	QTY	BOTANICAL / COMMON NAME	REMARKS
HP2	59	HESPERALOE PARVIFLORA 'YELLOW' YELLOW YUCCA	192 6032 LANDSCAPE PLANTING (5 GAL)
RD	56	ROSMARINUS OFFICINALIS 'BLUE SPIRES' ROSEMARY	192 6003 LANDSCAPE PLANTING (3 GAL)
GROUND COVERS	QTY	BOTANICAL / COMMON NAME	REMARKS
MS	92	MISCANTHUS SINENSIS 'ADAGIO' ADAGIO MAIDEN GRASS	192 6003 LANDSCAPE PLANTING (3 GAL)
MR	343	MUHLENBERGIA CAPILLARIS PINK MUHLY	192 6003 LANDSCAPE PLANTING (3 GAL)
SEED	QTY	BOTANICAL / COMMON NAME	REMARKS
BG	6,670 SF	NATIVE SEED MIX BUFFALO GRASS AND BLUE GRAMA	180 6001 WILDFLOWER SEED (NATIVE SEED MIX)

REFERENCE NOTES SCHEDULE I		
CODE	DESCRIPTION	QTY
1	1G1 6022 GENERAL USE COMPOST (4')	5,644 SF
2	1G1 6022 EROSION CONTROL COMPOST (2')	6,677 SF
3	192 6013 LANDSCAPE PLANTING (MULCH) (BARK)	3,541 SF
4	192 6028 CONCRETE LANDSCAPE EDGE (1.2' WIDTH)	591 LF
5	1005 6001 LOOSE AGGR FOR GROUND COVER (TYP I) (DECOMPOSED GRANITE)	15.88 CY
6	1005 6002 LOOSE AGGR FOR GROUND COVER (TYP II) (RIP RAP, SMALL)	35.52 CY




### GENERAL NOTES

1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.




1 STA 00+00 - STA 04+50  
1" = 20'-0"



INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
DOROTHY J. WITMEYER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-10008001  
4060 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155



PLANTING PLAN STA 00+00 - STA 04+50			
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 029	
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT	
CONTROL 1094	SECTION 02	JOB 017	HIGHWAY NO FM 731


OKFENNY 03/01/2023 - 2:27PM M:\DWG-36\3696-22\645\DWG\LANDSCAPE FX 2018\SHEETS\PLANTING PLAN.DWG

MARCH 2023 - 90% PLAN SET




PLANT SCHEDULE 2			
TREES	QTY	BOTANICAL / COMMON NAME	REMARKS
QH	3	QUERCUS VIRGINIANA "HIGH RISE" HIGH RISE LIVE OAK	192 G026 LANDSCAPE PLANTING (65 GAL)
UC	5	ULMUS CRASSIFOLIA CEDAR ELM	192 G026 LANDSCAPE PLANTING (65 GAL)
VC	5	VITEX AGNUS-CASTUS "SHOAL CREEK" CHASTE TREE	192 G025 LANDSCAPE PLANTING (45 GAL)
SHRUBS	QTY	BOTANICAL / COMMON NAME	REMARKS
HP2	36	HESPERALOE PARVIFLORA "YELLOW" YELLOW YUCCA	192 G032 LANDSCAPE PLANTING (5 GAL)
YC	87	YUCCA FILAMENTOSA "COLOR GUARD" ADAM'S NEEDLE	192 G003 LANDSCAPE PLANTING (3 GAL)
GROUND COVERS	QTY	BOTANICAL / COMMON NAME	REMARKS
MR	248	MUHLENBERGIA CAPILLARIS PINK MUHLY	192 G003 LANDSCAPE PLANTING (3 GAL)
SEED	QTY	BOTANICAL / COMMON NAME	REMARKS
BG	12,774 SF	NATIVE SEED MIX BUFFALO GRASS AND BLUE GRAMA	180 G001 WILDFLOWER SEED (NATIVE SEED MIX)

REFERENCE NOTES SCHEDULE 2		
CODE	DESCRIPTION	QTY
1	161 G022 GENERAL USE COMPOST (4")	4,057 SF
2	161 G022 EROSION CONTROL COMPOST (2")	13,099 SF
3	192 G013 LANDSCAPE PLANTING (MULCH) (BARK)	2,512 SF
4	192 G028 CONCRETE LANDSCAPE EDGE (1 1/2" WIDTH)	714 LF
5	1005 G001 LOOSE AGGR FOR GROUNDCOVER (TYP I) (DECOMPOSED GRANITE)	15.14 CY
6	1005 G002 LOOSE AGGR FOR GROUNDCOVER (TYP II) (RIP RAP, SMALL)	21.76 CY




### GENERAL NOTES

1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.



1 STA 04+50 - STA 09+00  
1" = 20'-0"



INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
DOROTHY J. NEWBERRY  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4660 BRYANT IRVIN RD. • FORT WORTH, TX 76103 • 817-412-7155  
©2023  
Texas Department of Transportation


PLANTING PLAN STA 04+50 - STA 09+00			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	030	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO.
1094	02	017	FM 731

03/01/2023 - 2:27PM  
M:\DWG-36\3696-22\645\DWG\LANDSCAPE\_FX\_2018\SHEETS\PLANTING\_PLANDWG

MARCH 2023 - 90% PLAN SET


PLANT SCHEDULE 3			
TREES	QTY	BOTANICAL / COMMON NAME	REMARKS
CL	5	CHILOPSIS LINEARIS 'BUBBA' DESERT WILLOW	192 6025 LANDSCAPE PLANTING (45 GAL)
QT	4	QUERCUS TEXANA TEXAS RED OAK	192 6026 LANDSCAPE PLANTING (65 GAL)
QH	4	QUERCUS VIRGINIANA 'HIGH RISE' HIGH RISE LIVE OAK	192 6026 LANDSCAPE PLANTING (65 GAL)
SHRUBS	QTY	BOTANICAL / COMMON NAME	REMARKS
RD	28	ROSMARINUS OFFICINALIS 'BLUE SPIRES' ROSEMARY	192 6003 LANDSCAPE PLANTING (3 GAL)
YC	86	YUCCA FILAMENTOSA 'COLOR GUARD' ADAM'S NEEDLE	192 6003 LANDSCAPE PLANTING (3 GAL)
GROUND COVERS	QTY	BOTANICAL / COMMON NAME	REMARKS
MS	134	MISCANTHUS SINENSIS 'ADAGIO' ADAGIO MAIDEN GRASS	192 6003 LANDSCAPE PLANTING (3 GAL)
MR	253	MUHLENBERGIA CAPILLARIS PINK MUHLY	192 6003 LANDSCAPE PLANTING (3 GAL)
SEED	QTY	BOTANICAL / COMMON NAME	REMARKS
BG	6,789 SF	NATIVE SEED MIX BUFFALO GRASS AND BLUE GRAMA	180 6001 WILDFLOWER SEED (NATIVE SEED MIX)

REFERENCE NOTES SCHEDULE 3		
CODE	DESCRIPTION	QTY
1	161 6022 GENERAL USE COMPOST (4")	5,219 SF
2	161 6022 EROSION CONTROL COMPOST (2")	6,493 SF
3	192 6013 LANDSCAPE PLANTING (MULCH) (BARK)	4,472 SF
4	192 6028 CONCRETE LANDSCAPE EDGE (1 1/2" WIDTH)	339 LF
5	1005 6001 LOOSE AGGR FOR GROUND COVER (TYP I) (DECOMPOSED GRANITE)	27.29 CY
6	1005 6002 LOOSE AGGR FOR GROUND COVER (TYP II) (RIP RAP, SMALL)	16.95 CY




### GENERAL NOTES

1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.



1 STA 09+00 - STA 13+50  
1" = 20'-0"



INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
DOROTHY J. NEWBLES  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4660 BRYANT IRVIN RD. • FORT WORTH, TX 76103 • 817-412-7156  
©2023  
Texas Department of Transportation


PLANTING PLAN STA 09+00 - STA 13+50			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	031	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO.
1094	02	017	FM 731

03/01/2023 - 2:27PM  
M:\DWG-36\3696-22.645\DWG\LANDSCAPE.FX 2018\SHEETS\PLANTING PLANDWG

MARCH 2023 - 90% PLAN SET


PLANT SCHEDULE 4			
TREES	QTY	BOTANICAL / COMMON NAME	REMARKS
CT	5	CERCIS CANADENSIS TEXENSIS 'TEXAS WHITE' TEXAS WHITE REDBUD	192 6025 LANDSCAPE PLANTING (45 GAL)
QH1	2	QUERCUS VIRGINIANA 'HIGH RISE' HIGH RISE LIVE OAK	192 6026 LANDSCAPE PLANTING (65 GAL)
SHRUBS	QTY	BOTANICAL / COMMON NAME	REMARKS
HP2	36	HESPERALOE PARVIFLORA 'YELLOW' YELLOW YUCCA	192 6032 LANDSCAPE PLANTING (5 GAL)
YC	36	YUCCA FILAMENTOSA 'COLOR GUARD' ADAM'S NEEDLE	192 6003 LANDSCAPE PLANTING (3 GAL)
GROUND COVERS	QTY	BOTANICAL / COMMON NAME	REMARKS
MR	107	MUHLENBERGIA CAPILLARIS PINK MUHLY	192 6003 LANDSCAPE PLANTING (3 GAL)
SEED	QTY	BOTANICAL / COMMON NAME	REMARKS
BG	2,467 SF	NATIVE SEED MIX BUFFALO GRASS AND BLUE GRAMA	180 6001 WILDFLOWER SEED (NATIVE SEED MIX)

REFERENCE NOTES SCHEDULE 4		
CODE	DESCRIPTION	QTY
1	161 6022 GENERAL USE COMPOST (4")	1,897 SF
2	161 6022 EROSION CONTROL COMPOST (2")	2,464 SF
3	192 6013 LANDSCAPE PLANTING (MULCH) (BARK)	1,077 SF
4	192 6028 CONCRETE LANDSCAPE EDGE (1 1/2" WIDTH)	258 LF
5	1005 6001 LOOSE AGGR FOR GROUND COVER (TYP I) (DECOMPOSED GRANITE)	20.12 CY
6	1005 6002 LOOSE AGGR FOR GROUND COVER (TYP II) (RIP RAP, SMALL)	9.57 CY




**GENERAL NOTES**

1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINEWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.



1 STA 13+50 - STA 18+00  
1" = 20'-0"



INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
DOROTHY J. NEWBERRY  
TEXAS REGISTRATION NUMBER 3159


**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4660 BRYANT IRVIN RD. • FORT WORTH, TX 76103 • 817.412.7155

©2023 Texas Department of Transportation


PLANTING PLAN STA 13+50 - STA 18+00			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	032	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO.
1094	02	017	FM 731

03/01/2023 - 2:27PM  
M:\DWG-36\3696-22645\DWG\LANDSCAPE\_FX\_2018\SHEETS\PLANTING\_PLANDWG

MARCH 2023 - 90% PLAN SET




NOTE: DO NOT CREATE WATERING RING (SAUCER) AROUND TREE PIT




NOTE: AUGER EXCAVATION OF TREE PIT IS NOT ACCEPTABLE.

1 CANOPY TREE W/ UNDERGROUND STAKES  
3/4" = 1'-0"




- PLANTING SOIL IN SHRUB BEDS:
- EXCAVATE EXISTING SOILS 4" BELOW ADJACENT CURB OR SIDEWALK
  - ADD 4" COMPOST & TILL INTO 6" EXISTING SOILS, CREATING 10" PLANTING SOIL
  - ADD 3" MULCH AFTER PLANTING

2 TYP. SHRUB PLANTING  
1" = 1'-0"



3 LOOSE AGGR FOR GROUNDCOVER  
1" = 1'-0"



NOTE: PLACE EXPANSION JOINTS BETWEEN MOW CURB AND EXISTING VEHICULAR CURBS, W/ CONTROL JOINTS @ 5' O.C.

4 1.2" CONCRETE MOW CURB  
1" = 1'-0"

PLANT SCHEDULE					
TREES	CODE	BOTANICAL / COMMON NAME	SIZE/COND.	SPACING	REMARKS
	CT	CERCIS CANADENSIS TEXENSIS 'TEXAS WHITE' TEXAS WHITE REDBUD	45 GAL		192 6025 LANDSCAPE PLANTING (45 GAL)
	CL	CHILOPSIS LINEARIS 'BUBBA' DESERT WILLOW	45 GAL		192 6025 LANDSCAPE PLANTING (45 GAL)
	QT	QUERCUS TEXANA TEXAS RED OAK	65 GAL		192 6026 LANDSCAPE PLANTING (65 GAL)
	QH	QUERCUS VIRGINIANA 'HIGH RISE' HIGH RISE LIVE OAK	65 GAL		192 6026 LANDSCAPE PLANTING (65 GAL)
	UC	ULMUS CRASSIFOLIA CEDAR ELM	65 GAL		192 6026 LANDSCAPE PLANTING (65 GAL)
	VC	VITEC AGNIUS-CASTUS 'SHOAL CREEK' CHASTE TREE	45 GAL		192 6025 LANDSCAPE PLANTING (45 GAL)
SHRUBS	CODE	BOTANICAL / COMMON NAME	SIZE	SPACING	REMARKS
	HP2	HESPERALOE PARVIFLORA 'YELLOW' YELLOW YUCCA	10 GAL	36" o.c.	192 6032 LANDSCAPE PLANTING (5 GAL)
	RD	ROSMARINUS OFFICINALIS 'BLUE SPIRES' ROSEMARY	3 GAL	42" o.c.	192 6003 LANDSCAPE PLANTING (3 GAL)
	YC	YUCCA FILAMENTOSA 'COLOR GUARD' ADAM'S NEEDLE	3 GAL	36" o.c.	192 6003 LANDSCAPE PLANTING (3 GAL)
GROUND COVERS	CODE	BOTANICAL / COMMON NAME	SIZE	SPACING	REMARKS
	MS	MISCANTHUS SINENSIS 'ADAGIO' ADAGIO MAIDEN GRASS	3 GAL	46" o.c.	192 6003 LANDSCAPE PLANTING (3 GAL)
	MR	MUHLENBERGIA CAPILLARIS PINK MUHLY	3 GAL	36" o.c.	192 6003 LANDSCAPE PLANTING (3 GAL)
SEED	CODE	BOTANICAL / COMMON NAME	SIZE	SPACING	REMARKS
	BG	NATIVE SEED MIX BUFFALO GRASS AND BLUE GRAMA	50D		180 6001 WILDFLOWER SEED (NATIVE SEED MIX)

INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL/PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
DOROTHY J. WITMEYER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-10008001  
4060 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155  
©2023  
Texas Department of Transportation

PLANT DETAILS

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 033
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT
CONTROL 1094	SECTION 02	JOB 017
		HIGHWAY NO FM 731

# IRRIGATION SCHEDULE


SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	SYMBOL	MANUFACTURER/MODEL/DESCRIPTION
	HUNTER ICZ-101-25 DRIP CONTROL ZONE KIT. 1" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 25PSI. FLOW RANGE: 2 GPM TO 20 GPM. 150 MESH STAINLESS STEEL SCREEN.		NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"
	HUNTER ICZ-151-XL-40 DRIP CONTROL ZONE KIT. 1-1/2" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 40PSI. FLOW RANGE: 20 GPM TO 60 GPM. 120 MESH STAINLESS STEEL SCREEN. 1-1/2" INLET X SINGLE 2" OUTLET		IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21 ONLY LATERAL TRANSITION PIPE SIZES 1" AND ABOVE ARE INDICATED ON THE PLAN, WITH ALL OTHERS BEING 3/4" IN SIZE.
	AREA TO RECEIVE DRIPLINE NETAFIM TLHCVR-CS-033-18 TECHLINE HCVXR-CS PRESSURE COMPENSATING LANDSCAPE DRIPLINE WITH COPPER STRIPE, CHECK VALVE AND ANTI-SIPHON FEATURE. 0.33 GPH EMITTERS AT 18" O.C. DRIPLINE LATERALS SPACED AT 18" APART, WITH EMITTERS OFFSET FOR TRIANGULAR PATTERN. 17MM.		IRRIGATION MAINLINE: PVC CLASS 200 SDR 21
	PIPE SLEEVE: PVC CLASS 200 SDR 21 2 SIZES LARGER THAN PIPE WITHIN.		Valve Callout Valve Number Valve Flow Valve Size
	NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"		

# IRRIGATION MODIFICATION NOTES

- THE CONTRACTOR SHALL VISIT THE SITE & DOCUMENT THE EXISTING IRRIGATION SYSTEM TO A LEVEL SUFFICIENT TO DETERMINE:
1. THAT THE BACKFLOW PREVENTION DEVICE ON THE EXISTING SYSTEM IS FUNCTIONAL. IF NOT, HE SHALL PROVIDE A NEW ONE.
  2. THAT THE EXISTING CONTROLLER CAN ACCOMMODATE NEW ZONES OR EXISTING ZONES MODIFIED WITHIN TCEQ DESIGN CRITERIA TO ACCOMMODATE EXISTING ZONES. PROVIDE NEW CONTROLLER IS NECESSARY.
  3. IF EXISTING RAIN/FREEZE SENSOR IS PRESENT & FUNCTIONAL. IF NOT, PROVIDE ONE COMPATIBLE WITH CONTROLLER.
  4. WHAT MANUFACTURER IS CURRENTLY IN USE & PROVIDE SAME BRAND OF EQUIPMENT TO MODIFIED ZONES.

# CONTRACTOR SHALL:

1. FOLLOW ALL TCEQ IRRIGATION REQUIREMENTS & STANDARDS.
2. PROVIDE LAMINATED 6 1/2" X 11" AS-BUILT OF THE FINISHED/MODIFIED SYSTEM.
3. DEMONSTRATE TO AN OWNER'S REPRESENTATIVE THAT THE IRRIGATION SYSTEM IS FULLY FUNCTIONAL AND RUNNING PROPERLY PRIOR TO FINAL ACCEPTANCE AND BEGINNING OF THE WARRANTY PERIOD
4. PROVIDE THAT ALL TRENCHING WITHIN DRIP LINE OF EXISTING TREES SHALL BE DONE WITH HAND TOOLS AND SHALL NOT CUT ANY ROOT OVER 3" DIAMETER.
5. EXAMINE THE PLANS IN THEIR ENTIRETY TO DETERMINE THE APPROXIMATE LOCATION OF EXISTING AND PROPOSED UTILITIES. HE SHALL ALSO CONTACT THE APPROPRIATE AUTHORITY TO MARK UTILITIES ON THE SITE. THE IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES TO UTILITIES ON THE SITE CAUSED BY HIS WORK.




# GENERAL NOTES


1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.

# BORING NOTES

1. ADVERSE ROAD SURFACE CONDITIONS CREATED FROM BORING (I.E. HUMPS, BROKEN CURBS, ETC.) AS EVALUATED BY THE ENGINEER, WILL BE REPAIRED AT CONTRACTOR'S EXPENSE.



1 STA 00+00 - STA 04+50  
1" = 20'-0"



# CONTROLLER AND METER LOCATION

1. EXISTING IRRIGATION CONTROLLER IS LOCATED APPROXIMATELY 900 LF NORTH EAST OF STATION 18+00 ACROSS FROM TACO BELL IN THE MEDIAN.
2. EXISTING WATER METER AND BACKFLOW PREVENTION DEVICE ARE LOCATED WITH IN THE ROW ON THE EAST SIDE OF FM 731 AT APPROXIMATELY THE SAME LOCATION AS THE IRRIGATION CONTROLLER

**INTERIM REVIEW**  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
BENJAMIN J. WINTERER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155



©2023 Texas Department of Transportation

IRRIGATION PLAN  
STA 00+00 - STA 04+50

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 034
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT
CONTROL 1094	SECTION 02	JOB 017
		HIGHWAY NO FM 731

# IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	SYMBOL	MANUFACTURER/MODEL/DESCRIPTION
	HUNTER ICZ-101-25 DRIP CONTROL ZONE KIT. 1" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 25PSI. FLOW RANGE: 2 GPM TO 20 GPM. 150 MESH STAINLESS STEEL SCREEN.		NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"
	HUNTER ICZ-151-XL-40 DRIP CONTROL ZONE KIT. 1-1/2" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 40PSI. FLOW RANGE: 20 GPM TO 60 GPM. 120 MESH STAINLESS STEEL SCREEN. 1-1/2" INLET X SINGLE 2" OUTLET		IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21 ONLY LATERAL TRANSITION PIPE SIZES 1" AND ABOVE ARE INDICATED ON THE PLAN, WITH ALL OTHERS BEING 3/4" IN SIZE.
	AREA TO RECEIVE DRIPLINE NETAFIM TLHCVR-CS-033-18 TECHLINE HCVXR-CS PRESSURE COMPENSATING LANDSCAPE DRIPLINE WITH COPPER STRIPE, CHECK VALVE AND ANTI-SIPHON FEATURE. 0.33 GPH EMITTERS AT 18" O.C. DRIPLINE LATERALS SPACED AT 18" APART, WITH EMITTERS OFFSET FOR TRIANGULAR PATTERN. 17MM.		IRRIGATION MAINLINE: PVC CLASS 200 SDR 21
	PIPE SLEEVE: PVC CLASS 200 SDR 21 2 SIZES LARGER THAN PIPE WITHIN.		Valve Callout Valve Number Valve Flow Valve Size
	NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"		




## GENERAL NOTES


1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINEWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.

## BORING NOTES

1. ADVERSE ROAD SURFACE CONDITIONS CREATED FROM BORING (I.E. HUMPS, BROKEN CURBS, ETC.) AS EVALUATED BY THE ENGINEER, WILL BE REPAIRED AT CONTRACTOR'S EXPENSE.



1 STA 04+50 - STA 09+00  
1" = 20'-0"



### CONTROLLER AND METER LOCATION

1. EXISTING IRRIGATION CONTROLLER IS LOCATED APPROXIMATELY 900 LF NORTH EAST OF STATION 18+00 ACROSS FROM TACO BELL IN THE MEDIAN.
2. EXISTING WATER METER AND BACKFLOW PREVENTION DEVICE ARE LOCATED WITH IN THE ROW ON THE EAST SIDE OF FM 731 AT APPROXIMATELY THE SAME LOCATION AS THE IRRIGATION CONTROLLER

INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
BENJAMIN J. WINTER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155  
©2023 Texas Department of Transportation




IRRIGATION PLAN STA 04+50 - STA 09+00			
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 035	
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT	
CONTROL 1094	SECTION 02	JOB 017	HIGHWAY NO FM 731

L:\DWG\2023\2-54\PM\MX\DWG-36\3666-22\645\DWG\LANDSCAPE\_FX\_2018\SHEETS\IRRIGATION\_PLAN.DWG

MARCH 2023 - 90% PLAN SET

# IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	SYMBOL	MANUFACTURER/MODEL/DESCRIPTION
	HUNTER ICZ-101-25 DRIP CONTROL ZONE KIT. 1" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 25PSI. FLOW RANGE: 2 GPM TO 20 GPM. 150 MESH STAINLESS STEEL SCREEN.		NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"
	HUNTER ICZ-151-XL-40 DRIP CONTROL ZONE KIT. 1-1/2" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 40PSI. FLOW RANGE: 20 GPM TO 60 GPM. 120 MESH STAINLESS STEEL SCREEN. 1-1/2" INLET X SINGLE 2" OUTLET		IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21 ONLY LATERAL TRANSITION PIPE SIZES 1" AND ABOVE ARE INDICATED ON THE PLAN, WITH ALL OTHERS BEING 3/4" IN SIZE.
	AREA TO RECEIVE DRIPLINE NETAFIM TLHCVR-CS-033-18 TECHLINE HCVXR-CS PRESSURE COMPENSATING LANDSCAPE DRIPLINE WITH COPPER STRIPE, CHECK VALVE AND ANTI-SIPHON FEATURE. 0.33 GPH EMITTERS AT 18" O.C. DRIPLINE LATERALS SPACED AT 18" APART, WITH EMITTERS OFFSET FOR TRIANGULAR PATTERN. 17MM.		IRRIGATION MAINLINE: PVC CLASS 200 SDR 21
	NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"		PIPE SLEEVE: PVC CLASS 200 SDR 21 2 SIZES LARGER THAN PIPE WITHIN.




## GENERAL NOTES


1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINEWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.

## BORING NOTES

1. ADVERSE ROAD SURFACE CONDITIONS CREATED FROM BORING (I.E. HUMPS, BROKEN CURBS, ETC.) AS EVALUATED BY THE ENGINEER, WILL BE REPAIRED AT CONTRACTOR'S EXPENSE.



1 STA 09+00 - STA 13+50  
1" = 20'-0"



### CONTROLLER AND METER LOCATION

1. EXISTING IRRIGATION CONTROLLER IS LOCATED APPROXIMATELY 900 LF NORTH EAST OF STATION 18+00 ACROSS FROM TACO BELL IN THE MEDIAN.
2. EXISTING WATER METER AND BACKFLOW PREVENTION DEVICE ARE LOCATED WITH IN THE ROW ON THE EAST SIDE OF FM 731 AT APPROXIMATELY THE SAME LOCATION AS THE IRRIGATION CONTROLLER

**INTERIM REVIEW**  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
DOROTHY J. WINTERER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155  
©2023 Texas Department of Transportation



IRRIGATION PLAN		STA 09+00 - STA 13+50	
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.	
6	SEE TITLE SHEET	036	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO
1094	02	017	FM 731

L:\DWG\2023\2-564PM\23-366-36\DWG-36\IRRIGATION\LANDSCAPE.FX.2018\SHEETS\IRRIGATION.PLAN.DWG

MARCH 2023 - 90% PLAN SET

# IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	SYMBOL	MANUFACTURER/MODEL/DESCRIPTION
	HUNTER ICZ-101-25 DRIP CONTROL ZONE KIT. 1" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 25PSI. FLOW RANGE: 2 GPM TO 20 GPM. 150 MESH STAINLESS STEEL SCREEN.		NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"
	HUNTER ICZ-151-XL-40 DRIP CONTROL ZONE KIT. 1-1/2" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM. PRESSURE REGULATION: 40PSI. FLOW RANGE: 20 GPM TO 60 GPM. 120 MESH STAINLESS STEEL SCREEN. 1-1/2" INLET X SINGLE 2" OUTLET		IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21 ONLY LATERAL TRANSITION PIPE SIZES 1" AND ABOVE ARE INDICATED ON THE PLAN, WITH ALL OTHERS BEING 3/4" IN SIZE.
	AREA TO RECEIVE DRIPLINE NETAFIM TLHCVR-CS-033-18 TECHLINE HCVXR-CS PRESSURE COMPENSATING LANDSCAPE DRIPLINE WITH COPPER STRIPE, CHECK VALVE AND ANTI-SIPHON FEATURE. 0.33 GPH EMITTERS AT 18" O.C. DRIPLINE LATERALS SPACED AT 18" APART, WITH EMITTERS OFFSET FOR TRIANGULAR PATTERN. 17MM.		IRRIGATION MAINLINE: PVC CLASS 200 SDR 21
	PIPE SLEEVE: PVC CLASS 200 SDR 21 2 SIZES LARGER THAN PIPE WITHIN.		PIPE SLEEVE: PVC CLASS 200 SDR 21 2 SIZES LARGER THAN PIPE WITHIN.
	NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"		PIPE SLEEVE: PVC CLASS 200 SDR 21 2 SIZES LARGER THAN PIPE WITHIN.




## GENERAL NOTES


1. THE ENTIRE LIMITS OF IMPROVEMENTS WERE NOT SURVEYED. ALL LINEWORK IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
2. ALL UTILITIES SHOWN ON PLANS ARE APPROXIMATE IN NATURE AND DO NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY TO COORDINATE WITH APPROPRIATE AUTHORITIES.
3. CALL TxDOT TRAFFIC MANAGEMENT CENTER (817-370-3661) FOR TxDOT LOCATES WHEN WORKING NEAR EXISTING TRAFFIC SIGNAL.

## BORING NOTES

1. ADVERSE ROAD SURFACE CONDITIONS CREATED FROM BORING (I.E. HUMPS, BROKEN CURBS, ETC.) AS EVALUATED BY THE ENGINEER, WILL BE REPAIRED AT CONTRACTOR'S EXPENSE.



1 STA 13+50 - STA 18+00  
1" = 20'-0"



### CONTROLLER AND METER LOCATION

1. EXISTING IRRIGATION CONTROLLER IS LOCATED APPROXIMATELY 900 LF NORTH EAST OF STATION 18+00 ACROSS FROM TACO BELL IN THE MEDIAN.
2. EXISTING WATER METER AND BACKFLOW PREVENTION DEVICE ARE LOCATED WITH IN THE ROW ON THE EAST SIDE OF FM 731 AT APPROXIMATELY THE SAME LOCATION AS THE IRRIGATION CONTROLLER

INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
BENJAMIN J. WINTER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155


©2023  
Texas Department of Transportation

IRRIGATION PLAN STA 13+50 - STA 18+00			
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. SEE TITLE SHEET	SHEET NO. 037	
STATE TEXAS	DISTRICT FTW	COUNTY TARRANT	
CONTROL 1094	SECTION 02	JOB 017	HIGHWAY NO FM 731

L:\WORK\2023 - 2:54PM  
M:\DWG-36\3666-22\645\DWG\LANDSCAPE.FX.2018\SHEETS\IRRIGATION.PLAN.DWG


MARCH 2023 - 90% PLAN SET






1 BRASS ISOLATION VALVE  
1/2" = 1'-0"

2 DRIP ZONE VALVE ASSEMBLY-AT GRADE  
1/2" = 1'-0"



3 DRIP ZONE TYPICAL ENLARGEMENT  
3/8" = 1'-0"



4 DRIP TUBE INSTALLATION - AT GRADE  
3" = 1'-0"

INTERIM REVIEW  
THESE DOCUMENTS ARE INTENDED FOR INTERIM REVIEW ONLY AND NOT FOR REGULATORY APPROVAL, PERMITTING, OR CONSTRUCTION.  
REGISTERED LANDSCAPE ARCHITECT  
BENJAMIN J. WINTER  
TEXAS REGISTRATION NUMBER 3159

**Pacheco Koch** TX REG. ENGINEERING FIRM F-469  
a Westwood company TX REG. SURVEYING FIRM LS-1008001  
4000 BRYANT IRVIN RD. • FORT WORTH, TX 76109 • 817.412.7155

©2023 Texas Department of Transportation

IRRIGATION DETAILS

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		SHEET NO.
6	SEE TITLE SHEET		038
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HIGHWAY NO
1094	02	017	FM 731

L:\KING\2023\23-033 - 2:54PM\23-033-36\DWG-36\IRRI\LANDSCAPE.FX 2018\SHEETS\IRRIGATION PLAN.DWG

MARCH 2023 - 90% PLAN SET