

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL PROJECT NO. STP 2023(306)HES

IH 10

PECOS COUNTY

INDEX OF SHEETS

SEE SHEET 2 FOR INDEX

DESIGN	FED. RD. DIV. NO.	STATE PROJECT NO.		SHEET NO.
MDM	6	STP 2023(306)HES		1
GRAPHICS	STATE	STATE DIST. NO.	COUNTY	
MDM	TEXAS	6	PECOS	
CHECKED	CONT.	SECT.	JOB	HIGHWAY NO.
JKB	0140	02	050	IH 10
CHECKED	JKB			


CSJ	HWY	LIMITS	ROADWAY		BRIDGE		PROJECT LENGTH	
			FEET	MILES	FEET	MILES	FEET	MILES
0140-02-050	IH 10	FROM RM 285 TO RM 293	42027.00	7.960	-	-	42027.00	7.960

DESIGN SPEEDS:
MAINLANES = 80 MPH

AVERAGE DAILY TRAFFIC
IH 10 (2021) = 9,108
IH 10 (2041) = 12,387

FUNCTIONAL CLASSIFICATION:
MAINLANES = INTERSTATE

FOR THE CONSTRUCTION OF: SAFETY IMPROVEMENT PROJECT
CONSISTING OF: INSTALL MEDIAN BARRIER



END PROJECT
CSJ: 0140-02-050
STA. 1027+50.25
RM 293.00

BEGIN PROJECT
CSJ: 0140-02-050
STA. 607+60.00
RM 285.00

EQUATIONS : NONE
RAILROAD : NONE
EXCEPTIONS : NONE



RECOMMENDED FOR LETTING: 7/17/2023 DATE
 [Signature]
 DIRECTOR OF TRANSPORTATION PLANNING & DEVELOPMENT

SUBMITTED FOR LETTING: 7/17/2023 DATE
 [Signature]
 AREA ENGINEER

APPROVED FOR LETTING: 7/17/2023 DATE
 [Signature]
 DISTRICT ENGINEER



_____, P.E. _____ DATE

NOTES:
SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT:
REQUIRED CONTRACT PROVISIONS, FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)


COUNTY _____ PROJ. NO. _____
 HWY. NO. _____ LETTING DATE _____
 DATE ACCEPTED _____

D:\MOM CK: JKB
 D:\MOM CK: JKB
 D:\MOM CK: JKB

SHEET	DESCRIPTION
<u>I. GENERAL</u>	
1	TITLE SHEET
2	INDEX OF SHEETS
3	PROJECT LAYOUT
4 - 4B	GENERAL NOTES
5	ESTIMATE & QUANTITY
6 - 7	TYPICAL SECTIONS
8	SUMMARY OF QUANTITIES
9 - 13	SUMMARY OF EARTHWORK QUANTITIES
<u>II. TRAFFIC CONTROL PLAN</u>	
14	SEQUENCE OF CONSTRUCTION
15	ADVANCED WARNING LAYOUT
STANDARDS	
16 - 27	* BC (1)-21 THRU BC (12)-21
28	* WZ (BRK) -13
29	* WZ (RS) -22
30	* TCP (5-1)-18
31	* TCP (6-1)-12
<u>III. ROADWAY DETAILS</u>	
32 - 33	HORIZONTAL & VERTICAL SURVEY CONTROL
34	ALIGNMENT DATA
35 - 52	MEDIAN BARRIER LAYOUT
53	SUMMARY OF SMALL SIGNS
STANDARDS	
54	* CASS (TL4) -14
55	* GF (31) -19
56	* GF (31) DAT-19
57	* GF (31) MS-19
58	* SGT (12) 31-18
59	* SGT (15) 31-20
60	* SMD (GEN) -08
61	* SMD (SLIP-1) -08
62	* SMD (SLIP-2) -08
63	* SMD (SLIP-3) -08
64	* TSR (4) -13
<u>IV. ENVIRONMENTAL ISSUES</u>	
65	SW3P LAYOUT
66 - 67	STORMWATER POLLUTION PREVENTION PLAN (SW3P)
68	ENVIRONMENTAL PERMITS, ISSUES AND
STANDARDS	
69 - 71	* EC (9) -16

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET WITH A "#" HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Christopher Hartke, P.E. 7/14/2023
 NAME DATE








IH 10
 INDEX OF SHEETS

SHEET 1 OF 1			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	2	

DATE: FILE:

DATE: FILE:
DIN: MDM
CHK: JKB
DWF: MDM



IH 10
PROJECT LAYOUT

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	3	

DATE: FILE:

County: Pecos
Highway: IH 10

Control: 0140-02-050

Contractor questions on this project are to be addressed to the following individual(s):
ODA-PreLettingQuestions@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 5: Control of the Work

For any structures containing bird nests, schedule all work to complete the demolition of the existing structures identified in the plans between September 15, 2023 and March 15, 2024. Failure to complete this work during the specified timeframe may cause construction delays due to environmental regulations.

The existing alignment is the control for the Contractor staking. Establish reference points for the control prior to removing the existing surface.

Use Method C for construction surveying.

Item 6: Control of Materials

Restrict storage of equipment and materials to approved areas. The Engineer will not approve storage in any TxDOT yard.

Promptly and properly dispose of any waste generated from servicing equipment on the project.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.
<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Item 7: Legal Relations and Responsibilities

If access to the project is required through a new or unapproved driveway (i.e. Material source, stockpile location, field office, etc.), obtain an approved "Permit to Construct Access Driveway Facilities on Highway Right Of Way" (TxDOT Form 1058) before beginning any construction operations.

County: Pecos
Highway: IH 10

Control: 0140-02-050

Utilities (public, private and TxDOT) exist throughout the project. Prior to any excavation, investigate to determine the utility locations within the project right of way. Contact the TxDOT Odessa Traffic Operations shop at 432-498-4690 to investigate and determine the location of any TxDOT utility that may exist within the project right of way. Exercise caution when excavating in areas where investigations have determined that utilities exist. The contractor is responsible for maintaining utility markings

No significant traffic generator events identified.

As an element of ensuring public safety and convenience under Article 7.2.4, the Contractor is hereby directed to open all closed lanes and shoulder and remove all traffic control devices from any areas where work is not being actively performed unless overnight traffic control is required and approved by the engineer. Removed devices must be stored outside of the clear zones near the right of way line or removed from the right of way line entirely.

At any time during construction that a previously installed crash cushion is damaged by the traveling public and is requested to be repaired by the Engineer, the repair will be paid at the same unit cost as the original installation.

Item 8: Prosecution and Progress

The following portions of the plans may affect the Contractor's planned construction sequencing. The Contractor's attention is directed to the appropriate plan sheet or standard sheet.

-Traffic Control Plan

-Storm Water Pollution Prevention Plan

-Environmental Permit, Issues And Commitments (EPIC)

Maintain ingress and egress to side streets and private property at all times.

Maintain ingress and egress to the frontage roads at all times.

Working day charges will start November 6, 2023.

Working days will be computed and charged in accordance with Article 8. 3.1.1. "Five-Day Workweek."

Incentive for early contract completion shall be based on contract administrative liquidated damage rates.

The road-user cost liquidated damages are \$7,856.00 per day.

90 day lead time is needed to allow for sufficient time to obtain and produce materials needed for various bid items in this project.

Item 110: Excavation

Broom the existing base or subgrade to remove any loose material dropped during excavation operations. This work is considered subsidiary to this item.

County: Pecos
Highway: IH 10

Control: 0140-02-050

Before excavation and embankment operations begin, windrow all topsoil (approx. 4 inches) to be reused on side slopes or behind the proposed curb and gutter. This work is subsidiary to Item 110, "Excavation" and Item 132, "Embankment".

Item 132: Embankment

For all material with a plasticity index of less than 20, use test method Tex-113-E in lieu of test method Tex-114-E for determining the percent of density.

Item 150: Blading

Use blading to construct and remove side road turnouts, rebuild existing dikes, ditch blocks, and other work as directed.

When directed, fill and grade low areas outside the embankment areas to drain.

Preserve the top 4" of topsoil outside of the work area. Preserve this material in windrows until topsoil can be replaced and seeded to stabilize all exposed terrain.

Item 432: Riprap

Reinforce all riprap on this project with no. 3 bars spaced 12 inches O.C.B.W. or no. 4 bars spaced at 18 inches O.C.B.W.

Broom finish all riprap on this project unless otherwise directed.

Polypropylene fiber may not be used in lieu of reinforcing steel.

In addition to reinforcing steel, polypropylene fiber is required at a rate of 1.5 lbs. /cy.

Item 502: Barricades, Signs, and Traffic Handling

Stop work immediately if any major traffic control element such as an advanced warning flashing panel or TMA or PCMS is not in good working order or control setup.

Maintain "No Center Line", "Do Not Pass" and "Pass With Care" signs until the permanent lane markings have been placed in accordance with plans.

This project has a regulatory work zone speed reduction within the project limits. The work zone speed limit is reduced from 80 mph to 65 mph. Placement of speed reduction zone signs shall comply with BC (3)-21. Speed resumption sign(s) is required at the end of a speed reduction zone.

Place chevrons, at a minimum, on every other drum used for outsides of curves, merging tapers and shifting tapers.

Vertical panels shall be self-righting.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer

County: Pecos
Highway: IH 10

Control: 0140-02-050

and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

When construction operations result in a drop-off of more than 2 inches, a 3:1 or flatter slope will be required. The slope must be constructed with a compacted material capable of supporting vehicles as approved by the Engineer. This work shall be done expeditiously during daylight hours. Flaggers and appropriate signing to safely guide traffic through the work area will be required as directed by the Engineer. This shall be considered subsidiary to Item 502.

Item 506: Temporary Erosion, Sedimentation, and Environmental Controls

In accordance with the Construction General Permit (CGP), erosion control and stabilization measures should be initiated as soon as practicable to include (list what our stabilization measures are – for example, replacing topsoil from windrow, erosion control blankets, seeding, etc.)

The total disturbed area for this project is 8.51 Acres. The disturbed area in this project, all project locations in the contract, and Contractor Project Specific Locations (PSLS), within 1 mile of the project limits, for the contract will further establish the authorization requirements for storm water discharges. The department will obtain an authorization to discharge storm water from the Texas Commission On Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain any required authorization from the TCEQ for any Contractor PSLS for construction support activities on or off the right of way. When the total area disturbed for all projects in the contract and PSLS within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLS on the right of way, to the Engineer (or to the appropriate MS4 operator when on an off-state system route).

Upon acceptance of the project, all SW3P devices will become property of the State and maintenance responsibility is transferred to the State until final stabilization is attained. (

Provide a minimum of two SW3P Signs. Obtain from the Engineer a copy of the project's completed TPDES Storm Water Program Construction Site Notice (TxDOT) and Contractor's copy of the Construction Site Notice. Laminate the sheets and bond with adhesive to 36" X 36" plywood sign blanks. Ensure the sheets remain dry. Apply Type C Blue reflective sheeting as the background and add the text "SW3P" in 5" white lettering, centered at the top. Attach the signs to approved temporary mounts and locate at each of the project limits just inside the right of way line at a readable height or as directed by the Engineer. If the sign cannot be placed outside the clear zone, it must adhere to the TMUTCD. SW3P signs, maintenance, and reposting (for replacement or as needed to ensure readability) will be subsidiary to Item 502.

Item 540: Metal Beam Guard Fence

Provide steel post for this project.

Item 644: Small Roadside Sign Assemblies

For standard small sign details and dimensions, refer to the "Standard Highway Sign Designs for Texas (SHSD)"; a supplement to the Texas Manual on Uniform Traffic Control Devices (TMUTCD)".

Locate and mark existing reference marker(s) perpendicular to the road and along the right of way, or as directed, prior to removal. Erect new reference marker(s) at the original location, upon completion of construction.

Only bolt clamp style slip bases will be allowed for sign assemblies. Set screws will not be allowed.

County: Pecos
 Highway: IH 10

Control: 0140-02-050

Item 6001: Portable Changeable Message Sign

PCMS shall be placed in operation a minimum of one (1) week prior to construction. Location(s) and duration for PCMS shall be as directed by the Engineer;

Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

There are no General Notes for additional shadow vehicle(s) with truck mounted attenuator (TMA) on TCP (5-1)-18; the shadow vehicle(s) with TMA specified on the traffic control plan as “required” is the quantity that has been estimated for this operation. BASIS OF ESTIMATE - STATIONARY

There are no General Notes for additional shadow vehicle(s) with truck mounted attenuator (TMA) on TCP (6-1)-12; the shadow vehicle(s) with TMA specified on the traffic control plan as “required” is the quantity that has been estimated for this operation. BASIS OF ESTIMATE - STATIONARY

The Contractor will be responsible for determining if one or more operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

BASIS OF ESTIMATE – STATIONARY

TCP STANDARD	TMA REQUIRED	TMA OPTIONAL	TOTAL
TCP(5-1)-18	1	0	1
TCP(6-1)-18	1	0	1



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0140-02-050





DISTRICT Odessa

COUNTY Pecos

HIGHWAY IH 10

CONTROL SECTION JOB				0140-02-050		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00176679			
COUNTY				Pecos			
HIGHWAY				IH 10			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	110-6001	EXCAVATION (ROADWAY)	CY	158.000		158.000	
	132-6007	EMBANKMENT (FINAL)(ORD COMP)(TY D)	CY	219.000		219.000	
	150-6002	BLADING	HR	40.000		40.000	
	164-6001	BROADCAST SEED (PERM) (RURAL) (SANDY)	SY	27,424.000		27,424.000	
	316-6065	AGGR(TY-A GR-1 SAC-A)	CY	96.000		96.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	1,530.000		1,530.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	7.000		7.000	
	506-6042	BIODEG EROSN CONT LOGS (IN STL) (18")	LF	1,440.000		1,440.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,440.000		1,440.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	200.000		200.000	
	540-6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	2.000		2.000	
	543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	40,166.000		40,166.000	
	543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EA	12.000		12.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	2.000		2.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	4.000		4.000	
	644-6030	IN SM RD SN SUP&AM TYS80(1)SA(T)	EA	8.000		8.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	4.000		4.000	
	6185-6002	TMA (STATIONARY)	DAY	248.000		248.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	

CK: JKB
 DW: MDM
 CK: JKB
 DW: MDM




**IH 10
 TYPICAL SECTIONS**

SHEET 1 OF 2


CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	6	

DATE:
 FILE:


CK: JKB
 DW: MDM
 CK: JKB
 DW: MDM




IH 10
 PROPOSED TYPICAL SECTION
 STA 607+60.00 TO STA 608+38.75



IH 10
 PROPOSED TYPICAL SECTION
 STA 608+38.75 TO STA 609+16.25
 STA 772+95.00 TO STA 774+51.25



CABLE BARRIER AND MOW STRIP DETAIL (LT)



CABLE BARRIER AND MOW STRIP DETAIL (RT)

FIRM REGISTRATION NO. F-230

IH 10
TYPICAL SECTIONS

SHEET 2 OF 2

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	7

DATE:
 FILE:


DATE:
 FILE:
 CK: JKB
 DNE: MDM

SUMMARY OF ROADWAY ITEMS


LOCATION	110	132	150	164	316	432	506	506	540	540	543	543	544	644	644
	6001	6007	6002	6001	6065	6045	6042	6043	6002	6016	6002	6020	6001	6004	6030
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)	BLADING	BROADCAST SEED (PERM) (RURAL) (SANDY)	AGGR (TY-A GR-1 SAC-A)	RIPRAP (MOW STRIP) (4 IN)	BIODEG EROSN CONT LOGS (INSTL) (18")	BIODEG EROSN CONT LOGS (REMOVE)	MTL W-BEAM GD FEN (STEEL POST)	DOWNSTREAM ANCHOR TERMINAL SECTION	CABLE BARRIER SYSTEM (TL-4)	CABLE BARRIER TERMINAL SECTION (TL-4)	GUARDRAIL END TREATMENT (INSTALL)	IN SM RD SN SUP&AM TY10BWG (1) SA (T)	IN SM RD SN SUP&AM TYS80 (1) SA (T)
	CY	CY	HR	SY	CY	CY	LF	LF	LF	EA	LF	EA	EA	EA	
PLAN LAYOUT (1 OF 18)	49	70		1484		84	60	60	100	1	2010	1	1		1
PLAN LAYOUT (2 OF 18)	26	32		1584	24	88	60	60			2269	2		1	
PLAN LAYOUT (3 OF 18)	6	8		1600		89	60	60			2400				
PLAN LAYOUT (4 OF 18)	5	8		1600		89	120	120			2400				1
PLAN LAYOUT (5 OF 18)	6	8		1600		89	60	60			2400				1
PLAN LAYOUT (6 OF 18)	5	8		1560	24	87	120	120			2233	2		1	
PLAN LAYOUT (7 OF 18)	5	8		1607		90	120	120			2400				1
PLAN LAYOUT (8 OF 18)	5	8		1701		96	60	60	100	1	2400		1		
PLAN LAYOUT (9 OF 18)	6	8		1600		89	60	60			2400				1
PLAN LAYOUT (10 OF 18)	5	8		1559	24	87	120	120			2232	2		1	
PLAN LAYOUT (11 OF 18)	7	8		1600		89	60	60			2400				1
PLAN LAYOUT (12 OF 18)	5	8		1600		89	60	60			2400				
PLAN LAYOUT (13 OF 18)	3	5		984		55	60	60			1369	2			1
PLAN LAYOUT (14 OF 18)	6	7		1577	24	88	60	60			2258	2		1	
PLAN LAYOUT (15 OF 18)	5	7		1600		89	120	120			2400				1
PLAN LAYOUT (16 OF 18)	6	7		1600		89	120	120			2396				
PLAN LAYOUT (17 OF 18)	6	7		1600		89	60	60			2400				
PLAN LAYOUT (18 OF 18)	2	4		968		54	60	60			1399	1			
PROJECT TOTALS	158	219	40	27424	96	1530	1440	1440	200	2	40166	12	2	4	8

SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS

LOCATION	6001	6185
	6002	6002
	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)
	EA	DAY
PLAN LAYOUT (1 OF 18)		
PLAN LAYOUT (2 OF 18)		
PLAN LAYOUT (3 OF 18)		
PLAN LAYOUT (4 OF 18)		
PLAN LAYOUT (5 OF 18)		
PLAN LAYOUT (6 OF 18)		
PLAN LAYOUT (7 OF 18)		
PLAN LAYOUT (8 OF 18)		
PLAN LAYOUT (9 OF 18)		
PLAN LAYOUT (10 OF 18)		
PLAN LAYOUT (11 OF 18)		
PLAN LAYOUT (12 OF 18)		
PLAN LAYOUT (13 OF 18)		
PLAN LAYOUT (14 OF 18)		
PLAN LAYOUT (15 OF 18)		
PLAN LAYOUT (16 OF 18)		
PLAN LAYOUT (17 OF 18)		
PLAN LAYOUT (18 OF 18)		
PROJECT TOTALS	4	248



FIRM REGISTRATION NO. F-230



IH 10

SUMMARY OF QUANTITIES

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	8	



DATE:
 FILE:

DATE:
 FILE:
 DNE:MDM
 CK:JKB
 CK:JKB
 DNE:MDM

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
				EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)		
SF	SF	FT	CY	CY	CY	CY	
607+55							
608+00	0.43	1.04	45	0.00	0.00	0.0	0.0
609+00	0.50	0.97	100	0.87	1.78	0.9	1.8
610+00	0.56	0.93	100	1.95	3.52	2.8	5.3
611+00	0.49	1.02	100	1.94	3.61	4.8	8.9
612+00	0.66	0.90	100	2.13	3.55	6.9	12.5
613+00	0.72	0.90	100	2.56	3.32	9.5	15.8
614+00	0.59	0.93	100	2.42	3.37	11.9	19.1
615+00	0.60	0.93	100	2.19	3.44	14.1	22.6
616+00	0.63	0.90	100	2.28	3.40	16.3	26.0
617+00	0.66	0.91	100	2.40	3.36	18.7	29.3
618+00	0.59	0.93	100	2.32	3.41	21.1	32.8
619+00	0.54	0.96	100	2.09	3.50	23.1	36.3
620+00	0.68	0.87	100	2.25	3.39	25.4	39.6
621+00	0.65	0.89	100	2.46	3.26	27.9	42.9
622+00	0.69	0.89	100	2.47	3.31	30.3	46.2
623+00	0.71	0.90	100	2.59	3.31	32.9	49.5
624+00	0.68	0.90	100	2.58	3.32	35.5	52.8
625+00	0.81	0.92	100	2.77	3.36	38.3	56.2
626+00	0.79	0.91	100	2.96	3.39	41.2	59.6
627+00	0.74	0.90	100	2.83	3.36	44.1	62.9
628+00	0.69	0.90	100	2.64	3.34	46.7	66.3
629+00	0.59	0.92	100	2.37	3.38	49.1	69.7
630+00	0.66	0.92	100	0.73	1.06	49.8	70.7
631+00	0.71	0.88	100	0.46	0.61	50.3	71.3
632+00	0.49	0.96	100	0.11	0.20	50.4	71.5
633+00	0.63	0.91	100	1.09	1.69	51.5	73.2
634+00	0.54	0.96	100	0.82	1.27	52.3	74.5
635+00	0.90	0.89	100	0.66	0.80	52.9	75.3
636+00	0.74	0.90	100	0.31	0.38	53.2	75.7
637+00	0.65	0.90	100	1.56	1.88	54.8	77.6
638+00	0.67	0.87	100	1.03	1.38	55.8	78.9
639+00	0.75	0.88	100	0.82	0.97	56.7	79.9
640+00	0.80	0.89	100	0.49	0.56	57.2	80.5
641+00	0.71	0.89	100	0.11	0.14	57.3	80.6
642+00	0.95	1.02	100	1.41	1.71	58.7	82.3
643+00	0.90	0.93	100	1.16	1.17	59.8	83.5
644+00	0.89	0.91	100	0.75	0.77	60.6	84.2
645+00	0.72	0.89	100	0.25	0.32	60.8	84.6
646+00	0.82	0.88	100	1.47	1.76	62.3	86.3
647+00	0.87	0.95	100	1.31	1.43	63.6	87.7
648+00	0.76	0.89	100	3.01	3.41	66.6	91.2
649+00	0.72	0.90	100	2.74	3.32	69.4	94.5
650+00	0.74	0.90	100	2.71	3.33	72.1	97.8
651+00	0.69	0.90	100	2.64	3.33	74.7	101.1

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
				EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)		
SF	SF	FT	CY	CY	CY	CY	
652+00	0.64	0.93	100	0.00	0.00	74.7	101.1
653+00	0.75	0.90	100	0.28	0.33	75.0	101.5
654+00	0.63	0.93	100	0.23	0.34	75.2	101.8
655+00	0.77	0.90	100	0.29	0.33	75.5	102.1
656+00	0.58	0.93	100	0.21	0.35	75.7	102.5
657+00	0.65	0.91	100	0.24	0.34	75.9	102.8
658+00	0.58	0.94	100	0.21	0.35	76.2	103.2
659+00	0.53	0.97	100	0.20	0.35	76.4	103.5
660+00	0.65	0.89	100	0.24	0.34	76.6	103.9
661+00	0.65	0.91	100	0.24	0.34	76.8	104.2
662+00	0.61	0.97	100	0.23	0.35	77.1	104.5
663+00	0.50	1.03	100	0.19	0.37	77.3	104.9
664+00	0.48	1.02	100	0.18	0.37	77.4	105.3
665+00	0.44	1.03	100	0.16	0.38	77.6	105.7
666+00	0.62	0.91	100	0.23	0.34	77.8	106.0
667+00	0.66	0.90	100	0.25	0.33	78.1	106.3
668+00	0.66	0.90	100	0.24	0.33	78.3	106.7
669+00	0.58	0.92	100	0.21	0.34	78.5	107.0
670+00	0.61	0.91	100	0.22	0.34	78.8	107.4
671+00	0.72	0.89	100	0.26	0.33	79.0	107.7
672+00	0.69	0.91	100	0.26	0.34	79.3	108.0
673+00	0.64	0.91	100	0.24	0.34	79.5	108.4
674+00	0.62	0.93	100	0.24	0.34	79.8	108.7
675+00	0.68	0.89	100	0.25	0.33	80.0	109.0
676+00	0.68	0.90	100	0.26	0.33	80.3	109.4
677+00	0.66	0.90	100	0.25	0.33	80.5	109.7
678+00	0.65	0.91	100	0.25	0.34	80.7	110.0
679+00	0.67	0.89	100	0.25	0.33	81.0	110.4
680+00	0.63	0.89	100	0.23	0.33	81.2	110.7
681+00	0.44	1.13	100	0.24	0.39	81.5	111.1
682+00	0.67	0.88	100	0.25	0.33	81.7	111.4
683+00	0.58	0.92	100	0.21	0.35	81.9	111.8
684+00	0.55	0.99	100	0.21	0.36	82.1	112.1
685+00	0.60	0.95	100	0.22	0.35	82.3	112.5
686+00	0.56	0.94	100	0.21	0.35	82.6	112.8
687+00	0.65	0.90	100	0.24	0.34	82.8	113.1
688+00	0.68	0.91	100	0.26	0.34	83.1	113.5
689+00	0.64	0.92	100	0.24	0.34	83.3	113.8
690+00	0.64	0.93	100	0.25	0.34	83.5	114.2
691+00	0.68	0.90	100	0.25	0.33	83.8	114.5
692+00	0.59	0.94	100	0.22	0.35	84.0	114.8
693+00	0.60	0.96	100	0.22	0.36	84.2	115.2
694+00	0.71	0.88	100	0.26	0.33	84.5	115.5
695+00	0.70	0.88	100	0.26	0.33	84.7	115.9
696+00	0.59	0.98	100	0.20	0.37	84.9	116.2
697+00	0.49	1.02	100	0.19	0.37	85.1	116.6

FIRM REGISTRATION NO. F-230

IH 10
 SUMMARY OF
 EARTHWORK
 QUANTITIES

SHEET 1 OF 5

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY		SHEET NO.
ODA	PECOS		9


DATE: FILE:

DATE:
 FILE:
 DNE:MDM
 CK:JKB
 CK:JKB
 DNE:MDM

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
698+00	0.68	0.89	100	0.25	0.34	85.4	116.9
699+00	0.47	1.06	100	0.17	0.40	85.6	117.3
700+00	0.53	0.98	100	0.20	0.36	85.7	117.7
701+00	0.64	0.90	100	0.24	0.33	86.0	118.0
702+00	0.63	0.91	100	0.23	0.34	86.2	118.4
703+00	0.66	0.90	100	0.24	0.34	86.5	118.7
704+00	0.63	0.91	100	0.23	0.34	86.7	119.1
705+00	0.65	0.89	100	0.23	0.34	86.9	119.4
706+00	0.71	0.90	100	0.26	0.33	87.2	119.7
707+00	0.59	0.94	100	0.22	0.34	87.4	120.1
708+00	0.62	0.91	100	0.23	0.34	87.6	120.4
709+00	0.57	0.96	100	0.21	0.35	87.8	120.8
710+00	0.71	0.90	100	0.25	0.34	88.1	121.1
711+00	0.69	0.90	100	0.25	0.33	88.3	121.4
712+00	0.62	0.92	100	0.24	0.34	88.6	121.8
713+00	0.61	0.92	100	0.23	0.34	88.8	122.1
714+00	0.61	0.91	100	0.23	0.34	89.0	122.4
715+00	0.68	0.91	100	0.25	0.34	89.3	122.8
716+00	0.75	0.89	100	0.27	0.33	89.5	123.1
717+00	0.63	0.90	100	0.23	0.34	89.8	123.4
718+00	0.57	0.95	100	0.22	0.35	90.0	123.8
719+00	0.54	0.99	100	0.20	0.36	90.2	124.2
720+00	0.65	0.90	100	0.23	0.34	90.4	124.5
721+00	0.49	1.07	100	0.21	0.37	90.6	124.9
722+00	0.68	0.87	100	0.25	0.33	90.9	125.2
723+00	0.69	0.88	100	0.25	0.33	91.1	125.5
724+00	0.62	0.90	100	0.24	0.33	91.4	125.9
725+00	0.58	0.93	100	0.22	0.34	91.6	126.2
726+00	0.45	1.11	100	0.18	0.40	91.8	126.6
727+00	0.41	1.19	100	0.15	0.44	91.9	127.0
728+00	0.55	0.94	100	0.20	0.35	92.1	127.4
729+00	0.55	0.94	100	0.20	0.35	92.3	127.7
730+00	0.65	0.89	100	0.00	0.00	92.3	127.7
731+00	0.63	0.91	100	0.00	0.00	92.3	127.7
732+00	0.70	0.86	100	0.23	0.34	92.6	128.1
733+00	0.62	0.88	100	0.26	0.32	92.8	128.4
734+00	0.63	0.93	100	0.22	0.34	93.0	128.7
735+00	0.50	1.04	100	0.23	0.34	93.3	129.1
736+00	0.52	0.96	100	0.19	0.38	93.4	129.4
737+00	0.53	0.96	100	0.19	0.36	93.6	129.8
738+00	0.63	0.88	100	0.20	0.36	93.8	130.2
739+00	0.64	0.89	100	0.23	0.33	94.1	130.5
740+00	0.66	0.92	100	0.24	0.33	94.3	130.8
741+00	0.65	0.89	100	0.24	0.34	94.5	131.1
742+00	0.65	0.88	100	0.24	0.33	94.8	131.5
743+00	0.51	0.96	100	0.24	0.33	95.0	131.8

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
744+00	0.58	0.94	100	0.19	0.35	95.2	132.2
745+00	0.44	1.20	100	0.21	0.35	95.4	132.5
746+00	0.62	0.91	100	0.16	0.41	95.6	132.9
747+00	0.66	0.88	100	0.23	0.34	95.8	133.3
748+00	0.61	0.92	100	0.24	0.33	96.1	133.6
749+00	0.59	0.94	100	0.23	0.34	96.3	133.9
750+00	0.52	0.99	100	0.23	0.34	96.5	134.3
751+00	0.67	0.89	100	0.19	0.36	96.7	134.6
752+00	0.69	0.90	100	0.25	0.33	97.0	134.9
753+00	0.57	0.94	100	0.26	0.33	97.2	135.3
754+00	0.58	0.92	100	0.21	0.35	97.4	135.6
755+00	0.61	0.91	100	0.21	0.34	97.6	136.0
756+00	0.61	0.93	100	0.23	0.34	97.9	136.3
757+00	0.61	0.92	100	0.23	0.34	98.1	136.6
758+00	0.65	0.89	100	0.23	0.34	98.3	137.0
759+00	0.66	0.91	100	0.24	0.33	98.6	137.3
760+00	0.71	0.90	100	0.24	0.34	98.8	137.7
761+00	0.60	0.94	100	0.26	0.33	99.1	138.0
762+00	0.55	0.96	100	0.22	0.35	99.3	138.3
763+00	0.60	0.92	100	0.21	0.36	99.5	138.7
764+00	0.61	0.91	100	0.22	0.34	99.7	139.0
765+00	0.58	0.98	100	0.22	0.34	99.9	139.4
766+00	0.58	0.97	100	0.22	0.36	100.1	139.7
767+00	0.55	0.96	100	0.22	0.36	100.4	140.1
768+00	0.60	0.92	100	0.20	0.35	100.6	140.4
769+00	0.56	0.94	100	0.22	0.34	100.8	140.8
770+00	0.55	0.93	100	0.21	0.35	101.0	141.1
771+00	0.51	1.00	100	0.20	0.35	101.2	141.5
772+00	0.56	0.96	100	0.19	0.37	101.4	141.9
773+00	0.65	0.91	100	0.20	0.35	101.6	142.2
774+00	0.68	0.88	100	0.24	0.34	101.8	142.6
775+00	0.62	0.94	100	0.25	0.33	102.1	142.9
776+00	0.68	0.91	100	0.23	0.34	102.3	143.2
777+00	0.67	0.90	100	0.25	0.34	102.5	143.6
778+00	0.65	0.90	100	0.25	0.33	102.8	143.9
779+00	0.65	0.94	100	0.24	0.33	103.0	144.2
780+00	0.67	0.88	100	0.24	0.34	103.3	144.6
781+00	0.66	0.90	100	0.25	0.33	103.5	144.9
782+00	0.60	0.94	100	0.24	0.33	103.8	145.2
783+00	0.57	0.92	100	0.22	0.34	104.0	145.6
784+00	0.64	0.91	100	0.21	0.34	104.2	145.9
785+00	0.68	0.87	100	0.24	0.34	104.4	146.2
786+00	0.57	0.94	100	0.25	0.33	104.7	146.6
787+00	0.51	1.00	100	0.21	0.35	104.9	146.9
788+00	0.61	0.93	100	0.19	0.37	105.1	147.3
789+00	0.59	0.99	100	0.23	0.35	105.3	147.6

FIRM REGISTRATION NO. F-230



Texas Department of Transportation
 IH 10
 SUMMARY OF EARTHWORK QUANTITIES

SHEET 2 OF 5

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	10


DATE: FILE:

DATE:
 FILE:
 DNE:MDM
 CK:JKB
 DNE:MDM
 CK:JKB

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
790+00	0.89	0.00	100	3.42	0.00	369.8	7.6
791+00	0.98	0.00	100	3.47	0.00	373.3	7.6
792+00	1.06	0.00	100	3.78	0.00	377.1	7.6
793+00	0.95	0.00	100	3.71	0.00	380.8	7.6
794+00	0.88	0.00	100	3.38	0.00	384.2	7.6
795+00	0.30	0.38	100	2.18	0.70	386.4	8.3
796+00	0.99	0.00	100	2.39	0.70	388.8	9.1
797+00	1.01	0.00	100	3.70	0.00	392.5	9.1
798+00	0.94	0.00	100	3.60	0.00	396.1	9.1
799+00	1.02	0.00	100	3.64	0.00	399.7	9.1
800+00	0.99	0.00	100	3.73	0.00	403.4	9.1
801+00	0.95	0.00	100	3.60	0.00	407.0	9.1
802+00	0.97	0.00	100	3.57	0.00	410.6	9.1
803+00	0.92	0.00	100	3.51	0.00	414.1	9.1
804+00	0.94	0.00	100	3.44	0.00	417.5	9.1
805+00	0.98	0.00	100	3.55	0.00	421.1	9.1
806+00	0.96	0.00	100	3.59	0.00	424.7	9.1
807+00	0.94	0.00	100	3.51	0.00	428.2	9.1
808+00	0.94	0.00	100	3.49	0.00	431.7	9.1
809+00	0.93	0.00	100	3.47	0.00	435.1	9.1
810+00	0.83	0.00	100	3.26	0.00	438.4	9.1
811+00	0.89	0.00	100	3.17	0.00	441.6	9.1
812+00	0.42	0.05	100	2.41	0.10	444.0	9.1
813+00	1.08	0.00	100	2.76	0.10	446.7	9.2
814+00	0.89	0.00	100	3.65	0.00	450.4	9.2
815+00	0.84	0.00	100	3.21	0.00	453.6	9.2
816+00	0.92	0.00	100	3.25	0.00	456.9	9.2
817+00	0.85	0.00	100	3.28	0.00	460.1	9.2
818+00	0.93	0.00	100	3.31	0.00	463.4	9.2
819+00	0.91	0.00	100	3.41	0.00	466.8	9.2
820+00	0.85	0.00	100	3.26	0.00	470.1	9.2
821+00	0.81	0.00	100	3.07	0.00	473.2	9.2
822+00	0.86	0.00	100	3.08	0.00	476.3	9.2
823+00	0.83	0.00	100	3.13	0.00	479.4	9.2
824+00	0.81	0.00	100	3.04	0.00	482.4	9.2
825+00	0.89	0.00	100	3.14	0.00	485.6	9.2
826+00	0.82	0.00	100	3.15	0.00	488.7	9.2
827+00	0.83	0.00	100	3.05	0.00	491.8	9.2
828+00	0.89	0.00	100	3.20	0.00	495.0	9.2
829+00	0.64	0.00	100	2.84	0.00	497.8	9.2
830+00	0.00	0.00	100	1.80	0.00	499.6	9.2
831+00	0.48	0.00	100	0.52	0.00	500.1	9.2
832+00	0.34	0.18	100	1.53	0.33	501.6	9.6
833+00	0.46	0.01	100	1.48	0.33	503.1	9.9
834+00	0.42	0.02	100	1.62	0.04	504.7	9.9
835+00	0.34	0.29	100	1.40	0.57	506.1	10.5

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
836+00	0.60	0.95	100	0.25	0.34	116.0	163.5
837+00	0.60	0.92	100	0.21	0.35	116.2	163.8
838+00	0.75	0.88	100	0.25	0.33	116.4	164.2
839+00	0.64	0.90	100	0.24	0.33	116.7	164.5
840+00	0.81	0.88	100	0.30	0.33	117.0	164.8
841+00	0.50	1.03	100	0.20	0.37	117.2	165.2
842+00	0.55	0.96	100	0.21	0.35	117.4	165.5
843+00	0.68	0.88	100	0.23	0.33	117.6	165.9
844+00	0.60	0.92	100	0.21	0.34	117.8	166.2
845+00	0.49	1.05	100	0.21	0.37	118.0	166.6
846+00	0.55	0.97	100	0.22	0.35	118.3	166.9
847+00	0.53	0.98	100	0.20	0.36	118.5	167.3
848+00	0.66	0.90	100	0.25	0.33	118.7	167.6
849+00	0.66	0.90	100	0.24	0.33	118.9	168.0
850+00	0.57	0.94	100	0.21	0.35	119.2	168.3
851+00	0.61	0.92	100	0.22	0.35	119.4	168.7
852+00	0.62	0.91	100	0.21	0.38	119.6	169.0
853+00	0.72	0.89	100	0.27	0.33	119.9	169.4
854+00	0.81	0.91	100	0.30	0.34	120.2	169.7
855+00	0.82	0.91	100	0.29	0.34	120.4	170.0
856+00	0.57	0.94	100	0.21	0.35	120.7	170.4
857+00	0.81	0.92	100	0.31	0.34	121.0	170.7
858+00	0.93	0.96	100	0.33	0.35	121.3	171.1
859+00	0.92	0.96	100	0.34	0.36	121.6	171.4
860+00	0.88	0.90	100	0.32	0.33	122.0	171.8
861+00	0.92	0.89	100	0.34	0.33	122.3	172.1
862+00	0.87	0.88	100	0.31	0.33	122.6	172.4
863+00	0.69	0.88	100	0.27	0.32	122.9	172.8
864+00	0.78	0.88	100	0.29	0.34	123.2	173.1
865+00	0.82	0.90	100	0.30	0.33	123.5	173.4
866+00	0.76	0.89	100	0.28	0.33	123.8	173.8
867+00	0.80	0.90	100	0.30	0.34	124.1	174.1
868+00	0.76	0.88	100	0.29	0.32	124.3	174.4
869+00	0.69	0.87	100	0.26	0.32	124.6	174.7
870+00	0.64	0.90	100	0.24	0.33	124.8	175.1
871+00	0.61	0.90	100	0.23	0.33	125.1	175.4
872+00	0.67	0.86	100	0.25	0.32	125.3	175.7
873+00	0.67	0.87	100	0.25	0.32	125.6	176.0
874+00	0.64	0.86	100	0.24	0.32	125.8	176.4
875+00	0.60	0.91	100	0.23	0.33	126.0	176.7
876+00	0.62	0.90	100	0.22	0.34	126.2	177.0
877+00	0.72	0.87	100	0.26	0.32	126.5	177.4
878+00	0.74	0.91	100	0.28	0.34	126.8	177.7
879+00	0.70	0.88	100	0.26	0.33	127.0	178.0
880+00	0.59	0.96	100	0.22	0.35	127.3	178.4
881+00	0.64	0.88	100	0.23	0.33	127.5	178.7

FIRM REGISTRATION NO. F-230



Texas Department of Transportation
 IH 10
 SUMMARY OF EARTHWORK QUANTITIES

SHEET 3 OF 5

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	11

DATE: FILE:

DATE:
 FILE:
 DNE:MDM
 CK:JKB
 CK:JKB
 DNE:MDM

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
882+00	0.64	0.92	100	0.24	0.34	127.7	179.0
883+00	0.63	0.90	100	0.23	0.33	128.0	179.4
884+00	0.62	0.89	100	0.23	0.33	128.2	179.7
885+00	0.61	0.92	100	0.23	0.34	128.4	180.0
886+00	0.61	0.90	100	0.22	0.34	128.6	180.4
887+00	0.50	1.04	100	0.19	0.37	128.8	180.7
888+00	0.55	0.95	100	0.20	0.35	129.0	181.1
889+00	0.55	0.95	100	0.20	0.35	129.2	181.5
890+00	0.53	1.00	100	0.20	0.36	129.4	181.8
891+00	0.63	0.90	100	0.23	0.34	129.7	182.1
892+00	0.49	1.02	100	0.19	0.37	129.9	182.5
893+00	0.56	0.93	100	0.20	0.36	130.0	182.9
894+00	0.60	0.92	100	0.22	0.35	130.3	183.2
895+00	0.68	0.89	100	0.26	0.33	130.5	183.5
896+00	0.76	0.88	100	0.28	0.33	130.8	183.9
897+00	0.92	0.89	100	0.34	0.33	131.1	184.2
898+00	0.00	0.00	100	0.00	0.00	131.1	184.2
899+00	0.00	0.00	100	0.00	0.00	131.1	184.2
900+00	0.00	0.00	100	0.00	0.00	131.1	184.2
901+00	0.00	0.00	100	0.00	0.00	131.1	184.2
902+00	0.00	0.00	100	0.00	0.00	131.1	184.2
903+00	0.00	0.00	100	0.00	0.00	131.1	184.2
904+00	0.00	0.00	100	0.00	0.00	131.1	184.2
905+00	0.00	0.00	100	0.00	0.00	131.1	184.2
906+00	0.00	0.00	100	0.00	0.00	131.1	184.2
907+00	0.58	0.94	100	0.00	0.00	131.1	184.2
908+00	0.43	1.15	100	0.15	0.44	131.3	184.6
909+00	0.56	0.93	100	0.21	0.35	131.5	185.0
910+00	0.65	0.90	100	0.22	0.34	131.7	185.3
911+00	0.58	0.90	100	0.21	0.33	131.9	185.7
912+00	0.59	0.92	100	0.22	0.34	132.2	186.0
913+00	0.57	0.92	100	0.22	0.34	132.4	186.3
914+00	0.61	0.91	100	0.23	0.34	132.6	186.7
915+00	0.56	0.95	100	0.21	0.35	132.8	187.0
916+00	0.50	0.93	100	0.19	0.35	133.0	187.4
917+00	0.67	0.87	100	0.25	0.32	133.2	187.7
918+00	0.60	0.91	100	0.22	0.34	133.5	188.0
919+00	0.67	0.88	100	0.24	0.33	133.7	188.4
920+00	0.81	0.91	100	0.30	0.34	134.0	188.7
921+00	0.58	0.89	100	0.21	0.33	134.2	189.0
922+00	0.86	0.87	100	0.30	0.32	134.5	189.3
923+00	0.55	0.77	100	0.00	0.00	134.5	189.3
924+00	0.55	0.76	100	0.21	0.28	134.7	189.6
925+00	0.56	0.76	100	0.22	0.28	134.9	189.9
926+00	0.68	0.75	100	0.24	0.28	135.2	190.2
927+00	0.61	0.76	100	0.23	0.28	135.4	190.5

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
928+00	0.61	0.76	100	0.22	0.28	135.6	190.8
929+00	0.64	0.75	100	0.23	0.28	135.9	191.0
930+00	0.59	0.76	100	0.22	0.28	136.1	191.3
931+00	0.65	0.76	100	0.24	0.28	136.3	191.6
932+00	0.56	0.76	100	0.16	0.19	136.5	191.8
933+00	0.67	0.75	100	0.24	0.28	136.7	192.1
934+00	1.54	0.74	100	0.52	0.27	137.2	192.3
935+00	1.41	0.73	100	0.54	0.27	137.8	192.6
936+00	1.00	0.74	100	0.38	0.27	138.1	192.9
937+00	0.72	0.75	100	0.27	0.28	138.4	193.2
938+00	0.92	0.74	100	0.33	0.27	138.7	193.4
939+00	0.45	0.77	100	0.20	0.28	138.9	193.7
940+00	0.68	0.75	100	0.24	0.28	139.2	194.0
941+00	0.75	0.75	100	0.28	0.28	139.5	194.3
942+00	0.75	0.74	100	0.28	0.28	139.7	194.5
943+00	0.78	0.74	100	0.30	0.28	140.0	194.8
944+00	0.67	0.75	100	0.26	0.28	140.3	195.1
945+00	0.79	0.74	100	0.32	0.27	140.6	195.4
946+00	1.49	0.73	100	0.61	0.27	141.2	195.6
947+00	0.55	0.77	100	0.22	0.28	141.4	195.9
948+00	0.55	0.76	100	0.23	0.28	141.7	196.2
949+00	0.59	0.76	100	0.22	0.28	141.9	196.5
950+00	0.53	0.77	100	0.19	0.29	142.1	196.8
951+00	0.66	0.75	100	0.24	0.28	142.3	197.1
952+00	0.66	0.75	100	0.25	0.28	142.6	197.3
953+00	0.66	0.75	100	0.24	0.28	142.8	197.6
954+00	0.69	0.75	100	0.24	0.28	143.1	197.9
955+00	0.66	0.76	100	0.25	0.28	143.3	198.2
956+00	0.59	0.76	100	0.22	0.28	143.5	198.5
957+00	0.59	0.76	100	0.21	0.28	143.7	198.7
958+00	0.41	0.78	100	0.17	0.29	143.9	199.0
959+00	0.33	0.79	100	0.12	0.29	144.0	199.3
960+00	0.31	0.79	100	0.14	0.29	144.2	199.6
961+00	0.37	0.78	100	0.14	0.29	144.3	199.9
962+00	0.27	0.79	100	0.11	0.29	144.4	200.2
963+00	0.29	0.79	100	0.11	0.29	144.5	200.5
964+00	0.33	0.79	100	0.11	0.29	144.6	200.8
965+00	0.37	0.78	100	0.13	0.29	144.8	201.1
966+00	0.37	0.79	100	0.14	0.29	144.9	201.4
967+00	0.56	0.77	100	0.22	0.28	145.1	201.6
968+00	0.72	0.75	100	0.27	0.28	145.4	201.9
969+00	0.77	0.74	100	0.27	0.28	145.6	202.2
970+00	1.15	0.73	100	0.37	0.27	146.0	202.5
971+00	0.75	0.75	100	0.27	0.28	146.3	202.7
972+00	0.75	0.75	100	0.27	0.28	146.6	203.0
973+00	0.69	0.75	100	0.26	0.28	146.8	203.3

FIRM REGISTRATION NO. F-230

Texas Department of Transportation

IH 10

SUMMARY OF EARTHWORK QUANTITIES

SHEET 4 OF 5


CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	12

DATE:
 FILE:


DATE:
 FILE:
 DNE:MDM
 CK:JKB
 DNE:MDM
 CK:JKB

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
974+00	0.81	0.74	100	0.28	0.28	147.1	203.6
975+00	0.59	0.76	100	0.22	0.28	147.3	203.8
976+00	0.57	0.76	100	0.22	0.28	147.5	204.1
977+00	0.75	0.75	100	0.26	0.28	147.8	204.4
978+00	0.53	0.77	100	0.11	0.16	147.9	204.6
979+00	0.52	0.77	100	0.19	0.29	148.1	204.8
980+00	0.53	0.77	100	0.19	0.29	148.3	205.1
981+00	0.61	0.76	100	0.21	0.28	148.5	205.4
982+00	0.77	0.74	100	0.28	0.28	148.8	205.7
983+00	0.50	0.77	100	0.19	0.29	149.0	206.0
984+00	0.49	0.77	100	0.14	0.21	149.1	206.2
985+00	0.49	0.77	100	0.20	0.28	149.3	206.5
986+00	0.54	0.77	100	0.20	0.28	149.5	206.8
987+00	0.61	0.76	100	0.21	0.28	149.7	207.0
988+00	1.24	0.74	100	0.45	0.27	150.1	207.3
989+00	0.76	0.74	100	0.36	0.27	150.5	207.6
990+00	0.66	0.75	100	0.25	0.28	150.8	207.9
991+00	0.59	0.76	100	0.22	0.28	151.0	208.1
992+00	0.63	0.76	100	0.24	0.28	151.2	208.4
993+00	0.69	0.75	100	0.24	0.28	151.5	208.7
994+00	0.73	0.75	100	0.27	0.28	151.7	209.0
995+00	0.78	0.74	100	0.28	0.28	152.0	209.3
996+00	0.66	0.75	100	0.24	0.28	152.2	209.5
997+00	0.88	0.74	100	0.30	0.28	152.5	209.8
998+00	1.10	0.74	100	0.39	0.27	152.9	210.1
999+00	0.64	0.76	100	0.24	0.28	153.2	210.4
1000+00	0.68	0.75	100	0.26	0.28	153.4	210.6
1001+00	0.82	0.74	100	0.27	0.28	153.7	210.9
1002+00	1.56	0.73	100	0.54	0.27	154.2	211.2
1003+00	0.71	0.75	100	0.27	0.28	154.5	211.5
1004+00	0.65	0.75	100	0.25	0.28	154.7	211.8
1005+00	0.50	0.77	100	0.20	0.28	154.9	212.0
1006+00	0.37	0.78	100	0.15	0.29	155.1	212.3
1007+00	0.34	0.78	100	0.13	0.29	155.2	212.6
1008+00	0.42	0.78	100	0.14	0.29	155.4	212.9
1009+00	0.49	0.77	100	0.18	0.29	155.5	213.2
1010+00	0.55	0.77	100	0.22	0.28	155.8	213.5
1011+00	0.46	0.77	100	0.17	0.29	155.9	213.8
1012+00	0.43	0.78	100	0.17	0.29	156.1	214.0
1013+00	0.37	0.78	100	0.15	0.29	156.2	214.3
1014+00	0.37	0.78	100	0.15	0.29	156.4	214.6
1015+00	0.40	0.78	100	0.14	0.29	156.5	214.9
1016+00	0.41	0.78	100	0.15	0.29	156.7	215.2
1017+00	0.42	0.78	100	0.15	0.29	156.8	215.5
1018+00	0.39	0.78	100	0.16	0.29	157.0	215.8
1019+00	0.33	0.79	100	0.13	0.29	157.1	216.1

SUMMARY OF EARTHWORK QUANTITIES							
STATION	END AREA		DISTANCE BETWEEN CROSS SECTIONS	VOLUME		CUMULATIVE VOLUME	
	EXCAVATION	EMBANKMENT		110	132	EXCAVATION	EMBANKMENT
				6001	6007		
			EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY D)			
1020+00	0.92	0.00	100	3.35	0.00	879.3	48.1
1021+00	0.59	0.00	100	2.78	0.00	882.1	48.1
1022+00	0.63	0.00	100	2.25	0.00	884.4	48.1
1023+00	0.76	0.00	100	2.57	0.00	886.9	48.1
1024+00	0.61	0.00	100	2.53	0.00	889.5	48.1
1025+00	0.59	0.00	100	2.22	0.00	891.7	48.1
1026+00	0.43	0.03	100	1.89	0.06	893.6	48.1
1027+00	0.40	0.17	100	1.54	0.38	895.1	48.5
1027+12	0.41	0.04	12	0.19	0.05	895.3	48.6



 FIRM REGISTRATION NO. F-230



IH 10

SUMMARY OF EARTHWORK QUANTITIES

SHEET 5 OF 5

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY		SHEET NO.
ODA	PECOS		13

DATE: FILE:


CK: _____
 DW: _____
 CK: _____
 DW: _____

SEQUENCE OF CONSTRUCTION


1. PLACE ADVANCE WARNING SIGNS, TRAFFIC CONTROL DEVICES, AND SIGNS IN ACCORDANCE WITH TRAFFIC CONTROL STANDARDS, TMUTCD, AND GENERAL NOTES.
2. USING DAYTIME CLOSURES, CLOSE THE INSIDE LANE ADJACENT TO CABLE BARRIER CONSTRUCTION USING TXDOT STANDARD TCP(6-1)-12 AND CLOSE THE INSIDE SHOULDER OPPOSITE OF CABLE CABLE USING TXDOT STANDARD TCP(5-1)-18. LIMIT LANE CLOSURES TO 2 MILE SEGMENTS.
3. PLACE EROSION CONTROL LOGS AT INLETS AS SHOWN IN THE MEDIAN BARRIER LAYOUTS.
4. CONSTRUCT MOW STRIP AND INSTALL CABLE BARRIER AS SHOWN ON MEDIAN BARRIER LAYOUTS.
5. PLACE EMERGENCY CROSSING SIGNS AS SHOWN IN THE MEDIAN BARRIER LAYOUTS.
6. GRADE THE SIDE SLOPES TO MEET A TYPICAL 6:1 SLOPE.
7. CLEAN UP AND REMOVE TRAFFIC CONTROL DEVICES.

GENERAL NOTES

1. ALL EXISTING SIGNS ON OPEN ROADWAYS THAT ARE NOT IN CONFLICT WITH THE CONSTRUCTION AND TRAFFIC SHALL REMAIN IN PLACE UNLESS OTHERWISE DIRECTED TXDOT. SIGNS THAT ARE IN CONFLICT, SHALL BE COVERED OR REMOVED, STORED AND REPLACED IN FINAL LOCATION IF NOT BEING REPLACED.
2. CONTRACTOR SHALL ERECT REQUIRED CONSTRUCTION AND TRAFFIC CONTROL SIGNS PRIOR TO DETOUR OF TRAFFIC.
3. THE CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE DURING CONSTRUCTION.
4. TEMPORARY SW3P EROSION & SEDIMENT CONTROL MEASURES SHALL ONLY BE PLACED IN AREAS WHERE SOIL DISTURBANCE IS EXPECTED TO OCCUR WITHIN TWO WEEKS.
5. TEMPORARY SW3P EROSION CONTROL MEASURES SHALL BE REMOVED IN EACH AREA WITHIN TWO WEEKS OF VEGETATION ESTABLISHMENT OR AS APPROVED BY THE ENGINEER.
6. LANE CLOSURES SHALL BE LIMITED TO THE LENGTH NEEDED TO COMPLETE ONE DAY'S WORK.
7. LANE CLOSURES SHALL BE BETWEEN 7:00 AM AND 5:00 PM.
8. EQUIPMENT SHALL NOT BE STORED IN THE MEDIAN OVERNIGHT, ON WEEKENDS OR NON-WORKING DAYS.
9. EQUIPMENT STORED WITHIN THE PROJECT ROW SHALL BE LOCATED OUTSIDE OF THE CLEAR ZONE AND APPROVED BY THE ENGINEER.
10. THE CONTRACTOR MAY CONSTRUCT MULTIPLE LOCATIONS CONCURRENTLY WITH APPROVAL FROM TXDOT ENGINEER.



TCP TYPICAL SECTION
 (MIRROR PROCESS FOR PLACEMENT ON OPPOSITE SIDE ONF MEDIAN)





IH 10

SEQUENCE OF
CONSTRUCTION


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	14


D:\MOM CK: JKB
 D:\MOM CK: JKB
 D:\MOM CK: JKB




① PROJECT LIMITS DETAIL
N. T. S.



② SIDE STREET DETAIL
N. T. S.



RAMP DETAIL
N. T. S.



IH 10
 ADVANCED WARNING
 LAYOUT

SHEET 1 OF 1			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY		SHEET NO.
ODA	PECOS		15

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 12:59:13 PM
 FILE: \$FILES

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
 GENERAL NOTES
 AND REQUIREMENTS**

BC (1) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
4-03	7-13	0140	02	050	IH 10				
9-07	8-14	DIST	COUNTY	SHEET NO.					
5-10	5-21	ODA	PECOS	16					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ODA	PECOS	17	

DATE: 7/14/2023 12:59:20 PM
FILE: \$FILES

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/14/2023 12:59:27 PM
FILE: \$FILES

SHEET 3 OF 12

<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) -21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CON:	0140
REVISIONS		SECT:	02
9-07	8-14	JOB:	050
7-13	5-21	HIGHWAY:	IH 10
		DIST:	ODA
		COUNTY:	PECOS
		SHEET NO.:	18

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0140	02	050	IH 10				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ODA	PECOS	19					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- ### GENERAL NOTES
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ODA	PECOS	20	

DATE: 7/14/2023 12:59:32 PM
FILE: \$FILES

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	0140	SECT:	02	JOB:	050	HIGHWAY:	IH 10
REVISIONS		DIST:		COUNTY:		SHEET NO.:			
9-07	8-14	ODA		PECOS					21
7-13	5-21								


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0140	02	050	IH 10				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	ODA	PECOS	22					

DATE: 7/14/2023 12:59:37 PM
 FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 12:59:39 PM
 FILE: \$FILES\$

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.



BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0140	02	050	IH 10				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	ODA	PECOS	23					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE

VERTICAL PANELS (VPs)


- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)


- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ODA	PECOS	24	

DATE: 7/14/2023 1:00:10 PM
FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	ODA	PECOS	25	

DATE: 7/14/2023 1:00:12 PM
FILE: \$FILES

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	ODA	PECOS	26	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:00:15 PM
FILE: \$FILES

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
1-97 9-07 5-21				
2-98 7-13				
11-02 8-14	DIST	COUNTY	SHEET NO.	
	ODA	PECOS	27	


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:00:17 PM
FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:00:22 PM
FILE: \$FILES



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

BACKGROUND COLOR	SIGN DESIGNATION	SIGN	SIGN DIMENSIONS	REFLECTIVE SHEETING	SQ FT	GALVANIZED STRUCTURAL STEEL		DRILLED SHAFT
						Size	(LF)	
							① ②	24" DIA. (LF)
Orange	G20-7T		96" X 48"	Type B _{FL} or C _{FL}	32	▲	▲ ▲	▲
Orange	G20-7T		192" X 96"	Type B _{FL} or C _{FL}	128	W8x18	16 17	12

▲ See Note 6 Below

LEGEND

	Sign
	Large Sign
	Traffic Flow

DEPARTMENTAL MATERIAL SPECIFICATIONS

PLYWOOD SIGN BLANKS	DMS-7100
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL}
BLACK	LEGEND & BORDERS	NON-REFLECTIVE ACRYLIC FILM

GENERAL NOTES

- See BC and SMD sheets for additional sign support details.
- Sign locations shall be approved by the Engineer.
- For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
- Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
- Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
- The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
- The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:
Item 636 - Aluminum Signs
Item 647 - Large Roadside Sign Supports and Assemblies.
Item 416 - Drilled Shaft Foundations
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.


				Traffic Operations Division Standard	
WORK ZONE "GIVE US A BRAKE" SIGNS					
WZ (BRK) - 13					
FILE:	wzbrk-13.dgn	DN:	TxDOT	CK:	TxDOT
©TxDOT	August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS		0140	02	050	IH 10
6-96	5-98	7-13	DIST	COUNTY	SHEET NO.
8-96	3-03		ODA	PECOS	28

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/14/2023 1:01:14 PM
FILE: \$FILES

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/2 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
 * For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation
 Traffic Safety Division Standard


TEMPORARY RUMBLE STRIPS

WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	ODA	PECOS	29	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:01:18 PM
FILE: \$FILES



TCP (5-1a)

WORK AREA ON SHOULDER



TCP (5-1b)

WORK AREA ON SHOULDER

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	L = WS ² / 60	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

GENERAL NOTES

1. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
2. 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.




**TRAFFIC CONTROL PLAN
SHOULDER WORK FOR
FREEWAYS / EXPRESSWAYS**

TCP (5-1) - 18


FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0140	02	050
	DIST	COUNTY	SHEET NO.	
	ODA	PECOS	30	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:01:22 PM
FILE: \$FILES



TCP (6-1a)
TYPICAL FREEWAY ONE LANE CLOSURE



TCP (6-1b)
TYPICAL FREEWAY TWO LANE CLOSURE

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.




**TRAFFIC CONTROL PLAN
FREEWAY LANE CLOSURES**

TCP (6-1) - 12

FILE:	tcp6-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
8-12	REVISIONS	0140	02	050	IH 10				
	DIST	COUNTY	SHEET NO.						
	ODA	PECOS	31						



NOT TO SCALE



POINT	NORTHING	EASTING	ELEVATION	STATION	ALIGN	OFFSET	RT/LT	DESCRIPTION
CP100	10,291,888.03	1,629,604.19	2,667.25	608+50.69	IH 10	16.68'	RT.	5/8" Iron rod with cap stamped "TNP RANDOM" set 36.25' South West of West edge of McKenzie Rd. overpass, being 13.37' North West of edge of pavement of the Eastbound lane of IH 10.
CP101	10,291,958.98	1,629,674.65	2,668.79	609+45.29	IH 10	15.73'	LT.	5/8" Iron rod with cap stamped "TNP RANDOM" set 32.50' North East of East edge of McKenzie Rd. overpass, being 14.29' South East of edge of pavement of the Westbound lane of IH 10.
CP102	10,292,099.31	1,629,982.82	2,665.56	612+83.74	IH 10	5.04'	LT.	5/8" Iron rod with cap stamped "TNP RANDOM" set 370.96' North East of East edge of McKenzie Rd. overpass, being 24.67' South East of edge of pavement of the Westbound lane of IH 10.
CP103	10,295,302.22	1,645,678.80	2,565.39	773+87.57	IH 10	16.41'	RT.	5/8" Iron rod with cap stamped "TNP RANDOM" set 33.30' West of West Edge of overpass located 16,250' East along IH 10 from the McKenzie Rd. overpass. Being 14.06' North of edge of asphalt of the Eastbound lane of IH 10.
CP104	10,295,345.84	1,645,760.13	2,565.71	774+74.67	IH 10	14.10'	LT.	5/8" Iron rod with cap stamped "TNP RANDOM" set 28.02' East of East Edge of overpass located 16,250' East along IH 10 from the McKenzie Rd. overpass. Being 15.47' South of edge of asphalt of the Westbound lane of IH 10.
CP105	10,295,386.17	1,646,086.32	2,563.43	778+03.17	IH 10	3.46'	LT.	5/8" Iron rod with cap stamped "TNP RANDOM" set 356.51' East of East Edge of overpass located 16,250' East along IH 10 from the McKenzie Rd. overpass. Being 26.31' South of edge of asphalt of the Westbound lane of IH 10.

▲ 5/8" IRON ROD WITH CAP STAMPED "TNP RANDOM"



IH 10 HORIZONTAL & VERTICAL SURVEY CONTROL

SHEET 1 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
		IH 10
STATE	DISTRICT	COUNTY
TEXAS	ODESSA	PECOS
CONTROL	SECTION	JOB
0140	02	050

32

DRAWING DATE:


Timothy A. Frost 9/16/2022
 TIMOTHY A. FROST, REGISTERED PROFESSIONAL LAND SURVEYOR
 TEXAS REGISTRATION NO. 5316



- NOTES:
- BEARINGS OF LINES SHOWN HEREON REFER TO GRID NORTH OF THE TEXAS COORDINATE SYSTEM OF 1983 (CENTRAL ZONE 4203; NAD83(2011) EPOCH 2010) AS DERIVED LOCALLY FROM TXDOT'S CONTINUOUSLY OPERATING REFERENCE STATIONS (CORS) VIA REAL TIME KINEMATIC (RTK) METHODS. AN AVERAGE COMBINATION FACTOR OF 1.0002 WAS USED TO SCALE GRID COORDINATES AND DISTANCES TO SURFACE. ALL COORDINATES SHOWN ARE SURFACE.
 - THE ELEVATIONS SHOWN ARE NAVD88 AND WERE DERIVED FROM THE ABOVE RTK OBSERVATIONS. ORTHOMETRIC HEIGHTS WERE CALCULATED BY APPLYING THE GEOID12B MODEL TO THE ELLIPSOID HEIGHTS.
 - FIELD SURVEYS WERE CONDUCTED BY TEAGUE NALL & PERKINS, INC., SEPTEMBER 2022



NOT TO SCALE



POINT	NORTHING	EASTING	ELEVATION	STATION	ALIGN	OFFSET	RT/LT	DESCRIPTION
CP106	10,297,037.23	1,657,768.72	2,523.73	896+07.59	IH 10	8.89'	RT.	5/8" Iron rod with cap stamped "TNP RANDOM" set in center median of IH 10, being 21.72' North of edge of pavement of the Eastbound lane of IH 10.
CP107	10,296,337.59	1,669,360.06	2,573.88	1013+21.17	IH 10	13.46'	LT.	5/8" Iron rod with cap stamped "TNP RANDOM" set in center median of IH 10, being 15.93' South of edge of pavement of the Eastbound lane of IH 10.

▲ 5/8" IRON ROD WITH CAP STAMPED "TNP RANDOM"



IH 10
HORIZONTAL & VERTICAL
SURVEY CONTROL

SHEET 2 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
			IH 10
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	ODESSA	PECOS	33
CONTROL	SECTION	JOB	
0140	02	050	

DRAWING DATE:

Timothy A. Frost 9/14/2022
TIMOTHY A. FROST, REGISTERED PROFESSIONAL LAND SURVEYOR
TEXAS REGISTRATION NO. 5316

DATE



NOTES:

1. BEARINGS OF LINES SHOWN HEREON REFER TO GRID NORTH OF THE TEXAS COORDINATE SYSTEM OF 1983 (CENTRAL ZONE 4203; NAD83(2011) EPOCH 2010) AS DERIVED LOCALLY FROM TXDOT'S CONTINUOUSLY OPERATING REFERENCE STATIONS (CORS) VIA REAL TIME KINEMATIC (RTK) METHODS. AN AVERAGE COMBINATION FACTOR OF 1.0002 WAS USED TO SCALE GRID COORDINATES AND DISTANCES TO SURFACE. ALL COORDINATES SHOWN ARE SURFACE.

2. THE ELEVATIONS SHOWN ARE NAVD88 AND WERE DERIVED FROM THE ABOVE RTK OBSERVATIONS. ORTHOMETRIC HEIGHTS WERE CALCULATED BY APPLYING THE GEOID12B MODEL TO THE ELLIPSOID HEIGHTS.

3. FIELD SURVEYS WERE CONDUCTED BY TEAGUE NALL & PERKINS, INC., SEPTEMBER 2022

DATE: FILE:
 CHK: JKB
 DWF: MDM
 DWT: WDM

PROPOSED IH 10 HORIZONTAL ALIGNMENT

START STA 585+00.00 R1 X 10290861.814 Y 1627489.263
 PC STA 629+52.62 R1 X 10292833.959 Y 1631481.292

Tangential Direction: N63.71° E
 Tangential Length: 4452.60

CURVE DATA

PC STA 629+52.620 R1 X 10292833.959 Y 1631481.292
 HPI STA 638+26.811 R1 X 10293220.964 Y 1632265.152
 CC X 10287696.419 Y 1634017.779
 PT STA 646+87.621 R1 X 10293356.607 Y 1633128.755
 Radius: 5729.580
 Delta: 17.350° Right
 Degree: 1.000°
 Length: 1735.001
 Tangent: 874.191
 Chord: 1728.379
 Mid Ord: 65.548
 External: 66.306
 Back Tangent Direction: N63.714° E
 Back Radial Direction: S26.286° E
 Chord Direction: N72.399° E
 Ahead Radial Direction: S8.888° E
 Ahead Tangent Direction: N81.112° E

PT STA 646+87.621 R1 X 10293356.607 Y 1633128.755
 PC STA 859+73.980 R1 X 10296645.517 Y 1654159.498
 Tangential Direction: N81.112° E
 Tangential Length: 21286.359

CURVE DATA

PC STA 859+73.980 R1 X 10296645.517 Y 1654159.498
 HPI STA 864+06.443 R1 X 10296712.408 Y 1654586.757
 CC X 10279663.687 Y 1656818.141
 PT STA 868+38.724 R1 X 10296757.728 Y 1655016.839
 Radius: 17188.686
 Delta: 2.882° Right
 Degree: 0.333°
 Length: 864.745
 Tangent: 432.464
 Chord: 864.654
 Mid Ord: 5.438
 External: 5.439
 Back Tangent Direction: N81.112° E
 Back Radial Direction: S8.888° E
 Chord Direction: N82.543° E
 Ahead Radial Direction: S5.984° E
 Ahead Tangent Direction: N84.016° E

PT STA 868+38.724 R1 X 10296757.708 Y 1655016.649
 PC STA 926+45.996 R1 X 10297363.079 Y 1660792.282
 Tangential Direction: N84.016° E
 Tangential Length: 5807.272

CURVE DATA

PC STA 926+45.996 R1 X 10297363.079 Y 1660792.282
 HPI STA 931+25.295 R1 X 10297413.054 Y 1661268.967
 CC X 10291663.360 Y 1661389.822
 PT STA 936+02.367 R1 X 10297383.154 Y 1661747.332
 Radius: 5730.955
 Delta: 9.561° Right
 Degree: 1.000°
 Length: 956.371
 Tangent: 479.298
 Chord: 955.261
 Mid Ord: 19.938
 External: 20.008
 Back Tangent Direction: N84.016° E
 Back Radial Direction: S5.984° E
 Chord Direction: N88.796° E
 Ahead Radial Direction: S3.565° W
 Ahead Tangent Direction: S86.435° E

PT STA 936+02.367 R1 X 10297383.154 Y 1661747.332
 PC STA 978+08.599 R1 X 10297121.620 Y 1665945.425
 Tangential Direction: S86.435° E
 Tangential Length: 4206.232

CURVE DATA

PC STA 978+08.599 R1 X 10297121.620 Y 1665945.425
 HPI STA 983+85.567 R1 X 10297085.938 Y 1666521.289
 CC X 102+91403.007 Y 1665591.088
 PT STA 989+58.658 R1 X 10296936.159 Y 1667078.476
 Radius: 5729.580
 Delta: 11.501° Right
 Degree: 1.000°
 Length: 1150.059
 Tangent: 576.968
 Chord: 1148.129
 Mid Ord: 28.831
 External: 28.977
 Back Tangent Direction: S86.435° E
 Back Radial Direction: S3.565° W
 Chord Direction: S80.704° E
 Ahead Radial Direction: S15.027° W
 Ahead Tangent Direction: S74.973° E

PT STA 989+58.658 R1 X 10296936.159 Y 1667078.476
 END STA 1030+00.020 R1 X 10295888.333 Y 1670981.638
 Tangential Direction: S74.973° E
 Tangential Length: 4041.362

FIRM REGISTRATION NO. F-230

IH 10


ALIGNMENT DATA

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	38



DATE: FILE:

CK: JKB
 DNE: MOM
 CK: JKB
 DNE: MOM




NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR TO CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




DATE: 7/14/2023 1:03:21 PM
 FILE: \$FILES





IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 1 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	35	

CK: JKB
 DNF: MDM
 CK: JKB
 DNF: MDM



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




Texas Department of Transportation

IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 2 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY		SHEET NO.
ODA	PECOS		36



DATE: 7/14/2023 1:03:30 PM
 FILE: \$FILES

CK: JKB
 DNE: MDM
 CK: JKB
 DNE: MDM



NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.



Texas Department of Transportation


IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 3 OF 18





CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	37	

DATE: 7/14/2023 1:03:36 PM
 FILE: \$FILES

D:\MOM CK: JKB
 D:\MOM CK: JKB
 D:\MOM CK: JKB



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 4 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	38	

DATE: 7/14/2023 1:03:42 PM
 FILE: \$FILES

CK: JKB
 DNF: MDM
 CK: JKB
 DNF: MDM




NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.



MATCHLINE STA. 701+00.00

MATCHLINE STA. 713+00.00



MATCHLINE STA. 713+00.00

MATCHLINE STA. 725+00.00




IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 5 OF 18



CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	39	

DATE: 7/14/2023 1:03:47 PM
 FILE: \$FILES

CK: JKB
 DNF: MOM
 CK: JKB
 DNF: MOM



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




IH 10
MEDIAN BARRIER
LAYOUT



SHEET 6 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	40	

DATE: 7/14/2023 1:03:53 PM
 FILE: \$FILES

CK: JKB
 DNE: MDM
 CK: JKB
 DNE: MDM



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 7 OF 18

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	41	

DATE: 7/14/2023 1:03:59 PM
 FILE: \$FILES

DNE: MDM CK: JKB DNE: MDM CK: JKB




NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.


MATCHLINE STA. 773+00.00

MATCHLINE STA. 785+00.00



MATCHLINE STA. 785+00.00

MATCHLINE STA. 797+00.00



DATE: 7/14/2023 1:04:05 PM
 FILE: \$FILES

tnp

Texas Department of Transportation


IH 10

MEDIAN BARRIER LAYOUT

SHEET 8 OF 18

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	42	

CK: JKB
 DNF: MDM
 CK: JKB
 DNF: MDM





NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR TO CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.


MATCHLINE STA. 797+00.00

MATCHLINE STA. 809+00.00



MATCHLINE STA. 809+00.00

MATCHLINE STA. 821+00.00



Justin K. Baker
7/14/2023


IH 10

MEDIAN BARRIER LAYOUT



SHEET 9 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY		SHEET NO.
ODA	PECOS		43

DATE: 7/14/2023 1:04:11 PM
 FILE: \$FILES

CK: JKB
 DNE: MDM
 CK: JKB
 DNE: MDM



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR TO CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.



DATE: 7/14/2023 1:04:19 PM
 FILE: \$FILES

FIRM REGISTRATION NO. F-230


IH 10

MEDIAN BARRIER LAYOUT

SHEET 10 OF 18


CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	44	

CK: JKB
 DNE: MDM
 CK: JKB
 DNE: MDM





NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.



FOR OFFICIAL
 OR EMERGENCY
 VEHICLE USE
ONLY
 1/2
 MLE
 R5-11T
 48" X 48"
 W16-3P
 30" X 24"




IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 11 OF 18

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	45	



DATE: 7/14/2023 1:04:24 PM
 FILE: \$FILES

CK: JKB
 DNE: MDM
 CK: JKB
 DNE: MDM




NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




DATE: 7/14/2023 1:04:30 PM
 FILE: \$FILES



IH 10
 MEDIAN BARRIER
 LAYOUT




SHEET 12 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	46	

CK: JKB
 DNF: WDM
 CK: JKB
 DNF: WDM



NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




IH 10
MEDIAN BARRIER
LAYOUT



SHEET 13 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	47	

DATE: 7/14/2023 1:04:35 PM
 FILE: \$FILES

CK: JKB
 DWF: MDM
 CK: JKB
 DWF: MDM



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.



DATE: 7/14/2023 1:04:40 PM
 FILE: \$FILES



IH 10

MEDIAN BARRIER LAYOUT




SHEET 14 OF 18

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	48	

DNE: MDM CK: JKB DNE: MDM CK: JKB



- NOTES:
1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
 2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
 3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
 4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 15 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	49	




DATE: 7/14/2023 1:04:50 PM
 FILE: \$FILES

DNE: MDM
 CK: JKB
 DNE: MDM
 CK: JKB



NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 16 OF 18

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST		COUNTY	SHEET NO.
ODA		PECOS	50



DATE: 7/14/2023 1:04:57 PM
 FILE: \$FILES\$

D:\MOM CK: JKB
 D:\MOM CK: JKB
 D:\MOM CK: JKB




NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.




DATE: 7/14/2023 1:05:05 PM
 FILE: \$FILES



IH 10
 MEDIAN BARRIER
 LAYOUT



SHEET 17 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	51	

CK: JKB
 DNE: MDM
 CK: JKB
 DNE: MDM



NOTES:

1. THE CONTRACTOR SHALL LOCATE ANY UTILITIES THAT CROSS THE CABLE BARRIER PRIOR TO CONSTRUCTION.
2. THE CONTRACTOR SHALL PLACE CABLE BARRIER FOOTINGS TO AVOID ANY OBSTRUCTIONS, INCLUDING UTILITIES, CULVERTS, ETC.
3. THE LOCATION AND DEPTH OF DRAINAGE STRUCTURES SHALL BE VERIFIED PRIOR TO CONSTRUCTION OF MOW STRIP AND CABLE BARRIER BY THE CONTRACTOR.
4. CONTRACTOR TO STOP AND START THE MOW STRIP AS NEEDED TO AVOID IMPACTS TO CULVERTS.



JUSTIN K. BAKER
 114172
 7/14/2023

tnp
 Texas Department of Transportation

IH 10
 MEDIAN BARRIER
 LAYOUT

SHEET 18 OF 18			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	52	

DATE: 7/14/2023 1:05:26 PM
 FILE: \$FILES\$


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN TEXT	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U" EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL = Extruded Alum Sign Panels	
35	1	R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
36	1	R5-11T BACK-TO-BACK	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY	48" X 48"	X		10BWG	1	SA	T	
38	1	R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
39	1	R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
40		R5-11T BACK-TO-BACK	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY	48" X 48"	X		10BWG	1	SA	T	
41		R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
43		R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
44		R5-11T BACK-TO-BACK	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY	48" X 48"	X		10BWG	1	SA	T	
45		R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
47		R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	
48		R5-11T BACK-TO-BACK	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY	48" X 48"	X		10BWG	1	SA	T	
49		R5-11T W16-3P	FOR OFFICIAL OR EMERGENCY VEHICLE USE ONLY 1/2 MILE	48" X 48" 30"X24"	X		S80	1	SA	T	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).





IH 10

SUMMARY OF SMALL SIGNS


SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	53	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Preferred Installation: Locate post #2 away from nearest traffic. System has been successfully tested with opposite installation.




Length-of-Need Cass Cable Terminal (CCT):
Departure Installation: Length-of-Need: 44'-9" (At Post #8)
Approach Installation: Length-of-Need: 19'-9" (12" Post Post #4)




PLAN VIEW




ELEVATION VIEW (TYPICAL LAY-OUT)



VIEW A-A (CABLE RELEASE POST 1-3)
VIEW B-B (TERMINAL LINE POST 4-7)



SECTION C-C (SOCKETED POST)
SECTION D-D (BASE PLATED POST)



STANDARD POST & CONCRETE FOOTING (SOCKETED POST)

GENERAL NOTES

1. This drawing is a general overview of CASS TL-4 Barrier System. See SS-740 (latest version) for specific details of CASS cable terminal (CCT) and cable safety system (CASS) requirements, proper installation, options and specification.
2. CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity (800-527-6050) or consult the design, installation, or repair manual(s) for additional information.
3. All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
4. All posts shall be socketed unless otherwise specified. All cables shall be pre-stretched unless otherwise specified.
5. For payment see Special Specification "Cable Barrier System".
6. CASS-TL4 shall be installed on shoulders or medians with slopes of 6:1 or flatter without obstructions, depressions, etc. That may significantly affect the stability of an errant vehicle. Grading of site and/or appropriate fill materials may be required. The designer/installer shall "Flatten" or "Round" various topographical inconsistencies that could interfere with the ability of the installer to consistently maintain the design height (in relation to the terrain) of the cables. Please consult manual(s) and / or TxDOT Memo(s) for installations in "Ditch Sections".
7. CASS TL-4 post spacing may be modified to avoid obstacles that conflict with the installation of cass-tl4 line posts or to reduce deflection on radiuses. No post space can exceed the maximum post TxDOT space limit of 20'. Reducing or increasing post spacing affects deflection. CASS TL-4 may be laterally transferred at a rate not to exceed 30:1.
8. Post foundations may be drilled through existing pavement. Please see line post foundation chart for minimum footing requirements in various applications.
9. For aesthetic purposes Trinity recommends all sleeves, driven posts, and lower cable release posts to be installed reasonably plumb (approximately 1/8" per foot).
10. CASS TL-4 shall be installed in well-drained, compacted, NCHRP Report 350 Standard soil. If soil does not meet this classification, if solid rock/concrete is encountered below grade or if soil is susceptible to severe freeze/thaw cycles, please contact Trinity about alternate footing designs(s). Trinity suggests the use of "Mow strips" for erosion prevention and ease of maintenance / installation.
11. See the Texas MUTCD for proper "Barrier" Delineation.

MOW STRIP DETAIL*			CONCRETE FOOTING CHART		
MOW STRIP	DEPTH	WIDTH	FOOTING	TUBE SLEEVE	REBAR RING
NONE			30" Min.	27" Min.	YES
HMA	6" Min.	3' Min.	27" Min.	15" Min.	NO
HMA	8" Min.	3' Min.	24" Min.	15" Min.	NO
RC	3" Min.	3' Min.	24" Min.	15" Min.	NO

Chart does not apply to Terminal Posts 1 thru 9.
 * Mow strip or pavement.
 HMA = Hot Mix Asphalt (Not Recycled Asphalt Pavement).
 RC = Reinforced Concrete (TxDOT Class A Minimum).

Trinity Highway Products, LLC.
 2525 Stemmons Freeway
 Dallas, TX 75207
 Phone: (800) 644-7976
 Product. INFO@TRIN.NET

CABLE TENSION CHART	
FAHRENHEIT DEGREES	PRE-STRETCHED LB / FORCE
-10	7300
0	7000
10	6600
20	6300
30	6000
40	5600
50	5300
60	5000
70	4600
80	4300
90	4000
100	3600
110	3300
120	3000
130	2700
140	2500
150	2300

Allowable deviation from chart in tangent sections: +800, -200 pounds/force. Cable tension readings are typically higher in curved cable sections.


Texas Department of Transportation
TRINITY CABLE SAFETY SYSTEM (TL-4)
CASS (TL4) - 14

FILE: CASST1414.dgn	DN: TxDOT	CK: RM	DW: VP	CK:
©TxDOT: March 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
	DIST	COUNTY	SHEET NO.	
	ODA	PECOS	54	


Design Division Standard

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 7/14/2023
FILE: \$FILES




TYPICAL POST PLACEMENT



WOOD BLOCK TO ROUND WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**




ELEVATION MID-SPAN RAIL SPLICE




ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.



BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.


WOOD BLOCK TO ROUND WOOD POST

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.

- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

12" x 12" x 1/4" (ASTM A36) STEEL BOTTOM PLATE WITH 1" DIA. HOLES REQUIRED WITH BOLT-THROUGH INSTALLATION.

NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.




METAL BEAM GUARD FENCE
TL-3 MASH COMPLIANT
GF(31)-19

FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
	DIST	COUNTY	SHEET NO.	
	ODA	PECOS	55	

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 7/14/2023
FILE: \$FILES






DOWNSTREAM ANCHOR TERMINAL (DAT)

NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.

- GENERAL NOTES**
1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
 2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
 3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
 4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
 5. REFER TO GF (31) SHEET FOR TERMINAL CONNECTION DETAILS.

MOW STRIP INSTALLATION
IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.

#	(DAT) PARTS LIST	QTY
1	STEEL FOUNDATION TUBE	2
2	DAT TERMINAL POST	2
3	CHANNEL STRUT	2
4	TERMINAL RAIL ELEMENT	1
5	SHELF ANGLE BRACKET	1
6	BCT BEARING PLATE	1
7	BCT POST SLEEVE	1
8	GUARDRAIL ANCHOR BRACKET	1
9	(ROUNDED) W-BEAM END SECTION	1
10	BCT CABLE ANCHOR	1
11	RECESSED NUT, GUARDRAIL	20
12	1 1/4" BUTTON HEAD BOLT	4
13	10" BUTTON HEAD BOLT	2
14	5/8" X 2" HEX HEAD BOLT	8
15	5/8" X 8" HEX HEAD BOLT	4
16	5/8" X 10" HEX HEAD BOLT	2
17	5/8" FLAT WASHER	18




Design Division Standard

**METAL BEAM GUARD FENCE
(DOWNSTREAM ANCHOR TERMINAL)
TL-3 MASH COMPLIANT
GF (31) DAT-19**


FILE: gf31dat19.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019 REVISIONS	CONT: 0140	SECT: 02	JOB: 050	HIGHWAY: IH 10
DIST: ODA	COUNTY: PECOS	SHEET NO. 56		

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)




SECTION A-A

Typical




MOW STRIP DETAIL

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)

Curb shown on top of mow strip



CURB OPTION (3)

GENERAL NOTES


1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type I or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.

DATE: 7/14/2023
 FILE: \$FILES

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF(31)MS-19			
FILE: gf31ms19.dgn	DN: TxDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0140	02	050
DIST	COUNTY	SHEET NO.	
ODA	PECOS	57	

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



DATE: 7/14/2023
FILE: \$FILES




- * NOTES:
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	3/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	3/8" WASHER	W0516
c	2	3/8" HEX NUT	N0516
d	25	3/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	3/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	3/8" WASHER	W050
g	33	3/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	3/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. *
* ITEM (P) 8" WOOD-BLOCKOUT
** ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Texas Department of Transportation
Design Division Standard

SINGLE GUARDRAIL TERMINAL


MSKT-MASH-TL-3

SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CL
© TxDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
	DIST	COUNTY	SHEET NO.	
	ODA	PECOS	58	






DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 7/14/2023
FILE: \$FILES



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CB08
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WB08
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/8"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBLK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GGRI17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81
SMALL HARDWARE			
a	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPLICE BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15) 31-20

FILE: sg+153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
	DIST	COUNTY	SHEET NO.	
	ODA	PECOS	59	

Design Division Standard

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


Post Type
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)

Anchor Type
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft. in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




BEHIND BARRIER




BEHIND GUARDRAIL

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.



BEHIND CONCRETE BARRIER

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND




RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.



* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

Texas Department of Transportation
 Traffic Operations Division


SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD(GEN)-08

© TxDOT July 2002	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONTRACT	SECTION	JOB
		0140	02	050
		DIST	COUNTY	INCH
		ODA	PECOS	10
				SHEET NO.
				60

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



5/8" diameter Concrete Anchor - 8 places (embed a minimum of 5 1/2" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

DATE: 7/14/2023 1:06:12 PM
FILE: \$FILES

Texas Department of Transportation
Traffic Operations Division















SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
9-08	REVISIONS		CONT	SECT	JOB	HIGHWAY
			0140	02	050	IH 10
	DIST	COUNTY	ODA		PECOS	SHEET NO. 61

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:06:16 PM
FILE: \$FILES



GENERAL NOTES:

SIGN SUPPORT	# OF POSTS	MAX. SIGN AREA
10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF

- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
- Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.
- Sign blanks shall be the sizes and shapes shown on the plans.

	REQUIRED SUPPORT	
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.




**SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-2)-08**


© TxDOT July 2002	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	CON: 0140	SECT: 02	JOB: 050	HIGHWAY: IH 10
	DIST: ODA	COUNTY: PECOS	SHEET NO. 62	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/14/2023 1:06:20 PM
FILE: \$FILES



SM RD SGN ASSM TY XXXX(1)XX(T-2EXT)
(* - See Note 12)




Detail B




Detail C

Splices shall only be allowed behind the sign substrate.




SM RD SGN ASSM TY XXXX(1)XX(U-XX)




Typical Sign Mount


SM RD SGN ASSM TY S80(2)XX(IP-EXAL)
* Additional stiffener placed at approximate center of signs when sign width is greater than 10'.



Detail E




Detail A




Detail D

EXTRUDED ALUMINUM SIGN WITH T BRACKET



Extruded Aluminum Sign With T Bracket



Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details
See Detail E for clamp installation

GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT

	SIGN DESCRIPTION		SUPPORT
	Regulatory	48-inch STOP sign (R1-1)	
60-inch YIELD sign (R1-2)		TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)	
48x16-inch ONE-WAY sign (R6-1)		TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)	
36x48, 48x36, and 48x48-inch signs		TY 10BWG(1)XX(T)	
48x60-inch signs		TY S80(1)XX(T)	
Warning	48x48-inch signs (diamond or square)		TY 10BWG(1)XX(T)
	48x60-inch signs		TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)		TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)		TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)		TY 10BWG(1)XX(T)

Texas Department of Transportation
Traffic Operations Division

SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-3)-08


© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CON	SECT	JOB	HIGHWAY
		0140	02	050	IH 10
		DIST	COUNTY		SHEET NO.
		ODA	PECOS		63

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023 1:06:23 PM
 FILE: \$FILES

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>




TYPICAL SIGN REQUIREMENTS

TSR(4) - 13





FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0140	02	050	IH 10				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		ODA	PECOS	64					


DATE: 7/14/2023 1:06:28 PM
 FILE: \$FILES




NTS

LEGEND

	AREA OF CONSTRUCTION
	INLET PROTECTION EROSION CONTROL LOG
	EROSION CONTROL LOG
	DIRECTION OF FLOW



JUSTIN K. BAKER
114172
LICENSED PROFESSIONAL ENGINEER
7/14/2023



tnp
Texas Department of Transportation

IH 10
SW3P LAYOUT

SHEET 1 OF 1			
CONT	SECT	JOB	HIGHWAY
0140	02	050	IH 10
DIST	COUNTY	SHEET NO.	
ODA	PECOS	65	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

CSJ 0140-02-050

1.2 PROJECT LIMITS:

From: MM 285

To: MM 293

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 30°52'44" N, (Long) 102°27'40" W

END: (Lat) 30°53'32" N, (Long) 102°19'47" W

1.4 TOTAL PROJECT AREA (Acres): 385.63

1.5 TOTAL AREA TO BE DISTURBED (Acres): 8.51

1.6 NATURE OF CONSTRUCTION ACTIVITY:

CONSTRUCT MOWSTRIP AND CABLE BARRIER
IN THE IN THE MEDIAN

1.7 MAJOR SOIL TYPES:

Soil Type	Description
SILTY CLAY LOAM	

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
 - Blade existing topsoil into windrows, prep ROW, clear and grub
 - Remove existing pavement
- Grading operations, excavation, and embankment
 - Excavate and prepare subgrade for proposed pavement widening
 - Remove existing culverts, safety end treatments (SETs)
 - Remove existing metal beam guard fence (MBGF), bridge rail
 - Install proposed pavement per plans
 - Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
 - Place flex base
 - Rework slopes, grade ditches
 - Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- Other: _____
- Other: _____
- Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Tunas Creek	Upper Pecos River, Segment 2311 of Rio Grande Basin

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:

MS4 Entity

STORMWATER POLLUTION PREVENTION PLAN (SWP3)



Sheet 1 of 2

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
6	SEE TITLE SHEET			66
STATE	STATE DIST.	COUNTY		
TEXAS	ODA	PECOS		
CONT.	SECT.	JOB	HIGHWAY NO.	
0140	02	050	IH 10	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

T / P

- Sediment Trap
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
 - Not required (<10 acres disturbed)
 - Required (>10 acres) and implemented.
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
 - Required (>10 acres), but not feasible due to:
 - Available area/Site geometry
 - Site slope/Drainage patterns
 - Site soils/Geotechnical factors
 - Public safety
 - Other: _____

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

STORMWATER POLLUTION PREVENTION PLAN (SWP3)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	SEE TITLE SHEET		67
STATE	STATE DIST.	COUNTY	
TEXAS	ODA	PECOS	
CONT.	SECT.	JOB	HIGHWAY NO.
0140	02	050	IH 10

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023
FILE: \$FILES

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.
2.
 No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
 Individual 404 Permit Required
 Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.
2.
3.
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

1.
2.
3.


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)


- No Action Required Required Action

Action No.


1.
2.
3.

 Texas Department of Transportation		<i>Design Division Standard</i>	
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC			
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (DS) REVISIONS	0140	02	050
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	ODA	PECOS	68

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PLAN VIEW




SECTION A-A
EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B
EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW




SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:

1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
 - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
 - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
 - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
 - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
 - CL-DI EROSION CONTROL LOG AT DROP INLET
 - CL-CI EROSION CONTROL LOG AT CURB INLET
 - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET


SHEET 1 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES			
EROSION CONTROL LOG			
EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0140	02	050
DIST	COUNTY	SHEET NO.	
ODA	PECOS	69	

DATE: 7/14/2023
FILE: \$FILES\$


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/14/2023
FILE: \$FILES



**EROSION CONTROL LOGS ON SLOPES
STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




**EROSION CONTROL LOGS ON SLOPES
STAKE AND LASHING ANCHORING**

CL-SSL



STAKE AND TRENCHING ANCHORING DETAIL


CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL

LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"



STAKE NOTCH DETAIL




SHEET 2 OF 3

Design Division Standard

**TEMPORARY EROSION,
SEDIMENT AND WATER
POLLUTION CONTROL MEASURES
EROSION CONTROL LOG
EC (9) - 16**


FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0140	02	050	IH 10
DIST	COUNTY	SHEET NO.		
ODA	PECOS	70		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0140	02	050
DIST	COUNTY	SHEET NO.	
ODA	PECOS	71	

DATE: 7/14/2023
FILE: \$FILES