

INDEX OF SHEETS

SEE SHEET 2

**STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT.

BR 2021(530)
CSJ 0920-03-081
HARDIN COUNTY

0920-03-081 FROM: CR 101 @ FLAT CYPRESS CREEK

NET LENGTH OF ROADWAY- 200 FT.- 0.04 MI.
NET LENGTH OF BRIDGE- 90 FT.- 0.02 MI.
NET LENGTH OF PROJECT- 290 FT.- 0.06 MI.

FOR THE CONSTRUCTION OF A BRIDGE REPLACEMENT
CONSISTING OF REPLACE BRIDGE AND APPROACHES.

FEDERAL AID PROJECT NO.			
BR 2021(530)			
CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		1

DESIGN CRITERIA:
0920-03-081 - SPECIAL FACILITIES:
OFF SYSTEM BRIDGE
DESIGN SPEED - 30
ADT (2011) - 10
ADT (2040) - 14

FINAL PLANS

LETTING DATE: _____


DATE CONTRACTOR BEGAN WORK: _____

DATE WORK WAS COMPLETED & ACCEPTED: _____

FINAL CONTRACT COST: \$ _____

CONTRACTOR : _____

PROJECT LOCATION
CSJ 0920-03-081
FROM STA. 3+88 TO STA. 6+78



N.T.S

EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH
BC (1)-21 THRU BC (12)-21 AND THE "TEXAS MANUAL
ON UNIFORM TRAFFIC CONTROL DEVICES".



©2023 BY TEXAS DEPARTMENT OF TRANSPORTATION. ALL RIGHTS RESERVED.

SUBMITTED FOR LETTING: 8/4/2023

[Signature]
DISTRICT DESIGN ENGINEER

RECOMMENDED FOR LETTING: 8/4/2023

Lisa Collins
DISTRICT DIRECTOR OF TRANSPORTATION
PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 8/4/2023

Martha N. Goff, P.E.
DISTRICT ENGINEER

FILE: 7/12/2023 9:23:13 AM
DATE: I:\BMT\DESIGN\Projects\0920-03-081_CRI\01.Flat.Cypress.Creek\working_files\0920-03-081\cedu_to_print\TITLE_SHEET.dgn


SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION,
NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS.
SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL
FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022)

INDEX OF SHEETS

The "PC" signifies to the Plans Office that the index sheet was created with the Excel workbook. Please do not delete.

	GENERAL
1	TITLE SHEET
2	INDEX OF SHEETS
3	LOCATION MAP
4	TYPICAL SECTIONS
5-7A	GENERAL NOTES
8	ESTIMATE & QUANTITY
9	QUANTITY SUMMARY
	TRAFFIC CONTROL PLAN
10	DETOUR LAYOUT
11	SEQUENCE OF WORK
** 12-23	BC (1)-21 THRU BC (12)-21
** 24	WZ (RCD)-13
	ROADWAY DETAILS
25-26	SURVEY CONTROL INDEX
27-28	0920-03-081 PLAN & PROFILE
** 29	GF(31)-19
** 30	GF(31)MS-19
** 31-32	GF(31)TRTL3-20
** 33	CCCG-21
** 34	SGT(10S)31-16
** 35	SGT(11S)31-18
** 36	SGT(12S)31-18
** 37	BED-14
** 38-39	SRR
	BRIDGE
40	0920-03-081 HYDRAULIC & HYDROLOGIC DATA
41	0920-03-081 BRIDGE LAYOUT
42	0920-03-081 ESTIMATED QUANTITIES & BEARING SEAT ELEVATIONS
43	0920-03-081 BRIDGE BORE DATA
** 44	APSB-24
** 45	BPSB-24
** 46	SPSB-24
** 47	PSBSD
** 48	PSB-5B12
** 49	PSBEB
** 50	PSBRA
** 51	AJ
** 52	BAS-A
** 53-54	CSAB
** 55-56	FD
** 57-59	TYPE T223
** 60	CP
	TRAFFIC DETAILS
** 61	D&OM(1)-20
** 62	D&OM(2)-20
** 63	D&OM(5)-20
** 64	D&OM(VIA)-20
	ENVIRONMENTAL ISSUES
65	SW3P/UTILITY LAYOUTS
** 66-66A	SW3P-1
** 67	EC(1)-16
** 68	EC(2)-16
** 69	EPIC

FILE: T:\BMTDESIGN\Projects\0920-03-081_CR101_Flat_Cypress_Creek\working files\0920-03-081\ready to print\INDEX OF SHEETS.dgn
DATE: 7/11/2023 1:18:16 PM



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A "*" HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

NAME John DATE 07/13/2023

INDEX OF SHEETS

Texas Department of Transportation


FHWA PROJECT NO.		SHEET NO.	
BR 2021(530)		2	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	HARDIN	
CONTROL SECTION	JOB	HIGHWAY NO.	
0920	03 081	CR 101	

HARDIN COUNTY


PROJ. REF. NO.	PROJECT CSJ	HWY	COUNTY	STA. TO STA.	STRUCTURE NO.	LATITUDE/ LONGITUDE
①	0920-03-081	CR 101	HARDIN	3+88 TO 6+78	20-1010-AA01-01-001	30.41920881 / -94.54012906



DATE: 12/20/2021 11:29:49 AM
FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\ready to print\LOCATION MAP.dgn





LOCATION MAP
N. T. S.




CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST		COUNTY	SHEET NO.
BMT		HARDIN	3

llite

DATE: 12/15/2021 9:16:04 PM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\ready to print\TYPICAL_SECTION.dgn



NOTES:
 EMBANKMENT WILL BE ADDED TO COMPENSATE INCREASE IN ELEVATION OF PGL AS WELL AS ADDITIONAL ROAD CROWN.



Andrew C. Lee

12/15/2021

TYPICAL SECTIONS
 N. T. S



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		4

County: Hardin

Control: 0920-03-081

Highway: CR 101

GENERAL NOTES:

Contractor questions on this project are to be addressed to the following individual(s):

Name Dave Collins, P.E.

Email [Dave.Collins@txdot.gov]

Name Richard Bradley, P.E.

Email [Richard.Bradley@txdot.gov]

Contractor questions will be accepted through email, phone and in person by the above individuals.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed

from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 000 Utilities

Locations of underground utilities depicted on the plans are approximate and avoid damaging, or accommodate utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities. If utility damage (breaks, leaks, nicks, dents, gouges, etc.) occurs, contact the utility facility owner or operator immediately. In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others.

Item 5 Control of the Work

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

County: Hardin

Control: 0920-03-081

Highway: CR 101

Verify all horizontal and vertical control, approach grades to structures and driveways before beginning work. Notify the Engineer immediately if discrepancies are discovered.

Furnish, to the Engineer, a list of the final centerline elevations based on the alignment stationing shown on the plans. When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impact to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

Item 6 Control of Materials

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work. Mixing of materials, storing of materials, storing of equipment, or repairing of equipment on top of concrete pavement or bridge decks will not be permitted unless specifically authorized.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product. Refer to the Buy America Material Classification Sheet for clarification on material categorization. The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Item 7 Legal Relations and Responsibilities

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle because of their operation.

Do not park any vehicle within the right of way at any time including any section closed to public traffic, unless the vehicle is being used for construction procedures. However, the Contractor's employees may park on the right of way at sites where the contractor has their office, equipment and materials storage yard.

Be familiar with the right of way map and the location of any monumentation. Protect and avoid disturbance to the right of way monumentation. Any monument disturbed by the Contractor Sheet will be repaired and/or replaced to the satisfaction of the Engineer. This work will be corrected at the Contractor's expense.

County: Hardin

Control: 0920-03-081

Highway: CR 101

No significant traffic generator events have been identified in the project limits

Item 100 Preparing Right of Way

When bridge demolition, tree trimming or tree/brush removal is required from February 15 to September 30, the contractor will provide a qualified biologist with a Bachelor's Degree in biology and demonstrated bird nest survey experience to conduct nesting surveys before work can begin and until vegetation work is completed to ensure compliance with the Migratory Bird Treaty Act (MBTA). See EPIC sheet for details.

Item 110 Excavation

Any earthwork cross-sections, computer printouts, data files and any other information provided is for non-construction purposes only and it is the responsibility of the prospective bidder to validate the data with the appropriate plans, specifications and estimates for the projects. Contact the Area Office for information on availability.

Do not windrow or stockpile material next to or along the roadway. Remove excess material from the project daily.

Transition the ditch grades and channel bottom widths at structure locations. Use only approved channel excavation in the embankment.

Item 132 Embankment

Compaction method specified as ordinary compaction.

It is the Contractor's responsibility to advise the Engineer of the location of the material source enough in advance to avoid delay due to testing requirements.

Item 247 Flexible Base

Use Type A, Grade 1-2 flexible base

The minimum plasticity index for this material will be 4. Use ordinary compaction. Do not damage existing or proposed structures during base operations.

Item 420 Concrete Substructures

Paint the Control Section (CSS) number on a location approved by the Engineer using black exterior paint and stencils that result in four (4) inch high numbers. All numbers should be legible and free of smears or drips. The painting of these numbers will not be paid for directly but will be considered subsidiary to the various bid items.

Item 409.6002 Prestr Conc Pil (18 in sq) and Item 425.6010 Prestr Conc Slab Beam (5SB12) are currently stockpiled at the Beaumont Maintenance yard, located at 8450 Eastex Fwy, Beaumont, Tx 77708. It is the Contractor's responsibility to coordinate the loading and transport of the

County: Hardin

Control: 0920-03-081

Highway: CR 101

stockpiled material with the Beaumont Maintenance Section Supervisor, Kevin Emerson @ 409-924-6537. This is considered subsidiary to various Bid Items.

Item 421 Hydraulic Cement Concrete

Entrained air is required in all slip formed concrete (bridge rail, concrete traffic barrier, pavement, etc.), but is not required for other structural concrete. Adjust the dosage of air entraining agent for low air content as directed or allowed.

Item 496 Removing Structures

Provide a demolition plan to the Engineer for review and approval that is signed and sealed by an Engineer licensed in the State of Texas. Submit the Demolition Plan to the Jasper Area Office at least thirty (30) days prior to cutting any existing bridge members or elements.

Item 502 Barricades, Signs, and Traffic Handling

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

<u>Square Feet</u>	<u>Minimum Thickness</u>
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506 Temporary Erosion, Sedimentation, and Environmental Controls

Construct all side slopes on rock filter dams with 6:1 slopes.

Item 540 Metal Beam Guard Fence

Provide Type II galvanization metal beam rail elements.

Provide round timber posts.

County: Hardin

Control: 0920-03-081

Highway: CR 101

Item 585 Ride Quality for Pavement Surfaces

Use Surface Test Type A to evaluate ride quality of travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

Item 658 Delineator and Object Marker Assemblies

Mount reflectors on a steel or concrete bridge rail, where the bridge is 200' or less in length, at the same height as the reflectors in the MBGF rail element.

Item 3076 Dense Graded Hot Mix Asphalt

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC "Superpave Gyrotory Compactor" and TGC "Texas Gyrotory Compactor". All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68oF through 72oF).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.

Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.

Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.

County: Hardin

Control: 0920-03-081

Highway: CR 101

An operational telephone system.

Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.

Water (for testing purposes) from an approved source

Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.

A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment

A laboratory sink measuring 24 × 30 in. and 12 in. deep

Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.

Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class B for all surface mixes. RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements. Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the

County: Hardin

Control: 0920-03-081

Highway: CR 101

Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

A material transfer device (MTD) will be required for all surface courses of HMA on this project. An MTD is defined as a self-propelled, wheel-mounted vehicle capable of receiving HMA from the haul trucks separate from the paver. The MTD will have a minimum storage capacity of approximately 25 tons and will be equipped with a pivoting discharge conveyor and a means of completely remixing the HMA before placement. The Engineer may approve an alternative device on a trial basis for the surface course. This device will be capable of receiving HMA separate from the paver and must have remixing capabilities. For all other courses of HMA, other than the surface, an alternative device may be used as long as it is capable of receiving HMA separate from the paver.

Overlay across the ends of any curb ramps must not create a barrier to their use. Changes in level up to ¼" may be vertical; between ¼" and ½" must be beveled with a slope no greater than 1:2; greater than ½" will require a "ramp".



CONTROLLING PROJECT ID 0920-03-081

DISTRICT Beaumont
HIGHWAY CR

COUNTY Hardin

Estimate & Quantity Sheet

CONTROL SECTION JOB				0920-03-081		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00062635			
COUNTY				Hardin			
HIGHWAY				CR			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6028	PREP ROW (TREE PRUNING)	EA	5.000		5.000	
	110-6001	EXCAVATION (ROADWAY)	CY	326.000		326.000	
	112-6001	SUBGRADE WIDENING (ORD COMP)	STA	2.000		2.000	
	132-6007	EMBANKMENT (FINAL)(ORD COMP)(TY D)	CY	31.000		31.000	
	216-6001	PROOF ROLLING	HR	10.000		10.000	
	247-6041	FL BS (CMP IN PLC)(TYA GR1-2)(FNAL POS)	CY	80.000		80.000	
	310-6005	PRIME COAT (AE-P)	GAL	86.000		86.000	
	400-6005	CEM STABIL BKFL	CY	25.000		25.000	
	409-6002	PRESTR CONC PIL (18 IN SQ)	LF	676.000		676.000	
	420-6013	CL C CONC (ABUT)	CY	17.600		17.600	
	420-6025	CL C CONC (BENT)	CY	13.200		13.200	
	422-6007	REINF CONC SLAB (SLAB BEAM)	SF	2,340.000		2,340.000	
	422-6015	APPROACH SLAB	CY	38.500		38.500	
	425-6010	PRESTR CONC SLAB BEAM (5SB12)	LF	442.500		442.500	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	683.000		683.000	
	450-6006	RAIL (TY T223)	LF	204.000		204.000	
	454-6003	ARMOR JOINT	LF	44.000		44.000	
	496-6009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000		1.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		5.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	50.000		50.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	50.000		50.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	320.000		320.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	320.000		320.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	50.000		50.000	
	540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	4.000		4.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000	
	658-6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	8.000		8.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	8.000		8.000	
	3076-6066	TACK COAT	GAL	43.000		43.000	
	3076-6071	D-GR HMA TY-D PG 64-22 (EXEMPT)	TON	47.000		47.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
18		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	

DISTRICT	COUNTY	CCSJ	SHEET
Beaumont	Hardin	0920-03-081	8

BASIS OF ESTIMATE

ITEM	DESCRIPTION	RATE	• OF UNITS	UNIT	QUANTITY	UNIT
0920-03-081						
310-6005	PRIME COAT (AE-P)	0.2 GAL/SY	427	SY	86	GAL
3076-6071	D-GR HMA(SQ) TY-D PG 64-22 (EXEMPT)	220 LBS/SY	427	SY	47	TON
3076-6066	TACK COAT	0.1 GAL/SY	427	SY	43	GAL

RAILING ITEMS

	540		544	658	
	6001	6006	6001	6062	6014
	MTL W-BEAM GD FEN (TIM POST)	MTL BEAM GD FEN TRANS (THRIE BEAM)	GUARDRAIL END TREATMENT (INSTALL)	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2 (BI)	INSTL DEL ASSM (D-SW)SZ 1(BRF)CTB (BI)
UNIT OF MEASURE	LF	EA	EA	EA	EA
0920-03-081	50	4	4	8	8
TOTALS	50	4	4	8	8

SW3P ITEMS

	506			
	6002	6011	6038	6039
	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
UNIT OF MEASURE	LF	LF	LF	LF
0920-03-081	50	50	320	320
TOTALS	50	50	320	320

ROADWAY ITEMS

	100	110	112	132	216	247*	310	3076	
	6028	6001	6001	6007	6001	6041	6005	6071	6066
	PREP ROW (TREE PRUNING)	EXCAVATION (ROADWAY)	SUBGRADE WIDENING (ORD COMP)	EMBANKMENT (FINAL) (ORD COMP) (TY D)	PROOF ROLLING	FL BS (CMP IN PLC) (TY A GRI-2)	PRIME COAT (AE-P)	D-GR HMA(SQ) TY-D PG 64-22	TACK COAT
UNIT OF MEASURE	EA	CY	STA	CY	HR	CY	SY	SY	SY
0920-03-081	5	326	2	31	10	80	427	427	427
TOTALS	5	326	2	31	10	80	427	427	427

* QUANTITY INCLUDES FLEX BASE AMOUNT FOR THE MOW STRIPS

MISC. ITEMS

DESCRIPTION	6001
	6002
PORTABLE CHANGEABLE MESSAGE SIGN	
UNIT OF MEASURE	EA
0920-03-081	2
TOTALS	2

BRIDGE ITEMS*

	400	409	420		422		425	432	450	454	496
	6005	6002	6013	6025	6007	6015	6010	6033	6006	6003	6009
	CEM STABIL BKFL	PRESTR CONC PIL (18IN SQ)	CL C CONC (ABUT)	CL C CONC (BENT)	REINF CONC SLAB (SLAB BEAM)	APPROACH SLAB	PRESTR CONC SLAB BEAM (5SB12)	RIPRAP (STONE PROTECTION) (18 IN)	RAIL (TY T223)	ARMOR JOINT	REMOV STR (BRIDGE 0-99 FT LENGTH)
UNIT OF MEASURE	CY	LF	CY	CY	SF	CY	LF	CY	LF	LF	EA
0920-03-081	25	676	17.6	13.2	2340	38.5	442.5	683	204	44	1
TOTALS	25	676	17.6	13.2	2340	38.5	442.5	683	204	44	1

* FOR CONTRACTOR INFORMATION ONLY SEE ESTIMATED QUANTITY SHEETS FOR BRIDGE QUANTITIES

NOTE:

ITEM 409.6002 PRESTR CONC PIL (18 IN SQ) AND ITEM 425.6010 PRESTR CONC SLAB BEAM (5SB12) ARE CURRENTLY STOCKPILED AT THE BEAUMONT MAINTENANCE YARD, LOCATED AT 8450 EASTEX FWY, BEAUMONT, TX 77708. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE LOADING AND TRANSPORT OF THE STOCKPILED MATERIAL WITH THE BEAUMONT MAINTENANCE SECTION SUPERVISOR, KEVIN EMERSON @ 409-924-6537.

SUMMARIES



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		9


DATE: 7/11/2023 12:55:33 PM FILE: I:\BMT\DESIGN\PROJECTS\0920-03-081\CR101\Flet\Cupress\Creek\working_files\0920-03-081\summary.s.dgn

DATE: 12/15/2021 9:16:54 PM
 FILE: C:\Users\NPASTORE\Desktop\VPW Exports\0920-03-081_ETC 95% development\0920-03-081\ready to print\DETOUR LAYOUT.dgn



LEGEND	
	Type 3 Barricade
	Sign
	Traffic Flow
	Portable Changeable Message Sign (PCMS)

NOTE:
 PORTABLE CHANGEABLE MESSAGE SIGN TO BE PLACED TWO (2) WEEKS IN ADVANCE OF CONSTRUCTION OR AS DIRECTED BY THE ENGINEER.



Andrew C. Lee
 12/16/2021

0920-03-081
CR 101
FLAT CYPRESS CREEK
DETOUR LAYOUT
N. T. S.

SIGN LEGEND

A	B	C	D	E	F	G
M4-12T 21" x 12"	M4-12T 21" x 12"	M4-12T 21" x 12"	M4-12T 21" x 12"	R11-3a 60" x 30"	R11-3a 60" x 30"	R11-2aT 48" x 30"
M4-8 24" x 12"	M4-8a 24" x 12"	M4-8 24" x 12"	M4-8 24" x 12"			
M6-3 21" x 15"		M6-1L 21" x 15"				



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	10	


SEQUENCE OF WORK

FOLLOW THE GENERAL SEQUENCE BELOW FOR EACH BRIDGE UNLESS OTHERWISE APPROVED.

1. INSTALL PORTABLE CHANGEABLE MESSAGE BOARDS PROVIDING 2 WEEKS NOTICE FOR BRIDGE CLOSURE AND DETOUR.
2. INSTALL CONSTRUCTION BARRICADES AND SIGNS. MAINTAIN AS NEEDED FOR DURATION OF PROJECT.
3. REPLACE BRIDGE.
 - a. INSTALL SW3P ITEMS (MAINTAIN AS NEEDED).
 - b. REMOVE EXISTING BRIDGE STRUCTURE.
 - c. EXCAVATE, CONSTRUCT EMBANKMENT, AND RE GRADE AS NECESSARY FOR CONSTRUCTING BRIDGE SUBSTRUCTURE.
 - d. CONSTRUCT BENT PILINGS AND CAPS (AS NEEDED PER LAYOUTS).
 - e. CONSTRUCT ABUTMENT PILINGS AND ABUTMENTS.
 - f. CONSTRUCT STONE RIP RAP.
 - g. PLACE BRIDGE BEAMS.
 - h. POUR BRIDGE DECK SLAB.
 - i. CONSTRUCT BRIDGE RAILING.
4. CONSTRUCT ROADWAY APPROACHES.
 - a. PLACE APPROACH SLABS
 - b. PLACE 0"-6" FLEX BASE ACCORDING TO PLANS.
 - c. PLACE AE-P PRIME.
 - d. PLACE 2" HMA OVERLAY ACCORDING TO PLANS.
5. INSTALL APPROACH RAILING ELEMENTS AND MOW STRIPS .
6. INSTALL OBJECT MARKERS.
7. CLEAN SITE. REMOVE CONSTRUCTION BARRICADES & SIGNS AND SW3P ITEMS AFTER FINAL ACCEPTANCE.

NOTES:

1. REFER TO THE GENERAL NOTES & PLAN SHEETS FOR ADDITIONAL DIRECTION.
2. PREPARE THE BID FOLLOWING THE PROPOSED SEQUENCE OF WORK. THE ENGINEER MAY APPROVE ADJUSTMENTS TO THE SEQUENCE OF WORK AFTER LETTING.
3. REFER TO THE GENERAL NOTES & QUANTITY SUMMARY SHEET FOR INFORMATION ON STOCKPILED MATERIAL.



J. Horne

07/13/2023

**CR 101
SEQUENCE OF WORK**



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		11

DATE: 12/15/2021 9:17:03 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Exp\0920-03-081, ETC 95% development\0920-03-081\Standard\BC-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for incorrect results or damages resulting from its use.

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) - 21			
FILE:	bc-21.dgn	DN:	TxDOT
		CR:	TxDOT
		DW:	TxDOT
		CK:	TxDOT
© TxDOT	November 2002	CONT	SECT
		0920	03
		JOB	HIGHWAY
		081	CR 101
4-03	7-13	DIST	COUNTY
9-07	8-14		
5-10	5-21	BMT	HARDIN
			SHEET NO.
			12

DATE: 12/15/2021 9:17:05 PM
 FILE: C:\Users\RPASTORE\Desktop\VP_Export\ts\0920-03-081.dgn
 ETC 95% development
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.


TYPICAL LOCATION OF CROSSROAD SIGNS



May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

△ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- 1. The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- 2. The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- 3. CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- 4. Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- 5. Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	HARDIN	13	

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

DATE: 12/15/2021 9:17:07 PM
FILE: C:\Users\RPASTORE\Desktop\Exports\0920-03-081, ETC 95% development\0920-03-081.dgn


SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT:	0920 03
REVISIONS		JOB:	081
9-07	8-14	HIGHWAY:	CR 101
7-13	5-21	DIST:	BMT
		COUNTY:	HARDIN
		SHEET NO.:	14

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/15/2021 9:17:09 PM
 FILE: C:\Users\RPASTOR\Desktop\PW_Export\0920-03-081_ETC_95%_development\0920-03-081\Standards\6.bc-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Nails shall NOT be allowed.
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12




BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21



FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0920	03	081	CR 101				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	HARDIN	15					

DATE: 12/15/2021 9:17:11 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Exp\0920-03-081, ETC 95% development\0920-03-081\Standards\6-BC-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats for incorrect results or damages resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS





GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0920 03	081	CR 101						
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	HARDIN	16					

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		0920	03	081	CR 101				
9-07	8-14	DIST:	COUNTY:	SHEET NO.:					
7-13	5-21	BMT	HARDIN	17					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 12/15/2021 9:17:15 PM
 FILE: C:\Users\RPASTORE\Desktop\Exports\0920-03-081, ETC 95% development\0920-03-081\Standards\6_bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation
 Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0920	03	081	CR 101				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	HARDIN	18					

DATE: 12/20/2021 11:29:59 AM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081\Standards\6.bc-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS




- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0920	03	081	CR 101				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	BMT	HARDIN	19					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/15/2021 9:17:20 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\0920-03-081, ETC 95% development\0920-03-081\Standards\6_bc-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	HARDIN	20	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 12/15/2021 9:17:22 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\0920-03-081_ETC_95%_development\0920-03-081_Standards\6_bc-21.dgn

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.



TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) -21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	HARDIN	21	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	HARDIN	22	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 12/15/2021 9:17:24 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081\Standards\6.bc-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	BMT	HARDIN	23	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/15/2021 9:17:26 PM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\Standards\6_bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any manner other than that intended by the original author.

DATE: 12/15/2021 11:08:08 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081.dwg



ROAD CLOSURE BEYOND THE INTERSECTION
 Signing for a Numbered Route with an Off-Site Detour



ROAD CLOSURE AT THE INTERSECTION
 Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "x" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'



* Conventional Roads Only

GENERAL NOTES


1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.

		Traffic Operations Division Standard	
WORK ZONE ROAD CLOSURE DETAILS			
WZ (RCD) - 13			
FILE: wzrcd-13.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
© TxDOT August 1995	CON: 0920	SECT: 03	JOB: 081
REVISIONS	DIST: BMT		COUNTY: HARDIN
1-97 4-98 7-13	SHEET NO. 24		
2-98 3-03			

DATE: 9/4/2019 11:19:42 AM
 FILE: L:\CIVIL CORP\LLC\ACTIVE\CEC\1912301-Bridge Locat\ions\Data\CR 101\Dgn\Ref Base\CR101*ACTRL01.dgn



- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, CENTRAL ZONE (4204), NAD83. ALL COORDINATES AND DISTANCES SHOWN HEREON ARE SURFACE AND MAY BE CONVERTED TO GRID BY DIVIDING BY A COMBINED ADJUSTMENT FACTOR OF 1.00003 (HARDIN COUNTY).
 2. ALL HORIZONTAL COORDINATE VALUES WERE DERIVED FROM GPS OBSERVATIONS UTILIZING THE TXDOT VRS.
 3. ELEVATION OF CONTROL POINT 1010 DERIVED FROM GPS OBSERVATIONS UTILIZING THE TXDOT VRS, ALL OTHER CONTROL POINT ELEVATIONS DERIVED BY THIRD ORDER DIGITAL LEVEL LOOP.
 4. ALL MEASUREMENTS ARE US SURVEY FEET.



SIGNED: *Brandon Absher*
 BRANDON M. ABSHER
 REGISTERED PROFESSIONAL
 LAND SURVEYOR TEXAS No. 6654




SURVEY CONTROL INDEX

SHEET 1 OF 1


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		SHEET NO.
6			25
STATE	STATE DISTRICT	COUNTY	
TEXAS	20	HARDIN	
CONST. C.S.J.	CONTRACT SECT.	JOB	HIGHWAY NO.
0920	03	081	CR 101

POINT	NORTH	EAST	ELEVATION	DESCRIPTION
1010	10,164,055.06	4,122,489.79	114.41	5/8" IRON ROD W/RED CAP STAMPED "CONTROL POINT"
1011	10,164,044.47	4,122,129.87	115.43	5/8" IRON ROD W/RED CAP STAMPED "CONTROL POINT"
1012	10,164,026.99	4,121,908.92	115.42	5/8" IRON ROD W/RED CAP STAMPED "CONTROL POINT"
1013	10,164,010.39	4,121,430.18	114.49	5/8" IRON ROD W/RED CAP STAMPED "CONTROL POINT"


FROM	TO	DIRECTION	DISTANCE
CP 1010	CP 1011	S 88° 18' 49" W	360.07
CP 1011	CP 1012	S 85° 28' 43" W	221.65
CP 1012	CP 1013	S 88° 00' 50" W	479.02




SITUATED ON THE SOUTH SIDE OF CR 101
APPROXIMATELY 8,500 FEET EAST OF BRAGG RD



SITUATED ON THE SOUTH SIDE OF CR 101
APPROXIMATELY 8,140 FEET EAST OF BRAGG RD




SITUATED ON THE SOUTH SIDE OF CR 101
APPROXIMATELY 7,920 FEET EAST OF BRAGG RD



SITUATED ON THE SOUTH SIDE OF CR 101
APPROXIMATELY 7,440 FEET EAST OF BRAGG RD

NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, CENTRAL ZONE (4204), NAD83. ALL COORDINATES AND DISTANCES SHOWN HEREON ARE SURFACE AND MAY BE CONVERTED TO GRID BY DIVIDING BY A COMBINED ADJUSTMENT FACTOR OF 1.00003 (HARDIN COUNTY).
2. ALL HORIZONTAL COORDINATE VALUES WERE DERIVED FROM GPS OBSERVATIONS UTILIZING THE TXDOT VRS.
3. ELEVATION OF CONTROL POINT 1010 DERIVED FROM GPS OBSERVATIONS UTILIZING THE TXDOT VRS. ALL OTHER CONTROL POINT ELEVATIONS DERIVED BY THIRD ORDER DIGITAL LEVEL LOOP.
4. ALL MEASUREMENTS ARE US SURVEY FEET.



SIGNED: *Brandon M. Absher*
BRANDON M. ABSHER
REGISTERED PROFESSIONAL
LAND SURVEYOR TEXAS No. 6654




HORIZONTAL AND
VERTICAL CONTROL



SHEET 1 OF 1

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		SHEET NO.
6			26
STATE	STATE DISTRICT	COUNTY	
TEXAS	20	HARDIN	
CONT.	SECT.	JOB	HIGHWAY NO.
0920	03	081	CR 101

DATE: 12/15/2021 9:18:00 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081\ready to print\0920-03-081\ROADWAY 1.dgn



* NOTE:
 ROW ASSUMED BASED ON GOVERNING
 COUNTY INFORMATION



Andrew C. Lee
 12/16/2021


0920-03-081
CR 101
FLAT CYPRESS
CREEK
PLAN & PROFILE

0 10 20
 SCALE IN FEET





CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	27	

DATE: 12/15/2021 9:18:03 PM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\ready to print\0920-03-081 ROADWAY 2.dgn



* SEE NOTE SHEET 27



Andrew C. Lee
 12/16/2021

0920-03-081
 CR 101
 FLAT CYPRESS
 CREEK
 PLAN & PROFILE




SHEET 3 OF 3



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	28	


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\Standards\gf3119.dgn




TYPICAL POST PLACEMENT

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25' - 0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




ELEVATION 25' - 0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.




WOOD BLOCK TO RECTANGULAR WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**

GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25' - 0", OR 12' - 6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.


				Design Division Standard
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19				
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	29	

DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081_ ETC 95% development\0920-03-081\Standards\gf31ms19.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)



SECTION A-A


Typical



MOW STRIP DETAIL


Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
 2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
 3. The leave-out behind the post shall be a minimum of 7".
 4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
 5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
 6. Thickness of the mow strip will be 4".
 7. The limits of payment for reinforced concrete will include leave-outs for the posts.
 8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)


Curb shown on top of mow strip



CURB OPTION (3)

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF(31)MS-19			
FILE: gf31ms19.dgn	DN: TxDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0920 03	081	CR 101
	DIST	COUNTY	SHEET NO.
	BMT	HARDIN	30





DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\0920-03-081_ETC_95%_development\0920-03-081_Standards\gf31tr+1320.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- (5) 1" DIA. HOLES.
- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (FACING TRAFFIC SIDE) (ASTM F3125 GR A325 OR A449).
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 7/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563).

NOTE:
HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE:
CURB IS A REQUIRED COMPONENT FOR THE TRANSITION TO FUNCTION PROPERLY. SEE GENERAL NOTES: 2-4 AND 16-17.




BRIDGE APPROACH - UPSTREAM: THE NESTED RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.
 BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.



THRIE-BEAM TERMINAL - CURB TABLE	
PRECAST CURB FULL LENGTH EQUALS 12'- 2"	
THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS.	
CURB (1) LENGTH	5'- 8"
CURB (2) LENGTH	6'- 6"
TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7	
CONNECTING PRECAST CURB SECTIONS (1) & (2):	
FORM OR CORE	1" DIA. HOLE 9" LONG INTO EACH CURB END.
USE	(1) #5 GR.60 REBAR 18" LONG TO CONNECT BOTH CURBS.
SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE *:	
FORM OR CORE	(4) 1" DIA. HOLES, SEE PLAN AND ELEVATION VIEWS FOR HOLE LOCATIONS. DRIVE (4) #5 GR.60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB.
FILL HOLES WITH APPROVED GROUT MIXTURE.	

* NOTES: NOT NEEDED FOR CAST-IN-PLACE. SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS. PERCUSSION DRILLING IS NOT PERMITTED WITH: TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.



NOTE: OPTIONS FOR TYPE II CURB:
 1. PRECAST
 2. CAST-IN-PLACE

GENERAL NOTES

1. CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
2. CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5- 3/4" HEIGHT); SEE CURRENT CCGG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE:17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
3. CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
4. UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
5. FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
6. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF (31) STANDARD SHEET.
7. THE POST LENGTH SHALL BE MARKED ON ALL 7'- 0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 5/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
8. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
9. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
10. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
11. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
12. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
13. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
14. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TxDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
15. REFER TO GF (31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
16. THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
17. IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION, (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED) (TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED) (STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT.2 FOR ADDITIONAL INFORMATION.

**HIGH-SPEED TRANSITION
SHEET 1 OF 2**

		Design Division Standard	
METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT GF (31) TR TL3-20			
FILE: gf31tr+1320.dgn	DN: TxDOT	CK: KM	DW: VP
© TxDOT: NOVEMBER 2020	CONT: 0920 03	SECT: 081	JOB: CR 101
REVISIONS	DIST: BMT	COUNTY: HARDIN	SHEET NO.: 31


DISCLAIMER:
 THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER.
 TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\Standards\gf31tr+1320.dgn


REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)

END PAYMENT FOR METAL BEAM GUARD FENCE TRANSITION.
 BEGIN PAYMENT FOR METAL BEAM GUARD FENCE.


(SEE GF (31) STANDARD SHEET)



ELEVATION VIEW



SECTION D-D



THRIE BEAM TRANSITION BLOCKOUT DETAILS

HIGH-SPEED TRANSITION

SHEET 2 OF 2




METAL BEAM GUARD FENCE
 THRIE-BEAM TRANSITION
 TL-3 MASH COMPLIANT

GF (31) TR TL3-20


FILE: gf31tr+1320.dgn	DN: TXDOT	CK: KM	DW: KM	CK: CGL/AG
©TXDOT: NOVEMBER 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	32	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW_Exports\0920-03-081_ETC_95%_development\0920-03-081_Standards\cccg21.dgn




TYPE I CURB (MONOLITHIC)
 2" - 4" HEIGHT




TYPE I CURB
 2" - 4" HEIGHT




TYPE I CURB AND GUTTER
 2" - 4" HEIGHT




TYPE II CURB (MONOLITHIC)
 5" - 5 3/4" HEIGHT




TYPE II CURB
 5" - 5 3/4" HEIGHT




TYPE II CURB AND GUTTER
 5" - 5 3/4" HEIGHT




TYPE III CURB (KEYED)
 2" - 4" HEIGHT




TYPE IIa CURB
 5" - 5 3/4" HEIGHT




TYPE IIa CURB AND GUTTER
 5" - 5 3/4" HEIGHT



TYPE IV CURB (KEYED)
 5" - 5 3/4" HEIGHT




EXPANSION JOINT DETAIL



CURB TRANSITION
 Note: To be paid for as Highest Curb


GENERAL NOTES

- All materials and construction shall be in accordance with Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- Concrete shall be Class A.
- When reinforcing bars are used, they shall be No.4 unless otherwise shown. The use of fiber reinforced concrete in lieu of reinforcing steel is acceptable. Use fibers meeting the requirements of DMS 4550, "Fibers for Concrete," and dose fibers in accordance with Material Producers List (MPL) "Fibers for Class A and B Concrete Applications."
- Round exposed sharp edges with a rounding tool, to a minimum radius of 1/4 inch.
- All existing curbs and driveways to be removed shall be sawed or removed at existing joints.
- Where concrete curb is to be placed on existing concrete pavement, Bar B may be drilled and the grouted in place, or may be inserted into fresh concrete.
- Expansion and contraction joints shall be constructed to match pavement joints in all curbs and curb and gutter adjacent to jointed concrete pavement. Where placement of curb or curb and gutter is not adjacent to concrete pavement, expansion joints shall be provided at structures, curb returns at streets, and at locations directed by The Engineer.
- Vertical and horizontal dowel bars and transverse reinforcing bars shall be placed at four feet C-C.
- Dimension 'T' shown is the thickness of concrete pavement. When curb is installed adjacent to flexible pavement dimension 'T' is 8" maximum.
- Usual profile grade line. Refer to typical sections and plan-profile sheets for exact locations.
- One-half inch expansion joint material shall be provided where curb or curb and gutter is adjacent to sidewalk or riprap.
- When horizontal permissible construction joints are used, the longitudinal pavement steel shall be placed in accordance with pavement details shown elsewhere in the plans. Reinforcing steel for curb section shall then conform to that required for concrete curb.
- Bar B used as needed to support curb reinforcing steel during concrete placement.



CURB TRANSITION NOTE:
 Field conditions may require a longer or shorter transition, and shall be shown elsewhere in the plans, or as directed by the Engineer.

				Design Division Standard	
CONCRETE CURB AND GUTTER					
CCCG-21					
FILE: cccg21.dgn	DN: TxDOT	CK: AN	DW: SS	CK: KM	
© TxDOT: FEBRUARY 2021	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0920	03	081	CR 101	
	DIST	COUNTY		SHEET NO.	
	BMT	HARDIN		33	



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; Soft+Stop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IT IS ACCEPTABLE TO INSTALL THE Soft+Stop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
 - DO NOT ATTACH THE Soft+Stop SYSTEM DIRECTLY TO A RIGID BARRIER.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE Soft+Stop SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoaching ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTE: A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE: B PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

NOTE: C W-BEAM SPLICE LOCATED BETWEEN LINE POST (4) AND LINE POST (5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	Soft+Stop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	Soft+Stop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	Soft+Stop DOWNSTREAM W-BEAM RAIL (12GA) (25' - 0")
15205A	1	POST #0 - ANCHOR POST (6' - 5 7/8")
15203G	1	POST #1 - (SYTP) (4' - 9 1/2")
15000G	1	POST #2 - (SYTP) (6' - 0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 x 8.5) (6' - 0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" x 8" x 14")
6777B	7	BLOCKOUT - COMPOSITE (4" x 7 1/2" x 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" x 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" x 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" x 10" HGR POST BOLT A307
3391G	1	5/8" x 1 3/4" HEX HD BOLT A325
4489G	1	5/8" x 9" HEX HD BOLT A325
4372G	4	3/8" WASHER F436
105285G	2	5/8" x 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" x 1 1/2" HEX HD BOLT GR-5
3240G	6	3/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B


Texas Department of Transportation
 Design Division Standard

**TRINITY HIGHWAY
 SOFTSTOP END TERMINAL
 MASH - TL-3
 SGT (10S) 31-16**

FILE: sgt10s3116	DW: TxDOT	CK: KM	DW: VP	CK: MB/VP
©TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
DIST	COUNTY		SHEET NO.	
BMT	HARDIN		34	

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE Soft+Stop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.





DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\Exp\ts\0920-03-081, ETC 95% development\0920-03-081.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings or specifications to any other format or for any errors or omissions resulting from its use.




NOTES:
 1. ITEM ② COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (9) THRU LINE POST (2).
 2. DO NOT INSTALL A BLOCKOUT AT LINE POST (1).

NOTE: SECURE THE (TSS) PANEL TO OUTSIDE OF RAIL 2 WITH THE PANEL ARROWS POINTING TOWARDS THE HEAD.


- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
 - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL. P/N MANMAX REV D (ECN 3516).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
 - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
 - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
 - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
 - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
 - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.



ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	3/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	3/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1



* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN.
 ITEM (26) 8" WOOD-BLOCKOUTS
 ITEM (27) 25' GUARD FENCE PANELS




NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

MAX-TENSION END TERMINAL
MASH - TL-3
SGT (11S) 31-18



FILE: sg11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
DIST	COUNTY		SHEET NO.	
BMT	HARDIN		35	

DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081\Standards\sgt12s3118.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSG STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSG.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSG PANELS, ONE 25'-0" MBSG PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
o	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard

SINGLE GUARDRAIL TERMINAL




MSKT-MASH-TL-3

SGT (12S) 31-18



FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS				
0920	03	081	CR 101	
DIST	COUNTY		SHEET NO.	
BMT	HARDIN		36	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/15/2021 9:18:30 PM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\Standards\bed14.dgn



- GENERAL NOTES**
1. For more detail: See GF(31), SGT()31, GF(31)TR, and GF(31)TL2 standard sheets.
 2. Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
 3. Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
 4. MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
 5. Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
 6. Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal, See Detail A)
 7. The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
 8. For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge locations shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
 9. Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
 10. A minimum 25' length of MBGF will be required.



Texas Department of Transportation
 Design Division Standard


BRIDGE END DETAILS
 (METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)

BED-14


FILE: bed14.dgn	DN: TxDOT	CK: AM	DW: BD/VP	CK: CGL
© TxDOT: December 2011	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920 03	081	CR 101	
REVISED APRIL 2014 SEE (MEMO 0414)	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	37	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this drawing or for any damages resulting from its use.


DATE: 12/15/2021 9:18:33 PM
 FILE: C:\User\s\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081.dgn




PLAN



ELEVATION




SECTION A-A AT CAP




SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A



CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2

		Bridge Division Standard	
<h2>STONE RIPRAP</h2>			
<h3>SRR</h3>			
FILE: srrstde1-19.dgn	DN: AES	CK: JGD	DW: BWH
©TxDOT April 2019	CONT	SECT	HIGHWAY
REVISIONS	0920	03	081 CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		38

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or damages resulting from its use.

DATE: 12/15/2021 9:18:35 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081\Standard\0920-03-081.dwg




FIGURE 1 ~ TYPE R STONE RIPRAP
dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP
dry or mortared






FIGURE 3 ~ TYPE F STONE RIPRAP
grouted

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



PROTECTION STONE RIPRAP TOE OPTIONS ⑤




FIGURE 4 ~ COMMON STONE RIPRAP
dry or grouted




FIGURE 5 ~ PROTECTION STONE RIPRAP ⑤

STONE RIPRAP

SRR

FILE: srrside1-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	39	

EXISTING

Plan: DN FCCCR101 Flat Cypress FCC RS: 429 Profile: 10

E.G. US. (ft)	111.77	Element	Inside BR US	Inside BR DS
W.S. US. (ft)	111.76	E.G. Elev (ft)	111.74	111.68
Q Total (cfs)	180.00	W.S. Elev (ft)	111.68	111.64
Q Bridge (cfs)	180.00	Crit W.S. (ft)	111.13	110.86
Q Weir (cfs)		Max Chl Dpth (ft)	1.07	1.41
Weir Sta Lft (ft)		Vel Total (ft/s)	1.90	1.54
Weir Sta Rgt (ft)		Flow Area (sq ft)	94.68	116.82
Weir Submerg		Froude # Chl	0.32	0.24
Weir Max Depth (ft)		Specif Force (cu ft)	60.20	84.86
Min El Weir Flow (ft)	115.62	Hydr Depth (ft)	1.05	1.29
Min El Prs (ft)	114.90	W.P. Total (ft)	92.63	93.04
Delta EG (ft)	0.12	Conv. Total (cfs)	3568.8	4736.7
Delta WS (ft)	0.11	Top Width (ft)	90.44	90.44
BR Open Area (sq ft)	371.50	Frctn Loss (ft)	0.05	0.01
BR Open Vel (ft/s)	1.90	C & E Loss (ft)	0.01	0.02
BR Sluice Coef		Shear Total (lb/sq ft)	0.16	0.11
BR Sel Method	Energy only	Power Total (lb/ft s)	0.31	0.17

Plan: DN FCCCR101 Flat Cypress FCC RS: 429 Profile: 100

E.G. US. (ft)	112.15	Element	Inside BR US	Inside BR DS
W.S. US. (ft)	112.13	E.G. Elev (ft)	112.10	112.03
Q Total (cfs)	300.00	W.S. Elev (ft)	112.01	111.96
Q Bridge (cfs)	300.00	Crit W.S. (ft)	111.34	111.08
Q Weir (cfs)		Max Chl Dpth (ft)	1.40	1.73
Weir Sta Lft (ft)		Vel Total (ft/s)	2.41	2.06
Weir Sta Rgt (ft)		Flow Area (sq ft)	124.69	145.83
Weir Submerg		Froude # Chl	0.36	0.29
Weir Max Depth (ft)		Specif Force (cu ft)	108.40	138.07
Min El Weir Flow (ft)	115.62	Hydr Depth (ft)	1.38	1.61
Min El Prs (ft)	114.90	W.P. Total (ft)	93.29	93.68
Delta EG (ft)	0.16	Conv. Total (cfs)	5620.2	6802.5
Delta WS (ft)	0.15	Top Width (ft)	90.39	90.40
BR Open Area (sq ft)	371.50	Frctn Loss (ft)	0.06	0.01
BR Open Vel (ft/s)	2.41	C & E Loss (ft)	0.01	0.03
BR Sluice Coef		Shear Total (lb/sq ft)	0.24	0.19
BR Sel Method	Energy only	Power Total (lb/ft s)	0.57	0.39

HEC-RAS Plan: DN FCCCR101 River: Flat Cypress Reach: FCC

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
FCC	25	10	180.00	110.01	111.02	110.51	111.04	0.005001	1.02	175.93	254.89	0.22
FCC	25	100	300.00	110.01	111.29	110.63	111.32	0.005006	1.21	248.79	281.76	0.23
FCC	125	10	180.00	110.10	111.34		111.35	0.002084	0.76	235.87	276.17	0.15
FCC	125	100	300.00	110.10	111.63		111.64	0.002218	0.95	316.93	281.00	0.16
FCC	225	10	180.00	110.23	111.51		111.52	0.001421	0.71	252.70	245.00	0.12
FCC	225	100	300.00	110.23	111.82		111.83	0.001654	0.91	328.37	245.00	0.14
FCC	325	10	180.00	110.23	111.62		111.62	0.000797	0.54	331.30	313.00	0.09
FCC	325	100	300.00	110.23	111.94		111.95	0.000906	0.69	433.56	313.00	0.10
FCC	396	10	180.00	110.23	111.65		111.65	0.000322	0.80	357.30	342.20	0.12
FCC	396	100	300.00	110.23	111.98		111.99	0.000391	1.02	475.10	367.70	0.14
FCC	429		Bridge									
FCC	462	10	180.00	110.58	111.76	110.97	111.77	0.000471	0.86	253.34	282.76	0.14
FCC	462	100	300.00	110.58	112.13	111.09	112.15	0.000471	1.05	364.85	319.04	0.15
FCC	525	10	180.00	110.58	111.84		111.85	0.001848	0.89	202.22	170.00	0.14
FCC	525	100	300.00	110.58	112.21		112.23	0.002078	1.13	265.52	170.00	0.16
FCC	625	10	180.00	110.68	111.95		111.96	0.000665	0.54	334.71	279.00	0.09
FCC	625	100	300.00	110.68	112.34		112.35	0.000727	0.68	443.29	279.00	0.09
FCC	725	10	180.00	110.63	112.02		112.02	0.000574	0.53	341.71	263.00	0.08
FCC	725	100	300.00	110.63	112.41		112.42	0.000659	0.67	445.99	263.00	0.09
FCC	825	10	180.00	110.74	112.08		112.09	0.000797	0.62	292.23	227.00	0.10
FCC	825	100	300.00	110.74	112.49		112.50	0.000894	0.78	384.05	227.00	0.11
FCC	925	10	180.00	110.69	112.15		112.15	0.000536	0.51	351.98	269.00	0.08
FCC	925	100	300.00	110.69	112.56		112.57	0.000598	0.65	463.20	269.00	0.09

PROPOSED

Plan: temp 1 Flat Cypress FCC RS: 429 Profile: 10yr


E.G. US. (ft)	112.13	Element	Inside BR US	Inside BR DS
W.S. US. (ft)	112.10	E.G. Elev (ft)	112.06	111.88
Q Total (cfs)	193.22	W.S. Elev (ft)	111.97	111.73
Q Bridge (cfs)	193.22	Crit W.S. (ft)	111.35	111.31
Q Weir (cfs)		Max Chl Dpth (ft)	1.36	1.45
Weir Sta Lft (ft)		Vel Total (ft/s)	2.41	2.69
Weir Sta Rgt (ft)		Flow Area (sq ft)	80.27	71.92
Weir Submerg		Froude # Chl	0.38	0.77
Weir Max Depth (ft)		Specif Force (cu ft)	66.62	60.52
Min El Weir Flow (ft)	115.81	Hydr Depth (ft)	1.23	1.14
Min El Prs (ft)	114.90	W.P. Total (ft)	71.18	69.11
Delta EG (ft)	0.34	Conv. Total (cfs)	3230.7	1609.8
Delta WS (ft)	0.38	Top Width (ft)	65.46	63.67
BR Open Area (sq ft)	302.89	Frctn Loss (ft)	0.17	0.05
BR Open Vel (ft/s)	2.69	C & E Loss (ft)	0.02	0.04
BR Sluice Coef		Shear Total (lb/sq ft)	0.25	0.94
BR Sel Method	Energy only	Power Total (lb/ft s)	0.61	2.51

Plan: temp 1 Flat Cypress FCC RS: 429 Profile: 100yr

E.G. US. (ft)	112.55	Element	Inside BR US	Inside BR DS
W.S. US. (ft)	112.50	E.G. Elev (ft)	112.46	112.24
Q Total (cfs)	303.15	W.S. Elev (ft)	112.33	112.01
Q Bridge (cfs)	303.15	Crit W.S. (ft)	111.59	111.58
Q Weir (cfs)		Max Chl Dpth (ft)	1.72	1.73
Weir Sta Lft (ft)		Vel Total (ft/s)	2.91	3.37
Weir Sta Rgt (ft)		Flow Area (sq ft)	104.12	89.83
Weir Submerg		Froude # Chl	0.41	0.88
Weir Max Depth (ft)		Specif Force (cu ft)	112.69	100.06
Min El Weir Flow (ft)	115.81	Hydr Depth (ft)	1.54	1.38
Min El Prs (ft)	114.90	W.P. Total (ft)	75.41	72.39
Delta EG (ft)	0.43	Conv. Total (cfs)	4795.7	2267.5
Delta WS (ft)	0.49	Top Width (ft)	68.15	65.76
BR Open Area (sq ft)	302.89	Frctn Loss (ft)	0.19	0.06
BR Open Vel (ft/s)	3.37	C & E Loss (ft)	0.03	0.06
BR Sluice Coef		Shear Total (lb/sq ft)	0.34	1.38
BR Sel Method	Energy only	Power Total (lb/ft s)	1.00	4.67

HEC-RAS Plan: temp 1 River: Flat Cypress Reach: FCC

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
FCC	25	10yr	193.22	110.01	111.06	110.52	111.07	0.005005	1.05	184.47	258.19	0.22
FCC	25	100yr	303.15	110.01	111.30	110.63	111.32	0.005006	1.21	250.58	282.39	0.23
FCC	125	10yr	193.22	110.10	111.37		111.38	0.002112	0.79	245.89	278.31	0.15
FCC	125	100yr	303.15	110.10	111.63		111.65	0.002222	0.95	318.78	281.00	0.16
FCC	225	10yr	193.22	110.23	111.55		111.56	0.001447	0.74	262.25	245.00	0.13
FCC	225	100yr	303.15	110.23	111.83		111.84	0.001659	0.92	330.10	245.00	0.14
FCC	325	10yr	193.22	110.23	111.66		111.66	0.000808	0.56	344.31	313.00	0.09
FCC	325	100yr	303.15	110.23	111.95		111.96	0.000906	0.69	436.22	313.00	0.10
FCC	396	10yr	193.22	110.23	111.72		111.79	0.004108	2.87	108.99	347.75	0.44
FCC	396	100yr	303.15	110.23	112.01		112.12	0.005040	3.62	134.86	369.84	0.50
FCC	429		Bridge									
FCC	462	10yr	193.22	110.58	112.10	111.16	112.13	0.000996	1.51	132.10	316.08	0.22
FCC	462	100yr	303.15	110.58	112.50	111.35	112.55	0.001106	1.87	167.75	354.85	0.24
FCC	525	10yr	193.22	110.58	112.23		112.23	0.000841	0.72	267.52	170.00	0.10
FCC	525	100yr	303.15	110.58	112.65		112.66	0.000939	0.90	339.56	170.00	0.11
FCC	625	10yr	193.22	110.68	112.28		112.29	0.000344	0.45	426.13	279.00	0.06
FCC	625	100yr	303.15	110.68	112.71		112.72	0.000371	0.55	546.53	279.00	0.07
FCC	725	10yr	193.22	110.63	112.32		112.32	0.000333	0.46	420.43	263.00	0.06
FCC	725	100yr	303.15	110.63	112.75		112.76	0.000369	0.57	534.74	263.00	0.07
FCC	825	10yr	193.22	110.74	112.35		112.36	0.000486	0.55	354.01	227.00	0.08
FCC	825	100yr	303.15	110.74	112.79		112.80	0.000527	0.67	453.46	227.00	0.08
FCC	925	10yr	193.22	110.69	112.40		112.40	0.000347	0.46	418.65	269.00	0.07
FCC	925	100yr	303.15	110.69	112.84		112.84	0.000373	0.56	537.56	269.00	0.07



Andrew C. Lee

12/16/2021




0920-03-081
CR 101
HYDRAULIC &
HYDROLOGIC
DATA

N. T. S

CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		40

DATE: 12/15/2021 9:18:37 PM
FILE: C:\Users\NPASTORE\Desktop\0920-03-081 - ETC 95% development\0920-03-081\ready to print\HYDRAULIC & HYDROLOGIC DATA v2.dgn


DATE: 12/17/2021 3:57:41 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081\ready to print\0920-03-081 BRIDGE LAYOUT.dgn




LaDonna M. Waters

12/17/2021

ALL BENTS ARE ON BEARING N/S 92°24' 0"
 *NOTE: ROW ASSUMED BASED ON GOVERNING COUNTY INFORMATION



EX NBI #: 20-101-0-AA01-01-001
 PROP. NBI #: 20-101-0-AA01-01-002
 DESIGN SPEED: 30 MPH
 ADT (2019): 10
 TERRIAN: LEVEL
 FUNCT CLASS: LOCAL



Andrew C. Lee

12/17/2021

**0920-03-081
 CR 101
 FLAT CYPRESS
 CREEK
 BRIDGE LAYOUT**



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	41	

DATE: 12/17/2021 9:41:45 AM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\ready to print\BRIDGE\SUMMARY(S).dgn

SUMMARY OF ESTIMATED QUANTITIES										
ITEM #		409-6002	420-6013	420-6025	422-6007	425-6010	432-6033	450-6006	454-6003	496-6009
BRIDGE ELEMENT	BID ITEM DESCRIPTION	PRESTR CONC PIL (18 IN SQ)	CL C CONC (ABUT)	CL C CONC (BENT)	REINF CONC SLAB (SLAB BEAM)	PRESTR CONC SLAB BEAM (5SB12)	RIPRAP (STONE PROTECTIO N)	RAIL (TY T223)	ARMOR JOINT	REMOV STR (BRIDGE 0-99 FT LENGTH)
	No.	UNIT	LF	CY	CY	SF	LF	CY	LF	EA
2	ABUTMENTS	322.00	17.6	-	-	-	683	24.0	44	-
2	INTERIOR BENTS	354.00	-	13.2	-	-	-	-	-	-
3	30' PRESTR CONC SLAB BEAM SPANS	-	-	-	2340.0	442.50	-	180.0	-	-
TOTAL		676.00	17.60	13.20	2340.00	442.50	683.00	204.00	44.00	1.00

CAP ELEVATIONS (FT)

	STEP 1 (RIGHT)	STEP 3 (LT. SIDE)	STEP 3 (RT. SIDE)	STEP 4 (LT. SIDE)	STEP 4 (RT. SIDE)	STEP 6 (LEFT)
ABUT 1 (FWD)	114.495	114.702	114.702	114.702	114.702	114.495
BENT 2 (BK) (FWD)	114.495	114.702	114.702	114.702	114.702	114.495
BENT 3 (BK) (FWD)	114.495	114.702	114.702	114.702	114.702	114.495
ABUT 4 (BK)	114.495	114.702	114.702	114.702	114.702	114.495

BEAM SLOPES (FT/FT)

	BEAM 1	BEAM 2	BEAM 3	BEAM 4	BEAM 5
SPAN 1	0.0000	0.0000	0.0000	0.0000	0.0000
SPAN 2	0.0000	0.0000	0.0000	0.0000	0.0000
SPAN 3	0.0000	0.0000	0.0000	0.0000	0.0000

ELEVATION LOCATIONS

DISTANCE FROM PGL TO STEP 1 ALONG CENTERLINE OF BEARING = 13.000 FT LT

STEP SPACING (ALONG C. L. OF BEARING)

STEP 1	10.372 FT
STEP 3	5.255 FT
STEP 4	10.372 FT
STEP 6	


STEP POSITIONS

STEP 1 is located to the left of BEAM 1.
 STEP 3 is located to the between BEAM 2 and BEAM 3.
 STEP 4 is located to the between BEAM 3 and BEAM 4.
 STEP 6 is located to the right of BEAM 5.

BEARING PAD TAPER (IN/IN) -- FABRICATOR'S REPORT PERPENDICULAR TO THE CENTERLINE OF BEARING.

SUMMATION OF BEARING PAD TAPER DUE TO CROSS-SLOPE, GRADE, AND SKEW, MEASURED IN IN/IN. A POSITIVE TAPER INDICATES INCREASING PAD THICKNESS IN DIRECTION OF INCREASING STATIONS. A NEGATIVE TAPER INDICATES DECREASING PAD THICKNESS IN DIRECTION OF INCREASING STATIONS.

	BEAM 1	BEAM 2	BEAM 3	BEAM 4	BEAM 5
ABUT 1 (FWD)	0.0000	0.0000	0.0000	0.0000	0.0000
BENT 2 (BK) (FWD)	0.0000	0.0000	0.0000	0.0000	0.0000
BENT 3 (BK) (FWD)	0.0000	0.0000	0.0000	0.0000	0.0000
ABUT 4 (BK)	0.0000	0.0000	0.0000	0.0000	0.0000




Andrew C. Lee
12/17/2021

**0920-03-081
ESTIMATED QUANTITIES
& BEARING SEAT ELEVATIONS**



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	42	

DATE: 12/16/2021 10:23:28 AM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\ready to print\BRIDGE BORINGS.dgn




A	SAND, GRAVEL, ASPHALT, BASE
B	CLAY, SOFT, BROWN, SANDY, W/SAND SEAMS & GRAVEL (CL)
C	CLAY, SOFT, REDDISH TAN, VERY SANDY W/SAND SEAMS (CL)
D	SAND, SLIGHTLY COMPACT, LIGHT BROWN, CLAYEY (SC)
E	CLAY, WET, LIGHT BROWN SANDY (CL)
F	CLAY, SOFT, LIGHT BROWN, SANDY W/ SAND SEAMS (CL)
G	CLAY, VERY SOFT LIGHT GRAY SANDY W/ IRON STAINS (CL)
H	CLAY, SOFT, REDDISH BROWN, SANDY (CL)
I	CLAY, VERY SOFT TO STIFF, LIGHT GRAY, SILTY, SANDY, W/IRON STAINS (CL)
J	SAND, SLIGHTLY COMPACT TO DENSE, WET, LIGHT BROWN, SILTY (SM)
K	CLAY, STIFF, LIGHT GRAY, SILTY W/IRON STAINS AND TRACE SAND (CL)
L	CLAY, BROWN, SANDY, BASE (CL)
M	CLAY, STIFF, BROWN, SANDY, W/ IRON STAINS AND NODULES, AND SAND SEAMS AND LAYERS (CL)
N	CLAY, SOFT, LIGHT BROWN, SANDY (CL)
O	CLAY, SOFT, WET, LIGHT BROWN, SANDY (CL)
P	CLAY, VERY SOFT, LIGHT BROWN, SANDY, W/ IRON STAINS (CL)
Q	CLAY, SOFT TO STIFF, LIGHT GRAY, SILTY, SANDY, W/ IRON STAINS (CL)
R	SAND, COMPACT, WET, LIGHT BROWN, SILTY (SM)
S	SAND, COMPACT TO SLIGHTLY COMPACT, WET, LIGHT BROWN, CLAYEY, W/ CLAY SEAMS (SC)
T	CLAY, VERY STIFF TO STIFF, LIGHT GRAY, SILTY, W/ TRACE SAND (CL)



Ladonna M. Waters


12/16/2021

0920-03-081
CR 101
BRIDGE BORINGS




CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	43	


DATE: 12/15/2021 9:18:59 PM
 FILE: C:\User\SRPASTORE\Desktop\0920-03-081.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion results or damages resulting from its use.



SHOWING DRILLED SHAFTS PLAN SHOWING PILES





ELEVATION ~ DRILLED SHAFT ABUTMENT




ELEVATION ~ PILING ABUTMENT

Note: For piles larger than 16", adjust Bars S spacing as required to avoid piles.




SECTION A-A

(With approach slab)
 Note: At Contractor's option, backwall may be cast with approach slab.




BACKWALL DETAIL

(Without approach slab)
 Note: At Contractor's option, backwall may be cast in one lift to roadway surface.



WINGWALL ELEVATION

(Earwall not shown for clarity.)



BACKWALL CAP CORNER DETAILS

Span Length	FOUNDATION LOADS			
	Drilled Shaft Loads		Vertical Pile Loads	
	5SB12	5SB15	5SB12	5SB15
25	39	41	29	31
30	43	46	33	34
35	48	51	36	38
40	52	55	39	41
45	59		44	
50		63		47

TABLE OF ESTIMATED QUANTITIES							
Bar	No.	Size	Length (5)		Weight (5)		
			5SB12	5SB15	5SB12	5SB15	
A	6	#11	27'-1"	27'-1"	863	863	
E	4	#4	2'-2"	2'-2"	6	6	
F	10	#4	6'-4"	6'-4"	43	43	
H	2	#5	25'-8"	25'-8"	54	54	
L	6	#6	4'-0"	4'-0"	36	36	
S	34	#4	9'-4"	9'-4"	212	212	
U	4	#6	7'-1"	7'-1"	43	43	
V	25	#5	7'-4"	7'-10"	191	204	
wH1	8	#6	5'-8"	5'-8"	68	68	
wH2	8	#6	6'-11"	6'-11"	83	83	
wU	12	#4	1'-8"	1'-8"	14	14	
wV	28	#5	3'-10"	4'-1"	112	119	
Reinforcing Steel					Lb	1,725	1,745
CI "C" Conc (Abut)					CY	8.8	9.2

- Top of cap elevations are based on section depths shown on Span Details.
- See Span Details for "Y".
- Increase as required to maintain 3" from finished grade.
- See Bridge Layout to determine if approach slab is present.
- See Bridge Layout for beam type used in the superstructure.
- Quantities shown are for one abutment only (with approach slab). Without approach slab, add 1.0 CY Class "C" concrete and 54 Lb reinforcing steel for 2 additional Bars H.
- 1/2" preformed bituminous fiber material between slab beam and earwall. Bond to earwall with an approved adhesive. Cast inside face of earwall perpendicular to cap. (Typ)

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Designed for a normal embankment header slope of 3:1 and a maximum span length of 50 feet.
 See Bridge Layout for header slope and foundation type, size, and length.
 See Common Foundation Details (FD) standard sheet for all foundation details and notes.
 See Concrete Riprap (CRR) standard sheet or Stone Riprap (SRR) standard sheet for riprap attachment details, if applicable.
 See applicable rail details for rail anchorage in wingwalls.
 These abutment details may be used with standard SPSB-24 only.


Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

MATERIAL NOTES:
 Provide Class C concrete (f'c = 3,600 psi).
 Provide Class C (HPC) concrete if shown elsewhere in the plans.
 Provide Grade 60 reinforcing steel.


HL93 LOADING

Texas Department of Transportation		Bridge Division Standard	
ABUTMENTS			
PRESTR CONCRETE SLAB BEAM			
24' ROADWAY			
APSB-24			
FILE: pbsbte09-17.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT January 2017	CONV	SECT	JOB
REVISIONS	0920	03	081
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	44	


DATE: 12/15/2021 9:19:02 PM
 FILE: C:\Users\RPASTOR\OneDrive\Documents\0920-03-081\SPSB-24.dgn
 ETC 95% development
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information shown on this drawing.



SHOWING COLUMNS PLAN SHOWING PILES



ELEVATION ~ 3 COLUMN BENT



ELEVATION ~ 5 PILE BENT




Note: For piles larger than 16", adjust Bars S spacing as required to avoid piles.

FOUNDATION LOADS				
Average Span Length	Drilled Shaft Loads (5)		Vertical Pile Loads	
	5SB12	5SB15	5SB12	5SB15
25	57	61	34	37
30	66	71	40	42
35	73	79	44	47
40	80	87	48	52
45		94		57
50		102		61

TABLE OF ESTIMATED QUANTITIES (3)					
3 COLUMN BENT					
Bar	No.	Size	Length	Weight	
A	8	#11	27'-9"	1,180	
E	4	#4	2'-2"	6	
F	14	#4	6'-6"	61	
S	34	#5	9'-8"	343	
T	4	#5	27'-9"	116	
V	24	#7	26'-3"	1,288	
Z	3	#3	242'-2"	273	
Reinforcing Steel				Lb	3,267
Cl "C" Conc (Cap)				CY	6.6
Cl "C" Conc (Column)				CY	8.4

TABLE OF ESTIMATED QUANTITIES					
5 PILE BENT					
Bar	No.	Size	Length	Weight	
A	5	#11	27'-9"	737	
E	4	#4	2'-2"	6	
F	14	#4	6'-6"	61	
S	34	#5	9'-8"	343	
T	4	#5	27'-9"	116	
Reinforcing Steel				Lb	1,263
Cl "C" Conc (Cap)				CY	6.6

TABLE OF MAXIMUM ALLOWABLE EXPOSED PILE HEIGHTS AND PILE LOADS (4)			
Pile Type		Max Ht	Max Load
Concrete	Steel	Ft	Tons/Pile
16" Sq	HP14x73	16	75
18" Sq	HP14x117 (6)	20	90



- Top of cap elevations are based on section depths shown on Span Details.
- 1/2" preformed bituminous fiber material between slab beam and earwall. Bond to earwall with an approved adhesive. Cast inside face of earwall perpendicular to cap. (Typ)
- Quantities shown are based on an "H" value of 24 feet. For each linear foot variation in "H" value, make the following adjustments:
 Bars V length, 1'-0"
 Bars Z length, 9'-6"
 Reinforcing Steel, 60 Lb
 Class "C" conc (column), 0.35 CY
- This standard may not be used for "H" heights exceeding 24 feet or exposed pile heights exceeding the values shown in the table. In areas of very soft soil or where scour is anticipated, allowable "H" heights or exposed pile heights must be evaluated by the Engineer prior to the use of this standard.
- Foundation Loads based on "H" = 24 feet.
- When HP14x117 steel piling is specified in the plans, the Contractor has the option of furnishing either HP14x117 or HP16x101 steel piling.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications. Bent selected must be based on the average span length rounded up to the next 5-foot increment.
 For pile bents supporting unequal spans, the shorter span cannot be less than 80 percent of the longer span.
 See Bridge Layout for foundation type, size, and length.
 See Common Foundation Details (FD) standard sheet for all foundation details and notes.
 These bent details do not support the use of multi-pile footings shown on the FD standard.
 These bent details may be used with standard SPSB-24 only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.


MATERIAL NOTES:
 Provide Class C concrete (f'c = 3,600 psi).
 Provide Class C (HPC) concrete if shown elsewhere in the plans.
 Provide Grade 60 reinforcing steel.

HL93 LOADING


		Bridge Division Standard
<h2>INTERIOR BENTS</h2> <h3>PRESTR CONCRETE SLAB BEAM</h3>		
<h2>24' ROADWAY</h2>		
<h2>BPSB-24</h2>		
FILE: pbsste21-17.dgn	DN: TxDOT	CK: TxDOT
©TxDOT January 2017	CON: 0920	SECT: 03
REVISIONS	JOB: 081	HIGHWAY: CR 101
DIST: BMT	COUNTY: HARDIN	SHEET NO: 45

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of any information contained herein. DATE: 12/15/2021 9:19:05 PM FILE: C:\Users\RPASTORE\Desktop\0920-03-081_ ETC 95% development\0920-03-081\SPSB-24.dgn


DATE: 12/15/2021 9:19:05 PM FILE: C:\Users\RPASTORE\Desktop\0920-03-081_ ETC 95% development\0920-03-081\SPSB-24.dgn




PLAN




DETAIL "A"



CONTINUOUS SLAB DETAIL




TYPICAL TRANSVERSE SECTION



TYPE A JOINT DETAIL (9)

TABLE OF VARIABLE VALUES

Span Length	Beam Type	Dead Load Deflection		Section Depths (3)	
		"A"	"B"	"X"	"Y"
Ft	(1)	Ft	Ft	In	Ft/In
25	5SB12	0.004	0.005	5 1/4"	1'-5 1/4"
30	5SB12	0.008	0.011	5 1/2"	1'-5 1/2"
35	5SB12	0.015	0.021	6"	1'-6"
40	5SB12	0.026	0.036	6 1/2"	1'-6 1/2"
25	5SB15	0.002	0.003	5 1/4"	1'-8 1/4"
30	5SB15	0.004	0.006	5 1/2"	1'-8 1/2"
35	5SB15	0.008	0.011	5 3/4"	1'-8 3/4"
40	5SB15	0.013	0.019	6 1/2"	1'-9 1/2"
45	5SB15	0.022	0.030	7"	1'-10"
50	5SB15	0.034	0.047	7"	1'-10"



DEAD LOAD DEFLECTION DIAGRAM

NOTE: Deflections shown are due to concrete slab only ($E_c = 5,000$ ksi). Calculated deflections shown are theoretical and actual dimensions may vary. Adjust based on field verification.

BAR TABLE

BAR	SIZE
A	#5
T	#4

TABLE OF ESTIMATED QUANTITIES

SPAN LENGTH	REINF CONCRETE SLAB (SLAB BEAM)	PRESTR CONC SLAB BEAM (5SB12 OR 5SB15) (1)			TOTAL REINF STEEL (2)
		ABUT TO INT BT	INT BT TO INT BT	ABUT TO ABUT	
Ft	SF	LF (4)	LF (4)	LF (4)	Lb
25	650	122.50	122.50	122.50	1,820
30	780	147.50	147.50	147.50	2,180
35	910	172.50	172.50	172.50	2,550
40	1,040	197.50	197.50	197.50	2,910
45	1,170	222.50	222.50	222.50	3,280
50	1,300	247.50	247.50	247.50	3,640

- (1) See Bridge Layout for beam type used in the superstructure. These standards do not provide for the use of both SB12 and SB15 beams within the same structure.
- (2) Reinforcing steel weight is calculated using an approximate factor of 2.8 Lbs/SF.
- (3) Based on theoretical beam camber, dead load deflections of 5" cast-in-place concrete slab and a constant grade. The Contractor will adjust these values for any vertical curve.
- (4) Fabricator will adjust beam lengths for beam slopes as required.
- (5) Where slab is continuous over Interior Bents, Bars T are continuous through Joint. See "Continuous Slab Detail".
- (6) This standard does not provide for changes in roadway cross-slopes within the structure.
- (7) 1 1/4" backer rod must be compatible with joint sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as shown.
- (8) Class 7 silicone sealant that conforms to DMS-6310. Install when ambient temperature is between 55°F and 85°F and rising. Engineer to determine allowable hours for sealant application.
- (9) See Bridge Layout for expansion joint locations. If using Type A expansion joints, the maximum distance between joints is 100 feet. Type A joints are subsidiary to Item 422, "Concrete Superstructures".

GENERAL NOTES:

Designed according to AASHTO LRFD Bridge Design Specifications. Two- or three-span units, with slab continuous over interior bents, may be formed with the details shown on this sheet. See applicable rail details for rail anchorage in slab. This standard does not support the use of transition bents.

Cover dimensions are clear dimensions, unless noted otherwise.

MATERIAL NOTES:

Provide Class S concrete ($f'_c = 4,000$ psi). Provide Class S (HPC) concrete if shown elsewhere in the plans. Provide Grade 60 reinforcing steel. Provide bar laps, where required, as follows:
Uncoated ~ #4 = 1'-7"
~ #5 = 2'-0"
Epoxy coated ~ #4 = 2'-5"
~ #5 = 3'-0"
Deformed welded wire reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars A or T unless noted otherwise.

HL93 LOADING

Texas Department of Transportation				Bridge Division Standard	
PRESTRESSED CONCRETE SLAB BEAM SPANS (TY SB12 OR SB15) 24' ROADWAY					
SPSB-24					
FILE: pbsbte30-17.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT	
©TxDOT January 2017	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0920 03		081	CR 101	
DIST	COUNTY		SHEET NO.		
BMT	HARDIN		46		


DATE: 12/15/2021 9:19:07 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081.dgn
 C:\Users\RPASTORE\Desktop\0920-03-081.dgn
 ETC 95% development
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein.

STRUCTURE	DESIGNED BEAMS (STRAIGHT STRANDS)																			OPTIONAL DESIGN					LOAD RATING			
	SPAN LENGTH (ft)	BEAM NO.	BEAM TYPE	PRESTRESSING STRANDS							DEBONDED STRANDS PER ROW					CONCRETE		DESIGN LOAD COMP STRESS (TOP ϵ) (SERVICE I) fct (ksi)	DESIGN LOAD TENSILE STRESS (BOT ϵ) (SERVICE III) fcb (ksi)	REQUIRED MINIMUM ULTIMATE MOMENT CAPACITY (STRENGTH I) (kip-ft)	LIVE LOAD DISTRIBUTION FACTOR		STRENGTH I			SERVICE III		
				NON-STD STRAND PATTERN	TOTAL NO.	SIZE (in)	STRGTH fpu (ksi)	"e" \bar{c} (in)	"e" END (in)	TOT NO. DEB	DIST FROM BOTTOM (in)	NO. OF STRANDS		NUMBER OF STRANDS DEBONDED TO (ft from end)							RELEASE STRGTH f'_{ci} (ksi)	MINIMUM 28 DAY COMP STRGTH f'_c (ksi)	②		Inv	Opr	Inv	
												TOTAL	DE-BONDED	3	6	9	12						15	Moment				Shear
24' ROADWAY SB12 BEAM	25	ALL	5SB12		8	0.6	270	3.50	3.50	0	2.5	8	0	0	0	0	0	4.000	5.000	0.914	-1.217	448	0.450	0.450	1.40	1.82	1.71	
	30	ALL	5SB12		10	0.6	270	3.50	3.50	0	2.5	10	0	0	0	0	0	4.000	5.000	1.292	-1.685	530	0.450	0.450	1.25	1.62	1.29	
	35	ALL	5SB12		14	0.6	270	3.50	3.50	0	2.5	14	0	0	0	0	0	4.000	5.000	1.730	-2.219	675	0.450	0.450	1.33	1.73	1.23	
	40	ALL	5SB12		18	0.6	270	3.50	3.50	0	2.5	18	0	0	0	0	0	4.000	5.000	2.218	-2.796	820	0.440	0.440	1.34	1.74	1.12	
24' ROADWAY SB15 BEAM	25	ALL	5SB15		8	0.6	270	5.00	5.00	0	2.5	8	0	0	0	0	0	4.000	5.000	0.725	-0.897	551	0.450	0.450	1.77	2.29	2.41	
	30	ALL	5SB15		8	0.6	270	5.00	5.00	0	2.5	8	0	0	0	0	0	4.000	5.000	1.020	-1.244	574	0.450	0.450	1.23	1.59	1.45	
	35	ALL	5SB15		10	0.6	270	5.00	5.00	0	2.5	10	0	0	0	0	0	4.000	5.000	1.361	-1.640	708	0.450	0.450	1.15	1.49	1.14	
	40	ALL	5SB15		14	0.6	270	5.00	5.00	0	2.5	14	0	0	0	0	0	4.000	5.000	1.739	-2.068	864	0.440	0.440	1.32	1.71	1.19	
	45	ALL	5SB15		18	0.6	270	5.00	5.00	2	2.5	18	2	2	0	0	0	4.000	5.000	2.179	-2.574	1054	0.440	0.440	1.34	1.73	1.08	
28' ROADWAY SB12 BEAM	25	ALL	5SB12		8	0.6	270	3.50	3.50	0	2.5	8	0	0	0	0	0	4.000	5.000	0.903	-1.184	444	0.430	0.430	1.47	1.91	1.80	
	30	ALL	5SB12		10	0.6	270	3.50	3.50	0	2.5	10	0	0	0	0	0	4.000	5.000	1.276	-1.639	508	0.430	0.430	1.32	1.71	1.37	
	35	ALL	5SB12		12	0.6	270	3.50	3.50	0	2.5	12	0	0	0	0	0	4.000	5.000	1.708	-2.159	647	0.430	0.430	1.18	1.53	1.02	
	40	ALL	5SB12		18	0.6	270	3.50	3.50	0	2.5	18	0	0	0	0	0	4.000	5.000	2.200	-2.744	799	0.430	0.430	1.37	1.78	1.17	
28' ROADWAY SB15 BEAM	25	ALL	5SB15		8	0.6	270	5.00	5.00	0	2.5	8	0	0	0	0	0	4.000	5.000	0.716	-0.874	529	0.430	0.430	1.85	2.40	2.53	
	30	ALL	5SB15		8	0.6	270	5.00	5.00	0	2.5	8	0	0	0	0	0	4.000	5.000	1.007	-1.212	570	0.430	0.430	1.29	1.67	1.53	
	35	ALL	5SB15		10	0.6	270	5.00	5.00	0	2.5	10	0	0	0	0	0	4.000	5.000	1.343	-1.598	680	0.430	0.430	1.21	1.57	1.22	
	40	ALL	5SB15		14	0.6	270	5.00	5.00	0	2.5	14	0	0	0	0	0	4.000	5.000	1.725	-2.032	842	0.430	0.430	1.36	1.76	1.24	
	45	ALL	5SB15		18	0.6	270	5.00	5.00	2	2.5	18	2	2	0	0	0	4.000	5.000	2.149	-2.508	1013	0.420	0.420	1.41	1.82	1.16	
30' ROADWAY SB12 BEAM	25	ALL	4SB12		6	0.6	270	3.50	3.50	0	2.5	6	0	0	0	0	0	4.000	5.000	0.904	-1.187	341	0.340	0.340	1.38	1.79	1.67	
	30	ALL	4SB12		8	0.6	270	3.50	3.50	0	2.5	8	0	0	0	0	0	4.000	5.000	1.277	-1.646	407	0.340	0.340	1.32	1.71	1.37	
	35	ALL	4SB12		10	0.6	270	3.50	3.50	0	2.5	10	0	0	0	0	0	4.000	5.000	1.711	-2.169	518	0.340	0.340	1.24	1.60	1.08	
	40	ALL	4SB12		14	0.6	270	3.50	3.50	0	2.5	14	0	0	0	0	0	4.000	5.000	2.205	-2.758	640	0.340	0.340	1.34	1.73	1.11	
30' ROADWAY SB15 BEAM	25	ALL	4SB15		6	0.6	270	5.00	5.00	0	2.5	6	0	0	0	0	0	4.000	5.000	0.723	-0.888	431	0.350	0.350	1.69	2.19	2.32	
	30	ALL	4SB15		6	0.6	270	5.00	5.00	0	2.5	6	0	0	0	0	0	4.000	5.000	1.017	-1.231	438	0.350	0.350	1.16	1.50	1.37	
	35	ALL	4SB15		8	0.6	270	5.00	5.00	0	2.5	8	0	0	0	0	0	4.000	5.000	1.346	-1.605	545	0.340	0.340	1.21	1.57	1.21	
	40	ALL	4SB15		12	0.6	270	5.00	5.00	0	2.5	12	0	0	0	0	0	4.000	5.000	1.729	-2.043	675	0.340	0.340	1.47	1.91	1.38	
	45	ALL	4SB15		14	0.6	270	5.00	5.00	2	2.5	14	2	2	0	0	0	4.000	5.000	2.166	-2.542	823	0.340	0.340	1.33	1.73	1.06	
50	ALL	4SB15		18	0.6	270	5.00	5.00	4	2.5	18	4	2	2	0	0	0	4.000	5.000	2.665	-3.115	998	0.340	0.340	1.32	1.71	1.02	

① Based on the following allowable stresses (ksi):
 Compression = 0.65 f'ci
 Tension = 0.24 $\sqrt{f'ci}$
 Optional designs must likewise conform.
 ② Portion of full HL93.

DESIGN NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications. Load rated using Load and Resistance Factor Rating according to AASHTO Manual for Bridge Evaluation. Prestress losses for the designed beams have been calculated for a relative humidity of 60 percent. Optional designs must likewise conform.


FABRICATION NOTES:
 Provide Class H concrete. Provide Grade 60 reinforcing steel. Use low relaxation strands, each pretensioned to 75 percent of fpu. Full-length debonded strands are not permitted in positions "A" and "B". Strand debonding must comply with Item 424.4.2.2.4. When shown on this sheet, the Fabricator has the option of furnishing either the designed beam or an approved optional beam design. All optional design submittals and shop drawings must be signed, sealed and dated by a Professional Engineer registered in the State of Texas. Locate strands for the designed beam as low as possible on the 2" grid system unless a non-standard strand pattern is indicated. Fill row "2.5", then row "4.5". Place strands within a row as follows:
 1) Locate a strand in each "A" position.
 2) Place strand symmetrically about vertical centerline of beam.
 3) Space strands as equally as possible across the entire width. Do not debond strands in position "A". Distribute debonded strands symmetrically about the vertical centerline. Increase debonded lengths working outward, with debonding staggered in each row.




HL93 LOADING

		Bridge Division Standard	
PRESTRESSED CONCRETE SLAB BEAM STD DESIGNS (TY SB12 OR SB15) 24', 28' & 30' ROADWAY PSBSD			
FILE: psbts08-21.dgn	DN: SRW	CK: BMP	DW: SFS
©TxDOT January 2017	CONT	SECT	HIGHWAY
REVISIONS	0920	03	081
1-21: Added load rating.	DIST	COUNTY	SHEET NO.
	BMT	HARDIN	47


DATE: 12/15/2021 9:19:10 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081, ETC development\0920-03-081\5B12.dgn
 PSB-5SB12.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of calculations or results or damages resulting from its use.




PART PLAN



ELEVATION




SECTION




END MAT REINFORCING

Bars H not shown for clarity.




PART SKEW PLAN

(Showing θ over 0° to 15° Skew)




PART SKEW PLAN


(Showing θ over 15° to 30° Skew)




BARS D (#6)




BARS M (#4)




BARS H (#4)




BARS M1 (#4)




BARS M2 (#4)




BARS C (#4)




BARS U (#5)




BARS N (#4)



BARS C1 (#4)



BARS N1 (#4)



ELEVATION OF BLOCKOUT

BEAM PROPERTIES		
Area	in ²	717.0
Y top	in	6.00
Y bott	in	6.00
I	in ⁴	8,604
Weight	lb/ft	747

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Provide Class H concrete. Provide Class H (HPC) if shown elsewhere in the plans.
 Provide Grade 60 reinforcing steel.
 An equal area of welded wire reinforcement (WWR) (ASTM 1064) may be substituted for bars C and D if approved by the Engineer.
 These details can be used for any skew angle up to a maximum of 30 degrees.
 Chamfer all exposed corners 3/4" or round to a 3/4" radius.
 Details are drawn showing right forward skew. See Bridge Layout for actual direction.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

- ① See End Mat Reinforcing detail.
- ② Adjust bars M vertically to avoid strands.
- ③ See sheet PSBND or PSBSD for strand locations.
- ④ Assumes 150 pcf weight density of concrete.
- ⑤ 90° at conventional interior bents. End of beam must be vertical at abutment backwall and inverted-T stem.
- ⑥ Blockout required at armor joint (AJ) and sealed expansion joint (SEJ) locations to accommodate joint anchorage.

HL93 LOADING

PRESTRESSED CONCRETE SLAB BEAM DETAILS
 (TYPE 5SB12)
PSB-5SB12

FILE: psbsts03-17.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT January 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
DIST	COUNTY		SHEET NO.	
BMT	HARDIN		48	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard. PSBEB.dgn

DATE: 12/15/2021 9:19:13 PM
 FILE: C:\User\SRPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081.dgn


TABLE OF BEARING PAD DIMENSIONS (ALL PRESTR CONC SLAB BM TYPES)

One-Pad (Ty SB1-"N") (2)			Two-Pad (Ty SB2-"N") (2)		
W	L	T	W	L	T
14"	7"	2"	7"	7"	2"


Pad sizes shown are applicable for the following conditions:
 (1) All one, two and three span units where the minimum span length is not less than 25' and the maximum span is not more than 50'.
 (2) Skews less than or equal to 30°.




TWO-PAD DETAIL PLAN
 (At abutment or inverted-T cap or at interior bent)




TWO-PAD DETAIL SKEW PLAN
 (At abutment or inverted-T cap)




TWO-PAD DETAIL SKEW PLAN
 (At interior bent)



ONE-PAD DETAIL PLAN
 (At abutment or inverted-T cap or at interior bent)



ONE-PAD DETAIL SKEW PLAN
 (At abutment or inverted-T cap)




ONE-PAD DETAIL SKEW PLAN
 (At interior bent)

GENERAL NOTES:
 These details accommodate skew angles up to 30°. Shop drawings for approval are required. A bearing layout which identifies location and orientation of all bearings must be developed by the bearing fabricator. Permanently mark each bearing in accordance with the bearing layout. A copy of the bearing layout is to be provided to the Engineer. Cost of furnishing and installing elastomeric bearings must be included in unit price bid for "Prestressed Concrete Slab Beams".

ELASTOMERIC BEARING PAD PLACEMENT AND BEAM END DIAGRAMS

Place one bearing pad at forward station beam end.
 Place two bearing pads at back station beam end.



LAMINATED ELASTOMERIC BEARING PAD
 (50 DUROMETER)

- Maximum and minimum layer thicknesses shown are for elastomer only, on tapered layers.
- Indicate BEARING TYPE on all pads. For tapered pads, locate BEARING TYPE on the high side. The Fabricator must include the value of "N" (amount of taper in 1/8 inch increments) in this mark. Examples: N=0, (for 0 inch taper) N=1, (for 1/8 inch taper) N=2, (for 1/4 inch taper) (etc.) Fabricated pad top surface slope must not vary from plan beam slope by more than $(\frac{0.0625}{\text{Length}})$ IN/IN.
- Locate permanent mark here.

HL93 LOADING

Texas Department of Transportation Bridge Division Standard


ELASTOMERIC BEARING AND BEAM END DETAILS

PRESTR CONCRETE SLAB BEAM


PSBEB

FILE: psbste06-17.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT January 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	49	

DATE: 12/15/2021 9:19:15 PM
 FILE: C:\Users\RPASTORE\Desktop\Exports\0920-03-081_ETC_95%_development\0920-03-081_PSBRA.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions. PSBRA.dgn




CAST-IN-PLACE ANCHORAGE OPTION




ADHESIVE ANCHORAGE OPTION

T631LS & T631 RAIL ANCHORAGE PLACEMENT (2)(7)



PART SPAN ELEVATION




SECTION


TYPICAL CONCRETE RAIL ANCHORAGE

(Showing typical concrete rail anchorage)

3/8" Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563).



T631LS & T631 RAIL C-I-P ANCHOR BOLT



PLAN OF CONCRETE RAILS AT EXPANSION JOINTS

- ① Cast-in-place slab thickness varies due to beam camber (5" minimum).
- ② Replace cast-in-place anchor bolts shown on T631LS and T631 Rail standard with an adhesive anchor system or cast-in-place anchor bolts shown on this sheet.
- ③ Bar length shown on rail standard, minus 1 1/4". Adjust bar length for a raised sidewalk.
- ④ See rail standard for projection from finished grade or top of sidewalk.
- ⑤ Place additional (#5) longitudinal bar.
- ⑥ Excess bolt length has been provided to accommodate a variable slab thickness due to beam camber. If slab thickness on span details exceed 7", bolt length must be increased accordingly. After posts have been set and bolts tightened, bolt projection above nuts of more than 1/2" must be cut off and painted with two coats of zinc-rich paint conforming to the Item 445 "Galvanizing".
- ⑦ Distance from end of top outside edge of slab to center of first bolt group can not be less than 9", except: 15° Skew: 1'-0" (acute corner only) 30° Skew: 1'-3" (acute corner only)
- ⑧ Location of rail expansion joint must be at the intersection of centerline of slab expansion joint, centerline of rail footprint and perpendicular to slab outside edge.
- ⑨ Cross-hatched area must have 1/2" preformed bituminous fiber material under concrete rail, as shown.

CONSTRUCTION NOTES:

Rail anchorage bars may be field bent as required to clear rail reinforcing or provide minimum cover shown on standard rail detail sheets.
 Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.

MATERIAL NOTES:

Galvanize all steel components of steel rail system.
 Provide Grade 60 reinforcing steel.
 Cast-in-place anchorage system for T631LS and T631 Rail must be 3/8" Dia heavy hex head anchor bolts (ASTM F3125 Gr 325 or A449) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed anchor bolts 4 1/2" minimum.
 Adhesive anchors for T631LS and T631 Rail must be 3/8" Dia ASTM A193 Gr B7 or F1554 Gr 105 fully threaded rods with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed fully threaded rod into slab and/or abutment wingwall using a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4 3/4". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 8 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing."
 Epoxy coat or galvanize reinforcing steel shown on this standard if rail reinforcement is epoxy coated or galvanized.

GENERAL NOTES:


Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 This standard is for use with structures with a 5" minimum cast-in-place concrete slab.
 This standard may require modification for interior rails. This standard does not apply to median barriers.
 This standard does not provide details for Type T221P, T224, T80HT, T80SS, C412, PR11, PR22 and PR3 rails on slab beam bridges.
 See rail standards for approved speed restrictions, notes and details not shown.

Cover dimensions are clear dimensions, unless noted otherwise.


		Bridge Division Standard	
RAIL ANCHORAGE DETAILS			
PRESTR CONCRETE SLAB BEAMS			
PSBRA			
FILE: psbste07-18.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT January 2017	CONTRACT	SECTION	HIGHWAY
REVISIONS	0920	03	081 CR 101
03-18: Updated adhesive anchor notes.	DIST	COUNTY	SHEET NO.
	BMT	HARDIN	50

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for incorrect results or damages resulting from its use.

DATE: 12/15/2021 9:19:18 PM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC_95% development\0920-03-081\0920-03-081.dwg




JOINTS AT ABUTMENTS
SKEWS OVER 15°
SKEWS THRU 15°
PLANS OF ARMOR PLATES




ELEVATION OF BASIC ARMOR PLATE

- ① Adjust 6" plate height for overlay thicknesses other than the 2" shown. Adjust weight by 1.70 plf for each 1/2" variation in thickness.
- ② Do not paint top 1/2" of plate if using sealed armor joint.
- ③ Set top of backer rod 1" below top of armor plate. Backer rod must be compatible with joint sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as shown.
- ④ Blast clean entire contact area between sealant and plate (SSPC-SP10) before installing sealant. Light brush blast and thoroughly clean all dust and debris from concrete surfaces in contact with joint sealant before application of silicone seal.
- ⑤ Use Class 7 joint sealant that conforms to DMS-6310.
- ⑥ Place sealant while ambient temperature is between 55°F and 80°F and is rising.
- ⑦ Armor joint does not include joint sealant or backer rod.
- ⑧ Armor joint (sealed) includes Class 7 joint sealant and backer rod.
- ⑨ Form vertical leg of seal as per the Manufacturer's recommendations. Use Class 4 joint sealant if Class 7 cannot be installed correctly. Install according to Manufacturer's recommendations.
- ⑩ Unless shown otherwise, terminate armor plate at slab break point if break is more than 2'-0" from slab edge.
- ⑪ See "Plans of Armor Plates".
- ⑫ At Fabricator's option, armor plate may extend up to 6" beyond this point for skews through 15°.
- ⑬ Align shipping angle perpendicular to joint.



SHOWN WITHOUT 2" OVERLAY AT JOINT LOCATION



SHOWN WITH 2" OVERLAY AT JOINT LOCATION

ARMOR JOINT SECTIONS
 Showing Armor Joint (Sealed)

FABRICATION NOTES:

Match mark corresponding plate sections and secure together for shipment with shipping angle. Do not use erection bolts. Ship armor joints in convenient lengths of 10'-0" Min and 24'-0" Max unless necessary for stage construction or widenings. One shop splice is permitted in each shipping length provided no piece is less than 2'-0" long and sufficient studs are added to limit the stud to shop splice distance to 2" Min and 4" Max. Weld studs in accordance with AWS D1.1. Use groove welds for all shop and field butt splices. Grind smooth areas in contact with seal. Make all necessary field splice joint preparations in the shop. Paint the entire steel section, except as stated in Note 2, with System II or IV primer in accordance with Item 446 "Field Cleaning and Painting Steel." Provide paints in accordance with Item 446.2. Prepare steel and apply paint in accordance with Items 446.4.7.3 and 446.4.7.4. Shop drawings for the fabrication of armor joints will not require the Engineer's approval if fabrication is in accordance with the details shown on this standard.


CONSTRUCTION NOTES:

Secure armor joints in position and place to proper grade and alignment by welding braces to adjacent reinforcing steel, to prestressed beam stirrups, or to anchors cast in concrete diaphragms. Include cost of temporary bracing in the price bid for Armor Joint. Remove shipping angle immediately after each joint half is secured in place. Grind smooth, and touch up with organic zinc-rich paint.


GENERAL NOTES:

Provide armor joints at locations shown on the plans. Provide the seal when "Armor Joint (Sealed)" is noted on the plans. These joint details accommodate a joint movement range of 1 3/8" (3/4" opening movement and 5/8" closure movement). Payment for armor joint, with or without seal, is based on length of armor plate.

WEIGHTS FOR ONE ARMOR JOINT (2 PLATES)	
WITHOUT OVERLAY	16.10 plf
WITH 2" OVERLAY ①	22.90 plf



JOINT SEALANT TERMINATION DETAILS
 Armor joint (sealed) only. Armor plate is not shown for clarity.




SHIPPING ANGLE

An alternate method of securing joint sections may be used if approved by the Bridge Division. Erection bolts are not allowed.

				Bridge Division Standard	
ARMOR JOINT DETAILS					
AJ					
FILE: ajstde01-19.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT	
REVISONS	0920	03	081	CR 101	
DIST	COUNTY		SHEET NO.		
BMT	HARDIN		51		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein. 0920-03-081, ETC 95% development

DATE: 12/15/2021 9:19:21 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081, ETC 95% development\BAS-A.dgn



BAR TABLE	
BAR	SIZE
A	#8
B	#5
D	#5
T	#5

APPROXIMATE QUANTITIES ④

Reinf steel weight = 8.5 Lbs/SF of Approach Slab


Volume of Appr Slab Conc (CY) = 0.802W + 0.02W² Tan S

W = Width of Approach Slab (ft)

S = Skew Angle (deg)

- ① Flare Bars B and D in this region (1'-6" Max Spa, 3" Min Spa). Minimum flared bar length = 2'-6". Bend bars as necessary.
- ② Provide longitudinal construction joints that align with longitudinal construction joints in the bridge slab with bridges built in stages. Other longitudinal construction joints must receive approval of the Engineer.
- ③ See details elsewhere in plans for shoulder drain location and details.
- ④ For Contractor's information only. Quantities shown are for one approach slab.
- ⑤ Multiple piece tie bars are acceptable at longitudinal construction joints provided minimum laps shown are achieved.
- ⑥ See details elsewhere in plans for required cross-slope.
- ⑦ Place in accordance with Item 438.
- ⑧ Provide backer rod that is 25% larger than joint opening and compatible with the sealant.
- ⑨ If bridge rail is present at the wingwall or CIP retaining wall, place 1/2" rebonded recycled tire rubber between concrete railing and top of approach slab as shown when concrete railing projects over the approach slab.

LONGITUDINAL SAW CUT JOINT DETAIL



GENERAL NOTES:

Construct approach slab in accordance with Item 422.

Provide Class "S" concrete with a minimum compressive strength of 4,000 psi.

Provide Grade 60 reinforcing steel.

Provide longitudinal joints as shown on the Longitudinal Saw Cut Joint Detail at lane lines and shoulders when width between longitudinal construction joints or edges of approach slab exceeds 16 feet. Saw cut joints within 24 hours of concrete placement to a depth of 1 1/2" and seal in accordance with Item 438. Alternately, provide a controlled joint consisting of 1 1/2" vinyl or plastic joint former (Stress Cap, Zip Strip, Stress Lock, or equal as approved by the Engineer.)

Provide rebonded recycled tire rubber joint filler that meets the requirements of DMS-6310. "Joint Sealants and Fillers."





Construct the subgrade or subbase away from the bridge for a minimum distance of 100 feet prior to the approach slab, unless otherwise indicated on the plans.

Compact and finish the subgrade or foundation for the approach slab to the typical cross-section and to the lines and grades shown on the plans.

Cure for 4 days using water or membrane curing per Item 422.

All details shown herein are subsidiary to bridge approach slab.

Cover dimensions are clear dimensions, unless noted otherwise.



Texas Department of Transportation
 Bridge Division Standard


BRIDGE APPROACH SLAB
 ASPHALTIC CONCRETE PAVEMENT

BAS-A

FILE: basaste1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
02-20: Removed stress relieving pad.	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	52	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/11/2023 9:54:06 AM
 FILE: c:\ttdot\pw_online\ttdot5\pwnonline_richard.pastorella\d0343939\MS-CSAB-23.dgn



OPTION 1 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.



OPTION 1 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans, flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a). If flowable backfill is to be placed over MSE backfill, then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b). Place flowable fill in lifts not exceeding 2 feet in height. Place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).

GENERAL NOTES:


See the Bridge Layout for selected Option. Option 1 is intended for construction only requiring plasticity index (PI) controlled embankment fill or excavation in competent soils/rocks in order to construct the abutment. Option 2 is intended for new construction requiring high plasticity embankment fill with a PI greater than 30 or pavement built in poor native soil. Poor soils are defined as high plasticity clays or expansive clays.

Construct abutment backfill in accordance with Item 400, "Excavation and Backfill for Structures". Provide Cement Stabilized Backfill (CSB) meeting the requirements of Item 400, "Excavation and Backfill for Structures", to the limits shown at bridge abutments.


If required elsewhere in the plans, provide Flowable Backfill meeting the requirements of Item 401, "Flowable Backfill", to the limits shown at bridge abutments.

Details are drawn showing left forward skew. See Bridge Layout for actual skew direction.

These details do not apply when Concrete Block retaining walls are used in lieu of wingwalls.



WITHOUT APPROACH SLAB



WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)


SECTION A-A

SHEET 1 OF 2

		Bridge Division Standard	
CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT			
CSAB			
FILE: MS-CSAB-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT	CON: 0920	SECT: 03	HIGHWAY: 081
REVISIONS	JOB		CR 101
02-20: Added Option 2.	DIST: BMT	COUNTY: HARDIN	SHEET NO. 53
03-23: Updated General Notes.			


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/11/2023 9:56:08 AM
 FILE: c:\t\dot\pw_online\txdot5\pwnline_richard.pastorella\d0343939 MS-CSAB-23.dgn




OPTION 2 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.




OPTION 2 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans, flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a). If flowable backfill is to be placed over MSE backfill, then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b). Place flowable fill in lifts not exceeding 2 feet in height. Place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).
- ⑥ 1'-0" for BAS-A
1'-10" for BAS-C



WITHOUT APPROACH SLAB



SECTION B-B

WITH APPROACH SLAB
(Showing BAS-C, BAS-A similar.)

SHEET 2 OF 2




**CEMENT STABILIZED
 ABUTMENT BACKFILL
 BRIDGE ABUTMENT**


CSAB

FILE: MS-CSAB-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
02-20: Added Option 2. 03-23: Updated General Notes.	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	54	


DATE: 12/15/2021 9:19:27 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081_ETC_95%_development\0920-03-081_S1\0920-03-081.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this document.




ABUTMENTS, WINGWALLS AND MULTI-DRILLED SHAFT FOOTINGS




INTERIOR BENTS DRILLED SHAFT DIA EQUAL TO COLUMN DIA



INTERIOR BENTS DRILLED SHAFT DIA GREATER THAN COLUMN DIA



OPTIONAL INTERIOR BENT DRILLED SHAFT DETAIL




DRILLED SHAFT SECTIONS


DRILLED SHAFT DETAILS

TABLE OF PILE EMBEDMENT	
Pile Type	Embedment Depth (Ft)
16" Sq Concrete 18" Sq Concrete HP14 Steel HP16 Steel	1'-0"
20" Sq Concrete 24" Sq Concrete HP18 Steel	1'-6"


See Prestressed Concrete Piling (CP) standard for additional details on concrete pile embedment.



ORIENTATION OF STEEL H-PIILING




PIILING DETAILS (Concrete or steel H)




DETAIL "A" (Showing plan view of a 30° skewed abutment)


- ① #3 spiral at 6" pitch (one and a half flat turns top and bottom).
- ② Min extension into supported element:
#6 Bars = 1'-11"
#7 Bars = 2'-0"
#9 Bars = 2'-3"
- ③ Min lap with column reinf:
#7 Bars = 2'-11"
#9 Bars = 3'-9"
#11 Bars = 4'-8"
- ④ Min extension into supported element:
#6 Bars = 1'-11"
#7 Bars = 2'-3"
#9 Bars = 2'-9"
- ⑤ Drilled shafts may extend to the bottom of bent caps for "H" heights of 6 ft and less (as shown on the Bridge Layout), if approved. This option can only be used when the drilled shaft diameter equals the column diameter. Obtain approval of the forming method above the ground line prior to construction. No adjustments in payment will be made if this option is used.
- ⑥ 1'-0" Min, unless shown otherwise on plans.
- ⑦ Or as shown on plans.




ELEVATION



SECTION A-A



SECTION B-B



SECTION THRU FLANGE OR WEB

STEEL H-PILE TIP REINFORCEMENT

See Item 407 "Steel Piling" to determine when tip reinforcement is required and for options to the details shown.

STEEL H-PILE SPLICE DETAIL

Use when required.



		Bridge Division Standard	
COMMON FOUNDATION DETAILS			
FD			
FILE: fdstde01-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
CONTRACT: 0920 03	SECTION: 081	HIGHWAY: CR 101	
DIST: BMT		COUNTY: HARDIN	
SHEET NO. 55			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. If you have any questions, please contact the Texas Department of Transportation, 1100 West 11th Street, Austin, Texas 78768, (512) 463-1300.


DATE: 12/15/2021 9:19:30 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081.dgn

TABLE OF FOOTING QUANTITIES FOR 30" COLUMNS


ONE 3 PILE FOOTING					
Bar	No.	Size	Length	Weight	
F1	11	#4	3'- 2"	23	
F2	6	#4	8'- 2"	33	
F3	6	#4	6'- 11"	28	
F4	8	#9	3'- 2"	86	
F5	4	#9	6'- 11"	94	
F6	4	#9	8'- 2"	111	
FC	12	#4	3'- 6"	28	
FD ^⑩	8	#9	8'- 1"	220	
Reinforcing Steel				Lb	623
Class "C" Concrete				CY	4.8
ONE 4 PILE FOOTING					
Bar	No.	Size	Length	Weight	
F1	20	#4	7'- 2"	96	
F2	16	#8	7'- 2"	306	
FC	16	#4	3'- 6"	37	
FD ^⑩	8	#9	8'- 1"	220	
Reinforcing Steel				Lb	659
Class "C" Concrete				CY	6.3
ONE 5 PILE FOOTING					
Bar	No.	Size	Length	Weight	
F1	20	#4	8'- 2"	109	
F2	16	#9	8'- 2"	444	
FC	24	#4	3'- 6"	56	
FD ^⑩	8	#9	8'- 1"	220	
Reinforcing Steel				Lb	829
Class "C" Concrete				CY	8.0



THREE PILE FOOTING^⑧
 For 36" Dia and smaller columns.



FOUR PILE FOOTING^⑧
 For 42" Dia and smaller columns.



FIVE PILE FOOTING^⑧
 For 42" Dia and smaller columns.

CONSTRUCTION NOTES:


- See Bridge Layout for foundation type required. Use these foundation details unless shown otherwise.
- Drive piling under abutment wingwalls to a minimum resistance of 10 Tons/Pile unless shown otherwise.
- Provide Class C Concrete ($f'_c = 3,600$ psi), unless shown otherwise.
- Provide Grade 60 reinforcing steel.
- Galvanize reinforcing if shown elsewhere in the plans.
- Provide bar laps for drilled shaft reinforcing, where required, as follows:
 - Uncoated or galvanized (#6) ~ 2'-6"
 - Uncoated or galvanized (#7) ~ 2'-11"
 - Uncoated or galvanized (#9) ~ 3'-9"

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications.
- Cover dimensions are clear dimensions, unless noted otherwise.
- Reinforcing bar dimensions shown are out-to-out of bar.

DESIGNER NOTES:

- Do not use the drilled shaft details shown on this standard for retaining wall, noise wall, barrier, or sign foundations without structural evaluation.
- Do not use the footings shown on this standard in direct contact with salt water or exposed to salt water spray.
- Maximum allowable pile loads for the footings shown are:
 - 72 Tons/Pile with 24" Dia Columns
 - 80 Tons/Pile with 30" Dia Columns
 - 100 Tons/Pile with 36" Dia Columns
 - 120 Tons/Pile with 42" Dia Columns




- ③ Min lap with column reinforcing:
 - #7 Bars = 2'-11"
 - #9 Bars = 3'-9"
 - #11 Bars = 4'-8"
- ⑥ 1'-0" Min, unless shown otherwise on plans.
- ⑦ Or as shown on plans.
- ⑧ See Bridge Layout for type, size and length of piling.
- ⑨ Number and size of FD bars must match column reinforcing. Tie FD bars to the top of the bottom reinforcing mat.
- ⑩ Adjust FD quantity, size and weight as needed to match column reinforcing.

COMMON FOUNDATION DETAILS


FD

FILE: fdstd01-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
01-20: Added #11 bars to the FD bars.	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	56	

12/15/2021 9:19:32 PM
 DATE: C:\User\RPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081.dwg
 FILE: C:\User\RPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the results or damages resulting from its use.



ROADWAY ELEVATION OF RAIL ON BRIDGE



ROADWAY ELEVATION OF RAIL ON BOX CULVERTS

Showing 0° skew culvert. Skewed culverts similar. See RAC standard for details not shown. Vertical joints in concrete rail are not required, unless shown elsewhere.





- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Wingwall Length minus 5'-0" (Varies)

SHEET 1 OF 3

		Bridge Division Standard	
<p>TRAFFIC RAIL</p> <p>TYPE T223</p>			
FILE: r1std005-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONT	SECT	HIGHWAY
REVISIONS	0920 03	081	CR 101
DIST	COUNTY		SHEET NO.
BMT	HARDIN		57

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in the drawings or for any results or damages resulting from its use.

DATE: 12/15/2021 9:19:34 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081_PW_Exp\ts\0920-03-081_PW_Exp.dgn



- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Wingwall Length minus 5'-0" (Varies)
- ③ Increase 2" for structures with overlay.
- ④ Bars L(#5) are part of rail reinforcing and are included in unit price bid for railing. Space with Bars U. Bars L match slab bar cover. Bars L may be bundled with top slab reinforcing if spacing is equivalent.
- ⑤ Bars SU1(#3), SU2(#3) and WU(#5) not shown for clarity.
- ⑥ Substitute Bars U(#5) for Bars WU(#5) when parapet end is located on anchorage curb over culvert top slab. Use Bars WU(#5) in culvert parallel wings.

SHEET 2 OF 3





Texas Department of Transportation
 Bridge Division Standard

TRAFFIC RAIL

TYPE T223


FILE: r1std005-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: AES
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	58	

DATE: 12/15/2021 9:19:36 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions.



SECTIONS THRU RAIL
 Sections on box culverts similar.


- ② Wingwall Length minus 5'-0" (Varies)
- ③ Increase 2" for structures with overlay.
- ④ Bars L(#5) are part of rail reinforcing and are included in unit price bid for railing. Space with Bars U. Bars L match slab bar cover. Bars L may be bundled with top slab reinforcing if spacing is equivalent.
- ⑥ Substitute Bars U(#5) for Bars WU(#5) when parapet end is located on anchorage curb over culvert top slab. Use Bars WU(#5) in culvert parallel wings.
- ⑦ When vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls on traffic side of wall, move the horizontal wingwall/retaining wall reinforcing to the inside of Bars WU where bars conflict.
- ⑧ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑨ At the Contractor's option, Bars V may be replaced by extending Bars U to 2'-5 1/4" above the roadway surface without overlay.



PLAN OF RAIL AT EXPANSION JOINTS
 Example showing Slab Expansion Joints without breakbacks.

- CONSTRUCTION NOTES:**
 Face of rail and parapet must be vertical transversely unless otherwise shown in the plans or approved by the Engineer.
 Provide water barriers at openings draining onto undercrossing roadways and sidewalks. They may be cast-in-place or precast in convenient lengths and bonded to the bridge deck with an approved epoxy cement.
 Chamfer all exposed corners.
- MATERIAL NOTES:**
 Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.
 Provide Grade 60 reinforcing steel.
 Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized.
 Deformed Welded Wire Reinforcing (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars U, V, and WU unless noted otherwise. Provide the same laps as required for reinforcing bars.
 Provide bar laps, where required, as follows:
 Uncoated or galvanized ~ #5 = 2'-0"
 Epoxy coated ~ #5 = 3'-0"
- GENERAL NOTES:**
 This rail has been evaluated by full-scale crash test to meet MASH TL-3 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can be used for speeds of 45 mph and less.
 Do not use this railing on bridges with expansion joints providing more than 5" movement.
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
 Shop drawings are not required for this rail.
 Average weight of railing with no overlay is 358 plf.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.




SHEET 3 OF 3


		Bridge Division Standard	
<h1>TRAFFIC RAIL</h1>			
<h2>TYPE T223</h2>			
FILE: r1std005-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONT: 0920 03	SECT: 081	HIGHWAY: CR 101
REVISIONS		DIST: BMT	COUNTY: HARDIN
		SHEET NO. 59	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/11/2023 9:58:40 AM
 FILE: c:\txdot\pw_online\txdot5\pwnline_richard.pastorello\0343939.ms-CP-23.dgn



PILE DETAILS



TYPICAL SECTION THRU PILE



PILE BUILD-UP DETAIL


Pile Size "D"	Area of Pile Section in ²	I in ⁴	Weight Lb/Ft	Prestress (5)				Concrete Final Prestress (15% Loss) psi	
				Size in	No.	Initial	Force		Concrete Final Prestress (15% Loss) psi
						each kips	Total kips		
16"	254	5,340	265	1/2"	8	28.9	231	774	
				0.6	8	29	232	776	
18"	322	8,600	336	1/2"	10	28.9	289	763	
				0.6	8	36	288	760	
20"	398	13,150	415	1/2"	14	28.9	405	864	
				0.6	12	34	408	871	
24"	574	27,380	598	1/2"	18	28.9	520	770	
				0.6	12	44	528	782	

- 1 Locate strands symmetrically about the axis of the pile, with no more than one strand difference between any two adjacent sides.
- 2 Provide Class S concrete (f_c = 4,000 psi) for pile build-ups.
- 3 Use typical pile embedment details unless shown otherwise elsewhere in the plans. Payment for piles will be in accordance with the details shown. Strip back piling and extend prestressing strands into substructure when piling conflicts with substructure reinforcing or when the side cover from pile edge to substructure edge is less than 4" after driving.
- 4 When stripped back piles are required, strip back piling after driving or cast short with strands protruding from top of piling as shown.
- 5 Provide 1/2" or 0.6" 270 ksi low relaxation strands tensioned to the forces shown in the table. If an optional design is used, provide a minimum concrete final prestress of 750 psi. Submit optional designs for approval.
- 6 Saw cut 1/2" deep around perimeter of pile at the breakback line.
- 7 Unless shown otherwise.
- 8 3/4" deformed bar anchors (DBA), electric arc-welded to stinger anchor plate with complete fusion.
- 9 Place center of stinger within 1/2" of center of piling.


FABRICATION NOTES:
 Provide Class H concrete. Provide sulfate resistant concrete when required.
 Minimum release strength, f_{ci} = 4,000 psi.
 Minimum 28-day strength, f_c = 5,000 psi.
 All dimensions relating to prestressing steel are to centers of strands.
 Provide Grade 60 reinforcing steel.
 Provide deformed wire reinforcement meeting ASTM A1064.

GENERAL NOTES:
 See Bridge Layout for size, number, and length of piling.
 See Bridge Layout or elsewhere in the plans for stinger assembly requirements. Stinger assembly is subsidiary to the pile.
 Shop drawing submittal and approval is not required if fabrication is in accordance with the details shown on this standard.
 For treatment of damaged pile and the lifting loops, see the Concrete Repair Manual.


Cover dimensions are clear dimensions, unless noted otherwise.




PILE EMBEDMENT DETAILS



SIDE ELEVATION



STINGER SECTION



STINGER ANCHOR PLATE DETAIL

TYPICAL PILE AND STINGER ASSEMBLY DETAILS

Pile strands, reinforcing, and holes in stinger anchor plate not shown for clarity.

Showing stinger anchor plate for 20" pile, stinger anchor plates for other pile sizes are similar.

Texas Department of Transportation Bridge Division Standard

PRESTRESSED CONCRETE PILING

CP

FILE: MS-CP-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
3/2023: Added 0.6" strand option.	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	60	

DATE: 12/15/2021 9:19:41 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081, ETC 95% development\0920-03-081.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the use of this standard in any way that may result in incorrect results or damages resulting from its use.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES		
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back	
SHEETING	Yellow, White or Red Type B or C reflective sheeting				Yellow, White or Red Type B or C Reflective Sheeting					
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX	
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF	

OBJECT MARKERS										D & OM DESCRIPTIVE CODES	
DEVICE	Type 1 (OM-1)		Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)		INSTL OM ASSM (OM-XX) (XXXX)XXX(XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
SHEETING	Yellow-Type B _{FL} or C _{FL} Sheeting		Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			Red -Type B _{FL} or C _{FL} Sheeting		
POST TYPE	TWT		WC	WC	WFLX	TWT			TWT		
MOUNT TYPE	WAS, WAP		GND	GND	GND, SRF	WAS, WAP			WAS, WAP		

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE:		
DEVICE				 W1-8				 W1-6		Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.	
SHEETING	Yellow, White, Red			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)		48" x 24" (Conventional)
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only		MOUNTING HEIGHT	7'-0"	
				NOTE	1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).						

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION
D & OM(1)-20


FILE: dom1-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	BMT	HARDIN	61	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard.

DATE: 12/15/2021 9:19:43 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\0920-03-081, ETC 95% development\0920-03-081.dwg

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS																										
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT																									
GND	GND	SRF	WAS	WAP	GF 1																									
	EMBEDDED	SURFACE MOUNT	STEEL	PLASTIC	GF 2																									
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.		NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.																										
TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS																										
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		See general notes 1, 2 and 3.																										
CONCRETE TRAFFIC BARRIER (CTB)																														
GENERAL NOTES																														
1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.																														
DELINEATOR & OBJECT MARKER INSTALLATION D & OM(2)-20																														
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>FILE: dom2-20.dgn</td> <td>DN: TxDOT</td> <td>CK: TxDOT</td> <td>DW: TxDOT</td> <td>CR: TxDOT</td> </tr> <tr> <td>© TxDOT August 2004</td> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>REVISIONS</td> <td>0920</td> <td>03</td> <td>081</td> <td>CR 101</td> </tr> <tr> <td>10-09 3-15</td> <td>DIST</td> <td>COUNTY</td> <td colspan="2">SHEET NO.</td> </tr> <tr> <td>4-10 7-20</td> <td>BMT</td> <td>HARDIN</td> <td colspan="2">62</td> </tr> </table>						FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY	REVISIONS	0920	03	081	CR 101	10-09 3-15	DIST	COUNTY	SHEET NO.		4-10 7-20	BMT	HARDIN	62	
FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT																										
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY																										
REVISIONS	0920	03	081	CR 101																										
10-09 3-15	DIST	COUNTY	SHEET NO.																											
4-10 7-20	BMT	HARDIN	62																											


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**








D & OM(5)-20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0920	03	081	CR 101
7-20	DIST	COUNTY	SHEET NO.	
	BMT	HARDIN	63	


DATE: 12/15/2021 9:19:46 PM
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings or specifications to any other format or for any errors or omissions. TxDOT is not responsible for any damages resulting from its use.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard or for any damages resulting from its use.

DATE: 12/15/2021 9:19:48 PM
 FILE: C:\Users\RPASTORE\Desktop\PW_Export\ts\0920-03-081, ETC 95% development\0920-03-081.dwg



OBJECT MARKERS SMALLER THAN 3 FT²




- NOTES**
- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
 - Mounting should be flush with top of attenuator. Minimum size 96" x 24".

- NOTES**
- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
 - Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
 - Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
 - Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
 - Object Marker at nose of attenuator is subsidiary to the attenuator.
 - See D & OM (1-4) for required barrier reflectors.


		Traffic Safety Division Standard	
DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS			
D & OM(VIA) -20			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT	SECT	HIGHWAY
REVISIONS		0920 03	081 CR 101
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	BMT	HARDIN	64
4-98 7-20			
20G			

DATE: 12/15/2021 9:19:55 PM
 FILE: C:\Users\RPASTORE\Desktop\0920-03-081\ready to print\SW3P_LAYOUT.dgn




BMP #	BMP TYPE	INSTALL DATE	INITIALS	REMOVE DATE	INITIALS
1	SCF				
2	SCF				
3	RFD2				
4	RFD2				
5	RFD2				
6	SCF				
7	RFD2				
8	SCF				

* NOTE:
 ROW ASSUMED BASED ON GOVERNING
 COUNTY INFORMATION



NOTE:
 *ROW ASSUMED BASED ON GOVERNING
 COUNTY INFORMATION



Andrew C. Lee

12/16/2021

0920-03-081
 CR 101
 FLAT CYPRESS
 CREEK
 SW3P / UTILITY
 LAYOUT

N. T. S.



CONT	SECT	JOB	HIGHWAY
0920	03	081	CR 101
DIST	COUNTY	SHEET NO.	
BMT	HARDIN	65	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):
0920-03-081

1.2 PROJECT LIMITS:

From: CR 101 @ FLAT CYPRESS CREEK

To: (STR 201010AA0101001)

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 30.419217°, (Long) -94.540600°

END: (Lat) 30.419215°, (Long) -94.539673°

1.4 TOTAL PROJECT AREA (Acres): 0.32

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.10

1.6 NATURE OF CONSTRUCTION ACTIVITY:

REMOVE EXISTING BRIDGE, INSTALL PROPOSED BRIDGE
INSTALL STONE RIPRAP
INSTALL MBGF, CONSTRUCT APPROACH ROAD

1.7 MAJOR SOIL TYPES:

Soil Type	Description
KoA	KOURY VERY FINE SANDY LOAM

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: _____
 Other: _____
 Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
	DRY CREEK
	CYPRESS CREEK

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: _____
- Other: _____

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
	BR 2021(530)			66
STATE	STATE DIST.	COUNTY		
TEXAS	20	HARDIN		
CONT.	SECT.	JOB	HIGHWAY NO.	
C	03	081	CR 101	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: SILT FENCE
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: SILT FENCE
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.9 MAINTENANCE:


Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)




FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
	BR 2021(530)		66A
STATE	STATE DIST.	COUNTY	
TEXAS	20	HARDIN	
CONT.	SECT.	JOB	HIGHWAY NO.
C	03	081	CR 101

10/15/2021
 C:\Users\RPASTORE\Desktop\PW_Export\0920-03-081_EC116.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. ETC_95%_development\0920-03-081_Standards.ec116.dgn



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0920	03	081	CR 101	
	DIST	COUNTY		SHEET NO.	
	BMT	HARDIN		67	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/15/2021
 FILE: C:\Users\RPASTORE\Desktop\PW Exports\0920-03-081, ETC 95% development\0920-03-081\Standards\ec216.dgn




FILTER DAM AT TOE OF SLOPE

(RFD1)




FILTER DAM AT SEDIMENT TRAP

(RFD1) OR (RFD2)




FILTER DAM AT CHANNEL SECTIONS


(RFD1) OR (RFD2) OR (RFD3)




PLAN VIEW




"V" SHAPE PLAN VIEW



SECTION B-B



PROFILE



SECTION C-C

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.


Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)



TYPE 4 (SACK GABIONS)

(RFD4)



SECTION A-A

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC(2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0920 03	081	CR 101
	DIST	COUNTY	SHEET NO.
	BMT	HARDIN	68

DATE: 12/16/2021 3:46:53 PM
 FILE: C:\Users\RPASTORE\Desktop\Exports\0920-03-081, ETC 95% development\0920-03-081-0920-03-081.dwg
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.
 DISCLAIMER:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- 1. TxDOT - Beaumont District

No Action Required Required Action

Action No.

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
2. Comply with the SW3P and revise when necessary to control pollution or as required by the Engineer.
3. The project is estimated to involve less than one acre of soil disturbance. In the event the project disturbance acreage becomes equal to or greater than one acre, the CGP is applicable. Contact TxDOT project inspector for coordination with DEQC for necessary action.
4. Take measures to prevent construction materials and debris including, but not limited to wastewater (i.e., cooling liquid, etc.) associated with concrete removal from entering any inlets, ditches, or waterways.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions, including Regional conditions for the State of Texas, associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required: Permit # _____
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1. Maintain a neat and clean worksite next to the water and do not allow any debris to fall into the water.
2. Comply with "Work In or Near Waters/Wetlands Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
3. USACE NWP 14 #SWG-2021-00647 applies to Flat Cypress and adjacent wetlands: Wet 1 (on the north side of CR 101 from approximately STA 4+92 to STA 5+10), WET 2 (on the south side of CR 101 from approximately STA 5+00 to STA 5+19) as shown in Section 404 permit drawings and in the Plan and Profile section of the plan set.
4. Only the work identified in the USACE 404 permit is authorized within WOUS. Contractor must ensure all work conducted in WOUS is in accordance with the permitted plan sheets of the USACE permit. Any WOUS for which no work is shown in the permit must be avoided. The contractor is responsible for ensuring impacts to WOUS do not exceed what is shown in the permit drawings. A copy of the permit will be provided at the pre-construction meeting or upon request to the TxDOT Inspector or DEQC. The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

- | | | |
|---|--|--|
| Erosion | Sedimentation | Post-Construction TSS |
| <input type="checkbox"/> Temporary Vegetation | <input checked="" type="checkbox"/> Silt Fence | <input type="checkbox"/> Vegetative Filter Strips |
| <input type="checkbox"/> Blankets/Matting | <input type="checkbox"/> Rock Berm | <input type="checkbox"/> Retention/Irrigation Systems |
| <input type="checkbox"/> Mulch | <input type="checkbox"/> Triangular Filter Dike | <input type="checkbox"/> Extended Detention Basin |
| <input type="checkbox"/> Sodding | <input type="checkbox"/> Sand Bag Berm | <input type="checkbox"/> Constructed Wetlands |
| <input type="checkbox"/> Interceptor Swale | <input type="checkbox"/> Straw Bale Dike | <input type="checkbox"/> Wet Basin |
| <input type="checkbox"/> Diversion Dike | <input type="checkbox"/> Brush Berms | <input type="checkbox"/> Erosion Control Compost |
| <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Erosion Control Compost | <input type="checkbox"/> Mulch Filter Berm and Socks |
| <input checked="" type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks |
| <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks | <input checked="" type="checkbox"/> Vegetation Lined Ditches |
| | <input type="checkbox"/> Stone Outlet Sediment Traps | <input type="checkbox"/> Sand Filter Systems |
| | <input type="checkbox"/> Sediment Basins | |

III. CULTURAL RESOURCES

No Action Required Required Action
Action No.

1. Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

IV. VEGETATION RESOURCES

No Action Required Required Action
Action No.

1. Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.
2. Comply with "Vegetation and Habitat Impacts: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
3. Any equipment that comes into contact with water is required to follow TPWD Clean, Drain, Dry procedure to protect against the spreading of invasive aquatic species. See http://tpwd.texas.gov/fishboat/boat/protect*water or contact District Environmental staff for guidance

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required Required Action
Action No.

1. The project area contains habitat for Southern crawfish frog, Strecker's chorus frog, Woodhouse's toad, Swallow-tailed kite, Blackspot Shiner, Big brown bat, Eastern spotted skunk, Long-tailed weasel, Rafinesque's big-eared bat, Southeastern myotis bat, Swamp rabbit, Tricolored bat, Alligator snapping turtle, Eastern box turtle, Slender glass lizard, Timber rattlesnake, Western box turtle.
2. If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEQC for guidance.
3. Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
4. Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and (TPW) Code Section 64.002. For compliance with MBTA and TPW Code, bridge demolition, clearing of vegetation, and tree trimming activities are to be scheduled from October 1 to February 14 (outside of migratory bird nesting season). Contractor is responsible for securing a qualified biologist to conduct a nest survey for any bridge demolition, tree trimming, or vegetation clearing that occurs during migratory bird nesting season. The qualified biologist must submit a survey protocol for approval by District environmental staff prior to construction. A nesting survey will remain valid up to five days. Any activity not completed within 5 days of a nesting survey will require another survey. Migratory bird nesting season is from February 15 to September 30. No removal of active nests is allowed during migratory bird nesting season; therefore, any structure or vegetation containing an active nest may not be disturbed, cleared, or trimmed. No removal of inactive nests is allowed during migratory bird nesting season except by an approved, qualified biologist. Contractor is responsible for ensuring all nests on bridge structures are removed prior to the start of nesting season. The full TxDOT MBTA guidance may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/toolkit/350-01-gui.pdf>
5. Comply with the TPWD MOU regarding Amphibian, Water Quality, Bird, Bat, Aquatic Reptile, Terrestrial Reptile, Fish, and Plains Spotted Skunk BMPs. A copy of the TPWD MOU BMPs for compliance with the above BMPs can be found at: <https://ftp.txdot.gov/pub/txdot-info/env/toolkit/300-01-bmp.pdf>

LIST OF ABBREVIATIONS

- | | |
|---|---|
| BMP: Best Management Practice | SPCC: Spill Prevention Control and Countermeasure |
| CGP: Construction General Permit | SW3P: Storm Water Pollution Prevention Plan |
| DSHS: Texas Department of State Health Services | PCN: Pre-Construction Notification |
| FHWA: Federal Highway Administration | PSL: Project Specific Location |
| MOA: Memorandum of Agreement | TCEQ: Texas Commission on Environmental Quality |
| MOU: Memorandum of Understanding | TPDES: Texas Pollutant Discharge Elimination System |
| MS4: Municipal Separate Stormwater Sewer System | TPWD: Texas Parks and Wildlife Department |
| MBTA: Migratory Bird Treaty Act | TxDOT: Texas Department of Transportation |
| NOT: Notice of Termination | T&E: Threatened and Endangered Species |
| NMP: Nationwide Permit | USACE: U.S. Army Corps of Engineers |
| NOI: Notice of Intent | USFWS: U.S. Fish and Wildlife Service |

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

No Action Required Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances
- * Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
CR 101 @ Flat Cypress Creek	20-101-0-AA01-01-001	Various	N/A	None Detected

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

Action No.

1. Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous materials or contamination is noted during construction.
2. Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required Required Action

Action No.

1. Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.

		Beaumont District Standard	
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC			
FILE: epic.dgn	DN: TxDOT	CK: AM	DW: VP
©TxDOT February 2019	CONT	SECT	JOB
	0920 03	081	CR 101
	DIST	COUNTY	SHEET NO.
	BMT	HARDIN	69

Ashley Bogrand 12/16/2021

APPROVED BY DATE

DISTRICT ENVIRONMENTAL DEPARTMENT