

**INDEX OF SHEETS**

SEE SHEET 2 FOR INDEX OF SHEETS

**STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT NO.  
STP 2024 (077) HES

**US 82  
LAMAR AND RED RIVER**

LIMITS: FROM LOOP 286 TO BOWIE COUNTY LINE

FOR THE CONSTRUCTION OF: SAFETY END TREATMENT AND FIXED OBJECTS  
CONSISTING OF: SAFETY END TREATMENTS OF CULVERTS  
AND IMPROVING GUARDRAIL TO DESIGN STANDARDS

**PROJECT TOTALS**

NET LENGTH OF ROADWAY = 46.79 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 46.79 MI

**CSJ: 0045-09-116**

NET LENGTH OF ROADWAY = 6.26 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 6.26 MI

LIMITS: FROM LOOP 286 TO 4,971 FT WEST  
OF FM 196

**CSJ: 0045-12-093**

NET LENGTH OF ROADWAY = 1.66 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 1.66 MI

LIMITS: FROM SH 37 S TO SH 37 N

**CSJ: 0045-11-046**

NET LENGTH OF ROADWAY = 5.33 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 5.33 MI

LIMITS: FROM 4,971 FT WEST OF FM 196  
TO THE RED RIVER COUNTY LINE

**CSJ: 0046-10-007**

NET LENGTH OF ROADWAY = 1.56 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 1.56 MI

LIMITS: FROM SH 37 N TO BU 82 J

**CSJ: 0045-12-094**



NET LENGTH OF ROADWAY = 14.84 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 14.84 MI

LIMITS: FROM THE RED RIVER COUNTY  
LINE TO SH 37 S

**CSJ: 0046-01-071**

NET LENGTH OF ROADWAY = 17.15 MI  
NET LENGTH OF BRIDGE = 0 MI  
NET LENGTH OF PROJECT = 17.15 MI

LIMITS: FROM BU 82 J TO THE BOWIE  
COUNTY LINE



BEGIN PROJECT  
BEGIN CSJ: 0045-09-116  
STA: 0+00  
REF MRK: 710+0.735

END CSJ: 0045-09-116  
STA: 330+42  
REF MRK: 716+0.986  
  
BEGIN CSJ: 0045-11-046  
STA: 330+42  
REF MRK: 716+0.986

END CSJ: 0045-11-046  
STA: 611+80  
REF MRK: 722+0.005  
  
BEGIN CSJ: 0045-12-094  
STA: 611+80  
REF MRK: 722+0.005

END CSJ: 0045-12-094  
STA: 1395+16  
REF MRK: 737-0.052  
  
BEGIN CSJ: 0045-12-093  
STA: 1395+16  
REF MRK: 737-0.052

END CSJ: 0045-12-093  
STA: 1482+60  
REF MRK: 738+0.463  
  
BEGIN CSJ: 0046-10-007  
STA: 1482+60  
REF MRK: 738+0.463

END CSJ: 0046-10-007  
STA: 1565+09  
REF MRK: 738+2.024  
  
BEGIN CSJ: 0046-01-071  
STA: 0+00  
REF MRK: 738+2.024

END PROJECT  
END CSJ: 0046-01-071  
STA: 905+64  
REF MRK: 756+0.562

EXCEPTIONS: N/A  
EQUATIONS: N/A  
RAILROAD CROSSINGS: N/A

© 2023  
BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED.

DESIGN SPEED: N/A  
ADT: 7,195 EXISTING  
ADT: 10,072 PROJECTED  
FUNCTIONAL CLASS: 3

FHWA TEXAS DIVISION		SHEET NO. 1	
STATE	DISTRICT	COUNTY	
TEXAS	PAR	LAMAR, ETC.	
CONTROL	SECTION	JOB	HIGHWAY NO.
0045	09	116, ETC.	US 82

**FINAL PLANS**

LETTING DATE: \_\_\_\_\_  
DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_  
DATE WORK WAS COMPLETED: \_\_\_\_\_  
DATE WORK WAS ACCEPTED: \_\_\_\_\_  
ORIGINAL CONTRACT WORKING DAYS: \_\_\_\_\_  
USED OF WORKING DAYS \_\_\_\_\_  
NO. OF CHANGE ORDERS: \_\_\_\_\_  
FINAL CONTRACT COST: \_\_\_\_\_  
PERCENT OVER/UNDER RUN: \_\_\_\_\_  
CONTRACTOR: \_\_\_\_\_

I CERTIFY THAT THIS PROJECT WAS BUILT IN ACCORDANCE WITH PLANS AND SPECIFICATIONS.

AREA ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".



SUBMITTED FOR LETTING: 07/31/2023

*Austin R. Shatto, P.E.*  
DESIGN ENGINEER

RECOMMENDED FOR LETTING: 8/3/2023

DocuSigned by:  
*Amrith H. Jayaraj, P.E.*  
038568848965429  
AREA ENGINEER

APPROVED FOR LETTING: 8/3/2023

DocuSigned by:  
*Noel Paramanathan*  
AF7AF41AF6049E  
DISTRICT ENGINEER

T:\PARISAO\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Plan Sheets\Title Sheet.dgn  
FILE: 7/28/2023 11:23:01 AM  
DATE:

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 5, 2022)

# INDEX OF SHEETS

SHEET NO. DESCRIPTION

**GENERAL**

1 TITLE SHEET  
2 INDEX OF SHEETS  
3-4 PROJECT LAYOUT  
5, 5A-5C GENERAL NOTES  
6, 6A ESTIMATE & QUANTITY  
7-16 QUANTITY SUMMARIES

**TRAFFIC CONTROL PLAN**

17 SEQUENCE OF WORK

**TRAFFIC CONTROL PLAN STANDARDS**

\* 18-29 BC (1)-21 THRU BC (12)-21  
\* 30 TCP(2-1)-18  
\* 31 TCP(2-2)-18  
\* 32 TCP(2-4)-18  
\* 33 TCP(3-1)-13  
\* 34 WZ(STPM)-23  
\* 35 WZ(RS)-22  
\* 36 TREATMENT FOR VARIOUS EDGE CONDITIONS

**ROADWAY DETAILS**

37 MBGF DETAIL FOR CROSS CULVERTS  
38 MBGF DETAIL CUTHAND CREEK  
39 DRIVEWAY DETAILS

**ROADWAY DETAIL STANDARDS**

\* 40 GF(31)-19  
\* 41 GF(31)DAT-19  
\* 42 GF(31)MS-19  
\* 43-45 SRG(TL-3)-21 (MOD)  
\* 46 SGT(12S)31-18  
\* 47 SGT(15)31-20  
\* 48 TE(HMAC)-11

**DRAINAGE DETAILS**

49-56 CULVERT LAYOUT  
\* 57 BCS

**DRAINAGE DETAIL STANDARDS**

\* 58 SCC-MD  
\* 59-60 SCC-3 & 4  
\* 61-62 SCC-5 & 6  
\* 63 SCP-MD  
\* 64 SCP-3  
\* 65 SCP-4

SHEET NO. DESCRIPTION

\* 66 SCP-5  
\* 67 SCP-6  
\* 68 MC-MD  
\* 69-70 MC-5-20  
\* 71 ECD  
\* 72 PW  
\* 73-74 SETP-CD  
\* 75 SETP-PD  
\* 76 PSET-SC  
\* 77 PSET-SP  
\* 78 PSET-RR

**PAVEMENT MARKINGS & DELINEATION STANDARDS**


\* 79 D&OM(1)-20  
\* 80 D&OM(2)-20  
\* 81 D&OM(3)-20  
\* 82 D&OM(4)-20  
\* 83 D&OM(5)-20  
\* 84 D&OM(6)-20  
\* 85 D&OM(VIA)-20  
\* 86 PM(1)-22  
\* 87 PM(2)-22

**ENVIRONMENTAL ISSUES**

\* 88-89 SWP3  
\* 90 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

**ENVIRONMENTAL ISSUES STANDARDS**

\* 91 EC(1)-16  
\* 92 EC(2)-16



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A \* ON THIS SHEET HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

*Austin R. Shatto, P.E.* 08/04/2023  
NAME DATE




## INDEX OF SHEETS

2023			
CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		2

DATE: 8/4/2023 9:10:20 AM  
FILE: I:\PARISAD\DESIGN\US 82 E Saf.teu I-reet 0045-09-116\Design\CAD Plan Sheets\index of sheets.dgn

DATE: 7/31/2023 2:31:33 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.txd

DATE: 7/31/2023 2:31:33 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.txd



*Austin R. Shatto, P.E.*  
 07/31/2023



**US 82  
 PROJECT LAYOUT**

SHEET 1 OF 2

© 2023			
CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		3

DATE: 7/28/2023 11:23:02 AM  
 FILE: I:\PARIS\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD\_Plan\_Sheets\Project\_Layout.dgn

CR: [ ]  
 DW: [ ]  
 CK: [ ]  
 DN: [ ]



*Austin R. Shatto, P.E.*  
 07/31/2023  
**US 82**  
**PROJECT LAYOUT**



SHEET 2 OF 2

© 2023

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	4	



County: Lamar, Etc.

Control: 0045-09-116, Etc.

Highway: US 82

Sheet:

## GENERAL NOTES

### General:

This project contains the following modified standard sheets: SRG(TL-3)-21 (MOD)

Contractor questions on this project are to be addressed to the following individual(s):

Paris Area Office

Daniel Taylor P.E. - [Daniel.Taylor@txdot.gov](mailto:Daniel.Taylor@txdot.gov)

Zachary Smith P.E. - [Zachary.Smith@txdot.gov](mailto:Zachary.Smith@txdot.gov)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

On Contractor request, earthwork cross sections and construction timelines will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Dispose of waste materials at an approved site. Furnish written approval from the property owner before disposal of waste materials.

Locate equipment a minimum of 30 feet from roadway when possible. Place signs and barricades as approved.

Stockpile sites for construction materials must be approved. Give at least 48 hours notification prior to stockpiling material.

County: Lamar, Etc.

Control: 0045-09-116, Etc.

Highway: US 82

Sheet: 5

### Item 5 Control of the Work:

The responsibility for the construction surveying on this contract will be in accordance with Section 5.9.3, Method C.

Working days will be computed and charged in accordance with Article 8.3.1.4 Standard Work Week.

Right and left are determined based upon the forward direction of stationing in the specific control section.

### Item 6 Control of Materials:

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html>

### Item 7 Legal Relations and Responsibilities:

No significant traffic generator events identified.

### Item 8 Prosecution and Progress:

Before beginning work on this project submit in writing, for approval, a plan of construction operations outlining in detail a sequence of work to be followed.

Provide a Bar Chart progress schedule for this project.

This project includes SP 008-003 which allows up to a 90-day delay to begin work on the project to allow for Contractor Mobilization.

### Item 9 Measurement and Payment:

Items of work for the Monthly Estimate will be cut off on the 25<sup>th</sup> of each month. Items of work performed after the 25<sup>th</sup> will be processed and paid on the following month's estimate. Material On Hand (MOH) will cut off on the 20<sup>th</sup> of each month. Special circumstances will be considered on a case-by-case basis.

**County:** Lamar, ETC.

**Control:** 0045-09-116, ETC.

**Highway:** US 82

**Sheet:**

**Item 100 Preparing Right of Way:**

Remove all trees 40 foot from centerline on both sides of roadway. At cross structures, remove trees to ROW line and within 100' of the structure, parallel to the roadway. Remove underbrush and neatly trim trees and overhanging branches to produce a 60' vertical clear area within the limits of Prep ROW. Remove any trees or underbrush that interferes with any construction operation, including relocation of ditches or other drainage elements. Receive approval of equipment used to trim limbs. A boom axe will not be allowed. Remove all trimmed debris from the ROW or mulch all debris and incorporate into the topsoil on State ROW to the satisfaction of the Engineer.

Trimming and removal of trees or brush necessary for construction operations will not be paid for directly but will be subsidiary to other items.

**Item 110 Excavation:**

Material below finished subgrade elevation suspected of containing sulfates will be tested in accordance with Tex-145-E by the Department. Treat subgrade material to the required depth and width in accordance with the Soil Sulfates Mitigation General Notes.

Before excavation operations the existing topsoil shall be salvaged in a manner to preserve the vigor of the existing Bermuda grass sod per Item 160.

**Item 134 Backfilling Pavement Edges:**

Use Type A backfill Material for final backfill. Provide material free of vegetation and other objectionable material with a Plasticity Index between 15 and 30.

The backfill material source shall be approved.

**Item 164 Seeding for Erosion Control, 166 Fertilizer:**

Apply fertilizer with a ratio of 3-1-2 (N-P-K) over the areas to be seeded. This work will not be paid for directly, but will be considered subsidiary.

**Item 168 Vegetative Watering:**

Use water trucks equipped with a sprinkler system adequate to permit coverage of the entire seeded area from the roadbed. This equipment must be available to perform watering throughout the duration of vegetative establishment.

Water all seeded areas the day seed is applied. Thereafter, maintain the seeded areas in a well-watered condition throughout the duration of vegetative establishment.

**County:** Lamar, ETC.

**Control:** 0045-09-116, ETC.

**Highway:** US 82

**Sheet:** 5A

**Item 400 Excavation and Backfill for Structures:**

Excavation and backfill for bridge, culvert and Safety End Treatment construction/installation will be subsidiary to Item 462, 464, 466, and 467.

Pavement markings and RPM replacement will be subsidiary to "Cut and Restore Pavement".

Cut and Restore Pavement: Backfill to top of pipe using HES flowable fill. Use an accelerator that produces a minimum strength of 250 psi in 4 hours. Provide rheofill or equivalent to ensure flowability. Anchor pipes to ensure no movement or displacement by the flowable fill. Furnish paper type cylinder test molds. Place Type B or C HMA from the top of the flowable fill to the existing roadway surface.

**Item 402 Trench Excavation Protection**

Submit a Trench Excavation Protection Plan to the Engineer a minimum of three weeks prior to use. The excavation support plan shall address excavation/protection methods, work sequencing, traffic control, backfill operations, etc.

**Item 403 Temporary Special Shoring**

Submit a Temporary Special Shoring Plan to the Engineer a minimum of three weeks prior to use. The excavation support plan shall address excavation/protection methods, work sequencing, traffic control, backfill operations, etc.

**Item 432 Riprap:**

The Engineer may adjust placement of riprap in the field.

Filter fabric is required for stone riprap.

Bridge demolition waste concrete may be used for stone rip rap. Cut protruding rebar within 2" of concrete surface. Maximum waste concrete cobble size shall match proposed stone rip rap Dmax size.

Grout and backfill mow strip within 10 days of placement. Payment will be withheld until this work is performed.

**Item 462 Concrete Box Culverts and Drains**

Required excavation and backfill will be subsidiary to this Item. Use 2" minimum granular material as bedding for precast concrete box culverts.

Shaping and bedding will conform to item 400.

**County:** Lamar, ETC.

**Control:** 0045-09-116, ETC.

**Highway:** US 82

**Sheet:**

**Item 464 Reinforced Concrete Pipe:**

Required excavation and backfill will be subsidiary to this Item.

Concrete pipe collars shall be subsidiary this item.

**Item 466 Headwalls and Wingwalls:**

Unless shown in plans to obtain from offsite source, obtain headwall and wingwall backfill from ROW and perform grading to shape ditch to headwall/wingwall, per Engineers directions. This work will be subsidiary to this Item.

Riprap apron, between wingwalls, will be subsidiary to this Item.

Required excavation, backfill and pipe saw cutting will be subsidiary to this Item.

Removed headwalls and wingwalls may be broken into riprap size pieces (12" average diameter) for use as stone riprap on the project. Cut protruding steel reinforcement flush with concrete pieces. Broken concrete and riprap must be stored according to the requirements for material stockpiles indicated on the BC standards.

**Item 467 Safety End Treatment:**

Parallel pipe culverts ~ 30" diameter and smaller require precast SET unless directed by the Engineer to use cast-in-place SETs when precast SETs would project over 3" above surrounding ground surface or when otherwise indicated in the plans. Additional work to install cast in place SETs will be subsidiary to this Item.

Cross pipe culverts ~ 30" diameter and smaller require precast SET unless indicated otherwise in the plans.

Repair damage culvert ends prior to SET installation. Straighten CMP ends by straightening or cutting off damaged ends. Paint cut off ends with zinc paint. Repair minor damaged RCP ends with epoxy mortar. This work will be subsidiary to this Item.

When necessary to close connection gaps, grout precast SETs to culvert ends. Materials, labor, and equipment will be subsidiary to this item.

On existing CMP parallel culverts with mitered metal ends, construct concrete cast in place SETs or remove the mitered ends and install precast or cast-in-place SETs. Replace/remove existing mitered metal ends that are not 6:1 or flatter.

Required excavation, backfill and pipe saw cutting will be subsidiary to this Item.

**County:** Lamar, ETC.

**Control:** 0045-09-116, ETC.

**Highway:** US 82

**Sheet:** 5B

Unless shown in the plans to obtain backfill from offsite source, obtain SET backfill from the Right-of-Way. This work will be subsidiary to this Item.

Placement of concrete Riprap between multiple SETs on multiple barrel culverts will be subsidiary to this Item.

Prior to SET installation for parallel pipe culverts, ensure the slope from the top of the SET to the top of grade is no steeper than 6:1. At locations where the slope is steeper than 6:1, additional pipe will be added. This work will be paid for by using applicable items.

During SET installation, unless indicated otherwise in the plans, match SET flow line grade with the culvert flow line grade.

Removed concrete headwalls and wingwalls may be broken into riprap size pieces (12" average diameter) for use as stone riprap. Cut protruding steel reinforcement. Broken concrete and riprap must be stored according to the requirements for material stockpiles indicated on BC(10)-21.

**Item 502 Barricades, Signs and Traffic Handling:**

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The following items will be required for flagger on this project:

1. Flaggers are required to wear a white hard hat while performing flagging operations.
2. Flaggers will be required at the intersection of all State maintained roadways.
3. Flaggers may be required at other high traffic generating intersections as deemed necessary by the Area Engineer.

The traffic control plan for this contract consists of the installation and maintenance of warning signs and other traffic control devices shown in the plans, specification data which may be included in the general notes, applicable provisions of the Texas Manual on Uniform Traffic Control Devices (TMUTCD), traffic control plan sheets included in the plans, standard BC sheets and Item 502 of the Standard Specifications.

**County:** Lamar, ETC.

**Control:** 0045-09-116, ETC.

**Highway:** US 82

**Sheet:**

***Item 502 Barricades, Signs and Traffic Handling (Cont.):***

Do not begin Item 502, Barricades, Signs, and Traffic Handling, on the roadway until both of the following conditions are met:

1. The work schedule is approved.
2. No more than 5 workdays will pass between the beginning of Item 502 and the actual commencement of roadway work bid items.

The final estimate will be withheld until all disturbed areas are covered with at least 70% perennial vegetative cover.

Correct all deficiencies within the time frame noted on the Traffic Control Device Inspection Form 599. Failure to make corrections within time frame specified may result in no payment for this Item for the month of the noted deficiency.

Provide shadow vehicles equipped with Truck Mounted Attenuators (TMA) as shown on Traffic Control Plan (TCP) standards.

Ensure that all travel lanes are open at night.

Road closures must be approved by the Engineer. Provide a two-week advance notice to the Engineer prior to desired roadway closure period. Begin display of closure information on PCMBs ten days prior to roadway closure.

**Item 506 Temporary Erosion, Sedimentation & Environmental Controls:**

The Temporary Erosion Control measures for this project will consist of using the following items, as directed:

1. Temporary Silt Fence
2. Rock Filter Dams

Silt fences will remain the property of the Contractor upon completion of the project. The final estimate will not be released until all silt fences have been properly removed, or as directed and 70% establishment of vegetative cover is obtained.

Acquire approval for any change to the location of temporary sediment fence, as shown in the plans, prior to installation. Placement of erosion protection devices may be altered, as directed, to satisfy the requirements of the SW3P.

The pay item to remove rock filter dams will require only a partial removal after 70 percent perennial vegetation has been established and approved. When removing the rock filter dams, leave the lower layer of rock adjacent to the ground in place so as not to disturb the soil.

Refer to the SW3P sheet for the total disturbed area for the project.

**County:** Lamar, ETC.

**Control:** 0045-09-116, ETC.

**Highway:** US 82

**Sheet:** 5C

The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs) within one mile of the project limits will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within one mile of the project limits exceeds five acres, provide a copy of the Contractors NOI for PSLs on the ROW (to the appropriate MS4 operator when on an off-system route).

**Item 540 Metal Beam Guard Fence:**

Reinstall removed MBGF and SGT's on the same day.

MBGF delineation shall be installed within ten (10) working days of the completion of each MBGF section. Concrete mow strip is not considered to be a part of this work.

**Item 644 Small Roadside Sign Support and Assemblies:**

Upon removal of sign assemblies, deliver sign faces to TxDOT office at 3600 SW Loop 286, Paris TX. Dispose of foundations, posts, and hardware.

Use the Southern Plains style triangular slip base for all post types.

When city or county signs are located on TxDOT signs – replace with new signs of the same dimensions and style. This work will be subsidiary to Item 644.

Stake proposed sign locations and obtain Engineer's approval of locations prior to placing foundations.

**Item 6001 Portable Changeable Message Board:**

Two (2) portable changeable message boards are required for advance warning. Limit the distance between message boards to 10 miles.

**Item 6185 Truck Mounted Attenuators:**

Shadow vehicles with truck mounted attenuator (TMA) are required on the traffic control plan and TCP standards for this project. The contractor will be responsible for determining if one or more of these traffic control operations will be ongoing at the same time to determine the total number of TMAs needed for the project.





CONTROLLING PROJECT ID 0045-09-116

DISTRICT Paris  
HIGHWAY US 82

# Estimate & Quantity Sheet

COUNTY Lamar, Red River

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	110-6002	EXCAVATION (CHANNEL)	CY	50.000	
	134-6001	BACKFILL (TY A)	STA	13.100	
	164-6009	BROADCAST SEED (TEMP) (WARM)	SY	9,719.000	
	164-6011	BROADCAST SEED (TEMP) (COOL)	SY	9,719.000	
	164-6023	CELL FBR MLCH SEED(PERM)(RURAL)(CLAY)	SY	19,435.000	
	168-6001	VEGETATIVE WATERING	MG	232.000	
	400-6006	CUT & RESTORING PAV	SY	55.000	
	400-6007	CUT & RESTORE CONC PAVING	SY	241.000	
	400-6008	CUT & RESTORE ASPH PAVING	SY	723.000	
	400-6012	CUT AND RESTORE PAV (FLEX BASE)	SY	1,536.000	
	401-6001	FLOWABLE BACKFILL	CY	51.000	
	402-6001	TRENCH EXCAVATION PROTECTION	LF	62.000	
	403-6001	TEMPORARY SPL SHORING	SF	526.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	138.280	
	462-6009	CONC BOX CULV (5 FT X 5 FT)	LF	64.000	
	462-6045	CONC BOX CULV (3 FT X 2 FT)(EXTEND)	LF	6.000	
	462-6047	CONC BOX CULV (4 FT X 2 FT)(EXTEND)	LF	4.000	
	462-6050	CONC BOX CULV (5 FT X 2 FT)(EXTEND)	LF	12.000	
	462-6053	CONC BOX CULV (5 FT X 5 FT)(EXTEND)	LF	4.000	
	462-6057	CONC BOX CULV (6 FT X 6 FT)(EXTEND)	LF	4.000	
	462-6118	CONC BOX CULV (6 FT X 2.5 FT) (EXTEND)	LF	4.000	
	464-6003	RC PIPE (CL III)(18 IN)	LF	5,962.000	
	464-6005	RC PIPE (CL III)(24 IN)	LF	1,128.000	
	464-6007	RC PIPE (CL III)(30 IN)	LF	104.000	
	464-6008	RC PIPE (CL III)(36 IN)	LF	162.000	
	466-6193	WINGWALL (PW - 2) (HW=4 FT)	EA	5.000	
	466-6196	WINGWALL (PW - 2) (HW=7 FT)	EA	4.000	
	466-6197	WINGWALL (PW - 2) (HW=8 FT)	EA	1.000	
	467-6363	SET (TY II) (18 IN) (RCP) (6: 1) (P)	EA	594.000	
	467-6388	SET (TY II) (24 IN) (RCP) (3: 1) (C)	EA	2.000	
	467-6395	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA	118.000	
	467-6423	SET (TY II) (30 IN) (RCP) (6: 1) (P)	EA	10.000	
	467-6454	SET (TY II) (36 IN) (RCP) (6: 1) (P)	EA	12.000	
	480-6001	CLEAN EXIST CULVERTS	EA	112.000	
	496-6001	REMOV STR (BOX CULVERT)	EA	2.000	
	496-6005	REMOV STR (WINGWALL)	EA	12.000	
	496-6006	REMOV STR (HEADWALL)	EA	24.000	
	496-6007	REMOV STR (PIPE)	LF	7,111.000	
	500-6001	MOBILIZATION	LS	1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	17.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	360.000	

## ESTIMATE & QUANTITY



DISTRICT	COUNTY	CCSJ	SHEET
Paris	Lamar	0045-09-116	6



CONTROLLING PROJECT ID 0045-09-116

DISTRICT Paris  
HIGHWAY US 82

# Estimate & Quantity Sheet

COUNTY Lamar, Red River

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	360.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	1,130.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	1,130.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	1,250.000	
	540-6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	8.000	
	540-6020	MTL W - BEAM GD FEN (LOW FILL CULVERT)	LF	175.000	
	540-6048	TL-3 31" SHORT RADIUS (COMPLETE)	EA	2.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	10.000	
	644-6068	RELOCATE SM RD SN SUP&AM TY 10BWG	EA	2.000	
	658-6047	INSTL OM ASSM (OM-2Y)(WC)GND	EA	24.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	42.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000	
	6185-6002	TMA (STATIONARY)	DAY	241.000	
	6185-6003	TMA (MOBILE OPERATION)	HR	8.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	

## ESTIMATE & QUANTITY



DISTRICT	COUNTY	CCSJ	SHEET
Paris	Lamar	0045-09-116	<b>6A</b>




DATE: 7/31/2023 2:31:33 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.tty.Treet 0045-09-116\Design\CAD\_Plan\_Sheets\estimates.dgn

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0045-09-116														
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	467	467	480	496	496	
				6007	6008	6012	6003	6005	6363	6395	6001	6006	6007	
				CUT & RESTORE CONC PAVING	CUT & RESTORE ASPH PAVING	CUT AND RESTORE PAV (FLEX BASE)	RC PIPE (CL III)(24 IN)	RC PIPE (CL III)(24 IN)	SET (TY II) (18 IN) (RCP) (6:1) (P)	SET (TY II) (24 IN) (RCP) (6:1) (P)	CLEAN EXIST CULVERTS	REMOV STR (HEADWALL)	REMOV STR (PIPE)	
				SY	SY	SY	LF	LF	EA	EA	EA	EA	EA	EA
24+17		RT	BASE								1			
27+67	NO WORK	RT	CONCRETE											
40+40	47TH ST	RT	ASPHALT											
68+47	NO WORK	RT	CONCRETE											
84+07	NO WORK	RT	CONCRETE											
84+67	NO WORK	RT	CONCRETE											
85+75		RT	CONCRETE								1			
86+16		RT	CONCRETE								1			
87+61	NO WORK	RT	CONCRETE											
88+20	NO WORK	RT	CONCRETE											
102+01		RT	BASE			16	40		2					54
103+84	NO WORK	RT	CONCRETE											
104+80		RT	CONCRETE								1			
106+56		RT	CONCRETE								1			
114+29		RT	CONCRETE						2					
114+82		RT	CONCRETE						2		1			
144+19	FM 1508	RT	ASPHALT											
163+57		LT	CONCRETE	13			30		2					25
175+61	NO WORK	LT	ASPHALT											
177+01	NO WORK	LT	ASPHALT											
178+13	NO WORK	LT	BASE											
179+92	NO WORK	LT	ASPHALT											
180+88	NO WORK	LT	ASPHALT											
184+53	NO WORK	LT	ASPHALT											
191+03		RT	ASPHALT								1			
192+58	NO WORK	LT	ASPHALT											
193+45	NO WORK	LT	ASPHALT											
194+72	NO WORK	LT	ASPHALT											
195+52	NO WORK	RT	ASPHALT											
195+73	NO WORK	LT	ASPHALT											
196+88	NO WORK	LT	ASPHALT											
197+48	NO WORK	LT	ASPHALT											
197+77	NO WORK	RT	ASPHALT											
203+17	NO WORK	RT	BASE											
203+72	NO WORK	LT	ASPHALT											
204+47	NO WORK	LT	ASPHALT											
206+00	NO WORK	LT	BASE											
207+02	NO WORK	RT	ASPHALT											
211+23	NO WORK	LT	BASE											
215+01	NO WORK	LT	ASPHALT											
215+99	NO WORK	LT	ASPHALT											
216+28	NO WORK	RT	BASE											
217+35	NO WORK	LT	ASPHALT											
218+35	NO WORK	LT	ASPHALT											
220+05	NO WORK	LT	ASPHALT											
220+50	NO WORK	RT	ASPHALT											
221+54	NO WORK	LT	ASPHALT											
223+26	CR 43600	RT	ASPHALT											
223+83		RT	ASPHALT		8		28		2					0
226+89		RT	ASPHALT								1			
227+96	NO WORK	LT	ASPHALT											
228+32	NO WORK	RT	ASPHALT											
229+32	NO WORK	RT	ASPHALT											
229+65	NO WORK	LT	ASPHALT											
231+53	FM 2121	RT	ASPHALT											
231+77	NO WORK	LT	ASPHALT											
234+16	NO WORK	LT	ASPHALT											
237+00	NO WORK	LT	CONCRETE											
238+32	NO WORK	LT	CONCRETE											
242+85	P 43790	LT	BASE											
243+82		RT	ASPHALT								1			
244+95		RT	ASPHALT								1			
244+98	NO WORK	LT	ASPHALT											
246+17	NO WORK	LT	ASPHALT											
246+38		RT	ASPHALT								1			
247+32	NO WORK	RT	ASPHALT											
247+56	NO WORK	LT	ASPHALT											
250+99	NO WORK	LT	ASPHALT											
252+21		RT	ASPHALT								1			
252+24	NO WORK	LT	ASPHALT											
252+87	NO WORK	LT	ASPHALT											
254+11	NO WORK	LT	ASPHALT											
255+55	NO WORK	RT	ASPHALT											
257+61	NO WORK	LT	ASPHALT											
258+95		RT	ASPHALT								1			
260+70	NO WORK	LT	ASPHALT											
261+56	NO WORK	LT	ASPHALT		13		28		2					27
264+70	NO WORK	LT	ASPHALT											
266+06	NO WORK	LT	ASPHALT											
266+34		RT	ASPHALT								1			
267+38	NO WORK	LT	ASPHALT											
269+88	NO WORK	LT	ASPHALT											
275+80	NO WORK	LT	ASPHALT											
276+91	NO WORK	LT	ASPHALT											
279+41	CR 43900	LT	ASPHALT											
280+35	NO WORK	LT	ASPHALT											
281+94	NO WORK	LT	ASPHALT											
CSJ: 0045-09-116 SUBTOTALS =				13	21	16	126	0	12	0	14	0	106	

**US 82  
QUANTITY SUMMARIES**

SHEET 1 OF 10

© 2023



CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		7

DATE: 7/31/2023 2:31:34 PM  
 FILE: I:\PARISAD\DESIGN\US 82 E Saftey Treat 0045-09-116\Design\CAD Plan Sheets\estimates.dgn


SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0045-09-116, CONTINUED														
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	467	467	480	496	496	
				6007	6008	6012	6003	6005	6363	6395	6001	6006	6007	
				CUT & RESTORE CONC PAVING	CUT & RESTORE ASPH PAVING	CUT AND RESTORE PAV	RC PIPE (CL III)(18 IN)	RC PIPE (CL III)(24 IN)	SET (TY II) (18 IN) (RCP) (6:1) (P)	SET (TY II) (24 IN) (RCP) (6:1)	CLEAN EXIST CULVERTS	REMOV STR (HEADWALL)	REMOV STR (PIPE)	
				SY	SY	SY	LF	LF	EA	EA	EA	EA	EA	LF
283+52	NO WORK	LT	ASPHALT											
285+65	NO WORK	LT	ASPHALT											
290+70		RT	ASPHALT								1			
291+66	NO WORK	RT	ASPHALT											
293+09		RT	ASPHALT								1			
294+26		RT	ASPHALT								1			
301+99	NO WORK	RT	BASE											
303+48	NO WORK	LT	BASE											
306+23	NO WORK	LT	CONCRETE											
308+16		RT	ASPHALT								1			
310+03	NO WORK	RT	ASPHALT											
312+53		RT	BASE						2					
318+01	NO WORK	LT	ASPHALT											
323+86	NO WORK	RT	ASPHALT											
325+31	NO WORK	RT	ASPHALT											
325+84		LT	ASPHALT		15		68		4					48
326+69		LT	ASPHALT		17		70		4					48
327+40		LT	ASPHALT		13		60		4					36
327+77		RT	BASE							2				
328+72	CR 13200	RT	ASPHALT							2				
329+33		LT	BASE						2					
329+71		RT	BASE				8		2			2		
330+38		LT	BASE						2					
CSJ: 0045-09-116 SUBTOTALS =				0	45	0	198	8	18	6	4	2	132	
CSJ: 0045-09-116 TOTALS =				13	66	16	324	8	30	6	18	2	238	

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0045-12-093								
STATION	DESCRIPTION	LT/RT	SURFACE	400	464	467	480	496
				6012	6005	6395	6001	6007
				CUT AND RESTORE PAV (FLEX BASE)	RC PIPE (CL III)(24 IN)	SET (TY II) (24 IN) (RCP) (6:1) (P)	CLEAN EXIST CULVERTS	REMOV STR (PIPE)
				SY	LF	EA	EA	LF
1407+88		RT	BASE	7	30	2		30
1410+45		RT	BASE				1	
1412+01		RT	BASE				1	
1414+13	NO WORK	LT	BASE					
1423+08	NO WORK	LT	CONCRETE					
1425+25	NO WORK	LT	BASE					
1428+47	NO WORK	LT	BASE					
1465+19	NO WORK	RT	ASPHALT					
CSJ: 0045-12-093 TOTALS =				7	30	2	2	30

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0046-10-007								
STATION	DESCRIPTION	LT/RT	SURFACE	400	464	467	480	496
				6008	6003	6363	6001	6007
				CUT & RESTORE ASPH PAVING	RC PIPE (CL III)(18 IN)	SET (TY II) (18 IN) (RCP) (6:1) (P)	CLEAN EXIST CULVERTS	REMOV STR (PIPE)
				SY	LF	EA	EA	LF
1507+69	NO WORK	RT	ASPHALT					
1508+91	NO WORK	LT	ASPHALT					
1509+08	NO WORK	RT	ASPHALT					
1513+24	NO WORK	RT	ASPHALT					
1514+52	NO WORK	LT	ASPHALT					
1520+99	NO WORK	LT	ASPHALT					
1522+76	NO WORK	RT	ASPHALT					
1523+72	NO WORK	LT	ASPHALT					
1528+54		RT	BASE			2		
1529+39	NO WORK	LT	ASPHALT					
1532+15	NO WORK	LT	ASPHALT					
1541+91		RT	ASPHALT				1	
1542+64		LT	ASPHALT	9	24	2		24
1545+39	FM 1159	LT	ASPHALT					
1553+79		LT	ASPHALT				1	
1558+93	NO WORK	RT	ASPHALT					
1564+41	NO WORK	LT	ASPHALT					
CSJ: 0046-10-007 TOTALS =				9	24	4	2	24

**US 82  
QUANTITY SUMMARIES**

SHEET 2 OF 10



CONT	SECT	JOB	HIGHWAY
0045 09		116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		8




DATE: 7/31/2023 2:31:34 PM  
 FILE: I:\PARISAD\DESIGN\US 82 E Saftey I-reet 0045-09-116\Design\CAD\_Plan\_Sheets\estimates.dgn

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0045-12-094																
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	464	467	467	467	480	496	496	644
				6007	6008	6012	6003	6005	6007	6363	6395	6423	6001	6006	6007	6068
				CUT & RESTORE CONC PAVING	CUT & RESTORE ASPH PAVING	CUT AND RESTORE PAV (FLEX BASE)	RC PIPE (CL III)(18 IN)	RC PIPE (CL III)(24 IN)	RC PIPE (CL III)(30 IN)	SET (TY II) (18 IN) (RCP) (6:1) (P)	SET (TY II) (24 IN) (RCP) (6:1) (P)	SET (TY II) (30 IN) (RCP) (6:1) (P)	CLEAN EXIST CULVERTS	REMOV STR (HEADWALL)	REMOV STR (PIPE)	RELOCATE SM RD SN SUP&AM TY 10BWG
				SY	SY	SY	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA
611+94	CR 2113	RT	ASPHALT													
612+28	NO WORK	LT	BASE		15		44			2					40	
617+83	CR 2007	LT	BASE													
648+40	PR 6002	LT	BASE													
661+71	NO WORK	RT	BASE													
662+35		LT	BASE			9		26			2				26	
669+99	NO WORK	LT	BASE													
675+90		LT	BASE			6	20			2					20	
691+67		LT	BASE			11		28			2				28	
694+89	NO WORK	LT	BASE													
695+31		RT	BASE			8	22			2					22	
696+53	NO WORK	RT	BASE													
696+96	NO WORK	LT	BASE													
698+27		RT	BASE							2			1			
699+09		RT	BASE							2			1			
700+07		RT	BASE							2			1			
701+25		RT	BASE							2			1			
702+66		RT	BASE							2			1			
704+04		RT	BASE							2			1			
704+41	NO WORK	LT	BASE													
705+13		LT	BASE										1			
706+67		RT	BASE							2			1			
707+67		RT	BASE							2			1			
707+80	NO WORK	LT	ASPHALT													
709+49		LT	ASPHALT		8			30			2				30	
710+22		LT	ASPHALT		8			26			2				26	
710+77		RT	BASE			8	26			2					22	
711+07		RT	BASE			7	24			2					18	
712+64		LT	BASE			6	18			2					18	
712+81		RT	BASE			8	24			2					22	
714+44		RT	BASE							2						
716+00		LT	BASE			6	16			2					16	
718+52		RT	BASE							2			1			
720+55	9TH SW ST	RT	ASPHALT													
721+08	NO WORK	LT	BASE													
721+59		RT	BASE							2						
722+02		RT	BASE			6	18			2					15	
724+79		RT	BASE			6	16			2					16	
724+96		LT	BASE			6	16			2					16	
726+08		LT	BASE			7	18			2					18	
726+22		RT	BASE							2			1			
727+32		LT	CONCRETE	11			24			2					24	
727+76		LT	BASE			5	16			2					16	
728+42		LT	CONCRETE	11			24			2					24	
728+50		RT	BASE			8	22			2					22	
729+17		RT	BASE							2			1			
730+30		RT	BASE			19	58			2					58	
735+37		RT	BASE			17	46			2					46	
736+18		RT	CONCRETE	16			34			2					30	
737+54		RT	CONCRETE	17			36			2					36	
738+55		RT	CONCRETE	17			36			2					36	
739+91		RT	BASE			18	40			2					40	
742+38	NO WORK	RT	BASE													
743+16	5TH NW ST	LT	ASPHALT		16		42			2					42	2
747+94	NO WORK	LT	ASPHALT													
756+50	FM 410	LT	ASPHALT													
768+04	NO WORK	LT	ASPHALT													
772+52		LT	ASPHALT		12		40			2					40	
783+40		RT	BASE							2			1			
785+05		RT	BASE			7	20			2					20	
786+11		RT	BASE							2			1			
786+49	REMOVE DRIVEWAY	LT	BASE			0									10	
787+77	NO WORK	RT	BASE													
790+11		RT	BASE			6	20			2					20	
791+49		RT	BASE			8	20			2					20	
792+79	NO WORK	LT	ASPHALT													
793+20	7TH SE	RT	BASE			10	36			2			1	2	36	
794+08		RT	BASE							2						
795+04		RT	BASE							2						
795+99		RT	BASE							2						
796+01	FM 2573	LT	ASPHALT													
798+83	NO WORK	RT	CONCRETE													
799+68	NO WORK	LT	BASE													
802+44		RT	BASE			9	20			2					20	
807+57		LT	BASE			8	26			2					26	
808+29		LT	BASE			8	22			2					22	
811+92		RT	BASE			9	20			2					20	
815+32	NO WORK	RT	BASE													
817+65		LT	BASE			6	22			2					22	
854+77	NO WORK	RT	BASE													
858+07		RT	BASE			9	20			2					20	
862+91	CR 2116	RT	ASPHALT													
869+09		LT	BASE			7	24			2					24	
869+63	CR 1215	RT	ASPHALT		12		50			2				2	36	
875+14	CR 2127S	LT	BASE													
876+46		RT	BASE							2						
897+29		RT	BASE							2			1			
CSJ: 0045-12-094 SUBTOTALS =				72	71	248	980	110	0	112	8	0	16	4	1063	2

**US 82**  
**QUANTITY SUMMARIES**

SHEET 4 OF 10

© 2023



Texas Department of Transportation

CONT	SECT	JOB	HIGHWAY
0045 09		116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		10


DATE: 7/31/2023 2:31:35 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.tty I-reet 0045-09-116\Design\CAD Plan Sheets\estimates.dgn

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0045-12-094, CONTINUED																	
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	464	467	467	467	480	496	496	644	
				6007	6008	6012	6003	6005	6007	6363	6395	6423	6001	6006	6007	6068	
				CUT & RESTORE CONC PAVING	CUT & RESTORE ASPH PAVING	CUT AND RESTORE PAV (FLEX BASE)	RC PIPE (CL III)(18 IN)	RC PIPE (CL III)(24 IN)	RC PIPE (CL III)(30 IN)	SET (TY II) (18 IN) (RCP) (6:1) (P)	SET (TY II) (24 IN) (RCP) (6:1) (P)	SET (TY II) (30 IN) (RCP) (6:1) (P)	CLEAN EXIST CULVERTS	REMOV STR (HEADWALL)	REMOV STR (PIPE)	RELOCATE SM RD SN SUP&AM TY 10BWG	
				SY	SY	SY	LF	LF	LF	EA	EA	EA	EA	EA	LF	EA	
897+30		LT	BASE			7	22			2					22		
899+00		LT	BASE			8	28			2					28		
899+63		LT	BASE			10	32			2					32		
904+82		LT	BASE			8		26			2				26		
906+14		LT	BASE			10		36			2				36		
909+85		LT	BASE			11		48			2				48		
915+16	NO WORK	RT	BASE														
922+46		LT	BASE			10			24			2			24		
942+82		LT	BASE			7		26			2				26		
950+70		LT	BASE			7		22			2				22		
957+08		RT	BASE			13	30			2					0		
957+96		RT	BASE							2							
958+27		LT	BASE			9		32			2				32		
961+66		LT	BASE			9		28			2				28		
967+60	CR 2104	RT	ASPHALT														
970+54		LT	BASE			7	24			2					24		
979+79		RT	BASE			10	30			2					30		
984+27		LT	BASE			9	26			2					26		
1001+28	NO WORK	RT	ASPHALT														
1002+39		LT	BASE			7	22			2					22		
1024+82		LT	ASPHALT		7		22			2					22		
1027+49		LT	BASE			9	26			2					26		
1030+37		RT	BASE							2							
1037+78	CR 2106	LT	BASE				8			2				2			
1043+34		RT	ASPHALT		10				28			2			28		
1049+03		LT	ASPHALT		16			42			2				42		
1050+06		LT	ASPHALT		14			40			2				40		
1069+60		RT	ASPHALT							2				2			
1069+60	CR 1290	RT	ASPHALT							2			1	2			
1069+85		LT	BASE			9	20			2					20		
1091+53		RT	BASE			26		76			4				68		
1094+21		RT	BASE			27		64			4				60		
1122+59	NO WORK	LT	BASE														
1128+11	NO WORK	LT	BASE														
1128+23	NO WORK	RT	BASE														
1137+82	CR 1286	RT	ASPHALT				8			2			1	2			
1140+45	NO WORK	RT	BASE														
1182+23		RT	BASE							2							
1188+36		RT	BASE			10	28			2					28		
1195+48		LT	BASE			10	52			2					52		
1197+10		LT	BASE			12	50			2					50		
1199+71	FM 2573	LT	ASPHALT							2				2			
1202+35		LT	BASE			8	32			2					24		
1206+29	CR 1245	RT	ASPHALT						8			2	1	2			
1218+61		LT	BASE			8	32			2					20		
1227+37		RT	BASE			7	18			2					18		
1229+04		LT	BASE			9		32			2				32		
1233+63	NO WORK	RT	BASE														
1235+27	CR 2165	LT	BASE														
1242+25		LT	BASE			8		24			2				24		
1243+16		RT	BASE			11	26			2					20		
1252+32		RT	BASE							2			1				
1252+43		LT	BASE			7		28			2				28		
1253+62		RT	BASE			7	24			2					24		
1256+99		LT	BASE			14		26			2				26		
1259+56	CR 2123	LT	ASPHALT														
1260+01	NO WORK	RT	BASE														
1261+18		LT	BASE			10	44			2					44		
1263+08		LT	BASE			8	22			2					21		
1264+78		LT	BASE			9	26			2					26		
1264+96		RT	BASE			10	20			2					20		
1266+67		LT	BASE			7	18			2					17		
1267+21		RT	BASE			8	20			2					20		
1268+87		RT	BASE			8	20			2					20		
1270+55		LT	BASE			7	28			2					28		
1270+98		RT	BASE							2			1				
1288+34		LT	BASE			7	22			2					21		
1289+61		RT	BASE			9	30			2					30		
1297+70	NO WORK	RT	BASE														
1298+76	NO WORK	LT	BASE														
1305+63		RT	BASE			8		20			2				20		
1306+40		RT	BASE			9		20			2				20		
1308+36		RT	BASE			8		26			2				26		
1310+74		RT	BASE								2						
1311+92		RT	BASE								2						
1312+61		RT	ASPHALT								2						
1313+86		LT	ASPHALT		7		28			2					28		
1317+26	NO WORK	RT	CONCRETE														
1318+74		LT	ASPHALT		13		34			2					34		
1321+13	FM 2825	RT	ASPHALT					8			2						
1321+78	NO WORK	LT	ASPHALT														
1322+36	NO WORK	LT	ASPHALT														
1324+01	NO WORK	LT	ASPHALT														
1333+88	NO WORK	RT	CONCRETE														
1339+69	CR 2155	LT	ASPHALT					8			2			2			
1340+05		RT	ASPHALT														
1341+99		LT	ASPHALT										1				
CSJ: 0045-12-094 SUBTOTALS =				0	67	432	872	632	60	82	50	6	6	14	1453	0	

US 82  
 QUANTITY SUMMARIES

SHEET 5 OF 10

© 2023



Texas  
 Department  
 of Transportation

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		11

DATE: 7/31/2023 2:31:35 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.tey I-reet 0045-09-116\Design\CAD\_Plan\_Sheets\estimates.dgn


CK: DW: DK: DN:

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0045-12-094, CONTINUED																
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	464	467	467	467	480	496	496	644
				6007	6008	6012	6003	6005	6007	6363	6395	6423	6001	6006	6007	6068
				CUT & RESTORE CONC PAVING	CUT & RESTORE ASPH PAVING	CUT AND RESTORE PAV (FLEX BASE)	RC PIPE (CL III)(18 IN)	RC PIPE (CL III)(24 IN)	RC PIPE (CL III)(30 IN)	SET (TY II) (18 IN) (RCP) (6:1) (P)	SET (TY II) (24 IN) (RCP) (6:1) (P)	SET (TY II) (30 IN) (RCP) (6:1) (P)	CLEAN EXIST CULVERTS	REMOV STR (HEADWALL)	REMOV STR (PIPE)	RELOCATE SM RD SN SUP&AM TY 10BWG
				SY	SY	SY	LF	LF	LF	EA	EA	EA	EA	EA	LF	EA
1343+72	NO WORK	RT	ASPHALT													
1345+74	NO WORK	RT	ASPHALT													
1346+31	NO WORK	LT	ASPHALT													
1347+05	NO WORK	RT	CONCRETE													
1347+79	NO WORK	LT	ASPHALT													
1349+22	NO WORK	RT	ASPHALT													
1350+38	NO WORK	RT	ASPHALT													
1350+45		LT	ASPHALT										1			
1351+16	NO WORK	RT	ASPHALT													
1355+38	NO WORK	RT	ASPHALT													
1356+28	NO WORK	LT	ASPHALT													
1357+12	NO WORK	RT	ASPHALT													
1358+43	NO WORK	LT	ASPHALT													
1358+72	NO WORK	RT	ASPHALT													
1359+68	NO WORK	LT	CONCRETE													
1360+18	NO WORK	RT	ASPHALT													
1360+40	NO WORK	LT	CONCRETE													
1361+19	NO WORK	RT	ASPHALT													
1362+11	NO WORK	LT	CONCRETE													
1365+22	NO WORK	LT	CONCRETE													
1365+41	NO WORK	RT	ASPHALT													
1366+78	NO WORK	RT	CONCRETE													
1367+75	NO WORK	RT	CONCRETE													
1368+13	NO WORK	LT	ASPHALT													
1368+89	NO WORK	RT	CONCRETE													
1369+17	NO WORK	LT	ASPHALT													
1370+55	NO WORK	LT	ASPHALT													
1370+72	NO WORK	RT	CONCRETE													
1371+64	NO WORK	LT	ASPHALT													
1372+51	NO WORK	LT	ASPHALT													
1373+51	NO WORK	LT	ASPHALT													
1374+30	NO WORK	LT	CONCRETE													
1374+51	NO WORK	RT	CONCRETE													
1375+15	NO WORK	LT	CONCRETE													
1375+66	NO WORK	LT	ASPHALT													
1376+41	NO WORK	LT	CONCRETE													
1377+70	NO WORK	RT	CONCRETE													
1378+08	NO WORK	LT	CONCRETE													
1378+57	NO WORK	RT	ASPHALT													
1379+82	NO WORK	RT	ASPHALT													
1380+86	NO WORK	RT	ASPHALT													
1380+87	NO WORK	LT	ASPHALT													
1381+77	NO WORK	RT	CONCRETE													
1382+71	NO WORK	RT	CONCRETE													
1383+89	NO WORK	RT	CONCRETE													
1385+43	NO WORK	RT	CONCRETE													
CSJ: 0045-12-094 SUBTOTALS =				0	0	0	0	0	0	0	0	0	1	0	0	0
CSJ: 0045-12-094 TOTALS =				72	138	680	1852	742	60	194	58	6	23	18	2516	2

US 82  
 QUANTITY SUMMARIES

SHEET 6 OF 10

© 2023



CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		12




DATE: 7/31/2023 2:31:35 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.tty I-reet 0045-09-116\Design\CAD Plan Sheets\estimates.dgn

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0046-01-071																	
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	464	464	467	467	467	467	480	496	496
				6007	6008	6012	6003	6005	6007	6008	6363	6395	6423	6454	6001	6006	6007
				CUT & RESTORE CONC PAVING	CUT & RESTORE ASPH PAVING	CUT AND RESTORE PAV (FLEX BASE)	RC PIPE (CL III)(18 IN)	RC PIPE (CL III)(24 IN)	RC PIPE (CL III)(30 IN)	RC PIPE (CL III)(36 IN)	SET (TY II) (18 IN) (RCP) (6: 1) (P)	SET (TY II) (24 IN) (RCP) (6: 1) (P)	SET (TY II) (30 IN) (RCP) (6: 1) (P)	SET (TY II) (36 IN) (RCP) (6: 1) (P)	CLEAN EXIST CULVERTS	REMOV STR (HEADWALL)	REMOV STR (PIPE)
				SY	SY	SY	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	LF
10+77		RT	ASPHALT														
14+04	NO WORK	RT	CONCRETE												1		
14+43	NO WORK	LT	ASPHALT														
16+94		RT	BASE			8	20				2						15
18+85		RT	ASPHALT		9		26				2						25
20+71		RT	ASPHALT		9		26				2						32
21+28		RT	ASPHALT		8		22				2						26
21+90		RT	ASPHALT		7		24				2						33
23+24		RT	BASE			7	24				2						35
34+73	FM 412	RT	ASPHALT														
40+58	NO WORK	LT	BASE														
43+91	NO WORK	LT	BASE														
46+03	NO WORK	LT	BASE														
61+24		RT	ASPHALT		8		22				2						22
63+66		RT	BASE								2						
75+64		LT	BASE			8	16				2						14
79+35	NO WORK	RT	BASE														
79+47	NO WORK	LT	BASE														
81+81		LT	BASE			8	18				2						18
96+64		RT	BASE								2				1		
106+31		RT	ASPHALT								2				1		
106+39		LT	ASPHALT		9		22				2						22
121+64		RT	BASE			7	20				2						20
131+21		LT	BASE			11	26				2						26
133+51		RT	BASE			6	20				2						20
137+97		RT	ASPHALT		8			28					2				27
161+14		RT	BASE			16		38					2				37
184+58		RT	BASE			8	22				2						22
201+56		RT	BASE			8		20					2				20
204+14	CR 3212	LT	ASPHALT														
206+77		RT	ASPHALT		9		24				2						21
238+25	NO WORK	RT	BASE														
250+85		RT	BASE			10	26				2						26
257+08		LT	BASE										2				
275+03		RT	BASE								2				1		
275+86	NO WORK	LT	BASE														
276+37	CR 4210	RT	ASPHALT														
281+97		LT	BASE			10	22				2						22
283+10		LT	BASE			11	36				2						35
284+04		LT	BASE			10	22				2						22
285+04		RT	BASE								2				1		
285+11		LT	BASE			6	20				2						20
286+91		LT	BASE			17	42				2						41
297+28	NO WORK	RT	BASE														
311+70	NO WORK	LT	BASE														
319+18		LT	ASPHALT		7		22				2						20
322+91	NO WORK	RT	ASPHALT														
324+91		LT	BASE			12	48				2						48
325+29		RT	BASE			9	26				2						26
325+87		RT	BASE			6	26				2						26
326+06		LT	ASPHALT		10		28				2						28
326+97		RT	ASPHALT		7		28				2						20
327+25		RT	BASE			8	30				2						24
327+64		RT	BASE			12	36				2						30
341+82		RT	BASE												1		
343+56	NO WORK	LT	BASE														
344+21	NO WORK	LT	BASE														
345+76	NO WORK	LT	BASE														
347+44	NO WORK	LT	BASE														
349+52	FM 44 N	LT	ASPHALT														
351+51	FM 44 S	RT	ASPHALT														
351+69	NO WORK	LT	CONCRETE														
353+09	NO WORK	LT	ASPHALT														
354+17	NO WORK	LT	BASE														
354+77	NO WORK	LT	BASE														
355+70	NO WORK	RT	BASE														
356+04	NO WORK	LT	ASPHALT														
356+55	NO WORK	RT	ASPHALT														
357+12	NO WORK	RT	ASPHALT														
358+23	NO WORK	LT	ASPHALT														
359+33	NO WORK	LT	ASPHALT														
360+44	NO WORK	LT	BASE														
366+30	NO WORK	LT	BASE														
367+11	NO WORK	LT	BASE														
369+64	2ND ST	RT	ASPHALT														
369+66	NO WORK	LT	BASE														
371+02	NO WORK	RT	BASE														
371+78	NO WORK	RT	BASE														
381+51		RT	BASE			9	22				2						22
383+02		RT	BASE			8	34				2						33
384+82		LT	ASPHALT		6		16				2						15
386+95		LT	BASE			11	24				2						24
393+05		LT	BASE			9	18				2						17
395+56		RT	CONCRETE										2		1		
396+74		RT	CONCRETE										2		1		
397+26		LT	CONCRETE		9		22				2						22
398+57		RT	ASPHALT								2				1		
CSJ: 0046-01-071 SUBTOTALS=				9	97	235	880	86	0	0	82	12	0	0	9	0	956

**US 82  
QUANTITY SUMMARIES**

SHEET 7 OF 10

© 2023




CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		13

DATE: 7/31/2023 2:31:36 PM  
 FILE: I:\PARISAD\DESIGN\US 82 E Saf.teu I=ret 0045-09-116\Design\CAD\_Plan\_Sheets\estimates.dgn

SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0046-01-071, CONTINUED																	
STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	464	464	467	467	467	467	480	496	496
				6007	6008	6012	6003	6005	6007	6008	6363	6395	6423	6454	6001	6006	6007
				CUT & RESTORE CONC PAVING SY	CUT & RESTORE ASPH PAVING SY	CUT AND RESTORE PAV SY	RC PIPE (CL III)(18 IN) LF	RC PIPE (CL III)(24 IN) LF	RC PIPE (CL III)(30 IN) LF	RC PIPE (CL III)(36 IN) LF	SET (TY II) (18 IN) (RCP) (6:1) (P) EA	SET (TY II) (24 IN) (RCP) (6:1) EA	SET (TY II) (30 IN) (RCP) (6:1) EA	SET (TY II) (36 IN) (RCP) (6:1) (P) EA	CLEAN EXIST CULVERTS EA	REMOV STR (HEADWALL) EA	REMOV STR (PIPE) LF
398+86		LT	BASE			9	22										22
400+34		RT	BASE														
401+91	NO WORK	RT	BASE														
403+13	OLD ENGLISH RD	RT	ASPHALT														
416+06		RT	BASE														
439+95		RT	BASE														
446+75	NO WORK	RT	ASPHALT														
449+03	NO WORK	LT	BASE														
451+08	NO WORK	RT	ASPHALT														
454+06		RT	ASPHALT														
458+53		RT	ASPHALT														
459+06	NO WORK	LT	ASPHALT														
459+82		LT	BASE														
477+12	NO WORK	RT	BASE														
483+89	NO WORK	RT	BASE														
500+85	NO WORK	LT	BASE														
501+71		LT	BASE														
507+73	CR 4305	RT	ASPHALT											2		2	
509+55		LT	BASE														
511+17		LT	BASE														
512+00	NO WORK	RT	ASPHALT														
512+46		LT	ASPHALT														
515+04		LT	BASE														
517+47		LT	BASE														
520+27	NO WORK	LT	BASE														
566+42	NO WORK	LT	BASE														
575+08	CR 4310	RT	ASPHALT														
589+90		LT	BASE														
590+86	NO WORK	RT	BASE														
597+81		LT	BASE														
598+58	NO WORK	RT	BASE														
606+89		LT	ASPHALT														
606+93		RT	BASE														
608+35		LT	ASPHALT														
608+59	NO WORK	RT	BASE														
615+34	NO WORK	LT	BASE														
621+89	NO WORK	LT	BASE														
622+05	NO WORK	RT	BASE														
623+05	NO WORK	LT	BASE														
627+91		RT	BASE														
630+03		RT	BASE														
630+45	NO WORK	LT	ASPHALT														
631+28		RT	BASE														
636+59		RT	BASE														
636+82	NO WORK	LT	BASE														
646+33	NO WORK	RT	BASE														
652+44	NO WORK	RT	BASE														
662+15	NO WORK	LT	ASPHALT														
663+26		RT	ASPHALT														
672+79	FM 1699	LT	ASPHALT														
676+25		RT	BASE			8	16										
676+49	NO WORK	LT	ASPHALT														
676+75		RT	BASE														
681+53		LT	BASE														
687+72		LT	ASPHALT														
687+84		RT	BASE														
689+94	CR 3322	LT	ASPHALT														
700+07		LT	BASE														
705+23		RT	ASPHALT														
709+82		LT	BASE														
710+67	NO WORK	LT	BASE														
718+45	CR 3325S	RT	ASPHALT														
720+65		LT	BASE														
722+18		RT	BASE														
723+09		RT	BASE														
723+88		RT	BASE														
724+76		LT	BASE														
727+15		RT	BASE														
728+73		LT	ASPHALT														
731+64		RT	ASPHALT														
732+17		LT	ASPHALT														
733+97		LT	BASE														
735+43		RT	ASPHALT														
739+91		LT	BASE														
741+20		RT	BASE														
745+49		LT	ASPHALT														
747+78		LT	BASE														
749+13		LT	BASE														
750+35		LT	ASPHALT														
752+02		LT	ASPHALT														
765+30	NO WORK	LT	BASE														
767+12		RT	BASE														
768+32	NO WORK	LT	ASPHALT														
770+87	NO WORK	LT	ASPHALT														
774+44	CR 4316	RT	BASE														
775+07	NO WORK	LT	BASE														
776+25		LT	ASPHALT														
CSJ: 0046-01-071 SUBTOTALS				0	65	156	350	26	44	162	34	10	4	12	29	2	665

**US 82  
QUANTITY SUMMARIES**

SHEET 8 OF 10

© 2023			
			
CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		14

DATE: 7/31/2023 2:31:36 PM  
 FILE: I:\PARISAD\DESIGN\US 82 E Saf.tey.Treet 0045-09-116\Design\CAD\_Plan\_Sheets\estimates.dgn


SUMMARY OF PARALLEL DRAINAGE ITEMS FOR CSJ: 0046-01-071, CONTINUED

STATION	DESCRIPTION	LT/RT	SURFACE	400	400	400	464	464	464	464	467	467	467	467	480	496	496
				6007	6008	6012	6003	6005	6007	6008	6363	6395	6423	6454	6001	6006	6007
				CUT & RESTORE CONC PAVING SY	CUT & RESTORE ASPH PAVING SY	CUT AND RESTORE PAV SY	RC PIPE (CL III)(18 IN) LF	RC PIPE (CL III)(24 IN) LF	RC PIPE (CL III)(30 IN) LF	RC PIPE (CL III)(36 IN) LF	SET (TY II) (18 IN) (RCP) (6:1) (P) EA	SET (TY II) (24 IN) (RCP) (6:1) EA	SET (TY II) (30 IN) (RCP) (6:1) EA	SET (TY II) (36 IN) (RCP) (6:1) (P) EA	CLEAN EXIST CULVERTS EA	REMOV STR (HEADWALL) EA	REMOV STR (PIPE) LF
778+93	NO WORK	LT	ASPHALT														
780+19	NO WORK	LT	CONCRETE														
781+68		RT	BASE									2			1		
781+76	FM 911 N	RT	ASPHALT														
782+96	SAN ANTONIO ST	RT	ASPHALT		22			54				2					44
783+20		RT	ASPHALT								4				1		
783+48		LT	ASPHALT									2					
786+67		LT	ASPHALT		16			40				2					40
789+65	NO WORK	LT	BASE														
790+98		LT	ASPHALT		16			36			2						35
795+09		RT	BASE			10		26			2						26
795+66	NO WORK	LT	BASE														
796+38		RT	BASE			7		18			2						18
796+55	NO WORK	LT	BASE														
797+45	AUSTIN ST	LT	ASPHALT														
798+59		RT	BASE			11		34			2						33
799+39		RT	BASE			7		20			2						19
800+26		RT	BASE								2				1		
800+36	NO WORK	LT	BASE														
801+32	NO WORK	LT	BASE														
804+61		RT	ASPHALT		15			36			2						35
804+70	NO WORK	LT	ASPHALT														
805+19		RT	BASE			7		20			2						19
805+81		RT	ASPHALT		13			36			2						36
806+37		RT	BASE			6		14			2						13
806+63		RT	BASE			8		24			2						24
806+68		RT	BASE			7		16			2						16
806+76	NO WORK	LT	BASE														
806+94		RT	BASE			8		24			2						24
807+46	NO WORK	LT	ASPHALT														
808+80	NO WORK	LT	ASPHALT														
809+14	NO WORK	RT	BASE														
810+13	NO WORK	RT	BASE														
811+12		RT	ASPHALT		9			26			2						26
811+58		RT	CONCRETE	9				26			2						26
812+32	NO WORK	LT	CONCRETE														
812+58		RT	BASE								2			1			
818+17		RT	ASPHALT								2			1			
818+93		RT	ASPHALT								2			1			
819+01	NO WORK	LT	ASPHALT														
819+57		RT	ASPHALT		7			20			2						20
819+86	NO WORK	LT	ASPHALT														
820+13		RT	ASPHALT		6			18			2						17
820+85	NO WORK	LT	BASE														
821+51	NO WORK	LT	BASE														
822+21	NO WORK	LT	ASPHALT														
822+52	NO WORK	RT	BASE														
823+07	NO WORK	RT	BASE														
823+43		LT	ASPHALT		22			58			2						58
824+18	CR 3330	LT	ASPHALT		10			32			2						32
824+29		RT	BASE			9		28			2						27
825+33		RT	BASE			6		18			2						18
825+74		RT	BASE			7		22			2						21
826+41		RT	BASE			7		24			2						24
827+33		RT	CONCRETE	11				24			2						24
827+94		LT	BASE								2			1			
828+44		RT	ASPHALT		11			26			2						26
828+61	RUST ST	LT	ASPHALT		7			32			2						31
829+57		LT	BASE			10		24			2						24
830+16		LT	BASE			7		20			2						20
832+78	NO WORK	RT	ASPHALT														
834+84	NO WORK	RT	ASPHALT														
836+06	NO WORK	RT	ASPHALT														
837+07	NO WORK	RT	ASPHALT														
838+53	NO WORK	LT	BASE														
838+57	NO WORK	RT	ASPHALT														
840+00		RT	BASE			8		24			2						13
840+55		LT	BASE			13		40			2						40
841+26		RT	BASE								2						
842+16		RT	ASPHALT		14			50			2						50
843+06		LT	ASPHALT		7			24			2						24
846+94	NO WORK	LT	BASE														
857+55		RT	ASPHALT		1			0			2						0
857+97	CR 3335	LT	ASPHALT		13			42				2					42
877+72		RT	BASE			12		36			2						35
878+54	NO WORK	LT	BASE														
880+58	NO WORK	LT	BASE														
904+67	CR 3355	LT	ASPHALT		14			36			2						35
CSJ: 0046-01-071 SUBTOTALS =				20	203	150	912	136	0	0	84	10	0	0	7	0	1015
CSJ: 0046-01-071 TOTALS =				29	365	541	2142	248	44	162	200	32	4	12	45	2	2636

**US 82  
QUANTITY SUMMARIES**

SHEET 9 OF 10

© 2023



CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		15

DATE: 7/31/2023 2:31:36 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Plan Sheets\estimates.dgn

**SUMMARY OF CROSS STRUCTURE ITEMS**

STATION	DESCRIPTION (EXISTING)	DESCRIPTION (PROPOSED)	110	400	401	402	403	462	462	462	462	462	462	462	464	466	466	466	467	496	496	496	658	
			6002	6006	6001	6001	6001	6001	6009	6045	6047	6050	6053	6057	6118	6005	6193	6196	6197	6388	6005	6006	6001	6047
			EXCAVATION (CHANNEL)	CUT & RESTORING PAV	FLOWABLE BACKFILL	TRENCH EXCAVATION PROTECTION	TEMPORARY SPL SHORING	CONC BOX CULV (5 FT X 5 FT)	CONC BOX CULV (3 FT X 2 FT)(EXTEND)	CONC BOX CULV (4 FT X 2 FT)(EXTEND)	CONC BOX CULV (5 FT X 2 FT)(EXTEND)	CONC BOX CULV (5 FT X 5 FT)(EXTEND)	CONC BOX CULV (6 FT X 6 FT)(EXTEND)	CONC BOX CULV (6 FT X 2.5 FT)(EXTEND)	RC PIPE (CL III)(24 IN)	WINGWALL (PW - 2) (HW=4 FT)	WINGWALL (PW - 2) (HW=7 FT)	WINGWALL (PW - 2) (HW=8 FT)	SET (TY II) (24 IN) (RCP) (3:1) (C)	REMOV STR (WINGWALL)	REMOV STR (HEADWALL)	REMOV STR (BOX CULVERT)	INSTL OM ASSM (OM-2Y)(W C)GND	
CY	SY	CY	LF	SF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA			
647+99	1 - 4' X 2' X 62' SBC	1 - 4' X 2' X 66' SBC	50						4							1				1		2		
665+99	1 - 5' X 5' X 64' SBC	1 - 5' X 5' X 68' SBC					106						4							1		2		
708+50	1 - 3' X 2' X 54' SBC	1 - 3' X 2' X 60' SBC								6						2	1			2		4		
730+70	2 - 5' X 2' X 54' MBC	2 - 5' X 2' X 60' MBC									12					2				2		4		
750+75	1 - 6' X 2' X 48' SBC 1 - 3' X 2' X 55' SBC	1 - 5' X 5' X 64' SBC		55	51	62	196	64									2			4		4		
1162+23	1 - 24" X 63' RCP	1 - 24" X 71' RCP													10				2			4		
1185+73	1 - 6' X 6' X 58' SBC	1 - 6' X 6' X 62' SBC					128						4					1		2		2		
0045-12-094 TOTALS =			50	55	51	62	430	64	6	4	12	4	4	0	10	5	3	1	2	11	2	22		
850+74	1 - 6' X 2.5' X 59'	1 - 6' X 2.5' X 63'					96						4			1				1		2		
0046-01-071 TOTALS =			0	0	0	0	96	0	0	0	0	0	0	0	0	0	0	0	0	1	0	2		
TOTALS =			50	55	51	62	526	64	6	4	12	4	4	4	10	5	4	1	2	12	2	24		

**SUMMARY OF CROSS STRUCTURE SEEDING AND EROSION CONTROL ITEMS**

STATION	DESCRIPTION (EXISTING)	DESCRIPTION (PROPOSED)	164	164	164	168	506	506	506	506
			6009	6011	6023	6001	6002	6011	6038	6039
			BROADCAST SEED (TEMP) (WARM)	BROADCAST SEED (TEMP) (COOL)	CELL FBR MLCH SEED(PERM)(RURAL)(CLAY)	VEGETATIVE WATERING	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
			SY	SY	SY	MG	LF	LF	LF	LF
647+99	1 - 4' X 2' X 62' SBC	1 - 4' X 2' X 66' SBC	42	42	83	1	20	20	20	20
665+99	1 - 5' X 5' X 64' SBC	1 - 5' X 5' X 68' SBC	50	50	100	1	60	60	20	20
708+50	1 - 3' X 2' X 54' SBC	1 - 3' X 2' X 60' SBC	79	79	157	2	60	60	40	40
730+70	2 - 5' X 2' X 54' MBC	2 - 5' X 2' X 60' MBC	98	98	196	2	80	80	40	40
750+75	1 - 6' X 2' X 48' SBC 1 - 3' X 2' X 55' SBC	1 - 5' X 5' X 64' SBC	100	100	200	2	60	60	30	30
1162+23	1 - 24" X 63' RCP	1 - 24" X 71' RCP	73	73	145	2		0	80	80
1185+73	1 - 6' X 6' X 58' SBC	1 - 6' X 6' X 62' SBC	51	51	102	1	40	40	20	20
0045-12-094 TOTALS =			493	493	983	11	320	320	250	250
850+74	1 - 6' X 2.5' X 59'	1 - 6' X 2.5' X 63'	51	51	102	1	40	40	20	20
0046-01-071 TOTALS =			51	51	102	1	40	40	20	20
TOTALS =			544	544	1085	12	360	360	270	270

INSTALL TEMP SEDMT CONT FENCE & ROCK FILTER DAMS AS DIRECTED BY ENGINEER  
 WATERING: BASED ON 2 APPLICATIONS, 0.5" RAINFALL EQUIVALENT = 0.003 MG/SY/CY

**SUMMARY OF PARALLEL STRUCTURES SEEDING AND EROSION CONTROL ITEMS**

CSJ	164	164	164	168	506	506
	6009	6011	6023	6001	6038	6039
	BROADCAST SEED (TEMP) (WARM)	BROADCAST SEED (TEMP) (COOL)	CELL FBR MLCH SEED(PERM)(RURAL)(CLAY)	VEGETATIVE WATERING	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	SY	SY	SY	MG	LF	LF
0045-09-116	450	450	900	11	60	60
0045-11-046	2325	2325	4650	56	200	200
0045-12-093	25	25	50	1	20	20
0045-12-094	3225	3225	6450	77	260	260
0046-01-071	3100	3100	6200	74	300	300
0046-10-007	50	50	100	1	20	20
TOTALS =						
	9175	9175	18350	220	860	860

INSTALL TEMP SEDMT CONT FENCE AS DIRECTED BY ENGINEER  
 WATERING: BASED ON 2 APPLICATIONS, 0.5" RAINFALL EQUIVALENT = 0.003 MG/SY/CY

**SUMMARY OF GUARDRAIL ITEMS**

STATION	NBI#	LT / RT	134	432	540	540	540	540	544	658
			6001	6045	6002	6016	6020	6048	6001	6062
			BACKFILL (TY A)	RIPRAP (MOW STRIP)(4 IN)	MTL W-BEAM GD FEN (STEEL POST)	DOWNSTREAM ANCHOR TERMINAL	MTL W - BEAM GD FEN (LOW FILL CULVERT)	TL-3 31" SHORT RADIUS (COMPLETE)	GUARDRAIL END TREATMENT (INSTALL)	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)
			STA	CY	LF	EA	LF	EA	EA	EA
288+75	01-139-0-0045-09-084	RT	2.1	12.87	125	1	0	0	1	4
		LT		12.87	125	1	0	0	1	4
319+52	01-139-0-0045-09-085	RT	2.1	12.87	125	1	0	0	1	4
		LT		12.87	125	1	0	0	1	4
0045-09-116 TOTALS =			4.2	51.48	500	4	0	0	4	16
410+46	01-139-0-0045-09-086	RT	4.2	16	25	0	100	1	1	4
		LT		15	25	0	75	1	1	4
0045-11-046 TOTALS =			4.2	31	50	0	175	2	2	8
1547+58	01-194-0-0046-01-032	RT	2.6	15.03	200	1	0	0	1	5
		LT		15.03	200	1	0	0	1	5
1554+39	01-194-0-0046-01-033	RT	2.1	12.87	150	1	0	0	1	4
		LT		12.87	150	1	0	0	1	4
0046-10-007 TOTALS =			4.7	55.8	700	4	0	0	4	18
TOTALS =			13.1	138.28	1250	8	175	2	10	42


**SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS**

LOCATION	6001	6185	6185
	6002	6002	6003
	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	DAY	HR
0045-09-116		16	0
0045-11-046		49	0
0045-12-093		4	0
0045-12-094		91	8
0046-01-071		73	0
0046-10-007		8	0
TOTALS =			
	2	241	8

**US 82 QUANTITY SUMMARIES**

SHEET 10 OF 10

© 2023



CONT	SECT	JOB	HIGHWAY
0045 09		116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		16

DATE: 7/31/2023 3:26:45 PM  
FILE: I:\PARISAD\DESIGN\US 82 E Saf.tey.Treet 0045-09-116\Design\CAD Plan Sheets\sequence of work.dgn

DN:  
CK:  
DW:  
CK:

**Phase I ~ Initial Traffic Control**

Install project limit traffic control devices (TCD) per the BC standard sheets. Utilize the applicable TCP (2-1)-18 or TCP (2-2b)-18 layout for TCD installation.

**Phase II ~ Erosion Control**

Install erosion control devices utilizing the applicable TCP (2-1)-18 layout or TCP (2-2b)-18.

**Phase III ~ Culvert Work (Cross and Parallel Culverts)**

Perform off-pavement culvert operations utilizing the applicable TCP (2-1)-18 layout.

Perform on-pavement culvert operations utilizing TCP(2-2b)-18.

Work performed at cross culvert station 750+75 shall be constructed in half widths.

Adhere to the Worksheet for Edge Condition Treatment Types.

**Phase IV ~ MBGF**

Remove existing MBGF and install proposed MBGF utilizing TCP (2-1)-18 or TCP (2-2b)-18 as required.

**Phase V ~ Project Clean Up**


Remove erosion control devices, construction debris and waste material utilizing TCP (2-1)-18.

**Notes:**

Prior to a specific construction operation, the traffic control standard specified for the construction phase in this narrative must be evaluated thoroughly for appropriateness. All traffic control operations must adhere to the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the applicable Traffic Control Standards. Construction phase order may be varied when approved by the Engineer. Submit a Work and Traffic Control Sequence plan to the Engineer for approval. Ensure that both travel lanes are open at night. Provide access to private property and Public Roads at all times. Road closures must be approved by the Engineer.

Limit work area to 10 miles unless agreed by engineer. Limit work area to one side of the road.

Seeding to be performed within 14 days of structure work utilizing TCP (2-1)-18.



*Austin R. Shatto, P.E.*  
07/31/2023

**US 82**  
**SEQUENCE OF WORK**

© 2023			
CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		17

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

<p><b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b>  <a href="http://www.txdot.gov">http://www.txdot.gov</a></p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

DATE: 7/28/2023 11:23:16 AM  
 FILE: I:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\Traffic Control Plan Standards\bc-21.dgn



**BARRICADE AND CONSTRUCTION  
GENERAL NOTES  
AND REQUIREMENTS**


**BC(1)-21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0045	09	116, ETC.		US 82			
4-03	7-13								
9-07	8-14								
5-10	5-21	DIST	COUNTY		SHEET NO.				
		PAR	LAMAR, ETC.		18				




DATE: 7/28/2023 11:23:16 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARD.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING**


Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Spacing "X" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW23			40	240
CW25			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
*			*	* <sup>3</sup>

- For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

**BARRICADE AND CONSTRUCTION PROJECT LIMIT**


**BC(2)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	LAMAR, ETC.	19	

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present.

Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
  - 40 mph and greater 0.2 to 2 miles
  - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Low enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form \*1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

DATE: 7/28/2023 11:23:17 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Tree 0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\BC(3)-21.dgn

SHEET 3 OF 12




## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

### BC(3)-21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0045	09	116, ETC.	US 82				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	PAR	LAMAR, ETC.	20					


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\* \* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nois shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectorized when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>TL</sub> OR C <sub>TL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCO list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCO) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCO lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B or Type C, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCO list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12





**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

BC(4)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	LAMAR, ETC.	21	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 7/28/2023 11:23:17 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD Standards\CAD Standards\bc-21.dgn

DATE: 7/28/2023 11:23:17 AM  
 FILE: I:\PARISAD\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD Standards\Traffic Control Plan Standards\bc-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

**WEDGE ANCHORS**  
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**  
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."  
 \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.  
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC(5)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	LAMAR, ETC.	22	

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other standards or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHs
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation = IH-number, US-number, SH-number, FM-number

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXXX BLVD CLOSED

### Other Condition List

FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE	

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXXX TO XXXXXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM- X PM
APR XX- XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM- XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS should be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and M, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flogger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



# BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	LAMAR, ETC.	23	

DATE: 7/28/2023 11:23:19 AM  
FILE: I:\PARISAD\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARD\bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 7/28/2023 11:23:19 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edge line being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B or C sheeting, meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC(7)-21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0045	09	116, ETC.	US 82				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	PAR	LAMAR, ETC.	24					



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 7/28/2023 11:23:19 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\bc-21.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B or Type C Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used of each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(8)-21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0045	09	116, ETC.	US 82				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	PAR	LAMAR, ETC.	25					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/28/2023 11:23:20 AM  
 FILE: T:\PARIS\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\bc-21.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VPs) are normally used to channelize traffic or divide opposing lanes of traffic.
- VPs may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use of VPs for drop-offs.
- VPs should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VPs used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VPs shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panels is 36 inches or greater, a panel stripe of 6 inches shall be used.




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B or Type C conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B or Type C conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long cones and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70	700'	770'	840'	70'	140'	
75	750'	825'	900'	75'	150'	
80	800'	880'	960'	80'	160'	

x x Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(9)-21**


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	SECT	JOB:	HIGHWAY				
REVISIONS		0045	09	116, ETC.		US 82			
9-07	8-14	DIST:	COUNTY	SHEET NO.					
7-13	5-21	PAR	LAMAR, ETC.	26					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 7/28/2023 11:23:20 AM  
 FILE: I:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\bc-21.dgn


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stocked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.


Barricades shall NOT be used as a sign support.



**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined in BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.

**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(10)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	LAMAR, ETC.	27	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Block-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242





A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12

<span style="font-size: small; vertical-align: middle;">Texas Department of Transportation</span>		<span style="font-size: x-small;">Traffic Safety Division Standard</span>
<h1 style="margin: 0;">BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS</h1> <h2 style="margin: 0;">BC(11)-21</h2>		
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT
REVISIONS	JOB	HIGHWAY
2-98 9-07 5-21	0045 09	116, ETC. US 82
1-02 7-13	DIST	COUNTY
11-02 8-14	PAR	SHEET NO.
	LAMAR, ETC.	28



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 7/28/2023 11:23:21 AM  
 FILE: I:\PARISAD\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\bc-21.dgn

# PAVEMENT MARKING PATTERNS





Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS





Prefabricated markings may be substituted for reflectorized pavement markings.

## EDGE & LANE LINES FOR DIVIDED HIGHWAY



Prefabricated markings may be substituted for reflectorized pavement markings.


## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS





Prefabricated markings may be substituted for reflectorized pavement markings.

## TWO-WAY LEFT TURN LANE



# STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



## SOLID LINES




## BROKEN LINES



## REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	PAR	LAMAR, ETC.	29	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for inaccurate results or damages resulting from its use.

DATE: 7/28/2023 11:23:22 AM  
FILE: T:\PARISAD\DESIGN\US 82 E Safety Tree\0045-09-116\Design\CAD\_Standards\TRAFFIC CONTROL PLAN STANDARDS\bc-21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard or for any damages resulting from its use.

DATE: 7/28/2023 11:23:23 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Sef.tcy Treeet 0045-09-116\Design\CAD\_Standards\TrafficControlPlans\CONVENTIONAL\TCP(2-1)-18.dwg




TCP (2-1a)

**WORK SPACE NEAR SHOULDER**  
 Conventional Roads



TCP (2-1b)

**WORK SPACE ON SHOULDER**  
 Conventional Roads



TCP (2-1c)

**WORK VEHICLES ON SHOULDER**  
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed x	Formula	Minimum Desirable Taper Lengths x			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40	L = WS	265'	295'	320'	40'	80'	240'	155'
45		450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65	L = WS	650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

x Conventional Roads Only  
 \* \* Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.


**TRAFFIC CONTROL PLAN**  
**CONVENTIONAL ROAD**  
**SHOULDER WORK**

**TCP(2-1)-18**


FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	PAR	LAMAR, ETC.	30	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT is not responsible for any damages resulting from its use.

DATE: 7/28/2023 11:23:23 AM  
 FILE: T:\PARIS\DESIGN\US 82 E Sef.tty Treeet 0045-09-116\Design\CAD\_Standards\Traffic\TrafficControl\TCP2-2-18.dgn



TCP (2-2a)  
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS  
 ONE LANE TWO-WAY  
 CONTROL WITH YIELD SIGNS  
 (Less than 2000 ADT - See Note 9)



TCP (2-2b)  
 2-LANE ROADWAY WITHOUT PAVED SHOULDERS  
 ONE LANE TWO-WAY  
 CONTROL WITH FLAGGERS

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed x	Formula	Minimum Desirable Taper Lengths x x			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

x Conventional Roads Only  
 x x Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
  - Flaggers should use two-way radios or other methods of communication to control traffic.
  - Length of work space should be based on the ability of flaggers to communicate.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
  - The R1-2oP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support of a 7 foot minimum mounting height.
- TCP (2-2b)
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
  - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
  - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

		Traffic Operations Division Standard	
<b>TRAFFIC CONTROL PLAN</b> <b>ONE-LANE TWO-WAY</b> <b>TRAFFIC CONTROL</b>			
<b>TCP(2-2)-18</b>			
FILE:	tcp2-2-18.dgn	DN:	CK:
© TxDOT	December 1985	CON:	SECT:
REVISIONS 8-95 3-03 1-97 2-12 4-98 2-18		JOB 0045 09 116, ETC.	HIGHWAY US 82
DIST:	COUNTY:	SHEET NO.	
PAR	LAMAR, ETC.	31	










DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/28/2023 11:23:25 AM  
 FILE: T:\PARISAO\DESIGN\INUS 82 E Safety Treat\0045-09-116\Design\CAD Standards\TRAFFIC CONTROL PLAN STANDARDS\wz(stpm)23.dgn

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)



## WORK ZONE SHORT TERM PAVEMENT MARKINGS

### WZ(STPM)-23


FILE:	wzstpm-23.dgn	DWG:	CK:	DWG:	CK:
© TxDOT	February 2023	CONT:	0045	SECT:	09
REVISIONS		JOB		HIGHWAY	
4-92	7-13	116, ETC.		US 82	
1-97	2-23	COUNTY		SHEET NO.	
3-03		LAMAR, ETC.		34	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. TxDOT is not responsible for any damages resulting from its use.


DATE: 7/28/2023 11:23:26 AM  
 FILE: I:\PARISAD\DESIGN\AUS 82 E Safety Treat 0045-09-116\Design\CAD Standards\TAB\RS\WZ(RS)-22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	• 35'+

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed "x"	Formula	Minimum Desirable Taper Lengths "x"			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40	L = WS	265'	295'	320'	40'	80'	240'	155'
45		450'	495'	540'	45'	90'	320'	195'
50	L = WS	500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60	L = WS	600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	L = WS	700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

x Conventional Roads Only  
 x x Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT)  
 S=Posted Speed(MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

• For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation  
 Traffic Safety Division Standard


## TEMPORARY RUMBLE STRIPS

### WZ(RS)-22



FILE: wzs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT: 0045	SECT: 09	JOB: 116, ETC.	HSWAY: US 82
2-14 1-22 4-16	REVISIONS: 0045 09	DIST: PAR	COUNTY: LAMAR, ETC.	SHEET NO.: 35

# DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS


Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet





**Edge Condition I**  
S = (3:1) (or flatter)



**Edge Condition II**  
S = ((2.99):1) to (1:1)



**Edge Condition III**  
S is steeper than (1:1)



### FACTORS CONSIDERED IN THE GUIDELINES:


- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

Zone	Treatment Types Guidelines:
①	No treatment
②	CW 8-11 "Uneven Lanes" signs.
③	CW 8-9a Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.
④	CW8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge slope to that of the profered Edge Condition I.
⑤	Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone-4 may be used after consideration of other applicable factors.

### Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

**FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5** ( )




- $E = ADT \times T$   
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within the clear zone.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exists parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



Date 07/31/2023  
*Austin R. Shatto, P.E.*




## TREATMENT FOR VARIOUS EDGE CONDITIONS


FILE: edgecon.dgn	DN:	CK:	DW:	CK:
© TxDOT August 2000	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
03-01	DIST	COUNTY		SHEET NO.
08-01	PAR	LAMAR, ETC.		36
9-21				

CK: DW: CK: DN:

DATE: 7/28/2023 11:23:27 AM  
 FILE: I:\PARIS\DESIGN\US 82 E Saf.tty.Treet 0045-09-116\Design\CAD\_Plan\_Sheets\MBGF AT CULVERT DETAIL.dgn



STATION	NBI #	A	B	X	Y
<b>CSJ 0045-09-116</b>					
288+75	01-139-0-0045-09-084	96	54	96	54
319+52	01-139-0-0045-09-085	96	54	96	54
<b>CSJ 0046-10-007</b>					
1547+58	01-194-0-0046-01-032	117	83	117	83
1554+39	01-194-0-0046-01-033	89	61	89	61



*Austin R. Shatto, P.E.*

07/31/2023

**US 82**

**MBGF DETAIL  
FOR CROSS  
CULVERTS**



NOT TO SCALE



CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	37	


DN: CK: DW: CK: CK:

DATE: 7/28/2023 11:23:27 AM  
FILE: I:\PARIS\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Plan Sheets\radius\_rail.dgn



*Austin R. Shatto, P.E.*  
07/31/2023

**US 82**  
**MBGF DETAIL**  
**CUTHAND CREEK**  
**CSJ: 0045-11-046**  
**STATION: 410+46**






© 2023

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	38	

DATE: 7/28/2023 11:23:27 AM  
 FILE: I:\PARISAD\DESIGN\US 82 E Saf.tey.Treet.0045-09-116\Design\CAD\_Standards\ROADWAY\_DETAIL\_STANDARDS\Driveway\_CutRestore.dgn

DW: CK: DN:




*Austin R. Shatto, P.E.*

07/31/2023

**US 82  
DRIVEWAY  
DETAILS**

NOT TO SCALE  
SHEET 1 OF 1




CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	39	




DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Tree 0045-09-116\Design\CAD Standards\Roadway Detail Standards\gf3119.dgn



TYPICAL POST PLACEMENT




WOOD BLOCK TO ROUND WOOD POST

WOOD BLOCK TO RECTANGULAR WOOD POST

ROUTED WOOD BLOCK TO I-BEAM STEEL POST


- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBSG SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
  2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0" OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
  3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
  4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
  7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
  8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
  9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAY BE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
  10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
  12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
  13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
  14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

NOTE: \*WOOD\* INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.

SPLICE BOLT LENGTH

FBB01 - 1 1/4"

FBB02 - 2"


POST & BLOCK LENGTH

FBB03 - 10"

FBB04 - 18"

BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.




MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

\*POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.

9" MIN. FILL DEPTH CULVERT SLAB



LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.

1. BOLT-THROUGH OPTION: REQUIRES A 6" MIN. SLAB THICKNESS. 3/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.

2. EPOXY ANCHOR OPTION: THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 3/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.


NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

		Design Division Standard	
<h1>METAL BEAM GUARD FENCE</h1> <h2>TL-3 MASH COMPLIANT</h2> <h3>GF(31)-19</h3>			
FILE: gf3119.dgn	DN: TxDOT	CK: KM	DW: VP
© TxDOT: NOVEMBER 2019	CONT: 0045 09	SECT: 116, ETC.	HIGHWAY: US 82
DIST: COUNTY		SHEET NO.	
PAR: LAMAR, ETC.		40	



DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treeet\_0045-09-116\Design\CAD\_Standards\Roadway\_Detail\_Standards\gf31dat19.dgn







**DOWNSTREAM ANCHOR TERMINAL (DAT)**  
 NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.

- GENERAL NOTES**
1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
  2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
  3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
  4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
  5. REFER TO GF(31) SHEET FOR TERMINAL CONNECTION DETAILS.

**MOW STRIP INSTALLATION**  
 IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.

(DAT) PARTS LIST	QTY
1 STEEL FOUNDATION TUBE	2
2 DAT TERMINAL POST	2
3 CHANNEL STRUT	2
4 TERMINAL RAIL ELEMENT	1
5 SHELF ANGLE BRACKET	1
6 BCT BEARING PLATE	1
7 BCT POST SLEEVE	1
8 GUARDRAIL ANCHOR BRACKET	1
9 (ROUNDED) W-BEAM END SECTION	1
10 BCT CABLE ANCHOR	1
11 RECESSED NUT, GUARDRAIL	20
12 1 1/4" BUTTON HEAD BOLT	4
13 10" BUTTON HEAD BOLT	2
14 5/8" X 2" HEX HEAD BOLT	8
15 5/8" X 8" HEX HEAD BOLT	4
16 5/8" X 10" HEX HEAD BOLT	2
17 5/8" FLAT WASHER	18




Texas Department of Transportation  
 Design Division Standard

**METAL BEAM GUARD FENCE (DOWNSTREAM ANCHOR TERMINAL) TL-3 MASH COMPLIANT GF(31)DAT-19**

FILE: gf31dat19.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CGL / AG
© TxDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045/09	116, ETC.	US 82	
DIST	COUNTY	SHEET NO.		
PAR	LAMAR, ETC.	41		

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treeet\_0045-09-116\Design\CAD\_Standards\ROADWAY\_DETAIL\_STANDARDS\gf31ms19.dgn



**GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS**

Note: Site Condition(s)

Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.  
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




**PLAN**

GF(31) shown with Mow Strip (See GF(31) standard sheet for proper installation)


**GENERAL NOTES**

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




**SECTION A-A**

Typical




**MOW STRIP DETAIL**

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




**CURB OPTION (1)**

This option will increase the post embedment throughout the system.



**CURB OPTION (2)**

Curb shown on top of mow strip




**CURB OPTION (3)**

				Design Division Standard
<b>METAL BEAM GUARD FENCE (MOW STRIP)</b> <b>TL-3 MASH COMPLIANT</b> <b>GF(31)MS-19</b>				
FILE: gf31ms19.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CGL/AG
© TxDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82	
DIST	COUNTY	SHEET NO.		
PAR	LAMAR, ETC.	42		

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. THE USER OF THIS STANDARD ASSUMES ALL LIABILITY FOR ANY DAMAGE TO PROPERTY OR PERSONS RESULTING FROM ITS USE. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: sDATES FILE: sFILES



PLAN VIEW




SECTION VIEW (A-A) TIMBER POST WITH METAL FOUNDATION TUBE (TYP) BCT POSTS 2-4-5-6




SECTION VIEW (B-B) (TYP) CRT TIMBER POSTS 3


NOTE: SEE SPECIAL APPLICATION NOTES ON SHEET 3 OF 3. CRT POST WILL REQUIRE AN ADDITIONAL 3/4" HOLE TO ACCOMMODATE THE 22" LONG BLOCKOUT.



SECTION VIEW (D-D) (TYP) AT POSTS 7-8



SECTION VIEW (C-C) (TYP) AT POSTS 9-10-11-12-13



FULL-LENGTH ELEVATION VIEW

NOTE: ALL CABLE BRACKET ASSEMBLIES ARE LOCATED ON THE FIELD-SIDE. SHOWN HERE FOR CLARITY.

NOTE: FOR BCT POSTS 2-4-5-6 INSTALL (1) OR (2) ITEM A15-A4-A5 BOLT ASSEMBLIES TO PREVENT TIMBER POST SLIDING DOWN FOUNDATION TUBE.

ANCHOR POST 1 FABRICATION DETAILS	
SHEET DESCRIPTION	SHEET NUMBER
ANCHOR POST	SHEET 1 OF 8
ANCHOR SLEEVE	SHEET 2 OF 8
RADIUS RAIL	SHEET 3 OF 8
THRIE-BEAM RAILS	SHEET 4 OF 8
BCT TIMBER POST	SHEET 5 OF 8
STRUT RADIUS ANCHOR	SHEET 6 OF 8
FOUNDATION TUBE	SHEET 7 OF 8
ANCHOR CABLE	SHEET 8 OF 8



*Christopher Lindsey*


08/28/2023

SHEET 1 OF 3

Texas Department of Transportation			
<b>TL-3</b>			
<b>SHORT RADIUS GUARDRAIL</b>			
<b>MASH COMPLIANT</b>			
<b>SRG(TL-3)-21 (MOD)</b>			
FILE:	srgtl321	DNTxDOT	CK:
© TxDOT:	FEBRUARY_2021	CONT SECT	JOB
		0045 09	116, ETC.
		DIST	COUNTY
		PAR	LAMAR, ETC.
		CK: CGL	
		HIGHWAY	US 82
		SHEET NO.	43

(MASH TL-3 COMPLIANT)  
TESTED TO MASH TL-3 WITH A 3:1 SLOPE

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



NOTE: SAND BARREL (ITEM V)  
55-GALLON BARRELS ARE CONSTRUCTED OF HIGH-DENSITY POLYETHYLENE. SEE GN 17 FOR SPECIFIC MATERIAL INFORMATION.



*Christopher Lindsey*

08/28/2023

(MASH TL-3 COMPLIANT)  
TESTED TO MASH TL-3 WITH A 3:1 SLOPE

SHEET 2 OF 3

Texas Department of Transportation		TL-3	
SHORT RADIUS GUARDRAIL		MASH COMPLIANT	
SRG(TL-3)-21 (MOD)			
FILE: srgtl321	TxDOT CK: DN:	CK: CGL	
© TxDOT: FEBRUARY_2021	CONT SECT	JOB	HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82
	DIST	COUNTY	SHEET NO.
	PAR	LAMAR, ETC.	44

DATE: \$DATE\$  
FILE: \$FILE\$



DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

ITEM	ALL LARGE & SMALL COMPONENT DESCRIPTIONS	END ANCHOR (POST 1 & POST 2)		TL-3 SHORT RADIUS (POST 2 TO POST 7)		TRANSITION TO W-BEAM (POST 7 TO POST 13)		TL-3 SHORT RADIUS GUARDRAIL COMPLETE SYSTEM	
		ITEM	QTY	ITEM	QTY	ITEM	QTY	ITEM	TOTAL QTY
A	POST 1 TOP (SCH.80 PIPE) (8" X 80" LENGTH)	A	1					A	1
B	POST 1 TOP (WELDED SUPPORT COLLAR 10" X 10" X 1/2" ASTM A36)	B	1					B	1
C	POST 1 TUBE (HSS 10" X 10" X 1/2" X 72" LENGTH) A500 GR.B	C	1					C	1
D	POST 1 (WELDED PLATE 9 1/4" X 9 1/4" X 1/8") A36	D	1					D	1
E	POST 1 STRUT BRACKET (C8 X 11.50 A36)	E	1					E	1
F	(POST 1 & 2) CHANNEL STRUTS (4" X 71 1/2")(C4 X 7.25)A36	F	2					F	2
G	THRIE-BEAM RAIL (END ANCHOR - ROUNDED TYPE) 12GA. (RTE02a)	G	1					G	1
H	THRIE-BEAM RAIL (ANCHOR) (6'-3" LENGTH) 12GA. (RWM14a)	H	1	H	1			H	2
I	THRIE-BEAM RAIL (8 SPACE) (12'-6" LENGTH) 12GA. (RTM08)	I	1	I	1	1	2	I	1
J	THRIE-BEAM RAIL (RADIUS 8'-4 1/2") (SLOTTED) 12GA.	J	1	J	1			J	1
K	NON-SYMMETRICAL W-BEAM TO THRIE-BEAM TRANSITION					K	1	K	1
L	THRIE-BEAM RAIL (TERMINAL CONNECTOR) (BRIDGE-RAIL) (RTE01b)					L	1	L	1
M	POST 2,4,5,6 BCT TIMBER (5 1/2" X 7 1/2" X 46") (PDF04)			M	4			M	4
N	POST 2,4, BCT TUBE (6" X 8" X 3/16" X 72" LENGTH) (PTE05)			N	2			N	2
O	POST 5,6 MODIFIED BCT TUBES (FOR WELDED CABLE SADDLES)			O	2			O	2
P	POST 3,4,6 THRIE-BEAM BLOCK-OUT (6" X 8" X 22")(PDB02a)			P	3	P		P	3
Q	POST 3,7,8 CRT TIMBER POSTS (6" X 8" X 72" LENGTH)(PDE09)			Q	1	Q	2	Q	3
R	POST 9,10,11,12,13 I-BEAM POSTS (W6X8.5 X 72" LENGTH) (PWE01)					R	5	R	5
S	POST 7,8,9,10,11,12,13 ROUTED W-BEAM BLOCK-OUT(6" X 8" X 14")(PDB01b)					S	7	S	7
T	POST 12 THRU 17 I-BEAM POSTS (W6X8.5 X 84" LENGTH) (PWE07)					T	6	T	6
U	POST 12 THRU 17 ROUTED BLOCK-OUT (6" X 8" X 18") (PDB??)					U	6	U	6
V	SAND BARRELS 700-715 LBS							V	6
W	NON-SYMMETRICAL Transition to W-Beam					W	1	W	1
X	W-BEAM RAIL (12'-6" LENGTH)					X	2	X	2
Y	ROUTED W-BEAM BLOCK-OUT 6" X 8" X 14"					Y	7	Y	2
A1	BCT CABLE ANCHOR ASSEMBLIES (3/4" X 6'-6 3/4" LENGTH) (FCA01)	A1	2					A1	2
A2	BCT CABLE ANCHOR BRACKET (FPA01)	A2	2	A2	1			A2	3
A3	5/8" X 2" HEX BOLT A307 GRD.5 (FOR CABLE BRACKETS)	A3	18	A3	8			A3	26
A4	5/8" FLAT WASHER A307 GRD.5 (1 WASHER UNDER BOLT HEAD & 1 NUT)	A4	36	A4	40			A4	76
A5	5/8" RECESSED H.G.R NUT (NUTS FOR HEX BOLTS)	A5	22	A5	20			A5	42
A6	STRUT BRACKET HARDWARE (1/2" X 1 1/2") HEX BOLT A307 GRD.5	A6	2					A6	2
A7	CHANNEL STRUT HARDWARE (5/8" X 10") HEX BOLT A307 GRD.5	A7	2					A7	2
A8	BCT CABLE ANCHOR ASSEMBLY (FCA02) (3/4" X 18'-5" LENGTH)			A8	1			A8	1
A9	BCT POST SLEEVE (FMM02a) (POST 4 ONLY)			A9	1			A9	1
A10	BCT CABLE BEARING PLATE (5/8" X 8" X 8" (FPB01) (POST 4 ONLY)			A10	1			A10	1
A11	5/8" X 1 1/4" H.G.R. BOLTS (FBB01) (SPLICES AT POST 2,4,6,7)			A11	48			A11	48
A12	5/8" X 2" H.G.R. BOLTS (FBB02)(ROUND TERM-POST 10-END SPLICE)	A12	4			A12	24	A12	28
A13	5/8" X 10" H.G.R. BOLTS (FBB03) (I-BEAM POSTS RAIL & BLOCKOUT)					A13	18	A13	18
A14	5/8" X 18" H.G.R. BOLTS (FBB04) (POSTS 3,4,6,7,8)			A14	8	A14	2	A14	10
A15	5/8" X 7 1/2" HEX BOLTS A307 GRD.5 (BCT POSTS 2,4,5,6)			A15	8			A15	8
A16	5/8" X 10" HEX BOLTS A307 GRD.5 (BCT POSTS 2,4,5,6)			A16	4			A16	4
A17	RECTANGULAR WASHERS (FWR03) (FOR TERMINAL CONNECTOR RTE01b)					A17	12	A17	12
A18	7/8" X (LENGTH VARIES) HEX BOLTS A325 OR A449 GR.5					A18	5	A18	5
A19	1 3/4" O.D. HARDENED FLAT WASHER A325					A19	10	A19	10
A20	7/8" HEX NUT GR.5 A325					A20	5	A20	5

- GENERAL NOTES**
- FOR ADDITIONAL INSTALLATION INFORMATION AND GUIDANCE CONTACT: TEXAS DEPARTMENT OF TRANSPORTATION, (TXDOT'S DESIGN DIVISION), (512) 416-2678. THE EXACT POSITION OF MBSG SHALL BE SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER. THE SIGHT DISTANCE OF THE INSTALLATION WILL NEED TO BE VERIFIED WITH RESPECT TO THE SPECIFIC SITE PLACEMENT.
  - STEEL POSTS ARE NOT PERMITTED AT CRT OR BCT POST POSITIONS.
  - RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 12 1/2" OR 25 FOOT NOMINAL LENGTHS.
  - BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
  - FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  - THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A SLOPE RATE OF NOT MORE THAN 1V:10H.
  - IT IS NOT RECOMMENDED THAT GUARD FENCE BE PLACED IN THE VICINITY OF CURBS.
  - GUARDRAIL POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  - SPECIAL FABRICATION WILL BE REQUIRED FOR THRIE BEAM RAIL RADIUS (ITEM J).
  - ALL MATERIAL AND WORK INVOLVED IS SUBSIDIARY TO SHORT RADIUS BID ITEM, INCLUDING, BUT NOT LIMITED TO FOUNDATIONS, GRADING, THRIE BEAM RAIL, SAND BARRELS, AND OTHER PARTS.
  - ALL CABLE ASSEMBLIES SHOULD BE TAUT AFTER INSTALLATION. WHEN CABLES ARE MANIPULATED BY HAND THE CABLES SHOULD NOT MOVE MORE THAN 1" IN ANY DIRECTION PERPENDICULAR TO THE CABLE.
  - THE BCT BEARING PLATE INSTALLED AT POST 4 SHOULD BE ORIENTED SUCH THAT THE 3" DIMENSION FROM PLATE EDGE TO CENTER OF BOLT HOLE IS ON THE BOTTOM AND 5" DIMENSION FROM PLATE EDGE TO CENTER OF BOLT HOLE IS ON THE TOP.
  - FOUNDATION AT POST 1 SHALL BE CLASS C CONCRETE.
  - POST (1) IS NOT A CRASHWORTHY TERMINAL. THE DESIGN AND PLACEMENT OF POST (1) MUST BE OUTSIDE OF THE CLEAR ZONE OF THE SECONDARY ROADWAY USING THE RESPECTIVE CLEAR ZONE CRITERIA. PLEASE CONTACT THE DESIGN DIVISION (512) 416-2678 FOR ASSISTANCE IN DETERMINING THE APPROPRIATE USE AND/OR PLACEMENT OF THE SYSTEM IN CONSTRAINED LOCATIONS. THE PAYMENT OF THE COMPLETE SYSTEM WILL BE WITH BID ITEMS: 540 XXXX TL-3 31" SHORT RADIUS (COMPLETE).
  - TESTED TO MASH WITH A 3:1 SLOPE OR SHALLOWER IS PREFERABLE IN THE LIMITS OF THE TOP AND BOTTOM OF THE SLOPE AS SHOWN IN THE PLAN VIEW. IF FIELD CONDITIONS REQUIRE A STEEPER SLOPE, THIS MAY BE ALLOWABLE UP TO A 2:1 SLOPE. CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE.
  - THE BARRELS ARE ENERGY ABSORPTION ENERGITE III, MODEL 640 FILLED WITH 715 LB (•/•-15) SAND; OR AN APPROVED EQUIVALENT. THE APPROXIMATE HEIGHT OF THE BARREL IS 41" (•/•).
  - ALTERNATE METHODS TO TERMINATE THE SRG ALONG THE PRIMARY ROADWAY ARE AVAILABLE WHEN SITE CONDITIONS DICTATE. CONTACT DESIGN DIVISION FOR DETAILS: 512 416-2678

NOTE: SEE SHEET 1 OF 3.

(MASH TL-3 COMPLIANT)  
TESTED TO MASH TL-3 WITH A 3:1 SLOPE



*Christopher Lindsey*

08/28/2023

SHEET 3 OF 3

**SPECIAL APPLICATION NOTES.**


- THIS IS A MASH COMPLIANT TL-3 SHORT RADIUS GUARDRAIL SYSTEM WITH A TOP RAIL HEIGHT OF 31". AVAILABLE FOR USE ON ANY SPEED ROADWAY. THE SYSTEM REQUIRES A MINIMUM PLACEMENT FOOTPRINT OF 34'-10" ALONG THE PRIMARY ROAD AND A 35'-0" ALONG SECONDARY DRIVEWAY.
- IT IS CRITICAL THAT THE PRIMARY GUARDRAIL MAINTAIN A (4 DEGREE FLARE) WITH THE SECONDARY DRIVEWAY.
- THE SYSTEM REQUIRES A MINIMUM 5' WIDE (WORK ZONE) DIRECTLY BEHIND THE GUARDRAIL SYSTEM WITH A SLOPE AT 1V:10H OR FLATTER FROM THERE A MAXIMUM 3:1 SLOPE IS RECOMMENDED. SEE SHEET 1 OF 3 FOR FLARE AND SLOPE DETAILS.
- NOTE FOR INSTALLER: THE THREE (3) CRT POSTS ITEM (Q), AT POST LOCATIONS, 3, 7, & 8.), REQUIRE THE FOLLOWING FIELD ADJUSTMENT. USING A 3/4" X 10" LONG SPADE BIT DRILL ONE (1) ADDITIONAL HOLE 7-7/8" DIRECTLY BELOW THE EXISTING TOP HOLE TO ACCOMMODATE THE HARDWARE FOR THE 22" LONG BLOCKOUT.

OPTION FOR ADDITIONAL 3/4" HOLE. THE 22" LONG BLOCKOUT (PDB01a) IS MANUFACTURED WITH TWO 3/4" DRILLED HOLES FOR THE POST HARDWARE, THEREFORE THE BLOCKOUT CAN BE USED AS A TEMPLATE GUIDE FOR THE BOTTOM 3/4" HOLE. AFTER INSTALLING THE CRT POST USE THE TOP HOLE TO MOUNT THE 22" LONG BLOCKOUT TO POST, USE THE BLOCKOUT'S PRE-DRILLED HOLE AS A GUIDE FOR THE BOTTOM 3/4" HOLE.

Texas Department of Transportation		TL-3	
SHORT RADIUS GUARDRAIL		MASH COMPLIANT	
SRG(TL-3)-21 (MOD)			
FILE: srgtl321	TxDOT CK: DN: CK: CGL	CONT SECT: 0045 09	JOB HIGHWAY: 116, ETC. US 82
REVISIONS: FEBRUARY_2021	DIST: COUNTY: PAR: LAMAR, ETC.	SHEET NO.:	45



DATE: \$DATE\$ FILE: \$FILE\$

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US\_82 E Safety Tree\0045-09-116\Design\CAD Standards\ROADWAY\_DETAIL STANDARDS\sgt12s3118.dgn  
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
  - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MGF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - SYSTEM MUST BE ATTACHED TO STANDARD 31" MGBF.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - THE SYSTEM IS SHOWN WITH TWO 12'-6" MGBF PANELS, ONE 25'-0" MGBF PANEL IS ALSO ALLOWED IN THEIR PLACE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6" W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6" W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
o	2	3/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	3/8" WASHER	W0516
c	2	3/8" HEX NUT	N0516
d	25	3/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	3/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	3/8" WASHER	W050
g	33	3/8" Dia. H.G.R. NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	1/2" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	3/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151







DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\Roadway Detail Standards\sgt153120.dgn



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT (1267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S: SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
  - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.



ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	I26SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" x 8" x 14"	CB08
G	6	WOOD BLOCKOUT 6" x 8" x 14"	WBO8
H	1	STRUT 3" x 3" x 80" x 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" x 8" x 72" x 3/8"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" x 7 1/2" x 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" x 2 1/2" x 16 1/2"	GGR17
O	1	BEARING PLATE 8" x 8 5/8" x 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" x 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" x 81" LENGTH	CBL81
SMALL HARDWARE			
o	1	5/8" x 12" GUARDRAIL BOLT 307A HDG	I2GRBLT
b	7	5/8" x 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" x 1 1/4" GR SPLICE BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" x 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" x 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" x 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563DH HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" x 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

Texas Department of Transportation  
 Design Division Standard


**SPIG INDUSTRY, LLC**  
**SINGLE GUARDRAIL TERMINAL**  
**SGET - TL-3 - MASH**  
**SGT(15)31-20**

FILE: sgt153120.dgn	DN: TxDOT	CK: KM	DW: VP	CK: VP
© TxDOT: APRIL 2020	CONT: 0045	SECT: 09	JOB: 116, ETC.	HIGHWAY: US 82
REVISIONS	0045	09	116, ETC.	US 82
DIST: PAR	COUNTY: LAMAR, ETC.	SHEET NO.: 47		




DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\ROADWAY DETAIL STANDARDS\tehmec11.dgn



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS


**CONDITION - 1**  
 THIN HMAC SURFACES OR HMAC OVERLAY  
 WITH THICKNESS OF 2.5" OR LESS



\*\* EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 2**  
 OVERLAY OF EXISTING PAVEMENT  
 HMAC THICKNESS 2.5" TO 5"



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 3**  
 NEW OR RECONSTRUCTED PAVEMENT  
 HMAC THICKNESS 2.5" TO 5"



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS


**CONDITION - 4**  
 NEW OR RECONSTRUCTED PAVEMENT  
 HMAC THICKNESS 5" OR GREATER

**GENERAL NOTES**


1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H 1V: OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

(NOT TO SCALE)

				Design Division Standard	
<b>TAPERED EDGE DETAILS          HMAC PAVEMENT</b>					
<b>TE(HMAC)-11</b>					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0045 09	116, ETC.	US 82		
DIST	COUNTY		SHEET NO.		
PAR	LAMAR, ETC.		48		



ESTIMATED QUANTITIES		
0110 6002 EXCAVATION (CHANNEL)		50 CY
0462 6047 CONC BOX CULV (4 FT X 2 FT) EXTEND)		4 LF
0466 6193 WINGWALL (PW - 2) (HW=4 FT)		1 EA
0496 6005 REMOV STR (WINGWALL)		1 EA
0658 6047 INSTL OM ASSM (OM-2Y)(WC)(GND)		2 EA



STANDARDS: PW, SCC-3' & 4', SCP-4

BM ON TOP OF RT HEADWALL  
STA. 647+99  
ELEV = 100.00


SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'

*Austin R. Shatto, P.E.*  
07/31/2023  
US 82  
CULVERT LAYOUT  
CSJ: 0045-12-094  
STA. 647+99


SHEET 1 OF 8

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		49

DATE: 7/28/2023 11:23:34 AM  
 FILE: I:\PARISAD\DESIGN\US\_82 E Saf.seu Treeet 0045-09-116\Design\CAD Design\culvert layouts.dwg



ESTIMATED QUANTITIES			
0403	6001	TEMPORARY SPL SHORING	106 SF
0462	6053	CONC BOX CULV (5 FT X 5 FT) EXTEND	4 LF
0466	6196	WINGWALL (PW - 2) (HW=7 FT)	1 EA
0496	6005	REMOV STR (WINGWALL)	1 EA
0658	6047	INSTL OM ASSM (OM-2Y)(WC)(GND)	2 EA



BM ON CENTER LINE  
 STA. 665+99  
 ELEV = 100.00


SCALE  
 HORIZONTAL: 1"=10'  
 VERTICAL: 1"=10'

*Austin R. Shatto, P.E.*  
 07/31/2023  
**US 82**  
 CULVERT LAYOUT  
 CSJ: 0045-12-094  
 STA. 665+99


SHEET 2 OF 8

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		50

DATE: 7/28/2023 11:23:34 AM  
 FILE: I:\PARISAD\DESIGN\US 82 E Sef.seu.Treet 0045-09-116\Design\CAD\_Design\Culvert\_Layouts.dwg



ESTIMATED QUANTITIES		
0462	6045 CONC BOX CULV (3 FT X 2 FT)X(EXTEND)	6 LF
0466	6193 WINGWALL (PW - 2) (HW=4 FT)	2 EA
0496	6005 REMOV STR (WINGWALL)	2 EA
0658	6047 INSTL OM ASSM (OM-2Y)(WC)(GND)	4 EA



STANDARDS: PW, SCC-3' & 4', SCP-3

BM ON CENTER LINE  
STA. 708+50  
ELEV = 100.00

SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'


*Austin R. Shatto, P.E.*  
07/31/2023

**US 82**  
CULVERT LAYOUT  
CSJ: 0045-12-094  
STA. 708+50


SHEET 3 OF 8

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	51	

DATE: 7/28/2023 11:23:34 AM  
 FILE: I:\PARISAD\DESIGN\US\_82 E Saf.seu Treet 0045-09-116\Design\CAD\_Design\culvert\_Layouts.dwg



ESTIMATED QUANTITIES		
0462	6050 CONC BOX CULV (5 FT X 2 FT)X(EXTEND)	12 LF
0466	6193 WINGWALL (PW - 2) (HW=4 FT)	2 EA
0496	6005 REMOV STR (WINGWALL)	2 EA
0658	6047 INSTL OM ASSM (OM-2Y)(WC)(GND)	4 EA



BM ON CENTER LINE  
STA. 730+70  
ELEV = 100.00

SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'



*Austin R. Shatto, P.E.*  
07/31/2023

**US 82**  
**CULVERT LAYOUT**  
CSJ: 0045-12-094  
STA. 730+70


SHEET 4 OF 8

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		52

DATE: 7/28/2023 11:23:34 AM  
 FILE: I:\PARISAD\DESIGN\US\_82 E Saf.seu Treeet 0045-09-116\Design\CAD\_Design\culvert\_Layouts.dwg




ESTIMATED QUANTITIES				
0400	6006	CUT & RESTORE ASPH PAV	55	SY
0401	6001	FLOWABLE BACKFILL	51	CY
0402	6001	TRENCH EXCAVATION PROTECTION	62	LF
0403	6001	TEMPORARY SPL SHORING	196	SF
0462	6009	CONC BOX CULV (5 FT X 5 FT)	64	LF
0466	6196	WINGWALL (PW - 2) (HW=7 FT)	2	EA
0496	6001	REMOV STR (BOX CULVERT)	2	EA
0496	6005	REMOV STR (WINGWALL)	4	EA
0658	6047	INSTL OM ASSM (OM-2Y)(WC)(GND)	4	EA




BM ON CENTER LINE  
STA. 750+75  
ELEV = 100.00

SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'




*Austin R. Shatto, P.E.*  
07/31/2023  
**US 82**  
CULVERT LAYOUT  
CSJ: 0045-12-094  
STA. 750+75

SHEET 5 OF 8




CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	53	

DATE: 7/31/2023 2:32:04 PM  
FILE: I:\PARISAD\DESIGN\US\_82 E Saf.seu Treet 0045-09-116\Design\CAD\_Design\Culvert\_Layouts.dwg



ESTIMATED QUANTITIES		
0464	6005 RC PIPE (CL 111X24 IN)	10 LF
0467	6388 SET (TY 11) (24 IN) (RCP) (3:1) (C)	2 EA
0496	6006 REMOV STR (HEADWALL)	2 EA
0658	6047 INSTL OM ASSM (OM-2Y)(WC)(GND)	4 EA



BM ON CENTER LINE  
STA. 1162+23  
ELEV = 100.00

SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'

Austin R. Shatto, P.E.  
07/31/2023


**US 82**  
CULVERT LAYOUT  
CSJ: 0045-12-094  
STA. 1162+23

SHEET 6 OF 8

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		54


DATE: 7/31/2023 2:32:05 PM  
FILE: I:\PARISAD\DESIGN\US\_82 E Saf.seu I-reet 0045-09-116\Design\CAD\_Design\culvert layouts.dwg





ESTIMATED QUANTITIES

0403	6001	TEMPORARY SPL SHORING	128 SF
0462	6057	CONC BOX CULV (6 FT X 6 FT) EXTEND	4 LF
0466	6197	WINGWALL (PW - 2) (HW=8 FT)	1 EA
0496	6005	REMOV STR (WINGWALL)	1 EA
0658	6047	INSTL OM ASSM (OM-2Y)(WC)(GND)	2 EA



BM ON CENTER LINE STA. 1185+73 ELEV = 100.00

SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'


Austin R. Shatto, P.E.  
07/31/2023

US 82  
CULVERT LAYOUT  
CSJ: 0045-12-094  
STA. 1185+73

SHEET 7 OF 8


CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		55

DATE: 7/28/2023 11:23:35 AM  
FILE: I:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Design\culvert layouts.dwg



ESTIMATED QUANTITIES

0403	6001	TEMPORARY SPL SHORING	96 SF
0462	6118	CONC BOX CULV (6 FT X 2.5 FT)(EXTEND)	4 LF
0466	6196	WINGWALL (PW - 2) (HW=7 FT)	1 EA
0496	6005	REMOV STR (WINGWALL)	1 EA
0658	6047	INSTL OM ASSM (OM-2Y)(WC)(GND)	2 EA



BM ON CENTER LINE STA. 850+74 ELEV = 100.00

SCALE  
HORIZONTAL: 1"=10'  
VERTICAL: 1"=10'

Austin R. Shatto, P.E.  
07/31/2023

US 82  
CULVERT LAYOUT  
CSJ: 0046-01-071  
STA. 850+74

SHEET 8 OF 8

© 2023 Texas Department of Transportation

CONT	SECT	JOB	HIGHWAY
0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.
PAR	LAMAR, ETC.		56

DATE: 7/28/2023 11:23:35 AM  
FILE: I:\PARISAD\DESIGN\US\_82 E Saf.seu Treet 0045-09-116\Design\CAD Design\culvert layouts.dwg

DATE: 7/31/2023 2:32:05 PM  
 FILE: I:\PARIS\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\CAD Standards\0045-09-116\0045-09-116.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information resulting from its use.

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert No. Spans ~ Span X Height	Max Fill Height (Ft)	Applicable Box Culvert Standard (4)	Applicable Wingwall or End Treatment Standard	Skew Angle (0°, 15°, 30° or 45°)	Side Slope or Channel Slope Ratio (SL:1)	T Culvert Top Slab Thickness (In)	U Culvert Wall Thickness (In)	C Estimated Curb Height (Ft)	Hw Height of Wingwall (Ft) (1)	A Curb to End of Wingwall (Ft)	B Offset of End of Wingwall (Ft)	Lw Length of Longest Wingwall (Ft)	Ltw Culvert Toewall Length (Ft)	Atw Anchor Toewall Length (Ft)	Riprap Apron (CY)	Class "C" Conc (Curb) (CY) (2)	Class "C" Conc (Wingwall) (CY) (3)	Total Wingwall Area (SF)
647+99 (Lt)	1~4' X 2'	2'	SCC-3&4	PW-2	0	6:1	8"	7"	1.000	3.667	N/A	N/A	19.000	5.167	N/A	0.0	0.2	10.4	138
665+99 (Lt)	1~5' X 5'	2'	SCC-5&6	PW-2	0	6:1	8"	7"	1.000	6.667	N/A	N/A	34.000	6.167	N/A	0.0	0.2	29.7	447
708+50 (Both)	1~3' X 2'	1'	SCC-3&4	PW-2	0	6:1	8"	7"	1.000	3.667	N/A	N/A	19.000	4.167	N/A	0.0	0.4	20.6	276
730+70 (Both)	2~5' X 2'	2'	MC-5-20	PW-2	0	6:1	8"	7"	1.000	3.667	N/A	N/A	19.000	11.750	N/A	0.0	0.8	21.6	276
750+75 (Both)	1~5' X 5'	2'	SCP-5	PW-2	0	6:1	6"	6"	1.000	6.500	N/A	N/A	33.000	6.000	N/A	0.0	0.4	51.2	846
1185+73 (Rt)	1~6' X 6'	2'	SCC-5&6	PW-2	0	4:1	8"	7"	1.000	7.667	N/A	N/A	26.667	7.167	N/A	0.0	0.3	26.1	403
850+74 (Rt)	1~6' X 2.5'	4'	SCC-5&6	PW-2	0	6:1	8"	7"	3.500	6.667	N/A	N/A	34.000	7.167	N/A	0.0	0.9	29.8	447

**NOTES:**

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets;  
 30° maximum for safety end treatment

SL:1 = Horizontal : 1 Vertical

- Side slope at culvert for flared or straight wingwalls.
- Channel slope for parallel wingwalls.
- Slope must be 3:1 or flatter for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)

B = Offset of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)

Atw = Length of anchor toewall (applicable to safety end treatment only)

Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt.  
 Area for four wingwalls (two structure ends) if Both.

- Round the wall heights shown to the nearest foot for bidding purposes.
- Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class S concrete is required for the top slab of the culvert, also provide Class S concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.
- Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.
- Regardless of the type of culvert shown on this sheet, the Contractor has the option of furnishing cast-in-place or precast culverts unless otherwise shown elsewhere on the plans. If the Contractor elects to provide culverts of a different type than those shown on this sheet, it is the Contractor's responsibility to make the necessary adjustments to the dimensions and quantities shown.

**SPECIAL NOTE:**

This sheet is a supplement to the box culvert standards. It is to be filled out by the culvert specifier and provides dimensions for the construction of the box culvert wingwalls and safety end treatments.

An Excel 2010 spreadsheet to assist in completing this table can be downloaded from the Bridge Standards (English) web page on the TxDOT web site. The completed sheet must be signed, sealed, and dated by a licensed Professional Engineer.



*Austin R. Shatto, P.E.*




**BOX CULVERT SUPPLEMENT  
WINGS AND END TREATMENTS**


**BCS**

FILE: bcsstd1-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>	
	DIST	COUNTY	SHEET NO.	
	<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>57</b>	


DATE: 7/28/2023 11:23:35 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Sef.tey Treet 0045-09-116\Design\CAD Standards\STANDARD\STANDARD.DWG  
 DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information resulting from its use.




PLAN OF SKEWED ENDS ~ FROM 0° TO 15°



PLAN OF SKEWED ENDS ~ OVER 30° TO 45°



PLAN OF SKEWED ENDS ~ OVER 15° TO 30°



LENGTHENING DETAIL

① For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed. Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.

- ② When the spacing between Bars B becomes less than half of the normal spacing, cut bars to avoid conflict.
- ③ The length of Bars B vary in the skewed end sections.
- ④  $[ \text{One half of overall width} ] \times [ \text{tangent of the skew angle} ]$
- ⑤ Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- ⑥ When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- ⑦ At the Contractor's option, for skews of 15° or less, place Bars B, C, and D parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B shown on the Single Box Culverts Cast-In-Place (SCC) standards sheets to accommodate the skew.

**CONSTRUCTION NOTES:**

Do not use permanent forms.  
 When required, lap Bars H 1'-8" for uncoated or galvanized bars.  
 Provide a minimum of 1 1/2" clear cover.


**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel, if required elsewhere in the plans.  
 Provide Class C concrete (f'c = 3,600 psi) with these exceptions:  
 provide Class S concrete (f'c = 4,000 psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.


**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications.  
 Refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for details of straight sections of culvert.  
 For skewed sections and angle sections, refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.  
 For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the culvert Single Box Culverts Cast-In-Place (SCC) standard sheets by the cosine of the skew angle.


Cover dimensions are clear dimensions, unless noted otherwise.



PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ OVER 30° TO 45°


HL93 LOADING

		Bridge Division Standard	
<b>SINGLE BOX CULVERTS          CAST-IN-PLACE          MISCELLANEOUS DETAILS</b>			
<b>SCC-MD</b>			
FILE: scmdiste-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT	SECT	JOB
REVISIONS	0045	09	116, ETC.
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	58	


DATE: 7/28/2023 11:23:36 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Sef.tey Treet 0045-09-116\Design\CAD Standards\DRAINAGE\DETAILS\STANDARDS\SCC-3 & 4.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.




**TYPICAL SECTION**




**PLAN OF REINF STEEL**




**SECTION THRU CURB**



BARS C



BARS D



BARS K (#4)  
 (Spa = 1'-0" Max)  
 (Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.  
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.  
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

**CONSTRUCTION NOTES:**

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

**MATERIAL NOTES:**

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete (f<sub>c</sub> = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f<sub>c</sub> = 4,000 psi) for top slabs of:
  - culverts with overlay,
  - culverts with 1-to-2 course surface treatment, or
  - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
  - Uncoated or galvanized ~ #4 = 1'-8" Min
  - Uncoated or galvanized ~ #5 = 2'-1" Min

**GENERAL NOTES:**

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING

SHEET 1 OF 2



**SINGLE BOX CULVERTS  
 CAST-IN-PLACE  
 0' TO 30' FILL**


**SCC-3 & 4**

FILE: scc34ste-21.dgn	DN: TBE	ck: BMP	DW: TxDOT	ck: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82	
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	PAR	LAMAR, ETC.	59	


DATE: 7/28/2023 11:23:36 AM  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Saf.tey Treeet 0045-09-116\Design\CAD\_Standards\DRAINAGE\SCC-3 & 4.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any data resulting from its use.

SECTION DIMENSIONS				FILL HEIGHT	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																								QUANTITIES														
					Bars B					Bars C					Bars D					Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total					
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
3' - 0"	2' - 0"	8"	7"	30'	108	#5	9"	3' - 11"	441	108	#4	9"	5' - 4"	385	2' - 6"	2' - 10"	108	#4	9"	5' - 1"	367	2' - 10"	2' - 3"	108	9"	2' - 0"	144	3	39' - 9"	80	19	39' - 9"	505	3' - 11"	10	10	28	0.292	48.1	0.3	38	12.0	1,960
3' - 0"	3' - 0"	8"	7"	30'	108	#5	9"	3' - 11"	441	108	#4	9"	6' - 4"	457	3' - 6"	2' - 10"	108	#4	9"	5' - 1"	367	2' - 10"	2' - 3"	108	9"	3' - 0"	216	3	39' - 9"	80	23	39' - 9"	611	3' - 11"	10	10	28	0.335	54.3	0.3	38	13.7	2,210
4' - 0"	2' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	5' - 8"	613	2' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	2' - 0"	144	3	39' - 9"	80	21	39' - 9"	558	4' - 11"	13	12	33	0.342	63.4	0.4	46	14.1	2,581
4' - 0"	3' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	6' - 8"	721	3' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	3' - 0"	216	3	39' - 9"	80	25	39' - 9"	664	4' - 11"	13	12	33	0.385	70.5	0.4	46	15.8	2,867
4' - 0"	4' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	7' - 8"	830	4' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	4' - 0"	289	3	39' - 9"	80	25	39' - 9"	664	4' - 11"	13	12	33	0.428	75.1	0.4	46	17.5	3,049


⑤ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.

				Bridge Division Standard			
<b>SINGLE BOX CULVERTS          CAST-IN-PLACE          0' TO 30' FILL</b>							
<b>SCC-3 &amp; 4</b>							
FILE:	sc34ste-21.dgn	DN:	TBE	CK:	BMP	DW:	TxDOT
©TxDOT	February 2020	CONT:	SECT	JOB:	HIGHWAY		
REVISIONS		0045	09	116, ETC.		US 82	
04/2021 Updated X values.		DIST:	PAR	COUNTY:	LAMAR, ETC.	SHEET NO. 60	


DATE: 7/28/2023 11:23:37 AM  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Saf.tey\_T-reet\_0045-09-116\Design\CAD\_Standards\DRAINAGE\DETAILS\STANDARDS\SCC-5&6-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion resulting from its use.




**TYPICAL SECTION**




**PLAN OF REINF STEEL**




**SECTION THRU CURB**



BARS C



BARS D



BARS K (#4)  
(Spa = 1'-0" Max)  
(Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.  
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.  
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

**CONSTRUCTION NOTES:**

Do not use permanent forms.  
 Chamfer the bottom edge of the top slab 3" at the entrance.  
 Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.  
 Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
 

- culverts with overlay,
- culverts with 1-to-2 course surface treatment, or
- culverts with the top slab as the final riding surface.

 Provide bar laps, where required, as follows:
 

- Uncoated or galvanized ~ #4 = 1'-8" Min
- Uncoated or galvanized ~ #5 = 2'-1" Min
- Uncoated or galvanized ~ #6 = 2'-6" Min

**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.  
 See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING

SHEET 1 OF 2



**SINGLE BOX CULVERTS  
CAST-IN-PLACE  
0' TO 30' FILL**

**SCC-5 & 6**

FILE: scc5ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	PAR	LAMAR, ETC.	61	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information presented herein. **STANDARDS** shall be used for all dimensions unless otherwise noted.

DATE: 7/28/2023 11:23:37 AM  
 FILE: I:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treeet\_0045-09-116\Design\CAD\_Standards\SCC-5&6-21.dgn

SECTION DIMENSIONS				⑤ FILL HEIGHT	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																											QUANTITIES											
					Bars B						Bars C						Bars D						Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total		
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
5' - 0"	2' - 0"	8"	7"	26'	108	#6	9"	5' - 11"	960	108	#5	9"	6' - 3"	704	2' - 6"	3' - 9"	108	#5	9"	6' - 5"	723	3' - 9"	2' - 8"	108	9"	2' - 0"	144	4	39' - 9"	106	22	39' - 9"	584	5' - 11"	16	14	39	0.391	80.5	0.5	55	16.1	3,276
5' - 0"	2' - 0"	9"	7"	30'	108	#6	9"	5' - 11"	960	108	#5	9"	6' - 4"	713	2' - 7"	3' - 9"	108	#5	9"	6' - 6"	732	3' - 9"	2' - 9"	108	9"	2' - 0"	144	4	39' - 9"	106	22	39' - 9"	584	5' - 11"	16	14	39	0.429	81.0	0.5	55	17.6	3,294
5' - 0"	3' - 0"	8"	7"	26'	108	#6	9"	5' - 11"	960	108	#5	9"	7' - 3"	817	3' - 6"	3' - 9"	108	#5	9"	6' - 5"	723	3' - 9"	2' - 8"	108	9"	3' - 0"	216	4	39' - 9"	106	26	39' - 9"	690	5' - 11"	16	14	39	0.434	87.8	0.5	55	17.8	3,567
5' - 0"	3' - 0"	9"	7"	30'	108	#6	9"	5' - 11"	960	108	#5	9"	7' - 4"	826	3' - 7"	3' - 9"	108	#5	9"	6' - 6"	732	3' - 9"	2' - 9"	108	9"	3' - 0"	216	4	39' - 9"	106	26	39' - 9"	690	5' - 11"	16	14	39	0.472	88.3	0.5	55	19.3	3,585
5' - 0"	4' - 0"	8"	7"	26'	108	#6	9"	5' - 11"	960	108	#5	9"	8' - 3"	929	4' - 6"	3' - 9"	108	#5	9"	6' - 5"	723	3' - 9"	2' - 8"	108	9"	4' - 0"	289	4	39' - 9"	106	26	39' - 9"	690	5' - 11"	16	14	39	0.477	92.4	0.5	55	19.5	3,752
5' - 0"	4' - 0"	9"	7"	30'	108	#6	9"	5' - 11"	960	108	#5	9"	8' - 4"	939	4' - 7"	3' - 9"	108	#5	9"	6' - 6"	732	3' - 9"	2' - 9"	108	9"	4' - 0"	289	4	39' - 9"	106	26	39' - 9"	690	5' - 11"	16	14	39	0.515	92.9	0.5	55	21.1	3,771
5' - 0"	5' - 0"	8"	7"	26'	108	#6	9"	5' - 11"	960	108	#5	9"	9' - 3"	1,042	5' - 6"	3' - 9"	108	#5	9"	6' - 5"	723	3' - 9"	2' - 8"	108	9"	5' - 0"	361	4	39' - 9"	106	30	39' - 9"	797	5' - 11"	16	14	39	0.521	99.7	0.5	55	21.3	4,044
5' - 0"	5' - 0"	9"	7"	30'	108	#6	9"	5' - 11"	960	108	#5	9"	9' - 4"	1,051	5' - 7"	3' - 9"	108	#5	9"	6' - 6"	732	3' - 9"	2' - 9"	108	9"	5' - 0"	361	4	39' - 9"	106	30	39' - 9"	797	5' - 11"	16	14	39	0.559	100.2	0.5	55	22.8	4,062
6' - 0"	2' - 0"	8"	7"	20'	108	#6	9"	6' - 11"	1,122	108	#5	9"	6' - 7"	742	2' - 6"	4' - 1"	108	#5	9"	6' - 9"	760	4' - 1"	2' - 8"	108	9"	2' - 0"	144	5	39' - 9"	133	25	39' - 9"	664	6' - 11"	18	16	45	0.440	89.1	0.5	63	18.1	3,628
6' - 0"	2' - 0"	9"	7"	26'	108	#6	9"	6' - 11"	1,122	162	#5	6"	6' - 8"	1,126	2' - 7"	4' - 1"	162	#5	6"	6' - 10"	1,155	4' - 1"	2' - 9"	108	9"	2' - 0"	144	5	39' - 9"	133	25	39' - 9"	664	6' - 11"	18	16	45	0.485	108.6	0.5	63	19.9	4,407
6' - 0"	2' - 0"	10"	8"	30'	108	#6	9"	7' - 1"	1,149	162	#5	6"	6' - 10"	1,155	2' - 8"	4' - 2"	162	#5	6"	7' - 0"	1,183	4' - 2"	2' - 10"	82	12"	2' - 0"	110	5	39' - 9"	133	25	39' - 9"	664	7' - 1"	19	18	50	0.551	109.9	0.5	69	22.6	4,463
6' - 0"	3' - 0"	8"	7"	20'	108	#6	9"	6' - 11"	1,122	108	#5	9"	7' - 7"	854	3' - 6"	4' - 1"	108	#5	9"	6' - 9"	760	4' - 1"	2' - 8"	108	9"	3' - 0"	216	5	39' - 9"	133	29	39' - 9"	770	6' - 11"	18	16	45	0.484	96.4	0.5	63	19.9	3,918
6' - 0"	3' - 0"	9"	7"	26'	108	#6	9"	6' - 11"	1,122	162	#5	6"	7' - 8"	1,295	3' - 7"	4' - 1"	162	#5	6"	6' - 10"	1,155	4' - 1"	2' - 9"	108	9"	3' - 0"	216	5	39' - 9"	133	29	39' - 9"	770	6' - 11"	18	16	45	0.528	117.3	0.5	63	21.6	4,754
6' - 0"	3' - 0"	10"	8"	30'	108	#6	9"	7' - 1"	1,149	162	#5	6"	7' - 10"	1,324	3' - 8"	4' - 2"	162	#5	6"	7' - 0"	1,183	4' - 2"	2' - 10"	82	12"	3' - 0"	164	5	39' - 9"	133	29	39' - 9"	770	7' - 1"	19	18	50	0.601	118.1	0.5	69	24.6	4,792
6' - 0"	4' - 0"	8"	7"	20'	108	#6	9"	6' - 11"	1,122	108	#5	9"	8' - 7"	967	4' - 6"	4' - 1"	108	#5	9"	6' - 9"	760	4' - 1"	2' - 8"	108	9"	4' - 0"	289	5	39' - 9"	133	29	39' - 9"	770	6' - 11"	18	16	45	0.527	101.0	0.5	63	21.6	4,104
6' - 0"	4' - 0"	9"	7"	26'	108	#6	9"	6' - 11"	1,122	162	#5	6"	8' - 8"	1,464	4' - 7"	4' - 1"	162	#5	6"	6' - 10"	1,155	4' - 1"	2' - 9"	108	9"	4' - 0"	289	5	39' - 9"	133	29	39' - 9"	770	6' - 11"	18	16	45	0.571	123.3	0.5	63	23.4	4,996
6' - 0"	4' - 0"	10"	8"	30'	108	#6	9"	7' - 1"	1,149	162	#5	6"	8' - 10"	1,493	4' - 8"	4' - 2"	162	#5	6"	7' - 0"	1,183	4' - 2"	2' - 10"	82	12"	4' - 0"	219	5	39' - 9"	133	29	39' - 9"	770	7' - 1"	19	18	50	0.650	123.7	0.5	69	26.5	5,016
6' - 0"	5' - 0"	8"	7"	20'	108	#6	9"	6' - 11"	1,122	108	#5	9"	9' - 7"	1,080	5' - 6"	4' - 1"	108	#5	9"	6' - 9"	760	4' - 1"	2' - 8"	108	9"	5' - 0"	361	5	39' - 9"	133	33	39' - 9"	876	6' - 11"	18	16	45	0.570	108.3	0.5	63	23.3	4,395
6' - 0"	5' - 0"	9"	7"	26'	108	#6	9"	6' - 11"	1,122	162	#5	6"	9' - 8"	1,633	5' - 7"	4' - 1"	162	#5	6"	6' - 10"	1,155	4' - 1"	2' - 9"	108	9"	5' - 0"	361	5	39' - 9"	133	33	39' - 9"	876	6' - 11"	18	16	45	0.614	132.0	0.5	63	25.1	5,343
6' - 0"	5' - 0"	10"	8"	30'	108	#6	9"	7' - 1"	1,149	162	#5	6"	9' - 10"	1,661	5' - 8"	4' - 2"	162	#5	6"	7' - 0"	1,183	4' - 2"	2' - 10"	82	12"	5' - 0"	274	5	39' - 9"	133	33	39' - 9"	876	7' - 1"	19	18	50	0.700	131.9	0.5	69	28.5	5,345
6' - 0"	6' - 0"	8"	7"	20'	108	#6	9"	6' - 11"	1,122	108	#5	9"	10' - 7"	1,192	6' - 6"	4' - 1"	108	#5	9"	6' - 9"	760	4' - 1"	2' - 8"	108	9"	6' - 0"	433	5	39' - 9"	133	37	39' - 9"	982	6' - 11"	18	16	45	0.613	115.6	0.5	63	25.0	4,685
6' - 0"	6' - 0"	9"	7"	26'	108	#6	9"	6' - 11"	1,122	162	#5	6"	10' - 8"	1,802	6' - 7"	4' - 1"	162	#5	6"	6' - 10"	1,155	4' - 1"	2' - 9"	108	9"	6' - 0"	433	5	39' - 9"	133	37	39' - 9"	982	6' - 11"	18	16	45	0.657	140.7	0.5	63	26.8	5,690
6' - 0"	6' - 0"	10"	8"	30'	108	#6	9"	7' - 1"	1,149	162	#5	6"	10' - 10"	1,830	6' - 8"	4' - 2"	162	#5	6"	7' - 0"	1,183	4' - 2"	2' - 10"	82	12"	6' - 0"	329	5	39' - 9"	133	37	39' - 9"	982	7' - 1"	19	18	50	0.749	140.2	0.5	69	30.5	5,675

⑤ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.




**SINGLE BOX CULVERTS  
CAST-IN-PLACE  
0' TO 30' FILL**


**SCC-5 & 6**

FILE: scc56ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0045</b>	<b>09</b>	<b>116, ETC.</b>	<b>US 82</b>
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>62</b>	


DATE: 7/28/2023 11:23:37 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Saf.tey T-rect 0045-09-116\Design\CAD Standards\DRAINAGE\SCPDSTS-20.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.




**MULTIPLE UNIT PLACEMENT**



**SECTION B-B**




**DETAIL "A"**




**WINGWALL CONNECTION**

(Also applies to safety end treatment.)




**SECTION THRU TOP SLABS LESS THAN 8"**




**SECTION THRU CURB**


QUANTITIES PER FOOT OF CURB (10)	
Reinforcing Steel	4.12 Lb
Concrete	0.037 CY




BARS C (#4)  
(Spa = 1'-0" Max)




BARS K (#4)  
(Spa = 1'-0" Max)  
(Length = 4'-2")



**ANGLE DETAIL**



**SECTION A-A**



**PLAN OF SKEWED ENDS**

(Showing multi-box placement.)

- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail, bicycle rail, or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- Extend curb, wingwall, or safety end treatment reinforcing into concrete closure. Bend or trim, as necessary, any reinforcing that does not fit into closure area.
- Provide a 3'-0" Min cast-in-place concrete closure. Break back boxes in the field or cast boxes short. Provide bands of reinforcing in the closure that are the same size and spacing as in the precast box section. Provide #4 longitudinal reinforcement spaced at 12 inches Max within the closure. Except where shown otherwise, construct the cast-in-place closure flush with the inside and outside faces of the precast box section.
- For multiple unit placements, adjust the length of the closure for the interior walls as necessary. Provide a 3'-0" Min cast-in-place closure in the top slab, bottom slab, and exterior wall. See Section B-B detail when interior walls are cast full length.
- Extend precast box reinforcing a minimum of 1'-0" into concrete closure (Typ).
- Place bands of reinforcing matching the inside and outside face reinforcing in the gaps of the top and bottom slabs. Place a band matching the outside face reinforcing of the wall in the gaps of the walls (placed in the outside face only). Tack weld the bands to the exposed reinforcing at each point of contact.
- For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- Cement stabilized backfill between boxes is considered part of the box culvert for payment.
- All curb concrete and reinforcing is considered part of the box culvert for payment.
- Any additional concrete and reinforcing required for the closures will be considered subsidiary to the box culvert for payment.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- For multiple unit placement with overlay, with 1 to 2 course surface treatment, or with the top slab as the final riding surface, provide wall closure as shown in Detail "A".
- This dimension may be increased with approval of the Engineer to allow the precast boxes to be tunneled or jacked in accordance with Item 476, "Jacking, Boring, or Tunneling Pipe or Box". No payment will be made for any additional material in the gap between adjacent boxes.

**MATERIAL NOTES:**  
 Provide Grade 60 reinforcing steel.  
 Provide ASTM A1064 welded wire reinforcement.  
 Provide Class C concrete (f<sub>c</sub> = 3,600 psi) for the closures.  
 Provide cement stabilized backfill meeting the requirements of Item 400, "Excavation and Backfill for Structures."  
 Any additional concrete required for the closures will be considered subsidiary to the box culvert.

**GENERAL NOTES:**  
 Designed according to AASHTO LRFD Bridge Design Specifications.  
 Refer to the Single Box Culverts Precast (SCP) standard sheets for details and notes not shown.  
 Chamfer the bottom edge of the top slab closure 3 inches at culvert closure ends.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bars dimensions are out-to-out of bars.

HL93 LOADING


		Bridge Division Standard	
<b>BOX CULVERTS PRECAST MISCELLANEOUS DETAILS</b>			
<b>SCP-MD</b>			
FILE: scpmdsts-20.dgn	DN: GAF	CK: LMW	DW: BWH/TXDOT
©TxDOT	February 2020	CONTRACT	SECTION
REVISIONS	0045 09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.	
PAR	LAMAR, ETC.	63	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.


DATE: 7/28/2023 11:23:38 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Saftey Trest 0045-09-116\Design\CAD Standards\DRAINAGE\STANDARD\SC3.dwg

**BOX DATA**


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) <sup>②</sup>								① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8		
3	2	7	6	4	< 2	-	0.17	0.25	0.16	0.10	0.17	0.17	0.14	3.3	
3	2	4	4	4	2 < 3	31	0.13	0.19	0.18	0.10	-	-	-	2.4	
3	2	4	4	4	3 - 5	31	0.10	0.11	0.12	0.10	-	-	-	2.4	
3	2	4	4	4	10	31	0.10	0.10	0.10	0.10	-	-	-	2.4	
3	2	4	4	4	15	31	0.10	0.13	0.13	0.10	-	-	-	2.4	
3	2	4	4	4	20	31	0.11	0.17	0.17	0.10	-	-	-	2.4	
3	2	4	4	4	25	31	0.14	0.21	0.21	0.10	-	-	-	2.4	
3	2	4	4	4	30	31	0.17	0.25	0.25	0.10	-	-	-	2.4	
3	2	4	4	4	35	31	0.20	0.29	0.30	0.10	-	-	-	2.4	
3	3	7	6	4	< 2	-	0.17	0.27	0.17	0.10	0.17	0.17	0.14	3.7	
3	3	4	4	4	2 < 3	31	0.10	0.22	0.21	0.10	-	-	-	2.8	
3	3	4	4	4	3 - 5	31	0.10	0.14	0.14	0.10	-	-	-	2.8	
3	3	4	4	4	10	31	0.10	0.11	0.11	0.10	-	-	-	2.8	
3	3	4	4	4	15	31	0.10	0.14	0.15	0.10	-	-	-	2.8	
3	3	4	4	4	20	31	0.10	0.18	0.19	0.10	-	-	-	2.8	
3	3	4	4	4	25	31	0.10	0.23	0.23	0.10	-	-	-	2.8	
3	3	4	4	4	30	31	0.12	0.27	0.28	0.10	-	-	-	2.8	
3	3	4	4	4	35	31	0.14	0.32	0.32	0.10	-	-	-	2.8	



**FILL HEIGHT 2 FT AND GREATER**



**FILL HEIGHT LESS THAN 2 FT**



**SECTION A-A**

(Showing top and bottom slab joint reinforcement.)

**MATERIAL NOTES:**

Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.  
 Provide Class H concrete (f'c = 5,000 psi).

**GENERAL NOTES:**

Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.  
 See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.  
 In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

**HL93 LOADING**

		<b>Bridge Division Standard</b>	
<b>SINGLE BOX CULVERTS          PRECAST          3'-0" SPAN</b>			
<b>SCP-3</b>			
FILE:	scp03sts-20.dgn	DN: TxDOT	CK: TxDOT
©TxDOT	February 2020	CON: TxDOT	SECT: TxDOT
REVISIONS	0045 09	JOB	HIGHWAY
		116, ETC.	US 82
DIST:	PAR	COUNTY	SHEET NO.
		LAMAR, ETC.	64

① For box length = 8'-0"


② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.


DATE: 7/28/2023 11:23:38 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Saftey Treat 0045-09-116\Design\CAD Standards\DRAINAGE\SCPs\SCP-4.dwg

**BOX DATA**


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) <sup>②</sup>								① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8		
4	2	7.5	6	5	< 2	-	0.18	0.27	0.15	0.12	0.18	0.18	0.14	4.5	
4	2	5	5	5	2 < 3	38	0.18	0.19	0.17	0.12	-	-	-	3.6	
4	2	5	5	5	3 - 5	38	0.13	0.13	0.13	0.12	-	-	-	3.6	
4	2	5	5	5	10	38	0.12	0.12	0.12	0.12	-	-	-	3.6	
4	2	5	5	5	15	38	0.14	0.16	0.16	0.12	-	-	-	3.6	
4	2	5	5	5	20	38	0.18	0.20	0.21	0.12	-	-	-	3.6	
4	2	5	5	5	25	38	0.23	0.25	0.25	0.12	-	-	-	3.6	
4	2	5	5	5	30	38	0.28	0.30	0.30	0.12	-	-	-	3.6	
4	3	7.5	6	5	< 2	-	0.18	0.31	0.18	0.12	0.18	0.18	0.14	5.0	
4	3	5	5	5	2 < 3	38	0.15	0.23	0.20	0.12	-	-	-	4.1	
4	3	5	5	5	3 - 5	38	0.12	0.16	0.16	0.12	-	-	-	4.1	
4	3	5	5	5	10	38	0.12	0.14	0.14	0.12	-	-	-	4.1	
4	3	5	5	5	15	38	0.12	0.18	0.18	0.12	-	-	-	4.1	
4	3	5	5	5	20	38	0.14	0.23	0.24	0.12	-	-	-	4.1	
4	3	5	5	5	25	38	0.17	0.29	0.29	0.12	-	-	-	4.1	
4	3	5	5	5	30	38	0.21	0.35	0.35	0.12	-	-	-	4.1	
4	4	7.5	6	5	< 2	-	0.18	0.33	0.20	0.12	0.18	0.18	0.14	5.5	
4	4	5	5	5	2 < 3	38	0.12	0.26	0.23	0.12	-	-	-	4.6	
4	4	5	5	5	3 - 5	38	0.12	0.18	0.18	0.12	-	-	-	4.6	
4	4	5	5	5	10	38	0.12	0.15	0.15	0.12	-	-	-	4.6	
4	4	5	5	5	15	38	0.12	0.19	0.20	0.12	-	-	-	4.6	
4	4	5	5	5	20	38	0.12	0.25	0.25	0.12	-	-	-	4.6	
4	4	5	5	5	25	38	0.14	0.31	0.31	0.12	-	-	-	4.6	
4	4	5	5	5	30	38	0.17	0.37	0.37	0.12	-	-	-	4.6	



**FILL HEIGHT 2 FT AND GREATER**



**FILL HEIGHT LESS THAN 2 FT**



**SECTION A-A**

(Showing top and bottom slab joint reinforcement.)

**MATERIAL NOTES:**

Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.  
 Provide Class H concrete (f'c = 5,000 psi).

**GENERAL NOTES:**

Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.  
 See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.  
 In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

HL93 LOADING

		<i>Bridge Division Standard</i>	
<b>SINGLE BOX CULVERTS          PRECAST          4'-0" SPAN</b>			
<b>SCP-4</b>			
FILE:	scp04sts-20.dgn	DN: TxDOT	CK: TxDOT
©TxDOT	February 2020	CON: TxDOT	SECT: HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82
DIST:	PAR	COUNTY:	LAMAR, ETC.
		SHEET NO.:	65

① For box length = 8'-0"


② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcing per linear foot of box length. AS5 is minimum required area of reinforcing per linear foot of box width.

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.


DATE: 7/28/2023 11:23:38 AM  
 FILE: I:\PARISAD\DESIGN\US\_82\_E\_Saf.tey\_T-reot\_0045-09-116\_Design\CAD\_Standards\DRAINAGE\DETAILS\0045-09-116.dwg

**BOX DATA**


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) <sup>②</sup>								① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8		
5	2	8	7	6	< 2	-	0.19	0.27	0.18	0.14	0.19	0.19	0.17	6.0	
5	2	6	6	6	2 < 3	44	0.22	0.20	0.16	0.14	-	-	-	5.1	
5	2	6	6	6	3 - 5	44	0.16	0.14	0.14	0.14	-	-	-	5.1	
5	2	6	6	6	10	36	0.15	0.14	0.14	0.14	-	-	-	5.1	
5	2	6	6	6	15	36	0.20	0.18	0.18	0.14	-	-	-	5.1	
5	2	6	6	6	20	36	0.26	0.23	0.24	0.14	-	-	-	5.1	
5	2	6	6	6	25	36	0.33	0.29	0.29	0.14	-	-	-	5.1	
5	2	6	6	6	30	36	0.39	0.34	0.35	0.14	-	-	-	5.1	
5	3	8	7	6	< 2	-	0.19	0.31	0.21	0.14	0.19	0.19	0.17	6.6	
5	3	6	6	6	2 < 3	45	0.18	0.24	0.19	0.14	-	-	-	5.7	
5	3	6	6	6	3 - 5	36	0.14	0.17	0.16	0.14	-	-	-	5.7	
5	3	6	6	6	10	36	0.14	0.16	0.17	0.14	-	-	-	5.7	
5	3	6	6	6	15	35	0.16	0.21	0.22	0.14	-	-	-	5.7	
5	3	6	6	6	20	35	0.21	0.27	0.28	0.14	-	-	-	5.7	
5	3	6	6	6	25	35	0.26	0.34	0.34	0.14	-	-	-	5.7	
5	3	6	6	6	30	35	0.31	0.41	0.41	0.14	-	-	-	5.7	
5	4	8	7	6	< 2	-	0.19	0.33	0.24	0.14	0.19	0.19	0.17	7.2	
5	4	6	6	6	2 < 3	45	0.16	0.27	0.22	0.14	-	-	-	6.3	
5	4	6	6	6	3 - 5	45	0.14	0.19	0.18	0.14	-	-	-	6.3	
5	4	6	6	6	10	36	0.14	0.18	0.18	0.14	-	-	-	6.3	
5	4	6	6	6	15	35	0.14	0.23	0.24	0.14	-	-	-	6.3	
5	4	6	6	6	20	35	0.17	0.30	0.31	0.14	-	-	-	6.3	
5	4	6	6	6	25	35	0.21	0.37	0.38	0.14	-	-	-	6.3	
5	4	6	6	6	30	35	0.25	0.44	0.45	0.14	-	-	-	6.3	
5	5	8	7	6	< 2	-	0.19	0.35	0.26	0.14	0.19	0.19	0.17	7.8	
5	5	6	6	6	2 < 3	45	0.14	0.29	0.24	0.14	-	-	-	6.9	
5	5	6	6	6	3 - 5	45	0.14	0.21	0.20	0.14	-	-	-	6.9	
5	5	6	6	6	10	45	0.14	0.19	0.20	0.14	-	-	-	6.9	
5	5	6	6	6	15	36	0.14	0.24	0.25	0.14	-	-	-	6.9	
5	5	6	6	6	20	35	0.15	0.31	0.32	0.14	-	-	-	6.9	
5	5	6	6	6	25	35	0.18	0.38	0.39	0.14	-	-	-	6.9	
5	5	6	6	6	30	35	0.21	0.46	0.47	0.14	-	-	-	6.9	



**FILL HEIGHT 2 FT AND GREATER**



**FILL HEIGHT LESS THAN 2 FT**



**SECTION A-A**

(Showing top and bottom slab joint reinforcement.)

**MATERIAL NOTES:**

Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.  
 Provide Class H concrete (f'c = 5,000 psi).

**GENERAL NOTES:**

Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.  
 See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.  
 In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

HL93 LOADING

<b>SINGLE BOX CULVERTS          PRECAST          5'-0" SPAN</b>			
<b>SCP-5</b>			
FILE:	scp05sts-20.dgn	DN: TxDOT	ck: TxDOT
©TxDOT	February 2020	CON: TxDOT	SECT: TxDOT
REVISIONS	0045 09	JOB	HIGHWAY
		116, ETC.	US 82
DIST:	PAR	COUNTY	SHEET NO.
		LAMAR, ETC.	66


① For box length = 8'-0"

② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.


DATE: 7/28/2023 11:23:39 AM  
 FILE: I:\PARISAD\DESIGN\US\_82 E Saf.tey T-reot 0045-09-116\Design\CAD Standards\DRAINAGE\STANDARDS\SCPs\SCP-6.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion resulting from its use.

### BOX DATA


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) <sup>②</sup>								Lift Weight (tons) <sup>①</sup>
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8		
6	2	8	7	7	< 2	-	0.23	0.27	0.19	0.17	0.19	0.17	7.2		
6	2	7	7	7	2 < 3	43	0.25	0.21	0.17	0.17	-	-	6.8		
6	2	7	7	7	3 - 5	43	0.20	0.17	0.17	0.17	-	-	6.8		
6	2	7	7	7	10	39	0.20	0.17	0.17	0.17	-	-	6.8		
6	2	7	7	7	15	39	0.26	0.20	0.20	0.17	-	-	6.8		
6	2	7	7	7	20	39	0.34	0.26	0.26	0.17	-	-	6.8		
6	2	7	7	7	25	39	0.43	0.32	0.32	0.17	-	-	6.8		
6	2	7	7	7	30	39	0.52	0.38	0.39	0.17	-	-	6.8		
6	3	8	7	7	< 2	-	0.20	0.31	0.22	0.17	0.19	0.19	7.9		
6	3	7	7	7	2 < 3	43	0.21	0.24	0.19	0.17	-	-	7.5		
6	3	7	7	7	3 - 5	39	0.17	0.18	0.17	0.17	-	-	7.5		
6	3	7	7	7	10	39	0.17	0.18	0.19	0.17	-	-	7.5		
6	3	7	7	7	15	38	0.22	0.24	0.24	0.17	-	-	7.5		
6	3	7	7	7	20	38	0.28	0.31	0.31	0.17	-	-	7.5		
6	3	7	7	7	25	38	0.35	0.38	0.39	0.17	-	-	7.5		
6	3	7	7	7	30	38	0.42	0.46	0.46	0.17	-	-	7.5		
6	4	8	7	7	< 2	-	0.19	0.34	0.25	0.17	0.19	0.19	8.6		
6	4	7	7	7	2 < 3	43	0.19	0.27	0.21	0.17	-	-	8.2		
6	4	7	7	7	3 - 5	39	0.17	0.21	0.19	0.17	-	-	8.2		
6	4	7	7	7	10	39	0.17	0.20	0.21	0.17	-	-	8.2		
6	4	7	7	7	15	38	0.18	0.27	0.27	0.17	-	-	8.2		
6	4	7	7	7	20	38	0.24	0.34	0.35	0.17	-	-	8.2		
6	4	7	7	7	25	38	0.29	0.43	0.42	0.17	-	-	8.2		
6	4	7	7	7	30	38	0.35	0.51	0.52	0.17	-	-	8.2		
6	5	8	7	7	< 2	-	0.19	0.37	0.28	0.17	0.19	0.19	9.3		
6	5	7	7	7	2 < 3	43	0.17	0.30	0.24	0.17	-	-	8.9		
6	5	7	7	7	3 - 5	43	0.17	0.23	0.21	0.17	-	-	8.9		
6	5	7	7	7	10	39	0.17	0.22	0.23	0.17	-	-	8.9		
6	5	7	7	7	15	38	0.17	0.28	0.29	0.17	-	-	8.9		
6	5	7	7	7	20	38	0.20	0.37	0.38	0.17	-	-	8.9		
6	5	7	7	7	25	38	0.25	0.45	0.46	0.17	-	-	8.9		
6	5	7	7	7	30	38	0.30	0.54	0.55	0.17	-	-	8.9		
6	6	8	7	7	< 2	-	0.19	0.38	0.30	0.17	0.19	0.19	10		
6	6	7	7	7	2 < 3	52	0.17	0.32	0.26	0.17	-	-	9.6		
6	6	7	7	7	3 - 5	52	0.17	0.24	0.22	0.17	-	-	9.6		
6	6	7	7	7	10	43	0.17	0.23	0.24	0.17	-	-	9.6		
6	6	7	7	7	15	39	0.17	0.29	0.31	0.17	-	-	9.6		
6	6	7	7	7	20	39	0.18	0.38	0.39	0.17	-	-	9.6		
6	6	7	7	7	25	38	0.23	0.46	0.48	0.17	-	-	9.6		
6	6	7	7	7	30	38	0.27	0.55	0.57	0.17	-	-	9.6		



**FILL HEIGHT 2 FT AND GREATER**



**FILL HEIGHT LESS THAN 2 FT**



**SECTION A-A**

(Showing top and bottom slab joint reinforcement.)

**MATERIAL NOTES:**  
 Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.  
 Provide Class H concrete ( $f'c = 5,000$  psi).

**GENERAL NOTES:**  
 Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.  
 See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.  
 In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design fill height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)".

- ① For box length = 8'-0"
- ② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.

HL93 LOADING

Bridge Division Standard


## SINGLE BOX CULVERTS PRECAST 6'-0" SPAN

### SCP-6


FILE: scp06sts-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>	
DIST	COUNTY	SHEET NO.		
<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>67</b>		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.


DATE: 7/28/2023 11:23:39 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\DRAINAGE\DETAILS\MISC\MISC-02.dgn




PLAN OF SKEWED ENDS ~ FROM 0° TO 15°




PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ OVER 30° TO 45°




PLAN OF SKEWED ENDS ~ OVER 15° TO 30°

- ① For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.  
 For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, Class C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.  
 Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.
- ② When the spacing between Bars B or Bars E becomes less than half of the normal spacing, cut bars to avoid conflict.
- ③ The length of Bars B and Bars E will vary in the skewed end sections.
- ④  $[\text{One half of overall width}] \times [\text{tangent of the skew angle}]$



PLAN OF SKEWED ENDS ~ OVER 30° TO 45°



LENGTHENING DETAIL

- ⑤ Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- ⑥ When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skew angles of 30° thru 45°.
- ⑦ At the Contractor's option, for skew angles of 15° or less, place Bars B, C, D, and E parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B and Bars E shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets to accommodate the skew.
- ⑧ Extend Bars E as shown on the MC standard sheet for direct traffic culverts.

**CONSTRUCTION NOTES:**

Do not use permanent forms.  
 When required, lap Bars H 1'-8" for uncoated or galvanized bars.  
 Provide a minimum of 1 1/2" clear cover.

**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel, if required elsewhere in the plans.  
 Provide Class C concrete (f'c = 3,600 psi) with these exceptions:  
 provide Class S concrete (f'c = 4,000 psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.

**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications.  
 Refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for details of straight sections of culvert.  
 For skewed sections and angle sections, refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.  
 For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets by the cosine of the skew angle.

Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING




**MULTIPLE BOX CULVERTS  
 CAST-IN-PLACE  
 MISCELLANEOUS DETAILS**

MC-MD


FILE: mc-mdste-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
	0045	09	116, ETC.	US 82
	DIST	COUNTY	SHEET NO.	
	PAR	LAMAR, ETC.	68	



DATE: 7/28/2023 11:23:40 AM  
 FILE: T:\PARISAD\DESIGN\AUS\_82\_E\_Saf.tey  
 T-reet 0045-09-116\Design\CAD\_Standards\DRAINAGE\DETAILS\STANDARDS\REF\2019-2023




**TYPICAL SECTION**




**BOTTOM SLAB**      **TOP SLAB**

**PART PLANS**



**SECTION THRU CURB**

TABLE OF BAR DIMENSIONS		
H	"X"	"Y"
2'-0"	2'-6 1/2"	3'-8 1/2"
3'-0"	3'-6 1/2"	3'-8 1/2"
4'-0"	4'-6 1/2"	3'-8 1/2"
5'-0"	5'-6 1/2"	3'-8 1/2"



- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR  
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.  
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

**CONSTRUCTION NOTES:**

Do not use permanent forms.  
 Chamfer the bottom edge of the top slab 3" at the entrance.  
 Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed, and Bars Y and Z may be reversed.

**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.  
 Provide Class C concrete (f<sub>c</sub> = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f<sub>c</sub> = 4,000 psi) for top slabs of:  
 · culverts with overlay,  
 · culverts with 1-to-2 course surface treatment, or  
 · culverts with the top slab as the final riding surface.  
 Provide bar laps, where required, as follows:  
 · Uncoated or galvanized ~ #4 = 1'-8" Min  
 · Uncoated or galvanized ~ #5 = 2'-1" Min  
 · Uncoated or galvanized ~ #6 = 2'-6" Min

**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.  
 See the Multiple Box Culverts Cast-In-Place Miscellaneous Detail (MC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING      SHEET 1 OF 2

Bridge Division Standard

**MULTIPLE BOX CULVERTS  
CAST-IN-PLACE  
5'-0" SPAN  
0' TO 20' FILL**

**MC-5-20**

FILE: mc520ste-20.dgn	DN: TBE	CK: BMP	DW: TXDOT	CK: TXDOT
©TXDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS		<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>
DIST	COUNTY	SHEET NO.		
<b>PAR</b>	<b>LAMAR, ETC.</b>			<b>69</b>

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units. FILE: \\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\DRAINAGE DETAIL STANDARDS\REF-201919-2019.dgn

NUMBER OF SPANS	SECTION DIMENSIONS				BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																									QUANTITIES																			
					Bars B					Bars C & D						Bars E				Bars F1 ~ #4			Bars F2 ~ #4			Bars M ~ #4			Bars Y & Z ~ #4					Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total							
	S	H	T	U	No.	Size	Spa	Length	Wt	No.	Size	Spa	Bars C		Bars D		No.	Size	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Bars Y		Bars Z		Length	Wt	No.	Wt	Conc (CY)	Renf (Lb)	Conc (CY)	Renf (Lb)	Conc (CY)	Renf (Lb)
													Length	Wt	Length	Wt																				Length	Wt	Length	Wt										
2	5'-0"	2'-0"	8"	7"	108	#5	9"	11'-6"	1,295	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	38	18"	39'-9"	1,009	108	9"	2'-0"	144	54	9"	4'-7"	165	5'-3"	189	11'-6"	31	26	72	0.710	135.2	0.9	103	29.3	5,510
3	5'-0"	2'-0"	8"	7"	108	#5	9"	17'-1"	1,924	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	54	18"	39'-9"	1,434	108	9"	2'-0"	144	108	9"	4'-7"	331	5'-3"	379	17'-1"	46	38	106	1.029	188.8	1.3	152	42.4	7,705
4	5'-0"	2'-0"	8"	7"	108	#5	9"	22'-8"	2,553	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	70	18"	39'-9"	1,859	108	9"	2'-0"	144	162	9"	4'-7"	496	5'-3"	568	22'-8"	61	48	134	1.348	242.4	1.7	195	55.6	9,891
5	5'-0"	2'-0"	8"	7"	108	#5	9"	28'-3"	3,182	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	86	18"	39'-9"	2,284	108	9"	2'-0"	144	216	9"	4'-7"	661	5'-3"	758	28'-3"	75	60	167	1.667	296.0	2.1	242	68.8	12,082
6	5'-0"	2'-0"	8"	7"	108	#5	9"	33'-10"	3,811	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	102	18"	39'-9"	2,708	108	9"	2'-0"	144	270	9"	4'-7"	827	5'-3"	947	33'-10"	90	70	195	1.986	349.6	2.5	285	82.0	14,268
2	5'-0"	3'-0"	8"	7"	108	#6	9"	11'-6"	1,865	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	44	18"	39'-9"	1,168	108	9"	3'-0"	216	54	9"	4'-7"	165	7'-3"	262	11'-6"	31	26	72	0.775	159.9	0.9	103	31.9	6,497
3	5'-0"	3'-0"	8"	7"	108	#6	9"	17'-1"	2,771	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	62	18"	39'-9"	1,646	108	9"	3'-0"	216	108	9"	4'-7"	331	7'-3"	523	17'-1"	46	38	106	1.115	223.5	1.3	152	45.9	9,093
4	5'-0"	3'-0"	8"	7"	108	#6	9"	22'-8"	3,677	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	80	18"	39'-9"	2,124	108	9"	3'-0"	216	162	9"	4'-7"	496	7'-3"	785	22'-8"	61	48	134	1.456	287.2	1.7	195	59.9	11,682
5	5'-0"	3'-0"	8"	7"	108	#6	9"	28'-3"	4,583	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	98	18"	39'-9"	2,602	108	9"	3'-0"	216	216	9"	4'-7"	661	7'-3"	1,046	28'-3"	75	60	167	1.796	350.8	2.1	242	73.9	14,274
6	5'-0"	3'-0"	8"	7"	108	#6	9"	33'-10"	5,488	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	116	18"	39'-9"	3,080	108	9"	3'-0"	216	270	9"	4'-7"	827	7'-3"	1,308	33'-10"	90	70	195	2.137	414.5	2.5	285	88.0	16,863
2	5'-0"	4'-0"	8"	7"	108	#6	9"	11'-6"	1,865	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	44	18"	39'-9"	1,168	108	9"	4'-0"	289	54	9"	4'-7"	165	9'-3"	334	11'-6"	31	26	72	0.840	166.3	0.9	103	34.5	6,754
3	5'-0"	4'-0"	8"	7"	108	#6	9"	17'-1"	2,771	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	62	18"	39'-9"	1,646	108	9"	4'-0"	289	108	9"	4'-7"	331	9'-3"	667	17'-1"	46	38	106	1.202	231.8	1.3	152	49.4	9,422
4	5'-0"	4'-0"	8"	7"	108	#6	9"	22'-8"	3,677	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	80	18"	39'-9"	2,124	108	9"	4'-0"	289	162	9"	4'-7"	496	9'-3"	1,001	22'-8"	61	48	134	1.564	297.2	1.7	195	64.3	12,083
5	5'-0"	4'-0"	8"	7"	108	#6	9"	28'-3"	4,583	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	98	18"	39'-9"	2,602	108	9"	4'-0"	289	216	9"	4'-7"	661	9'-3"	1,335	28'-3"	75	60	167	1.926	362.7	2.1	242	79.1	14,748
6	5'-0"	4'-0"	8"	7"	108	#6	9"	33'-10"	5,488	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	116	18"	39'-9"	3,080	108	9"	4'-0"	289	270	9"	4'-7"	827	9'-3"	1,668	33'-10"	90	70	195	2.288	428.1	2.5	285	94.0	17,408
2	5'-0"	5'-0"	8"	7"	108	#6	9"	11'-6"	1,865	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	50	18"	39'-9"	1,328	108	9"	5'-0"	361	54	9"	4'-7"	165	11'-3"	406	11'-6"	31	26	72	0.904	176.7	0.9	103	37.0	7,171
3	5'-0"	5'-0"	8"	7"	108	#6	9"	17'-1"	2,771	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	70	18"	39'-9"	1,859	108	9"	5'-0"	361	108	9"	4'-7"	331	11'-3"	812	17'-1"	46	38	106	1.288	245.3	1.3	152	52.8	9,965
4	5'-0"	5'-0"	8"	7"	108	#6	9"	22'-8"	3,677	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	90	18"	39'-9"	2,390	108	9"	5'-0"	361	162	9"	4'-7"	496	11'-3"	1,217	22'-8"	61	48	134	1.672	313.9	1.7	195	68.6	12,750
5	5'-0"	5'-0"	8"	7"	108	#6	9"	28'-3"	4,583	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	110	18"	39'-9"	2,921	108	9"	5'-0"	361	216	9"	4'-7"	661	11'-3"	1,623	28'-3"	75	60	167	2.056	382.5	2.1	242	84.3	15,540
6	5'-0"	5'-0"	8"	7"	108	#6	9"	33'-10"	5,488	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	130	18"	39'-9"	3,452	108	9"	5'-0"	361	270	9"	4'-7"	827	11'-3"	2,029	33'-10"	90	70	195	2.439	451.0	2.5	285	100.1	18,326

HL93 LOADING SHEET 2 OF 2

**Bridge Division Standard**


## MULTIPLE BOX CULVERTS CAST-IN-PLACE 5'-0" SPAN 0' TO 20' FILL

### MC-5-20

FILE: mc520ste-20.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>	
DIST	COUNTY	SHEET NO.		
<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>70</b>		

DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information to any other standard or format. This standard is not intended to be used as a basis for litigation. © TEXAS DEPARTMENT OF TRANSPORTATION, 2018


DATE: 7/28/2023 11:23:40 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Saftey Treat 0045-09-116\Design\CAD Standards\CAD Standards\STANDARD\STANDARD.dwg




**TYPICAL SECTION**

Used for curbs over 1'-0" to 5'-0"


**BARS V (#5)**  
 Spaced at 12" Max



**BARS L (#5)**  
 Spaced at 12" Max



**OPTIONAL BARS L (#5)**  
 Spaced at 12" Max



**BARS U (#4)**  
 Spaced at 12" Max

- ① "C" is equal to the culvert top slab thickness. For precast boxes with slabs less than 8" thick, see SCP-MD standard for additional details.
- ② Adjust normal culvert slab bars as necessary to clear obstructions.
- ③ Place bars L as shown. Tilt hook as necessary to maintain cover.
- ④ Place normal culvert curb bars H(#4) as shown. Adjust as necessary to clear obstructions.
- ⑤ Additional bars H(#4) as required to maintain 12" Max spacing.
- ⑥ Replace normal culvert curb bars K with one bar U and two bars V as shown spaced at 12" Max. Adjust length of bars V as necessary to maintain clear cover.
- ⑦ Optional bars L are to be used only for precast box culverts with 3'-0" closure pour.
- ⑧ Quantities shown are for Contractor's information only. Quantities are per linear foot of curb length. The value in table can be interpolated for intermediate values of curb height, "C". Quantity includes bars K (when applicable).

TABLE OF ESTIMATED CURB QUANTITIES ⑧		
Curb Height "C"	Conc (CY/LF)	Reinf Steel (Lb/LF)
1'-0"	0.037	10.4
1'-6"	0.056	14.5
2'-0"	0.074	15.6
2'-6"	0.093	18.0
3'-0"	0.111	19.0
3'-6"	0.130	21.3
4'-0"	0.148	22.4
4'-6"	0.167	24.8
5'-0"	0.185	25.9

**CONSTRUCTION NOTES:**

- Adjust reinforcing steel as necessary to provide 1/4" cover.
- For vehicle safety, top of the curb must not project more than 3" above the finished grade.

**MATERIAL NOTES:**

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class "C" concrete ( $f_c = 3,600$  psi) minimum for curbs.
- Provide bar laps, where required, as follows:
  - Uncoated or galvanized ~ #4 = 1'-8" Min

**GENERAL NOTES:**

- Designed according to AASHTO LRFD Bridge Design Specifications.
- These extended curb details have sufficient strength to allow for future retrofit of Type T631 or T631LS railing.
- These details are suitable for use with PR11, PR22 and PR3 type rails. These details are not suitable for the mounting of other rail types. For new construction using T631 or T631LS railing, use the T631-CM standard.
- This Curb is considered as part of the Box Culvert for payment.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing bar dimensions shown are out-to-out of bar.

**EXTENDED CURB DETAILS**  
 FOR BOX CULVERTS WITH CURBS OVER 1'-0" TO 5'-0" TALL

**ECD**

FILE: ecdstd1-20.dgn	DN: GAF	CK: TxDOT	DW: TxDOT	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>	
DIST	COUNTY	SHEET NO.		
<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>71</b>		

DATE: 7/28/2023 11:23:41 AM  
 FILE: I:\PARISAD\DESIGN\US\_82\_E\_Saftey\_Treet\_0045-09-116\Design\CAD\_Standards\DRAINAGE\STANDARDS\STANDARD\STANDARD.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.

**TABLE OF DIMENSIONS AND REINFORCING STEEL**  
(Wings for one structure end)




Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings) ④	Estimated Quantities per ft of Toewall (1-toewall)		
	W	X	Y	Z	Bars J1		Bars J2					
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

**TABLE OF WINGWALL REINFORCING**  
(2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

**TABLE OF TOEWALL REINFORCING**

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



**WING DIMENSION FORMULAS:**  
(All values are in feet.)







$Hw = H + T + C$   
 $Lw = (Hw)(SL) + \text{cosine}(\theta)$  for Type PW-1  
 $= (Hw - 1')(SL) + \text{cosine}(\theta)$  for Type PW-2 and  $Hw \ge 4'$   
 $= (Hw - 0.5')(SL) + \text{cosine}(\theta)$  for Type PW-2 and  $Hw < 4'$

For cast-in-place culverts:  
 $Ltw = [(N)(S) + (N + 1)(U)] + \text{cosine}(\theta)$

For precast culverts:  
 $Ltw = [(N)(2U + S) + (N - 1)(0.5')] + \text{cosine}(\theta)$   
 Total Wingwall Area (two wings ~ SF)  
 $= (2)(Hw)(Lw)$  for Type PW-1  
 $= (2)(Hw)(Lw) - 6 \text{ SF}$  for Type PW-2 and  $Hw \ge 4'$   
 $= (2)(Hw)(Lw) - 1.5 \text{ SF}$  for Type PW-2 and  $Hw < 4'$

$Hw$  = Height of wingwall  
 $Lw$  = Length of wingwall  
 $Ltw$  = Culvert toewall length  
 $N$  = Number of culvert spans  
 $SL:1$  = Channel slope ratio. (horizontal: 1 vertical, usual value is 2:1)  
 $\theta$  = Culvert skew  
 See applicable box culvert standard sheet for S, H, T, and U values.

- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"  
For 30° skew ~ 2"  
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.



**DESIGNER NOTES:**  
 Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall. Type PW-2 can only be used for applications without a railing mounted to the wingwall.

**MATERIAL NOTES:**  
 Provide Class C concrete (f'c=3,600 psi).  
 Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.

**GENERAL NOTES:**  
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.  
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.  
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information.  
 Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing dimensions are out-to-out of bars.

Bridge Division Standard

**CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2**


**PW**

FILE: pwside01-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
	0045	09	116, ETC.	US 82
	DIST	COUNTY	SHEET NO.	
	PAR	LAMAR, ETC.	72	

CROSS PIPE LENGTHS AND PIPE RUNNER LENGTHS

① ②

Nominal Culvert I.D.	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length											
			3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
			0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
24"	1' - 7"	3' - 5"	N/A	N/A	N/A	5' - 10"	N/A	N/A	N/A	8' - 1"	N/A	N/A	N/A	12' - 9"
27"	1' - 8"	3' - 8"	N/A	N/A	5' - 5"	6' - 11"	N/A	N/A	7' - 7"	9' - 7"	N/A	N/A	11' - 11"	14' - 11"
30"	1' - 10"	3' - 11"	N/A	N/A	6' - 4"	8' - 0"	N/A	N/A	8' - 9"	11' - 0"	N/A	N/A	13' - 8"	17' - 0"
33"	1' - 11"	4' - 2"	6' - 2"	6' - 5"	7' - 3"	9' - 1"	8' - 6"	8' - 10"	10' - 0"	12' - 5"	13' - 3"	13' - 9"	15' - 5"	19' - 2"
36"	2' - 1"	4' - 5"	6' - 11"	7' - 3"	8' - 2"	10' - 2"	9' - 6"	9' - 11"	11' - 2"	13' - 10"	14' - 9"	15' - 3"	17' - 2"	21' - 3"
42"	2' - 4"	4' - 11"	8' - 6"	8' - 10"	9' - 11"	12' - 4"	11' - 7"	12' - 0"	13' - 6"	16' - 8"	17' - 9"	18' - 5"	20' - 8"	25' - 7"
48"	2' - 7"	5' - 5"	10' - 1"	10' - 5"	11' - 9"	N/A	13' - 7"	14' - 2"	15' - 10"	N/A	20' - 9"	21' - 6"	24' - 2"	N/A
54"	3' - 0"	5' - 11"	11' - 8"	12' - 1"	N/A	N/A	15' - 8"	16' - 3"	N/A	N/A	23' - 10"	24' - 8"	N/A	N/A
60"	3' - 3"	6' - 5"	13' - 3"	N/A	N/A	N/A	17' - 9"	N/A	N/A	N/A	26' - 10"	N/A	N/A	N/A



NOTE: All pipe runners, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER

(Showing corrugated metal pipe (CMP) culvert. Details of reinforced concrete pipe (RCP) culvert are similar.)

TYPICAL PIPE CULVERT MITERS

Side Slope	0° Skew	15° Skew	30° Skew	45° Skew
3:1	3:1	3.106:1	3.464:1	4.243:1
4:1	4:1	4.141:1	4.619:1	5.657:1
6:1	6:1	6.212:1	6.928:1	8.485:1

CONDITIONS WHERE PIPE RUNNERS ARE NOT REQUIRED

Nominal Culvert I.D.	Single Pipe Culvert	Multiple Pipe Culverts
12" thru 21"	Skews thru 45°	Skews thru 45°
24"	Skews thru 45°	Skews thru 30°
27"	Skews thru 30°	Skews thru 15°
30"	Skews thru 15°	Skews thru 15°
33"	Skews thru 15°	Always required
36"	Normal (no skew)	Always required
42" thru 60"	Always required	Always required

STANDARD PIPE SIZES AND MAX PIPE RUNNER LENGTHS



Pipe Size	Pipe O.D.	Pipe I.D.	Max Pipe Runner Length
2" STD	2.375"	2.067"	N/A
3" STD	3.500"	3.068"	10' - 0"
4" STD	4.500"	4.026"	19' - 8"
5" STD	5.563"	5.047"	34' - 2"

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY)

Nominal Culvert I.D.	3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
12"	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.6	0.7	0.7	0.7	0.8
15"	0.5	0.5	0.5	0.6	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9
18"	0.5	0.5	0.6	0.6	0.6	0.7	0.7	0.8	0.8	0.8	0.9	1.0
21"	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9	0.9	0.9	1.0	1.2
24"	0.6	0.7	0.7	0.8	0.8	0.8	0.8	1.0	1.0	1.0	1.1	1.3
27"	0.7	0.7	0.8	0.9	0.8	0.9	0.9	1.1	1.1	1.1	1.2	1.4
30"	0.8	0.8	0.8	0.9	0.9	0.9	1.0	1.2	1.2	1.2	1.3	1.6
33"	0.8	0.8	0.9	1.0	1.0	1.0	1.1	1.3	1.3	1.4	1.5	1.7
36"	0.9	0.9	0.9	1.1	1.1	1.1	1.2	1.4	1.4	1.5	1.6	1.8
42"	1.0	1.0	1.1	1.3	1.2	1.3	1.3	1.6	1.6	1.7	1.8	2.1
48"	1.1	1.1	1.2	N/A	1.4	1.4	1.5	N/A	1.9	1.9	2.1	N/A
54"	1.3	1.3	N/A	N/A	1.6	1.6	N/A	N/A	2.1	2.1	N/A	N/A
60"	1.4	N/A	N/A	N/A	1.7	N/A	N/A	N/A	2.3	N/A	N/A	N/A

SIDE ELEVATION OF CAST-IN-PLACE CONCRETE

(Showing reinforced concrete pipe (RCP) culvert. Details of corrugated metal pipe (CMP) culvert are similar. Pipe runners not shown for clarity)



ISOMETRIC VIEW OF TYPICAL INSTALLATION

(Showing installation with no skew.)

① Provide pipe runner of the size shown in the tables. Provide cross pipe of the same size as the pipe runner. Provide cross pipe stub out and bottom anchor pipe of the next smaller size pipe as shown in the Standard Pipe Sizes and Max Pipe Runner Lengths table.

② This standard allows for the placement of only one pipe runner across each culvert pipe opening. In order to limit the clear opening to be traversed by an errant vehicle, the following conditions must be met:

For 60" culvert pipes, the skew must not exceed 0°.  
 For 54" culvert pipes, the skew must not exceed 15°.  
 For 48" culvert pipes, the skew must not exceed 30°.  
 For all culvert pipe sizes 42" and less, the skew must not exceed 45°.

If the above conditions cannot be met, the designer should consider using a safety end treatment with flared wings. For further information, refer to the TxDOT Roadway Design Manual.

③ Miter = slope of mitered end of pipe culvert.

④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".

⑤ Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only.

SHEET 1 OF 2




SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE

SETP-CD


FILE: setpdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
DIST	COUNTY		SHEET NO.	
PAR	LAMAR, ETC.		73	

DATE: 7/28/2023 11:23:41 AM  
 FILE: I:\PARISAD\DESIGN\US\_82\_E\_Saf.tey\_Treet\_0045-09-116\Design\CAD\_Standards\Drainage\SETP-CD.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented. © 2020 TEXAS DEPARTMENT OF TRANSPORTATION

DATE: 7/28/2023 11:23:42 AM  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Saf.tty  
 T:\045-09-116\Design\CAD\_Standards\DRAINAGE\SETP-CD.dwg  
 STANDARD: 0045-09-116  
 DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.




**CROSS PIPE AND CONNECTIONS DETAILS**




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

**PIPE RUNNER DETAILS**




**BOTTOM ANCHOR PIPE DETAILS**




**BOTTOM ANCHOR TOEWALL DETAILS**

(Culvert and riprap not shown for clarity.)




**SIDE ELEVATION OF SAFETY END TREATMENT INSTALLATION**


(Showing pipe runner with Cross Pipe Connection Option A1 and Anchor Pipe Option B2 on corrugated metal pipe (CMP) culvert. Reinforced concrete pipe culvert (RCP) details are similar. Riprap not shown for clarity)



**PLAN OF SKEWED INSTALLATION**



**SHOWING CROSS PIPE AND ANCHOR TOEWALL**



**SHOWING TYPICAL PIPE CULVERT AND RIPRAP**

**SECTION A-A**

- ④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- ⑥ Recommended values of side slope are 3:1, 4:1, and 6:1. All quantities, calculations, and dimensions shown herein are based on these recommended values. Slope of 3:1 or flatter is required for vehicle safety.
- ⑦ Note that actual slope of pipe runner may vary slightly from side slope of riprap and trimmed culvert pipe edge.
- ⑧ Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1/2 inch hole to ensure that the lap of the pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.


**MATERIAL NOTES:**  
 Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Provide pipe runners, cross pipes, and anchor pipes conforming to the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
 Provide ASTM A307 bolts and nuts.  
 Galvanize all steel components, except concrete reinforcing, after fabrication.  
 Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**  
 Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.  
 Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.  
 Payment for riprap and toewall is included in the price bid for each safety end treatment.  
 Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap".

SHEET 2 OF 2

		<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT</b> FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE			
<b>SETP-CD</b>			
FILE: setpdse-20.dgn	DN: GAF	CK: CAT	DW: JRP
©TxDOT February 2020	CONT: 09	SECT: 116, ETC.	HIGHWAY: US 82
DIST: PAR	COUNTY: LAMAR, ETC.	SHEET NO. 74	


DATE: 7/28/2023 11:23:42 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\DRAINAGE\SETP-PD.dwg  
 STANDARD: 0045-09-116  
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.




NOTE: All cross pipes, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

**SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER**

(Showing corrugated metal pipe (CMP) culvert. Details at reinforced concrete pipe (RCP) culvert are similar.)




**ISOMETRIC VIEW OF TYPICAL INSTALLATION**




**SIDE ELEVATION OF CAST-IN-PLACE CONCRETE**


(Showing reinforced concrete pipe (RCP) culvert. Details at corrugated metal pipe (CMP) culvert are similar.)



**PIPE WITH BOLTED ANCHOR**




**PIPE WITH ANCHOR BARS**




**SECTION C-C**

**CROSS PIPE DETAILS**



**DETAIL "A"**


(Showing invert with corrugated metal pipe (CMP) culvert. Reinforced concrete pipe (RCP) culvert details are similar. Cross pipes not shown for clarity.)




**SECTION B-B**

(Cross pipes not shown for clarity.)


Limits of riprap (to be included with SET for payment)



**SHOWING TYPICAL PIPE CULVERT AND RIPRAP**



**SHOWING CROSS PIPE WITH ANCHOR BAR**



**SHOWING CROSS PIPE WITH BOLTED ANCHOR**

**SECTION A-A**

**CROSS PIPE LENGTHS, REQUIRED PIPE SIZES, AND RIPRAP QUANTITIES**

Nominal Culvert I.D.	Conc Riprap (CY) (6)	Pipe Culvert Spa ~ G	Single Barrel ~ Q1	Multi-Barrel ~ Q1	Q2	Conditions for Use of Cross Pipes	Cross Pipe Sizes
12"	0.6	0' - 9"	N/A	2' - 1"	1' - 9"	3 or more pipe culverts	3" Std (3.500" O.D.)
15"	0.7	0' - 11"	N/A	2' - 5"	2' - 2"		
18"	0.8	1' - 2"	N/A	2' - 10"	2' - 8"		
21"	0.9	1' - 4"	N/A	3' - 2"	3' - 1"	3 or more pipe culverts	3 1/2" Std (4.000" O.D.)
24"	0.9	1' - 7"	N/A	3' - 6"	3' - 7"		
27"	1.0	1' - 8"	N/A	3' - 10"	3' - 11"	2 or more pipe culverts	3 1/2" Std (4.000" O.D.)
30"	1.1	1' - 10"	N/A	4' - 2"	4' - 4"	All pipe culverts	
33"	1.2	1' - 11"	4' - 2"	4' - 5"	4' - 8"	All pipe culverts	4" Std (4.500" O.D.)
36"	1.3	2' - 1"	4' - 5"	4' - 9"	5' - 1"		
42"	1.5	2' - 4"	4' - 11"	5' - 5"	5' - 10"	All pipe culverts	5" Std (5.563" O.D.)
48"	1.7	2' - 7"	5' - 5"	6' - 0"	6' - 7"		
54"	2.0	3' - 0"	5' - 11"	6' - 9"	7' - 6"	All pipe culverts	5" Std (5.563" O.D.)
60"	2.2	3' - 3"	6' - 5"	7' - 4"	8' - 3"		
66"	2.4	3' - 3"	6' - 11"	7' - 10"	8' - 9"		
72"	2.7	3' - 4"	7' - 5"	8' - 5"	9' - 4"		

- The proper installation of the first cross pipe is critical for vehicle safety. Place the top of the first cross pipe no more than 6" above the flow line.
- Provide cross pipes, except the first bottom pipe, of the size shown in the table. Provide a 3 1/2" standard pipe (4" O.D.) for the first bottom pipe.
- Install the third cross pipe from the bottom of the culvert using a bolted connection. Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access. At the Contractor's option, install all other cross pipes using the bolted connection details.
- Match cross slope as shown elsewhere in the plans. Cross slope of 6:1 or flatter is required for vehicle safety.
- Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for contractor's information only.

**MATERIAL NOTES:**

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. Provide cross pipes that meet the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 (Gr B), or API 5LX52. Provide ASTM A307 bolts and nuts. Galvanize all steel components, except concrete reinforcing, after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**

Cross pipes are designed for a traversing load of 10,000 pounds at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981. Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the cross pipes. Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap". Payment for riprap and toewall is included in the Price Bid for each Safety End Treatment.

**Bridge Division Standard**

**SAFETY END TREATMENT**  
FOR 12" DIA TO 72" DIA  
PIPE CULVERTS  
TYPE II ~ PARALLEL DRAINAGE

**SETP-PD**

FILE: setppdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT	REVISIONS	CON: SECT	JOB	HIGHWAY
		<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>
		DIST	COUNTY	SHEET NO.
		<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>75</b>




# REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness (8)	"D" (1)	Slope	Min Length of Unit	Single Pipe		Multiple Pipes	
						Skew	Pipe Runners Required	Skew	Pipe Runners Required
12"	2"	1.15"	17.00"	3:1	2' - 11"	≤ 45°	No	≤ 45°	No
				4:1	3' - 6"				
				6:1	4' - 9"				
15"	2 1/4"	1.30"	20.50"	3:1	3' - 8"	≤ 45°	No	≤ 45°	No
				4:1	4' - 7"				
				6:1	6' - 5"				
18"	2 1/2"	1.60"	24.00"	3:1	4' - 6"	≤ 45°	No	≤ 45°	No
				4:1	5' - 8"				
				6:1	8' - 0"				
24"	3"	1.95"	31.00"	3:1	6' - 2"	≤ 45°	No	= 30°	No
				4:1	7' - 10"				
				6:1	11' - 3"				
30"	3 1/2"	2.65"	38.50"	3:1	7' - 10"	= 15°	No	= 15°	No
				4:1	10' - 1"				
				6:1	14' - 8"				
36"	4"	2.75"	45.50"	3:1	9' - 5"	= 0°	No	≥ 0°	Yes
				4:1	12' - 3"				
				6:1	17' - 11"				
42"	4 1/2"	2.7"	52.50"	3:1	11' - 1"	≥ 0°	Yes	≥ 0°	Yes
				4:1	14' - 5"				
				6:1	21' - 2"				

# SAFETY PIPE RUNNER DIMENSIONS


Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"



Pocket is to be formed to fit O.D. of pipe support post if safety pipe runners are used.

### PLAN

(Showing bell end connection.)



### LONGITUDINAL ELEVATION

(Showing bell end connection.)

- Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- Slope as shown elsewhere in plans. Slope of 3:1 or flatter is required for vehicle safety.
- Toewall to be used only when dimension is shown elsewhere in the plans.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- Measured along slope.
- Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

### GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".

When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.

Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:

A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).

B. For precast (steel formed) sections, provide Class "C" concrete (f<sub>c</sub> = 3,600 psi).


At the option and expense of the Contractor, the next larger size of safety end treatment may be furnished as long as the "D" dimension cast is that of the required size of pipe.

Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.

Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.


Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464 "Reinforced Concrete Pipe". Connect TP by grouting. See Pipe and Box Grouted Connections (PBGC) standard for grouted connections with TP and precast safety end treatment.




### END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS

(If required)




### OPTIONAL JOINT FOR RCP

(Showing joint between RCP and precast safety end treatment)




### OPTION A




### OPTION B

### DETAIL A


(If required)




### MULTIPLE PIPE INSTALLATION



### OPTION WITH SQUARE BOTTOM



### OPTION WITH INVERT BOTTOM



### INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS

(If required)

### SECTION A-A

Bridge Division Standard

## PRECAST SAFETY END TREATMENT


### TYPE II ~ CROSS DRAINAGE

### PSET-SC

FILE: psetscs-21.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
© TXDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
12-21: Added 42" TP	DIST	COUNTY	SHEET NO.	
	PAR	LAMAR, ETC.	76	


DATE: 7/28/2023 11:23:42 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\DRAINAGE\DETAILS\STANDARDS\PRECAST SAFETY END TREATMENT\0045-09-116.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of units or for any errors or omissions resulting from its use.

DATE: 7/28/2023 11:23:43 AM  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\STANDARDS\STANDARDS.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.




**PLAN**

(Showing bell end connection.)




**LONGITUDINAL ELEVATION**

(Showing bell end connection.)




**INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS**

(If required)




**OPTION A**




**OPTION B**

**END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS**

(If required)




**MULTIPLE PIPE INSTALLATION**




**SECTION A-A**

OPTION WITH SQUARE BOTTOM



**OPTION WITH INVERT BOTTOM**



**OPTIONAL JOINT FOR RCP**

(Showing joint between RCP and precast safety end treatment.)

**REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS**

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness	"D"	Slope	Min Length	Pipe Runners Required		Required Pipe Runner Size		
						Single Pipe	Multiple Pipe	Nominal Dia.	O.D.	I.D.
12"	2"	1.15"	17.00"	6:1	4' - 9"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
15"	2 1/4"	1.30"	20.50"	6:1	6' - 5"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
18"	2 1/2"	1.60"	24.00"	6:1	8' - 0"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
24"	3"	1.95"	31.00"	6:1	11' - 3"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
30"	3 1/2"	2.65"	38.50"	6:1	14' - 8"	No	Yes	4" STD	4.500"	4.026"
36"	4"	2.75"	45.50"	6:1	17' - 11"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	2.7"	52.50"	6:1	21' - 2"	Yes	Yes	4" STD	4.500"	4.026"

- Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- Toewall to be used only when dimension is shown elsewhere in the plans.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

**GENERAL NOTES:**

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".

When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.

Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:

A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).

B. For precast (steel formed) sections, provide Class "C" concrete (f'c = 3,600 psi).

At the option and expense of the Contractor the next larger size of safety end treatment may be furnished; as long as the "D" dimension cast is that of the required size of pipe.

Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.

Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.

Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464, "Reinforced Concrete Pipe". Connect TP by grouting. See Pipe and Box Grouted Connections (PBGC) standard for grouted connections with TP and precast safety end treatment.

**Bridge Division Standard**





**PRECAST SAFETY END TREATMENT**  
TYPE II ~ PARALLEL DRAINAGE

**PSET-SP**

FILE: psetspss-21.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0045 09</b>	<b>116, ETC.</b>	<b>US 82</b>	
12-21: Added 42" TP	DIST	COUNTY	SHEET NO.	
	<b>PAR</b>	<b>LAMAR, ETC.</b>	<b>77</b>	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information resulting from its use.

DATE: 7/28/2023 11:23:43 AM  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Saf.tey\_Treeet\_0045-09-116\Design\CAD\_Standards\STANDARD\STANDARD.dwg



SECTION A-A

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY)								
Nominal Culvert (Pipe) I.D.	PSET-SC and PSET-SP Standards				PSET-RC and PSET-RP Standards			
	Unit Width "W"	Side Slope			Unit Width "W"	Side Slope		
		3:1	4:1	6:1		3:1	4:1	6:1
12"	23.0"	0.1	0.2	0.2	16.0"	0.1	0.1	0.2
15"	26.5"	0.2	0.2	0.3	19.5"	0.1	0.2	0.2
18"	30.0"	0.2	0.2	0.3	23.0"	0.2	0.2	0.3
24"	37.0"	0.3	0.3	0.5	30.0"	0.2	0.3	0.4
30"	44.5"	0.3	0.4	0.6	37.0"	0.3	0.3	0.5
36"	51.5"	0.4	0.5	0.7	44.0"	0.3	0.4	0.6
42"	58.5"	0.5	0.6	0.8	51.0"	0.4	0.5	0.7

- Riprap placed beyond the limits shown will be paid as concrete riprap in accordance with Item 432, "Riprap". When riprap is cast integrally with the precast safety end treatment, this dimension is 1'-0" minimum.
- 1#2" Dia ASTM A307 Gr A threaded anchor rod with 2 nuts and 2 washers. Galvanize all components in accordance with Item 445, "Galvanizing". Repair galvanizing that is damaged during transport or construction in accordance with the specifications.
- 3/4" through holes in walls of safety end treatment for riprap anchor rods may be drilled with rotary (coring or masonry) type drilling equipment or may be formed. Do not use percussive (star) type drilling equipment. If holes are drilled, patch spalls in the inside face of the wall exceeding 1#2" from the holes.
- Provide riprap toe wall when dimension is shown elsewhere in the plans or when field conditions require a toe wall.
- Quantities shown are for one end of one reinforced concrete pipe culvert. For multiple pipe culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only. Quantities are based on the minimum unit lengths shown on the Precast Safety End Treatment (SET) standard sheets.

**MATERIAL NOTES:**  
 Provide Class "B" riprap in accordance with Item 432, "Riprap". Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. The anchor rods shown are always required.

**GENERAL NOTES:**  
 Precast safety end treatment for reinforced concrete pipe may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment". Refer to PSET-SC or PSET-SP standard sheets for details of square safety end treatments not shown. Refer to PSET-RC or PSET-RP standard sheets for details of round safety end treatments not shown. For precast units with integrally cast riprap, substitute reinforcing steel in the amount on 0.26 in./ft. minimum for the threaded anchor rods shown. When requested, submit sealed engineering drawings for approval prior to construction. Shop drawings will not be required. Note that a proprietary precast unit with integral riprap is available from L&R Precast Concrete Works, Inc. (956) 583-6293 or www.lrpccast.com. Payment for riprap and toewalls is included in the price bid for each safety end treatment.

These riprap details are only applicable when notes that require placement of riprap with precast safety end treatments are shown elsewhere in the plans.  
 Precast units with integrally cast riprap are permitted unless noted otherwise on the plans.

				Bridge Division Standard	
<b>PRECAST SAFETY END TREATMENT TYPE II RIPRAP DETAILS</b> <b>PSET-RR</b>					
FILE:	psetrrse-20.dgn	DN:	GAF	CK:	TxDOT
©TxDOT	February 2020	CON:	SECT	JOB:	HIGHWAY
REVISIONS		0045	09	116, ETC.	US 82
DIST:	PAR	COUNTY:	LAMAR, ETC.	SHEET NO.:	78

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treeet\_0045-09-116\Design\CAD\_Standards\PAVEMENT\PROJECT\REFLECTOR\REFLECTOR.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion or damages resulting from its use.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required Bi = Bi-Directional BR = Bi-Directional with red on back
SHEETING	Yellow, White or Red Type B or C reflective sheeting				SHEETING Yellow, White or Red Type B or C Reflective Sheeting				
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF

OBJECT MARKERS								D & OM DESCRIPTIVE CODES	
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)	INSTL OM ASSM (OM-XX) (XXXX)XXX(XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required Bi = Bi-Directional
SHEETING	Yellow-Type B or C Sheeting FL	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B or C Sheeting			Red -Type B or C Sheeting	
POST TYPE	TWT	WC	WC	WFLX	TWT			TWT	
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP	

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.		
DEVICE	GF1	GF2	CTB								
	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
				MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only		MOUNTING HEIGHT	7'-0"	
NOTE	1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).							
SHEETING	Yellow, White, Red										

Texas Department of Transportation  
 Traffic Safety Division Standard












### DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION


#### D & OM(1)-20

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	PAR	LAMAR, ETC.	79	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions, or damages resulting from its use.

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS		
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT	
GND	GND	SRF	WAS	WAP	GF1	
						
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC	
<b>NOTES</b> 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.		<b>NOTES</b> 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		<b>NOTE</b> 1. Install per manufacturer's recommendations.		<b>GENERAL NOTES</b> 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.
<b>TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS</b>		<b>CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN</b>		<b>DELINEATORS AND TYPE 2 OBJECT MARKERS</b>		
						
<b>NOTE</b> Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		<b>NOTE</b> Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		See general notes 1, 2 and 3.		


 Texas Department of Transportation  
 Traffic Safety Division Standard

## DELINEATOR & OBJECT MARKER INSTALLATION

### D & OM(2)-20


FILE: dom2-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82	
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	PAR	LAMAR, ETC.	80	

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD Standards\PAVEMENT\PROJECT\NEW\PROJECTING\2023\2023-08-15\TXDOT\TXDOT.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard.

### MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS


Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons

### SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



**NOTE**  
 ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

### SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



**NOTE**  
 At least one chevron pair is installed beyond the point of tangent in tangent section.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

### DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Fwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Fwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Fwy./Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MGBF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

#### NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation  
Traffic Safety Division Standard

## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS


### D & OM(3)-20

FILE: dom3-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045 09	116, ETC.	US 82	
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	PAR	LAMAR, ETC.	81	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from any source into any format or for any damages resulting from its use.


DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD\_Standards\PAVE\PAVE\PAVE\PROJECT\NEW\PROJECT\0045-09-116\0045-09-116.dgn

**CROSSOVERS**




**DETAIL 1**

**FOR CULVERTS WITHOUT MBGF**




**DETAIL 2**

**FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES**




**DETAIL 3**

**TYPICAL APPLICATION OF DEAD END BARRICADE**



**DETAIL 4**

**TYPICAL DEAD END BARRICADE INSTALLATION**



**NOTES**

1. Barricade striping shall be red and white reflective sheeting for all permanent road closures.
2. Barricade striping is red and white sloping toward the center of the roadway.
3. Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

**DETAIL 5**

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator



**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(4)-20**

FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
3-15	DIST	COUNTY		SHEET NO.
7-20	PAR	LAMAR, ETC.		82





**CONTINUOUS CONCRETE OR STEEL BARRIER**





**MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)**

**DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)**

**EMERGENCY CROSSOVER**

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions, or damages resulting from its use.

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treet\_0045-09-116\Design\CAD\_Standards\PAVEMENT\PROJECT\NEW\PROJECT\0045-09-116\0045-09-116.dgn



**NOTES**

1. Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delineators. On Continuous Barrier, equal spacing (100' max.)
2. Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delineators.
3. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**LEGEND**

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow








**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(6)-20**



FILE: dom6-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
7-20	0045	09	116, ETC.	US 82
DIST	COUNTY	SHEET NO.		
PAR	LAMAR, ETC.	84		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units or for any damages resulting from its use.

DATE: 7/28/2023  
 FILE: T:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treeet\_0045-09-116\Design\CAD\_Standards\PAVE\MARKING\INCORPORATING\PROJECT\NEW\PROJECT\0045\09\01\01.dwg



OBJECT MARKERS SMALLER THAN 3 FT<sup>2</sup>



- NOTES**
1. Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
  2. Mounting should be flush with top of attenuator. Minimum size 96" x 24".


**NOTES**

1. Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
2. Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
3. Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
4. Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
5. Object Marker at nose of attenuator is subsidiary to the attenuator.
6. See D & OM (1-4) for required barrier reflectors.


		Traffic Safety Division Standard	
<b>DELINEATOR &amp; OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</b> <b>D &amp; OM(VIA)-20</b>			
FILE: _domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT	SECT	JOB
REVISIONS		0045 09	116, ETC.
4-92 8-04	DIST		COUNTY
8-95 3-15	PAR		LAMAR, ETC.
4-98 7-20	HIGHWAY		US 82
			SHEET NO.
			85
20G			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:





**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**





**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**



**YIELD LINES**



**NOTES**


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

**GENERAL NOTES**

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**  
Based on Traveled Way and Pavement Widths for Undivided Roadways



**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

Texas Department of Transportation  
Traffic Safety Division Standard

**TYPICAL STANDARD PAVEMENT MARKINGS**


**PM(1)-22**

FILE: pml-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
11-78 8-00 6-20	DIST	COUNTY		SHEET NO.
8-95 3-03 12-22	PAR	LAMAR, ETC.		86
5-00 2-12				


22A

# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS**




**CENTERLINE & LANE LINES  
FOR FOUR LANE TWO-WAY ROADWAYS**




**DETAIL "A"**

**DETAIL "B"**

**DETAIL "C"**




**CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE**




**LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)**

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.  
See Note 3.




CENTER OR EDGE LINE (see note 1)

BROKEN LANE LINE



6" EDGE LINE, 6" CENTERLINE  
OR 6" LANE LINE

**REFLECTORIZED PROFILE  
PATTERN DETAIL**  
USING REFLECTIVE PROFILE PAVEMENT MARKINGS



A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

**NOTES**


- Edge lines should typically be 6" wide and the materials shall be specified in the plans.
- Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

**GENERAL NOTES**


- All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
- Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**Type I (Top View)**



**Type II (Top View)**



**SECTION A**

**RAISED PAVEMENT MARKERS**



**POSITION GUIDANCE USING  
RAISED MARKERS  
REFLECTORIZED PROFILE  
MARKINGS  
PM(2)-22**

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0045	09	116, ETC.	US 82
4-77 8-00 6-20	DIST	COUNTY	SHEET NO.	
4-92 2-10 12-22	PAR	LAMAR, ETC.	87	
5-00 2-12				

DATE:  
FILE:

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**  
0045-09-116, ETC.

**1.2 PROJECT LIMITS:**

From: LOOP 286

To: BOWIE COUNTY LINE

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 33.6615083, (Long) 95.50978889

END: (Lat) 33.55436111, (Long) 94.74607222

**1.4 TOTAL PROJECT AREA (Acres):** 681

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** 4.02

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

CONSTRUCTION OF SAFETY END TREATMENTS AND GUARDRAIL

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
FREESTONE HICOTA COMPLEX	0 TO 3 PERCENT SLOPES MODERATELY WELL DRAINED
ANNOVA - FREESTONE COMPLEX	1 TO 3 PERCENT SLOPES MODERATELY WELL DRAINED
DEPORT CLAY	1 TO 3 PERCENT SLOPES SOMEWHAT POORLY DRAINED
HOUSTON BLACK CLAY	1 TO 3 PERCENT SLOPES MODERATELY WELL DRAINED
KULLIT - ADDIELOU COMPLEX	1 TO 3 PERCENT SLOPES MODERATELY WELL DRAINED
WOODTELL FINE SANDY LOAM	1 TO 5 PERCENT SLOPES WELL DRAINED

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
  - Blade existing topsoil into windrows, prep ROW, clear and grub
  - Remove existing pavement
  - Grading operations, excavation, and embankment
  - Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
  - Remove existing metal beam guard fence (MBGF), bridge rail
  - Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
  - Place flex base
- Rework slopes, grade ditches
  - Blade windrowed material back across slopes
  - Revegetation of unpaved areas
  - Achieve site stabilization and remove sediment and erosion control measures
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
  - Contaminated water from excavation or dewatering pump-out water
  - Sanitary waste from onsite restroom facilities
  - Trash from various construction activities/receptacles
  - Long-term stockpiles of material and waste
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
CUTHAND CREEK	
SCATTER CREEK	
KICKAPOO CREEK	

\* Add (\*) for impaired waterbodies with pollutant in ().

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity



*Austin R. Shatto, P.E.*  
07/31/2023

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

© 2023 Sheet 1 of 2  
Texas Department of Transportation

FED. RD. DIV. NO.				SHEET NO.
				88
STATE	STATE DIST.	COUNTY		
TEXAS		LAMAR, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
0045	09	116, ETC.	US 82	



**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

**T / P**

- Sediment Trap
  - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
  - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
  - Not required (<10 acres disturbed)
  - Required (>10 acres) and implemented.
    - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
    - 3,600 cubic feet of storage per acre drained
  - Required (>10 acres), but not feasible due to:
    - Available area/Site geometry
    - Site slope/Drainage patterns
    - Site soils/Geotechnical factors
    - Public safety
    - Other: \_\_\_\_\_

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**


- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

**2.9 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.



*Austin R. Shatto, P.E.*  
07/31/2023

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

© 2023 Sheet 2 of 2  
Texas Department of Transportation

FED. RD. DIV. NO.				SHEET NO.
				89
STATE	STATE DIST.	COUNTY		
TEXAS		LAMAR, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
0045	09	116, ETC.	US 82	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/28/2023 FILE: T:\PARISAD\DESIGN\US 82 E Safety Treat 0045-09-116\Design\CAD\_Standards\epic.dgn

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- No Action Required       Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- 
- 
- 
- 

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

**Best Management Practices:**

<b>Erosion</b>	<b>Sedimentation</b>	<b>Post-Construction TSS</b>
<input checked="" type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Mulching	<input checked="" type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input checked="" type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required       Required Action

Action No.

- 
- 
- 
- 

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required       Required Action

Action No.

- 
- 
- 
- 

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

- No Action Required       Required Action

Action No.

- 
- 
- 
- 

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If coves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MSA: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes       No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes       No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required       Required Action

Action No.

- 
- 
- 


**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required       Required Action


Action No.

- 
- 
- 

 Texas Department of Transportation		Design Division Standard		
<h2>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</h2> <h3>EPIC</h3>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
© TxDOT - February 2015		CONT	SECT	HIGHWAY
12-12-2011 (DS) REVISIONS		0045 09	116, ETC.	US 82
09-07-14 ADDED NOTE SECTION IV.		DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.		PAR	LAMAR, ETC.	90


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

7/28/2023  
 T:\PARISAD\DESIGN\US\_82\_E\_Safety\_Treeet\_0045-09-116\Design\CAD\_Standards\ENVIRONMENTAL\_STANDARDS\ec116.dgn



**TEMPORARY SEDIMENT CONTROL FENCE**

SCF



**HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL**

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

**SEDIMENT CONTROL FENCE USAGE GUIDELINES**

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.


Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.

**LEGEND**

Sediment Control Fence  
 SCF

**GENERAL NOTES**

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




**VERTICAL TRACKING**

				Design Division Standard	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE &amp; VERTICAL TRACKING EC(1)-16</b>					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0045	09	116, ETC.	US 82	
	DIST	COUNTY	SHEET NO.		
	PAR	LAMAR, ETC.	91		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




**FILTER DAM AT TOE OF SLOPE**

RFD1




**FILTER DAM AT SEDIMENT TRAP**

RFD1 OR RFD2




**FILTER DAM AT CHANNEL SECTIONS**


RFD1 OR RFD2 OR RFD3




**PLAN VIEW**




**"V" SHAPE PLAN VIEW**



**SECTION B-B**



**PROFILE**



**SECTION C-C**

**ROCK FILTER DAM USAGE GUIDELINES**

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT<sup>2</sup> of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

**Type 1 (18" high with no wire mesh) (3" to 6" aggregate):** Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

**Type 2 (18" high with wire mesh) (3" to 6" aggregate):** Type 2 may be used in ditches and at dike or swale outlets.

**Type 3 (36" high with wire mesh) (4" to 8" aggregate):** Type 3 may be used in stream flow and should be secured to the stream bed.

**Type 4 (Sack gabions) (3" to 6" aggregate):** Type 4 may be used in ditches and smaller channels to form an erosion control dam.


**Type 5:** Provide rock filter dams as shown on plans.

**GENERAL NOTES**

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4"
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


**PLAN SHEET LEGEND**

- Type 1 Rock Filter Dam — RFD1
- Type 2 Rock Filter Dam — RFD2
- Type 3 Rock Filter Dam — RFD3
- Type 4 Rock Filter Dam — RFD4



**TYPE 4 (SACK GABIONS)**

RFD4



**SECTION A-A**

		Design Division Standard	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>ROCK FILTER DAMS</b> <b>EC(2)-16</b>			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT: SECT	JOB: HIGHWAY	REVISIONS
	0045 09	116, ETC.	US 82
	DIST: PAR	COUNTY: LAMAR, ETC.	SHEET NO.: 92