

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT
FEDERAL PROJECT: F 2B23(295), ETC
HIGHWAY - SH 152
CARSON COUNTY

CONTROL: 0455 - 02 - 031, ETC
FOR THE CONSTRUCTION OF SUPER 2 PASSING LANES
CONSISTING OF PAVEMENT REPAIR, ACP OVERLAY, SAFETY END TREATMENTS AND UPGRADE STANDARDS.

PROJECT LIMITS FROM: HUTCHINSON COUNTY LINE
TO: GRAY COUNTY LINE
ROADWAY LENGTH = 68,360.47 FT. = 12.95 MILES
BRIDGE LENGTH = 630.00 FT. = 0.12 MILES
TOTAL LENGTH = 68,990.47 FT. = 13.07 MI.

FED. RD. DIV. NO.	FEDERAL PROJECT NO.	SHEET NO.
6	F 2B23 (295), ETC	1
STATE	STATE DIST.	COUNTY
TEXAS	AMA	CARSON
CONT.	SECT.	JOB
0455	02	031, ETC
		SH 152

DESIGN SPEED = 40
2023 ADT = 3,100
2043 ADT = 4,300
RURAL MINOR ARTERIAL

FINAL PLANS


LETTING DATE: _____
DATE CONTRACTOR BEGAN WORK: _____
DATE WORK WAS COMPLETED & ACCEPTED: _____
FINAL CONTRACT COST: \$ _____
CONTRACTOR: _____
AREA ENGINEER: _____

0455-02-032

SAFETY TREAT FIXED OBJECTS
FROM: HUTCHISON COUNTY LINE
TO: GRAY COUNTY LINE

STA. 984+32.65
BEGIN CONTROL: 0455-02-031, ETC
BEGIN CSJ: 0455-02-031, ETC
RM: 340+0.0

STA. 1675+47.35
END CONTROL: 0455-02-031, ETC
END CSJ: 0455-02-031, ETC
RM: 352+1.134



EXCEPTIONS:

NONE

RAILROADS:

NONE

EQUATIONS:

STA 1102+31.06	(BK) = STA 1102+63.30	(AH) = -32.24'
STA 1113+09.58	(BK) = STA 1113+05.13	(AH) = -4.45'
STA 1166+79.30	(BK) = STA 1167+03.92	(AH) = -75.38'
STA 1237+67.09	(BK) = STA 1237+62.91	(AH) = 4.18'
STA 1376+37.10	(BK) = STA 1376+35.30	(AH) = 1.8'
STA 1418+91.98	(BK) = STA 1418+89.20	(AH) = 2.78'
STA 1495+28.57	(BK) = STA 1493+45.64	(AH) = 182.93'
STA 1514+74.73	(BK) = STA 1516+70.83	(AH) = -196.10'
STA 1664+83.35	(BK) = STA 1665+00.00	(AH) = -16.65'

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT. REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, JULY 2022).

FILE: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\01 General\SH152*COVER*S2.dgn
DATE: 8/12/2023 3:57:37 PM

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

2023 Texas Department of Transportation
© 2023 BY TEXAS DEPARTMENT OF TRANSPORTATION
ALL RIGHTS RESERVED.

RECOMMENDED FOR LETTING: 8/28/2023

DocuSigned by:
Spencer K. Mayer P.E.
3719DE174B2A4C6...

AREA ENGINEER DATE: 8/29/2023

DocuSigned by:
Kit Black
9B5A6E6A6E8B46E...

DISTRICT DIRECTOR OF TRANSPORTATION
PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 8/29/2023

DocuSigned by:
Blair Johnson
8B80E3AEB2BC43A...

DISTRICT ENGINEER


FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\01 General\SH 152*INDEX*OF*SHEETS.dgn

DRAWING DATE: 8/12/2023

SHEET	DESCRIPTION
GENERAL	
1	TITLE SHEET
2	INDEX OF SHEETS
3-5	EXISTING TYPICAL SECTIONS
6-9	PROPOSED TYPICAL SECTIONS
10, 10A-10G	GENERAL NOTES
11, 11A-11B	ESTIMATE AND QUANTITY
12-16	SUMMARY OF QUANTITIES
17	DELETED
18-21	SUMMARY OF QUANTITIES
TRAFFIC CONTROL PLAN	
22	TRAFFIC CONTROL PLAN GENERAL NOTES
23	TRAFFIC CONTROL PLAN SEQUENCE OF CONSTRUCTION
24	TRAFFIC CONTROL PLAN TYPICAL SECTION PHASE I STAGE I
25	TRAFFIC CONTROL PLAN TYPICAL SECTION PHASE I STAGE II
26	TRAFFIC CONTROL PLAN TYPICAL SECTION PHASE II
27-35	TRAFFIC CONTROL PLAN PHASE I STAGE I
36-38	TRAFFIC CONTROL PLAN PHASE I STAGE II
TRAFFIC CONTROL STANDARDS	
39-50	BC(1) THRU BC(12)-21
51	TCP(1-1)-18
52	TCP(2-1)-18
53	TCP(3-1)-13
54	TCP(3-3)-14
55	TCP(7-1)-13
56	WZ(STPM)-23
57	WZ(UL)-13
58	WZ(RS)-22
ROADWAY DETAILS	
59-73	HORIZONTAL & VERTICAL CONTROL INDEX
74-82	HORIZONTAL & VERTICAL CONTROL SHEET
83-85	HORIZONTAL ALIGNMENT DATA SHEET
86-115	ROADWAY PLAN
116-117	ADDITIONAL AREAS
118	PAVEMENT REPAIR DETAIL
ROADWAY STANDARDS	
119	TE (HMAC)-11
120	GF (31)-19
121-122	GF (31)TR TL3-20
123	GF (31)MS-19
124	SGT (10S)31-16
125	SGT (12S)31-18

SHEET	DESCRIPTION
DRAINAGE DETAILS	
126	OVERALL DRAINAGE AREA MAP
127	DRAINAGE AREA MAP
128-150	CULVERT PLAN & PROFILE
DRAINAGE STANDARDS	
151	BCS
152	PW
152A	PSET-RR
153	SCC-MD
154-155	SCC-3&4
156-157	SCC-5&6
158-159	SCC-7
160-161	SCC-8
162-163	MC-5-20
164	ECD
165-167	SETB-SW-0
SIGNING & PAVEMENT MARKING DETAILS	
168-197	SIGNING AND PAVEMENT MARKINGS
198-206	SUMMARY OF SMALL SIGNS
207	SMALL SIGN DETAILS
SIGNING & PAVEMENT MARKING STANDARDS	
208-210	PM(1)-22, PM(2)-22, PM(3)-22
211	AMARILLO DISTRICT RECESSED RAISED PAVEMENT MARKER DETAIL
212	SMD (GEN)-08
213-215	SMD(SLIP-1)-08 THRU SMD(SLIP-3)-08
216	SMD(TWT)-08
217	TS2(PL-1)-23
218	TSR(3)-13
219	TSR(4)-13
220-225	D&OM(1)-20 - D&OM(5) - 20, D&OM(VIA) - 20
226	RS(6)-23
227	RS(4)-23
ENVIRONMENTAL ISSUES	
228-229	STORM WATER POLLUTION PREVENTION PLAN (SW3P)
230	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)
231-234	SW3P DRILL SEEDING DETAIL
235	EROSION CONTROL LAYOUT
ENVIRONMENTAL STANDARDS	
236-238	EC(9)-16
239	VEGETATION SPECIFICATION SHEET

THE STANDARD SHEETS IDENTIFIED HERE WERE SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



8/12/2023

Rev. No.	C.O. No.	Description	Date	By

Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657



SH 152

INDEX OF SHEETS


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	2
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*EX*TP*01.dgn


DRAWING DATE: 8/12/2023



EXISTING SECTION A - SH 152
 STA 988+25.00 TO STA 1031+00.00
 STA 1201+00.00 TO STA 1308+50.00
 STA 1351+75.00 TO STA 1378+50.00
 STA 1597+00.00 TO STA 1675+47.35



EXISTING SECTION B - SH 152
 STA 1031+00.00 TO STA 1036+50.00 LT TRANSITION (40' TO 52')
 STA 1036+50.00 TO STA 1112+55.04
 STA 1378+50.00 TO STA 1383+25.00 LT TRANSITION (40' TO 52')
 STA 1383+25.00 TO STA 1492+88.41



8/12/2023





I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
EXISTING TYPICAL SECTIONS

SHEET 1 OF 3		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		3


FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*EX*TP*02.dgn

DRAWING DATE: 8/12/2023




EXISTING SECTION C - SH 152

- STA 1139+38.48 TO STA 1196+00.00
- STA 1196+00.00 TO STA 1201+00.00 RT TRANSITION (52' TO 40')
- STA 1327+00.00 TO STA 1344+50.00
- STA 1344+50.00 TO STA 1351+75.00 RT TRANSITION (52' TO 40')
- STA 1515+29.79 TO STA 1523+50.00
- STA 1544+00.00 TO STA 1593+00.00
- STA 1593+00.00 TO STA 1597+00.00 RT TRANSITION (52' TO 40')



EXISTING SECTION D - SH 152

- STA 1308+50.00 TO STA 1312+00.00 LT TRANSITION (40' TO 46')
- STA 1310+00.00 TO STA 1316+00.00 RT TRANSITION (46' TO 58')
- STA 1316+00.00 TO STA 1324+00.00
- STA 1324+00.00 TO STA 1327+00.00 LT TRANSITION (58' TO 52')



8/12/2023



SH 152

EXISTING TYPICAL SECTIONS



SHEET 2 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


4

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*EX*TP*03.dgn

DRAWING DATE: 8/12/2023



EXISTING SECTION E - SH 152
 STA 1523+50.00 TO STA 1529+50.00 LT TRANSITION (52' TO 64')
 STA 1529+50.00 TO STA 1536+00.00
 STA 1536+00.00 TO STA 1544+00.00 LT TRANSITION (64' TO 52')



8/12/2023



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152


EXISTING TYPICAL SECTIONS

SHEET 3 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	5
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*PR*TP*01.dgn

DRAWING DATE: 8/28/2023




**(A) REGULAR TYPICAL SECTION - OVERLAY
SH 152**

STA 988+00.00 TO STA 1031+00.00
 STA 1267+00.00 TO STA 1301+50.00
 STA 1352+00.00 TO STA 1374+00.00
 STA 1639+00.00 TO STA 1673+47.35




**(B) CLIMBING LANE SECTION - OVERLAY
SH 152**

STA 1031+00.00 TO STA 1040+00.00 LT TRANSITION (40' TO 52') (AVG 46')
 STA 1040+00.00 TO STA 1112+55.04
 STA 1374+00.00 TO STA 1383+00.00 LT TRANSITION (40' TO 52') (AVG 46')
 STA 1383+00.00 TO STA 1492+88.41



NOTE:

1. PREP ROW AND BACKFILL TY A. REFER TO EROSION CONTROL LAYOUT SHEETS FOR SEEDING AND EROSION CONTROL INFORMATION.
2. SEE GENERAL NOTES FOR RUMBLE STRIP DETAILS.
3. REMOVE EXIST ASPH AND BASE MATERIAL (8"-12")



8/28/2023



SH 152


PROPOSED TYPICAL SECTIONS

SHEET 1 OF 4

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	6
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: L:\amortillo\District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*PR*TYP*02.dgn

DRAWING DATE: 8/28/2023






NOTE:

1. PREP ROW AND BACKFILL TO A. REFER TO EROSION CONTROL LAYOUT SHEETS FOR SEEDING AND EROSION CONTROL INFORMATION.
2. SEE GENERAL NOTES FOR RUMBLE STRIP DETAILS.
3. REMOVE EXIST ASPH AND BASE MATERIAL (8"-12")




(C) CLIMBING LANE SECTION - OVERLAY SH 152

STA 1139+38.48 TO STA 1195+00.00
 STA 1332+75.00 TO STA 1344+00.00
 STA 1344+00.00 TO STA 1352+00.00 RT TRANSITION (52' TO 40') (AVG 46')
 STA 1515+29.79 TO STA 1522+00.00
 STA 1550+50.00 TO STA 1591+50.00



8/28/2023



(D) PROPOSED TYPICAL SECTION (SUPER 2) SH 152

STA 1195+00.00 TO STA 1258+00.00
 STA 1258+00.00 TO STA 1267+00.00 RT TRANSITION (52' TO 40') (AVG 46') (WIDENING AVG 14')
 STA 1591+50.00 TO STA 1630+00.00
 STA 1630+00.00 TO STA 1639+00.00 RT TRANSITION (52' TO 40') (AVG 46') (WIDENING AVG 14')



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152


PROPOSED TYPICAL SECTIONS

FED. RD. DIV. NO.			FEDERAL AID PROJECT NO.	HIGHWAY NO.
6			(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY	SHEET NO.	
TEXAS	AMA	CARSON	7	
CONTROL	SECTION	JOB		
0455	02	031, ETC		

SHEET 2 OF 4


FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*PR*TYP*03.dgn

DRAWING DATE: 8/28/2023




(E) PROPOSED TYPICAL SECTION (SUPER 2 AND RIGHT TURN LANE)
SH 152

STA 1301+50.00 TO STA 1304+95.00 TRANSITION RT (40' TO 46'-6") (AVG 43'-3") (WIDENING AVG 11'-3")
 STA 1304+95.00 TO STA 1307+85.00 TRANSITION LT & RT (46'-6" TO 64') (AVG 55'-3") (WIDENING AVG (31'-3"))
 STA 1307+85.00 TO STA 1317+00.00





DETAIL A
1" = 3'



DETAIL B
1" = 3'

- NOTE:**
1. PREP ROW AND BACKFILL TY A. REFER TO EROSION CONTROL LAYOUT SHEETS FOR SEEDING AND EROSION CONTROL INFORMATION.
 2. SEE GENERAL NOTES FOR RUMBLE STRIP DETAILS.
 3. REMOVE EXIST ASPH AND BASE MATERIAL (8"-12")



(F) PROPOSED TYPICAL SECTION (SUPER 2 AND RIGHT TURN LANE)
SH 152

STA 1317+00.00 TO STA 1331+27.00
 STA 1331+27.00 TO STA 1332+75.00 TRANSITION LT (64' TO 52') (AVG 58') (WIDENING AVG 14')





Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152			
PROPOSED TYPICAL SECTIONS			
SHEET 3 OF 4			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	8
CONTROL	SECTION	JOB	
0455	02	031, ETC	





FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\02 Typical Sections\SH1 52*PR*TP*04.dgn
DRAWING DATE: 8/28/2023



- NOTE:**
- 1. PREP ROW AND BACKFILL TY A. REFER TO EROSION CONTROL LAYOUT SHEETS FOR SEEDING AND EROSION CONTROL SHEETS INFORMATION.
 - 2. SEE GENERAL NOTES FOR RUMBLE STRIP DETAILS.
 - 3. REMOVE EXIST ASPH AND BASE MATERIAL (8"-12")

**(G) PROPOSED TYPICAL SECTION (SUPER 2 AND LEFT TURN LANE) - OVERLAY
SH 152**

STA 1522+00.00 TO STA 1531+00.00 LT TRANSITION (52' TO 64') (AVG 58')
STA 1531+00.00 TO STA 1535+41.00



**(H) PROPOSED TYPICAL SECTION (SUPER 2 AND LEFT TURN LANE)
SH 152**

STA 1535+41.00 TO STA 1541+50.00
STA 1541+50.00 TO STA 1550+50.00 TRANSITION LT (64' TO 52') (AVG 58') (WIDENING AVG 14')

I. S. ENGINEERS, LLC 7670 WOODWAY DRIVE, SUITE 320 HOUSTON, TEXAS 77063 TBPE REG. # F-11657			
SH 152			
PROPOSED TYPICAL SECTIONS			
SHEET 4 OF 4			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	9
CONTROL	SECTION	JOB	
0455	02	031, ETC	

GENERAL NOTES

CSJ: 0455-02-031, ETC				
BASIS OF ESTIMATE FOR CONSTRUCTION				
Item	Description	Unit	Rate	
164	SEEDING		SEE PLAN SHEETS	
275 ⁽³⁾	CEMENT TREAT (8")	SY	3% Cement at 21.6 LBS/SY	
310	PRIME COAT (MC-30)	GAL	0.25 GAL/SY	
314	EMULSION ASPHALT (MULTI) (MS-2 OR SS-1)	GAL	SEE NOTE 2	
316	ASPH (AC-5)	GAL	0.38 GAL/SY	
	AGGR (TY-B GR-4 SAC-B)	CY	110 SY/CY	
3032	ASPH FOR REINF FAB	GAL	0.22 GAL/SY	
3076 ⁽¹⁾	D-GR HMA TY-B PG64-28	TON	3"	330 LB/SY/2000
3076 ⁽¹⁾	SP-D SAC-A PG70-28	TON	2"	220 LB/SY/2000
3085	UNDERSEAL COARSE	GAL	SEE GENERAL NOTE FOR RATE INFORMATION	
NOTE:				
(1)	D-GR HMA and SP-D SAC-A Mixtures Weight Based On 110Lbs/SY/In			
(2)	40% Emulsified Asphalt 60% Water Mixture Applied At 0.25 Gal/Sy. Paid using 0.1 Gal/Sy.			
(3)	Weight based on 120 LBS/CF			

General

Contractor questions on this project are to be addressed to the following individual(s):

TO: Pampa Area Engineer Zachary.Mayer@txdot.gov
 CC: Assistant Area Engineer Ivan.Fuentes@txdot.gov
 Director of Construction Kenneth.Petr@txdot.gov
 Construction Manager LaDenia.Jewitt@txdot.gov

Contractor questions will be accepted through email, phone, or in person by the above individuals.

For Q&A's on Proposals navigate to:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

Use the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink of the project you want to view the Q&A for and click on the link in the window that pops up.

All relevant project documentation including CTD and cross sections (if applicable) will be posted to TxDOT District's FTP website.

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

Verify all survey control prior to beginning construction. Notify Engineer of any discrepancies in control prior to beginning construction.

There are approximately 7 "reference markers" within the project limits. If a marker needs to be moved for any reason during construction operations, the Contractor is to remove it, install it in a temporary location and then reinstall it in its correct permanent location. Both the temporary and permanent locations are to be on a line that is perpendicular to the original "station" along the roadway. The temporary location is to be at or near the right-of-way. The permanent location is to be directed by the Engineer.

The Contractor is advised that a construction speed zone will be applicable for this project and is to be limited to the actual work areas under construction. The approved construction speed limit will be made available upon request to the Engineer.

If portions of the right-of-way is used to store materials, equipment, and other uses with the approval of the Engineer, materials, equipment, etc., must either be located outside the 30 feet traffic safety clearance zone or be adequately protected.

Contractor facilities, such as asphalt plants, concrete plants, rock crushers, etc. are not allowed to be located within Department right of way.

Do not store any equipment or material under any bridge.

The slopes indicated on the typical sections may be varied when fixed features required slopes are re-established as directed by the Engineer.

Dust caused by construction operations is to be controlled by applying water in conformance with the requirements of Item 204, "Sprinkling". Sprinkling for dust control will not be paid for directly, but will be considered as subsidiary work to the various bid items.

Highway: SH 152

Control: 0455-02-031, ETC

Any work necessary to provide temporary ingress and egress during construction (such as building gravel ramps, etc.) Will not be paid for directly, but will be considered as subsidiary work to the various bid items.

Verify all existing grades, elevations, and cross slopes that will connect to any proposed grades and elevations. If adjustments are warranted, the Contractor is to submit proposed changes to the Engineer for verification.

Item 6 Control of Materials

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Item 7 Legal Relations and Responsibilities

No significant traffic generator events identified.

The total area disturbed for this project is approximately 8 acres. The disturbed area in this project, all project locations in the Contract, and the Contractor Project Specific Locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the ROW. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer and to the local government that operates a separate storm sewer system.

Item 8 Prosecution and Progress

Create, maintain, and submit for approval, a Critical Path Method (CPM) project schedule and a Project Schedule Summary Report (PSSR) using computer software that is fully compatible with the latest version of Primavera Systems, Inc. or Primavera P6.

Prosecute the work following the sequence shown in the traffic control plan narrative and corresponding traffic control plan. Prosecuting the work in concurrent phases is not allowed unless approved in writing by the engineer.

Contractor will be required to coordinate their work / traffic control plan with adjacent contractor CCSJ: 0455-02-027 to ensure continuous, uninterrupted work / traffic control plan.

Item 100 Preparing Right Of Way

Preparing right of way will consist exclusively of mowing the vegetation to the width shown in the plans for Backfilling Pavement Edges and removal of trees as shown on the plans. Set mower cutting height to cut as low as practical but no higher than 6 inches. Payment for Preparing Right Of Way will be made only in the case where mowing is actually used.

All tree removal activities are to take place outside nesting season. See EPIC for nesting season.

Remove trees of various diameters as shown on the plans, or as directed. Remove tree stumps to at least 12 in. below the surrounding terrain. Before backfilling holes treat the remainder of the stump with the following herbicide: Manufacture - Dow AgroScience; Product - Remedy or other as approved by the Engineer. Follow manufacture recommendations for herbicide. Backfill holes with acceptable material and compact flush with surrounding areas.

Identify each individual tree proposed to be removed. Obtain approval from the Engineer in the field for each individual tree proposed to be removed prior to any tree being removed.

Item 110 Excavation

Before grading begins, the vegetative cover within the areas to be graded are to be bladed into a windrow outside the limits of the slopes. After all grading is complete; the vegetative cover is to be spread over the adjacent disturbed areas. This work is not to be paid for directly, but will be considered subsidiary work to the various bid items.

Prior to excavation and placement of embankment, the top-soil (6-inch depth) within the areas to be disturbed will be bladed into a windrow, or stockpiled, outside the limits of the fill slope. After all grading is completed; the top soil (6-inch depth) will be spread over the disturbed areas that will not receive concrete riprap. This work is not paid for directly, but will be considered as subsidiary work to the various bid items.

Item 132 Embankment

The plasticity index for TY B will not exceed 25.

Materials excavated from the project will be allowed to be used on the project as directed by the Engineer.

Highway: SH 152

Control: 0455-02-031, ETC

Item 134 Backfilling Pavement Edges

Mow according to Item 100 just prior to backfill pavement edge operations.

Do not overlay any roadway unless the pavement edges can be backfilled within 24 hours. Preferably, both edges of all roadways should be completely backfilled at the end of each day's overlay operations. Damage to delineators, signs, or other roadside features will be repaired or replaced at the expense of the Contractor.

Item 164 Seeding for Erosion Control

Perform planting operations in accordance with the recommendations contained in the latest version of the TxDOT manual "A Guide to Roadside Vegetation Establishment" developed by the Vegetation Management Section of the Maintenance Division.

Seeding may require more than one mobilization, depending upon the Contractor's sequence of work.

Item 166 Fertilizer

Fertilize all areas of project to be seeded or sodded in accordance with the Amarillo District Vegetation Specification Sheet.

Item 247 Flexible Base

SPECIFICATION FOR FLEX BASE TY A OR B, GR 4								
GRADING REQUIREMENTS PERCENT RETAINED – SIEVES SIEVE SIZES INCHES					SOIL CONSTANTS		MAX WET BALL *	MAX % INCREASE IN PASSING # 40 *
1 3/4	7/8	3/8	# 4	# 40	L.L. MAX	P.I. MAX		
0	17-32	40-60	50-70	70-85	40	12	45	20

*Applies to TY A & D material only.

Item 275 Cement Treatment (Road-Mixed)

The intent of this item is to pulverize existing ACP and blend with the existing flexible base. Consider the existing ACP and flexible base as existing base material, and payment made under this item includes pulverizing the existing materials.

All required moisture added for the mixing and compaction operation is to be injected through the mixing process. Sprinkle the base material to prevent excessive loss of moisture as directed by the Engineer.

Backfill any vertical edge nightly with a material approved by the Engineer and at a minimum slope of 3:1.

Item 314 Emulsified Asphalt Treatment

A 5' strip of finished material adjacent to each shoulder is to be treated with an emulsified asphalt mixture. The mixture may be placed in one or more applications at a total rate of 0.25 gallons per square yard, unless directed otherwise by the Engineer. The homogeneous mixture may be composed of approximately 40% asphalt (MS-2 or SS-1) and 60% water, unless directed otherwise by the Engineer.

Item 316 Seal Coat

Place one course surface treatment on finished base course as soon as practical, but no later than 7 calendar days after completion of the base treatment process.

For items of work that include both summer and winter materials or the Asphalt (Multi Option), the Engineer will determine which asphalt to apply based on timing and prevailing weather conditions. The Asphalt (Multi Option) is to consist of the following choices and rates:

- ASPH (AC-5) @ 0.38 GAL/SY
- ASPH (CRS-2P) @ 0.38 GAL/SY

The rates shown are for estimating purposes and that the Engineer can dictate higher or lower rates based on roadway conditions.

Item 320 Equipment for Asphalt Concrete Pavement

A self-propelled, wheel mounted material transfer vehicle (MTV) capable of receiving hot mix from the haul trucks separate from the paver is required on all courses and all types of hot mix for this project. The MTV is to have a minimum storage capacity of approximately 25 tons, and equipped with a pivoting discharge conveyor and a means of completely remixing the hot mix prior to placement. The paver hopper is to be equipped with a separate surge storage insert with a minimum capacity of approximately 20 tons.

If used, the IR bar read out screen must be visible at all times to the Engineer.

When performing any scheduled work during night time hours (sunset to sunrise) all work areas will be fully illuminated using devices designed to not incumber or distract oncoming traffic. All illumination equipment must be approved by the Engineer in writing 48 hours before any scheduled night time work can begin. All associated equipment and labor is considered subsidiary to the item of work and will not be paid for directly.

Item 351 Flexible Pavement Structure Repair

Contractor is not to remove more pavement than can be replaced that same day.

All flexible pavement structure repairs must be overlaid within the same asphalt season.

Item 354 Planing and Texturing Pavement

The Contractor will retain ownership of planed materials.

Item 432 Riprap

24" tie bars (#3 bars at 18" c-c) are to be used across all construction joints. Tie bars should be 12" into each side of the construction joint. When tying new riprap into existing riprap drill and epoxy grout 8" minimum into existing concrete. This is to be considered subsidiary to the payment for riprap.

Item 462 Concrete Box Culverts and Storm Drains

Joint material for reinforced concrete pipe is to be either cold applied preformed plastic gaskets or cold applied plastic asphalt sewer joint compound.

Backfill pipe up to the springline with granular material. The ponding method of backfilling will be allowed for the granular material only.

Item 466 Headwalls and Wingwalls

Do not use precast headwalls/wingwalls.

Item 467 Safety End Treatment

Pre-cast Safety End Treatments are allowed; however, a cast-in-place concrete apron will be required as shown on the plans & will be subsidiary to the Safety End Treatment.

Item 502 Barricades, Signs, and Traffic Handling

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Temporary rumble strips will be required as shown on WZ(RS)-22 regardless of loose gravel, and/or soft or bleeding asphalt. Adjust the traffic control setup such that rumble strips are not

placed in areas of heavily rutted pavements, unpaved surfaces, or horizontal curves. Temporary rumble strips will not be allowed on interstate highway.

The Contractor is to have the option of using either plastic drums, vertical panels, grabber cones or a combination where drums are shown as channelizing devices, as approved by the Engineer. Plastic drums are to be used in all transition areas in accordance with BC(8)-21 and WZ(TD)-17.

Furnish and install "soft shoulder" signs as directed by the Engineer. This work will not be paid for directly, but will be considered as subsidiary to item 502, "Barricades, Signs and Traffic Handling".

Provide a 3:1 backfill "safety slope" at the end of the day for any drop off exceeding 2" that is adjacent to a travel lane.

Lane closures are to be limited to a maximum of: 3 miles

If more than one lane closure location is desired a minimum of 2 miles passing zone is required between each location.

Notify the Engineer 24 hours prior to any lane closure.

Item 504 Field Office and Laboratory

The following building(s) will be required for this project:

One Type (D) structure, asphalt mix control laboratory

Each building is to be provided before work is begun on the pertinent construction items for which it is needed.

Any laboratory furnished is to be a minimum of 10 ft in width.

All-weather parking area and chain link security fence will not be required.

The Type D structures are to be equipped with the following in addition to requirements specified under item 504:

- a. Safety equipment
 - (1) One eye wash station
 - (2) One fire extinguisher
 - (3) One first aid kit

Furnish a Type D structure for the asphalt mix control laboratory for the Engineer's exclusive use. In addition to requirements of item 504, this structure is to have a minimum height of 8 feet and provide a minimum 400 square feet gross floor area for permanently located plants or 200 square feet for temporary located plants serving one project. The floor area will be partitioned into a minimum of two interconnected rooms, each room furnished with an exterior door and a

minimum of two windows. The floor is to have sufficient strength to support the testing equipment and have an impervious covering.

The Type D structures are to be adequately air conditioned and be furnished with a minimum of one desk and three chairs. The structure is to be provided with a 240-volt electrical service entrance. The service is to consist of a minimum of 4 - 120 volt circuits with 20 amp breakers and no more than two grounded convenience outlets per circuit and provisions for a minimum of two 220-volt ovens with vents to the outside. The structure is to have a minimum of 2 convenience outlets per wall, and a utility sink with an adequate clean potable water supply for testing. The state building is to be equipped with at minimum a hot water dispenser or hot water heater capable of generating 1 gallon of water per use at 140° F with adequate water pressure. Space heaters for heating the structure are unacceptable. Portable structures are to be support blocked for stability and are to be tied down.

For this project, asphalt content will be determined utilizing the ignition method so the structure is to provide for the following in lieu of the item 504 requirements for asphalt content by extraction. The room to contain the ignition oven is to be adequately power ventilated and contain a NEMA 6-50r (208/240 v, 50 a) outlet within 2.5 feet of the ignition oven location and an independent exhaust outlet to the outside no further than 8 feet from the oven. The surface for the ignition oven location is to be level, sturdy, and fireproof with at least 6-inch clearance between the furnace and other vertical surfaces.

If needed, each building is to be moved to a new location as directed by the Engineer. Any building that is no longer required on the job after completion of the pertinent construction items may be released to the Contractor upon consent of the Engineer.

Item 506 Temporary Erosion, Sedimentation, and Environmental Controls


Erosion control devices are to be installed as needed in coordination with the work progress, or as directed by the Engineer.

Use wooden stakes to secure logs unless engineer gives permission to use rebar stakes.

Item 533 Milled Rumble Strips

Use the applicable option in the table below for installation of the continuous milled depressions, as shown on the Rumble Strips standards.

Edge Line Rumble Strips will require a gap spacing of 20' following 60' of rumble strip to allow for bicycle consideration as shown on RS(6)-23.



SHOULDER WIDTH (SW)	RUMBLE STRIP WIDTH (RS)	PLACEMENT "A"	OPTION (SEE RS(1)-23 or RS(2)-23)
SW ≤ 2'	8" RS	SEE RS(1)-13	Option 1
2' < SW ≤ 8'	8" RS	4" OFF EDGE LINE	Option 3
SW ≥ 8'	16" RS	24" OFF EDGE LINE	Option 4
All Inside Shoulders on 4-lane Divided Highways	16" RS	4" OFF EDGE LINE	Option 3

Use milled option 1 for installation of the Centerline Rumble Strips, as shown on the Standard Sheet RS(4)-23.

Item 540 Metal Beam Guard Fence

Drive steel posts for metal beam guard fence a minimum of 1/3 of the post length to final specified depth.

Item 542 Removing Metal Beam Guard Fence

All MBGF, GET & TAS materials will remain property of the Contractor.

Item 544 Guardrail End Treatments

Use Single Guardrail End Treatment (Ty III)(Steel Post).

Item 585 Ride Quality for Pavement Surfaces

Use Surface Test Type B pay adjustment schedule 2 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

Item 644 Small Roadside Sign Supports and Assemblies

ALUMINUM SIGN BLANKS THICKNESS	Square Feet	Minimum Thickness
	Less than 7.5	0.100
	7.5 or Greater	0.125

All slip base signs will have a triangular slip base with a 2-bolt clamp to prevent rotation of signpost. Set screw type slip base will not be allowed.

A 7" x 1/2" diameter galvanized rod or #4 rebar is to be installed in the sign stub as shown on SMD(SLIP-1)-08 to prevent rotation of the sign stub in the concrete footing.

The exact locations of the large and small roadside signs are to be as designated by the Engineer.

The existing riprap aprons are to be removed and disposed of as approved by the Engineer. This work is not to be paid for directly, but will be considered subsidiary to the removal of foundations under this item.

Probe before drilling for foundations to determine the location of all utilities and structures. This work will not be paid for directly, but will be considered subsidiary to bid items involved.

Details for standard signs not shown on the signing standards of the signing detail plan sheets are to be in conformance with the department's "Standard Highway Sign Designs for Texas" Manual, Latest Edition.

Install a wrap of retroreflective sheeting conforming to DMS-8300 on all posts for small road sign assemblies. Sign post wraps will not be paid for directly, but are considered subsidiary to Item 644.

Install red sheeting on the posts containing the following signs:
Stop, Yield, Wrong Way & Do Not Enter

Install yellow sheeting on all other small sign posts.

Install all retroreflective wraps at a height of 4 ft. from bottom of the wrap to the edge of the travel lane surface. All retroreflective wraps will cover the full circumference of the sign post for a vertical width of 12 inches.

Item 658 Delineator and Object Marker Assemblies

For all ground mount applications provide hollow or tubular posts embedded in concrete using plastic wedged anchor system.

For all concrete barrier, bridge rail, and guard fence post mounted applications provide hollow or tubular posts with approved anchorage..

Item 666 Reflectorized Pavement Markings

Retroreflectivity Requirements:

All Type I markings must meet the minimum retroreflectivity values for edgeline markings, centerline or no passing barrier-line, and lane lines when measured any time after 3 days, but not later than 10 days after application:

- ◆ White markings: 250 millicandelas per square meter per lux (mcd/m²/lx)
- ◆ Yellow markings: 175 mcd/m²/lx

Retroreflectivity Measurements: Mobile or portable retroreflectometers may be used at the Contractor's discretion.

All Type I markings must meet the minimum retroreflectivity values for edgeline markings, centerline or no passing barrier-line, and lane lines when measured any time after 3 days, but not later than 10 days after application.

Item 677 Eliminating Existing Pavement Markings and Markers

Do not remove any existing pavement markings in any area in which the contractor is not able to place work zone pavement markings at the proper location within the same day.

Item 3032 Reinforced Paving Mat for Asphalt Pavement Overlays

Contractor to furnish tack coat either AC-20-5TR or PG70-28 in accordance with Item 3096.

Item 3076 Dense Graded Hot Mix Asphalt

Use aggregate that meets the SAC requirement of class A.

Use of RAS is not allowed.

Only fractionated RAP is allowed.

Provide a laboratory mixture design with the minimum target asphalt binder content shown below:

D-GR HMA TY B 4.6%

When laying ACP on a roadway that has two or more lanes and the work is being done under traffic, then the adjacent lane or lanes are to be overlaid by the end of the following day.

Make a smooth, clean, minimum 1 inch deep butt joint where each end of the new pavement joins the existing pavement. Any method approved by the Engineer can be used to make the joint.

The District Lab will perform a maximum of 2(two) design verification tests. If additional verification tests are needed, the Contractor will be billed \$3,500.00 per each additional verification test required to obtain an approved asphaltic concrete pavement mix design.

If lime is not used as an antistrip agent, then the production and placement testing frequency for the Boil test (TEX-530-C) shown in the table below.

Description	Test Method	Minimum Contractor Testing Frequency	Minimum Engineer Testing Frequency
Boil test	Tex-530-C	1 per lot	1 per 12 sublots

If used, the IR bar read out screen must be visible at all times to the Engineer.

Item 3077 Superpave Mixtures

Use aggregate that meets the SAC requirement of class A.

Only fractionated RAP is allowed.

Use of RAS is not allowed.

All SP-D on this project is considered surface mix. A substitution PG binder is not allowed, as shown in Table 5.

When laying ACP on a roadway that has two or more lanes and the work is being done under traffic, then the adjacent lane or lanes are to be overlaid by the end of the following day.

Make a smooth, clean, minimum 1 inch deep butt joint where each end of the new pavement joins the existing pavement. Any method approved by the Engineer can be used to make the joint.

The District Lab will perform a maximum of 2(two) design verification tests. If additional verification tests are needed, the Contractor will be billed \$3,500.00 per each additional verification test required to obtain an approved asphaltic concrete pavement mix design.

If lime is not used as an antistrip agent, then the production and placement testing frequency for the Boil test (TEX-530-C) shown in the table below.

Description	Test Method	Minimum Contractor Testing Frequency	Minimum Engineer Testing Frequency
Boil test	Tex-530-C	1 per lot	1 per 12 sublots

If used, the IR bar read out screen must be visible at all times to the Engineer.

Item 3085 Underseal Course

For estimating purposes the Underseal Course is applied at a rate of 0.25 Gal/SY.

Item	Option	Material	Application Rate	Conversion Rate
316	Seal Coat	AGGR ⁴	110 SY/CY	0.66 ¹
		ASPH ⁵	0.38 Gal/SY	
3002	Spray Applied Underseal Membrane	ASPH	0.25 Gal/SY	1.0 ²
3019	TRAIL-Ultrafuse and Jebro	ASPH	0.15 Gal/SY	1.67 ³

- Aggregate is considered subsidiary to the asphalt. For estimating purposes 0.66 Gallons of Seal Coat Asphalt is equivalent to 1.0 Gallons of Underseal Course. Refer to Item 316 in these General notes for more information on this option.
- For estimating purposes 1.0 Gallon of Spray Applied Underseal Membrane is equivalent to 1.0 Gallon of Underseal Course. Refer to Special Specification SS3002 for more information on this item.
- For estimating purposes 1.67 Gallons of TRAIL is equivalent to 1.0 Gallons of Underseal Course. Refer to Special Specification SS3085 for more information on this item.
- Use GR4 TY B SAC B in accordance with Item 316
- Use AC-10 or other equivalent as approved by the Engineer.

Example: If TRAIL Option Is Selected For Use.
A conversion rate of 1.67 will be applied to every one gallon of oil that is used.
If the NET gallons determined after strapping the tank is 1,000 gallons. Then the 1,000 gallons will be multiplied by the 1.67 conversion rate in the table above.
1,000 GAL * 1.67 CR = 1670 gallons for payment.

Ultrafuse and Jebro is the only allowed “seal” for the TRAIL option. None of the “tack” options are allowed.

If the Spray Applied Underseal Membrane or TRAIL options are used, the use of tack is not required.

Item 3096 Asphalts, Oils, and Emulsions

Asphalt from different sources is not to be blended.

The "Open" seasons for applying asphaltic materials and mixtures for the listed items are to be as follows, unless authorized otherwise in writing by the Engineer:

ITEMS	OPEN SEASON
310, 314	All Year
316 (Underseal on Base)	All Year
351, 3076, 3077	From April 15 th through October 31st

Item 6001 Portable Changeable Message Sign

Supply 3 Portable Changeable Message Signs (Type II – Lamp Matrix) for this project. No payment will be made for removing and replacing damaged PCMS.

If the Contractor chooses to have more than one lane closure set-up at a time, provide additional PCMS in accordance with TCP at no additional charge to the department.

Item 6158 Trailer Mounted Solar Powered Radar Speed Control Monitor

Supply 2 (TMSP) units for this project. This work will be paid at the unit price bid for each unit, which will include any moving, maintenance, and removing of the TMSP. No payment will be made for removing and replacing damaged TMSP.

Item 6185 Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

In addition to the shadow vehicles with truck mounted attenuator (TMA) that are specified as being required on the traffic control plan for this project, provide 0 additional shadow vehicle(s) with TMA for TCP (1-1)-18, (2-1)-18, (3-1)-13, (3-4)-14, (7-1)-13 as detailed on the General Notes of this standard sheets.

Therefore, 2 total shadow vehicles with TMA will be required for this type of work. The Contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

Item 6362 Recessed Reflective Pavement Markers

Remove all existing raised pavement markers as directed by the Engineer, removing existing markers will be subsidiary to Item 6362.

Place all recessed reflective pavement markers in proper alignment with the guides/stripes. The maximum deviation rate in alignment is 1 in. per 200 ft. of roadway. The maximum deviation is to not exceed 2 in. or be abrupt.

Reflector face must be free of any adhesive or the reflector shall be cleaned or replaced.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0455-02-031

DISTRICT Amarillo
HIGHWAY SH 152

COUNTY Carson

CONTROL SECTION JOB				0455-02-031		0455-02-032		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00184859		A00193232			
COUNTY				Carson		Carson			
HIGHWAY				SH 152		SH 152			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	100-6001	PREPARING ROW	AC	43.430				43.430	
	100-6008	PREPARING ROW (TREE) (0" TO 6" DIA)	EA			184.000		184.000	
	100-6009	PREPARING ROW (TREE) (6" TO 24" DIA)	EA			27.000		27.000	
	105-6091	REMOVING STAB BASE & ASPH PAV (8"-12")	SY	24,058.000				24,058.000	
	110-6001	EXCAVATION (ROADWAY)	CY	12,240.000				12,240.000	
	132-6003	EMBANKMENT (FINAL)(ORD COMP)(TY B)	CY			51.600		51.600	
	132-6004	EMBANKMENT (FINAL)(DENS CONT)(TY B)	CY	5,943.000				5,943.000	
	134-6001	BACKFILL (TY A)	STA	636.000				636.000	
	164-6034	DRILL SEEDING (PERM) (RURAL) (SANDY)	AC	43.430				43.430	
	164-6053	DRILL SEEDING (TEMP)(WARM OR COOL)	AC	43.430				43.430	
	247-6258	FL BS (CMP IN PLC)(TY A OR B GR4)(12")	SY	37,987.000				37,987.000	
	275-6001	CEMENT	TON	430.000				430.000	
	275-6010	CEMENT TREAT (SUBGRADE) (8")	SY	39,830.000				39,830.000	
	310-6009	PRIME COAT (MC-30)	GAL	9,497.000				9,497.000	
	314-6009	EMULS ASPH (EROSN CONT)(MULTI)	GAL	7,069.000				7,069.000	
	316-6010	ASPH (AC-5)	GAL	14,066.000				14,066.000	
	316-6175	AGGR(TY-B GR-4 SAC-B)	CY	337.000				337.000	
	351-6019	FLEXIBLE PAVEMENT STRUCTURE REPAIR(3")	SY	48,000.000				48,000.000	
	354-6021	PLANE ASPH CONC PAV(0" TO 2")	SY	9,258.000				9,258.000	
	403-6001	TEMPORARY SPL SHORING	SF			480.000		480.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY			11.000		11.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY			66.000		66.000	
	462-6045	CONC BOX CULV (3 FT X 2 FT)(EXTEND)	LF			91.000		91.000	
	462-6046	CONC BOX CULV (3 FT X 3 FT)(EXTEND)	LF			2.000		2.000	
	462-6052	CONC BOX CULV (5 FT X 4 FT)(EXTEND)	LF			20.000		20.000	
	462-6055	CONC BOX CULV (6 FT X 4 FT)(EXTEND)	LF			4.000		4.000	
	462-6062	CONC BOX CULV (7 FT X 7 FT)(EXTEND)	LF			6.000		6.000	
	462-6067	CONC BOX CULV (8 FT X 8 FT)(EXTEND)	LF			18.000		18.000	
	462-6095	CONC BOX CULV (6 FT X 2 FT) (EXTEND)	LF			13.000		13.000	
	466-6173	WINGWALL (PW - 1) (HW=12 FT)	EA			1.000		1.000	
	466-6174	WINGWALL (PW - 1) (HW=13 FT)	EA			1.000		1.000	
	466-6178	WINGWALL (PW - 1) (HW=3 FT)	EA			1.000		1.000	
	466-6181	WINGWALL (PW - 1) (HW=6 FT)	EA			1.000		1.000	
	466-6196	WINGWALL (PW - 2) (HW=7 FT)	EA			8.000		8.000	
	467-6105	SET (TY I)(S=3 FT)(HW=3FT)(3:1)(C)	EA			8.000		8.000	
	467-6106	SET (TY I)(S=3 FT)(HW=3FT)(4:1)(C)	EA			8.000		8.000	
	467-6109	SET (TY I)(S=3 FT)(HW= 3 FT)(6:1)(C)	EA			3.000		3.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0455-02-031

DISTRICT Amarillo
HIGHWAY SH 152

COUNTY Carson

CONTROL SECTION JOB				0455-02-031		0455-02-032		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00184859		A00193232			
COUNTY				Carson		Carson			
HIGHWAY				SH 152		SH 152			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	467-6111	SET (TY I)(S=3 FT)(HW= 4 FT)(3:1)(C)	EA			3.000		3.000	
	467-6112	SET (TY I)(S=3 FT)(HW= 4 FT)(4:1)(C)	EA			1.000		1.000	
	467-6182	SET (TY I)(S= 5 FT)(HW= 5 FT)(4:1) (C)	EA			3.000		3.000	
	467-6191	SET (TY I)(S= 5 FT)(HW= 7 FT)(4:1) (C)	EA			1.000		1.000	
	467-6205	SET (TY I)(S= 6 FT)(HW= 3 FT)(4:1) (C)	EA			2.000		2.000	
	467-6219	SET (TY I)(S= 6 FT)(HW= 5 FT)(4:1) (C)	EA			2.000		2.000	
	467-6261	SET (TY I)(S= 7 FT)(HW= 8 FT)(4:1) (C)	EA			1.000		1.000	
	480-6001	CLEAN EXIST CULVERTS	EA			33.000		33.000	
	496-6002	REMOV STR (INLET)	EA			6.000		6.000	
	496-6005	REMOV STR (WINGWALL)	EA			29.000		29.000	
	496-6008	REMOV STR (BOX CULVERT)	LF			74.000		74.000	
	500-6001	MOBILIZATION	LS	0.850		0.150		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		7.000		12.000	
	506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	125.000				125.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	125.000				125.000	
	530-6002	INTERSECTIONS (ACP)	SY	6,788.000				6,788.000	
	530-6021	DRIVEWAYS (ACP) (TYPE 2)	SY	832.000				832.000	
	533-6001	RUMBLE STRIPS (SHOULDER)	LF	127,245.000				127,245.000	
	533-6002	RUMBLE STRIPS (CENTERLINE)	LF	63,623.000				63,623.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF			1,350.000		1,350.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF			150.000		150.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA			12.000		12.000	
	544-6003	GUARDRAIL END TREATMENT (REMOVE)	EA			2.000		2.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	32.000				32.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	41.000				41.000	
	644-6007	IN SM RD SN SUP&AM TY10BWG(1)SA(U)	EA	16.000				16.000	
	644-6036	IN SM RD SN SUP&AM TYS80(1)SA(U-BM)	EA	1.000				1.000	
	644-6037	IN SM RD SN SUP&AM TYS80(1)SA(U-WC)	EA	5.000				5.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	85.000				85.000	
	658-6060	REMOVE DELIN & OBJECT MARKER ASSMS	EA	114.000		6.000		120.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA			24.000		24.000	
	658-6081	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	EA	120.000				120.000	
	658-6082	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BR)	EA	30.000				30.000	
	658-6093	INSTL DEL ASSM (D-DW)SZ 1(WFLX)GND(BI)	EA	37.000				37.000	
	658-6099	INSTL OM ASSM (OM-2Z)(WFLX)GND	EA	59.000				59.000	
	658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA			6.000		6.000	
	658-6103	INSTL OM ASSM (OM-3L)(WFLX)GND)GND	EA	2.000				2.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0455-02-031

DISTRICT Amarillo
HIGHWAY SH 152




COUNTY Carson

CONTROL SECTION JOB				0455-02-031		0455-02-032		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00184859		A00193232			
COUNTY				Carson		Carson			
HIGHWAY				SH 152		SH 152			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	658-6106	INSTL OM ASSM (OM-3R)(WFLX)GND)GND	EA	2.000				2.000	
	662-6005	WK ZN PAV MRK NON-REMOV (W)6"(BRK)	LF	5,869.000				5,869.000	
	662-6008	WK ZN PAV MRK NON-REMOV (W)6"(SLD)	LF	46,948.000				46,948.000	
	662-6037	WK ZN PAV MRK NON-REMOV (Y)6"(SLD)	LF	87,164.000				87,164.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	4,887.000				4,887.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	6,508.000				6,508.000	
	666-6017	REFL PAV MRK TY I (W)6"(DOT)(090MIL)	LF	1,965.000				1,965.000	
	666-6029	REFL PAV MRK TY I (W)8"(DOT)(090MIL)	LF	218.000				218.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	5,471.000				5,471.000	
	666-6047	REFL PAV MRK TY I (W)24"(SLD)(090MIL)	LF	125.000				125.000	
	666-6053	REFL PAV MRK TY I (W)(ARROW)(090MIL)	EA	12.000				12.000	
	666-6071	REFL PAV MRK TY I(W)(LNDP ARW)(090MIL)	EA	12.000				12.000	
	666-6077	REFL PAV MRK TY I (W)(WORD)(090MIL)	EA	12.000				12.000	
	677-6001	ELIM EXT PAV MRK & MRKS (4")	LF	67,056.000				67,056.000	
	3032-6001	REINFORCED FAB FOR ASPH PVMNT OVERLAYS	SY	253,423.000				253,423.000	
	3032-6003	ASPH FOR REINF FAB (PG70-28)	GAL	55,753.000				55,753.000	
	3076-6005	D-GR HMA TY-B PG64-28	TON	6,107.000				6,107.000	
	3077-6058	SP MIXESSP-DSAC-A PG70-28	TON	39,560.000				39,560.000	
	3085-6001	UNDERSEAL COURSE	GAL	24,742.000				24,742.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1.000		2.000		3.000	
	6024-6008	HPPM W/RET REQ TY I(W)6"(BRK)(090MIL)	LF	8,762.000				8,762.000	
	6024-6011	HPPM W/RET REQ TY I(W)6"(SLD)(090MIL)	LF	139,543.000				139,543.000	
	6024-6020	HPPM W/RET REQ TY I(Y)6"(BRK)(090MIL)	LF	3,155.000				3,155.000	
	6024-6023	HPPM W/RET REQ TY I(Y)6"(SLD)(090MIL)	LF	130,738.000				130,738.000	
	6158-6001	TMSP RADAR SPEED CONTROL MONITOR	EA	2.000				2.000	
	6185-6002	TMA (STATIONARY)	DAY	110.000		90.000		200.000	
	6185-6003	TMA (MOBILE OPERATION)	HR	136.000				136.000	
	6362-6002	REC REFL PAV MRKR TY I-C	EA	815.000				815.000	
	6362-6004	REC REFL PAV MRKR TY II-A-A	EA	3,898.000				3,898.000	
18		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000	

LOCATION	SUMMARY OF WORKZONE TRAFFIC CONTROL ITEMS					
	662	662	662	662	662	677
	6005	6008	6037	6109	6111	6001
	WK ZN PAV MRK NON-REMOV (W) 6" (BRK)	WK ZN PAV MRK NON-REMOV (W) 6" (SLD)	WK ZN PAV MRK NON-REMOV (Y) 6" (SLD)	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y- 2	ELIM EXT PAV MRK & MRKS (4")
0455-02-031 SH 152	LF	LF	LF	EA	EA	LF
PHASE I STAGE I	4455	35636	64240			49938
PHASE I STAGE II	1414	11312	22924			17118
PHASE 2				4887	6508	
0455-02-031 TOTAL	5869	46948	87164	4887	6508	67056

FILENAME: \$FILES

DRAWING DATE: \$DATES


 TBPE Registration No. F-1481		
 I. S. ENGINEERS, LLC 7670 WOODWAY DRIVE, SUITE 320 HOUSTON, TEXAS 77063 TBPE REG. # F-11657		
 © 2023		
SH 152 SUMMARY OF QUANTITIES		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		12

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\03 Quantity Summaries\SH152*SUM*WIDENING AREAS.dgn


DRAWING DATE: 8/28/2023

LOCATION	SUMMARY OF ROADWAY ITEMS							
	100	105	134	247	275	275	310	316
	6001	6091	6001	6258	6001	6010	6009	6010
	PREPARING ROW	REMOVING STAB BASE & ASPH PAV (8"-12")	BACKFILL (TY A)	FL BS (CMP IN PLC) (TY A OR B GR 4) (12")	CEMENT (3% CEMENT @ 21.6 LBS / SY)	CEMENT TREAT (SUBGRADE) (8")	PRIME COAT (MC-30) (0.25 GAL / SY)	ASPH (AC-5) (0.38 GAL / SY)
	AC	SY	STA	SY	TON	SY	GAL	GAL
TYPICAL SECTION A	3.08		133.97					
TYPICAL SECTION B	4.60		200.43					
TYPICAL SECTION C	2.81		122.57					
TYPICAL SECTION D	26.88	11950	119.50	26019	295	27347	6505	9635
TYPICAL SECTION E	2.35	6372	15.50	5642	63	5814	1410	2092
TYPICAL SECTION F	1.74	2275	15.75	3489	40	3664	872	1293
TYPICAL SECTION G	0.31		13.41					
TYPICAL SECTION H	1.66	1844	15.09	2837	32	3005	709	1046
ADDITIONAL AREAS (DRIVEWAYS & INTERSECTIONS)								
ADDITIONAL AREAS (VERTICAL TRANSITIONS & PAVEMENT REMOVAL)		1616						
PAVEMENT REPAIR								
0455-02-031 TOTAL	43.43	24058	636	37987	430	39830	9497	14066

LOCATION	SUMMARY OF ROADWAY ITEMS					
	316	351	354	530	530	533
	6175	6019	6021	6002	6021	6001
	AGGR (TY-B GR 4 SAC-B) (1 CY / 110 SY)	FLEXIBLE PAVEMENT STRUCTURE REPAIR(3")	PLANE ASPH CONC PAV(0" TO 2")	INTERSECTIONS (ACP)	DRIVEWAYS (ACP) (TYPE 2)	RUMBLE STRIPS (SHOULDER)
	CY	SY	SY	SY	SY	LF
TYPICAL SECTION A						26795
TYPICAL SECTION B						40087
TYPICAL SECTION C						24513
TYPICAL SECTION D	231					23900
TYPICAL SECTION E	50					3100
TYPICAL SECTION F	31					3150
TYPICAL SECTION G						2682
TYPICAL SECTION H	25					3018
ADDITIONAL AREAS (DRIVEWAYS & INTERSECTIONS)			2016	6788	832	
ADDITIONAL AREAS (VERTICAL TRANSITIONS & PAVEMENT REMOVAL)			7242			
PAVEMENT REPAIR		48000				
0455-02-031 TOTAL	337	48000	9258	6788	832	127245



Texas Department of Transportation



I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657

SH 152

SUMMARY OF QUANTITIES


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		13

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\03 Quantity Summaries\SH152*SUM*OVERLAY AREAS.dgn


DRAWING DATE: 8/28/2023

LOCATION	SUMMARY OF ROADWAY ITEMS					
	533 6002	3032 6001	3032 6003	3076 6005	3077 6058	3085 6001
	RUMBLE STRIPS (CENTERLINE)	REINFORCED FAB FOR ASPH PVMNT OVERLAYS	ASPH FOR REINF FAB (PG70-28) (0.22 GAL/SY)	D-GR HMA TY-B PG64-28 (330 LB/SY)	SP MIXES SP-D SAC-A PG70-28 (220 LB/SY)	UNDERSEAL COURSE (0.25 GAL/SY)
LF	SY	GAL	TON	TON	GAL	
TYPICAL SECTION A	13397	38703	8515		6550	5210
TYPICAL SECTION B	20043	83428	18354		12607	7795
TYPICAL SECTION C	12257	51217	11268		7731	4767
TYPICAL SECTION D	11950	49256	10836	4184	7463	4647
TYPICAL SECTION E	1550	7534	1657	908	1094	603
TYPICAL SECTION F	1575	8651	1903	561	1221	613
TYPICAL SECTION G	1341	6850	1507		983	522
TYPICAL SECTION H	1509	7783	1712	454	1114	587
ADDITIONAL AREAS (DRIVEWAYS & INTERSECTIONS)						
ADDITIONAL AREAS (VERTICAL TRANSITIONS & PAVEMENT REMOVAL)					797	
PAVEMENT REPAIR						
0455-02-031 TOTAL	63623	253423	55753	6107	39560	24742

LOCATION	SUMMARY OF EROSION CONTROL ITEMS				
	164 6034	164 6053	314 6009	506 6040	506 6043
	DRILL SEEDING (PERM) (RURAL) (SANDY)	DRILL SEEDING (TEMP) (WARM OR COOL)	EMULS ASPH (EROSN CONT) (MULTI) (0.1 GAL/SY)	BIODEG EROSN CONT LOGS (INSTL) (8")	BIODEG EROSN CONT LOGS (REMOVE)
AC	AC	GAL	LF	LF	
0455-02-031 TOTALS	43.43	43.43	7069	125	125



Texas Department of Transportation



I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152

SUMMARY OF QUANTITIES

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

14



FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\03 Quantity Summaries\SH152*SUM*EARTHWORK.dgn

DRAWING DATE: 8/12/2023

SUMMARY OF EARTHWORK		
STATION	110	132
	6001	6004
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (DENS CONT) (TY B)
SH 152	CY	CY
1195+00.000 R4	3.621	2.142
1196+00.000 R4	43.32	3.407
1196+29.535 R4	63.721	3.905
1197+00.000 R4	112.394	5.092
1198+00.000 R4	106.175	10.166
1199+00.000 R4	101.377	22.028
1200+00.000 R4	82.52	36.964
1201+00.000 R4	60.335	51.257
1202+00.000 R4	54.35	72.667
1203+00.000 R4	55.41	59.137
1204+00.000 R4	59.276	32.158
1205+00.000 R4	63.457	32.387
1206+00.000 R4	80.431	24.573
1207+00.000 R4	75.278	28.373
1208+00.000 R4	57.622	82.367
1209+00.000 R4	52.376	153.455
1210+00.000 R4	55.743	155.325
1211+00.000 R4	70.27	73.624
1212+00.000 R4	68.252	29.145
1213+00.000 R4	61.232	41.623
1214+00.000 R4	71.197	35.077
1215+00.000 R4	80.587	31.828
1216+00.000 R4	70.488	39.334
1217+00.000 R4	58.267	45.297
1218+00.000 R4	60.407	49.394
1219+00.000 R4	67.079	43.249
1220+00.000 R4	66.016	39.211
1221+00.000 R4	73.9	44.868
1222+00.000 R4	75.098	48.43
1223+00.000 R4	69.17	40.087
1224+00.000 R4	72.553	30.993
1225+00.000 R4	75.818	27.389
1226+00.000 R4	75.728	25.237
1227+00.000 R4	86.345	15.123
1228+00.000 R4	82.908	19.917
1229+00.000 R4	60.728	42.151
1230+00.000 R4	57.213	54.165
1231+00.000 R4	54.176	55.096
1232+00.000 R4	58.32	44.224
1233+00.000 R4	71.622	37.582
1234+00.000 R4	73.869	35.591
1235+00.000 R4	66.896	39.022
1236+00.000 R4	59.362	51.396
1237+00.000 R4	60.802	60.752
1238+00.000 R5	68.884	100.552
1239+00.000 R5	72.341	74.464
1240+00.000 R5	70.404	33.329
1241+00.000 R5	61.555	46.476
1242+00.000 R5	60.546	45.274
1243+00.000 R5	67.669	52.619
1244+00.000 R5	89.221	30.752
1245+00.000 R5	80.082	23.093
1246+00.000 R5	61.614	40.443
1247+00.000 R5	70.862	36.301
1248+00.000 R5	67.595	48.145
1249+00.000 R5	60.418	92.856
1250+00.000 R5	66.618	82.838
1251+00.000 R5	73.679	41.175
1252+00.000 R5	73.068	38.866
1253+00.000 R5	78.068	25.964
1254+00.000 R5	103.322	16.5
1255+00.000 R5	99.001	18.654
1256+00.000 R5	71.308	25.774
1257+00.000 R5	73.915	37.631
1258+00.000 R5	78.333	40.439

SUMMARY OF EARTHWORK		
STATION	110	132
	6001	6004
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (DENS CONT) (TY B)
SH 152	CY	CY
1259+00.000 R5	69.088	33.969
1260+00.000 R5	60.313	36.483
1261+00.000 R5	56.814	38.922
1262+00.000 R5	59.947	28.784
1263+00.000 R5	57.75	17.712
1264+00.000 R5	49.441	15.677
1265+00.000 R5	44.075	16.496
1266+00.000 R5	40.144	10.078

SUMMARY OF EARTHWORK		
STATION	110	132
	6001	6004
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (DENS CONT) (TY B)
SH 152	CY	CY
1301+00.000 R5	2.6	3.054
1302+00.000 R5	17.155	5.404
1303+00.000 R5	35.884	6.808
1304+00.000 R5	38.34	10.799
1305+00.000 R5	58.3605	11.979
1306+00.000 R5	30.392	6.529
1307+00.000 R5	50.53	9.95
1308+00.000 R5	60.679	56.843
1309+00.000 R5	49.168	167.036
1310+00.000 R5	62.166	199.723
1311+00.000 R5	104.769	112.385
1312+00.000 R5	122.519	34.876
1313+00.000 R5	129.202	9.027
1314+00.000 R5	140.816	7.211
1315+00.000 R5	143.581	4.384
1316+00.000 R5	143.918	3.013
1317+00.000 R5	68.411	1.616
1318+00.000 R5	79.383	0.539
1319+00.000 R5	86.422	0.315
1320+00.000 R5	86.735	0.278
1321+00.000 R5	77.204	0.346
1322+00.000 R5	79.163	0.336
1323+00.000 R5	90.287	0.339
1324+00.000 R5	93.911	0.351
1325+00.000 R5	89.653	0.33
1326+00.000 R5	87.196	0.315
1327+00.000 R5	85.432	0.416
1328+00.000 R5	87.76	0.433
1329+00.000 R5	95.159	0.342
1330+00.000 R5	93.571	0.432
1331+00.000 R5	88.53	0.428
1332+00.000 R5	69.836	0.468



		
		
SH 152 SUMMARY OF QUANTITIES		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		15

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\03 Quantity Summaries\SH152*SUM*EARTHWORK*2.dgn

DRAWING DATE: 8/12/2023

SUMMARY OF EARTHWORK		
STATION	110	132
	6001	6004
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (DENS CONT) (TY B)
SH 152	CY	CY
1535+00.000 R9	4.862	2.927
1536+00.000 R9	33.031	1.547
1537+00.000 R9	99.428	0.354
1538+00.000 R9	91.462	3.818
1539+00.000 R9	97.667	3.714
1540+00.000 R9	108.674	0.168
1541+00.000 R9	116.797	0.16
1542+00.000 R9	116.608	1.009
1543+00.000 R9	104.128	1.069
1544+00.000 R9	84.792	0.375
1545+00.000 R9	70.096	0.553
1546+00.000 R9	61.051	0.442
1547+00.000 R9	53.003	0.252
1548+00.000 R9	45.173	0.287
1549+00.000 R9	39.85	0.347
1550+00.000 R9	31.046	0.296

SUMMARY OF EARTHWORK		
STATION	110	132
	6001	6004
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (DENS CONT) (TY B)
SH 152	CY	CY
1591+00.000 R9	0.322	10.981
1592+00.000 R9	40.999	14.117
1593+00.000 R9	110.681	16.36
1594+00.000 R9	100.811	27.664
1595+00.000 R9	89.387	43.632
1596+00.000 R9	83.443	50.643
1597+00.000 R9	79.796	49.447
1598+00.000 R9	71.677	51.427
1599+00.000 R9	64.686	55.184
1600+00.000 R9	59.653	58.4
1601+00.000 R9	59.689	56.873
1602+00.000 R9	61.089	50.853
1603+00.000 R9	61.023	47.822
1604+00.000 R9	60.961	48.466
1605+00.000 R9	65.235	49.267
1606+00.000 R9	67.111	48.052
1607+00.000 R9	62.57	46.323
1608+00.000 R9	64.758	46.888
1609+00.000 R9	68.405	48.805
1610+00.000 R9	70.875	46.563
1611+00.000 R9	69.736	46.857
1612+00.000 R9	73.997	46.087
1613+00.000 R9	79.62	41.661
1614+00.000 R9	76.348	41.429
1615+00.000 R9	74.288	41.836
1616+00.000 R9	76.436	77.755
1617+00.000 R9	78.784	79.408
1618+00.000 R9	80.354	38.951
1619+00.000 R9	83.416	34.515
1620+00.000 R9	86.353	38.063
1621+00.000 R9	82.923	44.889
1622+00.000 R9	77.791	51.266
1623+00.000 R9	78.586	155.332
1624+00.000 R9	73.191	160.794
1625+00.000 R9	69.872	61.499
1626+00.000 R9	71.285	61.398
1627+00.000 R9	69.9	53.435
1628+00.000 R9	77.899	48.455
1629+00.000 R9	94.359	32.577
1630+00.000 R9	91.886	34.294
1631+00.000 R9	79.683	57.193
1632+00.000 R9	78.244	48.463
1633+00.000 R9	75.338	31.788
1634+00.000 R9	137.166	19.63
1635+00.000 R9	132.334	10.768
1636+00.000 R9	57.379	8.819
1637+00.000 R9	51.608	6.591
1638+00.000 R9	49.657	2.386
PROJECT TOTAL	12240	5943


		
		
SH 152 SUMMARY OF QUANTITIES		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		16

DRAWING DATE: 8/12/2023 FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\03 Quantity Summaries\SH152*SUM*DRN.dgn


SUMMARY OF DRAINAGE ITEMS											
LOCATION	403	432	462	462	462	462	462	462	462	466	466
	6001	6001	6045	6046	6052	6055	6062	6067	6095	6173	6174
	TEMPORARY SPL SHORING	RIPRAP (CONC) (4 IN)	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	CONC BOX CULV (3 FT X 3 FT) (EXTEND)	CONC BOX CULV (5 FT X 4 FT) (EXTEND)	CONC BOX CULV (6 FT X 4 FT) (EXTEND)	CONC BOX CULV (7 FT X 7 FT) (EXTEND)	CONC BOX CULV (8 FT X 8 FT) (EXTEND)	CONC BOX CULV (6 FT X 2 FT) (EXTEND)	WINGWALL (PW-1) (HW=12 FT)	WINGWALL (PW-1) (HW=13 FT)
	SF	CY	LF	LF	LF	LF	LF	LF	LF	EA	EA
0455-02-032 TOTALS	480	11	91	2	20	4	6	18	13	1	1

SUMMARY OF DRAINAGE ITEMS											
LOCATION	466	466	466	467	467	467	467	467	467	467	467
	6178	6181	6196	6105	6106	6109	6111	6112	6182	6191	6205
	WINGWALL (PW-1) (HW=3 FT)	WINGWALL (PW-1) (HW=6 FT)	HEADWALL (PW-2) (HW=7 FT)	SET (TY I) (S=3FT) (HW=3FT) (3:1) (C)	SET (TY I) (S=3FT) (HW=3FT) (4:1) (C)	SET (TY I) (S=3FT) (HW=3FT) (6:1) (C)	SET (TY I) (S=3FT) (HW=4FT) (3:1) (C)	SET (TY I) (S=3FT) (HW=4FT) (4:1) (C)	SET (TY I) (S=5FT) (HW=5FT) (4:1) (C)	SET (TY I) (S=5FT) (HW=7FT) (4:1) (C)	SET (TY I) (S=6FT) (HW=3FT) (4:1) (C)
	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
0455-02-032 TOTALS	1	1	8	8	8	3	3	1	3	1	2

SUMMARY OF DRAINAGE ITEMS						
LOCATION	467	467	480	496	496	496
	6219	6261	6001	6002	6005	6008
	SET (TY I) (S=6FT) (HW=5FT) (4:1) (C)	SET (TY I) (S=7FT) (HW=8FT) (4:1) (C)	CLEAN EXIST CULVERTS	REMOV STR (INLET)	REMOV STR (WINGWALL)	REMOV STR (BOX CULVERT)
	EA	EA	EA	EA	EA	LF
0455-02-032 TOTALS	2	1	33	6	29	74



Texas Department of Transportation



I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPPE REG. # F-11657



SH 152

SUMMARY OF QUANTITIES

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		18

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\03 Quantity Summaries\SH152*SUM*SW3P.dgn
 DRAWING DATE: 8/12/2023

SUMMARY OF ROADWAY ITEMS											
LOCATION	100	100	132	432	540	542	544	544	658	658	658
	6008	6009	6003	6045	6002	6001	6001	6003	6100	6060	6062
	PREPARING ROW (TREE) (0" TO 6" DIA)	PREPARING ROW (TREE) (6" TO 24" DIA)	EMBANKMENT (FINAL) (ORD COMP) (TY B)	RIPRAP (MOW STRIP) (4IN)	MTL W-BEAM GND FNC STEEL POST	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL END TREATMENT (INSTALL)	GUARDRAIL END TREATMENT (REMOVE)	INSTL OM ASSM (OM-2Z) (FLX) GND (BI)	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)
	EA	EA	CY	CY	LF	LF	EA	EA	EA	EA	EA
0455-02-032 TOTALS	184	27	51.6	66	1350	150	12	2	6	6	24

		
		
SH 152 SUMMARY OF QUANTITIES		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		19

DRAWING DATE: 7/24/2023 FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\

SUMMARY OF SIGNING AND PAVEMENT MARKINGS

LOCATION	0644	0644	0644	0644	0644	0644	0658	0658	0658	0658	0658	0658	0658	0666	0666
	6001	6004	6007	6036	6037	6076	6060	6081	6082	6093	6099	6103	6106	6017	6029
	IN SM RD SN SUP&AM TY10BWG (1) SA (P)	IN SM RD SN SUP&AM TY10BWG (1) SA (T)	IN SM RD SN SUP&AM TY10BWG (1) SA (U)	IN SM RD SN SUP&AM TYS80 (1) SA (U-BM)	IN SM RD SN SUP&AM TYS80 (1) SA (U-WC)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSL DEL ASSM (D-SW) SZ 1 (WFLX) GND (BI)	INSL DEL ASSM (D-SW) SZ 1 (WFLX) GND (BR)	INSL DEL ASSM (D-DW) SZ 1 (WFLX) GND (BI)	INSL OM ASSM (OM-2Z) (WFLX) GND	INSL OM ASSM (OM-3L) (WFLX) GND GND	INSL OM ASSM (OM-3R) (WFLX) GND GND	REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)	REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF
SHEET 1 OF 30		1	1			2	4	6			2				
SHEET 2 OF 30			1				2	2			2				
SHEET 3 OF 30						1			10					253	
SHEET 4 OF 30		2				1	2				2				
SHEET 5 OF 30	2					3		3							
SHEET 6 OF 30							1	17			1	1	1		
SHEET 7 OF 30							2				2				
SHEET 8 OF 30	1					1		2					1		
SHEET 9 OF 30	1					3	8	14				1			
SHEET 10 OF 30	1					1	2				2				
SHEET 11 OF 30	3	6	2		1	9	9	8			3				
SHEET 12 OF 30	2	2				2	10	8	10		2			250	
SHEET 13 OF 30			1				4				4				
SHEET 14 OF 30	1	1	1			3	3			12	4			292	38
SHEET 15 OF 30	2	4	2			8	3			3	4				104
SHEET 16 OF 30							4				4				
SHEET 17 OF 30	1	1				2	4	6		15	1			375	
SHEET 18 OF 30	6	8	5		3	19	6	7		17	6			100	39
SHEET 19 OF 30	1	1	1			2	7	8			4			254	
SHEET 20 OF 30		2				3	3	1			3				
SHEET 21 OF 30						1	3	2			2				
SHEET 22 OF 30		2				1	9	9			1				
SHEET 23 OF 30	1	1				1	11	9			2				
SHEET 24 OF 30	5	3	1		1	9	2				2				37
SHEET 25 OF 30						1	9	8			3				
SHEET 26 OF 30						1	3	7							
SHEET 27 OF 30	2	4	1			4	2	3			2				
SHEET 28 OF 30	1					1	1		6		1			441	
SHEET 29 OF 30	2	2				4			4						
SHEET 30 OF 30		1		1		2									
TOTAL	32	41	16	1	5	85	114	120	30	37	59	2	2	1,965	218

© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152

SUMMARY OF
QUANTITIES

SHEET 1 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*369\DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023

SUMMARY OF SIGNING AND PAVEMENT MARKINGS

LOCATION	0666	0666	0666	0666	0666	6024	6024	6024	6024	6362	6362
	6035	6047	6053	6071	6077	6008	6011	6020	6023	6002	6004
	REFL PAV MRK TY I (W)8" (SLD) (090 MIL)	REFL PAV MRK TY I (W)24" (SLD) (090 MIL)	REFL PAV MRK TY I (W) (ARROW) (090 MIL)	REFL PAV MRK TY I (W) (LNDP ARW) (090MIL)	REFL PAV MRK TY I (W) (WORD) (090 MIL)	HPPM W/RET REQ TY I (W)6" (BRK) (090 MIL)	HPPM W/RET REQ TY I (W)6" (SLD) (090 MIL)	HPPM W/RET REQ TY I (Y)6" (BRK) (090 MIL)	HPPM W/RET REQ TY I (Y)6" (SLD) (090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
LF	LF	EA	EA	EA	LF	LF	LF	LF	EA	EA	
SHEET 1 OF 30							4,135	367	3,203		85
SHEET 2 OF 30							4,800	600	1,073		44
SHEET 3 OF 30		22		2		75	4,800	50	4,600	4	115
SHEET 4 OF 30						600	4,800		4,800	30	120
SHEET 5 OF 30						600	4,800		4,800	30	120
SHEET 6 OF 30						350	4,800		4,800	18	120
SHEET 7 OF 30						436	4,800		4,800	22	120
SHEET 8 OF 30						600	4,800		4,800	30	120
SHEET 9 OF 30						600	4,800		4,800	30	120
SHEET 10 OF 30						600	4,800		4,800	30	120
SHEET 11 OF 30		35				600	5,228		5,056	30	111
SHEET 12 OF 30				2		75	4,800		4,800	4	120
SHEET 13 OF 30							4,800	388	2,950		77
SHEET 14 OF 30	651		1	1	1		4,800	213	4,964	62	259
SHEET 15 OF 30	2,332	14	5	1	5		4,549		6,596	139	347
SHEET 16 OF 30							4,800	300	6,000		270
SHEET 17 OF 30				1			4,800	325	3,500	32	88
SHEET 18 OF 30	1,601	38	4	1	4		5,652		5,304	91	103
SHEET 19 OF 30				2		147	4,800		4,800	8	120
SHEET 20 OF 30						600	4,800		4,800	30	120
SHEET 21 OF 30						600	4,800		4,800	30	120
SHEET 22 OF 30						325	4,000		4,000	17	100
SHEET 23 OF 30						419	4,400		5,324	21	133
SHEET 24 OF 30	887		2		2	600	5,237		7,952	80	364
SHEET 25 OF 30						600	4,800		4,800	30	120
SHEET 26 OF 30						300	2,400		2,400	15	60
SHEET 27 OF 30		16				600	4,648		4,616	30	116
SHEET 28 OF 30				2		35	4,800		4,800	2	120
SHEET 29 OF 30							4,800	500	800		45
SHEET 30 OF 30							3,294	412			21
TOTAL	5,471	125	12	12	12	8,762	139,543	3,155	130,738	815	3,898

© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152

SUMMARY OF QUANTITIES


SHEET 2 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


TCP GENERAL NOTES:

1. THIS IS A SUGGESTED TRAFFIC CONTROL PLAN (TCP). THE CONTRACTOR MAY USE A DIFFERENT CONSTRUCTION PHASING AND TRAFFIC CONTROL PLAN. ANY VARIATION FROM THE PLANS SHALL BE FORMALLY SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL. ANY CHANGES PROPOSED BY THE CONTRACTOR WILL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER.
2. THE CONTRACTOR WILL NOT BEGIN ANY WORK ASSOCIATED WITH A CHANGE IN THE PLANS WITHOUT THE ENGINEER'S APPROVAL IN WRITING.
3. REFER TO ITEM 8 "PROSECUTION AND PROGRESS" AND PROJECT GENERAL NOTES FOR ADDITIONAL INFORMATION REGARDING THE TRAFFIC CONTROL PLAN.
4. FURNISH AND INSTALL ALL TRAFFIC CONTROL PLANS DEVICES, INCLUDING BUT NOT LIMITED TO BARRICADES, SIGNS, AND WORK ZONE MARKINGS, IN COMPLIANCE WITH THE LATEST VERSION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES(TXMUTCD), THE STATE STANDARD TRAFFIC CONTROL PLANS (TCP) SHEETS, AND THE BARRICADES AND CONSTRUCTION (BC) SHEETS. REFER TO THE PROJECT GENERAL NOTES FOR ADDITIONAL INFORMATION REGARDING THE TRAFFIC CONTROL PLAN.
5. VERIFY THE LOCATION AND SPACING OF SIGNS, BARRICADES, AND CHANNELIZING DEVICES PRIOR TO THEIR PLACEMENT ALONG VERTICAL CURVES, HORIZONTAL CURVES, AND OTHER GEOMETRIC CONSTRAINTS TO ASSURE VISIBILITY TO ALL MOTORISTS.
6. PLACE THE TRAFFIC CONTROL DEVICES ONLY WHILE WORK IS ACTUALLY IN PROGRESS OR A DEFINITE NEED EXISTS. ALWAYS HAVE ENOUGH BARRICADES, CHANNELIZING DEVICES, AND SIGNS AT ALL TIMES TO REPLACE THOSE DAMAGED.
7. COVER ALL EXISTING SIGNS THAT CONFLICT WITH THE TRAFFIC CONTROL PLAN AND UNCOVER DURING NON-WORKING HOURS OR AS DIRECTED BY THE ENGINEER. PARTIAL COVERAGE OF THE SIGN OR COVERAGE BY MATERIAL THAT WILL NOT COVER THE ENTIRE SIGN ALL THE TIME IS NOT PERMITTED.
8. VARY THE SPACING OF SIGNS TO MEET TRAFFIC CONDITIONS OR AS DIRECTED BY THE ENGINEER AND ASSURE THAT ALL TRAFFIC CONTROL DEVICES AND WORK ZONE PAVEMENT MARKINGS ARE KEPT IN A HIGHLY VISIBLE CONDITION (CLEAN, UPRIGHT AND AT PROPER LOCATION).
9. THE CONTRACTOR SHALL MAINTAIN ACCESS TO DRIVEWAYS AND LOCAL STREETS AT ALL TIMES. THE CONTRACTOR SHALL OBTAIN PERMISSION FROM THE RESPECTIVE PROPERTY OWNERS 24 HOURS PRIOR TO THE CONTRACTOR CONSTRUCTING PROPOSED DRIVEWAYS.
10. UNLESS OTHERWISE NOTED, CONSTRUCTION OF TEMPORARY DRIVEWAYS, ROAD, AND STREET CROSSINGS WILL BE SUBSIDIARY TO THE VARIOUS BID ITEMS.
11. SUPPLEMENT ALL TEMPORARY STRIPING WITH APPROPRIATE EDGE LINE CHANNELIZERS THROUGHOUT THE PROJECT.
12. MAINTAIN THE ROADWAY SURFACE AND WORK ZONE STRIPING WITHIN THE PROJECT WHILE THE TRAFFIC CONTROL PLAN IS IN EFFECT. PLACE AND BE RESPONSIBLE FOR ALL WORK ZONE PAVEMENT MARKINGS IN ACCORDANCE WITH STANDARD SHEETS WZ(STPM)-23, BC (11)-21, BC (12)-21 AND THE TXMUTCD.
13. USE ONLY TEMPORARY REMOVABLE PAVEMENT MARKINGS ON FINAL PAVEMENT SURFACES.
14. REFER TO STANDARD WZ(UL)-13 FOR SIGNING OF EDGE CONDITIONS/UNEVEN LANES.
15. DURING NON-WORKING HOURS, ALL DROP-OFFS ARE TO BE FILLED. REFER TO STANDARD WZ(UL)-13 FOR LATERAL DROP-OFFS AND TO DETAILS SHOWN IN PLANS FOR LONGITUDINAL DROP-OFFS OR AS DIRECTED BY THE ENGINEER.
16. MAINTAIN ALL EXISTING DRAINAGE CONDITIONS DURING ALL CONSTRUCTION PHASES UNTIL THE PERMANENT DRAINAGE FACILITIES ARE CONSTRUCTED AND READY TO USE. HANDLE EVACUATED AND STOCKPILED MATERIAL IN SUCH A WAY THAT IT WILL NOT BLOCK DRAINAGE.
17. REGULATE ALL CONSTRUCTION TRAFFIC SO AS TO CAUSE A MINIMAL INCONVENIENCE TO THE TRAVELING PUBLIC. AT THE ITEMS WHEN IT IS NECESSARY FOR TRUCKS TO STOP, UNLOAD OR CROSS ROADWAYS UNDER TRAFFIC, PROVIDE WARNING SIGNS AND FLAGGERS AS NEEDED TO ADEQUATELY PROTECT THE TRAVELING PUBLIC.
18. NOTIFY THE ENGINEER IN WRITING TWO WEEKS PRIOR TO SHIFTING OF TRAFFIC WITHIN EACH PHASE OF THE TRAFFIC CONTROL PLAN.
19. REMOVE FROM THE WORK AREA ALL LOOSE MATERIALS AND DEBRIS RESULTING FROM CONSTRUCTION OPERATION AT THE END OF EACH WORK DAY.
20. IMPLEMENT ALL REQUIRED EROSION CONTROL MEASURES AS SHOWN IN THE PLANS.
21. MOVING AN EXISTING SIGN TO A TEMPORARY LOCATION IS SUBSIDIARY TO THIS ITEM. INSTALLATIONS WITH PERMANENT SUPPORTS AT PERMANENT LOCATION WILL BE PAID FOR UNDER THE APPLICABLE BID ITEM(S).
22. ADDITIONAL SIGNS, BARRICADES AND CHANNELIZING DEVICES MAY BE REQUIRED TO MAINTAIN TRAFFIC DURING CONSTRUCTION, AS SHOWN ON TCP STANDARDS. ADDITIONAL SIGNS, BARRICADES, ETC. (IF ANY), WILL BE SUBSIDIARY TO ITEMS 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING".
23. REFER TO BC(6)-21 PORTABLE CHANGEABLE MESSAGE SIGN (PCMS) STANDARDS FOR A LISTING OF ABBREVIATED WORDS AND TWO-WORD PHRASES THAT ARE ACCEPTABLE FOR USE ON PCMS. SUBMIT THE SUGGESTED MESSAGE FOR THE BOARD TO THE ENGINEER FOR APPROVAL.
24. REGULATORY CONSTRUCTION SPEED LIMIT SIGNS ARE ERECTED ONLY FOR THE LIMITS OF THE SECTION OF ROADWAY WHERE SPEED REDUCTION IS NECESSARY FOR THE SAFE OPERATION OF TRAFFIC AND PROTECTION OF CONSTRUCTION PERSONNEL. IF THE REGULATORY CONSTRUCTION SPEED LIMIT SIGNS ARE NOT NECESSARY FOR THE SAFE OPERATION OF TRAFFIC DURING CERTAIN CONSTRUCTION OPERATIONS OR THOSE DAYS AND HOURS WHEN THE CONTRACTOR IS NOT WORKING, THESE SIGNS SHOULD BE MADE INOPERATIVE BY (1) MOVING THE SIGN TO THE EDGE OF THE RIGHT-OF-WAY AND FACING THEM AWAY FROM THE ROADWAY OR (2) COVERING THE SIGNS WHEN THE REDUCE SPEED LIMITS ARE NOT NECESSARY (CARE SHOULD BE TAKEN, HOWEVER, TO DELINEATE THE SIGN POST SO IT DOES NOT BECOME INVISIBLE OBSTACLE AT NIGHT ADJACENT TO THE ROADWAY).

DRAWING DATE: 7/25/2023 FILENAME: \$FILES



2023.07.26 17:17:06 -05'00'



**SH 152
TRAFFIC CONTROL PLAN
GENERAL NOTES**

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	22
CONTROL	SECTION	JOB	
0455	02	031, ETC	

CONSTRUCTION SEQUENCE AND TCP PHASING

PHASE I

OBJECTIVE: EXTEND/INSTALL S.E.T.'S ON EXISTING DRAINAGE STRUCTURES AND CONSTRUCT SUPER TWO LANES.

IT WILL BE NECESSARY TO BACKFILL PAVEMENT EDGES WITH 3:1 OR FLATTER SLOPES AT THE END OF EACH WORKING DAY OR ONCE WORK HAS CEASED WITHIN THE AREA. THIS WORK WILL BE SUBSIDIARY TO ITEM 502.

THE CONTRACTOR WILL ONLY BE ALLOWED TO PERFORM WORK ON ONE SIDE OF THE ROADWAY AT A TIME, THROUGH COMPLETION, BEFORE STARTING ON THE OPPOSITE SIDE.

1. INSTALL TRAFFIC CONTROL DEVICES INCLUDING ADVANCE WARNING SIGNS IN ACCORDANCE WITH TXDOT BC AND TCP STANDARDS.
2. PLACE SW3P DEVICES NEEDED FOR THIS PHASE.
3. CONTRACTOR SHALL COMPLETE PAVEMENT REPAIR AT LOCATIONS IDENTIFIED BY THE ENGINEER.

STAGE I

OBJECTIVE: CONSTRUCT SUPER TWO LANES ON EAST BOUND SIDE

1. REMOVE CONFLICTING SIGNING AND MARKINGS. PLACE WORK ZONE SIGNING AND CHANNELIZING DEVICES PER TXDOT BC AND TCP STANDARDS, THE LATEST EDITION OF THE TEXAS MUTCD, AND AS DIRECTED BY THE ENGINEER.
2. PLACE TEMPORARY PAVEMENT MARKING AS SHOWN IN PHASE I STAGE 1 TCP PLANS.
3. USE EXISTING LANE EDGELINE AND WIDEN PAVEMENT, AS SHOWN IN ROADWAY PLANS.
4. EXTEND CULVERTS AND INSTALL PROPOSED SET'S, AS SHOWN IN THE DRAINAGE DETAILS, USING BC (10)-21.
5. REMOVE CHANNELIZATION DEVICES TO OPEN 12' LANE AND 8' SHOULDER AFTER PAVEMENT WIDENING IS COMPLETED. PLACE WORKZONE STRIPING ON SH 152 EAST BOUND SIDE AS SHOWN ON PHASE I STAGE 1 TCP TYPICAL SECTIONS.

STAGE II

OBJECTIVE: CONSTRUCT LANE WIDENING ON WEST BOUND SIDE

1. REMOVE CONFLICTING SIGNING AND MARKINGS. PLACE WORK ZONE SIGNING AND CHANNELIZING DEVICES PER TXDOT BC AND TCP STANDARDS, THE LATEST EDITION OF THE TEXAS MUTCD, AND AS DIRECTED BY THE ENGINEER.
2. USE EXISTING LANE EDGELINE AND WIDEN PAVEMENT, AS SHOWN IN ROADWAY PLANS.
3. EXTEND CULVERTS AND INSTALL PROPOSED SET'S, AS SHOWN IN THE DRAINAGE DETAILS, USING BC (10)-21.
4. REMOVE CHANNELIZATION DEVICES TO OPEN 12' LANE AND 8' SHOULDER AFTER PAVEMENT WIDENING IS COMPLETED. PLACE WORKZONE STRIPING ON SH 152 WEST BOUND SIDE AS SHOWN ON PHASE I STAGE II TCP TYPICAL SECTIONS.

PHASE II

OBJECTIVE: PLACE 2" OVERLAY.


1. PLACE SW3P DEVICES NEEDED FOR THIS PHASE.
2. REMOVE CONFLICTING SIGNING AND MARKINGS. PLACE WORK ZONE SIGNING AND CHANNELIZING DEVICES PER TXDOT BC AND TCP STANDARDS, THE LATEST EDITION OF THE TEXAS MUTCD, AND AS DIRECTED BY THE ENGINEER.
3. PLACE 2" SUPERPAVE MIXTURES (FULL WIDTH) AS SHOWN ON THE PHASE II TCP TYPICAL SECTIONS, IN ACCORDANCE WITH TCP (7-1)-13.
4. AFTER FINAL SURFACE IS PLACED, PERFORM FINAL GRADING AND PERMANENT SEEDING.
5. INSTALL PERMANENT SIGNING AND PAVEMENT MARKINGS ACCORDING TO LATEST EDITION OF TEXAS MUTCD, SIGNING AND PAVEMENT MARKING STANDARDS, SIGNING AND PAVEMENT MARKING LAYOUTS, OR AS DIRECTED BY THE ENGINEER. UTILIZE TCP (3-1)-13 AND TCP (3-3)-14.
6. PERFORM FINAL PROJECT CLEANUP AND REMOVE ALL PROJECT BARRICADES, TEMPORARY SIGNS, AND SW3P ONCE AUTHORIZED OR DIRECTED BY THE FIELD ENGINEER.

FILENAME: \$FILES

DRAWING DATE: 7/25/2023





2023.07.26 17:17:07 -05'00'




SH 152 TRAFFIC CONTROL PLAN SEQUENCE OF CONSTRUCTION

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	23
CONTROL	SECTION	JOB	
0455	02	031, ETC	


LEGEND:

- ➔ DIRECTION OF TRAFFIC
-  CONSTRUCTION AREA
-  CONSTRUCTION CONE
- A** WK ZN PAV MRK NON REMOV (W) 6" (SLD) (100 MIL)
- B** WK ZN PAV MRK NON REMOV (Y) 6" (SLD) (100 MIL)
- C** WK ZN PAV MRK SHT TERM TY Y-2
- D** WK ZN PAV MRK SHT TERM TY W
- G** WK ZN PAV MRK NON REMOV (W) 6" (BRK) (100 MIL)



BACKFILL PAVEMENT EDGES AT THE END OF EACH WORKING DAY OR ONCE WORK HAS CEASED WITHIN AN AREA.

DETAIL A
 NIGHTTIME EDGE CONDITION




PHASE I STAGE I - SH 152 EASTBOUND

SUPER 2 WIDENING
 STA 1195+00.00 TO STA 1267+00.00
 STA 1301+50.00 TO STA 1317+00.00
 STA 1591+52.46 TO STA 1639+00.00
 NOT TO SCALE

FILENAME: \$FILES\$

DRAWING DATE: \$DATES\$





**TRAFFIC CONTROL PLAN
 TYPICAL SECTION
 PHASE I STAGE I**


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
24		

LEGEND:

- ➔ DIRECTION OF TRAFFIC
- ▨ CONSTRUCTION AREA
- 🚧 CONSTRUCTION CONE
- Ⓐ WK ZN PAV MRK NON REMOV (W) 6" (SLD) (100 MIL)
- Ⓑ WK ZN PAV MRK NON REMOV (Y) 6" (SLD) (100 MIL)
- Ⓒ WK ZN PAV MRK SHT TERM (TAB) TY Y-2
- Ⓓ WK ZN PAV MRK SHT TERM (TAB) TY W
- Ⓔ WK ZN PAV MRK NON REMOV (W) 6" (BRK) (100 MIL)



DETAIL Ⓐ
NIGHTTIME EDGE CONDITION




PHASE I STAGE II - SH 152 WESTBOUND

SUPER 2 WIDENING
 STA 1305+00.00 TO STA 1332+77.00
 STA 1535+41.00 TO STA 1550+50.00
 NOT TO SCALE

FILENAME: \$FILES\$

DRAWING DATE: \$DATES\$




TRAFFIC CONTROL PLAN
TYPICAL SECTION
PHASE I STAGE II

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
25		

FILENAME: \$FILES

DRAWING DATE: \$DATES



PHASE II - SH 152

2" OVERLAY
 STA 984+32.65 TO STA 1114+55.00
 STA 1137+38.48 TO STA 1494+88.41
 STA 1513+29.79 TO STA 1675+47.35
 NOT TO SCALE

LEGEND:

- DIRECTION OF TRAFFIC
- ▨ CONSTRUCTION AREA
- ⏏ CONSTRUCTION CONE
- A WK ZN PAV MRK NON REMOV (W) 6" (SLD) (100 MIL)
- B WK ZN PAV MRK NON REMOV (Y) 6" (SLD) (100 MIL)
- C WK ZN PAV MRK SHT TERM (TAB) TY Y-2
- D WK ZN PAV MRK SHT TERM (TAB) TY W
- G WK ZN PAV MRK NON REMOV (W) 6" (BRK) (100 MIL)


PARSONS
 TBPE Registration No. F-1481

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

Texas Department of Transportation
 © 2023

**TRAFFIC CONTROL PLAN
 TYPICAL SECTION
 PHASE II**

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	26
CONTROL	SECTION	JOB	
0455	02	031, ETC	




LEGEND

- [A] WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- ▨ PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.



DRAWING DATE: \$DATE\$

FILENAME: \$FILE\$

PARSONS
TBPE Registration No. F-1481

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

Texas Department of Transportation
© 2023

**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
BEGIN TO STA 1185+00
STA 1185+00 TO STA 1197+00**

SHEET 1 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC






LEGEND

- A WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- B WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:


1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.



**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
STA 1197+00 TO STA 1209+00
STA 1209+00 TO STA 1221+00**

SHEET 2 OF 9		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
28		

DRAWING DATE: \$DATES\$ FILENAME: \$FILES\$



LEGEND

- A WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- B WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- 42" GRABBER CONES
- TY III BARRICADES
- PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:



1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.


MATCH LINE STA 1221+00

MATCH LINE STA 1233+00


MATCH LINE STA 1233+00

MATCH LINE STA 1245+00






TBPE Registration No. F-1481



7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657



© 2023


**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
STA 1221+00 TO STA 1233+00
STA 1233+00 TO STA 1245+00**

SHEET 3 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


29

DRAWING DATE: \$DATES\$ FILENAME: \$FILES\$





LEGEND

- [A] WK ZN PAV MRK NON-REMOV (W)6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y)6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- ▨ PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE



NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.



PARSONS
TBPE Registration No. F-1481


I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

Texas Department of Transportation
© 2023

**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
STA 1245+00 TO STA 1257+00
STA 1257+00 TO END**

SHEET 4 OF 9			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	30
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: \$FILES\$
DRAWING DATE: \$DATES\$



LEGEND

- [A] WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- ⇨ DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- ▨ PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:




1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.

MATCH LINE STA 1293+00


MATCH LINE STA 1305+00

MATCH LINE STA 1305+00

MATCH LINE STA 1317+15



FILENAME: \$FILES\$
DRAWING DATE: \$DATES\$



**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
BEGIN TO STA 1305+00
STA 1305+00 TO END**

SHEET 5 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

31

0 25 50 100



SCALE IN FEET

LEGEND

- A WK ZN PAV MRK NON-REMOV (W)6" (SLD) (100MIL)
- B WK ZN PAV MRK NON-REMOV (Y)6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- 42" GRABBER CONES
- TY III BARRICADES
- PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.




**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
BEGIN TO STA 1575+00
STA 1575+00 TO STA 1587+00**

SHEET 6 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
32		

FILENAME: \$FILES\$

DRAWING DATE: \$DATES\$





LEGEND


- A WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- B WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- 42" GRABBER CONES
- TY III BARRICADES
- PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.


MATCH LINE STA 1587+00

MATCH LINE STA 1599+00



MATCH LINE STA 1599+00

MATCH LINE STA 1611+00



PARSONS
TBPE Registration No. F-1481

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657


Texas Department of Transportation
© 2023

**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
STA 1587+00 TO STA 1599+00
STA 1599+00 TO STA 1611+00**

SHEET 7 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

DRAWING DATE: \$DATES\$ FILENAME: \$FILES\$




LEGEND

- A WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- B WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- 42" GRABBER CONES
- TY III BARRICADES
- PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

MATCH LINE STA 1611+00

MATCH LINE STA 1623+00




NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.

MATCH LINE STA 1623+00

MATCH LINE STA 1635+00





PARSONS
TBPE Registration No. F-1481



I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657



Texas Department of Transportation
© 2023

**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
STA 1611+00 TO STA 1623+00
STA 1623+00 TO STA 1635+00**


SHEET 8 OF 9			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	
TEXAS	AMA	CARSON	
CONTROL	SECTION	JOB	
0455	02	031, ETC	
			34

DRAWING DATE: \$DATES\$

FILENAME: \$FILES\$



MATCH LINE STA 1635+00



LEGEND

- [A] WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- [Hatched Box] PERMANENT CONSTRUCTION THIS PHASE
- [Solid Box] PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.

DRAWING DATE: \$DATES\$ FILENAME: \$FILES\$

TBPE Registration No. F-1481

7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

© 2023

**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE I
STA 1635+00 TO END**

SHEET 9 OF 9			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	
TEXAS	AMA	CARSON	
CONTROL	SECTION	JOB	
0455	02	031, ETC	
			35





LEGEND

- [A] WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- ➔ DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- ▨ PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:


1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.




**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE II
BEGIN TO STA 1305+00
STA 1305+00 TO STA 1317+00**

SHEET 1 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	36
CONTROL	SECTION	JOB	
0455	02	031, ETC	



FILENAME: \$FILES\$
DRAWING DATE: \$DATES\$



LEGEND


- [A] WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- ▨ PERMANENT CONSTRUCTION THIS PHASE
- ▩ PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:

1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER.
3. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.



MATCH LINE STA 1317+00

MATCH LINE STA 1329+00



MATCH LINE STA 1329+00

MATCH LINE STA 1341+00



PARSONS
TBPE Registration No. F-1481

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

Texas Department of Transportation
© 2023


**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE II
STA 1317+00 TO STA 1329+00
STA 1329+00 TO END**

SHEET 2 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

FILENAME: \$FILES\$

DRAWING DATE: \$DATES\$




LEGEND

- [A] WK ZN PAV MRK NON-REMOV (W) 6" (SLD) (100MIL)
- [B] WK ZN PAV MRK NON-REMOV (Y) 6" (SLD) (100MIL)
- DIRECTION OF TRAFFIC
- ... 42" GRABBER CONES
- TY III BARRICADES
- ▨ PERMANENT CONSTRUCTION THIS PHASE
- PERMANENT CONSTRUCTION PREVIOUS PHASE

NOTES:






1. CONTRACTOR SHALL ADHERE AT ALL TIMES TO TXDOT STANDARDS BC(1)-21 THROUGH BC(12)-21 FOR SIGN DETAILS, DIMENSIONS, AND PLACEMENTS.
2. ALL DRIVEWAYS AND CROSS STREETS SHALL REMAIN OPEN DURING CONSTRUCTION ACTIVITIES AND AS APPROVED BY THE ENGINEER. CONTRACTOR SHALL COVER OR REMOVE THE EXISTING CONFLICTING SIGNS AS DIRECTED BY THE ENGINEER.



**SH 152
TRAFFIC CONTROL PLAN
PHASE I STAGE II
BEGIN TO STA 1545+00
STA 1545+00 TO END**

SHEET 3 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC



MATCH LINE STA 1545+00

MATCH LINE STA 1557+00

MATCH LINE STA 1557+00

FILENAME: \$FILES\$

DRAWING DATE: \$DATES\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:



1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<p>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov</p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		 Traffic Safety Division Standard	
<p>BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS</p> <p>BC (1) - 21</p>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
REVISONS	CONT	SECT	JOB
4-03 7-13	0455	02	031, ETC
9-07 8-14	DIST	COUNTY	
5-10 5-21	AMA	CARSON	
SH	SHEET NO.		39


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031,ETC	SH 152
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	AMA	CARSON	40	

DATE: FILE:

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 21

FILE:	bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0455	02	031, ETC	SH 152
9-07	8-14	DIST	COUNTY	SHEET NO.	
7-13	5-21	AMA	CARSON	41	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0455	02	031, ETC		SH 152			
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	AMA	CARSON		42				


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- #### GENERAL NOTES
- Nails may be used in the assembly of wooden sign supports, but 3/8 inch bolts with nuts or 3/8 inch x 3 1/2 inch lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	0455	SECT:	02	JOB:	031, ETC	HIGHWAY:	SH 152
REVISIONS		DIST:	AMA	COUNTY:	CARSON	SHEET NO.:	43		
9-07	8-14								
7-13	5-21								

DATE:
FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLRs
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

Other Condition List

FRONTAGE ROAD CLOSED
SHOULDER CLOSED XXX FT
RIGHT LN CLOSED XXX FT
RIGHT X LANES OPEN
DAYTIME LANE CLOSURES
I-XX SOUTH EXIT CLOSED
EXIT XXX CLOSED X MILE
RIGHT LN TO BE CLOSED
X LANES CLOSED TUE - FRI

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	0455	SECT:	02	JOB:	031, ETC	HIGHWAY:	SH 152
REVISIONS									
9-07	8-14								
7-13	5-21	DIST:	AMA	COUNTY:	CARSON	SHEET NO.:			44

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)




DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	0455	SECT:	02	JOB:	031, ETC	SH:	152
REVISIONS		DIST:	AMA	COUNTY:	CARSON	SHEET NO.:			
9-07	8-14								
7-13	5-21								

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign
substrates shall NOT be used on
plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	0455	SECT:	02	JOB:	031, ETC	SH:	152
REVISIONS		DIST:	AMA	COUNTY:	CARSON	SHEET NO.		46	
4-03	8-14								
9-07	5-21								
7-13									


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	AMA	CARSON	47	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) -21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	AMA	CARSON	48	

DATE: FILE:

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DR: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	AMA	CARSON	49	
11-02 8-14				

105

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE



STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS


BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
1-97 9-07 5-21				
2-98 7-13				
11-02 8-14				
	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	50	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TCP (1-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK


TCP (1-1) - 18

FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
2-94 4-98				
8-95 2-12				
1-97 2-18				
	DIST	COUNTY		SHEET NO.
	AMA	CARSON		51

DATE:
FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




TCP (2-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (2-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (2-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	700'	770'	840'	70'	140'	800'	475'	
75	750'	825'	900'	75'	150'	900'	540'	

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.




TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK


TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031,ETC	SH 152
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	AMA	CARSON	52	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY




TRAIL/SHADOW VEHICLE A
with RIGHT Directional display Flashing Arrow Board

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)


TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES


1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.




TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



TRAIL/SHADOW VEHICLE B
with Flashing Arrow Board in CAUTION display



STRIPING FOR TMA


**TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
UNDIVIDED HIGHWAYS**

TCP (3-1) - 13


FILE:	tcp3-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	December 1985	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0455	02	031, ETC	SH 152				
2-94	4-98	DIST	COUNTY	SHEET NO.					
8-95	7-13	AMA	CARSON	53					
1-97									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




TCP (3-3a)
TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3b)
TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)




TCP (3-3c)
DIVIDED MULTILANE HIGHWAY




TCP (3-3d)
UNDIVIDED MULTILANE HIGHWAY




TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display
 Flashing Arrow Board



TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board
 in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				


GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

 Texas Department of Transportation		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/REMOVAL TCP (3-3) - 14			
FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT September 1987	CONT: 0455	SECT: 02	JOB: 031, ETC
REVISIONS	DATE	BY	SH
2-94	4-98		SH 152
8-95	7-13		
1-97	7-14		
DIST: AMA	COUNTY: CARSON	SHEET NO.: 54	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



NOTE
Signing shown for one direction of travel only.

NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS



TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS
For seal coat, micro-surface or similar operations

"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

- Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshield and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one days operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- R4-1 and R4-2 are to remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (CW8-12)

- Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately 2 mile intervals within the work area, beyond major intersections and other locations deemed necessary by the Engineer.
- The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (CW8-7)

- When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.
- The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

- Temporary markings for surfacing projects shall be Temporary Flexible-reflective Roadway Marker Tabs unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two (2) days before the surfacing is applied. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.
- Tabs shall not be used to simulate edge lines.
- Tab placement for overlay/inlay operations shall be as shown on the WZ(STPM) standard sheet.

COORDINATION OF SIGN LOCATIONS

- The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- Where possible the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed in the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) and the TRAFFIC FINES DOUBLE (R20-5T) sign, and one "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing. LOOSE GRAVEL and NO CENTER LINE signs will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where tabs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
- Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
- Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.




TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS

TCP (7-1) - 13

FILE: tcp7-1.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT March 1991	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
4-92 4-98	DIST	COUNTY	SHEET NO.	
1-97 7-13	AMA	CARSON	55	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS




NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS





WZ(STPM)-23

FILE:	wzstpm-23.dgn	DN:	CK:	DW:	CK:
© TxDOT	February 2023	CONTRACT	SECT	JOB	HIGHWAY
		0455	02	031,ETC	SH 152
REVISIONS		DIST	COUNTY	SHEET NO.	
4-92	7-13	AMA	CARSON	56	
1-97	2-23				
3-03					

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"

Texas Department of Transportation

SIGNING FOR UNEVEN LANES


WZ (UL) - 13

FILE: wzu1-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
8-95 2-98 7-13	DIST	COUNTY	SHEET NO.	
1-97 3-03	AMA	CARSON	57	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/2 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
 * For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.


Texas Department of Transportation
 Traffic Safety Division Standard

TEMPORARY RUMBLE STRIPS

WZ (RS) - 22


FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	AMA	CARSON	58	

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 1.dgn



BEGIN PROJECT
CSJ: 0455-02-029, ETC.
STA=984+32.65
N=3,873,062.46
E= 723,047.91
LAT=35° 37' 29.72862"N
LONG=101° 16' 31.47755"W

PI STATION = 993+90.11
DELTA = 7° 05' 41.42" (LT)
DEGREE OF CURVE = 1° 00' 00.00"
TANGENT = 355.20
LENGTH = 709.48
RADIUS = 5,729.58
PC STATION = 990+34.91
PT STATION = 997+44.39



Point	North	East	Elevation	Station	Offset	Description
CP-1	3,872,917.01	723,230.00	3,171.91'	986+59.18	54.73' RT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (1)
T-301	3,872,988.11	723,263.54	3,166.50'	986+59.48	23.89' LT	SET MAG NAIL IN ASPH
T-302	3,872,945.29	723,262.19	3,167.17'	986+76.38	15.47' RT	SET MAG NAIL IN ASPH
CP-101	3,872,555.26	724,381.38	3,145.18'	998+63.94	46.48' LT	SET 5/8" IR W/RODS CAP
T-303	3,872,408.30	724,582.67	3,146.50'	1001+00.71	31.34' RT	SET MAG NAIL IN ASPH
TXBR	3,878,591.69	686,643.50	3,197.34'	Off Chain	Off Chain	CORS TXBR

From	To	Direction	Distance
CP-1	CP-101	S 72° 33' 29" E	1,206.88'
CP-101	CP-102	S 66° 41' 37" E	1,043.01'



NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy D. Walton
6-27-2023

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



Point	North	East	Elevation	Station	Offset	Description
CP-102	3,872,142.60	725,339.28	3,138.96'	1009+02.38	51.05' RT	SET 5/8" IR W/RODS CAP
CP-103	3,871,866.12	726,505.78	3,141.80'	1020+97.33	45.24' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-101	CP-102	S 66° 41' 37" E	1,043.01'
CP-102	CP-103	S 76° 39' 58" E	1,198.82'
CP-103	CP-104	S 72° 04' 32" E	1,080.81'

RODS
Surveying, Inc.
6810 LEE ROAD, STE.100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPES SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023


I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	59
CONTROL	SECTION	JOB	
0455	02	031, ETC	


DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 2.dgn

MATCHLINE STA 1031+00




Point	North	East	Elevation	Station	Offset	Description
CP-104	3,871,533.48	727,534.13	3,151.22'	1031+78.14	45.54' LT	SET 5/8" IR W/RODS CAP
CP-2	3,871,223.18	728,190.84	3,159.98'	1038+98.49	47.38' RT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (2)
T-304	3,871,016.96	728,873.48	3,150.10'	1046+11.46	33.30' RT	SET MAG NAIL IN ASPH
CP-105	3,871,009.81	729,180.80	3,143.58'	1049+06.04	54.57' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-103	CP-104	S 72° 04' 32" E	1,080.81'
CP-104	CP-2	S 64° 42' 32" E	726.33'
CP-2	CP-105	S 77° 50' 12" E	1,012.69'
CP-105	CP-106	S 67° 08' 25" E	1,199.25'




MATCHLINE STA 1055+00



Point	North	East	Elevation	Station	Offset	Description
CP-106	3,870,543.93	730,285.86	3,113.05'	1061+00.87	48.26' RT	SET 5/8" IR W/RODS CAP
CP-107	3,870,300.42	731,461.22	3,099.61'	1072+94.09	82.12' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-105	CP-106	S 67° 08' 25" E	1,199.25'
CP-106	CP-107	S 78° 17' 42" E	1,200.32'
CP-107	CP-108	S 64° 35' 44" E	1,014.35'



- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

MATCHLINE STA 1079+00

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX



(SH 152)

SHEET 2 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
SHEET NO. 60		

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 3.dgn

MATCHLINE STA 1079+00




Point	North	East	Elevation	Station	Offset	Description
CP-108	3,869,865.26	732,377.48	3,088.99'	1082+99.84	49.64' RT	SET 5/8" IR W/RODS CAP
CP-3	3,869,728.21	733,205.43	3,091.90'	1091+29.75	75.01' LT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (3)
T-305	3,869,682.63	733,197.28	3,095.10'	1091+36.04	29.14' LT	SET MAG NAIL IN ASPH
CP-109	3,869,403.03	733,780.34	3,092.01'	1097+76.87	57.26' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-107	CP-108	S 64° 35' 44" E	1,014.35'
CP-108	CP-3	S 80° 36' 05" E	839.22'
CP-3	CP-109	S 60° 30' 24" E	660.51'
CP-109	CP-110	S 76° 21' 13" E	1,008.21'

NOTES:



1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

MATCHLINE STA 1103+00



PI STATION	= 1107+87.90	PI STATION	= 1113+86.19
DELTA	= 10° 27' 45.78" (RT)	DELTA	= 3° 14' 28.71" (RT)
DEGREE OF CURVE	= 1° 00' 00.00"	DEGREE OF CURVE	= 1° 59' 59.20"
TANGENT	= 524.59	TANGENT	= 81.06
LENGTH	= 1,046.27	LENGTH	= 162.08
RADIUS	= 5,729.58	RADIUS	= 2,865.11
PC STATION	= 1102+63.30	PC STATION	= 1113+05.13
PT STATION	= 1113+09.57	PT STATION	= 1114+67.21

Point	North	East	Elevation	Station	Offset	Description
T-307	3,869,163.12	734,519.17	3,057.72'	1105+88.86	48.75' RT	SET MAG NAIL IN ASPH
T-306	3,869,230.05	734,563.13	3,059.39'	1106+05.57	29.57' LT	SET MAG NAIL IN ASPH
CP-110	3,869,165.17	734,760.09	3,056.08'	1108+11.07	44.61' LT	SET 5/8" IR W/RODS CAP
CP-111	3,868,621.49	735,564.15	3,056.44'	1117+72.83	50.13' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-109	CP-110	S 76° 21' 13" E	1,008.21'
CP-110	CP-111	S 55° 56' 05" E	970.62'
CP-111	CP-112	S 57° 38' 01" E	1,100.13'

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700


Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657


HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	61
CONTROL	SECTION	JOB	
0455	02	031, ETC	

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Control Sheet 4.dgn



PI STATION = 1132+93.64
 DELTA = 23° 51' 54.15" (RT)
 DEGREE OF CURVE = 1° 59' 59.47"
 TANGENT = 605.45
 LENGTH = 1,193.34
 RADIUS = 2,865.00
 PC STATION = 1126+88.20
 PT STATION = 1138+81.54



Point	North	East	Elevation	Station	Offset	Description
CP-112	3,868,032.56	736,493.36	3,041.38'	1128+76.68	55.37' RT	SET 5/8" IR W/RODS CAP
CP-113	3,867,217.90	737,244.43	3,067.00'	1140+12.58	66.15' RT	SET 5/8" IR W/RODS CAP
CP-4	3,866,812.26	737,508.62	3,092.26'	1144+96.54	76.97' RT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (4)

From	To	Direction	Distance
CP-111	CP-112	S 57° 38' 01" E	1,100.13'
CP-112	CP-113	S 42° 40' 27" E	1,108.05'
CP-113	CP-4	S 33° 04' 36" E	484.08'
CP-4	CP-114	S 41° 33' 41" E	1,036.53'




- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy D. Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



Point	North	East	Elevation	Station	Offset	Description
T-308	3,866,187.88	737,992.88	3,106.88'	1152+85.27	29.59' RT	SET MAG NAIL IN ASPH
CP-114	3,866,036.68	738,196.28	3,114.53'	1155+24.89	53.00' LT	SET 5/8" IR W/RODS CAP
CP-115	3,864,989.54	738,783.56	3,174.44'	1167+45.39	53.15' RT	SET 5/8" IR W/RODS CAP

EQUATION:
Sta 1166+79.30 BK =
Sta 1167+03.92 AH

From	To	Direction	Distance
CP-4	CP-114	S 41° 33' 41" E	1,036.53'
CP-114	CP-115	S 29° 17' 07" E	1,200.59'
CP-115	CP-116	S 36° 47' 54" E	1,201.75'

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700


Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 5.dgn




- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.





Jimmy D. Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



Point	North	East	Elevation	Station	Offset	Description	From	To	Direction	Distance
CP-116	3,864,027.23	739,503.41	3,191.53'	1179+35.04	73.71' RT	SET 5/8" IR W/RODS CAP	CP-115	CP-116	S 36° 47' 54" E	1,201.75'
CP-117	3,863,554.27	740,180.42	3,193.05'	1187+42.73	74.58' RT	SET 5/8" IR W/RODS CAP	CP-116	CP-117	S 55° 03' 41" E	825.85'
T-309	3,863,592.20	740,313.11	3,191.21'	1188+44.49	17.51' LT	SET MAG NAIL IN ASPH	CP-117	CP-5	S 71° 09' 35" E	1,040.91'



Point	North	East	Elevation	Station	Offset	Description	From	To	Direction	Distance
CP-5	3,863,218.13	741,165.56	3,201.31'	1197+74.96	46.09' LT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (5)	CP-117	CP-5	S 71° 09' 35" E	1,040.91'
CP-118	3,862,702.54	742,262.28	3,196.73'	1209+86.82	51.87' LT	SET 5/8" IR W/RODS CAP	CP-5	CP-118	S 64° 49' 15" E	1,211.87'
CP-119	3,862,187.19	743,119.90	3,221.71'	1219+82.68	44.89' RT	SET 5/8" IR W/RODS CAP	CP-118	CP-119	S 58° 59' 52" E	1,000.55'
							CP-119	CP-120	S 70° 01' 48" E	963.94'

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023




I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

SHEET 5 OF 15		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		63

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 6.dgn

MATCHLINE STA 1221+00




Point	North	East	Elevation	Station	Offset	Description	From	To	Direction	Distance
CP-120	3,861,857.97	744,025.88	3,234.72'	1229+42.21	47.21' LT	SET 5/8" IR W/RODS CAP	CP-119	CP-120	S 70° 01' 48" E	963.94'
T-310	3,861,578.39	744,657.99	3,230.52'	1236+33.13	66.42' LT	SET MAG NAIL IN ASPH	CP-120	CP-121	S 64° 09' 47" E	1,056.75'
CP-121	3,861,397.43	744,977.00	3,229.58'	1239+91.07	49.35' LT	SET 5/8" IR W/RODS CAP	CP-121	CP-6	S 49° 28' 39" E	1,065.60'


NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.


THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



PI STATION = 1244+75.19
 DELTA = 27° 55' 30.31" (RT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 712.28
 LENGTH = 1,396.25
 RADIUS = 2,864.79
 PC STATION = 1237+62.91
 PT STATION = 1251+59.16



Point	North	East	Elevation	Station	Offset	Description	From	To	Direction	Distance
CP-6	3,860,705.06	745,787.01	3,227.34'	1250+44.46	49.86' LT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (6)	CP-121	CP-6	S 49° 28' 39" E	1,065.60'
CP-122	3,860,035.38	746,169.91	3,234.95'	1258+08.38	44.66' RT	SET 5/8" IR W/RODS CAP	CP-6	CP-122	S 29° 45' 33" E	771.41'
							CP-122	CP-123	S 41° 47' 28" E	1,050.91'

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700



I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
 (SH 152)


SHEET 6 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

64

MATCHLINE STA 1267+00

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 7.dgn



- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.




Jimmy D. Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E


MATCHLINE STA 1267+00

MATCHLINE STA 1290+00




Point	North	East	Elevation	Station	Offset	Description
CP-123	3,859,251.84	746,870.25	3,235.13'	1268+55.01	50.01' LT	SET 5/8" IR W/RODS CAP
CP-124	3,858,395.26	747,388.45	3,225.18'	1278+51.62	45.08' RT	SET 5/8" IR W/RODS CAP
T-311	3,857,865.03	747,866.58	3,195.25'	1285+62.39	22.36' LT	SET MAG NAIL IN ASPH

From	To	Direction	Distance
CP-122	CP-123	S 41° 47' 28" E	1,050.91'
CP-123	CP-124	S 31° 10' 20" E	1,001.13'
CP-124	CP-125	S 36° 36' 07" E	1,236.87'



MATCHLINE STA 1290+00

MATCHLINE STA 1314+00



Point	North	East	Elevation	Station	Offset	Description
CP-125	3,857,402.30	748,125.93	3,190.72'	1290+88.49	45.52' RT	SET 5/8" IR W/RODS CAP
CP-7	3,856,448.96	748,950.79	3,187.12'	1303+45.69	47.79' LT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (7)

From	To	Direction	Distance
CP-124	CP-125	S 36° 36' 07" E	1,236.87'
CP-125	CP-7	S 40° 52' 03" E	1,260.66'
CP-7	CP-126	S 36° 37' 52" E	1,200.01'

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)


SHEET 7 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	65
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 8.dgn
DRAWING DATE: 6/26/2023


MATCHLINE STA 1314+00

MATCHLINE STA 1338+00



Point	North	East	Elevation	Station	Offset	Description
CP-126	3,855,485.96	749,666.79	3,214.27'	1315+45.70	47.97' LT	SET 5/8" IR W/RODS CAP
T-312	3,855,095.26	749,979.81	3,229.31'	1320+46.00	66.12' LT	SET MAG NAIL IN ASPH
T-313	3,854,910.92	749,977.12	3,236.83'	1321+92.34	46.00' RT	SET MAG NAIL IN ASPH
CP-127	3,854,846.86	750,023.36	3,238.68'	1322+71.33	47.10' RT	SET 5/8" IR W/RODS CAP
CP-128	3,854,301.19	750,543.03	3,247.53'	1330+19.29	44.46' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-7	CP-126	S 36° 37' 52" E	1,200.01'
CP-126	CP-127	S 29° 09' 29" E	731.84'
CP-127	CP-128	S 43° 36' 06" E	753.54'
CP-128	CP-129	S 36° 30' 00" E	1,001.60'





- NOTES:
- ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 - ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 - COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 - HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 - ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



Point	North	East	Elevation	Station	Offset	Description
CP-129	3,853,496.04	751,138.80	3,239.05'	1340+20.89	42.32' LT	SET 5/8" IR W/RODS CAP
FL0792	3,855,849.11	754,426.53	3,280.83'	1340+93.61	4,084.69' LT	FND DISK IN CONC SLAB (K 228 1934)
CP-130	3,852,801.13	751,547.88	3,244.54'	1348+22.64	43.91' RT	SET 5/8" IR W/RODS CAP
CP-8	3,852,144.40	752,031.20	3,235.48'	1356+38.05	47.77' RT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (8)

From	To	Direction	Distance
CP-128	CP-129	S 36° 30' 00" E	1,001.60'
CP-129	CP-130	S 30° 29' 03" E	806.37'
CP-130	CP-8	S 36° 21' 03" E	815.42'
CP-8	CP-131	S 41° 57' 55" E	1,001.01'

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPES SURVEYING FIRM REG. No. 10030700




I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPES REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

SHEET 8 OF 15		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		66


DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 9.dgn

MATCHLINE STA 1362+00




Point	North	East	Elevation	Station	Offset	Description
CP-131	3,851,400.09	752,700.56	3,245.00'	1366+34.71	45.44' LT	SET 5/8" IR W/RODS CAP
CP-132	3,850,548.12	753,220.97	3,269.97'	1376+28.93	45.13' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-8	CP-131	S 41° 57' 55" E	1,001.01'
CP-131	CP-132	S 31° 25' 04" E	998.34'
CP-132	CP-133	S 38° 15' 15" E	1,201.59'



PI STATION = 1387+74.74
 DELTA = 10° 45' 31.64" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 539.53
 LENGTH = 1,075.88
 RADIUS = 5,729.58
 PC STATION = 1382+35.22
 PT STATION = 1393+11.10

MATCHLINE STA 1386+00




Point	North	East	Elevation	Station	Offset	Description
CP-133	3,849,604.54	753,964.93	3,272.95'	1388+25.02	41.46' RT	SET 5/8" IR W/RODS CAP
CP-134	3,848,982.77	754,750.16	3,282.27'	1398+20.93	53.43' LT	SET 5/8" IR W/RODS CAP
T-314	3,848,614.03	754,962.51	3,284.22'	1402+26.87	74.13' RT	SET MAG NAIL IN ASPH
CP-135	3,848,561.34	755,045.85	3,284.14'	1403+23.88	56.47' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-132	CP-133	S 38° 15' 15" E	1,201.59'
CP-133	CP-134	S 51° 37' 35" E	1,001.59'
CP-134	CP-135	S 35° 03' 17" E	514.81'
CP-135	CP-9	S 55° 48' 32" E	750.01'

MATCHLINE STA 1410+00

- NOTES:
- ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 - ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 - COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 - HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 - ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700



I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
 (SH 152)

SHEET 9 OF 15


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

67

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 10.dgn
DRAWING DATE: 6/26/2023

MATCHLINE STA 1410+00

MATCHLINE STA 1434+00




PI STATION = 1423+69.51
 DELTA = 9° 35' 01.69" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 480.31
 LENGTH = 958.38
 RADIUS = 5,729.58
 PC STATION = 1418+89.20
 PT STATION = 1428+47.58

EQUATION:
 Sta 1418+91.98 BK =
 Sta 1418+89.20 AH

Point	North	East	Elevation	Station	Offset	Description
CP-9	3,848,139.87	755,666.23	3,269.40'	1410+65.79	53.45' LT	SET 5/8" IR W/TXDOT ALUM DISK IN CONC (9)
CP-136	3,847,389.31	756,326.89	3,276.79'	1420+55.84	53.97' RT	SET 5/8" IR W/RODS CAP
CP-137	3,846,887.53	757,023.33	3,232.68'	1429+08.32	39.84' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-135	CP-9	S 55° 48' 32" E	750.01'
CP-9	CP-136	S 41° 21' 17" E	999.90'
CP-136	CP-137	S 54° 13' 39" E	858.38'
CP-137	CP-138	S 61° 42' 10" E	1,100.94'




- NOTES:
- ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 - ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 - COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 - HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 - ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.




6-27-2023
Jimmy Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



Point	North	East	Elevation	Station	Offset	Description
CP-138	3,846,365.64	757,992.71	3,240.73'	1440+05.50	51.09' LT	SET 5/8" IR W/RODS CAP
CP-139	3,845,785.98	758,697.93	3,237.89'	1449+12.71	50.40' RT	SET 5/8" IR W/RODS CAP
CP-140	3,845,487.26	759,371.55	3,245.23'	1456+40.28	66.39' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-137	CP-138	S 61° 42' 10" E	1,100.94'
CP-138	CP-139	S 50° 34' 55" E	912.88'
CP-139	CP-140	S 66° 05' 04" E	736.88'
CP-140	CP-10	S 45° 17' 08" E	742.30'



RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700



I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX



(SH 152)

SHEET 10 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	68
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 11.dgn
DRAWING DATE: 6/26/2023

MATCHLINE STA 1458+00



Point	North	East	Elevation	Station	Offset	Description
CP-10	3,844,964.99	759,899.05	3,284.80'	1463+67.28	83.88' RT	SET 5/8" IR W/TXDOT ALUM DISK IN CONC (10)
T-315	3,844,622.63	760,609.51	3,238.89'	1471+49.00	29.69' LT	SET MAG NAIL IN ASPH
CP-141	3,844,607.65	760,678.47	3,233.36'	1472+14.48	56.01' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-140	CP-10	S 45° 17' 08" E	742.30'
CP-10	CP-141	S 65° 22' 13" E	857.44'
CP-141	CP-142	S 50° 34' 53" E	1,200.12'

MATCHLINE STA 1482+00

NOTES:
 1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.



THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



6-27-2023
Jimmy D. Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

MATCHLINE STA 1482+00



Point	North	East	Elevation	Station	Offset	Description
CP-142	3,843,845.60	761,605.60	3,236.18'	1484+09.54	54.10' RT	SET 5/8" IR W/RODS CAP
CP-143	3,843,357.55	762,356.86	3,209.40'	1492+97.02	66.92' RT	FND 5/8" IR W/TXDOT ALUM DISK
CP-144	3,843,248.44	763,148.78	3,166.43'	1499+01.69	71.92' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-141	CP-142	S 50° 34' 53" E	1,200.12'
CP-142	CP-143	S 56° 59' 26" E	895.87'
CP-143	CP-144	S 82° 09' 19" E	799.41'
CP-144	CP-145	S 67° 24' 26" E	882.83'

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
 © 2023

I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBP REG. # F-11657



HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

SHEET 11 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	69
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 12.dgn
 DRAWING DATE: 6/26/2023

PI STATION = 1510+01.86
 DELTA = 21° 56' 49.39" (RT)
 DEGREE OF CURVE = 2° 17' 30.59"
 TANGENT = 484.75
 LENGTH = 957.62
 RADIUS = 2,500.00
 PC STATION = 1505+17.11
 PT STATION = 1514+74.73




Point	North	East	Elevation	Station	Offset	Description
CP-145	3,842,909.27	763,963.86	3,157.69'	1507+78.15	75.19' RT	SET 5/8" IR W/RODS CAP
CP-11	3,842,782.72	764,623.62	3,205.29'	1514+27.03	96.61' LT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (11)



From	To	Direction	Distance
CP-144	CP-145	S 67° 24' 26" E	882.83'
CP-145	CP-11	S 79° 08' 31" E	671.78'
CP-11	CP-146	S 49° 53' 48" E	1,357.98'

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



Point	North	East	Elevation	Station	Offset	Description
CP-146	3,841,907.96	765,662.32	3,244.19'	1529+71.76	46.43' RT	SET 5/8" IR W/RODS CAP
CP-147	3,841,446.05	766,556.95	3,260.22'	1539+71.58	72.25' LT	SET 5/8" IR W/RODS CAP
CP-148	3,840,997.09	767,213.93	3,275.31'	1547+67.30	68.48' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-11	CP-146	S 49° 53' 48" E	1,357.98'
CP-146	CP-147	S 62° 41' 33" E	1,006.84'
CP-147	CP-148	S 55° 39' 07" E	795.73'
CP-148	CP-149	S 55° 27' 59" E	1,139.18'

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPES SURVEYING FIRM REG. No. 10030700



I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657



HORIZONTAL & VERTICAL CONTROL INDEX
 (SH 152)

SHEET 12 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	70
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 13.dgn
DRAWING DATE: 6/26/2023

MATCHLINE STA 1552+00



Point	North	East	Elevation	Station	Offset	Description
CP-149	3,840,351.30	768,152.37	3,285.12'	1559+06.44	59.40' LT	SET 5/8" IR W/RODS CAP
CP-12	3,839,631.39	769,030.67	3,306.80'	1570+33.33	53.66' RT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (12)

From	To	Direction	Distance
CP-148	CP-149	S 55° 27' 59" E	1,139.18'
CP-149	CP-12	S 50° 39' 35" E	1,135.64'
CP-12	CP-150	S 68° 20' 40" E	841.34'

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.



THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy Walton

THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

MATCHLINE STA 1575+00



PI STATION = 1577+14.16
 DELTA = 35° 02' 37.40" (LT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 904.47'
 LENGTH = 1,752.19'
 RADIUS = 2,864.79'
 PC STATION = 1568+09.70
 PT STATION = 1585+61.88

Point	North	East	Elevation	Station	Offset	Description
CP-150	3,839,320.91	769,812.63	3,324.21'	1578+61.37	58.58' RT	SET 5/8" IR W/RODS CAP
CP-151	3,839,358.66	771,015.15	3,322.13'	1590+57.14	45.83' LT	SET 5/8" IR W/RODS CAP
T-316	3,839,378.80	771,093.25	3,322.16'	1591+35.57	64.65' LT	SET MAG NAIL IN ASPH
T-317	3,839,230.72	771,112.78	3,320.48'	1591+52.60	83.74' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-12	CP-150	S 68° 20' 40" E	841.34'
CP-150	CP-151	N 88° 12' 07" E	1,203.11'
CP-151	CP-152	S 86° 38' 20" E	1,198.98'

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700




I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
 (SH 152)

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	71
CONTROL	SECTION	JOB	
0455	02	031, ETC	


DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Control Sheet 14.dgn

MATCHLINE STA 1597+00



Point	North	East	Elevation	Station	Offset	Description
CP-152	3,839,288.37	772,212.07	3,321.03'	1602+52.70	44.65' RT	SET 5/8" IR W/RODS CAP
CP-153	3,839,305.94	773,184.92	3,320.22'	1612+25.71	43.49' RT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-151	CP-152	S 86° 38' 20" E	1,198.98'
CP-152	CP-153	N 88° 57' 55" E	973.02'
CP-153	CP-13	N 89° 13' 40" E	1,066.04'



MATCHLINE STA 1616+00

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.


THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



Jimmy Walton


THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

MATCHLINE STA 1616+00



Point	North	East	Elevation	Station	Offset	Description
CP-13	3,839,320.31	774,250.87	3,317.76'	1622+91.75	47.11' RT	SET 5/8" IR W/TXDOT ALUM CAP IN CONC (13)
CP-154	3,839,430.62	775,410.40	3,313.38'	1634+52.98	43.62' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-153	CP-13	N 89° 13' 40" E	1,066.04'
CP-13	CP-154	N 84° 33' 57" E	1,164.77'
CP-154	CP-155	N 88° 57' 04" E	1,198.36'



MATCHLINE STA 1640+00

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023


I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
(SH 152)

SHEET 14 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6	(SEE TITLE SHEET)	SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	72
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Index Sheet 15.dgn
DRAWING DATE: 6/26/2023



NOTES:
 1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E



RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700

Control Infrastructure Transportation Land Development




I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL INDEX
 (SH 152)


SHEET 15 OF 15

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC



Point	North	East	Elevation	Station	Offset	Description
T-318	3,839,271.20	776,397.07	3,309.53'	1644+36.82	132.42' RT	SET 5/8" IR W/RODS CAP
CP-155	3,839,452.55	776,608.56	3,308.85'	1646+51.34	45.33' LT	SET 5/8" IR W/RODS CAP
CP-156	3,839,473.17	777,807.46	3,301.18'	1658+50.41	45.72' LT	SET 5/8" IR W/RODS CAP

From	To	Direction	Distance
CP-154	CP-155	N 88° 57' 04" E	1,198.36'
CP-155	CP-156	N 89° 00' 53" E	1,199.07'
CP-156	CP-157	N 89° 06' 29" E	860.11'



From	To	Direction	Distance
CP-156	CP-157	N 89° 06' 29" E	860.11'
CP-157	CP-14	S 83° 31' 33" E	829.42'
CP-14	CP-158	N 83° 49' 54" E	1,004.24'


Point	North	East	Elevation	Station	Offset	Description
CP-157	3,839,486.56	778,667.46	3,291.93'	1667+26.26	46.84' LT	SET 5/8" IR W/RODS CAP
CP-14	3,839,393.03	779,491.60	3,284.47'	1675+49.72	43.76' RT	SET 5/8" IR W/TXDOT ALUM DISK IN CONC (14)
CP-158	3,839,500.94	780,490.02	3,273.97'	Off Chain	Off Chain	SET 5/8" IR W/RODS CAP
FL0642	3,841,069.62	816,810.84	3,237.93'	Off Chain	Off Chain	FND DISK IN CONC (PAMPA 1934)
TXPM	3,840,398.41	826,302.01	3,236.64'	Off Chain	Off Chain	CORS TXPM

Control Name	Published Coordinate Information			Measured Coordinate Information			Residuals (Published - Measured)		
	North	East	Elev.	North	East	Elev.	North	East	Elev.
FL0642	3,841,064	816,810	3,237.90	3,841,069.62	816,810.84	3,237.93	-5.6	-0.8	-0.03
FL0792	3,855,849.5	754,427.3	3,280.84	3,855,849.11	754,426.53	3,280.83	0.4	0.8	0.01


Notes:
 1. Measured values are based on redundant GPS VRS observations measured from CORS TXPM and TXBR during September 2022 and an applied surface adjustment factor of 1.000190.
 2. NGS monument PIDs FL0642 and FL0792 are of second vertical order, class zero; published values are based on NAD83 (1986 adjustment), NAVD88; horizontal coordinates are approximate, orthometric heights (elevations) were established by differential leveling in June 1991.

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn


DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.41 MILE EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 1.64 MILE EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.83 MILE EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 2.06 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 2.27 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 2.40 MILES EAST OF FM 280.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 2.59 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 2.81 MILES EAST OF FM 280.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 3.04 MILES EAST OF FM 280.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TxDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
Surveying, Inc.
6810 LEE ROAD, STE.100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657


HORIZONTAL & VERTICAL CONTROL SHEET
(SH 152)

SHEET 1 OF 9


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		74

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn


DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 3.23 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 3.39 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 3.51 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 3.70 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 3.88 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 4.09 MILES EAST OF FM 280.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 4.31 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 4.40 MILES EAST OF FM 280.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 4.59 MILES EAST OF FM 280.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023


I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657

HORIZONTAL & VERTICAL CONTROL SHEET
(SH 152)


SHEET 2 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		75


FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn
 DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 4.82 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 5.39 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 5.99 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 5.04 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 5.62 MILES EAST OF FM 280.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 348' EAST OF FM 1059.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 5.19 MILES EAST OF FM 280.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 5.81 MILES EAST OF FM 280.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.26 MILE EAST OF FM 1059.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E


RODS
 Surveying, Inc.
 6810 LEE ROAD, STE.100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
 © 2023


I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBP REG. # F-11657

HORIZONTAL & VERTICAL CONTROL SHEET			
(SH 152)			
SHEET 3 OF 9			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	
CONTROL	SECTION	JOB	76
0455	02	031, ETC	


FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn
 DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.41 MILE EAST OF FM 1059.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.61 MILE EAST OF FM 1059.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.80 MILE EAST OF FM 1059.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.03 MILE EAST OF FM 1059.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 1.27 MILE EAST OF FM 1059.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 1.50 MILE EAST OF FM 1059.



STATION IS LOCATED 308' EAST OF ELM ST, AND LYING 0.13 MILE NORTH OF 1ST ST.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 237' EAST OF 1ST ST.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.18 MILE EAST OF 1ST ST.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
 © 2023

I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBP REG. # F-11657


HORIZONTAL & VERTICAL CONTROL SHEET
 (SH 152)

SHEET 4 OF 9


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		77

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn


DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.37 MILE EAST OF 1ST ST.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.86 MILE EAST OF 1ST ST.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 157' EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.52 MILE EAST OF 1ST ST.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.05 MILE EAST OF 1ST ST.




STATION IS LOCATED ON THE SOUTHEAST CORNER OF THE INTERSECTION OF SH 152 AND FM 294.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.67 MILE EAST OF 1ST ST.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.28 MILE EAST OF 1ST ST.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.17 MILE EAST OF FM 294.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
Surveying, Inc.
6810 LEE ROAD, STE.100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657


HORIZONTAL & VERTICAL CONTROL SHEET
(SH 152)

SHEET 5 OF 9


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		78

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn


DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.36 MILE EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.90 MILE EAST OF FM 294.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 1.34 MILE EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.52 MILE EAST OF FM 294.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 1.04 MILE EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.56 MILE EAST OF FM 294.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.73 MILE EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.18 MILE EAST OF FM 294.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 1.73 MILE EAST OF FM 294.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657


HORIZONTAL & VERTICAL CONTROL SHEET
(SH 152)

SHEET 6 OF 9


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		79

FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn


DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 1.88 MILE EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 2.04 MILES EAST OF FM 294.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 2.16 MILES EAST OF FM 294.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 128' WEST OF FM 2386.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.16 MILE EAST OF FM 2386.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.31 MILE EAST OF FM 2386.



STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.53 MILE EAST OF FM 2386.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.74 MILE EAST OF FM 2386.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.89 MILE EAST OF FM 2386.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E


RODS
Surveying, Inc.
6810 LEE ROAD, STE. 100
SPRING, TEXAS 77379
TEL (281) 257-4020
FAX (281) 257-4021
TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
© 2023


I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBP REG. # F-11657

HORIZONTAL & VERTICAL CONTROL SHEET			
(SH 152)			
SHEET 7 OF 9			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	80
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn
 DRAWING DATE: 6/26/2023




STATION IS LOCATED ON THE NORTHWEST CORNER OF THE INTERSECTION OF SH 152 AND COUNTY RD CC.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.59 MILE EAST OF COUNTY RD CC.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.27 MILE EAST OF COUNTY RD DD.




STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.21 MILE EAST OF COUNTY RD CC.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.81 MILE EAST OF COUNTY RD CC.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.43 MILE EAST OF COUNTY RD DD.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.39 MILE EAST OF COUNTY RD CC.




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 242' EAST OF COUNTY RD DD.



STATION IS LOCATED ON THE SOUTH SIDE OF SH 152, AND LYING 0.59 MILE EAST OF COUNTY RD DD.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.
- THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
 Surveying, Inc.
 Control Infrastructure Transportation Land Development
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700

Texas Department of Transportation
 © 2023


I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBP REG. # F-11657

HORIZONTAL & VERTICAL CONTROL SHEET
 (SH 152)


SHEET 8 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		81

DRAWING DATE: 6/26/2023 FILENAME: N:\I.S. Engineers\528\21942005\CAD\H&V Control\CARSON COUNTY\H&V Sketches\Carson Cnty.dgn




STATION IS LOCATED ON THE NORTH SIDE OF SH 152, AND LYING 0.78 MILE EAST OF COUNTY RD DD.



STATION IS LOCATED ON THE SOUTH SIDE OF FOSTER AVE, AND LYING 121' WEST OF BALLARD ST.

- NOTES:
1. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS COORDINATE SYSTEM, NORTH ZONE (4201), NORTH AMERICAN DATUM OF 1983 (NAD83) (2011 ADJ.; EPOCH 2010.00).
 2. ALL ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (GEOID MODEL 12B).
 3. COORDINATES AND DISTANCES ARE U.S. SURVEY FEET, DISPLAYED IN SURFACE VALUES, AND MAY BE CONVERTED TO NAD83 (GRID) VALUES BY APPLYING THE SURFACE ADJUSTMENT FACTOR (SAF) FOR CARSON AND GRAY COUNTIES, SAF = 1.000190, USING THE FORMULA: SURFACE / SAF = GRID
 4. HORIZONTAL COORDINATES ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS MEASURED FROM TXDOT CORS TXPM AND TXBR DURING SEPTEMBER 2022.
 5. ELEVATIONS ARE BASED ON REDUNDANT GPS RTN OBSERVATIONS, ADJUSTED WITH DIGITAL LEVELING.


THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



THIS SURVEY CONTROL INFORMATION HAS BEEN ACCEPTED AND INCORPORATED INTO THIS PS&E

RODS
 Surveying, Inc.
 6810 LEE ROAD, STE. 100
 SPRING, TEXAS 77379
 TEL (281) 257-4020
 FAX (281) 257-4021
 TBPELS SURVEYING FIRM REG. No. 10030700

Control Infrastructure Transportation Land Development



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

HORIZONTAL & VERTICAL CONTROL SHEET
 (SH 152)

SHEET 9 OF 9

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	GRAY	82
CONTROL	SECTION	JOB	
0455	02	031, ETC	

PROPOSED SH 152 ALIGNMENT

Beginning chain SH152 description

Feature: ML_CL

Point SH1521 N 3,873,065.5251 E 723,041.3382 Sta 984+25.40

Course from SH1521 to PC SH152_3 S 64° 57' 51.46" E Dist 609.5100

Curve Data

Curve SH152_3
 P.I. Station 993+90.11 N 3,872,657.2779 E 723,915.4046
 Delta = 7° 05' 41.42" (LT)
 Degree = 1° 00' 00.00"
 Tangent = 355.1961
 Length = 709.4843
 Radius = 5,729.5800
 External = 10.9993
 Long Chord = 709.0311
 Mid. Ord. = 10.9783
 P.C. Station 990+34.91 N 3,872,807.5909 E 723,593.5812
 P.T. Station 997+44.39 N 3,872,547.8650 E 724,253.3293
 C.C. = N 3,877,998.8438 E 726,018.2420
 Back = S 64° 57' 51.46" E
 Ahead = S 72° 03' 32.88" E
 Chord Bear = S 68° 30' 42.17" E

Course from PT SH152_3 to PC SH152_61 S 72° 03' 32.88" E Dist 10,486.6634

Curve Data

Curve SH152_61
 P.I. Station 1102+31.06 N 3,869,317.6025 E 734,230.0791
 Delta = 0° 00' 00.08" (RT)
 Degree = 1° 00' 00.00"
 Tangent = 0.0012
 Length = 0.0023
 Radius = 5,729.5800
 External = 0.0000
 Long Chord = 0.0023
 Mid. Ord. = 0.0000
 P.C. Station 1102+31.06 N 3,869,317.6028 E 734,230.0780
 P.T. Station 1102+31.06 N 3,869,317.6021 E 734,230.0802
 C.C. = N 3,863,866.6240 E 732,465.1653
 Back = S 72° 03' 32.88" E
 Ahead = S 72° 03' 32.80" E
 Chord Bear = S 72° 03' 32.86" E

Equation: Sta 1102+31.06 (BK) = Sta 1102+63.30 (AH)

End Region 1
 Begin Region 2

Curve Data

Curve SH152_62
 P.I. Station 1107+87.89 N 3,869,156.0082 E 734,729.1664
 Delta = 10° 27' 45.78" (RT)
 Degree = 1° 00' 00.00"
 Tangent = 524.5947
 Length = 1,046.2722
 Radius = 5,729.5800
 External = 23.9656
 Long Chord = 1,044.8191
 Mid. Ord. = 23.8657
 P.C. Station 1102+63.30 N 3,869,317.6021 E 734,230.0802
 P.T. Station 1113+09.57 N 3,868,906.4693 E 735,190.6096
 C.C. = N 3,863,866.6240 E 732,465.1653
 Back = S 72° 03' 32.80" E
 Ahead = S 61° 35' 47.01" E
 Chord Bear = S 66° 49' 39.90" E

Curve Data

Curve SH152_71
 P.I. Station 1113+09.58 N 3,868,906.4674 E 735,190.6130
 Delta = 0° 00' 00.56" (RT)
 Degree = 1° 59' 58.50"
 Tangent = 0.0039
 Length = 0.0078
 Radius = 2,865.3855
 External = 0.0000
 Long Chord = 0.0078
 Mid. Ord. = 0.0000
 P.C. Station 1113+09.57 N 3,868,906.4693 E 735,190.6096
 P.T. Station 1113+09.58 N 3,868,906.4655 E 735,190.6165
 C.C. = N 3,866,389.1761 E 733,821.7894
 Back = S 61° 27' 50.85" E
 Ahead = S 61° 27' 50.29" E
 Chord Bear = S 61° 27' 50.57" E

Equation: Sta 1113+09.58 (BK) = Sta 1113+05.13 (AH)

End Region 2
 Begin Region 3

PROPOSED SH 152 ALIGNMENT

Curve Data

Curve SH152_72
 P.I. Station 1113+86.20 N 3,868,867.7388 E 735,261.8354
 Delta = 3° 14' 28.14" (RT)
 Degree = 1° 59' 58.50"
 Tangent = 81.0673
 Length = 162.0913
 Radius = 2,865.3855
 External = 1.1465
 Long Chord = 162.0697
 Mid. Ord. = 1.1461
 P.C. Station 1113+05.13 N 3,868,906.4655 E 735,190.6165
 P.T. Station 1114+67.22 N 3,868,825.0474 E 735,330.7509
 C.C. = N 3,866,389.1761 E 733,821.7894
 Back = S 61° 27' 50.29" E
 Ahead = S 58° 13' 22.15" E
 Chord Bear = S 59° 50' 36.22" E

Course from PT SH152_72 to PC SH152_10 S 58° 13' 22.15" E Dist 1,220.9740

Curve Data

Curve SH152_10
 P.I. Station 1132+93.64 N 3,867,863.2216 E 736,883.3975
 Delta = 23° 51' 54.15" (RT)
 Degree = 1° 59' 59.47"
 Tangent = 605.4488
 Length = 1,193.3399
 Radius = 2,865.0000
 External = 63.2748
 Long Chord = 1,184.7322
 Mid. Ord. = 61.9075
 P.C. Station 1126+88.20 N 3,868,182.0613 E 736,368.7040
 P.T. Station 1138+81.54 N 3,867,363.4057 E 737,225.0878
 C.C. = N 3,865,746.5177 E 734,859.9454
 Back = S 58° 13' 22.15" E
 Ahead = S 34° 21' 28.00" E
 Chord Bear = S 46° 17' 25.07" E

Course from PT SH152_10 to STAEQU3 S 34° 21' 28.00" E Dist 2,797.7648

Equation: Sta 1166+79.30 (BK) = Sta 1167+03.92 (AH) End Region 3
 Begin Region 4

Point STAEQU3 N 3,865,053.7680 E 738,804.0310 Sta 1167+03.92

Course from STAEQU3 to PC SH152_15 S 34° 21' 28.00" E Dist 596.7972

Curve Data

Curve SH152_15
 P.I. Station 1180+73.42 N 3,863,923.2023 E 739,576.9223
 Delta = 30° 11' 23.31" (LT)
 Degree = 2° 00' 00.00"
 Tangent = 772.7063
 Length = 1,509.4910
 Radius = 2,864.7900
 External = 102.3798
 Long Chord = 1,492.0894
 Mid. Ord. = 98.8473
 P.C. Station 1173+00.72 N 3,864,561.0943 E 739,140.8387
 P.T. Station 1188+10.21 N 3,863,591.1230 E 740,274.6317
 C.C. = N 3,866,177.8637 E 741,505.8077
 Back = S 34° 21' 28.00" E
 Ahead = S 64° 32' 51.31" E
 Chord Bear = S 49° 27' 09.65" E

Course from PT SH152_15 to STAEQU4 S 64° 32' 51.31" E Dist 4,956.8819

Equation: Sta 1237+67.09 (BK) = Sta 1237+62.91 (AH) End Region 4
 Begin Region 5

Point STAEQU4 N 3,861,460.8469 E 744,750.4111 Sta 1237+62.91

Curve Data


Curve SH152_18
 P.I. Station 1244+75.20 N 3,861,154.7342 E 745,393.5639
 Delta = 27° 55' 30.31" (RT)
 Degree = 2° 00' 00.00"
 Tangent = 712.2834
 Length = 1,396.2548
 Radius = 2,864.7900
 External = 87.2211
 Long Chord = 1,382.4761
 Mid. Ord. = 84.6440
 P.C. Station 1237+62.91 N 3,861,460.8461 E 744,750.4129
 P.T. Station 1251+59.17 N 3,860,583.0674 E 745,818.4695
 C.C. = N 3,858,874.1053 E 743,519.2369
 Back = S 64° 32' 51.31" E
 Ahead = S 36° 37' 21.00" E
 Chord Bear = S 50° 35' 06.15" E

Course from PT SH152_18 to STAEQU5 S 36° 37' 21.00" E Dist 12,477.9333

Equation: Sta 1376+37.10 (BK) = Sta 1376+35.30 (AH) End Region 5
 Begin Region 6

Point STAEQU5 N 3,850,568.4868 E 753,262.0569 Sta 1376+35.30

Course from STAEQU5 to PC SH152_23 S 36° 37' 21.00" E Dist 599.9187



8/12/2023



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152

HORIZONTAL ALIGNMENT DATA

SHEET 1 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	83
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152\HAD\SH152\HAD.dgn
 DRAWING DATE: 8/12/2023

PROPOSED SH 152 ALIGNMENT

Curve Data

Curve SH152_23				
P.I. Station	1387+74.74	N	3,849,653.9877	E 753,941.7813
Delta	10° 45' 31.64"	(LT)		
Degree	1° 00' 00.00"			
Tangent	539.5258			
Length	1,075.8792			
Radius	5,729.5800			
External	25.3462			
Long Chord	1,074.2992			
Mid. Ord.	25.2345			
P.C. Station	1382+35.22	N	3,850,087.0021	E 753,619.9325
P.T. Station	1393+11.10	N	3,849,288.6659	E 754,338.8054
C.C.		N	3,853,504.9263	E 758,218.3976
Back	= S 36° 37' 21.00"	E		
Ahead	= S 47° 22' 52.63"	E		
Chord Bear	= S 42° 00' 06.82"	E		

Course from PT SH152_23 to PC SH152_261 S 47° 22' 52.63" E Dist 2,580.8820

Curve Data

Curve SH152_261				
P.I. Station	1418+91.98	N	3,847,541.1085	E 756,238.0145
Delta	0° 00' 00.01"	(LT)		
Degree	1° 00' 00.00"			
Tangent	0.0001			
Length	0.0002			
Radius	5,729.5800			
External	0.0000			
Long Chord	0.0002			
Mid. Ord.	0.0000			
P.C. Station	1418+91.98	N	3,847,541.1086	E 756,238.0144
P.T. Station	1418+91.98	N	3,847,541.1085	E 756,238.0145
C.C.		N	3,851,757.3689	E 760,117.6066
Back	= S 47° 22' 52.63"	E		
Ahead	= S 47° 22' 52.64"	E		
Chord Bear	= S 47° 22' 52.47"	E		

Equation: Sta 1418+91.98 (BK) = Sta 1418+89.20 (AH) End Region 6
Begin Region 7

Curve Data

Curve SH152_262				
P.I. Station	1423+69.51	N	3,847,215.8823	E 756,591.4636
Delta	9° 35' 01.69"	(LT)		
Degree	1° 00' 00.00"			
Tangent	480.3107			
Length	958.3806			
Radius	5,729.5800			
External	20.0970			
Long Chord	957.2637			
Mid. Ord.	20.0267			
P.C. Station	1418+89.20	N	3,847,541.1085	E 756,238.0145
P.T. Station	1428+47.58	N	3,846,954.0409	E 756,994.1266
C.C.		N	3,851,757.3689	E 760,117.6066
Back	= S 47° 22' 52.64"	E		
Ahead	= S 56° 57' 54.33"	E		
Chord Bear	= S 52° 10' 23.48"	E		

Course from PT SH152_262 to PC SH152_29 S 56° 57' 54.33" E Dist 3,510.4126

Curve Data

Curve SH152_29				
P.I. Station	1464+69.95	N	3,844,979.3078	E 760,030.8968
Delta	1° 07' 10.22"	(RT)		
Degree	0° 29' 59.99"			
Tangent	111.9547			
Length	223.9022			
Radius	11,459.2000			
External	0.5469			
Long Chord	223.8987			
Mid. Ord.	0.5469			
P.C. Station	1463+57.99	N	3,845,040.3398	E 759,937.0409
P.T. Station	1465+81.90	N	3,844,916.4536	E 760,123.5424
C.C.		N	3,835,433.6504	E 753,690.0591
Back	= S 56° 57' 54.33"	E		
Ahead	= S 55° 50' 44.10"	E		
Chord Bear	= S 56° 24' 19.22"	E		

Course from PT SH152_29 to PC SH152_321 S 55° 50' 44.10" E Dist 2,300.0488

Curve Data

Curve SH152_321				
P.I. Station	1492+06.64	N	3,843,442.8577	E 762,295.5881
Delta	12° 55' 57.04"	(LT)		
Degree	2° 00' 00.00"			
Tangent	324.6926			
Length	646.6258			
Radius	2,864.7900			
External	18.3415			
Long Chord	645.2540			
Mid. Ord.	18.2248			
P.C. Station	1488+81.94	N	3,843,625.1483	E 762,026.8961
P.T. Station	1495+28.57	N	3,843,325.3252	E 762,598.2618
C.C.		N	3,845,995.8408	E 763,635.2613
Back	= S 55° 50' 44.10"	E		
Ahead	= S 68° 46' 41.15"	E		
Chord Bear	= S 62° 18' 42.63"	E		

Equation: Sta 1495+28.57 (BK) = Sta 1493+45.64 (AH) End Region 7
Begin Region 8

PROPOSED SH 152 ALIGNMENT

Curve Data

Curve SH152_322				
P.I. Station	1493+45.64	N	3,843,325.3251	E 762,598.2620
Delta	0° 00' 00.02"	(LT)		
Degree	2° 00' 00.00"			
Tangent	0.0002			
Length	0.0003			
Radius	2,864.7900			
External	0.0000			
Long Chord	0.0003			
Mid. Ord.	0.0000			
P.C. Station	1493+45.64	N	3,843,325.3252	E 762,598.2618
P.T. Station	1493+45.64	N	3,843,325.3250	E 762,598.2621
C.C.		N	3,845,995.8408	E 763,635.2613
Back	= S 68° 46' 41.15"	E		
Ahead	= S 68° 46' 41.17"	E		
Chord Bear	= S 68° 46' 41.13"	E		

Curve Data

Curve SH152_33				
P.I. Station	1495+44.41	N	3,843,253.3729	E 762,783.5557
Delta	9° 05' 31.14"	(LT)		
Degree	2° 17' 30.60"			
Tangent	198.7733			
Length	396.7120			
Radius	2,499.9962			
External	7.8897			
Long Chord	396.2959			
Mid. Ord.	7.8649			
P.C. Station	1493+45.64	N	3,843,325.3250	E 762,598.2621
P.T. Station	1497+42.35	N	3,843,211.6049	E 762,977.8912
C.C.		N	3,845,655.7853	E 763,503.2129
Back	= S 68° 46' 41.17"	E		
Ahead	= S 77° 52' 12.31"	E		
Chord Bear	= S 73° 19' 26.74"	E		

Course from PT SH152_33 to PC SH152_36 S 77° 52' 12.31" E Dist 774.7551

Curve Data

Curve SH152_36				
P.I. Station	1510+01.86	N	3,842,946.9459	E 764,209.2781
Delta	21° 56' 49.39"	(RT)		
Degree	2° 17' 30.59"			
Tangent	484.7521			
Length	957.6208			
Radius	2,500.0000			
External	46.5633			
Long Chord	951.7771			
Mid. Ord.	45.7119			
P.C. Station	1505+17.11	N	3,843,048.8063	E 763,735.3488
P.T. Station	1514+74.73	N	3,842,675.3363	E 764,610.7914
C.C.		N	3,840,604.6222	E 763,210.0262
Back	= S 77° 52' 12.31"	E		
Ahead	= S 55° 55' 22.92"	E		
Chord Bear	= S 66° 53' 47.62"	E		

Course from PT SH152_36 to STAEQU8 S 55° 55' 22.92" E Dist 0.0017

Equation: Sta 1514+74.73 (BK) = Sta 1516+70.83 (AH) End Region 8
Begin Region 9

Point STAEQU8 N 3,842,675.3353 E 764,610.7928 Sta 1516+70.83

Course from STAEQU8 to PC SH152_39 S 55° 55' 22.92" E Dist 5,138.8664


Curve Data

Curve SH152_39				
P.I. Station	1577+14.16	N	3,839,289.2192	E 769,616.3989
Delta	35° 02' 37.40"	(LT)		
Degree	2° 00' 00.00"			
Tangent	904.4667			
Length	1,752.1867			
Radius	2,864.7900			
External	139.3874			
Long Chord	1,725.0027			
Mid. Ord.	132.9201			
P.C. Station	1568+09.70	N	3,839,795.9973	E 768,867.2421
P.T. Station	1585+61.88	N	3,839,304.4796	E 770,520.7368
C.C.		N	3,842,168.8618	E 770,472.4013
Back	= S 55° 55' 22.92"	E		
Ahead	= N 89° 01' 59.68"	E		
Chord Bear	= S 73° 26' 41.62"	E		

Course from PT SH152_39 to STAEQU9 N 89° 01' 59.68" E Dist 7,921.4669

Equation: Sta 1664+83.35 (BK) = Sta 1665+00.00 (AH) End Region 9
Begin Region 10

Point STAEQU9 N 3,839,438.1327 E 778,441.0761 Sta 1665+00.00



8/12/2023

Texas Department of Transportation
I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152		
HORIZONTAL ALIGNMENT DATA		
SHEET 2 OF 3		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		84

DRAWING DATE: 8/12/2023 FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152\HAD\SH152*HAD.dgn

PROPOSED SH 152 ALIGNMENT

Curve Data

Curve SH152_42
P.I. Station 1666+82.84 N 3,839,441.2176 E 778,623.8876
Delta = 1° 49' 41.54" (RT)
Degree = 0° 29' 59.99"
Tangent = 182.8367
Length = 365.6424
Radius = 11,459.2000
External = 1.4585
Long Chord = 365.6269
Mid. Ord. = 1.4583
P.C. Station 1665+00.00 N 3,839,438.1327 E 778,441.0769
P.T. Station 1668+65.64 N 3,839,438.4687 E 778,806.7036
C.C. = N 89° 01' 59.68" E 3,827,980.5639 E 778,634.4196
Back = S 89° 08' 18.78" E
Ahead = N 89° 56' 50.45" E
Chord Bear = N 89° 56' 50.45" E

Course from PT SH152_42 to PC SH152_45 S 89° 08' 18.78" E Dist 237.7338

Curve Data

Curve SH152_45
P.I. Station 1673+03.40 N 3,839,431.8873 E 779,244.4083
Delta = 1° 59' 59.97" (LT)
Degree = 0° 29' 59.99"
Tangent = 200.0203
Length = 400.0000
Radius = 11,459.2000
External = 1.7455
Long Chord = 399.9797
Mid. Ord. = 1.7453
P.C. Station 1671+03.38 N 3,839,434.8945 E 779,044.4106
P.T. Station 1675+03.38 N 3,839,435.8617 E 779,444.3891
C.C. = N 89° 08' 18.78" E 3,850,892.7993 E 779,216.6946
Back = S 89° 08' 18.78" E
Ahead = N 88° 51' 41.25" E
Chord Bear = N 89° 51' 41.23" E


Course from PT SH152_45 to SH15247 N 88° 51' 41.25" E Dist 100.0000

Point SH15247 N 3,839,437.8487 E 779,544.3694 Sta 1676+03.38

Ending chain SH152 description

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*HAD.dgn

DRAWING DATE: 8/12/2023



8/12/2023



I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152

HORIZONTAL ALIGNMENT DATA

SHEET 3 OF 3

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	85
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN1\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'

HUTCHINSON COUNTY LINE
 CARSON COUNTY LINE

PI STATION = 993+90.11
 DELTA = 7° 05' 41.42" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 355.20
 LENGTH = 709.48
 RADIUS = 5,729.58
 PC STATION = 990+34.91
 PT STATION = 997+44.39




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:


- ← PROPOSED TRAFFIC
- ⇄ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▨ PROP WIDENING
- ▩ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▨ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- ▩ PAVEMENT REMOVAL



8/12/2023

MATCH LINE STA 993+00

PI STATION = 993+90.11
 DELTA = 7° 05' 41.42" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 355.20
 LENGTH = 709.48
 RADIUS = 5,729.58
 PC STATION = 990+34.91
 PT STATION = 997+44.39



MATCH LINE STA 1005+00



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657



SH 152
ROADWAY PLAN
BEGIN TO STA 1005+00

SHEET 1 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	86
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN2\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▭ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1005+00 TO 1029+00



SHEET 2 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	87
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN3\$.dgn

DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▭ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1029+00 TO 1053+00



SHEET 3 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	88
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN4\$.dgn

DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152
ROADWAY PLAN
1053+00 TO 1077+00

SHEET 4 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	89
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN5\$.dgn


DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
SCALE 1"=100'

MATCH LINE STA 1077+00

MATCH LINE STA 1089+00



SECTION B - OVERLAY

NOTES:


- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:


- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL

MATCH LINE STA 1089+00

MATCH LINE STA 1101+00



SECTION B - OVERLAY



8/12/2023





I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1077+00 TO 1101+00

SHEET 5 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	90
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN6\$.dgn

DRAWING DATE: 8/12/2023




HORZ 0' 50' 100'
SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1101+00 TO 1124+00

SHEET 6 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


91

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN7\$.dgn
 DRAWING DATE: 8/12/2023

PI STATION = 1132+93.64
 DELTA = 23° 51' 54.15" (RT)
 DEGREE OF CURVE = 1° 59' 59.47"
 TANGENT = 605.45
 LENGTH = 1,193.34
 RADIUS = 2,865.00
 PC STATION = 1126+88.20
 PT STATION = 1138+81.54



HORZ 0' 50' 100'
 SCALE 1"=100'





NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation
I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1124+00 TO 1148+00

SHEET 7 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

92

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN8\$.dgn



DRAWING DATE: 8/12/2023

MATCH LINE STA 1148+00

MATCH LINE STA 1160+00

MATCH LINE STA 1160+00

MATCH LINE STA 1172+00




HORZ 0' 50' 100'
SCALE 1"=100'

NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023



I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1148+00 TO 1172+00

SHEET 8 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	93
CONTROL	SECTION	JOB	
0455	02	031, ETC	



FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN9\$.dgn

DRAWING DATE: 8/12/2023

PI STATION = 1180+73.42
 DELTA = 30° 11' 23.31" (LT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 772.71
 LENGTH = 1,509.49
 RADIUS = 2,864.79
 PC STATION = 1173+00.72
 PT STATION = 1188+10.21



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152

ROADWAY PLAN

STA 1172+00 TO 1196+00

SHEET 9 OF 30



FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

94

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN10\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1196+00 TO STA 1220+00



SHEET 10 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
95		

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN11\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




PI STATION = 1244+75.20
 DELTA = 27° 55' 30.31" (RT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 712.28
 LENGTH = 1,396.25
 RADIUS = 2,864.79
 PC STATION = 1237+62.91
 PT STATION = 1251+59.17

NOTES:


- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023



SH 152
ROADWAY PLAN
STA 1220+00 TO STA 1243+00

SHEET 11 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

96

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN12#.dgn
 DRAWING DATE: 8/12/2023

PI STATION = 1244+75.20
 DELTA = 27° 55' 30.31" (RT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 712.28
 LENGTH = 1,396.25
 RADIUS = 2,864.79
 PC STATION = 1237+62.91
 PT STATION = 1251+59.17




HORZ 0' 50' 100'
 SCALE 1"=100'

NOTES:



- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023




I. S. ENGINEERS, LLC 7670 WOODWAY DRIVE, SUITE 320 HOUSTON, TEXAS 77063 TBPE REG. # F-11657		
SH 152		
ROADWAY PLAN		
STA 1243+00 TO STA 1267+00		
SHEET 12 OF 30		
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. (SEE TITLE SHEET)	HIGHWAY NO. SH 152
STATE TEXAS	DISTRICT AMA	COUNTY CARSON
CONTROL 0455	SECTION 02	JOB 031, ETC
		97


FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN13\$.dgn
 DRAWING DATE: 8/12/2023

MATCH LINE STA 1267+00

MATCH LINE STA 1279+00



SECTION A - OVERLAY



SECTION A - OVERLAY




HORZ 0' 50' 100'
 SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023





SH 152
ROADWAY PLAN
STA 1267+00 TO STA 1291+00

SHEET 13 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	align="center">(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	98
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN14\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.



LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- ▭ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL



I. S. ENGINEERS, LLC 7670 WOODWAY DRIVE, SUITE 320 HOUSTON, TEXAS 77063 TBPE REG. # F-11657			
SH 152			
ROADWAY PLAN			
STA 1291+00 TO STA 1315+00			
SHEET 14 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	99
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN15\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1315+00 TO STA 1339+00

SHEET 15 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC




HORZ 0' 50' 100'
SCALE 1"=100'

NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▭ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL





8/12/2023

MATCH LINE STA 1339+00

MATCH LINE STA 1351+00

MATCH LINE STA 1351+00

MATCH LINE STA 1363+00



FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN168.dgn



DRAWING DATE: 8/12/2023

Texas Department of Transportation			
I.S. ENGINEERS, LLC 7670 WOODWAY DRIVE, SUITE 320 HOUSTON, TEXAS 77063 TBPE REG. # F-11657			
SH 152			
ROADWAY PLAN			
STA 1339+00 TO STA 1363+00			
SHEET 16 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	101
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN17\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▭ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023


Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1363+00 TO STA 1386+00

SHEET 17 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	102
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN188.dgn
 DRAWING DATE: 8/12/2023



PI STATION = 1387+74.74
 DELTA = 10° 45' 31.64" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 539.53
 LENGTH = 1,075.88
 RADIUS = 5,729.58
 PC STATION = 1382+35.22
 PT STATION = 1393+11.10

LT: REPLACE EXISTING WINGWALLS WITH SET
 RT: REPLACE EXISTING WINGWALLS WITH SET

LT: REPLACE EXISTING WINGWALLS WITH SET
 RT: REPLACE EXISTING TY-A INLET WITH SET




HORZ 0' 50' 100'
 SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

**SH 152
 ROADWAY PLAN
 STA 1386+00 TO STA 1410+00**

FED. RD. DIV. NO.			FEDERAL AID PROJECT NO.	HIGHWAY NO.
6			(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY	SHEET NO.	
TEXAS	AMA	CARSON	103	
CONTROL	SECTION	JOB		
0455	02	031, ETC		


SHEET 18 OF 30

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN198.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'

PI STATION = 1423+69.51
 DELTA = 9° 35' 01.69" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 480.31
 LENGTH = 958.38
 RADIUS = 5,729.58
 PC STATION = 1418+89.20
 PT STATION = 1428+47.58





NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL

PI STATION = 1423+69.51
 DELTA = 9° 35' 01.69" (LT)
 DEGREE OF CURVE = 1° 00' 00.00"
 TANGENT = 480.31
 LENGTH = 958.38
 RADIUS = 5,729.58
 PC STATION = 1418+89.20
 PT STATION = 1428+47.58



8/12/2023



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1410+00 TO STA 1433+00

SHEET 19 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	104
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\amortillo\District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN20\$.dgn



DRAWING DATE: 8/12/2023

MATCH LINE STA 1433+00

MATCH LINE STA 1445+00

MATCH LINE STA 1445+00

MATCH LINE STA 1457+00




HORZ 0' 50' 100'
SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023



I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPB REG. # F-11657

SH 152
ROADWAY PLAN
STA 1433+00 TO STA 1457+00

SHEET 20 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	105
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN21\$.dgn

DRAWING DATE: 8/12/2023

PI STATION = 1464+69.95
 DELTA = 1° 07' 10.22" (RT)
 DEGREE OF CURVE = 0° 29' 59.99"
 TANGENT = 111.95
 LENGTH = 223.90
 RADIUS = 11,459.20
 PC STATION = 1463+57.99
 PT STATION = 1465+81.90



HORZ 0' 50' 100'
 SCALE 1"=100'

MATCH LINE STA 1457+00


MATCH LINE STA 1469+00

NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▭ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

MATCH LINE STA 1469+00

MATCH LINE STA 1481+00





I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1457+00 TO STA 1481+00

SHEET 21 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	106
CONTROL	SECTION	JOB	
0455	02	031, ETC	




CULVERT 26
 80 LF 5' X 4' SBC
 1476+76
 LT: REPLACE EXISTING WINGWALLS WITH SET
 RT: EXISTING SET TO REMAIN

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152\PLAN22#.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'

PI STATION = 1492+06.64
 DELTA = 12° 55' 56.89" (LT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 324.69
 LENGTH = 646.62
 RADIUS = 2,864.79
 PC STATION = 1488+81.94
 PT STATION = 1495+28.57



NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:



- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL

LT: REPLACE EXISTING WINGWALLS WITH SET
 RT: REPLACE EXISTING WINGWALLS WITH SET


BEGIN OVERLAY OF CSJ: 0455-02-028 SCOPE OF WORK STA 1492+88.41

SECTION B - OVERLAY

PI STATION = 1495+44.41
 DELTA = 9° 05' 31.14" (LT)
 DEGREE OF CURVE = 2° 17' 30.59"
 TANGENT = 198.77
 LENGTH = 396.71
 RADIUS = 2,500.00
 PC STATION = 1493+45.64
 PT STATION = 1497+42.35



8/12/2023



**SH 152
 ROADWAY PLAN
 STA 1481+00 TO STA 1503+00**


SHEET 22 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	107
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN23\$.dgn
 DRAWING DATE: 8/12/2023

PI STATION = 1510+01.86
 DELTA = 21° 56' 49.39" (RT)
 DEGREE OF CURVE = 2° 17' 30.59"
 TANGENT = 484.75
 LENGTH = 957.62
 RADIUS = 2,500.00
 PC STATION = 1505+17.11
 PT STATION = 1514+74.73



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:


- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1503+00 TO STA 1527+00

SHEET 23 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	108
CONTROL	SECTION	JOB	
0455	02	031, ETC	



FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN24\$.dgn
 DRAWING DATE: 8/12/2023

MATCH LINE STA 1527+00

MATCH LINE STA 1539+00

MATCH LINE STA 1539+00

MATCH LINE STA 1551+00




HORZ 0' 50' 100'
 SCALE 1"=100'

NOTES:


1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023





**SH 152
 ROADWAY PLAN
 STA 1527+00 TO STA 1551+00**

SHEET 24 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	109
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN25\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




PI STATION = 1577+14.16
 DELTA = 35° 02' 37.40" (LT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 904.47
 LENGTH = 1,752.19
 RADIUS = 2,864.79
 PC STATION = 1568+09.70
 PT STATION = 1585+61.88

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152

ROADWAY PLAN

STA 1551+00 TO STA 1575+00

SHEET 25 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

110

PI STATION = 1577+14.16
 DELTA = 35° 02' 37.40" (LT)
 DEGREE OF CURVE = 2° 00' 00.00"
 TANGENT = 904.47
 LENGTH = 1,752.19
 RADIUS = 2,864.79
 PC STATION = 1568+09.70
 PT STATION = 1585+61.88




HORZ 0' 50' 100'
 SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:



- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN268.dgn

DRAWING DATE: 8/12/2023



TEXAS DEPARTMENT OF TRANSPORTATION

I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657



SH 152
ROADWAY PLAN
STA 1575+00 TO STA 1599+00

SHEET 26 OF 30		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		111

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN27\$.dgn
 DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
 SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▬ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1599+00 TO STA 1623+00



SHEET 27 OF 30			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	112
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Details\SH152\PLAN28.dgn

DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
SCALE 1"=100'




NOTES:

1. HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
2. ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
3. SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
4. CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- ← PROPOSED TRAFFIC
- ⇐ EXISTING TRAFFIC
- - - EXISTING RIGHT-OF-WAY LINE
- ▒ PROP WIDENING
- ▨ 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- ▧ 0" - 2" PLANE, 2" ACP & TACK
- ▩ CONCRETE RIPRAP
- ▭ PAVEMENT REMOVAL



8/12/2023



L.S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1623+00 TO STA 1647+00



SHEET 28 OF 30		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		113

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN29\$.dgn

DRAWING DATE: 8/12/2023



HORZ 0' 50' 100'
SCALE 1"=100'




PI STATION = 1666+82.84
 DELTA = 1° 49' 41.54" (RT)
 DEGREE OF CURVE = 0° 29' 59.99"
 TANGENT = 182.84
 LENGTH = 365.64
 RADIUS = 11,459.20
 PC STATION = 1665+00.00
 PT STATION = 1668+65.64

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023

Texas Department of Transportation

I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1647+00 TO STA 1671+00


SHEET 29 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

114

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Detail\SH152*PLAN30\$.dgn

DRAWING DATE: 8/12/2023




HORZ 0' 50' 100'
SCALE 1"=100'

NOTES:

- HORIZONTAL ALIGNMENT AS WELL AS EXISTING ROW LINE ARE RECREATED FROM THE AVAILABLE AS-BUILT INFORMATION. NO ROW SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.
- ALL UTILITIES ARE SHOWN ACCORDING TO THEIR APPROXIMATE LOCATIONS AND ARE INTENDED FOR GENERAL INFORMATION ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL UTILITY OWNERS FOR ACTUAL LOCATIONS.
- SEE "MISCELLANEOUS ROADWAY DETAILS" SHEETS FOR INTERSECTION AND DRIVEWAY TIE-IN INFORMATION.
- CONTRACTOR TO VERIFY THAT MINIMUM CLEARANCE REQUIREMENTS PER TEXAS UTILITY CODE ARE MET BETWEEN OVERHEAD POWER AND PAVEMENT OVERLAY.

LEGEND:

- PROPOSED TRAFFIC
- EXISTING TRAFFIC
- EXISTING RIGHT-OF-WAY LINE
- PROP WIDENING
- 2" OVERLAY & UNDERSEAL (ADDITIONAL AREAS)
- 0" - 2" PLANE, 2" ACP & TACK
- CONCRETE RIPRAP
- PAVEMENT REMOVAL



8/12/2023




I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPE REG. # F-11657

SH 152
ROADWAY PLAN
STA 1671+00 TO END


SHEET 30 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	115
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\Additional Areas\SH152*ADD*AREAS*01.dgn
 DRAWING DATE: 8/12/2023




TYPICAL DRIVEWAY TIE-IN DETAIL



SECTION A-A



TYPICAL CR / LOCAL ROAD INTERSECTION TIE-IN DETAIL



SECTION A-A

		DRIVEWAY ITEMS		
STATION	LT/RT	530	3077 ①	3077 ①
		6021	6058	6075
		DRIVEWAYS (ACP) (TYPE 2)	SP MIXES SP-D SAC-A PG70-28 (220 LBS/SY)	TACK COAT 0.13 GAL/SY
		SY	TON	GAL
994+50	LT	34	4	4
1001+00	RT	46	5	6
1033+00	RT	31	3	4
1046+00	RT	31	3	4
1049+50	LT	31	3	4
1068+00	LT	12	1	2
1091+50	LT	26	3	3
1091+50	RT	26	3	3
1106+00	LT	33	4	4
1106+00	RT	35	4	5
1171+00	LT	24	3	3
1188+00	RT	24	3	3
1197+50	LT	20	2	3
1205+00	RT	13	1	2
1227+00	LT	22	2	3
1227+00	RT	28	3	4
1244+00	LT	21	2	3
1244+00	RT	10	1	1
1285+00	RT	21	2	3
1285+50	LT	27	3	4
1341+50	LT	8	1	1
1380+00	RT	14	2	2
1439+00	RT	13	1	2
1455+50	RT	18	2	2
1472+00	LT	33	4	4
1480+50	RT	15	2	2
1490+00	LT	27	3	4
1521+00	LT	22	2	3
1554+50	LT	33	4	4
1555+50	RT	19	2	2
1600+00	LT	19	2	2
1624+50	LT	19	2	2
1629+00	RT	16	2	2
1629+25	LT	17	2	2
1637+50	LT	22	2	3
1639+75	LT	22	2	3
PROJECT TOTALS		832	92	108

NOTES


① FOR CONTRACTOR'S INFORMATION ONLY. ALL ITEMS LISTED AS "FOR CONTRACTOR'S INFORMATION ONLY" WILL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE TxDOT STANDARD SPECIFICATIONS, AND ARE CONSIDERED SUBSIDIARY TO ITEM 530 DRIVEWAYS (ACP) (TYPE 2).

		INTERSECTION ITEMS				
STATION	LT/RT	ROADNAME	L	530	3077 ①	3077 ①
				6002	6058	6075
				INTERSECTIONS (ACP)	SP MIXES SP-D SAC-A PG70-28 (220 LBS/SY)	TACK COAT 0.13 GAL/SY
				SY	TON	GAL
1320+00	LT	CR-Y / 1st ST	90	815	90	106
1321+50	RT	CR-Y	18	140	15	18
1400+50	LT	CONLEY DR	100	727	80	95
1591+50	LT	CR-CC	30	158	17	21
1591+50	RT	CR-CC	18	58	6	8
1644+50	LT	CR-DD	30	156	17	20
1644+50	RT	CR-DD	30	93	10	12
PROJECT TOTALS				2147	236	279

NOTES

① FOR CONTRACTOR'S INFORMATION ONLY. ALL ITEMS LISTED AS "FOR CONTRACTOR'S INFORMATION ONLY" WILL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE TxDOT STANDARD SPECIFICATIONS, AND ARE CONSIDERED SUBSIDIARY TO ITEM 530 INTERSECTIONS (ACP).

LEGEND:




2" SP MIXES SP-D SAC-A PG70-28 (AVG 220LB/SY) AND TACK COAT (0.13 GAL/SY)



BACKFILL

NOTES:

- DRIVEWAY AND INTERSECTION INFORMATION PROVIDED IN THESE PLANS IS APPROXIMATE. EXACT LOCATIONS AND DIMENSIONS SHALL BE ESTABLISHED DURING CONSTRUCTION BY THE FIELD ENGINEER AS REQUIRED.
- ADDITIONAL AREAS FOR INTERSECTION TIE-IN ARE CALCULATED GRAPHICALLY.
- THE CONTRACTOR SHALL OBTAIN PERMISSION FROM THE RESPECTIVE PROPERTY OWNERS 24 HOURS PRIOR TO THE CONTRACTOR CONSTRUCTING PROPOSED DRIVEWAYS.



8/12/2023




I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152
ADDITIONAL AREAS

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	116
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\05 Roadway Detail\Additional Areas\SH152*ADD*AREAS*02.dgn
 DRAWING DATE: 8/12/2023






TYPICAL FM ROAD INTERSECTION TIE-IN DETAIL

FM ROADS INTERSECTION ITEMS							
STATION	LT/RT	ROADNAME	L	354	530	3077 ①	3077 ①
				6021	6002	6058	6075
				PLANE ASPH CONC PAV (0" TO 2")	INTERSECTIONS (ACP)	SP MIXES SP-D SAC-A PG70-28 (220 LBS/SY)	TACK COAT (0.13 GAL/SY)
				SY	SY	TON	GAL
1397+00	LT	FM 294	440	502	1167	128	152
1402+00	RT	FM 294	325	669	1611	177	209
1531+00	RT	FM 2386	328	845	1863	205	242
PROJECT TOTALS				2016	4641	511	603

NOTES


① FOR CONTRACTOR'S INFORMATION ONLY. ALL ITEMS LISTED AS "FOR CONTRACTOR'S INFORMATION ONLY" SHALL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE TXDOT STANDARD SPECIFICATIONS, AND / BE CONSIDERED SUBSIDIARY TO ITEM 530 INTERSECTIONS (ACP).

LEGEND:


-  2" SP MIXES SP-D SAC-A PG70-28 (AVG 220LB/SY), TACK COAT (0.13 GAL/SY)
-  BACKFILL
-  PLANE ASPH CONC PAVEMENT (0" - 2") AND 2" SP MIXES SP-D SAC-A PG70-28 (AVG 220 LB/SY), AND TACK COAT (0.13 GAL/SY)

NOTES:


1. INTERSECTION INFORMATION PROVIDED IN THESE PLANS IS APPROXIMATE. EXACT LOCATIONS AND DIMENSIONS SHALL BE ESTABLISHED DURING CONSTRUCTION BY THE FIELD ENGINEER AS REQUIRED.
2. ADDITIONAL AREAS FOR INTERSECTION TIE-IN ARE CALCULATED GRAPHICALLY.



8/12/2023



SECTION A-A



I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152


ADDITIONAL AREAS

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

117

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\05 Roadway Details\Additional Areas\SH1 52*PAVEMENT*REPAIR*DETAIL.dgn

DRAWING DATE: 8/28/2023



PAVEMENT REPAIR NOTES:

1. QUANTITIES ARE CARRIED OVER TO "SUMMARY OF QUANTITIES". ALL QUANTITIES ARE BASED ON 25% PAVEMENT REPAIR OF THE TRAVEL LANES FOR THE STATION LIMITS, PLUS AN ADDITIONAL 26,000 SY FOR ANTICIPATED PAVEMENT REPAIRS NEEDED ALONG THE CENTERLINE AFTER THE TRAFFIC CONTROL SHIFT.
2. FOR CONTRACTOR'S INFORMATION ONLY. ALL ITEMS LISTED AS "FOR CONTRACTOR'S INFORMATION ONLY" WILL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE TXDOT STANDARD SPECIFICATIONS, AND ARE CONSIDERED SUBSIDIARY TO ITEM 351. FLEXIBLE PAVEMENT STRUCTURE REPAIR.
3. CONTRACTOR WILL NOT REMOVE MORE MATERIAL THAN CAN BE REPLACED IN A SINGLE WORK DAY.
4. LOCATIONS OF PAVEMENT REPAIR TO VARY AS DIRECTED BY THE ENGINEER.
5. PAVEMENT REPAIR AREA WILL BE A MINIMUM 20'-0" IN LENGTH.
6. EXTEND REPAIR WIDTH TO INCLUDE INTERIOR EXISTING PAVEMENT JOINTS, WHERE INSTRUCTED BY THE ENGINEER. PAVEMENT REPAIR ON OUTSIDE EDGE OF TRAVEL LANE WILL INCLUDE AN OVERLAP OF 6" ONTO SHOULDER.
7. HOT MIX TO BE USED FOR FLEXIBLE PAVEMENT REPAIR WILL BE D-GR HMA OR APPROVED ALTERNATIVE, BY THE ENGINEER.
8. TRACKLESS TACK COAT WILL BE USED FOR ALL REPAIR AREAS.


PAVEMENT REPAIR DETAIL

PAVEMENT REPAIR ITEMS				
	351 ②	354 ①	3076 ①	3077 ①
	6019	6022	6005	6075
	FLEXIBLE PAVEMENT STRUCTURE REPAIR(3")	PLANE ASPH CONC PAVEMENT (0" - 3")	D-GR HMA TY-B PG64-28	TACK COAT
			(330 LBS/SY)	0.13 GAL/SY
	SY	SY	TON	GAL
PROJECT TOTALS	48,000	48,000	7,920	6,240

NOTES

① FOR CONTRACTOR'S INFORMATION ONLY. ALL ITEMS LISTED AS "FOR CONTRACTOR'S INFORMATION ONLY" WILL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE TXDOT STANDARD SPECIFICATIONS, AND ARE CONSIDERED SUBSIDIARY TO ITEM 351 FLEXIBLE PAVEMENT STRUCTURE REPAIR.

② BASED ON 25% PAVEMENT REPAIR OF THE EXISTING DRIVING LANES.



8/28/2023




**SH 152
PAVEMENT REPAIR
DETAIL**

SHEET 1 OF 1

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	118
CONTROL	SECTION	JOB	
0455	02	031, ETC	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\05 Roadway Detail\TXDOT Standards\TE (HMAC) - 11.dgn



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS


CONDITION - 1
 THIN HMAC SURFACES OR HMAC OVERLAY
 WITH THICKNESS OF 2.5" OR LESS



** EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 2
 OVERLAY OF EXISTING PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 3
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



*** SEE TYPICAL SECTION FOR ROADSIDE DETAILS

CONDITION - 4
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 5" OR GREATER


GENERAL NOTES

- UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
- FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
- PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
- THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
- THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.


(NOT TO SCALE)

				Design Division Standard	
TAPERED EDGE DETAILS HMAC PAVEMENT					
TE (HMAC) - 11					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS		0455 02	031, ETC	SH 152	
DIST	COUNTY	SHEET NO.			
AMA	CARSON	119			

DATE: 8/12/2023
 FILE: L:\Amorillo District\SH 152_WA 6\CADD\Sheets\05 Roadway Detail\Standards\GF3119.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




TYPICAL POST PLACEMENT



WOOD BLOCK TO ROUND WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**


- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC16d) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.



ELEVATION MID-SPAN RAIL SPLICE


NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.



BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.




MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.

12" X 12" X 1/4" (ASTM A36) STEEL BOTTOM PLATE WITH 1" DIA. HOLES REQUIRED WITH BOLT-THROUGH INSTALLATION.

LOW FILL CULVERT POST




NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

				Design Division Standard	
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19					
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG	
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0455	02	031, ETC	SH 152	
	DIST	COUNTY		SHEET NO.	
	AMA	CARSON		120	





DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\05 Roadway Detail\txdot Standards\gf31tr+1320.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- (5) 1" DIA. HOLES.
- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (FACING TRAFFIC SIDE) (ASTM F3125 GR A325 OR A449).
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 7/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563).

NOTE:
HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE:
CURB IS A REQUIRED COMPONENT FOR THE TRANSITION TO FUNCTION PROPERLY. SEE GENERAL NOTES: 2-4 AND 16-17.




THRIE-BEAM TERMINAL CONNECTOR 10GA.
PART DESIGNATOR RTE01D
NOTE: SEE GENERAL NOTE: 9

NESTED THRIE-BEAM RAIL
PART DESIGNATOR RTM10a
(12) 5/8" X 2" BUTTON HEAD SPLICE BOLTS WITH RECESSED NUTS: (FBB02)
(12) RECTANGULAR GUARDRAIL PLATE WASHERS: (FWR03)

NON-SYMMETRICAL W-BEAM TO THRIE-BEAM TRANSITION 10GA.
PART DESIGNATOR RWT02a OR RWT02b

PLATE WASHER INSTRUCTIONS


BRIDGE APPROACH - UPSTREAM: THE NESTED RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.
BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.



NOTE: ONLY (1) 5/8" BOLT REQUIRED AT THIS POST LOCATION.

THRIE-BEAM TERMINAL - CURB TABLE	
PRECAST CURB FULL LENGTH EQUALS 12'-2"	
THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS.	
CURB (1) LENGTH	5'-8"
CURB (2) LENGTH	6'-6"
TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7	
CONNECTING PRECAST CURB SECTIONS (1) & (2):	
FORM OR CORE	1" DIA. HOLE 9" LONG INTO EACH CURB END.
USE	(1) #5 GR. 60 REBAR 18" LONG TO CONNECT BOTH CURBS.
SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE *:	
FORM OR CORE	(4) 1" DIA. HOLES, SEE PLAN AND ELEVATION VIEWS FOR HOLE LOCATIONS. DRIVE (4) #5 GR. 60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB.
FILL HOLES WITH APPROVED GROUT MIXTURE.	

* NOTES: NOT NEEDED FOR CAST-IN-PLACE. SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS. PERCUSSION DRILLING IS NOT PERMITTED WITH: TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.



NOTE: OPTIONS FOR TYPE II CURB:
1. PRECAST
2. CAST-IN-PLACE

GENERAL NOTES

1. CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
2. CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5- 3/4" HEIGHT); SEE CURRENT CCG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE: 17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
3. CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
4. UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
5. FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
6. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF (31) STANDARD SHEET.
7. THE POST LENGTH SHALL BE MARKED ON ALL 7'- 0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 5/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
8. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
9. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
10. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
11. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
12. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
13. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
14. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TXDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
15. REFER TO GF (31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
16. THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
17. IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION, (SEE SHT. 2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED) (TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED) (STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT. 2 FOR ADDITIONAL INFORMATION.

HIGH-SPEED TRANSITION
SHEET 1 OF 2

		Design Division Standard	
METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT GF (31) TR TL3-20			
FILE: gf31tr+1320.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2020	CONT: 0455	SECT: 02	JOB: 031, ETC
REVISIONS	DIST: AMA	COUNTY: CARSON	SHEET NO.: 121


DISCLAIMER:
 THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER.
 TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\05 Roadway Detail\TXDOT Standards\gf31trtl320.dgn


REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)

END PAYMENT FOR METAL BEAM GUARD FENCE TRANSITION.
 BEGIN PAYMENT FOR METAL BEAM GUARD FENCE.


(SEE GF (31) STANDARD SHEET)



ELEVATION VIEW



SECTION D-D



THRIE BEAM TRANSITION BLOCKOUT DETAILS

HIGH-SPEED TRANSITION

SHEET 2 OF 2




METAL BEAM GUARD FENCE
 THRIE-BEAM TRANSITION
 TL-3 MASH COMPLIANT
 GF (31) TR TL3-20

FILE: gf31trtl320.dgn	DN: TXDOT	CK: KM	DW: KM	CK: CGL/AG
©TXDOT: NOVEMBER 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
DIST	COUNTY		SHEET NO.	
AMA	CARSON		122	


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\05 Roadway_Details\TXDOT_Standards\GF31MS19.dgn



GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)


GENERAL NOTES

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




SECTION A-A

Typical




MOW STRIP DETAIL

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)


Curb shown on top of mow strip



CURB OPTION (3)

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF (31) MS-19			
FILE: gf31ms19.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0455	02	031, ETC
DIST	COUNTY	SHEET NO.	
AMA	CARSON	123	

DATE: 8/12/2023
 FILE: L:\Amorillo District\SH 152_WA 6\CADD\Sheets\05 Roadway Detail\sgt10s\SGT10.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE SoftStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MBOGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IT IS ACCEPTABLE TO INSTALL THE SoftStop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
 - DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTE: A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE: B PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)
 PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

NOTE: C W-BEAM SPLICE LOCATED BETWEEN LINE POST (4) AND LINE POST (5)
 GUARDRAIL PANEL 25'-0" PN:61G
 ANCHOR RAIL 25'-0" PN:15215G
 LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25'-0")
15205A	1	POST #0 - ANCHOR POST (6'-5 3/8")
15203G	1	POST #1 - (SYTP) (4'-9 1/2")
15000G	1	POST #2 - (SYTP) (6'-0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6'-0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE: B







TRINITY HIGHWAY
SOFTSTOP END TERMINAL
MASH - TL-3
SGT (10S) 31-16

FILE: sgt10s3116	DN: TxDOT	CK: KM	DW: VP	CR: MB/VP
©TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
	DIST	COUNTY		SHEET NO.
	AMA	CARSON		124


THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER, THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard

SINGLE GUARDRAIL TERMINAL
MSKT-MASH-TL-3
SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CL
© TxDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	125	

DATE: FILE:




HORZ 0' 2500' 5000'

LEGEND:

- DRAINAGE AREA BOUNDARY
- DIRECTION OF FLOW


NOTES:

1. CONTOURS DISPLAYED REFLECT 2018 USGS DEM.



CULVERT SUMMARY TABLE						
Culvert No.	Station	Number of Barrels	Sizes	Exist. Length ft	Type (shape & material)	Description of Work
1	999+88	1	6'x2'	53	Conc Box	LT: Extend and install new SET RT: Extend and install new SET Clean existing culvert
2	1013+66	3	5'x4'	59	Conc Box	LT: Extend and install new SET RT: To Remain Clean existing culverts
3	1069+88	2	6'x6'	99	Conc Box	LT: To Remain RT: To Remain Clean existing culvert
4	1081+40	1	3'x2'	107	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing wingwalls with SET Clean existing culvert
5	1103+95	1	8'x7'	111	Conc Box	LT: To Remain RT: To Remain Clean existing culvert
6	1146+58	1	2'x2'	80	Conc Box	RT: Replace existing wingwalls with SET Clean existing culverts
7	1172+07	1	3'x2'	89	Conc Box	LT: Replace existing wingwalls with SET RT: To Remain Clean existing culverts
8	1209+07	1	3'x2'	74	Conc Box	LT: To Remain RT: Replace existing wingwalls with SET Clean existing culvert
9	1238+00	1	3'x2'	62	Conc Box	LT: Replace existing wingwalls with SET RT: Extend and install new parallel wingwalls Clean existing culvert
10	1249+00	1	3'x2'	68	Conc Box	LT: Replace existing wingwalls with SET RT: Extend and install new parallel wingwalls Clean existing culvert
11	1271+00	1	3'x2'	69	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing wingwalls with SET Clean existing culverts
12	1287+44	1	4'x3'	54	Conc Box	LT: To Remain RT: To Remain Clean existing culvert
13	1296+18	1	4'x3'	63	Conc Box	LT: To Remain RT: To Remain Clean existing culvert
14	1309+42	1	8'x8'	65	Conc Box	LT: Extend and install parallel wing walls RT: Extend and install parallel wing walls Clean existing culverts
15	1322+22	1	3'x2'	77	Conc Box	LT: Extend and install SET RT: To Remain Clean existing culverts
16	1335+61	1	3'x3'	74	Conc Box	LT: Replace existing wingwalls with SET RT: To Remain Clean existing culverts
17	1352+27	1	4'x3'	60	Conc Box	LT: To Remain RT: To Remain Clean existing culvert

CULVERT SUMMARY TABLE						
Culvert No.	Station	Number of Barrels	Sizes	Exist. Length ft	Type (shape & material)	Description of Work
18	1361+79	1	5'x6.5'	56	Conc Box	LT: To Remain RT: To Remain Clean existing culvert
19	1383+20	1	4'x3'	75	Conc Box	LT: To Remain RT: To Remain Clean existing culverts
20	1395+92	1	3'x2'	73	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing wingwalls with SET Clean existing culverts
21	1409+79	1	3'x2'	87	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing TY-A inlet with SET Clean existing culverts
22	1431+51	1	7'x7'	78	Conc Box	LT: Extend and install SET RT: To Remain Clean existing culvert
23	1435+31	1	6'x4'	83	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing wingwalls with SET Clean existing culverts
24	1447+85	1	3'x2'	73	Conc Box	LT: Replace existing wingwalls with SET RT: To Remain Clean existing culverts
25	1450+61	1	5'x6.5'	80	SpI Box TyB	LT: To Remain RT: To Remain Clean existing culvert
26	1476+76	1	5'x4'	80	Conc Box	LT: Replace existing wingwalls with SET RT: To Remain Clean existing culverts
27	1489+74	1	3'x2'	94	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing wingwalls with SET Clean existing culverts
28	1525+00	1	3'x2'	70	Conc Box	LT: Replace existing wingwalls with SET RT: To Remain Clean existing culverts
29	1537+00	1	3'x2'	77	Conc Box	LT: Extend and install SET RT: Replace existing wingwalls with SET Clean existing culverts
30	1553+20	1	5'x6.5'	84	Conc Box	LT: To Remain RT: To Remain Clean existing culvert
31	1569+50	1	3'x2'	75	Conc Box	LT: Replace existing wingwalls with SET RT: Replace existing wingwalls with SET Clean existing culvert
32	1591+00	1	3'x2'	67	Conc Box	LT: Extend and install SET RT: Replace existing wingwalls with SET Clean existing culverts
33	1644+06	1	4'x2'	86	Conc Box	LT: To Remain RT: To Remain Clean existing culvert



SH 152
OVERALL DRAINAGE AREA MAP



SHEET 1 OF 1		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		126

FILENAME: L:\Amarillo District\SH 152\KWA 6\CADD\Sheets\07 Drainage Detail\SH152*DAMI.dgn

DRAWING DATE: 8/12/2023

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152*DAM2.dgn

DRAWING DATE: 8/12/2023



LEGEND:

- DRAINAGE AREA BOUNDARY
- DIRECTION OF FLOW

- ID #
 - AREA (ACRES)
- DRAINAGE AREA ID

NOTES:

1. CONTOURS DISPLAYED REFLECT 2018 USGS DEM.
2. CALCULATIONS ARE BASED ON TXDOT HYDRAULIC MANUAL (SEPTEMBER 2019).
3. PEAK FLOWS ARE DETERMINED BY THE NRCS METHOD.



NRCS RUNOFF CURVE NUMBER METHOD PEAK FLOW CALCULATION

ID	Name	Area (acre)	Area (sqmi)	Curve Number	Time of Concentration (min)	Lag Time (min)	Runoff (cfs)					
							Q-50%	Q-20%	Q-10%	Q-4%	Q-2%	Q-1%
14	A-14	391.1	0.61	62	65	39	147.9	232.6	320.0	464.4	590.9	735.7

HEC-RAS SUMMARY TABLE

SH 152 STA	DESIGN FREQUENCY (10 YR)															
	FLOWS (CFS)						WATER SURFACE ELEVATIONS (FT)						VELOCITIES (FPS)			
	TOTAL FLOWS		CULVERT FLOWS		WEIR FLOWS		EXIST		PROP		DIFFERENCE		EXIST		PROP	
	EXIST	PROP	EXIST	PROP	EXIST	PROP	US	DS	US	DS	US	DS	US	DS	US	DS
1309+42	320.0	320.0	320.0	320.0	0.0	0.0	3184.93	3178.73	3186.35	3178.73	1.42	0.00	5.00	10.16	5.00	9.29

SH 152 STA	DESIGN FREQUENCY (100 YR)															
	FLOWS (CFS)						WATER SURFACE ELEVATIONS (FT)						VELOCITIES (FPS)			
	TOTAL FLOWS		CULVERT FLOWS		WEIR FLOWS		EXIST		PROP		DIFFERENCE		EXIST		PROP	
	EXIST	PROP	EXIST	PROP	EXIST	PROP	US	DS	US	DS	US	DS	US	DS	US	DS
1309+42	735.7	735.7	354.4	308.8	391.4	422.4	3189.09	3181.20	3189.11	3181.20	0.02	0.00	5.54	5.54	4.82	4.82



SH 152
DRAINAGE AREA MAP



SHEET 1 OF 1

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

127

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152*CULV*P&P1.dgn

DRAWING DATE: 8/29/2023





UTILITY LEGEND

- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.

ITEM NO	DESCRIPTION	UNIT	QTY
462 6095	CONC BOX CULV (6 FT X 2 FT) (EXTEND)	LF	13.0
467 6205	SET (TY I) (S=6 FT) (HW= 3 FT) (4:1) (C)	EA	2
496 6002	REMOVE STR (INLET)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 1
 STA 999+98**


SHEET 1 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

128

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152*CULV*P&P2.dgn

DRAWING DATE: 8/12/2023





UTILITY LEGEND

- (C)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G)--- GAS


NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.




**SH 152
CULVERT PLAN AND PROFILE
CULVERT 2
STA 1013+66**

FED. RD. DIV. NO.			FEDERAL AID PROJECT NO.	HIGHWAY NO.
6			(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY	SHEET NO.	
TEXAS	AMA	CARSON	129	
CONTROL	SECTION	JOB		
0455	02	031, ETC		



ITEM NO	DESCRIPTION	UNIT	QTY
462 6052	CONC BOX CULV (5' FT X 4 FT) (EXTEND)	LF	18.0
467 6182	SET (TY 1) (S=5 FT) (HW= 5 FT) (4:1) (C)	EA	3
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	6.0


CULVERT 2 ~ STA 1013+66
 EXIST: 3 - 5' X 4' X 59 LF MBC W/ STRAIGHT WING WALL W/ PIPE RUNNERS LT AND TY A INLET W/ PIPE RUNNERS RT
 PROP: EXTEND 4.0' W/MC-5-20 AND SETB-SW-0 (HW=5') (4:1) LT (EACH BOX)





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	4.0
467 6105	SET (TY I) (S=3 FT) (HW= 3 FT) (3:1) (C)	EA	1
467 6112	SET (TY I) (S=3 FT) (HW= 4 FT) (4:1) (C)	EA	1
496 6002	REMOVE STR (INLET)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 4
 STA 1081+40**


SHEET 3 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

FILENAME: L:\amort\110 District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P4.dgn
 DRAWING DATE: 8/12/2023

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152*CULV*P&P6.dgn

DRAWING DATE: 8/12/2023




UTILITY LEGEND




- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	2.0
467 6106	SET (TY 1) (S=3 FT) (HW= 3 FT) (4:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0




**SH 152
CULVERT PLAN AND PROFILE
CULVERT 6
STA 1146+58**

SHEET 4 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


131





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	2.0
467 6105	SET (TY 1) (S=3 FT) (HW= 3 FT) (3:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657


**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 7
 STA 1172+07**

SHEET 5 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

132


FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P7.dgn
 DRAWING DATE: 8/12/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	2.0
466 6196	WINGWALL (PW + 2) (HW=7 FT)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

**SH 152
CULVERT PLAN AND PROFILE
CULVERT 8
STA 1209+07**

SHEET 6 OF 23


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

133

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P8.dgn
 DRAWING DATE: 8/12/2023

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P9.dgn

DRAWING DATE: 8/12/2023




UTILITY LEGEND



- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462.6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	13.0
466.6181	WINGWALL (PW - 1) (HW=6 FT)	EA	1
467.6106	SET (TY I) (S=3 FT) (HW= 3 FT) (4:1) (C)	EA	1
496.6005	REMOVE STR (WINGWALL)	EA	2
496.6008	REMOVE STR (BOX CULVERT)	LF	4.0




**SH 152
CULVERT PLAN AND PROFILE
CULVERT 9
STA 1238+00**

SHEET 7 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

134




UTILITY LEGEND



- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	15.0
466 6178	WINGWALL (PW - 1) (HW=3 FT)	EA	1
467 6106	SET (TY I) (S=3 FT) (HW= 3 FT) (4:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	2
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0




**SH 152
CULVERT PLAN AND PROFILE
CULVERT 10
STA 1249+00**

SHEET 8 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

135


FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P10.dgn
 DRAWING DATE: 8/12/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	4.0
467 6106	SET (TY I) (S=3 FT):(HW= 3 FT) (4:1) (C)	EA	1
467 6111	SET (TY I) (S=3 FT):(HW= 4 FT) (3:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	2
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



Texas Department of Transportation

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPPE REG. # F-11657


**SH 152
CULVERT PLAN AND PROFILE
CULVERT 11
STA 1271+00**

SHEET 9 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

136

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P11.dgn
 DRAWING DATE: 8/12/2023




UTILITY LEGEND



- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
403 6001	TEMPORARY SPL SHORING	SF	480.0
462 6067	CONC BOX CULV (8 FT X 8 FT) (EXTEND)	LF	18.0
466 6173	WINGWALL (PW - 1) (HW=12 FT)	EA	1
466 6174	WINGWALL (PW - 1) (HW=13 FT)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	2
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



**SH 152
CULVERT PLAN AND PROFILE
CULVERT 14
STA 1309+42**


SHEET 10 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

137

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P14.dgn

DRAWING DATE: 8/12/2023




UTILITY LEGEND

- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS



NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.

EXIST STRAIGHT WING WALL TO BE REMOVED AND REPLACED WITH SETB-SW-0 (HW=3')



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT)(EXTEND)	LF	9.0
467 6105	SET (TY I) (S=3 FT) (HW= 3 FT) (3:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0



**SH 152
CULVERT PLAN AND PROFILE
CULVERT 15
STA 1322+22**

SHEET 11 OF 23



FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

138

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152*CULV*P&P15.dgn

DRAWING DATE: 8/12/2023


FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P16.dgn
 DRAWING DATE: 8/12/2023



UTILITY LEGEND

(C1)	AT&T
(FOC1)	CABLE ONE
(FOC2)	FIBERLIGHT
(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657


**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 16
 STA 1335+61**


SHEET 12 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

139

ITEM NO	DESCRIPTION	UNIT	QTY
462 6046	CONC BOX CULV (3 FT X 3 FT) (EXTEND)	LF	2.0
467 6111	SET (TY 1) (S=3 FT) (HW= 4 FT) (3:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0






UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.




Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657


**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 20
 STA 1395+92**

SHEET 13 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC




ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	4.0
467 6106	SET (TY I) (S=3 FT) (HW= 3 FT) (4:1) (C)	EA	1
467 6109	SET (TY I) (S=3 FT) (HW= 3 FT) (6:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	2
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P20.dgn
 DRAWING DATE: 8/12/2023

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152*CULV*P&P21.dgn
 DRAWING DATE: 8/12/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.

ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3' FT X 2' FT) (EXTEND)	LF	4.0'
467 6106	SET (TY I) (S=3 FT) (HW= 3 FT) (4:1) (C)	EA	1
467 6109	SET (TY I) (S=3 FT) (HW= 3 FT) (6:1) (C)	EA	1
496 6002	REMOVE STR (INLET)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0'



Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657



**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 21
 STA 1409+79**

SHEET 14 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

141

FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P22.dgn
 DRAWING DATE: 8/12/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.

ITEM NO	DESCRIPTION	UNIT	QTY
462 6062	CONC BOX CULV (7 FT X 7 FT) (EXTEND)	LF	6.0
467 6261	SET (TY I) (S=7 FT) (HW= 8 FT) (4:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0




Texas Department of Transportation
I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 22
 STA 1431+51**

SHEET 15 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC




UTILITY LEGEND

- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:

1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



**SH 152
CULVERT PLAN AND PROFILE
CULVERT 23
STA 1435+31**


SHEET 16 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	143
CONTROL	SECTION	JOB	
0455	02	031, ETC	


EXIST WING WALL TO BE REMOVED AND REPLACED WITH SETB-SW-0 (HW=5') (4:1)

EXIST WING WALL TO BE REMOVED AND REPLACED WITH SETB-SW-0 (HW=5') (4:1)

CULVERT 23
STA 1435+31
1-6' X 4' SBC




ITEM NO.	DESCRIPTION	UNIT	QTY
462 6055	CONC BOX CULV. (6 FT X 4 FT) (EXTEND)	LF	4.0
467 6219	SET (TY I) (S=6 FT) (HW= 5 FT) (4:1) (C)	EA	2
496 6005	REMOVE STR (WINGWALL)	EA	2
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P23.dgn

DRAWING DATE: 8/12/2023



UTILITY LEGEND

- (C1)--- AT&T
- (FOC1)--- CABLE ONE
- (FOC2)--- FIBERLIGHT
- (G1)--- GAS

NOTES:


1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
6. DELETED
7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.

EXIST STRAIGHT WING WALL TO BE REMOVED AND REPLACED W/SETB-SW-0 (HW=3')




CULVERT 24 STA 1447+85 1-3' X 2'

EXIST TYP B INLET TO REMAIN

1448+00



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	2.0
467 6109	SET (TY I) (S=3 FT) (HW= 3 FT) (6:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0



SH 152 CULVERT PLAN AND PROFILE CULVERT 24 STA 1447+85


SHEET 17 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

144

FILENAME: L:\amort\110 District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P24.dgn
 DRAWING DATE: 8/12/2023


FILENAME: L:\amort\110 District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P26.dgn
DRAWING DATE: 8/12/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6052	CONC BOX CULV (5 FT X 4 FT) (EXTEND)	LF	2.0
467 6191	SET (TY 1) (S=5 FT) (HW= 7 FT) (4:1) (C)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0




Texas Department of Transportation
I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 26
 STA 1476+76**

SHEET 18 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


145



UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.





Texas Department of Transportation

I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657

SH 152			
CULVERT PLAN AND PROFILE			
CULVERT 27			
STA 1489+74			
SHEET 19 OF 23			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	146
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P27.dgn
 DRAWING DATE: 8/12/2023



ITEM NO	DESCRIPTION	UNIT	QTY
462.6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	4.0
467.6106	SET (TY 1) (S=3 FT) (HW= 3 FT) (4:1) (C)	EA	2
496.6005	REMOVE STR (WINGWALL)	EA	2
496.6008	REMOVE STR (BOX CULVERT)	LF	4.0

CULVERT 27 ~ STA 1489+74
 EXIST: 3' X 2' X 94 LF SBC W/6:1 SWW ON LT AND HEADWALL ON RT
 PROP: SETB-SW-0 (HW=3') (4:1) LT AND STEB-SW-0 (HW=3') (4:1) RT


FILENAME: L:\amr\1110\District\SH 152\WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P28.dgn
DRAWING DATE: 8/29/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	2.0
467 6111	SET (TY I) (S=3 FT) (HW= 4 FT) (3:1) (C)	EA	1
496 6002	REMOVE STR (INLET)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0



Texas Department of Transportation


I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPPE REG. # F-11657

**SH 152
CULVERT PLAN AND PROFILE
CULVERT 28
STA 1525+00**

SHEET 20 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


147





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	9.0
467 6105	SET (TY 1) (S=3 FT) (HW= 3 FT) (3:1) (C)	EA	1
496 6002	REMOVE STR (INLET)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	2.0



Texas Department of Transportation

I.S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657


**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 29
 STA 1537+00**

SHEET 21 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

148


FILENAME: L:\amortillo\District\SH 152\WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P29.dgn
 DRAWING DATE: 8/29/2023





UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	4.0
467 6105	SET (TY 1) (S=3 FT):(HW= 3 FT) (3:1) (C)	EA	2
496 6005	REMOVE STR (WINGWALL)	EA	2
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



Texas Department of Transportation


I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
TBPB REG. # F-11657

**SH 152
CULVERT PLAN AND PROFILE
CULVERT 31
STA 1569+50**

SHEET 22 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


DRAWING DATE: 8/12/2023
FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P31.dgn



UTILITY LEGEND

---	(C1)	AT&T
---	(FOC1)	CABLE ONE
---	(FOC2)	FIBERLIGHT
---	(G1)	GAS

- NOTES:**
1. REGRADE PARALLEL DITCHES TO FLOW TO PROPOSED CULVERT END ELEVATIONS AS NECESSARY.
 2. REGRADE DITCH FLOWLINES TO ENSURE EXISTING DRAINAGE PATTERN IS MAINTAINED
 3. REFER TO DRAINAGE AREA MAP SHEETS FOR HYDROLOGIC DATA.
 4. REFER CULVERT HYDRAULIC DATA SHEET FOR HYDRAULIC DATA.
 5. BREAK BACK DISTANCE SHALL APPLY TO ENTIRE PERIMETER OF PIPE. REPLACEMENT OF 2' BREAK BACK QUANTIFIED WITH ITEM 496.
 6. DELETED
 7. BASED ON THE HORIZONTAL LOCATION OF THIS UTILITY, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.
 8. SINCE THE EXISTING STRUCTURE WILL REMAIN, OR THE PROPOSED STRUCTURE WILL REPLACE AN EXISTING STRUCTURE AT THE SAME ELEVATION AND LOCATION, IT WAS DETERMINED THAT THERE IS NO POTENTIAL CONFLICT. POTHOLES TO DETERMINE THE SIZE AND DEPTH WAS NOT PERFORMED.




Texas Department of Transportation

I. S. ENGINEERS, LLC
 7670 WOODWAY DRIVE, SUITE 320
 HOUSTON, TEXAS 77063
 TBPE REG. # F-11657


**SH 152
 CULVERT PLAN AND PROFILE
 CULVERT 32
 STA 1591+00**

SHEET 23 OF 23

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC



ITEM NO	DESCRIPTION	UNIT	QTY
462 6045	CONC BOX CULV (3 FT X 2 FT) (EXTEND)	LF	6.5
467 6105	SET (TY I) (S=3 FT) (HW= 3 FT) (3:1) (C)	EA	2
496 6002	REMOVE STR (INLET)	EA	1
496 6005	REMOVE STR (WINGWALL)	EA	1
496 6008	REMOVE STR (BOX CULVERT)	LF	4.0



FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\07 Drainage Detail\SH152\CULV*P&P32.dgn
 DRAWING DATE: 8/12/2023

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert No. Spans ~ Span X Height	Max Fill Height (Ft)	Applicable Box Culvert Standard (4)	Applicable Wingwall or End Treatment Standard	Skew Angle (0°, 15°, 30° or 45°)	Side Slope or Channel Ratio (SL:1)	T Culvert Top Slab Thickness (In)	U Culvert Wall Thickness (In)	C Estimated Curb Height (Ft)	Hw Height of Wingwall (Ft) (1)	A Curb to End of Wingwall (Ft)	B Offset of End of Wingwall (Ft)	Lw Length of Longest Wingwall (Ft)	Ltw Culvert Toewall Length (Ft)	Atw Anchor Toewall Length (Ft)	Riprap Apron (CY)	Class "C" Conc (Curb) (CY) (2)	Class "C" Conc (Wingwall) (CY) (3)	Total Wingwall Area (SF)
CULVERT 1 (Lt)	1 ~ 6' X 2'	2.5'	SCC-5&6	SETB-SW-0	0	4:1	8"	7"	0.750	3.167	N/A	N/A	11.333	N/A	6.000	0.7	0.2	3.4	N/A
CULVERT 1 (Rt)	1 ~ 6' X 2'	2.5'	SCC-5&6	SETB-SW-0	0	4:1	8"	7"	0.750	3.167	N/A	N/A	11.333	N/A	6.000	0.7	0.2	3.4	N/A
CULVERT 2 (Rt)	3 ~ 5' X 4'	2.5'	MC-5-20	SETB-SW-0	0	4:1	8"	7"	0.250	4.667	N/A	N/A	17.333	N/A	16.167	3.6	0.2	7.0	N/A
CULVERT 4 (Lt)	1 ~ 3' X 2'	7.5'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	1.125	3.542	N/A	N/A	12.833	N/A	3.000	0.3	0.2	3.8	N/A
CULVERT 4 (Rt)	1 ~ 3' X 2'	7.5'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.250	2.667	N/A	N/A	7.000	N/A	3.000	0.1	0.0	1.9	N/A
CULVERT 6 (Rt)	1 ~ 3' X 2'	3.5'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.250	2.667	N/A	N/A	9.333	N/A	3.000	0.2	0.0	2.5	N/A
CULVERT 7 (Lt)	1 ~ 3' X 2'	3.7'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.250	2.667	N/A	N/A	7.000	N/A	3.000	0.1	0.0	1.9	N/A
CULVERT 8 (Rt)	1 ~ 3' X 2'	4.9'	SCC-3&4	PW-2	0	2:1	8"	7"	3.917	6.583	N/A	N/A	11.167	4.167	N/A	0.0	0.6	9.8	141
CULVERT 9 (Lt)	1 ~ 3' X 2'	2.4'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.375	2.792	N/A	N/A	9.833	N/A	3.000	0.2	0.1	2.7	N/A
CULVERT 9 (Rt)	1 ~ 3' X 2'	2.4'	SCC-3&4	PW-1	0	2:1	8"	7"	1.750	4.417	N/A	N/A	8.833	4.167	N/A	0.0	0.3	5.3	78
CULVERT 10 (Lt)	1 ~ 3' X 2'	3.1'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.250	2.667	N/A	N/A	9.333	N/A	3.000	0.2	0.0	2.5	N/A
CULVERT 10 (Rt)	1 ~ 3' X 2'	3.1'	SCC-3&4	PW-1	0	2:1	8"	7"	0.458	3.125	N/A	N/A	6.250	4.167	N/A	0.0	0.1	3.2	39
CULVERT 11 (Lt)	1 ~ 3' X 2'	4.1'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	1.313	3.729	N/A	N/A	10.188	N/A	3.000	0.2	0.2	3.0	N/A
CULVERT 11 (Rt)	1 ~ 3' X 2'	4.1'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.250	2.667	N/A	N/A	9.333	N/A	3.000	0.2	0.0	2.5	N/A
CULVERT 14 (Lt)	1 ~ 8' X 8'	5.3'	SCC-8	PW-1	0	2:1	8"	7"	3.063	11.729	N/A	N/A	23.458	9.167	N/A	0.0	1.0	38.8	550
CULVERT 14 (Rt)	1 ~ 8' X 8'	5.3'	SCC-8	PW-1	0	2:1	8"	7"	4.292	12.958	N/A	N/A	25.917	9.167	N/A	0.0	1.5	48.5	672
CULVERT 15 (Lt)	1 ~ 3' X 2'	2.9'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.250	2.667	N/A	N/A	7.000	N/A	3.000	0.1	0.0	1.9	N/A
CULVERT 16 (Lt)	1 ~ 3' X 3'	4.3'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.250	3.667	N/A	N/A	10.000	N/A	3.000	0.2	0.0	3.0	N/A
CULVERT 20 (Lt)	1 ~ 3' X 2'	3.4'	SCC-3&4	SETB-SW-0	0	6:1	8"	7"	0.250	2.667	N/A	N/A	14.000	N/A	3.000	0.3	0.0	3.8	N/A
CULVERT 20 (Rt)	1 ~ 3' X 2'	3.4'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.250	2.667	N/A	N/A	9.333	N/A	3.000	0.2	0.0	2.5	N/A
CULVERT 21 (Lt)	1 ~ 3' X 2'	4.2'	SCC-3&4	SETB-SW-0	0	6:1	8"	7"	0.250	2.667	N/A	N/A	14.000	N/A	3.000	0.3	0.0	3.8	N/A
CULVERT 21 (Rt)	1 ~ 3' X 2'	4.2'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.250	2.667	N/A	N/A	9.333	N/A	3.000	0.2	0.0	2.5	N/A
CULVERT 22 (Lt)	1 ~ 7' X 7'	2.5'	SCC-7	SETB-SW-0	0	4:1	8"	7"	0.438	7.854	N/A	N/A	30.083	N/A	7.000	1.8	0.1	14.9	N/A
CULVERT 23 (Lt)	1 ~ 6' X 4'	3.6'	SCC-5&6	SETB-SW-0	0	4:1	8"	7"	0.750	5.167	N/A	N/A	19.333	N/A	6.000	1.1	0.2	7.2	N/A
CULVERT 23 (Rt)	1 ~ 6' X 4'	3.6'	SCC-5&6	SETB-SW-0	0	4:1	8"	7"	0.313	4.729	N/A	N/A	17.583	N/A	6.000	1.0	0.1	6.3	N/A
CULVERT 24 (Lt)	1 ~ 3' X 2'	2.4'	SCC-3&4	SETB-SW-0	0	6:1	8"	7"	0.688	3.104	N/A	N/A	16.625	N/A	3.000	0.4	0.1	4.6	N/A
CULVERT 26 (Lt)	1 ~ 5' X 4'	5'	SCC-5&6	SETB-SW-0	0	4:1	8"	7"	2.667	7.083	N/A	N/A	27.000	N/A	5.000	0.8	0.6	13.3	N/A
CULVERT 27 (Lt)	1 ~ 3' X 2'	8.5'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.250	2.667	N/A	N/A	9.333	N/A	3.000	0.2	0.0	2.5	N/A
CULVERT 27 (Rt)	1 ~ 3' X 2'	8.5'	SCC-3&4	SETB-SW-0	0	4:1	8"	7"	0.396	2.813	N/A	N/A	9.917	N/A	3.000	0.2	0.1	2.7	N/A
CULVERT 28 (Lt)	1 ~ 3' X 2'	2.8'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	1.667	4.083	N/A	N/A	11.250	N/A	3.000	0.2	0.3	3.8	N/A
CULVERT 29 (Lt)	1 ~ 3' X 2'	3'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.292	2.708	N/A	N/A	7.125	N/A	3.000	0.1	0.0	2.0	N/A
CULVERT31 (Lt)	1 ~ 3' X 2'	3.4'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.250	2.667	N/A	N/A	7.000	N/A	3.000	0.1	0.0	1.9	N/A
CULVERT31 (Rt)	1 ~ 3' X 2'	3.4'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	1.063	3.479	N/A	N/A	9.438	N/A	3.000	0.2	0.2	2.7	N/A
CULVERT32 (Lt)	1 ~ 3' X 2'	2.9'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.729	3.146	N/A	N/A	8.438	N/A	3.000	0.2	0.1	2.4	N/A
CULVERT32 (Rt)	1 ~ 3' X 2'	2.9'	SCC-3&4	SETB-SW-0	0	3:1	8"	7"	0.500	2.917	N/A	N/A	7.750	N/A	3.000	0.2	0.1	2.1	N/A

NOTES:

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets; 30° maximum for safety end treatment

SL:1 = Horizontal : 1 Vertical

- Side slope at culvert for flared or straight wingwalls.
- Channel slope for parallel wingwalls.
- Slope must be 3:1 or flatter for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)

B = Offset of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)

Atw = Length of anchor toewall (applicable to safety end treatment only)

Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt. Area for four wingwalls (two structure ends) if Both.

(1) Round the wall heights shown to the nearest foot for bidding purposes.

(2) Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class 5 concrete is required for the top slab of the culvert, also provide Class 5 concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.

(3) Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.

(4) Regardless of the type of culvert shown on this sheet, the Contractor has the option of furnishing cast-in-place or precast culverts unless otherwise shown elsewhere on the plans. If the Contractor elects to provide culverts of a different type than those shown on this sheet, it is the Contractor's responsibility to make the necessary adjustments to the dimensions and quantities shown.



				Bridge Division Standard	
BOX CULVERT SUPPLEMENT WINGS AND END TREATMENTS					
BCS					
FILE:	bcsstdel-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT	February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152	
DIST	AMA	COUNTY	CARSON	SHEET NO. 151	

DATE: FILE:

DATE: 8/12/2023 4:53:37 PM
 FILE: L:\Amorillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\SH 152-WA 6\CADD\Sheets\07 Drainage Detail.dwg
 PW1 and PW2.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided.

TABLE OF DIMENSIONS AND REINFORCING STEEL
(Wings for one structure end)



Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings)		Estimated Quantities per ft of Toewall (1-toewall)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

TABLE OF WINGWALL REINFORCING (2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

TABLE OF TOEWALL REINFORCING

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



WING DIMENSION FORMULAS:
(All values are in feet.)



$Hw = H + T + C$
 $Lw = (Hw)(SL) \div \cosine(\theta)$ for Type PW-1
 $Lw = (Hw - 1')(SL) \div \cosine(\theta)$ for Type PW-2 and $Hw \geq 4'$
 $Lw = (Hw - 0.5')(SL) \div \cosine(\theta)$ for Type PW-2 and $Hw < 4'$

For cast-in-place culverts:
 $Ltw = [(N)(S) + (N + 1)(U)] \div \cosine(\theta)$

For precast culverts:
 $Ltw = [(N)(2U + S) + (N - 1)(0.5')] \div \cosine(\theta)$
 Total Wingwall Area (two wings ~ SF)
 $= (2)(Hw)(Lw)$ for Type PW-1
 $= (2)(Hw)(Lw) - 6 SF$ for Type PW-2 and $Hw \geq 4'$
 $= (2)(Hw)(Lw) - 1.5 SF$ for Type PW-2 and $Hw < 4'$

Hw = Height of wingwall
 Lw = Length of wingwall
 Ltw = Culvert toewall length
 N = Number of culvert spans
 $SL:1$ = Channel slope ratio, (horizontal: 1 vertical, usual value is 2:1)
 θ = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.




- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"
For 30° skew ~ 2"
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.

DESIGNER NOTES:
 Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall.
 Type PW-2 can only be used for applications without a railing mounted to the wingwall.


MATERIAL NOTES:
 Provide Class C concrete (f'c=3,600 psi).
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel if required elsewhere in the plans.

GENERAL NOTES:
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information.
 Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.


Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.




PARTIAL ELEVATION - PW-1




PARTIAL ELEVATION - PW-2




SECTION A-A
(Showing wing reinforcement.)



SECTION B-B
(Showing wing reinforcement.)



DETAILS FOR NON-SKEWED BOX CULVERTS



DETAILS FOR SKEWED BOX CULVERTS
(Showing 30° skew.)

Texas Department of Transportation Bridge Division Standard


CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2

PW


FILE: pwstde01-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
REVISIONS	CONTRACT	SECTION	JOB	HIGHWAY
	0455	02	031, ETC	SH 152
	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	152	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided. **Project: 20-0901**


DATE: 8/12/2023 4:53:38 PM
 FILE: L:\Amarillo District\SH 152-WA 6\CADD\Sheets\07 Drainage Detail\psetrrse-20.dgn




PLAN



LONGITUDINAL ELEVATION



MULTIPLE PIPE INSTALLATION



SINGLE PIPE INSTALLATION

SECTION A-A

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY)

Nominal Culvert (Pipe) I.D.	PSET-SC and PSET-SP Standards					PSET-RC and PSET-RP Standards		
	Unit Width "W"	Side Slope			Unit Width "W"	Side Slope		
		3:1	4:1	6:1		3:1	4:1	6:1
12"	23.0"	0.1	0.2	0.2	16.0"	0.1	0.1	0.2
15"	26.5"	0.2	0.2	0.3	19.5"	0.1	0.2	0.2
18"	30.0"	0.2	0.2	0.3	23.0"	0.2	0.2	0.3
24"	37.0"	0.3	0.3	0.5	30.0"	0.2	0.3	0.4
30"	44.5"	0.3	0.4	0.6	37.0"	0.3	0.3	0.5
36"	51.5"	0.4	0.5	0.7	44.0"	0.3	0.4	0.6
42"	58.5"	0.5	0.6	0.8	51.0"	0.4	0.5	0.7

- ① Riprap placed beyond the limits shown will be paid as concrete riprap in accordance with Item 432, "Riprap". When riprap is cast integrally with the precast safety end treatment, this dimension is 1'-0" minimum.
- ② 1#2" Dia ASTM A307 Gr A threaded anchor rod with 2 nuts and 2 washers. Galvanize all components in accordance with Item 445, "Galvanizing". Repair galvanizing that is damaged during transport or construction in accordance with the specifications.
- ③ 3#4" through holes in walls of safety end treatment for riprap anchor rods may be drilled with rotary (coring or masonry) type drilling equipment or may be formed. Do not use percussive (star) type drilling equipment. If holes are drilled, patch spalls in the inside face of the wall exceeding 1#2" from the holes.
- ④ Provide riprap toe wall when dimension is shown elsewhere in the plans or when field conditions require a toe wall.
- ⑤ Quantities shown are for one end of one reinforced concrete pipe culvert. For multiple pipe culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only. Quantities are based on the minimum unit lengths shown on the Precast Safety End Treatment (SET) standard sheets.

MATERIAL NOTES:

Provide Class "B" riprap in accordance with Item 432, "Riprap". Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. The anchor rods shown are always required.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment". Refer to PSET-SC or PSET-SP standard sheets for details of square safety end treatments not shown. Refer to PSET-RC or PSET-RP standard sheets for details of round safety end treatments not shown. For precast units with integrally cast riprap, substitute reinforcing steel in the amount on 0.26 in./ft. minimum for the threaded anchor rods shown. When requested, submit sealed engineering drawings for approval prior to construction. Shop drawings will not be required. Note that a proprietary precast unit with integral riprap is available from L&R Precast Concrete Works, Inc. (956) 583-6293 or www.lrpccast.com. Payment for riprap and toewalls is included in the price bid for each safety end treatment.


These riprap details are only applicable when notes that require placement of riprap with precast safety end treatments are shown elsewhere in the plans.
 Precast units with integrally cast riprap are permitted unless noted otherwise on the plans.

Texas Department of Transportation Bridge Division Standard


PRECAST SAFETY END TREATMENT TYPE II RIPRAP DETAILS PSET-RR

FILE: psetrrse-20.dgn	DN: GAF	CK: TxDOT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT SECT	JOB	HIGHWAY	
REVISIONS	0455 02	031, ETC	SH 152	
DIST	COUNTY	SHEET NO.		
AMA	CARSON	152A		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard. 08/12/2023 4:53:39 PM L:\Amorillo\District\SH_152_WA_6\CADD\Sheets\07 Drainage Detail\15\TxDOT_Schmdste-20.dgn




PLAN OF SKEWED ENDS ~ FROM 0° TO 15°



PLAN OF SKEWED ENDS ~ OVER 30° TO 45°



PLAN OF SKEWED ENDS ~ OVER 15° TO 30°



LENGTHENING DETAIL

1 For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.
 For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, Nba, of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.
 Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.


- 2 When the spacing between Bars B becomes less than half of the normal spacing, cut bars to avoid conflict.
- 3 The length of Bars B vary in the skewed end sections.
- 4 $[One\ half\ of\ overall\ width] \times [tangent\ of\ the\ skew\ angle]$
- 5 Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- 6 When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- 7 At the Contractor's option, for skews of 15° or less, place Bars B, C, and D parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B shown on the Single Box Culverts Cast-In-Place (SCC) standards sheets to accommodate the skew.

CONSTRUCTION NOTES:
 Do not use permanent forms.
 When required, lap Bars H 1'-8" for uncoated or galvanized bars.
 Provide a minimum of 1 1/2" clear cover.


MATERIAL NOTES:
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel, if required elsewhere in the plans.
 Provide Class C concrete (f'c = 3,600 psi) with these exceptions:
 provide Class S concrete (f'c = 4,000 psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for details of straight sections of culvert.
 For skewed sections and angle sections, refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.
 For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the culvert Single Box Culverts Cast-In-Place (SCC) standard sheets by the cosine of the skew angle.


Cover dimensions are clear dimensions, unless noted otherwise.



PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ OVER 30° TO 45°

HL93 LOADING


		Bridge Division Standard	
SINGLE BOX CULVERTS CAST-IN-PLACE MISCELLANEOUS DETAILS			
SCC-MD			
FILE: sccmdste-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT February 2020	CONT: 0455	SECT: 02	JOB: 031, ETC
REVISIONS	SH: 152	HIGHWAY	
DIST: AMA	COUNTY: CARSON	SHEET NO: 153	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors, omissions, or damages resulting from its use.


DATE: 8/12/2023 4:53:40 PM
 FILE: L:\Amarillo District\SH 152_WA_6\CADD\Sheets\07 Drainage Detail\TXDOT Standards\sc34ste-21.dgn




TYPICAL SECTION




PLAN OF REINF STEEL




SECTION THRU CURB



BARS C



BARS D



BARS K (#4)
 (Spa = 1'-0" Max)
 (Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

MATERIAL NOTES:

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete ($f'c = 3,600$ psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete ($f'c = 4,000$ psi) for top slabs of:
 - culverts with overlay,
 - culverts with 1-to-2 course surface treatment, or
 - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
 - Uncoated or galvanized ~ #4 = 1'-8" Min
 - Uncoated or galvanized ~ #5 = 2'-1" Min

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2



**SINGLE BOX CULVERTS
 CAST-IN-PLACE
 0' TO 30' FILL**

SCC-3 & 4

FILE: scc34ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	154	

DATE: 8/12/2023 4:53:41 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Details\TXDOT_Standards\SCC34ste-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any kind of units or for any errors or omissions in the drawings.

SECTION DIMENSIONS				FILL HEIGHT ⁵	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																								QUANTITIES														
					Bars B				Bars C				Bars D				Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total								
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
3' - 0"	2' - 0"	8"	7"	30'	108	#5	9"	3' - 11"	441	108	#4	9"	5' - 4"	385	2' - 6"	2' - 10"	108	#4	9"	5' - 1"	367	2' - 10"	2' - 3"	108	9"	2' - 0"	144	3	39' - 9"	80	19	39' - 9"	505	3' - 11"	10	10	28	0.292	48.1	0.3	38	12.0	1,960
3' - 0"	3' - 0"	8"	7"	30'	108	#5	9"	3' - 11"	441	108	#4	9"	6' - 4"	457	3' - 6"	2' - 10"	108	#4	9"	5' - 1"	367	2' - 10"	2' - 3"	108	9"	3' - 0"	216	3	39' - 9"	80	23	39' - 9"	611	3' - 11"	10	10	28	0.335	54.3	0.3	38	13.7	2,210
4' - 0"	2' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	5' - 8"	613	2' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	2' - 0"	144	3	39' - 9"	80	21	39' - 9"	558	4' - 11"	13	12	33	0.342	63.4	0.4	46	14.1	2,581
4' - 0"	3' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	6' - 8"	721	3' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	3' - 0"	216	3	39' - 9"	80	25	39' - 9"	664	4' - 11"	13	12	33	0.385	70.5	0.4	46	15.8	2,867
4' - 0"	4' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	7' - 8"	830	4' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	4' - 0"	289	3	39' - 9"	80	25	39' - 9"	664	4' - 11"	13	12	33	0.428	75.1	0.4	46	17.5	3,049

⁵ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.




**SINGLE BOX CULVERTS
CAST-IN-PLACE
0' TO 30' FILL**

SCC-3 & 4


FILE: scc34ste-21.dgn	DN: TBE	CK: BMP	DW: TXDOT	CK: TXDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	155	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information shown on this drawing. If you find any errors, please contact the project engineer at the address below.


DATE: 8/12/2023 4:53:42 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\SCC-5&6\SCC-5&6.dgn




TYPICAL SECTION




PLAN OF REINF STEEL




SECTION THRU CURB



BARS C



BARS D



BARS K (#4)
 (Spa = 1'-0" Max)
 (Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

MATERIAL NOTES:

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
 - culverts with overlay,
 - culverts with 1-to-2 course surface treatment, or
 - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
 - Uncoated or galvanized ~ #4 = 1'-8" Min
 - Uncoated or galvanized ~ #5 = 2'-1" Min
 - Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2



**SINGLE BOX CULVERTS
 CAST-IN-PLACE
 0' TO 30' FILL**

SCC-5 & 6

FILE: scc56ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	156	

DATE: 8/12/2023 4:53:43 PM
 FILE: L:\Amarillo District\SH 152_WA_6\CADD\Sheets\07 Drainage Detail\TXDOT_S\sc56ste-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of incorrect results or damages resulting from its use.


SECTION DIMENSIONS				FILL HEIGHT ⁵	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																								QUANTITIES														
					Bars B					Bars C					Bars D					Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total					
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
5'-0"	2'-0"	8"	7"	26'	108	#6	9"	5'-11"	960	108	#5	9"	6'-3"	704	2'-6"	3'-9"	108	#5	9"	6'-5"	723	3'-9"	2'-8"	108	9"	2'-0"	144	4	39'-9"	106	22	39'-9"	584	5'-11"	16	14	39	0.391	80.5	0.5	55	16.1	3,276
5'-0"	2'-0"	9"	7"	30'	108	#6	9"	5'-11"	960	108	#5	9"	6'-4"	713	2'-7"	3'-9"	108	#5	9"	6'-6"	732	3'-9"	2'-9"	108	9"	2'-0"	144	4	39'-9"	106	22	39'-9"	584	5'-11"	16	14	39	0.429	81.0	0.5	55	17.6	3,294
5'-0"	3'-0"	8"	7"	26'	108	#6	9"	5'-11"	960	108	#5	9"	7'-3"	817	3'-6"	3'-9"	108	#5	9"	6'-5"	723	3'-9"	2'-8"	108	9"	3'-0"	216	4	39'-9"	106	26	39'-9"	690	5'-11"	16	14	39	0.434	87.8	0.5	55	17.8	3,567
5'-0"	3'-0"	9"	7"	30'	108	#6	9"	5'-11"	960	108	#5	9"	7'-4"	826	3'-7"	3'-9"	108	#5	9"	6'-6"	732	3'-9"	2'-9"	108	9"	3'-0"	216	4	39'-9"	106	26	39'-9"	690	5'-11"	16	14	39	0.472	88.3	0.5	55	19.3	3,585
5'-0"	4'-0"	8"	7"	26'	108	#6	9"	5'-11"	960	108	#5	9"	8'-3"	929	4'-6"	3'-9"	108	#5	9"	6'-5"	723	3'-9"	2'-8"	108	9"	4'-0"	289	4	39'-9"	106	26	39'-9"	690	5'-11"	16	14	39	0.477	92.4	0.5	55	19.5	3,752
5'-0"	4'-0"	9"	7"	30'	108	#6	9"	5'-11"	960	108	#5	9"	8'-4"	939	4'-7"	3'-9"	108	#5	9"	6'-6"	732	3'-9"	2'-9"	108	9"	4'-0"	289	4	39'-9"	106	26	39'-9"	690	5'-11"	16	14	39	0.515	92.9	0.5	55	21.1	3,771
5'-0"	5'-0"	8"	7"	26'	108	#6	9"	5'-11"	960	108	#5	9"	9'-3"	1,042	5'-6"	3'-9"	108	#5	9"	6'-5"	723	3'-9"	2'-8"	108	9"	5'-0"	361	4	39'-9"	106	30	39'-9"	797	5'-11"	16	14	39	0.521	99.7	0.5	55	21.3	4,044
5'-0"	5'-0"	9"	7"	30'	108	#6	9"	5'-11"	960	108	#5	9"	9'-4"	1,051	5'-7"	3'-9"	108	#5	9"	6'-6"	732	3'-9"	2'-9"	108	9"	5'-0"	361	4	39'-9"	106	30	39'-9"	797	5'-11"	16	14	39	0.559	100.2	0.5	55	22.8	4,062
6'-0"	2'-0"	8"	7"	20'	108	#6	9"	6'-11"	1,122	108	#5	9"	6'-7"	742	2'-6"	4'-1"	108	#5	9"	6'-9"	760	4'-1"	2'-8"	108	9"	2'-0"	144	5	39'-9"	133	25	39'-9"	664	6'-11"	18	16	45	0.440	89.1	0.5	63	18.1	3,628
6'-0"	2'-0"	9"	7"	26'	108	#6	9"	6'-11"	1,122	162	#5	6"	6'-8"	1,126	2'-7"	4'-1"	162	#5	6"	6'-10"	1,155	4'-1"	2'-9"	108	9"	2'-0"	144	5	39'-9"	133	25	39'-9"	664	6'-11"	18	16	45	0.485	108.6	0.5	63	19.9	4,407
6'-0"	2'-0"	10"	8"	30'	108	#6	9"	7'-1"	1,149	162	#5	6"	6'-10"	1,155	2'-8"	4'-2"	162	#5	6"	7'-0"	1,183	4'-2"	2'-10"	82	12"	2'-0"	110	5	39'-9"	133	25	39'-9"	664	7'-1"	19	18	50	0.551	109.9	0.5	69	22.6	4,463
6'-0"	3'-0"	8"	7"	20'	108	#6	9"	6'-11"	1,122	108	#5	9"	7'-7"	854	3'-6"	4'-1"	108	#5	9"	6'-9"	760	4'-1"	2'-8"	108	9"	3'-0"	216	5	39'-9"	133	29	39'-9"	770	6'-11"	18	16	45	0.484	96.4	0.5	63	19.9	3,918
6'-0"	3'-0"	9"	7"	26'	108	#6	9"	6'-11"	1,122	162	#5	6"	7'-8"	1,295	3'-7"	4'-1"	162	#5	6"	6'-10"	1,155	4'-1"	2'-9"	108	9"	3'-0"	216	5	39'-9"	133	29	39'-9"	770	6'-11"	18	16	45	0.528	117.3	0.5	63	21.6	4,754
6'-0"	3'-0"	10"	8"	30'	108	#6	9"	7'-1"	1,149	162	#5	6"	7'-10"	1,324	3'-8"	4'-2"	162	#5	6"	7'-0"	1,183	4'-2"	2'-10"	82	12"	3'-0"	164	5	39'-9"	133	29	39'-9"	770	7'-1"	19	18	50	0.601	118.1	0.5	69	24.6	4,792
6'-0"	4'-0"	8"	7"	20'	108	#6	9"	6'-11"	1,122	108	#5	9"	8'-7"	967	4'-6"	4'-1"	108	#5	9"	6'-9"	760	4'-1"	2'-8"	108	9"	4'-0"	289	5	39'-9"	133	29	39'-9"	770	6'-11"	18	16	45	0.527	101.0	0.5	63	21.6	4,104
6'-0"	4'-0"	9"	7"	26'	108	#6	9"	6'-11"	1,122	162	#5	6"	8'-8"	1,464	4'-7"	4'-1"	162	#5	6"	6'-10"	1,155	4'-1"	2'-9"	108	9"	4'-0"	289	5	39'-9"	133	29	39'-9"	770	6'-11"	18	16	45	0.571	123.3	0.5	63	23.4	4,996
6'-0"	4'-0"	10"	8"	30'	108	#6	9"	7'-1"	1,149	162	#5	6"	8'-10"	1,493	4'-8"	4'-2"	162	#5	6"	7'-0"	1,183	4'-2"	2'-10"	82	12"	4'-0"	219	5	39'-9"	133	29	39'-9"	770	7'-1"	19	18	50	0.650	123.7	0.5	69	26.5	5,016
6'-0"	5'-0"	8"	7"	20'	108	#6	9"	6'-11"	1,122	108	#5	9"	9'-7"	1,080	5'-6"	4'-1"	108	#5	9"	6'-9"	760	4'-1"	2'-8"	108	9"	5'-0"	361	5	39'-9"	133	33	39'-9"	876	6'-11"	18	16	45	0.570	108.3	0.5	63	23.3	4,395
6'-0"	5'-0"	9"	7"	26'	108	#6	9"	6'-11"	1,122	162	#5	6"	9'-8"	1,633	5'-7"	4'-1"	162	#5	6"	6'-10"	1,155	4'-1"	2'-9"	108	9"	5'-0"	361	5	39'-9"	133	33	39'-9"	876	6'-11"	18	16	45	0.614	132.0	0.5	63	25.1	5,343
6'-0"	5'-0"	10"	8"	30'	108	#6	9"	7'-1"	1,149	162	#5	6"	9'-10"	1,661	5'-8"	4'-2"	162	#5	6"	7'-0"	1,183	4'-2"	2'-10"	82	12"	5'-0"	274	5	39'-9"	133	33	39'-9"	876	7'-1"	19	18	50	0.700	131.9	0.5	69	28.5	5,345
6'-0"	6'-0"	8"	7"	20'	108	#6	9"	6'-11"	1,122	108	#5	9"	10'-7"	1,192	6'-6"	4'-1"	108	#5	9"	6'-9"	760	4'-1"	2'-8"	108	9"	6'-0"	433	5	39'-9"	133	37	39'-9"	982	6'-11"	18	16	45	0.613	115.6	0.5	63	25.0	4,685
6'-0"	6'-0"	9"	7"	26'	108	#6	9"	6'-11"	1,122	162	#5	6"	10'-8"	1,802	6'-7"	4'-1"	162	#5	6"	6'-10"	1,155	4'-1"	2'-9"	108	9"	6'-0"	433	5	39'-9"	133	37	39'-9"	982	6'-11"	18	16	45	0.657	140.7	0.5	63	26.8	5,690
6'-0"	6'-0"	10"	8"	30'	108	#6	9"	7'-1"	1,149	162	#5	6"	10'-10"	1,830	6'-8"	4'-2"	162	#5	6"	7'-0"	1,183	4'-2"	2'-10"	82	12"	6'-0"	329	5	39'-9"	133	37	39'-9"	982	7'-1"	19	18	50	0.749	140.2	0.5	69	30.5	5,675

⁵ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.


				Bridge Division Standard	
SINGLE BOX CULVERTS CAST-IN-PLACE 0' TO 30' FILL					
SCC-5 & 6					
FILE: scc56ste-21.dgn	DN: TBE	CK: BMP	DW: TXDOT	CR: TXDOT	
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0455	02	031, ETC	SH 152	
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.		
	AMA	CARSON	157		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any drawings or specifications to any other format, including electronic, without the express written consent of TxDOT. Incorrect results or damages resulting from its use.


DATE: 8/12/2023 4:53:44 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standard\SCC-7.sht.dgn




TYPICAL SECTION



PLAN OF REINF STEEL



SECTION THRU CURB



- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:
 Do not use permanent forms.
 Chamfer the bottom edge of the top slab 3" at the entrance.
 Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

MATERIAL NOTES:
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel if required elsewhere in the plans.
 Provide Class C concrete ($f'_c = 3,600$ psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete ($f'_c = 4,000$ psi) for top slabs of:

- culverts with overlay,
- culverts with 1-to-2 course surface treatment, or
- culverts with the top slab as the final riding surface.

 Provide bar laps, where required, as follows:

- Uncoated or galvanized ~ #4 = 1'-8" Min
- Uncoated or galvanized ~ #5 = 2'-1" Min
- Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
 See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2

Texas Department of Transportation Bridge Division Standard

SINGLE BOX CULVERTS CAST-IN-PLACE
0' TO 30' FILL

SCC-7


FILE: scc07ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	158	

DATE: 8/12/2023 4:53:45 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standard\SCC07ste-21.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of incorrect results or damages resulting from its use.

SECTION DIMENSIONS				FILL HEIGHT ⑤	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																										QUANTITIES												
					Bars B					Bars C					Bars D					Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total					
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
7'-0"	3'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	7'-11"	1,338	3'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	3'-0"	216	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.533	124.8	0.6	71	21.9	5,062
7'-0"	3'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	8'-0"	1,352	3'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	3'-0"	216	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.583	125.5	0.6	71	23.9	5,090
7'-0"	3'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	8'-2"	1,380	3'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	3'-0"	164	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.663	126.3	0.6	78	27.1	5,128
7'-0"	3'-0"	11"	8"	30'	108	#6	9"	8'-1"	1,311	162	#5	6"	8'-3"	1,394	3'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	3'-0"	164	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.714	127.0	0.6	78	29.2	5,156
7'-0"	4'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	8'-11"	1,507	4'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	4'-0"	289	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.576	130.8	0.6	71	23.6	5,304
7'-0"	4'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	9'-0"	1,521	4'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	4'-0"	289	5	39'-9"	133	31	39'-9"	823	7'-11"	21	18	50	0.627	131.5	0.6	71	25.7	5,332
7'-0"	4'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	9'-2"	1,549	4'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	4'-0"	219	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.712	131.9	0.6	78	29.1	5,352
7'-0"	4'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	9'-3"	1,563	4'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	4'-0"	219	5	39'-9"	133	31	39'-9"	823	8'-1"	22	20	56	0.763	149.0	0.6	78	31.1	6,036
7'-0"	5'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	9'-11"	1,676	5'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	5'-0"	361	5	39'-9"	133	35	39'-9"	929	7'-11"	21	18	50	0.619	139.5	0.6	71	25.4	5,651
7'-0"	5'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	10'-0"	1,690	5'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	5'-0"	361	5	39'-9"	133	35	39'-9"	929	7'-11"	21	18	50	0.670	140.2	0.6	71	27.4	5,679
7'-0"	5'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	10'-2"	1,718	5'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	5'-0"	274	5	39'-9"	133	35	39'-9"	929	8'-1"	22	20	56	0.761	140.1	0.6	78	31.1	5,682
7'-0"	5'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	10'-3"	1,732	5'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	5'-0"	274	5	39'-9"	133	35	39'-9"	929	8'-1"	22	20	56	0.813	157.2	0.6	78	33.1	6,366
7'-0"	6'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	10'-11"	1,845	6'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	6'-0"	433	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.663	148.2	0.6	71	27.1	5,999
7'-0"	6'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	11'-0"	1,859	6'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	6'-0"	433	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.713	148.9	0.6	71	29.1	6,027
7'-0"	6'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	11'-2"	1,887	6'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	82	12"	6'-0"	329	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.811	148.4	0.6	78	33.1	6,013
7'-0"	6'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	11'-3"	1,901	6'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	82	12"	6'-0"	329	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.862	165.5	0.6	78	35.1	6,697
7'-0"	7'-0"	8"	7"	16'	108	#6	9"	7'-11"	1,284	162	#5	6"	11'-11"	2,014	7'-6"	4'-5"	162	#5	6"	7'-1"	1,197	4'-5"	2'-8"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.706	154.2	0.6	71	28.8	6,240
7'-0"	7'-0"	9"	7"	20'	108	#6	9"	7'-11"	1,284	162	#5	6"	12'-0"	2,028	7'-7"	4'-5"	162	#5	6"	7'-2"	1,211	4'-5"	2'-9"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	7'-11"	21	18	50	0.756	154.9	0.6	71	30.8	6,268
7'-0"	7'-0"	10"	8"	23'	108	#6	9"	8'-1"	1,311	162	#5	6"	12'-2"	2,056	7'-8"	4'-6"	162	#5	6"	7'-4"	1,239	4'-6"	2'-10"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.860	157.0	0.6	78	35.0	6,358
7'-0"	7'-0"	11"	8"	30'	162	#6	6"	8'-1"	1,967	162	#5	6"	12'-3"	2,070	7'-9"	4'-6"	162	#5	6"	7'-5"	1,253	4'-6"	2'-11"	108	9"	7'-0"	505	5	39'-9"	133	39	39'-9"	1,036	8'-1"	22	20	56	0.912	174.1	0.6	78	37.1	7,042


⑤ For direct traffic culverts (fill height ≤ 2 ft.), identify the required box size and select the option with the minimum fill height.

HL93 LOADING SHEET 2 OF 2


				Bridge Division Standard	
SINGLE BOX CULVERTS CAST-IN-PLACE 0' TO 30' FILL					
SCC-7					
FILE: scc07ste-21.dgn	DN: TBE	CK: BMP	DW: TXDOT	CK: TXDOT	
© TXDOT February 2020	CONT	SECT	JOB	HIGHWAY	
REVISIONS		0455	02	031, ETC	SH 152
04/2021 Updated X values.		DIST	COUNTY	SHEET NO.	
		AMA	CARSON	159	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another, or for any errors or omissions, or for any damages resulting from its use.


DATE: 8/12/2023 4:53:46 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standard\SCC8ste-21.dgn




TYPICAL SECTION




PLAN OF REINF STEEL




SECTION THRU CURB



BARS C



BARS D



BARS K (#4)
 (Spa = 1'-0" Max)
 (Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed.

MATERIAL NOTES:

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
 - culverts with overlay,
 - culverts with 1-to-2 course surface treatment, or
 - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
 - Uncoated or galvanized ~ #4 = 1'-8" Min
 - Uncoated or galvanized ~ #5 = 2'-1" Min
 - Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING

SHEET 1 OF 2




**SINGLE BOX CULVERTS
 CAST-IN-PLACE
 0' TO 30' FILL**

SCC-8


FILE: scc08ste-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	160	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



TYPICAL SECTION




BOTTOM SLAB **TOP SLAB**
PART PLANS



SECTION THRU CURB

TABLE OF BAR DIMENSIONS		
H	"X"	"Y"
2'-0"	2'-6 1/2"	3'-8 1/2"
3'-0"	3'-6 1/2"	3'-8 1/2"
4'-0"	4'-6 1/2"	3'-8 1/2"
5'-0"	5'-6 1/2"	3'-8 1/2"



- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR
Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed, and Bars Y and Z may be reversed.

MATERIAL NOTES:

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
 - culverts with overlay,
 - culverts with 1-to-2 course surface treatment, or
 - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
 - Uncoated or galvanized ~ #4 = 1'-8" Min
 - Uncoated or galvanized ~ #5 = 2'-1" Min
 - Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Multiple Box Culverts Cast-In-Place Miscellaneous Detail (MC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.



MULTIPLE BOX CULVERTS CAST-IN-PLACE
5'-0" SPAN
0' TO 20' FILL



MC-5-20

FILE: mc520ste-20.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	162	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

NUMBER OF SPANS	SECTION DIMENSIONS				BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																								QUANTITIES																								
					Bars B				Bars C & D				Bars E				Bars F1 ~ #4		Bars F2 ~ #4		Bars M ~ #4		Bars Y & Z ~ #4				Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total																		
	S	H	T	U	No.	Size	Spa	Length	Wt	No.	Size	Spa	Bars C		Bars D		No.	Size	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Bars Y		Bars Z		Length	Wt	No.	Wt	Conc (CY)	Ref (Lb)	Conc (CY)	Ref (Lb)	Conc (CY)	Ref (Lb)
													Length	Wt	Length	Wt																								Length	Wt	Length	Wt										
2	5'-0"	2'-0"	8"	7"	108	#5	9"	11'-6"	1,295	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	38	18"	39'-9"	1,009	108	9"	2'-0"	144	54	9"	4'-7"	165	5'-3"	189	11'-6"	31	26	72	0.710	135.2	0.9	103	29.3	5,510				
3	5'-0"	2'-0"	8"	7"	108	#5	9"	17'-1"	1,924	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	54	18"	39'-9"	1,434	108	9"	2'-0"	144	108	9"	4'-7"	331	5'-3"	379	17'-1"	46	38	106	1.029	188.8	1.3	152	42.4	7,705				
4	5'-0"	2'-0"	8"	7"	108	#5	9"	22'-8"	2,553	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	70	18"	39'-9"	1,859	108	9"	2'-0"	144	162	9"	4'-7"	496	5'-3"	568	22'-8"	61	48	134	1.348	242.4	1.7	195	55.6	9,891				
5	5'-0"	2'-0"	8"	7"	108	#5	9"	28'-3"	3,182	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	86	18"	39'-9"	2,284	108	9"	2'-0"	144	216	9"	4'-7"	661	5'-3"	758	28'-3"	75	60	167	1.667	296.0	2.1	242	68.8	12,082				
6	5'-0"	2'-0"	8"	7"	108	#5	9"	33'-10"	3,811	108	#5	9"	6'-3"	704	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	102	18"	39'-9"	2,708	108	9"	2'-0"	144	270	9"	4'-7"	827	5'-3"	947	33'-10"	90	70	195	1.986	349.6	2.5	285	82.0	14,268				
2	5'-0"	3'-0"	8"	7"	108	#6	9"	11'-6"	1,865	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	44	18"	39'-9"	1,168	108	9"	3'-0"	216	54	9"	4'-7"	165	7'-3"	262	11'-6"	31	26	72	0.775	159.9	0.9	103	31.9	6,497				
3	5'-0"	3'-0"	8"	7"	108	#6	9"	17'-1"	2,771	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	62	18"	39'-9"	1,646	108	9"	3'-0"	216	108	9"	4'-7"	331	7'-3"	523	17'-1"	46	38	106	1.115	223.5	1.3	152	45.9	9,093				
4	5'-0"	3'-0"	8"	7"	108	#6	9"	22'-8"	3,677	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	80	18"	39'-9"	2,124	108	9"	3'-0"	216	162	9"	4'-7"	496	7'-3"	785	22'-8"	61	48	134	1.456	287.2	1.7	195	59.9	11,682				
5	5'-0"	3'-0"	8"	7"	108	#6	9"	28'-3"	4,583	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	98	18"	39'-9"	2,602	108	9"	3'-0"	216	216	9"	4'-7"	661	7'-3"	1,046	28'-3"	75	60	167	1.796	350.8	2.1	242	73.9	14,274				
6	5'-0"	3'-0"	8"	7"	108	#6	9"	33'-10"	5,488	108	#5	9"	7'-3"	817	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	116	18"	39'-9"	3,080	108	9"	3'-0"	216	270	9"	4'-7"	827	7'-3"	1,308	33'-10"	90	70	195	2.137	414.5	2.5	285	88.0	16,863				
2	5'-0"	4'-0"	8"	7"	108	#6	9"	11'-6"	1,865	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	44	18"	39'-9"	1,168	108	9"	4'-0"	289	54	9"	4'-7"	165	9'-3"	334	11'-6"	31	26	72	0.840	166.3	0.9	103	34.5	6,754				
3	5'-0"	4'-0"	8"	7"	108	#6	9"	17'-1"	2,771	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	62	18"	39'-9"	1,646	108	9"	4'-0"	289	108	9"	4'-7"	331	9'-3"	667	17'-1"	46	38	106	1.202	231.8	1.3	152	49.4	9,422				
4	5'-0"	4'-0"	8"	7"	108	#6	9"	22'-8"	3,677	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	80	18"	39'-9"	2,124	108	9"	4'-0"	289	162	9"	4'-7"	496	9'-3"	1,001	22'-8"	61	48	134	1.564	297.2	1.7	195	64.3	12,083				
5	5'-0"	4'-0"	8"	7"	108	#6	9"	28'-3"	4,583	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	98	18"	39'-9"	2,602	108	9"	4'-0"	289	216	9"	4'-7"	661	9'-3"	1,335	28'-3"	75	60	167	1.926	362.7	2.1	242	79.1	14,748				
6	5'-0"	4'-0"	8"	7"	108	#6	9"	33'-10"	5,488	108	#5	9"	8'-3"	929	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	116	18"	39'-9"	3,080	108	9"	4'-0"	289	270	9"	4'-7"	827	9'-3"	1,668	33'-10"	90	70	195	2.288	428.1	2.5	285	94.0	17,408				
2	5'-0"	5'-0"	8"	7"	108	#6	9"	11'-6"	1,865	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	8'-8"	976	8	18"	39'-9"	212	50	18"	39'-9"	1,328	108	9"	5'-0"	361	54	9"	4'-7"	165	11'-3"	406	11'-6"	31	26	72	0.904	176.7	0.9	103	37.0	7,171				
3	5'-0"	5'-0"	8"	7"	108	#6	9"	17'-1"	2,771	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	14'-3"	1,605	12	18"	39'-9"	319	70	18"	39'-9"	1,859	108	9"	5'-0"	361	108	9"	4'-7"	331	11'-3"	812	17'-1"	46	38	106	1.288	245.3	1.3	152	52.8	9,965				
4	5'-0"	5'-0"	8"	7"	108	#6	9"	22'-8"	3,677	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	19'-10"	2,234	16	18"	39'-9"	425	90	18"	39'-9"	2,390	108	9"	5'-0"	361	162	9"	4'-7"	496	11'-3"	1,217	22'-8"	61	48	134	1.672	313.9	1.7	195	68.6	12,750				
5	5'-0"	5'-0"	8"	7"	108	#6	9"	28'-3"	4,583	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	25'-5"	2,863	20	18"	39'-9"	531	110	18"	39'-9"	2,921	108	9"	5'-0"	361	216	9"	4'-7"	661	11'-3"	1,623	28'-3"	75	60	167	2.056	382.5	2.1	242	84.3	15,540				
6	5'-0"	5'-0"	8"	7"	108	#6	9"	33'-10"	5,488	108	#5	9"	9'-3"	1,042	6'-4"	713	108	#5	9"	31'-0"	3,492	24	18"	39'-9"	637	130	18"	39'-9"	3,452	108	9"	5'-0"	361	270	9"	4'-7"	827	11'-3"	2,029	33'-10"	90	70	195	2.439	451.0	2.5	285	100.1	18,326				

			
MULTIPLE BOX CULVERTS CAST-IN-PLACE 5'-0" SPAN 0' TO 20' FILL			
MC-5-20			
FILE: mc520ste-20.dgn	DN: TBE	CK: BMP	DW: TxDOT
©TxDOT February 2020	CONT	SECT	JOB
REVISIONS	0455	02	031, ETC
	DIST	COUNTY	SHEET NO.
	AMA	CARSON	163


DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any errors or omissions resulting from its use.

DATE: 8/12/2023 4:53:54 PM
FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Details\TxDOT Standards\ecdsheet152-07.dgn




TYPICAL SECTION


Used for curbs over 1'-0" to 5'-0"




BARS V (#5)
Spaced at 12" Max



BARS L (#5)
Spaced at 12" Max



OPTIONAL BARS L (#5)
Spaced at 12" Max



BARS U (#4)
Spaced at 12" Max

- ① "T" is equal to the culvert top slab thickness. For precast boxes with slabs less than 8" thick, see SCP-MD standard for additional details.
- ② Adjust normal culvert slab bars as necessary to clear obstructions.
- ③ Place bars L as shown. Tilt hook as necessary to maintain cover.
- ④ Place normal culvert curb bars H(#4) as shown. Adjust as necessary to clear obstructions.
- ⑤ Additional bars H(#4) as required to maintain 12" Max spacing.
- ⑥ Replace normal culvert curb bars K with one bar U and two bars V as shown spaced at 12" Max. Adjust length of bars V as necessary to maintain clear cover.
- ⑦ Optional bars L are to be used only for precast box culverts with 3'-0" closure pour.
- ⑧ Quantities shown are for Contractor's information only. Quantities are per linear foot of curb length. The value in table can be interpolated for intermediate values of curb height, "C". Quantity includes bars K (when applicable).

TABLE OF ESTIMATED CURB QUANTITIES ^⑧		
Curb Height "C"	Conc (CY/LF)	Reinf Steel (Lb/LF)
1'-0"	0.037	10.4
1'-6"	0.056	14.5
2'-0"	0.074	15.6
2'-6"	0.093	18.0
3'-0"	0.111	19.0
3'-6"	0.130	21.3
4'-0"	0.148	22.4
4'-6"	0.167	24.8
5'-0"	0.185	25.9

CONSTRUCTION NOTES:
Adjust reinforcing steel as necessary to provide 1 1/4" cover.
For vehicle safety, top of the curb must not project more than 3" above the finished grade.

MATERIAL NOTES:
Provide Grade 60 reinforcing steel.
Provide galvanized reinforcing steel if required elsewhere in the plans.
Provide Class "C" concrete (f'c = 3,600 psi) minimum for curbs.
Provide bar laps, where required, as follows:
• Uncoated or galvanized ~ #4 = 1'-8" Min

GENERAL NOTES:
Designed according to AASHTO LRFD Bridge Design Specifications.
These extended curb details have sufficient strength to allow for future retrofit of Type T631 or T631LS railing. These details are suitable for use with PR11, PR22 and PR3 type rails. These details are not suitable for the mounting of other rail types. For new construction using T631 or T631LS railing, use the T631-CM standard.
This Curb is considered as part of the Box Culvert for payment.

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bar dimensions shown are out-to-out of bar.



EXTENDED CURB DETAILS
FOR BOX CULVERTS WITH CURBS OVER 1'-0" TO 5'-0" TALL

ECD				
FILE: ecdside1-20.dgn	DN: GAF	CK: TxDOT	DW: TxDOT	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	164	

8/12/2023 4:53:55 PM
 DATE: L:\Amorillo\Dist\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standards\setbs0se-20.dgn
 FILE: L:\Amorillo\Dist\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standards\setbs0se-20.dgn
 No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of drawings to PDF format.

TABLE OF DIMENSIONS AND REINFORCING STEEL
(Wings for One Structure End)

Maximum Wingwall Height Hw (9)	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing length (Two-Wings) (3)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)
2'-6"	2'-5"	1'-0"	9"	7"	#4	1'-0"	#4	1'-0"	33.73	0.248
3'-0"	2'-5"	1'-0"	9"	7"	#4	1'-0"	#4	1'-0"	37.07	0.261
3'-6"	2'-5"	1'-0"	9"	7"	#4	1'-0"	#4	1'-0"	37.74	0.273
4'-0"	2'-5"	1'-0"	9"	7"	#4	1'-0"	#4	1'-0"	38.41	0.285
4'-6"	3'-2"	1'-6"	1'-0"	7"	#4	1'-0"	#4	1'-0"	41.75	0.330
5'-0"	3'-2"	1'-6"	1'-0"	7"	#4	1'-0"	#4	1'-0"	45.09	0.343
5'-6"	3'-2"	1'-6"	1'-0"	7"	#4	1'-0"	#4	1'-0"	45.75	0.355
6'-0"	3'-2"	1'-6"	1'-0"	7"	#4	1'-0"	#4	1'-0"	46.42	0.367
7'-0"	3'-8"	1'-9"	1'-3"	7"	#4	1'-0"	#4	1'-0"	52.77	0.414
8'-0"	4'-2"	2'-0"	1'-6"	8"	#5	1'-0"	#4	1'-0"	60.19	0.486
9'-0"	4'-8"	2'-3"	1'-9"	8"	#4	6"	#4	6"	81.49	0.535
10'-0"	5'-2"	2'-6"	2'-0"	8"	#5	6"	#4	6"	97.25	0.584
11'-0"	5'-8"	2'-9"	2'-3"	8"	#6	6"	#5	6"	133.65	0.634
12'-0"	6'-2"	3'-0"	2'-6"	9"	#7	6"	#5	6"	162.29	0.721

TABLE OF WINGWALL REINFORCING (Two-Wings)

Bar	Size	No.	Spa
D	#5	~	1'-0"
E	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	4	~
M	#4	4	~
P	#4	~	1'-0"
R	#5	6	~
V	#4	~	1'-0"

TABLE OF ESTIMATED CULVERT TOEWALL QUANTITIES

Bar	Size	No.	Spa
L	#4	~	1'-6"
Q	#4	1	~
Reinf (Lb/Ft)	2.45		
Conc (CY/Ft)	0.037		

TABLE OF ESTIMATED ANCHOR TOEWALL QUANTITIES

Bar	Size	No.	Spa
K	#4	~	1'-0"
N	#5	6	~
OL	#4	6	~
Reinf (Lb/Ft)	9.82		
Conc (CY/Ft)	0.074		

- Extend Bars P 3'-0" Min into bottom slab of box culvert.
- Adjust to fit as necessary to maintain 1 1/2" clear cover and 4" Min between bars.
- Quantities shown are based on an average wing height for two wings (one structure end). To determine total quantities for two wings multiply the tabulated values by Lw.
- Recommended values of slope are: 3:1, 4:1, and 6:1. Provide 3:1 or flatter slope.
- When shown elsewhere on the plans, construct 5" deep concrete riprap. Payment for riprap is as required by Item 432, "Riprap". Unless otherwise shown on the plans or directed by the Engineer, extend construction joints or grooved joints, oriented in the direction of flow, across the full distance of the riprap, at intervals of approximately 20'. When such riprap is provided, the culvert toewall shown in SECTION B-B is not required.
- At Contractor's option, end the culvert toewall flush with wingwall toewall. Adjust reinforcing as needed.
- 3" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures without railing and curbs taller than 1'-0", refer to Extended Curb Details (ECD) standard sheet.
- For vehicle safety, reduce curbs height, if necessary, to provide a maximum 3" projection above finished grade. No changes will be made in quantities and no additional compensation will be allowed for this work.
- See Table of Maximum Wing Heights for various slopes. Height is limited based on a 33'-6" maximum safety pipe runner length.


TABLE OF MAXIMUM WING HEIGHTS (9)

Side Slope	Hw Max
3:1	11'-5"
4:1	8'-10"
6:1	6'-1"


WING DIMENSION CALCULATIONS:

$$\begin{aligned}
 Hw &= H + T + C - 0.250' \quad (9) \\
 Lw &= (Hw - 0.333') (SL) \\
 &\text{For cast-in-place culverts:} \\
 Ltw &= (N) (S) + (N + 1) (U) \\
 &\text{For precast culverts:} \\
 Ltw &= (N) (2U + S) + (N - 1) (0.500') \\
 Lc &= (Ltw) - (2U) \\
 Atw &= Lc \\
 \text{Total Wingwall Area (two wings ~ SF)} &= (Hw + 0.333') (Lw)
 \end{aligned}$$


Hw = Height of wingwall (feet)
 SL:1 = Side slope ratio (horizontal : 1 vertical)
 Lw = Length of wingwall (feet)
 Ltw = Culvert toewall length (feet)
 Lc = Culvert curb between wings (feet)
 Atw = Anchor toewall length (feet)
 N = Number of culvert spans
 See applicable box culvert standard for H, S, T, and U values. See Table of Maximum Wall Heights for limits on Hw.




BARS J1 BARS V




BARS L and OL BARS J2




BARS R



BARS D




BARS K
(Length = 5'-6")




INSIDE ELEVATION OF WINGWALL

(Showing reinforcing. Culvert and culvert toewall reinforcing not shown for clarity.)




PLAN


(Showing dimensions.)




SECTION A-A




WINGWALL



FOOTING AND TOEWALL



SECTION B-B (5)








SECTION C-C

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.

		Bridge Division Standard	
SAFETY END TREATMENT WITH STRAIGHT WINGS FOR 0° SKEW BOX CULVERTS TYPE I ~ CROSS DRAINAGE			
SETB-SW-0			
FILE: setbs0se-20.dgn	DN: GAF	CK: CAT	DW: TxDOT
REVISIONS	CONTRACT	SECTION	JOB
	0455	02	031, ETC
	DIST	COUNTY	SHEET NO.
	AMA	CARSON	165

8/12/2023 4:53:56 PM
 L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standards\setbs0se-20.dgn
 DATE: 8/12/2023 4:53:56 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\TXDOT Standards\setbs0se-20.dgn



MAXIMUM PIPE RUNNER LENGTHS AND REQUIRED PIPE RUNNER AND ANCHOR PIPE SIZES

Maximum Pipe Runner Length (Pc)	Required Pipe Runner Size			Required Anchor Pipe Size		
	Pipe Size	Pipe O.D.	Pipe I.D.	Pipe Size	Pipe O.D.	Pipe I.D.
9'-4"	3" STD	3.500"	3.068"	2" STD	2.375"	2.067"
19'-0"	4" STD	4.500"	4.026"	3" STD	3.500"	3.068"
33'-6"	5" STD	5.563"	5.047"	4" STD	4.500"	4.026"

- (10) After installation of pipe runner, use the 1/2" inspection hole to ensure that the lap of the anchor pipe with the pipe runner is adequate.
- (11) At Contractor's option, an adhesive anchor may be used. Provide 3/4" Dia adhesive anchors that meet the requirements of ASTM A307. Gr A fully threaded rods. Embed threaded rods into curb, wingwalls, and toewall using a Type III, Class C, D, E, or F anchor adhesive. Minimum embedment depth is 5 1/2". Provide anchor adhesive able to achieve a basic bond strength in tension, Nba, of 20 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use.

PIPE RUNNER DIMENSION CALCULATIONS:

$$Pc = (Lw) (K) - (1.688)$$

Pc = Pipe runner length (feet)

K = Constant values for use in formulas

Slope SL:1 K

3:1 ~ 1.054

4:1 ~ 1.031

6:1 ~ 1.014

SHEET 2 OF 3

Texas Department of Transportation

Bridge Division Standard

SAFETY END TREATMENT WITH STRAIGHT WINGS
 FOR 0° SKEW BOX CULVERTS
 TYPE I ~ CROSS DRAINAGE


SETB-SW-O

FILE: setbs0se-20.dgn	DN: GAF	CK: CAT	DW: TXDOT	CK: TXDOT
©TXDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	166	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from a digital file to a printed format. Incorrect results or damages resulting from its use.

DATE: 8/12/2023 4:53:57 PM
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\07 Drainage Detail\setb0se-20.dgn

Culvert Station and/or Creek name followed by applicable end (Lt, Rt or Both) ⁽¹²⁾	Lc (Ft)	L2			Pipe Runner (Pc)				3'-0" Anchor Pipe	
		No. Spa	Spa at (Ft)	Overall Length (Ft)	No.	Length (Ft)	Size (3", 4" or 5")	Total Length ⁽¹²⁾ (Ft)	Size (2", 3" or 4")	Total ⁽¹²⁾ Length (Ft)
CULVERT 1 (Lt)	6.000	3	2.000	6.000	2	10.000	4"	20.000	3"	6.000
CULVERT 1 (Rt)	6.000	3	2.000	6.000	2	10.000	4"	20.000	3"	6.000
CULVERT 2 (Rt)	16.167	7	2.310	16.167	6	16.188	4"	97.125	3"	18.000
CULVERT 4 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 4 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 6 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 7 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 9 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 10 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 11 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 11 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 15 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 16 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 20 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 20 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 21 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 21 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 22 (Lt)	7.000	3	2.333	7.000	2	29.333	5"	58.667	4"	6.000
CULVERT 23 (Lt)	6.000	3	2.000	6.000	2	18.250	4"	36.500	3"	6.000
CULVERT 23 (Rt)	6.000	3	2.000	6.000	2	16.438	4"	32.875	3"	6.000
CULVERT 24 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 26 (Lt)	5.000	2	2.500	5.000	1	19.646	5"	19.646	4"	3.000
CULVERT 27 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 27 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 28 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 29 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 31 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 31 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 32 (Lt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG
CULVERT 32 (Rt)	3.000	2	1.500	3.000	NG	NG	NG	NG	NG	NG



PIPE RUNNER LAYOUT

⁽¹²⁾ Quantities shown are for one structure end if Lt or Rt. Quantities shown are for two structure ends if Both.

SPECIAL NOTE:

This tabular sheet is to be filled out by the culvert specifier and provides information for the construction details and quantities of pipe runners.



An Excel 2010 spreadsheet to assist in completing this table can be downloaded from the Bridge Standards (English) web page on the TxDOT web site. The completed sheet must be signed, sealed, and dated by a licensed Professional Engineer.

Note that the tabular quantities are given for estimating purposes only. It is likely that these quantities will change due to field conditions. Therefore, all dimensions must be verified by the Contractor in the field prior to fabrication of the safety end treatment components.

SHEET 3 OF 3

				Bridge Division Standard	
SAFETY END TREATMENT WITH STRAIGHT WINGS FOR 0° SKEW BOX CULVERTS TYPE I ~ CROSS DRAINAGE					
SETB-SW-O					
FILE: setb0se-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
CTxDOT	February 2020	CONT SECT	JOB	HIGHWAY	
REVISIONS		0455 02	031, ETC	SH 152	
DIST	COUNTY	SHEET NO.			
AMA	CARSON	167			

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Project Execution\03.04 Design\DRAWING DATE: 7/24/2023




LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (W) (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- Ⓢ SIGN NUMBER


- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



LOCATION	0644 6004	0644 6007	0644 6076	0658 6060	0658 6081	0658 6099	6024 6011	6024 6020	6024 6023	6362 6004
	IN SM RD SN SUP&AM TY 10BWG(1)SA (T)	IN SM RD SN SUP&AM TY 10BWG(1)SA (U)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA
SHEET 1 OF 30	1	1	2	4	6	2	4,135	367	3,203	85





© 2023
 Texas Department of Transportation
RS&H
 RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 BEGIN PROJECT TO STA 993+00
 STA 993+00 TO STA 1005+00

SHEET 1 OF 30


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	168
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.00 Project Execution\03.04 Design\...
 DRAWING DATE: 7/24/2023




- ### LEGEND
- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [R] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0644	0658	0658	0658	6024	6024	6024	6362
	6007	6060	6081	6099	6011	6020	6023	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (U)	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA
SHEET 2 OF 30	1	2	2	2	4,800	600	1,073	44



MATCH LINE STA 1029+00

© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1005+00 TO STA 1017+00
 STA 1017+00 TO STA 1029+00

SHEET 2 OF 30



FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

169

FILENAME: P:\TxDOT\10124272\ISE\TxDOT\10124272\10124272001\TxDOT\SH152*Super*2*Carson\County\03.04 Design\ PROJECT: Execution\03.04 Design\ DRAWING DATE: 7/24/2023




LOCATION	0644	0658	0666	0666	0666	6024	6024	6024	6024	6362	6362
	6076	6082	6017	6047	6071	6008	6011	6020	6023	6002	6004
	REMOVE SM RD SN SUP&AM	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BR)	REFL PAV MRK TY I (W)6"(DOT)(090 MIL)	REFL PAV MRK TY I (W)24"(SLD)(090 MIL)	REFL PAV MRK TY I(W)(LNDP ARW)(090MIL)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	LF	LF	EA	LF	LF	LF	LF	EA	EA
SHEET 3 OF 30	1	10	253	22	2	75	4,800	50	4,600	4	115



LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [#] SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
 ⇩ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401



**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**

STA 1029+00 TO STA 1041+00
 STA 1041+00 TO STA 1053+00

SHEET 3 OF 30


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	170
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*Svcs\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\DRAWING DATE: 7/24/2023



- ### LEGEND
- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [#] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

LOCATION	0644 6004	0644 6076	0658 6060	0658 6099	6024 6008	6024 6011	6024 6023	6362 6002	6362 6004
	IN SM RD SN SUP&AM TY 10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 4 OF 30	2	1	2	2	600	4,800	4,800	30	120



Bruce W. Pate
JULY 27, 2023

© 2023

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
SIGNING AND
PAVEMENT MARKINGS**
 STA 1053+00 TO STA 1065+00
 STA 1065+00 TO STA 1077+00

SHEET 4 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	171
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*Svcs\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023

MATCH LINE STA 1077+00



MATCH LINE STA 1089+00


LOCATION	0644 6001	0644 6076	0658 6081	6024 6008	6024 6011	6024 6023	6362 6002	6362 6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	REMOVE SM RD SN SUP&AM	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 5 OF 30	2	3	3	600	4,800	4,800	30	120

- LEGEND**
- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - F REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - G REFL PAV MRKR TY I-C
 - H REF PAV MRKR TY II-A-A
 - I DIRECTIONAL DELINEATOR
 - J BIDIRECTIONAL DELINEATOR
 - K OBJECT MARKER
 - L REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - R SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



MATCH LINE STA 1089+00



MATCH LINE STA 1101+00


© 2023
 Texas Department of Transportation
RS&H Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1077+00 TO STA 1089+00
 STA 1089+00 TO STA 1101+00
 SHEET 5 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

DRAWING DATE: 7/24/2023 FILENAME: P:\TXDOT\10124272\ISE\TXDOT\3691DP5089\PS\F\SVCS\10124272001\TXDOT\SH\152\Super\2\Carson\County\03.04 Design\

MATCH LINE STA 1101+00




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- ⊕ SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.


2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0658 6060	0658 6081	0658 6099	0658 6103	0658 6106	6024 6008	6024 6011	6024 6023	6362 6002	6362 6004
	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	INSTL OM ASSM (OM-3L)(WFLX)GND	INSTL OM ASSM (OM-3R)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 6 OF 30	1	17	1	1	1	350	4,800	4,800	18	120

MATCH LINE STA 1113+00



MATCH LINE STA 1125+00

© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401



**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1101+00 TO STA 1113+00
 STA 1113+00 TO STA 1125+00

SHEET 6 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

173

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.00 Project Execution\03.04 Design\...
 DRAWING DATE: 7/24/2023



LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - ⊕ SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
 ⇨ PROPOSED TRAFFIC FLOW ARROW


NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0658 6060	0658 6099	6024 6008	6024 6011	6024 6023	6362 6002	6362 6004
	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	LF	LF	LF	EA	EA
SHEET 7 OF 30	2	2	436	4,800	4,800	22	120



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401



**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1125+00 TO STA 1137+00
 STA 1137+00 TO STA 1149+00

SHEET 7 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	174
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH152*Super*2*Carson*County\03.00 Project Execution\03.04 Design\DRAWING DATE: 7/24/2023

MATCH LINE STA 1149+00




LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (W) (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- ⊕ SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:


1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
JULY 27, 2023

LOCATION	0644	0644	0658	0658	6024	6024	6024	6362	6362
	6001	6076	6081	6106	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	REMOVE SM RD SN SUP&AM	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-3R)(WFLX)GND GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 8 OF 30	1	1	2	1	600	4,800	4,800	30	120

MATCH LINE STA 1161+00



© 2023
Texas Department of Transportation



RS&H, Inc.
3200 Southwest Freeway, Suite 3150
Houston, Texas 77027
713-914-4455 FAX 713-914-0155
Texas Registration No. F-3401

**SH 152
SIGNING AND
PAVEMENT MARKINGS**
STA 1149+00 TO STA 1161+00
STA 1161+00 TO STA 1173+00

SHEET 8 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	175
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272\ISE\TXDOT\3691DP5089*PS*E\Svcs\10124272001\10124272001*SH*152*Super*2*Carson*County\03.04 Design\




LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (W) (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- # SIGN NUMBER
- ⇌ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.

LOCATION	0644	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6001	6076	6060	6081	6103	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-3L)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 9 OF 30	1	3	8	14	1	600	4,800	4,800	30	120



STATE OF TEXAS
 BRUCE W. PATE
 98343
 LICENSED PROFESSIONAL ENGINEER
 Bruce W. Pate
 JULY 27, 2023


© 2023
 Texas Department of Transportation
RS&H
 RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152
SIGNING AND PAVEMENT MARKINGS
 STA 1173+00 TO STA 1185+00
 STA 1185+00 TO STA 1197+00
 SHEET 9 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

DRAWING DATE: 7/24/2023

FILENAME: P:\TxDOT\10124272*ISE*TxDOT*SH152*Super*2*Carson*County\03.04 Project Execution\03.04 Design\ DRAWING DATE: 7/24/2023





LEGEND


- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [#] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



LOCATION	0644 6001	0644 6076	0658 6060	0658 6099	6024 6008	6024 6011	6024 6023	6362 6002	6362 6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (OM-2Z)(WFL)(GND)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 10 OF 30	1	1	2	2	600	4,800	4,800	30	120



© 2023
 Texas Department of Transportation
RS&H Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401



**SH 152
SIGNING AND
PAVEMENT MARKINGS**

STA 1197+00 TO STA 1209+00
STA 1209+00 TO STA 1221+00

SHEET 10 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	177
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TxDOT\10124272*ISE*TxDOT\3691DP5089*PS*E*SVCS\10124272001*TxDOT*SH*152*Super*2*Carson*County\03_04_Design\...
 DRAWING DATE: 7/24/2023




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDRP ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



LOCATION	0644	0644	0644	0644	0644	0658	0658	0658	0666	6024	6024	6024	6362	6362
	6001	6004	6007	6037	6076	6060	6081	6099	6047	6008	6011	6023	6002	6004
	IN SM RD SN SUP&M TY 10BWG(1)SA (P)	IN SM RD SN SUP&M TY 10BWG(1)SA (T)	IN SM RD SN SUP&M TY 10BWG(1)SA (U)	IN SM RD SN SUP&M TYS80(1)SA(U-WC)	REMOVE SM RD SN SUP&M	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)24"(SLD)(090 MIL)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	EA	EA
SHEET 11 OF 30	3	6	2	1	9	9	8	3	35	600	5,228	5,056	30	111



© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1221+00 TO STA 1233+00
 STA 1233+00 TO STA 1245+00

SHEET 11 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


178

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023



MATCH LINE STA 1245+00

MATCH LINE STA 1257+00




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [#] SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
 ⇨ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.

LOCATION	0644	0644	0644	0658	0658	0658	0658	0666	0666	6024	6024	6024	6362	6362
	6001	6004	6076	6060	6081	6082	6099	6017	6071	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BR)	INSTL OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)6"(DOT)(090 MIL)	REFL PAV MRK TY I(W)(LNDP ARW)(090MIL)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	EA	LF	LF	LF	EA	EA
SHEET 12 OF 30	2	2	2	10	8	10	2	250	2	75	4,800	4,800	4	120



MATCH LINE STA 1257+00

MATCH LINE STA 1269+00

Bruce W. Pate
 JULY 27, 2023

© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152
 SIGNING AND
 PAVEMENT MARKINGS
 STA 1245+00 TO STA 1257+00
 STA 1257+00 TO STA 1269+00

SHEET 12 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

179

FILENAME: P:\TxDOT\10124272\ISE\TxDOT\SH152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [⊕] SIGN NUMBER

- ↔ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1269+00 TO STA 1281+00
 STA 1281+00 TO STA 1293+00

SHEET 13 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	180
CONTROL	SECTION	JOB	
0455	02	031, ETC	

MATCH LINE STA 1269+00


MATCH LINE STA 1281+00



LOCATION	0644	0658	0658	6024	6024	6024	6362
	6007	6060	6099	6011	6020	6023	6004
	IN SM RD SN SUP&AM TY 10BWG(1)SA (U)	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	LF	LF	LF	EA
SHEET 13 OF 30	1	4	4	4,800	388	2,950	77

MATCH LINE STA 1281+00

MATCH LINE STA 1293+00





FILENAME: P:\TXDOT\10124272*ISE*TXDOT*369\DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\1
 DRAWING DATE: 7/24/2023

MATCH LINE STA 1293+00

MATCH LINE STA 1305+00

MATCH LINE STA 1305+00

MATCH LINE STA 1317+00



LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [S] SIGN NUMBER


- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0644 6001	0644 6004	0644 6007	0644 6076	0658 6060	0658 6093	0658 6099	0666 6017	0666 6029	0666 6035	0666 6053	0666 6071	0666 6077	6024 6011	6024 6020	6024 6023	6362 6002	6362 6004
	IN SM RD SN SUP&AM TY 10BWG(1)SA (P)	IN SM RD SN SUP&AM TY 10BWG(1)SA (T)	IN SM RD SN SUP&AM TY 10BWG(1)SA (U)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-DW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)6"(DOT)(090 MIL)	REFL PAV MRK TY I (W)8"(DOT)(090 MIL)	REFL PAV MRK TY I (W)8"(SLD)(090 MIL)	REFL PAV MRK TY I (W)(ARROW)(090 MIL)	REFL PAV MRK TY I (W)(LNDR ARW)(090MIL)	REFL PAV MRK TY I (W)(WORD)(090 MIL)	HPPM W/RET REQ TY I (W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I (Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I (Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 14 OF 30	1	1	1	3	3	12	4	292	38	651	1	1	1	4,800	213	4,964	62	259





© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152
SIGNING AND
PAVEMENT MARKINGS
 STA 1293+00 TO STA 1305+00
 STA 1305+00 TO STA 1317+00

SHEET 14 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	181
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\1
 DRAWING DATE: 7/24/2023



LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (W) (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- R SIGN NUMBER

- EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW


NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0644 6001	0644 6004	0644 6007	0644 6076	0658 6060	0658 6093	0658 6099	0666 6029	0666 6035	0666 6047	0666 6053	0666 6071	0666 6077	6024 6011	6024 6023	6362 6002	6362 6004
	IN SM RD SN SUP&AM TY 10BWG(1)SA (P)	IN SM RD SN SUP&AM TY 10BWG(1)SA (T)	IN SM RD SN SUP&AM TY 10BWG(1)SA (U)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-W)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM- 2Z)(WFLX)GND	REFL PAV MRK TY I (W)8"(SLD)(090 MIL)	REFL PAV MRK TY I (W)8"(SLD)(090 MIL)	REFL PAV MRK TY I (W)24"(SLD)(090 MIL)	REFL PAV MRK TY I (W)(ARROW)(090 MIL)	REFL PAV MRK TY I(W)(LNDR ARW)(090MIL)	REFL PAV MRK TY I (W)(WORD)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA	EA	LF	LF	EA	EA
SHEET 15 OF 30	2	4	2	8	3	3	4	104	2,332	14	5	1	5	4,549	6,596	139	347



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401



**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1317+00 TO STA 1329+00
 STA 1329+00 TO STA 1341+00

SHEET 15 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.04 Project Execution\03.04 Design\...
 DRAWING DATE: 7/24/2023

MATCH LINE STA 1341+00




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW


NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0658	0658	6024	6024	6024	6362
	6060	6099	6011	6020	6023	6004
	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY II-A-A
	EA	EA	LF	LF	LF	EA
SHEET 16 OF 30	4	4	4,800	300	6,000	270

MATCH LINE STA 1353+00



© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1341+00 TO STA 1353+00
 STA 1353+00 TO STA 1365+00

SHEET 16 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC



LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (W) (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- + SIGN NUMBER

- ↔ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
SIGNING AND
PAVEMENT MARKINGS**


STA 1365+00 TO STA 1377+00
 STA 1377+00 TO STA 1389+00

SHEET 17 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		184

MATCH LINE STA 1365+00


MATCH LINE STA 1377+00




LOCATION	0644	0644	0644	0658	0658	0658	0658	0666	0666	6024	6024	6024	6362	6362
	6001	6004	6076	6060	6081	6093	6099	6017	6071	6011	6020	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR DEL ASSM (D-DW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)6"(DOT)(090 MIL)	REFL PAV MRK TY I(W)(LNDP ARW)(090MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	EA	LF	LF	LF	EA	EA
SHEET 17 OF 30	1	1	2	4	6	15	1	375	1	4,800	325	3,500	32	88

MATCH LINE STA 1377+00

MATCH LINE STA 1389+00



FILENAME: P:\TXDOT\10124272*ISE*TxDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023



LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- ⊕ SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0644	0644	0644	0644	0644	0658	0658	0658	0658
	6001	6004	6007	6037	6076	6060	6081	6093	6099
	IN SM RD SN SUP&M TY10BWG(1)SA (P)	IN SM RD SN SUP&M TY10BWG(1)SA (T)	IN SM RD SN SUP&M TY10BWG(1)SA (U)	IN SM RD SN SUP&M TYS80(1)SA(U-WC)	REMOVE SM RD SN SUP&M	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL DEL ASSM (D-DW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM) 2Z(WFLX)GND
	EA	EA	EA	EA	EA	EA	EA	EA	EA
SHEET 18 OF 30	6	8	5	3	19	6	7	7	6

LOCATION	0666	0666	0666	0666	0666	0666	0666	0666	6024	6024	6362	6362
	6017	6029	6035	6047	6053	6071	6077	6011	6023	6002	6004	
	REFL PAV MRK TY I (W)6"(DOT)(090 MIL)	REFL PAV MRK TY I (W)8"(DOT)(090 MIL)	REFL PAV MRK TY I (W)8"(SLD)(090 MIL)	REFL PAV MRK TY I (W)24"(SLD)(090 MIL)	REFL PAV MRK TY I (W)(ARROW)(090 MIL)	REFL PAV MRK TY I (W)(LNDR ARW)(090MIL)	REFL PAV MRK TY I (W)(WORD)(090 MIL)	HPPM W/RET REQ TY I (W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I (Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A	
	LF	LF	LF	LF	EA	EA	EA	LF	LF	EA	EA	
SHEET 18 OF 30	100	39	1,601	38	4	1	4	5,652	5,304	91	103	


© 2023
 Texas Department of Transportation
RS&H
 RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1389+00 TO STA 1401+00
 STA 1401+00 TO STA 1413+00

SHEET 18 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		185

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023




- LEGEND**
- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - F REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
 - G REF PAV MRKR TY I-C
 - H REF PAV MRKR TY II-A-A
 - I DIRECTIONAL DELINEATOR
 - J BIDIRECTIONAL DELINEATOR
 - K OBJECT MARKER
 - L REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - R SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

NOTE:

- ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
- PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



LOCATION	0644	0644	0644	0644	0658	0658	0658	0666	0666	6024	6024	6024	6362	6362
	6001	6004	6007	6076	6060	6081	6099	6017	6071	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA A(P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	IN SM RD SN SUP&AM TY10BWG(1)SA (U)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)(DOT)(090 MIL)	REFL PAV MRK TY I(W)(LNDR ARW)(090MIL)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	EA	LF	LF	LF	EA	EA
SHEET 19 OF 30	1	1	1	2	7	8	4	254	2	147	4,800	4,800	8	120



© 2023 Texas Department of Transportation


RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1413+00 TO STA 1425+00
 STA 1425+00 TO STA 1437+00


SHEET 19 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	186
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.00 Project Execution\03.04 Design\...
 DRAWING DATE: 7/24/2023



LOCATION	0644	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6004	6076	6060	6081	6099	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 20 OF 30	2	3	3	1	3	600	4,800	4,800	30	120



LOCATION	0644	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6004	6076	6060	6081	6099	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 20 OF 30	2	3	3	1	3	600	4,800	4,800	30	120




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1437+00 TO STA 1449+00
 STA 1449+00 TO STA 1461+00

SHEET 20 OF 30


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	187
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272\ISE\TXDOT\3691DP5089\PS\F\SVCS\10124272001\TXDOT\SH\152*Super*2*Carson*County\03.04 Design\

DRAWING DATE: 7/24/2023



MATCH LINE STA 1461+00



MATCH LINE STA 1473+00

LEGEND


- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (W) (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- ⊕ SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.




LOCATION	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6076	6060	6081	6099	6008	6011	6023	6002	6004
	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 21 OF 30	1	3	2	2	600	4,800	4,800	30	120

MATCH LINE STA 1473+00



MATCH LINE STA 1485+00



Bruce W. Pate
 JULY 27, 2023



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1461+00 TO STA 1473+00
 STA 1473+00 TO STA 1485+00

SHEET 21 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	188
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [S] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 → PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.

LOCATION	0644	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6004	6076	6060	6081	6099	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	IN STL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	IN STL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 22 OF 30	2	1	9	9	1	325	4,000	4,000	17	100



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**

STA 1485+00 TO STA 1495+00
 STA 1495+00 TO STA 1505+00

SHEET 22 OF 30


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.	
6		SH 152	
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	189
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023



- LEGEND**
- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [R] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

LOCATION	0644	0644	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6001	6004	6076	6060	6081	6099	6008	6011	6023	6002	6004
	IN SM RD SN SUP&M TY10BWG(1)SA (P)	IN SM RD SN SUP&M TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&M	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 23 OF 30	1	1	1	11	9	2	419	4,400	5,324	21	133



Bruce W. Pate
 LICENSED PROFESSIONAL ENGINEER
 JULY 27, 2023


RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152
SIGNING AND PAVEMENT MARKINGS
 STA 1505+00 TO STA 1514+00
 STA 1514+00 TO STA 1527+00

SHEET 23 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	190
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: P:\TXDOT\10124272*ISE*TXDOT\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023



LEGEND


- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [S] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

LOCATION	0644	0644	0644	0644	0644	0658	0658	0666	0666	0666	0666	0666	0624	0624	0624	6362	6362
	6001	6004	6007	6037	6076	6060	6099	6029	6035	6053	6077	6008	6011	6023	6002	6004	
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	IN SM RD SN SUP&AM TY10BWG(1)SA (U)	IN SM RD SN SUP&AM TYS80(1)SA(U-WC)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)8"(DOT)(090 MIL)	REFL PAV MRK TY I (W)8"(SLD)(090 MIL)	REFL PAV MRK TY I (W)(ARROW)(090 MIL)	REFL PAV MRK TY I (W)(WORD)(090 MIL)	HPPM W/RET REQ TY I (W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I (W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I (Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A	
	EA	EA	EA	EA	EA	EA	EA	LF	LF	EA	EA	LF	LF	LF	EA	EA	
SHEET 24 OF 30	5	3	1	1	9	2	2	37	887	2	2	600	5,237	7,952	80	364	



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152
SIGNING AND PAVEMENT MARKINGS
 STA 1527+00 TO STA 1539+00
 STA 1539+00 TO STA 1551+00

SHEET 24 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC


FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\ PROJECT EXECUTION\03.04 Design\ DRAWING DATE: 7/24/2023

MATCH LINE STA 1551+00

MATCH LINE STA 1563+00

MATCH LINE STA 1563+00

MATCH LINE STA 1575+00




LOCATION	0644	0658	0658	0658	6024	6024	6024	6362	6362
	6076	6060	6081	6099	6008	6011	6023	6002	6004
	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTL OM ASSM (OM-2Z)(WFLX)GND	HPPM W/RET REQ TY (W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY (W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY (Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 25 OF 30	1	9	8	3	600	4,800	4,800	30	120

- LEGEND**
- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
 - [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
 - [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
 - [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
 - [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
 - [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
 - [G] REF PAV MRKR TY I-C
 - [H] REF PAV MRKR TY II-A-A
 - [I] DIRECTIONAL DELINEATOR
 - [J] BIDIRECTIONAL DELINEATOR
 - [K] OBJECT MARKER
 - [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
 - [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
 - [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
 - [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
 - [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
 - [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
 - [#] SIGN NUMBER
- EXISTING TRAFFIC FLOW ARROW
 PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.

Bruce W. Pate
 JULY 27, 2023



© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**

STA 1551+00 TO STA 1563+00
 STA 1563+00 TO STA 1575+00

SHEET 25 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	192
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\ DRAWING DATE: 7/24/2023




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDRP ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER
- ⇨ EXISTING TRAFFIC FLOW ARROW
- ⇩ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023



LOCATION	0644	0658	0658	6024	6024	6024	6362	6362
	6076	6060	6081	6008	6011	6023	6002	6004
	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	LF	LF	LF	EA	EA
SHEET 26 OF 30	1	3	7	300	2,400	2,400	15	60

© 2023
 Texas Department of Transportation
RS&H RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS
 STA 1575+00 TO STA 1587+00**


SHEET 26 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	193
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023

MATCH LINE STA 1587+00


MATCH LINE STA 1599+00




LOCATION	0644	0644	0644	0644	0658	0658	0658	0666	6024	6024	6024	6362	6362
	6001	6004	6007	6076	6060	6081	6099	6047	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	IN SM RD SN SUP&AM TY10BWG(1)SA (U)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)24\"(SLD)(090 MIL)	HPPM W/RET REQ TY I (W)6\"(BRK)(090 MIL)	HPPM W/RET REQ TY I (W)6\"(SLD)(090 MIL)	HPPM W/RET REQ TY I (Y)6\"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	EA	EA
SHEET 27 OF 30	2	4	1	4	2	3	2	16	600	4,648	4,616	30	116

MATCH LINE STA 1599+00

MATCH LINE STA 1611+00



LOCATION	0644	0644	0644	0644	0658	0658	0658	0666	6024	6024	6024	6362	6362
	6001	6004	6007	6076	6060	6081	6099	6047	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	IN SM RD SN SUP&AM TY10BWG(1)SA (U)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSTR DEL ASSM (D-SW)SZ 1(WFLX)GND(BI)	INSTR OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)24\"(SLD)(090 MIL)	HPPM W/RET REQ TY I (W)6\"(BRK)(090 MIL)	HPPM W/RET REQ TY I (W)6\"(SLD)(090 MIL)	HPPM W/RET REQ TY I (Y)6\"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	EA	EA
SHEET 27 OF 30	2	4	1	4	2	3	2	16	600	4,648	4,616	30	116



LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.
 2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



© 2023 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152
SIGNING AND PAVEMENT MARKINGS
 STA 1587+00 TO STA 1599+00
 STA 1599+00 TO STA 1611+00


SHEET 27 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

194

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*369\DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Project Execution\03.04 Design\

DRAWING DATE: 7/24/2023



LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDR ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.




© 2023
 Texas Department of Transportation
RS&H
 RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1611+00 TO STA 1623+00
 STA 1623+00 TO STA 1635+00

FED. RD. DIV. NO.		FEDERAL AID PROJECT NO.		HIGHWAY NO.
6				SH 152
STATE	DISTRICT	COUNTY		SHEET NO.
TEXAS	AMA	CARSON		195
CONTROL	SECTION	JOB		
0455	02	031, ETC		

MATCH LINE STA 1611+00


MATCH LINE STA 1623+00



LOCATION	0644	0644	0658	0658	0658	0666	0666	6024	6024	6024	6362	6362
	6001	6076	6060	6082	6099	6017	6071	6008	6011	6023	6002	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	REMOVE SM RD SN SUP&AM	REMOVE DELIN & OBJECT MARKER ASSMS	INSL DEL ASSM (D-SW)SZ 1(WFLX)GND(BR)	INSL OM ASSM (OM-2Z)(WFLX)GND	REFL PAV MRK TY I (W)6"(DOT)(090 MIL)	REFL PAV MRK TY I(W)(LNDR ARW)(090MIL)	HPPM W/RET REQ TY I(W)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY I-C	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	EA	LF	EA	LF	LF	LF	EA	EA
SHEET 28 OF 30	1	1	1	6	1	441	2	35	4,800	4,800	2	120

MATCH LINE STA 1623+00


MATCH LINE STA 1635+00



FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\...
 DRAWING DATE: 7/24/2023


MATCH LINE STA 1635+00

MATCH LINE STA 1647+00



MATCH LINE STA 1647+00

LOCATION	0644	0644	0644	0658	6024	6024	6024	6362
	6001	6004	6076	6082	6011	6020	6023	6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (P)	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	REMOVE SM RD SN SUP&AM	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND(BR)	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(SLD)(090 MIL)	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	EA	LF	LF	LF	EA
SHEET 29 OF 30	2	2	4	4	4,800	500	800	45



LEGEND

- A HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- B HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- C REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- D HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- E HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- F REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- G REF PAV MRKR TY I-C
- H REF PAV MRKR TY II-A-A
- I DIRECTIONAL DELINEATOR
- J BIDIRECTIONAL DELINEATOR
- K OBJECT MARKER
- L REFL PAV MRK TY I (WORD) (90 MIL)
- M REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- N REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- O REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- P PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- Q REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- R SIGN NUMBER

- EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

© 2023
 Texas Department of Transportation
RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401


**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1635+00 TO STA 1647+00
 STA 1647+00 TO STA 1659+00

SHEET 29 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	196
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County\03.04 Design\03.04 Execution\03.04 Design\

DRAWING DATE: 7/24/2023




LEGEND

- [A] HPPM W/RET REQ TY I (W) 6" (BRK) (090 MIL)
- [B] HPPM W/RET REQ TY I (W) 6" (SLD) (090 MIL)
- [C] REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)
- [D] HPPM W/RET REQ TY I (Y) 6" (BRK) (090 MIL)
- [E] HPPM W/RET REQ TY I (Y) 6" (SLD) (090 MIL)
- [F] REFL PAV MRK TY I (W) (LNDP ARW) (090 MIL)
- [G] REF PAV MRKR TY I-C
- [H] REF PAV MRKR TY II-A-A
- [I] DIRECTIONAL DELINEATOR
- [J] BIDIRECTIONAL DELINEATOR
- [K] OBJECT MARKER
- [L] REFL PAV MRK TY I (W) (WORD) (90 MIL)
- [M] REFL PAV MRK TY I (W) 6" (DOT) (090 MIL)
- [N] REFL PAV MRK TY I (W) 8" (DOT) (090 MIL)
- [O] REFL PAV MRK TY I (W) 8" (SLD) (090 MIL)
- [P] PREFAB PAV MRK TY B(W) (36") (YLD TRI)
- [Q] REFL PAV MRK TY I (W) (ARROW) (090 MIL)
- [#] SIGN NUMBER

- ⇨ EXISTING TRAFFIC FLOW ARROW
- ➔ PROPOSED TRAFFIC FLOW ARROW

NOTE:
 1. ALL SIGNS TO REMAIN IN PLACE FROM STA 1112+00 TO STA 1140+00 AND STA 1493+00 TO STA 1513+00.

2. PROP CENTERLINE AND EDGE LINE ALONG SIDESTREETS EXTEND 300 LF FROM STOP BAR.



Bruce W. Pate
 JULY 27, 2023

© 2023
Texas Department of Transportation


RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

**SH 152
 SIGNING AND
 PAVEMENT MARKINGS**
 STA 1659+00 TO STA 1671+00
 STA 1671+00 TO END PROJECT


SHEET 30 OF 30

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6		SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC

SHEET NO. 197



LOCATION	0644 6004	0644 6036	0644 6076	6024 6011	6024 6020	6362 6004
	IN SM RD SN SUP&AM TY10BWG(1)SA (T)	IN SM RD SN SUP&AM TYS80(1)SA(U- BM)	REMOVE SM RD SN SUP&AM	HPPM W/RET REQ TY I(W)6"(SLD)(090 MIL)	HPPM W/RET REQ TY I(Y)6"(BRK)(090 MIL)	REC REFL PAV MRKR TY II-A-A
	EA	EA	EA	LF	LF	EA
SHEET 30 OF 30	1	1	2	3,294	412	21



SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	P = "Plain" T = "T" U = "U"	BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels	TY = TYPE TY N TY S
01/30	1	W6-1		36 X 36	A		10BWG	1	SA	T		
	2	D15-11T		54 X 48	A		10BWG	1	SA	U		
2/30	1	D15-10T		54 X 42	A		10BWG	1	SA	U		
04/30	1	W9-2L		36 X 36	A		10BWG	1	SA	T		
	2	W9-1R		36 X 36	A		10BWG	1	SA	T		
05/30	1	M1-6T D10-7aT		24 X 24 3 X 10 (BACK TO BACK)	A		10BWG	1	SA	P		
	2	R4-1		24 X 30	A		10BWG	1	SA	P		
08/30	1	R4-1		24 X 30	A		10BWG	1	SA	P		
09/30	1	M1-6T D10-7aT		24 X 24 3 X 10 (BACK TO BACK)	A		10BWG	1	SA	P		
10/30	1	M2-1 M1-6F		21 X 15 24 X 24	A		10BWG	1	SA	P		
11/30	1	D15-10T		54 X 42	A		10BWG	1	SA	U		
	2	R2-1		30 X 36	A		10BWG	1	SA	T		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS
























SOSS 1 OF 9

FILE: SLMS16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
4-16	DIST	COUNTY	SHEET NO.	
8-16	AMA	CARSON	198	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext
11/30	3	W2-2		36 X 36	A		10BWG	1	SA	T		
	4	M3-4 M1-6T	 	24 X 12 24 X 24	A		10BWG	1	SA	P		
	5	M3-1 M1-6F M6-1R	  	24 X 12 24 X 24 21 X 15	A		10BWG	1	SA	P		
	6	W2-2		36 X 36	A		10BWG	1	SA	T		
	7	R1-1 W4-4P	 	36 X 36 24 X 12	A		10BWG	1	SA	T		
	8	M3-1 M1-6F M6-1L	  	24 X 12 24 X 24 21 X 15	A		10BWG	1	SA	P		
	9	M3-2 M1-6T M6-1L M3-4 M1-6T M6-1R	     	24 X 12 24 X 24 21 X 15 24 X 12 24 X 24 21 X 15	A		10BWG	1	SA	U		
	10	W1-7T		96 X 36	G		S80	1	SA	U	WC	
	11	W9-1R		36 X 36	A		10BWG	1	SA	T		
	12	W9-2L		36 X 36	A		10BWG	1	SA	T		
12/30	1	M2-1 M1-6F	 	21 X 15 24 X 24	A		10BWG	1	SA	P		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SOSS 2 OF 9

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
4-16	0455	02	031, ETC	SH 152
8-16	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	199	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U" EXAL= Extruded Alum Sign Panels	
12/30	2	M3-2 M1-6T	 	24 x 12 24 x 24	A		10BWG	1	SA	P	
	3	R2-1		30 x 36	A		10BWG	1	SA	T	
	4	R12-1T		36 x 24	A		10BWG	1	SA	T	
13/30	1	D15-11T		54 x 48	A		10BWG	1	SA	U	
14/30	1	D15-11T		54 x 48	A		10BWG	1	SA	U	
	2	M1-6T D10-7aT	 	24 x 24 3 x 10	A		10BWG	1	SA	P	
	3	W2-2		36 x 36	A		10BWG	1	SA	T	
15/30	1	R1-1		36 x 36	A		10BWG	1	SA	T	
	2	R1-1 W4-4P	 	36 x 36 24 x 12	A		10BWG	1	SA	T	
	3	R3-7R		36 x 36	A		10BWG	1	SA	U	
	4	D20-2		24 x 24	A		10BWG	1	SA	P	
	5	D20-2		24 x 24	A		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SOSS 3 OF 9

FILE: SLMS16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
4-16	DIST	COUNTY	SHEET NO.	
8-16	AMA	CARSON	200	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U" EXAL= Extruded Alum Sign Panels	
15/30	6	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	
	7	R3-7R		36 X 36	A		10BWG	1	SA	U	
	8	W2-2		36 X 36	A		10BWG	1	SA	T	
17/30	1	W11-10R		36 X 36	A		10BWG	1	SA	T	
	2	M2-1 M1-6F		21 X 15 24 X 24	A		10BWG	1	SA	P	
18/30	1	R2-1		30 X 36	A		10BWG	1	SA	T	
	2	M3-4 M1-6T		24 X 12 24 X 24	A		10BWG	1	SA	P	
	3	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	
	4	R2-1		30 X 36	A		10BWG	1	SA	T	
	5	M3-1 M1-6F M6-1R		24 X 12 24 X 24 21 X 15	A		10BWG	1	SA	P	
	6	R3-7R		36 X 36	A		10BWG	1	SA	U	
	7	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SOSS 4 OF 9

FILE: SLMS16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
4-16	DIST	COUNTY	SHEET NO.	
8-16	AMA	CARSON	201	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)											
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION												
										PREFABRICATED		1EXT or 2EXT = # of Ext										
18/30	8	R12-1T		36 X 24	A		10BWG	1	SA	T												
	9	M3-1		24 X 12	A		10BWG	1	SA	P												
		M1-6F		24 X 24																		
		M6-1L		21 X 15																		
	10	M3-2		24 X 12	A		10BWG	1	SA	U												
		M1-6T		24 X 24																		
		M6-1L		21 X 15																		
		M3-4		24 X 12																		
	11	W1-7T		96 X 36	G		S80	1	SA	U	WC											
				12									R12-7bT		84 X 36	A		S80	1	SA	U	WC
				13									D15-10T		54 X 42	A		10BWG	1	SA	U	
	14	M3-3		24 X 12	A		10BWG	1	SA	P												
		M1-6F		24 X 24																		
		M6-1R		21 X 15																		
	15	W1-7T		96 X 36	G		S80	1	SA	U	WC											
	16	M3-4		24 X 12	A		10BWG	1	SA	U												
		M1-6T		24 X 24																		
		M6-1L		21 X 15																		
		M3-2		24 X 12																		
		M1-6T		24 X 24																		
	17	M1-6F		24 X 24	A		10BWG	1	SA	P												
				M6-1L										21 X 15								

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SOSS 5 OF 9

FILE: slms16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
4-16	0455	02	031, ETC	SH 152
8-16	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	202	

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
18/30	18	M3-2 M1-6T D10-7aT		24 X 12 24 X 24 3 X 10	A		10BWG	1	SA	P	
	19	R12-1T		36 X 24	A		10BWG	1	SA	T	
	20	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	
	21	R2-1		30 X 36	A		10BWG	1	SA	T	
	22	R3-7R		36 X 36	A		10BWG	1	SA	U	
19/30	1	D15-11T		54 X 48	A		10BWG	1	SA	U	
	2	M2-1 M1-6F		21 X 15 24 X 24	A		10BWG	1	SA	P	
	3	W9-2L		36 X 36	A		10BWG	1	SA	T	
20/30	1	W9-1R		36 X 36	A		10BWG	1	SA	T	
	2	R4-2aT		24 X 36	A		10BWG	1	SA	T	
22/30	1	R4-3		24 X 30	A		10BWG	1	SA	T	
	2	W8-13aT		36 X 36	A		10BWG	1	SA	T	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SOSS 6 OF 9

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
4-16	0455	02	031, ETC	SH 152
8-16	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	203	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext
23/30	1	M2-1 M1-6F		21 x 15 24 x 24	A		10BWG	1	SA	P		
	2	R2-1		30 x 36	A		10BWG	1	SA	T	WC	
24/30	1	M3-4 M1-6T		24 x 12 24 x 24	A		10BWG	1	SA	P		
	2	W1-7T		96 x 36	G		S80	1	SA	U		
	3	M3-4 M1-6T M6-1L M3-2 M1-6T M6-1R		24 x 12 24 x 24 21 x 15 24 x 12 24 x 24 21 x 15	A		10BWG	1	SA	U		
	4	M3-3 M1-6F M6-1L		24 x 12 24 x 24 21 x 15	A		10BWG	1	SA	P		
	5	R12-1T		36 x 24	A		10BWG	1	SA	T		
	6	M3-3 M1-6F M6-1R		24 x 12 24 x 24 21 x 15	A		10BWG	1	SA	P		
	7	R1-1 W4-4P		36 x 36 24 x 12	A		10BWG	1	SA	T		
	8	M3-2 M1-6T		24 x 12 24 x 24	A		10BWG	1	SA	P		
	9	R2-1		30 x 36	A		10BWG	1	SA	T		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS













SOSS 7 OF 9

FILE: slms16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
4-16	DIST	COUNTY	SHEET NO.	
8-16	AMA	CARSON	204	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
24/30	10	M2-1 M1-6F		21 X 15 24 X 24	A		10BWG	1	SA	P	
27/30	1	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	
	2	D20-2		24 X 24	A		10BWG	1	SA	P	
	3	D20-2		24 X 24	A		10BWG	1	SA	P	
	4	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	
	5	D15-10T		54 X 42	A		10BWG	1	SA	U	
	6	W9-1R		36 X 36	A		10BWG	1	SA	T	
	7	W9-2L		36 X 36	A		10BWG	1	SA	T	
28/30	1	M1-6T D10-7aT	 (BACK TO BACK)	24 X 24 3 X 10	A		10BWG	1	SA	P	
29/30	1	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T	
	2	D20-2		24 X 24	A		10BWG	1	SA	P	
	3	D20-2		24 X 24	A		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS

SOSS 8 OF 9

FILE: SLMS16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
4-16	0455	02	031, ETC	SH 152
8-16	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	205	

DATE:
FILE:

SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext
29/30	4	R1-1 W4-4P		36 X 36 24 X 12	A		10BWG	1	SA	T		
30/30	1	I-2dT		54 X 24	A		10BWG	1	SA	T		
	2	I-2dT R19-10aT M1-6T D10-7aT		48 X 24 24 X 24 24 X 24 3 X 10	A		S80	1	S80	U	BM	

Square Feet	Minimum Thickness
Less than 7.5	0.100
7.5 or Greater	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



SUMMARY OF SMALL SIGNS


SOSS 9 OF 9

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
4-16	DIST	COUNTY	SHEET NO.	
8-16	AMA	CARSON	206	

DATE:
FILE:


FILENAME: P:\TXDOT\10124272*ISE*TXDOT*3691DP5089*PS*E*SVCS\10124272001*TXDOT*SH*152*Super*2*Carson*County*03.00 Project Execution\03.04 Design\

SHEET 2 OF 30: SIGN 1
 SHEET 11 OF 30: SIGN 1
 SHEET 18 OF 30: SIGN 13
 SHEET 27 OF 30: SIGN 5




D15-10T_54x42:
 3.00" Radius, 1.00" Border, White on Green;
 "PASSING", ClearviewHwy-3-W;
 "LANE", ClearviewHwy-3-W;
 "2 MILES", ClearviewHwy-3-W;

SHEET 5 OF 30: SIGN 1




D10-7aT 3in;
 No border, White on Green;
 "3", ClearviewHwy-4-W;
 "4", ClearviewHwy-4-W;
 "2", ClearviewHwy-4-W;

SHEET 9 OF 30: SIGN 1




D10-7aT 3in;
 No border, White on Green;
 "3", ClearviewHwy-4-W;
 "4", ClearviewHwy-4-W;
 "4", ClearviewHwy-4-W;

SHEET 1 OF 30: SIGN 2
 SHEET 14 OF 30: SIGN 1




D15-11T_54x48:
 3.00" Radius, 1.00" Border, White on Green;
 "NEXT", ClearviewHwy-3-W;
 "PASSING", ClearviewHwy-3-W;
 "LANE", ClearviewHwy-3-W;
 "3 MILES", ClearviewHwy-3-W;

SHEET 14 OF 30: SIGN 2




D10-7aT 3in;
 No border, White on Green;
 "3", ClearviewHwy-4-W;
 "4", ClearviewHwy-4-W;
 "6", ClearviewHwy-4-W;

SHEET 15 OF 30: SIGN 4
 SHEET 15 OF 30: SIGN 5




D20-2T_24x24:
 1.50" Radius, 0.75" Border, White on Green;
 "CO RD", ClearviewHwy-3-W;
 "Y", ClearviewHwy-3-W;

SHEET 18 OF 30: SIGN 12




R12-7aT_VARx36:
 1.50" Radius, 0.63" Border, 0.38" Indent, Black on White;
 "LOAD ZONED ROAD", D; "F.M. 294", D;
 Standard Arrow Custom 7.25" X 4.38" 0"; "NORTH AND SOUTH", D;
 "GROSS WEIGHTS OVER 58,000 LBS", D;
 "DETOUR BY WAY OF PAMPA", D;

SHEET 18 OF 30: SIGN 18




D10-7aT 3in;
 No border, White on Green;
 "3", ClearviewHwy-4-W;
 "4", ClearviewHwy-4-W;
 "8", ClearviewHwy-4-W;

SHEET 13 OF 30: SIGN 1
 SHEET 19 OF 30: SIGN 1




D15-11T_54x48:
 3.00" Radius, 1.00" Border, White on Green;
 "NEXT", ClearviewHwy-3-W;
 "PASSING", ClearviewHwy-3-W;
 "LANE", ClearviewHwy-3-W;
 "5 MILES", ClearviewHwy-3-W;

SHEET 27 OF 30: SIGN 2
 SHEET 27 OF 30: SIGN 3



D20-2T_24x24:
 1.50" Radius, 0.75" Border, White on Green;
 "CO RD", ClearviewHwy-3-W;
 "CC", ClearviewHwy-3-W;

SHEET 28 OF 30: SIGN 1




D10-7aT 3in;
 No border, White on Green;
 "3", ClearviewHwy-4-W;
 "5", ClearviewHwy-4-W;
 "0", ClearviewHwy-4-W;




BRUCE W. PATE
 JULY 27, 2023

SHEET 29 OF 30: SIGN 2
 SHEET 29 OF 30: SIGN 3




D20-2T_24x24:
 1.50" Radius, 0.75" Border, White on Green;
 "CO RD", ClearviewHwy-3-W;
 "DD", ClearviewHwy-3-W;

SHEET 30 OF 30: SIGN 1




I-2aT 8in;
 1.50" Radius, 0.75" Border, White on Green;
 "Carson", ClearviewHwy-5-W-R;
 "COUNTY LINE", ClearviewHwy-3-W;

SHEET 30 OF 30: SIGN 2



I-2aT 8in;
 1.50" Radius, 0.75" Border, White on Green;
 "Gray", ClearviewHwy-5-W-R;
 "COUNTY LINE", ClearviewHwy-3-W;

SHEET 30 OF 30: SIGN 2



D10-7aT 3in;
 No border, White on Green;
 "3", ClearviewHwy-4-W;
 "5", ClearviewHwy-4-W;
 "4", ClearviewHwy-4-W;

© 2023
 Texas Department of Transportation

RS&H, Inc.
 3200 Southwest Freeway, Suite 3150
 Houston, Texas 77027
 713-914-4455 FAX 713-914-0155
 Texas Registration No. F-3401

SH 152


SMALL SIGN DETAILS

SHEET 1 OF 1


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	207
CONTROL	SECTION	JOB	
0455	02	031, ETC	

DRAWING DATE: 7/24/2023


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




DETAIL "A"
 9" min. - 10" typ.
 (18" max. for traveled way
 greater than 48' only)


* 2" minimum for restripe projects when approved by the Engineer.
 ** 8" minimum for restripe projects when approved by the Engineer.



**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**




**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




DETAIL "B"
 16" min. - 20" max.
 (16" minimum for restripe projects
 when approved by the Engineer.)

* 2" minimum for restripe projects when approved by the Engineer.



YIELD LINES



For posted speed on road being marked equal to or less than 40 MPH.


GENERAL NOTES

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**

Based on Traveled Way and Pavement Widths for Undivided Roadways



**TYPICAL STANDARD
PAVEMENT MARKINGS**


PM(1) - 22

FILE: pml-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
11-78 8-00 6-20	DIST	COUNTY	SHEET NO.	
8-95 3-03 12-22	AMA	CARSON	208	
5-00 2-12				

NOTES

- Where divided highways are separated by median widths that the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


FOUR LANE DIVIDED ROADWAY CROSSOVERS




DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS




**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY ROADWAYS**




DETAIL "A"

DETAIL "B"

DETAIL "C"





CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.
 See Note 3.



**REFLECTORIZED PROFILE
PATTERN DETAIL**
USING REFLECTIVE PROFILE PAVEMENT MARKINGS

6" EDGE LINE, 6" CENTERLINE
OR 6" LANE LINE



A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

NOTES


- Edge lines should typically be 6" wide and the materials shall be specified in the plans.
- Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

GENERAL NOTES


- All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
- Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A


RAISED PAVEMENT MARKERS



**POSITION GUIDANCE USING
RAISED MARKERS
REFLECTORIZED PROFILE
MARKINGS
PM(2) - 22**

FILE: pm2-22.dgn	DN: December 2022	CK: 0455	DW: 02	CK: 031, ETC	SH 152
© TxDOT December 2022		REV. NO.	DATE	COUNTY	SHEET NO.
		4-77	8-00	6-20	
		4-92	2-10	12-22	
		5-00	2-12		
		AMA	CARSON		209

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LANE REDUCTION

NOTES

1. Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
2. On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
3. Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
4. For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.


ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	L=WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

GENERAL NOTES


1. Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
2. When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
3. Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
4. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY




TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS



DETAIL A



DETAIL B

* 2" minimum allowed for restripe projects when approved by the Engineer.


Texas Department of Transportation
Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3)-22


FILE: pm3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
4-98 3-03 6-20	0455	02	031, ETC	SH 152
5-00 2-10 12-22	DIST	COUNTY		SHEET NO.
8-00 2-12	AMA	CARSON		210

DATE:
FILE:


RECESSED RAISED PAVEMENT MARKER DETAIL FOR TWO LANE
TWO-WAY HIGHWAY OR MULTILANE UNDIVIDED HIGHWAY



PLAN VIEW



SECTION A-A




SECTION B-B

LEGEND

- BI-DIRECTIONAL RAISED PAVEMENT MARKER TYPE II (SEE NOTE #3).
- MONO-DIRECTIONAL RAISED PAVEMENT MARKER TYPE I.

NOTES

1. DEPTH AND WIDTH OF GROOVE MAY BE ADJUSTED SLIGHTLY TO FIT PHYSICAL DIMENSIONS OF MARKER SELECTED IF APPROVED IN ADVANCE BY THE ENGINEER.
2. ALL PAVEMENT MARKING MATERIALS WILL MEET THE REQUIRED DEPARTMENTAL MATERIAL SPECIAL SPECIFICATIONS FOR 6362.
3. SEE ELSEWHERE IN PLANS FOR SPECIFIED TYPE AND REFLECTORIZED SURFACE LIGHT COLOR.



AMARILLO DISTRICT
RECESSED RAISED PAVEMENT MARKER DETAIL
FOR TWO LANE TWO-WAY HIGHWAYS
OR MULTILANE UNDIVIDED HIGHWAYS

SCALE: N. T. S.



SHEET 1 OF 1

DSM	CK	CONT	SECT	JOB	HIGHWAY
		0455	02	031, ETC	SH 152
DRWN	CK	DIST	COUNTY	SHEET NO.	
		AMA	CARSON	211	

DATE: 7-20-2021 9:45 AM
FILE: T:\AMATPD\Design Resources*.AMA Design Team Resources\District Standard Detail\AMA_DIST_RRPM_STD.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

Post Type

FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)


Anchor Type

UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted Down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




BEHIND BARRIER




BEHIND GUARDRAIL

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.



BEHIND CONCRETE BARRIER

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND



RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

Texas Department of Transportation
 Traffic Operations Division


SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD (GEN) -08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0455	02	031, ETC	SH 152
		DIST		COUNTY	SHEET NO.
		AMA		CARSON	212

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For pre-coated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxy and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

DATE:
FILE:


















SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0455	02	031, ETC	SH 152
		DIST	COUNTY	SHEET NO.	
		AMA	CARSON	213	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



GENERAL NOTES:

SIGN SUPPORT	# OF POSTS	MAX. SIGN AREA
10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF

- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
- Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.
- Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT	
SIGN DESCRIPTION	SUPPORT
48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
48x60-inch signs	TY S80(1)XX(T)
48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
48x60-inch signs	TY S80(1)XX(T)
48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Texas Department of Transportation
Traffic Operations Division











**SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD (SLIP-2) -08**

© TxDOT July 2002		DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0455	02	031, ETC	SH 152
		DIST	COUNTY	COUNTY	SHEET NO.
		AMA	CARSON		214

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)


Texas Department of Transportation
Traffic Operations Division

SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD (SLIP-3) -08


© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0455	02	031, ETC	SH 152
		DIST	COUNTY	SHEET NO.	
		AMA	CARSON	215	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



Wedge Anchor Steel System



Wedge Anchor High Density Polyethylene (HDPE) System




Universal Anchor System with Thin-Walled Tubing Post





Plastic insert must be used when using the TWT with either the Universal Anchor System or the Bolt Down Universal Anchor System. The insert should be approx. 10" long and cover the tubing from just above the top of the stub pipe to the bottom of the sign post when using the Universal Anchor System. The insert should be cut to approx. 4 1/2" when used with the Bolt Down Universal Anchor System.

5/8" diameter Concrete Anchor - 4 places (embed a min. of 3 3/8" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. A heavy hex nut per ASTM A563 and hardened washer per ASTM F436. The stud bolt shall have minimum yield and ultimate tensile strengths of 50 and 75 ksi, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Top of bolt shall extend at least flush with top of nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 3 3/8" minimum embedment, shall have a minimum allowable tension and shear of 2450 and 1525 psi, respectively. Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations.



Sign Installation Using a Prefabricated T-Bracket for Thin-Wall Tubing Post



NOTE
The devices shall be installed per manufacturer's recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- The Wedge Anchor System and the Universal Anchor System with thin wall tubing post may be used to support up to 10 square feet of sign area.
- The tubular socket, wedge and prefabricated T-bracket shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to the approval of the TxDOT Traffic Standards Engineer.
- Except for posts (13 BWG Tubing), clamps, nuts and bolts, all components shall be prequalified. A list of prequalified vendors may be obtained from the Material Producer List web page. The website address is: http://www.txdot.gov/business/producer_list.htm
- Material used as post with this system shall conform to the following specifications:
13 BWG Tubing (2.375" outside diameter) (TWT)
0.095" nominal wall thickness
Seamless or electric-resistance welded steel tubing
Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
Other steels may be used if they meet the following:
55,000 PSI minimum yield strength
70,000 PSI minimum tensile strength
18% minimum elongation in 2"
Wall thickness (uncoated) shall be within the range of .083" to .099"
Outside diameter (uncoated) shall be within the range of 2.369" to 2.381"
Galvanization per ASTM 123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24" high signs. Place clamp at least 3" above bottom of sign when possible.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- See the Traffic Operations Division website for detailed drawings of sign clamps and Wedge Anchor System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>

WEDGE ANCHOR SYSTEM INSTALLATION PROCEDURE

- Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Place concrete into hole until it is approximately flush with the ground. Concrete shall be Class A.
- Insert tubular socket into concrete until top of socket is approximately 1/4" above the concrete footing.
- Plumb the socket. Allow a minimum 4 days for concrete to set, unless otherwise directed by Engineer.
- Attach the sign to the sign post.
- Insert the sign post into socket and align sign face with roadway.
- Drive the wedge into the socket to secure post. This will leave approximately 3 inches of the wedge exposed.

UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURE

- Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- Insert base post in hole to depths shown and backfill hole with concrete.
- Level and plumb the base post using a torpedo level and allow concrete adequate time to set. The bottom of the slots provided in the stub pipe shall remain above the top of the concrete foundation.
- Attach the sign to the sign post.
- Install plastic insert around bottom of post.
- Insert sign post into base post. Lower until the post comes to rest on steel rod.
- Seat compression ring using a hammer. Typically, the top of compression ring will be approximately level with top of stub post when optimally installed.
- Check sign post by hand to ensure it is unable to turn. If loose, increase the tightening of the compression ring.


Texas Department of Transportation
Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS WEDGE & UNIVERSAL ANCHOR WITH THIN WALL TUBING POST SMD(TWT) - 08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0455	02	031, ETC	SH 152
		DIST	COUNTY	SHEET NO.	
		AMA	CARSON	216	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



LEGEND	
	Sign
	Traffic Flow

TYPICAL TAPER LENGTH (L)	
Formula	$L = WS$

* Transition length should be rounded up to nearest 5 foot increment.

L=Length of Transition (FT)
W=Width of Offset (FT)
S=Posted Speed (MPH)

EXAMPLE
A 12 foot lane is added on a 70 mph roadway.
The length of the transition should be:
 $L = 12 \times 70 = 840$ ft

**TABLE 1
ADVANCE WARNING SIGN
DISTANCE (D)
AND BUFFER DISTANCE (B)**

Posted Speed	D (FT)	B (FT)
40	670	305
45	775	360
50	885	425
55	990	495
60	1100	570
65	1200	645
70	1250	730
75	1350	820

GENERAL NOTES

- For minimum and desirable design details, see the Roadway Design Manual, Chapter 4, Section 6, Super 2 Highways.
- For Raised Pavement Markers (RPM) details, see Pavement Markings Standard sheet, PM(2) - Centerline for All Two Lane Two-Way Roadways. Note that RPMs are not recommended on the 6" dotted white extension lines.
- For rumble strip options available for the designed shoulder width, see Rumble Strip Standard sheet RS(2).
- For pavement marking details, see Pavement Marking Standard sheet PM(1).



**TEXAS SUPER 2
PASSING LANES**

TS2(PL-1)-23




FILE: ts2-1-23.dgn	DWG:	CK:	DWG:	CK:
© TxDOT February 2023	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
5-10 3-18	DIST	COUNTY	SHEET NO.	
2-12 2-23	AMA	CARSON	217	
3-12				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS





SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

Texas Department of Transportation
Traffic Operations Division Standard

TYPICAL SIGN REQUIREMENTS


TSR (3) - 13

FILE: tsr3-13.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	AMA	CARSON	218	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

**REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS
(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)**



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING


**REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS
(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)**



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

		<i>Texas Department of Transportation</i>		<i>Traffic Operations Division Standard</i>	
<h2>TYPICAL SIGN REQUIREMENTS</h2>					
<h3>TSR(4) - 13</h3>					
FILE:	tsr4-13.dgn	DW:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT:	0455	SECT:	02
REVISIONS		JOB		HIGHWAY	
12-03	7-13	DIST:	AMA	COUNTY:	CARSON
9-08		SHEET NO.		219	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS					DELINEATORS				D & OM DESCRIPTIVE CODES		
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	DEVICE	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back	
											INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
SHEETING Yellow, White or Red Type B or C reflective sheeting					SHEETING Yellow, White or Red Type B or C Reflective Sheeting						
NOTE 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.					POST TYPE WC YFLX, WFLX WC YFLX, WFLX						
					MOUNT TYPE GND GND, SRF GND GND, SRF						
OBJECT MARKERS											
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)		DEPARTMENTAL MATERIAL SPECIFICATIONS FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES) DMS-4400 SIGN FACE MATERIALS DMS-8300 DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS DMS-8600	
		OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4		
SHEETING Yellow-Type B _{FL} or C _{FL} Sheeting Yellow - Type B or C Sheeting Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting Red -Type B _{FL} or C _{FL} Sheeting											
POST TYPE TWT WC WC WFLX TWT TWT											
MOUNT TYPE WAS, WAP GND GND GND, SRF WAS, WAP WAS, WAP											
BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW				
DEVICE	GF1	GF2	CTB	 W1-8				 W1-6			
	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
SHEETING Yellow, White, Red			MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only		MOUNTING HEIGHT	7'-0"		
NOTE 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			NOTE 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).								

NOTE:
 Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.














DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION D & OM(1)-20

FILE: dom1-20.dgn	DW: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	AMA	CARSON	220	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS																										
WING CHANNEL (WC)	FLEXIBLE POSTS (CYFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT																									
GND	GND	SRF	WAS	WAP	GF 1																									
																														
			STEEL	PLASTIC	GF 2																									
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.		NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.																										
TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS																										
 <p style="text-align: center;">NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)</p>		 <p style="text-align: center;">NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.</p>		 <p style="text-align: center;">See general notes 1, 2 and 3.</p>																										
CONCRETE TRAFFIC BARRIER (CTB)																														
																														
GENERAL NOTES 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.																														
																														
DELINEATOR & OBJECT MARKER INSTALLATION D & OM(2)-20																														
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>FILE: dom2-20.dgn</td> <td>DN: TxDOT</td> <td>CK: TxDOT</td> <td>DW: TxDOT</td> <td>CK: TxDOT</td> </tr> <tr> <td>© TxDOT August 2004</td> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>REVISIONS</td> <td>0455</td> <td>02</td> <td>031, ETC</td> <td>SH 152</td> </tr> <tr> <td>10-09 3-15</td> <td>DIST</td> <td>COUNTY</td> <td colspan="2">SHEET NO.</td> </tr> <tr> <td>4-10 7-20</td> <td>AMA</td> <td>CARSON</td> <td colspan="2">221</td> </tr> </table>						FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY	REVISIONS	0455	02	031, ETC	SH 152	10-09 3-15	DIST	COUNTY	SHEET NO.		4-10 7-20	AMA	CARSON	221	
FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT																										
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY																										
REVISIONS	0455	02	031, ETC	SH 152																										
10-09 3-15	DIST	COUNTY	SHEET NO.																											
4-10 7-20	AMA	CARSON	221																											

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS


Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	● RPMs	● RPMs
15 MPH & 20 MPH	● RPMs and One Direction Large Arrow sign	● RPMs and Chevrons; or ● RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	● RPMs and Chevrons; or ● RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	● RPMs and Chevrons

SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE
ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE
At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy./Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

1. Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
2. Barrier reflectors may be used to replace required delineators.
3. Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

DELINATOR & OBJECT MARKER PLACEMENT DETAILS


D & OM(3) - 20

FILE: dom3-20.dgn	DW: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS		0455	02	031, ETC
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	AMA	CARSON	222	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:

CROSSOVERS




DETAIL 1

FOR CULVERTS WITHOUT MBGF




DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES




DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

1. Barricade striping shall be red and white reflective sheeting for all permanent road closures.
2. Barricade striping is red and white sloping toward the center of the roadway.
3. Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4) - 20


FILE: dom4-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
3-15	DIST	COUNTY	SHEET NO.	
7-20	AMA	CARSON	223	

**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**




NOTE:
1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:
1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow

Texas Department of Transportation
Traffic Safety Division Standard

**DELINEATOR & OBJECT MARKER
PLACEMENT DETAILS**






D & OM(5) - 20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0455	02	031, ETC	SH 152
7-20	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	224	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



OBJECT MARKERS SMALLER THAN 3 FT²



NOTES



- *1. Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- 2. Mounting should be flush with top of attenuator. Minimum size 96" x 24".


NOTES

1. Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
2. Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
3. Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
4. Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
5. Object Marker at nose of attenuator is subsidiary to the attenuator.
6. See D & OM (1-4) for required barrier reflectors.

<p>DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</p> <p>D & OM(VIA)-20</p>			
FILE: domv1a20.dgn	DW: TXDOT	CK: TXDOT	DW: TXDOT
© TxDOT December 1989	CONT	SECT	JOB
REVISIONS		0455 02	031, ETC
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	AMA	CARSON	225
4-98 7-20			
20G			



DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GAP LENGTH TABLE (L)	
BICYCLISTS OPERATING <= 20 MPH	>= 15 FEET
BICYCLISTS OPERATING > 20 MPH	>= 20 FEET*
* Or the rumble strips should be located on the right side of the shoulder to allow bicyclists to avoid them if they encounter a need to enter the travel lane (e.g. a downhill location).	

RUMBLE STRIP GAP SPACING



* 5' minimum if adjacent to curb, guardrail, vertical element, or obstacle.
 ** Options A-C for consideration of horizontal placement using engineering judgment. See RS(1) and RS(2) for rumble strip device options. Care should be taken to consider bicycles in applying the tables by shoulder width. Narrow rumble strip options include RS(1) Options 1, 2, and 6 and RS(2) Options 1, 2, 6, and 8.

RUMBLE STRIP HORIZONTAL PLACEMENT

GENERAL NOTES

- The Engineer must consider accommodating bicycles during the planning and implementation of all construction and rehabilitation projects. See the TxDOT Roadway Design Manual (RDM) Bicycle Facilities section for applicable policies, references, and guidance; including additional detail regarding rumble strip gap and horizontal placement, as well as explanation of desirable, minimum, and constrained values.
- For non-freeway facilities with bike lanes, buffered bike lanes, or bike-accessible shoulders, the Engineer shall place rumble strips considering the safety of and crash risk for bicyclists. The Engineer shall include a detail of rumble strip gap spacing, horizontal spacing from the edge line, and material / installation method in the plans.
- See RS(5) General Note 8 regarding bicycle safety with transverse (in-line rumble strips).

GAPS

- Rumble strip gaps to allow bicyclists to safely enter or exit a shoulder, as needed. In addition to gaps provided for vehicles (e.g. at cross-streets), the Engineer shall ensure gaps are available every 40 to 60 feet. See Gap Spacing detail. The Engineer should consider significant grades as they affect bicycle speeds in applying the Gap Length Table, for example downhill versus uphill bicycle speeds.

HORIZONTAL SPACING

- Rumble strip horizontal spacing considerations affect bicyclist safety and mobility. The Engineer shall consider desirable, minimum, and constrained widths, as shown in the horizontal placement detail. The Engineer shall apply engineering judgment to choose placement and material options in the Shoulder Width Tables on each RS sheet to optimize safety for all users. Horizontal width for bikes does not include standard drainage inlets, rumble strips, or raised pavement markers (RPMs).


RUMBLE STRIP BICYCLE CONSIDERATIONS FOR NON-FREWAY FACILITIES RS(6)-23			
FILE: rs(6)-23.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT
© TxDOT	January 2023	CONT	SECT
REVISIONS	0455	02	031, ETC
1-23	DIST	COUNTY	SHEET NO.
	AMA	CARSON	226

DATE: FILE:




DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

TWO LANE TWO-WAY
HIGHWAYS






CENTERLINE RUMBLE STRIPS






PLAN VIEW
OPTION 1

MILLED CENTERLINE
RUMBLE STRIPS






PLAN VIEW
OPTION 2

RAISED CENTERLINE
RUMBLE STRIPS



PLAN VIEW
OPTION 3

PREFORMED THERMOPLASTIC
RUMBLE STRIPS



PLAN VIEW
OPTION 4

PROFILE CENTERLINE MARKINGS
AND PREFORMED THERMOPLASTIC
RUMBLE STRIPS

GENERAL NOTES

1. This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
2. Centerline and edge line rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections or driveways with high usage of large trucks.
6. Use standard sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips.

WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
11. The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.
12. Consideration shall be given to bicyclists. See RS(6).

WHEN INSTALLING EDGE LINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

13. See standard sheet RS(2).

<h2>CENTERLINE RUMBLE STRIPS ON TWO LANE TWO-WAY HIGHWAYS</h2> <h3>RS(4)-23</h3>			
FILE: rs(4)-23.dgn	DN: TxDOT	CK: TxDOT	PW: TxDOT
© TxDOT	January 2023	CONT	SECT
REVISIONS	0455	02	031, ETC
10-13	DIST	COUNTY	SHEET NO.
1-23	AMA	CARSON	227

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

0455-02-031

1.2 PROJECT LIMITS:

From: Hutchinson County Line

To: Gray County Line

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 35° 37' 29.73" N, (Long) 101° 16' 31.48" W

END: (Lat) 35° 31' 55.41" N, (Long) 101° 05' 09.61" W

1.4 TOTAL PROJECT AREA (Acres): 158.40

1.5 TOTAL AREA TO BE DISTURBED (Acres): 7.40

1.6 NATURE OF CONSTRUCTION ACTIVITY:

Construction of Super 2 passing lanes, pavement repair, ACP overlay, and safety end treatment upgrades.

1.7 MAJOR SOIL TYPES:

Soil Type	Description
	Ady fine sandy loam 1-3% slopes, 0-10" fine sandy loam
	Likes loamy fine sand 1-8% slopes, 0-10" loamy fine sand
	Mobeetie-Veal-Potter complex 3-20% slopes, 0-10" fine sandy loam
	Potter-Mobeetie association 8-45% slopes, 0-6" gravelly loam
	Manson-Palo Duro association 1-8% slopes, 0-5" loam
	Plemons loam 3-5% slopes, 0-6" loam
	Pullman clay loam 0-1% slopes, 0-5" clay loam

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: _____
 Other: _____
 Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Spring Creek	Intermittent Stream
White Deer Creek	Intermittent Stream
Playa Lakes	Non-jurisdictional

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT


- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:

MS4 Entity
NOT APPLICABLE



8/12/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3)

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				228
STATE	STATE DIST.	COUNTY		
TEXAS	AMA	CARSON		
CONT.	SECT.	JOB	HIGHWAY NO.	
0455	02	031, ETC	SH 152	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

T / P

- Sediment Trap
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
 - Not required (<10 acres disturbed)
 - Required (>10 acres) and implemented.
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
 - Required (>10 acres), but not feasible due to:
 - Available area/Site geometry
 - Site slope/Drainage patterns
 - Site soils/Geotechnical factors
 - Public safety
 - Other: _____

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:


- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.



8/12/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3)

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				229
STATE	STATE DIST.	COUNTY		
TEXAS	AMA	CARSON		
CONT.	SECT.	JOB	HIGHWAY NO.	
0455	02	031, ETC	SH 152	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152-WA 6\CADD\Sheets\11 Erosion Control Plan\epic.dgn

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. N/A

No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 1500000
- Comply with the Construction General Permit and implement SW3P's, revise when necessary to control pollution or required by the Engineer.
- Post a large Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA, or other inspectors.
- Submit NOI to TCEQ.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- TRIBUTARIES OF SPRING CREEK
- TRIBUTARIES OF WHITE DEER CREEK

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input checked="" type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input checked="" type="checkbox"/> Vegetative Filter Strips
<input checked="" type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required Required Action

Action No.

- In the event that unanticipated archeological deposits are encountered during construction, work in the immediate area will cease and TxDOT archeological staff will be contacted to initiate post-review discovery procedures.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

No Action Required Required Action

Action No.

- Comply with Executive Order 13112 on Invasive Species and the intent of the Executive Order Memorandum on Beneficial Landscapes for re-vegetating the project area. The proposed seed mixture (both grasses and forbs) would be in accordance with Item 164, Seeding for Erosion Control in TxDOT's Standard Specifications for the construction of Highways, Streets, and Bridges.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required Required Action

Action No.

- If any species on the Carson County T&E List is sighted in the project area during construction, stop construction and notify the Area Engineer.
- Eastern Spotted Skunk, Swift Fox: Contractors will be advised of potential occurrence in the project area, and to avoid harming the species if encountered, and to avoid unnecessary impacts to dens.
- Texas Horned Lizard, Western Box Turtle, Western Hognose Snake, Prairie Rattlesnake, Western Massasauga, Woodhouse's Toad:
 - Contractors will be advised of potential occurrence in the project area, and to avoid harming the species if encountered. If reptiles are found on project site, contractors are to allow them to leave the project site safely.
 - For the Texas Horned Lizard, avoidance should include avoiding harvester ant beds in the selection of Project Specific Locations (PSL's).
 - If erosion control blankets or soil retention blankets are needed, the product should not contain netting, but should only contain loosely woven natural fiber netting in which the mesh design allows the threads to move, therefore allowing expansion of the mesh openings. Plastic netting should be avoided.
- Bird BMP's: a) Do not disturb, destroy, or remove active nests, including ground nesting birds, during the nesting season; b) avoid the removal of unoccupied, inactive nests, as practicable; c) do not collect, capture, relocate, or transport birds, eggs, young, or active nests without a permit.
- The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, egg in part or in whole, without a Federal permit issued in accordance with the Act's policies and regulations. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young would be avoided.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required Required Action


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required Required Action


Action No.

- Tree removal should be planned to take place outside the bird nesting season (April 1-Aug 31). If the tree removal occurs between April 1 and August 31, the contractor shall obtain the services of a qualified biologist to complete a survey of active bird nests. Prior to commencing the survey, the biologist will consult with the TxDOT Amarillo District Environmental Coordinator to determine appropriate survey procedures in accordance with TxDOT requirements.
- Avoid direct impacts to playa lakes and perennial and intermittent streams adjacent to the ROW during construction including selection of and access to project specific locations (PSLs). Ensure sediment and erosion controls near the playa lakes and streams are adequate to prevent additional sedimentation into these water features.

		Design Division Standard	
<p>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC</p>			
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (DS) REVISIONS	0455	02	031, ETC
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	AMA	CARSON	230


FILENAME: L:\Amorillo District\SH 152*WA 6\CADD\Sheets\02 - 1 Drill Seeding\SH 152*Drill Seeding*01.dgn

DRAWING DATE: 8/12/2023




**(A) SEEDING TYPICAL SECTION - OVERLAY
SH 152**

STA 988+00.00 TO STA 1031+00.00
 STA 1267+00.00 TO STA 1301+50.00
 STA 1352+00.00 TO STA 1374+00.00
 STA 1639+00.00 TO STA 1673+47.35




LEGEND:

- ① EMULS ASPH (EROSN CONT) (MS-2)
- ② DRILL SEEDING (TEMP) (WARM OR COOL)
- ③ DRILL SEEDING (PERM) (RURAL) (SANDY)



**(B) CLIMBING LANE SECTION - OVERLAY
SH 152**

STA 1031+00.00 TO STA 1040+00.00 LT TRANSITION (40' TO 52') (AVG 46')
 STA 1040+00.00 TO STA 1112+55.04
 STA 1374+00.00 TO STA 1383+00.00 LT TRANSITION (40' TO 52') (AVG 46')
 STA 1383+00.00 TO STA 1492+88.41



8/12/2023





**SH 152
SW3P DRILL SEEDING
DETAIL**

Sheet 1 of 4

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	231
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amarillo District\SH 152\WA 6\CADD\Sheets\02 - 1 Drill Seeding\SH 152*Drill Seeding*02.dgn

DRAWING DATE: 8/12/2023




LEGEND:

- ① EMULS ASPH (EROSN CONT) (MS-2)
- ② DRILL SEEDING (TEMP) (WARM OR COOL)
- ③ DRILL SEEDING (PERM) (RURAL) (SANDY)


**Ⓒ CLIMBING LANE SECTION - OVERLAY
SH 152**

STA 1139+38.48 TO STA 1195+00.00
 STA 1332+75.00 TO STA 1344+00.00
 STA 1344+00.00 TO STA 1352+00.00 RT TRANSITION (52' TO 40') (AVG 46')
 STA 1515+29.79 TO STA 1522+00.00
 STA 1550+50.00 TO STA 1591+50.00



**Ⓓ SEEDING TYPICAL SECTION (SUPER 2)
SH 152**

STA 1195+00.00 TO STA 1258+00.00
 STA 1258+00.00 TO STA 1267+00.00 RT TRANSITION (52' TO 40') (AVG 46')
 STA 1591+50.00 TO STA 1630+00.00
 STA 1630+00.00 TO STA 1639+00.00 RT TRANSITION (52' TO 40') (AVG 46')



8/12/2023





**SH 152
SW3P DRILL SEEDING
DETAIL**

Sheet 2 of 4

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		232

FILENAME: L:\Amarillo District\SH 152*WA 6\CADD\Sheets\02 - 1 Drill Seeding\SH 152*Drill Seeding*03.dgn

DRAWING DATE: 8/12/2023




LEGEND:

- ① EMULS ASPH (EROSN CONT) (MS-2)
- ② DRILL SEEDING (TEMP) (WARM OR COOL)
- ③ DRILL SEEDING (PERM) (RURAL) (SANDY)


(E) SEEDING TYPICAL SECTION (SUPER 2 AND RIGHT TURN LANE)
SH 152

STA 1301+50.00 TO STA 1307+85.00 TRANSITION LT & RT (40' TO 64') (AVG 52')
STA 1307+85.00 TO STA 1317+00.00




(F) SEEDING TYPICAL SECTION (SUPER 2 AND RIGHT TURN LANE)
SH 152

STA 1317+00.00 TO STA 1331+27.00
STA 1331+27.00 TO STA 1332+75.00 TRANSITION LT (64' TO 52') (AVG 58')



8/12/2023




SH 152
SW3P DRILL SEEDING
DETAIL

Sheet 3 of 4			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	233
CONTROL	SECTION	JOB	
0455	02	031, ETC	


FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\02 - 1 Drill Seeding\SH 152*Drill Seeding*04.dgn

DRAWING DATE: 8/12/2023




G SEEDING TYPICAL SECTION (SUPER 2 AND LEFT TURN LANE) - OVERLAY
SH 152

STA 1522+00.00 TO STA 1531+00.00 LT TRANSITION (52' TO 64') (AVG 58')
STA 1531+00.00 TO STA 1535+41.00




LEGEND:

- ① EMULS ASPH (EROSN CONT) (MS-2)
- ② DRILL SEEDING (TEMP) (WARM OR COOL)
- ③ DRILL SEEDING (PERM) (RURAL) (SANDY)



H SEEDING TYPICAL SECTION (SUPER 2 AND LEFT TURN LANE)
SH 152

STA 1535+41.00 TO STA 1541+50.00
STA 1541+50.00 TO STA 1550+50.00 TRANSITION LT (64' TO 52') (AVG 58')



8/12/2023

Texas Department of Transportation

I. S. ENGINEERS, LLC
7670 WOODWAY DRIVE, SUITE 320
HOUSTON, TEXAS 77063
T&PE REG. # F-11657


SH 152
SW3P DRILL SEEDING
DETAIL

Sheet 4 of 4

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	(SEE TITLE SHEET)		SH 152
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	AMA	CARSON	234
CONTROL	SECTION	JOB	
0455	02	031, ETC	

FILENAME: L:\Amorillo District\SH 152\WA 6\CADD\Sheets\11 Erosion Control Plan\SH152*EROSION CONTROL LAYOUT.dgn

DRAWING DATE: 8/12/2023




TYPICAL EROSION CONTROL LOG LAYOUT

* APPLIES ONLY TO UPSTREAM ENDS WHERE WORK IS BEING PERFORMED

BMP'S RECORD LOG			
STATION	BMP #	INSTALL DATE	REMOVAL DATE
1244+00 EB	1		
1310+00 WB	2		
1322+00 WB	3		
1537+00 WB	4		
1629+00 EB	5		

DRILL SEEDING SUMMARY			
LOCATION	164	164	314
	6034	6053	6009
	DRILL SEEDING (PERM) (RURAL) (SANDY)	DRILL SEEDING (TEMP) (WARM OR COOL)	EMULS ASPH (EROSN CONT) (MULTI) (0.1 GAL/SY)
	AC	AC	GAL
SEEDING TYPICAL SECTION A	3.08	3.08	1489
SEEDING TYPICAL SECTION B	4.60	4.60	2227
SEEDING TYPICAL SECTION C	2.81	2.81	1362
SEEDING TYPICAL SECTION D	26.88	26.88	1328
SEEDING TYPICAL SECTION E	2.35	2.35	172
SEEDING TYPICAL SECTION F	1.74	1.74	175
SEEDING TYPICAL SECTION G	0.31	0.31	149
SEEDING TYPICAL SECTION H	1.66	1.66	168
PROJECT TOTALS	43.43	43.43	7069




8/12/2023

EROSION CONTROL SUMMARY					
LOCATION	164	164	314	506	506
	6034	6053	6009	6040	6043
	DRILL SEEDING (PERM) (RURAL) (SANDY)	DRILL SEEDING (TEMP) (WARM OR COOL)	EMULS ASPH (EROSN CONT) (MULTI) (0.1 GAL/SY)	BIODEG EROSN CONT LOGS (INSTL) (8")	BIODEG EROSN CONT LOGS (REMOVE)
	AC	AC	GAL		LF
CSJ: 0455-02-031	43.43	43.43	7069	125	125
PROJECT TOTALS	43.43	43.43	7069	125	125


SH 152 EROSION CONTROL LAYOUT		
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	(SEE TITLE SHEET)	SH 152
STATE	DISTRICT	COUNTY
TEXAS	AMA	CARSON
CONTROL	SECTION	JOB
0455	02	031, ETC
		SHEET NO.
		235

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\11 Erosion Control Plan\TxDOT Standards\EC (9) -16.dgn



PLAN VIEW




SECTION A-A
EROSION CONTROL LOG DAM


CL-D

LEGEND

- CL-D EROSION CONTROL LOG DAM
- CL-BOC EROSION CONTROL LOG AT BACK OF CURB
- CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
- CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
- CL-DI EROSION CONTROL LOG AT DROP INLET
- CL-CI EROSION CONTROL LOG AT CURB INLET
- CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



REBAR STAKE DETAIL




PLAN VIEW



SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.


GENERAL NOTES:

1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) -16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0455 02	031, ETC	SH 152
	DIST	COUNTY	SHEET NO.
	AMA	CARSON	236

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\11 Erosion Control Plan\TxDOT Standards\EC (9) -16.dgn



**EROSION CONTROL LOGS ON SLOPES
STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




**EROSION CONTROL LOGS ON SLOPES
STAKE AND LASHING ANCHORING**

CL-SSL



STAKE AND TRENCHING ANCHORING DETAIL


CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL

LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"



STAKE NOTCH DETAIL



SHEET 2 OF 3


Design Division Standard

**TEMPORARY EROSION,
 SEDIMENT AND WATER
 POLLUTION CONTROL MEASURES
 EROSION CONTROL LOG
 EC (9) -16**

FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT	CK: LS
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY	
REVISIONS	0455 02	031, ETC	SH 152	
DIST	COUNTY	SHEET NO.		
AMA	CARSON	237		


DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 8/12/2023
 FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\11 Erosion Control Plan\TxDOT Standards\EC (9) -16.dgn




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET


CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) -16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0455 02	031, ETC	SH 152
DIST	COUNTY	SHEET NO.	
AMA	CARSON	238	

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 8/12/2023
FILE: L:\Amarillo District\SH 152_WA 6\CADD\Sheets\11 Erosion Control Plan\VERLAY\AMARILLO DISTRICT GRASS SEEDING SPECIFICATION.dgn

ITEM 164 SEEDING FOR EROSION CONTROL

SEED (PERM) (RURAL or URBAN) (SAND or CLAY)

"WARM SEASON" PLANTING DATES	SEED MIXTURE	PURE LIVE SEED RATE & PLANT DEPTH
PERMANENT: EARLY SPRING SEED FROM FEBRUARY 15th THROUGH May 15th. AS AREAS OF THE ROW ARE PREPARED AND DETERMINED READY FOR DRILL SEEDING.	NEW CROP SEED: TYPE: BUFFALO GRASS (Texoka) "Fluffy" WESTERN WHEATGRASS (ARRIBA) "Hard" BERMUDA GRASS (BLACK JACK) "Hard" Tiny Seed" 100% "Unhulled"	3.0 LBS PLS / ACRE 6.0 LBS PLS / ACRE 5.0 LBS PLS / ACRE @ 1/4" - 1/2" SOIL DEPTH
PERMANENT and TEMP. LATE SPRING SEED FROM MAY 15th THROUGH AUGUST 1st AS AREAS OF THE ROW THAT ARE LAID BY BUT DETERMINED TO BE OUT OF SEASON FOR PERMANENT DRILL SEEDING.	TYPE: MILLET (BROWN TOP) "Hard Shell, "Small Seed" - Nurse crop BERMUDA GRASS (BLACK JACK) "Hard" Tiny Seed" 100% "Unhulled"	30. LBS PLS / ACRE @ 1/4" SOIL DEPTH 5.0 LBS PLS / ACRE
SOIL PREPARATION EQUIPMENT AND PRACTICES: RIPPER --- DISK --- HARROW --- CULTI-PACKER.		

NOTES:

- ALL SEED MIXTURE TYPES SHALL BE PURCHASED IN PRE- MIXED BAGS, "BY TYPE" BLENDED BY THE GROWER SHIPPER.
- SOILS THAT ARE COMPACTED, HAVE CLODS, SHALL BE REWORKED UNTIL READY FOR SEEDING, AS DIRECTED.
- ALL SOIL SURFACES SHALL BE LEVEL WITH NATURAL FLOWING SMOOTH GRADES. NO TIRE RUTS OR FURTHER TRAFFIC ALLOWED.
- SOIL SURFACE SHALL BE FIRM BUT NOT COMPACTED, ALLOWING 1/4" DEPRESSION UNDER NORMAL FOOT TRAFFIC.
- SEED 100% OF THE BED AREA. NO SKIPS OR VOID AREAS ALLOWED. EXAMPLE: AREAS AROUND SIGN POSTS AND INLETS.
- SEED UP TO THE FIRST 6" OF THE EDGE OF PAVEMENT. AS DIRECTED, HAND RAKE ISOLATED SEEDING AREAS.
- WEIGH ALL CALIBRATED SEED SAMPLES FOR ACCURACY AND PRESENT DOCUMENTATION TO ENGINEER.

FOR DRILL SEEDING

- USE ONLY PROFESSIONAL NATIVE GRASS OR TURF GRASS (MULTI- 3 BIN) DRILL SEEDERS.
- CALIBRATE DRILL SEEDER FOR SPECIFIED (PLS) PER ACRE BEFORE DRILL SEEDING.
- DRILL SEEDER MUST BE EQUIPPED WITH THE LARGE FRONT CUTTING COULTERS DURING THE INSPECTION OF DRILL SEEDER.

FOR BROADCAST SEEDING

- USE ONLY COMMERCIAL TYPE CYCLONE TYPE SPREADERS.
- CALIBRATE CYCLONE SPREADER FOR 1000 Sq. Ft. (PLS) PER ACRE BEFORE SEEDING.
- TO PREVENT SEED SEPARATION IN SPREADERS, SPREAD ALL SEED TYPES INDEPENDENTLY IN A SEPARATE APPLICATION.
- IMMEDIATELY AFTER SEEDING, IN ONE OR TWO OPERATIONS, CULTI-PACK THE SEEDING SOILS AND FIRM SEED INTO SURFACE.
- DISCONTINUE SEEDING IF WIND EXCEEDS 10 MPH.

ITEM 164 SEEDING FOR EROSION CONTROL

SEED (TEMPORARY) COOL SEASON SEEDING

"COOL SEASON" PLANTING DATES	SEED MIXTURE	PURE LIVE SEED RATE & PLANT DEPTH
TEMPORARY: EARLY FALL SEED FROM AUGUST 1st THROUGH DECEMBER 1st. AS AREAS OF THE ROW ARE PREPARED AND DETERMINED READY FOR DRILL SEEDING.	NEW CROP SEED: TYPE: WESTERN WHEATGRASS "Hard Shell" RED WINTER WHEAT, VAR:TAM III "Hard Shell"	6.0 LBS PLS / ACRE 34. LBS PLS / ACRE @ 1" SOIL DEPTH
TEMPORARY: LATE FALL SEED FROM DECEMBER 1st THROUGH DECEMBER 31st. AS AREAS OF THE ROW ARE PREPARED AND DETERMINED READY FOR DRILL SEEDING.	NEW CROP SEED: TYPE: RED WINTER WHEAT, VAR:TAM III "Hard Shell"	34. LBS ACRE / PLS @ 1" SOIL DEPTH
SOIL PREPARATION EQUIPMENT AND PRACTICES: RIPPER --- DISK --- HARROW --- CULTI-PACKER.		

ITEM 314 EMULSIFIED ASPHALT TREATMENT

TIME SCHEDULE:

IMMEDIATELY AFTER SOIL PREPARATION OR WITHIN 24 HOURS AFTER SEEDING, APPLY THE TACK COAT TO DESIGNATED SOIL SURFACES.

FUNCTIONAL USE:

SOIL EROSION CONTROL, OR MOISTURE RETENTION BARRIER.

NOTES:

- ALL TRUCK APPLICATIONS SHALL BE COMPLETED IN ONE PASS OF THE DISTRIBUTOR. ALL TOUCH UP WORK WILL BE FINISHED BY HAND AND HOSE PROCEDURES. APPLY FROM EDGE OF PAVEMENT THROUGH THE FULL SPECIFIED AREAS.
- ENGINEER WILL INSPECT FOR ACCURACY THE OVERALL DEPTH OF THE APPLIED TACK COAT MATERIALS.
- FURTHER VEHICULAR TRAFFIC IS NOT ALLOWED ON LAID BY TACK COAT SURFACES. AT THE CONTRACTORS EXPENSE ALL DAMAGES TO TACK COAT SURFACES WILL BE RE -SHOT AS DIRECTED BY THE ENGINEER.

ITEM 166 FERTILIZER

TIME SCHEDULE:

AFTER TOPSOIL PLOWING PREPARATIONS ARE COMPLETED, FERTILIZE R.O.W. SOIL SURFACES AND HARROW 2" TO 4" DEEP INTO PLACE.


FUNCTIONAL USE:

PLANT NUTRIENTS FOR PLANT AND ROOT DEVELOPMENT.

FERTILIZER SHALL BE EVENLY DISTRIBUTED AT A RATE OF 28 LBS OF NITROGEN PER ACRE. THE BREAK DOWN OF THE NITROGEN ELEMENT SHALL BE IN A 50% SLOW RELEASE FORM. ANALYSIS OF THE (NPK) IS: 1-5-0 A HIGH PHOSPHATE BLEND. AS DIRECTED BY THE VEGETATION MANAGER.

ITEM 166 NOTES:

- BROADCAST SPECIFIED FERTILIZER FROM THE EDGE OF PAVEMENT, THROUGH THE ENTIRE ROW SEED BED AREA. APPLICATIONS FOR EDGE OF PAVEMENT, CULVERTS, SIGN POST AREAS, GUARD RAILS AND ISOLATED AREAS SHALL BE APPLIED BY WALK BEHIND SPREADERS AND BY HAND. NO FERTILIZER ALLOWED ON PAVEMENT SURFACES.
- ALL SPREADERS SHALL BE CALIBRATED BY THE CONTRACTOR AND THE ENGINEER FOR ACCURACY AND PERFORMANCE. SHALL USE UNOPENED 50# BAGS OF SPECIFIED FERTILIZER FOR DAILY CALIBRATIONS. APPLICATION SHALL BE AN EVEN DISTRIBUTION OF PRODUCT ON DESIGNATED SOIL SURFACES.
- FERTILIZER SHALL BE DELIVERED IN 50# BAGS UNLESS OTHERWISE SPECIFIED OR APPROVED PRIOR TO DELIVERY. BAGS SHALL BE CLEARLY LABELED SHOWING CONTENTS. IF BULK FERTILIZER IS APPROVED, DOCUMENTATION WILL BE REQUIRED FOR EACH LOAD OF MATERIAL DELIVERED VERIFYING AUTHENTICITY OF THE MATERIAL. CULTURAL PROCEDURES ARE UNDER THE DIRECTION OF THE TxDOT VEGETATION MANAGER.



8/12/2023



AMARILLO DISTRICT STANDARD

VEGETATION SPECIFICATION SHEET

FEDERAL AID PROJECT	DN:ADD	CK:ADD	DW:ADD	CK:ADD
See Title Sheet	CONT	SECT	JOB	HIGHWAY
03/27/20	0455	02	031, ETC	SH 152
REVISIONS	DIST	COUNTY	SHEET NO.	
	AMA	CARSON	239	